CALCULUS

with CalcChat® and CalcView®

12e



Ron Larson Bruce Edwards

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Index of Applications

Engineering and Physical Sciences

Acceleration, 128, 132, 160, 162, 180, 257, 910
Air pressure, 440
Air traffic control, 158, 750, 854
Aircraft glide path, 197
Angle of elevation, 155, 159, 160
Angular rate of change, 381
Angular speed, 38, 381
Apparent temperature, 903
Archimedes' Principle, 514
Architecture, 698
Asteroid Apollo, 742
Atmospheric pressure and altitude, 323, 349, 955
Automobile aerodynamics, 30
Average speed, 44, 93
Average temperature, 988, 1039
Average velocity, 116
Beam deflection, 697
Beam strength, 226
Boyle's Law, 493, 512
Braking load, 778
Breaking strength of a steel cable, 360
Bridge design, 698
Building design, 453, 571, 1012, 1040, 1068
Cable tension, 761, 769
Carbon dating, 421
Center of mass, 504
Centripetal acceleration, 854
Centripetal force, 854
Centroid, 502, 503, 527
Charles's Law, 78
Chemical mixture problem, 435, 437
Chemical reaction, 430, 558, 967
Circular motion, 844, 852
Comet Hale-Bopp, 745
Construction, 158, 769
Cooling superconducting magnets with liquid helium, 78
Cycloidal motion, 844, 853
Dissolving chlorine, 85
Doppler effect, 142
Einstein's Special Theory of Relativity and Newton's First Law of Motion, 207
Electric circuit, 371, 414, 434, 437
Electric force, 492
Electric force fields, 1045
Electric potential, 882
Electrical resistance, 189, 910
Electricity, 159, 307
Electromagnetic theory, 581
Electronically controlled thermostat, 29
Emptying a tank of oil, 489
Engine design, 1067
Engine efficiency, 207
Escape velocity, 98, 257
Explorer 1, 698
Explorer 18, 745
Explorer 55, 698
Falling object, 312, 434, 437
Ferris wheel, 870
Field strength, 548
Flight control, 159
Flow rate, 290, 294, 307, 351, 1109
Fluid force, 506, 507, 508, 509, 510, 513, 514, 546, 549
Force, 293, 509, 774, 775, 785, 786
Free-falling object, 72, 96
Frictional force, 862, 866
Fuel efficiency, 581
Gauss's Law, 1107, 1109
Geography, 807, 817
Gravitational fields, 1045
Gravitational force, 581
Halley's Comet, 698, 741
Hanging power cables, 393, 397
Harmonic motion, 142, 163, 349
Heat equation, 901
Heat flux, 1128
Heat transfer, 332
Heat-seeking particle, 925, 930
Height
  of a Ferris wheel, 40
  of a man, 581
  rate of change of, 157
Highway design, 173, 197, 870
Honeycomb, 173
Hooke's Law, 487, 491, 512
Hydraulics, 1005
Hyperbolic detection system, 695
Hyperbolic mirror, 699
Ideal Gas Law, 883, 903, 918
Illumination, 226, 246
Inductance, 910
Kepler's Laws, 741, 742, 866
Kinetic and potential energy, 1075, 1078
Law of Conservation of Energy, 1075
Length
  of a cable, 477, 481
  of Gateway Arch, 482
  of pursuit, 484
  of a stream, 483
  of warblers, 585
Linear vs. angular speed, 160, 163
Load supports, 769
Lunar gravity, 257
Machine design, 159
Machine part, 471
Magnetic field of Earth, 1054
Mass, 1059, 1065, 1066
  on the surface of Earth, 494
Mechanical design, 453, 797
Meteorology, 883
Motion
  of a liquid, 1122, 1123, 1127
  of a spring, 531
Moving ladder, 93, 158
Moving shadow, 159, 160, 162, 163
Muzzle velocity, 761
Navigation, 699, 761
Newton's Law of Cooling, 419, 422
Newton's Law of Gravitation, 1045
Newton's Law of Universal Gravitation, 487, 492, 854
Oblateness of Saturn, 473
Ohm's Law, 241
Oil leak, 294
Orbit
  of Earth, 698
  of the moon, 690
  of a satellite, 698, 731, 870
Orbital speed, 854
Parabolic reflector, 688
Particle motion, 132, 291, 294, 295, 698, 717, 827, 835, 837, 844, 853, 854, 865
Path
  of a ball, 706, 842
  of a baseball, 709, 841, 842, 843, 864
  of a football, 843
  of a projectile, 186, 716, 842, 843
  of a shot, 843
Pendulum, 142, 241, 910
Planetary motion, 745
Planetary orbits, 691
Power, 173, 910
Producing a machine part, 463
Projectile motion, 164, 241, 679, 709, 761, 840, 842, 843, 851, 853, 854, 864, 868, 870, 917
Psychrometer, 844
Radioactive decay, 352, 417, 421, 430, 440
Rectilinear motion, 257
Refraction of light, 963
Resultant force, 758, 760, 761
Resultant velocity, 758
Ripples in a pond, 29, 153
Rotary engine, 747
Satellite antenna, 747
Satellites, 131
Sending a space module into orbit, 488, 575
Solar collector, 697
Sound intensity, 323, 422
Specific gravity of water, 198
Speed of sound, 286
Surveying, 241, 565
Suspension bridge, 484
Temperature, 18, 180, 208, 322, 340, 413, 963
  normal daily maximum in Chicago, 142
  at which water boils, 323
Temperature distribution, 882, 902, 925, 930, 968
Theory of Relativity, 93
Topography, 875, 929, 930

(continued on back inside cover)

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Tear out Formula Cards for Homework Success.

DERIVATIVES AND INTEGRALS

Basic Differentiation Rules

1. $\frac{d}{dx}[cu] = cu'$
2. $\frac{d}{dx}[u \pm v] = u' \pm v'$
3. $\frac{d}{dx}[uv] = uv' + vu'$
4. $\frac{d}{dx}\left[\frac{u}{v}\right] = \frac{vu' - uv'}{v^2}$
5. $\frac{d}{dx}[c] = 0$
6. $\frac{d}{dx}[u^n] = nu^{n-1}u'$
7. $\frac{d}{dx}[x] = 1$
8. $\frac{d}{dx}[|u|] = \frac{u}{|u|}(u'), \quad u \neq 0$
9. $\frac{d}{dx}[\ln u] = \frac{u'}{u}$
10. $\frac{d}{dx}[e^u] = e^u u'$
11. $\frac{d}{dx}[\log_a u] = \frac{u'}{(\ln a)u}$
12. $\frac{d}{dx}[a^u] = (\ln a)a^u u'$
13. $\frac{d}{dx}[\sin u] = (\cos u)u'$
14. $\frac{d}{dx}[\cos u] = -(\sin u)u'$
15. $\frac{d}{dx}[\tan u] = (\sec^2 u)u'$
16. $\frac{d}{dx}[\cot u] = -(\csc^2 u)u'$
17. $\frac{d}{dx}[\sec u] = (\sec u \tan u)u'$
18. $\frac{d}{dx}[\csc u] = -(\csc u \cot u)u'$
19. $\frac{d}{dx}[\arcsin u] = \frac{u'}{\sqrt{1 - u^2}}$
20. $\frac{d}{dx}[\arccos u] = \frac{-u'}{\sqrt{1 - u^2}}$
21. $\frac{d}{dx}[\arctan u] = \frac{u'}{1 + u^2}$
22. $\frac{d}{dx}[\operatorname{arccot} u] = \frac{-u'}{1 + u^2}$
23. $\frac{d}{dx}[\operatorname{arcsec} u] = \frac{u'}{|u|\sqrt{u^2 - 1}}$
24. $\frac{d}{dx}[\operatorname{arccsc} u] = \frac{-u'}{|u|\sqrt{u^2 - 1}}$
25. $\frac{d}{dx}[\sinh u] = (\cosh u)u'$
26. $\frac{d}{dx}[\cosh u] = (\sinh u)u'$
27. $\frac{d}{dx}[\tanh u] = (\operatorname{sech}^2 u)u'$
28. $\frac{d}{dx}[\coth u] = -(\operatorname{csch}^2 u)u'$
29. $\frac{d}{dx}[\operatorname{sech} u] = -(\operatorname{sech} u \tanh u)u'$
30. $\frac{d}{dx}[\operatorname{csch} u] = -(\operatorname{csch} u \coth u)u'$
31. $\frac{d}{dx}[\sinh^{-1} u] = \frac{u'}{\sqrt{u^2 + 1}}$
32. $\frac{d}{dx}[\cosh^{-1} u] = \frac{u'}{\sqrt{u^2 - 1}}$
33. $\frac{d}{dx}[\tanh^{-1} u] = \frac{u'}{1 - u^2}$
34. $\frac{d}{dx}[\coth^{-1} u] = \frac{u'}{1 - u^2}$
35. $\frac{d}{dx}[\operatorname{sech}^{-1} u] = \frac{-u'}{u\sqrt{1 - u^2}}$
36. $\frac{d}{dx}[\operatorname{csch}^{-1} u] = \frac{-u'}{|u|\sqrt{1 + u^2}}$

Basic Integration Formulas

1. $\int kf(u)\,du = k\int f(u)\,du$
2. $\int [f(u) \pm g(u)]\,du = \int f(u)\,du \pm \int g(u)\,du$
3. $\int du = u + C$
4. $\int u^n\,du = \frac{u^{n+1}}{n+1} + C, \quad n \neq -1$
5. $\int \frac{du}{u} = \ln|u| + C$
6. $\int e^u\,du = e^u + C$
7. $\int a^u\,du = \left(\frac{1}{\ln a}\right)a^u + C$
8. $\int \sin u\,du = -\cos u + C$
9. $\int \cos u\,du = \sin u + C$
10. $\int \tan u\,du = -\ln|\cos u| + C$
11. $\int \cot u\,du = \ln|\sin u| + C$
12. $\int \sec u\,du = \ln|\sec u + \tan u| + C$
13. $\int \csc u\,du = -\ln|\csc u + \cot u| + C$
14. $\int \sec^2 u\,du = \tan u + C$
15. $\int \csc^2 u\,du = -\cot u + C$
16. $\int \sec u \tan u\,du = \sec u + C$
17. $\int \csc u \cot u\,du = -\csc u + C$
18. $\int \frac{du}{\sqrt{a^2 - u^2}} = \arcsin\frac{u}{a} + C$
19. $\int \frac{du}{a^2 + u^2} = \frac{1}{a}\arctan\frac{u}{a} + C$
20. $\int \frac{du}{u\sqrt{u^2 - a^2}} = \frac{1}{a}\operatorname{arcsec}\frac{|u|}{a} + C$

© Cengage Learning

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

TRIGONOMETRY

Definition of the Six Trigonometric Functions

Right triangle definitions, where $0 < \theta < \pi/2$.



$$\sin\theta = \frac{\text{opp}}{\text{hyp}} \quad \csc\theta = \frac{\text{hyp}}{\text{opp}}$$
$$\cos\theta = \frac{\text{adj}}{\text{hyp}} \quad \sec\theta = \frac{\text{hyp}}{\text{adj}}$$
$$\tan\theta = \frac{\text{opp}}{\text{adj}} \quad \cot\theta = \frac{\text{adj}}{\text{opp}}$$

Circular function definitions, where θ is any angle.



$$\sin\theta = \frac{y}{r} \quad \csc\theta = \frac{r}{y}$$
$$\cos\theta = \frac{x}{r} \quad \sec\theta = \frac{r}{x}$$
$$\tan\theta = \frac{y}{x} \quad \cot\theta = \frac{x}{y}$$



Reciprocal Identities

$$\sin x = \frac{1}{\csc x} \quad \cos x = \frac{1}{\sec x} \quad \tan x = \frac{1}{\cot x}$$
$$\csc x = \frac{1}{\sin x} \quad \sec x = \frac{1}{\cos x} \quad \cot x = \frac{1}{\tan x}$$

Quotient Identities

$$\tan x = \frac{\sin x}{\cos x} \quad \cot x = \frac{\cos x}{\sin x}$$

Pythagorean Identities

$$\sin^2 x + \cos^2 x = 1$$
$$1 + \tan^2 x = \sec^2 x \qquad 1 + \cot^2 x = \csc^2 x$$

Cofunction Identities

$$\sin\left(\frac{\pi}{2} - x\right) = \cos x \qquad \cos\left(\frac{\pi}{2} - x\right) = \sin x$$
$$\csc\left(\frac{\pi}{2} - x\right) = \sec x \qquad \tan\left(\frac{\pi}{2} - x\right) = \cot x$$
$$\sec\left(\frac{\pi}{2} - x\right) = \csc x \qquad \cot\left(\frac{\pi}{2} - x\right) = \tan x$$

Even/Odd Identities

$$\sin(-x) = -\sin x \qquad \cos(-x) = \cos x$$
$$\csc(-x) = -\csc x \qquad \tan(-x) = -\tan x$$
$$\sec(-x) = \sec x \qquad \cot(-x) = -\cot x$$

Sum and Difference Formulas

$$\sin(u \pm v) = \sin u \cos v \pm \cos u \sin v$$
$$\cos(u \pm v) = \cos u \cos v \mp \sin u \sin v$$
$$\tan(u \pm v) = \frac{\tan u \pm \tan v}{1 \mp \tan u \tan v}$$

Double-Angle Formulas

$$\sin 2u = 2 \sin u \cos u$$
$$\cos 2u = \cos^2 u - \sin^2 u = 2\cos^2 u - 1 = 1 - 2\sin^2 u$$
$$\tan 2u = \frac{2\tan u}{1 - \tan^2 u}$$

Power-Reducing Formulas

$$\sin^2 u = \frac{1 - \cos 2u}{2}$$
$$\cos^2 u = \frac{1 + \cos 2u}{2}$$
$$\tan^2 u = \frac{1 - \cos 2u}{1 + \cos 2u}$$

Sum-to-Product Formulas

$$\sin u + \sin v = 2\sin\left(\frac{u+v}{2}\right)\cos\left(\frac{u-v}{2}\right)$$
$$\sin u - \sin v = 2\cos\left(\frac{u+v}{2}\right)\sin\left(\frac{u-v}{2}\right)$$
$$\cos u + \cos v = 2\cos\left(\frac{u+v}{2}\right)\cos\left(\frac{u-v}{2}\right)$$
$$\cos u - \cos v = -2\sin\left(\frac{u+v}{2}\right)\sin\left(\frac{u-v}{2}\right)$$

Product-to-Sum Formulas

$$\sin u \sin v = \frac{1}{2}[\cos(u - v) - \cos(u + v)]$$
$$\cos u \cos v = \frac{1}{2}[\cos(u - v) + \cos(u + v)]$$
$$\sin u \cos v = \frac{1}{2}[\sin(u + v) + \sin(u - v)]$$
$$\cos u \sin v = \frac{1}{2}[\sin(u + v) - \sin(u - v)]$$

© Cengage Learning

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

CALCULUS

with CalcChat® and CalcView®

12e

Ron Larson

The Pennsylvania State University
The Behrend College

Bruce Edwards

University of Florida

CENGAGE

Australia • Brazil • Canada • Mexico • Singapore • United Kingdom • United States

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

This is an electronic version of the print textbook. Due to electronic rights restrictions, some third party content may be suppressed. Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. The publisher reserves the right to remove content from this title at any time if subsequent rights restrictions require it. For valuable information on pricing, previous editions, changes to current editions, and alternate formats, please visit www.cengage.com/highered to search by ISBN#, author, title, or keyword for materials in your areas of interest.

Important Notice: Media content referenced within the product description or the product text may not be available in the eBook version.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

CENGAGE

Calculus
with CalcChat® and CalcView®
Twelfth Edition
Ron Larson
Bruce Edwards

SVP, Higher Education Product Management: Erin Joyner
VP, Product Management, Learning Experiences: Thais Alencar
Product Director: Mark Santee
Senior Product Manager: Gary Whalen
Senior Product Assistant: Tim Rogers
Senior Learning Designer: Laura Gallus
Content Manager: Rachel Pancare
Manufacturing Planner: Ron Montgomery
Digital Delivery Quality Partner: Nikkita Kendrick
Director, Product Marketing: Jennifer Fink
Executive Marketing Manager: Tom Ziolkowski
IP Analyst: Ashley Maynard
IP Project Manager: Nick Barrows
Production Service: Larson Texts, Inc.
Compositor: Larson Texts, Inc.
Text and Cover Designer: Larson Texts, Inc.
Illustrator: Larson Texts, Inc.
Cover Image Source: Philipp Tur/Shutterstock.com

© 2023, 2018, 2014 Cengage Learning, Inc. ALL RIGHTS RESERVED.

WCN: 02-300

No part of this work covered by the copyright herein may be reproduced or distributed in any form or by any means, except as permitted by U.S. copyright law, without the prior written permission of the copyright owner.

Unless otherwise noted, all content is © Cengage.

For product information and technology assistance, contact us at **Cengage Customer & Sales Support, 1-800-354-9706 or support.cengage.com.**

For permission to use material from this text or product, submit all requests online at **www.copyright.com.**

Library of Congress Control Number: 2021943658

Student Edition
ISBN: 978-0-357-74913-5

Loose-leaf Edition
ISBN: 978-0-357-74916-6

Cengage
200 Pier 4 Boulevard
Boston, MA 02210
USA

Cengage is a leading provider of customized learning solutions with employees residing in nearly 40 different countries and sales in more than 125 countries around the world. Find your local representative at **www.cengage.com.**

To learn more about Cengage platforms and services, register or access your online learning solution, or purchase materials for your course, visit **www.cengage.com.**

Printed in the United States of America
Print Number: 01 Print Year: 2022

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Contents

P Preparation for Calculus 1

P.1 Graphs and Models 2
P.2 Linear Models and Rates of Change 10
P.3 Functions and Their Graphs 19
P.4 Review of Trigonometric Functions 31
Review Exercises 41
P.S. Problem Solving 44

1 Limits and Their Properties 45

1.1 A Preview of Calculus 46
1.2 Finding Limits Graphically and Numerically 52
1.3 Evaluating Limits Analytically 63
1.4 Continuity and One-Sided Limits 74
1.5 Infinite Limits 87
Section Project: Graphs and Limits of Trigonometric Functions 94
Review Exercises 95
P.S. Problem Solving 98

2 Differentiation 99

2.1 The Derivative and the Tangent Line Problem 100
2.2 Basic Differentiation Rules and Rates of Change 110
2.3 Product and Quotient Rules and Higher-Order Derivatives 122
2.4 The Chain Rule 133
2.5 Implicit Differentiation 144
Section Project: Optical Illusions 151
2.6 Related Rates 152
Review Exercises 161
P.S. Problem Solving 164

3 Applications of Differentiation 165

3.1 Extrema on an Interval 166
3.2 Rolle's Theorem and the Mean Value Theorem 174
3.3 Increasing and Decreasing Functions and the First Derivative Test 181
Section Project: Even Polynomial Functions of Fourth Degree 190
3.4 Concavity and the Second Derivative Test 191
3.5 Limits at Infinity 199
3.6 A Summary of Curve Sketching 209
3.7 Optimization Problems 219
Section Project: Minimum Time 228
3.8 Newton's Method 229
3.9 Differentials 235
Review Exercises 242
P.S. Problem Solving 246

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

4 Integration **247**

4.1 Antiderivatives and Indefinite Integration 248
4.2 Area 258
4.3 Riemann Sums and Definite Integrals 270
4.4 The Fundamental Theorem of Calculus 281
4.5 Integration by Substitution 296
Section Project: Probability 308
Review Exercises 309
P.S. Problem Solving 312

5 Logarithmic, Exponential, and Other Transcendental Functions **313**

5.1 The Natural Logarithmic Function: Differentiation 314
5.2 The Natural Logarithmic Function: Integration 324
5.3 Inverse Functions 333
5.4 Exponential Functions: Differentiation and Integration 342
5.5 Bases Other than *e* and Applications 352
Section Project: Using a Graphing Utility to Estimate Slope 361
5.6 Indeterminate Forms and L'Hôpital's Rule 362
5.7 Inverse Trigonometric Functions: Differentiation 373
5.8 Inverse Trigonometric Functions: Integration 382
5.9 Hyperbolic Functions 390
Section Project: Mercator Map 399
Review Exercises 400
P.S. Problem Solving 404

6 Differential Equations **405**

6.1 Slope Fields and Euler's Method 406
6.2 Growth and Decay 415
6.3 Separation of Variables and the Logistic Equation 423
6.4 First-Order Linear Differential Equations 432
Section Project: Weight Loss 438
Review Exercises 439
P.S. Problem Solving 442

7 Applications of Integration **443**

7.1 Area of a Region Between Two Curves 444
7.2 Volume: The Disk Method 454
7.3 Volume: The Shell Method 465
Section Project: Saturn 473
7.4 Arc Length and Surfaces of Revolution 474
7.5 Work 485
Section Project: Pyramid of Khufu 493
7.6 Moments, Centers of Mass, and Centroids 494
7.7 Fluid Pressure and Fluid Force 505
Review Exercises 511
P.S. Problem Solving 514

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

8 Integration Techniques and Improper Integrals 515

8.1 Basic Integration Rules 516
8.2 Integration by Parts 523
8.3 Trigonometric Integrals 532
Section Project: The Wallis Product 540
8.4 Trigonometric Substitution 541
8.5 Partial Fractions 550
8.6 Numerical Integration 559
8.7 Integration by Tables and Other Integration Techniques 566
8.8 Improper Integrals 572
Review Exercises 583
P.S. Problem Solving 586

9 Infinite Series 587

9.1 Sequences 588
9.2 Series and Convergence 599
Section Project: Cantor's Disappearing Table 608
9.3 The Integral Test and *p*-Series 609
Section Project: The Harmonic Series 615
9.4 Comparisons of Series 616
9.5 Alternating Series 623
9.6 The Ratio and Root Tests 631
9.7 Taylor Polynomials and Approximations 640
9.8 Power Series 651
9.9 Representation of Functions by Power Series 661
9.10 Taylor and Maclaurin Series 668
Review Exercises 680
P.S. Problem Solving 684

10 Conics, Parametric Equations, and Polar Coordinates 685

10.1 Conics and Calculus 686
10.2 Plane Curves and Parametric Equations 700
Section Project: Cycloids 709
10.3 Parametric Equations and Calculus 710
10.4 Polar Coordinates and Polar Graphs 719
Section Project: Cassini Oval 728
10.5 Area and Arc Length in Polar Coordinates 729
10.6 Polar Equations of Conics and Kepler's Laws 738
Review Exercises 746
P.S. Problem Solving 750

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

11 Vectors and the Geometry of Space **751**

11.1 Vectors in the Plane 752
11.2 Space Coordinates and Vectors in Space 762
11.3 The Dot Product of Two Vectors 770
11.4 The Cross Product of Two Vectors in Space 779
11.5 Lines and Planes in Space 787
Section Project: Distances in Space 797
11.6 Surfaces in Space 798
11.7 Cylindrical and Spherical Coordinates 808
Review Exercises 815
P.S. Problem Solving 818

12 Vector-Valued Functions **819**

12.1 Vector-Valued Functions 820
Section Project: Witch of Agnesi 827
12.2 Differentiation and Integration of Vector-Valued Functions 828
12.3 Velocity and Acceleration 836
12.4 Tangent Vectors and Normal Vectors 845
12.5 Arc Length and Curvature 855
Review Exercises 867
P.S. Problem Solving 870

13 Functions of Several Variables **871**

13.1 Introduction to Functions of Several Variables 872
13.2 Limits and Continuity 884
13.3 Partial Derivatives 894
13.4 Differentials 904
13.5 Chain Rules for Functions of Several Variables 911
13.6 Directional Derivatives and Gradients 919
13.7 Tangent Planes and Normal Lines 931
Section Project: Wildflowers 939
13.8 Extrema of Functions of Two Variables 940
13.9 Applications of Extrema 948
Section Project: Building a Pipeline 955
13.10 Lagrange Multipliers 956
Review Exercises 964
P.S. Problem Solving 968

14 Multiple Integration **969**

14.1 Iterated Integrals and Area in the Plane 970
14.2 Double Integrals and Volume 978
14.3 Change of Variables: Polar Coordinates 990
14.4 Center of Mass and Moments of Inertia 998
Section Project: Center of Pressure on a Sail 1005
14.5 Surface Area 1006
Section Project: Surface Area in Polar Coordinates 1012
14.6 Triple Integrals and Applications 1013
14.7 Triple Integrals in Other Coordinates 1024
Section Project: Wrinkled and Bumpy Spheres 1030
14.8 Change of Variables: Jacobians 1031
Review Exercises 1038
P.S. Problem Solving 1042

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

15 Vector Analysis **1043**

15.1 Vector Fields 1044
15.2 Line Integrals 1055
15.3 Conservative Vector Fields and Independence of Path 1069
15.4 Green's Theorem 1079
Section Project: Hyperbolic and Trigonometric Functions 1087
15.5 Parametric Surfaces 1088
15.6 Surface Integrals 1098
Section Project: Hyperboloid of One Sheet 1109
15.7 Divergence Theorem 1110
15.8 Stokes's Theorem 1118
Review Exercises 1124
P.S. Problem Solving 1128

16 Additional Topics in Differential Equations (Online)*

16.1 Exact First-Order Equations
16.2 Second-Order Homogeneous Linear Equations
16.3 Second-Order Nonhomogeneous Linear Equations
Section Project: Parachute Jump
16.4 Series Solutions of Differential Equations
Review Exercises
P.S. Problem Solving

Appendices

Appendix A: **Proofs of Selected Theorems** A2
Appendix B: **Integration Tables** A3
Appendix C: **Precalculus Review (Online)***
Appendix D: **Rotation and the General Second-Degree Equation (Online)***
Appendix E: **Complex Numbers (Online)***
Appendix F: **Business and Economic Applications (Online)***
Appendix G: **Fitting Models to Data (Online)***

Answers to All Odd-Numbered Exercises A7
Index A123

*Available at the text companion website *LarsonCalculus.com*

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Preface

Welcome to *Calculus* with CalcChat® and CalcView®, Twelfth Edition. We are excited to offer you a new edition with more resources then ever that will help you understand and master calculus. This text includes features and resources that continue to make *Calculus* a valuable learning tool for students and a trustworthy teaching tool for instructors.

Calculus provides the clear instruction, precise mathematics, and thorough coverage that you expect for your course. Additionally, this new edition provides you with **free** access to a variety of digital resources.

- **GO DIGITAL**—direct access to digital content on your mobile device or computer
- **CalcView.com**—video solutions to selected exercises
- **CalcChat.com**—worked-out solutions to odd-numbered exercises and access to online tutors
- **LarsonCalculus.com**—companion website with resources to supplement your learning

These digital resources will help enhance and reinforce your understanding of the material presented in this text and prepare you for future mathematics courses. CalcView® and CalcChat® are also available as free mobile apps.

Features

NEW GO DIGITAL

Scan the on-page codes of this text to *GO DIGITAL* on your mobile device. This will give you easy access to

- instructional and proof videos,
- interactive examples,
- solutions to exercises,
- free online tutoring,

and many other resources.

UPDATED CalcView®

The website *CalcView.com* provides video solutions of selected exercises. Watch instructors progress step-by-step through solutions, providing guidance to help you solve the exercises. The CalcView mobile app is available for free at the Apple® App Store® or Google Play™ store. You can access the video solutions by scanning the on-page codes at the beginning of the section exercises or visiting the *CalcView.com* website.

UPDATED CalcChat®

Solutions to all odd-numbered exercises are provided for free at *CalcChat.com.* Additionally, you can chat with a tutor, at no charge, during the hours posted at the site. **For over 20 years, millions of students have visited our site for help!** The CalcChat mobile app is also available as a free download at the Apple® App Store® or Google Play™ store.

UPDATED LarsonCalculus.com

All companion website features have been updated based on this revision. Watch videos explaining concepts or proofs from the text, explore examples, view three-dimensional graphs, download articles from math journals, and much more.

App Store is a service mark of Apple Inc. Google Play is a trademark of Google Inc.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

NEW Big Ideas of Calculus

We have added a new feature to help you discover and understand the Big Ideas of Calculus. This feature, which is denoted by , has four parts.

- The **Big Ideas of Calculus** notes give you an overview of the major concepts of a chapter and how they relate to the earlier concepts you have studied. These notes appear near the beginning of a chapter and in the chapter review.
- In each section and in the chapter review, make sure you do the **Concept Check** exercises and the **Exploring Concepts** exercises. These exercises will help you develop a deeper and clearer knowledge of calculus. Work through these exercises to build and strengthen your understanding of the concepts.
- To continue exploring calculus, do the **Building on Concepts** exercises at the end of the chapter review. Not only will these exercises help you expand your knowledge and use of calculus, they will prepare you to learn concepts in later chapters.

Big Ideas of Calculus

In this chapter, you will study integration. Integration, like differentiation, is a major theme of calculus. Interestingly, as you will learn in the Fundamental Theorem of Calculus, these two major themes have an inverse relationship. As part of your study of integration, you will examine the areas of plane regions.

Concept Check

1. Explain what it means for a function F to be an antiderivative of a function f on an interval I.
2. Can two different functions both be antiderivatives of the same function? Explain.
3. Explain how to find a particular solution of a differential equation.
4. Describe the difference between the general solution and a particular solution of a differential equation.

Exploring Concepts

In Exercises 49 and 50, the graph of the derivative of a function is given. Sketch the graphs of *two* functions that have the given derivative. (There is more than one correct answer.) To print an enlarged copy of the graph, go to *MathGraphs.com*.

49.



50.



Building on Concepts

75. Consider the function

$$F(x) = \int_0^x \sin^2 t\, dt.$$

(a) Evaluate F at $x = 0, \pi/6, \pi/3, \pi/2, 2\pi/3, 5\pi/6$, and π. Are the values of F increasing or decreasing? Explain.

(b) Use the integration capabilities of a graphing utility to graph F and $y_1 = \sin^2 t$ on the interval $0 \le t \le \pi$.

(c) Use the differentiation capabilities of a graphing utility to graph F'. How is this graph related to the graph in part (b)?

(d) Verify that $\sin^2 t$ is the derivative of

$$y = \frac{1}{2}t - \frac{1}{4}\sin 2t.$$

Graph y and write a short paragraph about how this graph is related to those in parts (b) and (c).

UPDATED Exercise Sets

The exercise sets have been carefully and extensively examined to ensure they are rigorous and relevant and to include topics our users have suggested. The exercises are organized and titled so you can better see the connections between examples and exercises. Multi-step, real-life exercises reinforce problem-solving skills and mastery of concepts by giving you the opportunity to apply the concepts in real-life situations.

Section Projects

Projects appear in selected sections and encourage you to explore applications related to the topics you are studying. All of these projects provide an interesting and engaging way for you and other students to work and investigate ideas collaboratively.

UPDATED Chapter Opener

Each Chapter Opener highlights real-life applications used in the examples and exercises. For this edition, we also highlight the online resources at *CalcView.com* and *CalcChat.com*.

SECTION PROJECT

Graphs and Limits of Trigonometric Functions

Recall from Theorem 1.9 that the limit of

$$f(x) = \frac{\sin x}{x}$$

as x approaches 0 is 1.

(a) Use a graphing utility to graph the function f on the interval $-\pi \le x \le \pi$. Explain how the graph helps confirm this theorem.

(b) Explain how you could use a table of values to confirm the value of this limit numerically.

(c) Graph $g(x) = \sin x$ by hand. Sketch a tangent line at the point $(0, 0)$ and visually estimate the slope of this tangent line.

(d) Let $(x, \sin x)$ be a point on the graph of g near $(0, 0)$, and write a formula for the slope of the secant line joining $(x, \sin x)$ and $(0, 0)$. Evaluate this formula at $x = 0.1$ and $x = 0.01$. Then find the exact slope of the tangent line to g at the point $(0, 0)$.

(e) Sketch the graph of the cosine function $h(x) = \cos x$. What is the slope of the tangent line at the point $(0, 1)$? Use limits to find this slope analytically.

(f) Find the slope of the tangent line to $k(x) = \tan x$ at $(0, 0)$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Section Objectives
A bulleted list of learning objectives provides you with the opportunity to preview what will be presented in the upcoming section.

Theorems
Theorems provide the conceptual framework for calculus. Theorems are clearly stated and separated from the rest of the text by boxes for quick visual reference. Key proofs often follow the theorem and can be found at *LarsonCalculus.com.*

Definitions
As with theorems, definitions are clearly stated using precise, formal wording and are separated from the text by boxes for quick visual reference.

Explorations
Explorations provide unique challenges to study concepts that have not yet been formally covered in the text. They allow you to learn by discovery and introduce topics related to ones presently being studied. Exploring topics in this way encourages you to think outside the box.

UPDATED Remarks
These hints and tips reinforce or expand upon concepts, help you learn how to study mathematics, caution you about common errors, address special cases, or show an alternative solution to an example. We have added several new Remarks to help students who need more in-depth algebra support.


166 Chapter 3 Applications of Differentiation

3.1 Extrema on an Interval

GO DIGITAL

- Define extrema of a function on an interval.
- Define relative extrema of a function on an open interval.
- Find extrema on a closed interval.

Extrema of a Function

In calculus, much effort is devoted to determining the behavior of a function f on an interval I. Does f have a maximum value on I? Does it have a minimum value? Where is the function increasing? Where is it decreasing? In this chapter, you will learn how derivatives can be used to answer these questions. You will also see why these questions are important in real-life applications.

Definition of Extrema

Let a function f be defined on an interval I containing c.

1. $f(c)$ is the **minimum of f on I** when $f(c) \leq f(x)$ for all x in I.
2. $f(c)$ is the **maximum of f on I** when $f(c) \geq f(x)$ for all x in I.

The minimum and maximum of a function on an interval are the **extreme values,** or **extrema** (the singular form of extrema is extremum), of the function on the interval. The minimum and maximum of a function on an interval are also called the **absolute minimum** and **absolute maximum,** or the **global minimum** and **global maximum,** on the interval. Extrema can occur at interior points or endpoints of an interval (see Figure 3.1). Extrema that occur at the endpoints are called **endpoint extrema.**

A function need not have a minimum or a maximum on an interval. For instance, in Figures 3.1(a) and (b), you can see that the function $f(x) = x^2 + 1$ has both a minimum and a maximum on the closed interval $[-1, 2]$ but does not have a maximum on the open interval $(-1, 2)$. Moreover, in Figure 3.1(c), you can see that continuity (or the lack of it) can affect the existence of an extremum on the interval. This suggests the theorem below. (Although the Extreme Value Theorem is intuitively plausible, a proof of this theorem is not within the scope of this text.)

THEOREM 3.1 The Extreme Value Theorem

If a function f is continuous on a closed interval $[a, b]$, then f has both a minimum and a maximum on the interval.

Exploration

Finding Minimum and Maximum Values The Extreme Value Theorem (like the Intermediate Value Theorem) is an *existence theorem* because it tells of the existence of minimum and maximum values but does not show how to find these values. Use the *minimum* and *maximum* features of a graphing utility to find the extrema of each function. In each case, do you think the x-values are exact or approximate? Explain your reasoning.

a. $f(x) = x^2 - 4x + 5$ on the closed interval $[-1, 3]$

b. $f(x) = x^3 - 2x^2 - 3x - 2$ on the closed interval $[-1, 3]$

(a) f is continuous; $[-1, 2]$ is closed.

(b) f is continuous; $(-1, 2)$ is open.

(c) g is not continuous; $[-1, 2]$ is closed.

Figure 3.1

UPDATED Historical Notes and Biographies
Historical Notes provide you with background information on the foundations of calculus. The Biographies introduce you to the people who created and contributed to calculus. We have added several new biographies, and more biographies are available at *LarsonCalculus.com*.

Technology
Throughout the book, technology boxes show you how to use technology to solve problems and explore concepts of calculus. These tips also point out some pitfalls of using technology.

How Do You See It? Exercise
The How Do You See It? exercise in each section presents a problem that you will solve by visual inspection using the concepts learned in the lesson.

UPDATED Applications
Carefully chosen applied exercises and examples are included throughout to address the question, "When will I use this?" These applications are pulled from diverse sources, such as current events, world data, industry trends, and more, and relate to a wide range of interests. Understanding where calculus is (or can be) used promotes fuller understanding of the material.

Putnam Exam Challenges
Putnam Exam questions appear in selected sections. These actual Putnam Exam questions will challenge you and push the limits of your understanding of calculus.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Student Resources

CENGAGE | WEBASSIGN

Prepare for class with confidence using WebAssign from Cengage. This online learning platform, which includes an interactive eBook, fuels practice so that you truly absorb what you learn and prepare better for tests. Videos and tutorials walk you through concepts and deliver instant feedback and grading, so you always know where you stand in class. Focus your study time and get extra practice where you need it most. Study smarter with WebAssign! Ask your instructor today how you can get access to WebAssign, or learn about self-study options at *cengage.com/webassign*.

Student Solutions Manual

Student Solutions Manual for Calculus of a Single Variable, 12e
(ISBN-13: 978-0-357-74919-7)
Student Solutions Manual for Multivariable Calculus, 12e
(ISBN-13: 978-0-357-74920-3)
These manuals provide step-by-step solutions for all odd-numbered exercises, including Review Exercises and P.S. Problem Solving. The manual for *Calculus of a Single Variable* contains solutions for Chapters P–10, and the manual for *Multivariable Calculus* contains solutions for Chapters 11–16.

Cengage.com

Additional student resources for this product are available online. Sign up or sign in at *cengage.com* to search for and access this product and its online resources.

LarsonCalculus.com

Of the many features at this website, students have told us that the videos are the most helpful. Watch instructional videos presented by Dana Mosely, as he explains various calculus concepts. Watch proof videos presented by Bruce Edwards, as he explains various calculus theorems and their proofs. Other helpful features are the data downloads (editable spreadsheets so you do not have to enter the data), algebra help videos, interactive examples, and much more. You can access these features by going to *LarsonCalculus.com* or by scanning the on-page code .

CalcChat.com

This website provides free step-by-step solutions to all odd-numbered exercises and tests. Additionally, you can chat with a tutor, at no charge, during the hours posted at the site. You can access the solutions by going to *CalcChat.com* or by scanning the on-page code on the first page of any exercise set.

CalcView.com

This website has free video solutions of selected exercises. Watch instructors progress step-by-step through solutions, providing guidance to help you solve the exercises. You can access the videos by going to *CalcView.com* or by scanning the on-page code on the first page of the section exercises.

MathGraphs.com

For exercises that ask you to draw on the graph, we have provided free, printable graphs at *MathGraphs.com*. You can access the printable graphs by going to *MathGraphs.com* or by scanning the on-page code on the first page of any exercise set.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Instructor Resources

CENGAGE | WEBASSIGN

Built by educators, WebAssign from Cengage is a fully customizable online solution for STEM disciplines. WebAssign includes the flexibility, tools, and content you need to create engaging learning experiences for your students. The patented grading engine provides unparalleled answer evaluation, giving students instant feedback, and insightful analytics highlight exactly where students are struggling. For more information, visit *cengage.com/webassign*.

Cengage.com

Additional instructor resources for this product are available online. Instructor assets include an Instructor's Manual, Educator's Guide, PowerPoint® slides, a Solution and Answer Guide, and a test bank powered by Cognero®. Sign up or sign in at *cengage.com* to search for and access this product and its online resources. The Cengage Instructor Center is an all-in-one resource for class preparation, presentation, and testing. The instructor resources available for download include:

Instructor's Manual Includes activities and assessments correlated by learning objectives, chapter and section outline, key formulas and terms with definitions, ideas for student collaboration and class discussions, and more.

Solution and Answer Guide Provides answers and solutions to all exercises, including Review Exercises, P.S. Problem Solving, and Putnam Exam Challenge.

Cengage Testing Powered by Cognero® A flexible online system that allows you to author, edit, and manage test bank content online. You can create multiple tests in an instant and deliver them from your LMS, or export to printable PDF or Word format for in-class assessment.

PowerPoint® Slides The PowerPoint® slides are ready-to-use, visual outlines of each section that can be easily customized for your lectures. Presentations include activities, examples, and ample opportunities for student engagement and interaction.

Transition Guide Highlights the content changes from the previous edition to the new edition, including exercise correlations.

Guide to Online Teaching Provides technological and pedagogical considerations and tips for teaching a calculus course online.

Educator's Guide Offers suggested content and activities for Cengage WebAssign —like videos and assignments—that you can integrate into your course to help boost engagement and outcomes.

LarsonCalculus.com

In addition to its student resources, *LarsonCalculus.com* also has resources to help instructors. For students who need algebra help, we have provided instructional videos to explain various algebra and precalculus concepts. Students can assess their knowledge of these concepts through self-grading progress checks. You can also give your students experience using an online graphing utility with the Interactive Examples. You can access these features by going to *LarsonCalculus.com* or by scanning the on-page code .

MathArticles.com

This text contains over 50 references to articles from mathematics journals noted in the For Further Information feature. To make the articles easily accessible to instructors and students, they are available at *MathArticles.com* or by scanning the on-page code .

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Acknowledgments

We would like to thank the many people who have helped us at various stages of *Calculus* over the last 48 years. Their encouragement, criticisms, and suggestions have been invaluable.

Reviewers

Stan Adamski, *Owens Community College;* Tilak de Alwis; Darry Andrews; Alexander Arhangelskii, *Ohio University;* Seth G. Armstrong, *Southern Utah University;* Jim Ball, *Indiana State University;* Denis Bell, *University of Northern Florida;* Marcelle Bessman, *Jacksonville University;* Abraham Biggs, *Broward Community College;* Jesse Blosser, *Eastern Mennonite School;* Linda A. Bolte, *Eastern Washington University;* James Braselton, *Georgia Southern University;* Harvey Braverman, *Middlesex County College;* Mark Brittenham, *University of Nebraska;* Tim Chappell, *Penn Valley Community College;* Fan Chen, *El Paso Community College;* Mingxiang Chen, *North Carolina A&T State University;* Oiyin Pauline Chow, *Harrisburg Area Community College;* Julie M. Clark, *Hollins University;* P.S. Crooke, *Vanderbilt University;* Jim Dotzler, *Nassau Community College;* Murray Eisenberg, *University of Massachusetts at Amherst;* Donna Flint, *South Dakota State University;* Michael Frantz, *University of La Verne;* David French, *Tidewater Community College;* Sudhir Goel, *Valdosta State University;* Arek Goetz, *San Francisco State University;* Donna J. Gorton, *Butler County Community College;* John Gosselin, *University of Georgia;* Arran Hamm; Shahryar Heydari, *Piedmont College;* Guy Hogan, *Norfolk State University;* Dr. Enayat Kalantarian, *El Paso Community College;* Marcia Kleinz, *Atlantic Cape Community College;* Ashok Kumar, *Valdosta State University;* Kevin J. Leith, *Albuquerque Community College;* Maxine Lifshitz, *Friends Academy;* Douglas B. Meade, *University of South Carolina;* Bill Meisel, *Florida State College at Jacksonville;* Shahrooz Moosavizadeh; Teri Murphy, *University of Oklahoma;* Darren Narayan, *Rochester Institute of Technology;* Susan A. Natale, *The Ursuline School, NY;* Martha Nega, *Georgia Perimeter College;* Francis Nkansah, *Bunker Hill Community College;* Sam Pearsall, *Los Angeles Pierce College;* Terence H. Perciante, *Wheaton College;* James Pommersheim, *Reed College;* Laura Ritter, *Southern Polytechnic State University;* Carson Rogers, *Boston College;* Leland E. Rogers, *Pepperdine University;* Paul Seeburger, *Monroe Community College;* Edith A. Silver, *Mercer County Community College;* Howard Speier, *Chandler-Gilbert Community College;* Desmond Stephens, *Florida A&M University;* Jianzhong Su, *University of Texas at Arlington;* James K. Vallade, *Monroe County Community College;* Patrick Ward, *Illinois Central College;* Chia-Lin Wu, *Richard Stockton College of New Jersey;* Diane M. Zych, *Erie Community College*

Many thanks to Robert Hostetler, The Behrend College, The Pennsylvania State University, and David Heyd, The Behrend College, The Pennsylvania State University, for their significant contributions to previous editions of this text.

We would also like to thank the staff at Larson Texts, Inc., who assisted in the production, composition, and illustration of the text and its supplements. Additionally, we are thankful for their help in developing and maintaining *CalcChat.com*, *CalcView.com*, *LarsonCalculus.com*, *MathArticles.com*, and *MathGraphs.com*.

On a personal level, we are grateful to our wives, Deanna Gilbert Larson and Consuelo Edwards, for their love, patience, and support. Also, a special note of thanks goes out to R. Scott O'Neil.

If you have suggestions for improving this text, please feel free to write to us. Over the years we have received many useful comments from both instructors and students, and we value these very much.

Ron Larson

Bruce Edwards

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P Preparation for Calculus

GO DIGITAL

P.1 Graphs and Models
P.2 Linear Models and Rates of Change
P.3 Functions and Their Graphs
P.4 Review of Trigonometric Functions

CalcView®



CalcChat®


Chapter P
Section 1
Exercise 45
GO
y = x³ + 2
y = 0³ + 2 = 2, y-intercept
0 = x³ + 2 ⇒ x³ = −2 ⇒ x = −∛2, x-intercept
Intercepts: (−∛2, 0), (0, 2)
Symmetry: none
PREV. 39 41 43 45 47 49 51 53 55 57 59 NEXT

P.3 Automobile Aerodynamics *(Exercise 101, p. 30)*

P.1 Modeling Carbon Dioxide Concentration *(Example 6, p. 7)*

left, Viaframe/Getty Images; right, iStockPhoto/trait2lumiere

© Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.1 Graphs and Models

GO DIGITAL

- **Sketch the graph of an equation.**
- **Find the intercepts of a graph.**
- **Test a graph for symmetry with respect to an axis and the origin.**
- **Find the points of intersection of two graphs.**
- **Interpret mathematical models for real-life data.**

RENÉ DESCARTES (1596–1650)

Descartes made many contributions to philosophy, science, and mathematics. The idea of representing points in the plane by pairs of real numbers and representing curves in the plane by equations was described by Descartes in his book *La Géométrie*, published in 1637.

See LarsonCalculus.com to read more of this biography.

The Graph of an Equation

In 1637, the French mathematician René Descartes revolutionized the study of mathematics by combining its two major fields—algebra and geometry. With Descartes's coordinate plane, geometric concepts could be formulated analytically and algebraic concepts could be viewed graphically. The power of this approach was such that within a century of its introduction, much of calculus had been developed.

The same approach can be followed in your study of calculus. That is, by viewing calculus from multiple perspectives—*graphically*, *analytically*, and *numerically*—you will increase your understanding of core concepts.

Consider the equation $3x + y = 7$. The point $(2, 1)$ is a **solution point** of the equation because the equation is satisfied (is true) when 2 is substituted for x and 1 is substituted for y. This equation has many other solutions, such as $(1, 4)$ and $(0, 7)$. To find other solutions systematically, solve the original equation for y.

$y = 7 - 3x$ Analytic approach

Then construct a **table of values** by substituting several values of x.

x	0	1	2	3	4
y	7	4	1	-2	-5

Numerical approach

From the table, note that $(0, 7)$, $(1, 4)$, $(2, 1)$, $(3, -2)$, and $(4, -5)$ are solutions of the original equation $3x + y = 7$. Like many equations, this equation has an infinite number of solutions. The set of all solution points is the **graph** of the equation, as shown in Figure P.1. Note that the sketch shown in Figure P.1 is referred to as the graph of $3x + y = 7$, even though it really represents only a *portion* of the graph. The entire graph would extend beyond the page.



Graphical approach: $3x + y = 7$
Figure P.1

In this course, you will study many sketching techniques. The simplest is point plotting—that is, you plot points until the basic shape of the graph seems apparent.

EXAMPLE 1 Sketching a Graph by Point Plotting

To sketch the graph of $y = x^2 - 2$, first construct a table of values. Next, plot the points shown in the table. Then connect the points with a smooth curve, as shown in Figure P.2. This graph is a **parabola.** It is one of the conics you will study in Chapter 10.

x	-2	-1	0	1	2	3
y	2	-1	-2	-1	2	7



The parabola $y = x^2 - 2$
Figure P.2

Scan the to access digital content available for this page.

iStockPhoto/GeorgiosArt

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

One disadvantage of point plotting is that to get a good idea about the shape of a graph, you may need to plot many points. With only a few points, you could badly misrepresent the graph. For instance, to sketch the graph of

$$y = \frac{1}{30}x(39 - 10x^2 + x^4)$$

you plot five points:

$$(-3, -3), \quad (-1, -1), \quad (0, 0), \quad (1, 1), \quad \text{and} \quad (3, 3)$$

as shown in Figure P.3(a). From these five points, you might conclude that the graph is a line. This, however, is not correct. By plotting several more points, you can see that the graph is more complicated, as shown in Figure P.3(b).



(a) (b)

Figure P.3

TECHNOLOGY Graphing an equation has been made easier by technology. Even with technology, however, it is possible to misrepresent a graph badly. For instance, each graphing utility* screen in Figure P.4 shows a portion of the graph of

$$y = x^3 - x^2 - 25.$$

From Figure P.4(a), you might assume that the graph is a line. From Figure P.4(b), however, you can see that the graph is not a line. So, when you are graphing an equation, either with or without a graphing utility, you must realize that different "viewing windows" can produce very different views of a graph. In choosing a viewing window, your goal is to show a view of the graph that fits well in the context of the problem.



(a) (b)

Graphing utility screens of $y = x^3 - x^2 - 25$

Figure P.4

Exploration

Comparing Graphical and Analytic Approaches

Use a graphing utility to graph each equation. In each case, find a viewing window that shows the important characteristics of the graph.

a. $y = x^3 - 3x^2 + 2x + 5$

b. $y = x^3 - 3x^2 + 2x + 25$

c. $y = -x^3 - 3x^2 + 20x + 5$

d. $y = 3x^3 - 40x^2 + 50x - 45$

e. $y = -(x + 12)^3$

f. $y = (x - 2)(x - 4)(x - 6)$

A purely graphical approach to this problem would involve a simple "guess, check, and revise" strategy. What types of things do you think an analytic approach might involve? For instance, does the graph have symmetry? Does the graph have turns? If so, where are they? Later, in Chapters 1, 2, and 3, you will study many new analytic tools that will help you analyze graphs of equations.

*In this text, the term *graphing utility* refers to graphing calculators (such as the *TI-Nspire* and *Desmos*) and mathematical software (such as *Maple* and *Mathematica*).

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

REMARK Some texts denote the x-intercept as the x-coordinate of the point $(a, 0)$ rather than the point itself. Unless it is necessary to make a distinction, when the term *intercept* is used in this text, it will mean either the point or the coordinate.

Intercepts of a Graph

Two types of solution points that are especially useful in graphing an equation are those having zero as their x- or y-coordinate. Such points are called **intercepts** because they are the points at which the graph intersects the x- or y-axis. The point $(a, 0)$ is an ***x*-intercept** of the graph of an equation when it is a solution point of the equation. To find the x-intercepts of a graph, let y be zero and solve the equation for x. The point $(0, b)$ is a ***y*-intercept** of the graph of an equation when it is a solution point of the equation. To find the y-intercepts of a graph, let x be zero and solve the equation for y.

It is possible for a graph to have no intercepts, or it might have several. For instance, consider the four graphs shown in Figure P.5.



No x-intercepts
One y-intercept

Three x-intercepts
One y-intercept

One x-intercept
Two y-intercepts

No intercepts

Figure P.5

EXAMPLE 2 Finding *x*- and *y*-Intercepts

Find the x- and y-intercepts of the graph of $y = x^3 - 4x$.

Solution To find the x-intercepts, let y be zero and solve for x.

$$x^3 - 4x = 0 \qquad \text{Let } y \text{ be zero.}$$
$$x(x^2 - 4) = 0 \qquad \text{Factor out common monomial factor.}$$
$$x(x - 2)(x + 2) = 0 \qquad \text{Factor difference of two squares.}$$
$$x = 0, 2, \text{ or } -2 \qquad \text{Solve for } x.$$

This equation has three solutions, so the graph has three x-intercepts:

$$(0, 0), \quad (2, 0), \quad \text{and} \quad (-2, 0). \qquad x\text{-intercepts}$$

To find the y-intercepts, let x be zero. Doing this produces $y = 0$. So, the y-intercept is

$$(0, 0). \qquad y\text{-intercept}$$

(See Figure P.6.)



Intercepts of a graph
Figure P.6

GO DIGITAL

TECHNOLOGY

Example 2 uses an analytic approach to find the intercepts. When an analytic approach is not possible, use a graphical approach to find the points at which the graph intersects the axes. Use the *trace* feature of a graphing utility to approximate the intercepts of the graph of the equation in Example 2. Note that the utility may have a *root* or *zero* feature that can find the x-intercepts of a graph. If so, use this feature to find the x-intercepts of the graph of the equation in Example 2.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure P.7

Symmetry of a Graph

Knowing the symmetry of a graph before attempting to sketch it is useful because you need only half as many points to sketch the graph. The three types of symmetry listed below can be used to help sketch the graphs of equations (see Figure P.7).

1. A graph is **symmetric with respect to the *y*-axis** if, whenever (x, y) is a point on the graph, then $(-x, y)$ is also a point on the graph. This means that the portion of the graph to the left of the y-axis is a mirror image of the portion to the right of the y-axis.
2. A graph is **symmetric with respect to the *x*-axis** if, whenever (x, y) is a point on the graph, then $(x, -y)$ is also a point on the graph. This means that the portion of the graph below the x-axis is a mirror image of the portion above the x-axis.
3. A graph is **symmetric with respect to the origin** if, whenever (x, y) is a point on the graph, then $(-x, -y)$ is also a point on the graph. This means that the graph is unchanged by a rotation of 180° about the origin.

Tests for Symmetry

1. The graph of an equation in x and y is symmetric with respect to the y-axis when replacing x by $-x$ yields an equivalent equation.
2. The graph of an equation in x and y is symmetric with respect to the x-axis when replacing y by $-y$ yields an equivalent equation.
3. The graph of an equation in x and y is symmetric with respect to the origin when replacing x by $-x$ and y by $-y$ yields an equivalent equation.

The graph of a polynomial has symmetry with respect to the y-axis when each term has an even exponent (or is a constant). For instance, the graph of

$$y = 2x^4 - x^2 + 2$$

has symmetry with respect to the y-axis. Similarly, the graph of a polynomial has symmetry with respect to the origin when each term has an odd exponent, as illustrated in Example 3.

EXAMPLE 3 Testing for Symmetry

Test the graph of $y = 2x^3 - x$ for symmetry with respect to (a) the y-axis and (b) the origin.

Solution

a. $y = 2x^3 - x$ Write original equation.

$y = 2(-x)^3 - (-x)$ Replace x by $-x$.

$y = -2x^3 + x$ Simplify. The result is *not* an equivalent equation.

Replacing x by $-x$ does *not* yield an equivalent equation, so the graph of $y = 2x^3 - x$ is *not* symmetric with respect to the y-axis.

b. $y = 2x^3 - x$ Write original equation.

$-y = 2(-x)^3 - (-x)$ Replace x by $-x$ and y by $-y$.

$-y = -2x^3 + x$ Simplify.

$y = 2x^3 - x$ Equivalent equation

Replacing x by $-x$ and y by $-y$ yields an equivalent equation, so the graph of $y = 2x^3 - x$ is symmetric with respect to the origin, as shown in Figure P.8. ■



Origin symmetry

Figure P.8

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



Figure P.9

EXAMPLE 4 Using Intercepts and Symmetry to Sketch a Graph

See LarsonCalculus.com for an interactive version of this type of example.

Sketch the graph of $x - y^2 = 1$.

Solution The graph is symmetric with respect to the x-axis because replacing y by $-y$ yields an equivalent equation.

$$\begin{aligned} x - y^2 &= 1 && \text{Write original equation.} \\ x - (-y)^2 &= 1 && \text{Replace } y \text{ by } -y. \\ x - y^2 &= 1 && \text{Equivalent equation} \end{aligned}$$

This means that the portion of the graph below the x-axis is a mirror image of the portion above the x-axis. To sketch the graph, first plot the x-intercept and the points above the x-axis. Then reflect in the x-axis to obtain the entire graph, as shown in Figure P.9. ■

TECHNOLOGY Some graphing utilities are designed so that they most easily graph equations in which y is a function of x (see Section P.3 for a definition of *function*). To graph other types of equations, you may need to split the graph into two or more parts *or* you may need to use a different graphing mode. For instance, one way to graph the equation in Example 4 is to split it into two parts.

$$\begin{aligned} y_1 &= \sqrt{x - 1} && \text{Top portion of graph} \\ y_2 &= -\sqrt{x - 1} && \text{Bottom portion of graph} \end{aligned}$$

Points of Intersection

A **point of intersection** of the graphs of two equations is a point that satisfies both equations. You can find all points of intersection of two graphs by solving their equations simultaneously.

EXAMPLE 5 Finding Points of Intersection



Two points of intersection

Figure P.10

Find all points of intersection of the graphs of

$$x^2 - y = 3 \quad \text{and} \quad x - y = 1.$$

Solution Begin by sketching the graphs of both equations in the *same* rectangular coordinate system, as shown in Figure P.10. From the figure, it appears that the graphs have two points of intersection. You can find these two points as follows.

$$\begin{aligned} y &= x^2 - 3 && \text{Solve first equation for } y. \\ y &= x - 1 && \text{Solve second equation for } y. \\ x^2 - 3 &= x - 1 && \text{Equate } y\text{-values}. \\ x^2 - x - 2 &= 0 && \text{Write in general form.} \\ (x - 2)(x + 1) &= 0 && \text{Factor.} \\ x &= 2 \text{ or } -1 && \text{Solve for } x. \end{aligned}$$

The corresponding values of y are obtained by substituting $x = 2$ and $x = -1$ into either of the original equations. Doing this produces two points of intersection:

$$(2, 1) \quad \text{and} \quad (-1, -2). \qquad \text{Points of intersection}$$ ■

You can check the points of intersection in Example 5 by substituting into *both* of the original equations or by using the *intersect* feature of a graphing utility.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Big Ideas of Calculus

You will use the concepts in this chapter throughout your study of calculus. Take the time to fully grasp each concept now so that you are ready to apply that concept later. Be sure to complete all concept exercises in this text—Concept Checks, Exploring Concepts, and Building on Concepts. These exercises are denoted by .

Mathematical Models

Real-life applications of mathematics often use equations as **mathematical models.** In developing a mathematical model to represent actual data, you should strive for two (often conflicting) goals—accuracy and simplicity. That is, you want the model to be simple enough to be workable, yet accurate enough to produce meaningful results. Appendix G explores these goals more completely.

EXAMPLE 6 Comparing Two Mathematical Models

The Mauna Loa Observatory in Hawaii records the carbon dioxide (CO_2) concentration y (in parts per million) in Earth's atmosphere. The January readings for various years are shown in Figure P.11. In 1990, these data were used to predict the carbon dioxide level in Earth's atmosphere in 2035, using the quadratic model

$$y = 0.020t^2 + 0.68t + 316.7$$ Quadratic model for 1960–1990 data

where $t = 0$ represents 1960, as shown in Figure P.11(a). The data shown in Figure P.11(b) represent the years 1960 through 2020 and can be modeled by

$$y = 0.013t^2 + 0.85t + 316.2$$ Quadratic model for 1960–2020 data

where $t = 0$ represents 1960. What was the prediction given by the first model for 1960 through 1990? Given the second model for the 1960 through 2020 data, does this prediction for 2035 seem accurate?

The Mauna Loa Observatory in Hawaii has been measuring the increasing concentration of carbon dioxide in Earth's atmosphere since 1958.



Figure P.11

Solution To answer the first question, substitute $t = 75$ (for 2035) into the first model.

$$y = 0.020(75)^2 + 0.68(75) + 316.7 = 480.2$$ Model for 1960–1990 data

So, according to this model, the carbon dioxide concentration in Earth's atmosphere would reach about 480 parts per million in 2035. Using the model for the 1960–2020 data, the prediction for 2035 is

$$y = 0.013(75)^2 + 0.85(75) + 316.2 = 453.075.$$ Model for 1960–2020 data

So, based on the second model, it appears that the 1990 prediction was too high. ■

The models in Example 6 were developed using a procedure called *least squares regression* (see Section 13.9). Note that you can use the regression capabilities of a graphing utility to find a mathematical model (see Exercises 69 and 70).

GO DIGITAL

iStockPhoto/trait2lumiere

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.1 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe how to find the x- and y-intercepts of the graph of an equation.
2. Explain how to use symmetry to sketch the graph of an equation.

Matching In Exercises 3–6, match the equation with its graph. [The graphs are labeled (a), (b), (c), and (d).]

(a)



(b)



(c)



(d)



3. $y = -\frac{3}{2}x + 3$
4. $y = \sqrt{9 - x^2}$
5. $y = 3 - x^2$
6. $y = x^3 - x$

Sketching a Graph by Point Plotting In Exercises 7–16, sketch the graph of the equation by point plotting.

7. $y = \frac{1}{2}x + 2$
8. $y = 5 - 2x$
9. $y = 4 - x^2$
10. $y = (x - 3)^2$
11. $y = |x + 1|$
12. $y = |x| - 1$
13. $y = \sqrt{x} - 6$
14. $y = \sqrt{x + 2}$
15. $y = \dfrac{3}{x}$
16. $y = \dfrac{1}{x + 2}$

Approximating Solution Points In Exercises 17 and 18, use a graphing utility to graph the equation. Move the cursor along the curve to approximate the unknown coordinate of each solution point accurate to two decimal places.

17. $y = \sqrt{5 - x}$
    (a) $(2, y)$
    (b) $(x, 3)$
18. $y = x^5 - 5x$
    (a) $(-0.5, y)$
    (b) $(x, -4)$

Finding Intercepts In Exercises 19–28, find any intercepts.

19. $y = 2x - 5$
20. $y = 4x^2 + 3$
21. $y = x^2 + x - 2$
22. $y^2 = x^3 - 4x$
23. $y = x\sqrt{16 - x^2}$
24. $y = (x - 1)\sqrt{x^2 + 1}$
25. $y = \dfrac{2 - \sqrt{x}}{5x + 1}$
26. $y = \dfrac{x^2 + 3x}{(3x + 1)^2}$
27. $x^2y - x^2 + 4y = 0$
28. $y = 2x - \sqrt{x^2 + 1}$

Testing for Symmetry In Exercises 29–40, test for symmetry with respect to each axis and to the origin.

29. $y = x^2 - 6$
30. $y = 9x - x^2$
31. $y^2 = x^3 - 8x$
32. $y = x^3 + x$
33. $xy = 4$
34. $xy^2 = -10$
35. $y = 4 - \sqrt{x + 3}$
36. $xy - \sqrt{4 - x^2} = 0$
37. $y = \dfrac{x}{x^2 + 1}$
38. $y = \dfrac{x^5}{4 - x^2}$
39. $y = |x^3 + x|$
40. $|y| - x = 3$

Using Intercepts and Symmetry to Sketch a Graph In Exercises 41–58, find any intercepts and test for symmetry. Then sketch the graph of the equation.

41. $y = 2 - 3x$
42. $y = \frac{2}{3}x + 1$
43. $y = 9 - x^2$
44. $y = 2x^2 + x$
45. $y = x^3 + 2$
46. $y = x^3 - 4x$
47. $y = x\sqrt{x + 5}$
48. $y = \sqrt{25 - x^2}$
49. $x = y^3$
50. $x = y^4 - 16$
51. $y = \dfrac{8}{x}$
52. $y = \dfrac{10}{x^2 + 1}$
53. $y = 6 - |x|$
54. $y = |6 - x|$
55. $x^2 + y^2 = 9$
56. $x^2 + 4y^2 = 4$
57. $3y^2 - x = 9$
58. $3x - 4y^2 = 8$

Finding Points of Intersection In Exercises 59–64, find the points of intersection of the graphs of the equations.

59. $x + y = 8$
    $4x - y = 7$
60. $3x - 2y = -4$
    $4x + 2y = -10$
61. $x^2 + y = 15$
    $-3x + y = 11$
62. $x = 3 - y^2$
    $y = x - 1$
63. $x^2 + y^2 = 5$
    $x - y = 1$
64. $x^2 + y^2 = 16$
    $x + 2y = 4$

A blue exercise number indicates that a video solution can be seen at *CalcView.com*.

The symbol indicates an exercise in which you are instructed to use a graphing utility or a symbolic computer algebra system. The solutions of other exercises may also be facilitated by the use of appropriate technology.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding Points of Intersection **In Exercises 65–68, use a graphing utility to find the points of intersection of the graphs of the equations. Check your results analytically.**

65. $y = x^3 - 2x^2 + x - 1$
$y = -x^2 + 3x - 1$

66. $y = x^4 - 2x^2 + 1$
$y = 1 - x^2$

67. $y = \sqrt{x + 6}$
$y = \sqrt{-x^2 - 4x}$

68. $y = -|2x - 3| + 6$
$y = 6 - x$

69. Modeling Data The table shows the gross domestic product, or GDP (in trillions of dollars), for 2012 through 2019. *(Source: U.S. Bureau of Economic Analysis)*

Year	2012	2013	2014	2015
GDP	16.2	16.8	17.5	18.2

Year	2016	2017	2018	2019
GDP	18.7	19.5	20.6	21.4

(a) Use the regression capabilities of a graphing utility to find a mathematical model of the form $y = at + b$ for the data. In the model, y represents the GDP (in trillions of dollars) and t represents the year, with $t = 12$ corresponding to 2012.

(b) Use a graphing utility to plot the data and graph the model. Compare the data with the model.

(c) Use the model to predict the GDP in the year 2029.

70. Modeling Data

The table shows the numbers of cell phone subscriptions (in billions) worldwide for 2012 through 2019. *(Source: Statista)*

Year	2012	2013	2014	2015
Number	6.3	6.7	7.0	7.2

Year	2016	2017	2018	2019
Number	7.5	7.8	7.9	8.3

(a) Use the regression capabilities of a graphing utility to find a mathematical model of the form $y = at^2 + bt + c$ for the data. In the model, y represents the number of subscriptions (in billions) and t represents the year, with $t = 12$ corresponding to 2012.

(b) Use a graphing utility to plot the data and graph the model. Compare the data with the model.

(c) Use the model to predict the number of cell phone subscriptions worldwide in the year 2029.

PeopleImages/Getty Images

71. Break-Even Point Find the sales necessary to break even ($R = C$) when the cost C of producing x units is $C = 2.04x + 5600$ and the revenue R from selling x units is $R = 3.29x$.

72. Using Solution Points For what values of k does the graph of $y^2 = 4kx$ pass through the point?

(a) $(1, 1)$ (b) $(2, 4)$

(c) $(0, 0)$ (d) $(3, 3)$

Exploring Concepts

73. Write an equation whose graph has intercepts at $x = -\frac{3}{2}$, $x = 4$, and $x = \frac{5}{2}$. (There is more than one correct answer.)

74. A graph is symmetric with respect to the x-axis and to the y-axis. Is the graph also symmetric with respect to the origin? Explain.

75. A graph is symmetric with respect to one axis and to the origin. Is the graph also symmetric with respect to the other axis? Explain.

76. HOW DO YOU SEE IT? Use the graphs of the two equations to answer the questions below.



(a) What are the intercepts for each equation?

(b) Determine the symmetry for each equation.

(c) Determine the point of intersection of the two equations.

True or False? **In Exercises 77–80, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

77. If $(-4, -5)$ is a point on a graph that is symmetric with respect to the x-axis, then $(4, -5)$ is also a point on the graph.

78. If $(-4, -5)$ is a point on a graph that is symmetric with respect to the y-axis, then $(4, -5)$ is also a point on the graph.

79. If $b^2 - 4ac > 0$ and $a \neq 0$, then the graph of

$y = ax^2 + bx + c$

has two x-intercepts.

80. If $b^2 - 4ac = 0$ and $a \neq 0$, then the graph of

$y = ax^2 + bx + c$

has only one x-intercept.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.2 Linear Models and Rates of Change

GO DIGITAL

- **Find the slope of a line passing through two points.**
- **Write the equation of a line with a given point and slope.**
- **Interpret slope as a ratio or as a rate in a real-life application.**
- **Sketch the graph of a linear equation in slope-intercept form.**
- **Write equations of lines that are parallel or perpendicular to a given line.**

The Slope of a Line



$\Delta y = y_2 - y_1$ = change in y
$\Delta x = x_2 - x_1$ = change in x
Figure P.12

The **slope** of a nonvertical line is a measure of the number of units the line rises (or falls) vertically for each unit of horizontal change from left to right. Consider the two points (x_1, y_1) and (x_2, y_2) on the line in Figure P.12. As you move from left to right along this line, a vertical change of

$$\Delta y = y_2 - y_1 \qquad \text{Change in } y$$

units corresponds to a horizontal change of

$$\Delta x = x_2 - x_1 \qquad \text{Change in } x$$

units. (The symbol Δ is the uppercase Greek letter delta, and the symbols Δy and Δx are read "delta y" and "delta x.")

Definition of the Slope of a Line

The **slope** m of the nonvertical line passing through (x_1, y_1) and (x_2, y_2) is

$$m = \frac{\Delta y}{\Delta x} = \frac{y_2 - y_1}{x_2 - x_1}, \quad x_1 \neq x_2. \qquad \text{Slope of a nonvertical line}$$

Slope is not defined for vertical lines.

When using the formula for slope, note that

$$\frac{y_2 - y_1}{x_2 - x_1} = \frac{-(y_1 - y_2)}{-(x_1 - x_2)} = \frac{y_1 - y_2}{x_1 - x_2}. \qquad \text{Equivalent fractions}$$

So, it does not matter in which order you subtract *as long as* you are consistent and both "subtracted coordinates" come from the same point.

Figure P.13 shows four lines: one has a positive slope, one has a slope of zero, one has a negative slope, and one has an "undefined" slope. In general, the greater the absolute value of the slope of a line, the steeper the line. For instance, in Figure P.13, the line with a slope of -5 is steeper than the line with a slope of $\frac{1}{5}$.



If m is positive, then the line rises from left to right.



If m is zero, then the line is horizontal.



If m is negative, then the line falls from left to right.



If m is undefined, then the line is vertical.

Figure P.13

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploration

Investigating Equations of Lines Use a graphing utility to graph each linear equation. Which point is common to all seven lines? Which value in the equation determines the slope of each line?

a. $y - 4 = -2(x + 1)$
b. $y - 4 = -1(x + 1)$
c. $y - 4 = -\frac{1}{2}(x + 1)$
d. $y - 4 = 0(x + 1)$
e. $y - 4 = \frac{1}{2}(x + 1)$
f. $y - 4 = 1(x + 1)$
g. $y - 4 = 2(x + 1)$

Use your results to write an equation of a line passing through $(-1, 4)$ with a slope of m.

Equations of Lines

Any two points on a nonvertical line can be used to calculate its slope. This can be verified from the similar triangles shown in Figure P.14. (Recall that the ratios of corresponding sides of similar triangles are equal.)



Any two points on a nonvertical line can be used to determine its slope.
Figure P.14

If (x_1, y_1) is a point on a nonvertical line that has a slope of m and (x, y) is *any other* point on the line, then

$$\frac{y - y_1}{x - x_1} = m.$$

This equation in the variables x and y can be rewritten in the form

$$y - y_1 = m(x - x_1)$$

which is the **point-slope form** of the equation of a line.

Point-Slope Form of the Equation of a Line

The **point-slope form** of the equation of the line that passes through the point (x_1, y_1) and has a slope of m is

$$y - y_1 = m(x - x_1).$$ Point-slope form

REMARK Remember that only nonvertical lines have a slope. Consequently, vertical lines cannot be written in point-slope form. For instance, the equation of the vertical line passing through the point $(1, -2)$ is $x = 1$.

GO DIGITAL



The line with a slope of 3 passing through the point $(1, -2)$
Figure P.15

EXAMPLE 1 Finding an Equation of a Line

Find an equation of the line that has a slope of 3 and passes through the point $(1, -2)$. Then sketch the line.

Solution

$$y - y_1 = m(x - x_1)$$ Point-slope form
$$y - (-2) = 3(x - 1)$$ Substitute -2 for y_1, 1 for x_1, and 3 for m.
$$y + 2 = 3x - 3$$ Simplify.
$$y = 3x - 5$$ Solve for y.

To sketch the line, first plot the point $(1, -2)$. Then, because the slope is $m = 3$, you can locate a second point on the line by moving one unit to the right and three units upward, as shown in Figure P.15.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Ratios and Rates of Change

The slope of a line can be interpreted as either a *ratio* or a *rate*. If the x- and y-axes have the same unit of measure, then the slope has no units and is a **ratio.** If the x- and y-axes have different units of measure, then the slope is a rate or **rate of change.** In your study of calculus, you will encounter applications involving both interpretations of slope.

EXAMPLE 2 Using Slope as a Ratio

The maximum recommended slope of a wheelchair ramp is $\frac{1}{12}$. A business installs a wheelchair ramp that rises to a height of 22 inches over a length of 24 feet, as shown in Figure P.16. Is the ramp steeper than recommended? *(Source: ADA Standards for Accessible Design)*



Figure P.16

Solution The length of the ramp is 24 feet or $12(24) = 288$ inches. The slope of the ramp is the ratio of its height (the vertical change) to its length (the horizontal change).

$$\begin{aligned}\text{Slope of ramp} &= \frac{\text{vertical change}}{\text{horizontal change}} \\ &= \frac{22 \text{ in.}}{288 \text{ in.}} \\ &\approx 0.076\end{aligned}$$

Because the slope of the ramp is less than $\frac{1}{12} \approx 0.083$, the ramp is not steeper than recommended. Note that the slope is a ratio and has no units.

EXAMPLE 3 Using Slope as a Rate of Change

The population of Texas was about 25.2 million in 2010 and about 29.4 million in 2020. Find the average rate of change of the population over this ten-year period. What will the population of Texas be in 2028? *(Source: U.S. Census Bureau)*

Solution Over the ten-year period from 2010 through 2020, the average rate of change of the population of Texas was

$$\begin{aligned}\text{Rate of change} &= \frac{\text{change in population}}{\text{change in years}} \\ &= \frac{29.4 - 25.2}{2020 - 2010} \\ &= 0.42 \text{ million people per year.}\end{aligned}$$

Assuming the population of Texas continues to increase at this same rate for the next eight years, the population in 2028 will be about

$$29.4 + 8(0.42) \approx 32.8 \text{ million people.}$$ See Figure P.17.



Population of Texas

Figure P.17

The rate of change found in Example 3 is an **average rate of change.** An average rate of change is always calculated over an interval. In this case, the interval is [2010, 2020]. In Chapter 2, you will study another type of rate of change called an *instantaneous rate of change.*

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Graphing Linear Models

Many problems in coordinate geometry can be classified into two basic categories.

1. Given a graph (or parts of it), find its equation.
2. Given an equation, sketch its graph.

For lines, problems in the first category can be solved by using the point-slope form. The point-slope form, however, is not especially useful for solving problems in the second category. The form that is better suited to sketching the graph of a line is the **slope-intercept** form of the equation of a line.

The Slope-Intercept Form of the Equation of a Line

The graph of the linear equation

$$y = mx + b \qquad \text{Slope-intercept form}$$

is a line whose slope is m and whose y-intercept is $(0, b)$.

EXAMPLE 4 Sketching Graphs of Lines

Sketch the graph of each equation.

a. $y = 2x + 1$ **b.** $y = 2$ **c.** $3y + x - 6 = 0$

Solution

a. This equation is written in slope-intercept form.

$$y = 2x + 1 \qquad y = mx + b$$

Because $b = 1$, the y-intercept is $(0, 1)$. The slope is $m = 2$, so the line rises two units for each unit it moves to the right, as shown in Figure P.18(a).

b. By writing the equation $y = 2$ in slope-intercept form

$$y = (0)x + 2 \qquad y = mx + b$$

you can see that the slope is $m = 0$ and the y-intercept is $(0, 2)$. Because the slope is zero, the line is horizontal, as shown in Figure P.18(b).

c. Begin by writing the equation in slope-intercept form.

$$\begin{aligned} 3y + x - 6 &= 0 && \text{Write original equation.} \\ 3y &= -x + 6 && \text{Isolate } y\text{-term on the left.} \\ y &= -\tfrac{1}{3}x + 2 && y = mx + b \end{aligned}$$

In this form, you can see that the y-intercept is $(0, 2)$ and the slope is $m = -\frac{1}{3}$. This means that the line falls one unit for every three units it moves to the right, as shown in Figure P.18(c).



(a) $m = 2$; line rises to the right



(b) $m = 0$; line is horizontal



(c) $m = -\frac{1}{3}$; line falls to the right

Figure P.18

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Because the slope of a vertical line is not defined, its equation cannot be written in slope-intercept form. However, the equation of any line can be written in the **general form**

$$Ax + By + C = 0 \qquad \text{General form of the equation of a line}$$

where A and B are not *both* zero. For instance, the vertical line

$$x = a \qquad \text{Vertical line}$$

can be represented by the general form

$$x - a = 0. \qquad \text{General form}$$

REMARK Writing an equation of a line is an important concept in calculus. For example, in Chapter 2, you will use the point-slope form of a line to write equations of tangent lines.

Summary of Equations of Lines

1.	General form:	$Ax + By + C = 0$
2.	Vertical line:	$x = a$
3.	Horizontal line:	$y = b$
4.	Slope-intercept form:	$y = mx + b$
5.	Point-slope form:	$y - y_1 = m(x - x_1)$

Parallel and Perpendicular Lines

The slope of a line is a convenient tool for determining whether two lines are parallel or perpendicular, as shown in Figure P.19. Specifically, distinct nonvertical lines with the same slope are parallel, and nonvertical lines whose slopes are negative reciprocals are perpendicular.

REMARK In mathematics, the phrase "if and only if" is a way of stating two implications in one statement. For instance, the definition of parallel lines can be rewritten as the two implications below.

a. If two distinct nonvertical lines are parallel, then their slopes are equal.

b. If two distinct nonvertical lines have equal slopes, then they are parallel.



Parallel lines — Perpendicular lines

Figure P.19

Parallel and Perpendicular Lines

1. Two distinct nonvertical lines are **parallel** if and only if their slopes are equal—that is, if and only if

$$m_1 = m_2. \qquad \text{Parallel} \iff \text{Slopes are equal.}$$

2. Two nonvertical lines are **perpendicular** if and only if their slopes are negative reciprocals of each other—that is, if and only if

$$m_1 = -\frac{1}{m_2}. \qquad \text{Perpendicular} \iff \text{Slopes are negative reciprocals.}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



Lines parallel and perpendicular to $2x - 3y = 5$

Figure P.20

EXAMPLE 5 Finding Parallel and Perpendicular Lines

See LarsonCalculus.com for an interactive version of this type of example.

Find the general forms of the equations of the lines that pass through the point $(2, -1)$ and are (a) parallel to and (b) perpendicular to the line $2x - 3y = 5$.

Solution Begin by writing the linear equation $2x - 3y = 5$ in slope-intercept form.

$$2x - 3y = 5 \qquad \text{Write original equation.}$$
$$y = \tfrac{2}{3}x - \tfrac{5}{3} \qquad \text{Slope-intercept form}$$

So, the given line has a slope of $m = \frac{2}{3}$. (See Figure P.20.)

a. The line through $(2, -1)$ that is parallel to the given line also has a slope of $\frac{2}{3}$.

$$y - y_1 = m(x - x_1) \qquad \text{Point-slope form}$$
$$y - (-1) = \tfrac{2}{3}(x - 2) \qquad \text{Substitute.}$$
$$3(y + 1) = 2(x - 2) \qquad \text{Simplify.}$$
$$3y + 3 = 2x - 4 \qquad \text{Distributive Property}$$
$$2x - 3y - 7 = 0 \qquad \text{General form}$$

Note the similarity to the equation of the given line, $2x - 3y = 5$.

b. Use the negative reciprocal of the slope of the given line to determine that the slope of a line perpendicular to the given line is $-\frac{3}{2}$.

$$y - y_1 = m(x - x_1) \qquad \text{Point-slope form}$$
$$y - (-1) = -\tfrac{3}{2}(x - 2) \qquad \text{Substitute.}$$
$$2(y + 1) = -3(x - 2) \qquad \text{Simplify.}$$
$$2y + 2 = -3x + 6 \qquad \text{Distributive Property}$$
$$3x + 2y - 4 = 0 \qquad \text{General form}$$

TECHNOLOGY PITFALL The slope of a line will appear distorted if you use different tick-mark spacing on the x- and y-axes. For instance, the graphing utility screens in Figures P.21(a) and P.21(b) both show the lines

$$y = 2x \quad \text{and} \quad y = -\tfrac{1}{2}x + 3.$$

Because these lines have slopes that are negative reciprocals, they must be perpendicular. In Figure P.21(a), however, the lines do not appear to be perpendicular because the tick-mark spacing on the x-axis is not the same as that on the y-axis. In Figure P.21(b), the lines appear perpendicular because the tick-mark spacing on the x-axis is the same as on the y-axis. This type of viewing window is said to have a *square setting*.



(a) Tick-mark spacing on the x-axis is not the same as tick-mark spacing on the y-axis.



(b) Tick-mark spacing on the x-axis is the same as tick-mark spacing on the y-axis.

Figure P.21

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.2 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. In the form $y = mx + b$, what does m represent? What does b represent?
2. Is it possible for two lines with positive slopes to be perpendicular lines? Why or why not?

Estimating Slope **In Exercises 3–6, estimate the slope of the line from its graph. To print an enlarged copy of the graph, go to *MathGraphs.com*.**

3.



4.



5.



6.



Finding the Slope of a Line **In Exercises 7–12, plot the pair of points and find the slope of the line passing through them.**

7. $(3, -4), (5, 2)$
8. $(0, 0), (-2, 3)$
9. $(4, 6), (4, 1)$
10. $(3, -5), (5, -5)$
11. $\left(-\frac{1}{2}, \frac{2}{3}\right), \left(-\frac{3}{4}, \frac{1}{6}\right)$
12. $\left(\frac{7}{8}, \frac{3}{4}\right), \left(\frac{5}{4}, -\frac{1}{4}\right)$

Sketching Lines **In Exercises 13 and 14, sketch the lines through the point with the indicated slopes. Make the sketches on the same set of coordinate axes.**

	Point	Slopes			
13.	$(3, 4)$	(a) 1	(b) -2	(c) $-\frac{3}{2}$	(d) Undefined
14.	$(-2, 5)$	(a) 3	(b) -3	(c) $\frac{1}{3}$	(d) 0

Finding Points on a Line **In Exercises 15–18, use the point on the line and the slope of the line to find three additional points that the line passes through. (There is more than one correct answer.)**

	Point	Slope
15.	$(6, 2)$	$m = 0$
16.	$(-4, 3)$	m is undefined.
17.	$(1, 7)$	$m = -3$
18.	$(-2, -2)$	$m = 2$

Finding an Equation of a Line **In Exercises 19–24, find an equation of the line that passes through the point and has the indicated slope. Then sketch the line.**

	Point	Slope
19.	$(0, 3)$	$m = \frac{3}{4}$
20.	$(-5, -2)$	$m = \frac{6}{5}$
21.	$(1, 2)$	m is undefined.
22.	$(0, 4)$	$m = 0$
23.	$(3, -2)$	$m = 3$
24.	$(-2, 4)$	$m = -\frac{3}{5}$

25. **Road Grade** You are driving on a road that has a 6% uphill grade. This means that the slope of the road is $\frac{6}{100}$. Approximate the amount of vertical change in your position when you drive 200 feet.

26. **Conveyor Design**

A moving conveyor is built to rise 1 meter for each 3 meters of horizontal change.

(a) Find the slope of the conveyor.

(b) The conveyor runs between two floors in a factory. Find the length of the conveyor when the vertical distance between floors is 10 feet.

27. **Population** The table shows the populations y (in millions) of the United States for 2011 through 2020. The variable t represents the year, with $t = 11$ corresponding to 2011. (*Source: U.S. Census Bureau*)

t	11	12	13	14	15
y	312.0	314.2	316.3	318.6	320.9

t	16	17	18	19	20
y	323.2	325.2	326.9	328.5	330.1

(a) Plot the data and connect adjacent points with a line segment. Use the slope of each line segment to determine the year when the population increased least rapidly.

(b) Find the average rate of change of the population of the United States from 2011 through 2020.

(c) Use the average rate of change of the population to predict the population of the United States in 2030.

Westend61/Getty Images

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

28. Biomass-Based Diesel Fuel Production The table shows the biomass-based diesel fuel productions y (in millions of barrels per day) for the United States for 2014 through 2019. The variable t represents the year, with $t = 14$ corresponding to 2014. *(Source: U.S. Energy Information Administration)*

t	14	15	16	17	18	19
y	83	82	102	104	121	112

(a) Plot the data and connect adjacent points with a line segment. Use the slope of each line segment to determine the year when biomass-based diesel fuel production increased most rapidly.

(b) Find the average rate of change of biomass-based diesel fuel production for the United States from 2014 through 2019.

(c) Should the average rate of change be used to predict future biomass-based diesel fuel production? Explain.

Finding the Slope and *y*-Intercept **In Exercises 29–34, find the slope and the *y*-intercept (if possible) of the line.**

29. $y = 4x - 3$

30. $-x + y = 1$

31. $5x + y = 20$

32. $6x - 5y = 15$

33. $x = 4$

34. $y = -1$

Sketching a Line in the Plane **In Exercises 35–42, sketch the graph of the equation.**

35. $y = -3$

36. $x = 4$

37. $y = -2x + 1$

38. $y = \frac{1}{3}x - 1$

39. $y - 2 = \frac{3}{2}(x - 1)$

40. $y - 1 = 3(x + 4)$

41. $3x - 3y + 1 = 0$

42. $x + 2y + 6 = 0$

Finding an Equation of a Line **In Exercises 43–50, find an equation of the line that passes through the points. Then sketch the line.**

43. $(4, 3), (0, -5)$

44. $(-2, -2), (1, 7)$

45. $(2, 8), (5, 0)$

46. $(-3, 6), (1, 2)$

47. $(6, 3), (6, 8)$

48. $(1, -2), (3, -2)$

49. $(3, 1), (5, 1)$

50. $(2, 5), (2, 7)$

51. Writing an Equation Write an equation for the line that passes through the points $(0, b)$ and $(3, 1)$.

52. Using Intercepts Show that the line with intercepts $(a, 0)$ and $(0, b)$ has the equation

$$\frac{x}{a} + \frac{y}{b} = 1, \quad a \neq 0, b \neq 0.$$

Writing an Equation in General Form **In Exercises 53–56, use the result of Exercise 52 to write an equation of the line with the given characteristics in general form.**

53. x-intercept: $(2, 0)$
y-intercept: $(0, 3)$

54. x-intercept: $\left(-\frac{2}{3}, 0\right)$
y-intercept: $(0, -2)$

55. Point on line: $(9, -2)$
x-intercept: $(2a, 0)$
y-intercept: $(0, a)$
$(a \neq 0)$

56. Point on line: $\left(-\frac{2}{3}, -2\right)$
x-intercept: $(a, 0)$
y-intercept: $(0, -a)$
$(a \neq 0)$

Finding Parallel and Perpendicular Lines **In Exercises 57–62, find the general forms of the equations of the lines that pass through the point and are (a) parallel to the given line and (b) perpendicular to the given line.**

	Point	Line
57.	$(-7, -2)$	$x = 1$
58.	$(-1, 0)$	$y = -3$
59.	$(-3, 2)$	$x + y = 7$
60.	$(2, 5)$	$x - y = -2$
61.	$\left(\frac{3}{4}, \frac{7}{8}\right)$	$5x - 3y = 0$
62.	$\left(\frac{5}{6}, -\frac{1}{2}\right)$	$7x + 4y = 8$

Rate of Change **In Exercises 63 and 64, you are given the dollar value of a product in 2021 *and* the rate at which the value of the product is expected to change during the next 5 years. Write a linear equation that gives the dollar value V of the product in terms of the year t. (Let $t = 0$ represent 2020.)**

	2021 Value	Rate
63.	\$1850	\$250 increase per year
64.	\$17,200	\$1600 decrease per year

Collinear Points **In Exercises 65 and 66, determine whether the points are collinear. (Three points are *collinear* when they lie on the same line.)**

65. $(-2, 1), (-1, 0), (2, -2)$

66. $(0, 4), (7, -6), (-5, 11)$

Exploring Concepts

67. Show that the points $(-1, 0)$, $(3, 0)$, $(1, 2)$, and $(1, -2)$ are vertices of a square.

68. A line is represented by the equation $ax + by = 4$.

(a) When is the line parallel to the x-axis?

(b) When is the line parallel to the y-axis?

(c) Give values for a and b such that the line has a slope of $\frac{5}{8}$.

(d) Give values for a and b such that the line is perpendicular to $y = \frac{2}{5}x + 3$.

(e) Give values for a and b such that the line coincides with the graph of $5x + 6y = 8$.

69. Finding a Tangent Line Find an equation of the line tangent to the circle $x^2 + y^2 = 169$ at the point $(5, 12)$.

70. Finding a Tangent Line Find an equation of the line tangent to the circle $(x - 1)^2 + (y - 1)^2 = 25$ at the point $(4, -3)$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

71. Finding Points of Intersection Find the coordinates of the point of intersection of the given segments.

(a) Perpendicular bisectors (b) Medians



72. HOW DO YOU SEE IT? Several lines are shown in the figure below. (The lines are labeled *a*–*f*.)

(a) Which lines have a positive slope?

(b) Which lines have a negative slope?

(c) Which lines appear parallel?

(d) Which lines appear perpendicular?



73. Temperature Conversion Find a linear equation that expresses the relationship between the temperature in degrees Celsius C and degrees Fahrenheit F. Use the fact that water freezes at 0°C (32°F) and boils at 100°C (212°F). Use the equation to convert 72°F to degrees Celsius.

74. Choosing a Job As a salesperson, you receive a monthly salary of $2000, plus a commission of 7% of sales. You are offered a new job at $2300 per month, plus a commission of 5% of sales.

(a) Write linear equations for your monthly wage W in terms of your monthly sales s for your current job and your job offer.

(b) Use a graphing utility to graph each equation and find the point of intersection. What does it signify?

(c) You think you can sell $20,000 worth of a product per month. Should you change jobs? Explain.

75. Apartment Rental A real estate office manages an apartment complex with 50 one-bedroom units. When the rent is $780 per month, all 50 units are occupied. However, when the rent is $825, the average number of occupied units drops to 47. Assume that the relationship between the monthly rent p and the demand x is linear. (*Note:* The term *demand* refers to the number of occupied units.)

(a) Write a linear equation giving the demand x in terms of the rent p.

(b) *Linear extrapolation* Use a graphing utility to graph the demand equation and use the *trace* feature to predict the number of units occupied when the rent is raised to $855.

(c) *Linear interpolation* Predict the number of units occupied when the rent is lowered to $795. Verify graphically.

76. Modeling Data An instructor gives regular 20-point quizzes and 100-point exams in a mathematics course. Average scores for six students, given as ordered pairs (x, y), where x is the average quiz score and y is the average exam score, are (18, 87), (10, 55), (19, 96), (16, 79), (13, 76), and (15, 82).

(a) Use the regression capabilities of a graphing utility to find the least squares regression line for the data.

(b) Use a graphing utility to plot the points and graph the regression line in the same viewing window.

(c) Use the regression line to predict the average exam score for a student with an average quiz score of 17.

(d) Interpret the meaning of the slope of the regression line.

(e) The instructor adds 4 points to the average exam score of everyone in the class. Describe the changes in the positions of the plotted points and the change in the equation of the line.

77. Distance Show that the distance between the point (x_1, y_1) and the line $Ax + By + C = 0$ is

$$\text{Distance} = \frac{|Ax_1 + By_1 + C|}{\sqrt{A^2 + B^2}}.$$

78. Distance Write the distance d between the point (3, 1) and the line $y = mx + 4$ in terms of m. Use a graphing utility to graph the equation. When is the distance 0? Explain the result geometrically.

Distance **In Exercises 79 and 80, use the result of Exercise 77 to find the distance between the point and line.**

79. Point: $(-2, 1)$
Line: $x - y - 2 = 0$

80. Point: $(2, 3)$
Line: $4x + 3y = 10$

81. Proof Prove that the diagonals of a rhombus intersect at right angles. (A rhombus is a quadrilateral with sides of equal lengths.)

82. Proof Prove that the figure formed by connecting consecutive midpoints of the sides of any quadrilateral is a parallelogram.

83. Proof Prove that if the points (x_1, y_1) and (x_2, y_2) lie on the same line as (x_1^*, y_1^*) and (x_2^*, y_2^*), then

$$\frac{y_2^* - y_1^*}{x_2^* - x_1^*} = \frac{y_2 - y_1}{x_2 - x_1}.$$

Assume $x_1 \neq x_2$ and $x_1^* \neq x_2^*$.

84. Proof Prove that if the slopes of two nonvertical lines are negative reciprocals of each other, then the lines are perpendicular.

True or False? **In Exercises 85 and 86, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

85. The lines represented by

$$ax + by = c_1 \quad \text{and} \quad bx - ay = c_2$$

are perpendicular. Assume $a \neq 0$ and $b \neq 0$.

86. If a line contains points in both the first and third quadrants, then its slope must be positive.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.3 Functions and Their Graphs

GO DIGITAL

- **Use function notation to represent and evaluate a function.**
- **Find the domain and range of a function.**
- **Sketch the graph of a function.**
- **Identify different types of transformations of functions.**
- **Classify functions and recognize combinations of functions.**

REMARK The concepts in this section are essential to your study of calculus. It is important that you grasp them now so you are able to learn more advanced material later.

Functions and Function Notation

A **relation** between two sets X and Y is a set of ordered pairs, each of the form (x, y), where x is a member of X and y is a member of Y. A **function** from X to Y is a relation between X and Y that has the property that any two ordered pairs with the same x-value also have the same y-value. The variable x is the **independent variable,** and the variable y is the **dependent variable.**

Many real-life situations can be modeled by functions. For instance, the area A of a circle is a function of the circle's radius r.

$$A = \pi r^2 \qquad A \text{ is a function of } r.$$

In this case, r is the independent variable and A is the dependent variable.



A real-valued function f of a real variable

Figure P.22

Definition of a Real-Valued Function of a Real Variable

Let X and Y be sets of real numbers. A **real-valued function f of a real variable x** from X to Y is a correspondence that assigns to each number x in X exactly one number y in Y.

The **domain** of f is the set X. The number y is the **image** of x under f and is denoted by $f(x)$, which is called the **value of f at x.** The **range** of f is a subset of Y and consists of all images of numbers in X. (See Figure P.22.)

Functions can be specified in a variety of ways. In this text, however, you will concentrate primarily on functions that are given by equations involving the dependent and independent variables. For instance, the equation

$$x^2 + 2y = 1 \qquad \text{Equation in implicit form}$$

defines y, the dependent variable, as a function of x, the independent variable. To **evaluate** this function (that is, to find the y-value that corresponds to a given x-value), it is convenient to isolate y on the left side of the equation.

$$y = \frac{1}{2}(1 - x^2) \qquad \text{Equation in explicit form}$$

Using f as the name of the function, you can write this equation as

$$f(x) = \frac{1}{2}(1 - x^2). \qquad \text{Function notation}$$

The original equation $x^2 + 2y = 1$ **implicitly** defines y as a function of x. When you solve the equation for y, you are writing the equation in **explicit** form.

Function notation has the advantage of clearly identifying the dependent variable as $f(x)$ while at the same time telling you that x is the independent variable and that the function itself is "f." The symbol $f(x)$ is read "f of x." Function notation allows you to be less wordy. Instead of asking "What is the value of y that corresponds to $x = 3$?" you can ask "What is $f(3)$?"

FUNCTION NOTATION

The word *function* was first used by Gottfried Wilhelm Leibniz in 1694 as a term to denote any quantity connected with a curve, such as the coordinates of a point on a curve or the slope of a curve. Forty years later, Leonhard Euler used the word "function" to describe any expression made up of a variable and some constants. He introduced the notation $y = f(x)$. (To read more about Euler, see the biography on the next page.)

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

LEONHARD EULER (1707–1783)

In addition to making major contributions to almost every branch of mathematics, Euler was one of the first to apply calculus to real-life problems in physics. His extensive published writings include such topics as shipbuilding, acoustics, optics, astronomy, mechanics, and magnetism.

See LarsonCalculus.com to read more of this biography.

In an equation that defines a function of x, the role of the variable x is simply that of a placeholder. For instance, the function

$$f(x) = 2x^2 - 4x + 1 \qquad \text{Function of } x$$

can be described by the form

$$f(\square) = 2(\square)^2 - 4(\square) + 1 \qquad \text{Function of } \square$$

where rectangles are used instead of x. To evaluate $f(-2)$, replace each rectangle with -2.

$$\begin{aligned} f(-2) &= 2(-2)^2 - 4(-2) + 1 && \text{Substitute } -2 \text{ for } \square. \\ &= 2(4) + 8 + 1 && \text{Simplify.} \\ &= 17 && \text{Simplify.} \end{aligned}$$

Although f is often used as a convenient function name with x as the independent variable, you can use other symbols. For instance, these three equations all define the same function.

$$\begin{aligned} f(x) &= x^2 - 4x + 7 && \text{Function name is } f\text{; independent variable is } x. \\ h(t) &= t^2 - 4t + 7 && \text{Function name is } h\text{; independent variable is } t. \\ g(s) &= s^2 - 4s + 7 && \text{Function name is } g\text{; independent variable is } s. \end{aligned}$$

EXAMPLE 1 Evaluating a Function

For the function f defined by $f(x) = x^2 + 7$, evaluate each expression.

a. $f(3a)$ **b.** $f(b - 1)$ **c.** $\dfrac{f(x + \Delta x) - f(x)}{\Delta x}$

Solution

a. $\begin{aligned} f(3a) &= (3a)^2 + 7 && \text{Substitute } 3a \text{ for } x. \\ &= 9a^2 + 7 && \text{Simplify.} \end{aligned}$

b. $\begin{aligned} f(b - 1) &= (b - 1)^2 + 7 && \text{Substitute } b - 1 \text{ for } x. \\ &= b^2 - 2b + 1 + 7 && \text{Expand binomial.} \\ &= b^2 - 2b + 8 && \text{Simplify.} \end{aligned}$

c. $\begin{aligned} \frac{f(x + \Delta x) - f(x)}{\Delta x} &= \frac{[(x + \Delta x)^2 + 7] - (x^2 + 7)}{\Delta x} \\ &= \frac{x^2 + 2x\Delta x + (\Delta x)^2 + 7 - x^2 - 7}{\Delta x} \\ &= \frac{2x\Delta x + (\Delta x)^2}{\Delta x} \\ &= \frac{\Delta x(2x + \Delta x)}{\Delta x} \\ &= 2x + \Delta x, \quad \Delta x \neq 0 \end{aligned}$

REMARK The expression in Example 1(c) is called a *difference quotient* and has a special significance in calculus. You will learn more about this in Chapter 2.

In calculus, it is important to specify the domain of a function or expression clearly. For instance, in Example 1(c), the two expressions

$$\frac{f(x + \Delta x) - f(x)}{\Delta x} \quad \text{and} \quad 2x + \Delta x, \quad \Delta x \neq 0$$

are equivalent because $\Delta x = 0$ is excluded from the domain of each expression. Without a stated domain restriction, the two expressions would not be equivalent.

GO DIGITAL

North Wind Picture Archives/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The Domain and Range of a Function

The domain of a function can be described explicitly, or it may be described *implicitly* by an equation used to define the function. The **implied domain** is the set of all real numbers for which the equation is defined, whereas an explicitly defined domain is one that is given along with the function. For example, the function

$$f(x) = \frac{1}{x^2 - 4}, \quad 4 \le x \le 5$$ *f* has an *explicitly* defined domain.

has an explicitly defined domain given by $\{x: 4 \le x \le 5\}$. On the other hand, the function

$$g(x) = \frac{1}{x^2 - 4}$$ *g* has an *implied* domain.

has an implied domain that is the set $\{x: x \neq \pm 2\}$.



(a) The domain of f is $[1, \infty)$, and the range is $[0, \infty)$.



(b) The domain of g is $[-2, 2]$, and the range is $[0, 2]$.

Figure P.23

EXAMPLE 2 Finding the Domains and Ranges of Functions

Find the domain and range of each function.

a. $f(x) = \sqrt{x - 1}$ **b.** $g(x) = \sqrt{4 - x^2}$

Solution

a. The domain of the function

$$f(x) = \sqrt{x - 1}$$

is the set of all x-values for which $x - 1 \ge 0$, which is the interval $[1, \infty)$. To find the range, observe that $f(x) = \sqrt{x - 1}$ is never negative. So, the range is the interval $[0, \infty)$, as shown in Figure P.23(a).

b. The domain of the function

$$g(x) = \sqrt{4 - x^2}$$

is the set of all values for which $4 - x^2 \ge 0$, or $x^2 \le 4$. So, the domain of g is the interval $[-2, 2]$. To find the range, observe that $g(x) = \sqrt{4 - x^2}$ is never negative and is at most 2. So, the range is the interval $[0, 2]$, as shown in Figure P.23(b). Note that the graph of g is a *semicircle* of radius 2.

EXAMPLE 3 A Function Defined by More than One Equation

For the piecewise-defined function

$$f(x) = \begin{cases} 1 - x, & x < 1 \\ \sqrt{x - 1}, & x \ge 1 \end{cases}$$

f is defined for $x < 1$ and $x \ge 1$. So, the domain is the set of all real numbers. On the portion of the domain for which $x \ge 1$, the function behaves as in Example 2(a). For $x < 1$, the values of $1 - x$ are positive. So, the range of the function is the interval $[0, \infty)$. (See Figure P.24.)



The domain of f is $(-\infty, \infty)$, and the range is $[0, \infty)$.

Figure P.24

A function from X to Y is **one-to-one** when to each y-value in the range there corresponds exactly one x-value in the domain. For instance, the function in Example 2(a) is one-to-one, whereas the functions in Examples 2(b) and 3 are not one-to-one. A function from X to Y is **onto** when its range consists of all of Y.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The graph of a function
Figure P.25

The Graph of a Function

The graph of the function $y = f(x)$ consists of all points $(x, f(x))$, where x is in the domain of f. In Figure P.25, note that

x = the directed distance from the y-axis

and

$f(x)$ = the directed distance from the x-axis.

A vertical line can intersect the graph of a function of x at most *once*. This observation provides a convenient visual test, called the **Vertical Line Test,** for functions of x. That is, a graph in the coordinate plane is the graph of a function of x if and only if no vertical line intersects the graph at more than one point. For example, in Figure P.26(a), the graph does not define y as a function of x because a vertical line intersects the graph twice, whereas in Figures P.26(b) and (c), the graphs do define y as a function of x.



(a) Not a function of x **(b)** A function of x **(c)** A function of x
Figure P.26

Figure P.27 shows the graphs of six basic functions. You should be able to recognize these graphs. (The graphs of the six basic trigonometric functions are shown in Section P.4.)



Identity function



Squaring function



Cubing function



Square root function



Absolute value function



Rational (reciprocal) function

The graphs of six basic functions
Figure P.27

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

OLIVER HEAVISIDE (1850–1925)

Heaviside was a British mathematician and physicist who contributed to the field of applied mathematics, especially applications of mathematics to electrical engineering. The *Heaviside function* is a classic type of "on-off" function that has applications to electricity and computer science. (See Exercise 62.)

Transformations of Functions

Some families of graphs have the same basic shape. For example, compare the graph of $y = x^2$ with the graphs of the four other quadratic functions shown in Figure P.28.



(a) Vertical shift upward



(b) Horizontal shift to the left



(c) Reflection



(d) Shift left, reflect, and shift upward

Figure P.28

Each graph in Figure P.28 is a **transformation** of the graph of $y = x^2$. The three basic types of transformations illustrated by these graphs are vertical shifts, horizontal shifts, and reflections. Function notation lends itself well to describing transformations of graphs in the plane. For instance, using

$f(x) = x^2$ Original function

as the original function, the transformations shown in Figure P.28 can be represented by these equations.

a. $y = f(x) + 2$ Vertical shift up two units

b. $y = f(x + 2)$ Horizontal shift to the left two units

c. $y = -f(x)$ Reflection about the x-axis

d. $y = -f(x + 3) + 1$ Shift left three units, reflect about the x-axis, and shift up one unit

Basic Types of Transformations ($c > 0$)

Original graph:	$y = f(x)$
Horizontal shift c units to the **right:**	$y = f(x - c)$
Horizontal shift c units to the **left:**	$y = f(x + c)$
Vertical shift c units **downward:**	$y = f(x) - c$
Vertical shift c units **upward:**	$y = f(x) + c$
Reflection (about the x-axis):	$y = -f(x)$
Reflection (about the y-axis):	$y = f(-x)$
Reflection (about the origin):	$y = -f(-x)$

Science and Society/Superstock

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Classifications and Combinations of Functions

The modern notion of a function is derived from the efforts of many seventeenth- and eighteenth-century mathematicians. Of particular note was Leonhard Euler, who introduced the function notation $y = f(x)$. By the end of the eighteenth century, mathematicians and scientists had concluded that many real-world phenomena could be represented by mathematical models taken from a collection of functions called **elementary functions.** Elementary functions fall into three categories.

1. Algebraic functions (polynomial, radical, rational)
2. Trigonometric functions (sine, cosine, tangent, and so on)
3. Exponential and logarithmic functions

You will review the trigonometric functions in the next section. The other nonalgebraic functions, such as the inverse trigonometric functions and the exponential and logarithmic functions, are introduced in Chapter 5.

The most common type of algebraic function is a **polynomial function**

$$f(x) = a_n x^n + a_{n-1}x^{n-1} + \cdots + a_2 x^2 + a_1 x + a_0$$

REMARK Note that the *ellipsis points* (the three dots between the plus signs) indicate that the pattern continues.

where n is a nonnegative integer. The numbers a_i are **coefficients,** with a_n the **leading coefficient** and a_0 the **constant term** of the polynomial function. If $a_n \neq 0$, then n is the **degree** of the polynomial function. The zero polynomial $f(x) = 0$ is not assigned a degree. It is common practice to use subscript notation for coefficients of general polynomial functions, but for polynomial functions of low degree, these simpler forms are often used. (Note that $a \neq 0$.)

Zeroth degree:	$f(x) = a$	Constant function
First degree:	$f(x) = ax + b$	Linear function
Second degree:	$f(x) = ax^2 + bx + c$	Quadratic function
Third degree:	$f(x) = ax^3 + bx^2 + cx + d$	Cubic function

Although the graph of a nonconstant polynomial function can have several turns, eventually the graph will rise or fall without bound as x moves to the right or left. Whether the graph of

$$f(x) = a_n x^n + a_{n-1}x^{n-1} + \cdots + a_2 x^2 + a_1 x + a_0$$

eventually rises or falls can be determined by the function's degree (odd or even) and by the leading coefficient a_n, as indicated in Figure P.29. Note that the dashed portions of the graphs indicate that the **Leading Coefficient Test** determines *only* the right and left behavior of the graph.



Graphs of polynomial functions of even degree

Graphs of polynomial functions of odd degree

The Leading Coefficient Test for polynomial functions

Figure P.29

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Just as a rational number can be written as the quotient of two integers, a **rational function** can be written as the quotient of two polynomials. Specifically, a function f is rational when it has the form

$$f(x) = \frac{p(x)}{q(x)}, \quad q(x) \neq 0$$

where $p(x)$ and $q(x)$ are polynomials.

Polynomial functions and rational functions are examples of **algebraic functions.** An algebraic function of x is one that can be expressed as a finite number of sums, differences, multiples, quotients, and radicals involving x^n. For example, $f(x) = \sqrt{x+1}$ is algebraic. Functions that are not algebraic are **transcendental.** For instance, the trigonometric functions (see Section P.4) are transcendental.

Two functions can be combined in various ways to create new functions. For example, given $f(x) = 2x - 3$ and $g(x) = x^2 + 1$, you can form the functions shown.

$(f + g)(x) = f(x) + g(x) = (2x - 3) + (x^2 + 1)$ Sum

$(f - g)(x) = f(x) - g(x) = (2x - 3) - (x^2 + 1)$ Difference

$(fg)(x) = f(x)g(x) = (2x - 3)(x^2 + 1)$ Product

$(f/g)(x) = \frac{f(x)}{g(x)} = \frac{2x - 3}{x^2 + 1}$ Quotient

You can combine two functions in yet another way, called **composition.** The resulting function is called a **composite function.**



The domain of the composite function $f \circ g$

Figure P.30

Definition of Composite Function

Let f and g be functions. The function $(f \circ g)(x) = f(g(x))$ is the **composite** of f with g. The domain of $f \circ g$ is the set of all x in the domain of g such that $g(x)$ is in the domain of f (see Figure P.30).

The composite of f with g is generally not the same as the composite of g with f. This is shown in the next example.

EXAMPLE 4 Finding Composite Functions

See LarsonCalculus.com for an interactive version of this type of example.

For $f(x) = 2x - 3$ and $g(x) = x^2 + 1$, find (a) $f \circ g$ and (b) $g \circ f$.

Solution

a. $(f \circ g)(x) = f(g(x))$ Definition of $f \circ g$

$= f(x^2 + 1)$ Substitute $x^2 + 1$ for $g(x)$.

$= 2(x^2 + 1) - 3$ Definition of $f(x)$

$= 2x^2 - 1$ Simplify.

b. $(g \circ f)x = g(f(x))$ Definition of $g \circ f$

$= g(2x - 3)$ Substitute $2x - 3$ for $f(x)$.

$= (2x - 3)^2 + 1$ Definition of $g(x)$

$= 4x^2 - 12x + 10$ Simplify.

Note that $(f \circ g)(x) \neq (g \circ f)(x)$.

FOR FURTHER INFORMATION

For more on the history of the concept of a function, see the article "Evolution of the Function Concept: A Brief Survey" by Israel Kleiner in *The College Mathematics Journal*. To view this article, go to *MathArticles.com.*

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

In Section P.1, an x-intercept of a graph was defined to be a point $(a, 0)$ at which the graph crosses the x-axis. If the graph represents a function f, then the number a is a **zero** of f. In other words, *the zeros of a function f are the solutions of the equation $f(x) = 0$*. For example, the function

$$f(x) = x - 4$$

has a zero at $x = 4$ because $f(4) = 0$.

In Section P.1, you also studied different types of symmetry. In the terminology of functions, a function $y = f(x)$ is **even** when its graph is symmetric with respect to the y-axis, and is **odd** when its graph is symmetric with respect to the origin. The symmetry tests in Section P.1 yield the following test for even and odd functions.

Test for Even and Odd Functions

The function $y = f(x)$ is **even** when $f(-x) = f(x)$. The function $y = f(x)$ is **odd** when $f(-x) = -f(x)$.

It is important to note that some functions are neither even nor odd, as shown in the next example.



(a) Odd function



(b) Even function



(c) Neither even nor odd

Figure P.31

EXAMPLE 5 Even and Odd Functions and Zeros of Functions

Determine whether each function is even, odd, or neither. Then find the zeros of the function.

a. $f(x) = x^3 - x$ **b.** $g(x) = \dfrac{1}{x^2}$ **c.** $h(x) = -x^2 - x - 1$

Solution

a. This function is odd because

$$f(-x) = (-x)^3 - (-x) = -x^3 + x = -(x^3 - x) = -f(x).$$

The zeros of f are

$$\begin{aligned} x^3 - x &= 0 && \text{Let } f(x) = 0. \\ x(x^2 - 1) &= 0 && \text{Factor out common monomial factor.} \\ x(x - 1)(x + 1) &= 0 && \text{Factor difference of two squares.} \\ x &= 0, 1, -1. && \text{Zeros of } f \end{aligned}$$

See Figure P.31(a).

b. This function is even because

$$g(-x) = \frac{1}{(-x)^2} = \frac{1}{x^2} = g(x).$$

This function does not have zeros because $1/x^2$ is positive for all x in the domain, as shown in Figure P.31(b).

c. Substituting $-x$ for x produces

$$h(-x) = -(-x)^2 - (-x) - 1 = -x^2 + x - 1.$$

Because $h(x) = -x^2 - x - 1$ and $-h(x) = x^2 + x + 1$, you can conclude that

$$h(-x) \neq h(x) \qquad \text{Function is } \textit{not} \text{ even.}$$

and

$$h(-x) \neq -h(x). \qquad \text{Function is } \textit{not} \text{ odd.}$$

So, the function is neither even nor odd. This function does not have zeros because $-x^2 - x - 1$ is negative for all x, as shown in Figure P.31(c). ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.3 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Are all functions also relations? Are all relations also functions? Explain.
2. Explain the meanings of *domain* and *range*.
3. What are the three basic types of function transformations?
4. Describe the four cases of the Leading Coefficient Test.

Evaluating a Function **In Exercises 5–12, evaluate the function at each value of the independent variable. Simplify the results.**

5. $f(x) = 3x - 2$
   (a) $f(0)$ (b) $f(5)$ (c) $f(b)$ (d) $f(x - 1)$
6. $f(x) = 7x - 4$
   (a) $f(0)$ (b) $f(-3)$ (c) $f(b)$ (d) $f(x + 2)$
7. $f(x) = \sqrt{x^2 + 4}$
   (a) $f(-2)$ (b) $f(3)$ (c) $f(2)$ (d) $f(x + bx)$
8. $f(x) = \sqrt{x + 5}$
   (a) $f(-4)$ (b) $f(11)$ (c) $f(4)$ (d) $f(x + \Delta x)$
9. $g(x) = 5 - x^2$
   (a) $g(0)$ (b) $g(\sqrt{5})$ (c) $g(-2)$ (d) $g(t - 1)$
10. $g(x) = x^2(x - 4)$
    (a) $g(4)$ (b) $g(\frac{3}{2})$ (c) $g(c)$ (d) $g(t + 4)$
11. $f(x) = x^3$
    $\dfrac{f(x + \Delta x) - f(x)}{\Delta x}$
12. $f(x) = 3x - 1$
    $\dfrac{f(x) - f(1)}{x - 1}$

Finding the Domain and Range of a Function **In Exercises 13–22, find the domain and range of the function.**

13. $f(x) = 4x^2$
14. $g(x) = x^2 - 5$
15. $h(x) = 4 - x^2$
16. $f(x) = x^3$
17. $g(x) = \sqrt{6x}$
18. $h(x) = -\sqrt{x + 3}$
19. $f(x) = \sqrt{16 - x^2}$
20. $f(x) = |x - 3|$
21. $f(x) = \dfrac{3}{x}$
22. $f(x) = \dfrac{x - 2}{x + 4}$

Finding the Domain of a Function **In Exercises 23–26, find the domain of the function.**

23. $f(x) = \sqrt{x} + \sqrt{1 - x}$
24. $f(x) = \sqrt{x^2 - 3x + 2}$
25. $f(x) = \dfrac{1}{|x + 3|}$
26. $g(x) = \dfrac{1}{|x^2 - 4|}$

Evaluating a Piecewise-Defined Function **In Exercises 27–30, evaluate the function at each value of the independent variable. Then find the domain and range.**

27. $f(x) = \begin{cases} 2x + 1, & x < 0 \\ 2x + 2, & x \geq 0 \end{cases}$
    (a) $f(-1)$ (b) $f(0)$ (c) $f(2)$ (d) $f(t^2 + 1)$
28. $f(x) = \begin{cases} x^2 + 2, & x \leq 1 \\ 2x^2 + 2, & x > 1 \end{cases}$
    (a) $f(-2)$ (b) $f(0)$ (c) $f(1)$ (d) $f(s^2 + 2)$
29. $f(x) = \begin{cases} |x| + 1, & x < 1 \\ -x + 1, & x \geq 1 \end{cases}$
    (a) $f(-3)$ (b) $f(1)$ (c) $f(3)$ (d) $f(b^2 + 1)$
30. $f(x) = \begin{cases} \sqrt{x + 4}, & x \leq 5 \\ (x - 5)^2, & x > 5 \end{cases}$
    (a) $f(-3)$ (b) $f(0)$ (c) $f(5)$ (d) $f(10)$

Sketching a Graph of a Function **In Exercises 31–42, sketch a graph of the function and find its domain and range. Use a graphing utility to verify your graph.**

31. $f(x) = 4 - x$
32. $f(x) = \frac{5}{6} - \frac{2}{3}x$
33. $f(x) = x^2 + 5$
34. $f(x) = -2x^2 - 1$
35. $f(x) = (x - 1)^3 + 2$
36. $f(x) = \frac{1}{4}x^3 + 3$
37. $f(x) = \sqrt{9 - x^2}$
38. $f(x) = x + \sqrt{4 - x^2}$
39. $g(x) = |x| - 5$
40. $f(x) = |x^2 - 1|$
41. $g(x) = \dfrac{1}{x^2 + 2}$
42. $f(t) = \dfrac{2}{7 + t}$

Using the Vertical Line Test **In Exercises 43–46, use the Vertical Line Test to determine whether y is a function of x. To print an enlarged copy of the graph, go to *MathGraphs.com*.**

43. $x - y^2 = 0$



44. $\sqrt{x^2 - 4} - y = 0$



45. $y = \begin{cases} x + 1, & x \leq 0 \\ -x + 2, & x > 0 \end{cases}$



46. $x^2 + y^2 = 4$



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Determining Whether an Equation Is a Function **In Exercises 47–50, determine whether y is a function of x.**

47. $x^2 + y = 16$

48. $x^2 + y^2 = 16$

49. $y^2 = x^2 - 1$

50. $x^2y - x^2 + 4y = 0$

Transformation of a Function **In Exercises 51–54, the graph shows one of the six basic functions on page 22 and a transformation of the function. Describe the transformation. Then use your description to write an equation for the transformation.**

51.



52.



53.



54.



Matching **In Exercises 55–60, use the graph of $y = f(x)$ to match the function with its graph.**



55. $y = f(x + 5)$

56. $y = f(x) - 5$

57. $y = -f(-x) - 2$

58. $y = -f(x - 4)$

59. $y = f(x + 6) + 2$

60. $y = f(x - 1) + 3$

61. Sketching Transformations Use the graph of f shown in the figure to sketch the graph of each function. To print an enlarged copy of the graph, go to *MathGraphs.com*.

(a) $f(x + 3)$

(b) $f(x - 1)$

(c) $f(x) + 2$

(d) $f(x) - 4$

(e) $3f(x)$

(f) $\frac{1}{4}f(x)$

(g) $-f(x)$

(h) $-f(-x)$



62. Heaviside Function The Heaviside function $H(x)$ is widely used in engineering applications.

$$H(x) = \begin{cases} 1, & x \geq 0 \\ 0, & x < 0 \end{cases}$$

Sketch the graph of the Heaviside function and the graphs of the following functions.

(a) $H(x) - 2$ (b) $H(x - 2)$ (c) $-H(x)$

(d) $H(-x)$ (e) $\frac{1}{2}H(x)$ (f) $-H(x - 2) + 2$

Combinations of Functions **In Exercises 63 and 64, find (a) $(f + g)(x)$, (b) $(f - g)(x)$, (c) $(fg)(x)$, and (d) $(f/g)(x)$.**

63. $f(x) = 2x - 5$, $g(x) = 4 - 3x$

64. $f(x) = x^2 + 5x + 4$, $g(x) = x + 1$

65. Evaluating Composite Functions Let $f(x) = \sqrt{x}$ and $g(x) = x^2 - 1$. Evaluate each expression.

(a) $f(g(1))$ (b) $g(f(1))$

(c) $g(f(0))$ (d) $f(g(-4))$

(e) $f(g(x))$ (f) $g(f(x))$

66. Evaluating Composite Functions Let $f(x) = 2x^3$ and $g(x) = 4x + 3$. Evaluate each expression.

(a) $f(g(0))$ (b) $f\left(g\left(\frac{1}{2}\right)\right)$

(c) $g(f(0))$ (d) $g\left(f\left(-\frac{1}{4}\right)\right)$

(e) $f(g(x))$ (f) $g(f(x))$

Finding Composite Functions **In Exercises 67–72, find the composite functions $f \circ g$ and $g \circ f$. Find the domain of each composite function. Are the two composite functions equal?**

67. $f(x) = x$, $g(x) = x^2$

68. $f(x) = \sqrt[3]{x - 5}$, $g(x) = x^3 + 5$

69. $f(x) = x^2$, $g(x) = \sqrt{x}$

70. $f(x) = x^2 - 1$, $g(x) = -x$

71. $f(x) = \frac{3}{x}$, $g(x) = x^2 - 1$

72. $f(x) = \frac{1}{x}$, $g(x) = \sqrt{x + 2}$

73. Evaluating Composite Functions Use the graphs of f and g to evaluate each expression. When the result is undefined, explain why.



(a) $(f \circ g)(3)$ (b) $g(f(2))$

(c) $g(f(5))$ (d) $(f \circ g)(-3)$

(e) $(g \circ f)(-1)$ (f) $f(g(-1))$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

74. Ripples A pebble is dropped into a calm pond, causing ripples in the form of concentric circles. The radius (in feet) of the outer ripple is given by $r(t) = 0.6t$, where t is the time in seconds after the pebble strikes the water. The area of the circle is given by the function $A(r) = \pi r^2$. Find and interpret $(A \circ r)(t)$.

Think About It **In Exercises 75 and 76, $F(x) = f \circ g$. Identify functions for f and g. (There are many correct answers.)**

75. $F(x) = \sqrt{2x - 2}$

76. $F(x) = \dfrac{1}{4x^6}$

Think About It **In Exercises 77 and 78, find the coordinates of a second point on the graph of a function f when the given point is on the graph and the function is (a) even and (b) odd.**

77. $\left(-\frac{3}{2}, 4\right)$

78. $(4, 9)$

79. Even and Odd Functions The graphs of f, g, and h are shown in the figure. Decide whether each function is even, odd, or neither.



Figure for 79



Figure for 80

80. Even and Odd Functions The domain of the function f shown in the figure is $-6 \le x \le 6$.

(a) Complete the graph of f when f is even.

(b) Complete the graph of f when f is odd.

Even and Odd Functions and Zeros of Functions **In Exercises 81–84, determine whether the function is even, odd, or neither. Then find the zeros of the function. Use a graphing utility to verify your result.**

81. $f(x) = x^2(4 - x^2)$

82. $f(x) = \sqrt[3]{x}$

83. $f(x) = 2\sqrt[6]{x}$

84. $f(x) = 4x^4 - 3x^2$

Writing Functions **In Exercises 85–88, write an equation for a function that has the given graph.**

85. Line segment connecting $(-2, 4)$ and $(0, -6)$

86. Line segment connecting $(3, 1)$ and $(5, 8)$

87. The bottom half of the parabola $x + y^2 = 0$

88. The bottom half of the circle $x^2 + y^2 = 36$

Sketching a Graph **In Exercises 89–92, sketch a possible graph of the situation.**

89. The speed of an airplane as a function of time during a 5-hour flight

90. The height of a baseball as a function of horizontal distance during a home run

91. A student commutes 15 miles to attend college. After driving for a few minutes, the student remembers that a term paper that is due has been forgotten. Driving faster than usual, the student returns home, picks up the paper, and once again starts toward school. Consider the student's distance from home as a function of time.

92. A person buys a new car and keeps it for 6 years. During year 4, the person buys several expensive upgrades. Consider the value of the car as a function of time.

93. Domain Find the value of c such that the domain of

$f(x) = \sqrt{c - x^2}$

is $[-5, 5]$.

94. Domain Find all values of c such that the domain of

$f(x) = \dfrac{x + 3}{x^2 + 3cx + 6}$

is the set of all real numbers.

Exploring Concepts

95. Can the graph of a one-to-one function intersect a horizontal line more than once? Explain.

96. Give an example of functions f and g such that $f \circ g = g \circ f$ and $f(x) \neq g(x)$. Do not use any pair of applicable functions from Exercises 67–72.

97. Does the degree of a polynomial function determine whether the function is even or odd? Explain.

98. Determine whether the function $f(x) = 0$ is even, odd, both, or neither. Explain.

99. Graphical Reasoning An electronically controlled thermostat is programmed to lower the temperature during the night automatically. The temperature T (in degrees Celsius) is given in terms of t, the time in hours on a 24-hour clock (see figure).



(a) Approximate $T(4)$ and $T(15)$.

(b) The thermostat is reprogrammed to produce a temperature $H(t) = T(t - 1)$. How does this change the temperature?

(c) The thermostat is reprogrammed to produce a temperature $H(t) = T(t) - 1$. How does this change the temperature?

(d) Write a piecewise-defined function that represents the graph.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

100. HOW DO YOU SEE IT? Water runs into a vase of height 30 centimeters at a constant rate. The vase is full after 5 seconds. Use this information and the shape of the vase shown to answer the questions when d is the depth of the water in centimeters and t is the time in seconds (see figure).



(a) Explain why d is a function of t.

(b) Determine the domain and range of the function.

(c) Sketch a possible graph of the function.

(d) Use the graph in part (c) to approximate $d(4)$. What does this represent?

101. Automobile Aerodynamics

The horsepower H required to overcome wind drag on a particular automobile is given by

$$H(x) = 0.00004636x^3$$

where x is the speed of the car in miles per hour.

(a) Use a graphing utility to graph the function.

(b) Rewrite the horsepower function so that x represents the speed in kilometers per hour. [Find $H(x/1.6)$.]

102. Writing Use a graphing utility to graph the polynomial functions

$$p_1(x) = x^3 - x + 1 \quad \text{and} \quad p_2(x) = x^3 - x.$$

How many zeros does each function have? Is there a cubic polynomial that has no zeros? Explain.

103. Proof Prove that the function is odd.

$$f(x) = a_{2n+1}x^{2n+1} + \cdots + a_3x^3 + a_1x$$

104. Proof Prove that the function is even.

$$f(x) = a_{2n}x^{2n} + a_{2n-2}x^{2n-2} + \cdots + a_2x^2 + a_0$$

105. Proof Prove that the product of two even (or two odd) functions is even.

106. Proof Prove that the product of an odd function and an even function is odd.

107. Length A right triangle is formed in the first quadrant by the x- and y-axes and a line through the point $(3, 2)$ (see figure). Write the length L of the hypotenuse as a function of x.



108. Volume An open box of maximum volume is to be made from a square piece of material 24 centimeters on a side by cutting equal squares from the corners and turning up the sides (see figure).



(a) Write the volume V as a function of x, the length of the corner squares. What is the domain of the function?

(b) Use a graphing utility to graph the volume function and approximate the dimensions of the box that yield a maximum volume.

True or False? **In Exercises 109–114, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

109. If $f(a) = f(b)$, then $a = b$.

110. A vertical line can intersect the graph of a function at most once.

111. If $f(x) = f(-x)$ for all x in the domain of f, then the graph of f is symmetric with respect to the y-axis.

112. If f is a function, then $f(ax) = af(x)$.

113. The graph of a function of x cannot have symmetry with respect to the x-axis.

114. If the domain of a function consists of a single number, then its range must also consist of only one number.

PUTNAM EXAM CHALLENGE

115. Let R be the region consisting of the points (x, y) of the Cartesian plane satisfying both $|x| - |y| \leq 1$ and $|y| \leq 1$. Sketch the region R and find its area.

116. Consider a polynomial $f(x)$ with real coefficients having the property $f(g(x)) = g(f(x))$ for every polynomial $g(x)$ with real coefficients. Determine and prove the nature of $f(x)$.

These problems were composed by the Committee on the Putnam Prize Competition. © The Mathematical Association of America. All rights reserved.

Viaframe/Getty Images

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.4 Review of Trigonometric Functions

GO DIGITAL

- **Describe angles and use degree measure.**
- **Use radian measure.**
- **Understand the definitions of the six trigonometric functions.**
- **Evaluate trigonometric functions.**
- **Solve trigonometric equations.**
- **Graph trigonometric functions.**

Angles and Degree Measure

An **angle** has three parts: an **initial ray** (or side), a **terminal ray,** and a **vertex** (the point of intersection of the two rays), as shown in Figure P.32(a). An angle is in **standard position** when its initial ray coincides with the positive x-axis and its vertex is at the origin, as shown in Figure P.32(b).



(a) Angle **(b)** Angle in standard position

Figure P.32

It is assumed that you are familiar with the degree measure of an angle.* It is common practice to use θ (the lowercase Greek letter theta) to represent both an angle and its measure. Angles between 0° and 90° are **acute,** and angles between 90° and 180° are **obtuse.**



Coterminal angles

Figure P.33

Positive angles are measured *counterclockwise*, and negative angles are measured *clockwise*. For instance, Figure P.33 shows an angle whose measure is $-45°$. You cannot assign a measure to an angle by simply knowing where its initial and terminal rays are located. To measure an angle, you must also know how the terminal ray was rotated. For example, Figure P.33 shows that the angle measuring $-45°$ has the same terminal ray as the angle measuring 315°. Such angles are **coterminal.** In general, if θ is any angle, then $\theta + n(360)$, n is a nonzero integer, is coterminal with θ.

An angle that is larger than 360° is one whose terminal ray has been rotated more than one full revolution counterclockwise, as shown in Figure P.34(a). To form an angle whose measure is less than $-360°$, rotate a terminal ray more than one full revolution clockwise, as shown in Figure P.34(b).



(a) An angle whose measure is greater than 360° **(b)** An angle whose measure is less than $-360°$

Figure P.34

*For a more complete review of trigonometry, see *Precalculus*, 11th edition, or *Trigonometry: A Right Triangle Approach*, 1st edition, both by Ron Larson (Boston, Massachusetts: Cengage, 2022).

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Radian Measure

To assign a radian measure to an angle θ, consider θ to be a central angle of a circle of radius 1, as shown in Figure P.35. The **radian measure** of θ is then defined to be the length of the arc of the sector. Because the circumference of a circle is $2\pi r$, the circumference of a **unit circle** (of radius 1) is 2π. This implies that the radian measure of an angle measuring 360° is 2π. In other words, $360^\circ = 2\pi$ radians.

Using radian measure for θ, the **length** s of a circular arc of radius r is $s = r\theta$, as shown in Figure P.36.



Unit circle
Figure P.35



Circle of radius r
Figure P.36

You should know the conversions of the common angles shown in Figure P.37. For other angles, use the fact that 180° is equal to π radians.



Radian and degree measures for several common angles
Figure P.37

EXAMPLE 1 Conversions Between Degrees and Radians

a. $40^\circ = (40 \text{ deg})\left(\dfrac{\pi \text{ rad}}{180 \text{ deg}}\right) = \dfrac{2\pi}{9}$ radian

b. $540^\circ = (540 \text{ deg})\left(\dfrac{\pi \text{ rad}}{180 \text{ deg}}\right) = 3\pi$ radians

c. $-270^\circ = (-270 \text{ deg})\left(\dfrac{\pi \text{ rad}}{180 \text{ deg}}\right) = -\dfrac{3\pi}{2}$ radians

d. $-\dfrac{\pi}{2}$ radians $= \left(-\dfrac{\pi}{2} \text{ rad}\right)\left(\dfrac{180 \text{ deg}}{\pi \text{ rad}}\right) = -90^\circ$

e. 2 radians $= (2 \text{ rad})\left(\dfrac{180 \text{ deg}}{\pi \text{ rad}}\right) = \left(\dfrac{360}{\pi}\right)^\circ \approx 114.59^\circ$

f. $\dfrac{9\pi}{2}$ radians $= \left(\dfrac{9\pi}{2} \text{ rad}\right)\left(\dfrac{180 \text{ deg}}{\pi \text{ rad}}\right) = 810^\circ$

TECHNOLOGY Most graphing utilities have both *degree* and *radian* modes. You should learn how to use your graphing utility to convert from degrees to radians, and vice versa. Use a graphing utility to verify the results of Example 1.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



Sides of a right triangle
Figure P.38



An angle in standard position
Figure P.39

The Trigonometric Functions

There are two common approaches to the study of trigonometry. In one, the trigonometric functions are defined as ratios of two sides of a right triangle. In the other, these functions are defined in terms of a point on the terminal ray of an angle in standard position. The six trigonometric functions, **sine, cosine, tangent, cotangent, secant,** and **cosecant** (abbreviated as sin, cos, tan, cot, sec, and csc, respectively), are defined below from both viewpoints.

Definition of the Six Trigonometric Functions

Right triangle definitions, where $0 < \theta < \frac{\pi}{2}$ (see Figure P.38)

$$\sin\theta = \frac{\text{opposite}}{\text{hypotenuse}} \qquad \cos\theta = \frac{\text{adjacent}}{\text{hypotenuse}} \qquad \tan\theta = \frac{\text{opposite}}{\text{adjacent}}$$

$$\csc\theta = \frac{\text{hypotenuse}}{\text{opposite}} \qquad \sec\theta = \frac{\text{hypotenuse}}{\text{adjacent}} \qquad \cot\theta = \frac{\text{adjacent}}{\text{opposite}}$$

Circular function definitions, where θ *is any angle* (see Figure P.39)

$$\sin\theta = \frac{y}{r} \qquad \cos\theta = \frac{x}{r} \qquad \tan\theta = \frac{y}{x},\ x \neq 0$$

$$\csc\theta = \frac{r}{y},\ y \neq 0 \qquad \sec\theta = \frac{r}{x},\ x \neq 0 \qquad \cot\theta = \frac{x}{y},\ y \neq 0$$

The trigonometric identities listed below are direct consequences of the definitions. These identities and others are listed on the formula card inside the front cover. [Note that ϕ is the lowercase Greek letter phi and $\sin^2\theta$ is used to represent $(\sin\theta)^2$.]

Trigonometric Identities

Sum and Difference Formulas

$$\sin(\theta \pm \phi) = \sin\theta\cos\phi \pm \cos\theta\sin\phi$$

$$\cos(\theta \pm \phi) = \cos\theta\cos\phi \mp \sin\theta\sin\phi$$

$$\tan(\theta \pm \phi) = \frac{\tan\theta \pm \tan\phi}{1 \mp \tan\theta\tan\phi}$$

Power-Reducing Formulas

$$\sin^2\theta = \frac{1 - \cos 2\theta}{2}$$

$$\cos^2\theta = \frac{1 + \cos 2\theta}{2}$$

$$\tan^2\theta = \frac{1 - \cos 2\theta}{1 + \cos 2\theta}$$

Double-Angle Formulas

$$\sin 2\theta = 2\sin\theta\cos\theta$$

$$\cos 2\theta = 2\cos^2\theta - 1 = 1 - 2\sin^2\theta = \cos^2\theta - \sin^2\theta$$

$$\tan 2\theta = \frac{2\tan\theta}{1 - \tan^2\theta}$$

Pythagorean Identities

$$\sin^2\theta + \cos^2\theta = 1$$
$$1 + \tan^2\theta = \sec^2\theta$$
$$1 + \cot^2\theta = \csc^2\theta$$

Even/Odd Identities

$$\sin(-\theta) = -\sin\theta \qquad \csc(-\theta) = -\csc\theta$$
$$\cos(-\theta) = \cos\theta \qquad \sec(-\theta) = \sec\theta$$
$$\tan(-\theta) = -\tan\theta \qquad \cot(-\theta) = -\cot\theta$$

Reciprocal Identities

$$\csc\theta = \frac{1}{\sin\theta}$$

$$\sec\theta = \frac{1}{\cos\theta}$$

$$\cot\theta = \frac{1}{\tan\theta}$$

Cofunction Identities

$$\sin\left(\frac{\pi}{2} - u\right) = \cos u \qquad \cos\left(\frac{\pi}{2} - u\right) = \sin u$$

$$\tan\left(\frac{\pi}{2} - u\right) = \cot u \qquad \cot\left(\frac{\pi}{2} - u\right) = \tan u$$

$$\sec\left(\frac{\pi}{2} - u\right) = \csc u \qquad \csc\left(\frac{\pi}{2} - u\right) = \sec u$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Evaluating Trigonometric Functions

There are two ways to evaluate trigonometric functions: (1) decimal approximations with a calculator and (2) exact evaluations using trigonometric identities and formulas from geometry. When using a calculator to evaluate a trigonometric function, remember to set the calculator to the appropriate mode—*degree* mode or *radian* mode.

EXAMPLE 2 Evaluating Trigonometric Functions

Find the exact value of the sine, cosine, and tangent of $\pi/3$.

Solution Because $60° = \pi/3$ radians, draw an equilateral triangle with sides of length 1 and θ as one of its angles, as shown in Figure P.40. Because the altitude of this triangle bisects its base, you know that $x = \frac{1}{2}$. Using the Pythagorean Theorem, you obtain

$$y = \sqrt{r^2 - x^2} = \sqrt{1 - \left(\frac{1}{2}\right)^2} = \sqrt{\frac{3}{4}} = \frac{\sqrt{3}}{2}.$$

Now, knowing the values of x, y, and r, evaluate the sine, cosine, and tangent of $\pi/3$.

$$\sin\frac{\pi}{3} = \frac{y}{r} = \frac{\sqrt{3}/2}{1} = \frac{\sqrt{3}}{2} \qquad \sin\theta = \frac{y}{r}$$

$$\cos\frac{\pi}{3} = \frac{x}{r} = \frac{1/2}{1} = \frac{1}{2} \qquad \cos\theta = \frac{x}{r}$$

$$\tan\frac{\pi}{3} = \frac{y}{x} = \frac{\sqrt{3}/2}{1/2} = \sqrt{3} \qquad \tan\theta = \frac{y}{x}$$





Figure P.40

Note that all angles in this text are measured in radians unless stated otherwise. For example, when sin 3 is written, the sine of 3 radians is meant, and when sin 3° is written, the sine of 3 degrees is meant.

The degree and radian measures of several common angles are shown in the table below, along with the corresponding values of the sine, cosine, and tangent (see Figure P.41).

Trigonometric Values of Common Angles

θ (degrees)	0°	30°	45°	60°	90°	180°	270°
θ (radians)	0	$\frac{\pi}{6}$	$\frac{\pi}{4}$	$\frac{\pi}{3}$	$\frac{\pi}{2}$	π	$\frac{3\pi}{2}$
$\sin\theta$	0	$\frac{1}{2}$	$\frac{\sqrt{2}}{2}$	$\frac{\sqrt{3}}{2}$	1	0	-1
$\cos\theta$	1	$\frac{\sqrt{3}}{2}$	$\frac{\sqrt{2}}{2}$	$\frac{1}{2}$	0	-1	0
$\tan\theta$	0	$\frac{\sqrt{3}}{3}$	1	$\sqrt{3}$	Undefined	0	Undefined



Common angles

Figure P.41

EXAMPLE 3 Using Trigonometric Identities

a. $\sin\left(-\frac{\pi}{3}\right) = -\sin\frac{\pi}{3} = -\frac{\sqrt{3}}{2}$ $\qquad \sin(-\theta) = -\sin\theta$

b. $\sec 60° = \frac{1}{\cos 60°} = \frac{1}{1/2} = 2$ $\qquad \sec\theta = \frac{1}{\cos\theta}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Quadrant signs for trigonometric functions

Figure P.42

The quadrant signs for the sine, cosine, and tangent functions are shown in Figure P.42. To extend the use of the table on the preceding page to angles in quadrants other than the first quadrant, you can use the concept of a **reference angle** (see Figure P.43), with the appropriate quadrant sign. For instance, the reference angle for $3\pi/4$ is $\pi/4$, and because the sine is positive in Quadrant II, you can write

$$\sin\frac{3\pi}{4} = \sin\frac{\pi}{4} = \frac{\sqrt{2}}{2}.$$

Similarly, because the reference angle for $330°$ is $30°$, and the tangent is negative in Quadrant IV, you can write

$$\tan 330° = -\tan 30° = -\frac{\sqrt{3}}{3}.$$



Quadrant II
$\theta' = \pi - \theta$ (radians)
$\theta' = 180° - \theta$ (degrees)

Quadrant III
$\theta' = \theta - \pi$ (radians)
$\theta' = \theta - 180°$ (degrees)

Quadrant IV
$\theta' = 2\pi - \theta$ (radians)
$\theta' = 360° - \theta$ (degrees)

Figure P.43

Solving Trigonometric Equations

How would you solve the equation $\sin\theta = 0$? You know that $\theta = 0$ is one solution, but this is not the only solution. Any one of the following values of θ is also a solution.

$$\ldots, -3\pi, -2\pi, -\pi, 0, \pi, 2\pi, 3\pi, \ldots$$

You can write this infinite solution set as $\{n\pi:\ n \text{ is an integer}\}$.

GO DIGITAL

EXAMPLE 4 Solving a Trigonometric Equation

Solve the equation $\sin\theta = -\frac{\sqrt{3}}{2}$.

Solution To solve the equation, you should consider that the sine function is negative in Quadrants III and IV and that

$$\sin\frac{\pi}{3} = \frac{\sqrt{3}}{2}.$$

So, you are seeking values of θ in the third and fourth quadrants that have a reference angle of $\pi/3$. In the interval $[0, 2\pi]$, the two angles fitting these criteria are

$$\theta = \pi + \frac{\pi}{3} = \frac{4\pi}{3} \quad \text{and} \quad \theta = 2\pi - \frac{\pi}{3} = \frac{5\pi}{3}.$$

By adding integer multiples of 2π to each solution, you obtain the general solution

$$\theta = \frac{4\pi}{3} + 2n\pi \quad \text{or} \quad \theta = \frac{5\pi}{3} + 2n\pi \qquad \text{General solution}$$

where n is an integer. (See Figure P.44.)



Solution points of $\sin\theta = -\frac{\sqrt{3}}{2}$

Figure P.44

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

REMARK Be sure you understand the mathematical conventions regarding parentheses and trigonometric functions. For instance, in Example 5, $\cos 2\theta$ means $\cos(2\theta)$.

EXAMPLE 5 **Solving a Trigonometric Equation**

Solve the equation $\cos 2\theta = 2 - 3 \sin \theta$, where $0 \leq \theta \leq 2\pi$.

Solution The equation contains cosine and sine functions. Use the double-angle formula $\cos 2\theta = 1 - \sin^2 \theta$ to rewrite the equation so that it has only sine functions. Then treat the equation as quadratic in $\sin x$ and factor.

$$\begin{aligned} \cos 2\theta &= 2 - 3 \sin \theta && \text{Write original equation.} \\ 1 - 2 \sin^2 \theta &= 2 - 3 \sin \theta && \text{Double-angle formula} \\ 0 &= 2 \sin^2 \theta - 3 \sin \theta + 1 && \text{Equation of quadratic type } ax^2 + bx + c = 0 \\ 0 &= (2 \sin \theta - 1)(\sin \theta - 1) && \text{Factor.} \end{aligned}$$

If $2 \sin \theta - 1 = 0$, then $\sin \theta = 1/2$ and $\theta = \pi/6$ or $\theta = 5\pi/6$. If $\sin \theta - 1 = 0$, then $\sin \theta = 1$ and $\theta = \pi/2$. So, for $0 \leq \theta \leq 2\pi$, the solutions are

$$\theta = \frac{\pi}{6}, \quad \frac{5\pi}{6}, \quad \text{or} \quad \frac{\pi}{2}.$$

Graphs of Trigonometric Functions

A function f is **periodic** when there exists a positive real number p such that $f(x + p) = f(x)$ for all x in the domain of f. The least such positive value of p is the **period** of f. The sine, cosine, secant, and cosecant functions each have a period of 2π, and the other two trigonometric functions, tangent and cotangent, have a period of π, as shown in Figure P.45.

GO DIGITAL


Domain: (−∞, ∞)
Range: [−1, 1]
Period: 2π
y = sin x
Domain: (−∞, ∞)
Range: [−1, 1]
Period: 2π
y = cos x
Domain: all x ≠ π/2 + nπ
Range: (−∞, ∞)
Period: π
y = tan x
Domain: all x ≠ nπ
Range: (−∞, −1] and [1, ∞)
Period: 2π
y = csc x = 1/sin x
Domain: all x ≠ π/2 + nπ
Range: (−∞, −1] and [1, ∞)
Period: 2π
y = sec x = 1/cos x
Domain: all x ≠ nπ
Range: (−∞, ∞)
Period: π
y = cot x = 1/tan x

The graphs of the six trigonometric functions

Figure P.45

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

TECHNOLOGY

To produce the graphs shown in Figure P.45 with a graphing utility, make sure the graphing utility is set to *radian* mode.

Note in Figure P.45 that the maximum value of $\sin x$ and $\cos x$ is 1, and the minimum value is -1. The graphs of the functions $y = a \sin bx$ and $y = a \cos bx$ oscillate between $-a$ and a, and so they have an **amplitude** of $|a|$. Furthermore, because $bx = 0$ when $x = 0$ and $bx = 2\pi$ when $x = 2\pi/b$, it follows that the functions $y = a \sin bx$ and $y = a \cos bx$ each have a period of $2\pi/|b|$. The table below summarizes the amplitudes and periods of some types of trigonometric functions.

Function	Period	Amplitude
$y = a \sin bx$ or $y = a \cos bx$	$\frac{2\pi}{\lvert b\rvert}$	$\lvert a\rvert$
$y = a \tan bx$ or $y = a \cot bx$	$\frac{\pi}{\lvert b\rvert}$	Not applicable
$y = a \sec bx$ or $y = a \csc bx$	$\frac{2\pi}{\lvert b\rvert}$	Not applicable



Figure P.46

EXAMPLE 6 Sketching the Graph of a Trigonometric Function

Sketch the graph of $f(x) = 3 \cos 2x$.

Solution The graph of $f(x) = 3 \cos 2x$ has an amplitude of 3 and a period of $2\pi/2 = \pi$. Using the basic shape of the graph of the cosine function, sketch one period of the function on the interval $[0, \pi]$, using the following pattern.

Maximum: $(0, 3)$

Minimum: $\left(\frac{\pi}{2}, -3\right)$

Maximum: $(\pi, 3)$

By continuing this pattern, you can sketch several cycles of the graph, as shown in Figure P.46.

EXAMPLE 7 Shifts of Graphs of Trigonometric Functions

a. To sketch the graph of $f(x) = \sin(x + \pi/2)$, shift the graph of $y = \sin x$ to the left $\pi/2$ units, as shown in Figure P.47(a).

b. To sketch the graph of $f(x) = 2 + \sin x$, shift the graph of $y = \sin x$ upward two units, as shown in Figure P.47(b).

c. To sketch the graph of $f(x) = 2 + \sin(x - \pi/4)$, shift the graph of $y = \sin x$ upward two units and to the right $\pi/4$ units, as shown in Figure P.47(c).



(a) Horizontal shift to the left **(b)** Vertical shift upward **(c)** Horizontal and vertical shifts

Transformations of the graph of $y = \sin x$

Figure P.47

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.4 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain how to find coterminal angles in radians.
2. Explain how to convert from degrees to radians.
3. Find $\sin\theta$, $\cos\theta$, and $\tan\theta$.



4. Describe the meaning of *amplitude* and *period*.

Coterminal Angles in Degrees **In Exercises 5 and 6, determine two coterminal angles in degree measure (one positive and one negative) for each angle.**

5. (a) 

(b) 

6. (a) 

(b) 

Coterminal Angles in Radians **In Exercises 7 and 8, determine two coterminal angles in radian measure (one positive and one negative) for each angle.**

7. (a) 

(b) 

8. (a) 

(b) 

Degrees to Radians **In Exercises 9 and 10, convert each degree measure to radian measure as a multiple of π and as a decimal accurate to three decimal places.**

9. (a) 30° (b) 150° (c) 315° (d) 120°
10. (a) −20° (b) −240° (c) −330° (d) 144°

Radians to Degrees **In Exercises 11 and 12, convert each radian measure to degree measure.**

11. (a) $\frac{3\pi}{2}$ (b) $\frac{7\pi}{6}$ (c) $-\frac{7\pi}{12}$ (d) -2.367
12. (a) $\frac{7\pi}{3}$ (b) $-\frac{11\pi}{30}$ (c) $\frac{11\pi}{6}$ (d) 0.438

13. **Completing a Table** Let r represent the radius of a circle, θ the central angle (measured in radians), and s the length of the arc subtended by the angle. Use the relationship $s = r\theta$ to complete the table.

r	8 ft	15 in.	85 cm		
s	12 ft			96 in.	8642 mi
θ		1.6	$\frac{3\pi}{4}$	4	$\frac{2\pi}{3}$

14. **Angular Speed** A car is moving at the rate of 50 miles per hour, and the diameter of its wheels is 2.5 feet.
   (a) Find the number of revolutions per minute that the wheels are rotating.
   (b) Find the angular speed of the wheels in radians per minute.

Evaluating Trigonometric Functions **In Exercises 15 and 16, evaluate the six trigonometric functions of each angle θ.**

15. (a) 

(b) 

16. (a) 

(b) 

Evaluating Trigonometric Functions **In Exercises 17–20, sketch a right triangle corresponding to the trigonometric function of the acute angle θ. Then evaluate the other five trigonometric functions of θ.**

17. $\sin\theta = \frac{1}{2}$
18. $\sin\theta = \frac{1}{3}$
19. $\cos\theta = \frac{4}{5}$
20. $\sec\theta = \frac{13}{5}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Evaluating Trigonometric Functions **In Exercises 21 and 22, find the exact value of the sine, cosine, and tangent of each angle. Do not use a calculator.**

21. (a) $225°$ (b) $-225°$ (c) $\frac{5\pi}{3}$ (d) $\frac{11\pi}{6}$

22. (a) $60°$ (b) $120°$ (c) $\frac{\pi}{4}$ (d) $\frac{5\pi}{4}$

Using Trigonometric Identities **In Exercises 23 and 24, use trigonometric identities to find the exact value of each trigonometric function.**

23. (a) $\cos(-60°)$ (b) $\cot(\pi/6)$

24. (a) $\csc(\pi/3)$ (b) $\tan(-30°)$

Evaluating Trigonometric Functions **In Exercises 25–28, use a calculator to evaluate each trigonometric function. Round your answers to four decimal places.**

25. (a) $\sin 10°$ (b) $\csc 10°$

26. (a) $\sec 225°$ (b) $\sec 135°$

27. (a) $\tan\frac{\pi}{9}$ (b) $\tan\frac{10\pi}{9}$

28. (a) $\cot(1.35)$ (b) $\tan(1.35)$

Determining Quadrants **In Exercises 29 and 30, determine the quadrant in which θ lies.**

29. (a) $\sin\theta < 0$ and $\cos\theta < 0$
(b) $\sec\theta > 0$ and $\cot\theta < 0$

30. (a) $\sin\theta > 0$ and $\cos\theta < 0$
(b) $\csc\theta < 0$ and $\tan\theta > 0$

Solving Trigonometric Equations **In Exercises 31–34, find two solutions of each equation. Give your answers in radians ($0 \le \theta \le 2\pi$). Do not use a calculator.**

31. (a) $\cos\theta = \frac{\sqrt{2}}{2}$ (b) $\cos\theta = -\frac{\sqrt{2}}{2}$

32. (a) $\sec\theta = 2$ (b) $\sec\theta = -2$

33. (a) $\tan\theta = 1$ (b) $\cot\theta = -\sqrt{3}$

34. (a) $\sin\theta = \frac{\sqrt{3}}{2}$ (b) $\sin\theta = -\frac{1}{2}$

Solving a Trigonometric Equation **In Exercises 35–46, solve the equation for θ, where $0 \le \theta \le 2\pi$.**

35. $2\sin^2\theta = 1$

36. $\tan^2\theta = 3$

37. $\tan^2\theta - \tan\theta = 0$

38. $2\cos^2\theta - \cos\theta = 1$

39. $2\cos^2\theta + \cos\theta = 1$

40. $\csc^2\theta + \csc\theta - 2 = 0$

41. $\sec\theta\csc\theta = 2\csc\theta$

42. $\sin\theta = \cos\theta$

43. $\cos^2\theta + \sin\theta = 1$

44. $\tan^2\theta = \sec\theta - 1$

45. $\cos\frac{\theta}{2} - \cos\theta = 1$

46. $\cos\frac{\theta}{2} - \sin\theta = 0$

47. Airplane Ascent An airplane leaves the runway climbing at an angle of $18°$ with a speed of 275 feet per second (see figure). Find the altitude a of the plane after 1 minute.



48. Height of a Mountain While traveling across flat land, you notice a mountain directly in front of you. Its angle of elevation (to the peak) is $3.5°$. After you drive 13 miles closer to the mountain, the angle of elevation is $9°$. Approximate the height of the mountain.



Not drawn to scale

Period and Amplitude of a Trigonometric Function **In Exercises 49–52, determine the period and amplitude of the function.**

49. $y = 2\sin 2x$



50. $y = \frac{3}{2}\cos\frac{x}{2}$



51. $y = -3\sin 4\pi x$

52. $y = \frac{2}{3}\cos\frac{\pi x}{10}$

Period of a Trigonometric Function **In Exercises 53–56, find the period of the function.**

53. $y = 5\tan 2x$

54. $y = 7\tan 2\pi x$

55. $y = \sec 5x$

56. $y = \csc 4x$

Writing **In Exercises 57 and 58, use a graphing utility to graph each function in the same viewing window for $c = -2$, $c = -1$, $c = 1$, and $c = 2$. Give a written description of how the graph changes when c changes.**

57. (a) $f(x) = c\sin x$
(b) $f(x) = \cos cx$
(c) $f(x) = \cos(\pi x - c)$

58. (a) $f(x) = \sin x + c$
(b) $f(x) = -\sin(2\pi x - c)$
(c) $f(x) = c\cos x$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Sketching the Graph of a Trigonometric Function **In Exercises 59–72, sketch the graph of the function.**

59. $y = 2\cos 2x$

60. $y = \sin\frac{x}{2}$

61. $y = -\sin\frac{2\pi x}{3}$

62. $y = 2\tan x$

63. $y = \tan 2x$

64. $y = \csc\frac{x}{2}$

65. $y = \csc 2\pi x$

66. $y = 2\sec 2x$

67. $y = \sin(x + \pi)$

68. $y = \cos\left(x - \frac{\pi}{3}\right)$

69. $y = 1 + \cos\left(x - \frac{\pi}{2}\right)$

70. $y = 1 + \sin\left(x + \frac{\pi}{2}\right)$

71. $y = 3 + \sec\frac{\pi x}{2}$

72. $y = -1 - 4\csc\left(3x - \frac{3\pi}{2}\right)$

Graphical Reasoning **In Exercises 73 and 74, find *a*, *b*, and *c* such that the graph of the function matches the graph in the figure.**

73. $y = a\cos(bx - c)$



74. $y = a\sin(bx - c)$



Exploring Concepts

75. You know the value of $\tan\theta$. Is it possible to find the value of $\sec\theta$ without finding the measure of θ? Explain.

76. Explain how to restrict the domain of the sine function so that it becomes a one-to-one function.

77. How do the ranges of the cosine function and the secant function compare?

78. HOW DO YOU SEE IT? Consider an angle in standard position with $r = 12$ centimeters, as shown in the figure. Describe the changes in the values of x, y, $\sin\theta$, $\cos\theta$, and $\tan\theta$ as θ increases continually from 0 to $\pi/2$.



79. Ferris Wheel

A model for the height h (in feet) of a Ferris wheel car is

$h = 50 + 50\sin 8\pi t$

where t is measured in minutes. (The Ferris wheel has a radius of 50 feet.) This model yields a height of 50 feet when $t = 0$. Alter the model so that the height of the car is 1 foot when $t = 0$.

80. Sales The monthly sales S (in thousands of units) of a seasonal product are modeled by

$$S = 58.3 + 32.5\cos\frac{\pi t}{6}$$

where t is the month, with $t = 1$ corresponding to January. Use a graphing utility to graph the model for S and determine the months when sales exceed 75,000 units.

81. Think About It Sketch the graphs of

$$f(x) = \sin x, \quad g(x) = |\sin x|, \quad \text{and} \quad h(x) = \sin(|x|).$$

In general, how are the graphs of $|f(x)|$ and $f(|x|)$ related to the graph of f?

82. Pattern Recognition Use a graphing utility to compare the graph of

$$f(x) = \frac{4}{\pi}\left(\sin\pi x + \frac{1}{3}\sin 3\pi x\right)$$

with the graph below. Improve the approximation by adding a term to $f(x)$. Use a graphing utility to verify that your new approximation is better than the original. Can you find other terms to add to make the approximation even better? What is the pattern? (*Hint:* Use sine terms.)



True or False? **In Exercises 83–86, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

83. A measurement of 4 radians corresponds to two complete revolutions from the initial side to the terminal side of an angle.

84. Amplitude is always positive.

85. The function $y = \frac{1}{2}\sin 2x$ has an amplitude that is twice that of the function $y = \sin x$.

86. The function $y = 3\cos(x/3)$ has a period that is three times that of the function $y = \cos x$.

George Paul Antohi/EyeEm/Getty Images

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Review Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Exploring Concepts

In this chapter, you reviewed several mathematical concepts required for a successful study of calculus.

- Graphs of equations
- Functions
- Domain and range
- Six basic functions and their graphs
- Transformations
- Trigonometric functions

You will use functions and apply your knowledge of calculus to model and study real-life applications in science, business, and engineering.

1. Match the equation or equations with the given characteristic, if possible.

(i) $y = 3x^3 - 3x$ (ii) $y = (x + 3)^2$ (iii) $y = 3x - 3$

(iv) $y = \sqrt[3]{x}$ (v) $y = 3x^2 + 3$ (vi) $y = \sqrt{x + 3}$

(a) Symmetric with respect to the y-axis

(b) Three x-intercepts

(c) Symmetric with respect to the x-axis

(d) The point $(-2, 1)$ is on the graph

(e) Symmetric with respect to the origin

(f) Graph passes through the origin

2. Graph the equation $y = cx + 1$ for $c = 1, 2, 3, 4$, and 5. Then make a conjecture about the x-coefficient and the graph of the equation.

3. Give an example to justify each statement.

(a) $\sin(u + v) \neq \sin u + \sin v$

(b) $\cos(u + v) \neq \cos u + \cos v$

(c) $\tan(u + v) \neq \tan u + \tan v$

4. Use a graphing utility to graph $y = d + a\sin(bx - c)$ for several different values of a, b, c, and d. Write a paragraph describing the changes in the graph corresponding to changes in each constant.

5. Consider the functions $f(x) = 3\cos 2x$ and $g(x) = x|x|$.

(a) Determine the domain and range of each function.

(b) Discuss the symmetry of each function.

(c) Determine the intercepts of each function.

(d) Sketch the graph of each function.

(e) Find $f + g$, $f - g$, fg, and f/g.

(f) Find $f(g(x))$ and $g(f(x))$.

6. Consider the functions

$f(x) = x^2$ and $g(x) = \sqrt{x}$.

(a) Find $f(g(x))$ and $g(f(x))$.

(b) What are the domains of $f \circ g$ and $g \circ f$?

(c) What are the ranges of $f \circ g$ and $g \circ f$?

(d) Does $f(g(x)) = g(f(x))$? Explain your reasoning.

Finding Intercepts

In Exercises 7–10, find any intercepts.

7. $y = 5x - 8$

8. $y = x^2 - 8x + 12$

9. $y = \dfrac{x - 3}{x - 4}$

10. $y = (x - 3)\sqrt{x + 4}$

Testing for Symmetry

In Exercises 11–14, test for symmetry with respect to each axis and to the origin.

11. $y = x^2 + 4x$

12. $y = x^4 - x^2 + 3$

13. $y^2 = x^2 - 5$

14. $xy = -2$

Using Intercepts and Symmetry to Sketch a Graph

In Exercises 15–20, find any intercepts and test for symmetry. Then sketch the graph of the equation.

15. $y = -\frac{1}{2}x + 3$

16. $y = -x^2 + 4$

17. $y = 9x - x^3$

18. $y^2 = 9 - x$

19. $y = 2\sqrt{4 - x}$

20. $y = |x - 4| - 4$

Finding Points of Intersection

In Exercises 21–24, find the points of intersection of the graphs of the equations.

21. $5x + 3y = -1$
$x - y = -5$

22. $2x + 4y = 9$
$6x - 4y = 7$

23. $x - y = -5$
$x^2 - y = 1$

24. $x^2 + y^2 = 1$
$-x + y = 1$

Finding the Slope of a Line

In Exercises 25 and 26, plot the pair of points and find the slope of the line passing through them.

25. $\left(\frac{3}{2}, 1\right), \left(5, \frac{5}{2}\right)$

26. $(-7, 8), (-1, 8)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding an Equation of a Line **In Exercises 27–30, find an equation of the line that passes through the point and has the indicated slope. Then sketch the line.**

27. $(3, -5)$, $m = \frac{7}{4}$

28. $(-3, 0)$, $m = -\frac{2}{3}$

29. $(-8, 1)$, m is undefined

30. $(5, 4)$, $m = 0$

Finding the Slope and *y*-Intercept **In Exercises 31 and 32, find the slope and the *y*-intercept of the line.**

31. $y - 3x = 5$

32. $9 - y = x$

Sketching a Line in the Plane **In Exercises 33–36, sketch the graph of the equation.**

33. $y = 6$

34. $x = -3$

35. $y = 4x - 2$

36. $3x + 2y = 12$

Finding an Equation of a Line **In Exercises 37 and 38, find an equation of the line that passes through the points. Then sketch the line.**

37. $(0, 0)$, $(8, 2)$

38. $(-5, 5)$, $(10, -1)$

39. Finding Equations of Lines Find equations of the lines passing through $(-3, 5)$ and having each characteristic.

(a) Slope of $\frac{7}{16}$

(b) Parallel to the line $5x - 3y = 3$

(c) Perpendicular to the line $3x + 4y = 8$

(d) Parallel to the y-axis

40. Finding Equations of Lines Find equations of the lines passing through $(2, 4)$ and having each characteristic.

(a) Slope of $-\frac{2}{3}$

(b) Perpendicular to the line $x + y = 0$

(c) Parallel to the line $3x - y = 0$

(d) Parallel to the x-axis

41. Rate of Change The purchase price of a new machine is \$12,500, and its value will decrease by \$850 per year. Use this information to write a linear equation that gives the value V of the machine t years after it is purchased. Find its value at the end of 3 years.

42. Break-Even Analysis A contractor purchases a piece of equipment for \$36,500 that costs an average of \$9.25 per hour for fuel and maintenance. The equipment operator is paid \$13.50 per hour, and customers are charged \$30 per hour.

(a) Write a linear equation for the cost C of operating this equipment for t hours.

(b) Write a linear equation for the revenue R derived from t hours of use.

(c) Find the break-even point for this equipment by finding the time at which $R = C$.

Evaluating a Function **In Exercises 43–48, evaluate the function at each value of the independent variable. Simplify the results.**

43. $f(x) = 5x + 4$

(a) $f(0)$ (b) $f(5)$ (c) $f(-3)$ (d) $f(t + 1)$

44. $f(x) = x^3 - 2x$

(a) $f(-3)$ (b) $f(2)$ (c) $f(-1)$ (d) $f(c - 1)$

45. $f(x) = \begin{cases} x + 2, & x \le 1 \\ 2x - 3, & x > 1 \end{cases}$

(a) $f(-2)$ (b) $f(0)$ (c) $f(1)$ (d) $f(2)$

46. $f(x) = \begin{cases} |3x - 1|, & x < 0 \\ x^2 - 1, & x \ge 0 \end{cases}$

(a) $f(-1)$ (b) $f(0)$ (c) $f(1)$ (d) $f(a^2 + 3)$

47. $f(x) = 4x^2$

$$\frac{f(x + \Delta x) - f(x)}{\Delta x}$$

48. $f(x) = 2x - 6$

$$\frac{f(x) - f(1)}{x - 1}$$

Finding the Domain and Range of a Function **In Exercises 49–52, find the domain and range of the function.**

49. $f(x) = x^2 + 3$

50. $g(x) = \sqrt{6 - x}$

51. $f(x) = -|x + 1|$

52. $h(x) = \dfrac{2}{x + 1}$

Sketching a Graph of a Function **In Exercises 53–56, sketch a graph of the function and find its domain and range. Use a graphing utility to verify your graph.**

53. $f(x) = x^3 + x^2 - x - 1$

54. $g(x) = \sqrt{x + 1}$

55. $h(x) = |x + 3|$

56. $f(x) = \dfrac{4}{2x - 1}$

Using the Vertical Line Test **In Exercises 57 and 58, use the Vertical Line Test to determine whether *y* is a function of *x*. To print an enlarged copy of the graph, go to *MathGraphs.com*.**

57. $x + y^2 = 2$



58. $x^2 - y = 0$



Determining Whether an Equation Is a Function **In Exercises 59 and 60, determine whether *y* is a function of *x*.**

59. $xy + x^3 - 2y = 0$

60. $x = 9 - y^2$

61. Transformations of Functions Use a graphing utility to graph $f(x) = x^3 - 3x^2$. Use the graph to write a formula for the function g shown in the figure.

(a)



(b)



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

62. Think About It What is the minimum degree of the polynomial function whose graph approximates the graph shown? What sign must the leading coefficient have?

(a)



(b)



(c)



(d)



Finding Composite Functions **In Exercises 63 and 64, find the composite functions $f \circ g$ and $g \circ f$. Find the domain of each composite function. Are the two composite functions equal?**

63. $f(x) = 3x + 1$, $g(x) = -x$

64. $f(x) = \sqrt{x - 2}$, $g(x) = x^2$

Even and Odd Functions and Zeros of Functions **In Exercises 65 and 66, determine whether the function is even, odd, or neither. Then find the zeros of the function. Use a graphing utility to verify your result.**

65. $f(x) = x^4 - x^2$

66. $f(x) = \sqrt{x^3 + 1}$

Degrees to Radians **In Exercises 67–70, convert the degree measure to radian measure as a multiple of π and as a decimal accurate to three decimal places.**

67. $340°$

68. $300°$

69. $-480°$

70. $-900°$

Radians to Degrees **In Exercises 71–74, convert the radian measure to degree measure.**

71. $\frac{\pi}{6}$

72. $\frac{11\pi}{4}$

73. $-\frac{2\pi}{3}$

74. $-\frac{13\pi}{6}$

Evaluating Trigonometric Functions **In Exercises 75–80, find the exact value of the sine, cosine, and tangent of the angle. Do not use a calculator.**

75. $-45°$

76. $240°$

77. $\frac{13\pi}{6}$

78. $-\frac{4\pi}{3}$

79. $405°$

80. $180°$

Evaluating Trigonometric Functions **In Exercises 81–86, use a calculator to evaluate the trigonometric function. Round your answers to four decimal places.**

81. $\tan 33°$

82. $\cot 401°$

83. $\sec \frac{12\pi}{5}$

84. $\csc \frac{2\pi}{9}$

85. $\sin\left(-\frac{\pi}{9}\right)$

86. $\cos\left(-\frac{3\pi}{7}\right)$

Solving a Trigonometric Equation **In Exercises 87–92, solve the equation for θ, where $0 \le \theta \le 2\pi$.**

87. $2 \cos \theta + 1 = 0$

88. $2 \cos^2 \theta = 1$

89. $2 \sin^2 \theta + 3 \sin \theta = -1$

90. $\cos^3 \theta = \cos \theta$

91. $\sec^2 \theta - \sec \theta - 2 = 0$

92. $2 \sec^2 \theta + \tan^2 \theta = 5$

Sketching the Graph of a Trigonometric Function **In Exercises 93–100, sketch the graph of the function.**

93. $y = 9 \cos x$

94. $y = \sin \pi x$

95. $y = 3 \sin \frac{2x}{5}$

96. $y = 8 \cos \frac{x}{4}$

97. $y = \frac{1}{3} \tan x$

98. $y = \cot \frac{x}{2}$

99. $y = -\sec 2\pi x$

100. $y = -4 \csc 3x$

Building on Concepts

101. One of the fundamental themes of calculus is to find the slope of the tangent line to a curve at a point. To see how this can be done, consider the point $(4, 2)$ on the graph of $f(x) = \sqrt{x}$ (see figure).

(a) Find the slope m_1 of the line joining $(4, 2)$ and $(9, 3)$. Is the slope of the tangent line at $(4, 2)$ greater than or less than m_1?

(b) Find the slope m_2 of the line joining $(4, 2)$ and $(1, 1)$. Is the slope of the tangent line at $(4, 2)$ greater than or less than m_2?

(c) Find the slope m_3 of the line joining $(4, 2)$ and $(4.41, 2.1)$. Is the slope of the tangent line at $(4, 2)$ greater than or less than m_3?

(d) Find the slope of the line joining $(4, 2)$ and $(4 + h, f(4 + h))$ in terms of the nonzero number h.

(e) What is the slope of the tangent line at $(4, 2)$? Explain how you arrived at your answer.



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.S. Problem Solving

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

1. Finding Tangent Lines Consider the circle

$x^2 + y^2 - 6x - 8y = 0$

as shown in the figure.

(a) Find the center and radius of the circle.

(b) Find an equation of the tangent line to the circle at the point $(0, 0)$.

(c) Find an equation of the tangent line to the circle at the point $(6, 0)$.

(d) Where do the two tangent lines intersect?



Figure for 1



Figure for 2

2. Finding Tangent Lines There are two tangent lines from the point $(0, 1)$ to the circle $x^2 + (y + 1)^2 = 1$ (see figure). Find equations of these two lines by using the fact that each tangent line intersects the circle at *exactly* one point.

3. Writing a Function A person is in a boat 2 miles from the nearest point on the coast. The person travels to a point Q located 3 miles down the coast and 1 mile inland (see figure). The person can row at 2 miles per hour and walk at 4 miles per hour. Write the total time T of the trip as a function of x.



4. Sketching Transformations Consider the graph of the function f shown below. Use this graph to sketch the graph of each function. To print an enlarged copy of the graph, go to *MathGraphs.com.*

(a) $f(x + 1)$

(b) $f(x) + 1$

(c) $2f(x)$

(d) $f(-x)$

(e) $-f(x)$

(f) $|f(x)|$

(g) $f(|x|)$



5. Maximum Area A rancher plans to fence a rectangular pasture adjacent to a river. The rancher has 100 meters of fencing, and no fencing is needed along the river (see figure).

(a) Write the area A of the pasture as a function of x, the length of the side parallel to the river. What is the domain of A?

(b) Graph the area function and estimate the dimensions that yield the maximum amount of area for the pasture.

(c) Find the dimensions that yield the maximum amount of area for the pasture by completing the square.



Figure for 5



Figure for 6

6. Maximum Area A rancher has 300 feet of fencing to enclose two adjacent pastures (see figure).

(a) Write the total area A of the two pastures as a function of x. What is the domain of A?

(b) Graph the area function and estimate the dimensions that yield the maximum amount of area for the pastures.

(c) Find the dimensions that yield the maximum amount of area for the pastures by completing the square.

7. Average Speed You drive to the beach at a rate of 120 kilometers per hour. On the return trip, you drive at a rate of 60 kilometers per hour. What is your average speed for the entire trip? Explain your reasoning.

8. Composite Functions Let $f(x) = \dfrac{1}{1 - x}$.

(a) What are the domain and range of f?

(b) Find the composition $f(f(x))$. What is the domain of this function?

(c) Find $f(f(f(x)))$. What is the domain of this function?

(d) Graph $f(f(f(x)))$. Is the graph a line? Why or why not?

9. Lemniscate Let d_1 and d_2 be the distances from the point (x, y) to the points $(-1, 0)$ and $(1, 0)$, respectively, as shown in the figure. Show that the equation of the graph of all points (x, y) satisfying $d_1 d_2 = 1$ is

$(x^2 + y^2)^2 = 2(x^2 - y^2)$.

This curve is called a **lemniscate.** Graph the lemniscate and identify three points on the graph.



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

1 Limits and Their Properties

GO DIGITAL

1.1 A Preview of Calculus
1.2 Finding Limits Graphically and Numerically
1.3 Evaluating Limits Analytically
1.4 Continuity and One-Sided Limits
1.5 Infinite Limits

CalcView®



CalcChat®


Chapter 1
Section 3
Exercise 41
GO
$f(x) = \frac{x^2 + 3x}{x} = \frac{x(x+3)}{x}$ and $g(x) = x + 3$
agree except at $x = 0$.
$\lim_{x\to 0} f(x) = \lim_{x\to 0} g(x) = \lim_{x\to 0} (x + 3) = 0 + 3 = 3$
PREV. 31 33 35 37 39 41 43 45 47 49 51 NEXT

1.4 Charles's Law and Absolute Zero *(Example 5, p. 78)*

1.3 Free-Falling Object *(Exercises 101 and 102, p. 72)*

left, FABRICE COFFRINI/AFP/Getty Images; right, Kevin Fleming/Getty Images

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

1.1 A Preview of Calculus

GO DIGITAL

- **Describe what calculus is and how it compares with precalculus.**
- **Describe that the tangent line problem is basic to calculus.**
- **Describe that the area problem is also basic to calculus.**

What Is Calculus?

Calculus is the mathematics of change. For instance, calculus is the mathematics of velocities, accelerations, tangent lines, slopes, areas, volumes, arc lengths, centroids, curvatures, and a variety of other concepts that have enabled scientists, engineers, and economists to model real-life situations.

Although precalculus mathematics also deals with velocities, accelerations, tangent lines, slopes, and so on, there is a fundamental difference between precalculus mathematics and calculus. Precalculus mathematics is more static, whereas calculus is more dynamic. Here are some examples.

- An object traveling at a constant velocity can be analyzed with precalculus mathematics. To analyze the velocity of an accelerating object, you need calculus.
- The slope of a line can be analyzed with precalculus mathematics. To analyze the slope of a curve, you need calculus.
- The curvature of a circle is constant and can be analyzed with precalculus mathematics. To analyze the variable curvature of a general curve, you need calculus.
- The area of a rectangle can be analyzed with precalculus mathematics. To analyze the area under a general curve, you need calculus.

Each of these situations involves the same general strategy—the reformulation of precalculus mathematics through the use of a limit process. So, one way to answer the question "What is calculus?" is to say that calculus is a "limit machine" that involves three stages. The first stage is precalculus mathematics, such as the slope of a line or the area of a rectangle. The second stage is the limit process, and the third stage is a new calculus formulation, such as a derivative or integral.

Precalculus mathematics ⇨ Limit process ⇨ Calculus

Some students try to learn calculus as if it were simply a collection of new formulas. This is unfortunate. If you reduce calculus to the memorization of differentiation and integration formulas, you will miss a great deal of understanding, self-confidence, and satisfaction.

On the next two pages are listed some familiar precalculus concepts coupled with their calculus counterparts. Throughout the text, your goal should be to learn how precalculus formulas and techniques are used as building blocks to produce the more general calculus formulas and techniques. Do not worry if you are unfamiliar with some of the "old formulas" listed on the next two pages—you will be reviewing all of them.

As you proceed through this text, come back to this discussion repeatedly. Try to keep track of where you are relative to the three stages involved in the study of calculus. For instance, note how these chapters relate to the three stages.

Chapter P: Preparation for Calculus	Precalculus mathematics
Chapter 1: Limits and Their Properties	Limit process
Chapter 2: Differentiation	Calculus

This cycle is repeated many times on a smaller scale throughout the text.

REMARK As you progress through this course, remember that learning calculus is just one of your goals. Your most important goal is to learn how to use calculus to model and solve real-life problems. Here are a few problem-solving strategies that may help you.

- Be sure you understand the question. What is given? What are you asked to find?
- Outline a plan. There are many approaches you could use: look for a pattern, solve a simpler problem, work backwards, draw a diagram, use technology, or apply any of many other approaches.
- Complete your plan. Be sure to answer the question. Verbalize your answer. For example, rather than writing the answer as $x = 4.6$, it would be better to write the answer as, "The area of the region is 4.6 square meters."
- Look back at your work. Does your answer make sense? Is there a way to check the reasonableness of your answer?

Scan the to access digital content available for this page.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Without Calculus	With Differential Calculus
Value of f at $x = c$ 	Limit of $f(x)$ as x approaches c 
Slope of a line 	Slope of a curve 
Secant line to a curve 	Tangent line to a curve 
Average rate of change between $t = a$ and $t = b$ 	Instantaneous rate of change at $t = c$
Curvature of a circle 	Curvature of a curve 
Height of a curve when $x = c$ 	Maximum height of a curve on an interval 
Tangent plane to a sphere 	Tangent plane to a surface 
Direction of motion along a line 	Direction of motion along a curve

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Without Calculus		With Integral Calculus	
Area of a rectangle		Area under a curve	
Work done by a constant force		Work done by a variable force	
Center of a rectangle		Centroid of a region	
Length of a line segment		Length of an arc	
Surface area of a cylinder		Surface area of a solid of revolution	
Mass of a solid of constant density		Mass of a solid of variable density	
Volume of a rectangular solid		Volume of a region under a surface	
Sum of a finite number of terms	$a_1 + a_2 + \cdots + a_n = S$	Sum of an infinite number of terms	$a_1 + a_2 + a_3 + \cdots = S$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



The tangent line to the graph of f at P

Figure 1.1

The Tangent Line Problem

The notion of a limit is fundamental to the study of calculus. The following brief descriptions of two classic problems in calculus—*the tangent line problem* and *the area problem*—should give you some idea of the way limits are used in calculus.

In the tangent line problem, you are given a function f and a point P on its graph and are asked to find an equation of the tangent line to the graph at point P, as shown in Figure 1.1.

Except for cases involving a vertical tangent line, the problem of finding the **tangent line** at a point P is equivalent to finding the *slope* of the tangent line at P. To approximate this slope, sketch a line through the point of tangency and a second point on the curve, as shown in Figure 1.2(a). This line is called a **secant line.** If $P(c, f(c))$ is the point of tangency and

$$Q(c + \Delta x, f(c + \Delta x))$$

is a second point on the graph of f, then the slope of the secant line through these two points can be found using precalculus and is

$$m_{sec} = \frac{f(c + \Delta x) - f(c)}{c + \Delta x - c} = \frac{f(c + \Delta x) - f(c)}{\Delta x}.$$



(a) The secant line through $(c, f(c))$ and $(c + \Delta x, f(c + \Delta x))$



(b) As Q approaches P, the secant lines approach the tangent line.

Figure 1.2

As point Q approaches point P, the slopes of the secant lines approach the slope of the tangent line, as shown in Figure 1.2(b). When such a "limiting position" exists, the slope of the tangent line is said to be the **limit** of the slopes of the secant lines. (Much more will be said about this important calculus concept in Chapter 2.)

GRACE CHISHOLM YOUNG (1868–1944)

Grace Chisholm Young received her degree in mathematics from Girton College in Cambridge, England. Her early work was published under the name of William Young, her husband. Between 1914 and 1916, Grace Young published work on the foundations of calculus that won her the Gamble Prize from Girton College.

The Mistress and Fellows, Girton College, Cambridge

Exploration

The five points listed below lie on the graph of $f(x) = x^2$.

$$Q_1(1.5, f(1.5)), \quad Q_2(1.1, f(1.1)), \quad Q_3(1.01, f(1.01)),$$
$$Q_4(1.001, f(1.001)), \quad Q_5(1.0001, f(1.0001))$$

Each successive point gets closer to the point $P(1, 1)$. Find the slopes of the secant lines through Q_1 and P, Q_2 and P, and so on. Graph these secant lines on a graphing utility. Then use your results to estimate the slope of the tangent line to the graph of f at the point P.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The Area Problem

In the tangent line problem, the limit process was applied to the slope of a line to find the slope of a general curve. A second classic problem in calculus is finding the area of a plane region that is bounded by the graphs of functions. This problem can also be solved with a limit process. In this case, the limit process is applied to the area of a rectangle to find the area of a general region.

As a simple example, consider the region bounded by the graph of the function $y = f(x)$, the x-axis, and the vertical lines $x = a$ and $x = b$, as shown in Figure 1.3. You can approximate the area of the region with several rectangular regions, as shown in Figure 1.4. As you increase the number of rectangles, the approximation tends to become better and better because the amount of area missed by the rectangles decreases. Your goal is to determine the limit of the sum of the areas of the rectangles as the number of rectangles increases without bound.



Area under a curve
Figure 1.3



Approximation using four rectangles



Approximation using eight rectangles
Figure 1.4

The discovery of the relationship between the tangent line problem and the area problem led to the birth of calculus. You will learn more about this relationship when you study the Fundamental Theorem of Calculus in Chapter 4.

Exploration

Consider the region bounded by the graphs of $f(x) = x^2$, $y = 0$, and $x = 1$, as shown in part (a) of the figure. The area of the region can be approximated by two sets of rectangles—one set inscribed within the region and the other set circumscribed over the region, as shown in parts (b) and (c). Find the sum of the areas of each set of rectangles. Then use your results to approximate the area of the region.



(a) Bounded region



(b) Inscribed rectangles



(c) Circumscribed rectangles

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

1.1 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe the relationship between precalculus and calculus. List three precalculus concepts and their corresponding calculus counterparts.
2. Discuss the relationship between secant lines through a fixed point and a corresponding tangent line at that fixed point.

Precalculus or Calculus **In Exercises 3–6, decide whether the problem can be solved using precalculus or whether calculus is required. When the problem can be solved using precalculus, solve it. When the problem seems to require calculus, explain your reasoning and use a graphical or numerical approach to estimate the solution.**

3. Find the distance traveled in 15 seconds by an object traveling at a constant velocity of 20 feet per second.
4. Find the distance traveled in 15 seconds by an object moving with a velocity of $v(t) = 20 + 7\cos t$ feet per second.

5. Rate of Change

A bicyclist is riding on a path modeled by the function $f(x) = 0.04(8x - x^2)$, where x and $f(x)$ are measured in miles (see figure). Find the rate of change of elevation at $x = 2$.



6. A bicyclist is riding on a path modeled by the function $f(x) = 0.08x$, where x and $f(x)$ are measured in miles (see figure). Find the rate of change of elevation at $x = 2$.



7. **Secant Lines** Consider the function $f(x) = \sqrt{x}$ and the point $P(4, 2)$ on the graph of f.
   (a) Graph f and the secant lines passing through $P(4, 2)$ and $Q(x, f(x))$ for x-values of 1, 3, and 5.
   (b) Find the slope of each secant line.
   (c) Use the results of part (b) to estimate the slope of the tangent line to the graph of f at $P(4, 2)$. Describe how to improve your approximation of the slope.

8. **Secant Lines** Consider the function $f(x) = 6x - x^2$ and the point $P(2, 8)$ on the graph of f.
   (a) Graph f and the secant lines passing through $P(2, 8)$ and $Q(x, f(x))$ for x-values of 3, 2.5, and 1.5.
   (b) Find the slope of each secant line.
   (c) Use the results of part (b) to estimate the slope of the tangent line to the graph of f at $P(2, 8)$. Describe how to improve your approximation of the slope.

9. **Approximating Area** Use the rectangles in each graph to approximate the area of the region bounded by $y = 5/x$, $y = 0$, $x = 1$, and $x = 5$. Describe how you could continue this process to obtain a more accurate approximation of the area.





10. **HOW DO YOU SEE IT?** How would you describe the instantaneous rate of change of an automobile's position on a highway?

Exploring Concepts

11. Consider the length of the graph of $f(x) = 5/x$ from $(1, 5)$ to $(5, 1)$.





   (a) Approximate the length of the curve by finding the distance between its two endpoints, as shown in the first figure.
   (b) Approximate the length of the curve by finding the sum of the lengths of four line segments, as shown in the second figure.
   (c) Describe how you could continue this process to obtain a more accurate approximation of the length of the curve.

A blue exercise number indicates that a video solution can be seen at *CalcView.com*.

Westend61/Getty Images

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

1.2 Finding Limits Graphically and Numerically

GO DIGITAL

- **Estimate a limit using a numerical or graphical approach.**
- **Identify the ways that a limit fails to exist.**
- **Prove the existence of a limit using the formal definition of a limit.**

An Introduction to Limits

To sketch the graph of the function

$$f(x) = \frac{x^3 - 1}{x - 1} \qquad f \text{ is undefined at } x = 1.$$

for values other than $x = 1$, you can use standard curve-sketching techniques. At $x = 1$, however, it is not clear what to expect. To get an idea of the behavior of the graph of f near $x = 1$, you can use two sets of x-values—one set that approaches 1 from the left and one set that approaches 1 from the right, as shown in the table.

x approaches 1 from the left. | x approaches 1 from the right.

x	0.75	0.9	0.99	0.999	1	1.001	1.01	1.1	1.25
$f(x)$	2.313	2.710	2.970	2.997	?	3.003	3.030	3.310	3.813

$f(x)$ approaches 3. | $f(x)$ approaches 3.



The limit of $f(x)$ as x approaches 1 is 3.
Figure 1.5

The graph of f has the shape of a parabola with a hole at the point $(1, 3)$, as shown in Figure 1.5. Although x cannot equal 1, you can move arbitrarily close to 1, and as a result $f(x)$ moves arbitrarily close to 3. Using limit notation, you can write

$$\lim_{x \to 1} f(x) = 3. \qquad \text{This is read as "the limit of } f(x) \text{ as } x \text{ approaches 1 is 3."}$$

This discussion leads to an informal definition of limit. If $f(x)$ becomes arbitrarily close to a single real number L as x approaches c from either side (but $x \neq c$), then the **limit** of $f(x)$ as x approaches c is L. This limit is written as

$$\lim_{x \to c} f(x) = L.$$

REMARK Note that if $f(x)$ does *not* become arbitrarily close to a single real number L as x approaches c from either side, then the limit of $f(x)$ *fails to exist*.

Exploration

Estimate the limit

$$\lim_{x \to 2} \frac{x^2 - 3x + 2}{x - 2}$$

numerically by completing the table below. Then use a graphing utility to estimate the limit graphically.

x	1.75	1.9	1.99	1.999	2	2.001	2.01	2.1	2.25
$f(x)$	?	?	?	?	?	?	?	?	?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 1 Estimating a Limit Numerically

Evaluate the function $f(x) = x/\left(\sqrt{x+1} - 1\right)$ at several x-values near 0 and use the results to estimate the limit

$$\lim_{x \to 0} \frac{x}{\sqrt{x+1} - 1}.$$



The limit of $f(x)$ as x approaches 0 is 2.
Figure 1.6

Solution The table shows $f(x)$ for several x-values near 0.

x approaches 0 from the left. | x approaches 0 from the right.

x	-0.01	-0.001	-0.0001	0	0.0001	0.001	0.01
$f(x)$	1.99499	1.99950	1.99995	?	2.00005	2.00050	2.00499

$f(x)$ approaches 2. | $f(x)$ approaches 2.

From the results shown in the table, you can estimate the limit to be 2. This limit is reinforced by the graph of f shown in Figure 1.6. ■

In Example 1, note that the function is undefined at $x = 0$, and yet $f(x)$ appears to be approaching a limit as x approaches 0. This often happens, and it is important to realize that *the existence or nonexistence of $f(x)$ at $x = c$ has no bearing on the existence of the limit of $f(x)$ as x approaches c.*

EXAMPLE 2 Finding a Limit

Find the limit of $f(x)$ as x approaches 2, where

$$f(x) = \begin{cases} 1, & x \neq 2 \\ 0, & x = 2 \end{cases}.$$



The limit of $f(x)$ as x approaches 2 is 1.
Figure 1.7

Solution Because $f(x) = 1$ for all x other than $x = 2$, you can estimate that the limit is 1, as shown in Figure 1.7. So, you can write

$$\lim_{x \to 2} f(x) = 1.$$ The limit of $f(x)$ as x approaches 2 is 1.

The fact that $f(2) = 0$ has no bearing on the existence or value of the limit as x approaches 2. For instance, as x approaches 2, the function

$$g(x) = \begin{cases} 1, & x \neq 2 \\ 2, & x = 2 \end{cases}$$ $\lim_{x \to 2} g(x) = 1$

has the same limit as f. ■

So far in this section, you have been estimating limits numerically and graphically. These approaches produce an *estimate* of the limit. In Section 1.3, you will study analytic techniques for evaluating limits. Throughout the course, try to develop a habit of using this three-pronged approach to problem solving.

1. Numerical approach — Construct a table of values.
2. Graphical approach — Sketch a graph.
3. Analytic approach — Use algebra or calculus.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



$\lim_{x\to 0} f(x)$ does not exist.

Figure 1.8

Limits That Fail to Exist

In the next three examples, you will examine some limits that fail to exist.

EXAMPLE 3 Different Right and Left Behavior

Show that the limit $\lim_{x\to 0} \frac{|x|}{x}$ does not exist.

Solution Consider the graph of the function

$$f(x) = \frac{|x|}{x}.$$

In Figure 1.8 and from the definition of absolute value,

$$|x| = \begin{cases} x, & x \geq 0 \\ -x, & x < 0 \end{cases}$$ Definition of absolute value

you can see that

$$\frac{|x|}{x} = \begin{cases} 1, & x > 0 \\ -1, & x < 0 \end{cases}.$$

So, no matter how close x gets to 0, there will be both positive and negative x-values that yield $f(x) = 1$ or $f(x) = -1$. Specifically, if δ (the lowercase Greek letter delta) is a positive number, then for x-values satisfying the inequality $0 < |x| < \delta$, you can classify the values of $|x|/x$ as -1 or 1 on the intervals

$$(-\delta, 0) \quad \text{or} \quad (0, \delta).$$

Negative x-values yield $|x|/x = -1$.

Positive x-values yield $|x|/x = 1$.

Because $|x|/x$ approaches a different number from the right side of 0 than it approaches from the left side, the limit $\lim_{x\to 0} (|x|/x)$ does not exist.

EXAMPLE 4 Unbounded Behavior

Discuss the existence of the limit $\lim_{x\to 0} \frac{1}{x^2}$.

Solution Consider the graph of the function

$$f(x) = \frac{1}{x^2}.$$



$\lim_{x\to 0} f(x)$ does not exist.

Figure 1.9

In Figure 1.9, note that as x approaches 0 from either the right or the left, $f(x)$ increases without bound. This means that by choosing x close enough to 0, you can force $f(x)$ to be as large as you want. For instance, $f(x)$ will be greater than 100 when you choose x within $\frac{1}{10}$ of 0. That is,

$$0 < |x| < \frac{1}{10} \quad \Rightarrow \quad f(x) = \frac{1}{x^2} > 100.$$

Similarly, you can force $f(x)$ to be greater than 1,000,000, as shown.

$$0 < |x| < \frac{1}{1000} \quad \Rightarrow \quad f(x) = \frac{1}{x^2} > 1{,}000{,}000$$

Because $f(x)$ does not become arbitrarily close to a single number L as x approaches 0, you can conclude that the limit does not exist. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



$\lim_{x\to 0} f(x)$ does not exist.

Figure 1.10

EXAMPLE 5 Oscillating Behavior

See LarsonCalculus.com for an interactive version of this type of example.

Discuss the existence of the limit $\lim_{x\to 0} \sin\frac{1}{x}$.

Solution Let $f(x) = \sin(1/x)$. In Figure 1.10, you can see that as x approaches 0, $f(x)$ oscillates between -1 and 1. So, the limit does not exist because no matter how small you choose δ, it is possible to choose x_1 and x_2 within δ units of 0 such that $\sin(1/x_1) = 1$ and $\sin(1/x_2) = -1$, as shown in the table.

x	$\frac{2}{\pi}$	$\frac{2}{3\pi}$	$\frac{2}{5\pi}$	$\frac{2}{7\pi}$	$\frac{2}{9\pi}$	$\frac{2}{11\pi}$	$x\to 0$
$\sin\frac{1}{x}$	1	-1	1	-1	1	-1	Limit does not exist.

Common Types of Behavior Associated with Nonexistence of a Limit

1. $f(x)$ approaches a different number from the right side of c than it approaches from the left side.
2. $f(x)$ increases or decreases without bound as x approaches c.
3. $f(x)$ oscillates between two fixed values as x approaches c.

In addition to $f(x) = \sin(1/x)$, there are many other interesting functions that have unusual limit behavior. An often cited one is the *Dirichlet function*

$$f(x) = \begin{cases} 0, & \text{if } x \text{ is rational} \\ 1, & \text{if } x \text{ is irrational} \end{cases}.$$

Because this function has *no limit* at any real number c, it is *not continuous* at any real number c. You will study continuity more closely in Section 1.4.



PETER GUSTAV DIRICHLET (1805–1859)

In the early development of calculus, the definition of a function was much more restricted than it is today, and "functions" such as the Dirichlet function would not have been considered. The modern definition of function is attributed to the German mathematician Peter Gustav Dirichlet.

See LarsonCalculus.com to read more of this biography.

INTERFOTO/Alamy Stock Photo

TECHNOLOGY PITFALL When you use a graphing utility to investigate the behavior of a function near the x-value at which you are trying to evaluate a limit, remember that you cannot always trust the graphs that graphing utilities draw. When you use a graphing utility to graph the function in Example 5 over an interval containing 0, you will most likely obtain an incorrect graph such as that shown in Figure 1.11. The reason that a graphing utility cannot show the correct graph is that the graph has infinitely many oscillations over any interval that contains 0.



Incorrect graph of $f(x) = \sin(1/x)$

Figure 1.11

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

A Formal Definition of Limit

Consider again the informal definition of limit. If $f(x)$ becomes arbitrarily close to a single number L as x approaches c from either side, then the limit of $f(x)$ as x approaches c is L, written as

$$\lim_{x \to c} f(x) = L.$$

At first glance, this definition looks fairly technical. Even so, it is informal because exact meanings have not yet been given to the two phrases

"$f(x)$ becomes arbitrarily close to L"

and

"x approaches c."

The first person to assign mathematically rigorous meanings to these two phrases was Augustin-Louis Cauchy. His ***ε-δ* definition of limit** is the standard used today.

FOR FURTHER INFORMATION
For more on the introduction of rigor to calculus, see "Who Gave You the Epsilon? Cauchy and the Origins of Rigorous Calculus" by Judith V. Grabiner in *The American Mathematical Monthly*. To view this article, go to *MathArticles.com*.

In Figure 1.12, let ε (the lowercase Greek letter epsilon) represent a (small) positive number. Then the phrase "$f(x)$ becomes arbitrarily close to L" means that $f(x)$ lies in the interval $(L - \varepsilon, L + \varepsilon)$. Using absolute value, you can write this as

$$|f(x) - L| < \varepsilon.$$

Similarly, the phrase "x approaches c" means that there exists a positive number δ such that x lies in either the interval $(c - \delta, c)$ or the interval $(c, c + \delta)$. This fact can be concisely expressed by the double inequality

$$0 < |x - c| < \delta.$$



The ε-δ definition of the limit of $f(x)$ as x approaches c
Figure 1.12

The first inequality

$0 < |x - c|$ The distance between x and c is more than 0.

expresses the fact that $x \neq c$. The second inequality

$|x - c| < \delta$ x is within δ units of c.

says that x is within a distance δ of c.

Definition of Limit

Let f be a function defined on an open interval containing c (except possibly at c), and let L be a real number. The statement

$$\lim_{x \to c} f(x) = L$$

means that for each $\varepsilon > 0$ there exists a $\delta > 0$ such that if

$$0 < |x - c| < \delta$$

then

$$|f(x) - L| < \varepsilon.$$

REMARK Throughout this text, the expression

$$\lim_{x \to c} f(x) = L$$

implies two statements—the limit exists *and* the limit is L.

Some functions do not have limits as x approaches c, but those that do cannot have two different limits as x approaches c. That is, *if the limit of a function exists, then the limit is unique* (see Exercise 86).

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

The next three examples should help you develop a better understanding of the ε-δ definition of limit.

EXAMPLE 6 Finding a δ for a Given ε

Given the limit $\lim_{x \to 3} (2x - 5) = 1$, find δ such that

$$|(2x - 5) - 1| < 0.01$$

whenever

$$0 < |x - 3| < \delta.$$

Solution In this problem, you are working with a given value of ε—namely, $\varepsilon = 0.01$. To find an appropriate δ, try to establish a connection between the absolute values $|(2x - 5) - 1|$ and $|x - 3|$. Notice that

$$|(2x - 5) - 1| = |2x - 6| = 2|x - 3|.$$

Because the inequality $|(2x - 5) - 1| < 0.01$ is equivalent to $2|x - 3| < 0.01$, you can choose

$$\delta = \frac{1}{2}(0.01) = 0.005.$$ Choice for δ

This choice works because

$$0 < |x - 3| < 0.005$$

implies that

$$|(2x - 5) - 1| = 2|x - 3| < 2(0.005) = 0.01.$$

Figure 1.13 shows that for any x-value within 0.005 of 3 ($x \neq 3$), $f(x)$ is within 0.01 of 1.



The limit of $f(x)$ as x approaches 3 is 1.
Figure 1.13

In Example 6, note that 0.005 is the *largest* value of δ that will guarantee

$$|(2x - 5) - 1| < 0.01 \quad \text{whenever} \quad 0 < |x - 3| < \delta.$$

Any *smaller* positive value of δ would also work.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



The limit of $f(x)$ as x approaches 2 is 4.
Figure 1.14

In Example 6, you found a δ-value for a *given* ε. This does not prove the existence of the limit. To do that, you must prove that you can find a δ for *any* ε, as shown in the next example.

EXAMPLE 7 Using the ε-δ Definition of Limit

Use the ε-δ definition of limit to prove that

$$\lim_{x \to 2} (3x - 2) = 4.$$

Solution You must show that for each $\varepsilon > 0$, there exists a $\delta > 0$ such that

$$|(3x - 2) - 4| < \varepsilon$$

whenever

$$0 < |x - 2| < \delta.$$

Because your choice of δ depends on ε, you need to establish a connection between the absolute values $|(3x - 2) - 4|$ and $|x - 2|$.

$$|(3x - 2) - 4| = |3x - 6| = 3|x - 2|$$

So, for a given $\varepsilon > 0$, you can choose $\delta = \varepsilon/3$. This choice works because

$$0 < |x - 2| < \delta = \frac{\varepsilon}{3}$$

implies that

$$|(3x - 2) - 4| = 3|x - 2| < 3\left(\frac{\varepsilon}{3}\right) = \varepsilon.$$

Figure 1.14 shows that for any x-value within δ of 2 ($x \neq 2$), $f(x)$ is within ε of 4.

EXAMPLE 8 Using the ε-δ Definition of Limit

Use the ε-δ definition of limit to prove that $\lim_{x \to 2} x^2 = 4$.

Solution You must show that for each $\varepsilon > 0$, there exists a $\delta > 0$ such that

$$|x^2 - 4| < \varepsilon$$

whenever

$$0 < |x - 2| < \delta.$$

To find an appropriate δ, begin by writing $|x^2 - 4| = |x - 2||x + 2|$. You are interested in values of x close to 2, so choose x in the interval $(1, 3)$. To satisfy this restriction, let $\delta < 1$. Furthermore, for all x in the interval $(1, 3)$, $x + 2 < 5$ and thus $|x + 2| < 5$. So, letting δ be the minimum of $\varepsilon/5$ and 1, it follows that, whenever $0 < |x - 2| < \delta$, you have

$$|x^2 - 4| = |x - 2||x + 2| < \left(\frac{\varepsilon}{5}\right)(5) = \varepsilon.$$

Figure 1.15 shows that for any x-value within δ of 2 ($x \neq 2$), $f(x)$ is within ε of 4.



The limit of $f(x)$ as x approaches 2 is 4.
Figure 1.15

Throughout this chapter, you will use the ε-δ definition of limit primarily to prove theorems about limits and to establish the existence or nonexistence of particular types of limits. For *finding* limits, you will learn techniques that are easier to use than the ε-δ definition of limit.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

1.2 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Write a brief description of the meaning of the notation $\lim_{x\to 8} f(x) = 25$.
2. Identify three types of behavior associated with the nonexistence of a limit. Illustrate each type with a graph of a function.
3. Given the limit $\lim_{x\to 2} (2x + 1) = 5$, use a sketch to show the meaning of the phrase "$0 < |x - 2| < 0.25$ implies $|(2x + 1) - 5| < 0.5$."
4. Is the limit of $f(x)$ as x approaches c always equal to $f(c)$? Why or why not?

Estimating a Limit Numerically **In Exercises 5–10, complete the table and use the result to estimate the limit. Use a graphing utility to graph the function to confirm your result.**

5. $\lim_{x\to 4} \dfrac{x - 4}{x^2 - 5x + 4}$

x	3.9	3.99	3.999	4	4.001	4.01	4.1
$f(x)$				?			

6. $\lim_{x\to 3} \dfrac{x - 3}{x^2 - 9}$

x	2.9	2.99	2.999	3	3.001	3.01	3.1
$f(x)$				?			

7. $\lim_{x\to 0} \dfrac{\sqrt{x + 1} - 1}{x}$

x	-0.1	-0.01	-0.001	0	0.001	0.01	0.1
$f(x)$				?			

8. $\lim_{x\to 3} \dfrac{[1/(x + 1)] - (1/4)}{x - 3}$

x	2.9	2.99	2.999	3	3.001	3.01	3.1
$f(x)$				?			

9. $\lim_{x\to 0} \dfrac{\sin x}{x}$

x	-0.1	-0.01	-0.001	0	0.001	0.01	0.1
$f(x)$				?			

10. $\lim_{x\to 0} \dfrac{\cos x - 1}{x}$

x	-0.1	-0.01	-0.001	0	0.001	0.01	0.1
$f(x)$				?			

Finding a Limit Graphically **In Exercises 11–18, use the graph to find the limit (if it exists). If the limit does not exist, explain why.**

11. $\lim_{x\to 0} \sec x$



12. $\lim_{x\to 3} (4 - x)$



13. $\lim_{x\to 2} f(x)$

$$f(x) = \begin{cases} 4 - x, & x \neq 2 \\ 0, & x = 2 \end{cases}$$



14. $\lim_{x\to 1} f(x)$

$$f(x) = \begin{cases} x^2 + 3, & x \neq 1 \\ 2, & x = 1 \end{cases}$$



15. $\lim_{x\to 2} \dfrac{|x - 2|}{x - 2}$



16. $\lim_{x\to 5} \dfrac{2}{x - 5}$



17. $\lim_{x\to 0} \cos \dfrac{1}{x}$



18. $\lim_{x\to \pi/2} \tan x$



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Estimating a Limit Numerically **In Exercises 19–30, create a table of values for the function and use the result to estimate the limit. Use a graphing utility to graph the function to confirm your result.**

19. $\lim_{x\to 4}\dfrac{x^2-16}{x-4}$

20. $\lim_{x\to 7}\dfrac{7-x}{x^2-49}$

21. $\lim_{x\to 1}\dfrac{x-2}{x^2+x-6}$

22. $\lim_{x\to -4}\dfrac{x+4}{x^2+9x+20}$

23. $\lim_{x\to 1}\dfrac{x^4-1}{x^6-1}$

24. $\lim_{x\to -3}\dfrac{x^3+27}{x+3}$

25. $\lim_{x\to -6}\dfrac{\sqrt{10-x}-4}{x+6}$

26. $\lim_{x\to 1}\dfrac{\sqrt{3}-\sqrt{x+2}}{1-x}$

27. $\lim_{x\to 0}\dfrac{[2/(x+2)]-1}{x}$

28. $\lim_{x\to 2}\dfrac{[x/(x+1)]-(2/3)}{x-2}$

29. $\lim_{x\to 0}\dfrac{\sin 2x}{x}$

30. $\lim_{x\to 0}\dfrac{\tan x}{\tan 2x}$

A Limit That Fails to Exist **In Exercises 31 and 32, create a table of values for the function and use the result to explain why the limit does not exist.**

31. $\lim_{x\to 0}\dfrac{2}{x^3}$

32. $\lim_{x\to 0}\dfrac{3|x|}{x^2}$

Graphical Reasoning **In Exercises 33 and 34, use the graph of the function f to decide whether each quantity exists. If it does, find it. If not, explain why.**

33. (a) $f(1)$
(b) $\lim_{x\to 1} f(x)$
(c) $f(4)$
(d) $\lim_{x\to 4} f(x)$



34. (a) $f(-2)$
(b) $\lim_{x\to -2} f(x)$
(c) $f(0)$
(d) $\lim_{x\to 0} f(x)$
(e) $f(2)$
(f) $\lim_{x\to 2} f(x)$
(g) $f(4)$
(h) $\lim_{x\to 4} f(x)$



Limits of a Piecewise Function **In Exercises 35 and 36, sketch the graph of f. Then identify the values of c for which $\lim_{x\to c} f(x)$ exists.**

35. $f(x)=\begin{cases} x^2, & x\le 2 \\ 8-2x, & 2<x<4 \\ 4, & x\ge 4 \end{cases}$

36. $f(x)=\begin{cases} \sin x, & x<0 \\ 1-\cos x, & 0\le x\le \pi \\ \cos x, & x>\pi \end{cases}$

Sketching a Graph **In Exercises 37 and 38, sketch a graph of a function f that satisfies each value. (There are many correct answers.)**

37. $f(0)$ is undefined.
$\lim_{x\to 0} f(x)=4$
$f(2)=6$
$\lim_{x\to 2} f(x)=3$

38. $f(-2)=0$
$f(2)=0$
$\lim_{x\to -2} f(x)=0$
$\lim_{x\to 2} f(x)$ does not exist.

39. Finding δ The graph of $f(x)=x+1$ is shown in the figure. Find δ such that if $0<|x-2|<\delta$, then $|f(x)-3|<0.4$.



40. Finding δ The graph of

$$f(x)=\frac{1}{x-1}$$

is shown in the figure. Find δ such that if $0<|x-2|<\delta$, then $|f(x)-1|<0.01$.



41. Finding δ The graph of

$$f(x)=2-\frac{1}{x}$$

is shown in the figure. Find δ such that if $0<|x-1|<\delta$, then $|f(x)-1|<0.1$.



42. Finding δ Repeat Exercise 41 for each value of ε. What happens to the value of δ as the value of ε gets smaller?

(a) $\varepsilon=0.05$ (b) $\varepsilon=0.01$
(c) $\varepsilon=0.005$ (d) $\varepsilon=0.001$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding δ **In Exercises 43–48, find the limit L. Then find δ such that $|f(x) - L| < \varepsilon$ whenever $0 < |x - c| < \delta$ for (a) $\varepsilon = 0.01$ and (b) $\varepsilon = 0.005$.**

43. $\lim_{x\to 2}(3x + 2)$

44. $\lim_{x\to 6}\left(6 - \frac{1}{3}x\right)$

45. $\lim_{x\to 2}(x^2 - 3)$

46. $\lim_{x\to 4}(x^2 + 6)$

47. $\lim_{x\to 4}(x^2 - x)$

48. $\lim_{x\to 3} x^2$

Using the ε-δ Definition of Limit **In Exercises 49–60, find the limit L. Then use the ε-δ definition to prove that the limit is L.**

49. $\lim_{x\to 4}(x + 2)$

50. $\lim_{x\to -2}(4x + 5)$

51. $\lim_{x\to -4}\left(\frac{1}{2}x - 1\right)$

52. $\lim_{x\to 3}\left(\frac{3}{4}x + 1\right)$

53. $\lim_{x\to 6} 3$

54. $\lim_{x\to 2}(-1)$

55. $\lim_{x\to 0}\sqrt[3]{x}$

56. $\lim_{x\to 4}\sqrt{x}$

57. $\lim_{x\to -5}|x - 5|$

58. $\lim_{x\to 3}|x - 3|$

59. $\lim_{x\to 1}(x^2 + 1)$

60. $\lim_{x\to -4}(x^2 + 4x)$

61. Finding a Limit What is the limit of $f(x) = 4$ as x approaches π?

62. Finding a Limit What is the limit of $g(x) = x$ as x approaches π?

Writing **In Exercises 63–66, use a graphing utility to graph the function and estimate the limit (if it exists). What is the domain of the function? Can you detect a possible error in determining the domain of a function solely by analyzing the graph generated by a graphing utility? Write a short paragraph about the importance of examining a function analytically as well as graphically.**

63. $f(x) = \dfrac{x - 3}{x^2 - 4x + 3}$

$\lim_{x\to 3} f(x)$

64. $f(x) = \dfrac{\sqrt{x + 5} - 3}{x - 4}$

$\lim_{x\to 4} f(x)$

65. $f(x) = \dfrac{x - 9}{\sqrt{x} - 3}$

$\lim_{x\to 9} f(x)$

66. $f(x) = \dfrac{x - 5}{x^2 - 25}$

$\lim_{x\to 5} f(x)$

67. Shipping Charge An online retailer charges \$7.50 shipping for a package that weighs up to one pound and \$0.75 for each additional pound or fraction thereof. A formula for the shipping charge C (in dollars) is given by $C(x) = 7.5 - 0.75[\![1 - x]\!]$, $x > 0$, where x is the weight of the package (in pounds). (*Note:* $[\![x]\!]$ = greatest integer n such that $n \le x$. For example, $[\![3.2]\!] = 3$ and $[\![-1.6]\!] = -2$.)

(a) Evaluate $C(10.75)$. What does $C(10.75)$ represent?

(b) Use a graphing utility to graph the shipping charge function for $0 < x \le 6$. Does the limit of $C(x)$ as x approaches 3 exist? Explain.

68. Modeling Data An online retailer charges \$26.35 priority shipping for a package that weighs up to 0.5 pound and \$0.40 for each additional half pound or fraction thereof.

(a) Write a formula for the shipping charge C (in dollars) in terms of the weight of the package x (in pounds). (*Hint:* See Exercise 67.)

(b) Use a graphing utility to graph the shipping charge function for $0 < x \le 10$. Does the limit of $C(x)$ as x approaches 9 exist? Explain.

Concept Check

69. When using the definition of limit to prove that L is the limit of $f(x)$ as x approaches c, you find the largest satisfactory value of δ. Why would any smaller positive value of δ also work?

70. The definition of limit on page 56 requires that f is a function defined on an open interval containing c, except possibly at c. Why is this requirement necessary?

71. When $f(2) = 4$, can you conclude anything about the limit of $f(x)$ as x approaches 2? Explain your reasoning.

72. When the limit of $f(x)$ as x approaches 2 is 4, can you conclude anything about $f(2)$? Explain your reasoning.

73. Jewelry A jeweler resizes a ring so that its inner circumference is 6 centimeters.

(a) What is the radius of the ring?

(b) The inner circumference of the ring varies between 5.5 centimeters and 6.5 centimeters. How does the radius vary?

(c) Use the ε-δ definition of limit to describe this situation. Identify ε and δ.

74. Sports

A sporting goods manufacturer designs a golf ball having a volume of 2.48 cubic inches.

(a) What is the radius of the golf ball?

(b) The volume of the golf ball varies between 2.45 cubic inches and 2.51 cubic inches. How does the radius vary?

(c) Use the ε-δ definition of limit to describe this situation. Identify ε and δ.

75. Estimating a Limit Consider the function $f(x) = (1 + x)^{1/x}$. Estimate the limit of $f(x)$ as x approaches 0 by evaluating f at x-values near 0. Sketch the graph of f.

The symbol indicates an exercise in which you are instructed to use a graphing utility or a symbolic computer algebra system. The solutions of other exercises may also be facilitated by the use of appropriate technology.

photoinnovation/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

76. Estimating a Limit Consider the function

$$f(x) = \frac{|x + 1| - |x - 1|}{x}.$$

Estimate the limit of $f(x)$ as x approaches 0 by evaluating f at x-values near 0. Sketch the graph of f.

77. Graphical Reasoning The statement

$$\lim_{x\to 2} \frac{x^2 - 4}{x - 2} = 4$$

means that for each $\varepsilon > 0$ there corresponds a $\delta > 0$ such that if $0 < |x - 2| < \delta$, then

$$\left|\frac{x^2 - 4}{x - 2} - 4\right| < \varepsilon.$$

If $\varepsilon = 0.001$, then

$$\left|\frac{x^2 - 4}{x - 2} - 4\right| < 0.001.$$

Use a graphing utility to graph each side of this inequality. Use the *zoom* feature to find an interval $(2 - \delta, 2 + \delta)$ such that the inequality is true.

78. HOW DO YOU SEE IT? Use the graph of f to identify the values of c for which $\lim_{x\to c} f(x)$ exists.

(a)



(b)



True or False? **In Exercises 79–82, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

79. If f is undefined at $x = c$, then the limit of $f(x)$ as x approaches c does not exist.

80. If the limit of $f(x)$ as x approaches c is 0, then there must exist a number k such that $f(k) < 0.001$.

81. If $f(c) = L$, then $\lim_{x\to c} f(x) = L$.

82. If $\lim_{x\to c} f(x) = L$, then $f(c) = L$.

Think About It **In Exercises 83 and 84, consider the function $f(x) = \sqrt{x}$.**

83. Is $\lim_{x\to 0.25} \sqrt{x} = 0.5$ a true statement? Explain.

84. Is $\lim_{x\to 0} \sqrt{x} = 0$ a true statement? Explain.

85. Proof Consider the line $f(x) = mx + b$, where $m \neq 0$. Use the ε-δ definition of limit to prove that $\lim_{x\to c} f(x) = mc + b$.

86. Proof Prove that if the limit of $f(x)$ as x approaches c exists, then the limit must be unique. [*Hint:* Let

$$\lim_{x\to c} f(x) = L_1 \quad \text{and} \quad \lim_{x\to c} f(x) = L_2$$

and prove that $L_1 = L_2$.]

87. Proof Prove that

$$\lim_{x\to c} f(x) = L$$

is equivalent to $\lim_{x\to c} [f(x) - L] = 0$.

88. Proof

(a) Show that

$$\lim_{x\to 0} (3x + 1)(3x - 1)x^2 + 0.01 = 0.01.$$

Then prove that there exists an open interval (a, b) containing 0 such that $(3x + 1)(3x - 1)x^2 + 0.01 > 0$ for all $x \neq 0$ in (a, b).

(b) When

$$\lim_{x\to c} g(x) = L, \quad \text{where} \quad L > 0$$

prove that there exists an open interval (a, b) containing c such that $g(x) > 0$ for all $x \neq c$ in (a, b).

89. Evaluating Limits Use a graphing utility to evaluate

$$\lim_{x\to 0} \frac{\sin nx}{x}$$

for several values of n. What do you notice?

90. Evaluating Limits Use a graphing utility to evaluate

$$\lim_{x\to 0} \frac{\tan nx}{x}$$

for several values of n. What do you notice?

PUTNAM EXAM CHALLENGE

91. Inscribe a rectangle of base b and height h in a circle of radius one, and inscribe an isosceles triangle in a region of the circle cut off by one base of the rectangle (with that side as the base of the triangle). For what value of h do the rectangle and triangle have the same area?



92. A right circular cone has base of radius 1 and height 3. A cube is inscribed in the cone so that one face of the cube is contained in the base of the cone. What is the side length of the cube?

These problems were composed by the Committee on the Putnam Prize Competition. © The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

1.3 Evaluating Limits Analytically

GO DIGITAL

- Evaluate a limit using properties of limits.
- Develop and use a strategy for finding limits.
- Evaluate a limit using the dividing out technique.
- Evaluate a limit using the rationalizing technique.
- Evaluate a limit using the Squeeze Theorem.

Properties of Limits

In Section 1.2, you learned that the limit of $f(x)$ as x approaches c does not depend on the value of f at $x = c$. It may happen, however, that the limit is precisely $f(c)$. In such cases, you can evaluate the limit by **direct substitution.** That is,

$$\lim_{x \to c} f(x) = f(c). \qquad \text{Substitute } c \text{ for } x.$$

Such *well-behaved* functions are **continuous at *c*.** You will examine this concept more closely in Section 1.4.



Figure 1.16

THEOREM 1.1 Some Basic Limits

Let b and c be real numbers, and let n be a positive integer.

1. $\lim_{x \to c} b = b$
2. $\lim_{x \to c} x = c$
3. $\lim_{x \to c} x^n = c^n$

Proof The proofs of Properties 1 and 3 of Theorem 1.1 are left as exercises (see Exercises 107 and 108). To prove Property 2, you need to show that for each $\varepsilon > 0$ there exists a $\delta > 0$ such that $|x - c| < \varepsilon$ whenever $0 < |x - c| < \delta$. To do this, choose $\delta = \varepsilon$. The second inequality then implies the first, as shown in Figure 1.16.

EXAMPLE 1 Evaluating Basic Limits

a. $\lim_{x \to 2} 3 = 3$ **b.** $\lim_{x \to -4} x = -4$ **c.** $\lim_{x \to 2} x^2 = 2^2 = 4$

REMARK To help you learn these properties, write each property in words. For example, in words, Property 4 of Theorem 1.2 says, "the limit of the product of two functions is the product of their limits." Write the other properties in words.

THEOREM 1.2 Properties of Limits

Let b and c be real numbers, let n be a positive integer, and let f and g be functions with the limits $\lim_{x \to c} f(x) = L$ and $\lim_{x \to c} g(x) = K$.

1. Scalar multiple: $\lim_{x \to c} [bf(x)] = bL$
2. Sum: $\lim_{x \to c} [f(x) + g(x)] = L + K$
3. Difference: $\lim_{x \to c} [f(x) - g(x)] = L - K$
4. Product: $\lim_{x \to c} [f(x)g(x)] = LK$
5. Quotient: $\lim_{x \to c} \frac{f(x)}{g(x)} = \frac{L}{K}, \quad K \neq 0$
6. Power: $\lim_{x \to c} [f(x)]^n = L^n$

The proof of Property 1 is left as an exercise (see Exercise 121).
The proofs of the other properties are given in Appendix A.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The limit of $f(x)$ as x approaches 2 is 19.
Figure 1.17

EXAMPLE 2 The Limit of a Polynomial

Find the limit: $\lim_{x\to 2}(4x^2 + 3)$.

Solution

$$\begin{aligned}\lim_{x\to 2}(4x^2 + 3) &= \lim_{x\to 2} 4x^2 + \lim_{x\to 2} 3 && \text{Property 2, Theorem 1.2}\\ &= 4\left(\lim_{x\to 2} x^2\right) + \lim_{x\to 2} 3 && \text{Property 1, Theorem 1.2}\\ &= 4(2^2) + 3 && \text{Properties 1 and 3, Theorem 1.1}\\ &= 19 && \text{Simplify.}\end{aligned}$$

This limit is reinforced by the graph of $f(x) = 4x^2 + 3$ shown in Figure 1.17. ■

In Example 2, note that the limit (as x approaches 2) of the *polynomial function* $p(x) = 4x^2 + 3$ is simply the value of p at $x = 2$.

$$\lim_{x\to 2} p(x) = p(2) = 4(2^2) + 3 = 19$$

This *direct substitution* property is valid for all polynomial functions. Direct substitution can also be used to find the limit of a rational function, unless the substitution results in a zero denominator.

THEOREM 1.3 Limits of Polynomial and Rational Functions

If p is a polynomial function and c is a real number, then

$$\lim_{x\to c} p(x) = p(c). \qquad \text{Direct substitution}$$

If r is a rational function given by $r(x) = p(x)/q(x)$ and c is a real number such that $q(c) \neq 0$, then

$$\lim_{x\to c} r(x) = r(c) = \frac{p(c)}{q(c)}. \qquad \text{Direct substitution, } q(c) \neq 0$$



The limit of $f(x)$ as x approaches 1 is 2.
Figure 1.18

EXAMPLE 3 The Limit of a Rational Function

Find the limit: $\lim_{x\to 1} \dfrac{x^2 + x + 2}{x + 1}$.

Solution The denominator is not 0 when $x = 1$, so apply Theorem 1.3 to obtain

$$\lim_{x\to 1} \frac{x^2 + x + 2}{x + 1} = \frac{1^2 + 1 + 2}{1 + 1} = \frac{4}{2} = 2. \qquad \text{See Figure 1.18.}$$ ■

Polynomial functions and rational functions are two of the three basic types of algebraic functions. The next theorem deals with the limit of the third type of algebraic function—one that involves a radical.

THEOREM 1.4 The Limit of a Function Involving a Radical

Let n be a positive integer. The limit below is valid for all c when n is odd, and is valid for $c > 0$ when n is even.

$$\lim_{x\to c} \sqrt[n]{x} = \sqrt[n]{c} \qquad \text{Direct substitution}$$

A proof of this theorem is given in Appendix A.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Big Ideas of Calculus

The idea of a limit is central to calculus. You will use the concept of the limit of a function to develop some of the big ideas of calculus. such as differentiation and integration. Be sure to complete all concept exercises in this text — Concept Checks, Exploring Concepts, and Building on Concepts. These exercises are denoted by .

The next theorem greatly expands your ability to evaluate limits because it shows how to analyze the limit of a composite function.

THEOREM 1.5 The Limit of a Composite Function

If f and g are functions such that $\lim_{x\to c} g(x) = L$ and $\lim_{x\to L} f(x) = f(L)$, then

$$\lim_{x\to c} f(g(x)) = f\left(\lim_{x\to c} g(x)\right) = f(L).$$

A proof of this theorem is given in Appendix A.

EXAMPLE 4 Limits of Composite Functions

See LarsonCalculus.com for an interactive version of this type of example.

Find the limit.

a. $\lim_{x\to 0} \sqrt{x^2 + 4}$ **b.** $\lim_{x\to 3} \sqrt[3]{2x^2 - 10}$

Solution

a. Because

$$\lim_{x\to 0} (x^2 + 4) = 0^2 + 4 = 4 \quad \text{and} \quad \lim_{x\to 4} \sqrt{x} = \sqrt{4} = 2$$

you can conclude that

$$\lim_{x\to 0} \sqrt{x^2 + 4} = \sqrt{4} = 2.$$

b. Because

$$\lim_{x\to 3} (2x^2 - 10) = 2(3^2) - 10 = 8 \quad \text{and} \quad \lim_{x\to 8} \sqrt[3]{x} = \sqrt[3]{8} = 2$$

you can conclude that

$$\lim_{x\to 3} \sqrt[3]{2x^2 - 10} = \sqrt[3]{8} = 2.$$

You have seen that the limits of many algebraic functions can be evaluated by direct substitution. The six basic trigonometric functions also exhibit this desirable quality, as shown in the next theorem (presented without proof).

THEOREM 1.6 Limits of Trigonometric Functions

Let c be a real number in the domain of the given trigonometric function.

1. $\lim_{x\to c} \sin x = \sin c$
2. $\lim_{x\to c} \cos x = \cos c$
3. $\lim_{x\to c} \tan x = \tan c$
4. $\lim_{x\to c} \cot x = \cot c$
5. $\lim_{x\to c} \sec x = \sec c$
6. $\lim_{x\to c} \csc x = \csc c$

EXAMPLE 5 Limits of Trigonometric Functions

a. $\lim_{x\to 0} \tan x = \tan 0 = 0$

b. $\lim_{x\to \pi} (x \cos x) = \left(\lim_{x\to \pi} x\right)\left(\lim_{x\to \pi} \cos x\right) = \pi \cos \pi = -\pi$

c. $\lim_{x\to 0} \sin^2 x = \lim_{x\to 0} (\sin x)^2 = 0^2 = 0$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

A Strategy for Finding Limits

On the preceding three pages, you studied several types of functions whose limits can be evaluated by direct substitution. This knowledge, together with the next theorem, can be used to develop a strategy for finding limits.

THEOREM 1.7 Functions That Agree at All but One Point

Let c be a real number, and let $f(x) = g(x)$ for all $x \neq c$ in an open interval containing c. If the limit of $g(x)$ as x approaches c exists, then the limit of $f(x)$ also exists and

$$\lim_{x \to c} f(x) = \lim_{x \to c} g(x).$$

A proof of this theorem is given in Appendix A.



f and g agree at all but one point.
Figure 1.19

EXAMPLE 6 Finding the Limit of a Function

Find the limit.

$$\lim_{x \to 1} \frac{x^3 - 1}{x - 1}$$

Solution Let $f(x) = (x^3 - 1)/(x - 1)$. By factoring and dividing out common factors, you can rewrite f as

$$f(x) = \frac{(x - 1)(x^2 + x + 1)}{(x - 1)} = x^2 + x + 1 = g(x), \quad x \neq 1.$$

So, for all x-values other than $x = 1$, the functions f and g agree, as shown in Figure 1.19. Because the limit of $g(x)$ as x approaches 1 exists, you can apply Theorem 1.7 to conclude that f and g have the same limit at $x = 1$.

$$\begin{aligned}
\lim_{x \to 1} \frac{x^3 - 1}{x - 1} &= \lim_{x \to 1} \frac{(x - 1)(x^2 + x + 1)}{x - 1} && \text{Factor.} \\
&= \lim_{x \to 1} \frac{(x - 1)(x^2 + x + 1)}{(x - 1)} && \text{Divide out common factor.} \\
&= \lim_{x \to 1} (x^2 + x + 1) && \text{Apply Theorem 1.7.} \\
&= 1^2 + 1 + 1 && \text{Use direct substitution.} \\
&= 3 && \text{Simplify.}
\end{aligned}$$

REMARK When applying this strategy for finding a limit, remember that some functions do not have a limit (as x approaches c). For instance, the limit below does not exist.

$$\lim_{x \to 1} \frac{x^3 + 1}{x - 1}$$

A Strategy for Finding Limits

1. Learn to recognize which limits can be evaluated by direct substitution. (These limits are listed in Theorems 1.1 through 1.6.)
2. When the limit of $f(x)$ as x approaches c *cannot* be evaluated by direct substitution, try to find a function g that agrees with f for all x other than $x = c$. [Choose g such that the limit of $g(x)$ *can* be evaluated by direct substitution.] Then apply Theorem 1.7 to conclude *analytically* that
$$\lim_{x \to c} f(x) = \lim_{x \to c} g(x) = g(c).$$
3. Use a *graph* or *table* to reinforce your conclusion.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Dividing Out Technique

Another procedure for finding a limit analytically is the **dividing out technique.** This technique involves dividing out common factors, as shown in Example 7.

EXAMPLE 7 Dividing Out Technique

See LarsonCalculus.com for an interactive version of this type of example.

Find the limit: $\lim_{x \to -3} \frac{x^2 + x - 6}{x + 3}$.

Solution Although you are taking the limit of a rational function, you *cannot* apply Theorem 1.3 because the limit of the denominator is 0.

$$\lim_{x \to -3} \frac{x^2 + x - 6}{x + 3} \quad \begin{cases} \lim_{x \to -3} (x^2 + x - 6) = 0 \\ \text{Direct substitution fails.} \\ \lim_{x \to -3} (x + 3) = 0 \end{cases}$$

Because the limit of the numerator is also 0, the numerator and denominator have a *common factor* of $(x + 3)$. So, for all $x \neq -3$, you can divide out this factor to obtain

$$f(x) = \frac{x^2 + x - 6}{x + 3} = \frac{(x + 3)(x - 2)}{x + 3} = x - 2 = g(x), \quad x \neq -3.$$

Using Theorem 1.7, it follows that

$$\lim_{x \to -3} \frac{x^2 + x - 6}{x + 3} = \lim_{x \to -3} (x - 2) \qquad \text{Apply Theorem 1.7.}$$
$$= -5. \qquad \text{Use direct substitution.}$$

This result is shown graphically in Figure 1.20. Note that the graph of the function f coincides with the graph of the function $g(x) = x - 2$, except that the graph of f has a hole at the point $(-3, -5)$. ■

REMARK In the solution to Example 7, be sure you see the usefulness of the Factor Theorem of Algebra. This theorem states that if c is a zero of a polynomial function, then $(x - c)$ is a factor of the polynomial. So, when you apply direct substitution to a rational function and obtain

$$r(c) = \frac{p(c)}{q(c)} = \frac{0}{0}$$

you can conclude that $(x - c)$ must be a common factor of both $p(x)$ and $q(x)$.



f is undefined when $x = -3$. The limit of $f(x)$ as x approaches -3 is -5.
Figure 1.20

In Example 7, direct substitution produced the meaningless fractional form $0/0$. An expression such as $0/0$ is called an **indeterminate form** because you cannot (from the form alone) determine the limit. When you try to evaluate a limit and encounter this form, remember that you must rewrite the fraction so that the new denominator does not have 0 as its limit. One way to do this is to *divide out common factors*. Another way is to use the *rationalizing technique* shown on the next page.

TECHNOLOGY PITFALL A graphing utility can give misleading information about the graph of a function. For instance, try graphing the function from Example 7

$$f(x) = \frac{x^2 + x - 6}{x + 3}$$

on a graphing utility. On some graphing utilities, the graph may appear to be defined at every real number, as shown in the figure at the right. However, f is undefined when $x = -3$, so the graph of f has a hole at $x = -3$. Check this on a graphing utility using the *trace* or *table* feature.



Misleading graph of f

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Rationalizing Technique

Another way to find a limit analytically is the **rationalizing technique,** which involves rationalizing either the numerator or denominator of a fractional expression. Recall that rationalizing the numerator (denominator) means multiplying the numerator and denominator by the conjugate of the numerator (denominator). For instance, to rationalize the numerator of

$$\frac{\sqrt{x}+4}{x}$$

multiply the numerator and denominator by the conjugate of $\sqrt{x}+4$, which is $\sqrt{x}-4$.

EXAMPLE 8 Rationalizing Technique

Find the limit: $\lim_{x\to 0}\dfrac{\sqrt{x+1}-1}{x}$.

Solution By direct substitution, you obtain the indeterminate form $0/0$.

$$\lim_{x\to 0}\frac{\sqrt{x+1}-1}{x}\quad\begin{cases}\lim_{x\to 0}\left(\sqrt{x+1}-1\right)=0\\ \lim_{x\to 0}x=0\end{cases}$$

Direct substitution fails.

In this case, you can rewrite the fraction by rationalizing the numerator.

$$\begin{aligned}\frac{\sqrt{x+1}-1}{x}&=\left(\frac{\sqrt{x+1}-1}{x}\right)\left(\frac{\sqrt{x+1}+1}{\sqrt{x+1}+1}\right)\\&=\frac{(x+1)-1}{x\left(\sqrt{x+1}+1\right)}&&\text{Multiply.}\\&=\frac{\cancel{x}}{\cancel{x}\left(\sqrt{x+1}+1\right)}&&\text{Divide out common factor.}\\&=\frac{1}{\sqrt{x+1}+1},\quad x\neq 0\end{aligned}$$

Now, using Theorem 1.7, you can evaluate the limit as shown.

$$\begin{aligned}\lim_{x\to 0}\frac{\sqrt{x+1}-1}{x}&=\lim_{x\to 0}\frac{1}{\sqrt{x+1}+1}&&\text{Apply Theorem 1.7.}\\&=\frac{1}{1+1}&&\text{Use direct substitution.}\\&=\frac{1}{2}&&\text{Simplify.}\end{aligned}$$

A table or a graph can reinforce your conclusion that the limit is $\frac{1}{2}$. (See Figure 1.21.)

x approaches 0 from the left. / x approaches 0 from the right.

x	-0.25	-0.1	-0.01	-0.001	0	0.001	0.01	0.1	0.25
$f(x)$	0.5359	0.5132	0.5013	0.5001	?	0.4999	0.4988	0.4881	0.4721

$f(x)$ approaches 0.5. / $f(x)$ approaches 0.5.

REMARK The rationalizing technique for evaluating limits is based on multiplication by a convenient form of 1. In Example 8, the convenient form is

$$1=\frac{\sqrt{x+1}+1}{\sqrt{x+1}+1}.$$



The limit of $f(x)$ as x approaches 0 is $\frac{1}{2}$.
Figure 1.21

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

The Squeeze Theorem

The next theorem concerns the limit of a function that is squeezed between two other functions, each of which has the same limit at a given x-value, as shown in Figure 1.22.



The Squeeze Theorem
Figure 1.22

THEOREM 1.8 The Squeeze Theorem

If $h(x) \le f(x) \le g(x)$ for all x in an open interval containing c, except possibly at c itself, and if

$$\lim_{x \to c} h(x) = L = \lim_{x \to c} g(x)$$

then $\lim_{x \to c} f(x)$ exists and is equal to L.

A proof of this theorem is given in Appendix A.

You can see the usefulness of the Squeeze Theorem (also called the Sandwich Theorem or the Pinching Theorem) in the proof of Theorem 1.9.

THEOREM 1.9 Two Special Trigonometric Limits

1. $\lim_{x \to 0} \frac{\sin x}{x} = 1$ **2.** $\lim_{x \to 0} \frac{1 - \cos x}{x} = 0$



A circular sector is used to prove Theorem 1.9.
Figure 1.23

Proof The proof of the second limit is left as an exercise (see Exercise 122). To avoid the confusion of two different uses of x, the proof of the first limit is presented using the variable θ, where θ is an acute positive angle *measured in radians*. Figure 1.23 shows a circular sector that is squeezed between two triangles.



$$\begin{array}{ccccc} \text{Area of triangle} & \ge & \text{Area of sector} & \ge & \text{Area of triangle} \\ \frac{\tan \theta}{2} & \ge & \frac{\theta}{2} & \ge & \frac{\sin \theta}{2} \end{array}$$

Multiplying each expression by $2/\sin \theta$ produces

$$\left(\frac{\tan \theta}{2}\right)\left(\frac{2}{\sin \theta}\right) \ge \left(\frac{\theta}{2}\right)\left(\frac{2}{\sin \theta}\right) \ge \left(\frac{\sin \theta}{2}\right)\left(\frac{2}{\sin \theta}\right) \quad \Rightarrow \quad \frac{1}{\cos \theta} \ge \frac{\theta}{\sin \theta} \ge 1$$

and taking reciprocals and reversing the inequalities yields

$$\cos \theta \le \frac{\sin \theta}{\theta} \le 1.$$

Because $\cos \theta = \cos(-\theta)$ and $(\sin \theta)/\theta = [\sin(-\theta)]/(-\theta)$, you can conclude that this inequality is valid for *all* nonzero θ in the open interval $(-\pi/2, \pi/2)$. Finally, because $\lim_{\theta \to 0} \cos \theta = 1$ and $\lim_{\theta \to 0} 1 = 1$, you can apply the Squeeze Theorem to conclude that

$$\lim_{\theta \to 0} \frac{\sin \theta}{\theta} = 1.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 9 A Limit Involving a Trigonometric Function

Find the limit: $\lim_{x\to 0} \frac{\tan x}{x}$.

Solution Direct substitution yields the indeterminate form $0/0$. To solve this problem, rewrite $\tan x$ as $(\sin x)/(\cos x)$ and obtain

$$\lim_{x\to 0} \frac{\tan x}{x} = \lim_{x\to 0} \left(\frac{\sin x}{x}\right)\left(\frac{1}{\cos x}\right).$$

Now, because

$$\lim_{x\to 0} \frac{\sin x}{x} = 1$$

and

$$\lim_{x\to 0} \frac{1}{\cos x} = 1$$

you can obtain

$$\begin{aligned}\lim_{x\to 0} \frac{\tan x}{x} &= \left(\lim_{x\to 0} \frac{\sin x}{x}\right)\left(\lim_{x\to 0} \frac{1}{\cos x}\right)\\ &= (1)(1)\\ &= 1.\end{aligned}$$

(See Figure 1.24.)



The limit of $f(x)$ as x approaches 0 is 1.
Figure 1.24

REMARK Be sure you understand the mathematical conventions regarding parentheses and trigonometric functions. For instance, in Example 10, $\sin 4x$ means $\sin(4x)$.

EXAMPLE 10 A Limit Involving a Trigonometric Function

Find the limit: $\lim_{x\to 0} \frac{\sin 4x}{x}$.

Solution Direct substitution yields the indeterminate form $0/0$. To solve this problem, rewrite the limit as

$$\lim_{x\to 0} \frac{\sin 4x}{x} = 4\left(\lim_{x\to 0} \frac{\sin 4x}{4x}\right).$$ Multiply and divide by 4.

Now, by letting $y = 4x$ and observing that x approaches 0 if and only if y approaches 0, you can write

$$\begin{aligned}\lim_{x\to 0} \frac{\sin 4x}{x} &= 4\left(\lim_{x\to 0} \frac{\sin 4x}{4x}\right)\\ &= 4\left(\lim_{y\to 0} \frac{\sin y}{y}\right) && \text{Let } y = 4x.\\ &= 4(1) && \text{Apply Theorem 1.9(1).}\\ &= 4. && \text{See Figure 1.25.}\end{aligned}$$



The limit of $g(x)$ as x approaches 0 is 4.
Figure 1.25

TECHNOLOGY Use a graphing utility to confirm the limits in the examples and in the exercise set. For instance, Figures 1.24 and 1.25 show the graphs of

$$f(x) = \frac{\tan x}{x} \quad \text{and} \quad g(x) = \frac{\sin 4x}{x}.$$

Note that the first graph appears to contain the point $(0, 1)$ and the second graph appears to contain the point $(0, 4)$, which lends support to the conclusions obtained in Examples 9 and 10.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

1.3 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe how to find the limit of a polynomial function $p(x)$ as x approaches c.
2. What is meant by an indeterminate form?
3. Explain the Squeeze Theorem.
4. List the two special trigonometric limits.

Finding a Limit In Exercises 5–22, find the limit.

5. $\lim_{x\to 2} x^3$
6. $\lim_{x\to -3} x^4$
7. $\lim_{x\to -3} (2x + 5)$
8. $\lim_{x\to 9} (4x - 1)$
9. $\lim_{x\to -3} (x^2 + 3x)$
10. $\lim_{x\to 2} (-x^3 + 1)$
11. $\lim_{x\to -3} (2x^2 + 4x + 1)$
12. $\lim_{x\to 1} (2x^3 - 6x + 5)$
13. $\lim_{x\to 3} \sqrt{x + 8}$
14. $\lim_{x\to 2} \sqrt[3]{12x + 3}$
15. $\lim_{x\to -4} (1 - x)^3$
16. $\lim_{x\to 0} (3x - 2)^4$
17. $\lim_{x\to 2} \frac{3}{2x + 1}$
18. $\lim_{x\to -5} \frac{5}{x + 3}$
19. $\lim_{x\to 1} \frac{x}{x^2 + 4}$
20. $\lim_{x\to 1} \frac{3x + 5}{x + 1}$
21. $\lim_{x\to 7} \frac{3x}{\sqrt{x + 2}}$
22. $\lim_{x\to 3} \frac{\sqrt{x + 6}}{x + 2}$

Finding Limits In Exercises 23–26, find the limits.

23. $f(x) = 5 - x, g(x) = x^3$
    (a) $\lim_{x\to 1} f(x)$ (b) $\lim_{x\to 4} g(x)$ (c) $\lim_{x\to 1} g(f(x))$
24. $f(x) = x + 7, g(x) = x^2$
    (a) $\lim_{x\to -3} f(x)$ (b) $\lim_{x\to 4} g(x)$ (c) $\lim_{x\to -3} g(f(x))$
25. $f(x) = 4 - x^2, g(x) = \sqrt{x + 1}$
    (a) $\lim_{x\to 1} f(x)$ (b) $\lim_{x\to 3} g(x)$ (c) $\lim_{x\to 1} g(f(x))$
26. $f(x) = 2x^2 - 3x + 1, g(x) = \sqrt[3]{x + 6}$
    (a) $\lim_{x\to 4} f(x)$ (b) $\lim_{x\to 21} g(x)$ (c) $\lim_{x\to 4} g(f(x))$

Finding a Limit of a Trigonometric Function In Exercises 27–36, find the limit of the trigonometric function.

27. $\lim_{x\to \pi/2} \sin x$
28. $\lim_{x\to \pi} \tan x$
29. $\lim_{x\to 1} \cos \frac{\pi x}{3}$
30. $\lim_{x\to 2} \sin \frac{\pi x}{12}$
31. $\lim_{x\to 0} \sec 2x$
32. $\lim_{x\to \pi} \cos 3x$
33. $\lim_{x\to 5\pi/6} \sin x$
34. $\lim_{x\to 5\pi/3} \cos x$
35. $\lim_{x\to 3} \tan \frac{\pi x}{4}$
36. $\lim_{x\to 7} \sec \frac{\pi x}{6}$

Evaluating Limits In Exercises 37–40, use the information to evaluate the limits.

37. $\lim_{x\to c} f(x) = \frac{2}{5}$, $\lim_{x\to c} g(x) = 2$
    (a) $\lim_{x\to c} [5g(x)]$
    (b) $\lim_{x\to c} [f(x) + g(x)]$
    (c) $\lim_{x\to c} [f(x)g(x)]$
    (d) $\lim_{x\to c} \frac{f(x)}{g(x)}$
38. $\lim_{x\to c} f(x) = 2$, $\lim_{x\to c} g(x) = \frac{3}{4}$
    (a) $\lim_{x\to c} [4f(x)]$
    (b) $\lim_{x\to c} [f(x) + g(x)]$
    (c) $\lim_{x\to c} [f(x)g(x)]$
    (d) $\lim_{x\to c} \frac{f(x)}{g(x)}$
39. $\lim_{x\to c} f(x) = 16$
    (a) $\lim_{x\to c} [f(x)]^2$
    (b) $\lim_{x\to c} \sqrt{f(x)}$
    (c) $\lim_{x\to c} [3f(x)]$
    (d) $\lim_{x\to c} [f(x)]^{3/2}$
40. $\lim_{x\to c} f(x) = 27$
    (a) $\lim_{x\to c} \sqrt[3]{f(x)}$
    (b) $\lim_{x\to c} \frac{f(x)}{18}$
    (c) $\lim_{x\to c} [f(x)]^2$
    (d) $\lim_{x\to c} [f(x)]^{2/3}$

Finding a Limit In Exercises 41–46, write a simpler function that agrees with the given function at all but one point. Then find the limit of the function. Use a graphing utility to confirm your result.

41. $\lim_{x\to 0} \frac{x^2 + 3x}{x}$
42. $\lim_{x\to 0} \frac{x^4 - 5x^2}{x^2}$
43. $\lim_{x\to -1} \frac{x^2 - 1}{x + 1}$
44. $\lim_{x\to -2} \frac{3x^2 + 5x - 2}{x + 2}$
45. $\lim_{x\to 2} \frac{x^3 - 8}{x - 2}$
46. $\lim_{x\to -1} \frac{x^3 + 1}{x + 1}$

Finding a Limit In Exercises 47–62, find the limit.

47. $\lim_{x\to 0} \frac{x}{x^2 - x}$
48. $\lim_{x\to 0} \frac{7x^3 - x^2}{x}$
49. $\lim_{x\to 4} \frac{x - 4}{x^2 - 16}$
50. $\lim_{x\to 5} \frac{5 - x}{x^2 - 25}$
51. $\lim_{x\to -3} \frac{x^2 + x - 6}{x^2 - 9}$
52. $\lim_{x\to 2} \frac{x^2 + 2x - 8}{x^2 - x - 2}$
53. $\lim_{x\to 4} \frac{\sqrt{x + 5} - 3}{x - 4}$
54. $\lim_{x\to 3} \frac{\sqrt{x + 1} - 2}{x - 3}$
55. $\lim_{x\to 0} \frac{\sqrt{x + 5} - \sqrt{5}}{x}$
56. $\lim_{x\to 0} \frac{\sqrt{2 + x} - \sqrt{2}}{x}$
57. $\lim_{x\to 0} \frac{[1/(3 + x)] - (1/3)}{x}$
58. $\lim_{x\to 0} \frac{[1/(x + 4)] - (1/4)}{x}$
59. $\lim_{\Delta x\to 0} \frac{2(x + \Delta x) - 2x}{\Delta x}$
60. $\lim_{\Delta x\to 0} \frac{(x + \Delta x)^2 - x^2}{\Delta x}$
61. $\lim_{\Delta x\to 0} \frac{(x + \Delta x)^2 - 2(x + \Delta x) + 1 - (x^2 - 2x + 1)}{\Delta x}$
62. $\lim_{\Delta x\to 0} \frac{(x + \Delta x)^3 - x^3}{\Delta x}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding a Limit **In Exercises 63–74, find the limit.**

63. $\lim_{x\to 0} \frac{\sin x}{5x}$

64. $\lim_{x\to 0} \frac{3(1-\cos x)}{x}$

65. $\lim_{x\to 0} \frac{(\sin x)(1-\cos x)}{x^2}$

66. $\lim_{\theta\to 0} \frac{\cos\theta \tan\theta}{\theta}$

67. $\lim_{x\to 0} \frac{\sin^2 x}{x}$

68. $\lim_{x\to 0} \frac{\tan^2 x}{x}$

69. $\lim_{h\to 0} \frac{(1-\cos h)^2}{h}$

70. $\lim_{x\to 0} \frac{\cos x - \sin x - 1}{2x}$

71. $\lim_{x\to 0} \frac{6-6\cos x}{3}$

72. $\lim_{\phi\to \pi} \phi \sec\phi$

73. $\lim_{t\to 0} \frac{\sin 3t}{2t}$

74. $\lim_{x\to 0} \frac{\sin 2x}{\sin 3x}$ $\left[\textit{Hint: Find } \lim_{x\to 0}\left(\frac{2\sin 2x}{2x}\right)\left(\frac{3x}{3\sin 3x}\right).\right]$

Graphical, Numerical, and Analytic Analysis **In Exercises 75–82, use a graphing utility to graph the function and estimate the limit. Use a table to reinforce your conclusion. Then find the limit by analytic methods.**

75. $\lim_{x\to 0} \frac{\sqrt{x+2}-\sqrt{2}}{x}$

76. $\lim_{x\to 16} \frac{4-\sqrt{x}}{x-16}$

77. $\lim_{x\to 0} \frac{[1/(2+x)]-(1/2)}{x}$

78. $\lim_{x\to 2} \frac{x^5-32}{x-2}$

79. $\lim_{t\to 0} \frac{\sin 3t}{t}$

80. $\lim_{x\to 0} \frac{\cos x - 1}{2x^2}$

81. $\lim_{x\to 0} \frac{\sin x^2}{x}$

82. $\lim_{x\to 0} \frac{\sin x}{\sqrt[3]{x}}$

Finding a Limit **In Exercises 83–90, find**

$$\lim_{\Delta x\to 0} \frac{f(x+\Delta x)-f(x)}{\Delta x}.$$

83. $f(x) = 3x - 2$

84. $f(x) = -6x + 3$

85. $f(x) = x^2 - 4x$

86. $f(x) = 3x^2 + 1$

87. $f(x) = 2\sqrt{x}$

88. $f(x) = \sqrt{x} - 5$

89. $f(x) = \frac{1}{x+3}$

90. $f(x) = \frac{1}{x^2}$

Using the Squeeze Theorem **In Exercises 91 and 92, use the Squeeze Theorem to find $\lim_{x\to c} f(x)$.**

91. $c = 0$

$4 - x^2 \le f(x) \le 4 + x^2$

92. $c = a$

$b - |x-a| \le f(x) \le b + |x-a|$

Using the Squeeze Theorem **In Exercises 93–96, use a graphing utility to graph f and the equations $y = |x|$ and $y = -|x|$ in the same viewing window. Using the graphs to observe the Squeeze Theorem visually, find $\lim_{x\to 0} f(x)$.**

93. $f(x) = |x| \sin x$

94. $f(x) = |x| \cos x$

95. $f(x) = x \sin\frac{1}{x}$

96. $f(x) = x \cos\frac{1}{x}$

Kevin Fleming/Getty Images

Exploring Concepts

97. In the context of finding limits, discuss what is meant by two functions that agree at all but one point. Include an example.

98. Write a function of each specified type that has a limit of 4 as x approaches 8.

(a) linear

(b) polynomial of degree 2

(c) rational

(d) radical

(e) cosine

(f) sine

Free-Falling Object **In Exercises 99 and 100, use the position function $s(t) = -4.9t^2 + 200$, which gives the height (in meters) of an object that has fallen for t seconds from a height of 200 meters. The velocity at time $t = a$ seconds is given by**

$$\lim_{t\to a} \frac{s(a)-s(t)}{a-t}.$$

99. Find the velocity of the object when $t = 3$.

100. At what velocity will the object impact the ground?

Free-Falling Object

In Exercises 101 and 102, use the position function $s(t) = -16t^2 + 500$, which gives the height (in feet) of an object that has fallen for t seconds from a height of 500 feet. The velocity at time $t = a$ seconds is given by

$$\lim_{t\to a} \frac{s(a)-s(t)}{a-t}.$$

101. A construction worker drops a full paint can from a height of 500 feet. How fast will the paint can be falling after 2 seconds?

102. A construction worker drops a full paint can from a height of 500 feet. When will the paint can hit the ground? At what velocity will the paint can impact the ground?

103. Writing Use a graphing utility to graph

$$f(x) = x, \quad g(x) = \sin x, \quad \text{and} \quad h(x) = \frac{\sin x}{x}$$

in the same viewing window. Compare the magnitudes of $f(x)$ and $g(x)$ when x is close to 0. Use the comparison to write a short paragraph explaining why

$$\lim_{x\to 0} h(x) = 1.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

104. Writing Use a graphing utility to graph

$$f(x) = x, \quad g(x) = \sin^2 x, \quad \text{and} \quad h(x) = \frac{\sin^2 x}{x}$$

in the same viewing window. Compare the magnitudes of $f(x)$ and $g(x)$ when x is close to 0. Use the comparison to write a short paragraph explaining why

$$\lim_{x\to 0} h(x) = 0.$$

105. Finding Functions Find two functions f and g such that $\lim_{x\to 0} f(x)$ and $\lim_{x\to 0} g(x)$ do not exist, but

$$\lim_{x\to 0} [f(x) + g(x)]$$

does exist.

106. Proof Prove that if $\lim_{x\to c} f(x)$ exists and

$$\lim_{x\to c} [f(x) + g(x)]$$

does not exist, then $\lim_{x\to c} g(x)$ does not exist.

107. Proof Prove Property 1 of Theorem 1.1.

108. Proof Prove Property 3 of Theorem 1.1. (You may use Property 4 of Theorem 1.2.)

109. Proof Prove that if

$$\lim_{x\to c} f(x) = 0 \quad \text{and} \quad |g(x)| \le M$$

for a fixed number M and all $x \neq c$, then

$$\lim_{x\to c} [f(x)g(x)] = 0.$$

110. Proof Prove that if

$$\lim_{x\to c} f(x) = L$$

then $\lim_{x\to c} |f(x)| = |L|$.

[*Hint:* Use the inequality $\big||f(x)| - |L|\big| \le |f(x) - L|$.]

111. Proof

(a) Prove that if

$$\lim_{x\to c} f(x) = 0$$

then $\lim_{x\to c} |f(x)| = 0$.

(b) Prove that if

$$\lim_{x\to c} |f(x)| = 0$$

then $\lim_{x\to c} f(x) = 0$.

[*Note:* This is the converse of part (a).]

112. Think About It Find a function f to show that the converse of Exercise 110 is not true. [*Hint:* Find a function f such that $\lim_{x\to c} |f(x)| = |L|$ but $\lim_{x\to c} f(x)$ does not exist.]

113. Think About It When using a graphing utility to generate a table to approximate

$$\lim_{x\to 0} \frac{\sin x}{x}$$

a student concluded that the limit was 0.01745 rather than 1. Determine the probable cause of the error.

114. HOW DO YOU SEE IT? Would you use the dividing out technique or the rationalizing technique to find the limit of each function? Explain your reasoning.

(a) $\lim_{x\to -2} \dfrac{x^2 + x - 2}{x + 2}$ (b) $\lim_{x\to 0} \dfrac{\sqrt{x+4} - 2}{x}$





True or False? **In Exercises 115–120, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

115. $\lim_{x\to 0} \dfrac{|x|}{x} = 1$

116. $\lim_{x\to \pi} \dfrac{\sin x}{x} = 1$

117. If $f(x) = g(x)$ for all real numbers other than $x = 0$ and $\lim_{x\to 0} f(x) = L$, then $\lim_{x\to 0} g(x) = L$.

118. If $\lim_{x\to c} f(x) = L$, then $f(c) = L$.

119. $\lim_{x\to 2} f(x) = 3$, where $f(x) = \begin{cases} 3, & x \le 2 \\ 0, & x > 2 \end{cases}$

120. If $f(x) < g(x)$ for all $x \neq a$, then $\lim_{x\to a} f(x) < \lim_{x\to a} g(x)$.

121. Proof Prove Property 1 of Theorem 1.2.

122. Proof Prove the second part of Theorem 1.9.

$$\lim_{x\to 0} \frac{1 - \cos x}{x} = 0$$

123. Graphical Reasoning Consider $f(x) = \dfrac{\sec x - 1}{x^2}$.

(a) Find the domain of f.

(b) Use a graphing utility to graph f. Is the domain of f obvious from the graph? If not, explain.

(c) Use the graph of f to approximate $\lim_{x\to 0} f(x)$.

(d) Confirm your answer to part (c) analytically.

124. Approximation

(a) Find $\lim_{x\to 0} \dfrac{1 - \cos x}{x^2}$.

(b) Use your answer to part (a) to derive the approximation $\cos x \approx 1 - \frac{1}{2}x^2$ for x near 0.

(c) Use your answer to part (b) to approximate $\cos(0.1)$.

(d) Use a calculator to approximate $\cos(0.1)$ to four decimal places. Compare the result with part (c).

125. Piecewise Functions Let

$$f(x) = \begin{cases} 0, & \text{if } x \text{ is rational} \\ 1, & \text{if } x \text{ is irrational} \end{cases} \quad \text{and} \quad g(x) = \begin{cases} 0, & \text{if } x \text{ is rational} \\ x, & \text{if } x \text{ is irrational} \end{cases}.$$

Find (if possible) $\lim_{x\to 0} f(x)$ and $\lim_{x\to 0} g(x)$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

1.4 Continuity and One-Sided Limits

GO DIGITAL

- Determine continuity at a point and continuity on an open interval.
- Determine one-sided limits and continuity on a closed interval.
- Use properties of continuity.
- Explain and use the Intermediate Value Theorem.

Continuity at a Point and on an Open Interval

In mathematics, the term *continuous* has much the same meaning as it has in everyday usage. Informally, to say that a function f is continuous at $x = c$ means that there is no interruption in the graph of f at c. That is, its graph is unbroken at c, and there are no holes, jumps, or gaps. Figure 1.26 identifies three values of x at which the graph of f is *not* continuous. At all other points in the interval (a, b), the graph of f is uninterrupted and **continuous.**



Three conditions exist for which the graph of f is not continuous at $x = c$.
Figure 1.26

In Figure 1.26, it appears that continuity at $x = c$ can be destroyed by any one of three conditions.

1. The function is not defined at $x = c$.
2. The limit of $f(x)$ does not exist at $x = c$.
3. The limit of $f(x)$ exists at $x = c$, but it is not equal to $f(c)$.

If *none* of the three conditions is true, then the function f is **continuous at c,** as indicated in the important definition below.

Definition of Continuity

Continuity at a Point
A function f is **continuous at c** when these three conditions are met.

1. $f(c)$ is defined. **2.** $\lim_{x \to c} f(x)$ exists. **3.** $\lim_{x \to c} f(x) = f(c)$

Continuity on an Open Interval
A function is **continuous on an open interval (a, b)** when the function is continuous at each point in the interval. A function that is continuous on the entire real number line $(-\infty, \infty)$ is **everywhere continuous.**

A function may be continuous at some points and not continuous at others. A function that is continuous at all points *in its domain* is simply called **continuous.**

Exploration

Informally, a function is *continuous* on an open interval when its graph can be drawn with a pencil without lifting the pencil from the paper. Use a graphing utility to graph each function on the given interval. From the graphs, which functions would you say are continuous on the interval? Do you trust the results you obtained graphically? Explain your reasoning.

	Function	Interval
a.	$y = x^2 + 1$	$(-3, 3)$
b.	$y = \dfrac{1}{x - 2}$	$(-3, 3)$
c.	$y = \dfrac{\sin x}{x}$	$(-\pi, \pi)$
d.	$y = \dfrac{x^2 - 4}{x + 2}$	$(-3, 3)$

FOR FURTHER INFORMATION
For more information on the concept of continuity, see the article "Leibniz and the Spell of the Continuous" by Hardy Grant in *The College Mathematics Journal*. To view this article, go to *MathArticles.com*.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



(a) Removable discontinuity



(b) Nonremovable discontinuity



(c) Removable discontinuity

Figure 1.27

Consider an open interval I that contains a real number c. If a function f is defined on I (except possibly at c), and f is not continuous at c, then f is said to have a **discontinuity** at c. Discontinuities fall into two categories: **removable** and **nonremovable.** A discontinuity at c is called removable when f can be made continuous by appropriately defining (or redefining) $f(c)$. For instance, the functions shown in Figures 1.27(a) and (c) have removable discontinuities at c and the function shown in Figure 1.27(b) has a nonremovable discontinuity at c.

EXAMPLE 1 Continuity of a Function

Discuss the continuity of each function.

a. $f(x) = \dfrac{1}{x}$ **b.** $g(x) = \dfrac{x^2 - 1}{x - 1}$ **c.** $h(x) = \begin{cases} x + 1, & x \leq 0 \\ x^2 + 1, & x > 0 \end{cases}$ **d.** $y = \sin x$

Solution

a. The domain of f is all nonzero real numbers. From Theorem 1.3, you can conclude that f is continuous at every x-value in its domain. At $x = 0$, f has a nonremovable discontinuity, as shown in Figure 1.28(a). In other words, there is no way to define $f(0)$ so as to make the function continuous at $x = 0$.

b. The domain of g is all real numbers except $x = 1$. From Theorem 1.3, you can conclude that g is continuous at every x-value in its domain. At $x = 1$, the function has a removable discontinuity, as shown in Figure 1.28(b). By defining $g(1)$ as 2, the "redefined" function is continuous for all real numbers.

c. The domain of h is all real numbers. The function h is continuous on $(-\infty, 0)$ and $(0, \infty)$. At $x = 0$, $h(0) = 1$. Also, note that

$$\lim_{x \to 0} h(x) = 1.$$ Limit of $h(x)$ as x approaches 0 exists and is equal to $h(0)$.

So, h is continuous on the entire real number line, as shown in Figure 1.28(c).

d. The domain of y is all real numbers. From Theorem 1.6, you can conclude that the function is continuous on its entire domain, $(-\infty, \infty)$, as shown in Figure 1.28(d).



(a) Nonremovable discontinuity at $x = 0$



(b) Removable discontinuity at $x = 1$



(c) Continuous on entire real number line



(d) Continuous on entire real number line

Figure 1.28

REMARK You may want to refer to f in Example 1(a) as "discontinuous," but this terminology can be confusing. Rather than saying f is discontinuous, it is more precise to say that f has a discontinuity at $x = 0$.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



(a) Limit as x approaches c from the right.



(b) Limit as x approaches c from the left.

Figure 1.29

One-Sided Limits and Continuity on a Closed Interval

To understand continuity on a closed interval, you first need to look at a different type of limit called a **one-sided limit.** For instance, the **limit from the right** (or right-hand limit) means that x approaches c from values greater than c [see Figure 1.29(a)]. This limit is denoted as

$$\lim_{x \to c^+} f(x) = L.$$ Limit from the right

Similarly, the **limit from the left** (or left-hand limit) means that x approaches c from values less than c [see Figure 1.29(b)]. This limit is denoted as

$$\lim_{x \to c^-} f(x) = L.$$ Limit from the left

One-sided limits are useful in taking limits of functions involving radicals. For instance, if n is an even integer, then

$$\lim_{x \to 0^+} \sqrt[n]{x} = 0.$$



The limit of $f(x)$ as x approaches -2 from the right is 0.

Figure 1.30

EXAMPLE 2 A One-Sided Limit

Find the limit of $f(x) = \sqrt{4 - x^2}$ as x approaches -2 from the right.

Solution As shown in Figure 1.30, the limit as x approaches -2 from the right is

$$\lim_{x \to -2^+} \sqrt{4 - x^2} = 0.$$

One-sided limits can be used to investigate the behavior of **step functions.** One common type of step function is the **greatest integer function** $[\![x]\!]$, defined as

$$[\![x]\!] = \text{greatest integer } n \text{ such that } n \leq x.$$ Greatest integer function

For instance, $[\![2.5]\!] = 2$ and $[\![-2.5]\!] = -3$.

EXAMPLE 3 The Greatest Integer Function

Find the limit of the greatest integer function $f(x) = [\![x]\!]$ as x approaches 0 from the left and from the right.

Solution As shown in Figure 1.31, the limit as x approaches 0 *from the left* is

$$\lim_{x \to 0^-} [\![x]\!] = -1$$

and the limit as x approaches 0 *from the right* is

$$\lim_{x \to 0^+} [\![x]\!] = 0.$$

So, f has a discontinuity at zero because the left- and right-hand limits at zero are different. By similar reasoning, you can conclude that the greatest integer function has a discontinuity at any integer n.



Greatest integer function

Figure 1.31

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

When the limit from the left is not equal to the limit from the right, the (two-sided) limit *does not exist*. The next theorem makes this more explicit. The proof of this theorem follows directly from the definition of a one-sided limit.

THEOREM 1.10 The Existence of a Limit

Let f be a function, and let c and L be real numbers. The limit of $f(x)$ as x approaches c is L if and only if

$$\lim_{x \to c^-} f(x) = L \quad \text{and} \quad \lim_{x \to c^+} f(x) = L.$$

The concept of a one-sided limit allows you to extend the definition of continuity to closed intervals. Basically, a function is continuous on a closed interval when it is continuous in the interior of the interval and exhibits one-sided continuity at the endpoints. This is stated formally in the next definition.



Continuous function on a closed interval
Figure 1.32

Definition of Continuity on a Closed Interval

A function f is **continuous on the closed interval** $[a, b]$ when f is continuous on the open interval (a, b) and

$$\lim_{x \to a^+} f(x) = f(a)$$ Limit as x approaches a from the right

and

$$\lim_{x \to b^-} f(x) = f(b).$$ Limit as x approaches b from the left

The function f is **continuous from the right** at a and **continuous from the left** at b (see Figure 1.32).

Similar definitions can be made to cover continuity on intervals of the form $(a, b]$ and $[a, b)$ that are neither open nor closed, or on infinite intervals. For example,

$$f(x) = \sqrt{x}$$

is continuous on the infinite interval $[0, \infty)$, and the function

$$g(x) = \sqrt{2 - x}$$

is continuous on the infinite interval $(-\infty, 2]$.

EXAMPLE 4 Continuity on a Closed Interval

Discuss the continuity of

$$f(x) = \sqrt{1 - x^2}.$$



f is continuous on $[-1, 1]$.
Figure 1.33

Solution The domain of f is the closed interval $[-1, 1]$. At all points in the open interval $(-1, 1)$, the continuity of f follows from Theorems 1.4 and 1.5. Moreover, because

$$\lim_{x \to -1^+} \sqrt{1 - x^2} = 0 = f(-1)$$ Continuous from the right

and

$$\lim_{x \to 1^-} \sqrt{1 - x^2} = 0 = f(1)$$ Continuous from the left

you can conclude that f is continuous on the closed interval $[-1, 1]$, as shown in Figure 1.33. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

The next example uses a one-sided limit to investigate the "lower limit" of the temperature of matter.

REMARK Charles's Law for gases (assuming constant pressure) can be stated as

$$V = kT$$

where V is volume, k is a constant, and T is temperature.

EXAMPLE 5 Charles's Law and Absolute Zero

On the Kelvin scale, *absolute zero* is the temperature 0 K. Although temperatures very close to 0 K have been produced in laboratories, absolute zero has never been attained. In fact, evidence suggests that absolute zero *cannot* be attained. How did scientists determine that 0 K is the "lower limit" of the temperature of matter? What is absolute zero on the Celsius scale?

Solution The determination of absolute zero stems from the work of the French physicist Jacques Charles (1746–1823). Charles discovered that the volume of gas at a constant pressure increases linearly with the temperature of the gas. The table illustrates this relationship between volume and temperature. To generate the values in the table, one mole of hydrogen is held at a constant pressure of one atmosphere. The volume V is approximated and is measured in liters, and the temperature T is measured in degrees Celsius.

Liquid helium is used to cool superconducting magnets, such as those used in magnetic resonance imaging (MRI) machines or in the Large Hadron Collider (see photo). The magnets are made with materials that only superconduct at temperatures a few degrees above absolute zero. These temperatures are possible with liquid helium because helium becomes a liquid at −269°C, or 4.15 K.

T	−40	−20	0	20	40	60	80
V	19.1482	20.7908	22.4334	24.0760	25.7186	27.3612	29.0038

The points represented by the table are shown in the figure at the right. Moreover, by using the points in the table, you can determine that T and V are related by the linear equation

$$V = 0.08213T + 22.4334.$$

Solving for T, you get an equation for the temperature of the gas.

$$T = \frac{V - 22.4334}{0.08213}$$



The volume of hydrogen gas depends on its temperature.

By reasoning that the volume of the gas can approach 0 (but can never equal or go below 0), you can determine that the "least possible temperature" is

$$\lim_{V \to 0^+} T = \lim_{V \to 0^+} \frac{V - 22.4334}{0.08213}$$ Limit from the right

$$= \frac{0 - 22.4334}{0.08213}$$ Use direct substitution.

$$\approx -273.15.$$

So, absolute zero on the Kelvin scale (0 K) is approximately −273.15° on the Celsius scale. ■

The table below shows the temperatures in Example 5 converted to the Fahrenheit scale. Try repeating the solution shown in Example 5 using these temperatures and volumes. Use the result to find the value of absolute zero on the Fahrenheit scale.

T	−40	−4	32	68	104	140	176
V	19.1482	20.7908	22.4334	24.0760	25.7186	27.3612	29.0038

GO DIGITAL

FABRICE COFFRINI/AFP/Getty Images

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Properties of Continuity

In Section 1.3, you studied several properties of limits. Each of those properties yields a corresponding property pertaining to the continuity of a function. For instance, Theorem 1.11 follows directly from Theorem 1.2.

AUGUSTIN-LOUIS CAUCHY (1789–1857)

The concept of a continuous function was first introduced by Augustin-Louis Cauchy in 1821. The definition given in his text *Cours d'Analyse* stated that indefinite small changes in y were the result of indefinite small changes in x. "…$f(x)$ will be called a *continuous* function if … the numerical values of the difference $f(x + \alpha) - f(x)$ decrease indefinitely with those of α…."

See LarsonCalculus.com to read more of this biography.

THEOREM 1.11 Properties of Continuity

If b is a real number and f and g are continuous at $x = c$, then the functions listed below are also continuous at c.

1. Scalar multiple: bf
2. Sum: $f + g$
3. Difference: $f - g$
4. Product: fg
5. Quotient: $\frac{f}{g}$, $g(c) \neq 0$

A proof of this theorem is given in Appendix A.

It is important for you to be able to recognize functions that are continuous at every point in their domains. The list below summarizes the functions you have studied so far that are continuous at every point in their domains.

1. Polynomial: $p(x) = a_n x^n + a_{n-1}x^{n-1} + \cdots + a_1 x + a_0$
2. Rational: $r(x) = \frac{p(x)}{q(x)}$, $q(x) \neq 0$
3. Radical: $f(x) = \sqrt[n]{x}$
4. Trigonometric: $\sin x$, $\cos x$, $\tan x$, $\cot x$, $\sec x$, $\csc x$

Combining Theorem 1.11 with this list yields a wide variety of elementary functions that are continuous at every point in their domains.

EXAMPLE 6 Applying Properties of Continuity

See LarsonCalculus.com for an interactive version of this type of example.

By Theorem 1.11, it follows that each function below is continuous at every point in its domain.

$$f(x) = x + \sin x, \quad f(x) = 3 \tan x, \quad f(x) = \frac{x^2 + 1}{\cos x}$$

The next theorem, which is a consequence of Theorem 1.5, allows you to determine the continuity of *composite* functions such as

$$f(x) = \sin 3x, \quad f(x) = \sqrt{x^2 + 1}, \quad \text{and} \quad f(x) = \tan \frac{1}{x}.$$

REMARK One consequence of Theorem 1.12 is that when f and g satisfy the given conditions, you can determine the limit of $f(g(x))$ as x approaches c to be

$$\lim_{x \to c} f(g(x)) = f(g(c)).$$

THEOREM 1.12 Continuity of a Composite Function

If g is continuous at c and f is continuous at $g(c)$, then the composite function given by $(f \circ g)(x) = f(g(x))$ is continuous at c.

Proof By the definition of continuity, $\lim_{x \to c} g(x) = g(c)$ and $\lim_{x \to g(c)} f(x) = f(g(c))$.

Apply Theorem 1.5 with $L = g(c)$ to obtain $\lim_{x \to c} f(g(x)) = f\left(\lim_{x \to c} g(x)\right) = f(g(c))$. So, $(f \circ g)(x) = f(g(x))$ is continuous at c.

Bettmann/Getty Images

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 7 Testing for Continuity

Describe the interval(s) on which each function is continuous.

a. $f(x) = \tan x$ **b.** $g(x) = \begin{cases} \sin\frac{1}{x}, & x \neq 0 \\ 0, & x = 0 \end{cases}$ **c.** $h(x) = \begin{cases} x \sin\frac{1}{x}, & x \neq 0 \\ 0, & x = 0 \end{cases}$

Solution

a. The tangent function $f(x) = \tan x$ is undefined at

$$x = \frac{\pi}{2} + n\pi, \quad n \text{ is an integer.}$$

At all other points, f is continuous. So, $f(x) = \tan x$ is continuous on the open intervals

$$\ldots, \left(-\frac{3\pi}{2}, -\frac{\pi}{2}\right), \left(-\frac{\pi}{2}, \frac{\pi}{2}\right), \left(\frac{\pi}{2}, \frac{3\pi}{2}\right), \ldots$$

as shown in Figure 1.34(a).

b. Because $y = 1/x$ is continuous except at $x = 0$ and the sine function is continuous for all real values of x, it follows from Theorem 1.12 that

$$y = \sin\frac{1}{x}$$

is continuous at all real values except $x = 0$. At $x = 0$, the limit of $g(x)$ does not exist (see Example 5, Section 1.2). So, g is continuous on the intervals $(-\infty, 0)$ and $(0, \infty)$, as shown in Figure 1.34(b).

c. This function is similar to the function in part (b) except that the oscillations are damped by the factor x. For $x \neq 0$, $y = x \sin(1/x)$ is continuous. Note that

$$-|x| \leq x \sin\frac{1}{x} \leq |x|, \quad x \neq 0 \qquad \text{and} \qquad \lim_{x\to 0}\left(-|x|\right) = 0 = \lim_{x\to 0}|x|.$$

So, apply the Squeeze Theorem to conclude that

$$\lim_{x\to 0} h(x) = 0.$$

Because $h(0) = 0$, you know that h is continuous at $x = 0$. So, h is continuous on the entire real number line, as shown in Figure 1.34(c).



(a) f is continuous on each open interval in its domain.



(b) g is continuous on $(-\infty, 0)$ and $(0, \infty)$.



(c) h is continuous on the entire real number line.

Figure 1.34

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The Intermediate Value Theorem

Theorem 1.13 is an important theorem concerning the behavior of functions that are continuous on a closed interval.

THEOREM 1.13 Intermediate Value Theorem

If f is continuous on the closed interval $[a, b]$, $f(a) \neq f(b)$, and k is any number between $f(a)$ and $f(b)$, then there is at least one number c in $[a, b]$ such that

$$f(c) = k.$$

REMARK The Intermediate Value Theorem tells you that at least one number c exists, but it does not provide a method for finding c. Such theorems are called **existence theorems.** By referring to a text on advanced calculus, you will find that a proof of this theorem is based on a property of real numbers called *completeness*. The Intermediate Value Theorem states that for a continuous function f, if x takes on all values between a and b, then $f(x)$ must take on all values between $f(a)$ and $f(b)$.

As an example of the application of the Intermediate Value Theorem, consider a person's height. A person is 5 feet tall on their thirteenth birthday and 5 feet 2 inches tall on their fourteenth birthday. Then, for any height h between 5 feet and 5 feet 2 inches, there must have been a time t when their height was exactly h. This seems reasonable because human growth is continuous and a person's height does not abruptly change from one value to another.

The Intermediate Value Theorem guarantees the existence of *at least one* number c in the closed interval $[a, b]$. There may, of course, be more than one number c such that

$$f(c) = k$$

as shown in Figure 1.35. A function that is not continuous does not necessarily exhibit the intermediate value property. For example, the graph of the function shown in Figure 1.36 jumps over the horizontal line

$$y = k$$

and for this function there is no value of c in $[a, b]$ such that $f(c) = k$.



f is continuous on $[a, b]$.
[There exist three c's such that $f(c) = k$.]
Figure 1.35



f is not continuous on $[a, b]$.
[There are no c's such that $f(c) = k$.]
Figure 1.36

The Intermediate Value Theorem often can be used to locate the zeros of a function that is continuous on a closed interval. Specifically, if f is continuous on $[a, b]$ and $f(a)$ and $f(b)$ differ in sign, then the Intermediate Value Theorem guarantees the existence of at least one zero of f in the closed interval $[a, b]$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 8 An Application of the Intermediate Value Theorem

Use the Intermediate Value Theorem to show that the polynomial function

$$f(x) = x^3 + 2x - 1$$

has a zero in the interval $[0, 1]$.

Solution Note that f is continuous on the closed interval $[0, 1]$. Because

$$f(0) = 0^3 + 2(0) - 1 = -1 \quad \text{and} \quad f(1) = 1^3 + 2(1) - 1 = 2$$

it follows that $f(0) < 0$ and $f(1) > 0$. So, apply the Intermediate Value Theorem to conclude that there must be some c in $[0, 1]$ such that

$$f(c) = 0 \qquad f \text{ has a zero in the closed interval } [0, 1].$$

as shown in Figure 1.37.



f is continuous on $[0, 1]$ with $f(0) < 0$ and $f(1) > 0$.
Figure 1.37

The **bisection method** for approximating the real zeros of a continuous function is similar to the method used in Example 8. If you know that a zero exists in the closed interval $[a, b]$, then the zero must lie in the interval $[a, (a + b)/2]$ or $[(a + b)/2, b]$. From the sign of $f([a + b]/2)$, you can determine which interval contains the zero. By repeatedly bisecting the interval, you can "close in" on the zero of the function.

TECHNOLOGY You can use the *root* or *zero* feature of a graphing utility to approximate the real zeros of a continuous function. Using this feature, the zero of the function in Example 8, $f(x) = x^3 + 2x - 1$, is approximately 0.453, as shown in the figure.



Zero of $f(x) = x^3 + 2x - 1$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

1.4 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe the three conditions that are met when a function is continuous at a point.
2. What is the value of c?
   $\lim_{x \to c^+} 2\sqrt{x+1} = 0$
3. Determine whether $\lim_{x \to 3} f(x)$ exists. Explain.
   $\lim_{x \to 3^-} f(x) = 1$ and $\lim_{x \to 3^+} f(x) = 1$
4. Explain the Intermediate Value Theorem.

Limits and Continuity **In Exercises 5–10, use the graph to determine each limit, and discuss the continuity of the function.**

(a) $\lim_{x \to c^+} f(x)$ (b) $\lim_{x \to c^-} f(x)$ (c) $\lim_{x \to c} f(x)$

5.



6.



7.



8.



9.



10.



Finding a Limit **In Exercises 11–34, find the limit (if it exists). If it does not exist, explain why.**

11. $\lim_{x \to 8^+} \frac{1}{x+8}$
12. $\lim_{x \to 3^+} \frac{2}{x+3}$
13. $\lim_{x \to 5^+} \frac{x-5}{x^2-25}$
14. $\lim_{x \to 4^+} \frac{4-x}{x^2-16}$
15. $\lim_{x \to 1^-} \frac{x^2-2x+1}{x-1}$
16. $\lim_{x \to -3^+} \frac{x+3}{x^2+7x+12}$
17. $\lim_{x \to -3^-} \frac{x}{\sqrt{x^2-9}}$
18. $\lim_{x \to 4^-} \frac{\sqrt{x}-2}{x-4}$
19. $\lim_{x \to 0^-} \frac{|x|}{x}$
20. $\lim_{x \to 10^+} \frac{|x-10|}{x-10}$
21. $\lim_{x \to 1^-} \csc \frac{\pi x}{2}$
22. $\lim_{x \to 3/2^+} \cos \frac{\pi x}{3}$
23. $\lim_{x \to \pi} \cot x$
24. $\lim_{x \to \pi/2} \sec x$
25. $\lim_{x \to 4^-} (5[\![x]\!] - 7)$
26. $\lim_{x \to 2^+} (2x - [\![x]\!])$
27. $\lim_{x \to -1} \left(\left[\!\left[\frac{x}{3} \right]\!\right] + 3 \right)$
28. $\lim_{x \to 1} \left(1 - \left[\!\left[-\frac{x}{2} \right]\!\right] \right)$
29. $\lim_{\Delta x \to 0^-} \frac{\frac{1}{x+\Delta x} - \frac{1}{x}}{\Delta x}$
30. $\lim_{\Delta x \to 0^+} \frac{(x+\Delta x)^2 + x + \Delta x - (x^2+x)}{\Delta x}$
31. $\lim_{x \to 3^-} f(x)$, where $f(x) = \begin{cases} \frac{x+2}{2}, & x \le 3 \\ \frac{12-2x}{3}, & x > 3 \end{cases}$
32. $\lim_{x \to 3} f(x)$, where $f(x) = \begin{cases} x^2 - 4x + 6, & x < 3 \\ -x^2 + 4x - 2, & x \ge 3 \end{cases}$
33. $\lim_{x \to 1} f(x)$, where $f(x) = \begin{cases} x^3 + 1, & x < 1 \\ x + 1, & x \ge 1 \end{cases}$
34. $\lim_{x \to 1^+} f(x)$, where $f(x) = \begin{cases} x, & x \le 1 \\ 1 - x, & x > 1 \end{cases}$

Continuity of a Function **In Exercises 35–38, discuss the continuity of the function.**

35. $f(x) = \frac{1}{x^2-4}$



36. $f(x) = \frac{x^2-1}{x+1}$



37. $f(x) = \frac{1}{2}[\![x]\!] + x$



38. $f(x) = \begin{cases} x, & x < 1 \\ 2, & x = 1 \\ 2x - 1, & x > 1 \end{cases}$



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Continuity on a Closed Interval

In Exercises 39–42, discuss the continuity of the function on the closed interval.

Function	Interval
39. $g(x) = \sqrt{49 - x^2}$	$[-7, 7]$
40. $f(t) = 3 - \sqrt{9 - t^2}$	$[-3, 3]$
41. $f(x) = \begin{cases} 3 - x, & x \le 0 \\ 3 + \frac{1}{2}x, & x > 0 \end{cases}$	$[-1, 4]$
42. $g(x) = \dfrac{1}{x^2 - 4}$	$[-1, 2]$

Removable and Nonremovable Discontinuities

In Exercises 43–68, find the x-values (if any) at which f is not continuous. State whether the discontinuities are removable or nonremovable.

43. $f(x) = \dfrac{6}{x}$

44. $f(x) = \dfrac{4}{x - 6}$

45. $f(x) = x^2 - 9$

46. $f(x) = x^2 - 4x + 4$

47. $f(x) = \dfrac{1}{4 - x^2}$

48. $f(x) = \dfrac{1}{x^2 + 1}$

49. $f(x) = 3x - \cos x$

50. $f(x) = \sin x - 8x$

51. $f(x) = \dfrac{x}{x^2 - x}$

52. $f(x) = \dfrac{x}{x^2 - 4}$

53. $f(x) = \dfrac{x}{x^2 + 1}$

54. $f(x) = \dfrac{x - 5}{x^2 - 25}$

55. $f(x) = \dfrac{x + 2}{x^2 - 3x - 10}$

56. $f(x) = \dfrac{x + 2}{x^2 - x - 6}$

57. $f(x) = \dfrac{|x + 7|}{x + 7}$

58. $f(x) = \dfrac{2|x - 3|}{x - 3}$

59. $f(x) = \csc 2x$

60. $f(x) = \tan \dfrac{\pi x}{2}$

61. $f(x) = [\![x - 8]\!]$

62. $f(x) = 5 - [\![x]\!]$

63. $f(x) = \begin{cases} x, & x \le 1 \\ x^2, & x > 1 \end{cases}$

64. $f(x) = \begin{cases} -2x + 3, & x < 1 \\ x^2, & x \ge 1 \end{cases}$

65. $f(x) = \begin{cases} \frac{1}{2}x + 1, & x \le 2 \\ 3 - x, & x > 2 \end{cases}$

66. $f(x) = \begin{cases} -2x, & x \le 2 \\ x^2 - 4x + 1, & x > 2 \end{cases}$

67. $f(x) = \begin{cases} \tan \dfrac{\pi x}{4}, & |x| < 1 \\ x, & |x| \ge 1 \end{cases}$

68. $f(x) = \begin{cases} \csc \dfrac{\pi x}{6}, & |x - 3| \le 2 \\ 2, & |x - 3| > 2 \end{cases}$

Making a Function Continuous

In Exercises 69–74, find the constant a, or the constants a and b, such that the function is continuous on the entire real number line.

69. $f(x) = \begin{cases} 3x^2, & x \ge 1 \\ ax - 4, & x < 1 \end{cases}$

70. $f(x) = \begin{cases} 3x^3, & x \le 1 \\ ax + 5, & x > 1 \end{cases}$

71. $f(x) = \begin{cases} x^3, & x \le 2 \\ ax^2, & x > 2 \end{cases}$

72. $g(x) = \begin{cases} \dfrac{4 \sin x}{x}, & x < 0 \\ a - 2x, & x \ge 0 \end{cases}$

73. $f(x) = \begin{cases} 2, & x \le -1 \\ ax + b, & -1 < x < 3 \\ -2, & x \ge 3 \end{cases}$

74. $g(x) = \begin{cases} \dfrac{x^2 - a^2}{x - a}, & x \ne a \\ 8, & x = a \end{cases}$

Continuity of a Composite Function

In Exercises 75–80, discuss the continuity of the composite function $h(x) = f(g(x))$.

75. $f(x) = x^2$, $g(x) = x - 1$

76. $f(x) = 5x + 1$, $g(x) = x^3$

77. $f(x) = \dfrac{1}{x - 6}$, $g(x) = x^2 + 5$

78. $f(x) = \dfrac{1}{\sqrt{x}}$, $g(x) = x - 1$

79. $f(x) = \tan x$, $g(x) = \dfrac{x}{2}$

80. $f(x) = \sin x$, $g(x) = x^2$

Finding Discontinuities

In Exercises 81–84, use a graphing utility to graph the function. Use the graph to determine any x-values at which the function is not continuous.

81. $f(x) = [\![x]\!] - x$

82. $h(x) = \dfrac{1}{x^2 + 2x - 15}$

83. $g(x) = \begin{cases} x^2 - 3x, & x > 4 \\ 2x - 5, & x \le 4 \end{cases}$

84. $f(x) = \begin{cases} \dfrac{\cos x - 1}{x}, & x < 0 \\ 5x, & x \ge 0 \end{cases}$

Testing for Continuity

In Exercises 85–92, describe the interval(s) on which the function is continuous.

85. $f(x) = \dfrac{x}{x^2 + x + 2}$

86. $f(x) = \dfrac{x + 1}{\sqrt{x}}$

87. $f(x) = 3 - \sqrt{x}$

88. $f(x) = x\sqrt{x + 3}$

89. $f(x) = \sec \dfrac{\pi x}{4}$

90. $f(x) = \cos \dfrac{1}{x}$

91. $f(x) = \begin{cases} \dfrac{x^2 - 1}{x - 1}, & x \ne 1 \\ 2, & x = 1 \end{cases}$

92. $f(x) = \begin{cases} 2x - 4, & x \ne 3 \\ 1, & x = 3 \end{cases}$

Existence of a Zero

In Exercises 93–96, explain why the function has at least one zero in the given interval.

Function	Interval
93. $f(x) = \frac{1}{12}x^4 - x^3 + 4$	$[1, 2]$
94. $f(x) = x^3 + 5x - 3$	$[0, 1]$
95. $f(x) = x^2 - 2 - \cos x$	$[0, \pi]$
96. $f(x) = -\dfrac{5}{x} + \tan \dfrac{\pi x}{10}$	$[1, 4]$

Existence of Multiple Zeros

In Exercises 97 and 98, explain why the function has at least two zeros in the interval $[1, 5]$.

97. $f(x) = (x - 3)^2 - 2$

98. $f(x) = 2 \cos x$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Using the Intermediate Value Theorem **In Exercises 99–104, use the Intermediate Value Theorem and a graphing utility to approximate the zero of the function in the interval $[0, 1]$. Repeatedly "zoom in" on the graph of the function to approximate the zero accurate to two decimal places. Use the *zero* or *root* feature of the graphing utility to approximate the zero accurate to four decimal places.**

99. $f(x) = x^3 + x - 1$

100. $f(x) = x^4 - x^2 + 3x - 1$

101. $g(t) = 2\cos t - 3t$

102. $h(\theta) = \tan\theta + 3\theta - 4$

103. $f(x) = \sqrt{x^2 + 17x + 19} - 6$

104. $f(x) = \sqrt{x^4 + 39x + 13} - 4$

Using the Intermediate Value Theorem **In Exercises 105–110, verify that the Intermediate Value Theorem applies to the indicated interval and find the value of c guaranteed by the theorem.**

105. $f(x) = x^2 + x - 1, \quad [0, 5], \quad f(c) = 11$

106. $f(x) = x^2 - 6x + 8, \quad [0, 3], \quad f(c) = 0$

107. $f(x) = \sqrt{x + 7} - 2, \quad [0, 5], \quad f(c) = 1$

108. $f(x) = \sqrt[3]{x} + 8, \quad [-9, -6], \quad f(c) = 6$

109. $f(x) = \dfrac{x - x^3}{x - 4}, \quad [1, 3], \quad f(c) = 3$

110. $f(x) = \dfrac{x^2 + x}{x - 1}, \quad \left[\dfrac{5}{2}, 4\right], \quad f(c) = 6$

Exploring Concepts

111. (a) Write a function f that is continuous on (a, b) but not continuous on $[a, b]$.

(b) Write a function g that is defined and nonzero on $[a, b]$, where $g(a)$ and $g(b)$ have opposite signs. Is g continuous on $[a, b]$? Explain.

112. Sketch the graph of any function f such that

$$\lim_{x\to 3^+} f(x) = 1 \quad \text{and} \quad \lim_{x\to 3^-} f(x) = 0.$$

Is the function continuous at $x = 3$? Explain.

113. When the functions f and g are continuous for all real x, is $f + g$ always continuous for all real x? Is f/g always continuous for all real x? If either is not continuous, give an example to verify your conclusion.

114. Describe the difference between a discontinuity that is removable and a discontinuity that is nonremovable. Then give an example of a function that satisfies each description.

(a) A function with a nonremovable discontinuity at $x = 4$

(b) A function with a removable discontinuity at $x = -4$

(c) A function that has both of the characteristics described in parts (a) and (b)

True or False? **In Exercises 115–120, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

115. If $\lim_{x\to c} f(x) = L$ and $f(c) = L$, then f is continuous at c.

116. If $f(x) = g(x)$ for $x \neq c$ and $f(c) \neq g(c)$, then either f or g is not continuous at c.

117. The Intermediate Value Theorem guarantees that $f(a)$ and $f(b)$ differ in sign when a continuous function f has at least one zero on $[a, b]$.

118. The limit of the greatest integer function as x approaches 0 from the left is -1.

119. A rational function can have infinitely many x-values at which it is not continuous.

120. The function $f(x) = \dfrac{|x - 1|}{x - 1}$ is continuous on $(-\infty, \infty)$.

121. Think About It Describe how the functions

$$f(x) = 3 + [\![x]\!] \quad \text{and} \quad g(x) = 3 - [\![-x]\!]$$

differ.

122. HOW DO YOU SEE IT? Every day you dissolve 28 ounces of chlorine in a swimming pool. The graph shows the amount of chlorine $f(t)$ in the pool after t days. Estimate and interpret $\lim_{t\to 4^-} f(t)$ and $\lim_{t\to 4^+} f(t)$.



123. Parking Garage A parking garage charges \$3 to park up to one hour and \$1 for each additional hour or fraction thereof, up to a daily maximum of \$15.

(a) Write a formula for the parking charge C (in dollars) in terms of the number of hours parked t.

(b) Sketch the graph of the parking charge function and discuss its continuity.

124. Inventory Management The number of units in inventory in a small company is given by

$$N(t) = 25\left(2\left[\!\left[\frac{t + 2}{2}\right]\!\right] - t\right)$$

where t is the time in months. Sketch the graph of this function and discuss its continuity. How often must this company replenish its inventory?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

125. Déjà Vu At 8:00 A.M. on Saturday, a person begins running up the side of a mountain to a weekend campsite (see figure). At 8:00 A.M. on Sunday, the person runs back down the mountain. It takes 20 minutes to run up but only 10 minutes to run down. Prove that at some point on the way down, the person passed the same place at exactly the same time on Saturday. [*Hint:* Let $s(t)$ and $r(t)$ be the position functions for the runs up and down, and apply the Intermediate Value Theorem to the function $f(t) = s(t) - r(t)$.]



Not drawn to scale

Saturday 8:00 A.M. Sunday 8:00 A.M.

126. Volume Use the Intermediate Value Theorem to show that for all spheres with radii in the interval $[5, 8]$, there is one with a volume of 1500 cubic centimeters.

127. Proof Prove that if f is continuous and has no zeros on $[a, b]$, then either

$f(x) > 0$ for all x in $[a, b]$ or $f(x) < 0$ for all x in $[a, b]$.

128. Dirichlet Function Show that the Dirichlet function

$$f(x) = \begin{cases} 0, & \text{if } x \text{ is rational} \\ 1, & \text{if } x \text{ is irrational} \end{cases}$$

is not continuous at any real number.

129. Continuity of a Function Show that the function

$$f(x) = \begin{cases} 0, & \text{if } x \text{ is rational} \\ kx, & \text{if } x \text{ is irrational} \end{cases}$$

is continuous only at $x = 0$. (Assume that k is any nonzero real number.)

130. Signum Function The **signum function** is defined by

$$\operatorname{sgn}(x) = \begin{cases} -1, & x < 0 \\ 0, & x = 0 \\ 1, & x > 0 \end{cases}.$$

Sketch a graph of $\operatorname{sgn}(x)$ and find each limit (if possible).

(a) $\lim_{x \to 0^-} \operatorname{sgn}(x)$ (b) $\lim_{x \to 0^+} \operatorname{sgn}(x)$ (c) $\lim_{x \to 0} \operatorname{sgn}(x)$

131. Frequency The table lists the frequency F (in Hertz) of a musical note at various times t (in seconds).

t	0	1	2	3	4	5
F	436	444	434	446	433	444

(a) Plot the data and connect the points with a curve.

(b) Does there appear to be a limiting frequency of the note? Explain.

132. Creating Models A swimmer crosses a pool of width b by swimming straight from $(0, 0)$ to $(2b, b)$. (See figure.)



(a) Let f be a function defined as the y-coordinate of the point on the long side of the pool that is nearest the swimmer at any time during the swimmer's crossing of the pool. Determine the function f and sketch its graph. Is f continuous? Explain.

(b) Let g be the minimum distance between the swimmer and the long sides of the pool. Determine the function g and sketch its graph. Is g continuous? Explain.

133. Making Functions Continuous Find all values of c such that each function is continuous on $(-\infty, \infty)$.

(a) $f(x) = \begin{cases} x^3, & x \le c \\ 3x^2 - 2x, & x > c \end{cases}$

(b) $g(x) = \begin{cases} 1 - x^2, & x \le c \\ x, & x > c \end{cases}$

134. Making a Function Continuous Let

$$f(x) = \frac{\sqrt{x + c^2} - c}{x}, \quad c > 0.$$

What is the domain of f? How can you define f at $x = 0$ for f to be continuous there?

135. Proof Prove that for any real number y there exists x in $(-\pi/2, \pi/2)$ such that $\tan x = y$.

136. Proof Prove that if

$$\lim_{\Delta x \to 0} f(c + \Delta x) = f(c)$$

then f is continuous at c.

137. Continuity of a Function Discuss the continuity of the function $h(x) = x[\![x]\!]$.

138. Proof

(a) Let $f_1(x)$ and $f_2(x)$ be continuous on the closed interval $[a, b]$. When $f_1(a) < f_2(a)$ and $f_1(b) > f_2(b)$, prove that there exists c between a and b such that $f_1(c) = f_2(c)$.

(b) Show that there exists c in $\left[0, \frac{\pi}{2}\right]$ such that $\cos x = x$. Use a graphing utility to approximate c to three decimal places.

PUTNAM EXAM CHALLENGE

139. Prove or disprove: If x and y are real numbers with $y \ge 0$ and $y(y + 1) \le (x + 1)^2$, then $y(y - 1) \le x^2$.

140. Determine all polynomials $P(x)$ such that

$$P(x^2 + 1) = (P(x))^2 + 1 \text{ and } P(0) = 0.$$

These problems were composed by the Committee on the Putnam Prize Competition. © The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

1.5 Infinite Limits

GO DIGITAL

- **Determine infinite limits from the left and from the right.**
- **Find and sketch the vertical asymptotes of the graph of a function.**



$f(x)$ increases and decreases without bound as x approaches 2.
Figure 1.38

Infinite Limits

Consider the function $f(x) = 3/(x - 2)$. From Figure 1.38 and the table, notice that $f(x)$ *decreases without bound* as x approaches 2 from the left, and $f(x)$ *increases without bound* as x approaches 2 from the right.

x approaches 2 from the left. | x approaches 2 from the right.

x	1.5	1.9	1.99	1.999	2	2.001	2.01	2.1	2.5
$f(x)$	−6	−30	−300	−3000	?	3000	300	30	6

$f(x)$ decreases without bound. | $f(x)$ increases without bound.

This behavior is denoted as

$$\lim_{x \to 2^-} \frac{3}{x - 2} = -\infty$$ $f(x)$ decreases without bound as x approaches 2 from the left.

and

$$\lim_{x \to 2^+} \frac{3}{x - 2} = \infty.$$ $f(x)$ increases without bound as x approaches 2 from the right.

The symbols ∞ and $-\infty$ refer to positive infinity and negative infinity, respectively. These symbols do not represent real numbers. They are convenient symbols used to describe unbounded conditions more concisely. A limit in which $f(x)$ increases or decreases without bound as x approaches c is called an **infinite limit.**



Infinite limits
Figure 1.39

Definition of Infinite Limits

Let f be a function that is defined at every real number in some open interval containing c (except possibly at c itself). The statement

$$\lim_{x \to c} f(x) = \infty$$

means that for each $M > 0$ there exists a $\delta > 0$ such that $f(x) > M$ whenever $0 < |x - c| < \delta$ (see Figure 1.39). Similarly, the statement

$$\lim_{x \to c} f(x) = -\infty$$

means that for each $N < 0$ there exists a $\delta > 0$ such that $f(x) < N$ whenever $0 < |x - c| < \delta$. To define the **infinite limit from the left,** replace $0 < |x - c| < \delta$ by $c - \delta < x < c$. To define the **infinite limit from the right,** replace $0 < |x - c| < \delta$ by $c < x < c + \delta$.

Be sure you understand that the equal sign in the statement $\lim f(x) = \infty$ does not mean that the limit exists! On the contrary, it tells you how the limit **fails to exist** by denoting the unbounded behavior of $f(x)$ as x approaches c.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploration

Use a graphing utility to graph each function. For each function, analytically find the single real number c that is not in the domain. Then graphically estimate the limit (if it exists) of $f(x)$ as x approaches c from the left and from the right.

a. $f(x) = \dfrac{3}{x - 4}$

b. $f(x) = \dfrac{1}{2 - x}$

c. $f(x) = \dfrac{2}{(x - 3)^2}$

d. $f(x) = \dfrac{-3}{(x + 2)^2}$

EXAMPLE 1 Determining Infinite Limits from a Graph

Determine the limit of each function shown in Figure 1.40 as x approaches 1 from the left and from the right.



(a) **(b)**

Each graph has an asymptote at $x = 1$.

Figure 1.40

Solution

a. When x approaches 1 from the left or the right, $(x - 1)^2$ is a small positive number. Thus, the quotient $1/(x - 1)^2$ is a large positive number, and $f(x)$ approaches infinity from each side of $x = 1$. So, you can conclude that

$$\lim_{x \to 1} \frac{1}{(x - 1)^2} = \infty.$$ Limit from each side is infinity.

Figure 1.40(a) supports this analysis.

b. When x approaches 1 from the left, $x - 1$ is a small negative number. Thus, the quotient $-1/(x - 1)$ is a large positive number, and $f(x)$ approaches infinity from the left of $x = 1$. So, you can conclude that

$$\lim_{x \to 1^-} \frac{-1}{x - 1} = \infty.$$ Limit from the left side is infinity.

When x approaches 1 from the right, $x - 1$ is a small positive number. Thus, the quotient $-1/(x - 1)$ is a large negative number, and $f(x)$ approaches negative infinity from the right of $x = 1$. So, you can conclude that

$$\lim_{x \to 1^+} \frac{-1}{x - 1} = -\infty.$$ Limit from the right side is negative infinity.

Figure 1.40(b) supports this analysis. ■

TECHNOLOGY Remember that you can use a numerical approach to analyze a limit. For instance, you can use a graphing utility to create a table of values to analyze the limit in Example 1(a), as shown in the figure below.

Enter x-values using *ask* mode.

X	Y1
.9	100
.99	10000
.999	1E6
1	ERROR
1.001	1E6
1.01	10000
1.1	100

X=1

As x approaches 1 from the left, $f(x)$ increases without bound.

As x approaches 1 from the right, $f(x)$ increases without bound.

Use a graphing utility to make a table of values to analyze the limit in Example 1(b).

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Vertical Asymptotes

If it were possible to extend the graphs in Figure 1.40 toward positive and negative infinity, you would see that each graph becomes arbitrarily close to the vertical line $x = 1$. This line is a **vertical asymptote** of the graph of f. (You will study other types of asymptotes in Sections 3.5 and 3.6.)

REMARK If the graph of a function f has a vertical asymptote at $x = c$, then f is *not continuous* at c.

Definition of Vertical Asymptote

If $f(x)$ approaches infinity (or negative infinity) as x approaches c from the right or the left, then the line $x = c$ is a **vertical asymptote** of the graph of f.

In Example 1, note that each function is a *quotient* and that the vertical asymptote occurs at a number at which the denominator is 0 (and the numerator is not 0). The next theorem generalizes this observation.

THEOREM 1.14 Vertical Asymptotes

Let f and g be continuous on an open interval containing c. If $f(c) \neq 0$, $g(c) = 0$, and there exists an open interval containing c such that $g(x) \neq 0$ for all $x \neq c$ in the interval, then the graph of the function

$$h(x) = \frac{f(x)}{g(x)}$$

has a vertical asymptote at $x = c$.

A proof of this theorem is given in Appendix A.



(a)



(b)



(c)

Functions with vertical asymptotes

Figure 1.41

EXAMPLE 2 Finding Vertical Asymptotes

See LarsonCalculus.com for an interactive version of this type of example.

a. When $x = -1$, the denominator of

$$h(x) = \frac{1}{2(x + 1)}$$

is 0 and the numerator is not 0. So, by Theorem 1.14, you can conclude that $x = -1$ is a vertical asymptote, as shown in Figure 1.41(a).

b. By factoring the denominator as

$$h(x) = \frac{x^2 + 1}{x^2 - 1} = \frac{x^2 + 1}{(x - 1)(x + 1)}$$ Factor difference of two squares

you can determine that the denominator is 0 at $x = -1$ and $x = 1$. Also, because the numerator is not 0 at these two points, you can apply Theorem 1.14 to conclude that the graph of f has two vertical asymptotes, as shown in Figure 1.41(b).

c. By writing the cotangent function in the form

$$h(x) = \cot x = \frac{\cos x}{\sin x}$$ Quotient identity

you can apply Theorem 1.14 to conclude that vertical asymptotes occur at all values of x such that $\sin x = 0$ and $\cos x \neq 0$, as shown in Figure 1.41(c). So, the graph of this function has infinitely many vertical asymptotes. These asymptotes occur at $x = n\pi$, where n is an integer.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Theorem 1.14 requires that the value of the numerator at $x = c$ be nonzero. When both the numerator and the denominator are 0 at $x = c$, you obtain the *indeterminate form* $0/0$, and you cannot determine the limit behavior at $x = c$ without further investigation, as illustrated in Example 3.

EXAMPLE 3 A Rational Function with Common Factors

Determine all vertical asymptotes of the graph of

$$h(x) = \frac{x^2 + 2x - 8}{x^2 - 4}.$$

Solution Begin by simplifying the expression, as shown.

$$\begin{aligned} h(x) &= \frac{x^2 + 2x - 8}{x^2 - 4} && \text{Write original function.} \\ &= \frac{(x + 4)(x - 2)}{(x + 2)(x - 2)} && \text{Factor and divide out common factor.} \\ &= \frac{x + 4}{x + 2}, \quad x \neq 2 && \text{Simplify.} \end{aligned}$$



$h(x)$ increases and decreases without bound as x approaches -2.

Figure 1.42

At all x-values other than $x = 2$, the graph of h coincides with the graph of $k(x) = (x + 4)/(x + 2)$. So, you can apply Theorem 1.14 to k to conclude that there is a vertical asymptote at $x = -2$, as shown in Figure 1.42. From the graph, you can see that

$$\lim_{x \to -2^-} \frac{x^2 + 2x - 8}{x^2 - 4} = -\infty \quad \text{and} \quad \lim_{x \to -2^+} \frac{x^2 + 2x - 8}{x^2 - 4} = \infty.$$

Note that $x = 2$ is *not* a vertical asymptote.

EXAMPLE 4 Determining Infinite Limits

Find each limit.

$$\lim_{x \to 1^-} \frac{x^2 - 3x}{x - 1} \quad \text{and} \quad \lim_{x \to 1^+} \frac{x^2 - 3x}{x - 1}$$

Solution Because the denominator is 0 when $x = 1$ (and the numerator is not 0), you know that the graph of

$$h(x) = \frac{x^2 - 3x}{x - 1}$$

has a vertical asymptote at $x = 1$. This means that each of the given limits is either ∞ or $-\infty$. You can determine the result by analyzing h at values of x close to 1 or by using a graphing utility. From the graph of h shown in Figure 1.43, you can see that the graph approaches ∞ from the left of $x = 1$ and approaches $-\infty$ from the right of $x = 1$. So, you can conclude that

$$\lim_{x \to 1^-} \frac{x^2 - 3x}{x - 1} = \infty \qquad \text{The limit from the left is infinity.}$$

and

$$\lim_{x \to 1^+} \frac{x^2 - 3x}{x - 1} = -\infty. \qquad \text{The limit from the right is negative infinity.}$$



The graph of h has a vertical asymptote at $x = 1$.

Figure 1.43

TECHNOLOGY PITFALL When using a graphing utility, be careful to interpret correctly the graph of a function with a vertical asymptote—some graphing utilities have difficulty drawing this type of graph.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

THEOREM 1.15 Properties of Infinite Limits

Let c and L be real numbers, and let f and g be functions such that

$$\lim_{x\to c} f(x) = \infty \quad \text{and} \quad \lim_{x\to c} g(x) = L.$$

1. Sum: $\lim_{x\to c} [f(x) + g(x)] = \infty$
2. Difference: $\lim_{x\to c} [f(x) - g(x)] = \infty$
3. Product: $\lim_{x\to c} [f(x)g(x)] = \infty, \quad L > 0$

   $\lim_{x\to c} [f(x)g(x)] = -\infty, \quad L < 0$
4. Quotient: $\lim_{x\to c} \frac{g(x)}{f(x)} = 0$

Similar properties hold for one-sided limits and for functions for which the limit of $f(x)$ as x approaches c is $-\infty$ [see Example 5(d)].

REMARK Be sure you understand that Property 3 of Theorem 1.15 is not valid when $\lim_{x\to c} g(x) = 0$.

Proof Here is a proof of the sum property. (The proofs of the remaining properties are left as an exercise [see Exercise 78].) To show that the limit of $f(x) + g(x)$ is infinite, choose $M > 0$. You then need to find $\delta > 0$ such that $[f(x) + g(x)] > M$ whenever $0 < |x - c| < \delta$. For simplicity's sake, you can assume L is positive. Let $M_1 = M + 1$. Because the limit of $f(x)$ is infinite, there exists δ_1 such that $f(x) > M_1$ whenever $0 < |x - c| < \delta_1$. Also, because the limit of $g(x)$ is L, there exists δ_2 such that $|g(x) - L| < 1$ whenever $0 < |x - c| < \delta_2$. By letting δ be the smaller of δ_1 and δ_2, you can conclude that $0 < |x - c| < \delta$ implies $f(x) > M + 1$ and $|g(x) - L| < 1$. The second of these two inequalities implies that $g(x) > L - 1$, and adding this to the first inequality, you can write

$$f(x) + g(x) > (M + 1) + (L - 1) = M + L > M.$$

So, you can conclude that

$$\lim_{x\to c} [f(x) + g(x)] = \infty.$$

EXAMPLE 5 Determining Limits

a. Because $\lim_{x\to 0} 1 = 1$ and $\lim_{x\to 0} \frac{1}{x^2} = \infty$, you can write

$$\lim_{x\to 0} \left(1 + \frac{1}{x^2}\right) = \infty.$$ Property 1, Theorem 1.15

b. Because $\lim_{x\to 1^-} (x^2 + 1) = 2$ and $\lim_{x\to 1^-} (\cot \pi x) = -\infty$, you can write

$$\lim_{x\to 1^-} \frac{x^2 + 1}{\cot \pi x} = 0.$$ Property 4, Theorem 1.15

c. Because $\lim_{x\to 0^+} 3 = 3$ and $\lim_{x\to 0^+} \cot x = \infty$, you can write

$$\lim_{x\to 0^+} 3 \cot x = \infty.$$ Property 3, Theorem 1.15

d. Because $\lim_{x\to 0^-} x^2 = 0$ and $\lim_{x\to 0^-} \frac{1}{x} = -\infty$, you can write

$$\lim_{x\to 0^-} \left(x^2 + \frac{1}{x}\right) = -\infty.$$ Property 1, Theorem 1.15

REMARK Note that the solution to Example 5(d) uses Property 1 from Theorem 1.15 for which the limit of $f(x)$ as x approaches c is $-\infty$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

1.5 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe the meaning of an infinite limit. What does ∞ represent?
2. Describe what is meant by a vertical asymptote of a graph.

Determining Infinite Limits from a Graph In Exercises 3–6, determine whether $f(x)$ approaches ∞ or $-\infty$ as x approaches -2 from the left and from the right.

3. $f(x) = 2\left|\dfrac{x}{x^2-4}\right|$



4. $f(x) = \dfrac{1}{x+2}$



5. $f(x) = \tan\dfrac{\pi x}{4}$



6. $f(x) = \sec\dfrac{\pi x}{4}$



Determining Infinite Limits In Exercises 7–10, determine whether $f(x)$ approaches ∞ or $-\infty$ as x approaches 4 from the left and from the right.

7. $f(x) = \dfrac{1}{x-4}$
8. $f(x) = \dfrac{-1}{x-4}$
9. $f(x) = \dfrac{1}{(x-4)^2}$
10. $f(x) = \dfrac{-1}{(x-4)^2}$

Numerical and Graphical Analysis In Exercises 11–18, create a table of values for the function and use the result to determine whether $f(x)$ approaches ∞ or $-\infty$ as x approaches -3 from the left and from the right. Use a graphing utility to graph the function to confirm your answer.

11. $f(x) = \dfrac{1}{x^2-9}$
12. $f(x) = \dfrac{x}{x^2-9}$
13. $f(x) = \dfrac{x^2}{x^2-9}$
14. $f(x) = -\dfrac{1}{3+x}$
15. $f(x) = \cot\dfrac{\pi x}{3}$
16. $f(x) = \tan\dfrac{\pi x}{6}$
17. $f(x) = \sec\dfrac{\pi x}{6}$
18. $f(x) = \csc\dfrac{\pi x}{3}$

Finding Vertical Asymptotes In Exercises 19–34, find the vertical asymptotes (if any) of the graph of the function.

19. $f(x) = \dfrac{1}{x^2}$
20. $f(x) = \dfrac{2}{(x-3)^3}$
21. $f(x) = \dfrac{x^2}{x^2-4}$
22. $f(x) = \dfrac{3x}{x^2+9}$
23. $g(t) = \dfrac{t-1}{t^2+1}$
24. $h(s) = \dfrac{3s+4}{s^2-16}$
25. $f(x) = \dfrac{3}{x^2+x-2}$
26. $g(x) = \dfrac{x^2-5x+25}{x^3+125}$
27. $f(x) = \dfrac{x^2-2x-15}{x^3-5x^2+x-5}$
28. $h(t) = \dfrac{t^2-2t}{t^4-16}$
29. $f(x) = \dfrac{4x^2+4x-24}{x^4-2x^3-9x^2+18x}$
30. $h(x) = \dfrac{x^2-9}{x^3+3x^2-x-3}$
31. $f(x) = \csc x$
32. $f(x) = \tan \pi x$
33. $s(t) = \dfrac{t}{\sin t}$
34. $g(\theta) = \dfrac{\tan\theta}{\theta}$

Vertical Asymptote or Removable Discontinuity In Exercises 35–38, determine whether the graph of the function has a vertical asymptote or a removable discontinuity at $x = -1$. Graph the function using a graphing utility to confirm your answer.

35. $f(x) = \dfrac{x^2-1}{x+1}$
36. $f(x) = \dfrac{x^2-2x-8}{x+1}$
37. $f(x) = \dfrac{\cos(x^2-1)}{x+1}$
38. $f(x) = \dfrac{\sin(x+1)}{x+1}$

Finding a One-Sided Limit In Exercises 39–56, find the one-sided limit (if it exists).

39. $\lim\limits_{x\to -1^+} \dfrac{1}{x+1}$
40. $\lim\limits_{x\to 1^-} \dfrac{-1}{(x-1)^2}$
41. $\lim\limits_{x\to 2^+} \dfrac{x}{x-2}$
42. $\lim\limits_{x\to 2^-} \dfrac{x^2}{x^2+4}$
43. $\lim\limits_{x\to -3^-} \dfrac{x+3}{x^2+x-6}$
44. $\lim\limits_{x\to (-1/2)^+} \dfrac{6x^2+x-1}{4x^2-4x-3}$
45. $\lim\limits_{x\to 0^-} \left(1+\dfrac{1}{x}\right)$
46. $\lim\limits_{x\to 0^+} \left(6-\dfrac{1}{x^3}\right)$
47. $\lim\limits_{x\to -4^-} \left(x^2+\dfrac{2}{x+4}\right)$
48. $\lim\limits_{x\to 0^+} \left(x-\dfrac{1}{x}+3\right)$
49. $\lim\limits_{x\to 0^+} \left(\sin x+\dfrac{1}{x}\right)$
50. $\lim\limits_{x\to 3^+} \left(\dfrac{x}{3}+\cot\dfrac{\pi x}{2}\right)$
51. $\lim\limits_{x\to 0^+} \dfrac{2}{\sin x}$
52. $\lim\limits_{x\to (\pi/2)^+} \dfrac{-2}{\cos x}$
53. $\lim\limits_{x\to \pi^+} \dfrac{\sqrt{x}}{\csc x}$
54. $\lim\limits_{x\to 0^-} \dfrac{x+2}{\cot x}$
55. $\lim\limits_{x\to (1/2)^-} x \sec \pi x$
56. $\lim\limits_{x\to (1/2)^+} x^2 \tan \pi x$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding a One-Sided Limit **In Exercises 57 and 58, use a graphing utility to graph the function and determine the one-sided limit.**

57. $\lim_{x\to 1^+} \dfrac{x^2 + x + 1}{x^3 - 1}$

58. $\lim_{x\to 1^-} \dfrac{x^3 - 1}{x^2 + x + 1}$

Determining Limits **In Exercises 59 and 60, use the information to determine each limit.**

59. $\lim_{x\to c} f(x) = \infty$, $\lim_{x\to c} g(x) = -2$

(a) $\lim_{x\to c} [f(x) + g(x)]$

(b) $\lim_{x\to c} [f(x)g(x)]$

(c) $\lim_{x\to c} \dfrac{g(x)}{f(x)}$

60. $\lim_{x\to c} f(x) = -\infty$, $\lim_{x\to c} g(x) = 3$

(a) $\lim_{x\to c} [f(x) + g(x)]$

(b) $\lim_{x\to c} [f(x)g(x)]$

(c) $\lim_{x\to c} \dfrac{g(x)}{f(x)}$

Exploring Concepts

61. Write a rational function with vertical asymptotes at $x = 6$ and $x = -2$, and with a zero at $x = 3$.

62. Does the graph of every rational function have a vertical asymptote? Explain.

63. Use the graph of the function f (see figure) to sketch the graph of $g(x) = 1/f(x)$ on the interval $[-2, 3]$. To print an enlarged copy of the graph, go to *MathGraphs.com*.



64. Relativity According to the theory of relativity, the mass m of a particle depends on its velocity v. That is,

$$m = \frac{m_0}{\sqrt{1 - (v^2/c^2)}}$$

where m_0 is the mass when the particle is at rest and c is the speed of light. Find the limit of the mass as v approaches c from the left.

65. Numerical and Graphical Reasoning Use a graphing utility to complete the table for each function and graph each function to estimate the limit. What is the value of the limit when the power of x in the denominator is greater than 3?

x	1	0.5	0.2	0.1	0.01	0.001	0.0001
$f(x)$							

(a) $\lim_{x\to 0^+} \dfrac{x - \sin x}{x}$

(b) $\lim_{x\to 0^+} \dfrac{x - \sin x}{x^2}$

(c) $\lim_{x\to 0^+} \dfrac{x - \sin x}{x^3}$

(d) $\lim_{x\to 0^+} \dfrac{x - \sin x}{x^4}$

66. HOW DO YOU SEE IT? For a quantity of gas at a constant temperature, the pressure P is inversely proportional to the volume V. What is the limit of P as V approaches 0 from the right? Explain what this means in the context of the problem.



67. Rate of Change A 25-foot ladder is leaning against a house (see figure). When the base of the ladder is pulled away from the house at a rate of 2 feet per second, the top will move down the wall at a rate of

$$r = \frac{2x}{\sqrt{625 - x^2}} \text{ ft/sec}$$

where x is the distance between the base of the ladder and the house, and r is the rate in feet per second.



(a) Find the rate r when x is 15 feet.

(b) Find the limit of r as x approaches 25 from the left.

68. Average Speed

On a trip of d miles to another city, a truck driver's average speed was x miles per hour. On the return trip, the average speed was y miles per hour. The average speed for the round trip was 50 miles per hour.

(a) Verify that

$$y = \frac{25x}{x - 25}.$$

What is the domain?

(b) Create a table that shows corresponding values of y (in miles per hour) for x values of 30, 40, 50, and 60 miles per hour. Are the values of y different than you expected? Explain.

(c) Find the limit of y as x approaches 25 from the right and interpret its meaning.

69. Limit of a Sum A sum S is inversely proportional to $1 - r$, where $0 < |r| < 1$. Find the limit of S as $r \to 1^-$.

Jetta Productions Inc/Getty Images

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

70. Limit of a Quantity A quantity Q varies inversely as the square root of $t - 4$. Find the limit of Q as $t \to 4^+$.

71. Numerical and Graphical Analysis Consider the shaded region outside the sector of a circle of radius 10 meters and inside a right triangle (see figure).



(a) Write the area A of the region as a function of θ. Determine the domain of the function.

(b) Use a graphing utility to complete the table and graph the function over the appropriate domain.

θ	0.3	0.6	0.9	1.2	1.5
$f(\theta)$					

(c) Find the limit of A as θ approaches $\pi/2$ from the left.

72. Numerical and Graphical Reasoning A crossed belt connects a 20-centimeter pulley (10-cm radius) on an electric motor with a 40-centimeter pulley (20-cm radius) on a saw arbor (see figure). The electric motor runs at 1700 revolutions per minute.



(a) Determine the number of revolutions per minute of the saw.

(b) How does crossing the belt affect the saw in relation to the motor?

(c) Let L be the total length of the belt. Write L as a function of ϕ, where ϕ is measured in radians. What is the domain of the function? (*Hint:* Add the lengths of the straight sections of the belt and the length of the belt around each pulley.)

(d) Use a graphing utility to complete the table.

ϕ	0.3	0.6	0.9	1.2	1.5
L					

(e) Use a graphing utility to graph the function over the appropriate domain.

(f) Find $\lim_{\phi \to (\pi/2)^-} L$.

(g) Use a geometric argument as the basis of a second method of finding the limit in part (f).

(h) Find $\lim_{\phi \to 0^+} L$.

True or False? **In Exercises 73–76, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

73. The graph of a function cannot cross a vertical asymptote.

74. The graphs of polynomial functions have no vertical asymptotes.

75. The graphs of trigonometric functions have no vertical asymptotes.

76. If f has a vertical asymptote at $x = 0$, then f is undefined at $x = 0$.

77. Finding Functions Find functions f and g such that $\lim_{x \to c} f(x) = \infty$ and $\lim_{x \to c} g(x) = \infty$, but $\lim_{x \to c} [f(x) - g(x)] \neq 0$.

78. Proof Prove the difference, product, and quotient properties in Theorem 1.15.

79. Proof Prove that if $\lim_{x \to c} f(x) = \infty$, then $\lim_{x \to c} \frac{1}{f(x)} = 0$.

80. Proof Prove that if

$$\lim_{x \to c} \frac{1}{f(x)} = 0$$

then $\lim_{x \to c} f(x)$ does not exist.

Proof **In Exercises 81–84, use the ε–δ definition of infinite limits to prove the statement.**

81. $\lim_{x \to 3^+} \frac{1}{x - 3} = \infty$

82. $\lim_{x \to 5^-} \frac{1}{x - 5} = -\infty$

83. $\lim_{x \to 8^+} \frac{3}{8 - x} = -\infty$

84. $\lim_{x \to 9^-} \frac{6}{9 - x} = \infty$

SECTION PROJECT

Graphs and Limits of Trigonometric Functions

Recall from Theorem 1.9 that the limit of

$$f(x) = \frac{\sin x}{x}$$

as x approaches 0 is 1.

(a) Use a graphing utility to graph the function f on the interval $-\pi \leq x \leq \pi$. Explain how the graph helps confirm this theorem.

(b) Explain how you could use a table of values to confirm the value of this limit numerically.

(c) Graph $g(x) = \sin x$ by hand. Sketch a tangent line at the point $(0, 0)$ and visually estimate the slope of this tangent line.

(d) Let $(x, \sin x)$ be a point on the graph of g near $(0, 0)$, and write a formula for the slope of the secant line joining $(x, \sin x)$ and $(0, 0)$. Evaluate this formula at $x = 0.1$ and $x = 0.01$. Then find the exact slope of the tangent line to g at the point $(0, 0)$.

(e) Sketch the graph of the cosine function $h(x) = \cos x$. What is the slope of the tangent line at the point $(0, 1)$? Use limits to find this slope analytically.

(f) Find the slope of the tangent line to $k(x) = \tan x$ at $(0, 0)$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Review Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Exploring Concepts

The core idea of this chapter is the concept of the limit of a function. Limits will be used to develop three major ideas of calculus: the derivative, the integral, and infinite series. The statement

$$\lim_{x \to c} f(x) = L$$

means that if $f(x)$ becomes arbitrarily close to a single number L as x approaches c (from either side), then the limit of $f(x)$ as x approaches c is L. Otherwise, the limit fails to exist. The concept of limit leads naturally to the definition of continuity, which has three conditions: (1) $f(c)$ is defined, (2) $\lim_{x \to c} f(x)$ exists, and (3) $\lim_{x \to c} f(x) = f(c)$.

1. Find a function f that satisfies the first two conditions in the definition of continuity but not the third one.

2. Can a function that is continuous for all real x have a vertical asymptote? Explain.

3. Consider the function $f(x) = \sqrt{x(x-1)}$.

(a) Find the domain of f.

(b) Find $\lim_{x \to 0^-} f(x)$.

(c) Find $\lim_{x \to 1^+} f(x)$.

4. Consider the function

$$g(x) = \frac{1}{x-4}.$$

(a) Find the domain of g.

(b) Discuss the continuity of g.

(c) Describe the behavior of g as x gets closer and closer to 4.

5. Consider the function

$$f(x) = \frac{\tan 2x}{x}.$$

(a) Find $\lim_{x \to 0} f(x)$, if it exists.

(b) Can f be defined at $x = 0$ such that f is continuous at $x = 0$?

6. Consider the graphs of the functions g_1, g_2, g_3, and g_4.



For each given condition of the function f, which of the graphs could be the graph of f?

(a) $\lim_{x \to 2} f(x) = 3$

(b) f is continuous at 2.

(c) $\lim_{x \to 2^-} f(x) = 3$

Precalculus or Calculus **In Exercises 7 and 8, decide whether each problem can be solved using precalculus or whether calculus is required. When the problem can be solved using precalculus, solve it. When the problem seems to require calculus, explain your reasoning and use a graphical or numerical approach to estimate the solution.**

7. Find the area of the shaded region.

(a)



(b)



8. Find the distance between the points $(1, 1)$ and $(3, 9)$ (a) along the curve $y = x^2$ and (b) along the line $y = 4x - 3$.

Estimating a Limit Numerically **In Exercises 9–14, create a table of values for the function and use the result to estimate the limit. Use a graphing utility to graph the function to confirm your result.**

9. $\lim_{t \to 5} \dfrac{t^2 - 25}{t - 5}$

10. $\lim_{x \to 3} \dfrac{x - 3}{x^2 - 7x + 12}$

11. $\lim_{x \to 0} \dfrac{\sqrt{x+4} - 2}{x}$

12. $\lim_{x \to 1} \dfrac{1 - \sqrt[3]{x}}{x - 1}$

13. $\lim_{x \to 0} \dfrac{[1/(x+7)] - (1/7)}{x}$

14. $\lim_{x \to 0} \dfrac{[4/(x+2)] - 2}{x}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding a Limit Graphically **In Exercises 15 and 16, use the graph to find the limit (if it exists). If the limit does not exist, explain why.**

15. $h(x) = \left[\!\left[-\frac{x}{2}\right]\!\right] + x^2$



(a) $\lim_{x\to 2} h(x)$ (b) $\lim_{x\to 1} h(x)$

16. $g(x) = \dfrac{-2x}{x-3}$



(a) $\lim_{x\to 3} g(x)$ (b) $\lim_{x\to 0} g(x)$

Using the ε-δ Definition of Limit **In Exercises 17–20, find the limit L. Then use the ε-δ definition to prove that the limit is L.**

17. $\lim_{x\to 1}(x+4)$

18. $\lim_{x\to 9}\sqrt{x}$

19. $\lim_{x\to 2}(1-x^2)$

20. $\lim_{x\to 5} 9$

Finding a Limit **In Exercises 21–38, find the limit.**

21. $\lim_{x\to -6} x^2$

22. $\lim_{x\to 0}(5x-3)$

23. $\lim_{t\to 4}\sqrt{t+2}$

24. $\lim_{x\to 2}\sqrt{x^3+1}$

25. $\lim_{x\to 27}\left(\sqrt[3]{x}-1\right)^4$

26. $\lim_{x\to 7}(x-4)^3$

27. $\lim_{x\to 4}\dfrac{4}{x-1}$

28. $\lim_{x\to 2}\dfrac{x}{x^2+1}$

29. $\lim_{x\to -3}\dfrac{2x^2+11x+15}{x+3}$

30. $\lim_{t\to 4}\dfrac{t^2-16}{t-4}$

31. $\lim_{x\to 4}\dfrac{\sqrt{x-3}-1}{x-4}$

32. $\lim_{x\to 0}\dfrac{\sqrt{4+x}-2}{x}$

33. $\lim_{x\to 0}\dfrac{[1/(x+1)]-1}{x}$

34. $\lim_{s\to 0}\dfrac{\left(1/\sqrt{1+s}\right)-1}{s}$

35. $\lim_{x\to 0}\dfrac{1-\cos x}{\sin x}$

36. $\lim_{x\to \pi/4}\dfrac{4x}{\tan x}$

37. $\lim_{\Delta x\to 0}\dfrac{\sin[(\pi/6)+\Delta x]-(1/2)}{\Delta x}$

[*Hint:* $\sin(\theta+\phi) = \sin\theta\cos\phi + \cos\theta\sin\phi$]

38. $\lim_{\Delta x\to 0}\dfrac{\cos(\pi+\Delta x)+1}{\Delta x}$

[*Hint:* $\cos(\theta+\phi) = \cos\theta\cos\phi - \sin\theta\sin\phi$]

Evaluating a Limit **In Exercises 39–42, evaluate the limit when $\lim_{x\to c} f(x) = -6$ and $\lim_{x\to c} g(x) = \frac{1}{2}$.**

39. $\lim_{x\to c}[f(x)g(x)]$

40. $\lim_{x\to c}\dfrac{f(x)}{g(x)}$

41. $\lim_{x\to c}[f(x)+2g(x)]$

42. $\lim_{x\to c}[f(x)]^2$

Graphical, Numerical, and Analytic Analysis **In Exercises 43–46, use a graphing utility to graph the function and estimate the limit. Use a table to reinforce your conclusion. Then find the limit by analytic methods.**

43. $\lim_{x\to 0}\dfrac{\sqrt{2x+9}-3}{x}$

44. $\lim_{x\to 0}\dfrac{[1/(x+4)]-(1/4)}{x}$

45. $\lim_{x\to -9}\dfrac{x^3+729}{x+9}$

46. $\lim_{x\to 0}\dfrac{\cos x - 1}{x}$

Free-Falling Object **In Exercises 47 and 48, use the position function $s(t) = -4.9t^2 + 250$, which gives the height (in meters) of an object that has fallen for t seconds from a height of 250 meters. The velocity at time $t = a$ seconds is given by**

$$\lim_{t\to a}\frac{s(a)-s(t)}{a-t}.$$

47. Find the velocity of the object when $t = 4$.

48. When will the object hit the ground? At what velocity will the object impact the ground?

Finding a Limit **In Exercises 49–60, find the limit (if it exists). If it does not exist, explain why.**

49. $\lim_{x\to 3^+}\dfrac{1}{x+3}$

50. $\lim_{x\to 6^-}\dfrac{x-6}{x^2-36}$

51. $\lim_{x\to 10^+}\dfrac{x}{\sqrt{x^2-100}}$

52. $\lim_{x\to 25^+}\dfrac{\sqrt{x}-5}{x-25}$

53. $\lim_{x\to 3^-}\dfrac{|x-3|}{x-3}$

54. $\lim_{x\to 2^-}\dfrac{x^2-4}{|x-2|}$

55. $\lim_{x\to 2^-}(2[\![x]\!]+1)$

56. $\lim_{x\to 4}[\![x-1]\!]$

57. $\lim_{x\to 2} f(x)$, where $f(x) = \begin{cases}(x-2)^2, & x \le 2\\ 2-x, & x > 2\end{cases}$

58. $\lim_{x\to 1^+} g(x)$, where $g(x) = \begin{cases}\sqrt{1-x}, & x \le 1\\ x+1, & x > 1\end{cases}$

59. $\lim_{t\to 1} h(t)$, where $h(t) = \begin{cases}t^3+1, & t < 1\\ \frac{1}{2}(t+1), & t \ge 1\end{cases}$

60. $\lim_{s\to -2} f(s)$, where $f(s) = \begin{cases}-s^2-4s-2, & s \le -2\\ s^2+4s+6, & s > -2\end{cases}$

Continuity on a Closed Interval **In Exercises 61 and 62, discuss the continuity of the function on the closed interval.**

61. $g(x) = \sqrt{8-x^3}$, $[-2, 2]$

62. $h(x) = \dfrac{3}{5-x}$, $[0, 5]$

Removable and Nonremovable Discontinuities **In Exercises 63–68, find the x-values (if any) at which f is not continuous. State whether the discontinuities are removable or nonremovable.**

63. $f(x) = x^4 - 81x$

64. $f(x) = x^2 - x + 20$

65. $f(x) = \dfrac{4}{x-5}$

66. $f(x) = \dfrac{1}{x^2-9}$

67. $f(x) = \dfrac{x}{x^3-x}$

68. $f(x) = \dfrac{x+3}{x^2-3x-18}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

69. Making a Function Continuous Find the value of c such that f is continuous on the entire real number line.

$$f(x) = \begin{cases} x + 3, & x \le 2 \\ cx + 6, & x > 2 \end{cases}$$

70. Making a Function Continuous Find the values of b and c such that f is continuous on the entire real number line.

$$f(x) = \begin{cases} x + 1, & 1 < x < 3 \\ x^2 + bx + c, & |x - 2| \ge 1 \end{cases}$$

Testing for Continuity **In Exercises 71–76, describe the interval(s) on which the function is continuous.**

71. $f(x) = -3x^2 + 7$

72. $f(x) = \dfrac{4x^2 + 7x - 2}{x + 2}$

73. $f(x) = \sqrt{x} + \cos x$

74. $f(x) = [\![x + 3]\!]$

75. $f(x) = \begin{cases} \dfrac{3x^2 - x - 2}{x - 1}, & x \ne 1 \\ 0, & x = 1 \end{cases}$

76. $f(x) = \begin{cases} 5 - x, & x \le 2 \\ 2x - 3, & x > 2 \end{cases}$

77. Using the Intermediate Value Theorem Use the Intermediate Value Theorem to show that

$$f(x) = 2x^3 - 3$$

has a zero in the interval $[1, 2]$.

78. Using the Intermediate Value Theorem Use the Intermediate Value Theorem to show that

$$f(x) = x^2 + x - 2$$

has at least two zeros in the interval $[-3, 3]$.

Using the Intermediate Value Theorem **In Exercises 79 and 80, verify that the Intermediate Value Theorem applies to the indicated interval and find the value of c guaranteed by the theorem.**

79. $f(x) = x^2 + 5x - 4, \quad [-1, 2], \quad f(c) = 2$

80. $f(x) = (x - 6)^3 + 4, \quad [4, 7], \quad f(c) = 3$

Determining Infinite Limits **In Exercises 81 and 82, determine whether $f(x)$ approaches ∞ or $-\infty$ as x approaches 6 from the left and from the right.**

81. $f(x) = \dfrac{1}{x - 6}$

82. $f(x) = \dfrac{-1}{(x - 6)^2}$

Finding Vertical Asymptotes **In Exercises 83–88, find the vertical asymptotes (if any) of the graph of the function.**

83. $f(x) = \dfrac{3}{x}$

84. $f(x) = \dfrac{5}{(x - 2)^4}$

85. $f(x) = \dfrac{x^3}{x^2 - 9}$

86. $h(x) = \dfrac{6x}{36 - x^2}$

87. $f(x) = \sec \dfrac{\pi x}{2}$

88. $f(x) = \csc \pi x$

Finding a One-Sided Limit **In Exercises 89–98, find the one-sided limit (if it exists).**

89. $\lim\limits_{x \to 1^-} \dfrac{x^2 + 2x + 1}{x - 1}$

90. $\lim\limits_{x \to (1/2)^+} \dfrac{x}{2x - 1}$

91. $\lim\limits_{x \to -1^+} \dfrac{x + 1}{x^3 + 1}$

92. $\lim\limits_{x \to -1^-} \dfrac{x + 1}{x^4 - 1}$

93. $\lim\limits_{x \to 0^+} \left(x - \dfrac{1}{x^3}\right)$

94. $\lim\limits_{x \to 2^-} \dfrac{1}{\sqrt[3]{x^2 - 4}}$

95. $\lim\limits_{x \to 0^+} \dfrac{\sin 4x}{5x}$

96. $\lim\limits_{x \to 0^-} \dfrac{\sec x^3}{2x}$

97. $\lim\limits_{x \to 0^+} \dfrac{\csc 2x}{x}$

98. $\lim\limits_{x \to 0^-} \dfrac{\cos^2 x}{x}$

99. Environment A utility company burns coal to generate electricity. The cost C in dollars of removing $p\%$ of the air pollutants in the stack emissions is given by

$$C = \frac{80{,}000p}{100 - p}, \quad 0 \le p < 100.$$

(a) Find the cost of removing 90% of the pollutants.

(b) Find the limit of C as p approaches 100 from the left and interpret its meaning.

Building on Concepts

100. Consider the function

$$f(x) = \frac{x^2 - 4}{x - 2}.$$

(a) Find the domain of f.

(b) Factor the numerator and simplify the function. Describe the graph of f.

(c) Describe the behavior of f as x gets closer and closer to 2. Support your answer with an appropriate table.

(d) Find $\lim\limits_{x \to 2} f(x)$.

(e) Consider the parabola $h(x) = x^2$. Find the slope of the secant line joining the points $(2, 4)$ and $(2.1, 4.41)$ on the graph of h. Explain how you could find the slope of the tangent line to h at the point $(2, 4)$.

101. For positive numbers $a < b$, the **pulse function** is defined as

$$P_{a,b}(x) = H(x - a) - H(x - b) = \begin{cases} 0, & x < a \\ 1, & a \le x < b \\ 0, & x \ge b \end{cases}$$

where H is the Heaviside function (see Exercise 62, page 28).

(a) Sketch the graph of the pulse function.

(b) Find $\lim\limits_{x \to a^+} P_{a,b}(x)$, $\lim\limits_{x \to a^-} P_{a,b}(x)$, $\lim\limits_{x \to b^+} P_{a,b}(x)$, and $\lim\limits_{x \to b^-} P_{a,b}(x)$.

(c) Discuss the continuity of the pulse function.

(d) Why is U called the **unit pulse function?**

$$U(x) = \frac{1}{b - a} P_{a,b}(x)$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.S. Problem Solving

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

1. Perimeter and Area Let $P(x, y)$ be a point on the parabola $y = x^2$ in the first quadrant. Consider the triangle $\triangle PAO$ formed by P, $A(0, 1)$, and the origin $O(0, 0)$, and the triangle $\triangle PBO$ formed by P, $B(1, 0)$, and the origin (see figure).

(a) Write the perimeter of each triangle in terms of x.

(b) Let $r(x)$ be the ratio of the perimeters of the two triangles,

$$r(x) = \frac{\text{Perimeter } \triangle PAO}{\text{Perimeter } \triangle PBO}.$$

Complete the table. Calculate $\lim_{x \to 0^+} r(x)$.

x	4	2	1	0.1	0.01
Perimeter $\triangle PAO$					
Perimeter $\triangle PBO$					
$r(x)$					

(c) Write the area of each triangle in terms of x.

(d) Let $a(x)$ be the ratio of the areas of the two triangles,

$$a(x) = \frac{\text{Area } \triangle PBO}{\text{Area } \triangle PAO}.$$

Complete the table. Calculate $\lim_{x \to 0^+} a(x)$.

x	4	2	1	0.1	0.01
Area $\triangle PAO$					
Area $\triangle PBO$					
$a(x)$					



Figure for 1



Figure for 2

2. Area

(a) Find the area of a regular hexagon inscribed in a circle of radius 1 (see figure). How close is this area to that of the circle?

(b) Find the area A_n of an n-sided regular polygon inscribed in a circle of radius 1. Write your answer as a function of n.

(c) Complete the table. What number does A_n approach as n gets larger and larger?

n	6	12	24	48	96
A_n					

3. Tangent Line Let $P(5, -12)$ be a point on the circle $x^2 + y^2 = 169$.

(a) What is the slope of the line joining P and $O(0, 0)$?

(b) Find an equation of the tangent line to the circle at P.

(c) Let $Q(x, y)$ be another point on the circle in the fourth quadrant. Find the slope m_x of the line joining P and Q in terms of x.

(d) Calculate $\lim_{x \to 5} m_x$. How does this number relate to your answer in part (b)?

4. Findings Limits Let

$$\lim_{x \to c} [f(x) + g(x)] = 5 \quad \text{and} \quad \lim_{x \to c} [f(x) - g(x)] = 12.$$

Find $\lim_{x \to c} [f(x)g(x)]$ and $\lim_{x \to c} [f(x)/g(x)]$.

5. Finding Values Find values of a and b such that

$$\lim_{x \to 0} \frac{\sqrt{a + bx} - \sqrt{3}}{x} = \sqrt{3}.$$

6. Escape Velocity To escape Earth's gravitational field, a rocket must be launched with an initial velocity called the **escape velocity.** A rocket launched from the surface of Earth has velocity v (in miles per second) given by

$$v = \sqrt{\frac{2GM}{r} + v_0^2 - \frac{2GM}{R}} \approx \sqrt{\frac{192{,}000}{r} + v_0^2 - 48}$$

where v_0 is the initial velocity, r is the distance from the rocket to the center of Earth, G is the gravitational constant, M is the mass of Earth, and R is the radius of Earth (approximately 4000 miles).

(a) Find the value of v_0 for which you obtain an infinite limit for r as v approaches zero. This value of v_0 is the escape velocity for Earth.

(b) A rocket launched from the surface of the moon has velocity v (in miles per second) given by

$$v = \sqrt{\frac{1920}{r} + v_0^2 - 2.17}.$$

Find the escape velocity for the moon.

(c) A rocket launched from the surface of a planet has velocity v (in miles per second) given by

$$v = \sqrt{\frac{10{,}600}{r} + v_0^2 - 6.99}.$$

Find the escape velocity for this planet. Is the mass of this planet larger or smaller than that of Earth? (Assume that the mean density of this planet is the same as that of Earth.)

7. Proof Let a be a nonzero constant. Prove that if $\lim_{x \to 0} f(x) = L$, then $\lim_{x \to 0} f(ax) = L$. Show by means of an example that a must be nonzero.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

2 Differentiation

GO DIGITAL

2.1 The Derivative and the Tangent Line Problem
2.2 Basic Differentiation Rules and Rates of Change
2.3 Product and Quotient Rules and Higher-Order Derivatives
2.4 The Chain Rule
2.5 Implicit Differentiation
2.6 Related Rates

CalcView®



CalcChat®


Chapter 2
Section 1
Exercise 17
GO
$f(x) = -5x$
$f'(x) = \lim_{\Delta x \to 0} \frac{f(x + \Delta x) - f(x)}{\Delta x}$
$= \lim_{\Delta x \to 0} \frac{-5(x + \Delta x) - (-5x)}{\Delta x}$
$= \lim_{\Delta x \to 0} \frac{-5x - 5\Delta x + 5x}{\Delta x}$
$= \lim_{\Delta x \to 0} \frac{-5\Delta x}{\Delta x}$
$= \lim_{\Delta x \to 0} (-5) = -5$
PREV. 7 9 11 13 15 17 19 21 23 25 27 NEXT

2.4 Bacteria *(Exercise 107, p. 143)*

2.3 Acceleration Due to Gravity *(Example 10, p. 128)*

left, Lotus_studio/Shutterstock.com; right, Vadim Sadovski/Shutterstock.com
Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322
Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

2.1 The Derivative and the Tangent Line Problem

GO DIGITAL

- **Find the slope of the tangent line to a curve at a point.**
- **Use the limit definition to find the derivative of a function.**
- **Describe the relationship between differentiability and continuity.**

The Tangent Line Problem

Calculus grew out of four major problems that European mathematicians were working on during the seventeenth century.

1. The tangent line problem (Section 1.1 and this section)
2. The velocity and acceleration problem (Sections 2.2 and 2.3)
3. The minimum and maximum problem (Section 3.1)
4. The area problem (Sections 1.1 and 4.2)

Each problem involves the notion of a limit, and calculus can be introduced with any of the four problems.

A brief introduction to the tangent line problem is given in Section 1.1. Although partial solutions to this problem were given by Pierre de Fermat (1601–1665), René Descartes (1596–1650), Christian Huygens (1629–1695), and Isaac Barrow (1630–1677), credit for the first general solution is usually given to Isaac Newton (1642–1727) and Gottfried Leibniz (1646–1716). Newton's work on this problem stemmed from his interest in optics and light refraction.

ISAAC NEWTON (1642–1727)

In addition to his work in calculus, Newton made revolutionary contributions to physics, including the Law of Universal Gravitation and his three laws of motion.

See LarsonCalculus.com to read more of this biography.

What does it mean to say that a line is tangent to a curve at a point? For a circle, the tangent line at a point P is the line that is perpendicular to the radial line at point P, as shown in Figure 2.1.



Tangent line to a circle
Figure 2.1

For a general curve, however, the problem is more difficult. For instance, how would you define the tangent lines shown in Figure 2.2? You might say that a line is tangent to a curve at a point P when it touches, but does not cross, the curve at point P. This definition would work for the first curve shown in Figure 2.2 but not for the second. *Or* you might say that a line is tangent to a curve when the line touches or intersects the curve at exactly one point. This definition would work for a circle but not for more general curves, as the third curve in Figure 2.2 shows.



Tangent line to a curve at a point
Figure 2.2

Exploration

Use a graphing utility to graph $f(x) = 2x^3 - 4x^2 + 3x - 5$. On the same screen, graph $y = x - 5$, $y = 2x - 5$, and $y = 3x - 5$. Which of these lines, if any, appears to be tangent to the graph of f at the point $(0, -5)$? Explain your reasoning.

Pictorial Press Ltd/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The secant line through $(c, f(c))$ and $(c + \Delta x, f(c + \Delta x))$
Figure 2.3

Essentially, the problem of finding the tangent line at a point P boils down to the problem of finding the *slope* of the tangent line at point P. You can approximate this slope using a **secant line*** through the point of tangency and a second point on the curve, as shown in Figure 2.3. If $(c, f(c))$ is the point of tangency and

$$(c + \Delta x, f(c + \Delta x))$$

is a second point on the graph of f, then the slope of the secant line through the two points is given by substitution into the slope formula

$$m = \frac{y_2 - y_1}{x_2 - x_1}$$

$$m_{\text{sec}} = \frac{f(c + \Delta x) - f(c)}{(c + \Delta x) - c} \qquad \frac{\text{Change in } y}{\text{Change in } x}$$

$$m_{\text{sec}} = \frac{f(c + \Delta x) - f(c)}{\Delta x}. \qquad \text{Slope of secant line}$$

The expression on the right side of this equation is a **difference quotient.** The denominator Δx is the **change in x,** and the numerator

$$\Delta y = f(c + \Delta x) - f(c)$$

is the **change in y.**

The beauty of this procedure is that you can obtain more and more accurate approximations of the slope of the tangent line by choosing points closer and closer to the point of tangency, as shown in Figure 2.4.

GO DIGITAL

THE TANGENT LINE PROBLEM

In 1637, mathematician René Descartes stated this about the tangent line problem:

"And I dare say that this is not only the most useful and general problem in geometry that I know, but even that I ever desire to know."



Tangent line approximations
Figure 2.4

REMARK The variable Δx is used to represent the change in x in the definition of the slope of a graph. Other variables may also be used. Sometimes this definition is written as

$$m = \lim_{h \to 0} \frac{f(c + h) - f(c)}{h}.$$

Definition of Tangent Line with Slope m

If f is defined on an open interval containing c, and if the limit

$$\lim_{\Delta x \to 0} \frac{\Delta y}{\Delta x} = \lim_{\Delta x \to 0} \frac{f(c + \Delta x) - f(c)}{\Delta x} = m$$

exists, then the line passing through $(c, f(c))$ with slope m is the **tangent line** to the graph of f at the point $(c, f(c))$.

The slope of the tangent line to the graph of f at the point $(c, f(c))$ is also called the **slope of the graph of f at $x = c$.**

* This use of the word *secant* comes from the Latin *secare*, meaning to cut, and is not a reference to the trigonometric function of the same name.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The slope of f at $(2, 1)$ is $m = 2$.
Figure 2.5

EXAMPLE 1 The Slope of the Graph of a Linear Function

To find the slope of the graph of $f(x) = 2x - 3$ when $c = 2$, you can apply the definition of the slope of a tangent line, as shown.

$$\lim_{\Delta x \to 0} \frac{f(2 + \Delta x) - f(2)}{\Delta x} = \lim_{\Delta x \to 0} \frac{[2(2 + \Delta x) - 3] - [2(2) - 3]}{\Delta x}$$

$$= \lim_{\Delta x \to 0} \frac{4 + 2\Delta x - 3 - 4 + 3}{\Delta x}$$

$$= \lim_{\Delta x \to 0} \frac{2\cancel{\Delta x}}{\cancel{\Delta x}} \qquad \text{Combine like terms.}$$

$$= \lim_{\Delta x \to 0} 2 \qquad \text{Divide out common factor.}$$

$$= 2 \qquad \text{Property 1, Theorem 1.1}$$

The slope of f at $(c, f(c)) = (2, 1)$ is $m = 2$, as shown in Figure 2.5. Notice that the limit definition of the slope of f agrees with the definition of the slope of a line as discussed in Section P.2. ■

GO DIGITAL

The graph of a linear function has the same slope at any point. This is not true of nonlinear functions, as shown in the next example.



The slope of f at any point $(c, f(c))$ is $m = 2c$.
Figure 2.6

EXAMPLE 2 Tangent Lines to the Graph of a Nonlinear Function

Find the slopes of the tangent lines to the graph of $f(x) = x^2 + 1$ at the points $(0, 1)$ and $(-1, 2)$, as shown in Figure 2.6.

Solution Let $(c, f(c))$ represent an arbitrary point on the graph of f. Then the slope of the tangent line at $(c, f(c))$ can be found as shown below. [Note in the limit process that c is held constant (as Δx approaches 0).]

$$\lim_{\Delta x \to 0} \frac{f(c + \Delta x) - f(c)}{\Delta x} = \lim_{\Delta x \to 0} \frac{[(c + \Delta x)^2 + 1] - (c^2 + 1)}{\Delta x}$$

$$= \lim_{\Delta x \to 0} \frac{c^2 + 2c(\Delta x) + (\Delta x)^2 + 1 - c^2 - 1}{\Delta x}$$

$$= \lim_{\Delta x \to 0} \frac{2c(\Delta x) + (\Delta x)^2}{\Delta x} \qquad \text{Combine like terms.}$$

$$= \lim_{\Delta x \to 0} (2c + \Delta x) \qquad \text{Divide out common factor.}$$

$$= 2c \qquad \text{Use direct substitution and simplify.}$$

So, the slope at *any* point $(c, f(c))$ on the graph of f is $m = 2c$. At the point $(0, 1)$, the slope is $m = 2(0) = 0$, and at $(-1, 2)$, the slope is $m = 2(-1) = -2$. ■



The graph of f has a vertical tangent line at $(c, f(c))$.
Figure 2.7

The definition of a tangent line to a curve does not cover the possibility of a vertical tangent line. For vertical tangent lines, use the following definition. If f is continuous at c and

$$\lim_{\Delta x \to 0} \frac{f(c + \Delta x) - f(c)}{\Delta x} = \infty \quad \text{or} \quad \lim_{\Delta x \to 0} \frac{f(c + \Delta x) - f(c)}{\Delta x} = -\infty$$

then the vertical line $x = c$ passing through $(c, f(c))$ is a **vertical tangent line** to the graph of f. For example, the function shown in Figure 2.7 has a vertical tangent line at $(c, f(c))$. When the domain of f is the closed interval $[a, b]$, you can extend the definition of a vertical tangent line to include the endpoints by considering continuity and limits from the right (for $x = a$) and from the left (for $x = b$).

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The Derivative of a Function

You have now arrived at a crucial point in the study of calculus. The limit used to define the slope of a tangent line is also used to define one of the two fundamental operations of calculus—**differentiation.**

Definition of the Derivative of a Function

The **derivative** of f at x is

$$f'(x) = \lim_{\Delta x \to 0} \frac{f(x + \Delta x) - f(x)}{\Delta x}$$

provided the limit exists. For all x for which this limit exists, f' is a function of x.

REMARK The notation $f'(x)$ is read as "f prime of x."

Be sure you understand that the derivative of a function of x is also a function of x. This "new" function gives the slope of the tangent line to the graph of f at the point $(x, f(x))$, provided that the graph has a tangent line at this point. The derivative can also be used to determine the **instantaneous rate of change** (or simply the **rate of change**) of one variable with respect to another.

Big Ideas of Calculus

The derivative of a function, a major theme of calculus, gives the slope of the graph of the function at any point. Such information has many real-life applications in science, business, and engineering. For example, you can use a derivative to find velocity, acceleration, maximum profit, or minimum distance.

The process of finding the derivative of a function is called **differentiation.** A function is **differentiable at x** when its derivative exists at x and is **differentiable on an open interval (a, b)** when it is differentiable at every point in the interval. Also, a function is **differentiable** when its derivative exists at every point in its domain.

In addition to $f'(x)$, other notations are used to denote the derivative of $y = f(x)$. The most common are

$$f'(x), \quad \frac{dy}{dx}, \quad y', \quad \frac{d}{dx}[f(x)], \quad D_x[y].$$

Notations for derivatives

The notation dy/dx is read as "the derivative of y *with respect to* x" or simply "dy, dx." Using limit notation, you can write

$$\frac{dy}{dx} = \lim_{\Delta x \to 0} \frac{\Delta y}{\Delta x} = \lim_{\Delta x \to 0} \frac{f(x + \Delta x) - f(x)}{\Delta x} = f'(x).$$

EXAMPLE 3 Finding the Derivative by the Limit Process

See LarsonCalculus.com for an interactive version of this type of example.

To find the derivative of $f(x) = x^3 + 2x$, use the definition of the derivative as shown.

$$\begin{aligned}
f'(x) &= \lim_{\Delta x \to 0} \frac{f(x + \Delta x) - f(x)}{\Delta x} && \text{Definition of derivative} \\
&= \lim_{\Delta x \to 0} \frac{(x + \Delta x)^3 + 2(x + \Delta x) - (x^3 + 2x)}{\Delta x} \\
&= \lim_{\Delta x \to 0} \frac{x^3 + 3x^2\Delta x + 3x(\Delta x)^2 + (\Delta x)^3 + 2x + 2\Delta x - x^3 - 2x}{\Delta x} \\
&= \lim_{\Delta x \to 0} \frac{3x^2\Delta x + 3x(\Delta x)^2 + (\Delta x)^3 + 2\Delta x}{\Delta x} && \text{Combine like terms.} \\
&= \lim_{\Delta x \to 0} \frac{\Delta x[3x^2 + 3x\Delta x + (\Delta x)^2 + 2]}{\Delta x} && \text{Factor out common factor.} \\
&= \lim_{\Delta x \to 0} [3x^2 + 3x\Delta x + (\Delta x)^2 + 2] && \text{Divide out common factor.} \\
&= 3x^2 + 2 && \text{Use direct substitution.}
\end{aligned}$$

REMARK When using the definition to find a derivative of a function, the key is to rewrite the difference quotient so that Δx does not occur as a factor of the denominator.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

REMARK Remember that the derivative of a function f is itself a function, which can be used to find the slope of the tangent line at the point $(x, f(x))$ on the graph of f.

EXAMPLE 4 Using the Derivative to Find the Slope at a Point

Find $f'(x)$ for $f(x) = \sqrt{x}$. Then find the slopes of the graph of f at the points $(1, 1)$ and $(4, 2)$. Discuss the behavior of f at $(0, 0)$.

Solution Use the procedure for rationalizing numerators, as discussed in Section 1.3.

$$f'(x) = \lim_{\Delta x \to 0} \frac{f(x + \Delta x) - f(x)}{\Delta x}$$ Definition of derivative

$$= \lim_{\Delta x \to 0} \frac{\sqrt{x + \Delta x} - \sqrt{x}}{\Delta x}$$

$$= \lim_{\Delta x \to 0} \left(\frac{\sqrt{x + \Delta x} - \sqrt{x}}{\Delta x} \right) \left(\frac{\sqrt{x + \Delta x} + \sqrt{x}}{\sqrt{x + \Delta x} + \sqrt{x}} \right)$$

$$= \lim_{\Delta x \to 0} \frac{(x + \Delta x) - x}{\Delta x\left(\sqrt{x + \Delta x} + \sqrt{x}\right)}$$ Rationalize numerator.

$$= \lim_{\Delta x \to 0} \frac{\Delta x}{\Delta x\left(\sqrt{x + \Delta x} + \sqrt{x}\right)}$$ Combine like terms.

$$= \lim_{\Delta x \to 0} \frac{1}{\sqrt{x + \Delta x} + \sqrt{x}}$$ Divide out common factor.

$$= \frac{1}{2\sqrt{x}}$$ Use direct substitution and simplify.

At the point $(1, 1)$, the slope is $f'(1) = \frac{1}{2}$. At the point $(4, 2)$, the slope is $f'(4) = \frac{1}{4}$. See Figure 2.8. The domain of f' is all $x > 0$, so the slope of f is undefined at $(0, 0)$. Moreover, the graph of f has a vertical tangent line at $(0, 0)$.



For $x > 0$, the slope of f at $(x, f(x))$ is $m = 1/(2\sqrt{x})$.
Figure 2.8

REMARK In many applications, it is convenient to use a variable other than x as the independent variable, as shown in Example 5.

EXAMPLE 5 Finding the Derivative of a Function

See LarsonCalculus.com for an interactive version of this type of example.

Find the derivative with respect to t for the function $y = 2/t$.

Solution Considering $y = f(t)$, you obtain

$$\frac{dy}{dt} = \lim_{\Delta t \to 0} \frac{f(t + \Delta t) - f(t)}{\Delta t}$$ Definition of derivative

$$= \lim_{\Delta t \to 0} \frac{\frac{2}{t + \Delta t} - \frac{2}{t}}{\Delta t}$$ $f(t + \Delta t) = \frac{2}{t + \Delta t}$ and $f(t) = \frac{2}{t}$

$$= \lim_{\Delta t \to 0} \frac{\frac{2t - 2(t + \Delta t)}{t(t + \Delta t)}}{\Delta t}$$ Combine fractions in numerator.

$$= \lim_{\Delta t \to 0} \frac{-2\Delta t}{\Delta t(t)(t + \Delta t)}$$ Invert divisor and multiply. Combine like terms.

$$= \lim_{\Delta t \to 0} \frac{-2}{t(t + \Delta t)}$$ Divide out common factor.

$$= -\frac{2}{t^2}.$$ Use direct substitution and simplify.

GO DIGITAL



At the point $(1, 2)$, the line $y = -2t + 4$ is tangent to the graph of $y = 2/t$.
Figure 2.9

TECHNOLOGY You can use a graphing utility to support the result in Example 5. For instance, using $dy/dt = -2/t^2$, the slope of the graph of $y = 2/t$ at the point $(1, 2)$ is $m = -2$. Using the point-slope form, the equation of the tangent line to the graph at $(1, 2)$ is

$$y - 2 = -2(t - 1) \quad \text{or} \quad y = -2t + 4.$$ See Figure 2.9.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Differentiability and Continuity

The alternative limit form of the derivative shown below is useful in investigating the relationship between differentiability and continuity. The derivative of f at c is

$$f'(c) = \lim_{x \to c} \frac{f(x) - f(c)}{x - c}$$ Alternative form of derivative

provided this limit exists (see Figure 2.10). (A proof of the equivalence of the alternative form of the derivative is given in Appendix A.)

FOR FURTHER INFORMATION
For more information on the crediting of mathematical discoveries to the first "discoverers," see the article "Mathematical Firsts—Who Done It?" by Richard H. Williams and Roy D. Mazzagatti in *Mathematics Teacher*. To view this article, go to *MathArticles.com*.



As x approaches c, the secant line approaches the tangent line.
Figure 2.10

Note that the existence of the limit in this alternative form requires that the one-sided limits

$$\lim_{x \to c^-} \frac{f(x) - f(c)}{x - c}$$ x approaches c from the left.

and

$$\lim_{x \to c^+} \frac{f(x) - f(c)}{x - c}$$ x approaches c from the right.

exist and are equal. These one-sided limits are called the **derivatives from the left and from the right,** respectively. It follows that f is **differentiable on the closed interval** $[a, b]$ when it is differentiable on (a, b) and when the derivative from the right at a and the derivative from the left at b both exist.

When a function is not continuous at $x = c$, it is also not differentiable at $x = c$. For instance, the greatest integer function $f(x) = [\![x]\!]$ is not continuous at $x = 0$, and so it is not differentiable at $x = 0$ (see Figure 2.11). To verify this, note that the derivative from the left is

$$\lim_{x \to 0^-} \frac{f(x) - f(0)}{x - 0} = \lim_{x \to 0^-} \frac{[\![x]\!] - 0}{x} = \infty$$ Derivative from the left

and the derivative from the right is

$$\lim_{x \to 0^+} \frac{f(x) - f(0)}{x - 0} = \lim_{x \to 0^+} \frac{[\![x]\!] - 0}{x} = 0.$$ Derivative from the right



The greatest integer function is not differentiable at $x = 0$ because it is not continuous at $x = 0$.
Figure 2.11

Although it is true that differentiability implies continuity (as shown in Theorem 2.1 on the next page), the converse is not true. That is, it is possible for a function to be continuous at $x = c$ and *not* differentiable at $x = c$. Examples 6 and 7 illustrate this possibility.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



f is not differentiable at $x = 2$ because the derivatives from the left and from the right are not equal.
Figure 2.12

EXAMPLE 6 A Graph with a Sharp Turn

See LarsonCalculus.com for an interactive version of this type of example.

The function $f(x) = |x - 2|$, shown in Figure 2.12, is continuous at $x = 2$. The one-sided limits, however,

$$\lim_{x\to 2^-} \frac{f(x) - f(2)}{x - 2} = \lim_{x\to 2^-} \frac{|x - 2| - 0}{x - 2} = -1$$ Derivative from the left

and

$$\lim_{x\to 2^+} \frac{f(x) - f(2)}{x - 2} = \lim_{x\to 2^+} \frac{|x - 2| - 0}{x - 2} = 1$$ Derivative from the right

are not equal. So, f is not differentiable at $x = 2$ and the graph of f does not have a tangent line at the point $(2, 0)$.



f is not differentiable at $x = 0$ because f has a vertical tangent line at $x = 0$.
Figure 2.13

EXAMPLE 7 A Graph with a Vertical Tangent Line

The function $f(x) = x^{1/3}$ is continuous at $x = 0$, as shown in Figure 2.13. However, because the limit

$$\lim_{x\to 0} \frac{f(x) - f(0)}{x - 0} = \lim_{x\to 0} \frac{x^{1/3} - 0}{x} = \lim_{x\to 0} \frac{1}{x^{2/3}} = \infty$$

is infinite, you can conclude that the tangent line is vertical at $x = 0$. So, f is not differentiable at $x = 0$. ■

From Examples 6 and 7, you can see that a function is not differentiable at a point at which its graph has a sharp turn (see Figure 2.12) *or* a vertical tangent line (see Figure 2.13).

GO DIGITAL

THEOREM 2.1 Differentiability Implies Continuity

If f is differentiable at $x = c$, then f is continuous at $x = c$.

Proof You can prove that f is continuous at $x = c$ by showing that $f(x)$ approaches $f(c)$ as $x \to c$. To do this, use the differentiability of f at $x = c$ and consider the following limit. (Note the use of the alternative limit form of the derivative.)

$$\begin{aligned}
\lim_{x\to c} [f(x) - f(c)] &= \lim_{x\to c} \left[(x - c)\left(\frac{f(x) - f(c)}{x - c}\right)\right] && \text{Multiply and divide by } x - c. \\
&= \left[\lim_{x\to c} (x - c)\right]\left[\lim_{x\to c} \frac{f(x) - f(c)}{x - c}\right] && \text{Property 4, Theorem 1.2} \\
&= (0)[f'(c)] && \text{Alternative form of derivative} \\
&= 0
\end{aligned}$$

Because the difference $f(x) - f(c)$ approaches zero as $x \to c$, you can conclude that $\lim_{x\to c} f(x) = f(c)$. So, f is continuous at $x = c$. ■

The relationship between continuity and differentiability is summarized below.

1. If a function is differentiable at $x = c$, then it is continuous at $x = c$. So, differentiability implies continuity.
2. It is possible for a function to be continuous at $x = c$ and not be differentiable at $x = c$. So, continuity does not imply differentiability (see Examples 6 and 7).

TECHNOLOGY

Some graphing utilities have a *derivative* feature that performs *numerical differentiation* by finding values of derivatives using the formula

$$f'(x) \approx \frac{f(x + \Delta x) - f(x - \Delta x)}{2\Delta x}$$

where Δx is a small number such as 0.001. Do you see any problems with this definition? For instance, using this definition, what is the value of the derivative of $f(x) = |x|$ when $x = 0$?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

2.1 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe how to find the slope of the tangent line to the graph of a function at a point.
2. List four notation alternatives to $f'(x)$.
3. Describe how to find the derivative of a function using the limit process.
4. Describe the relationship between continuity and differentiability.

Estimating Slope **In Exercises 5 and 6, estimate the slope of the graph at the points (x_1, y_1) and (x_2, y_2).**

5.



6.



Slopes of Secant Lines **In Exercises 7 and 8, use the graph shown in the figure. To print an enlarged copy of the graph, go to *MathGraphs.com*.**



7. Identify or sketch each of the quantities on the figure.
   (a) $f(1)$ and $f(4)$ (b) $f(4) - f(1)$
   (c) $4 - 1$ (d) $y - 2 = \dfrac{f(4) - f(1)}{4 - 1}(x - 1)$
8. Insert the proper inequality symbol ($<$ or $>$) between the given quantities.
   (a) $\dfrac{f(4) - f(1)}{4 - 1}$ $\dfrac{f(4) - f(3)}{4 - 3}$
   (b) $\dfrac{f(4) - f(1)}{4 - 1}$ $f'(1)$

Finding the Slope of a Tangent Line **In Exercises 9–14, find the slope of the tangent line to the graph of the function at the given point.**

9. $f(x) = 3 - 5x, \quad (-1, 8)$
10. $g(x) = \frac{3}{2}x + 1, \quad (-2, -2)$
11. $f(x) = 2x^2 - 3, \quad (2, 5)$
12. $f(x) = 5 - x^2, \quad (3, -4)$
13. $f(t) = 3t - t^2, \quad (0, 0)$
14. $h(t) = t^2 + 4t, \quad (1, 5)$

Finding the Derivative by the Limit Process **In Exercises 15–28, find the derivative of the function using the limit process.**

15. $f(x) = 7$
16. $g(x) = -3$
17. $f(x) = -5x$
18. $f(x) = 7x - 3$
19. $h(s) = 3 + \frac{2}{3}s$
20. $f(x) = 5 - \frac{2}{3}x$
21. $f(x) = x^2 + x - 3$
22. $f(x) = x^2 - 5$
23. $f(x) = x^3 - 12x$
24. $g(t) = t^3 + 4t$
25. $f(x) = \dfrac{1}{x - 1}$
26. $f(x) = \dfrac{1}{x^2}$
27. $f(x) = \sqrt{x + 4}$
28. $h(s) = -2\sqrt{s}$

Finding an Equation of a Tangent Line **In Exercises 29–36, (a) find an equation of the tangent line to the graph of f at the given point, (b) use a graphing utility to graph the function and its tangent line at the point, and (c) use the *tangent* feature of a graphing utility to confirm your results.**

29. $f(x) = x^2 + 3, \quad (-1, 4)$
30. $f(x) = x^2 + 2x - 1, \quad (1, 2)$
31. $f(x) = x^3, \quad (2, 8)$
32. $f(x) = x^3 + 1, \quad (-1, 0)$
33. $f(x) = \sqrt{x}, \quad (1, 1)$
34. $f(x) = \sqrt{x - 1}, \quad (5, 2)$
35. $f(x) = x + \dfrac{4}{x}, \quad (-4, -5)$
36. $f(x) = x - \dfrac{1}{x}, \quad (1, 0)$

Finding an Equation of a Tangent Line **In Exercises 37–42, find an equation of the line that is tangent to the graph of f *and* parallel to the given line.**

Function	Line
37. $f(x) = -\frac{1}{4}x^2$	$x + y = 0$
38. $f(x) = 2x^2$	$4x + y + 3 = 0$
39. $f(x) = x^3$	$3x - y + 1 = 0$
40. $f(x) = x^3 + 2$	$3x - y - 4 = 0$
41. $f(x) = \dfrac{1}{\sqrt{x}}$	$x + 2y - 6 = 0$
42. $f(x) = \dfrac{1}{\sqrt{x - 1}}$	$x + 2y + 7 = 0$

Sketching a Derivative **In Exercises 43–48, sketch the graph of f'. Explain how you found your answer.**

43.



44.



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

45.



46.



47.



48.



Exploring Concepts

49. Sketch a graph of a function whose derivative is always negative. Explain how you found your answer.

50. Sketch a graph of a function whose derivative is zero at exactly two points. Explain how you found your answer.

51. Do f and f' always have the same domain? Explain.

52. A function f is symmetric with respect to the origin. Is f' necessarily symmetric with respect to the origin? Explain.

53. Using a Tangent Line The tangent line to the graph of $y = g(x)$ at the point $(4, 5)$ passes through the point $(7, 0)$. Find $g(4)$ and $g'(4)$.

54. Using a Tangent Line The tangent line to the graph of $y = h(x)$ at the point $(-1, 4)$ passes through the point $(3, 6)$. Find $h(-1)$ and $h'(-1)$.

Working Backwards **In Exercises 55–58, the limit represents $f'(c)$ for a function f and a number c. Find f and c.**

55. $\lim_{\Delta x \to 0} \dfrac{[5 - 3(1 + \Delta x)] - 2}{\Delta x}$

56. $\lim_{\Delta x \to 0} \dfrac{(-2 + \Delta x)^3 + 8}{\Delta x}$

57. $\lim_{x \to 6} \dfrac{-x^2 + 36}{x - 6}$

58. $\lim_{x \to 9} \dfrac{2\sqrt{x} - 6}{x - 9}$

Writing a Function Using Derivatives **In Exercises 59 and 60, identify a function f that satisfies each characteristic. Then sketch the function.**

59. $f(0) = 2$; $f'(x) = -3$ for $-\infty < x < \infty$

60. $f(0) = 4$; $f'(0) = 0$; $f'(x) < 0$ for $x < 0$; $f'(x) > 0$ for $x > 0$

Finding an Equation of a Tangent Line **In Exercises 61 and 62, find equations of the two tangent lines to the graph of f that pass through the indicated point.**

61. $f(x) = 4x - x^2$



62. $f(x) = x^2$



63. Graphical Reasoning Use a graphing utility to graph each function and its tangent lines at $x = -1$, $x = 0$, and $x = 1$. Based on the results, determine whether the slopes of tangent lines to the graph of a function at different values of x are always distinct.

(a) $f(x) = x^2$ (b) $g(x) = x^3$

64. HOW DO YOU SEE IT? The figure shows the graph of g'.



(a) $g'(0) =$ (b) $g'(3) =$

(c) What can you conclude about the graph of g knowing that $g'(1) = -\frac{8}{3}$?

(d) What can you conclude about the graph of g knowing that $g'(-4) = \frac{7}{3}$?

(e) Is $g(6) - g(4)$ positive or negative? Explain.

(f) Is it possible to find $g(2)$ from the graph? Explain.

65. Graphical Reasoning Consider the function $f(x) = \frac{1}{2}x^2$.

(a) Use a graphing utility to graph the function and estimate the values of $f'(0)$, $f'(\frac{1}{2})$, $f'(1)$, and $f'(2)$.

(b) Use your results from part (a) to determine the values of $f'(-\frac{1}{2})$, $f'(-1)$, and $f'(-2)$.

(c) Sketch a possible graph of f'.

(d) Use the definition of derivative to find $f'(x)$.

66. Graphical Reasoning Consider the function $f(x) = \frac{1}{3}x^3$.

(a) Use a graphing utility to graph the function and estimate the values of $f'(0)$, $f'(\frac{1}{2})$, $f'(1)$, $f'(2)$, and $f'(3)$.

(b) Use your results from part (a) to determine the values of $f'(-\frac{1}{2})$, $f'(-1)$, $f'(-2)$, and $f'(-3)$.

(c) Sketch a possible graph of f'.

(d) Use the definition of derivative to find $f'(x)$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Approximating a Derivative **In Exercises 67 and 68, evaluate $f(2)$ and $f(2.1)$ and use the results to approximate $f'(2)$.**

67. $f(x) = x(4 - x)$ **68.** $f(x) = \frac{1}{4}x^3$

Using the Alternative Form of the Derivative **In Exercises 69–78, use the alternative form of the derivative to find the derivative at $x = c$, if it exists.**

69. $f(x) = x^2 - 5,\ c = 3$ **70.** $g(x) = x^2 - x,\ c = 1$

71. $f(x) = x^3 + 2x^2 + 1,\ c = -2$

72. $f(x) = x^3 + 6x,\ c = 2$

73. $g(x) = \sqrt{|x|},\ c = 0$ **74.** $f(x) = 3/x,\ c = 4$

75. $f(x) = (x - 6)^{2/3},\ c = 6$ **76.** $g(x) = (x + 3)^{1/3},\ c = -3$

77. $h(x) = |x + 7|,\ c = -7$ **78.** $f(x) = |x - 6|,\ c = 6$

Determining Differentiability **In Exercises 79–82, describe the x-values at which f is differentiable.**

79. $f(x) = (x + 4)^{2/3}$ **80.** $f(x) = \dfrac{x^2}{x^2 - 4}$





81. $f(x) = \sqrt{x + 1} + 1$ **82.** $f(x) = \begin{cases} x^2 - 4, & x \le 0 \\ 4 - x^2, & x > 0 \end{cases}$





Graphical Analysis **In Exercises 83–86, use a graphing utility to graph the function and find the x-values at which f is differentiable.**

83. $f(x) = |x - 5|$ **84.** $f(x) = \dfrac{4x}{x - 3}$

85. $f(x) = x^{2/5}$

86. $f(x) = \begin{cases} x^3 - 3x^2 + 3x, & x \le 1 \\ x^2 - 2x, & x > 1 \end{cases}$

Determining Differentiability **In Exercises 87–90, find the derivatives from the left and from the right at $x = 1$ (if they exist). Is the function differentiable at $x = 1$?**

87. $f(x) = |x - 1|$ **88.** $f(x) = \sqrt{1 - x^2}$

89. $f(x) = \begin{cases} (x - 1)^3, & x \le 1 \\ (x - 1)^2, & x > 1 \end{cases}$ **90.** $f(x) = (1 - x)^{2/3}$

Determining Differentiability **In Exercises 91 and 92, determine whether the function is differentiable at $x = 2$.**

91. $f(x) = \begin{cases} x^2 + 1, & x \le 2 \\ 4x - 3, & x > 2 \end{cases}$ **92.** $f(x) = \begin{cases} \frac{1}{2}x + 2, & x < 2 \\ \sqrt{2x}, & x \ge 2 \end{cases}$

93. Graphical Reasoning A line with slope m passes through the point $(0, 4)$ and has the equation $y = mx + 4$.

(a) Write the distance d between the line and the point $(3, 1)$ as a function of m.

(b) Use a graphing utility to graph the function d in part (a). Based on the graph, is the function differentiable at every value of m? If not, where is it not differentiable?

94. Conjecture Consider the functions $f(x) = x^2$ and $g(x) = x^3$.

(a) Graph f and f' on the same set of axes.

(b) Graph g and g' on the same set of axes.

(c) Identify a pattern between f and g and their respective derivatives. Use the pattern to make a conjecture about $h'(x)$ when $h(x) = x^n$, where n is an integer and $n \ge 2$.

(d) Find $f'(x)$ if $f(x) = x^4$. Compare the result with the conjecture in part (c). Is this a proof of your conjecture? Explain.

True or False? **In Exercises 95–98, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

95. The slope of the tangent line to the differentiable function f at the point $(2, f(2))$ is

$$\frac{f(2 + \Delta x) - f(2)}{\Delta x}.$$

96. If a function is continuous at a point, then it is differentiable at that point.

97. If a function has derivatives from both the right and the left at a point, then it is differentiable at that point.

98. If a function is differentiable at a point, then it is continuous at that point.

99. Differentiability and Continuity Let

$$f(x) = \begin{cases} x \sin\dfrac{1}{x}, & x \ne 0 \\ 0, & x = 0 \end{cases}$$

and

$$g(x) = \begin{cases} x^2 \sin\dfrac{1}{x}, & x \ne 0 \\ 0, & x = 0 \end{cases}.$$

Show that f is continuous, but not differentiable, at $x = 0$. Show that g is differentiable at 0 and find $g'(0)$.

100. Writing Use a graphing utility to graph the two functions $f(x) = x^2 + 1$ and $g(x) = |x| + 1$ in the same viewing window. Use the *zoom* and *trace* features to analyze the graphs near the point $(0, 1)$. What do you observe? Which function is differentiable at this point? Write a short paragraph describing the geometric significance of differentiability at a point.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

2.2 Basic Differentiation Rules and Rates of Change

GO DIGITAL

- Find the derivative of a function using the Constant Rule.
- Find the derivative of a function using the Power Rule.
- Find the derivative of a function using the Constant Multiple Rule.
- Find the derivative of a function using the Sum and Difference Rules.
- Find the derivatives of the sine function and of the cosine function.
- Use derivatives to find rates of change.

The Constant Rule

In Section 2.1, you used the limit definition to find derivatives. In this and the next two sections, you will be introduced to several "differentiation rules" that allow you to find derivatives without the *direct* use of the limit definition.



Notice that the Constant Rule is equivalent to saying that the slope of a horizontal line is 0. This demonstrates the relationship between slope and derivative.

Figure 2.14

THEOREM 2.2 The Constant Rule

The derivative of a constant function is 0. That is, if c is a real number, then

$$\frac{d}{dx}[c] = 0.$$ See Figure 2.14.

Proof Let $f(x) = c$. Then, by the limit definition of the derivative,

$$\begin{aligned}\frac{d}{dx}[c] &= f'(x)\\ &= \lim_{\Delta x \to 0} \frac{f(x + \Delta x) - f(x)}{\Delta x} && \text{Definition of derivative}\\ &= \lim_{\Delta x \to 0} \frac{c - c}{\Delta x} && f(x + \Delta x) = f(x) = c\\ &= \lim_{\Delta x \to 0} 0\\ &= 0.\end{aligned}$$

EXAMPLE 1 Using the Constant Rule

Function	Derivative
a. $y = 7$	$dy/dx = 0$
b. $f(x) = 0$	$f'(x) = 0$
c. $s(t) = -3$	$s'(t) = 0$
d. $y = k\pi^2$, k is constant	$dy/dx = 0$

Exploration

Writing a Conjecture Use the definition of the derivative given in Section 2.1 to find the derivative of each function. What patterns do you see? Use your results to write a conjecture about the derivative of $f(x) = x^n$.

a. $f(x) = x^1$ **b.** $f(x) = x^2$ **c.** $f(x) = x^3$

d. $f(x) = x^4$ **e.** $f(x) = x^{1/2}$ **f.** $f(x) = x^{-1}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The Power Rule

Before proving the next rule, it is important to review the procedure for expanding a binomial.

$$(x + \Delta x)^2 = x^2 + 2x\Delta x + (\Delta x)^2$$
$$(x + \Delta x)^3 = x^3 + 3x^2\Delta x + 3x(\Delta x)^2 + (\Delta x)^3$$
$$(x + \Delta x)^4 = x^4 + 4x^3\Delta x + 6x^2(\Delta x)^2 + 4x(\Delta x)^3 + (\Delta x)^4$$
$$(x + \Delta x)^5 = x^5 + 5x^4\Delta x + 10x^3(\Delta x)^2 + 10x^2(\Delta x)^3 + 5x(\Delta x)^4 + (\Delta x)^5$$

The general binomial expansion for a positive integer n is

$$(x + \Delta x)^n = x^n + nx^{n-1}(\Delta x) + \underbrace{\frac{n(n-1)x^{n-2}}{2}(\Delta x)^2 + \cdots + (\Delta x)^n}_{(\Delta x)^2 \text{ is a factor of these terms.}}.$$

This binomial expansion is used in proving a special case of the Power Rule.

THEOREM 2.3 The Power Rule

If n is a rational number, then the function $f(x) = x^n$ is differentiable and

$$\frac{d}{dx}[x^n] = nx^{n-1}.$$

For f to be differentiable at $x = 0$, n must be a number such that x^{n-1} is defined on an interval containing 0.

REMARK Recall from Example 7 in Section 2.1 that the function $f(x) = x^{1/3}$ is defined at $x = 0$ but is not differentiable at $x = 0$. This is because $x^{-2/3}$ is not defined on an interval containing 0.

Proof If n is a positive integer greater than 1, then the binomial expansion produces

$$\begin{aligned}\frac{d}{dx}[x^n] &= \lim_{\Delta x \to 0} \frac{(x + \Delta x)^n - x^n}{\Delta x} \\ &= \lim_{\Delta x \to 0} \frac{x^n + nx^{n-1}(\Delta x) + \dfrac{n(n-1)x^{n-2}}{2}(\Delta x)^2 + \cdots + (\Delta x)^n - x^n}{\Delta x} \\ &= \lim_{\Delta x \to 0} \left[nx^{n-1} + \frac{n(n-1)x^{n-2}}{2}(\Delta x) + \cdots + (\Delta x)^{n-1} \right] \\ &= nx^{n-1} + 0 + \cdots + 0 \\ &= nx^{n-1}.\end{aligned}$$

This proves the case for which n is a positive integer greater than 1. It is left to you to prove the case for $n = 1$. Example 7 in Section 2.3 proves the case for which n is a negative integer. In Exercise 73 in Section 2.5, you are asked to prove the case for which n is rational. (In Section 5.5, the Power Rule will be extended to cover irrational values of n.)

When using the Power Rule, the case for which $n = 1$ is best thought of as a separate differentiation rule. That is,

$$\frac{d}{dx}[x] = 1. \qquad \text{Power Rule when } n = 1$$

This rule is consistent with the fact that the slope of the line $y = x$ is 1, as shown in Figure 2.15.



The slope of the line $y = x$ is 1.
Figure 2.15

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 2 Using the Power Rule

Function	Derivative
a. $f(x) = x^3$	$f'(x) = 3x^2$
b. $g(x) = \sqrt[3]{x}$	$g'(x) = \frac{d}{dx}[x^{1/3}] = \frac{1}{3}x^{-2/3} = \frac{1}{3x^{2/3}}$
c. $y = \frac{1}{x^2}$	$\frac{dy}{dx} = \frac{d}{dx}[x^{-2}] = (-2)x^{-3} = -\frac{2}{x^3}$

In Example 2(c), note that *before* differentiating, $1/x^2$ was rewritten as x^{-2}. Rewriting is the first step in *many* differentiation problems.

Given: $y = \frac{1}{x^2}$ ⇨ Rewrite: $y = x^{-2}$ ⇨ Differentiate: $\frac{dy}{dx} = (-2)x^{-3}$ ⇨ Simplify: $\frac{dy}{dx} = -\frac{2}{x^3}$

EXAMPLE 3 Finding the Slope of a Graph

See LarsonCalculus.com for an interactive version of this type of example.

Find the slope of the graph of $f(x) = x^4$ for each value of x.

a. $x = -1$ **b.** $x = 0$ **c.** $x = 1$

Solution The slope of a graph at a point is the value of the derivative at that point. The derivative of f is $f'(x) = 4x^3$.

a. When $x = -1$, the slope is $f'(-1) = 4(-1)^3 = -4$. Slope is negative.

b. When $x = 0$, the slope is $f'(0) = 4(0)^3 = 0$. Slope is zero.

c. When $x = 1$, the slope is $f'(1) = 4(1)^3 = 4$. Slope is positive.

See Figure 2.16.



Note that the slope of the graph is negative at the point $(-1, 1)$, the slope is zero at the point $(0, 0)$, and the slope is positive at the point $(1, 1)$.
Figure 2.16

EXAMPLE 4 Finding an Equation of a Tangent Line

See LarsonCalculus.com for an interactive version of this type of example.

Find an equation of the tangent line to the graph of $f(x) = x^2$ when $x = -2$.

Solution To find the *point* on the graph of f, evaluate the original function at $x = -2$.

$(-2, f(-2)) = (-2, 4)$ Point on graph

To find the *slope* of the graph when $x = -2$, evaluate the derivative, $f'(x) = 2x$, at $x = -2$.

$m = f'(-2) = -4$ Slope of graph at $(-2, 4)$

Now, use the point-slope form (see Section P.2) to write an equation of the tangent line.

$y - y_1 = m(x - x_1)$ Point-slope form

$y - 4 = -4[x - (-2)]$ Substitute for y_1, m, and x_1.

$y = -4x - 4$ Simplify.

You can check this result using the *tangent* feature of a graphing utility, as shown in Figure 2.17.



The line $y = -4x - 4$ is tangent to the graph of $f(x) = x^2$ at the point $(-2, 4)$.
Figure 2.17

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The Constant Multiple Rule

THEOREM 2.4 The Constant Multiple Rule

If f is a differentiable function and c is a real number, then cf is also differentiable and

$$\frac{d}{dx}[cf(x)] = cf'(x).$$

Proof

$$\begin{aligned}
\frac{d}{dx}[cf(x)] &= \lim_{\Delta x \to 0} \frac{cf(x+\Delta x) - cf(x)}{\Delta x} && \text{Definition of derivative} \\
&= \lim_{\Delta x \to 0} c\left[\frac{f(x+\Delta x) - f(x)}{\Delta x}\right] && \text{Factor out } c. \\
&= c\left[\lim_{\Delta x \to 0} \frac{f(x+\Delta x) - f(x)}{\Delta x}\right] && \text{Property 1, Theorem 1.2} \\
&= cf'(x) && \text{Definition of the derivative of } f
\end{aligned}$$

Informally, the Constant Multiple Rule states that constants can be factored out of the differentiation process, even when the constants appear in the denominator.

$$\frac{d}{dx}[cf(x)] = c\frac{d}{dx}[f(x)] = cf'(x)$$

$$\frac{d}{dx}\left[\frac{f(x)}{c}\right] = \frac{d}{dx}\left[\left(\frac{1}{c}\right)f(x)\right] = \left(\frac{1}{c}\right)\frac{d}{dx}[f(x)] = \left(\frac{1}{c}\right)f'(x)$$

EXAMPLE 5 Using the Constant Multiple Rule

	Function	Derivative
a.	$y = 5x^3$	$\frac{dy}{dx} = \frac{d}{dx}[5x^3] = 5\frac{d}{dx}[x^3] = 5(3)x^2 = 15x^2$
b.	$y = \frac{2}{x}$	$\frac{dy}{dx} = \frac{d}{dx}[2x^{-1}] = 2\frac{d}{dx}[x^{-1}] = 2(-1)x^{-2} = -\frac{2}{x^2}$
c.	$f(t) = \frac{4t^2}{5}$	$f'(t) = \frac{d}{dt}\left[\frac{4}{5}t^2\right] = \frac{4}{5}\frac{d}{dt}[t^2] = \frac{4}{5}(2t) = \frac{8}{5}t$
d.	$y = 2\sqrt{x}$	$\frac{dy}{dx} = \frac{d}{dx}[2x^{1/2}] = 2\left(\frac{1}{2}x^{-1/2}\right) = x^{-1/2} = \frac{1}{\sqrt{x}}$
e.	$y = \frac{1}{2\sqrt[3]{x^2}}$	$y' = \frac{d}{dx}\left[\frac{1}{2}x^{-2/3}\right] = \frac{1}{2}\left(-\frac{2}{3}\right)x^{-5/3} = -\frac{1}{3x^{5/3}}$
f.	$y = -\frac{3x}{2}$	$\frac{dy}{dx} = \frac{d}{dx}\left[-\frac{3}{2}x\right] = -\frac{3}{2}(1) = -\frac{3}{2}$

REMARK Before differentiating functions involving radicals, rewrite the function with rational exponents.

The Constant Multiple Rule and the Power Rule can be combined into one rule. The combination rule is

$$\frac{d}{dx}[cx^n] = cnx^{n-1}.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 6 **Using Parentheses When Differentiating**

	Original Function	Rewrite	Differentiate	Simplify
a.	$y = \frac{5}{2x^3}$	$y = \frac{5}{2}(x^{-3})$	$y' = \frac{5}{2}(-3x^{-4})$	$y' = -\frac{15}{2x^4}$
b.	$y = \frac{5}{(2x)^3}$	$y = \frac{5}{8}(x^{-3})$	$y' = \frac{5}{8}(-3x^{-4})$	$y' = -\frac{15}{8x^4}$
c.	$y = \frac{7}{3x^{-2}}$	$y = \frac{7}{3}(x^2)$	$y' = \frac{7}{3}(2x)$	$y' = \frac{14x}{3}$
d.	$y = \frac{7}{(3x)^{-2}}$	$y = 63(x^2)$	$y' = 63(2x)$	$y' = 126x$

The Sum and Difference Rules

REMARK To help you learn the differentiation rules, write them in words. For example, in words, the Sum Rule says, "the derivative of the sum of two differentiable functions is the sum of their derivatives." You can also write the rules in prime notation, such as

$$(f + g)' = f' + g'.$$

THEOREM 2.5 The Sum and Difference Rules

The sum (or difference) of two differentiable functions f and g is itself differentiable. Moreover, the derivative of $f + g$ (or $f - g$) is the sum (or difference) of the derivatives of f and g.

$$\frac{d}{dx}[f(x) + g(x)] = f'(x) + g'(x) \quad \text{Sum Rule}$$

$$\frac{d}{dx}[f(x) - g(x)] = f'(x) - g'(x) \quad \text{Difference Rule}$$

Proof A proof of the Sum Rule follows from Theorem 1.2. (The Difference Rule can be proved in a similar way.)

$$\begin{aligned}
\frac{d}{dx}[f(x) + g(x)] &= \lim_{\Delta x \to 0} \frac{[f(x + \Delta x) + g(x + \Delta x)] - [f(x) + g(x)]}{\Delta x} \\
&= \lim_{\Delta x \to 0} \frac{f(x + \Delta x) + g(x + \Delta x) - f(x) - g(x)}{\Delta x} \\
&= \lim_{\Delta x \to 0} \left[\frac{f(x + \Delta x) - f(x)}{\Delta x} + \frac{g(x + \Delta x) - g(x)}{\Delta x}\right] \\
&= \lim_{\Delta x \to 0} \frac{f(x + \Delta x) - f(x)}{\Delta x} + \lim_{\Delta x \to 0} \frac{g(x + \Delta x) - g(x)}{\Delta x} \\
&= f'(x) + g'(x)
\end{aligned}$$

The Sum and Difference Rules can be extended to any finite number of functions. For instance, if $F(x) = f(x) + g(x) - h(x)$, then $F'(x) = f'(x) + g'(x) - h'(x)$.

REMARK In Example 7(c), note that before differentiating,

$$\frac{3x^2 - x + 1}{x}$$

was rewritten as

$$3x - 1 + \frac{1}{x}.$$

EXAMPLE 7 **Using the Sum and Difference Rules**

	Function	Derivative
a.	$f(x) = x^3 - 4x + 5$	$f'(x) = 3x^2 - 4$
b.	$g(x) = -\frac{x^4}{2} + 3x^3 - 2x$	$g'(x) = -2x^3 + 9x^2 - 2$
c.	$y = \frac{3x^2 - x + 1}{x} = 3x - 1 + \frac{1}{x}$	$y' = 3 - \frac{1}{x^2} = \frac{3x^2 - 1}{x^2}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

FOR FURTHER INFORMATION
For the outline of a geometric proof of the derivatives of the sine and cosine functions, see the article "The Spider's Spacewalk Derivation of sin′ and cos′" by Tim Hesterberg in *The College Mathematics Journal*. To view this article, go to *MathArticles.com*.

GO DIGITAL





The derivative of the sine function is the cosine function.
Figure 2.18



$\frac{d}{dx}[a \sin x] = a \cos x$
Figure 2.19

Derivatives of the Sine and Cosine Functions

In Section 1.3, you studied the limits

$$\lim_{\Delta x \to 0} \frac{\sin \Delta x}{\Delta x} = 1 \quad \text{and} \quad \lim_{\Delta x \to 0} \frac{1 - \cos \Delta x}{\Delta x} = 0.$$ Theorem 1.9

These two limits can be used to prove differentiation rules for the sine and cosine functions. (The derivatives of the other four trigonometric functions are discussed in Section 2.3.)

THEOREM 2.6 Derivatives of Sine and Cosine Functions

$$\frac{d}{dx}[\sin x] = \cos x \qquad \frac{d}{dx}[\cos x] = -\sin x$$

Proof Here is a proof of the first rule. (The proof of the second rule is left as an exercise [see Exercise 114].) In the proof, note the use of the trigonometric identity $\sin(x + \Delta x) = \sin x \cos \Delta x + \cos x \sin \Delta x$.

$$\begin{aligned}
\frac{d}{dx}[\sin x] &= \lim_{\Delta x \to 0} \frac{\sin(x + \Delta x) - \sin x}{\Delta x} && \text{Definition of derivative} \\
&= \lim_{\Delta x \to 0} \frac{\sin x \cos \Delta x + \cos x \sin \Delta x - \sin x}{\Delta x} && \text{Trigonometric identity} \\
&= \lim_{\Delta x \to 0} \frac{\cos x \sin \Delta x - (\sin x)(1 - \cos \Delta x)}{\Delta x} && \text{Rearrange terms and factor.} \\
&= \lim_{\Delta x \to 0} \left[(\cos x)\left(\frac{\sin \Delta x}{\Delta x}\right) - (\sin x)\left(\frac{1 - \cos \Delta x}{\Delta x}\right) \right] && \text{Write as two fractions.} \\
&= (\cos x)\left(\lim_{\Delta x \to 0} \frac{\sin \Delta x}{\Delta x}\right) - (\sin x)\left(\lim_{\Delta x \to 0} \frac{1 - \cos \Delta x}{\Delta x}\right) && \text{Property of limits} \\
&= (\cos x)(1) - (\sin x)(0) \\
&= \cos x
\end{aligned}$$

This differentiation rule is shown graphically in Figure 2.18. Note that for each x, the *slope* of the sine curve is equal to the value of the cosine. ■

EXAMPLE 8 Derivatives Involving Sines and Cosines

See LarsonCalculus.com for an interactive version of this type of example.

Function	Derivative
a. $y = 2 \sin x$	$y' = 2 \cos x$
b. $y = \frac{\sin x}{2} = \frac{1}{2} \sin x$	$y' = \frac{1}{2} \cos x = \frac{\cos x}{2}$
c. $y = x + \cos x$	$y' = 1 - \sin x$
d. $y = \cos x - \frac{\pi}{3} \sin x$	$y' = -\sin x - \frac{\pi}{3} \cos x$

■

TECHNOLOGY A graphing utility can provide insight into the interpretation of a derivative. For instance, Figure 2.19 shows the graphs of $y = a \sin x$ for $a = \frac{1}{2}, 1, \frac{3}{2}$, and 2. Estimate the slope of each graph at the point $(0, 0)$. Then verify your estimates analytically by evaluating the derivative of each function when $x = 0$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Rates of Change

You have seen how the derivative is used to determine slope. The derivative can also be used to determine the rate of change of one variable with respect to another. Applications involving rates of change, sometimes referred to as instantaneous rates of change, occur in a wide variety of fields. A few examples are population growth rates, production rates, water flow rates, velocity, and acceleration.

A common use for rate of change is to describe the motion of an object moving in a straight line. In such problems, it is customary to use either a horizontal or a vertical line with a designated origin to represent the line of motion. On such lines, movement to the right (or upward) is considered to be in the positive direction, and movement to the left (or downward) is considered to be in the negative direction.

The function s that gives the position (relative to the origin) of an object as a function of time t is called a **position function.** If, over a period of time Δt, the object changes its position by the amount $\Delta s = s(t + \Delta t) - s(t)$, then, by the familiar formula

$$\text{Rate} = \frac{\text{distance}}{\text{time}}$$

the **average velocity** is

$$\frac{\text{Change in distance}}{\text{Change in time}} = \frac{\Delta s}{\Delta t}. \qquad \text{Average velocity}$$



This figure shows the positions of an object moving along a line at time t and shortly later at time $t + \Delta t$. In this case, the line is horizontal.
Figure 2.20

Note that the change in position Δs is also called the **displacement** of the object over the time interval from t to $t + \Delta t$. (See Figure 2.20.)

EXAMPLE 9 Finding Average Velocity of a Falling Object

A billiard ball is dropped from a height of 100 feet. The ball's height s at time t is the position function

$$s = -16t^2 + 100 \qquad \text{Position function}$$

where s is measured in feet and t is measured in seconds. Find the average velocity over each time interval.

a. $[1, 2]$ **b.** $[1, 1.5]$ **c.** $[1, 1.1]$



Time-lapse photograph of a free-falling billiard ball

Richard Megna/Fundamental Photographs

Solution

a. For the interval $[1, 2]$, the object falls from a height of $s(1) = -16(1)^2 + 100 = 84$ feet to a height of $s(2) = -16(2)^2 + 100 = 36$ feet. The average velocity is

$$\frac{\Delta s}{\Delta t} = \frac{36 - 84}{2 - 1} = \frac{-48}{1} = -48 \text{ feet per second.}$$

b. For the interval $[1, 1.5]$, the object falls from a height of 84 feet to a height of $s(1.5) = -16(1.5)^2 + 100 = 64$ feet. The average velocity is

$$\frac{\Delta s}{\Delta t} = \frac{64 - 84}{1.5 - 1} = \frac{-20}{0.5} = -40 \text{ feet per second.}$$

c. For the interval $[1, 1.1]$, the object falls from a height of 84 feet to a height of $s(1.1) = -16(1.1)^2 + 100 = 80.64$ feet. The average velocity is

$$\frac{\Delta s}{\Delta t} = \frac{80.64 - 84}{1.1 - 1} = \frac{-3.36}{0.1} = -33.6 \text{ feet per second.}$$

Note that the average velocities are *negative*, indicating that the object is moving downward. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The average velocity between t_1 and t_2 is the slope of the secant line, and the instantaneous velocity at t_1 is the slope of the tangent line.
Figure 2.21



Velocity is positive when an object is rising and is negative when an object is falling. Notice that the diver moves upward for the first half-second because the velocity is positive for $0 < t < \frac{1}{2}$. When the velocity is 0, the diver has reached the maximum height of the dive.
Figure 2.22

Suppose that in Example 9, you wanted to find the *instantaneous* velocity (or simply the velocity) of the object when $t = 1$. Just as you can approximate the slope of the tangent line by calculating the slope of the secant line, you can approximate the velocity at $t = 1$ by calculating the average velocity over a small interval $[1, 1 + \Delta t]$ (see Figure 2.21). By taking the limit as Δt approaches zero, you obtain the velocity when $t = 1$. Try doing this—you will find that the velocity when $t = 1$ is -32 feet per second.

In general, if $s = s(t)$ is the position function for an object moving along a straight line, then the **velocity** of the object at time t is

$$v(t) = \lim_{\Delta t \to 0} \frac{s(t + \Delta t) - s(t)}{\Delta t} = s'(t). \qquad \text{Velocity function}$$

In other words, the velocity function is the derivative of the position function. Velocity can be negative, zero, or positive. The **speed** of an object is the absolute value of its velocity. Speed cannot be negative.

The position of a free-falling object (neglecting air resistance) under the influence of gravity can be represented by the equation

$$s(t) = -\frac{1}{2}gt^2 + v_0 t + s_0 \qquad \text{Position function}$$

where s_0 is the initial height of the object, v_0 is the initial velocity of the object, and g is the acceleration due to gravity. On Earth, the value of g is approximately 32 feet per second per second or 9.8 meters per second per second.

EXAMPLE 10 Using the Derivative to Find Velocity

At time $t = 0$ seconds, a diver jumps from a platform diving board that is 32 feet above the water (see Figure 2.22). The initial velocity of the diver is 16 feet per second. When does the diver hit the water? What is the diver's velocity at impact?

Solution Begin by writing an equation to represent the position of the diver. Using the position function given above with $g = 32$ feet per second per second, $v_0 = 16$ feet per second, and $s_0 = 32$ feet, you can write

$$\begin{aligned} s(t) &= -\frac{1}{2}(32)t^2 + 16t + 32 \\ &= -16t^2 + 16t + 32. \end{aligned} \qquad \text{Position function}$$

To find the time t when the diver hits the water, let $s = 0$ and solve for t.

$$\begin{aligned} -16t^2 + 16t + 32 &= 0 && \text{Set position function equal to 0.} \\ -16(t + 1)(t - 2) &= 0 && \text{Factor.} \\ t &= -1 \text{ or } 2 && \text{Solve for } t. \end{aligned}$$

Because $t \geq 0$, choose the positive value to conclude that the diver hits the water at $t = 2$ seconds. The velocity at time t is given by the derivative

$$s'(t) = -32t + 16. \qquad \text{Velocity function}$$

So, the velocity at time $t = 2$ is

$$s'(2) = -32(2) + 16 = -48 \text{ feet per second.}$$

In Example 10, note that the unit for $s'(t)$ is the unit for s (feet) divided by the unit for t (seconds). In general, the unit for $f'(x)$ is the unit for f divided by the unit for x.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

2.2 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain how to find the derivative of a constant function.
2. Explain how to find the derivative of the function $f(x) = cx^n$.
3. Identify the derivatives of the sine and cosine functions.
4. Describe the difference between average velocity and velocity.

Estimating Slope In Exercises 5 and 6, use the graph to estimate the slope of the tangent line to $y = x^n$ at the point (1, 1). Verify your answer analytically. To print an enlarged copy of the graph, go to *MathGraphs.com*.

5. (a) $y = x^{1/2}$



(b) $y = x^3$



6. (a) $y = x^{-1/2}$



(b) $y = x^{-1}$



Finding a Derivative In Exercises 7–26, use differentiation rules to find the derivative of the function.

7. $y = 12$
8. $f(x) = -9$
9. $y = x^7$
10. $y = x^{12}$
11. $y = \dfrac{1}{x^5}$
12. $y = \dfrac{3}{x^7}$
13. $f(x) = \sqrt[9]{x}$
14. $g(x) = \sqrt[4]{x}$
15. $f(x) = x + 11$
16. $g(x) = 6x + 3$
17. $f(t) = -3t^2 + 2t - 4$
18. $y = t^2 - 3t + 1$
19. $g(x) = x^2 + 4x^3$
20. $y = 4x - 3x^3$
21. $s(t) = t^3 + 5t^2 - 3t + 8$
22. $y = 2x^3 + 6x^2 - 1$
23. $y = \dfrac{\pi}{2}\sin\theta$
24. $g(t) = \pi\cos t$
25. $y = x^2 - \frac{1}{2}\cos x$
26. $y = 7x^4 + 2\sin x$

Rewriting a Function Before Differentiating In Exercises 27–30, complete the table to find the derivative of the function.

Function	Rewrite	Differentiate	Simplify
27. $y = \dfrac{2}{7x^4}$			
28. $y = \dfrac{8}{5x^{-5}}$			
29. $y = \dfrac{6}{(5x)^3}$			
30. $y = \dfrac{3}{(2x)^{-2}}$			

Finding the Slope of a Graph In Exercises 31–38, find the slope of the graph of the function at the given point. Use the *derivative* feature of a graphing utility to verify your results.

Function	Point
31. $f(x) = \dfrac{8}{x^2}$	(2, 2)
32. $f(t) = 2 - \dfrac{4}{t}$	(4, 1)
33. $f(x) = -\frac{1}{2} + \frac{7}{5}x^3$	$\left(0, -\frac{1}{2}\right)$
34. $y = 2x^4 - 3$	(1, −1)
35. $y = (4x + 1)^2$	(0, 1)
36. $f(x) = 2(x - 4)^2$	(2, 8)
37. $f(\theta) = 4\sin\theta - \theta$	(0, 0)
38. $g(t) = -2\cos t + 5$	$(\pi, 7)$

Finding a Derivative In Exercises 39–54, find the derivative of the function.

39. $f(x) = x^2 + 5 - 3x^{-2}$
40. $f(x) = x^3 - 2x + 3x^{-3}$
41. $g(t) = t^2 - \dfrac{4}{t^3}$
42. $f(x) = 8x + \dfrac{3}{x^2}$
43. $f(x) = \dfrac{x^3 - 3x^2 + 4}{x^2}$
44. $h(x) = \dfrac{4x^3 + 2x + 5}{x}$
45. $g(t) = \dfrac{3t^2 + 4t - 8}{t^{3/2}}$
46. $h(s) = \dfrac{s^5 + 2s + 6}{s^{1/3}}$
47. $y = x(x^2 + 1)$
48. $y = x^2(2x^2 - 3x)$
49. $f(x) = \sqrt{x} - 6\sqrt[3]{x}$
50. $f(t) = t^{2/3} - t^{1/3} + 4$
51. $f(x) = 6\sqrt{x} + 5\cos x$
52. $f(x) = \dfrac{2}{\sqrt[3]{x}} + 3\cos x$
53. $y = \dfrac{1}{(3x)^{-2}} - 5\cos x$
54. $y = \dfrac{3}{(2x)^3} + 2\sin x$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding an Equation of a Tangent Line **In Exercises 55–58, (a) find an equation of the tangent line to the graph of the function at the given point, (b) sketch a graph of the function and its tangent line at the point, and (c) use the *tangent* feature of a graphing utility to verify your results.**

Function	Point
55. $f(x) = -2x^4 + 5x^2 - 3$	$(1, 0)$
56. $y = x^3 - 3x$	$(2, 2)$
57. $f(x) = \dfrac{2}{\sqrt[4]{x^3}}$	$(1, 2)$
58. $y = (x - 2)(x^2 + 3x)$	$(1, -4)$

Horizontal Tangent Line **In Exercises 59–64, determine the points (if any) at which the graph of the function has a horizontal tangent line.**

59. $y = x^4 - 2x^2 + 3$
60. $y = x^3 + x$
61. $y = \dfrac{1}{x^2}$
62. $y = x^2 + 9$
63. $y = x + \sin x, \quad 0 \le x < 2\pi$
64. $y = \sqrt{3}x + 2\cos x, \quad 0 \le x < 2\pi$

Finding a Value **In Exercises 65–68, find k such that the line is tangent to the graph of the function.**

Function	Line
65. $f(x) = k - x^2$	$y = -6x + 1$
66. $f(x) = kx^2$	$y = -2x + 3$
67. $f(x) = \dfrac{k}{x}$	$y = -\dfrac{3}{4}x + 3$
68. $f(x) = k\sqrt{x}$	$y = x + 4$

Exploring Concepts

In Exercises 69–72, the relationship between f and g is given. Explain the relationship between f' and g'.

69. $g(x) = f(x) + 6$
70. $g(x) = 2f(x)$
71. $g(x) = -5f(x)$
72. $g(x) = 3f(x) - 1$

In Exercises 73 and 74, the graphs of a function f and its derivative f' are shown on the same set of coordinate axes. Label the graphs as f or f' and write a short paragraph stating the criteria you used in making your selection. To print an enlarged copy of the graph, go to *MathGraphs.com*.

73.



74.



75. **Sketching a Graph** Sketch the graph of a function f such that $f' > 0$ for all x and the rate of change of the function is decreasing.

76. **HOW DO YOU SEE IT?** Use the graph of f to answer each question. To print an enlarged copy of the graph, go to *MathGraphs.com*.



(a) Between which two consecutive points is the average rate of change of the function greatest?

(b) Is the average rate of change of the function between A and B greater than or less than the instantaneous rate of change at B?

(c) Sketch a tangent line to the graph between C and D such that the slope of the tangent line is the same as the average rate of change of the function between C and D.

77. **Finding Equations of Tangent Lines** Sketch the graphs of $y = x^2$ and $y = -x^2 + 6x - 5$, and sketch the two lines that are tangent to both graphs. Find equations of these lines.

78. **Tangent Lines** Show that the graphs of the two equations

$$y = x \quad \text{and} \quad y = \frac{1}{x}$$

have tangent lines that are perpendicular to each other at their point of intersection.

79. **Horizontal Tangent Line** Show that the graph of the function

$$f(x) = 3x + \sin x + 2$$

does not have a horizontal tangent line.

80. **Tangent Line** Show that the graph of the function

$$f(x) = x^5 + 3x^3 + 5x$$

does not have a tangent line with a slope of 3.

Finding an Equation of a Tangent Line **In Exercises 81 and 82, find an equation of the tangent line to the graph of the function f through the point (x_0, y_0) not on the graph. To find the point of tangency (x, y) on the graph of f, solve the equation**

$$f'(x) = \frac{y_0 - y}{x_0 - x}.$$

81. $f(x) = \sqrt{x}$, $(x_0, y_0) = (-4, 0)$
82. $f(x) = \dfrac{2}{x}$, $(x_0, y_0) = (5, 0)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

83. Linear Approximation Consider the function $f(x) = x^{3/2}$ with the solution point (4, 8).

(a) Use a graphing utility to graph f. Use the *zoom* feature to obtain successive magnifications of the graph in the neighborhood of the point (4, 8). After zooming in a few times, the graph should appear nearly linear. Use the *trace* feature to determine the coordinates of a point near (4, 8). Find an equation of the secant line $S(x)$ through the two points.

(b) Find the equation of the line $T(x) = f'(4)(x - 4) + f(4)$ tangent to the graph of f passing through the given point. Why are the linear functions S and T nearly the same?

(c) Use a graphing utility to graph f and T on the same set of coordinate axes. Note that T is a good approximation of f when x is close to 4. What happens to the accuracy of the approximation as you move farther away from the point of tangency?

(d) Demonstrate the conclusion in part (c) by completing the table.

Δx	-3	-2	-1	-0.5	-0.1	0
$f(4 + \Delta x)$						
$T(4 + \Delta x)$						

Δx	0.1	0.5	1	2	3
$f(4 + \Delta x)$					
$T(4 + \Delta x)$					

84. Linear Approximation Repeat Exercise 83 for the function $f(x) = x^3$, where $T(x)$ is the line tangent to the graph at the point (1, 1). Explain why the accuracy of the linear approximation decreases more rapidly than in Exercise 83.

True or False? **In Exercises 85–90, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

85. If $f'(x) = g'(x)$, then $f(x) = g(x)$.

86. If $y = x^{a+2} + bx$, then $dy/dx = (a + 2)x^{a+1} + b$.

87. If $y = \pi^2$, then $dy/dx = 2\pi$.

88. If $f(x) = -g(x) + b$, then $f'(x) = -g'(x)$.

89. If $f(x) = 0$, then $f'(x)$ is undefined.

90. If $f(x) = \dfrac{1}{x^n}$, then $f'(x) = \dfrac{1}{nx^{n-1}}$.

Finding Rates of Change **In Exercises 91–94, find the average rate of change of the function over the given interval. Compare this average rate of change with the instantaneous rates of change at the endpoints of the interval.**

91. $f(t) = 3t + 5$, $[1, 2]$

92. $f(t) = t^2 - 7$, $[3, 3.1]$

93. $f(x) = \dfrac{-1}{x}$, $[1, 2]$

94. $f(x) = \sin x$, $\left[0, \dfrac{\pi}{6}\right]$

Vertical Motion **In Exercises 95 and 96, use the position function $s(t) = -16t^2 + v_0t + s_0$ for free-falling objects.**

95. A coin is dropped from the top of a building that is 1362 feet tall.

(a) Determine the position and velocity functions for the coin.

(b) Determine the average velocity on the interval $[1, 2]$.

(c) Find the instantaneous velocities when $t = 1$ and $t = 2$.

(d) Find the time required for the coin to reach ground level.

(e) Find the velocity of the coin at impact.

96. A ball is thrown straight down from the top of a 220-foot building with an initial velocity of -22 feet per second. What is its velocity after 3 seconds? What is its velocity after falling 108 feet?

Vertical Motion **In Exercises 97 and 98, use the position function $s(t) = -4.9t^2 + v_0t + s_0$ for free-falling objects.**

97. A projectile is shot upward from the surface of Earth with an initial velocity of 120 meters per second. What is its velocity after 5 seconds? After 10 seconds?

98. A rock is dropped from the edge of a cliff that is 214 meters above water.

(a) Determine the position and velocity functions for the rock.

(b) Determine the average velocity on the interval $[2, 5]$.

(c) Find the instantaneous velocities when $t = 2$ and $t = 5$.

(d) Find the time required for the rock to reach the surface of the water.

(e) Find the velocity of the rock at impact.

99. Think About It The graph of the position function (see figure) represents the distance in miles that a person drives during a 10-minute trip to work. Make a sketch of the corresponding velocity function.



Figure for 99



Figure for 100

100. Think About It The graph of the velocity function (see figure) represents the velocity in miles per hour a person drives during a 10-minute trip to work. Make a sketch of the corresponding position function.

101. Volume The volume of a cube with sides of length s is given by $V = s^3$. Find the rate of change of the volume with respect to s when $s = 6$ centimeters.

102. Area The area of a square with sides of length s is given by $A = s^2$. Find the rate of change of the area with respect to s when $s = 6$ meters.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

103. Modeling Data

The stopping distance of an automobile, on dry, level pavement, traveling at a speed v (in kilometers per hour) is the distance R (in meters) the car travels during the reaction time of the driver plus the distance B (in meters) the car travels after the brakes are applied (see figure). The table shows the results of an experiment.



Speed, v	20	40	60	80	100
Reaction Time Distance, R	8.3	16.7	25.0	33.3	41.7
Braking Time Distance, B	2.3	9.0	20.2	35.8	55.9

(a) Use the regression capabilities of a graphing utility to find a linear model for reaction time distance R.

(b) Use the regression capabilities of a graphing utility to find a quadratic model for braking time distance B.

(c) Determine the polynomial giving the total stopping distance T.

(d) Use a graphing utility to graph the functions R, B, and T in the same viewing window.

(e) Find the derivative of T and the rates of change of the total stopping distance for $v = 40$, $v = 80$, and $v = 100$.

(f) Use the results of this exercise to draw conclusions about the total stopping distance as speed increases.

104. Fuel Cost A car is driven 15,000 miles a year and gets x miles per gallon. Assume that the average fuel cost is \$3.48 per gallon. Find the annual cost of fuel C as a function of x and use this function to complete the table.

x	10	15	20	25	30	35	40
C							
dC/dx							

Who would benefit more from a one-mile-per-gallon increase in fuel efficiency—the driver of a car that gets 15 miles per gallon or the driver of a car that gets 35 miles per gallon? Explain.

105. Velocity Verify that the average velocity over the time interval $[t_0 - \Delta t, t_0 + \Delta t]$ is the same as the instantaneous velocity at $t = t_0$ for the position function

$$s(t) = -\frac{1}{2}at^2 + c.$$

106. Inventory Management The annual inventory cost C for a manufacturer is

$$C = \frac{1{,}008{,}000}{Q} + 6.3Q$$

where Q is the order size when the inventory is replenished. Find the change in annual cost when Q is increased from 350 to 351 and compare this with the instantaneous rate of change when $Q = 350$.

107. Finding an Equation of a Parabola Find an equation of the parabola $y = ax^2 + bx + c$ that passes through $(0, 1)$ and is tangent to the line $y = x - 1$ at $(1, 0)$.

108. Proof Let (a, b) be an arbitrary point on the graph of $y = 1/x$, $x > 0$. Prove that the area of the triangle formed by the tangent line through (a, b) and the coordinate axes is 2.

109. Tangent Lines Find equations of the tangent lines to the graph of the curve $y = x^3 - 9x$ through the point $(1, -9)$ not on the graph.

110. Tangent Lines Find equations of the tangent lines to the graph of the parabola $y = x^2$ through the given point not on the graph.

(a) $(0, a)$ (b) $(a, 0)$

Are there any restrictions on the constant a?

Making a Function Differentiable **In Exercises 111 and 112, find a and b such that f is differentiable everywhere.**

111. $f(x) = \begin{cases} ax^3, & x \le 2 \\ x^2 + b, & x > 2 \end{cases}$

112. $f(x) = \begin{cases} \cos x, & x < 0 \\ ax + b, & x \ge 0 \end{cases}$

113. Determining Differentiability Where are the functions $f_1(x) = |\sin x|$ and $f_2(x) = \sin|x|$ differentiable?

114. Proof Prove that $\frac{d}{dx}[\cos x] = -\sin x$.

FOR FURTHER INFORMATION For a geometric interpretation of the derivatives of trigonometric functions, see the article "Sines and Cosines of the Times" by Victor J. Katz in *Math Horizons*. To view this article, go to *MathArticles.com*.

PUTNAM EXAM CHALLENGE

115. Find all differentiable functions $f: \mathbb{R} \to \mathbb{R}$ such that

$$f'(x) = \frac{f(x + n) - f(x)}{n}$$

for all real numbers x and all positive integers n.

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Tumar/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

2.3 Product and Quotient Rules and Higher-Order Derivatives

GO DIGITAL

- Find the derivative of a function using the Product Rule.
- Find the derivative of a function using the Quotient Rule.
- Find the derivative of a trigonometric function.
- Find a higher-order derivative of a function.

The Product Rule

In Section 2.2, you learned that the derivative of the sum of two functions is simply the sum of their derivatives. The rules for the derivatives of the product and quotient of two functions are not as simple.

REMARK A version of the Product Rule that some people prefer is

$$\frac{d}{dx}[f(x)g(x)] = f'(x)g(x) + f(x)g'(x).$$

The advantage of this form is that it generalizes easily to products of three or more factors.

THEOREM 2.7 The Product Rule

The product of two differentiable functions f and g is itself differentiable. Moreover, the derivative of fg is the first function times the derivative of the second, plus the second function times the derivative of the first.

$$\frac{d}{dx}[f(x)g(x)] = f(x)g'(x) + g(x)f'(x)$$

Proof Some mathematical proofs, such as the proof of the Sum Rule, are straightforward. Others involve clever steps that may appear unmotivated to a reader. This proof involves such a step—subtracting and adding the same quantity. In this case, the quantity is $f(x + \Delta x)g(x)$. After this step, note how the functions f and g are separated by rewriting the fraction as the sum of two fractions and then factoring the numerators.

$$\begin{aligned}
\frac{d}{dx}[f(x)g(x)] &= \lim_{\Delta x\to 0}\frac{f(x+\Delta x)g(x+\Delta x) - f(x)g(x)}{\Delta x}\\
&= \lim_{\Delta x\to 0}\frac{f(x+\Delta x)g(x+\Delta x) - f(x+\Delta x)g(x) + f(x+\Delta x)g(x) - f(x)g(x)}{\Delta x}\\
&= \lim_{\Delta x\to 0}\left[f(x+\Delta x)\frac{g(x+\Delta x)-g(x)}{\Delta x} + g(x)\frac{f(x+\Delta x)-f(x)}{\Delta x}\right]\\
&= \lim_{\Delta x\to 0}\left[f(x+\Delta x)\frac{g(x+\Delta x)-g(x)}{\Delta x}\right] + \lim_{\Delta x\to 0}\left[g(x)\frac{f(x+\Delta x)-f(x)}{\Delta x}\right]\\
&= \lim_{\Delta x\to 0} f(x+\Delta x)\cdot \overbrace{\lim_{\Delta x\to 0}\frac{g(x+\Delta x)-g(x)}{\Delta x}}^{\text{Definition of } g'(x)} + \lim_{\Delta x\to 0} g(x)\cdot \overbrace{\lim_{\Delta x\to 0}\frac{f(x+\Delta x)-f(x)}{\Delta x}}^{\text{Definition of } f'(x)}\\
&= f(x)g'(x) + g(x)f'(x)
\end{aligned}$$

In the last step, note that because f is differentiable at x, you know from Theorem 2.1 that f is continuous at x. So, $\lim_{\Delta x\to 0} f(x+\Delta x) = f(x)$. ■

THE PRODUCT RULE

When Leibniz originally wrote a formula for the Product Rule, he was motivated by the expression

$$(x + dx)(y + dy) - xy$$

from which he subtracted $dx\,dy$ (as being negligible) and obtained the differential form $x\,dy + y\,dx$. This derivation resulted in the traditional form of the Product Rule. *(Source: The History of Mathematics by David M. Burton)*

The Product Rule can be extended to cover products involving more than two factors. For example, if f, g, and h are differentiable functions of x, then

$$\frac{d}{dx}[f(x)g(x)h(x)] = f'(x)g(x)h(x) + f(x)g'(x)h(x) + f(x)g(x)h'(x).$$

(See Exercise 139.) So, the derivative of $y = x^2 \sin x \cos x$ is

$$\begin{aligned}
y' &= 2x\sin x\cos x + x^2\cos x\cos x + x^2(\sin x)(-\sin x)\\
&= 2x\sin x\cos x + x^2(\cos^2 x - \sin^2 x).
\end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

The derivative of a product of two functions is not (in general) given by the product of the derivatives of the two functions. To demonstrate this, try comparing the product of the derivatives of

$$f(x) = 3x - 2x^2$$

and

$$g(x) = 5 + 4x$$

with the derivative in Example 1.

EXAMPLE 1 Using the Product Rule

Find the derivative of $h(x) = (3x - 2x^2)(5 + 4x)$.

Solution

$$\begin{aligned} h'(x) &= \overbrace{(3x - 2x^2)}^{\text{First}} \overbrace{\frac{d}{dx}[5 + 4x]}^{\text{Derivative of second}} + \overbrace{(5 + 4x)}^{\text{Second}} \overbrace{\frac{d}{dx}[3x - 2x^2]}^{\text{Derivative of first}} && \text{Apply Product Rule.} \\ &= (3x - 2x^2)(4) + (5 + 4x)(3 - 4x) && \text{Find the derivatives.} \\ &= (12x - 8x^2) + (15 - 8x - 16x^2) && \text{Multiply.} \\ &= -24x^2 + 4x + 15 && \text{Simplify.} \end{aligned}$$

In Example 1, you have the option of finding the derivative with or without the Product Rule. To find the derivative without the Product Rule, you can write

$$\begin{aligned} D_x[(3x - 2x^2)(5 + 4x)] &= D_x[-8x^3 + 2x^2 + 15x] \\ &= -24x^2 + 4x + 15. \end{aligned}$$

In the next example, you must use the Product Rule.

EXAMPLE 2 Using the Product Rule

Find the derivative of $y = 3x^2 \sin x$.

Solution

$$\begin{aligned} \frac{d}{dx}[3x^2 \sin x] &= 3x^2 \frac{d}{dx}[\sin x] + \sin x \frac{d}{dx}[3x^2] && \text{Apply Product Rule.} \\ &= 3x^2 \cos x + (\sin x)(6x) && \text{Find the derivatives.} \\ &= 3x^2 \cos x + 6x \sin x \\ &= 3x(x \cos x + 2 \sin x) && \text{Factor.} \end{aligned}$$

REMARK In Example 3, notice that you use the Product Rule when both factors of the product are variable, and you use the Constant Multiple Rule when one of the factors is a constant.

EXAMPLE 3 Using the Product Rule

Find the derivative of $y = 2x \cos x - 2 \sin x$.

Solution

$$\begin{aligned} \frac{dy}{dx} &= \overbrace{(2x)\left(\frac{d}{dx}[\cos x]\right) + (\cos x)\left(\frac{d}{dx}[2x]\right)}^{\text{Product Rule}} \overbrace{- 2\frac{d}{dx}[\sin x]}^{\text{Constant Multiple Rule}} \\ &= (2x)(-\sin x) + (\cos x)(2) - 2(\cos x) && \text{Find the derivatives.} \\ &= -2x \sin x && \text{Simplify.} \end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The Quotient Rule

THEOREM 2.8 The Quotient Rule

The quotient f/g of two differentiable functions f and g is itself differentiable at all values of x for which $g(x) \neq 0$. Moreover, the derivative of f/g is given by the denominator times the derivative of the numerator minus the numerator times the derivative of the denominator, all divided by the square of the denominator.

$$\frac{d}{dx}\left[\frac{f(x)}{g(x)}\right] = \frac{g(x)f'(x) - f(x)g'(x)}{[g(x)]^2}, \quad g(x) \neq 0$$

REMARK From the Quotient Rule, note that the derivative of a quotient is not (in general) the quotient of the derivatives.

Proof As with the proof of Theorem 2.7, the key to this proof is subtracting and adding the same quantity. In this case, the quantity is $f(x)g(x)$.

$$\begin{aligned}
\frac{d}{dx}\left[\frac{f(x)}{g(x)}\right] &= \lim_{\Delta x \to 0} \frac{\dfrac{f(x+\Delta x)}{g(x+\Delta x)} - \dfrac{f(x)}{g(x)}}{\Delta x} && \text{Definition of derivative} \\
&= \lim_{\Delta x \to 0} \frac{g(x)f(x+\Delta x) - f(x)g(x+\Delta x)}{\Delta x g(x)g(x+\Delta x)} \\
&= \lim_{\Delta x \to 0} \frac{g(x)f(x+\Delta x) - f(x)g(x) + f(x)g(x) - f(x)g(x+\Delta x)}{\Delta x g(x)g(x+\Delta x)} \\
&= \frac{\lim_{\Delta x \to 0} \dfrac{g(x)[f(x+\Delta x) - f(x)]}{\Delta x} - \lim_{\Delta x \to 0} \dfrac{f(x)[g(x+\Delta x) - g(x)]}{\Delta x}}{\lim_{\Delta x \to 0}[g(x)g(x+\Delta x)]} \\
&= \frac{g(x)\overbrace{\left[\lim_{\Delta x \to 0} \frac{f(x+\Delta x) - f(x)}{\Delta x}\right]}^{\text{Definition of } f'(x)} - f(x)\overbrace{\left[\lim_{\Delta x \to 0} \frac{g(x+\Delta x) - g(x)}{\Delta x}\right]}^{\text{Definition of } g'(x)}}{\lim_{\Delta x \to 0}[g(x)g(x+\Delta x)]} \\
&= \frac{g(x)f'(x) - f(x)g'(x)}{[g(x)]^2}
\end{aligned}$$

In the last step, note that because g is differentiable at x, you know from Theorem 2.1 that g is continuous at x. So, $\lim_{\Delta x \to 0} g(x + \Delta x) = g(x)$. ■

EXAMPLE 4 Using the Quotient Rule

Find the derivative of $y = \dfrac{5x - 2}{x^2 + 1}$.

Solution

$$\begin{aligned}
\frac{d}{dx}\left[\frac{5x-2}{x^2+1}\right] &= \frac{(x^2+1)\dfrac{d}{dx}[5x-2] - (5x-2)\dfrac{d}{dx}[x^2+1]}{(x^2+1)^2} && \text{Apply Quotient Rule.} \\
&= \frac{(x^2+1)(5) - (5x-2)(2x)}{(x^2+1)^2} && \text{Find the derivatives.} \\
&= \frac{(5x^2+5) - (10x^2-4x)}{(x^2+1)^2} && \text{Multiply.} \\
&= \frac{-5x^2+4x+5}{(x^2+1)^2} && \text{Simplify.}
\end{aligned}$$

■

TECHNOLOGY A graphing utility can be used to compare the graph of a function with the graph of its derivative. For instance, in the figure below, the graph of the function in Example 4 appears to have two points that have horizontal tangent lines. What are the values of y' at these two points?



Graphical comparison of a function and its derivative

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Note the use of parentheses in Example 4. A liberal use of parentheses is recommended for *all* types of differentiation problems. For instance, with the Quotient Rule, it is a good idea to enclose all factors and derivatives in parentheses and to pay special attention to the subtraction required in the numerator.

When differentiation rules were introduced in the preceding section, the need for rewriting *before* differentiating was emphasized. The next example illustrates this point with the Quotient Rule.

EXAMPLE 5 Rewriting Before Differentiating

Find an equation of the tangent line to the graph of $f(x) = \dfrac{3 - (1/x)}{x + 5}$ at $(-1, 1)$.

Solution Begin by rewriting the function.

$$f(x) = \frac{3 - (1/x)}{x + 5}$$ Write original function.

$$= \frac{x\left(3 - \frac{1}{x}\right)}{x(x + 5)}$$ Multiply numerator and denominator by x.

$$= \frac{3x - 1}{x^2 + 5x}$$ Rewrite.

Next, apply the Quotient Rule.

$$f'(x) = \frac{(x^2 + 5x)(3) - (3x - 1)(2x + 5)}{(x^2 + 5x)^2}$$ Quotient Rule

$$= \frac{(3x^2 + 15x) - (6x^2 + 13x - 5)}{(x^2 + 5x)^2}$$

$$= \frac{-3x^2 + 2x + 5}{(x^2 + 5x)^2}$$ Simplify.

To find the slope at $(-1, 1)$, evaluate $f'(-1)$.

$$f'(-1) = 0$$ Slope of graph at $(-1, 1)$

Then, using the point-slope form of the equation of a line, you can determine that the equation of the tangent line at $(-1, 1)$ is $y = 1$. See Figure 2.23.



The line $y = 1$ is tangent to the graph of f at the point $(-1, 1)$.
Figure 2.23

Not every quotient needs to be differentiated by the Quotient Rule. For instance, each quotient in the next example can be considered as the product of a constant times a function of x. In such cases, it is more convenient to use the Constant Multiple Rule.

EXAMPLE 6 Using the Constant Multiple Rule

	Original Function	Rewrite	Differentiate	Simplify
a.	$y = \dfrac{x^2 + 3x}{6}$	$y = \dfrac{1}{6}(x^2 + 3x)$	$y' = \dfrac{1}{6}(2x + 3)$	$y' = \dfrac{2x + 3}{6}$
b.	$y = \dfrac{5x^4}{8}$	$y = \dfrac{5}{8}x^4$	$y' = \dfrac{5}{8}(4x^3)$	$y' = \dfrac{5}{2}x^3$
c.	$y = \dfrac{-3(3x - 2x^{1/2})}{7x}$	$y = -\dfrac{3}{7}(3 - 2x^{-1/2})$	$y' = -\dfrac{3}{7}(x^{-3/2})$	$y' = -\dfrac{3}{7x^{3/2}}$
d.	$y = \dfrac{9}{5x^2}$	$y = \dfrac{9}{5}(x^{-2})$	$y' = \dfrac{9}{5}(-2x^{-3})$	$y' = -\dfrac{18}{5x^3}$

REMARK To see the benefit of using the Constant Multiple Rule for some quotients, use the Quotient Rule to differentiate the functions in Example 6. You should obtain the same results but with more work.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

In Section 2.2, the Power Rule was proved only for the case in which the exponent n is a positive integer greater than 1. The next example extends the proof to include negative integer exponents.

EXAMPLE 7 **Power Rule: Negative Integer Exponents**

If n is a negative integer, then there exists a positive integer k such that $n = -k$. So, by the Quotient Rule, you can write

$$\begin{aligned}
\frac{d}{dx}[x^n] &= \frac{d}{dx}\left[\frac{1}{x^k}\right] && x^n = x^{-k} = \frac{1}{x^k} \\
&= \frac{x^k(0) - (1)(kx^{k-1})}{(x^k)^2} && \text{Quotient Rule and Power Rule} \\
&= \frac{0 - kx^{k-1}}{x^{2k}} \\
&= -kx^{-k-1} && \frac{x^{k-1}}{x^{2k}} = x^{k-1-2k} = x^{-k-1} \\
&= nx^{n-1}. && n = -k
\end{aligned}$$

So, the Power Rule

$$\frac{d}{dx}[x^n] = nx^{n-1}$$ Power Rule

is valid for any integer n. In Exercise 73 in Section 2.5, you are asked to prove the case for which n is any rational number. ■

Derivatives of Trigonometric Functions

Knowing the derivatives of the sine and cosine functions, you can use the Quotient Rule to find the derivatives of the four remaining trigonometric functions.

THEOREM 2.9 Derivatives of Trigonometric Functions

$$\frac{d}{dx}[\tan x] = \sec^2 x \qquad \frac{d}{dx}[\cot x] = -\csc^2 x$$

$$\frac{d}{dx}[\sec x] = \sec x \tan x \qquad \frac{d}{dx}[\csc x] = -\csc x \cot x$$

Proof Considering $\tan x = (\sin x)/(\cos x)$ and applying the Quotient Rule, you obtain

$$\begin{aligned}
\frac{d}{dx}[\tan x] &= \frac{d}{dx}\left[\frac{\sin x}{\cos x}\right] \\
&= \frac{(\cos x)(\cos x) - (\sin x)(-\sin x)}{\cos^2 x} && \text{Apply Quotient Rule.} \\
&= \frac{\cos^2 x + \sin^2 x}{\cos^2 x} && \text{Multiply.} \\
&= \frac{1}{\cos^2 x} && \text{Pythagorean identity} \\
&= \sec^2 x. && \text{Reciprocal identity}
\end{aligned}$$

The proofs of the other three parts of the theorem are left as an exercise (see Exercise 89). ■

REMARK In the proof of Theorem 2.9, note the use of the trigonometric identities

$$\sin^2 x + \cos^2 x = 1$$

and

$$\sec x = \frac{1}{\cos x}.$$

These trigonometric identities and others are listed in Section P.4 and on the formula cards for this text.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 8 Differentiating Trigonometric Functions

See LarsonCalculus.com for an interactive version of this type of example.

Function	Derivative
a. $y = x - \tan x$	$\frac{dy}{dx} = 1 - \sec^2 x$
b. $y = x \sec x$	$y' = x(\sec x \tan x) + (\sec x)(1)$ $= (\sec x)(1 + x \tan x)$

REMARK Because of trigonometric identities, the derivative of a trigonometric function can take many forms. This presents a challenge when you are trying to match your answers to those given in the back of the text.

EXAMPLE 9 Different Forms of a Derivative

Differentiate both forms of

$$y = \frac{1 - \cos x}{\sin x} = \csc x - \cot x.$$

Solution

First form: $y = \dfrac{1 - \cos x}{\sin x}$ Write first form.

$$y' = \frac{(\sin x)(\sin x) - (1 - \cos x)(\cos x)}{\sin^2 x}$$ Quotient Rule

$$= \frac{\sin^2 x - \cos x + \cos^2 x}{\sin^2 x}$$ Multiply.

$$= \frac{1 - \cos x}{\sin^2 x}$$ $\sin^2 x + \cos^2 x = 1$

Second form: $y = \csc x - \cot x$ Write second form.

$y' = -\csc x \cot x + \csc^2 x$ Derivative with respect to x

To show that the two derivatives are equal, you can write

$$\frac{1 - \cos x}{\sin^2 x} = \frac{1}{\sin^2 x} - \frac{\cos x}{\sin^2 x}$$ Write as separate fractions.

$$= \frac{1}{\sin^2 x} - \left(\frac{1}{\sin x}\right)\left(\frac{\cos x}{\sin x}\right)$$ Product of fractions

$$= \csc^2 x - \csc x \cot x.$$ Reciprocal and quotient identities ■

The summary below shows that much of the work in obtaining a simplified form of a derivative occurs *after* differentiating. Note that two characteristics of a simplified form are the absence of negative exponents and the combining of like terms.

	$f'(x)$ After Differentiating	$f'(x)$ After Simplifying
Example 1	$(3x - 2x^2)(4) + (5 + 4x)(3 - 4x)$	$-24x^2 + 4x + 15$
Example 3	$(2x)(-\sin x) + (\cos x)(2) - 2(\cos x)$	$-2x \sin x$
Example 4	$\frac{(x^2 + 1)(5) - (5x - 2)(2x)}{(x^2 + 1)^2}$	$\frac{-5x^2 + 4x + 5}{(x^2 + 1)^2}$
Example 5	$\frac{(x^2 + 5x)(3) - (3x - 1)(2x + 5)}{(x^2 + 5x)^2}$	$\frac{-3x^2 + 2x + 5}{(x^2 + 5x)^2}$
Example 9	$\frac{(\sin x)(\sin x) - (1 - \cos x)(\cos x)}{\sin^2 x}$	$\frac{1 - \cos x}{\sin^2 x}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Higher-Order Derivatives

Just as you can obtain a velocity function by differentiating a position function, you can obtain an **acceleration** function by differentiating a velocity function. Another way of looking at this is that you can obtain an acceleration function by differentiating a position function *twice*.

$$\begin{aligned} s(t) &\quad \text{Position function} \\ v(t) = s'(t) &\quad \text{Velocity function} \\ a(t) = v'(t) = s''(t) &\quad \text{Acceleration function} \end{aligned}$$

The function $a(t)$ is the **second derivative** of $s(t)$ and is denoted by $s''(t)$.

The second derivative is an example of a **higher-order derivative.** You can define derivatives of any positive integer order. For instance, the **third derivative** is the derivative of the second derivative. Higher-order derivatives are denoted as shown below.

First derivative:	y',	$f'(x)$,	$\frac{dy}{dx}$,	$\frac{d}{dx}[f(x)]$,	$D_x[y]$
Second derivative:	y'',	$f''(x)$,	$\frac{d^2y}{dx^2}$,	$\frac{d^2}{dx^2}[f(x)]$,	$D_x^2[y]$
Third derivative:	y''',	$f'''(x)$,	$\frac{d^3y}{dx^3}$,	$\frac{d^3}{dx^3}[f(x)]$,	$D_x^3[y]$
Fourth derivative:	$y^{(4)}$,	$f^{(4)}(x)$,	$\frac{d^4y}{dx^4}$,	$\frac{d^4}{dx^4}[f(x)]$,	$D_x^4[y]$
⋮					
nth derivative:	$y^{(n)}$,	$f^{(n)}(x)$,	$\frac{d^ny}{dx^n}$,	$\frac{d^n}{dx^n}[f(x)]$,	$D_x^n[y]$

REMARK The second derivative of a function is the derivative of the first derivative of the function.

Vadim Sadovski/Shutterstock.com

The moon's mass is 7.349×10^{22} kilograms, and Earth's mass is 5.976×10^{24} kilograms. The moon's radius is 1737 kilometers, and Earth's radius is 6378 kilometers. Because the gravitational force on the surface of a planet is directly proportional to its mass and inversely proportional to the square of its radius, the ratio of the gravitational force on Earth to the gravitational force on the moon is

$$\frac{(5.976 \times 10^{24})/6378^2}{(7.349 \times 10^{22})/1737^2} \approx 6.0.$$

EXAMPLE 10 Finding the Acceleration Due to Gravity

Because the moon has no atmosphere, a falling object on the moon encounters no air resistance. In 1971, astronaut David Scott demonstrated that a feather and a hammer fall at the same rate on the moon. The position function for each of these falling objects is

$$s(t) = -0.81t^2 + 2$$

where $s(t)$ is the height in meters and t is the time in seconds, as shown in the figure at the right. What is the ratio of Earth's gravitational force to the moon's?



Solution To find the acceleration, differentiate the position function twice.

$$\begin{aligned} s(t) &= -0.81t^2 + 2 && \text{Position function} \\ s'(t) &= -1.62t && \text{Velocity function} \\ s''(t) &= -1.62 && \text{Acceleration function} \end{aligned}$$

Because $s''(t) = -g$, the acceleration due to gravity on the moon is $g = 1.62$ meters per second per second. The acceleration due to gravity on Earth is 9.8 meters per second per second, so the ratio of Earth's gravitational force to the moon's is

$$\begin{aligned} \frac{\text{Earth's gravitational force}}{\text{Moon's gravitational force}} &= \frac{9.8}{1.62} \\ &\approx 6.0. \end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

2.3 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain how to find the derivative of the product of two differentiable functions.
2. Explain how to find the derivative of the quotient of two differentiable functions.
3. Identify the derivatives of $\tan x$, $\cot x$, $\sec x$, and $\csc x$.
4. Explain how to find a higher-order derivative.

Using the Product Rule In Exercises 5–10, use the Product Rule to find the derivative of the function.

5. $g(x) = (2x - 3)(1 - 5x)$
6. $y = (3x - 4)(x^3 + 5)$
7. $h(t) = \sqrt{t}(1 - t^2)$
8. $g(s) = \sqrt{s}(s^2 + 8)$
9. $f(x) = x^3 \cos x$
10. $g(x) = \sqrt{x} \sin x$

Using the Quotient Rule In Exercises 11–16, use the Quotient Rule to find the derivative of the function.

11. $f(x) = \dfrac{x}{x - 5}$
12. $g(t) = \dfrac{3t^2 - 1}{2t + 5}$
13. $h(x) = \dfrac{\sqrt{x}}{x^3 + 1}$
14. $f(x) = \dfrac{x^2}{2\sqrt{x} + 1}$
15. $g(x) = \dfrac{\sin x}{x^2}$
16. $f(t) = \dfrac{\cos t}{t^3}$

Finding and Evaluating a Derivative In Exercises 17–22, find $f'(x)$ and $f'(c)$.

Function	Value of c
17. $f(x) = (x^3 + 4x)(3x^2 + 2x - 5)$	$c = 0$
18. $f(x) = (2x^2 - 3x)(9x + 4)$	$c = -1$
19. $f(x) = \dfrac{x^2 - 4}{x - 3}$	$c = 1$
20. $f(x) = \dfrac{x - 4}{x + 4}$	$c = 3$
21. $f(x) = x \cos x$	$c = \dfrac{\pi}{4}$
22. $f(x) = \dfrac{\sin x}{x}$	$c = \dfrac{\pi}{6}$

Using the Constant Multiple Rule In Exercises 23–28, complete the table to find the derivative of the function without using the Quotient Rule.

Function	Rewrite	Differentiate	Simplify
23. $y = \dfrac{x^3 + 6x}{3}$			
24. $y = \dfrac{5x^2 - 3}{4}$			
25. $y = \dfrac{6}{7x^2}$			
26. $y = \dfrac{10}{3x^3}$			
27. $y = \dfrac{4x^{3/2}}{x}$			
28. $y = \dfrac{2x}{x^{1/3}}$			

Finding a Derivative In Exercises 29–40, find the derivative of the algebraic function.

29. $f(x) = \dfrac{4 - 3x - x^2}{x^2 - 1}$
30. $f(x) = \dfrac{x^2 + 5x + 6}{x^2 - 4}$
31. $f(x) = x\left(1 - \dfrac{4}{x + 3}\right)$
32. $f(x) = x^4\left(1 - \dfrac{2}{x + 1}\right)$
33. $f(x) = \dfrac{3x - 1}{\sqrt{x}}$
34. $f(x) = \sqrt[3]{x}\left(\sqrt{x} + 3\right)$
35. $f(x) = \dfrac{2 - \dfrac{1}{x}}{x - 3}$
36. $h(x) = \dfrac{\dfrac{1}{x^2} + 5x}{x + 1}$
37. $g(s) = s^3\left(5 - \dfrac{s}{s + 2}\right)$
38. $g(x) = x^2\left(\dfrac{2}{x} - \dfrac{1}{x + 1}\right)$
39. $f(x) = (2x^3 + 5x)(x - 3)(x + 2)$
40. $f(x) = (x^3 - x)(x^2 + 2)(x^2 + x - 1)$

Finding a Derivative of a Trigonometric Function In Exercises 41–56, find the derivative of the trigonometric function.

41. $f(t) = t^2 \sin t$
42. $f(\theta) = (\theta + 1) \cos \theta$
43. $f(t) = \dfrac{\cos t}{t}$
44. $f(x) = \dfrac{\sin x}{x^3}$
45. $f(x) = -x + \tan x$
46. $y = x + \cot x$
47. $g(t) = \sqrt[4]{t} + 6 \csc t$
48. $h(x) = \dfrac{1}{x} - 12 \sec x$
49. $y = \dfrac{3(1 - \sin x)}{2 \cos x}$
50. $y = \dfrac{\sec x}{x}$
51. $y = -\csc x - \sin x$
52. $y = x \sin x + \cos x$
53. $f(x) = x^2 \tan x$
54. $f(x) = \sin x \cos x$
55. $y = 2x \sin x + x^2 \cos x$
56. $h(\theta) = 5\theta \sec \theta + \theta \tan \theta$

Finding a Derivative Using Technology In Exercises 57–60, use a computer algebra system to find the derivative of the function.

57. $g(x) = \left(\dfrac{x + 1}{x + 2}\right)(2x - 5)$
58. $f(x) = \left(\dfrac{x^2 - x - 3}{x^2 + 1}\right)(x^2 + x + 1)$
59. $g(\theta) = \dfrac{\theta}{1 - \sin \theta}$
60. $f(x) = \dfrac{\cos x}{1 - \sin x}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding the Slope of a Graph **In Exercises 61–64, find the slope of the graph of the function at the given point. Use the *derivative* feature of a graphing utility to confirm your results.**

Function	Point
61. $y = \dfrac{1 + \csc x}{1 - \csc x}$	$\left(\dfrac{\pi}{6}, -3\right)$
62. $f(x) = \tan x \cot x$	$(1, 1)$
63. $h(t) = \dfrac{\sec t}{t}$	$\left(\pi, -\dfrac{1}{\pi}\right)$
64. $f(x) = (\sin x)(\sin x + \cos x)$	$\left(\dfrac{\pi}{4}, 1\right)$

Finding an Equation of a Tangent Line **In Exercises 65–70, (a) find an equation of the tangent line to the graph of f at the given point, (b) sketch a graph of the function and its tangent line at the point, and (c) use the *tangent* feature of a graphing utility to confirm your results.**

65. $f(x) = (x^3 + 4x - 1)(x - 2), \quad (1, -4)$

66. $f(x) = (x - 2)(x^2 + 4), \quad (1, -5)$

67. $f(x) = \dfrac{x}{x + 4}, \quad (-5, 5)$

68. $f(x) = \dfrac{x + 3}{x - 3}, \quad (4, 7)$

69. $f(x) = \tan x, \quad \left(\dfrac{\pi}{4}, 1\right)$

70. $f(x) = \sec x, \quad \left(\dfrac{\pi}{3}, 2\right)$

Famous Curves **In Exercises 71–74, find an equation of the tangent line to the graph at the given point. (The graphs in Exercises 71 and 72 are called *Witches of Agnesi*. The graphs in Exercises 73 and 74 are called *serpentines*.)**

71.



72.



73.



74.



Horizontal Tangent Line **In Exercises 75–78, determine the point(s) at which the graph of the function has a horizontal tangent line.**

75. $f(x) = \dfrac{2x - 1}{x^2}$

76. $f(x) = \dfrac{x^2}{x^2 + 1}$

77. $f(x) = \dfrac{x^2}{x - 1}$

78. $f(x) = \dfrac{x - 4}{x^2 - 7}$

79. Tangent Lines Find equations of the tangent lines to the graph of

$$f(x) = \frac{x + 1}{x - 1}$$

that are parallel to the line $2y + x = 6$. Then graph the function and the tangent lines.

80. Tangent Lines Find equations of the tangent lines to the graph of $f(x) = x/(x - 1)$ that pass through the point $(-1, 5)$. Then graph the function and the tangent lines.

Exploring a Relationship **In Exercises 81 and 82, verify that $f'(x) = g'(x)$ and explain the relationship between f and g.**

81. $f(x) = \dfrac{3x}{x + 2}, \quad g(x) = \dfrac{5x + 4}{x + 2}$

82. $f(x) = \dfrac{\sin x - 3x}{x}, \quad g(x) = \dfrac{\sin x + 2x}{x}$

Finding Derivatives **In Exercises 83 and 84, use the graphs of f and g. Let $p(x) = f(x)g(x)$ and $q(x) = f(x)/g(x)$.**

83. (a) Find $p'(1)$.
(b) Find $q'(4)$.



84. (a) Find $p'(4)$.
(b) Find $q'(7)$.



85. Area The length of a rectangle is given by $6t + 5$ and its height is $\sqrt{t}$, where t is time in seconds and the dimensions are in centimeters. Find the rate of change of the area with respect to time.

86. Volume The radius of a right circular cylinder is given by $\sqrt{t + 2}$ and its height is $\frac{1}{2}\sqrt{t}$, where t is time in seconds and the dimensions are in inches. Find the rate of change of the volume with respect to time.

87. Inventory Management The ordering and transportation cost C for the components used in manufacturing a product is

$$C = 100\left(\frac{200}{x^2} + \frac{x}{x + 30}\right), \quad x \geq 1$$

where C is measured in thousands of dollars and x is the order size in hundreds. Find the rate of change of C with respect to x when (a) $x = 10$, (b) $x = 15$, and (c) $x = 20$. What do these rates of change imply about increasing order size?

88. Biology A population of 500 bacteria is introduced into a culture and grows in number according to the equation

$$P(t) = 500\left(1 + \frac{4t}{50 + t^2}\right)$$

where t is measured in hours. Find the rate at which the population is growing when $t = 2$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

89. Proof Prove each differentiation rule.

(a) $\frac{d}{dx}[\sec x] = \sec x \tan x$

(b) $\frac{d}{dx}[\csc x] = -\csc x \cot x$

(c) $\frac{d}{dx}[\cot x] = -\csc^2 x$

90. Rate of Change Determine whether there exist any values of x in the interval $[0, 2\pi)$ such that the rate of change of $f(x) = \sec x$ and the rate of change of $g(x) = \csc x$ are equal.

91. Modeling Data The table shows the national health care expenditures h (in billions of dollars) in the United States and the population p (in millions) of the United States for the years 2014 through 2019. The year is represented by t, with $t = 14$ corresponding to 2014. *(Source: U.S. Centers for Medicare & Medicaid Services and U.S. Census Bureau)*

Year, t	14	15	16	17	18	19
h	3008	3178	3325	3466	3630	3795
p	319	321	323	326	327	328

(a) Use a graphing utility to find linear models for the health care expenditures $h(t)$ and the population $p(t)$.

(b) Use a graphing utility to graph $h(t)$ and $p(t)$.

(c) Find $A = h(t)/p(t)$, then graph A using a graphing utility. What does this function represent?

(d) Find and interpret $A'(t)$ in the context of the problem.

92. Satellites When satellites observe Earth, they can scan only part of Earth's surface. Some satellites have sensors that can measure the angle θ shown in the figure. Let h represent the satellite's distance from Earth's surface, and let r represent Earth's radius.



(a) Show that $h = r(\csc \theta - 1)$.

(b) Find the rate at which h is changing with respect to θ when $\theta = 30°$. (Assume $r = 4000$ miles.)

Finding a Second Derivative **In Exercises 93–102, find the second derivative of the function.**

93. $f(x) = x^2 + 7x - 4$

94. $f(x) = 4x^5 - 2x^3 + 5x^2$

95. $f(x) = 4x^{3/2}$

96. $f(x) = x^2 + 3x^{-3}$

97. $f(x) = \frac{x}{x-1}$

98. $f(x) = \frac{x^2 + 3x}{x - 4}$

99. $f(x) = x \sin x$

100. $f(x) = x \cos x$

101. $f(x) = \csc x$

102. $f(x) = \sec x$

Finding a Higher-Order Derivative **In Exercises 103–106, find the indicated higher-order derivative.**

103. $f'(x) = x^3 - x^{2/5}, \quad f^{(3)}(x)$

104. $f^{(3)}(x) = \sqrt[5]{x^4}, \quad f^{(4)}(x)$

105. $f''(x) = -\sin x, \quad f^{(8)}(x)$

106. $f^{(4)}(t) = t \cos t, \quad f^{(5)}(t)$

Using Relationships **In Exercises 107–110, use the given information to find $f'(2)$.**

$g(2) = 3$ **and** $g'(2) = -2$

$h(2) = -1$ **and** $h'(2) = 4$

107. $f(x) = 2g(x) + h(x)$

108. $f(x) = 4 - h(x)$

109. $f(x) = \frac{g(x)}{h(x)}$

110. $f(x) = g(x)h(x)$

Exploring Concepts

111. Polynomials of what degree satisfy $f^{(n)} = 0$? Explain your reasoning.

112. Describe how to differentiate a piecewise function. Use your approach to find the first and second derivatives of

$f(x) = x|x|$.

Explain why $f''(0)$ does not exist.

In Exercises 113 and 114, the graphs of f, f', and f'' are shown on the same set of coordinate axes. Identify each graph. Explain your reasoning. To print an enlarged copy of the graph, go to *MathGraphs.com*.

113.



114.



In Exercises 115 and 116, the graph of f is shown. Sketch the graphs of f' and f''. To print an enlarged copy of the graph, go to *MathGraphs.com*.

115.



116.



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

117. Sketching a Graph Sketch the graph of a differentiable function f such that $f(2) = 0$, $f' < 0$ for $-\infty < x < 2$, and $f' > 0$ for $2 < x < \infty$. Explain how you found your answer.

118. Sketching a Graph Sketch the graph of a differentiable function f such that $f > 0$ and $f' < 0$ for all real numbers x. Explain how you found your answer.

119. Acceleration The velocity of an object is

$$v(t) = 36 - t^2, \quad 0 \le t \le 6$$

where v is measured in meters per second and t is the time in seconds. Find the velocity and acceleration of the object when $t = 3$. What can be said about the speed of the object when the velocity and acceleration have opposite signs?

120. Acceleration The velocity of an automobile starting from rest is

$$v(t) = \frac{100t}{2t + 15}$$

where v is measured in feet per second and t is the time in seconds. Find the acceleration at (a) 5 seconds, (b) 10 seconds, and (c) 20 seconds.

121. Stopping Distance A car is traveling at a rate of 66 feet per second (45 miles per hour) when the brakes are applied. The position function for the car is

$$s(t) = -8.25t^2 + 66t$$

where s is measured in feet and t is measured in seconds. Use this function to complete the table and find the average velocity during each time interval.

t	0	1	2	3	4
$s(t)$					
$v(t)$					
$a(t)$					

122. HOW DO YOU SEE IT? The figure shows the graphs of the position, velocity, and acceleration functions of a particle.



(a) Copy the graphs of the functions shown. Identify each graph. Explain your reasoning. To print an enlarged copy of the graph, go to *MathGraphs.com*.

(b) On your sketch, identify when the particle speeds up and when it slows down. Explain your reasoning.

Finding a Pattern **In Exercises 123 and 124, develop a general rule for $f^{(n)}(x)$ given $f(x)$.**

123. $f(x) = x^n$

124. $f(x) = \frac{1}{x}$

125. Finding a Pattern Consider the function $f(x) = g(x)h(x)$.

(a) Use the Product Rule to generate rules for finding $f''(x)$, $f'''(x)$, and $f^{(4)}(x)$.

(b) Use the results of part (a) to write a general rule for $f^{(n)}(x)$.

126. Finding a Pattern Develop a general rule for the nth derivative of $xf(x)$, where f is a differentiable function of x.

Finding a Pattern **In Exercises 127 and 128, find the derivatives of the function f for $n = 1$, 2, 3, and 4. Use the results to write a general rule for $f'(x)$ in terms of n.**

127. $f(x) = x^n \sin x$

128. $f(x) = \frac{\cos x}{x^n}$

Differential Equations **In Exercises 129–132, verify that the function satisfies the differential equation. (A *differential equation* in x and y is an equation that involves x, y, and derivatives of y.)**

	Function	Differential Equation
129.	$y = \frac{1}{x}, x > 0$	$x^3y'' + 2x^2y' = 0$
130.	$y = 2x^3 - 6x + 10$	$-y''' - xy'' - 2y' = -24x^2$
131.	$y = 2 \sin x + 3$	$y'' + y = 3$
132.	$y = 3 \cos x + \sin x$	$y'' + y = 0$

True or False? **In Exercises 133–138, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

133. If $h(x) = f(x)g(x)$, then $h'(x) = f'(x)g'(x)$.

134. If $h(x) = (x + 1)(x + 2)(x + 3)(x + 4)$, then $h^{(5)}(x) = 0$.

135. If $f'(c)$ and $g'(c)$ are zero and $h(x) = f(x)g(x)$, then $h'(c) = 0$.

136. If the position function of an object is linear, then its acceleration is zero.

137. The second derivative represents the rate of change of the first derivative.

138. The function $f(x) = \sin x + c$ satisfies $f^{(n)} = f^{(n+4)}$ for all integers $n \ge 1$.

139. Proof Use the Product Rule twice to prove that if f, g, and h are differentiable functions of x, then

$$\frac{d}{dx}[f(x)g(x)h(x)] = f'(x)g(x)h(x) + f(x)g'(x)h(x) + f(x)g(x)h'(x).$$

140. Think About It Let f and g be functions whose first and second derivatives exist on an interval I. Determine whether each formula is true.

(a) $fg'' - f''g = (fg' - f'g)'$

(b) $fg'' + f''g = (fg)''$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

2.4 The Chain Rule

GO DIGITAL

- Find the derivative of a composite function using the Chain Rule.
- Find the derivative of a function using the General Power Rule.
- Simplify the derivative of a function using algebra.
- Find the derivative of a trigonometric function using the Chain Rule.

The Chain Rule

This text has yet to discuss one of the most powerful differentiation rules—the **Chain Rule.** This rule deals with composite functions and adds a surprising versatility to the rules discussed in the two preceding sections. For example, compare the functions shown below. Those on the left can be differentiated without the Chain Rule, and those on the right are best differentiated with the Chain Rule.

Without the Chain Rule	With the Chain Rule
$y = x^2 + 1$	$y = \sqrt{x^2 + 1}$
$y = \sin x$	$y = \sin 6x$
$y = 3x + 2$	$y = (3x + 2)^5$
$y = x + \tan x$	$y = x + \tan x^2$

Basically, the Chain Rule states that if y changes dy/du times as fast as u, and u changes du/dx times as fast as x, then y changes $(dy/du)(du/dx)$ times as fast as x.

EXAMPLE 1 The Derivative of a Composite Function

Figure 2.24 shows a set of gears. The second and third gears are on the same axle. As the first axle revolves, it drives the second axle, which in turn drives the third axle. Let y, u, and x represent the numbers of revolutions per minute of the first, second, and third axles, respectively. Find dy/du, du/dx, and dy/dx, and show that

$$\frac{dy}{dx} = \frac{dy}{du} \cdot \frac{du}{dx}.$$



Axle 1: y revolutions per minute
Axle 2: u revolutions per minute
Axle 3: x revolutions per minute
Figure 2.24

Solution Because the circumference of the second gear is three times that of the first, the first axle must make three revolutions to turn the second axle once. Similarly, the second axle must make two revolutions to turn the third axle once, so

$$\frac{dy}{du} = 3 \quad \text{and} \quad \frac{du}{dx} = 2.$$

Combining these two results, note that the first axle must make six revolutions to turn the third axle once. So, you can write

$$\begin{aligned} \frac{dy}{dx} &= \left[\begin{array}{l}\text{Rate of change of first axle}\\ \text{with respect to second axle}\end{array}\right] \cdot \left[\begin{array}{l}\text{Rate of change of second axle}\\ \text{with respect to third axle}\end{array}\right] \\ &= \frac{dy}{du} \cdot \frac{du}{dx} \\ &= 3 \cdot 2 \\ &= 6 \\ &= \left[\begin{array}{l}\text{Rate of change of first axle}\\ \text{with respect to third axle}\end{array}\right]. \end{aligned}$$

In other words, the rate of change of y with respect to x is the product of the rate of change of y with respect to u and the rate of change of u with respect to x. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploration

Using the Chain Rule Each function below can be differentiated using rules that you studied in Sections 2.2 and 2.3. For each function, find the derivative using those rules. Then find the derivative using the Chain Rule. Compare your results. Which method is simpler?

a. $y = \dfrac{2}{3x + 1}$

b. $y = (x + 2)^3$

c. $y = \sin 2x$

Example 1 illustrates a simple case of the Chain Rule. The general rule is stated in the next theorem.

THEOREM 2.10 The Chain Rule

If $y = f(u)$ is a differentiable function of u and $u = g(x)$ is a differentiable function of x, then $y = f(g(x))$ is a differentiable function of x and

$$\frac{dy}{dx} = \frac{dy}{du} \cdot \frac{du}{dx}$$

or, equivalently,

$$\frac{d}{dx}[f(g(x))] = f'(g(x))g'(x).$$

Proof Let $h(x) = f(g(x))$. Then, using the alternative form of the derivative, you need to show that, for $x = c$,

$$h'(c) = f'(g(c))g'(c).$$

An important consideration in this proof is the behavior of g as x approaches c. A problem occurs when there are values of x, other than c, such that $g(x) = g(c)$. Appendix A shows how to use the differentiability of f and g to overcome this problem. For now, assume that $g(x) \neq g(c)$ for values of x other than c. In the proofs of the Product Rule and the Quotient Rule, the same quantity was added and subtracted to obtain the desired form. This proof uses a similar technique—multiplying and dividing by the same (nonzero) quantity. In this case, the quantity is $g(x) - g(c)$. Note that because g is differentiable, it is also continuous, and it follows that $g(x)$ approaches $g(c)$ as x approaches c.

$$\begin{aligned}
h'(c) &= \lim_{x \to c} \frac{f(g(x)) - f(g(c))}{x - c} && \text{Alternative form of derivative} \\
&= \lim_{x \to c} \left[\frac{f(g(x)) - f(g(c))}{x - c} \cdot \frac{g(x) - g(c)}{g(x) - g(c)} \right], \quad g(x) \neq g(c) \\
&= \lim_{x \to c} \left[\frac{f(g(x)) - f(g(c))}{g(x) - g(c)} \cdot \frac{g(x) - g(c)}{x - c} \right] \\
&= \left[\lim_{x \to c} \frac{f(g(x)) - f(g(c))}{g(x) - g(c)} \right] \left[\lim_{x \to c} \frac{g(x) - g(c)}{x - c} \right] \\
&\qquad \text{Definition of } f'(g(c)) \qquad \text{Definition of } g'(c) \\
&= f'(g(c))g'(c)
\end{aligned}$$

REMARK The alternative limit form of the derivative was given at the end of Section 2.1.

When applying the Chain Rule, it is helpful to think of the composite function $f \circ g$ as having two parts—an inner part and an outer part.

$$y = f(g(x)) = f(u)$$

Outer function

Inner function

The derivative of $y = f(u)$ is the derivative of the outer function (at the inner function u) *times* the derivative of the inner function.

$$y' = f'(u) \cdot u'$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 2 **Decomposition of a Composite Function**

	Original Function $y = f(g(x))$	Inner Function $u = g(x)$	Outer Function $y = f(u)$
a.	$y = \dfrac{1}{x+1}$	$u = x + 1$	$y = \dfrac{1}{u}$
b.	$y = \sin 2x$	$u = 2x$	$y = \sin u$
c.	$y = \sqrt{3x^2 - x + 1}$	$u = 3x^2 - x + 1$	$y = \sqrt{u}$
d.	$y = \tan^2 x$	$u = \tan x$	$y = u^2$

EXAMPLE 3 **Using the Chain Rule**

Find dy/dx for

$$y = (x^2 + 1)^3.$$

Solution For this function, let the inside function be $u = x^2 + 1$ and the outer function be $y = u^3$. By the Chain Rule, you obtain

$$\frac{dy}{dx} = \underbrace{3(x^2 + 1)^2}_{\frac{dy}{du}}\underbrace{(2x)}_{\frac{du}{dx}} = 6x(x^2 + 1)^2.$$

REMARK You could also solve the problem in Example 3 without using the Chain Rule by expanding the binomial to obtain

$$y = x^6 + 3x^4 + 3x^2 + 1$$

and then finding the derivative

$$y' = 6x^5 + 12x^3 + 6x.$$

Verify that this is the same as the derivative in Example 3. Which method would you use to find

$$\frac{d}{dx}[(x^2 + 1)^{50}]?$$

The General Power Rule

The function in Example 3 is an example of one of the most common types of composite functions, $y = [u(x)]^n$. The rule for differentiating such functions is called the **General Power Rule,** and it is a special case of the Chain Rule.

THEOREM 2.11 The General Power Rule

If $y = [u(x)]^n$, where u is a differentiable function of x and n is a rational number, then

$$\frac{dy}{dx} = n[u(x)]^{n-1}\frac{du}{dx}$$

or, equivalently,

$$\frac{d}{dx}[u^n] = nu^{n-1}u'.$$

Proof Because $y = [u(x)]^n = u^n$, you apply the Chain Rule to obtain

$$\frac{dy}{dx} = \left(\frac{dy}{du}\right)\left(\frac{du}{dx}\right) \quad \text{Apply Chain Rule.}$$

$$= \frac{d}{du}[u^n]\frac{du}{dx}.$$

By the (Simple) Power Rule in Section 2.2, you have $D_u[u^n] = nu^{n-1}$, and it follows that

$$\frac{dy}{dx} = nu^{n-1}\frac{du}{dx}. \quad \text{Apply (Simple) Power Rule.}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 4 Applying the General Power Rule

Find the derivative of $f(x) = (3x - 2x^2)^3$.

Solution Let $u = 3x - 2x^2$. Then

$$f(x) = (3x - 2x^2)^3 = u^3$$

and, by the General Power Rule, the derivative is

$$f'(x) = \overbrace{3}^{n}\overbrace{(3x - 2x^2)^2}^{u^{n-1}}\overbrace{\frac{d}{dx}[3x - 2x^2]}^{u'} \qquad \text{Apply General Power Rule.}$$

$$= 3(3x - 2x^2)^2(3 - 4x). \qquad \text{Differentiate } 3x - 2x^2.$$

EXAMPLE 5 Differentiating a Function Involving a Radical

Find all points on the graph of

$$f(x) = \sqrt[3]{(x^2 - 1)^2}$$

for which $f'(x) = 0$ and those for which $f'(x)$ does not exist.

Solution Begin by rewriting the function in rational exponent form.

$$f(x) = (x^2 - 1)^{2/3} \qquad \text{Rewrite original function.}$$

Then, applying the General Power Rule (with $u = x^2 - 1$) produces

$$f'(x) = \overbrace{\frac{2}{3}}^{n}\overbrace{(x^2 - 1)^{-1/3}}^{u^{n-1}}\overbrace{(2x)}^{u'} \qquad \text{Apply General Power Rule.}$$

$$= \frac{4x}{3\sqrt[3]{x^2 - 1}}. \qquad \text{Write in radical form.}$$

So, $f'(x) = 0$ when $x = 0$, and $f'(x)$ does not exist when $x = \pm 1$, as shown in Figure 2.25.



The derivative of f is 0 at $x = 0$ and is undefined at $x = \pm 1$.
Figure 2.25

EXAMPLE 6 Differentiating a Quotient: Constant Numerator

Differentiate the function

$$g(t) = \frac{-7}{(2t - 3)^2}.$$

Solution Begin by rewriting the function with a negative exponent.

$$g(t) = -7(2t - 3)^{-2} \qquad \text{Rewrite original function.}$$

Then, applying the General Power Rule (with $u = 2t - 3$) produces

$$g'(t) = \underbrace{(-7)}_{\substack{\text{Constant}\\ \text{Multiple Rule}}}\overbrace{(-2)}^{n}\overbrace{(2t - 3)^{-3}}^{u^{n-1}}\overbrace{(2)}^{u'} \qquad \text{Apply General Power Rule.}$$

$$= 28(2t - 3)^{-3} \qquad \text{Simplify.}$$

$$= \frac{28}{(2t - 3)^3}. \qquad \text{Write with positive exponent.}$$

REMARK Try differentiating the function in Example 6 using the Quotient Rule. You should obtain the same result, but using the Quotient Rule is less efficient than using the General Power Rule.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Simplifying Derivatives

The next three examples demonstrate techniques for simplifying the "raw derivatives" of functions involving products, quotients, and composites.

EXAMPLE 7 Simplifying by Factoring Out the Least Power

Find the derivative of $f(x) = x^2\sqrt{1 - x^2}$.

Solution

$$f(x) = x^2\sqrt{1 - x^2}$$ Write original function.

$$= x^2(1 - x^2)^{1/2}$$ Rewrite.

$$f'(x) = x^2\frac{d}{dx}[(1 - x^2)^{1/2}] + (1 - x^2)^{1/2}\frac{d}{dx}[x^2]$$ Product Rule

$$= x^2\left[\frac{1}{2}(1 - x^2)^{-1/2}(-2x)\right] + (1 - x^2)^{1/2}(2x)$$ General Power Rule

$$= -x^3(1 - x^2)^{-1/2} + 2x(1 - x^2)^{1/2}$$ Simplify.

$$= x(1 - x^2)^{-1/2}[-x^2(1) + 2(1 - x^2)]$$ Factor.

$$= x(1 - x^2)^{-1/2}(2 - 3x^2)$$ Simplify.

$$= \frac{x(2 - 3x^2)}{\sqrt{1 - x^2}}$$ Write in radical form.

REMARK In Example 7, note that you subtract exponents when factoring. That is, when $(1 - x^2)^{-1/2}$ is factored out of $(1 - x^2)^{1/2}$, the *remaining* factor has an exponent of $\frac{1}{2} - \left(-\frac{1}{2}\right) = 1$. So, $(1 - x^2)^{1/2}$ is equal to the product of $(1 - x^2)^{-1/2}$ and $(1 - x^2)^1$.

EXAMPLE 8 Simplifying the Derivative of a Quotient

$$f(x) = \frac{x}{\sqrt[3]{x^2 + 4}}$$ Original function

$$= \frac{x}{(x^2 + 4)^{1/3}}$$ Rewrite.

$$f'(x) = \frac{(x^2 + 4)^{1/3}(1) - x(1/3)(x^2 + 4)^{-2/3}(2x)}{(x^2 + 4)^{2/3}}$$ Quotient Rule

$$= \frac{1}{3}(x^2 + 4)^{-2/3}\left[\frac{3(x^2 + 4) - (2x^2)(1)}{(x^2 + 4)^{2/3}}\right]$$ Factor.

$$= \frac{x^2 + 12}{3(x^2 + 4)^{4/3}}$$ Simplify.

TECHNOLOGY Some graphing utilities are capable of differentiating very complicated functions. Often, however, the result is given in unsimplified form. If you have access to such a utility, use it to find the derivatives of the functions given in Examples 7, 8, and 9. Then compare the results with those given in these examples.

EXAMPLE 9 Simplifying the Derivative of a Power

See LarsonCalculus.com for an interactive version of this type of example.

$$y = \left(\frac{3x - 1}{x^2 + 3}\right)^2$$ Original function

$$y' = \overset{n}{2}\overbrace{\left(\frac{3x - 1}{x^2 + 3}\right)}^{u^{n-1}}\overbrace{\frac{d}{dx}\left[\frac{3x - 1}{x^2 + 3}\right]}^{u'}$$ General Power Rule

$$= \left[\frac{2(3x - 1)}{x^2 + 3}\right]\left[\frac{(x^2 + 3)(3) - (3x - 1)(2x)}{(x^2 + 3)^2}\right]$$ Quotient Rule

$$= \frac{2(3x - 1)(3x^2 + 9 - 6x^2 + 2x)}{(x^2 + 3)^3}$$ Multiply.

$$= \frac{2(3x - 1)(-3x^2 + 2x + 9)}{(x^2 + 3)^3}$$ Simplify.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Trigonometric Functions and the Chain Rule

The "Chain Rule versions" of the derivatives of the six trigonometric functions are shown below.

$$\frac{d}{dx}[\sin u] = (\cos u)u' \qquad \frac{d}{dx}[\cos u] = -(\sin u)u'$$

$$\frac{d}{dx}[\tan u] = (\sec^2 u)u' \qquad \frac{d}{dx}[\cot u] = -(\csc^2 u)u'$$

$$\frac{d}{dx}[\sec u] = (\sec u \tan u)u' \qquad \frac{d}{dx}[\csc u] = -(\csc u \cot u)u'$$

EXAMPLE 10 The Chain Rule and Trigonometric Functions

a. $y = \sin 2x$ $\qquad y' = \cos 2x \dfrac{d}{dx}[2x] = (\cos 2x)(2) = 2\cos 2x$

b. $y = \cos(x - 1)$ $\qquad y' = -\sin(x - 1)\dfrac{d}{dx}[x - 1] = -\sin(x - 1)$

c. $y = \tan 3x$ $\qquad y' = \sec^2 3x \dfrac{d}{dx}[3x] = (\sec^2 3x)(3) = 3\sec^2 3x$

Be sure you understand the mathematical conventions regarding parentheses and trigonometric functions. For instance, in Example 10(a), $\sin 2x$ is written to mean $\sin(2x)$.

EXAMPLE 11 Parentheses and Trigonometric Functions

a. $y = \cos 3x^2 = \cos(3x^2)$ $\qquad y' = (-\sin 3x^2)(6x) = -6x \sin 3x^2$

b. $y = (\cos 3)x^2$ $\qquad y' = (\cos 3)(2x) = 2x \cos 3$

c. $y = \cos(3x)^2 = \cos(9x^2)$ $\qquad y' = (-\sin 9x^2)(18x) = -18x \sin 9x^2$

d. $y = \cos^2 x = (\cos x)^2$ $\qquad y' = 2(\cos x)(-\sin x) = -2\cos x \sin x$

e. $y = \sqrt{\cos x} = (\cos x)^{1/2}$ $\qquad y' = \dfrac{1}{2}(\cos x)^{-1/2}(-\sin x) = -\dfrac{\sin x}{2\sqrt{\cos x}}$

REMARK Another way to write the derivative in Example 11(d) is to use the double angle identity, $2 \sin x \cos x = \sin 2x$. Applying this identity, the result is

$$\begin{aligned} y' &= -2 \cos x \sin x \\ &= -(2 \sin x \cos x) \\ &= -\sin 2x. \end{aligned}$$

To find the derivative of a function of the form $k(x) = f(g(h(x)))$, you need to apply the Chain Rule twice, as shown in Example 12.

EXAMPLE 12 Repeated Application of the Chain Rule

$$\begin{aligned} f(t) &= \sin^3 4t && \text{Original function} \\ &= (\sin 4t)^3 && \text{Rewrite.} \\ f'(t) &= 3(\sin 4t)^2 \frac{d}{dt}[\sin 4t] && \text{Apply Chain Rule once.} \\ &= 3(\sin 4t)^2(\cos 4t)\frac{d}{dt}[4t] && \text{Apply Chain Rule a second time.} \\ &= 3(\sin 4t)^2(\cos 4t)(4) \\ &= 12 \sin^2 4t \cos 4t && \text{Simplify.} \end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 2.26

EXAMPLE 13 Tangent Line of a Trigonometric Function

Find an equation of the tangent line to the graph of $f(x) = 2 \sin x + \cos 2x$ at the point $(\pi, 1)$, as shown in Figure 2.26. Then determine all values of x in the interval $(0, 2\pi)$ at which the graph of f has a horizontal tangent.

Solution Begin by finding $f'(x)$.

$$f(x) = 2 \sin x + \cos 2x \qquad \text{Write original function.}$$
$$f'(x) = 2 \cos x + (-\sin 2x)(2) \qquad \text{Apply Chain Rule to } \cos 2x.$$
$$= 2 \cos x - 2 \sin 2x \qquad \text{Simplify.}$$

To find the slope of the tangent line at $(\pi, 1)$, evaluate $f'(\pi)$.

$$f'(\pi) = 2 \cos \pi - 2 \sin 2\pi \qquad \text{Substitute.}$$
$$= -2 \qquad \text{Slope of tangent line at } (\pi, 1)$$

Now, use the point-slope form of the equation of a line to write

$$y - y_1 = m(x - x_1) \qquad \text{Point-slope form}$$
$$y - 1 = -2(x - \pi) \qquad \text{Substitute for } y_1, m, \text{ and } x_1.$$
$$y = -2x + 1 + 2\pi. \qquad \text{Equation of tangent line at } (\pi, 1)$$

Note that $f'(x) = 0$ in the interval $(0, 2\pi)$ when $x = \pi/6, \pi/2, 5\pi/6$, and $3\pi/2$. So, the graph of f has horizontal tangents at $x = \pi/6, \pi/2, 5\pi/6$, and $3\pi/2$. ■

GO DIGITAL

This section concludes with a summary of the differentiation rules studied so far. To become skilled at differentiation, you should learn each rule in words, not symbols. As an aid to memorization, note that the cofunctions (cosine, cotangent, and cosecant) require a negative sign as part of their derivatives.

Summary of Differentiation Rules

General Differentiation Rules

Let c be a real number, let n be a rational number, let u and v be differentiable functions of x, and let f be a differentiable function of u.

Constant Rule:

$$\frac{d}{dx}[c] = 0$$

(Simple) Power Rule:

$$\frac{d}{dx}[x^n] = nx^{n-1}, \quad \frac{d}{dx}[x] = 1$$

Constant Multiple Rule:

$$\frac{d}{dx}[cu] = cu'$$

Sum or Difference Rule:

$$\frac{d}{dx}[u \pm v] = u' \pm v'$$

Product Rule:

$$\frac{d}{dx}[uv] = uv' + vu'$$

Quotient Rule:

$$\frac{d}{dx}\left[\frac{u}{v}\right] = \frac{vu' - uv'}{v^2}$$

Chain Rule:

$$\frac{d}{dx}[f(u)] = f'(u)u'$$

General Power Rule:

$$\frac{d}{dx}[u^n] = nu^{n-1}u'$$

Derivatives of Trigonometric Functions

$$\frac{d}{dx}[\sin x] = \cos x \qquad \frac{d}{dx}[\tan x] = \sec^2 x \qquad \frac{d}{dx}[\sec x] = \sec x \tan x$$

$$\frac{d}{dx}[\cos x] = -\sin x \qquad \frac{d}{dx}[\cot x] = -\csc^2 x \qquad \frac{d}{dx}[\csc x] = -\csc x \cot x$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

2.4 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain how to find the derivative of the composition of two differentiable functions.
2. Explain the difference between the (Simple) Power Rule and the General Power Rule.

Decomposition of a Composite Function

In Exercises 3–8, complete the table.

$y = f(g(x))$	$u = g(x)$	$y = f(u)$
3. $y = (6x - 5)^4$		
4. $y = \sqrt[3]{4x + 3}$		
5. $y = \dfrac{1}{3x + 5}$		
6. $y = \dfrac{2}{\sqrt{x^2 + 10}}$		
7. $y = \csc^3 x$		
8. $y = \sin\dfrac{5x}{2}$		

Finding a Derivative

In Exercises 9–34, find the derivative of the function.

9. $y = (2x - 7)^3$
10. $y = 5(2 - x^3)^4$
11. $g(x) = 3(4 - 9x)^{5/6}$
12. $f(t) = (9t + 2)^{2/3}$
13. $h(s) = -2\sqrt{5s^2 + 3}$
14. $g(x) = \sqrt{4 - 3x^2}$
15. $y = \sqrt[3]{6x^2 + 1}$
16. $y = 2\sqrt[4]{9 - x^2}$
17. $y = \dfrac{1}{x - 2}$
18. $s(t) = \dfrac{1}{4 - 5t - t^2}$
19. $g(s) = \dfrac{6}{(s^3 - 2)^3}$
20. $y = -\dfrac{3}{(t - 2)^4}$
21. $y = \dfrac{1}{\sqrt{3x + 5}}$
22. $g(t) = \dfrac{1}{\sqrt{t^2 - 2}}$
23. $f(x) = x^2(x - 2)^7$
24. $f(x) = x(2x - 5)^3$
25. $y = x\sqrt{1 - x^2}$
26. $y = x^2\sqrt{16 - x^2}$
27. $y = \dfrac{x}{\sqrt{x^2 + 1}}$
28. $y = \dfrac{x}{\sqrt{x^4 + 4}}$
29. $g(x) = \left(\dfrac{x + 5}{x^2 + 2}\right)^2$
30. $h(t) = \left(\dfrac{t^2}{t^3 + 2}\right)^2$
31. $s(t) = \left(\dfrac{1 + t}{t + 3}\right)^4$
32. $g(x) = \left(\dfrac{3x^2 - 2}{2x + 3}\right)^{-2}$
33. $f(x) = ((x^2 + 3)^5 + x)^2$
34. $g(x) = (2 + (x^2 + 1)^4)^3$

Finding a Derivative of a Trigonometric Function

In Exercises 35–54, find the derivative of the trigonometric function.

35. $y = \cos 4x$
36. $y = \sin \pi x$
37. $g(x) = 5 \tan 3x$
38. $h(x) = \sec 6x$
39. $y = \sin(\pi x)^2$
40. $y = \csc(1 - 2x)^2$
41. $h(x) = \sin 2x \cos 2x$
42. $g(\theta) = \sec\left(\frac{1}{2}\theta\right)\tan\left(\frac{1}{2}\theta\right)$
43. $f(x) = \dfrac{\cot x}{\sin x}$
44. $g(v) = \dfrac{\cos v}{\csc v}$
45. $y = 4 \sec^2 x$
46. $g(t) = 5 \cos^2 \pi t$
47. $f(\theta) = \frac{1}{4}\sin^2 2\theta$
48. $h(t) = 2 \cot^2(\pi t + 2)$
49. $f(t) = 3 \sec(\pi t - 1)^2$
50. $y = 5 \cos(\pi x)^2$
51. $y = \sin(3x^2 + \cos x)$
52. $y = \cos(5x + \csc x)$
53. $y = \sin\sqrt{\cot 3\pi x}$
54. $y = \cos\sqrt{\sin(\tan \pi x)}$

Finding a Derivative Using Technology

In Exercises 55–58, use a computer algebra system to find the derivative of the function. Then use the utility to graph the function and its derivative on the same set of coordinate axes. Describe the behavior of the function that corresponds to any zeros of the graph of the derivative.

55. $y = \dfrac{\sqrt{x} + 1}{x^2 + 1}$
56. $y = \sqrt{\dfrac{2x}{x + 1}}$
57. $y = \dfrac{\cos \pi x + 1}{x}$
58. $y = x^2 \tan\dfrac{1}{x}$

Slope of a Tangent Line

In Exercises 59 and 60, find the slope of the tangent line to the sine function at the origin. Compare this value with the number of complete cycles in the interval $[0, 2\pi]$.

59.



60.



Finding the Slope of a Graph

In Exercises 61–68, find the slope of the graph of the function at the given point. Use the *derivative* feature of a graphing utility to confirm your results.

61. $y = \sqrt{x^2 + 8x}$, $(1, 3)$
62. $y = \sqrt[5]{3x^3 + 4x}$, $(2, 2)$
63. $f(x) = 5(x^3 - 2)^{-1}$, $\left(-2, -\frac{1}{2}\right)$
64. $f(x) = \dfrac{1}{(x^2 - 3x)^2}$, $\left(4, \dfrac{1}{16}\right)$
65. $y = \dfrac{4}{(x + 2)^2}$, $(0, 1)$
66. $y = \dfrac{4}{(x^2 - 2x)^3}$, $(1, -4)$
67. $y = 26 - \sec^3 4x$, $(0, 25)$
68. $y = \dfrac{1}{x} + \sqrt{\cos x}$, $\left(\dfrac{\pi}{2}, \dfrac{2}{\pi}\right)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding an Equation of a Tangent Line **In Exercises 69–76, (a) find an equation of the tangent line to the graph of the function at the given point, (b) sketch a graph of the function and its tangent line at the point, and (c) use the *tangent* feature of a graphing utility to confirm your results.**

69. $f(x) = \sqrt{2x^2 - 7}$, $(4, 5)$

70. $f(x) = \frac{1}{3}x\sqrt{x^2 + 5}$, $(2, 2)$

71. $y = (4x^3 + 3)^2$, $(-1, 1)$

72. $f(x) = (9 - x^2)^{2/3}$, $(1, 4)$

73. $f(x) = \sin 8x$, $(\pi, 0)$

74. $y = \cos 3x$, $\left(\frac{\pi}{4}, -\frac{\sqrt{2}}{2}\right)$

75. $f(x) = \tan^2 x$, $\left(\frac{\pi}{4}, 1\right)$

76. $y = 2\tan^3 x$, $\left(\frac{\pi}{4}, 2\right)$

Famous Curves **In Exercises 77 and 78, find an equation of the tangent line to the graph at the given point. Then use a graphing utility to graph the function and its tangent line at the point in the same viewing window.**

77. Semicircle



78. Bullet-nose curve



79. Horizontal Tangent Line Determine the point(s) in the interval $(0, 2\pi)$ at which the graph of $f(x) = 2\cos x + \sin 2x$ has a horizontal tangent.

80. Horizontal Tangent Line Determine the point(s) at which the graph of

$$f(x) = \frac{-4x}{\sqrt{2x - 1}}$$

has a horizontal tangent.

Finding a Second Derivative **In Exercises 81–86, find the second derivative of the function.**

81. $f(x) = 5(2 - 7x)^4$

82. $f(x) = 6(x^3 + 4)^3$

83. $f(x) = \frac{1}{11x - 6}$

84. $f(x) = \frac{8}{(x - 2)^2}$

85. $f(x) = \sin x^2$

86. $f(x) = \sec^2 \pi x$

Evaluating a Second Derivative **In Exercises 87–92, evaluate the second derivative of the function at the given point. Use a computer algebra system to verify your result.**

87. $h(x) = \frac{1}{9}(3x + 1)^3$, $\left(1, \frac{64}{9}\right)$

88. $h(t) = (2t^3 + 3)^2$, $(1, 25)$

89. $g(x) = 3\sqrt{2x + 7}$, $(-3, 3)$

90. $f(x) = \frac{1}{\sqrt{x + 4}}$, $\left(0, \frac{1}{2}\right)$

91. $f(x) = \cos x^2$, $(0, 1)$

92. $g(t) = \tan 2t$, $\left(\frac{\pi}{6}, \sqrt{3}\right)$

Exploring Checks

In Exercises 93 and 94, the graphs of a function f and its derivative f' are shown. Label the graphs as f or f' and write a short paragraph stating the criteria you used in making your selection. To print an enlarged copy of the graph, go to *MathGraphs.com*.

93.



94.



95. The relationship between f and g is given. Describe the relationship between f' and g'.

(a) $g(x) = f(3x)$ (b) $g(x) = f(x^2)$

96. Consider the function

$$r(x) = \frac{2x - 5}{(3x + 1)^2}.$$

(a) In general, how do you find the derivative of $h(x) = \frac{f(x)}{g(x)}$ using the Product Rule, where g is a composite function?

(b) Find $r'(x)$ using the Product Rule.

(c) Find $r'(x)$ using the Quotient Rule.

(d) Which method do you prefer? Explain.

97. Think About It The table shows some values of the derivative of an unknown function f. Complete the table by finding the derivative of each transformation of f, if possible.

(a) $g(x) = f(x) - 2$ (b) $h(x) = 2f(x)$

(c) $r(x) = f(-3x)$ (d) $s(x) = f(x + 2)$

x	-2	-1	0	1	2	3
$f'(x)$	4	$\frac{2}{3}$	$-\frac{1}{3}$	-1	-2	-4
$g'(x)$						
$h'(x)$						
$r'(x)$						
$s'(x)$						

98. Using Relationships Given that $g(5) = -3$, $g'(5) = 6$, $h(5) = 3$, and $h'(5) = -2$, find $f'(5)$ for each of the following, if possible. If it is not possible, state what additional information is required.

(a) $f(x) = g(x)h(x)$ (b) $f(x) = g(h(x))$

(c) $f(x) = \frac{g(x)}{h(x)}$ (d) $f(x) = [g(x)]^3$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding Derivatives **In Exercises 99 and 100, the graphs of f and g are shown. Let $h(x) = f(g(x))$ and $s(x) = g(f(x))$. Find each derivative, if it exists. If the derivative does not exist, explain why.**

99. (a) Find $h'(1)$.

(b) Find $s'(5)$.



100. (a) Find $h'(3)$.

(b) Find $s'(9)$.



101. Doppler Effect The frequency F of a fire truck siren heard by a stationary observer is

$$F = \frac{132{,}400}{331 \pm v}$$

where $\pm v$ represents the velocity of the accelerating fire truck in meters per second (see figure). Find the rate of change of F with respect to v when

(a) the fire truck is approaching at a velocity of 30 meters per second (use $-v$).

(b) the fire truck is moving away at a velocity of 30 meters per second (use $+ v$).



102. Harmonic Motion The displacement from equilibrium of an object in harmonic motion on the end of a spring is

$$y = \frac{1}{3}\cos 12t - \frac{1}{4}\sin 12t$$

where y is measured in feet and t is the time in seconds. Determine the position and velocity of the object when $t = \pi/8$.

103. Pendulum A 15-centimeter pendulum moves according to the equation $\theta = 0.2 \cos 8t$, where θ is the angular displacement from the vertical in radians and t is the time in seconds. Determine the maximum angular displacement and the rate of change of θ when $t = 3$ seconds.

104. Wave Motion A buoy oscillates in simple harmonic motion $y = A \cos \omega t$ as waves move past it. The buoy moves a total of 3.5 feet (vertically) from its low point to its high point. It returns to its high point every 10 seconds.

(a) Write an equation describing the motion of the buoy when it is at its high point at $t = 0$.

(b) Determine the velocity of the buoy as a function of t.

105. Modeling Data The normal daily maximum temperatures T (in degrees Fahrenheit) for Chicago, Illinois, are shown in the table. *(Source: National Oceanic and Atmospheric Administration)*

Month	Jan	Feb	Mar	Apr
Temperature	31.0	35.3	46.6	59.0

Month	May	Jun	Jul	Aug
Temperature	70.0	79.7	84.1	81.9

Month	Sep	Oct	Nov	Dec
Temperature	74.8	62.3	48.2	34.8

(a) Use a graphing utility to plot the data and find a model for the data of the form

$$T(t) = a + b \sin(ct - d)$$

where T is the temperature and t is the time in months, with $t = 1$ corresponding to January.

(b) Use a graphing utility to graph the model. How well does the model fit the data?

(c) Find T' and use a graphing utility to graph T'.

(d) Based on the graph of T', during what times does the temperature change most rapidly? Most slowly? Do your answers agree with your observations of the temperature changes? Explain.

106. HOW DO YOU SEE IT? The cost C (in dollars) of producing x units of a product is $C = 60x + 1350$. For one week, management determined that the number of units produced x at the end of t hours can be modeled by $x = -1.6t^3 + 19t^2 - 0.5t - 1$. The graph shows the cost C in terms of the time t.



(a) Using the graph, which is greater, the rate of change of the cost after 1 hour or the rate of change of the cost after 4 hours?

(b) Explain why the cost function is not increasing at a constant rate during the eight-hour shift.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

107. Biology

The number N of bacteria in a culture after t days is modeled by

$$N = 400\left[1 - \frac{3}{(t^2 + 2)^2}\right].$$

Find the rate of change of N with respect to t when (a) $t = 0$, (b) $t = 1$, (c) $t = 2$, (d) $t = 3$, and (e) $t = 4$. (f) What can you conclude?

Lotus_studio/Shutterstock.com

108. Depreciation The value V of a machine t years after it is purchased is inversely proportional to the square root of $t + 1$. The initial value of the machine is \$10,000.

(a) Write V as a function of t.

(b) Find the rate of depreciation when $t = 1$.

(c) Find the rate of depreciation when $t = 3$.

109. Finding a Pattern Consider the function $f(x) = \sin \beta x$, where β is a constant.

(a) Find the first-, second-, third-, and fourth-order derivatives of the function.

(b) Verify that the function and its second derivative satisfy the equation $f''(x) + \beta^2 f(x) = 0$.

(c) Use the results of part (a) to write general rules for the even- and odd-order derivatives $f^{(2k)}(x)$ and $f^{(2k-1)}(x)$.

[*Hint:* $(-1)^k$ is positive if k is even and negative if k is odd.]

110. Think About It Let f be a differentiable function of period p.

(a) Is the function f' periodic? Verify your answer.

(b) Consider the function $g(x) = f(2x)$. Is the function $g'(x)$ periodic? Verify your answer.

111. Think About It Let $r(x) = f(g(x))$ and $s(x) = g(f(x))$, where f and g are shown in the figure. Find (a) $r'(1)$ and (b) $s'(4)$.



112. Using Trigonometric Functions

(a) Find the derivative of the function $g(x) = \sin^2 x + \cos^2 x$ in two ways.

(b) For $f(x) = \sec^2 x$ and $g(x) = \tan^2 x$, show that

$$f'(x) = g'(x).$$

113. Even and Odd Functions

(a) Show that the derivative of an odd function is even. That is, if $f(-x) = -f(x)$, then $f'(-x) = f'(x)$.

(b) Show that the derivative of an even function is odd. That is, if $f(-x) = f(x)$, then $f'(-x) = -f'(x)$.

114. Proof Let u be a differentiable function of x. Use the fact that $|u| = \sqrt{u^2}$ to prove that

$$\frac{d}{dx}[|u|] = u'\frac{u}{|u|}, \quad u \neq 0.$$

Using Absolute Value **In Exercises 115–118, use the result of Exercise 114 to find the derivative of the function.**

115. $g(x) = |3x - 5|$ **116.** $f(x) = |x^2 - 9|$

117. $h(x) = |x| \cos x$ **118.** $f(x) = |\sin x|$

Linear and Quadratic Approximations **The linear and quadratic approximations of a function f at $x = a$ are**

$$P_1(x) = f'(a)(x - a) + f(a) \quad \text{and}$$
$$P_2(x) = \tfrac{1}{2}f''(a)(x - a)^2 + f'(a)(x - a) + f(a).$$

In Exercises 119 and 120, (a) find the specified linear and quadratic approximations of f, (b) use a graphing utility to graph f and the approximations, (c) determine whether P_1 or P_2 is the better approximation, and (d) state how the accuracy changes as you move farther from $x = a$.

119. $f(x) = \tan x; \quad a = \frac{\pi}{4}$ **120.** $f(x) = \sec x; \quad a = \frac{\pi}{6}$

True or False? **In Exercises 121–124, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

121. The slope of the function $f(x) = \sin ax$ at the origin is a.

122. The slope of the function $f(x) = \cos bx$ at the origin is $-b$.

123. If y is a differentiable function of u, and u is a differentiable function of x, then y is a differentiable function of x.

124. If y is a differentiable function of u, u is a differentiable function of v, and v is a differentiable function of x, then

$$\frac{dy}{dx} = \frac{dy}{du}\frac{du}{dv}\frac{dv}{dx}.$$

PUTNAM EXAM CHALLENGE

125. Let $f(x) = a_1 \sin x + a_2 \sin 2x + \cdots + a_n \sin nx$, where $a_1, a_2, \ldots, a_n$ are real numbers and where n is a positive integer. Given that $|f(x)| \leq |\sin x|$ for all real x, prove that $|a_1 + 2a_2 + \cdots + na_n| \leq 1$.

126. Let k be a fixed positive integer. The nth derivative of $\frac{1}{x^k - 1}$ has the form $\frac{P_n(x)}{(x^k - 1)^{n+1}}$ where $P_n(x)$ is a polynomial. Find $P_n(1)$.

These problems were composed by the Committee on the Putnam Prize Competition. © The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

2.5 Implicit Differentiation

GO DIGITAL

- **Distinguish between functions written in implicit form and explicit form.**
- **Use implicit differentiation to find the derivative of a function.**

Implicit and Explicit Functions

Up to this point in the text, most functions have been expressed in **explicit form.** For example, in the equation $y = 3x^2 - 5$, the variable y is explicitly written as a function of x. Some functions, however, are only implied by an equation. For instance, the function $y = 1/x$ is defined **implicitly** by the equation

$$xy = 1. \qquad \text{Implicit form}$$

To find dy/dx for this equation, you can write y explicitly as a function of x and then differentiate.

Implicit Form	Explicit Form	Derivative
$xy = 1$	$y = \frac{1}{x} = x^{-1}$	$\frac{dy}{dx} = -x^{-2} = -\frac{1}{x^2}$

This strategy works whenever you can solve for the function explicitly. You cannot, however, use this procedure when you are unable to solve for y as a function of x. For instance, how would you find dy/dx for the equation

$$x^2 - 2y^3 + 4y = 2?$$

For this equation, it is difficult to express y as a function of x explicitly. To find dy/dx, you can use **implicit differentiation.**

To understand how to find dy/dx implicitly, you must realize that the differentiation is taking place *with respect to* x. This means that when you differentiate terms involving x alone, you can differentiate as usual. However, when you differentiate terms involving y, you must apply the Chain Rule, because you are assuming that y is defined implicitly as a differentiable function of x.

REMARK When finding a derivative implicitly, you may find it helpful to write the Leibniz notation before each term. So, for Example 1(c), you could write

$$\frac{d}{dx}[x + 3y] = \frac{d}{dx}[x] + \frac{d}{dx}[3y]$$
$$= 1 + 3\frac{dy}{dx}.$$

Note how this technique is used in Example 2.

EXAMPLE 1 Differentiating with Respect to x

a. $\frac{d}{dx}[x^3] = 3x^2$ — Variables agree: use Simple Power Rule.

Variables agree

b. $\frac{d}{dx}[y^3] = \overbrace{3y^2}^{nu^{n-1}}\overbrace{\frac{dy}{dx}}^{u'}$ — Variables disagree: use Chain Rule.

Variables disagree

c. $\frac{d}{dx}[x + 3y] = 1 + 3\frac{dy}{dx}$ — Chain Rule: $\frac{d}{dx}[3y] = 3y'$

d. $\frac{d}{dx}[xy^2] = x\frac{d}{dx}[y^2] + y^2\frac{d}{dx}[x]$ — Product Rule

$= x\left(2y\frac{dy}{dx}\right) + y^2(1)$ — Chain Rule

$= 2xy\frac{dy}{dx} + y^2$ — Simplify.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Implicit Differentiation

Guidelines for Implicit Differentiation

1. Differentiate each side of the equation *with respect to* x.
2. Collect all terms involving dy/dx on the left side of the equation and move all other terms to the right side of the equation.
3. Factor dy/dx out of the left side of the equation.
4. Solve for dy/dx.

In Example 2, note that implicit differentiation can produce an expression for dy/dx that contains both x and y.

EXAMPLE 2 **Implicit Differentiation**

Find dy/dx given that $y^3 + y^2 - 5y - x^2 = -4$.

Solution

1. Differentiate each side of the equation with respect to x.

$$\frac{d}{dx}[y^3 + y^2 - 5y - x^2] = \frac{d}{dx}[-4]$$

$$\frac{d}{dx}[y^3] + \frac{d}{dx}[y^2] - \frac{d}{dx}[5y] - \frac{d}{dx}[x^2] = \frac{d}{dx}[-4]$$

$$3y^2\frac{dy}{dx} + 2y\frac{dy}{dx} - 5\frac{dy}{dx} - 2x = 0$$

2. Collect the dy/dx terms on the left side of the equation and move all other terms to the right side of the equation.

$$3y^2\frac{dy}{dx} + 2y\frac{dy}{dx} - 5\frac{dy}{dx} = 2x$$

3. Factor dy/dx out of the left side of the equation.

$$\frac{dy}{dx}(3y^2 + 2y - 5) = 2x$$

4. Solve for dy/dx by dividing by $(3y^2 + 2y - 5)$.

$$\frac{dy}{dx} = \frac{2x}{3y^2 + 2y - 5}$$



Point on Graph	Slope of Graph
$(2, 0)$	$-\frac{4}{5}$
$(1, -3)$	$\frac{1}{8}$
$x = 0$	0
$(1, 1)$	Undefined

The implicit equation

$$y^3 + y^2 - 5y - x^2 = -4$$

has the derivative

$$\frac{dy}{dx} = \frac{2x}{3y^2 + 2y - 5}.$$

Figure 2.27

To see how you can use an *implicit derivative*, consider the graph shown in Figure 2.27. From the graph, you can see that y is not a function of x. Even so, the derivative found in Example 2 gives a formula for the slope of the tangent line at a point on this graph. The slopes at several points on the graph are shown below the graph.

TECHNOLOGY Most graphing utilities can graph an equation that explicitly represents y as a function of x. Graphing other equations, however, may take some ingenuity. For instance, to graph the equation given in Example 2, use a graphing utility, set in *parametric* mode, to graph the parametric representations $x = \sqrt{t^3 + t^2 - 5t + 4}$, $y = t$, and $x = -\sqrt{t^3 + t^2 - 5t + 4}$, $y = t$, for $-5 \le t \le 5$. How does the result compare with the graph shown in Figure 2.27? (You will learn more about this type of representation when you study parametric equations in Section 10.2.)

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



(a)



(b)



(c)

Some graph segments can be represented by differentiable functions.

Figure 2.28



Figure 2.29

It is meaningless to solve for dy/dx in an equation that has no solution points. (For example, $x^2 + y^2 = -4$ has no solution points.) If, however, a segment of a graph can be represented by a differentiable function, then dy/dx will have meaning as the slope at each point on the segment. Recall that a function is not differentiable at (a) points with vertical tangents and (b) points at which the function is not continuous.

EXAMPLE 3 Graphs and Differentiable Functions

If possible, represent y as a differentiable function of x.

a. $x^2 + y^2 = 0$ **b.** $x^2 + y^2 = 1$ **c.** $x + y^2 = 1$

Solution

a. The graph of this equation is a single point. So, it does not define y as a differentiable function of x. See Figure 2.28(a).

b. The graph of this equation is the unit circle centered at $(0, 0)$. The upper semicircle is given by the differentiable function

$$y = \sqrt{1 - x^2}, \quad -1 < x < 1$$

and the lower semicircle is given by the differentiable function

$$y = -\sqrt{1 - x^2}, \quad -1 < x < 1.$$

At the points $(-1, 0)$ and $(1, 0)$, the slope of the graph is undefined. See Figure 2.28(b).

c. The upper half of this parabola is given by the differentiable function

$$y = \sqrt{1 - x}, \quad x < 1$$

and the lower half of this parabola is given by the differentiable function

$$y = -\sqrt{1 - x}, \quad x < 1.$$

At the point $(1, 0)$, the slope of the graph is undefined. See Figure 2.28(c).

EXAMPLE 4 Finding the Slope of a Graph Implicitly

See LarsonCalculus.com for an interactive version of this type of example.

Determine the slope of the tangent line to the graph of $x^2 + 4y^2 = 4$ at the point $\left(\sqrt{2}, -1/\sqrt{2}\right)$. See Figure 2.29.

Solution

$$x^2 + 4y^2 = 4 \qquad \text{Write original equation.}$$

$$2x + 8y\frac{dy}{dx} = 0 \qquad \text{Differentiate with respect to } x.$$

$$\frac{dy}{dx} = \frac{-2x}{8y} \qquad \text{Solve for } \frac{dy}{dx}.$$

$$= \frac{-x}{4y} \qquad \text{Simplify.}$$

So, at $\left(\sqrt{2}, -1/\sqrt{2}\right)$, the slope is

$$\frac{dy}{dx} = \frac{-\sqrt{2}}{-4/\sqrt{2}} = \frac{1}{2}. \qquad \text{Evaluate } \frac{dy}{dx} \text{ when } x = \sqrt{2} \text{ and } y = -\frac{1}{\sqrt{2}}.$$

GO DIGITAL

To see the benefit of implicit differentiation, try doing Example 4 using the explicit function $y = -\frac{1}{2}\sqrt{4 - x^2}$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 5 Finding the Slope of a Graph Implicitly

Determine the slope of the graph of $3(x^2 + y^2)^2 = 100xy$ at the point $(3, 1)$.

Solution

$$3(x^2 + y^2)^2 = 100xy$$ Write original equation.

$$\frac{d}{dx}[3(x^2 + y^2)^2] = \frac{d}{dx}[100xy]$$ Differentiate with respect to x.

$$3(2)(x^2 + y^2)\left(2x + 2y\frac{dy}{dx}\right) = 100\left[x\frac{dy}{dx} + y(1)\right]$$

$$12y(x^2 + y^2)\frac{dy}{dx} - 100x\frac{dy}{dx} = 100y - 12x(x^2 + y^2)$$ Collect terms.

$$[12y(x^2 + y^2) - 100x]\frac{dy}{dx} = 100y - 12x(x^2 + y^2)$$ Factor out $\frac{dy}{dx}$.

$$\frac{dy}{dx} = \frac{100y - 12x(x^2 + y^2)}{-100x + 12y(x^2 + y^2)}$$ Solve for $\frac{dy}{dx}$.

$$= \frac{25y - 3x(x^2 + y^2)}{-25x + 3y(x^2 + y^2)}$$

At the point $(3, 1)$, the slope of the graph is

$$\frac{dy}{dx} = \frac{25(1) - 3(3)(3^2 + 1^2)}{-25(3) + 3(1)(3^2 + 1^2)} = \frac{25 - 90}{-75 + 30} = \frac{-65}{-45} = \frac{13}{9}$$

as shown in Figure 2.30. This graph is called a **lemniscate.**



Lemniscate
Figure 2.30

EXAMPLE 6 Determining a Differentiable Function

Find dy/dx implicitly for the equation $\sin y = x$. Then find the largest interval of the form $-a < y < a$ on which y is a differentiable function of x (see Figure 2.31).

Solution

$$\sin y = x$$ Write original equation.

$$\frac{d}{dx}[\sin y] = \frac{d}{dx}[x]$$ Differentiate with respect to x.

$$\cos y\frac{dy}{dx} = 1$$

$$\frac{dy}{dx} = \frac{1}{\cos y}$$ Solve for $\frac{dy}{dx}$.

The largest interval about the origin for which y is a differentiable function of x is $-\pi/2 < y < \pi/2$. To see this, note that $\cos y$ is positive for all y in this interval and is 0 at the endpoints. When you restrict y to the interval $-\pi/2 < y < \pi/2$, you should be able to write dy/dx explicitly as a function of x. To do this, use the Pythagorean identity $\sin^2 y + \cos^2 y = 1$ in radical form. Because $\cos y$ is positive on $-\pi/2 < y < \pi/2$, you can write

$$\cos y = \sqrt{1 - \sin^2 y} = \sqrt{1 - x^2}, -\frac{\pi}{2} < y < \frac{\pi}{2}.$$ $\sin y = x$

So, you can conclude that y is differentiable on $-\pi/2 < y < \pi/2$, where

$$\frac{dy}{dx} = \frac{1}{\sqrt{1 - x^2}}.$$

You will study this example further when inverse trigonometric functions are defined in Section 5.7.



The derivative is $\frac{dy}{dx} = \frac{1}{\sqrt{1 - x^2}}$.
Figure 2.31

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

ISAAC BARROW (1630–1677)

The graph in Figure 2.32 is called the **kappa curve** because it resembles the Greek letter kappa, κ. The general solution for the tangent line to this curve was discovered by the English mathematician Isaac Barrow. Newton was Barrow's student, and they corresponded frequently regarding their work in the early development of calculus. *See LarsonCalculus.com to read more of this biography.*

With implicit differentiation, the form of the derivative often can be simplified (as in Example 6) by an appropriate use of the *original* equation. A similar technique can be used to find and simplify higher-order derivatives obtained implicitly.

EXAMPLE 7 Finding the Second Derivative Implicitly

Given $x^2 + y^2 = 25$, find $\dfrac{d^2y}{dx^2}$.

Solution Differentiating each term with respect to x produces

$$2x + 2y\frac{dy}{dx} = 0 \qquad \text{Differentiate with respect to } x.$$

$$2y\frac{dy}{dx} = -2x$$

$$\frac{dy}{dx} = \frac{-2x}{2y} \qquad \text{Solve for } \frac{dy}{dx}.$$

$$= -\frac{x}{y}.$$

Differentiating a second time with respect to x yields

$$\frac{d^2y}{dx^2} = -\frac{(y)(1) - (x)(dy/dx)}{y^2} \qquad \text{Quotient Rule}$$

$$= -\frac{y - (x)(-x/y)}{y^2} \qquad \text{Substitute } -\frac{x}{y} \text{ for } \frac{dy}{dx}.$$

$$= -\frac{y^2 + x^2}{y^3} \qquad \text{Simplify.}$$

$$= -\frac{25}{y^3}. \qquad \text{Substitute 25 for } x^2 + y^2.$$

EXAMPLE 8 Finding a Tangent Line to a Graph

Find the tangent line to the graph of $x^2(x^2 + y^2) = y^2$ at the point $\left(\sqrt{2}/2, \sqrt{2}/2\right)$, as shown in Figure 2.32.



The kappa curve
Figure 2.32

Solution By rewriting and differentiating implicitly, you obtain

$$x^4 + x^2y^2 - y^2 = 0 \qquad \text{Rewrite original equation.}$$

$$4x^3 + x^2\left(2y\frac{dy}{dx}\right) + 2xy^2 - 2y\frac{dy}{dx} = 0 \qquad \text{Differentiate with respect to } x.$$

$$2x^2y\frac{dy}{dx} - 2y\frac{dy}{dx} = -4x^3 - 2xy^2 \qquad \text{Collect terms.}$$

$$2y(x^2 - 1)\frac{dy}{dx} = -2x(2x^2 + y^2) \qquad \text{Factor.}$$

$$\frac{dy}{dx} = \frac{x(2x^2 + y^2)}{y(1 - x^2)}. \qquad \text{Solve for } \frac{dy}{dx}.$$

At the point $\left(\sqrt{2}/2, \sqrt{2}/2\right)$, the slope is

$$\frac{dy}{dx} = \frac{\left(\sqrt{2}/2\right)[2(1/2) + (1/2)]}{\left(\sqrt{2}/2\right)[1 - (1/2)]} = \frac{3/2}{1/2} = 3$$

and the equation of the tangent line at this point is

$$y - \frac{\sqrt{2}}{2} = 3\left(x - \frac{\sqrt{2}}{2}\right) \quad \text{or} \quad y = 3x - \sqrt{2}.$$

GO DIGITAL

SCIENCE PHOTO LIBRARY

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

2.5 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe the difference between the explicit form of a function and an implicit equation. Give an example of each.
2. State the guidelines for implicit differentiation.
3. Explain when implicit differentiation is required to find a derivative.
4. How is the Chain Rule applied when finding dy/dx implicitly?

Finding a Derivative **In Exercises 5–20, find dy/dx by implicit differentiation.**

5. $x^2 + y^2 = 9$
6. $x^2 - y^2 = 25$
7. $x^5 + y^5 = 16$
8. $2x^3 + 3y^3 = 64$
9. $x^3 - xy + y^2 = 7$
10. $x^2y + y^2x = -2$
11. $x^3y^3 - y = x$
12. $\sqrt{xy} = x^2y + 1$
13. $x^3 - 3x^2y + 2xy^2 = 12$
14. $x^4y - 8xy + 3xy^2 = 9$
15. $\sin x + 2\cos 2y = 1$
16. $(\sin \pi x + \cos \pi y)^2 = 2$
17. $\csc x = x(1 + \tan y)$
18. $\cot y = x - y$
19. $y = \sin xy$
20. $x = \sec \dfrac{1}{y}$

Finding Derivatives Implicitly and Explicitly **In Exercises 21–24, (a) find two explicit functions by solving the equation for y in terms of x, (b) sketch the graph of the equation and label the parts given by the corresponding explicit functions, (c) differentiate the explicit functions, and (d) find dy/dx implicitly and show that the result is equivalent to that of part (c).**

21. $x^2 + y^2 = 64$
22. $25x^2 + 36y^2 = 300$
23. $16y^2 - x^2 = 16$
24. $x^2 + y^2 - 4x + 6y + 9 = 0$

Finding the Slope of a Graph **In Exercises 25–32, find dy/dx by implicit differentiation. Then find the slope of the graph at the given point.**

25. $xy = 6, \quad (-6, -1)$
26. $3x^3y = 6, \quad (1, 2)$
27. $y^2 = \dfrac{x^2 - 49}{x^2 + 49}, \quad (7, 0)$
28. $4y^3 = \dfrac{x^2 - 36}{x^3 + 36}, \quad (6, 0)$
29. $(x + y)^3 = x^3 + y^3, \quad (-1, 1)$
30. $x^3 + y^3 = 6xy - 1, \quad (2, 3)$
31. $\tan(x + y) = x, \quad (0, 0)$
32. $x\cos y = 1, \quad \left(2, \dfrac{\pi}{3}\right)$

Famous Curves **In Exercises 33–36, find the slope of the tangent line to the graph at the given point.**

33. Witch of Agnesi: $(x^2 + 4)y = 8$



34. Cissoid of Diocles: $(4 - x)y^2 = x^3$



35. Bifolium: $(x^2 + y^2)^2 = 4x^2y$



36. Folium of Descartes: $x^3 + y^3 - 6xy = 0$



Famous Curves **In Exercises 37–42, find an equation of the tangent line to the graph at the given point. To print an enlarged copy of the graph, go to *MathGraphs.com*.**

37. Parabola



38. Circle



39. Cruciform



40. Astroid



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

41. Lemniscate



42. Kappa curve



Exploring Concepts

43. Write two different equations in implicit form that you can write in explicit form. Then write two different equations in implicit form that you cannot write in explicit form.

44. Write an explicit function for which dy/dx does not have meaning. Explain.

45. Ellipse

(a) Use implicit differentiation to find an equation of the tangent line to the ellipse $\frac{x^2}{2} + \frac{y^2}{8} = 1$ at $(1, 2)$.

(b) Show that the equation of the tangent line to the ellipse $\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$ at (x_0, y_0) is $\frac{x_0 x}{a^2} + \frac{y_0 y}{b^2} = 1$.

46. Hyperbola

(a) Use implicit differentiation to find an equation of the tangent line to the hyperbola $\frac{x^2}{6} - \frac{y^2}{8} = 1$ at $(3, -2)$.

(b) Show that the equation of the tangent line to the hyperbola $\frac{x^2}{a^2} - \frac{y^2}{b^2} = 1$ at (x_0, y_0) is $\frac{x_0 x}{a^2} - \frac{y_0 y}{b^2} = 1$.

Determining a Differentiable Function **In Exercises 47 and 48, find dy/dx implicitly and find the largest interval of the form $-a < y < a$ or $0 < y < a$ such that y is a differentiable function of x. Write dy/dx as a function of x.**

47. $\tan y = x$

48. $\cos y = x$

Finding a Second Derivative **In Exercises 49–54, find d^2y/dx^2 implicitly in terms of x and y.**

49. $x^2 + y^2 = 4$

50. $x^2y - 4x = 5$

51. $x^2y - 2 = 5x + y$

52. $xy - 1 = 2x + y^2$

53. $7xy + \sin x = 2$

54. $3xy - 4\cos x = -6$

Finding an Equation of a Tangent Line **In Exercises 55 and 56, use a graphing utility to graph the equation. Find an equation of the tangent line to the graph at the given point and graph the tangent line in the same viewing window.**

55. $\sqrt{x} + \sqrt{y} = 5, \quad (9, 4)$

56. $y^2 = \frac{x - 1}{x^2 + 1}, \quad \left(2, \frac{\sqrt{5}}{5}\right)$

Tangent Lines and Normal Lines **In Exercises 57 and 58, find equations for the tangent line and normal line to the circle at each given point. (The *normal line* at a point is perpendicular to the tangent line at the point.) Use a graphing utility to graph the circle, the tangent lines, and the normal lines.**

57. $x^2 + y^2 = 25$
$(4, 3), (-3, 4)$

58. $x^2 + y^2 = 36$
$(6, 0), \left(5, \sqrt{11}\right)$

59. Normal Lines Show that the normal line at any point on the circle $x^2 + y^2 = r^2$ passes through the origin.

60. Circles Two circles of radius 4 are tangent to the graph of $y^2 = 4x$ at the point $(1, 2)$. Find equations of these two circles.

Vertical and Horizontal Tangent Lines **In Exercises 61 and 62, find the points at which the graph of the equation has a vertical or horizontal tangent line.**

61. $25x^2 + 16y^2 + 200x - 160y + 400 = 0$

62. $4x^2 + y^2 - 8x + 4y + 4 = 0$

Orthogonal Trajectories **In Exercises 63–66, use a graphing utility to sketch the intersecting graphs of the equations and show that they are orthogonal. [Two graphs are *orthogonal* if at their point(s) of intersection, their tangent lines are perpendicular to each other.]**

63. $2x^2 + y^2 = 6$
$y^2 = 4x$

64. $y^2 = x^3$
$2x^2 + 3y^2 = 5$

65. $x + y = 0$
$x = \sin y$

66. $x^3 = 3(y - 1)$
$x(3y - 29) = 3$

Orthogonal Trajectories **In Exercises 67 and 68, verify that the two families of curves are orthogonal, where C and K are real numbers. Use a graphing utility to graph the two families for two values of C and two values of K.**

67. $xy = C, \quad x^2 - y^2 = K$

68. $x^2 + y^2 = C^2, \quad y = Kx$

69. Orthogonal Trajectories The figure below shows the topographic map carried by a group of hikers. The hikers are in a wooded area on top of the hill shown on the map, and they decide to follow the path of steepest descent (orthogonal trajectories to the contours on the map). Draw their routes when they start from point A and when they start from point B. Their goal is to reach the road along the top of the map. Which starting point should they use? To print an enlarged copy of the map, go to *MathGraphs.com*.



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

70. HOW DO YOU SEE IT? Use the graph to answer the questions.



(a) Which is greater, the slope of the tangent line at $x = -3$ or the slope of the tangent line at $x = -1$?

(b) Estimate the point(s) where the graph has a vertical tangent line.

(c) Estimate the point(s) where the graph has a horizontal tangent line.

71. Finding Equations of Tangent Lines Consider the equation $x^4 = 4(4x^2 - y^2)$.

(a) Use a graphing utility to graph the equation.

(b) Find and graph the four tangent lines to the curve for $y = 3$.

(c) Find the exact coordinates of the point of intersection of the two tangent lines in the first quadrant.

72. Tangent Lines and Intercepts Let L be any tangent line to the curve

$$\sqrt{x} + \sqrt{y} = \sqrt{c}.$$

Show that the sum of the x- and y-intercepts of L is c.

73. Proof Prove (Theorem 2.3) that

$$\frac{d}{dx}[x^n] = nx^{n-1}$$

for the case in which n is a rational number. (*Hint:* Write $y = x^{p/q}$ in the form $y^q = x^p$ and differentiate implicitly. Assume that p and q are integers, where $q > 0$.)

74. Slope Find all points on the circle $x^2 + y^2 = 100$ where the slope is $\frac{3}{4}$.

75. Tangent Lines Find equations of both tangent lines to the graph of the ellipse $\frac{x^2}{4} + \frac{y^2}{9} = 1$ that pass through the point $(4, 0)$ not on the graph.

76. Normals to a Parabola The graph shows the normal lines from the point $(2, 0)$ to the graph of the parabola $x = y^2$. How many normal lines are there from the point $(x_0, 0)$ to the graph of the parabola when (a) $x_0 = \frac{1}{4}$, (b) $x_0 = \frac{1}{2}$, and (c) $x_0 = 1$? (d) For what value of x_0 are two of the normal lines perpendicular to each other?



77. Normal Lines (a) Find an equation of the normal line to the ellipse $\frac{x^2}{32} + \frac{y^2}{8} = 1$ at the point $(4, 2)$. (b) Use a graphing utility to graph the ellipse and the normal line. (c) At what other point does the normal line intersect the ellipse?

SECTION PROJECT

Optical Illusions

In each graph below, an optical illusion is created by having lines intersect a family of curves. In each case, the lines appear to be curved. Find the value of dy/dx for the given values.

(a) Circles: $x^2 + y^2 = C^2$

$x = 3, y = 4, C = 5$



(b) Hyperbolas: $xy = C$

$x = 1, y = 4, C = 4$



(c) Lines: $ax = by$

$x = \sqrt{3}, y = 3,$

$a = \sqrt{3}, b = 1$



(d) Cosine curves: $y = C\cos x$

$x = \frac{\pi}{3}, y = \frac{1}{3}, C = \frac{2}{3}$



FOR FURTHER INFORMATION For more information on the mathematics of optical illusions, see the article "Descriptive Models for Perception of Optical Illusions" by David A. Smith in *The UMAP Journal*.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

2.6 Related Rates

- **Find a related rate.**
- **Use related rates to solve real-life problems.**



Volume is related to radius and height.
Figure 2.33

Finding Related Rates

You have seen how the Chain Rule can be used to find dy/dx implicitly. Another important use of the Chain Rule is to find the rates of change of two or more related variables that are changing with respect to *time*.

For example, when water is drained out of a conical tank (see Figure 2.33), the volume V, the radius r, and the height h of the water level are all functions of time t. Because these variables are related by the formula for the volume of a right circular cone

$$V = \frac{\pi}{3} r^2 h \qquad \text{Original equation}$$

you can differentiate implicitly with respect to t to obtain the **related-rate** equation

$$\begin{aligned} \frac{d}{dt}[V] &= \frac{d}{dt}\left[\frac{\pi}{3} r^2 h\right] \\ \frac{dV}{dt} &= \frac{\pi}{3}\left[r^2 \frac{dh}{dt} + h\left(2r \frac{dr}{dt}\right)\right] \qquad \text{Differentiate with respect to } t. \\ &= \frac{\pi}{3}\left(r^2 \frac{dh}{dt} + 2rh \frac{dr}{dt}\right). \end{aligned}$$

From this equation, you can see that the rate of change of V is related to the rates of change of both h and r.

Exploration

Finding a Related Rate In the conical tank shown in Figure 2.33, the height of the water level is changing at a rate of -0.2 foot per minute and the radius is changing at a rate of -0.1 foot per minute. What is the rate of change of the volume when the radius is $r = 1$ foot and the height is $h = 2$ feet? Does the rate of change of the volume depend on the values of r and h? Explain.

EXAMPLE 1 Two Rates That Are Related

The variables x and y are both differentiable functions of t and are related by the equation $y = x^2 + 3$. Find dy/dt when $x = 1$, given that $dx/dt = 2$ when $x = 1$.

Solution Use the Chain Rule to differentiate each side of the equation with respect to t.

$$\begin{aligned} y &= x^2 + 3 && \text{Write original equation.} \\ \frac{d}{dt}[y] &= \frac{d}{dt}[x^2 + 3] && \text{Differentiate with respect to } t. \\ \frac{dy}{dt} &= 2x \frac{dx}{dt} && \text{Chain Rule} \end{aligned}$$

When $x = 1$ and $dx/dt = 2$, you have

$$\frac{dy}{dt} = 2(1)(2) = 4.$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Problem Solving with Related Rates

In Example 1, you were *given* an equation that related the variables x and y and were asked to find the rate of change of y when $x = 1$.

Equation: $y = x^2 + 3$

Given rate: $\frac{dx}{dt} = 2$ when $x = 1$

Find: $\frac{dy}{dt}$ when $x = 1$

In each of the remaining examples in this section, you must *create* a mathematical model from a verbal description.

EXAMPLE 2 A Changing Area



Total area increases as the outer radius increases.
Figure 2.34

A pebble is dropped into a calm pond, causing ripples in the form of concentric circles, as shown in Figure 2.34. The radius r of the outer ripple is increasing at a constant rate of 1 foot per second. When the radius is 4 feet, at what rate is the total area A of the disturbed water changing?

Solution The variables r and A are related by the equation for the area of a circle, $A = \pi r^2$. The rate of change of the radius r is constant at 1 foot per second. So, $dr/dt = 1$.

Equation: $A = \pi r^2$ Area of a circle

Given rate: $\frac{dr}{dt} = 1$ foot per second (constant rate)

Find: $\frac{dA}{dt}$ when $r = 4$ feet

With this information, differentiate each side of the equation with respect to t and find dA/dt.

$$\frac{d}{dt}[A] = \frac{d}{dt}[\pi r^2]$$ Differentiate with respect to t.

$$\frac{dA}{dt} = 2\pi r \frac{dr}{dt}$$ Chain Rule

$$= 2\pi(4)(1)$$ Substitute 4 for r and 1 for $\frac{dr}{dt}$.

$$= 8\pi \text{ square feet per second}$$ Simplify.

When the radius is 4 feet, the area is changing at a rate of 8π square feet per second. ■

REMARK When using these guidelines, be sure you perform Step 3 before Step 4. Substituting the known values of the variables before differentiating will produce an inappropriate derivative.

Guidelines for Solving Related-Rate Problems

1. Identify all *given* quantities and quantities *to be determined*. Make a sketch and label the quantities.
2. Write an equation involving the variables whose rates of change either are given or are to be determined.
3. Using the Chain Rule, implicitly differentiate each side of the equation *with respect to time t*.
4. *After* completing Step 3, substitute into the resulting equation all known values for the variables and their rates of change. Then solve for the required rate of change.

severija/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

FOR FURTHER INFORMATION
To learn more about the history of related-rate problems, see the article "The Lengthening Shadow: The Story of Related Rates" by Bill Austin, Don Barry, and David Berman in *Mathematics Magazine*. To view this article, go to *MathArticles.com*.

The table below lists examples of mathematical models involving rates of change. For instance, the rate of change in the first example is the velocity of a car.

Verbal Statement	Mathematical Model
The velocity of a car after traveling for 1 hour is 50 miles per hour.	$x =$ distance traveled $\frac{dx}{dt} = 50$ mi/h when $t = 1$
Water is being pumped into a swimming pool at a rate of 10 cubic meters per hour.	$V =$ volume of water in pool $\frac{dV}{dt} = 10\ \text{m}^3/\text{h}$
A gear is revolving at a rate of 25 revolutions per minute (1 revolution $= 2\pi$ rad).	$\theta =$ angle of revolution $\frac{d\theta}{dt} = 25(2\pi)$ rad/min
A population of bacteria is increasing at a rate of 2000 per hour.	$x =$ number in population $\frac{dx}{dt} = 2000$ bacteria per hour

EXAMPLE 3 An Inflating Balloon

Air is being pumped into a spherical balloon at a rate of 4.5 cubic feet per minute. Find the rate of change of the radius when the radius is 2 feet.

Solution Let V be the volume of the balloon, and let r be its radius. Because the volume is increasing at a rate of 4.5 cubic feet per minute, you know that at time t the rate of change of the volume is $dV/dt = \frac{9}{2}$. So, the problem can be stated as shown.

Given rate: $\frac{dV}{dt} = \frac{9}{2}$ cubic feet per minute (constant rate)

Find: $\frac{dr}{dt}$ when $r = 2$ feet

To find the rate of change of the radius, write an equation that relates the radius r to the volume V. To do this, use the formula for the volume of a sphere.

Equation: $V = \frac{4}{3}\pi r^3$ Volume of a sphere

REMARK The formula for the volume of a sphere and other formulas from geometry are listed on the formula cards for this text.

Differentiating each side of the equation with respect to t produces

$$\frac{dV}{dt} = 4\pi r^2 \frac{dr}{dt}$$ Differentiate with respect to t.

$$\frac{dr}{dt} = \frac{1}{4\pi r^2}\left(\frac{dV}{dt}\right).$$ Solve for $\frac{dr}{dt}$.

Finally, when $r = 2$, the rate of change of the radius is

$$\frac{dr}{dt} = \frac{1}{4\pi(2)^2}\left(\frac{9}{2}\right) \approx 0.09 \text{ foot per minute.}$$ ■

In Example 3, note that the volume is increasing at a *constant* rate, but the radius is increasing at a *variable* rate. Just because two rates are related does not mean that they are proportional. In this particular case, the radius is growing more and more slowly as t increases. Do you understand why?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

EXAMPLE 4 The Speed of an Airplane Tracked by Radar

See LarsonCalculus.com for an interactive version of this type of example.

An airplane is flying on a flight path that will take it directly over a radar tracking station, as shown in Figure 2.35. The distance s is decreasing at a rate of 400 miles per hour when $s = 10$ miles. What is the speed of the plane?



An airplane is flying at an altitude of 6 miles, s miles from the station.
Figure 2.35

Solution Let x be the horizontal distance from the station, as shown in Figure 2.35. Notice that when $s = 10$, $x = \sqrt{10^2 - 6^2} = 8$. Also, ds/dt is negative because s represents a distance that is decreasing.

Given rate: $ds/dt = -400$ miles per hour when $s = 10$ miles
Find: dx/dt when $s = 10$ miles and $x = 8$ miles

In Figure 2.35, note that the distances 6, x, and s are the sides of a right triangle. So, use the Pythagorean Theorem to write an equation that relates these quantities.

Equation: $x^2 + 6^2 = s^2$ Pythagorean Theorem

$$2x\frac{dx}{dt} = 2s\frac{ds}{dt}$$ Differentiate with respect to t.

$$\frac{dx}{dt} = \frac{s}{x}\left(\frac{ds}{dt}\right)$$ Solve for $\frac{dx}{dt}$.

$$= \frac{10}{8}(-400)$$ Substitute for s, x, and $\frac{ds}{dt}$.

$$= -500 \text{ miles per hour}$$ Simplify.

Because the velocity is -500 miles per hour, the *speed* is 500 miles per hour. (Note that the velocity is negative because x represents a distance that is decreasing.)

EXAMPLE 5 A Changing Angle of Elevation

Find the rate of change in the angle of elevation of the camera shown in Figure 2.36 at 10 seconds after liftoff.



A television camera at ground level is filming the liftoff of a rocket that is rising vertically according to the position equation $s = 50t^2$, where s is measured in feet and t is measured in seconds. The camera is 2000 feet from the launch pad.
Figure 2.36

Solution Let θ be the angle of elevation, as shown in Figure 2.36. When $t = 10$, the height s of the rocket is $s = 50t^2 = 50(10)^2 = 5000$ feet.

Given rate: $ds/dt = 100t =$ velocity of rocket (in feet per second)
Find: $d\theta/dt$ when $t = 10$ seconds and $s = 5000$ feet

Using Figure 2.36, you can relate s and θ by the equation $\tan\theta = s/2000$.

Equation: $\tan\theta = \frac{s}{2000}$ See Figure 2.36.

$$(\sec^2\theta)\frac{d\theta}{dt} = \frac{1}{2000}\left(\frac{ds}{dt}\right)$$ Differentiate with respect to t.

$$\frac{d\theta}{dt} = \cos^2\theta\,\frac{100t}{2000}$$ Substitute $100t$ for $\frac{ds}{dt}$.

$$= \left(\frac{2000}{\sqrt{s^2 + 2000^2}}\right)^2 \frac{100t}{2000}$$ $\cos\theta = \frac{2000}{\sqrt{s^2 + 2000^2}}$

When $t = 10$ and $s = 5000$, you have

$$\frac{d\theta}{dt} = \frac{2000(100)(10)}{5000^2 + 2000^2} = \frac{2}{29} \text{ radian per second.}$$

So, when $t = 10$, θ is changing at a rate of $\frac{2}{29}$ radian per second.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 6 The Velocity of a Piston

In the engine shown in Figure 2.37, a seven-inch connecting rod is fastened to a crank of radius 3 inches. The crankshaft rotates counterclockwise at a constant rate of 200 revolutions per minute. Find the velocity of the piston when $\theta = \pi/3$.



The velocity of a piston is related to the angle of the crankshaft.
Figure 2.37

Solution Label the distances as shown in Figure 2.37. Because a complete revolution corresponds to 2π radians, it follows that $d\theta/dt = 200(2\pi) = 400\pi$ radians per minute.

Given rate: $\dfrac{d\theta}{dt} = 400\pi$ radians per minute (constant rate)

Find: $\dfrac{dx}{dt}$ when $\theta = \dfrac{\pi}{3}$



Law of Cosines:
$b^2 = a^2 + c^2 - 2ac\cos\theta$
Figure 2.38

Use the Law of Cosines (see Figure 2.38) with $a = 3$, $b = 7$, and $c = x$, to write an equation that relates x and θ.

Equation:

$$7^2 = 3^2 + x^2 - 2(3)(x)\cos\theta$$

$$0 = 2x\frac{dx}{dt} - 6\left(-x\sin\theta\frac{d\theta}{dt} + \cos\theta\frac{dx}{dt}\right)$$

$$(6\cos\theta - 2x)\frac{dx}{dt} = 6x\sin\theta\frac{d\theta}{dt}$$

$$\frac{dx}{dt} = \frac{6x\sin\theta}{6\cos\theta - 2x}\left(\frac{d\theta}{dt}\right)$$

When $\theta = \pi/3$, you can solve for x as shown.

$$7^2 = 3^2 + x^2 - 2(3)(x)\cos\frac{\pi}{3} \qquad \text{Substitute } \pi/3 \text{ for } \theta.$$

$$49 = 9 + x^2 - 6x\left(\frac{1}{2}\right)$$

$$0 = x^2 - 3x - 40 \qquad \text{Write in general form.}$$

$$0 = (x - 8)(x + 5) \qquad \text{Factor.}$$

$$x = 8 \text{ inches} \qquad \text{Choose positive solution.}$$

When $x = 8$ and $\theta = \pi/3$, you have

$$\frac{dx}{dt} = \frac{6(8)\left(\sqrt{3}/2\right)}{6(1/2) - 16}(400\pi)$$

$$= \frac{9600\pi\sqrt{3}}{-13}$$

$$\approx -4018 \text{ inches per minute.}$$

So, when $\theta = \pi/3$, the velocity of the piston is decreasing at a rate of 4018 inches per minute. (Note that the velocity is negative because x represents a distance that is decreasing.)

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

2.6 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. What is a related-rate equation?
2. State the guidelines for solving real-life related-rate problems.

Using Related Rates **In Exercises 3–6, assume that x and y are both differentiable functions of t. Find the required values of dy/dt and dx/dt.**

	Equation	Find	Given
3.	$y = \sqrt{x}$	(a) $\frac{dy}{dt}$ when $x = 4$	$\frac{dx}{dt} = 3$
		(b) $\frac{dx}{dt}$ when $x = 25$	$\frac{dy}{dt} = 2$
4.	$y = 3x^2 - 5x$	(a) $\frac{dy}{dt}$ when $x = 3$	$\frac{dx}{dt} = 2$
		(b) $\frac{dx}{dt}$ when $x = 2$	$\frac{dy}{dt} = 4$
5.	$xy = 4$	(a) $\frac{dy}{dt}$ when $x = 8$	$\frac{dx}{dt} = 10$
		(b) $\frac{dx}{dt}$ when $x = 1$	$\frac{dy}{dt} = -6$
6.	$x^2 + y^2 = 25$	(a) $\frac{dy}{dt}$ when $x = 3, y = 4$	$\frac{dx}{dt} = 8$
		(b) $\frac{dx}{dt}$ when $x = 4, y = 3$	$\frac{dy}{dt} = -2$

Moving Point **In Exercises 7–10, a point is moving along the graph of the given function at the rate dx/dt. Find dy/dt for the indicated given values of x.**

7. $y = 2x^2 + 1$; $\frac{dx}{dt} = 2$ centimeters per second

   (a) $x = -1$ (b) $x = 0$ (c) $x = 1$

8. $y = \frac{1}{1 + x^2}$; $\frac{dx}{dt} = 6$ inches per second

   (a) $x = -2$ (b) $x = 0$ (c) $x = 2$

9. $y = \tan x$; $\frac{dx}{dt} = 3$ feet per second

   (a) $x = -\frac{\pi}{3}$ (b) $x = -\frac{\pi}{4}$ (c) $x = 0$

10. $y = \cos x$; $\frac{dx}{dt} = 4$ centimeters per second

    (a) $x = \frac{\pi}{6}$ (b) $x = \frac{\pi}{4}$ (c) $x = \frac{\pi}{3}$

11. **Area** The radius r of a circle is increasing at a rate of 4 centimeters per minute. Find the rates of change of the area when $r = 37$ centimeters.

12. **Area** The length s of each side of an equilateral triangle is increasing at a rate of 13 feet per hour. Find the rate of change of the area when $s = 41$ feet. (*Hint:* The formula for the area of an equilateral triangle is $A = \frac{s^2\sqrt{3}}{4}$.)

13. **Volume** The radius r of a sphere is increasing at a rate of 3 inches per minute.

    (a) Find the rate of change of the volume when $r = 9$ inches and when $r = 36$ inches.

    (b) Explain why the rate of change of the volume of the sphere is not constant even though dr/dt is constant.

14. **Radius** A spherical balloon is inflated with gas at a rate of 800 cubic centimeters per minute.

    (a) Find the rate of change of the radius when $r = 30$ centimeters and when $r = 85$ centimeters.

    (b) Explain why the rate of change of the radius of the sphere is not constant even though dV/dt is constant.

15. **Volume** All edges of a cube are expanding at a rate of 6 centimeters per second. How fast is the volume changing when each edge is (a) 2 centimeters and (b) 10 centimeters?

16. **Surface Area** All edges of a cube are expanding at a rate of 6 centimeters per second. How fast is the surface area changing when each edge is (a) 2 centimeters and (b) 10 centimeters?

17. **Height** At a sand and gravel plant, sand is falling off a conveyor and onto a conical pile at a rate of 10 cubic feet per minute. The diameter of the base of the cone is approximately three times the altitude. At what rate is the height of the pile changing when the pile is 15 feet high? (*Hint:* The formula for the volume of a cone is $V = \frac{1}{3}\pi r^2 h$.)

18. **Height** The volume of oil in a cylindrical container is increasing at a rate of 150 cubic inches per second. The height of the cylinder is approximately ten times the radius. At what rate is the height of the oil changing when the oil is 35 inches high? (*Hint:* The formula for the volume of a cylinder is $V = \pi r^2 h$.)

19. **Depth** A swimming pool is 12 meters long, 6 meters wide, 1 meter deep at the shallow end, and 3 meters deep at the deep end (see figure). Water is being pumped into the pool at a rate of $\frac{1}{4}$ cubic meter per minute, and there is 1 meter of water at the deep end.



    (a) What percent of the pool is filled?

    (b) At what rate is the water level rising?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

20. Depth A trough is 12 feet long and 3 feet across the top (see figure). Its ends are isosceles triangles with altitudes of 3 feet.



(a) Water is being pumped into the trough at a rate of 2 cubic feet per minute. How fast is the water level rising when the depth h is 1 foot?

(b) The water is rising at a rate of $\frac{3}{8}$ inch per minute when $h = 2$ feet. Determine the rate at which water is being pumped into the trough.

21. Moving Ladder A ladder 25 feet long is leaning against the wall of a house (see figure). The base of the ladder is pulled away from the wall at a rate of 2 feet per second.

(a) How fast is the top of the ladder moving down the wall when its base is 7 feet, 15 feet, and 24 feet from the wall?

(b) Consider the triangle formed by the side of the house, the ladder, and the ground. Find the rate at which the area of the triangle is changing when the base of the ladder is 7 feet from the wall.

(c) Find the rate at which the angle between the ladder and the wall of the house is changing when the base of the ladder is 7 feet from the wall.



Figure for 21



Figure for 22

FOR FURTHER INFORMATION For more information on the mathematics of moving ladders, see the article "The Falling Ladder Paradox" by Paul Scholten and Andrew Simoson in *The College Mathematics Journal*. To view this article, go to *MathArticles.com*.

22. Construction A construction worker pulls a five-meter plank up the side of a building under construction by means of a rope tied to one end of the plank (see figure). Assume the opposite end of the plank follows a path perpendicular to the wall of the building and the worker pulls the rope at a rate of 0.15 meter per second. How fast is the end of the plank sliding along the ground when it is 2.5 meters from the wall of the building?

23. Construction A winch at the top of a 12-meter building pulls a pipe of the same length to a vertical position, as shown in the figure. The winch pulls in rope at a rate of -0.2 meter per second. Find the rate of vertical change and the rate of horizontal change at the end of the pipe when $y = 6$ meters.



Figure for 23



Figure for 24

24. Boating A boat is pulled into a dock by means of a winch 12 feet above the deck of the boat (see figure).

(a) The winch pulls in rope at a rate of 4 feet per second. Determine the speed of the boat when there is 13 feet of rope out. What happens to the speed of the boat as it gets closer to the dock?

(b) Suppose the boat is moving at a constant rate of 4 feet per second. Determine the speed at which the winch pulls in rope when there is a total of 13 feet of rope out. What happens to the speed at which the winch pulls in rope as the boat gets closer to the dock?

25. Air Traffic Control An air traffic controller spots two planes at the same altitude converging on a point as they fly at right angles to each other (see figure). One plane is 225 miles from the point, moving at 450 miles per hour. The other plane is 300 miles from the point, moving at 600 miles per hour.

(a) At what rate is the distance s between the planes decreasing?

(b) How much time does the air traffic controller have to get one of the planes on a different flight path?



Figure for 25



Figure for 26

26. Air Traffic Control An airplane is flying at an altitude of 5 miles and passes directly over a radar antenna (see figure). When the plane is 10 miles away ($s = 10$), the radar detects that the distance s is changing at a rate of 240 miles per hour. What is the speed of the plane?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

27. Sports A baseball diamond has the shape of a square with sides 90 feet long (see figure). A player running from second base to third base at a speed of 25 feet per second is 20 feet from third base. At what rate is the player's distance from home plate changing?



Figure for 27 and 28



Figure for 29

28. Sports For the baseball diamond in Exercise 27, suppose the player is running from first base to second base at a speed of 25 feet per second. Find the rate at which the distance from home plate is changing when the player is 20 feet from second base.

29. Shadow Length A 6-foot-tall student walks at a rate of 5 feet per second away from a light that is 15 feet above the ground (see figure).

(a) When the student is 10 feet from the base of the light, at what rate is the tip of their shadow moving?

(b) When the student is 10 feet from the base of the light, at what rate is the length of their shadow changing?

30. Shadow Length Repeat Exercise 29 for a 6-foot-tall student walking at a rate of 5 feet per second *toward* a light that is 20 feet above the ground (see figure).



Figure for 30



Figure for 31

31. Machine Design The endpoints of a movable rod of length 1 meter have coordinates $(x, 0)$ and $(0, y)$ (see figure). The position of the end on the x-axis is

$$x(t) = \frac{1}{2}\sin\frac{\pi t}{6}$$

where t is the time in seconds.

(a) Find the time of one complete cycle of the rod.

(b) What is the lowest point reached by the end of the rod on the y-axis?

(c) Find the speed of the y-axis endpoint when the x-axis endpoint is $\left(\frac{1}{4}, 0\right)$.

32. Machine Design Repeat Exercise 31 for a position function of $x(t) = \frac{3}{5}\sin \pi t$. Use the point $\left(\frac{3}{10}, 0\right)$ for part (c).

33. Evaporation As a spherical raindrop falls, it reaches a layer of dry air and begins to evaporate at a rate that is proportional to its surface area ($S = 4\pi r^2$). Show that the radius of the raindrop decreases at a constant rate.

34. HOW DO YOU SEE IT? Using the graph of f, (a) determine whether dy/dt is positive or negative given that dx/dt is negative, and (b) determine whether dx/dt is positive or negative given that dy/dt is positive. Explain.

(i)



(ii)



Exploring Concepts

35. Describe the relationship between the rate of change of y and the rate of change of x in each expression. Assume all variables and derivatives are positive.

(a) $\frac{dy}{dt} = 3\frac{dx}{dt}$ (b) $\frac{dy}{dt} = x(L - x)\frac{dx}{dt}$, $0 \le x \le L$

36. Let V be the volume of a cube of side length s that is changing with respect to time. If ds/dt is constant, how does dV/dt change? Explain.

37. Electricity The combined electrical resistance R of two resistors R_1 and R_2, connected in parallel, is

$$\frac{1}{R} = \frac{1}{R_1} + \frac{1}{R_2}$$

where R, R_1, and R_2 are measured in ohms. R_1 and R_2 are increasing at rates of 1 and 1.5 ohms per second, respectively. At what rate is R changing when $R_1 = 50$ ohms and $R_2 = 75$ ohms?

38. Electrical Circuit The voltage V in volts of an electrical circuit is $V = IR$, where R is the resistance in ohms and I is the current in amperes. R is increasing at a rate of 2 ohms per second, and V is increasing at a rate of 3 volts per second. At what rate is I changing when $V = 12$ volts and $R = 4$ ohms?

39. Flight Control An airplane is flying in still air with an airspeed of 275 miles per hour. The plane is climbing at an angle of 18°. Find the rate at which the plane is gaining altitude.

40. Angle of Elevation A balloon rises at a rate of 4 meters per second from a point on the ground 50 meters from an observer. Find the rate of change of the angle of elevation of the balloon from the observer when the balloon is 50 meters above the ground.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

41. Angle of Elevation A fish is reeled in along the water's surface at a rate of 1 foot per second from a point 10 feet above the surface (see figure). At what rate is the angle θ between the line and the water changing when there is a total of 25 feet of line from the end of the rod to the water?



Figure for 41



Figure for 42

42. Angle of Elevation An airplane flies at an altitude of 5 miles toward a point directly over an observer (see figure). The speed of the plane is 600 miles per hour. Find the rates at which the angle of elevation θ is changing when the angle is (a) $\theta = 30°$, (b) $\theta = 60°$, and (c) $\theta = 75°$.

43. Linear vs. Angular Speed A patrol car is parked 50 feet from a long warehouse (see figure). The revolving light on top of the car turns at a rate of 30 revolutions per minute. How fast is the light beam moving along the wall when the beam makes angles of (a) $\theta = 30°$, (b) $\theta = 60°$, and (c) $\theta = 70°$ with the perpendicular line from the light to the wall?



Figure for 43



Figure for 44

44. Linear vs. Angular Speed A wheel of radius 30 centimeters revolves at a rate of 10 revolutions per second. A dot is painted at a point P on the rim of the wheel (see figure).

(a) Find dx/dt as a function of θ.

(b) Use a graphing utility to graph the function in part (a).

(c) When is the absolute value of the rate of change of x greatest? When is it least?

(d) Find dx/dt when $\theta = 30°$ and $\theta = 60°$.

45. Area The included angle of the two sides of constant equal length s of an isosceles triangle is θ.

(a) Show that the area of the triangle is given by $A = \frac{1}{2}s^2 \sin\theta$.

(b) The angle θ is increasing at the rate of $\frac{1}{2}$ radian per minute. Find the rates of change of the area when $\theta = \pi/6$ and $\theta = \pi/3$.

46. Security Camera A security camera centered 50 feet above the floor pans back and forth along the length of a 100-foot hallway (see figure). A variable rate of rotation must be used to change the center of focus along the hallway floor at a constant rate. Find a model for the variable rate of rotation when $|dx/dt| = 2$ feet per second.



Figure for 46

47. Modeling Data The table shows the numbers (in millions) of participants in the free lunch program f and the reduced price lunch program r in the United States for the years 2013 through 2020. (*Source: U.S. Department of Agriculture*)

Year	2013	2014	2015	2016
f	18.9	19.2	19.8	20.1
r	2.6	2.5	2.2	2.0

Year	2017	2018	2019	2020
f	20.0	20.2	20.1	16.0
r	2.0	1.8	1.7	1.2

(a) Use the regression capabilities of a graphing utility to find a model of the form

$$r(f) = af^3 + bf^2 + cf + d$$

for the data, where t is the time in years, with $t = 13$ corresponding to 2013.

(b) Find dr/dt. Then use the model to estimate dr/dt for $t = 18$ when it is predicted that the number of participants in the free lunch program will increase at the rate of 0.25 million participants per year.

48. Moving Shadow A ball is dropped from a height of 20 meters, 12 meters away from the top of a 20-meter lamppost (see figure). The ball's shadow, caused by the light at the top of the lamppost, is moving along the level ground. How fast is the shadow moving 1 second after the ball is released? *(Submitted by Dennis Gittinger, St. Philips College, San Antonio, TX)*



Acceleration **In Exercises 49 and 50, find the acceleration of the specified object. (*Hint:* Recall that if a variable is changing at a constant rate, then its acceleration is zero.)**

49. Find the acceleration of the top of the ladder described in Exercise 21 when the base of the ladder is 7 feet from the wall.

50. Find the acceleration of the boat in Exercise 24(a) when there is a total of 13 feet of rope out.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Review Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Exploring Concepts

In this chapter, you learned that the limit used to define the slope of a tangent line is also used to define one of the big ideas of calculus—differentiation. The derivative of f at x is

$$f'(x) = \lim_{\Delta x \to 0} \frac{f(x + \Delta x) - f(x)}{\Delta x}$$

provided that the limit exists. Note how this definition allows you to do more than you can with precalculus. With precalculus, you can find the average change between $t = a$ and $t = b$. With the derivative, you can now find the instantaneous rate of change at $t = a$. The chapter also developed rules for finding derivatives, such as the product and chain rules.

1. Consider a car moving according to the position function $s(t) = -16t^2 + 64t + 80$.

(a) Determine the position at $t = 0$, $t = 2$, and $t = 4$.

(b) Calculate the average velocity between $s(2)$ and $s(4)$. Did you need to use calculus?

(c) Calculate the instantaneous velocity of the car when $t = 4$. Did you need calculus?

(d) Describe how you could use limits to find the instantaneous velocity of the car.

2. Sketch the graph of $f(x) = -16x^2 + 64x + 80$.

(a) Calculate the slope of the secant line through $f(2)$ and $f(4)$. Did you need calculus?

(b) Calculate the slope of the tangent line at the point $f(4)$. Did you need calculus?

(c) Explain how to use secant lines and limits to find the slope of a graph at a particular point.

(d) How does this exercise compare to Exercise 1?

3. Sketch a graph of a function whose derivative is always positive. Explain how you found your answer.

4. Find a second-degree polynomial

$$f(x) = ax^2 + bx + c$$

such that its graph has a tangent line with slope 10 at the point $(2, 7)$ and an x-intercept at $(1, 0)$.

5. Choose a differentiable function $p(x)$, a point $(c, p(c))$, and a nearby point $(c + h, p(c + h))$. Write equations for the tangent line to the graph of p at $(c, p(c))$ and the secant line passing through $(c, p(c))$ and $(c + h, p(c + h))$.

(a) Use a graphing utility to graph p, the tangent line, and the secant line.

(b) Find a function $D(x)$ for the difference between the tangent line and the secant line. Use a graphing utility to graph D. What do you notice about $D(x)$?

(c) Choose another function for p. What do you observe?

6. Let $f(x) = ax^3 + bx^2 + cx + d$, where $a \neq 0$. Determine conditions for a, b, c, and d when the graph of f has (a) no horizontal tangents, (b) exactly one horizontal tangent, and (c) exactly two horizontal tangents. Give an example for each case.

Finding the Derivative by the Limit Process

In Exercises 7–10, find the derivative of the function by the limit process.

7. $f(x) = 12$

8. $f(x) = 5x - 4$

9. $f(x) = x^3 - 2x + 1$

10. $f(x) = \dfrac{6}{x}$

Using the Alternative Form of the Derivative

In Exercises 11 and 12, use the alternative form of the derivative to find the derivative at $x = c$, if it exists.

11. $g(x) = 2x^2 - 3x, \quad c = 2$

12. $f(x) = \dfrac{1}{x + 4}, \quad c = 3$

Determining Differentiability

In Exercises 13 and 14, describe the x-values at which f is differentiable.

13. $f(x) = (x - 3)^{2/5}$



14. $f(x) = \dfrac{3x}{x + 1}$



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding a Derivative **In Exercises 15–26, use differentiation rules to find the derivative of the function.**

15. $y = 25$

16. $f(t) = \pi/6$

17. $f(x) = x^3 - 11x^2$

18. $g(s) = 3s^5 - 2s^4$

19. $h(x) = 6\sqrt{x} + 3\sqrt[3]{x}$

20. $f(x) = x^{1/2} - x^{-5/6}$

21. $g(t) = \dfrac{2}{3t^2}$

22. $h(x) = \dfrac{8}{5x^4}$

23. $f(\theta) = 4\theta - 5\sin\theta$

24. $g(\alpha) = 4\cos\alpha + 6$

25. $f(\theta) = 3\cos\theta - \dfrac{\sin\theta}{4}$

26. $g(\alpha) = \dfrac{5\sin\alpha}{3} - 2\alpha$

Finding the Slope of a Graph **In Exercises 27–30, find the slope of the graph of the function at the given point.**

27. $f(x) = \dfrac{27}{x^3}, \quad (3, 1)$

28. $f(x) = 3x^2 - 4x, \quad (1, -1)$

29. $f(x) = 4x^5 + 3x - \sin x, \quad (0, 0)$

30. $f(x) = 5\cos x - 9x, \quad (0, 5)$

31. Vibrating String When a guitar string is plucked, it vibrates with a frequency of $F = 200\sqrt{T}$, where F is measured in vibrations per second and the tension T is measured in pounds. Find the rates of change of the frequency when (a) $T = 4$ pounds and (b) $T = 9$ pounds.

32. Surface Area The surface area of a cube with sides of length x is given by $S = 6x^2$. Find the rate of change of the surface area with respect to x when $x = 4$ inches.

Vertical Motion **In Exercises 33 and 34, use the position function $s(t) = -16t^2 + v_0t + s_0$ for free-falling objects.**

33. A ball is thrown straight down from the top of a 600-foot building with an initial velocity of -30 feet per second.

(a) Determine the position and velocity functions for the ball.

(b) Determine the average velocity on the interval $[1, 3]$.

(c) Find the instantaneous velocities when $t = 1$ and $t = 3$.

(d) Find the time required for the ball to reach ground level.

(e) Find the velocity of the ball at impact.

34. A block is dropped from the top of a 450-foot platform. What is its velocity after 2 seconds? After 5 seconds?

Finding a Derivative **In Exercises 35–46, use the Product Rule or the Quotient Rule to find the derivative of the function.**

35. $f(x) = (5x^2 + 8)(x^2 - 4x - 6)$

36. $g(x) = (2x^3 + 5x)(3x - 4)$

37. $f(x) = (9x - 1)\sin x$

38. $f(t) = 2t^5\cos t$

39. $f(x) = \dfrac{x^2 + x - 1}{x^2 - 1}$

40. $f(x) = \dfrac{2x + 7}{x^2 + 4}$

41. $y = \dfrac{x^4}{\cos x}$

42. $y = \dfrac{\sin x}{x^4}$

43. $y = 3x^2\sec x$

44. $y = -x^2\tan x$

45. $y = x\cos x - \sin x$

46. $g(x) = x^4\cot x + 3x\cos x$

Finding an Equation of a Tangent Line **In Exercises 47–50, find an equation of the tangent line to the graph of f at the given point.**

47. $f(x) = (x + 2)(x^2 + 5), \quad (-1, 6)$

48. $f(x) = (x - 4)(x^2 + 6x - 1), \quad (0, 4)$

49. $f(x) = \dfrac{x + 1}{x - 1}, \quad \left(\dfrac{1}{2}, -3\right)$

50. $f(x) = \dfrac{1 + \cos x}{1 - \cos x}, \quad \left(\dfrac{\pi}{2}, 1\right)$

Finding a Second Derivative **In Exercises 51–58, find the second derivative of the function.**

51. $g(t) = -8t^3 - 5t + 12$

52. $h(x) = 6x^{-2} + 7x^2$

53. $f(x) = 15x^{5/2}$

54. $f(x) = 20\sqrt[5]{x}$

55. $f(\theta) = 3\tan\theta$

56. $h(t) = 10\cos t - 15\sin t$

57. $g(x) = 4\cot x$

58. $h(t) = -12\csc t$

59. Acceleration The velocity of an object is $v(t) = 20 - t^2$, $0 \le t \le 6$, where v is measured in meters per second and t is the time in seconds. Find the velocity and acceleration of the object when $t = 3$.

60. Acceleration The velocity of an automobile starting from rest is

$$v(t) = \frac{90t}{4t + 10}$$

where v is measured in feet per second and t is the time in seconds. Find the acceleration at (a) 1 second, (b) 5 seconds, and (c) 10 seconds.

Finding a Derivative **In Exercises 61–72, find the derivative of the function.**

61. $y = (7x + 3)^4$

62. $y = (x^2 - 6)^3$

63. $y = \dfrac{1}{(x^2 + 5)^3}$

64. $f(x) = \dfrac{1}{(5x + 1)^2}$

65. $y = 5\cos(9x + 1)$

66. $y = -6\sin 3x^4$

67. $y = \dfrac{x}{2} - \dfrac{\sin 2x}{4}$

68. $y = \dfrac{\sec^7 x}{7} - \dfrac{\sec^5 x}{5}$

69. $y = x(6x + 1)^5$

70. $f(s) = (s^2 - 1)^{5/2}(s^3 + 5)$

71. $f(x) = \left(\dfrac{x}{\sqrt{x + 5}}\right)^3$

72. $h(x) = \left(\dfrac{x + 5}{x^2 + 3}\right)^2$

Finding the Slope of a Graph **In Exercises 73–78, find the slope of the graph of the function at the given point.**

73. $f(x) = \sqrt{1 - x^3}, \quad (-2, 3)$

74. $f(x) = \sqrt[3]{x^2 - 1}, \quad (3, 2)$

75. $f(x) = \dfrac{x + 8}{\sqrt{3x + 1}}, \quad (0, 8)$

76. $f(x) = \dfrac{3x + 1}{(4x - 3)^3}, \quad (1, 4)$

77. $y = \dfrac{1}{2}\csc 2x, \quad \left(\dfrac{\pi}{4}, \dfrac{1}{2}\right)$

78. $y = \csc 3x + \cot 3x, \quad \left(\dfrac{\pi}{6}, 1\right)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding a Second Derivative **In Exercises 79–82, find the second derivative of the function.**

79. $y = (8x + 5)^3$

80. $y = \dfrac{1}{5x + 1}$

81. $f(x) = \cot x$

82. $y = x \sin^2 x$

83. Refrigeration The temperature T (in degrees Fahrenheit) of food in a freezer is

$$T = \frac{700}{t^2 + 4t + 10}$$

where t is the time in hours. Find the rate of change of T with respect to t at each of the following times.

(a) $t = 1$ (b) $t = 3$ (c) $t = 5$ (d) $t = 10$

84. Harmonic Motion The displacement from equilibrium of an object in harmonic motion on the end of a spring is

$$y = \frac{1}{4}\cos 8t - \frac{1}{4}\sin 8t$$

where y is measured in feet and t is the time in seconds. Determine the position and velocity of the object when $t = \pi/4$.

Finding a Derivative **In Exercises 85–90, find dy/dx by implicit differentiation.**

85. $x^2 + y^2 = 49$

86. $x^2 + 4xy - y^3 = 6$

87. $x^3y - xy^3 = 4$

88. $\sqrt{xy} = x - 4y$

89. $x \sin y = y \cos x$

90. $\cos(x + y) = x$

Tangent Lines and Normal Lines **In Exercises 91 and 92, find equations for the tangent line and the normal line to the graph of the equation at the given point. (The *normal line* at a point is perpendicular to the tangent line at the point.) Use a graphing utility to graph the equation, the tangent line, and the normal line.**

91. $x^2 + y^2 = 10$, $(3, 1)$

92. $x^2 - y^2 = 20$, $(6, 4)$

93. Rate of Change A point moves along the curve $y = \sqrt{x}$ in such a way that the y-component of the position of the point is increasing at a rate of 2 units per second. At what rate is the x-component changing when $x = 1/2$, 1, and 4?

94. Surface Area All edges of a cube are expanding at a rate of 8 centimeters per second. How fast is the surface area changing when each edge is 6.5 centimeters?

95. Linear vs. Angular Speed A rotating beacon is located 1 kilometer off a straight shoreline (see figure). The beacon rotates at a rate of 3 revolutions per minute. How fast (in kilometers per hour) does the beam of light appear to be moving to a viewer who is $\frac{1}{2}$ kilometer down the shoreline?



96. Moving Shadow A sandbag is dropped from a balloon at a height of 60 meters when the angle of elevation to the sun is 30° (see figure). The position of the sandbag is $s(t) = 60 - 4.9t^2$. Find the rate at which the shadow of the sandbag is traveling along the ground when the sandbag is at a height of 35 meters.



Building on Concepts

97. If a is the acceleration of an object, then the **jerk** j is defined by $j(t) = a'(t)$.

(a) Use this definition to give a physical interpretation of j.

(b) Find j for the slowing vehicle in Exercise 121 in Section 2.3 and interpret the result.

98. The movement of an elevator is given by the piecewise functions shown in the figure.

(a) Identify the position, velocity, acceleration, and jerk functions. (For a definition of jerk, see Exercise 97.)

(b) Which functions appear to be differentiable at $x = 3/4$?

(c) Describe how each form of movement might feel to a passenger. What are the implications of the non-differentiable parts of the graphs?



Figure for 98

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.S. Problem Solving

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

1. Finding Equations of Circles Consider the graph of the parabola $y = x^2$.

(a) Find the radius r of the largest possible circle centered on the y-axis that is tangent to the parabola at the origin, as shown in the figure. This circle is called the **circle of curvature.** Find the equation of this circle. Use a graphing utility to graph the circle and parabola in the same viewing window to verify your answer.

(b) Find the center $(0, b)$ of the circle of radius 1 centered on the y-axis that is tangent to the parabola at two points, as shown in the figure. Find the equation of this circle. Use a graphing utility to graph the circle and parabola in the same viewing window to verify your answer.



Figure for 1(a)



Figure for 1(b)

2. Finding Equations of Tangent Lines Graph the two parabolas $y = x^2$ and $y = -x^2 + 2x - 5$ in the same coordinate plane. Find equations of the two lines that are simultaneously tangent to both parabolas.

3. Finding a Polynomial Find a third-degree polynomial $p(x)$ that is tangent to the line $y = 14x - 13$ at the point $(1, 1)$, and tangent to the line $y = -2x - 5$ at the point $(-1, -3)$.

4. Tangent Lines and Normal Lines

(a) Find an equation of the tangent line to the parabola $y = x^2$ at the point $(2, 4)$.

(b) Find an equation of the normal line to $y = x^2$ at the point $(2, 4)$. (The *normal line* at a point is perpendicular to the tangent line at the point.) Where does this line intersect the parabola a second time?

(c) Find equations of the tangent line and normal line to $y = x^2$ at the point $(0, 0)$.

(d) Prove that for any point $(a, b) \neq (0, 0)$ on the parabola $y = x^2$, the normal line intersects the graph a second time.

5. Projectile Motion An astronaut standing on the moon throws a rock upward. The height of the rock is

$$s = -\frac{27}{10}t^2 + 27t + 6$$

where s is measured in feet and t is measured in seconds.

(a) Find expressions for the velocity and acceleration of the rock.

(b) Find the time when the rock is at its highest point. What is the height of the rock at this time?

(c) How does the acceleration of the rock compare with the acceleration due to gravity on Earth?

6. Finding Polynomials

(a) Find the polynomial $P_1(x) = a_0 + a_1x$ whose value and slope agree with the value and slope of $f(x) = \cos x$ at the point $x = 0$.

(b) Find the polynomial $P_2(x) = a_0 + a_1x + a_2x^2$ whose value and first two derivatives agree with the value and first two derivatives of $f(x) = \cos x$ at the point $x = 0$. This polynomial is called the second-degree **Taylor polynomial** of $f(x) = \cos x$ at $x = 0$.

(c) Complete the table comparing the values of $f(x) = \cos x$ and $P_2(x)$. What do you observe?

x	-1.0	-0.1	-0.001	0	0.001	0.1	1.0
$\cos x$							
$P_2(x)$							

(d) Find the third-degree Taylor polynomial of $f(x) = \sin x$ at $x = 0$.

7. Famous Curve Consider the graph of the **eight curve** $x^4 = a^2(x^2 - y^2)$, $a \neq 0$, which is shown below.

(a) Explain how you could use a graphing utility to graph this curve.

(b) Use a graphing utility to graph the curve for various values of the constant a. Describe how a affects the shape of the curve.

(c) Determine the points on the curve at which the tangent line is horizontal.



Figure for 7



Figure for 8

8. Famous Curve Consider the graph of the **pear-shaped quartic** $b^2y^2 = x^3(a - x)$, $a, b > 0$, which is shown above.

(a) Explain how you could use a graphing utility to graph this curve.

(b) Use a graphing utility to graph the curve for various values of the constants a and b. Describe how a and b affect the shape of the curve.

(c) Determine the points on the curve at which the tangent line is horizontal.

9. Proof Let L be a differentiable function for all x. Prove that if $L(a + b) = L(a) + L(b)$ for all a and b, then $L'(x) = L'(0)$ for all x. What does the graph of L look like?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

3 Applications of Differentiation

GO DIGITAL

3.1 Extrema on an Interval
3.2 Rolle's Theorem and the Mean Value Theorem
3.3 Increasing and Decreasing Functions and the First Derivative Test
3.4 Concavity and the Second Derivative Test
3.5 Limits at Infinity
3.6 A Summary of Curve Sketching
3.7 Optimization Problems
3.8 Newton's Method
3.9 Differentials

CalcView®



CalcChat®


Chapter 3
Section 3
Exercise 9
GO
$f(x) = \frac{1}{(x+1)^2}$
From the graph, f is increasing on $(-\infty, -1)$ and decreasing on $(-1, \infty)$.
Analytically, $f'(x) = \frac{-2}{(x+1)^3}$.
No critical numbers. Discontinuity: $x = -1$
Test intervals: $-\infty < x < -1$ | $-1 < x < \infty$
Sign of $f'(x)$: $f' > 0$ | $f' < 0$
Conclusion: Increasing | Decreasing
PREV. 1 3 5 7 9 11 13 15 17 19 21 NEXT

3.7 Offshore Oil Well *(Exercise 41, p. 226)*

3.2 Speed *(Exercise 59, p. 180)*

left, landbysea/Getty Images; right, Denis Belitsky/Shutterstock.com
Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322
Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

3.1 Extrema on an Interval

GO DIGITAL

- **Define extrema of a function on an interval.**
- **Define relative extrema of a function on an open interval.**
- **Find extrema on a closed interval.**

Extrema of a Function

In calculus, much effort is devoted to determining the behavior of a function f on an interval I. Does f have a maximum value on I? Does it have a minimum value? Where is the function increasing? Where is it decreasing? In this chapter, you will learn how derivatives can be used to answer these questions. You will also see why these questions are important in real-life applications.



(a) f is continuous; $[-1, 2]$ is closed.



(b) f is continuous; $(-1, 2)$ is open.



(c) g is not continuous; $[-1, 2]$ is closed.

Figure 3.1

Definition of Extrema

Let a function f be defined on an interval I containing c.

1. $f(c)$ is the **minimum of f on I** when $f(c) \leq f(x)$ for all x in I.
2. $f(c)$ is the **maximum of f on I** when $f(c) \geq f(x)$ for all x in I.

The minimum and maximum of a function on an interval are the **extreme values,** or **extrema** (the singular form of extrema is extremum), of the function on the interval. The minimum and maximum of a function on an interval are also called the **absolute minimum** and **absolute maximum,** or the **global minimum** and **global maximum,** on the interval. Extrema can occur at interior points or endpoints of an interval (see Figure 3.1). Extrema that occur at the endpoints are called **endpoint extrema.**

A function need not have a minimum or a maximum on an interval. For instance, in Figures 3.1(a) and (b), you can see that the function $f(x) = x^2 + 1$ has both a minimum and a maximum on the closed interval $[-1, 2]$ but does not have a maximum on the open interval $(-1, 2)$. Moreover, in Figure 3.1(c), you can see that continuity (or the lack of it) can affect the existence of an extremum on the interval. This suggests the theorem below. (Although the Extreme Value Theorem is intuitively plausible, a proof of this theorem is not within the scope of this text.)

THEOREM 3.1 The Extreme Value Theorem

If a function f is continuous on a closed interval $[a, b]$, then f has both a minimum and a maximum on the interval.

Exploration

Finding Minimum and Maximum Values The Extreme Value Theorem (like the Intermediate Value Theorem) is an *existence theorem* because it tells of the existence of minimum and maximum values but does not show how to find these values. Use the *minimum* and *maximum* features of a graphing utility to find the extrema of each function. In each case, do you think the x-values are exact or approximate? Explain your reasoning.

a. $f(x) = x^2 - 4x + 5$ on the closed interval $[-1, 3]$

b. $f(x) = x^3 - 2x^2 - 3x - 2$ on the closed interval $[-1, 3]$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



f has a relative maximum at $(0, 0)$ and a relative minimum at $(2, -4)$.

Figure 3.2

GO DIGITAL



(a) $f'(3) = 0$



(b) $f'(0)$ does not exist.



(c) $f'\left(\frac{\pi}{2}\right) = 0$; $f'\left(\frac{3\pi}{2}\right) = 0$

Figure 3.3

Relative Extrema and Critical Numbers

In Figure 3.2, the graph of $f(x) = x^3 - 3x^2$ has a **relative maximum** at the point $(0, 0)$ and a **relative minimum** at the point $(2, -4)$. Informally, for a continuous function, you can think of a relative maximum as occurring on a "hill" on the graph, and a relative minimum as occurring in a "valley" on the graph. Such a hill and valley can occur in two ways. When the hill (or valley) is smooth and rounded, the graph has a horizontal tangent line at the high point (or low point). When the hill (or valley) is sharp and peaked, the graph represents a function that is not differentiable at the high point (or low point).

Definition of Relative Extrema

1. If there is an open interval containing c on which $f(c)$ is a maximum, then $f(c)$ is called a **relative maximum** of f, or you can say that f has a **relative maximum at $(c, f(c))$.**
2. If there is an open interval containing c on which $f(c)$ is a minimum, then $f(c)$ is called a **relative minimum** of f, or you can say that f has a **relative minimum at $(c, f(c))$.**

The plural of relative maximum is relative maxima, and the plural of relative minimum is relative minima. A relative maximum is sometimes called a **local maximum,** and a relative minimum is sometimes called a **local minimum.**

Example 1 examines the derivatives of functions at *given* relative extrema. (Much more is said about *finding* the relative extrema of a function in Section 3.3.)

EXAMPLE 1 The Value of the Derivative at Relative Extrema

Find the value of the derivative at each relative extremum shown in Figure 3.3.

Solution

a. The derivative of $f(x) = \frac{9(x^2 - 3)}{x^3}$ is

$$f'(x) = \frac{x^3(18x) - (9)(x^2 - 3)(3x^2)}{(x^3)^2}$$ Differentiate using Quotient Rule.

$$= \frac{9x^2[2x^2 - 3(x^2 - 3)]}{x^6}$$ Factor.

$$= \frac{9(9 - x^2)}{x^4}.$$ Divide out common factor and combine like terms.

At the point $(3, 2)$, the value of the derivative is $f'(3) = 0$. [See Figure 3.3(a).]

b. At $x = 0$, the derivative of $f(x) = |x|$ *does not exist* because the following one-sided limits differ. [See Figure 3.3(b).]

$$\lim_{x \to 0^-} \frac{f(x) - f(0)}{x - 0} = \lim_{x \to 0^-} \frac{|x|}{x} = -1$$ Limit from the left

$$\lim_{x \to 0^+} \frac{f(x) - f(0)}{x - 0} = \lim_{x \to 0^+} \frac{|x|}{x} = 1$$ Limit from the right

c. The derivative of $f(x) = \sin x$ is $f'(x) = \cos x$. At the point $(\pi/2, 1)$, the value of the derivative is $f'(\pi/2) = \cos(\pi/2) = 0$. At the point $(3\pi/2, -1)$, the value of the derivative is $f'(3\pi/2) = \cos(3\pi/2) = 0$. [See Figure 3.3(c).] ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Note in Example 1 that at each relative extremum, the derivative either is zero or does not exist. The x-values at these special points are called **critical numbers.** Figure 3.4 illustrates the two types of critical numbers. Notice in the definition that the critical number c has to be in the domain of f, but c does not have to be in the domain of f'.

REMARK Critical numbers are sometimes referred to as *critical values*.

Definition of a Critical Number

Let f be defined at c. If $f'(c) = 0$ or if f is not differentiable at c, then c is a **critical number** of f.



c is a critical number of f.
Figure 3.4

PIERRE DE FERMAT (1601–1665)

For Fermat, who was trained as a lawyer, mathematics was more of a hobby than a profession. Nevertheless, Fermat made many contributions to analytic geometry, number theory, calculus, and probability. In letters to friends, he wrote of many of the fundamental ideas of calculus, long before Newton or Leibniz. For instance, Theorem 3.2 is sometimes attributed to Fermat.

See LarsonCalculus.com to read more of this biography.

THEOREM 3.2 Relative Extrema Occur Only at Critical Numbers

If f has a relative minimum or relative maximum at $x = c$, then c is a critical number of f.

Proof

Case 1: If f is *not* differentiable at $x = c$, then, by definition, c is a critical number of f and the theorem is valid.

Case 2: If f is differentiable at $x = c$, then $f'(c)$ must be positive, negative, or 0. Suppose $f'(c)$ is positive. Then

$$f'(c) = \lim_{x \to c} \frac{f(x) - f(c)}{x - c} > 0$$

which implies that there exists an interval (a, b) containing c such that

$$\frac{f(x) - f(c)}{x - c} > 0, \text{ for all } x \neq c \text{ in } (a, b).$$ See Exercise 88(b), Section 1.2.

Because this quotient is positive, the signs of the denominator and numerator must agree. This produces the following inequalities for x-values in the interval (a, b).

Left of c: $x < c$ and $f(x) < f(c)$ ⇨ $f(c)$ is not a relative minimum.

Right of c: $x > c$ and $f(x) > f(c)$ ⇨ $f(c)$ is not a relative maximum.

So, the assumption that $f'(c) > 0$ contradicts the hypothesis that $f(c)$ is a relative extremum. Assuming that $f'(c) < 0$ produces a similar contradiction, you are left with only one possibility—namely, $f'(c) = 0$. So, by definition, c is a critical number of f and the theorem is valid. ■

Pictorial Press Ltd/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Big Ideas of Calculus

In this chapter, you will study some of the applications of the derivative. These applications include graphical analysis and optimization. Additionally, you will see how the derivative is used in the Mean Value Theorem, one of the most important theorems in calculus.

Finding Extrema on a Closed Interval

Theorem 3.2 states that the relative extrema of a function can occur *only* at the critical numbers of the function. Knowing this, you can use these guidelines to find extrema on a closed interval.

Guidelines for Finding Extrema on a Closed Interval

To find the extrema of a continuous function f on a closed interval $[a, b]$, use these steps.

1. Find the critical numbers of f in (a, b).
2. Evaluate f at each critical number in (a, b).
3. Evaluate f at each endpoint of $[a, b]$.
4. The least of these values is the minimum. The greatest is the maximum.

The next three examples show how to apply these guidelines. Be sure you see that finding the critical numbers of the function is only part of the procedure. Evaluating the function at the critical numbers *and* the endpoints is the other part.

EXAMPLE 2 **Finding Extrema on a Closed Interval**

Find the extrema of

$$f(x) = 3x^4 - 4x^3$$

on the interval $[-1, 2]$.

Solution Begin by differentiating the function.

$$f(x) = 3x^4 - 4x^3 \qquad \text{Write original function.}$$
$$f'(x) = 12x^3 - 12x^2 \qquad \text{Differentiate.}$$

To find the critical numbers of f in the interval $(-1, 2)$, you must find all x-values for which $f'(x) = 0$ and all x-values for which $f'(x)$ does not exist.

$$12x^3 - 12x^2 = 0 \qquad \text{Set } f'(x) \text{ equal to 0.}$$
$$12x^2(x - 1) = 0 \qquad \text{Factor.}$$
$$12x^2 = 0 \Rightarrow x = 0 \qquad \text{Set first factor equal to 0.}$$
$$x - 1 = 0 \Rightarrow x = 1 \qquad \text{Set second factor equal to 0.}$$

Because f' is defined for all x, you can conclude that $x = 0$ and $x = 1$ are the only critical numbers of f. By evaluating f at these two critical numbers and at the endpoints of $[-1, 2]$, you can determine that the maximum is $f(2) = 16$ and the minimum is $f(1) = -1$, as shown in the table. The graph of f is shown in Figure 3.5.



On the closed interval $[-1, 2]$, f has a minimum at $(1, -1)$ and a maximum at $(2, 16)$.

Figure 3.5

Left Endpoint	Critical Number	Critical Number	Right Endpoint
$f(-1) = 7$	$f(0) = 0$	$f(1) = -1$ Minimum	$f(2) = 16$ Maximum

In Figure 3.5, note that the critical number $x = 0$ does not yield a relative minimum or a relative maximum. This tells you that the converse of Theorem 3.2 is not true. In other words, *the critical numbers of a function need not produce relative extrema.*

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



On the closed interval $[-1, 3]$, f has a minimum at $(-1, -5)$ and a maximum at $(0, 0)$.

Figure 3.6

EXAMPLE 3 Finding Extrema on a Closed Interval

Find the extrema of $f(x) = 2x - 3x^{2/3}$ on the interval $[-1, 3]$.

Solution Begin by differentiating the function.

$$f(x) = 2x - 3x^{2/3}$$ Write original function.

$$f'(x) = 2 - \frac{2}{x^{1/3}}$$ Differentiate.

$$= 2\left(\frac{x^{1/3} - 1}{x^{1/3}}\right)$$ Simplify.

From this derivative, you can see that the function has two critical numbers in the interval $(-1, 3)$. The number 1 is a critical number because $f'(1) = 0$, and the number 0 is a critical number because $f'(0)$ does not exist. By evaluating f at these two numbers and at the endpoints of the interval, you can conclude that the minimum is $f(-1) = -5$ and the maximum is $f(0) = 0$, as shown in the table. The graph of f is shown in Figure 3.6.

Left Endpoint	Critical Number	Critical Number	Right Endpoint
$f(-1) = -5$ Minimum	$f(0) = 0$ Maximum	$f(1) = -1$	$f(3) = 6 - 3\sqrt[3]{9} \approx -0.24$

EXAMPLE 4 Finding Extrema on a Closed Interval

See LarsonCalculus.com for an interactive version of this type of example.

Find the extrema of

$$f(x) = 2 \sin x - \cos 2x$$

on the interval $[0, 2\pi]$.

Solution Begin by differentiating the function.

$$f(x) = 2 \sin x - \cos 2x$$ Write original function.

$$f'(x) = 2 \cos x + 2 \sin 2x$$ Differentiate.

$$= 2 \cos x + 4 \cos x \sin x$$ $\sin 2x = 2 \cos x \sin x$

$$= 2(\cos x)(1 + 2 \sin x)$$ Factor.

Because f is differentiable for all real x, you can find all critical numbers of f by finding the zeros of its derivative. Considering $2(\cos x)(1 + 2 \sin x) = 0$ in the interval $(0, 2\pi)$, the factor $\cos x$ is zero when $x = \pi/2$ and when $x = 3\pi/2$. The factor $(1 + 2 \sin x)$ is zero when $x = 7\pi/6$ and when $x = 11\pi/6$. By evaluating f at these four critical numbers and at the endpoints of the interval, you can conclude that the maximum is $f(\pi/2) = 3$ and the minimum occurs at *two* points, $f(7\pi/6) = -3/2$ and $f(11\pi/6) = -3/2$, as shown in the table. The graph is shown in Figure 3.7.



On the closed interval $[0, 2\pi]$, f has two minima at $(7\pi/6, -3/2)$ and $(11\pi/6, -3/2)$ and a maximum at $(\pi/2, 3)$.

Figure 3.7

Left Endpoint	Critical Number	Critical Number	Critical Number	Critical Number	Right Endpoint
$f(0) = -1$	$f\left(\frac{\pi}{2}\right) = 3$ Maximum	$f\left(\frac{7\pi}{6}\right) = -\frac{3}{2}$ Minimum	$f\left(\frac{3\pi}{2}\right) = -1$	$f\left(\frac{11\pi}{6}\right) = -\frac{3}{2}$ Minimum	$f(2\pi) = -1$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

3.1 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain what it means to say that $f(c)$ is the minimum of f on an interval I.
2. Describe the Extreme Value Theorem.
3. Explain the difference between a relative maximum and an absolute maximum on an interval I.
4. Give the definition of a critical number.
5. Explain how to find the critical numbers of a function.
6. Explain how to find the extrema of a continuous function on a closed interval $[a, b]$.

The Value of the Derivative at Relative Extrema

In Exercises 7–12, find the value of the derivative (if it exists) at each indicated extremum.

7. $f(x) = \dfrac{x^2}{x^2 + 4}$



8. $f(x) = \cos\dfrac{\pi x}{2}$



9. $g(x) = x + \dfrac{4}{x^2}$



10. $f(x) = -3x\sqrt{x + 1}$



11. $f(x) = (x + 2)^{2/3}$



12. $f(x) = 4 - |x|$



Approximating Critical Numbers

In Exercises 13–16, approximate the critical numbers of the function shown in the graph. Determine whether the function has a relative maximum, a relative minimum, an absolute maximum, an absolute minimum, or none of these at each critical number on the interval shown.

13.



14.



15.



16.



Finding Critical Numbers

In Exercises 17–22, find the critical numbers of the function.

17. $f(x) = 4x^2 - 6x$
18. $g(x) = x - \sqrt{x}$
19. $g(t) = t\sqrt{4 - t}, \; t < 3$
20. $f(x) = \dfrac{4x}{x^2 + 1}$
21. $h(x) = \sin^2 x + \cos x, \quad 0 < x < 2\pi$
22. $f(\theta) = 2\sec\theta + \tan\theta, \quad 0 < \theta < 2\pi$

Finding Extrema on a Closed Interval

In Exercises 23–40, find the absolute extrema of the function on the closed interval.

23. $f(x) = 3 - x, \; [-1, 2]$
24. $f(x) = \dfrac{3}{4}x + 2, \; [0, 4]$
25. $h(x) = 5 - 2x^2, \; [-3, 1]$
26. $f(x) = 7x^2 + 1, \; [-1, 2]$
27. $f(x) = x^3 - \dfrac{3}{2}x^2, \; [-1, 2]$
28. $f(x) = 2x^3 - 6x, \; [0, 3]$
29. $y = 3x^{2/3} - 2x, \; [-1, 1]$
30. $g(x) = \sqrt[3]{x}, \; [-8, 8]$
31. $g(x) = \dfrac{6x^2}{x - 2}, \; [-2, 1]$
32. $h(t) = \dfrac{t}{t + 3}, \; [-1, 6]$
33. $y = 3 - |t - 3|, \; [-1, 5]$
34. $g(x) = |x + 4|, \; [-7, 1]$
35. $f(x) = [\![x]\!], \; [-2, 2]$
36. $h(x) = [\![2 - x]\!], \; [-2, 2]$
37. $f(x) = \sin x, \; \left[\dfrac{5\pi}{6}, \dfrac{11\pi}{6}\right]$
38. $g(x) = \sec x, \; \left[-\dfrac{\pi}{6}, \dfrac{\pi}{3}\right]$
39. $y = 3\cos x, \; [0, 2\pi]$
40. $y = \tan\dfrac{\pi x}{8}, \; [0, 2]$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding Extrema on an Interval **In Exercises 41–44, find the absolute extrema of the function (if any exist) on each interval.**

41. $f(x) = 2x - 3$

(a) $[0, 2]$ (b) $[0, 2)$

(c) $(0, 2]$ (d) $(0, 2)$

42. $f(x) = 5 - x$

(a) $[1, 4]$ (b) $[1, 4)$

(c) $(1, 4]$ (d) $(1, 4)$

43. $f(x) = x^2 - 2x$

(a) $[-1, 2]$ (b) $(1, 3]$

(c) $(0, 2)$ (d) $[1, 4)$

44. $f(x) = \sqrt{4 - x^2}$

(a) $[-2, 2]$ (b) $[-2, 0)$

(c) $(-2, 2)$ (d) $[1, 2)$

Finding Absolute Extrema Using Technology **In Exercises 45–48, use a graphing utility to graph the function and find the absolute extrema of the function on the given interval.**

45. $f(x) = \dfrac{3}{x - 1}, \quad (1, 4]$

46. $f(x) = \dfrac{2}{2 - x}, \quad [0, 2)$

47. $f(x) = \sqrt{x} + \dfrac{\sin x}{3}, \quad [0, \pi]$

48. $f(x) = -x + \cos 3\pi x, \quad \left[0, \dfrac{\pi}{6}\right]$

Finding Extrema Using Technology **In Exercises 49 and 50, (a) use a computer algebra system to graph the function and approximate any absolute extrema on the given interval. (b) Use the utility to find any critical numbers, and use them to identify any absolute extrema not located at the endpoints. Compare the results with those in part (a).**

49. $f(x) = 3.2x^5 + 5x^3 - 3.5x, \quad [0, 1]$

50. $f(x) = \dfrac{4}{3}x\sqrt{3 - x}, \quad [0, 3]$

Finding Maximum Values Using Technology **In Exercises 51 and 52, use a computer algebra system to find the maximum value of $|f''(x)|$ on the closed interval. (This value is used in the error estimate for the Trapezoidal Rule, as discussed in Section 8.6.)**

51. $f(x) = \sqrt{1 + x^3}, \quad [0, 2]$

52. $f(x) = \dfrac{1}{x^2 + 1}, \quad \left[\dfrac{1}{2}, 3\right]$

Finding Maximum Values Using Technology **In Exercises 53 and 54, use a computer algebra system to find the maximum value of $|f^{(4)}(x)|$ on the closed interval. (This value is used in the error estimate for Simpson's Rule, as discussed in Section 8.6.)**

53. $f(x) = (x + 1)^{2/3}, \quad [0, 2]$

54. $f(x) = \dfrac{1}{x^2 + 1}, \quad [-1, 1]$

55. Writing Write a short paragraph explaining why a continuous function on an open interval may not have a maximum or minimum. Illustrate your explanation with a sketch of the graph of such a function.

56. HOW DO YOU SEE IT? Determine whether each labeled point is an absolute maximum or minimum, a relative maximum or minimum, or none of these.



Exploring Concepts

In Exercises 57 and 58, determine from the graph whether f has a minimum in the open interval (a, b). Explain your reasoning.

57. (a) (b)





58. (a) (b)





59. Consider the function

$$f(x) = \frac{x - 4}{x + 2}.$$

Is $x = -2$ a critical number of f? Why or why not?

60. Graph a function on the interval $[-2, 5]$ having the given characteristics.

Relative minimum at $x = -1$

Critical number (but no extremum) at $x = 0$

Absolute maximum at $x = 2$

Absolute minimum at $x = 5$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

61. Power The formula for the power output P of a battery is

$$P = VI - RI^2$$

where V is the electromotive force in volts, R is the resistance in ohms, and I is the current in amperes. Find the current that corresponds to a maximum value of P in a battery for which $V = 12$ volts and $R = 0.5$ ohm. Assume that a 15-ampere fuse bounds the output in the interval $0 \le I \le 15$. Could the power output be increased by replacing the 15-ampere fuse with a 20-ampere fuse? Explain.

62. Lawn Sprinkler A lawn sprinkler is constructed in such a way that $d\theta/dt$ is constant, where θ ranges between 45° and 135° (see figure). The distance the water travels horizontally is

$$x = \frac{v^2 \sin 2\theta}{32}, \quad 45° \le \theta \le 135°$$

where v is the speed of the water. Find dx/dt and explain why this lawn sprinkler does not water evenly. What part of the lawn receives the most water?



Water sprinkler: $45° \le \theta \le 135°$

FOR FURTHER INFORMATION For more information on the "calculus of lawn sprinklers," see the article "Design of an Oscillating Sprinkler" by Bart Braden in *Mathematics Magazine*. To view this article, go to *MathArticles.com*.

63. Honeycomb The surface area of a cell in a honeycomb is

$$S = 6hs + \frac{3s^2}{2}\left(\frac{\sqrt{3} - \cos\theta}{\sin\theta}\right)$$

where h and s are positive constants and θ is the angle at which the upper faces meet the altitude of the cell (see figure). Find the angle θ $(\pi/6 \le \theta \le \pi/2)$ that minimizes the surface area S.



FOR FURTHER INFORMATION For more information on the geometric structure of a honeycomb cell, see the article "The Design of Honeycombs" by Anthony L. Peressini in UMAP Module 502, published by COMAP, Inc., Suite 210, 57 Bedford Street, Lexington, MA.

64. Highway Design In order to build a highway, it is necessary to fill a section of a valley where the grades (slopes) of the sides are 9% and 6% (see figure). The top of the filled region will have the shape of a parabolic arc that is tangent to the two slopes at the points A and B. The horizontal distances from A to the y-axis and from B to the y-axis are both 500 feet.



(a) Find the coordinates of A and B.

(b) Find a quadratic function $y = ax^2 + bx + c$ for $-500 \le x \le 500$ that describes the top of the filled region.

(c) Construct a table giving the depths d of the fill for $x = -500, -400, -300, -200, -100, 0, 100, 200, 300, 400$, and 500.

(d) What will be the lowest point on the completed highway? Will it be directly over the point where the two hillsides come together?

True or False? **In Exercises 65–68, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

65. The maximum of $y = x^2$ on the open interval $(-3, 3)$ is 9.

66. If a function is continuous on a closed interval, then it must have a minimum on the interval.

67. If $x = c$ is a critical number of the function f, then it is also a critical number of the function $g(x) = f(x) + k$, where k is a constant.

68. If $x = c$ is a critical number of the function f, then it is also a critical number of the function $g(x) = f(x - k)$, where k is a constant.

69. Functions Let the function f be differentiable on an interval I containing c. Show that if f has a maximum value at $x = c$, then $-f$ has a minimum value at $x = c$.

70. Critical Numbers Consider the cubic function $f(x) = ax^3 + bx^2 + cx + d$, where $a \ne 0$. Show that f can have zero, one, or two critical numbers and give an example of each case.

PUTNAM EXAM CHALLENGE

71. Determine all real numbers $a > 0$ for which there exists a nonnegative continuous function $f(x)$ defined on $[0, a]$ with the property that the region $R = \{(x, y); 0 \le x \le a, 0 \le y \le f(x)\}$ has perimeter k units and area k square units for some real number k.

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

3.2 Rolle's Theorem and the Mean Value Theorem

- **Describe and use Rolle's Theorem.**
- **Describe and use the Mean Value Theorem.**

Exploration

Extreme Values on a Closed Interval Sketch a rectangular coordinate plane on a piece of paper. Label the points (1, 3) and (5, 3). Using a pencil or pen, draw the graph of a differentiable function f that starts at (1, 3) and ends at (5, 3). Is there at least one point on the graph for which the derivative is zero? Would it be possible to draw the graph so that there is *not* a point for which the derivative is zero? Explain your reasoning.

Rolle's Theorem

The Extreme Value Theorem (see Section 3.1) states that a continuous function on a closed interval $[a, b]$ must have both a minimum and a maximum on the interval. Both of these values, however, can occur at the endpoints. **Rolle's Theorem,** named after the French mathematician Michel Rolle (1652–1719), gives conditions that guarantee the existence of an extreme value in the *interior* of a closed interval.

THEOREM 3.3 Rolle's Theorem

Let f be continuous on the closed interval $[a, b]$ and differentiable on the open interval (a, b). If $f(a) = f(b)$, then there is at least one number c in (a, b) such that $f'(c) = 0$.

Proof Let $f(a) = d = f(b)$.

Case 1: If $f(x) = d$ for all x in $[a, b]$, then f is constant on the interval and, by Theorem 2.2, $f'(x) = 0$ for all x in (a, b).

Case 2: Consider $f(x) > d$ for some x in (a, b). By the Extreme Value Theorem, f has a maximum at some c in the interval. Moreover, because $f(c) > d$, this maximum does not occur at either endpoint. So, f has a maximum in the *open* interval (a, b). This implies that $f(c)$ is a *relative* maximum and, by Theorem 3.2, c is a critical number of f. Finally, because f is differentiable at c, you can conclude that $f'(c) = 0$.

Case 3: When $f(x) < d$ for some x in (a, b), you can use an argument similar to that in Case 2 but involving the minimum instead of the maximum. ∎

ROLLE'S THEOREM

French mathematician Michel Rolle first published the theorem that bears his name in 1691. Before this time, however, Rolle was one of the most vocal critics of calculus, stating that it gave erroneous results and was based on unsound reasoning. Later in life, Rolle came to see the usefulness of calculus.

According to Rolle's Theorem, if a function f is continuous on $[a, b]$ and differentiable on (a, b), and if $f(a) = f(b)$, then there must be at least one x-value between a and b at which the graph of f has a horizontal tangent [See Figure 3.8(a)]. When the differentiability requirement is dropped from Rolle's Theorem, f will still have a critical number in (a, b), but it may not yield a horizontal tangent. Such a case is shown in Figure 3.8(b).



(a) f is continuous on $[a, b]$ and differentiable on (a, b).

(b) f is continuous on $[a, b]$ but *not* differentiable on (a, b).

Figure 3.8

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The x-value for which $f'(x) = 0$ is between the two x-intercepts.
Figure 3.9

EXAMPLE 1 Illustrating Rolle's Theorem

Find the two x-intercepts of

$$f(x) = x^2 - 3x + 2$$

and show that $f'(x) = 0$ at some point between the two x-intercepts.

Solution Note that f is differentiable on the entire real number line. Setting $f(x)$ equal to 0 produces

$$x^2 - 3x + 2 = 0 \qquad \text{Set } f(x) \text{ equal to 0.}$$
$$(x - 1)(x - 2) = 0 \qquad \text{Factor.}$$
$$x = 1, 2. \qquad \text{Solve for } x.$$

So, $f(1) = f(2) = 0$, and from Rolle's Theorem you know that there *exists* at least one c in the interval $(1, 2)$ such that $f'(c) = 0$. To *find* such a c, differentiate f to obtain

$$f'(x) = 2x - 3 \qquad \text{Differentiate.}$$

and then determine that $f'(x) = 0$ when $x = \frac{3}{2}$. Note that this x-value lies in the open interval $(1, 2)$, as shown in Figure 3.9. ■

GO DIGITAL

Rolle's Theorem states that when f satisfies the conditions of the theorem, there must be *at least* one point between a and b at which the derivative is 0. There may, of course, be more than one such point, as shown in the next example.

EXAMPLE 2 Illustrating Rolle's Theorem

Let $f(x) = x^4 - 2x^2$. Find all values of c in the interval $(-2, 2)$ such that $f'(c) = 0$.

Solution To begin, note that the function satisfies the conditions of Rolle's Theorem. That is, f is continuous on the interval $[-2, 2]$ and differentiable on the interval $(-2, 2)$. Moreover, because $f(-2) = f(2) = 8$, you can conclude that there exists at least one c in $(-2, 2)$ such that $f'(c) = 0$. Because

$$f'(x) = 4x^3 - 4x \qquad \text{Differentiate.}$$

setting the derivative equal to 0 produces

$$4x^3 - 4x = 0 \qquad \text{Set } f'(x) \text{ equal to 0.}$$
$$4x(x - 1)(x + 1) = 0 \qquad \text{Factor.}$$
$$x = 0, 1, -1. \qquad x\text{-values for which } f'(x) = 0$$

So, in the interval $(-2, 2)$, the derivative is zero when $x = -1$, 0, and 1, as shown in Figure 3.10. ■



$f'(x) = 0$ for more than one x-value in the interval $(-2, 2)$.
Figure 3.10

TECHNOLOGY PITFALL A graphing utility can be used to indicate whether the points on the graphs in Examples 1 and 2 are relative minima or relative maxima of the functions. When using a graphing utility, however, you should keep in mind that it can give misleading graphs. For example, use a graphing utility to graph

$$f(x) = 1 - (x - 1)^2 - \frac{1}{1000(x - 1)^{1/7} + 1}.$$

With most viewing windows, it appears that the function has a maximum of 1 when $x = 1$, as shown in Figure 3.11. Evaluating the function at $x = 1$, however, produces $f(1) = 0$. To determine the behavior of this function near $x = 1$, you need to examine the graph analytically to get the complete picture.



Figure 3.11

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The Mean Value Theorem

Rolle's Theorem can be used to prove another theorem—the **Mean Value Theorem.**

REMARK The "mean" in the Mean Value Theorem refers to the mean (or average) rate of change of f on the interval $[a, b]$.

THEOREM 3.4 The Mean Value Theorem

If f is continuous on the closed interval $[a, b]$ and differentiable on the open interval (a, b), then there exists a number c in (a, b) such that

$$f'(c) = \frac{f(b) - f(a)}{b - a}.$$



Figure 3.12

Proof Refer to Figure 3.12. The equation of the secant line that passes through the points $(a, f(a))$ and $(b, f(b))$ is

$$y = \overbrace{\left[\frac{f(b) - f(a)}{b - a}\right]}^{\text{Slope of secant line}}(x - a) + f(a). \qquad \text{Secant line through } (a, f(a)) \text{ and } (b, f(b))$$

Let $g(x)$ be the difference between $f(x)$ and y. Then

$$\begin{aligned} g(x) &= f(x) - y \\ &= f(x) - \left[\frac{f(b) - f(a)}{b - a}\right](x - a) - f(a). \qquad \text{Substitute for } y. \end{aligned}$$

Evaluating g at a and b shows that

$$g(a) = 0 = g(b).$$

Because f is continuous on $[a, b]$, it follows that g is also continuous on $[a, b]$. Furthermore, because f is differentiable, g is also differentiable, and you can apply Rolle's Theorem to the function g. So, there exists a number c in (a, b) such that $g'(c) = 0$, which implies that

$$\begin{aligned} g'(c) &= 0 \qquad \text{Set } g'(c) \text{ equal to 0.} \\ f'(c) - \frac{f(b) - f(a)}{b - a} &= 0. \qquad \text{Derivative of } g \end{aligned}$$

So, there exists a number c in (a, b) such that

$$f'(c) = \frac{f(b) - f(a)}{b - a}. \qquad \text{Solve for } f'(c).$$

Although the Mean Value Theorem can be used directly in problem solving, it is used more often to prove other theorems. In fact, some people consider this to be the most important theorem in calculus—it is closely related to the Fundamental Theorem of Calculus discussed in Section 4.4. For now, you can get an idea of the versatility of the Mean Value Theorem by looking at the results stated in Exercises 79–83 in this section.

The Mean Value Theorem has implications for both basic interpretations of the derivative. Geometrically, the theorem guarantees the existence of a tangent line that is parallel to the secant line through the points

$$(a, f(a)) \quad \text{and} \quad (b, f(b))$$

as shown in Figure 3.12. Example 3 illustrates this geometric interpretation of the Mean Value Theorem. In terms of rates of change, the Mean Value Theorem implies that there must be a point in the open interval (a, b) at which the instantaneous rate of change is equal to the average rate of change over the interval $[a, b]$. This is illustrated in Example 4.

JOSEPH-LOUIS LAGRANGE (1736–1813)

The Mean Value Theorem was first proved by the famous mathematician Joseph-Louis Lagrange. Born in Italy, Lagrange held a position in the court of Frederick the Great in Berlin for 20 years.

See LarsonCalculus.com to read more of this biography.

Pictorial Press Ltd / Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



The tangent line at (2, 3) is parallel to the secant line through (1, 1) and (4, 4).

Figure 3.13

EXAMPLE 3 Finding a Tangent Line

See LarsonCalculus.com for an interactive version of this type of example.

For $f(x) = 5 - (4/x)$, find all values of c in the open interval $(1, 4)$ such that

$$f'(c) = \frac{f(4) - f(1)}{4 - 1}.$$

Solution The slope of the secant line through $(1, f(1))$ and $(4, f(4))$ is

$$\frac{f(4) - f(1)}{4 - 1} = \frac{4 - 1}{4 - 1} = 1.$$ Slope of secant line

Note that f satisfies the conditions of the Mean Value Theorem. That is, f is continuous on the interval $[1, 4]$ and differentiable on the interval $(1, 4)$. So, there exists at least one number c in $(1, 4)$ such that $f'(c) = 1$. Solving the equation $f'(x) = 1$ yields

$$\frac{4}{x^2} = 1$$ Set $f'(x)$ equal to 1.

which implies that $x = \pm 2$. So, in the interval $(1, 4)$, you can conclude that $c = 2$. Figure 3.13 shows the graphs of f, the secant line passing through the points $(1, 1)$ and $(4, 4)$, and the tangent line at $x = 2$. Note that the tangent line is parallel to the secant line because both lines have the same slope.



At some time t, the instantaneous velocity is equal to the average velocity over 4 minutes.

Figure 3.14

EXAMPLE 4 Finding an Instantaneous Rate of Change

Two stationary patrol cars equipped with radar are 5 miles apart on a highway, as shown in Figure 3.14. As a truck passes the first patrol car, its speed is clocked at 55 miles per hour. Four minutes later, when the truck passes the second patrol car, its speed is clocked at 50 miles per hour. Prove that the truck must have exceeded the speed limit (of 55 miles per hour) at some time during the 4 minutes.

Solution Let $t = 0$ be the time (in hours) when the truck passes the first patrol car. The time when the truck passes the second patrol car is

$$t = \frac{4}{60} = \frac{1}{15} \text{ hour.}$$

By letting $s(t)$ represent the distance (in miles) traveled by the truck, you have $s(0) = 0$ and $s\left(\frac{1}{15}\right) = 5$. So, the average velocity of the truck over the five-mile stretch of highway is

$$\text{Average velocity} = \frac{s(1/15) - s(0)}{(1/15) - 0} = \frac{5}{1/15} = 75 \text{ miles per hour.}$$

Assuming that the position function is differentiable, you can apply the Mean Value Theorem to conclude that the truck must have been traveling at a rate of 75 miles per hour sometime during the 4 minutes. ■

A useful alternative form of the Mean Value Theorem is: If f is continuous on $[a, b]$ and differentiable on (a, b), then there exists a number c in (a, b) such that

$$f(b) = f(a) + (b - a)f'(c).$$ Alternative form of Mean Value Theorem

When doing the exercises for this section, keep in mind that polynomial functions, rational functions, and trigonometric functions are differentiable at all points in their domains.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

3.2 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain Rolle's Theorem.
2. Explain the Mean Value Theorem.

Writing **In Exercises 3–6, explain why Rolle's Theorem does not apply to the function even though there exist a and b such that $f(a) = f(b)$.**

3. $f(x) = \left|\frac{1}{x}\right|, [-1, 1]$
4. $f(x) = \cot\frac{x}{2}, [\pi, 3\pi]$
5. $f(x) = 1 - |x - 1|, [0, 2]$
6. $f(x) = \sqrt{(2 - x^{2/3})^3}, [-1, 1]$

Using Rolle's Theorem **In Exercises 7–10, find the two x-intercepts of the function f and show that $f'(x) = 0$ at some point between the two x-intercepts.**

7. $f(x) = x^2 - x - 2$
8. $f(x) = x^2 + 6x$
9. $f(x) = x\sqrt{x + 4}$
10. $f(x) = -3x\sqrt{x + 1}$

Using Rolle's Theorem **In Exercises 11–24, determine whether Rolle's Theorem can be applied to f on the closed interval $[a, b]$. If Rolle's Theorem can be applied, find all values of c in the open interval (a, b) such that $f'(c) = 0$. If Rolle's Theorem cannot be applied, explain why not.**

11. $f(x) = -x^2 + 3x, [0, 3]$
12. $f(x) = x^2 - 8x + 5, [2, 6]$
13. $f(x) = (x - 1)(x - 2)(x - 3), [1, 3]$
14. $f(x) = (x - 4)(x + 2)^2, [-2, 4]$
15. $f(x) = x^{2/3} - 1, [-8, 8]$
16. $f(x) = 3 - |x - 3|, [0, 6]$
17. $f(x) = \frac{x^2 - 2x - 3}{x + 2}, [-1, 3]$
18. $f(x) = \frac{x^2 - 4}{x - 1}, [-2, 2]$
19. $f(x) = \sin x, [0, 2\pi]$
20. $f(x) = \cos x, [\pi, 3\pi]$
21. $f(x) = \cos \pi x, [0, 2]$
22. $f(x) = \sin 3x, \left[\frac{\pi}{2}, \frac{7\pi}{6}\right]$
23. $f(x) = \tan x, [0, \pi]$
24. $f(x) = \sec x, [\pi, 2\pi]$

Using Rolle's Theorem **In Exercises 25–28, use a graphing utility to graph the function on the closed interval $[a, b]$. Determine whether Rolle's Theorem can be applied to f on the interval and, if so, find all values of c in the open interval (a, b) such that $f'(c) = 0$.**

25. $f(x) = |x| - 1, [-1, 1]$
26. $f(x) = x - x^{1/3}, [0, 1]$
27. $f(x) = \frac{x}{2} - \sin\frac{\pi x}{6}, [-1, 0]$
28. $f(x) = x - \tan \pi x, \left[-\frac{1}{4}, \frac{1}{4}\right]$

29. **Vertical Motion** The height of a ball t seconds after it is thrown upward from a height of 6 feet and with an initial velocity of 48 feet per second is

$$f(t) = -16t^2 + 48t + 6.$$

(a) Verify that $f(1) = f(2)$.

(b) According to Rolle's Theorem, what must the velocity be at some time in the interval $(1, 2)$? Find that time.

30. **Reorder Costs** The ordering and transportation cost C for components used in a manufacturing process is approximated by

$$C(x) = 10\left(\frac{1}{x} + \frac{x}{x + 3}\right)$$

where C is measured in thousands of dollars and x is the order size in hundreds.

(a) Verify that $C(3) = C(6)$.

(b) According to Rolle's Theorem, the rate of change of the cost must be 0 for some order size in the interval $(3, 6)$. Find that order size.

Mean Value Theorem **In Exercises 31 and 32, copy the graph and sketch the secant line to the graph through the points $(a, f(a))$ and $(b, f(b))$. Then sketch any tangent lines to the graph for each value of c guaranteed by the Mean Value Theorem. To print an enlarged copy of the graph, go to *MathGraphs.com*.**

31.



32.



Writing **In Exercises 33–36, explain why the Mean Value Theorem does not apply to the function f on the interval $[0, 6]$.**

33.



34.



35. $f(x) = \frac{1}{x - 3}$
36. $f(x) = |x - 3|$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

37. Mean Value Theorem Consider the graph of the function $f(x) = -x^2 + 5$ (see figure).

(a) Find the equation of the secant line joining the points $(-1, 4)$ and $(2, 1)$.

(b) Use the Mean Value Theorem to determine a point c in the interval $(-1, 2)$ such that the tangent line at c is parallel to the secant line.

(c) Find the equation of the tangent line through c.

(d) Use a graphing utility to graph f, the secant line, and the tangent line.



Figure for 37



Figure for 38

38. Mean Value Theorem Consider the graph of the function $f(x) = x^2 - x - 12$ (see figure).

(a) Find the equation of the secant line joining the points $(-2, -6)$ and $(4, 0)$.

(b) Use the Mean Value Theorem to determine a point c in the interval $(-2, 4)$ such that the tangent line at c is parallel to the secant line.

(c) Find the equation of the tangent line through c.

(d) Use a graphing utility to graph f, the secant line, and the tangent line.

Using the Mean Value Theorem **In Exercises 39–48, determine whether the Mean Value Theorem can be applied to f on the closed interval $[a, b]$. If the Mean Value Theorem can be applied, find all values of c in the open interval (a, b) such that**

$$f'(c) = \frac{f(b) - f(a)}{b - a}.$$

If the Mean Value Theorem cannot be applied, explain why not.

39. $f(x) = 6x^3, \quad [1, 2]$

40. $f(x) = x^6, \quad [-1, 1]$

41. $f(x) = x^3 + 2x + 4, \quad [-1, 0]$

42. $f(x) = x^3 - 3x^2 + 9x + 5, \quad [0, 1]$

43. $f(x) = \dfrac{x + 2}{x - 1}, \quad [-3, 3]$

44. $f(x) = \dfrac{x}{x - 5}, \quad [1, 4]$

45. $f(x) = |2x + 1|, \quad [-1, 3]$

46. $f(x) = \sqrt{2 - x}, \quad [-7, 2]$

47. $f(x) = \sin x, \quad [0, \pi]$

48. $f(x) = \cos x + \tan x, \quad [0, \pi]$

Using the Mean Value Theorem **In Exercises 49–52, use a graphing utility to (a) graph the function f on the given interval, (b) find and graph the secant line through points on the graph of f at the endpoints of the given interval, and (c) find and graph any tangent lines to the graph of f that are parallel to the secant line.**

49. $f(x) = \dfrac{x}{x + 1}, \quad \left[-\dfrac{1}{2}, 2\right]$

50. $f(x) = x - 2 \sin x, \quad [-\pi, \pi]$

51. $f(x) = \sqrt{x}, \quad [1, 9]$

52. $f(x) = x^4 - 2x^3 + x^2, \quad [0, 6]$

53. Vertical Motion The height of an object t seconds after it is dropped from a height of 300 meters is

$$s(t) = -4.9t^2 + 300.$$

(a) Find the average velocity of the object during the first 3 seconds.

(b) Use the Mean Value Theorem to verify that at some time during the first 3 seconds of fall, the instantaneous velocity equals the average velocity. Find that time.

54. Sales A company introduces a new product for which the number of units sold S is

$$S(t) = 200\left(5 - \frac{9}{2 + t}\right)$$

where t is the time in months.

(a) Find the average rate of change of S during the first year.

(b) During what month of the first year does $S'(t)$ equal the average rate of change?

Exploring Concepts

55. Let f be continuous on $[a, b]$ and differentiable on (a, b). If there exists c in (a, b) such that $f'(c) = 0$, does it follow that $f(a) = f(b)$? Explain.

56. Let f be continuous on $[a, b]$ and differentiable on (a, b). Also, suppose that $f(a) = f(b)$ and that c is a real number in the interval (a, b) such that $f'(c) = 0$. Find an interval for the function g over which Rolle's Theorem can be applied, and find the corresponding critical number of g, where k is a constant.

(a) $g(x) = f(x) + k$ (b) $g(x) = f(x - k)$

(c) $g(x) = f(kx)$

57. The function

$$f(x) = \begin{cases} 0, & x = 0 \\ 1 - x, & 0 < x \le 1 \end{cases}$$

is differentiable on $(0, 1)$ and satisfies $f(0) = f(1)$. However, its derivative is never zero on $(0, 1)$. Does this contradict Rolle's Theorem? Explain.

58. Can you find a function f such that $f(-2) = -2$, $f(2) = 6$, and $f'(x) < 1$ for all x? Why or why not?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

59. Speed

A plane begins its takeoff at 2:00 P.M. on a 2500-mile flight. After 5.5 hours, the plane arrives at its destination. Explain why there are at least two times during the flight when the speed of the plane is 400 miles per hour.

Denis Belitsky/Shutterstock.com

60. Temperature When an object is removed from a furnace and placed in an environment with a constant temperature of 90°F, its core temperature is 1500°F. Five hours later, the core temperature is 390°F. Explain why there must exist a time in the interval $(0, 5)$ when the temperature is decreasing at a rate of 222°F per hour.

61. Velocity Two bicyclists begin a race at 8:00 A.M. They both finish the race 2 hours and 15 minutes later. Prove that at some time during the race, the bicyclists are traveling at the same velocity.

62. Acceleration At 9:13 A.M., a sports car is traveling 35 miles per hour. Two minutes later, the car is traveling 85 miles per hour. Prove that at some time during this two-minute interval, the car's acceleration is exactly 1500 miles per hour squared.

63. Think About It Sketch the graph of an arbitrary function f that satisfies the given condition but does not satisfy the conditions of the Mean Value Theorem on the interval $[-5, 5]$.

(a) f is continuous. (b) f is not continuous.

64. HOW DO YOU SEE IT? The figure shows two parts of the graph of a continuous differentiable function f on $[-10, 4]$. The derivative f' is also continuous. To print an enlarged copy of the graph, go to *MathGraphs.com*.



(a) Explain why f must have at least one zero in $[-10, 4]$.

(b) Explain why f' must also have at least one zero in the interval $[-10, 4]$. What are these zeros called?

(c) Make a possible sketch of the function, where f' has one zero on the interval $[-10, 4]$.

Finding a Solution **In Exercises 65–68, prove that the equation has exactly one real solution.**

65. $x^5 + x^3 + x + 1 = 0$ **66.** $2x^5 + 7x - 1 = 0$

67. $3x + 1 - \sin x = 0$ **68.** $2x - 2 - \cos x = 0$

Using a Derivative **In Exercises 69–72, find a function f that has the derivative $f'(x)$ and whose graph passes through the given point. Explain your reasoning.**

69. $f'(x) = 0, \quad (2, 5)$ **70.** $f'(x) = 4, \quad (0, 1)$

71. $f'(x) = 2x, \quad (1, 0)$ **72.** $f'(x) = 6x - 1, \quad (2, 7)$

True or False? **In Exercises 73–76, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

73. The Mean Value Theorem can be applied to $f(x) = 1/x$ on the interval $[-1, 1]$.

74. If the graph of a function has three x-intercepts, then it must have at least two points at which its tangent line is horizontal.

75. If the graph of a polynomial function has three x-intercepts, then it must have at least two points at which its tangent line is horizontal.

76. The Mean Value Theorem can be applied to $f(x) = \tan x$ on the interval $[0, \pi/4]$.

77. Proof Prove that if $a > 0$ and n is any positive integer, then the polynomial function $p(x) = x^{2n+1} + ax + b$ cannot have two real roots.

78. Tangent Lines

(a) Let $f(x) = x^2$ and $g(x) = -x^3 + x^2 + 3x + 2$. Then $f(-1) = g(-1)$ and $f(2) = g(2)$. Show that there is at least one value c in the interval $(-1, 2)$ where the tangent line to f at $(c, f(c))$ is parallel to the tangent line to g at $(c, g(c))$. Identify c.

(b) Let f and g be differentiable functions on $[a, b]$, where $f(a) = g(a)$ and $f(b) = g(b)$. Show that there is at least one value c in the interval (a, b) where the tangent line to f at $(c, f(c))$ is parallel to the tangent line to g at $(c, g(c))$.

79. Proof Let $p(x) = Ax^2 + Bx + C$. Prove that for any interval $[a, b]$, the value c guaranteed by the Mean Value Theorem is the midpoint of the interval.

80. Proof Prove that if $f'(x) = 0$ for all x in an interval (a, b), then f is constant on (a, b).

81. Proof Prove that $|\cos a - \cos b| \leq |a - b|$ for all a and b.

82. Proof Prove that $|\sin a - \sin b| \leq |a - b|$ for all a and b.

83. Using the Mean Value Theorem Let $0 < a < b$. Use the Mean Value Theorem to show that

$$\sqrt{b} - \sqrt{a} < \frac{b - a}{2\sqrt{a}}.$$

PUTNAM EXAM CHALLENGE

84. Let f be a three times differentiable function (defined on $\mathbb{R}$ and real-valued) such that f has at least five distinct real zeros. Prove that

$$f + 6f' + 12f'' + 8f'''$$

has at least two distinct real zeros.

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

3.3 Increasing and Decreasing Functions and the First Derivative Test

GO DIGITAL

- **Determine intervals on which a function is increasing or decreasing.**
- **Apply the First Derivative Test to find relative extrema of a function.**

Increasing and Decreasing Functions

In this section, you will learn how derivatives can be used to *classify* relative extrema as either relative minima or relative maxima. First, it is important to define increasing and decreasing functions.

Definitions of Increasing and Decreasing Functions

A function f is **increasing** on an interval when, for any two numbers x_1 and x_2 in the interval, $x_1 < x_2$ implies $f(x_1) < f(x_2)$.

A function f is **decreasing** on an interval when, for any two numbers x_1 and x_2 in the interval, $x_1 < x_2$ implies $f(x_1) > f(x_2)$.

A function is increasing when, *as x moves to the right*, its graph moves up, and is decreasing when its graph moves down. For example, the function in Figure 3.15 is decreasing on the interval $(-\infty, a)$, is constant on the interval (a, b), and is increasing on the interval (b, ∞). As shown in Theorem 3.5 below, a positive derivative implies that the function is increasing, a negative derivative implies that the function is decreasing, and a zero derivative on an entire interval implies that the function is constant on that interval.



The derivative is related to the slope of a function.

Figure 3.15

REMARK The conclusions in the first two cases of Theorem 3.5 are valid even when $f'(x) = 0$ at a finite number of x-values in (a, b).

THEOREM 3.5 Test for Increasing and Decreasing Functions

Let f be a function that is continuous on the closed interval $[a, b]$ and differentiable on the open interval (a, b).

1. If $f'(x) > 0$ for all x in (a, b), then f is increasing on $[a, b]$.
2. If $f'(x) < 0$ for all x in (a, b), then f is decreasing on $[a, b]$.
3. If $f'(x) = 0$ for all x in (a, b), then f is constant on $[a, b]$.

Proof To prove the first case, assume that $f'(x) > 0$ for all x in the interval (a, b) and let $x_1 < x_2$ be any two points in the interval $[a, b]$. By the Mean Value Theorem, you know that there exists a number c such that $x_1 < c < x_2$, and

$$f'(c) = \frac{f(x_2) - f(x_1)}{x_2 - x_1}.$$

Because $f'(c) > 0$ and $x_2 - x_1 > 0$, you know that $f(x_2) - f(x_1) > 0$, which implies that $f(x_1) < f(x_2)$. So, f is increasing on the interval. The second case has a similar proof (see Exercise 97), and the third case is a consequence of Exercise 80 in Section 3.2. ∎

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



Figure 3.16



(a) Strictly monotonic function



(b) Not strictly monotonic

Figure 3.17

EXAMPLE 1 Intervals on Which *f* Is Increasing or Decreasing

Find the open intervals on which $f(x) = x^3 - \frac{3}{2}x^2$ is increasing or decreasing.

Solution Note that f is differentiable on the entire real number line and the derivative of f is

$$f(x) = x^3 - \tfrac{3}{2}x^2 \qquad \text{Write original function.}$$
$$f'(x) = 3x^2 - 3x. \qquad \text{Differentiate.}$$

To determine the critical numbers of f, set $f'(x)$ equal to zero.

$$3x^2 - 3x = 0 \qquad \text{Set } f'(x) \text{ equal to 0.}$$
$$3(x)(x - 1) = 0 \qquad \text{Factor.}$$
$$x = 0, 1 \qquad \text{Critical numbers}$$

Because there are no points for which f' does not exist, you can conclude that $x = 0$ and $x = 1$ are the only critical numbers. The table summarizes the testing of the three intervals determined by these two critical numbers.

Interval	$-\infty < x < 0$	$0 < x < 1$	$1 < x < \infty$
Test Value	$x = -1$	$x = \frac{1}{2}$	$x = 2$
Sign of $f'(x)$	$f'(-1) = 6 > 0$	$f'\left(\frac{1}{2}\right) = -\frac{3}{4} < 0$	$f'(2) = 6 > 0$
Conclusion	Increasing	Decreasing	Increasing

By Theorem 3.5, f is increasing on the intervals $(-\infty, 0)$ and $(1, \infty)$ and decreasing on the interval $(0, 1)$, as shown in Figure 3.16. ■

Example 1 gives you one instance of how to find intervals on which a function is increasing or decreasing. The guidelines below summarize the steps followed in that example.

Guidelines for Finding Intervals on Which a Function Is Increasing or Decreasing

Let f be continuous on the interval (a, b). To find the open intervals on which f is increasing or decreasing, use the following steps.

1. Locate the critical numbers of f in (a, b), and use these numbers to determine test intervals.
2. Determine the sign of $f'(x)$ at one test value in each of the intervals.
3. Use Theorem 3.5 to determine whether f is increasing or decreasing on each interval.

These guidelines are also valid when the interval (a, b) is replaced by an interval of the form $(-\infty, b)$, (a, ∞), or $(-\infty, \infty)$.

A function is **strictly monotonic** on an interval when it is either increasing on the entire interval or decreasing on the entire interval. For instance, the function $f(x) = x^3$ is strictly monotonic on the entire real number line because it is increasing on the entire real number line, as shown in Figure 3.17(a). The function shown in Figure 3.17(b) is not strictly monotonic on the entire real number line because it is constant on the interval $[0, 1]$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The First Derivative Test

After determining the intervals on which a function is increasing or decreasing, it is not difficult to locate the relative extrema of the function. For instance, in Figure 3.18 (from Example 1), the function

$$f(x) = x^3 - \frac{3}{2}x^2$$

has a relative maximum at the point $(0, 0)$ because f is increasing immediately to the left of $x = 0$ and decreasing immediately to the right of $x = 0$. Similarly, f has a relative minimum at the point $\left(1, -\frac{1}{2}\right)$ because f is decreasing immediately to the left of $x = 1$ and increasing immediately to the right of $x = 1$. The next theorem makes this more explicit.



Relative extrema of f
Figure 3.18

REMARK The guidelines below may help you to apply the First Derivative Test.

1. Find the derivative of f.
2. Locate the critical numbers of f and use these numbers to determine the test intervals.
3. Determine the sign of $f'(x)$ at an arbitrary number in each of the test intervals.
4. For each critical number c, use the First Derivative Test to decide whether $f(c)$ is a relative minimum, a relative maximum, or neither.

THEOREM 3.6 The First Derivative Test

Let c be a critical number of a function f that is continuous on an open interval I containing c. If f is differentiable on the interval, except possibly at c, then $f(c)$ can be classified as follows.

1. If $f'(x)$ changes from negative to positive at c, then f has a *relative minimum* at $(c, f(c))$.
2. If $f'(x)$ changes from positive to negative at c, then f has a *relative maximum* at $(c, f(c))$.
3. If $f'(x)$ is positive on both sides of c or negative on both sides of c, then $f(c)$ is neither a relative minimum nor a relative maximum.



Relative minimum



Relative maximum





Neither relative minimum nor relative maximum

Proof Assume that $f'(x)$ changes from negative to positive at c. Then there exist a and b in I such that

$$f'(x) < 0 \text{ for all } x \text{ in } (a, c) \quad \text{and} \quad f'(x) > 0 \text{ for all } x \text{ in } (c, b).$$

By Theorem 3.5, f is decreasing on $[a, c]$ and increasing on $[c, b]$. So, $f(c)$ is a minimum of f on the open interval (a, b) and, consequently, a relative minimum of f. This proves the first case of the theorem. The second case can be proved in a similar way (see Exercise 98).

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 2 Applying the First Derivative Test

Find the relative extrema of $f(x) = \frac{1}{2}x - \sin x$ in the interval $(0, 2\pi)$.

Solution Note that f is continuous on the interval $(0, 2\pi)$. The derivative of f is $f'(x) = \frac{1}{2} - \cos x$. To determine the critical numbers of f in this interval, set $f'(x)$ equal to 0.

$$\frac{1}{2} - \cos x = 0 \qquad \text{Set } f'(x) \text{ equal to 0.}$$

$$\cos x = \frac{1}{2} \qquad \text{Isolate } x\text{-term on the left and multiply each side by } -1.$$

$$x = \frac{\pi}{3}, \frac{5\pi}{3} \qquad \text{Critical numbers in the interval } (0, 2\pi)$$

Because there are no points for which f' does not exist, you can conclude that $x = \pi/3$ and $x = 5\pi/3$ are the only critical numbers. The table summarizes the testing of the three intervals determined by these two critical numbers. By applying the First Derivative Test, you can conclude that f has a relative minimum at the point where $x = \pi/3$ and a relative maximum at the point where $x = 5\pi/3$, as shown in Figure 3.19.



A relative minimum occurs where f changes from decreasing to increasing, and a relative maximum occurs where f changes from increasing to decreasing.
Figure 3.19

Interval	$0 < x < \frac{\pi}{3}$	$\frac{\pi}{3} < x < \frac{5\pi}{3}$	$\frac{5\pi}{3} < x < 2\pi$
Test Value	$x = \frac{\pi}{4}$	$x = \pi$	$x = \frac{7\pi}{4}$
Sign of $f'(x)$	$f'\left(\frac{\pi}{4}\right) < 0$	$f'(\pi) > 0$	$f'\left(\frac{7\pi}{4}\right) < 0$
Conclusion	Decreasing	Increasing	Decreasing

EXAMPLE 3 Applying the First Derivative Test

Find the relative extrema of $f(x) = (x^2 - 4)^{2/3}$.

Solution Begin by noting that f is continuous on the entire real number line. The derivative of f

$$f'(x) = \frac{2}{3}(x^2 - 4)^{-1/3}(2x) \qquad \text{General Power Rule}$$

$$= \frac{4x}{3(x^2 - 4)^{1/3}} \qquad \text{Simplify.}$$

is 0 when $x = 0$ and does not exist when $x = \pm 2$. So, the critical numbers are $x = -2$, $x = 0$, and $x = 2$. The table summarizes the testing of the four intervals determined by these three critical numbers. By applying the First Derivative Test, you can conclude that f has a relative minimum at the point $(-2, 0)$, a relative maximum at the point $(0, \sqrt[3]{16})$, and another relative minimum at the point $(2, 0)$, as shown in Figure 3.20.



Figure 3.20

Interval	$-\infty < x < -2$	$-2 < x < 0$	$0 < x < 2$	$2 < x < \infty$
Test Value	$x = -3$	$x = -1$	$x = 1$	$x = 3$
Sign of $f'(x)$	$f'(-3) < 0$	$f'(-1) > 0$	$f'(1) < 0$	$f'(3) > 0$
Conclusion	Decreasing	Increasing	Decreasing	Increasing

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Note that in Examples 1 and 2, the given functions are differentiable on the entire real number line. For such functions, the only critical numbers are those for which $f'(x) = 0$. Example 3 concerns a function that has two types of critical numbers—those for which $f'(x) = 0$ and those for which f is not differentiable.

When using the First Derivative Test, be sure to consider the domain of the function. For instance, in the next example, the function

$$f(x) = \frac{x^4 + 1}{x^2}$$

is not defined when $x = 0$. This x-value must be used with the critical numbers to determine the test intervals.

EXAMPLE 4 Applying the First Derivative Test

See LarsonCalculus.com for an interactive version of this type of example.

Find the relative extrema of $f(x) = \frac{x^4 + 1}{x^2}$.

Solution Note that f is not defined when $x = 0$.

$$f(x) = x^2 + x^{-2}$$ Rewrite original function.

$$f'(x) = 2x - 2x^{-3}$$ Differentiate.

$$= 2x - \frac{2}{x^3}$$ Rewrite with positive exponent.

$$= \frac{2(x^4 - 1)}{x^3}$$ Simplify.

$$= \frac{2(x^2 + 1)(x - 1)(x + 1)}{x^3}$$ Factor.

So, $f'(x)$ is zero at $x = \pm 1$. Moreover, because $x = 0$ is not in the domain of f, you should use this x-value along with the critical numbers to determine the test intervals.

$x = \pm 1$ Critical numbers, $f'(\pm 1) = 0$

$x = 0$ 0 is not in the domain of f.

The table summarizes the testing of the four intervals determined by these three x-values. By applying the First Derivative Test, you can conclude that f has one relative minimum at the point $(-1, 2)$ and another at the point $(1, 2)$, as shown in Figure 3.21.



x-values that are not in the domain of f, as well as critical numbers, determine test intervals for f'.

Figure 3.21

Interval	$-\infty < x < -1$	$-1 < x < 0$	$0 < x < 1$	$1 < x < \infty$
Test Value	$x = -2$	$x = -\frac{1}{2}$	$x = \frac{1}{2}$	$x = 2$
Sign of $f'(x)$	$f'(-2) < 0$	$f'\left(-\frac{1}{2}\right) > 0$	$f'\left(\frac{1}{2}\right) < 0$	$f'(2) > 0$
Conclusion	Decreasing	Increasing	Decreasing	Increasing

TECHNOLOGY The most difficult step in applying the First Derivative Test is finding the values for which the derivative is equal to 0. For instance, the values of x for which the derivative of

$$f(x) = \frac{x^4 + 1}{x^2 + 1}$$

is equal to zero are $x = 0$ and $x = \pm\sqrt{\sqrt{2} - 1}$. If you have access to technology that can perform symbolic differentiation and solve equations, use it to apply the First Derivative Test to this function.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

REMARK When a projectile is propelled from ground level and air resistance is neglected, the object will travel farthest with an initial angle of 45°. When, as in Example 5, a projectile is propelled from a point above ground level, the angle that yields a maximum horizontal distance is not 45°.

EXAMPLE 5 The Path of a Projectile

Neglecting air resistance, the path of a projectile that is propelled at an angle θ is

$$y = -\frac{g \sec^2 \theta}{2v_0^2}x^2 + (\tan \theta)x + h, \quad 0 \le \theta \le \frac{\pi}{2}$$

where y is the height, x is the horizontal distance, g is the acceleration due to gravity, v_0 is the initial velocity, and h is the initial height. (This equation is derived in Section 12.3.) Let $g = 32$ feet per second per second, $v_0 = 24$ feet per second, and $h = 9$ feet. What value of θ will produce a maximum horizontal distance?

Solution To find the distance the projectile travels, let $y = 0$, $g = 32$, $v_0 = 24$, and $h = 9$. Then substitute these values in the given equation as shown.

$$-\frac{g \sec^2 \theta}{2v_0^2}x^2 + (\tan \theta)x + h = y \qquad \text{Write original equation.}$$

$$-\frac{32 \sec^2 \theta}{2(24^2)}x^2 + (\tan \theta)x + 9 = 0 \qquad \text{Substitute.}$$

$$-\frac{\sec^2 \theta}{36}x^2 + (\tan \theta)x + 9 = 0 \qquad \text{Simplify.}$$

Next, solve for x using the Quadratic Formula with $a = (-\sec^2 \theta)/36$, $b = \tan \theta$, and $c = 9$.

$$x = \frac{-b \pm \sqrt{b^2 - 4ac}}{2a} \qquad \text{Quadratic Formula}$$

$$x = \frac{-\tan \theta \pm \sqrt{(\tan \theta)^2 - 4[(-\sec^2 \theta)/36](9)}}{2[(-\sec^2 \theta)/36]} \qquad \text{Substitute.}$$

$$x = \frac{-\tan \theta \pm \sqrt{\tan^2 \theta + \sec^2 \theta}}{(-\sec^2 \theta)/18}$$

$$x = 18(\cos \theta)\left(\sin \theta + \sqrt{\sin^2 \theta + 1}\right), \quad x \ge 0$$

At this point, you need to find the value of θ that produces a maximum value of x. Applying the First Derivative Test without using technology would be very tedious. Using technology to solve the equation $dx/d\theta = 0$, however, eliminates most of the messy computations. The result is that the maximum value of x occurs when

$$\theta \approx 0.61548 \text{ radian}, \quad \text{or} \quad \theta \approx 35.3°.$$

This conclusion is reinforced by sketching the path of the projectile for different values of θ, as shown in Figure 3.22. Of the three paths shown, note that the distance traveled is greatest for $\theta = 35°$.



The path of a projectile with initial angle θ

Figure 3.22

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

3.3 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe the Test for Increasing and Decreasing Functions.
2. Explain the First Derivative Test.

Using a Graph In Exercises 3 and 4, use the graph of f to find (a) the largest open interval on which f is increasing and (b) the largest open interval on which f is decreasing.

3.



4.



Using a Graph In Exercises 5–10, use the graph to estimate the open intervals on which the function is increasing or decreasing. Then find the open intervals analytically.

5. $y = -(x + 1)^2$



6. $f(x) = x^2 - 6x + 8$



7. $y = \frac{x^3}{4} - 3x$



8. $f(x) = x^4 - 2x^2$



9. $f(x) = \frac{1}{(x + 1)^2}$



10. $y = \frac{x^2}{2x - 1}$



Intervals on Which a Function Is Increasing or Decreasing In Exercises 11–18, find the open intervals on which the function is increasing or decreasing.

11. $g(x) = x^2 - 2x - 8$
12. $h(x) = 12x - x^3$
13. $y = x\sqrt{16 - x^2}$
14. $y = x + \frac{9}{x}$
15. $f(x) = \sin x - 1, \quad 0 < x < 2\pi$
16. $f(x) = \cos\frac{3x}{2}, \quad 0 < x < 2\pi$
17. $y = x - 2\cos x, \quad 0 < x < 2\pi$
18. $f(x) = \sin^2 x + \sin x, \quad 0 < x < 2\pi$

Applying the First Derivative Test In Exercises 19–40, (a) find the critical numbers of f, if any, (b) find the open intervals on which the function is increasing or decreasing, (c) apply the First Derivative Test to identify all relative extrema, and (d) use a graphing utility to confirm your results.

19. $f(x) = x^2 - 8x$
20. $f(x) = x^2 + 6x + 10$
21. $f(x) = -2x^2 + 4x + 3$
22. $f(x) = -3x^2 - 4x - 2$
23. $f(x) = -7x^3 + 21x + 3$
24. $f(x) = x^3 - 6x^2 + 15$
25. $f(x) = (x - 1)^2(x + 3)$
26. $f(x) = (8 - x)(x + 1)^2$
27. $f(x) = \frac{x^5 - 5x}{5}$
28. $f(x) = \frac{-x^6 + 6x}{10}$
29. $f(x) = x^{1/3} + 1$
30. $f(x) = x^{2/3} - 4$
31. $f(x) = (x + 2)^{2/3}$
32. $f(x) = (x - 3)^{1/3}$
33. $f(x) = 5 - |x - 5|$
34. $f(x) = |x + 3| - 1$
35. $f(x) = 2x + \frac{1}{x}$
36. $f(x) = \frac{x}{x - 5}$
37. $f(x) = \frac{x^2}{x^2 - 9}$
38. $f(x) = \frac{x^2 - 2x + 1}{x + 1}$
39. $f(x) = \begin{cases} 4 - x^2, & x \le 0 \\ -2x, & x > 0 \end{cases}$
40. $f(x) = \begin{cases} 2x + 1, & x \le -1 \\ x^2 - 2, & x > -1 \end{cases}$

Applying the First Derivative Test In Exercises 41–48, consider the function on the interval $(0, 2\pi)$. (a) Find the open intervals on which the function is increasing or decreasing. (b) Apply the First Derivative Test to identify all relative extrema. (c) Use a graphing utility to confirm your results.

41. $f(x) = x - 2\sin x$
42. $f(x) = \sin x \cos x + 5$
43. $f(x) = \sin x + \cos x$
44. $f(x) = \frac{x}{2} + \cos x$
45. $f(x) = \cos^2(2x)$
46. $f(x) = \sin x - \sqrt{3}\cos x$
47. $f(x) = \sin^2 x + \sin x$
48. $f(x) = \frac{\sin x}{1 + \cos^2 x}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding and Analyzing Derivatives Using Technology **In Exercises 49–54, (a) use a computer algebra system to differentiate the function, (b) sketch the graphs of f and f' on the same set of coordinate axes over the given interval, (c) find the critical numbers of f in the open interval, and (d) find the interval(s) on which f' is positive and the interval(s) on which f' is negative. Compare the behavior of f and the sign of f'.**

49. $f(x) = 2x\sqrt{9 - x^2}, \quad [-3, 3]$

50. $f(x) = 10\left(5 - \sqrt{x^2 - 3x + 16}\right), \quad [0, 5]$

51. $f(t) = t^2 \sin t, \quad [0, 2\pi]$

52. $f(x) = \frac{x}{2} + \cos\frac{x}{2}, \quad [0, 4\pi]$

53. $f(x) = -3 \sin\frac{x}{3}, \quad [0, 6\pi]$

54. $f(x) = 2 \sin 3x + 4 \cos 3x, \quad [0, \pi]$

Comparing Functions **In Exercises 55 and 56, use symmetry, extrema, and zeros to sketch the graph of f. How do the functions f and g differ?**

55. $f(x) = \frac{x^5 - 4x^3 + 3x}{x^2 - 1}$

$g(x) = x(x^2 - 3)$

56. $f(t) = \cos^2 t - \sin^2 t$

$g(t) = 1 - 2 \sin^2 t$

Think About It **In Exercises 57–62, the graph of f is shown in the figure. Sketch a graph of the derivative of f. To print an enlarged copy of the graph, go to *MathGraphs.com*.**

57.



58.



59.



60.



61.



62.



Exploring Concepts

In Exercises 63–66, assume that f is differentiable for all x. The signs of f' are as follows.

$f'(x) > 0$ on $(-\infty, -4)$

$f'(x) < 0$ on $(-4, 6)$

$f'(x) > 0$ on $(6, \infty)$

Supply the appropriate inequality sign for the indicated value of c.

Function	Sign of $g'(c)$
63. $g(x) = f(x) + 5$	$g'(0)$ ____ 0
64. $g(x) = 3f(x) - 3$	$g'(-5)$ ____ 0
65. $g(x) = -f(x)$	$g'(-6)$ ____ 0
66. $g(x) = f(x - 10)$	$g'(0)$ ____ 0

67. Sketch the graph of the arbitrary function f such that

$$f'(x)\begin{cases} > 0, & x < 4 \\ \text{undefined}, & x = 4 \\ < 0, & x > 4 \end{cases}.$$

68. Is the sum of two increasing functions always increasing? Explain.

69. Is the product of two increasing functions always increasing? Explain.

70. **HOW DO YOU SEE IT?** Use the graph of f' to (a) identify the critical numbers of f, (b) identify the open intervals on which f is increasing or decreasing, and (c) determine whether f has a relative maximum, a relative minimum, or neither at each critical number.

(i)



(ii)



(iii)



(iv)



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

71. Analyzing a Critical Number A differentiable function f has one critical number at $x = 5$. Identify the relative extrema of f at the critical number when $f'(4) = -2.5$ and $f'(6) = 3$.

72. Analyzing a Critical Number A differentiable function f has one critical number at $x = 2$. Identify the relative extrema of f at the critical number when $f'(1) = 2$ and $f'(3) = 6$.

Think About It **In Exercises 73 and 74, the function f is differentiable on the indicated interval. The table shows $f'(x)$ for selected values of x. (a) Sketch the graph of f, (b) approximate the critical numbers, and (c) identify the relative extrema.**

73. f is differentiable on $[-1, 1]$.

x	-1	-0.75	-0.50	-0.25	0
$f'(x)$	-10	-3.2	-0.5	0.8	5.6

x	0.25	0.50	0.75	1
$f'(x)$	3.6	-0.2	-6.7	-20.1

74. f is differentiable on $[0, \pi]$.

x	0	$\pi/6$	$\pi/4$	$\pi/3$	$\pi/2$
$f'(x)$	3.14	-0.23	-2.45	-3.11	0.69

x	$2\pi/3$	$3\pi/4$	$5\pi/6$	π
$f'(x)$	3.00	1.37	-1.14	-2.84

75. Rolling a Ball Bearing A ball bearing is placed on an inclined plane and begins to roll. The angle of elevation of the plane is θ. The distance (in meters) the ball bearing rolls in t seconds is $s(t) = 4.9(\sin\theta)t^2$.

(a) Determine the speed of the ball bearing after t seconds.

(b) Complete the table and use it to determine the value of θ that produces the maximum speed at a particular time.

θ	0	$\pi/4$	$\pi/3$	$\pi/2$	$2\pi/3$	$3\pi/4$	π
$s'(t)$							

76. Modeling Data The total expenditures of an account in the Supplementary Medical Insurance Trust Fund (in billions of dollars) for the years 2011 through 2019 are shown.

2011: 67.1 2012: 66.9 2013: 69.7
2014: 78.1 2015: 89.8 2016: 99.9
2017: 100.0 2018: 95.2 2019: 97.6

(Source: U.S. Centers for Medicare and Medicaid Services)

(a) Use the regression capabilities of a graphing utility to find a model of the form $M = at^3 + bt^2 + ct + d$ for the data. Let $t = 11$ represent 2011.

(b) Use a graphing utility to plot the data and graph the model.

(c) Find the maximum value of the model and compare the result with the actual data.

77. Numerical, Graphical, and Analytic Analysis The concentration C of a chemical in the bloodstream t hours after injection into muscle tissue is

$$C(t) = \frac{3t}{27 + t^3}, \quad t \geq 0.$$

(a) Complete the table and use it to approximate the time when the concentration is greatest.

t	0	0.5	1	1.5	2	2.5	3
$C(t)$							

(b) Use a graphing utility to graph the concentration function and use the graph to approximate the time when the concentration is greatest.

(c) Use calculus to determine analytically the time when the concentration is greatest.

78. Numerical, Graphical, and Analytic Analysis Consider the functions $f(x) = x$ and $g(x) = \sin x$ on the interval $(0, \pi)$.

(a) Complete the table and make a conjecture about which is the greater function on the interval $(0, \pi)$.

x	0.5	1	1.5	2	2.5	3
$f(x)$						
$g(x)$						

(b) Use a graphing utility to graph the functions and use the graphs to make a conjecture about which is the greater function on the interval $(0, \pi)$.

(c) Prove that $f(x) > g(x)$ on the interval $(0, \pi)$. [*Hint*: Show that $h'(x) > 0$, where $h = f - g$.]

79. Trachea Contraction Coughing forces the trachea (windpipe) to contract, which affects the velocity v of the air passing through the trachea. The velocity of the air during coughing is

$$v = k(R - r)r^2, \quad 0 \leq r < R$$

where k is a constant, R is the normal radius of the trachea, and r is the radius during coughing. What radius will produce the maximum air velocity?

80. Electrical Resistance The resistance R of a certain type of resistor is

$$R = \sqrt{0.001T^4 - 4T + 100}$$

where R is measured in ohms and the temperature T is measured in degrees Celsius.

(a) Use a computer algebra system to find dR/dT and the critical number of the function. Determine the minimum resistance for this type of resistor.

(b) Use a graphing utility to graph the function R and use the graph to approximate the minimum resistance for this type of resistor.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Motion Along a Line **In Exercises 81–84, the function $s(t)$ describes the motion of a particle along a line. (a) Find the velocity function of the particle at any time $t \geq 0$. (b) Identify the time interval(s) on which the particle is moving in a positive direction. (c) Identify the time interval(s) on which the particle is moving in a negative direction. (d) Identify the time(s) at which the particle changes direction.**

81. $s(t) = 6t - t^2$

82. $s(t) = t^2 - 10t + 29$

83. $s(t) = t^3 - 5t^2 + 4t$

84. $s(t) = t^3 - 20t^2 + 128t - 280$

Motion Along a Line **In Exercises 85 and 86, the graph shows the position of a particle moving along a line. Describe how the position of the particle changes with respect to time.**

85.



86.



Finding Polynomial Functions **In Exercises 87–90, find a polynomial function**

$$f(x) = a_n x^n + a_{n-1}x^{n-1} + \cdots + a_2 x^2 + a_1 x + a_0$$

that has only the specified extrema. (a) Determine the minimum degree of the function and give the criteria you used in determining the degree. (b) Using the fact that the coordinates of the extrema are solution points of the function, and that the x-coordinates are critical numbers, determine a system of linear equations whose solution yields the coefficients of the required function. (c) Use a graphing utility to solve the system of equations and determine the function. (d) Use a graphing utility to confirm your result graphically.

87. Relative minimum: $(0, 0)$; Relative maximum: $(2, 2)$

88. Relative minimum: $(0, 0)$; Relative maximum: $(4, 1000)$

89. Relative minima: $(0, 0)$, $(4, 0)$; Relative maximum: $(2, 4)$

90. Relative minimum: $(1, 2)$; Relative maxima: $(-1, 4)$, $(3, 4)$

True or False? **In Exercises 91–96, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

91. There is no function with an infinite number of critical points.

92. The function $f(x) = x$ has no extrema on any open interval.

93. Every nth-degree polynomial has $(n - 1)$ critical numbers.

94. An nth-degree polynomial has at most $(n - 1)$ critical numbers.

95. There is a relative extremum at each critical number.

96. The relative maxima of the function f are $f(1) = 4$ and $f(3) = 10$. So, f has at least one minimum for some x in the interval $(1, 3)$.

97. Proof Prove the second case of Theorem 3.5.

98. Proof Prove the second case of Theorem 3.6.

99. Proof Use the definitions of increasing and decreasing functions to prove that

$$f(x) = x^3$$

is increasing on $(-\infty, \infty)$.

100. Proof Use the definitions of increasing and decreasing functions to prove that

$$f(x) = \frac{1}{x}$$

is decreasing on $(0, \infty)$.

PUTNAM EXAM CHALLENGE

101. Find the minimum value of

$$|\sin x + \cos x + \tan x + \cot x + \sec x + \csc x|$$

for real numbers x.

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

SECTION PROJECT

Even Polynomial Functions of Fourth Degree

(a) Graph each of the fourth-degree polynomials below. Then find the critical numbers, the open intervals on which the function is increasing or decreasing, and the relative extrema.

(i) $f(x) = x^4 + 1$

(ii) $f(x) = x^4 + 2x^2 + 1$

(iii) $f(x) = x^4 - 2x^2 + 1$

(b) Consider the fourth-degree polynomial

$$f(x) = x^4 + ax^2 + b.$$

(i) Show that there is one critical number when $a = 0$. Then find the open intervals on which the function is increasing or decreasing.

(ii) Show that there is one critical number when $a > 0$. Then find the open intervals on which the function is increasing or decreasing.

(iii) Show that there are three critical numbers when $a < 0$. Then find the open intervals on which the function is increasing or decreasing.

(iv) Show that there are no real zeros when

$$a^2 < 4b.$$

(v) Determine the possible number of zeros when

$$a^2 \geq 4b.$$

Explain your reasoning.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

3.4 Concavity and the Second Derivative Test

GO DIGITAL

- **Determine intervals on which a function is concave upward or concave downward.**
- **Find any points of inflection of the graph of a function.**
- **Apply the Second Derivative Test to find relative extrema of a function.**

Concavity

You have already seen that locating the intervals on which a function f increases or decreases helps to describe its graph. In this section, you will see how locating the intervals on which f' increases or decreases can be used to determine where the graph of f is *curving upward* or *curving downward*.

Definition of Concavity

Let f be differentiable on an open interval I. The graph of f is **concave upward** on I when f' is increasing on the interval and **concave downward** on I when f' is decreasing on the interval.

The next two statements and Figure 3.23 give a useful graphical interpretation of concavity (see Appendix A for a proof of these results).

1. Let f be differentiable on an open interval I. If the graph of f is concave *upward* on I, then the graph of f lies *above* all of its tangent lines on I. [See Figure 3.23(a).]
2. Let f be differentiable on an open interval I. If the graph of f is concave *downward* on I, then the graph of f lies *below* all of its tangent lines on I. [See Figure 3.23(b).]



(a) The graph of f lies above its tangent lines.



(b) The graph of f lies below its tangent lines.

Figure 3.23



f' is decreasing. f' is increasing.

The concavity of f is related to the slope of the derivative.

Figure 3.24

To find the open intervals on which the graph of a function f is concave upward or concave downward, you need to find the intervals on which f' is increasing or decreasing. For instance, the graph of

$$f(x) = \frac{1}{3}x^3 - x \qquad \text{Original function}$$

is concave downward on the open interval $(-\infty, 0)$ because

$$f'(x) = x^2 - 1 \qquad \text{First derivative}$$

is decreasing there. (See Figure 3.24.) Similarly, the graph of f is concave upward on the interval $(0, \infty)$ because f' is increasing on $(0, \infty)$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The next theorem shows how to use the *second* derivative of a function f to determine intervals on which the graph of f is concave upward or concave downward. A proof of this theorem follows directly from Theorem 3.5 and the definition of concavity.

THEOREM 3.7 Test for Concavity

Let f be a function whose second derivative exists on an open interval I.

1. If $f''(x) > 0$ for all x in I, then the graph of f is concave upward on I.
2. If $f''(x) < 0$ for all x in I, then the graph of f is concave downward on I.

A proof of this theorem is given in Appendix A.

REMARK A third case of Theorem 3.7 could be that if $f''(x) = 0$ for all x in I, then f is linear. Note, however, that concavity is not defined for a line. In other words, a straight line is neither concave upward nor concave downward.

To apply Theorem 3.7, locate the x-values at which $f''(x) = 0$ or $f''(x)$ does not exist. Use these x-values to determine test intervals. Finally, test the sign of $f''(x)$ in each of the test intervals.

EXAMPLE 1 Determining Concavity

Determine the open intervals on which the graph of

$$f(x) = \frac{6}{x^2 + 3}$$

is concave upward or concave downward.



From the sign of $f''(x)$, you can determine the concavity of the graph of f.

Figure 3.25

Solution Begin by observing that f is continuous on the entire real number line. Next, find the second derivative of f.

$$f(x) = 6(x^2 + 3)^{-1}$$ Rewrite original function.

$$f'(x) = (-6)(x^2 + 3)^{-2}(2x)$$ Differentiate.

$$= \frac{-12x}{(x^2 + 3)^2}$$ First derivative

$$f''(x) = \frac{(x^2 + 3)^2(-12) - (-12x)(2)(x^2 + 3)(2x)}{(x^2 + 3)^4}$$ Differentiate.

$$= \frac{36(x^2 - 1)}{(x^2 + 3)^3}$$ Second derivative

Because $f''(x) = 0$ when $x = \pm 1$ and f'' is defined on the entire real number line, you should test f'' in the intervals $(-\infty, -1)$, $(-1, 1)$, and $(1, \infty)$. The results are shown in the table and in Figure 3.25.

Interval	$-\infty < x < -1$	$-1 < x < 1$	$1 < x < \infty$
Test Value	$x = -2$	$x = 0$	$x = 2$
Sign of $f''(x)$	$f''(-2) > 0$	$f''(0) < 0$	$f''(2) > 0$
Conclusion	Concave upward	Concave downward	Concave upward

The function given in Example 1 is continuous on the entire real number line. When there are x-values at which a function is not continuous, these values should be used, along with the points at which $f''(x) = 0$ or $f''(x)$ does not exist, to form the test intervals.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



Figure 3.26







The concavity of f changes at a point of inflection. Note that the graph crosses its tangent line at a point of inflection.

Figure 3.27

EXAMPLE 2 Determining Concavity

Determine the open intervals on which the graph of

$$f(x) = \frac{x^2 + 1}{x^2 - 4}$$

is concave upward or concave downward.

Solution Differentiating twice produces the following.

$$f(x) = \frac{x^2 + 1}{x^2 - 4}$$ Write original function.

$$f'(x) = \frac{(x^2 - 4)(2x) - (x^2 + 1)(2x)}{(x^2 - 4)^2}$$ Differentiate.

$$= \frac{-10x}{(x^2 - 4)^2}$$ First derivative

$$f''(x) = \frac{(x^2 - 4)^2(-10) - (-10x)(2)(x^2 - 4)(2x)}{(x^2 - 4)^4}$$ Differentiate.

$$= \frac{10(3x^2 + 4)}{(x^2 - 4)^3}$$ Second derivative

There are no points at which $f''(x) = 0$, but at $x = \pm 2$, the function f is not continuous. So, test for concavity in the intervals $(-\infty, -2)$, $(-2, 2)$, and $(2, \infty)$, as shown in the table. The graph of f is shown in Figure 3.26.

Interval	$-\infty < x < -2$	$-2 < x < 2$	$2 < x < \infty$
Test Value	$x = -3$	$x = 0$	$x = 3$
Sign of $f''(x)$	$f''(-3) > 0$	$f''(0) < 0$	$f''(3) > 0$
Conclusion	Concave upward	Concave downward	Concave upward

Points of Inflection

The graph in Figure 3.25 has two points at which the concavity changes. If the tangent line to the graph exists at such a point, then that point is a **point of inflection.** Three types of points of inflection are shown in Figure 3.27.

Definition of Point of Inflection

Let f be a function that is continuous on an open interval, and let c be a point in the interval. If the graph of f has a tangent line at the point $(c, f(c))$, then this point is a **point of inflection** of the graph of f when the concavity of f changes from upward to downward (or downward to upward) at the point.

The definition of *point of inflection* requires that the tangent line exists at the point of inflection. Some calculus texts do not require this. For instance, after applying the definition above to the function

$$f(x) = \begin{cases} x^3, & x < 0 \\ x^2 + 2x, & x \geq 0 \end{cases}$$ Graph of f does not have a tangent line at $(0, 0)$.

you would conclude that f does *not* have a point of inflection at the origin, even though the concavity of the graph changes from concave downward to concave upward.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

To locate *possible* points of inflection, determine the values of x for which $f''(x) = 0$ or $f''(x)$ does not exist. This is similar to the procedure for locating relative extrema of f.

THEOREM 3.8 Points of Inflection

If $(c, f(c))$ is a point of inflection of the graph of f, then either $f''(c) = 0$ or $f''(c)$ does not exist.



Points of inflection can occur where $f''(x) = 0$ or $f''(x)$ does not exist.
Figure 3.28

EXAMPLE 3 Finding Points of Inflection

Determine the points of inflection and discuss the concavity of the graph of

$$f(x) = x^4 - 4x^3.$$

Solution Differentiating twice produces the following.

$$f(x) = x^4 - 4x^3 \qquad \text{Write original function.}$$
$$f'(x) = 4x^3 - 12x^2 \qquad \text{Find first derivative.}$$
$$f''(x) = 12x^2 - 24x = 12x(x - 2) \qquad \text{Find second derivative.}$$

Setting $f''(x) = 0$, you can determine that the possible points of inflection occur at $x = 0$ and $x = 2$. By testing the intervals determined by these x-values, you can conclude that they both yield points of inflection, one at $(0, 0)$ and the other at $(2, -16)$. A summary of this testing is shown in the table, and the graph of f is shown in Figure 3.28.

Interval	$-\infty < x < 0$	$0 < x < 2$	$2 < x < \infty$
Test Value	$x = -1$	$x = 1$	$x = 3$
Sign of $f''(x)$	$f''(-1) > 0$	$f''(1) < 0$	$f''(3) > 0$
Conclusion	Concave upward	Concave downward	Concave upward

Exploration

Consider a general cubic function of the form

$$f(x) = ax^3 + bx^2 + cx + d.$$

You know that the value of d has a bearing on the location of the graph but has no bearing on the value of the first derivative at given values of x. Graphically, this is true because changes in the value of d shift the graph up or down but do not change its basic shape. Use a graphing utility to graph several cubic functions with different values of c. Then give a graphical explanation of why changes in c do not affect the values of the second derivative.

The converse of Theorem 3.8 is not generally true. That is, it is possible for the second derivative to be 0 at a point that is *not* a point of inflection. For instance, the graph of $f(x) = x^4$ is shown in Figure 3.29. The second derivative is 0 when $x = 0$, but the point $(0, 0)$ is not a point of inflection because the graph of f is concave upward on the intervals $-\infty < x < 0$ and $0 < x < \infty$.



$f''(x) = 0$, but $(0, 0)$ is not a point of inflection.
Figure 3.29

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



If $f'(c) = 0$ and $f''(c) > 0$, then $f(c)$ is a relative minimum.



If $f'(c) = 0$ and $f''(c) < 0$, then $f(c)$ is a relative maximum.

Figure 3.30

GO DIGITAL



(0, 0) is neither a relative minimum nor a relative maximum.

Figure 3.31

The Second Derivative Test

In addition to testing for concavity, the second derivative can be used to perform a simple test for relative maxima and minima. The test is based on the fact that if the graph of a function f is concave upward on an open interval containing c, and $f'(c) = 0$, then $f(c)$ must be a relative minimum of f. Similarly, if the graph of a function f is concave downward on an open interval containing c, and $f'(c) = 0$, then $f(c)$ must be a relative maximum of f. (See Figure 3.30.)

THEOREM 3.9 Second Derivative Test

Let f be a function such that $f'(c) = 0$ and the second derivative of f exists on an open interval containing c.

1. If $f''(c) > 0$, then f has a relative minimum at $(c, f(c))$.
2. If $f''(c) < 0$, then f has a relative maximum at $(c, f(c))$.

If $f''(c) = 0$, then the test fails. That is, f may have a relative maximum, a relative minimum, or neither. In such cases, use the First Derivative Test.

Proof Consider the first case where $f''(c) > 0$. Because

$$f''(c) = \lim_{x \to c} \frac{f'(x) - f'(c)}{x - c} > 0$$ Use limit definition of second derivative.

and $f'(c) = 0$, there exists an open interval I containing c for which

$$\frac{f'(x) - f'(c)}{x - c} = \frac{f'(x)}{x - c} > 0$$ See Exercise 88(b), Section 1.2.

for all $x \neq c$ in I. If $x < c$, then $x - c < 0$ and $f'(x) < 0$. Also, if $x > c$, then $x - c > 0$ and $f'(x) > 0$. So, $f'(x)$ changes from negative to positive at c, and the First Derivative Test implies that $f(c)$ is a relative minimum. A proof of the second case is left to you. ■

EXAMPLE 4 Using the Second Derivative Test

See LarsonCalculus.com for an interactive version of this type of example.

Find the relative extrema of $f(x) = -3x^5 + 5x^3$.

Solution The first derivative is $f'(x) = -15x^4 + 15x^2 = 15x^2(1 - x^2)$. From this derivative, you can see that $x = -1$, 0, and 1 are the only critical numbers of f. By finding the second derivative

$$f''(x) = -60x^3 + 30x = 30x(1 - 2x^2)$$

you can apply the Second Derivative Test as shown below.

Point	$(-1, -2)$	$(0, 0)$	$(1, 2)$
Sign of $f''(x)$	$f''(-1) > 0$	$f''(0) = 0$	$f''(1) < 0$
Conclusion	Relative minimum	Test fails	Relative maximum

Because the Second Derivative Test fails at $(0, 0)$, you can use the First Derivative Test and observe that f increases to the left and right of $x = 0$. So, $(0, 0)$ is neither a relative minimum nor a relative maximum (even though the graph has a horizontal tangent line at this point). The graph of f is shown in Figure 3.31. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

3.4 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe the Test for Concavity.
2. Describe the Second Derivative Test.

Using a Graph In Exercises 3 and 4, the graph of f is shown. State the signs of f' and f'' on the interval $(0, 2)$.

3.



4.



Determining Concavity In Exercises 5–16, determine the open intervals on which the graph of the function is concave upward or concave downward.

5. $f(x) = x^2 - 4x + 8$
6. $g(x) = 3x^2 - x^3$
7. $f(x) = x^4 - 3x^3$
8. $h(x) = x^5 - 5x + 2$
9. $f(x) = \dfrac{24}{x^2 + 12}$
10. $f(x) = \dfrac{2x^2}{3x^2 + 1}$
11. $f(x) = \dfrac{x - 2}{6x + 1}$
12. $f(x) = \dfrac{x + 8}{x - 7}$
13. $f(x) = \dfrac{x^2 + 1}{x^2 - 1}$
14. $h(x) = \dfrac{x^2 - 1}{2x - 1}$
15. $y = 2x - \tan x, \quad \left(-\dfrac{\pi}{2}, \dfrac{\pi}{2}\right)$
16. $y = x + \dfrac{2}{\sin x}, \quad (-\pi, \pi)$

Finding Points of Inflection In Exercises 17–32, find any points of inflection and discuss the concavity of the graph of the function.

17. $f(x) = x^3 - 9x^2 + 24x - 18$
18. $f(x) = -x^3 + 6x^2 - 5$
19. $f(x) = 2 - 7x^4$
20. $f(x) = 4 - x - 3x^4$
21. $f(x) = x(x - 4)^3$
22. $f(x) = (x - 2)^3(x - 1)$
23. $f(x) = x\sqrt{x + 3}$
24. $f(x) = x\sqrt{9 - x}$
25. $f(x) = \dfrac{6 - x}{\sqrt{x}}$
26. $f(x) = \dfrac{x + 3}{\sqrt{x}}$
27. $f(x) = \sin\dfrac{x}{2}, \quad [0, 4\pi]$
28. $f(x) = 2\csc\dfrac{3x}{2}, \quad (0, 2\pi)$
29. $f(x) = \sec\left(x - \dfrac{\pi}{2}\right), \quad (0, 4\pi)$
30. $f(x) = \sin x + \cos x, \quad [0, 2\pi]$
31. $f(x) = 2\sin x + \sin 2x, \quad [0, 2\pi]$
32. $f(x) = x + 2\cos x, \quad [0, 2\pi]$

Using the Second Derivative Test In Exercises 33–44, find all relative extrema of the function. Use the Second Derivative Test where applicable.

33. $f(x) = 6x - x^2$
34. $f(x) = x^2 + 3x - 8$
35. $f(x) = x^3 - 3x^2 + 3$
36. $f(x) = -x^3 + 7x^2 - 15x$
37. $f(x) = x^4 - 4x^3 + 2$
38. $f(x) = -x^4 + 2x^3 + 8x$
39. $f(x) = x^{2/3} - 3$
40. $f(x) = \sqrt{x^2 + 1}$
41. $f(x) = x + \dfrac{4}{x}$
42. $f(x) = \dfrac{9x - 1}{x + 5}$
43. $f(x) = \cos x - x, \quad [0, 4\pi]$
44. $f(x) = 2\sin x + \cos 2x, \quad [0, 2\pi]$

Finding Extrema and Points of Inflection Using Technology In Exercises 45–48, use a computer algebra system to analyze the function over the given interval. (a) Find the first and second derivatives of the function. (b) Find any relative extrema and points of inflection. (c) Graph f, f', and f'' on the same set of coordinate axes and state the relationship between the behavior of f and the signs of f' and f''.

45. $f(x) = 0.2x^2(x - 3)^3, \quad [-1, 4]$
46. $f(x) = x^2\sqrt{6 - x^2}, \quad \left[-\sqrt{6}, \sqrt{6}\right]$
47. $f(x) = \sin x - \frac{1}{3}\sin 3x + \frac{1}{5}\sin 5x, \quad [0, \pi]$
48. $f(x) = \sqrt{2x}\sin x, \quad [0, 2\pi]$

Exploring Concepts

49. Consider a function f such that f' is increasing. Sketch graphs of f for (a) $f' < 0$ and (b) $f' > 0$.
50. S represents weekly sales of a product. What can be said of S' and S'' for each of the following statements?
    (a) The rate of change of sales is increasing.
    (b) The rate of change of sales is constant.
    (c) Sales are steady.
    (d) Sales are declining but at a slower rate.
    (e) Sales have bottomed out and have started to rise.

Sketching Graphs In Exercises 51 and 52, the graph of f is shown. Graph f, f', and f'' on the same set of coordinate axes. To print an enlarged copy of the graph, go to *MathGraphs.com*.

51.



52.



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Think About It **In Exercises 53–56, sketch the graph of a function f having the given characteristics.**

53. $f(0) = f(2) = 0$
$f'(x) > 0$ for $x < 1$
$f'(1) = 0$
$f'(x) < 0$ for $x > 1$
$f''(x) < 0$

54. $f(0) = f(2) = 0$
$f'(x) < 0$ for $x < 1$
$f'(1) = 0$
$f'(x) > 0$ for $x > 1$
$f''(x) > 0$

55. $f(2) = f(4) = 0$
$f'(x) < 0$ for $x < 3$
$f'(3)$ does not exist.
$f'(x) > 0$ for $x > 3$
$f''(x) < 0, x \neq 3$

56. $f(1) = f(3) = 0$
$f'(x) > 0$ for $x < 2$
$f'(2)$ does not exist.
$f'(x) < 0$ for $x > 2$
$f''(x) > 0, x \neq 2$

57. Think About It The figure shows the graph of f''. Sketch a graph of f. (The answer is not unique.) To print an enlarged copy of the graph, go to *MathGraphs.com*.



58. HOW DO YOU SEE IT? Water is running into the vase shown in the figure at a constant rate.



(a) Graph the depth d of water in the vase as a function of time.

(b) Does the function have any extrema? Explain.

(c) Interpret the inflection points of the graph of d.

59. Conjecture Consider the function

$$f(x) = (x - 2)^n.$$

(a) Use a graphing utility to graph f for $n = 1, 2, 3$, and 4. Use the graphs to make a conjecture about the relationship between n and any inflection points of the graph of f.

(b) Verify your conjecture in part (a).

60. Inflection Point Consider the function $f(x) = \sqrt[3]{x}$.

(a) Graph the function and identify the inflection point.

(b) Does f'' exist at the inflection point? Explain.

Finding a Cubic Function **In Exercises 61 and 62, find a, b, c, and d such that the cubic function**

$$f(x) = ax^3 + bx^2 + cx + d$$

satisfies the given conditions.

61. Relative maximum: $(3, 3)$
Relative minimum: $(5, 1)$
Inflection point: $(4, 2)$

62. Relative maximum: $(2, 4)$
Relative minimum: $(4, 2)$
Inflection point: $(3, 3)$

63. Aircraft Glide Path A small aircraft starts its descent 4 miles west of the runway from an altitude of 1 mile (see figure).



(a) Find the cubic function $f(x) = ax^3 + bx^2 + cx + d$ on the interval $[-4, 0]$ that describes a smooth glide path for the landing.

(b) The function in part (a) models the glide path of the plane. When would the plane be descending at the greatest rate?

FOR FURTHER INFORMATION For more information on this type of modeling, see the article "How Not to Land at Lake Tahoe!" by Richard Barshinger in *The American Mathematical Monthly*. To view this article, go to *MathArticles.com*.

64. Highway Design A section of highway connecting two hillsides with grades of 6% and 4% is to be built between two points that are separated by a horizontal distance of 2000 feet (see figure). At the point where the two hillsides come together, there is a 50-foot difference in elevation.



(a) Find the cubic function

$$f(x) = ax^3 + bx^2 + cx + d, \quad -1000 \leq x \leq 1000$$

that describes the section of highway connecting the hillsides. At points A and B, the slope of the model must match the grade of the hillside.

(b) Use a graphing utility to graph the model.

(c) Use a graphing utility to graph the derivative of the model.

(d) Determine the grade at the steepest part of the transitional section of the highway.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

65. Average Cost A manufacturer has determined that the total cost C of operating a factory is

$$C = 0.5x^2 + 15x + 5000$$

where x is the number of units produced. At what level of production will the average cost per unit be minimized? (The average cost per unit is C/x.)

66. Specific Gravity A model for the specific gravity of water S is

$$S = \frac{5.755}{10^8}T^3 - \frac{8.521}{10^6}T^2 + \frac{6.540}{10^5}T + 0.99987, \quad 0 < T < 25$$

where T is the water temperature in degrees Celsius.

(a) Use the second derivative to determine the concavity of S.

(b) Use a computer algebra system to find the coordinates of the maximum value of the function.

(c) Use a graphing utility to graph the function over the specified domain. (Use a setting in which $0.996 \le S \le 1.001$.)

(d) Estimate the specific gravity of water when $T = 20°$.

67. Sales Growth The annual sales S of a new product are given by

$$S = \frac{5000t^2}{8 + t^2}, \quad 0 \le t \le 3$$

where t is time in years.

(a) Complete the table. Then use it to estimate when the annual sales are increasing at the greatest rate.

t	0.5	1	1.5	2	2.5	3
S						

(b) Use a graphing utility to graph the function S. Then use the graph to estimate when the annual sales are increasing at the greatest rate.

(c) Find the exact time when the annual sales are increasing at the greatest rate.

68. Modeling Data The average typing speeds S (in words per minute) of a typing student after t weeks of lessons are shown in the table.

t	5	10	15	20	25	30
S	28	56	79	90	93	94

A model for the data is

$$S = \frac{100t^2}{65 + t^2}, \quad t > 0.$$

(a) Use a graphing utility to plot the data and graph the model.

(b) Use the second derivative to determine the concavity of S. Compare the result with the graph in part (a).

(c) What is the sign of the first derivative for $t > 0$? By combining this information with the concavity of the model, what inferences can be made about the typing speed as t increases?

Linear and Quadratic Approximations **In Exercises 69–72, use a graphing utility to graph the function. Then graph the linear and quadratic approximations**

$$P_1(x) = f(a) + f'(a)(x - a)$$

and

$$P_2(x) = f(a) + f'(a)(x - a) + \tfrac{1}{2}f''(a)(x - a)^2$$

in the same viewing window. Compare the values of f, P_1, and P_2 and their first derivatives at $x = a$. How do the approximations change as you move farther away from $x = a$?

	Function	Value of a
69.	$f(x) = 2(\sin x + \cos x)$	$a = \frac{\pi}{4}$
70.	$f(x) = 2(\sin x + \cos x)$	$a = 0$
71.	$f(x) = \sqrt{1 - x}$	$a = 0$
72.	$f(x) = \frac{\sqrt{x}}{x - 1}$	$a = 2$

73. Point of Inflection and Extrema Consider the function

$$f(x) = \frac{\sin x}{x}, \quad x > 0.$$

(a) Show that the relative extrema of f lie on the curve $y^2(1 + x^2) = 1$.

(b) Show that the points of inflection of f lie on the curve $y^2(4 + x^4) = 4$.

74. Point of Inflection and Extrema Show that the point of inflection of

$$f(x) = x(x - 6)^2$$

lies midway between the relative extrema of f.

True or False? **In Exercises 75–78, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

75. The graph of every cubic polynomial has precisely one point of inflection.

76. The graph of

$$f(x) = \frac{1}{x}$$

is concave downward for $x < 0$ and concave upward for $x > 0$, and thus it has a point of inflection at $x = 0$.

77. If $f'(c) > 0$, then f is concave upward at $x = c$.

78. If $f''(2) = 0$, then the graph of f must have a point of inflection at $x = 2$.

Proof **In Exercises 79 and 80, let f and g represent differentiable functions such that $f'' \neq 0$ and $g'' \neq 0$.**

79. Show that if f and g are concave upward on the interval (a, b), then $f + g$ is also concave upward on (a, b).

80. Prove that if f and g are positive, increasing, and concave upward on the interval (a, b), then fg is also concave upward on (a, b).

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

3.5 Limits at Infinity

GO DIGITAL

- **Determine (finite) limits at infinity.**
- **Determine the horizontal asymptotes, if any, of the graph of a function.**
- **Determine infinite limits at infinity.**

Limits at Infinity

This section discusses the "end behavior" of a function on an *infinite* interval. Consider the graph of

$$f(x) = \frac{3x^2}{x^2 + 1}$$

as shown in Figure 3.32. Graphically, $f(x)$ appears to approach 3 as x increases without bound or decreases without bound. A numerical approach supports this conclusion, as shown in the table.



The limit of $f(x)$ as x approaches $-\infty$ or ∞ is 3.

Figure 3.32

x decreases without bound. | x increases without bound.

x	$-\infty\leftarrow$	-100	-10	-1	0	1	10	100	$\rightarrow\infty$
$f(x)$	$3\leftarrow$	2.9997	2.9703	1.5	0	1.5	2.9703	2.9997	$\rightarrow 3$

$f(x)$ approaches 3. | $f(x)$ approaches 3.

The table suggests that $f(x)$ approaches 3 as x increases without bound ($x \to \infty$). Similarly, $f(x)$ approaches 3 as x decreases without bound ($x \to -\infty$). These **limits at infinity** are denoted by

$$\lim_{x\to-\infty} f(x) = 3 \qquad \text{Limit at negative infinity}$$

and

$$\lim_{x\to\infty} f(x) = 3. \qquad \text{Limit at positive infinity}$$

To say that a statement is true as x increases *without bound* means that for some (large) real number M, the statement is true for *all* x in the interval $\{x: x > M\}$. The next definition uses this concept.

REMARK The statement $\lim_{x\to-\infty} f(x) = L$ or $\lim_{x\to\infty} f(x) = L$ means that the limit exists *and* the limit is equal to L.

Definition of Limits at Infinity

Let L be a real number.

1. The statement $\lim_{x\to\infty} f(x) = L$ means that for each $\varepsilon > 0$ there exists an $M > 0$ such that $|f(x) - L| < \varepsilon$ whenever $x > M$.
2. The statement $\lim_{x\to-\infty} f(x) = L$ means that for each $\varepsilon > 0$ there exists an $N < 0$ such that $|f(x) - L| < \varepsilon$ whenever $x < N$.



$f(x)$ is within ε units of L as $x \to \infty$.

Figure 3.33

The definition of a limit at infinity is shown in Figure 3.33. In this figure, note that for a given positive number ε, there exists a positive number M such that, for $x > M$, the graph of f will lie between the horizontal lines

$$y = L + \varepsilon \quad \text{and} \quad y = L - \varepsilon.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploration

Use a graphing utility to graph

$$f(x) = \frac{2x^2 + 4x - 6}{3x^2 + 2x - 16}.$$

Describe all the important features of the graph. Can you find a single viewing window that shows all of these features clearly? Explain your reasoning.

What are the horizontal asymptotes of the graph? How far to the right do you have to move on the graph so that the graph is within 0.001 unit of its horizontal asymptote? Explain your reasoning.

GO DIGITAL

Horizontal Asymptotes

In Figure 3.33, the graph of f approaches the line $y = L$ as x increases without bound. The line $y = L$ is called a **horizontal asymptote** of the graph of f.

Definition of a Horizontal Asymptote

The line $y = L$ is a **horizontal asymptote** of the graph of f when

$$\lim_{x \to -\infty} f(x) = L \quad \text{or} \quad \lim_{x \to \infty} f(x) = L.$$

Note that from this definition, it follows that the graph of a *function* of x can have at most two horizontal asymptotes—one to the right and one to the left.

Limits at infinity have many of the same properties of limits discussed in Section 1.3. For example, if $\lim_{x \to \infty} f(x)$ and $\lim_{x \to \infty} g(x)$ both exist, then

$$\lim_{x \to \infty} [f(x) + g(x)] = \lim_{x \to \infty} f(x) + \lim_{x \to \infty} g(x)$$ Property 2, Theorem 1.2

and

$$\lim_{x \to \infty} [f(x)g(x)] = \left[\lim_{x \to \infty} f(x)\right]\left[\lim_{x \to \infty} g(x)\right].$$ Property 4, Theorem 1.2

Similar properties hold for limits at $-\infty$.

When evaluating limits at infinity, the next theorem is helpful.

THEOREM 3.10 Limits at Infinity

If r is a positive rational number and c is any real number, then

$$\lim_{x \to \infty} \frac{c}{x^r} = 0.$$

Furthermore, if x^r is defined when $x < 0$, then

$$\lim_{x \to -\infty} \frac{c}{x^r} = 0.$$

A proof of this theorem is given in Appendix A.

EXAMPLE 1 Finding a Limit at Infinity

Find the limit: $\lim_{x \to \infty} \left(5 - \frac{2}{x^2}\right)$.

Solution Using several properties of limits, you can write

$$\lim_{x \to \infty} \left(5 - \frac{2}{x^2}\right) = \lim_{x \to \infty} 5 - \lim_{x \to \infty} \frac{2}{x^2}$$ Property 3, Theorem 1.2

$$= 5 - 0$$ Property 1, Theorem 1.1, and Theorem 3.10

$$= 5.$$

So, the line $y = 5$ is a horizontal asymptote to the right. Note that as $x \to -\infty$,

$$\lim_{x \to -\infty} \left(5 - \frac{2}{x^2}\right) = \lim_{x \to -\infty} 5 - \lim_{x \to -\infty} \frac{2}{x^2} = 5 - 0 = 5.$$

So, $y = 5$ is also a horizontal asymptote to the left. The graph of the function $f(x) = 5 - (2/x^2)$ is shown in Figure 3.34. (In Figure 3.34, the horizontal asymptote $y = 5$ is shown as a dashed line.)



$y = 5$ is a horizontal asymptote.
Figure 3.34

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 2 Finding a Limit at Infinity

Find the limit: $\lim_{x\to\infty} \frac{2x-1}{x+1}$.

Solution Note that both the numerator and the denominator approach infinity as x approaches infinity.

$$\lim_{x\to\infty} \frac{2x-1}{x+1} \quad \begin{cases} \lim_{x\to\infty} (2x-1) = \infty \\ \lim_{x\to\infty} (x+1) = \infty \end{cases}$$

This results in ∞/∞, an **indeterminate form.** To resolve this problem, divide both the numerator and the denominator by x. After dividing, the limit may be found as shown.

$$\lim_{x\to\infty} \frac{2x-1}{x+1} = \lim_{x\to\infty} \frac{\frac{2x-1}{x}}{\frac{x+1}{x}} \qquad \text{Divide numerator and denominator by } x.$$

$$= \lim_{x\to\infty} \frac{2-\frac{1}{x}}{1+\frac{1}{x}} \qquad \text{Simplify.}$$

$$= \frac{\lim_{x\to\infty} 2 - \lim_{x\to\infty} \frac{1}{x}}{\lim_{x\to\infty} 1 + \lim_{x\to\infty} \frac{1}{x}} \qquad \text{Properties 2, 3, and 5, Theorem 1.2}$$

$$= \frac{2-0}{1+0} \qquad \text{Property 1, Theorem 1.1, and Theorem 3.10}$$

$$= 2$$

So, the line $y = 2$ is a horizontal asymptote to the right. By taking the limit as $x \to -\infty$, you can see that $y = 2$ is also a horizontal asymptote to the left. Figure 3.35 shows the graph of $f(x) = (2x-1)/(x+1)$ and its horizontal asymptote, $y = 2$. (Note that the vertical asymptote, $x = -1$, is also shown.)

REMARK When you encounter an indeterminate form such as the one in Example 2, you should divide the numerator and denominator by the highest power of x in the *denominator*.



$y = 2$ is a horizontal asymptote.
Figure 3.35

TECHNOLOGY To test the reasonableness of the limit found in Example 2, evaluate $f(x)$ for a few large positive values of x. For instance,

$f(100) \approx 1.9703$, $f(1000) \approx 1.9970$, and $f(10{,}000) \approx 1.9997$.

Another way to test the reasonableness of the limit is to use a graphing utility. For instance, in Figure 3.36, the graph of

$$f(x) = \frac{2x-1}{x+1}$$

is shown with the horizontal line $y = 2$. Note that as x increases, the graph of f moves closer and closer to its horizontal asymptote.



As x increases, the graph of f moves closer and closer to the line $y = 2$.
Figure 3.36

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

MARIA GAETANA AGNESI (1718–1799)

Agnesi was one of a handful of women to receive credit for significant contributions to mathematics before the twentieth century. In her early twenties, she wrote the first text that included both differential and integral calculus. By age 30, she was an honorary member of the faculty at the University of Bologna.

See LarsonCalculus.com to read more of this biography.

FOR FURTHER INFORMATION

For more information on the contributions of women to mathematics, see the article "Why Women Succeed in Mathematics" by Mona Fabricant, Sylvia Svitak, and Patricia Clark Kenschaft in *Mathematics Teacher*. To view this article, go to *MathArticles.com*.



f has a horizontal asymptote at $y = 0$.
Figure 3.37

EXAMPLE 3 A Comparison of Three Rational Functions

See LarsonCalculus.com for an interactive version of this type of example.

Find each limit.

a. $\lim_{x\to\infty} \frac{2x + 5}{3x^2 + 1}$ **b.** $\lim_{x\to\infty} \frac{2x^2 + 5}{3x^2 + 1}$

c. $\lim_{x\to\infty} \frac{2x^3 + 5}{3x^2 + 1}$

Solution In each case, attempting to evaluate the limit produces the indeterminate form ∞/∞. Note that the highest power of x in the *denominator* of each fraction is x^2. So, to find each limit, divide both the numerator and the denominator by x^2.

a. $\lim_{x\to\infty} \frac{2x + 5}{3x^2 + 1} = \lim_{x\to\infty} \frac{(2/x) + (5/x^2)}{3 + (1/x^2)} = \frac{0 + 0}{3 + 0} = \frac{0}{3} = 0$

b. $\lim_{x\to\infty} \frac{2x^2 + 5}{3x^2 + 1} = \lim_{x\to\infty} \frac{2 + (5/x^2)}{3 + (1/x^2)} = \frac{2 + 0}{3 + 0} = \frac{2}{3}$

c. $\lim_{x\to\infty} \frac{2x^3 + 5}{3x^2 + 1} = \lim_{x\to\infty} \frac{2x + (5/x^2)}{3 + (1/x^2)} = \frac{\infty}{3}$ Limit does not exist

This limit *does not exist* because the numerator increases without bound while the denominator approaches 3. ■

Example 3 suggests the guidelines below for finding limits at infinity of rational functions. Use these guidelines to check the results in Example 3.

Guidelines for Finding Limits at $\pm\infty$ of Rational Functions

1. If the degree of the numerator is *less than* the degree of the denominator, then the limit of the rational function is 0.
2. If the degree of the numerator is *equal to* the degree of the denominator, then the limit of the rational function is the ratio of the leading coefficients.
3. If the degree of the numerator is *greater than* the degree of the denominator, then the limit of the rational function does not exist.

The guidelines for finding limits at infinity of rational functions seem reasonable when you consider that for large values of x, the highest-power term of the rational function is the most "influential" in determining the limit. For instance,

$\lim_{x\to\infty} \frac{1}{x^2 + 1}$ ← Degree of numerator is 0. ← Degree of denominator is 2.

is 0 because the denominator overpowers the numerator as x increases or decreases without bound, as shown in Figure 3.37.

The function shown in Figure 3.37 is a special case of a type of curve studied by the Italian mathematician Maria Gaetana Agnesi. The general form of this function is

$$f(x) = \frac{8a^3}{x^2 + 4a^2}$$ Witch of Agnesi

and, through a mistranslation of the Italian word *vertéré*, the curve has come to be known as the Witch of Agnesi. Agnesi's work with this curve first appeared in a comprehensive text on calculus that was published in 1748.

GO DIGITAL

Colport/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

In Figure 3.37, notice that the graph of $f(x) = 1/(x^2 + 1)$ approaches the same horizontal asymptote to the right and to the left. This is always true of rational functions. Functions that are not rational, however, may approach different horizontal asymptotes to the right and to the left. This is demonstrated in Example 4.

EXAMPLE 4 A Function with Two Horizontal Asymptotes

Find each limit.

a. $\lim_{x\to\infty} \dfrac{3x - 2}{\sqrt{2x^2 + 1}}$ **b.** $\lim_{x\to-\infty} \dfrac{3x - 2}{\sqrt{2x^2 + 1}}$

Solution

a. For $x > 0$, you can write $x = \sqrt{x^2}$. So, dividing both the numerator and the denominator by x produces

$$\frac{3x - 2}{\sqrt{2x^2 + 1}} = \frac{\frac{3x - 2}{x}}{\frac{\sqrt{2x^2 + 1}}{\sqrt{x^2}}} = \frac{3 - \frac{2}{x}}{\sqrt{\frac{2x^2 + 1}{x^2}}} = \frac{3 - \frac{2}{x}}{\sqrt{2 + \frac{1}{x^2}}}$$

and you can take the limit as follows.

$$\lim_{x\to\infty} \frac{3x - 2}{\sqrt{2x^2 + 1}} = \lim_{x\to\infty} \frac{3 - \frac{2}{x}}{\sqrt{2 + \frac{1}{x^2}}} = \frac{3 - 0}{\sqrt{2 + 0}} = \frac{3}{\sqrt{2}}$$

b. For $x < 0$, you can write $x = -\sqrt{x^2}$. So, dividing both the numerator and the denominator by x produces

$$\frac{3x - 2}{\sqrt{2x^2 + 1}} = \frac{\frac{3x - 2}{x}}{\frac{\sqrt{2x^2 + 1}}{-\sqrt{x^2}}} = \frac{3 - \frac{2}{x}}{-\sqrt{\frac{2x^2 + 1}{x^2}}} = \frac{3 - \frac{2}{x}}{-\sqrt{2 + \frac{1}{x^2}}}$$

and you can take the limit as follows.

$$\lim_{x\to-\infty} \frac{3x - 2}{\sqrt{2x^2 + 1}} = \lim_{x\to-\infty} \frac{3 - \frac{2}{x}}{-\sqrt{2 + \frac{1}{x^2}}} = \frac{3 - 0}{-\sqrt{2 + 0}} = -\frac{3}{\sqrt{2}}$$

The graph of $f(x) = (3x - 2)/\sqrt{2x^2 + 1}$ is shown in Figure 3.38. In the figure, notice that the line $y = 3/\sqrt{2}$ is a horizontal asymptote to the right, and the line $y = -3/\sqrt{2}$ is a horizontal asymptote to the left. ■

REMARK Be sure you understand that the guidelines on the preceding page *do not* apply to limits of functions that "look rational," such as those in Example 4. Remember, a rational function is the quotient of two *polynomials* (see Section P.3).



Functions that are not rational may have different right and left horizontal asymptotes.

Figure 3.38



The horizontal asymptote appears to be the line $y = 1$, but it is actually the line $y = 2$.

Figure 3.39

TECHNOLOGY PITFALL If you use a graphing utility to estimate a limit, be sure that you also confirm the estimate analytically—the graphs shown by a graphing utility can be misleading. For instance, Figure 3.39 shows one view of the graph of

$$y = \frac{2x^3 + 1000x^2 + x}{x^3 + 1000x^2 + x + 1000}.$$

From this view, it appears that the line $y = 1$ is a horizontal asymptote. An analytical approach shows that the horizontal asymptote is actually $y = 2$. Confirm this by adjusting the viewing window on the graphing utility.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

In Section 1.4, Example 7(c), you used the Squeeze Theorem to evaluate a limit involving a trigonometric function. The Squeeze Theorem is also valid for limits at infinity.

EXAMPLE 5 Limits Involving Trigonometric Functions

Find each limit.

a. $\lim_{x\to\infty} \sin x$ **b.** $\lim_{x\to\infty} \frac{\sin x}{x}$

Solution

a. As x approaches infinity, the sine function oscillates between 1 and -1. So, this limit does not exist.

b. Because $-1 \le \sin x \le 1$, it follows that for $x > 0$,

$$-\frac{1}{x} \le \frac{\sin x}{x} \le \frac{1}{x}$$

where

$$\lim_{x\to\infty}\left(-\frac{1}{x}\right) = 0 \quad \text{and} \quad \lim_{x\to\infty}\frac{1}{x} = 0.$$

So, by the Squeeze Theorem, you obtain

$$\lim_{x\to\infty}\frac{\sin x}{x} = 0$$

as shown in Figure 3.40.



As x increases without bound, $f(x)$ approaches 0.
Figure 3.40

EXAMPLE 6 Oxygen Level in a Pond

Let $f(t)$ measure the level of oxygen in a pond, where $f(t) = 1$ is the normal (unpolluted) level and the time t is measured in weeks. When $t = 0$, organic waste is dumped into the pond, and as the waste material oxidizes, the level of oxygen in the pond is

$$f(t) = \frac{t^2 - t + 1}{t^2 + 1}.$$

What percent of the normal level of oxygen exists in the pond after 1 week? After 2 weeks? After 10 weeks? What is the limit as t approaches infinity?

Solution

When $t = 1$, 2, and 10, the levels of oxygen are as shown.

$$f(1) = \frac{1^2 - 1 + 1}{1^2 + 1} = \frac{1}{2} = 50\% \qquad \text{1 week}$$

$$f(2) = \frac{2^2 - 2 + 1}{2^2 + 1} = \frac{3}{5} = 60\% \qquad \text{2 weeks}$$

$$f(10) = \frac{10^2 - 10 + 1}{10^2 + 1} = \frac{91}{101} \approx 90.1\% \qquad \text{10 weeks}$$

To find the limit as t approaches infinity, you can use the guidelines on page 202, or you can divide the numerator and the denominator by t^2 to obtain

$$\lim_{t\to\infty}\frac{t^2 - t + 1}{t^2 + 1} = \lim_{t\to\infty}\frac{1 - (1/t) + (1/t^2)}{1 + (1/t^2)} = \frac{1 - 0 + 0}{1 + 0} = 1 = 100\%.$$

See Figure 3.41.



The level of oxygen in a pond approaches the normal level of 1 as t approaches ∞.
Figure 3.41

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Infinite Limits at Infinity

Many functions do not approach a finite limit as x increases (or decreases) without bound. For instance, no polynomial function has a finite limit at infinity. The next definition is used to describe the behavior of polynomial and other functions at infinity.

REMARK Determining whether a function has an infinite limit at infinity is useful in analyzing the "end behavior" of its graph. You will see examples of this in Section 3.6 on curve sketching.

Definition of Infinite Limits at Infinity

Let f be a function defined on the interval (a, ∞).

1. The statement $\lim_{x\to\infty} f(x) = \infty$ means that for each positive number M, there is a corresponding number $N > 0$ such that $f(x) > M$ whenever $x > N$.
2. The statement $\lim_{x\to\infty} f(x) = -\infty$ means that for each negative number M, there is a corresponding number $N > 0$ such that $f(x) < M$ whenever $x > N$.

Similar definitions can be given for the statements

$$\lim_{x\to-\infty} f(x) = \infty \quad \text{and} \quad \lim_{x\to-\infty} f(x) = -\infty.$$



Figure 3.42

EXAMPLE 7 Finding Infinite Limits at Infinity

Find each limit.

a. $\lim_{x\to\infty} x^3$ **b.** $\lim_{x\to-\infty} x^3$

Solution

a. As x increases without bound, x^3 also increases without bound. So,

$$\lim_{x\to\infty} x^3 = \infty.$$

b. As x decreases without bound, x^3 also decreases without bound. So,

$$\lim_{x\to-\infty} x^3 = -\infty.$$

The graph of $f(x) = x^3$ in Figure 3.42 illustrates these two results. These results agree with the Leading Coefficient Test for polynomial functions as described in Section P.3.



Figure 3.43

EXAMPLE 8 Finding Infinite Limits at Infinity

Find each limit.

a. $\lim_{x\to\infty} \dfrac{2x^2 - 4x}{x + 1}$ **b.** $\lim_{x\to-\infty} \dfrac{2x^2 - 4x}{x + 1}$

Solution One way to evaluate each of these limits is to use long division to rewrite the improper rational function as the sum of a polynomial and a rational function.

a. $\lim_{x\to\infty} \dfrac{2x^2 - 4x}{x + 1} = \lim_{x\to\infty} \left(2x - 6 + \dfrac{6}{x + 1}\right) = \infty$

b. $\lim_{x\to-\infty} \dfrac{2x^2 - 4x}{x + 1} = \lim_{x\to-\infty} \left(2x - 6 + \dfrac{6}{x + 1}\right) = -\infty$

The statements above can be interpreted as saying that as x approaches $\pm\infty$, the function $f(x) = (2x^2 - 4x)/(x + 1)$ behaves like the function $g(x) = 2x - 6$. In Section 3.6, you will see that this is graphically described by saying that the line $y = 2x - 6$ is a *slant asymptote* of the graph of f, as shown in Figure 3.43.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

3.5 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe what each statement means.
   (a) $\lim_{x\to\infty} f(x) = -5$
   (b) $\lim_{x\to-\infty} f(x) = 3$
2. Explain what it means for the graph of a function to have a horizontal asymptote.
3. A graph can have a maximum of how many horizontal asymptotes? Explain.
4. Summarize the guidelines for finding limits at infinity of rational functions.

Matching **In Exercises 5–10, match the function with its graph using horizontal asymptotes as an aid. [The graphs are labeled (a), (b), (c), (d), (e), and (f).]**

(a)



(b)



(c)



(d)



(e)



(f)



5. $f(x) = \dfrac{2x^2}{x^2+2}$
6. $f(x) = \dfrac{2x}{\sqrt{x^2+2}}$
7. $f(x) = \dfrac{x}{x^2+2}$
8. $f(x) = 2 + \dfrac{x^2}{x^4+1}$
9. $f(x) = \dfrac{4\sin x}{x^2+1}$
10. $f(x) = \dfrac{2x^2-3x+5}{x^2+1}$

Finding Limits at Infinity **In Exercises 11 and 12, find $\lim_{x\to\infty} h(x)$, if it exists.**

11. $f(x) = 5x^3 - 3$
    (a) $h(x) = \dfrac{f(x)}{x^2}$
    (b) $h(x) = \dfrac{f(x)}{x^3}$
    (c) $h(x) = \dfrac{f(x)}{x^4}$
12. $f(x) = -4x^2 + 2x - 5$
    (a) $h(x) = \dfrac{f(x)}{x}$
    (b) $h(x) = \dfrac{f(x)}{x^2}$
    (c) $h(x) = \dfrac{f(x)}{x^3}$

Finding Limits at Infinity **In Exercises 13–16, find each limit, if it exists.**

13. (a) $\lim_{x\to\infty} \dfrac{x^2+2}{x^3-1}$
    (b) $\lim_{x\to\infty} \dfrac{x^2+2}{x^2-1}$
    (c) $\lim_{x\to\infty} \dfrac{x^2+2}{x-1}$
14. (a) $\lim_{x\to\infty} \dfrac{3-2x}{3x^3-1}$
    (b) $\lim_{x\to\infty} \dfrac{3-2x}{3x-1}$
    (c) $\lim_{x\to\infty} \dfrac{3-2x^2}{3x-1}$
15. (a) $\lim_{x\to\infty} \dfrac{5-2x^{3/2}}{3x^2-4}$
    (b) $\lim_{x\to\infty} \dfrac{5-2x^{3/2}}{3x^{3/2}-4}$
    (c) $\lim_{x\to\infty} \dfrac{5-2x^{3/2}}{3x-4}$
16. (a) $\lim_{x\to\infty} \dfrac{5x^{3/2}}{4x^2+1}$
    (b) $\lim_{x\to\infty} \dfrac{5x^{3/2}}{4x^{3/2}+1}$
    (c) $\lim_{x\to\infty} \dfrac{5x^{3/2}}{4\sqrt{x}+1}$

Finding a Limit **In Exercises 17–36, find the limit, if it exists.**

17. $\lim_{x\to\infty} \left(4 + \dfrac{3}{x}\right)$
18. $\lim_{x\to-\infty} \left(\dfrac{5}{x} - \dfrac{x}{3}\right)$
19. $\lim_{x\to\infty} \dfrac{7x+6}{9x-4}$
20. $\lim_{x\to-\infty} \dfrac{4x^2+5}{x^2+3}$
21. $\lim_{x\to-\infty} \dfrac{2x^2+x}{6x^3+2x^2+x}$
22. $\lim_{x\to\infty} \dfrac{5x^3+1}{10x^3-3x^2+7}$
23. $\lim_{x\to-\infty} \dfrac{5x^2}{x+3}$
24. $\lim_{x\to-\infty} \dfrac{x^3-4}{x^2+1}$
25. $\lim_{x\to-\infty} \dfrac{x}{\sqrt{x^2-x}}$
26. $\lim_{x\to-\infty} \dfrac{x}{\sqrt{x^2+1}}$
27. $\lim_{x\to-\infty} \dfrac{2x+1}{\sqrt{x^2-x}}$
28. $\lim_{x\to\infty} \dfrac{5x^2+2}{\sqrt{x^2+3}}$
29. $\lim_{x\to\infty} \dfrac{\sqrt{x^2-1}}{2x-1}$
30. $\lim_{x\to-\infty} \dfrac{\sqrt{x^4-1}}{x^3-1}$
31. $\lim_{x\to\infty} \dfrac{x+1}{(x^2+1)^{1/3}}$
32. $\lim_{x\to-\infty} \dfrac{2x}{(x^6-1)^{1/3}}$
33. $\lim_{x\to\infty} \dfrac{1}{2x+\sin x}$
34. $\lim_{x\to\infty} \cos\dfrac{1}{x}$
35. $\lim_{x\to\infty} \dfrac{\sin 2x}{x}$
36. $\lim_{x\to\infty} \dfrac{x-\cos x}{x}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding Horizontal Asymptotes Using Technology

In Exercises 37–40, use a graphing utility to graph the function and identify any horizontal asymptotes.

37. $f(x) = \dfrac{|x|}{x+1}$

38. $f(x) = \dfrac{|3x+2|}{x-2}$

39. $f(x) = \dfrac{3x}{\sqrt{x^2+2}}$

40. $f(x) = \dfrac{\sqrt{9x^2-2}}{2x+1}$

Finding a Limit

In Exercises 41 and 42, find the limit. (*Hint:* Let $x = 1/t$ and find the limit as $t \to 0^+$.)

41. $\lim_{x\to\infty} x \sin\dfrac{1}{x}$

42. $\lim_{x\to\infty} x \tan\dfrac{1}{x}$

Finding a Limit

In Exercises 43–46, find the limit. Use a graphing utility to verify your result. (*Hint*: Treat the expression as a fraction whose denominator is 1, and rationalize the numerator.)

43. $\lim_{x\to-\infty} \left(x + \sqrt{x^2+3}\right)$

44. $\lim_{x\to\infty} \left(x - \sqrt{x^2+x}\right)$

45. $\lim_{x\to-\infty} \left(3x + \sqrt{9x^2-x}\right)$

46. $\lim_{x\to\infty} \left(4x - \sqrt{16x^2-x}\right)$

Numerical, Graphical, and Analytic Analysis

In Exercises 47–50, use a graphing utility to complete the table and estimate the limit as x approaches infinity. Then use a graphing utility to graph the function and estimate the limit. Finally, find the limit analytically and compare your results with the estimates.

x	10^0	10^1	10^2	10^3	10^4	10^5	10^6
$f(x)$							

47. $f(x) = x - \sqrt{x(x-1)}$

48. $f(x) = x^2 - x\sqrt{x(x-1)}$

49. $f(x) = x \sin\dfrac{1}{2x}$

50. $f(x) = \dfrac{x+1}{x\sqrt{x}}$

51. Engine Efficiency

The efficiency (in percent) of an internal combustion engine is

$$\text{Efficiency} = 100\left[1 - \frac{1}{(v_1/v_2)^c}\right]$$

where v_1/v_2 is the ratio of the uncompressed gas to the compressed gas and c is a positive constant dependent on the engine design. Find the limit of the efficiency as the compression ratio approaches infinity.

Blanscape/Shutterstock.com

52. Physics Newton's First Law of Motion and Einstein's Special Theory of Relativity differ concerning the behavior of a particle as its velocity approaches the speed of light c. In the graph, functions N and E represent the velocity v, with respect to time t, of a particle accelerated by a constant force as predicted by Newton and Einstein, respectively. Write limit statements that describe these two theories.



Exploring Concepts

53. Explain the differences between limits at infinity and infinite limits.

54. Can the graph of a function cross a horizontal asymptote? Explain.

55. If f is a continuous function such that $\lim_{x\to\infty} f(x) = 5$, find, if possible, $\lim_{x\to-\infty} f(x)$ for each specified condition.

(a) The graph of f is symmetric with respect to the y-axis.

(b) The graph of f is symmetric with respect to the origin.

56. HOW DO YOU SEE IT? The graph shows the temperature T, in degrees Fahrenheit, of molten glass t seconds after it is removed from a kiln.



(a) Find $\lim_{t\to0^+} T$. What does this limit represent?

(b) Find $\lim_{t\to\infty} T$. What does this limit represent?

57. Modeling Data The average typing speeds S (in words per minute) of a typing student after t weeks of lessons are shown in the table.

t	5	10	15	20	25	30
S	28	56	79	90	93	94

A model for the data is $S = \dfrac{100t^2}{65+t^2}$, $t > 0$.

(a) Use a graphing utility to plot the data and graph the model.

(b) Does there appear to be a limiting typing speed? Explain.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

58. Modeling Data A heat probe is attached to the heat exchanger of a heating system. The temperature T (in degrees Celsius) is recorded t seconds after the furnace is started. The results for the first 2 minutes are recorded in the table.

t	0	15	30	45	60
T	25.2	36.9	45.5	51.4	56.0

t	75	90	105	120
T	59.6	62.0	64.0	65.2

(a) Use the regression capabilities of a graphing utility to find a model of the form $T_1 = at^2 + bt + c$ for the data.

(b) Use a graphing utility to graph T_1.

(c) A rational model for the data is

$$T_2 = \frac{1451 + 86t}{58 + t}.$$

Use a graphing utility to graph T_2.

(d) Find $\lim_{t\to\infty} T_2$.

(e) Interpret the result in part (d) in the context of the problem. Is it possible to do this type of analysis using T_1? Explain.

59. Using the Definition of Limits at Infinity The graph of

$$f(x) = \frac{2x^2}{x^2 + 2}$$

is shown (see figure).

(a) Find $L = \lim_{x\to\infty} f(x)$.

(b) Determine x_1 and x_2 in terms of ε.

(c) Determine M, where $M > 0$, such that $|f(x) - L| < \varepsilon$ for $x > M$.

(d) Determine N, where $N < 0$, such that $|f(x) - L| < \varepsilon$ for $x < N$.



Figure for 59



Figure for 60

60. Using the Definition of Limits at Infinity The graph of $f(x) = \dfrac{6x}{\sqrt{x^2 + 2}}$ is shown (see figure).

(a) Find $L = \lim_{x\to\infty} f(x)$ and $K = \lim_{x\to-\infty} f(x)$.

(b) Determine x_1 and x_2 in terms of ε.

(c) Determine M, where $M > 0$, such that $|f(x) - L| < \varepsilon$ for $x > M$.

(d) Determine N, where $N < 0$, such that $|f(x) - K| < \varepsilon$ for $x < N$.

61. Using the Definition of Limits at Infinity Consider

$$\lim_{x\to\infty} \frac{3x}{\sqrt{x^2 + 3}}.$$

(a) Use the definition of limits at infinity to find the value of M that corresponds to $\varepsilon = 0.5$.

(b) Use the definition of limits at infinity to find the value of M that corresponds to $\varepsilon = 0.1$.

62. Using the Definition of Limits at Infinity Consider

$$\lim_{x\to-\infty} \frac{3x}{\sqrt{x^2 + 3}}.$$

(a) Use the definition of limits at infinity to find the value of N that corresponds to $\varepsilon = 0.5$.

(b) Use the definition of limits at infinity to find the value of N that corresponds to $\varepsilon = 0.1$.

Proof **In Exercises 63–66, use the definition of limits at infinity to prove the limit.**

63. $\lim_{x\to\infty} \dfrac{1}{x^2} = 0$

64. $\lim_{x\to\infty} \dfrac{2}{\sqrt{x}} = 0$

65. $\lim_{x\to-\infty} \dfrac{1}{x^3} = 0$

66. $\lim_{x\to-\infty} \dfrac{1}{x - 2} = 0$

67. Distance A line with slope m passes through the point $(0, 4)$.

(a) Write the distance d between the line and the point $(3, 1)$ as a function of m. (*Hint:* See Section P.2, Exercise 77.)

(b) Use a graphing utility to graph the equation in part (a).

(c) Find $\lim_{m\to\infty} d(m)$ and $\lim_{m\to-\infty} d(m)$. Interpret the results geometrically.

68. Distance A line with slope m passes through the point $(0, -2)$.

(a) Write the distance d between the line and the point $(4, 2)$ as a function of m. (*Hint:* See Section P.2, Exercise 77.)

(b) Use a graphing utility to graph the equation in part (a).

(c) Find $\lim_{m\to\infty} d(m)$ and $\lim_{m\to-\infty} d(m)$. Interpret the results geometrically.

69. Proof Prove that if

$$p(x) = a_n x^n + \cdots + a_1 x + a_0$$

and

$$q(x) = b_m x^m + \cdots + b_1 x + b_0$$

where $a_n \neq 0$ and $b_m \neq 0$, then

$$\lim_{x\to\infty} \frac{p(x)}{q(x)} = \begin{cases} 0, & n < m \\ \dfrac{a_n}{b_m}, & n = m \\ \pm\infty, & n > m \end{cases}.$$

70. Proof Use the definition of infinite limits at infinity to prove that $\lim_{x\to\infty} x^3 = \infty$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

3.6 A Summary of Curve Sketching

GO DIGITAL

Analyze and sketch the graph of a function.

Analyzing the Graph of a Function

It would be difficult to overstate the importance of using graphs in mathematics. Descartes's introduction of analytic geometry contributed significantly to the rapid advances in calculus that began during the mid-seventeenth century. In the words of Lagrange, "As long as algebra and geometry traveled separate paths their advance was slow and their applications limited. But when these two sciences joined company, they drew from each other fresh vitality and thenceforth marched on at a rapid pace toward perfection."

So far, you have studied several concepts that are useful in analyzing the graph of a function.

- x-intercepts and y-intercepts (Section P.1)
- Symmetry (Section P.1)
- Domain and range (Section P.3)
- Continuity (Section 1.4)
- Vertical asymptotes (Section 1.5)
- Differentiability (Section 2.1)
- Relative extrema (Section 3.1)
- Increasing and decreasing functions (Section 3.3)
- Concavity (Section 3.4)
- Points of inflection (Section 3.4)
- Horizontal asymptotes (Section 3.5)
- Infinite limits at infinity (Section 3.5)



Different viewing windows for the graph of $f(x) = x^3 - 25x^2 + 74x - 20$

Figure 3.44

When you are graphing a function, either with or without a graphing utility, remember that normally you cannot show the *entire* graph. Deciding which part of the graph to show is often crucial. For instance, which of the viewing windows in Figure 3.44 better represents the graph of

$$f(x) = x^3 - 25x^2 + 74x - 20?$$

By seeing both views, it is clear that the second viewing window gives a more complete representation of the graph. But would a third viewing window reveal other interesting portions of the graph? To answer this, you need to use calculus to interpret the first and second derivatives. To determine a good viewing window for the graph of a function, use the guidelines below.

Guidelines for Analyzing the Graph of a Function

1. Determine the domain and range of the function.
2. Determine any intercepts, asymptotes, and symmetry of the graph.
3. Locate any x-values for which $f'(x)$ and $f''(x)$ either are zero or do not exist. Use the results to determine relative extrema and points of inflection.

In the guidelines above, note the importance of *algebra* (as well as calculus) for solving the equations $f(x) = 0$, $f'(x) = 0$, and $f''(x) = 0$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 1 Sketching the Graph of a Rational Function

Analyze and sketch the graph of

$$f(x) = \frac{2(x^2 - 9)}{x^2 - 4}.$$

Solution

Domain:	All real numbers except $x = \pm 2$
Range:	$(-\infty, 2) \cup \left[\frac{9}{2}, \infty\right)$
x-intercepts:	$(-3, 0), (3, 0)$
y-intercept:	$\left(0, \frac{9}{2}\right)$
Vertical asymptotes:	$x = -2, x = 2$
Horizontal asymptote:	$y = 2$
Symmetry:	With respect to y-axis
First derivative:	$f'(x) = \frac{20x}{(x^2 - 4)^2}$
Second derivative:	$f''(x) = \frac{-20(3x^2 + 4)}{(x^2 - 4)^3}$
Critical number:	$x = 0$
Possible points of inflection:	None
Test intervals:	$(-\infty, -2), (-2, 0), (0, 2), (2, \infty)$

The table shows how the test intervals are used to determine several characteristics of the graph. The graph of f is shown in Figure 3.45.



Using calculus, you can be certain that you have determined all characteristics of the graph of f.
Figure 3.45

	$f(x)$	$f'(x)$	$f''(x)$	Characteristic of Graph
$-\infty < x < -2$		$-$	$-$	Decreasing, concave downward
$x = -2$	Undef.	Undef.	Undef.	Vertical asymptote
$-2 < x < 0$		$-$	$+$	Decreasing, concave upward
$x = 0$	$\frac{9}{2}$	0	$+$	Relative minimum
$0 < x < 2$		$+$	$+$	Increasing, concave upward
$x = 2$	Undef.	Undef.	Undef.	Vertical asymptote
$2 < x < \infty$		$+$	$-$	Increasing, concave downward

FOR FURTHER INFORMATION
For more information on the use of technology to graph rational functions, see the article "Graphs of Rational Functions for Computer Assisted Calculus" by Stan Byrd and Terry Walters in *The College Mathematics Journal*. To view this article, go to *MathArticles.com*.

Be sure you understand all of the implications of creating a table such as that shown in Example 1. By using calculus, you can be *sure* that the graph has no relative extrema or points of inflection other than those shown in Figure 3.45.

TECHNOLOGY PITFALL Without using the type of analysis outlined in Example 1, it is easy to obtain an incomplete view of the basic characteristics of a graph. For instance, Figure 3.46 shows a view of the graph of

$$g(x) = \frac{2(x^2 - 9)(x - 20)}{(x^2 - 4)(x - 21)}.$$

From this view, it appears that the graph of g is about the same as the graph of f shown in Figure 3.45. The graphs of these two functions, however, differ significantly. Try adjusting the viewing window to see the differences.



By not using calculus, you may overlook important characteristics of the graph of g.
Figure 3.46

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 2 Sketching the Graph of a Rational Function

Analyze and sketch the graph of $f(x) = \dfrac{x^2 - 2x + 4}{x - 2}$.

Solution

Domain:	All real numbers except $x = 2$
Range:	$(-\infty, -2] \cup [6, \infty)$
x-intercepts:	None
y-intercept:	$(0, -2)$
Vertical asymptote:	$x = 2$
Horizontal asymptotes:	None
Symmetry:	None
End behavior:	$\lim_{x \to -\infty} f(x) = -\infty$, $\lim_{x \to \infty} f(x) = \infty$
First derivative:	$f'(x) = \dfrac{x(x - 4)}{(x - 2)^2}$
Second derivative:	$f''(x) = \dfrac{8}{(x - 2)^3}$
Critical numbers:	$x = 0, x = 4$
Possible points of inflection:	None
Test intervals:	$(-\infty, 0), (0, 2), (2, 4), (4, \infty)$



Figure 3.47

The analysis of the graph of f is shown in the table, and the graph is shown in Figure 3.47.

	$f(x)$	$f'(x)$	$f''(x)$	Characteristic of Graph
$-\infty < x < 0$		+	−	Increasing, concave downward
$x = 0$	-2	0	−	Relative maximum
$0 < x < 2$		−	−	Decreasing, concave downward
$x = 2$	Undef.	Undef.	Undef.	Vertical asymptote
$2 < x < 4$		−	+	Decreasing, concave upward
$x = 4$	6	0	+	Relative minimum
$4 < x < \infty$		+	+	Increasing, concave upward

Although the graph of the function in Example 2 has no horizontal asymptote, it does have a slant asymptote. The graph of a rational function (having no common factors and whose denominator is of degree 1 or greater) has a **slant asymptote** when the degree of the numerator exceeds the degree of the denominator by exactly 1. To find the slant asymptote, use long division to rewrite the rational function as the sum of a first-degree polynomial (the slant asymptote) and another rational function.

$$f(x) = \frac{x^2 - 2x + 4}{x - 2}$$ Write original function (see Example 2).

$$= x + \frac{4}{x - 2}$$ Rewrite using long division.



A slant asymptote

Figure 3.48

In Figure 3.48, note that the graph of f approaches the slant asymptote $y = x$ as x approaches $-\infty$ or ∞.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 3 A Function Involving a Radical

Analyze and sketch the graph of $f(x) = \dfrac{x}{\sqrt{x^2 + 2}}$.

Solution

$$f'(x) = \frac{2}{(x^2 + 2)^{3/2}}$$ Find first derivative.

$$f''(x) = -\frac{6x}{(x^2 + 2)^{5/2}}$$ Find second derivative.

The graph has only one intercept, $(0, 0)$. It has no vertical asymptotes, but it has two horizontal asymptotes: $y = 1$ (to the right) and $y = -1$ (to the left). The function has no critical numbers and one possible point of inflection (at $x = 0$). The domain of the function is all real numbers, and the graph is symmetric with respect to the origin. The analysis of the graph of f is shown in the table, and the graph is shown in Figure 3.49.



Figure 3.49

	$f(x)$	$f'(x)$	$f''(x)$	Characteristic of Graph
$-\infty < x < 0$		+	+	Increasing, concave upward
$x = 0$	0	+	0	Point of inflection
$0 < x < \infty$		+	−	Increasing, concave downward

EXAMPLE 4 A Function Involving Rational Exponents

Analyze and sketch the graph of $f(x) = 2x^{5/3} - 5x^{4/3}$.

Solution

$$f'(x) = \frac{10}{3}x^{1/3}(x^{1/3} - 2)$$ Find first derivative.

$$f''(x) = \frac{20(x^{1/3} - 1)}{9x^{2/3}}$$ Find second derivative.

The function has two intercepts: $(0, 0)$ and $\left(\frac{125}{8}, 0\right)$. There are no horizontal or vertical asymptotes. The function has two critical numbers ($x = 0$ and $x = 8$) and two possible points of inflection ($x = 0$ and $x = 1$). The domain is all real numbers. The analysis of the graph of f is shown in the table, and the graph is shown in Figure 3.50.



Figure 3.50

	$f(x)$	$f'(x)$	$f''(x)$	Characteristic of Graph
$-\infty < x < 0$		+	−	Increasing, concave downward
$x = 0$	0	0	Undef.	Relative maximum
$0 < x < 1$		−	−	Decreasing, concave downward
$x = 1$	−3	−	0	Point of inflection
$1 < x < 8$		−	+	Decreasing, concave upward
$x = 8$	−16	0	+	Relative minimum
$8 < x < \infty$		+	+	Increasing, concave upward

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 5 Sketching the Graph of a Polynomial Function

See LarsonCalculus.com for an interactive version of this type of example.

Analyze and sketch the graph of

$$f(x) = x^4 - 12x^3 + 48x^2 - 64x.$$

Solution Begin by factoring to obtain

$$f(x) = x(x^3 - 12x^2 + 48x - 64) \quad \text{Factor out common factor.}$$
$$= x(x - 4)^3. \quad \text{Factored form}$$

Then, use the factored form of $f(x)$ to perform the analysis below.

Domain:	All real numbers
Range:	$[-27, \infty)$
x-intercepts:	$(0, 0), (4, 0)$
y-intercept:	$(0, 0)$
Vertical asymptotes:	None
Horizontal asymptotes:	None
Symmetry:	None
End behavior:	$\lim_{x\to-\infty} f(x) = \infty, \lim_{x\to\infty} f(x) = \infty$
First derivative:	$f'(x) = 4(x - 1)(x - 4)^2$
Second derivative:	$f''(x) = 12(x - 4)(x - 2)$
Critical numbers:	$x = 1, x = 4$
Possible points of inflection:	$x = 2, x = 4$
Test intervals:	$(-\infty, 1), (1, 2), (2, 4), (4, \infty)$

The analysis of the graph of f is shown in the table, and the graph is shown in Figure 3.51(a). Use a graphing utility to check your work, as shown in Figure 3.51(b).

	$f(x)$	$f'(x)$	$f''(x)$	Characteristic of Graph
$-\infty < x < 1$		$-$	$+$	Decreasing, concave upward
$x = 1$	-27	0	$+$	Relative minimum
$1 < x < 2$		$+$	$+$	Increasing, concave upward
$x = 2$	-16	$+$	0	Point of inflection
$2 < x < 4$		$+$	$-$	Increasing, concave downward
$x = 4$	0	0	0	Point of inflection
$4 < x < \infty$		$+$	$+$	Increasing, concave upward



(a)
A polynomial function of even degree must have at least one relative extremum.



(b)
From the result shown by *Maple*, the sketch in Figure 3.51(a) appears to be correct.

Figure 3.51

The fourth-degree polynomial function in Example 5 has one relative minimum and no relative maxima. In general, a polynomial function of degree n can have *at most* $n - 1$ relative extrema and *at most* $n - 2$ points of inflection. Moreover, polynomial functions of even degree must have *at least* one relative extremum.

Remember from the Leading Coefficient Test described in Section P.3 that the "end behavior" of the graph of a polynomial function is determined by its leading coefficient and its degree. For instance, because the polynomial in Example 5 has a positive leading coefficient, the graph rises to the right. Moreover, because the degree is even, the graph also rises to the left.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 6 A Function Involving Sine and Cosine

Analyze and sketch the graph of $f(x) = (\cos x)/(1 + \sin x)$.

Solution Because the function has a period of 2π, you can restrict the analysis of the graph to any interval of length 2π. For convenience, choose $[-\pi/2, 3\pi/2]$.

Domain:	All real numbers except $x = \frac{3 + 4n}{2}\pi$
Range:	All real numbers
Period:	2π
x-intercept:	$\left(\frac{\pi}{2}, 0\right)$
y-intercept:	$(0, 1)$
Vertical asymptotes:	$x = -\frac{\pi}{2}, x = \frac{3\pi}{2}$
Horizontal asymptotes:	None
Symmetry:	None
First derivative:	$f'(x) = -\frac{1}{1 + \sin x}$
Second derivative:	$f''(x) = \frac{\cos x}{(1 + \sin x)^2}$
Critical numbers:	None
Possible point of inflection:	$x = \frac{\pi}{2}$
Test intervals:	$\left(-\frac{\pi}{2}, \frac{\pi}{2}\right), \left(\frac{\pi}{2}, \frac{3\pi}{2}\right)$

See Remark below.



Figure 3.52

The analysis of the graph of f on the interval $[-\pi/2, 3\pi/2]$ is shown in the table, and the graph is shown in Figure 3.52.

	$f(x)$	$f'(x)$	$f''(x)$	Characteristic of Graph
$x = -\frac{\pi}{2}$	Undef.	Undef.	Undef.	Vertical asymptote
$-\frac{\pi}{2} < x < \frac{\pi}{2}$		$-$	$+$	Decreasing, concave upward
$x = \frac{\pi}{2}$	0	$-$	0	Point of inflection
$\frac{\pi}{2} < x < \frac{3\pi}{2}$		$-$	$-$	Decreasing, concave downward
$x = \frac{3\pi}{2}$	Undef.	Undef.	Undef.	Vertical asymptote

REMARK In Example 6, substituting $-\pi/2$ or $3\pi/2$ into f yields the indeterminate form $0/0$, which you will study in Section 5.6. To determine that f has vertical asymptotes at these two values, rewrite f as

$$f(x) = \frac{\cos x}{1 + \sin x} = \frac{(\cos x)(1 - \sin x)}{(1 + \sin x)(1 - \sin x)} = \frac{(\cos x)(1 - \sin x)}{\cos^2 x} = \frac{1 - \sin x}{\cos x}.$$

Next, use Theorem 1.14 to conclude that the graph of f has vertical asymptotes at $x = -\pi/2$ and $3\pi/2$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

3.6 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain the guidelines for analyzing the graph of a function.
2. Explain how to create a table to determine characteristics of a graph. What elements are included?
3. Describe the type of function that can have a slant asymptote. Explain how to determine the equation of a slant asymptote.
4. A fifth-degree polynomial can have a maximum of how many relative extrema and points of inflection? Explain.

Matching **In Exercises 5–8, match the graph of the function with the graph of its derivative. [The graphs of the derivatives are labeled (a), (b), (c), and (d).]**

(a)



(b)



(c)



(d)



5.



6.



7.



8.



Analyzing the Graph of a Function **In Exercises 9–36, analyze and sketch a graph of the function. Label any intercepts, relative extrema, points of inflection, and asymptotes. Use a graphing utility to verify your results.**

9. $y = \frac{1}{x-2} - 3$
10. $y = \frac{x}{x^2+1}$
11. $y = \frac{x}{1-x}$
12. $y = \frac{x-4}{x-3}$
13. $y = \frac{x+1}{x^2-4}$
14. $y = \frac{2x}{9-x^2}$
15. $y = \frac{x^2}{x^2+3}$
16. $y = \frac{x^2+1}{x^2-4}$
17. $y = 3 + \frac{2}{x}$
18. $f(x) = \frac{x-3}{x}$
19. $f(x) = x + \frac{32}{x^2}$
20. $y = \frac{4}{x^2} + 1$
21. $y = \frac{3x}{x^2-1}$
22. $f(x) = \frac{x^3}{x^2-9}$
23. $y = \frac{x^2-6x+12}{x-4}$
24. $y = \frac{-x^2-4x-7}{x+3}$
25. $y = \frac{x^3}{\sqrt{x^2-4}}$
26. $y = \frac{x}{\sqrt{x^2-4}}$
27. $y = x\sqrt{4-x}$
28. $g(x) = x\sqrt{9-x^2}$
29. $y = 3x^{2/3} - 2x$
30. $y = (x+1)^2 - 3(x+1)^{2/3}$
31. $y = 2 - x - x^3$
32. $y = -\frac{1}{3}(x^3 - 3x + 2)$
33. $y = 3x^4 + 4x^3$
34. $y = -2x^4 + 3x^2$
35. $xy^2 = 9$
36. $x^2y = 9$

Analyzing the Graph of a Function **In Exercises 37–44, analyze and sketch a graph of the function over the given interval. Label any intercepts, relative extrema, points of inflection, and asymptotes. Use a graphing utility to verify your results.**

Function	Interval
37. $f(x) = 2x - 4\sin x$	$0 \le x \le 2\pi$
38. $f(x) = -x + 2\cos x$	$0 \le x \le 2\pi$
39. $y = \sin x - \frac{1}{18}\sin 3x$	$0 \le x \le 2\pi$
40. $y = 2(x-2) + \cot x$	$0 < x < \pi$
41. $y = 2(\csc x + \sec x)$	$0 < x < \frac{\pi}{2}$
42. $y = \sec^2\frac{\pi x}{8} - 2\tan\frac{\pi x}{8} - 1$	$-3 < x < 3$
43. $g(x) = x\tan x$	$-\frac{3\pi}{2} < x < \frac{3\pi}{2}$
44. $g(x) = x\cot x$	$-2\pi < x < 2\pi$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Analyzing the Graph of a Function Using Technology

In Exercises 45–50, use a computer algebra system to analyze and graph the function. Identify any relative extrema, points of inflection, and asymptotes.

45. $f(x) = \dfrac{20x}{x^2 + 1} - \dfrac{1}{x}$

46. $f(x) = x + \dfrac{4}{x^2 + 1}$

47. $f(x) = \dfrac{-2x}{\sqrt{x^2 + 7}}$

48. $f(x) = \dfrac{4x}{\sqrt{x^2 + 15}}$

49. $y = \cos x - \frac{1}{4}\cos 2x, \quad 0 \le x \le 2\pi$

50. $y = 2x - \tan x, \quad -\dfrac{\pi}{2} < x < \dfrac{\pi}{2}$

Identifying Graphs

In Exercises 51 and 52, the graphs of f' and f'' are shown on the same set of coordinate axes. Identify each graph, and then sketch the graph of f. Explain your reasoning. To print an enlarged copy of the graph, go to *MathGraphs.com*.

51.



52.



Graphical Reasoning

In Exercises 53–56, use the graph of f' to sketch a graph of f and the graph of f''. To print an enlarged copy of the graph, go to *MathGraphs.com*.

53.



54.



55.



56.



(Submitted by Bill Fox, Moberly Area Community College, Moberly, MO)

Graphical Reasoning

57. Consider the function

$$f(x) = \frac{\cos^2 \pi x}{\sqrt{x^2 + 1}}, \quad 0 < x < 4.$$

(a) Use a computer algebra system to graph the function and use the graph to approximate the critical numbers visually.

(b) Use a computer algebra system to find f' and approximate the critical numbers. Are the results the same as the visual approximation in part (a)? Explain.

Graphical Reasoning

58. Consider the function

$$f(x) = \tan(\sin \pi x).$$

(a) Use a graphing utility to graph the function.

(b) Identify any symmetry of the graph.

(c) Is the function periodic? If so, what is the period?

(d) Identify any extrema on $(-1, 1)$.

(e) Use a graphing utility to determine the concavity of the graph on $(0, 1)$.

Exploring Concepts

59. Sketch a graph of a differentiable function f that satisfies the following conditions and has $x = 2$ as its only critical number.

$f'(x) < 0$ for $x < 2$

$f'(x) > 0$ for $x > 2$

$\lim_{x \to -\infty} f(x) = 6$

$\lim_{x \to \infty} f(x) = 6$

60. Is it possible to sketch a graph of a function that satisfies the conditions of Exercise 59 and has *no* points of inflection? Explain.

61. Let $f'(t) < 0$ for all t in the interval $(2, 8)$. Explain why $f(3) > f(5)$.

62. Let $f(0) = 3$ and $2 \le f'(x) \le 4$ for all x in the interval $[-5, 5]$. Determine the greatest and least possible values of $f(2)$.

63. The graph of a function f is shown below. To print an enlarged copy of the graph, go to *MathGraphs.com*.



(a) Sketch f'.

(b) Use the graph to estimate $\lim_{x \to \infty} f(x)$ and $\lim_{x \to \infty} f'(x)$.

(c) Explain the answers you gave in part (b).

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

64. HOW DO YOU SEE IT? The graph of f is shown in the figure.



(a) For which values of x is $f'(x)$ zero? Positive? Negative? What do these values mean?

(b) For which values of x is $f''(x)$ zero? Positive? Negative? What do these values mean?

(c) On what open interval is f' an increasing function?

(d) For which value of x is $f'(x)$ minimum? For this value of x, how does the rate of change of f compare with the rates of change of f for other values of x? Explain.

Horizontal and Vertical Asymptotes **In Exercises 65–68, use a graphing utility to graph the function. Use the graph to determine whether it is possible for the graph of a function to cross its horizontal asymptote. Do you think it is possible for the graph of a function to cross its vertical asymptote? Why or why not?**

65. $f(x) = \dfrac{4(x-1)^2}{x^2-4x+5}$

66. $g(x) = \dfrac{3x^4-5x+3}{x^4+1}$

67. $h(x) = \dfrac{\sin 2x}{x}$

68. $f(x) = \dfrac{\cos 3x}{4x}$

Examining a Function **In Exercises 69 and 70, use a graphing utility to graph the function. Explain why there is no vertical asymptote when a superficial examination of the function may indicate that there should be one.**

69. $h(x) = \dfrac{6-2x}{3-x}$

70. $g(x) = \dfrac{x^2+x-2}{x-1}$

Slant Asymptote **In Exercises 71–76, use a graphing utility to graph the function and determine the slant asymptote of the graph analytically. Zoom out repeatedly and describe how the graph on the display appears to change. Why does this occur?**

71. $f(x) = -\dfrac{x^2-3x-1}{x-2}$

72. $g(x) = \dfrac{2x^2-8x-15}{x-5}$

73. $f(x) = \dfrac{2x^3}{x^2+1}$

74. $h(x) = \dfrac{-x^3+x^2+4}{x^2}$

75. $f(x) = \dfrac{x^3-3x^2+2}{x(x-3)}$

76. $f(x) = -\dfrac{x^3-2x^2+2}{2x^2}$

77. Investigation Let $P(x_0, y_0)$ be an arbitrary point on the graph of f that $f'(x_0) \neq 0$, as shown in the figure. Verify each statement.



(a) The x-intercept of the tangent line is

$$\left(x_0 - \frac{f(x_0)}{f'(x_0)}, 0\right).$$

(b) The y-intercept of the tangent line is

$$(0, f(x_0) - x_0 f'(x_0)).$$

(c) The x-intercept of the normal line is

$$(x_0 + f(x_0)f'(x_0), 0).$$

(The *normal line* at a point is perpendicular to the tangent line at the point.)

(d) The y-intercept of the normal line is

$$\left(0, y_0 + \frac{x_0}{f'(x_0)}\right).$$

(e) $|BC| = \left|\dfrac{f(x_0)}{f'(x_0)}\right|$

(f) $|PC| = \left|\dfrac{f(x_0)\sqrt{1+[f'(x_0)]^2}}{f'(x_0)}\right|$

(g) $|AB| = |f(x_0)f'(x_0)|$

(h) $|AP| = |f(x_0)|\sqrt{1+[f'(x_0)]^2}$

78. Graphical Reasoning Identify the real numbers x_0, x_1, x_2, x_3, and x_4 in the figure such that each of the following is true.



(a) $f'(x) = 0$

(b) $f''(x) = 0$

(c) $f'(x)$ does not exist.

(d) f has a relative maximum.

(e) f has a point of inflection.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Think About It **In Exercises 79–82, create a function whose graph has the given characteristics. (There is more than one correct answer.)**

79. Vertical asymptote: $x = 3$

Horizontal asymptote: $y = 0$

80. Vertical asymptote: $x = -5$

Horizontal asymptote: None

81. Vertical asymptote: $x = 3$

Slant asymptote: $y = 3x + 2$

82. Vertical asymptote: $x = 2$

Slant asymptote: $y = -x$

True or False? **In Exercises 83–86, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

83. If $f'(x) > 0$ for all real numbers x, then f increases without bound.

84. If $f''(x) < 0$ for all real numbers x, then f decreases without bound.

85. Every rational function has a slant asymptote.

86. Every polynomial function has an absolute maximum and an absolute minimum on $(-\infty, \infty)$.

87. Graphical Reasoning The graph of the first derivative of a function f on the interval $[-7, 5]$ is shown. Use the graph to answer each question.

(a) On what interval(s) is f decreasing?

(b) On what interval(s) is the graph of f concave downward?

(c) At what x-value(s) does f have relative extrema?

(d) At what x-value(s) does the graph of f have a point of inflection?



Figure for 87



Figure for 88

88. Graphical Reasoning The graph of the first derivative of a function f on the interval $[-4, 2]$ is shown. Use the graph to answer each question.

(a) On what interval(s) is f increasing?

(b) On what interval(s) is the graph of f concave upward?

(c) At what x-value(s) does f have relative extrema?

(d) At what x-value(s) does the graph of f have a point of inflection?

89. Graphical Reasoning Consider the function

$$f(x) = \frac{ax}{(x - b)^2}.$$

Determine the effect on the graph of f as a and b are changed. Consider cases where a and b are both positive or both negative and cases where a and b have opposite signs.

90. Graphical Reasoning Consider the function

$$f(x) = \frac{1}{2}(ax)^2 - ax, \quad a \neq 0.$$

(a) Determine the changes (if any) in the intercepts, extrema, and concavity of the graph of f when a is varied.

(b) In the same viewing window, use a graphing utility to graph the function for four different values of a.

Slant Asymptotes **In Exercises 91 and 92, the graph of the function has two slant asymptotes. Identify each slant asymptote. Then graph the function and its asymptotes.**

91. $y = \sqrt{4 + 16x^2}$ **92.** $y = \sqrt{x^2 + 6x}$

93. Investigation Consider the function

$$f(x) = \frac{2x^n}{x^4 + 1}$$

for nonnegative integer values of n.

(a) Discuss the relationship between the value of n and the symmetry of the graph.

(b) For which values of n will the x-axis be the horizontal asymptote?

(c) For which value of n will $y = 2$ be the horizontal asymptote?

(d) What is the asymptote of the graph when $n = 5$?

(e) Use a graphing utility to graph f for the indicated values of n in the table. Use the graph to determine the number of extrema M and the number of inflection points N of the graph.

n	0	1	2	3	4	5
M						
N						

PUTNAM EXAM CHALLENGE

94. Let $f(x)$ be defined for $a \leq x \leq b$. Assuming appropriate properties of continuity and derivability, prove for $a < x < b$ that

$$\frac{\dfrac{f(x) - f(a)}{x - a} - \dfrac{f(b) - f(a)}{b - a}}{x - b} = \frac{1}{2}f''(\varepsilon),$$

where ε is some number between a and b.

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

3.7 Optimization Problems

GO DIGITAL

Solve applied minimum and maximum problems.

Applied Minimum and Maximum Problems

One of the most common applications of calculus involves determining minimum and maximum values. Consider how frequently you hear or read terms such as greatest profit, least cost, least time, greatest voltage, optimum size, least size, greatest strength, and greatest distance. Before outlining a general problem-solving strategy for such problems, consider the next example.

EXAMPLE 1 Finding Maximum Volume

A manufacturer wants to design an open box having a square base and a surface area of 108 square inches, as shown in Figure 3.53. What dimensions will produce a box with maximum volume?



Open box with square base:
$S = x^2 + 4xh = 108$
Figure 3.53

Solution Because the box has a square base, its volume is

$$V = x^2h. \qquad \text{Primary equation}$$

This equation is called the **primary equation** because it gives a formula for the quantity to be optimized. Because V is to be maximized, you want to write V as a function of one variable. To do this, note that the surface area of the box is

$$S = (\text{area of base}) + (\text{area of four sides})$$
$$108 = x^2 + 4xh. \qquad \text{Secondary equation}$$

Next, solve this equation for h to obtain $h = (108 - x^2)/(4x)$. Substituting into the primary equation produces

$$V = x^2h \qquad \text{Function of two variables}$$
$$= x^2\left(\frac{108 - x^2}{4x}\right) \qquad \text{Substitute for } h.$$
$$= 27x - \frac{x^3}{4}. \qquad \text{Function of one variable}$$

Before finding which x-value will yield a maximum value of V, you should determine the *feasible domain*. That is, what values of x make sense in this problem? You know that $V \geq 0$. You also know that x must be nonnegative and that the area of the base $(A = x^2)$ is at most 108. So, the feasible domain is

$$0 \leq x \leq \sqrt{108}. \qquad \text{Feasible domain}$$

To maximize V, find its critical numbers on the interval $\left(0, \sqrt{108}\right)$.

$$\frac{dV}{dx} = 27 - \frac{3x^2}{4} \qquad \text{Differentiate with respect to } x.$$
$$27 - \frac{3x^2}{4} = 0 \qquad \text{Set derivative equal to 0.}$$
$$3x^2 = 108 \qquad \text{Simplify.}$$
$$x = \pm 6 \qquad \text{Critical numbers}$$

So, the critical numbers are $x = \pm 6$. You do not need to consider $x = -6$ because it is outside the domain. Evaluating V at the critical number $x = 6$ and at the endpoints of the domain produces $V(0) = 0$, $V(6) = 108$, and $V\left(\sqrt{108}\right) = 0$. So, V is maximum when $x = 6$, and the dimensions of the box are 6 inches by 6 inches by 3 inches. ■

TECHNOLOGY To check the solution to Example 1 on a graphing utility, graph the volume function

$$V = 27x - \frac{x^3}{4}.$$

Use a viewing window with $0 \leq x \leq \sqrt{108} \approx 10.4$ and $0 \leq y \leq 120$. Then use the *maximum* or *trace* feature to determine the x-value that produces a maximum volume.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

In Example 1, you should realize that there are infinitely many open boxes having 108 square inches of surface area. To begin solving the problem, you might ask yourself which basic shape would seem to yield a maximum volume. Should the box be tall, squat, or nearly cubical?

You might even try calculating a few volumes, as shown in Figure 3.54, to determine whether you can get a better feeling for what the optimum dimensions should be. Remember that you are not ready to begin solving a problem until you have clearly identified what the problem is.


Volume = $74\frac{1}{4}$
$3 \times 3 \times 8\frac{1}{4}$
Volume = 92
$4 \times 4 \times 5\frac{3}{4}$
Volume = $103\frac{3}{4}$
$5 \times 5 \times 4\frac{3}{20}$
Volume = 108
$6 \times 6 \times 3$
Volume = 88
$8 \times 8 \times 1\frac{3}{8}$

Which box has the greatest volume?

Figure 3.54

Example 1 illustrates the following guidelines for solving applied minimum and maximum problems.

Guidelines for Solving Applied Minimum and Maximum Problems

1. Identify all *given* quantities and all quantities *to be determined*. If possible, make a sketch.
2. Write a **primary equation** for the quantity that is to be maximized or minimized. (Several useful formulas from geometry are listed on the formula cards for this text.)
3. Reduce the primary equation to one having a *single independent variable*. This may involve the use of **secondary equations** relating the independent variables of the primary equation.
4. Determine the feasible domain of the primary equation. That is, determine the values for which the stated problem makes sense.
5. Determine the desired maximum or minimum value by the calculus techniques discussed in Sections 3.1 through 3.4.

REMARK For Step 5, recall that to determine the maximum or minimum value of a continuous function f on a closed interval, you should compare the values of f at its critical numbers with the values of f at the endpoints of the interval.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



The quantity to be minimized is distance: $d = \sqrt{(x - 0)^2 + (y - 2)^2}$.

Figure 3.55

EXAMPLE 2 Finding Minimum Distance

See LarsonCalculus.com for an interactive version of this type of example.

Which points on the graph of $y = 4 - x^2$ are closest to the point $(0, 2)$?

Solution Figure 3.55 shows that there are two points at a minimum distance from the point $(0, 2)$. The distance between the point $(0, 2)$ and a point (x, y) on the graph of $y = 4 - x^2$ is

$$d = \sqrt{(x - 0)^2 + (y - 2)^2}. \qquad \text{Primary equation}$$

Using the secondary equation $y = 4 - x^2$, rewrite the primary equation as

$$d = \sqrt{x^2 + (4 - x^2 - 2)^2} \qquad \text{Substitute } 4 - x^2 \text{ for } y.$$

$$= \sqrt{x^4 - 3x^2 + 4}. \qquad \text{Simplify.}$$

Because d is smallest when the expression inside the radical is smallest, you need only find the critical numbers of $f(x) = x^4 - 3x^2 + 4$. Note that the domain of f is the entire real number line. So, there are no endpoints of the domain to consider. Moreover, the derivative of f

$$f'(x) = 4x^3 - 6x \qquad \text{Differentiate with respect to } x.$$

$$= 2x(2x^2 - 3) \qquad \text{Factor.}$$

is zero when

$$x = 0, \quad \sqrt{\frac{3}{2}}, \quad \text{and} \quad -\sqrt{\frac{3}{2}}. \qquad \text{Zeros of } f'$$

Testing these critical numbers using the First Derivative Test verifies that $x = 0$ yields a relative maximum, whereas both $x = \sqrt{3/2}$ and $x = -\sqrt{3/2}$ yield a minimum distance. So, the closest points are $\left(\sqrt{3/2}, 5/2\right)$ and $\left(-\sqrt{3/2}, 5/2\right)$.



The quantity to be minimized is area: $A = (x + 3)(y + 2)$.

Figure 3.56

EXAMPLE 3 Finding Minimum Area

A rectangular page is to contain 24 square inches of print. The margins at the top and bottom of the page are to be $1\frac{1}{2}$ inches, and the margins on the left and right are to be 1 inch (see Figure 3.56). What should the dimensions of the page be so that the least amount of paper is used?

Solution Let A be the area to be minimized.

$$A = (x + 3)(y + 2) \qquad \text{Primary equation}$$

The printed area inside the margins is

$$24 = xy. \qquad \text{Secondary equation}$$

Solving this equation for y produces $y = 24/x$. Substituting $24/x$ for y in the primary equation produces

$$A = (x + 3)\left(\frac{24}{x} + 2\right) = 30 + 2x + \frac{72}{x}. \qquad \text{Function of one variable}$$

Because x must be positive, you are interested only in values of A for $x > 0$. To find the critical numbers, differentiate with respect to x

$$\frac{dA}{dx} = 2 - \frac{72}{x^2} \qquad \text{Differentiate with respect to } x.$$

and note that the derivative is zero when $x^2 = 36$, or $x = \pm 6$. So, the critical numbers are $x = \pm 6$. You do not have to consider $x = -6$ because it is outside the domain. The First Derivative Test confirms that A is a minimum when $x = 6$. So, $y = \frac{24}{6} = 4$ and the dimensions of the page should be $x + 3 = 9$ inches by $y + 2 = 6$ inches. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 4 Finding Minimum Length

Two posts, one 12 feet high and the other 28 feet high, stand 30 feet apart. They are to be stayed by two wires, attached to a single stake, running from ground level to the top of each post. Where should the stake be placed to use the least amount of wire?

Solution Let W be the wire length to be minimized. Using Figure 3.57, you can write

$$W = y + z. \qquad \text{Primary equation}$$

In this problem, rather than solving for y in terms of z (or vice versa), you can solve for both y and z in terms of a third variable x, as shown in Figure 3.57. From the Pythagorean Theorem, you obtain

$$x^2 + 12^2 = y^2$$
$$(30 - x)^2 + 28^2 = z^2$$

which implies that

$$y = \sqrt{x^2 + 144}$$
$$z = \sqrt{x^2 - 60x + 1684}.$$



The quantity to be minimized is length. From the diagram, you can see that x varies between 0 and 30.

Figure 3.57

So, you can rewrite the primary equation as

$$W = y + z$$
$$= \sqrt{x^2 + 144} + \sqrt{x^2 - 60x + 1684}, \quad 0 \le x \le 30.$$

Differentiating W with respect to x yields

$$\frac{dW}{dx} = \frac{x}{\sqrt{x^2 + 144}} + \frac{x - 30}{\sqrt{x^2 - 60x + 1684}}.$$

By letting $dW/dx = 0$, you obtain

$$\frac{x}{\sqrt{x^2 + 144}} + \frac{x - 30}{\sqrt{x^2 - 60x + 1684}} = 0$$
$$\frac{x}{\sqrt{x^2 + 144}} = \frac{30 - x}{\sqrt{x^2 - 60x + 1684}}$$
$$x\sqrt{x^2 - 60x + 1684} = (30 - x)\sqrt{x^2 + 144}$$
$$x^2(x^2 - 60x + 1684) = (30 - x)^2(x^2 + 144)$$
$$x^4 - 60x^3 + 1684x^2 = x^4 - 60x^3 + 1044x^2 - 8640x + 129{,}600$$
$$640x^2 + 8640x - 129{,}600 = 0$$
$$320(x - 9)(2x + 45) = 0$$
$$x = 9, -22.5.$$

Because $x = -22.5$ is not in the domain and

$$W(0) \approx 53.04, \quad W(9) = 50, \quad \text{and} \quad W(30) \approx 60.31$$

you can conclude that the wires should be staked at 9 feet from the 12-foot pole. ■



Figure 3.58

TECHNOLOGY From Example 4, you can see that applied optimization problems can involve a lot of algebra. Use a graphing utility to support the conclusion that $x = 9$ yields a minimum value of W by graphing

$$W = \sqrt{x^2 + 144} + \sqrt{x^2 - 60x + 1684}$$

as shown in Figure 3.58.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

In each of the first four examples, the extreme value occurred at a critical number. Although this happens often, remember that an extreme value can also occur at an endpoint of an interval, as shown in Example 5.

EXAMPLE 5 An Endpoint Maximum

Four feet of wire is to be used to form a square and a circle. How much of the wire should be used for the square and how much should be used for the circle to enclose the maximum total area?



The quantity to be maximized is area: $A = x^2 + \pi r^2$.

Figure 3.59

Solution The total area (see Figure 3.59) is

$$A = (\text{area of square}) + (\text{area of circle})$$

$$A = x^2 + \pi r^2. \qquad \text{Primary equation}$$

Because the total length of wire is 4 feet, you obtain

$$4 = (\text{perimeter of square}) + (\text{circumference of circle})$$

$$4 = 4x + 2\pi r. \qquad \text{Secondary equation}$$

So, $r = 2(1 - x)/\pi$, and by substituting into the primary equation you have

$$A = x^2 + \pi\left[\frac{2(1 - x)}{\pi}\right]^2$$

$$= x^2 + \frac{4(1 - x)^2}{\pi}$$

$$= \frac{1}{\pi}(\pi x^2 + 4 - 8x + 4x^2)$$

$$= \frac{1}{\pi}[(\pi + 4)x^2 - 8x + 4].$$

The feasible domain is $0 \le x \le 1$, restricted by the square's perimeter. Because

$$\frac{dA}{dx} = \frac{2(\pi + 4)x - 8}{\pi}$$

the only critical number in $(0, 1)$ is $x = 4/(\pi + 4) \approx 0.56$. So, using

$$A(0) \approx 1.27, \quad A(0.56) \approx 0.56, \quad \text{and} \quad A(1) = 1$$

you can conclude that the maximum area occurs when $x = 0$. That is, *all* the wire is used for the circle. ■

Exploration

What would the answer be if Example 5 asked for the dimensions needed to enclose the *minimum* total area?

Before doing the section exercises, review the primary equations developed in Examples 1–5. The applications in these five examples are fairly simple, and yet the resulting primary equations are quite complicated.

$$V = 27x - \frac{x^3}{4} \qquad \text{Example 1}$$

$$d = \sqrt{x^4 - 3x^2 + 4} \qquad \text{Example 2}$$

$$A = 30 + 2x + \frac{72}{x} \qquad \text{Example 3}$$

$$W = \sqrt{x^2 + 144} + \sqrt{x^2 - 60x + 1684} \qquad \text{Example 4}$$

$$A = \frac{1}{\pi}[(\pi + 4)x^2 - 8x + 4] \qquad \text{Example 5}$$

You must expect that real-life applications often involve equations that are *at least as complicated* as these five. Remember that one of the main goals of this course is to learn to use calculus to analyze equations that initially seem formidable.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

3.7 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Define *primary equation*, *secondary equation*, and *feasible domain*.
2. Describe the guidelines for solving applied minimum and maximum problems.

3. Numerical, Graphical, and Analytic Analysis Use the steps below to find two positive numbers whose sum is 110 and whose product is a maximum.

(a) Analytically complete six rows of a table such as the one below. (The first two rows are shown.) Use the table to guess the maximum product.

First Number, x	Second Number	Product, P
10	$110 - 10$	$10(110 - 10) = 1000$
20	$110 - 20$	$20(110 - 20) = 1800$

(b) Write the product P as a function of x.

(c) Use calculus to find the critical number of the function in part (b). Then find the first and second numbers.

(d) Use a graphing utility to graph the function in part (b) and verify the solution from the graph.

4. Numerical, Graphical, and Analytic Analysis An open box of maximum volume is to be made from a square piece of material, 24 inches on a side, by cutting equal squares from the corners and turning up the sides (see figure).



(a) Analytically complete six rows of a table such as the one below. (The first two rows are shown.) Use the table to guess the maximum volume.

Height, x	Length and Width	Volume, V
1	$24 - 2(1)$	$1[24 - 2(1)]^2 = 484$
2	$24 - 2(2)$	$2[24 - 2(2)]^2 = 800$

(b) Write the volume V as a function of x.

(c) Use calculus to find the critical number of the function in part (b). Then find the maximum volume.

(d) Use a graphing utility to graph the function in part (b) and verify the maximum volume from the graph.

Finding Numbers **In Exercises 5–10, find two positive numbers that satisfy the given requirements.**

5. The sum is S and the product is a maximum.
6. The product is 185 and the sum is a minimum.
7. The product is 147 and the sum of the first number plus three times the second number is a minimum.
8. The sum of the first number squared and the second number is 54 and the product is a maximum.
9. The sum of the first number and twice the second number is 108 and the product is a maximum.
10. The sum of the first number cubed and the second number is 500 and the product is a maximum.

Maximum Area **In Exercises 11 and 12, find the length and width of a rectangle that has the given perimeter and a maximum area.**

11. Perimeter: 80 meters
12. Perimeter: P units

Minimum Perimeter **In Exercises 13 and 14, find the length and width of a rectangle that has the given area and a minimum perimeter.**

13. Area: 49 square feet
14. Area: A square centimeters

Minimum Distance **In Exercises 15–18, find the points on the graph of the function that are closest to the given point.**

15. $y = x^2$, $(0, 3)$
16. $y = x^2 - 2$, $(0, -1)$
17. $f(x) = \sqrt{x}$, $(4, 0)$
18. $f(x) = \sqrt{x - 8}$, $(12, 0)$

19. **Minimum Area** A rectangular poster is to contain 648 square inches of print. The margins at the top and bottom of the poster are to be 2 inches, and the margins on the left and right are to be 1 inch. What should the dimensions of the poster be so that the least amount of poster is used?
20. **Minimum Area** A rectangular page is to contain 36 square inches of print. The margins on each side are to be $1\frac{1}{2}$ inches. Find the dimensions of the page such that the least amount of paper is used.
21. **Minimum Length** A farmer plans to fence a rectangular pasture adjacent to a river (see figure). The pasture must contain 405,000 square meters in order to provide enough grass for the herd. No fencing is needed along the river. What dimensions will require the least amount of fencing?



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

22. Maximum Volume A rectangular solid (with a square base) has a surface area of 337.5 square centimeters. Find the dimensions that will result in a solid with maximum volume.

23. Maximum Area A Norman window is constructed by adjoining a semicircle to the top of an ordinary rectangular window (see figure). Find the dimensions of a Norman window of maximum area when the total perimeter is 16 feet.



24. Maximum Area A rectangle is bounded by the x- and y-axes and the graph of $y = (6 - x)/2$ (see figure). What length and width should the rectangle have so that its area is a maximum?



Figure for 24



Figure for 25

25. Minimum Length and Minimum Area A right triangle is formed in the first quadrant by the x- and y-axes and a line through the point $(1, 2)$ (see figure).

(a) Write the length L of the hypotenuse as a function of x.

(b) Use a graphing utility to approximate x graphically such that the length of the hypotenuse is a minimum.

(c) Find the vertices of the triangle such that its area is a minimum.

26. Maximum Area Find the area of the largest isosceles triangle that can be inscribed in a circle of radius 6 (see figure).

(a) Solve by writing the area as a function of h.

(b) Solve by writing the area as a function of α.

(c) Identify the type of triangle of maximum area.



Figure for 26



Figure for 27

27. Maximum Area A rectangle is bounded by the x-axis and the semicircle

$$y = \sqrt{25 - x^2}$$

(see figure). What length and width should the rectangle have so that its area is a maximum?

28. Maximum Area Find the dimensions of the largest rectangle that can be inscribed in a semicircle of radius r (see Exercise 27).

29. Numerical, Graphical, and Analytic Analysis An exercise room consists of a rectangle with a semicircle on each end. A 200-meter running track runs around the outside of the room.

(a) Draw a figure to represent the problem. Let x and y represent the length and width of the rectangle, respectively.

(b) Analytically complete six rows of a table such as the one below. (The first two rows are shown.) Use the table to guess the maximum area of the rectangular region.

Length, x	Width, y	Area, xy
10	$\frac{2}{\pi}(100 - 10)$	$(10)\frac{2}{\pi}(100 - 10) \approx 573$
20	$\frac{2}{\pi}(100 - 20)$	$(20)\frac{2}{\pi}(100 - 20) \approx 1019$

(c) Write the area A of the rectangular region as a function of x.

(d) Use calculus to find the critical number of the function in part (c). Then find the maximum area and the dimensions that yield the maximum area.

(e) Use a graphing utility to graph the function in part (c) and verify the maximum area from the graph.

30. Numerical, Graphical, and Analytic Analysis A right circular cylinder is designed to hold 22 cubic inches of a soft drink (approximately 12 fluid ounces).

(a) Analytically complete six rows of a table such as the one below. (The first two rows are shown.)

Radius, r	Height, h	Surface Area, S
0.2	$\frac{22}{\pi(0.2)^2}$	$2\pi(0.2)\left[0.2 + \frac{22}{\pi(0.2)^2}\right] \approx 220.3$
0.4	$\frac{22}{\pi(0.4)^2}$	$2\pi(0.4)\left[0.4 + \frac{22}{\pi(0.4)^2}\right] \approx 111.0$

(b) Use a graphing utility to generate additional rows of the table. Use the table to estimate the minimum surface area.

(c) Write the surface area S as a function of r.

(d) Use calculus to find the critical number of the function in part (c). Then find the minimum surface area and the dimensions that yield the minimum surface area.

(e) Use a graphing utility to graph the function in part (c) and verify the minimum surface area from the graph.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploring Concepts

31. A shampoo bottle is a right circular cylinder. Because the surface area of the bottle does not change when it is squeezed, is it true that the volume remains the same? Explain.

32. The perimeter of a rectangle is 20 feet. Of all possible dimensions, the maximum area is 25 square feet when its length and width are both 5 feet. Are there dimensions that yield a minimum area? Explain.

33. Minimum Surface Area A solid is formed by adjoining two hemispheres to the ends of a right circular cylinder. The total volume of the solid is 14 cubic centimeters. Find the radius of the cylinder that produces the minimum surface area.

34. Minimum Cost An industrial tank of the shape described in Exercise 33 must have a volume of 4000 cubic feet. The hemispherical ends cost twice as much per square foot of surface area as the sides. Find the dimensions that will minimize cost.

35. Minimum Area The sum of the perimeters of an equilateral triangle and a square is 10. Find the dimensions of the triangle and the square that produce a minimum total area.

36. Maximum Area Twenty feet of wire is to be used to form two figures. In each of the following cases, how much wire should be used for each figure so that the total enclosed area is maximum?

(a) Equilateral triangle and square

(b) Square and regular pentagon

(c) Regular pentagon and regular hexagon

(d) Regular hexagon and circle

What can you conclude from this pattern? {*Hint:* The area of a regular polygon with n sides of length x is $A = (n/4)[\cot(\pi/n)]x^2$.}

37. Beam Strength A wooden beam has a rectangular cross section of height h and width w (see figure). The strength S of the beam is directly proportional to the width and the square of the height. What are the dimensions of the strongest beam that can be cut from a round log of diameter 20 inches? (*Hint:* $S = kh^2w$, where k is the proportionality constant.)



Figure for 37



Figure for 38

38. Minimum Length Two factories are located at the coordinates $(-x, 0)$ and $(x, 0)$, and their power supply is at $(0, h)$, as shown in the figure. Find y such that the total length of power line from the power supply to the factories is a minimum.

39. Maximum Perimeter Consider an isosceles triangle inscribed in a circle of radius 2, as shown in the figure. Find the value of the largest possible perimeter of the triangle.



Figure for 39



Figure for 40

40. Minimum Area Consider the tangent line L at $(2, 12)$ to the parabola $y = 16 - x^2$ (see figure). Find the area of the triangle in the first quadrant determined by the intersection of L with the x- and y-axes. Then find the point on the parabola for which the tangent line determines the triangle of least area.

41. Minimum Cost

An offshore oil well is 2 kilometers off the coast. The refinery is 4 kilometers down the coast. Laying pipe in the ocean is twice as expensive as laying it on land. What path should the pipe follow in order to minimize the cost?

42. Illumination A light source is located over the center of a circular table of diameter 4 feet (see figure). Find the height h of the light source such that the illumination I at the perimeter of the table is maximum when

$$I = \frac{k \sin \alpha}{s^2}$$

where s is the slant height, α is the angle at which the light strikes the table, and k is a constant.



Figure for 42



Figure for 43

43. Minimum Time A tour guide is in a boat 2 miles from the nearest point on the coast and is traveling to a point Q, located 3 miles down the coast and 1 mile inland (see figure). The tour guide can row at 2 miles per hour and walk at 4 miles per hour. Toward what point on the coast should the tour guide row in order to reach point Q in the least time?

landbysea/Getty Images

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

44. Minimum Time The conditions are the same as in Exercise 43 except that the tour guide can row at v_1 miles per hour and walk at v_2 miles per hour. If θ_1 and θ_2 are the magnitudes of the angles, show that the tour guide will reach point Q in the least time when

$$\frac{\sin\theta_1}{v_1} = \frac{\sin\theta_2}{v_2}.$$

45. Minimum Distance Sketch the graph of

$$f(x) = 2 - 2\sin x$$

on the interval $[0, \pi/2]$.

(a) Find the distance from the origin to the y-intercept and the distance from the origin to the x-intercept.

(b) Write the distance d from the origin to a point on the graph of f as a function of x.

(c) Use calculus to find the value of x that minimizes the function d on the interval $[0, \pi/2]$. What is the minimum distance? Use a graphing utility to verify your results.

(Submitted by Tim Chapell, Penn Valley Community College, Kansas City, MO)

46. Minimum Time When light waves traveling in a transparent medium strike the surface of a second transparent medium, they change direction. This change of direction is called *refraction* and is defined by **Snell's Law of Refraction,**

$$\frac{\sin\theta_1}{v_1} = \frac{\sin\theta_2}{v_2}$$

where θ_1 and θ_2 are the magnitudes of the angles shown in the figure and v_1 and v_2 are the velocities of light in the two media. Show that this problem is equivalent to that in Exercise 44 and that light waves traveling from P to Q follow the path of minimum time.



47. Maximum Volume A sector with central angle θ is cut from a circle of radius 12 inches (see figure), and the edges of the sector are brought together to form a cone. Find the magnitude of θ such that the volume of the cone is a maximum.



Figure for 47



Figure for 48

48. Numerical, Graphical, and Analytic Analysis The cross sections of an irrigation canal are isosceles trapezoids of which three sides are 8 feet long (see figure). Determine the angle of elevation θ of the sides such that the area of the cross sections is a maximum by completing the following.

(a) Analytically complete six rows of a table such as the one below. (The first two rows are shown.)

θ	Base 1	Base 2	Altitude	Area
10°	8	$8 + 16\cos 10°$	$8\sin 10°$	≈ 22.1
20°	8	$8 + 16\cos 20°$	$8\sin 20°$	≈ 42.5

(b) Use a graphing utility to generate additional rows of the table. Use the table to estimate the maximum cross-sectional area.

(c) Write the cross-sectional area A as a function of θ.

(d) Use calculus to find the critical number of the function in part (c). Then find the angle that will yield the maximum cross-sectional area. What is the maximum area?

(e) Use a graphing utility to graph the function in part (c) and verify the maximum cross-sectional area.

49. Maximum Profit Assume that the amount of money deposited in a bank is proportional to the square of the interest rate the bank pays on this money. Furthermore, the bank can reinvest this money at 8%. Find the interest rate the bank should pay to maximize profit. (Use the simple interest formula.)

50. HOW DO YOU SEE IT? The graph shows the profit P (in thousands of dollars) of a company in terms of its advertising cost x (in thousands of dollars).



(a) Estimate the interval on which the profit is increasing.

(b) Estimate the interval on which the profit is decreasing.

(c) Estimate the amount of money the company should spend on advertising in order to yield a maximum profit.

(d) The *point of diminishing returns* is the point at which the rate of growth of the profit function begins to decline. Estimate the point of diminishing returns.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Minimum Distance **In Exercises 51–53, consider a fuel distribution center located at the origin of the rectangular coordinate system (units in miles; see figures). The center supplies three factories with coordinates (4, 1), (5, 6), and (10, 3). A trunk line will run from the distribution center along the line $y = mx$, and feeder lines will run to the three factories. The objective is to find m such that the lengths of the feeder lines are minimized.**

51. Minimize the sum of the squares of the lengths of the vertical feeder lines (see figure) given by

$$S_1 = (4m - 1)^2 + (5m - 6)^2 + (10m - 3)^2.$$

Find the equation of the trunk line by this method and then determine the sum of the lengths of the feeder lines.

52. Minimize the sum of the absolute values of the lengths of the vertical feeder lines (see figure) given by

$$S_2 = |4m - 1| + |5m - 6| + |10m - 3|.$$

Find the equation of the trunk line by this method and then determine the sum of the lengths of the feeder lines. (*Hint:* Use a graphing utility to graph the function S_2 and approximate the required critical number.)



Figure for 51 and 52



Figure for 53

53. Minimize the sum of the lengths of the perpendicular feeder lines (see figure above and Exercise 77 in Section P.2) from the trunk line to the factories given by

$$S_3 = \frac{|4m - 1|}{\sqrt{m^2 + 1}} + \frac{|5m - 6|}{\sqrt{m^2 + 1}} + \frac{|10m - 3|}{\sqrt{m^2 + 1}}.$$

Find the equation of the trunk line by this method and then determine the sum of the lengths of the feeder lines. (*Hint:* Use a graphing utility to graph the function S_3 and approximate the required critical number.)

54. Maximum Area Consider a symmetric cross inscribed in a circle of radius r (see figure).



(a) Write the area A of the cross as a function of x and find the value of x that maximizes the area.

(b) Write the area A of the cross as a function of θ and find the value of θ that maximizes the area.

(c) Show that the critical numbers of parts (a) and (b) yield the same maximum area. What is that area?

55. Minimum Distance Find the point on the graph of the equation

$$16x = y^2$$

that is closest to the point (6, 0).

56. Minimum Distance Find the point on the graph of the function

$$x = \sqrt{10y}$$

that is closest to the point (0, 4). (*Hint:* Consider the domain of the function.)

PUTNAM EXAM CHALLENGE

57. Find, with explanation, the maximum value of $f(x) = x^3 - 3x$ on the set of all real numbers x satisfying $x^4 + 36 \leq 13x^2$.

58. Find the minimum value of

$$\frac{(x + 1/x)^6 - (x^6 + 1/x^6) - 2}{(x + 1/x)^3 + (x^3 + 1/x^3)} \quad \text{for} \quad x > 0.$$

These problems were composed by the Committee on the Putnam Prize Competition. © The Mathematical Association of America. All rights reserved.

SECTION PROJECT

Minimum Time

A person is at point A on the shore of a circular lake of radius 2 kilometers (see figure). They must walk around the lake to point B and then swim to point C in the least amount of time. Point C lies on the diameter through point A. Assume that the person can walk at v_1 kilometers per hour and swim at v_2 kilometers per hour, and that $0 \leq \theta \leq \pi$.



(a) Find the distance walked from point A to point B in terms of θ.

(b) Find the distance swam from point B to point C in terms of θ.

(c) Write the function $f(\theta)$ that represents the total time to move from point A to point C.

(d) Find $f'(\theta)$.

(e) If $v_1 = 5$ and $v_2 = 2$, approximate the critical number(s) of f. Does the critical number(s) correspond to a relative maximum or a relative minimum? Where should point B be located in order to minimize the time to get from point A to point C? Explain.

(f) Repeat part (e) for $v_1 = 3$ and $v_2 = 2$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

3.8 Newton's Method

GO DIGITAL

Approximate a zero of a function using Newton's Method.

Newton's Method

In this section, you will study a technique for approximating the real zeros of a function. The technique is called **Newton's Method,** and it uses tangent lines to approximate the graph of the function near its x-intercepts.

To see how Newton's Method works, consider a function f that is continuous on the interval $[a, b]$ and differentiable on the interval (a, b). If $f(a)$ and $f(b)$ differ in sign, then, by the Intermediate Value Theorem, f must have at least one zero in the interval (a, b). To estimate this zero, choose

$$x = x_1 \qquad \text{First estimate}$$

as shown in Figure 3.60(a). Newton's Method is based on the assumption that the graph of f and the tangent line at $(x_1, f(x_1))$ both cross the x-axis at *about* the same point. Because you can calculate the x-intercept for this tangent line, use it as a second (and, usually, better) estimate of the zero of f. The tangent line passes through the point $(x_1, f(x_1))$ with a slope of $f'(x_1)$. In point-slope form, the equation of the tangent line is

$$y - f(x_1) = f'(x_1)(x - x_1) \qquad \text{Point-slope form}$$
$$y = f'(x_1)(x - x_1) + f(x_1). \qquad \text{Isolate } y.$$

Letting $y = 0$ and solving for x produces

$$f'(x_1)(x - x_1) + f(x_1) = 0 \quad \Rightarrow \quad x - x_1 = -\frac{f(x_1)}{f'(x_1)} \quad \Rightarrow \quad x = x_1 - \frac{f(x_1)}{f'(x_1)}.$$

So, from the initial estimate x_1, calculate a second estimate of the actual zero.

$$x_2 = x_1 - \frac{f(x_1)}{f'(x_1)} \qquad \text{Second estimate [See Figure 3.60(a).]}$$

To obtain a better approximation, use x_2 to calculate a third estimate.

$$x_3 = x_2 - \frac{f(x_2)}{f'(x_2)} \qquad \text{Third estimate [See Figure 3.60(b).]}$$

Repeated application of this process is called Newton's Method.



(a)



(b)

The x-intercept of the tangent line approximates the zero of f.

Figure 3.60

NEWTON'S METHOD

Isaac Newton first described the method for approximating the real zeros of a function in his text *Method of Fluxions*. Although the book was written in 1671, it was not published until 1736. Meanwhile, in 1690, Joseph Raphson (1648–1715) published a paper describing a method for approximating the real zeros of a function that was very similar to Newton's. For this reason, the method is often referred to as the Newton-Raphson method.

Newton's Method for Approximating the Zeros of a Function

Let $f(c) = 0$, where f is differentiable on an open interval containing c. Then, to approximate c, use these steps.

1. Make an initial estimate x_1 that is close to c. (A graph is helpful.)
2. Determine a new approximation using the iterative formula

$$x_{n+1} = x_n - \frac{f(x_n)}{f'(x_n)}. \qquad \text{Iterative formula}$$

3. When $|x_n - x_{n+1}|$ is within the desired accuracy, let x_{n+1} serve as the final approximation. Otherwise, return to Step 2 and calculate a new approximation.

Each successive application of this procedure is called an **iteration.**

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

For many functions, just a few iterations of Newton's Method will produce approximations having very small errors, as shown in Example 1.

EXAMPLE 1 Using Newton's Method

Calculate three iterations of Newton's Method to approximate a zero of $f(x) = x^2 - 2$. Use $x_1 = 1$ as the initial guess.

Solution Because $f(x) = x^2 - 2$, you have $f'(x) = 2x$, and the iterative formula is

$$x_{n+1} = x_n - \frac{f(x_n)}{f'(x_n)} = x_n - \frac{x_n^2 - 2}{2x_n}.$$

The calculations for three iterations are shown in the table. The first iteration of this process is shown in Figure 3.61.



The first iteration of Newton's Method
Figure 3.61

n	x_n	$f(x_n)$	$f'(x_n)$	$\frac{f(x_n)}{f'(x_n)}$	$x_n - \frac{f(x_n)}{f'(x_n)}$
1	1.000000	−1.000000	2.000000	−0.500000	1.500000
2	1.500000	0.250000	3.000000	0.083333	1.416667
3	1.416667	0.006945	2.833334	0.002451	1.414216
4	1.414216				

Of course, in this case you know that the two zeros of the function are $\pm\sqrt{2}$. To six decimal places, $\sqrt{2} = 1.414214$. So, after only three iterations of Newton's Method, you have obtained an approximation that is within 0.000002 of an actual zero.

EXAMPLE 2 Using Newton's Method

See LarsonCalculus.com for an interactive version of this type of example.

Use Newton's Method to approximate the zeros of $f(x) = 2x^3 + x^2 - x + 1$. Continue the iterations until two successive approximations differ by less than 0.0001.

Solution Begin by sketching a graph of f, as shown in Figure 3.62. From the graph, notice that the function has only one zero, which occurs near $x = -1.2$. Next, differentiate f and form the iterative formula

$$x_{n+1} = x_n - \frac{f(x_n)}{f'(x_n)} = x_n - \frac{2x_n^3 + x_n^2 - x_n + 1}{6x_n^2 + 2x_n - 1}.$$

The calculations are shown in the table.



After three iterations of Newton's Method, the zero of f is approximated to the desired accuracy.
Figure 3.62

n	x_n	$f(x_n)$	$f'(x_n)$	$\frac{f(x_n)}{f'(x_n)}$	$x_n - \frac{f(x_n)}{f'(x_n)}$
1	−1.20000	0.18400	5.24000	0.03511	−1.23511
2	−1.23511	−0.00771	5.68276	−0.00136	−1.23375
3	−1.23375	0.00001	5.66533	0.00000	−1.23375
4	−1.23375				

Because two successive approximations differ by less than the required 0.0001, you can estimate the zero of f to be −1.23375. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

When, as in Examples 1 and 2, the approximations approach a limit, the sequence of approximations

$$x_1, x_2, x_3, \ldots, x_n, \ldots$$

is said to **converge.** Moreover, when the limit is c, it can be shown that c must be a zero of f.

FOR FURTHER INFORMATION
For more on when Newton's Method fails, see the article "No Fooling! Newton's Method Can Be Fooled" by Peter Horton in *Mathematics Magazine*. To view this article, go to *MathArticles.com*.

Newton's Method does not always yield a a convergent sequence. One way it can fail to do so is shown in Figure 3.63. Because Newton's Method involves division by $f'(x_n)$, it is clear that the method will fail when the derivative is zero for any x_n in the sequence. When you encounter this problem, you can usually overcome it by choosing a different value for x_1. Another way Newton's Method can fail is shown in the next example.



Newton's Method fails to converge when $f'(x_n) = 0$.
Figure 3.63

EXAMPLE 3 An Example in Which Newton's Method Fails

The function $f(x) = x^{1/3}$ is not differentiable at $x = 0$. Show that Newton's Method fails to converge using $x_1 = 0.1$.

Solution Because $f'(x) = \frac{1}{3}x^{-2/3}$, the iterative formula is

$$x_{n+1} = x_n - \frac{f(x_n)}{f'(x_n)} = x_n - \frac{x_n^{1/3}}{\frac{1}{3}x_n^{-2/3}} = x_n - 3x_n = -2x_n.$$

The calculations are shown in the table. This table and Figure 3.64 indicate that x_n continues to increase in magnitude as $n \to \infty$, and so the limit of the sequence does not exist.

n	x_n	$f(x_n)$	$f'(x_n)$	$\frac{f(x_n)}{f'(x_n)}$	$x_n - \frac{f(x_n)}{f'(x_n)}$
1	0.10000	0.46416	1.54720	0.30000	−0.20000
2	−0.20000	−0.58480	0.97467	−0.60000	0.40000
3	0.40000	0.73681	0.61401	1.20000	−0.80000
4	−0.80000	−0.92832	0.38680	−2.40000	1.60000

REMARK In Example 3, the initial estimate $x_1 = 0.1$ fails to produce a convergent sequence. Try showing that Newton's Method also fails for every other choice of x_1 (other than the actual zero).



Newton's Method fails to converge for every x-value other than the actual zero of f.
Figure 3.64

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

It can be shown that a condition sufficient to produce convergence of Newton's Method to a zero of f is that

$$\left|\frac{f(x)f''(x)}{[f'(x)]^2}\right| < 1 \qquad \text{Condition for convergence}$$

on an open interval containing the zero. For instance, in Example 1, this test would yield

$$f(x) = x^2 - 2, \quad f'(x) = 2x, \quad f''(x) = 2,$$

and

$$\left|\frac{f(x)f''(x)}{[f'(x)]^2}\right| = \left|\frac{(x^2 - 2)(2)}{4x^2}\right| = \left|\frac{1}{2} - \frac{1}{x^2}\right|. \qquad \text{Example 1}$$

On the interval $(1, 3)$, this quantity is less than 1 and so the convergence of Newton's Method is guaranteed. On the other hand, in Example 3, you have

$$f(x) = x^{1/3}, \quad f'(x) = \frac{1}{3}x^{-2/3}, \quad f''(x) = -\frac{2}{9}x^{-5/3}$$

and

$$\left|\frac{f(x)f''(x)}{[f'(x)]^2}\right| = \left|\frac{x^{1/3}(-2/9)(x^{-5/3})}{(1/9)(x^{-4/3})}\right| = 2 \qquad \text{Example 3}$$

which is not less than 1 for any value of x, so you cannot conclude that Newton's Method will converge.

You have learned several techniques for finding the zeros of functions. The zeros of some functions, such as

$$f(x) = x^3 - 2x^2 - x + 2$$

can be found by simple algebraic techniques, such as factoring. The zeros of other functions, such as

$$f(x) = x^3 - x + 1$$

cannot be found by *elementary* algebraic methods. This particular function has only one real zero, and by using more advanced algebraic techniques, you can determine the zero to be

$$x = -\sqrt[3]{\frac{3 - \sqrt{23/3}}{6}} - \sqrt[3]{\frac{3 + \sqrt{23/3}}{6}}.$$

Because the *exact* solution is written in terms of square roots and cube roots, it is called a **solution by radicals.**

The determination of radical solutions of a polynomial equation is one of the fundamental problems of algebra. The earliest such result is the Quadratic Formula, which dates back at least to Babylonian times. The general formula for the zeros of a cubic function was developed much later. In the sixteenth century, an Italian mathematician, Jerome Cardan, published a method for finding radical solutions to cubic and quartic equations. Then, for 300 years, the problem of finding a general quintic formula remained open. Finally, in the nineteenth century, the problem was answered independently by two young mathematicians. Niels Henrik Abel, a Norwegian mathematician, and Evariste Galois, a French mathematician, proved that it is not possible to solve a *general* fifth- (or higher-) degree polynomial equation by radicals. Of course, you can solve particular fifth-degree equations, such as $x^5 - 1 = 0$, but Abel and Galois were able to show that no general *radical* solution exists.



NIELS HENRIK ABEL (1802–1829)

EVARISTE GALOIS (1811–1832)

Although the lives of both Abel and Galois were brief, their work in the fields of analysis and abstract algebra was far-reaching. *See LarsonCalculus.com to read a biography about each of these mathematicians.*

Art Collection 2/Alamy Stock Photo

Science History Images/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

3.8 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain Newton's Method for approximating the zeros of a function. Include a sketch in your explanation.
2. Why does Newton's Method fail when $f'(x_n) = 0$? What does this mean graphically?

Using Newton's Method **In Exercises 3–6, calculate two iterations of Newton's Method to approximate a zero of the function using the given initial guess.**

3. $f(x) = x^2 - 5, \quad x_1 = 2$
4. $f(x) = x^3 - 3, \quad x_1 = 1.4$
5. $f(x) = \cos x, \quad x_1 = 1.6$
6. $f(x) = \tan x, \quad x_1 = 0.1$

Using Newton's Method **In Exercises 7–16, use Newton's Method to approximate the zero(s) of the function. Continue the iterations until two successive approximations differ by less than 0.001. Then find the zero(s) using a graphing utility and compare the results.**

7. $f(x) = x^3 + 4$
8. $f(x) = 2 - x^3$
9. $f(x) = x^3 + x - 1$
10. $f(x) = x^5 + x - 1$
11. $f(x) = 5\sqrt{x - 1} - 2x$
12. $f(x) = x - 2\sqrt{x + 1}$
13. $f(x) = x^3 - 3.9x^2 + 4.79x - 1.881$
14. $f(x) = -x^3 + 2.7x^2 + 3.55x - 2.422$
15. $f(x) = 1 - x + \sin x$
16. $f(x) = x^3 - \cos x$

Points of Intersection **In Exercises 17–20, apply Newton's Method to approximate the x-value(s) of the indicated point(s) of intersection of the two graphs. Continue the iterations until two successive approximations differ by less than 0.001.** [***Hint:*** **Let $h(x) = f(x) - g(x)$.**]

17. $f(x) = 2x + 1$
$g(x) = \sqrt{x + 4}$



18. $f(x) = 3 - x$
$g(x) = \dfrac{1}{x^2 + 1}$



19. $f(x) = x$
$g(x) = \tan x$



20. $f(x) = x^2$
$g(x) = \cos x$



21. **Using Newton's Method** Consider the function $f(x) = x^3 - 3x^2 + 3$.
   (a) Use a graphing utility to graph f.
   (b) Use Newton's Method to approximate a zero with $x_1 = 1$ as the initial guess.
   (c) Repeat part (b) using $x_1 = \frac{1}{4}$ as the initial guess and observe that the result is different.
   (d) To understand why the results in parts (b) and (c) are different, sketch the tangent lines to the graph of f at the points $(1, f(1))$ and $\left(\frac{1}{4}, f\left(\frac{1}{4}\right)\right)$. Describe why it is important to select the initial guess carefully.

22. **Using Newton's Method** Repeat the steps in Exercise 21 for the function $f(x) = \sin x$ with initial guesses of $x_1 = 1.8$ and $x_1 = 3$.

Failure of Newton's Method **In Exercises 23 and 24, apply Newton's Method using the given initial guess, and explain why the method fails.**

23. $y = 2x^3 - 6x^2 + 6x - 1, \quad x_1 = 1$



Figure for 23



Figure for 24

24. $y = x^3 - 2x - 2, \quad x_1 = 0$

Exploring Concepts

25. What will be the values of future guesses for x if your initial guess is a zero of f? Explain.
26. Does Newton's Method fail when the initial guess is a relative maximum of f? Explain.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Fixed Point **In Exercises 27 and 28, approximate the fixed point of the function to two decimal places. [A *fixed point* of a function f is a real number c such that $f(c) = c$.]**

27. $f(x) = \cos x$

28. $f(x) = \cot x, \quad 0 < x < \pi$

29. Proof Prove that if f is differentiable on $(-\infty, \infty)$ and $f'(x) < 1$ for all real numbers, then f has at most one fixed point. [A *fixed point* of a function f is a real number c such that $f(c) = c$.]

30. Fixed Point Use the result of Exercise 29 to show that $f(x) = \frac{1}{2}\cos x$ has at most one fixed point.

Using Newton's Method **Exercises 31–33 present problems similar to exercises from the previous sections of this chapter. In each case, use Newton's Method to approximate the solution.**

31. Minimum Distance Find the point on the graph of $f(x) = 4 - x^2$ that is closest to the point $(1, 0)$.

32. Medicine The concentration C of a chemical in the bloodstream t hours after injection into muscle tissue is given by

$$C = \frac{3t^2 + t}{50 + t^3}.$$

When is the concentration the greatest?

33. Minimum Time A person is in a boat 2 miles from the nearest point on the coast. They are traveling to a point Q that is 3 miles down the coast and 1 mile inland (see figure). They can row at 3 miles per hour and walk at 4 miles per hour. Toward what point on the coast should they row in order to reach point Q in the least time?



34. HOW DO YOU SEE IT? For what value(s) will Newton's Method fail to converge for the function shown in the graph? Explain your reasoning.



35. Mechanic's Rule The Mechanic's Rule for approximating $\sqrt{a}$, $a > 0$, is

$$x_{n+1} = \frac{1}{2}\left(x_n + \frac{a}{x_n}\right), \quad n = 1, 2, 3, \ldots$$

where x_1 is an approximation of $\sqrt{a}$.

(a) Use Newton's Method and the function $f(x) = x^2 - a$ to derive the Mechanic's Rule.

(b) Use the Mechanic's Rule to approximate $\sqrt{5}$ and $\sqrt{7}$ to three decimal places.

36. Approximating Radicals

(a) Use Newton's Method and the function $f(x) = x^n - a$ to obtain a general rule for approximating $x = \sqrt[n]{a}$.

(b) Use the general rule found in part (a) to approximate $\sqrt[4]{6}$ and $\sqrt[3]{15}$ to three decimal places.

37. Approximating Reciprocals Use Newton's Method to show that the equation $x_{n+1} = x_n(2 - ax_n)$ can be used to approximate $1/a$ when x_1 is an initial guess of the reciprocal of a. Note that this method of approximating reciprocals uses only the operations of multiplication and subtraction. (*Hint:* Consider

$$f(x) = \frac{1}{x} - a.\Big)$$

38. Approximating Reciprocals Use the result of Exercise 37 to approximate (a) $\frac{1}{3}$ and (b) $\frac{1}{11}$ to three decimal places.

True or False? **In Exercises 39–42, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

39. The zeros of $f(x) = \dfrac{p(x)}{q(x)}$ coincide with the zeros of $p(x)$.

40. If the coefficients of a polynomial function are all positive, then the polynomial has no positive zeros.

41. If $f(x)$ is a cubic polynomial such that $f'(x)$ is never zero, then any initial guess will force Newton's Method to converge to the zero of f.

42. Newton's Method fails when the initial guess x_1 corresponds to a horizontal tangent line for the graph of f at x_1.

43. Tangent Lines The graph of $f(x) = -\sin x$ has infinitely many tangent lines that pass through the origin. Use Newton's Method to approximate to three decimal places the slope of the tangent line having the greatest slope.

44. Point of Tangency The graph of $f(x) = \cos x$ and a tangent line to f through the origin are shown. Find the coordinates of the point of tangency to three decimal places.



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

3.9 Differentials

GO DIGITAL

- Describe the concept of a tangent line approximation.
- Compare the value of the differential, *dy*, with the actual change in y, Δy.
- Estimate a propagated error using a differential.
- Find the differential of a function using differentiation formulas.

Exploration

Tangent Line Approximation Let $f(x) = x^2$. Use a graphing utility to graph f and its tangent line at the point $(1, 1)$ in the same viewing window. Use a viewing window with $0.4 \le x \le 1.6$ and $0.4 \le y \le 1.6$. As both graphs approach $(1, 1)$, what do you notice? Use the *trace* feature to compare the values of f with the y-values of the tangent line. As the x-values get closer to 1, what do you notice?



The tangent line approximation of f at the point $(0, 1)$

Figure 3.65

Tangent Line Approximations

Newton's Method (see Section 3.8) is an example of the use of a tangent line to approximate the graph of a function. In this section, you will study other situations in which the graph of a function can be approximated by a straight line.

To begin, consider a function f that is differentiable at c. The equation for the tangent line at the point $(c, f(c))$ is

$$y - f(c) = f'(c)(x - c)$$

$$y = f(c) + f'(c)(x - c)$$

and is called the **tangent line approximation** (or **linear approximation**) **of f at c.** Because c is a constant, y is a linear function of x. Moreover, by restricting the values of x to those sufficiently close to c, the values of y can be used as approximations (to any desired degree of accuracy) of the values of the function f. In other words, as x approaches c, the limit of y is $f(c)$.

EXAMPLE 1 Using a Tangent Line Approximation

See LarsonCalculus.com for an interactive version of this type of example.

Find the tangent line approximation of $f(x) = 1 + \sin x$ at the point $(0, 1)$. Then use a table to compare the y-values of the tangent line with those of $f(x)$ on an open interval containing $x = 0$.

Solution The derivative of f is $f'(x) = \cos x$. So, the equation of the tangent line to the graph of f at the point $(0, 1)$ is

$$y = f(0) + f'(0)(x - 0)$$
$$y = 1 + (1)(x - 0)$$
$$y = 1 + x.$$ Tangent line approximation

The table compares the values of y given by this tangent line approximation with $f(x)$ near $x = 0$. Notice that the closer x is to 0, the better the approximation. This conclusion is reinforced by the graph shown in Figure 3.65.

x	-0.5	-0.1	-0.01	0	0.01	0.1	0.5
$f(x) = 1 + \sin x$	0.521	0.9002	0.9900002	1	1.0099998	1.0998	1.479
$y = 1 + x$	0.5	0.9	0.99	1	1.01	1.1	1.5

REMARK Note that this linear approximation of $f(x) = 1 + \sin x$ depends on the point of tangency. At a different point on the graph of f, you would obtain a different tangent line approximation. For instance, find the tangent line approximation of $f(x) = 1 + \sin x$ at the point $(\pi/6, 3/2)$ and compare the result to the one in Example 1.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Differentials

When the tangent line to the graph of f at the point $(c, f(c))$

$$y = f(c) + f'(c)(x - c)$$ Tangent line at $(c, f(c))$

is used as an approximation of the graph of f, the quantity $x - c$ is called the change in x, and is denoted by Δx, as shown in Figure 3.66. When Δx is small, the change in y (denoted by Δy) can be approximated as shown.

$$\Delta y = f(c + \Delta x) - f(c)$$ Actual change in y

$$\approx f'(c)\Delta x$$ Approximate change in y

For such an approximation, the quantity Δx is traditionally denoted by dx and is called the **differential of x.** The expression $f'(x)\,dx$ is denoted by dy and is called the **differential of y.**



When Δx is small, $\Delta y = f(c + \Delta x) - f(c)$ is approximated by $f'(c)\Delta x$.
Figure 3.66

Definition of Differentials

Let $y = f(x)$ represent a function that is differentiable on an open interval containing x. The **differential of x** (denoted by dx) is any nonzero real number. The **differential of y** (denoted by dy) is

$$dy = f'(x)\,dx.$$

In many types of applications, the differential of y can be used as an approximation of the change in y. That is,

$$\Delta y \approx dy \quad \text{or} \quad \Delta y \approx f'(x)\,dx.$$



The change in y, Δy, is approximated by the differential of y, dy.
Figure 3.67

EXAMPLE 2 Comparing Δy and dy

Let $y = x^2$. Find dy when $x = 1$ and $dx = 0.01$. Compare this value with Δy for $x = 1$ and $\Delta x = 0.01$.

Solution Because $y = f(x) = x^2$, you have $f'(x) = 2x$, and the differential dy is

$$dy = f'(x)\,dx = f'(1)(0.01) = 2(0.01) = 0.02.$$ Differential of y

Now, using $\Delta x = 0.01$, the change in y is

$$\Delta y = f(x + \Delta x) - f(x) = f(1.01) - f(1) = (1.01)^2 - 1^2 = 0.0201.$$

Figure 3.67 shows the geometric comparison of dy and Δy. Try comparing other values of dy and Δy. You will see that the values become closer to each other as dx (or Δx) approaches 0. ■

In Example 2, the tangent line to the graph of $f(x) = x^2$ at $x = 1$ is

$$y = 2x - 1.$$ Tangent line to the graph of f at $x = 1$.

For x-values near 1, this line is close to the graph of f, as shown in Figure 3.67 and in the table.

x	0.5	0.9	0.99	1	1.01	1.1	1.5
$f(x) = x^2$	0.25	0.81	0.9801	1	1.0201	1.21	2.25
$y = 2x - 1$	0	0.8	0.98	1	1.02	1.2	2

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Error Propagation

Physicists and engineers tend to make liberal use of the approximation of Δy by dy. One way this occurs in practice is in the estimation of errors propagated by physical measuring devices. For example, if you let x represent the measured value of a variable and let $x + \Delta x$ represent the exact value, then Δx is the *error in measurement*. Finally, if the measured value x is used to compute another value $f(x)$, then the difference between $f(x + \Delta x)$ and $f(x)$ is the **propagated error.**

$$\underbrace{f(\overbrace{x + \Delta x}^{\text{Measurement error}})}_{\text{Exact value}} - \underbrace{f(x)}_{\text{Measured value}} = \overbrace{\Delta y}^{\text{Propagated error}}$$

EXAMPLE 3 Estimation of Error

Ball bearings are used to reduce friction between moving machine parts.

The measured radius of a ball bearing is 0.7 inch, as shown in the figure. The measurement is correct to within 0.01 inch. Estimate the propagated error in the volume V of the ball bearing.



Ball bearing with measured radius that is correct to within 0.01 inch.

Solution The formula for the volume of a sphere is

$$V = \frac{4}{3}\pi r^3$$

where r is the radius of the sphere. So, you can write

$$r = 0.7 \qquad \text{Measured radius}$$

and

$$-0.01 \le \Delta r \le 0.01. \qquad \text{Possible error}$$

To approximate the propagated error in the volume, differentiate V to obtain $dV/dr = 4\pi r^2$ and write

$$\begin{aligned} \Delta V &\approx dV && \text{Approximate } \Delta V \text{ by } dV. \\ &= 4\pi r^2\, dr \\ &= 4\pi(0.7)^2(\pm 0.01) && \text{Substitute for } r \text{ and } dr. \\ &\approx \pm 0.06158 \text{ cubic inch.} \end{aligned}$$

So, the volume has a propagated error of about 0.06 cubic inch. ■

Would you say that the propagated error in Example 3 is large or small? The answer is best given in *relative* terms by comparing dV with V. The ratio

$$\begin{aligned} \frac{dV}{V} &= \frac{4\pi r^2\, dr}{\frac{4}{3}\pi r^3} && \text{Ratio of } dV \text{ to } V \\ &= \frac{3\, dr}{r} && \text{Simplify.} \\ &\approx \frac{3(\pm 0.01)}{0.7} && \text{Substitute for } dr \text{ and } r. \\ &\approx \pm 0.0429 \end{aligned}$$

is called the **relative error.** The corresponding **percent error** is approximately 4.29%.

Harper 3D/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Calculating Differentials

Each of the differentiation rules that you studied in Chapter 2 can be written in **differential form.** For example, let u and v be differentiable functions of x. By the definition of differentials, you have

$$du = u'\,dx \qquad \text{Differential of } u$$

and

$$dv = v'\,dx. \qquad \text{Differential of } v$$

So, you can write the differential form of the Product Rule as shown below.

$$\begin{aligned} d[uv] &= \frac{d}{dx}[uv]\,dx && \text{Differential of } uv \\ &= [uv' + vu']\,dx && \text{Product Rule} \\ &= uv'\,dx + vu'\,dx \\ &= u\,dv + v\,du \end{aligned}$$

Differential Formulas

Let u and v be differentiable functions of x.

Constant multiple:	$d[cu] = c\,du$
Sum or difference:	$d[u \pm v] = du \pm dv$
Product:	$d[uv] = u\,dv + v\,du$
Quotient:	$d\left[\frac{u}{v}\right] = \frac{v\,du - u\,dv}{v^2}$

EXAMPLE 4 Finding Differentials

Function	Derivative	Differential
a. $y = x^2$	$\frac{dy}{dx} = 2x$	$dy = 2x\,dx$
b. $y = \sqrt{x}$	$\frac{dy}{dx} = \frac{1}{2\sqrt{x}}$	$dy = \frac{dx}{2\sqrt{x}}$
c. $y = 2\sin x$	$\frac{dy}{dx} = 2\cos x$	$dy = 2\cos x\,dx$
d. $y = x\cos x$	$\frac{dy}{dx} = -x\sin x + \cos x$	$dy = (-x\sin x + \cos x)\,dx$
e. $y = \frac{1}{x}$	$\frac{dy}{dx} = -\frac{1}{x^2}$	$dy = -\frac{dx}{x^2}$

GOTTFRIED WILHELM LEIBNIZ (1646–1716)

Both Leibniz and Newton are credited with creating calculus. It was Leibniz, however, who tried to broaden calculus by developing rules and formal notation. He often spent days choosing an appropriate notation for a new concept. *See LarsonCalculus.com to read more of this biography.*

The notation in Example 4 is called the **Leibniz notation** for derivatives and differentials, named after the German mathematician Gottfried Wilhelm Leibniz. The beauty of this notation is that it provides an easy way to remember several important calculus formulas by making it seem as though the formulas were derived from algebraic manipulations of differentials. For instance, in Leibniz notation, the Chain Rule

$$\frac{dy}{dx} = \frac{dy}{du}\frac{du}{dx}$$

would appear to be true because the du's divide out. Even though this reasoning is *incorrect*, the notation does help one remember the Chain Rule.

Science History Images/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 5 Finding the Differential of a Composite Function

$$y = f(x) = \sin 3x \qquad \text{Original function}$$
$$f'(x) = 3\cos 3x \qquad \text{Apply Chain Rule.}$$
$$dy = f'(x)\,dx = 3\cos 3x\,dx \qquad \text{Differential form}$$

EXAMPLE 6 Finding the Differential of a Composite Function

$$y = f(x) = (x^2 + 1)^{1/2} \qquad \text{Original function}$$
$$f'(x) = \frac{1}{2}(x^2 + 1)^{-1/2}(2x) = \frac{x}{\sqrt{x^2 + 1}} \qquad \text{Apply Chain Rule.}$$
$$dy = f'(x)\,dx = \frac{x}{\sqrt{x^2 + 1}}\,dx \qquad \text{Differential form}$$

Differentials can be used to approximate function values. To do this for the function given by $y = f(x)$, use the formula

$$f(x + \Delta x) \approx f(x) + dy = f(x) + f'(x)\,dx$$

which is derived from the approximation

$$\Delta y = f(x + \Delta x) - f(x) \approx dy.$$

REMARK This formula is equivalent to the tangent line approximation given earlier in this section.

The key to using this formula is to choose a value for x that makes the calculations easier, as shown in Example 7.

EXAMPLE 7 Approximating Function Values

Use differentials to approximate $\sqrt{16.5}$.

Solution Using $f(x) = \sqrt{x}$, you can write

$$f(x + \Delta x) \approx f(x) + f'(x)\,dx = \sqrt{x} + \frac{1}{2\sqrt{x}}\,dx.$$

Now, choosing $x = 16$ and $dx = 0.5$, you obtain the approximation

$$f(x + \Delta x) = \sqrt{16.5} \approx \sqrt{16} + \frac{1}{2\sqrt{16}}(0.5) = 4 + \left(\frac{1}{8}\right)\left(\frac{1}{2}\right) = 4.0625.$$

So, $\sqrt{16.5} \approx 4.0625$.



Figure 3.68

The tangent line approximation to $f(x) = \sqrt{x}$ at $x = 16$ is the line $g(x) = \frac{1}{8}x + 2$. For x-values near 16, the graph of g closely approximates the graph of f, as shown in Figure 3.68. For instance,

$$f(16.5) = \sqrt{16.5} \approx 4.0620 \qquad \text{Original function when } x = 16.5$$

and

$$g(16.5) = \frac{1}{8}(16.5) + 2 = 4.0625. \qquad \text{Tangent line approximation when } x = 16.5$$

In fact, if you use a graphing utility to zoom in near the point of tangency (16, 4), you will see that the two graphs appear to coincide. Notice also that as you move farther away from the point of tangency, the linear approximation becomes less accurate.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

3.9 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Give the equation of the tangent line approximation to the graph of a function f at the point $(c, f(c))$.
2. Explain the meaning of the differentials of x and y.
3. Explain the terms *propagated error*, *relative error*, and *percent error*.
4. Explain how to find a differential of a function.

Using a Tangent Line Approximation **In Exercises 5–10, find the tangent line approximation T to the graph of f at the given point. Then complete the table.**

x	1.9	1.99	2	2.01	2.1
$f(x)$					
$T(x)$					

5. $f(x) = x^2, \quad (2, 4)$
6. $f(x) = \dfrac{6}{x^2}, \quad \left(2, \dfrac{3}{2}\right)$
7. $f(x) = x^5, \quad (2, 32)$
8. $f(x) = \sqrt{x}, \quad (2, \sqrt{2})$
9. $f(x) = \sin x, \quad (2, \sin 2)$
10. $f(x) = \csc x, \quad (2, \csc 2)$

Verifying a Tangent Line Approximation **In Exercises 11 and 12, verify the tangent line approximation of the function at the given point. Then use a graphing utility to graph the function and its approximation in the same viewing window.**

Function	Approximation	Point
11. $f(x) = \sqrt{x + 4}$	$y = 2 + \dfrac{x}{4}$	$(0, 2)$
12. $f(x) = \tan x$	$y = x$	$(0, 0)$

Comparing Δy and dy **In Exercises 13–18, use the information to find and compare Δy and dy.**

Function	x-Value	Differential of x
13. $y = 0.5x^3$	$x = 1$	$\Delta x = dx = 0.1$
14. $y = 6 - 2x^2$	$x = -2$	$\Delta x = dx = 0.1$
15. $y = x^4 + 1$	$x = -1$	$\Delta x = dx = 0.01$
16. $y = 2 - x^4$	$x = 2$	$\Delta x = dx = 0.01$
17. $y = x - 2x^3$	$x = 3$	$\Delta x = dx = 0.001$
18. $y = 7x^2 - 5x$	$x = -4$	$\Delta x = dx = 0.001$

Finding a Differential **In Exercises 19–28, find the differential dy of the given function.**

19. $y = 3x^2 - 4$
20. $y = 3x^{2/3}$
21. $y = x \tan x$
22. $y = \csc 2x$
23. $y = \dfrac{x + 1}{2x - 1}$
24. $y = \sqrt{x} + \dfrac{1}{\sqrt{x}}$
25. $y = \sqrt{9 - x^2}$
26. $y = x\sqrt{1 - x^2}$
27. $y = 3x - \sin^2 x$
28. $y = \dfrac{\sec^2 x}{x^2 + 1}$

Using Differentials **In Exercises 29 and 30, use differentials and the graph of f to approximate (a) $f(1.9)$ and (b) $f(2.04)$. To print an enlarged copy of the graph, go to *MathGraphs.com*.**

29.



30.



Using Differentials **In Exercises 31 and 32, use differentials and the graph of g' to approximate (a) $g(2.93)$ and (b) $g(3.1)$ given that $g(3) = 8$.**

31.



32.



33. **Area** The measurement of the side of a square floor tile is 10 inches, with a possible error of $\frac{1}{32}$ inch.
   (a) Use differentials to approximate the possible propagated error in computing the area of the square.
   (b) Approximate the percent error in computing the area of the square.
34. **Area** The measurements of the base and altitude of a triangle are found to be 36 and 50 centimeters, respectively. The possible error in each measurement is 0.25 centimeter.
   (a) Use differentials to approximate the possible propagated error in computing the area of the triangle.
   (b) Approximate the percent error in computing the area of the triangle.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

35. Volume and Surface Area The measurement of the edge of a cube is found to be 15 inches, with a possible error of 0.03 inch.

(a) Use differentials to approximate the possible propagated error in computing the volume of the cube.

(b) Use differentials to approximate the possible propagated error in computing the surface area of the cube.

(c) Approximate the percent errors in parts (a) and (b).

36. Volume and Surface Area The radius of a spherical balloon is measured as 8 inches, with a possible error of 0.02 inch.

(a) Use differentials to approximate the possible propagated error in computing the volume of the sphere.

(b) Use differentials to approximate the possible propagated error in computing the surface area of the sphere.

(c) Approximate the percent errors in parts (a) and (b).

37. Stopping Distance The total stopping distance T of a vehicle is

$$T = 2.2x + 0.05x^2$$

where T is in feet and x is the speed in miles per hour. Approximate the change and percent change in total stopping distance as speed changes from $x = 25$ to $x = 26$ miles per hour.

38. HOW DO YOU SEE IT? The graph shows the profit P (in dollars) from selling x units of an item. Use the graph to determine which is greater, the change in profit when the production level changes from 400 to 401 units or the change in profit when the production level changes from 900 to 901 units. Explain your reasoning.



39. Pendulum The period of a pendulum is given by

$$T = 2\pi\sqrt{\frac{L}{g}}$$

where L is the length of the pendulum in feet, g is the acceleration due to gravity, and T is the time in seconds. The pendulum has been subjected to an increase in temperature such that the length has increased by $\frac{1}{2}\%$.

(a) Find the approximate percent change in the period.

(b) Using the result in part (a), find the approximate error in this pendulum clock in 1 day.

40. Ohm's Law A current of I amperes passes through a resistor of R ohms. **Ohm's Law** states that the voltage E applied to the resistor is

$$E = IR.$$

The voltage is constant. Show that the magnitude of the relative error in R caused by a change in I is equal in magnitude to the relative error in I.

41. Projectile Motion The range R of a projectile is

$$R = \frac{v_0^2}{32}(\sin 2\theta)$$

where v_0 is the initial velocity in feet per second and θ is the angle of elevation. Use differentials to approximate the change in the range when $v_0 = 2500$ feet per second and θ is changed from 10° to 11°.

42. Surveying A surveyor standing 50 feet from the base of a large tree measures the angle of elevation to the top of the tree as 71.5°. How accurately must the angle be measured if the percent error in estimating the height of the tree is to be less than 6%?

Approximating Function Values **In Exercises 43–46, use differentials to approximate the value of the expression. Compare your answer with that of a calculator.**

43. $\sqrt{99.4}$

44. $\sqrt[3]{26}$

45. $\sqrt[4]{624}$

46. $(2.99)^3$

Exploring Concepts

47. Describe the change in accuracy of dy as an approximation for Δy when Δx approaches 0. Use a graph to support your answer.

48. Give a short explanation of why each approximation is valid.

(a) $\sqrt{4.02} \approx 2 + \frac{1}{4}(0.02)$

(b) $\tan 0.05 \approx 0 + 1(0.05)$

True or False? **In Exercises 49–53, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

49. If $y = x + c$, then $dy = dx$.

50. If $y = ax + b$, then $\dfrac{\Delta y}{\Delta x} = \dfrac{dy}{dx}$.

51. If y is differentiable, then $\lim_{\Delta x \to 0}(\Delta y - dy) = 0$.

52. If $y = f(x)$, f is increasing and differentiable, and $\Delta x > 0$, then $\Delta y \geq dy$.

53. The tangent line approximation at any point for any linear equation is the linear equation itself.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Review Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Exploring Concepts

In this chapter, you explored several applications of the derivative. One of the applications, graphical analysis, used concepts you reviewed in Chapter P and the concepts in Chapters 1–3 to help you fully sketch the graph of a function.

Chapter P
- x-intercepts and y-intercepts
- Symmetry
- Domain and range

Chapters 1–3
- Asymptotes
- Critical numbers
- Increasing and decreasing intervals
- Extrema
- Concavity and points of inflection

These concepts along with Rolle's Theorem and the Mean Value Theorem will help you to analyze real-life situations and solve optimization problems.

1. Give the definition of a critical number, and graph a function showing the different types of critical numbers.

2. Consider the function $f(x) = 3 - |x - 4|$.

(a) Graph the function and verify that $f(1) = f(7)$.

(b) Note that $f'(x)$ is not equal to zero for any x in $[1, 7]$. Explain why this does not contradict Rolle's Theorem.

3. Consider the inequality

$$\sqrt{x + 1} < \frac{1}{2}x + 1$$

where x is a positive real number.

(a) Use the *table* feature of a graphing utility to investigate the validity of the inequality.

(b) Use the Mean Value Theorem to prove that the inequality is true.

4. Consider the function $f(x) = 108x^2 - 4x^3$.

(a) Find the critical numbers of f.

(b) Find the relative extrema of f.

(c) Find the open intervals on which f is increasing or decreasing.

(d) Determine the open intervals on which f is concave upward or concave downward.

(e) Find the points of inflection of f.

(f) Sketch the graph of f.

5. A rectangular package to be sent by a shipping service can have a maximum combined length and girth (perimeter of a cross section) of 108 inches (see figure). Assume the cross section is square.



(a) Write the volume V of the package as a function of x. Compare this equation to the one in Exercise 4. What do you notice?

(b) Find the dimensions of the package of maximum volume that can be sent.

6. Consider the function

$$f(x) = 3\cos^2\left(\frac{\pi x}{2}\right).$$

(a) Use a graphing utility to graph f and f'.

(b) Is f a continuous function? Is f' a continuous function?

(c) Does Rolle's Theorem apply on the interval $[-1, 1]$? Does it apply on the interval $[1, 2]$? Explain.

(d) Evaluate, if possible, $\lim_{x\to 3^-} f'(x)$ and $\lim_{x\to 3^+} f'(x)$.

Finding Extrema on a Closed Interval **In Exercises 7–14, find the absolute extrema of the function on the closed interval.**

7. $f(x) = x^2 + 5x, \ [-4, 0]$

8. $f(x) = x^3 + 6x^2, \ [-6, 1]$

9. $f(x) = \sqrt{x} - 2, \ [0, 4]$

10. $h(x) = x - 3\sqrt{x}, \ [0, 9]$

11. $f(x) = \dfrac{4x}{x^2 + 9}, \ [-4, 4]$

12. $f(x) = \dfrac{x}{\sqrt{x^2 + 1}}, \ [0, 2]$

13. $g(x) = 2x + 5\cos x, \ [0, 2\pi]$

14. $f(x) = \sin 2x, \quad [0, 2\pi]$

Using Rolle's Theorem **In Exercises 15–18, determine whether Rolle's Theorem can be applied to f on the closed interval $[a, b]$. If Rolle's Theorem can be applied, find all values of c in the open interval (a, b) such that $f'(c) = 0$. If Rolle's Theorem cannot be applied, explain why not.**

15. $f(x) = x^3 - 3x - 6, \quad [-1, 2]$

16. $f(x) = (x - 2)(x + 3)^2, \quad [-3, 2]$

17. $f(x) = \dfrac{x^2}{1 - x^2}, \quad [-2, 2]$

18. $f(x) = \sin 2x, \quad [-\pi, \pi]$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Using the Mean Value Theorem **In Exercises 19–24, determine whether the Mean Value Theorem can be applied to f on the closed interval $[a, b]$. If the Mean Value Theorem can be applied, find all values of c in the open interval (a, b) such that**

$$f'(c) = \frac{f(b) - f(a)}{b - a}.$$

If the Mean Value Theorem cannot be applied, explain why not.

19. $f(x) = x^{2/3}, \quad [1, 8]$

20. $f(x) = \frac{1}{x}, \quad [1, 4]$

21. $f(x) = |5 - x|, \quad [2, 6]$

22. $f(x) = 2x - 3\sqrt{x}, \quad [-1, 1]$

23. $f(x) = x - \cos x, \quad \left[-\frac{\pi}{2}, \frac{\pi}{2}\right]$

24. $f(x) = \sqrt{x} - 2x, \quad [0, 4]$

25. Mean Value Theorem Can the Mean Value Theorem be applied to the function

$$f(x) = \frac{1}{x^2}$$

on the interval $[-2, 1]$? Explain.

26. Using the Mean Value Theorem

(a) For the function $f(x) = Ax^2 + Bx + C$, determine the value of c guaranteed by the Mean Value Theorem on the interval $[x_1, x_2]$.

(b) Demonstrate the result of part (a) for

$$f(x) = 2x^2 - 3x + 1$$

on the interval $[0, 4]$.

Intervals on Which a Function Is Increasing or Decreasing **In Exercises 27–32, find the open intervals on which the function is increasing or decreasing.**

27. $f(x) = x^2 + 3x - 12$

28. $h(x) = (x + 2)^{1/3} + 8$

29. $f(x) = (x - 1)^2(2x - 5)$

30. $g(x) = (x + 1)^3$

31. $h(x) = \sqrt{x}(x - 3), \quad x > 0$

32. $f(x) = \sin x + \cos x, \quad 0 < x < 2\pi$

Applying the First Derivative Test **In Exercises 33–40, (a) find the critical numbers of f, if any, (b) find the open intervals on which the function is increasing or decreasing, (c) apply the First Derivative Test to identify all relative extrema, and (d) use a graphing utility to confirm your results.**

33. $f(x) = x^2 - 6x + 5$

34. $f(x) = 4x^3 - 5x$

35. $f(t) = \frac{1}{4}t^4 - 8t$

36. $f(x) = \frac{x^3 - 8x}{4}$

37. $f(x) = \frac{x + 4}{x^2}$

38. $f(x) = \frac{x^2 - 3x - 4}{x - 2}$

39. $f(x) = \cos x - \sin x, \quad (0, 2\pi)$

40. $f(x) = \frac{3}{2}\sin\left(\frac{\pi x}{2} - 1\right), \quad (0, 4)$

Motion Along a Line **In Exercises 41 and 42, the function $s(t)$ describes the motion of a particle along a line.**

(a) Find the velocity function of the particle at any time $t \geq 0$.

(b) Identify the time interval(s) on which the particle is moving in a positive direction.

(c) Identify the time interval(s) on which the particle is moving in a negative direction.

(d) Identify the time(s) at which the particle changes direction.

41. $s(t) = 3t - 2t^2$

42. $s(t) = 6t^3 - 8t + 3$

Finding Points of Inflection **In Exercises 43–48, find any points of inflection and discuss the concavity of the graph of the function.**

43. $f(x) = x^3 - 9x^2$

44. $f(x) = 6x^4 - x^2$

45. $g(x) = x\sqrt{x + 5}$

46. $f(x) = 3x - 5x^3$

47. $f(x) = x + \cos x, \quad [0, 2\pi]$

48. $f(x) = \tan\frac{x}{4}, \quad (0, 2\pi)$

Using the Second Derivative Test **In Exercises 49–54, find all relative extrema of the function. Use the Second Derivative Test where applicable.**

49. $f(x) = (x + 9)^2$

50. $f(x) = x^4 - 2x^2 + 6$

51. $g(x) = 2x^2(1 - x^2)$

52. $h(t) = t - 4\sqrt{t + 1}$

53. $f(x) = 2x + \frac{18}{x}$

54. $h(x) = x - 2\cos x, \quad [0, 4\pi]$

Think About It **In Exercises 55 and 56, sketch the graph of a function f having the given characteristics.**

55.
$f(0) = f(6) = 0$
$f'(3) = f'(5) = 0$
$f'(x) > 0$ for $x < 3$
$f'(x) > 0$ for $3 < x < 5$
$f'(x) < 0$ for $x > 5$
$f''(x) < 0$ for $x < 3$ or $x > 4$
$f''(x) > 0$ for $3 < x < 4$

56.
$f(0) = 4, f(6) = 0$
$f'(x) < 0$ for $x < 2$ or $x > 4$
$f'(2)$ does not exist.
$f'(4) = 0$
$f'(x) > 0$ for $2 < x < 4$
$f''(x) < 0$ for $x \neq 2$

57. Writing A newspaper article states that "The rate of growth of the national deficit is decreasing." What does this mean? What does it imply about the graph of the deficit as a function of time?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

58. Inventory Cost The cost of inventory C depends on the ordering and storage costs according to the inventory model

$$C = \left(\frac{Q}{x}\right)s + \left(\frac{x}{2}\right)r.$$

Determine the order size that will minimize the cost, assuming that sales occur at a constant rate, Q is the number of units sold per year, r is the cost of storing one unit for one year, s is the cost of placing an order, and x is the number of units per order.

59. Modeling Data Outlays for national defense D (in billions of dollars) for 2011 through 2019 are shown in the table, where t is the time in years, with $t = 11$ corresponding to 2011. *(Source: U.S. Office of Management and Budget)*

t	11	12	13	14	15
D	705.6	677.9	633.4	603.5	589.7

t	16	17	18	19
D	593.4	598.7	631.1	686.0

(a) Use the regression capabilities of a graphing utility to find a model of the form $D = at^4 + bt^3 + ct^2 + dt + e$ for the data.

(b) Use a graphing utility to plot the data and graph the model.

(c) For the years shown in the table, when does the model indicate that the outlay for national defense was at a maximum? When was it at a minimum?

(d) For the years shown in the table, when does the model indicate that the outlay for national defense was increasing at the greatest rate?

60. Modeling Data The manager of a store recorded the annual sales S (in thousands of dollars) of a product over a period of 7 years, as shown in the table, where t is the time in years, with $t = 14$ corresponding to 2014.

t	14	15	16	17	18	19	20
S	8.1	7.3	7.8	9.2	11.3	12.8	12.9

(a) Use the regression capabilities of a graphing utility to find a model of the form $S = at^3 + bt^2 + ct + d$ for the data.

(b) Use a graphing utility to plot the data and graph the model.

(c) Use calculus and the model to find the time t when sales were increasing at the greatest rate.

(d) Do you think the model would be accurate for predicting future sales? Explain.

Finding a Limit **In Exercises 61–70, find the limit, if it exists.**

61. $\lim_{x\to\infty}\left(8 + \frac{1}{x}\right)$

62. $\lim_{x\to-\infty}\frac{1 - 4x}{x + 1}$

63. $\lim_{x\to\infty}\frac{x^2}{1 - 8x^2}$

64. $\lim_{x\to-\infty}\frac{9x^3 + 5}{7x^4}$

65. $\lim_{x\to-\infty}\frac{3x^2}{x + 5}$

66. $\lim_{x\to-\infty}\frac{\sqrt{x^2 + x}}{-2x}$

67. $\lim_{x\to\infty}\frac{5\cos x}{x}$

68. $\lim_{x\to\infty}\frac{x^3}{\sqrt{x^2 + 2}}$

69. $\lim_{x\to-\infty}\frac{6x}{x + \cos x}$

70. $\lim_{x\to-\infty}\frac{x}{2\sin x}$

Finding Horizontal Asymptotes Using Technology **In Exercises 71–74, use a graphing utility to graph the function and identify any horizontal asymptotes.**

71. $f(x) = \frac{3}{x} + 4$

72. $g(x) = \frac{5x^2}{x^2 + 2}$

73. $f(x) = \frac{x}{\sqrt{x^2 + 6}}$

74. $f(x) = \frac{\sqrt{4x^2 - 1}}{8x + 1}$

Analyzing the Graph of a Function **In Exercises 75–84, analyze and sketch a graph of the function. Label any intercepts, relative extrema, points of inflection, and asymptotes. Use a graphing utility to verify your results.**

75. $f(x) = 4x - x^2$

76. $f(x) = x^4 - 2x^2 + 6$

77. $f(x) = x\sqrt{16 - x^2}$

78. $f(x) = (x^2 - 4)^2$

79. $f(x) = x^{1/3}(x + 3)^{2/3}$

80. $f(x) = (x - 3)(x + 2)^3$

81. $f(x) = \frac{5 - 3x}{x - 2}$

82. $f(x) = \frac{2x}{1 + x^2}$

83. $f(x) = x^3 + x + \frac{4}{x}$

84. $f(x) = x^2 + \frac{1}{x}$

85. Finding Numbers Find two positive numbers such that the sum of twice the first number and three times the second number is 216 and the product is a maximum.

86. Minimum Distance Find the point on the graph of $f(x) = \sqrt{x}$ that is closest to the point $(6, 0)$.

87. Maximum Area A rancher has 400 feet of fencing with which to enclose two adjacent rectangular corrals (see figure). What dimensions should be used so that the enclosed area will be a maximum?



88. Maximum Area Find the dimensions of the rectangle of maximum area, with sides parallel to the coordinate axes, that can be inscribed in the ellipse given by

$$\frac{x^2}{144} + \frac{y^2}{16} = 1.$$

89. Minimum Length A right triangle in the first quadrant has the coordinate axes as sides, and the hypotenuse passes through the point $(1, 8)$. Find the vertices of the triangle such that the length of the hypotenuse is minimum.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

90. Minimum Length The wall of a building is to be braced by a beam that must pass over a parallel fence 5 feet high and 4 feet from the building. Find the length of the shortest beam that can be used.

91. Maximum Length Find the length of the longest pipe that can be carried level around a right-angle corner at the intersection of two corridors of widths 4 feet and 6 feet.

92. Maximum Length A hallway of width 6 feet meets a hallway of width 9 feet at right angles. Find the length of the longest pipe that can be carried level around this corner. [*Hint:* If L is the length of the pipe, show that

$$L = 6 \csc \theta + 9 \csc\left(\frac{\pi}{2} - \theta\right)$$

where θ is the angle between the pipe and the wall of the narrower hallway.]

93. Maximum Volume Find the volume of the largest right circular cone that can be inscribed in a sphere of radius r.



94. Maximum Volume Find the volume of the largest right circular cylinder that can be inscribed in a sphere of radius r.

Using Newton's Method **In Exercises 95–98, use Newton's Method to approximate the zero(s) of the function. Continue the iterations until two successive approximations differ by less than 0.001. Then find the zero(s) using a graphing utility and compare the results.**

95. $f(x) = x^3 - 3x - 1$

96. $f(x) = x^3 + 2x + 1$

97. $f(x) = x^4 + x^3 - 3x^2 + 2$

98. $f(x) = 3\sqrt{x - 1} - x$

Points of Intersection **In Exercises 99 and 100, apply Newton's Method to approximate the x-value(s) of the indicated point(s) of intersection of the two graphs. Continue the iterations until two successive approximations differ by less than 0.001. [*Hint:* Let $h(x) = f(x) - g(x)$.]**

99. $f(x) = 1 - x$
$g(x) = x^5 + 2$



100. $f(x) = \sin x$
$g(x) = x^2 - 2x + 1$



Comparing Δy and dy **In Exercises 101 and 102, use the information to find and compare Δy and dy.**

	Function	x-Value	Differential of x
101.	$y = 4x^3$	$x = 2$	$\Delta x = dx = 0.1$
102.	$y = x^2 - 5x$	$x = -3$	$\Delta x = dx = 0.01$

Finding a Differential **In Exercises 103 and 104, find the differential dy of the given function.**

103. $y = x(1 - \cos x)$

104. $y = \sqrt{36 - x^2}$

105. Approximating Function Values Use differentials to approximate the value of (a) $\sqrt{63.9}$ and (b) $(2.02)^4$. Compare your answers with that of a calculator.

106. Volume and Surface Area The radius of a sphere is measured as 9 centimeters, with a possible error of 0.025 centimeter.

(a) Use differentials to approximate the possible propagated error in computing the volume of the sphere.

(b) Use differentials to approximate the possible propagated error in computing the surface area of the sphere.

(c) Approximate the percent errors in parts (a) and (b).

Building on Concepts

107. The figures show a rectangle, a circle, and a semicircle inscribed in a triangle bounded by the coordinate axes and the first-quadrant portion of the line with intercepts $(3, 0)$ and $(0, 4)$. Find the dimensions of each inscribed figure such that its area is maximum. State whether calculus was helpful in finding the required dimensions. Explain your reasoning.



Figure for 107

108. Find the point on the graph of $y = 1/(1 + x^2)$ where the tangent line has the greatest slope, and the point where the tangent line has the least slope (see figure).



Figure for 108

109. Find a, b, and c so that the function f satisfies the hypotheses of the Mean Value Theorem on the interval $[0, 3]$.

$$f(x) = \begin{cases} 1, & x = 0 \\ ax + b, & 0 < x \le 1 \\ x^2 + 4x + c, & 1 < x \le 3 \end{cases}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.S. Problem Solving

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

1. Relative Extrema Graph the fourth-degree polynomial

$$p(x) = x^4 + ax^2 + 1$$

for various values of the constant a.

(a) Determine the values of a for which p has exactly one relative minimum.

(b) Determine the values of a for which p has exactly one relative maximum.

(c) Determine the values of a for which p has exactly two relative minima.

(d) Show that the graph of p cannot have exactly two relative extrema.

2. Relative Minimum Let

$$f(x) = \frac{c}{x} + x^2.$$

Determine all values of the constant c such that f has a relative minimum, but no relative maximum.

3. Points of Inflection

(a) Let

$$f(x) = ax^2 + bx + c, \quad a \neq 0$$

be a quadratic polynomial. How many points of inflection does the graph of f have?

(b) Let

$$f(x) = ax^3 + bx^2 + cx + d, \quad a \neq 0$$

be a cubic polynomial. How many points of inflection does the graph of f have?

(c) Suppose the function $y = f(x)$ satisfies the equation

$$\frac{dy}{dx} = ky\left(1 - \frac{y}{L}\right)$$

where k and L are positive constants. Show that the graph of f has a point of inflection at the point where $y = L/2$. (This equation is called the **logistic differential equation.**)

4. Proof

(a) Prove that $\lim_{x\to\infty} x^2 = \infty$.

(b) Prove that $\lim_{x\to\infty} \frac{1}{x^2} = 0$.

(c) Let L be a real number. Prove that if $\lim_{x\to\infty} f(x) = L$, then

$$\lim_{y\to 0^+} f\left(\frac{1}{y}\right) = L.$$

5. Darboux's Theorem Prove **Darboux's Theorem:** Let f be differentiable on the closed interval $[a, b]$ such that $f'(a) = y_1$ and $f'(b) = y_2$. If d lies between y_1 and y_2, then there exists c in (a, b) such that $f'(c) = d$.

6. Illumination The amount of illumination of a surface is proportional to the intensity of the light source, inversely proportional to the square of the distance from the light source, and proportional to $\sin\theta$, where θ is the angle at which the light strikes the surface. A rectangular room measures 10 feet by 24 feet, with a 10-foot ceiling (see figure). Determine the height at which the light should be placed to allow the corners of the floor to receive as much light as possible.



7. Minimum Distance Consider a room in the shape of a cube, 4 meters on each side. A bug at point P wants to walk to point Q at the opposite corner, as shown in the figure. Use calculus to determine the shortest path. Explain how you can solve this problem without calculus. (*Hint:* Consider the two walls as one wall.)



Figure for 7



Figure for 8

8. Areas of Triangles The line joining P and Q crosses the two parallel lines, as shown in the figure. The point R is d units from P. How far from Q should the point S be positioned so that the sum of the areas of the two shaded triangles is a minimum? So that the sum is a maximum?

9. Extended Mean Value Theorem Prove the **Extended Mean Value Theorem:** If f and f' are continuous on the closed interval $[a, b]$, and if f'' exists in the open interval (a, b), then there exists a number c in (a, b) such that

$$f(b) = f(a) + f'(a)(b - a) + \frac{1}{2}f''(c)(b - a)^2.$$

10. Mean Value Theorem Determine the values a, b, c, and d such that the function f satisfies the hypotheses of the Mean Value Theorem on the interval $[-1, 2]$.

$$f(x) = \begin{cases} a, & x = -1 \\ 2, & -1 < x \leq 0 \\ bx^2 + c, & 0 < x \leq 1 \\ dx + 4, & 1 < x \leq 2 \end{cases}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

4 Integration

GO DIGITAL

4.1 Antiderivatives and Indefinite Integration
4.2 Area
4.3 Riemann Sums and Definite Integrals
4.4 The Fundamental Theorem of Calculus
4.5 Integration by Substitution

CalcView®



CalcChat®


Chapter 4
Section 2
Exercise 31
GO
Δx = (5 − 2)/6 = 1/2
Left endpoints:
Area ≈ 1/2[5 + 9 + 14 + 20 + 27 + 35] = 55
Right endpoints:
Area ≈ 1/2[9 + 14 + 20 + 27 + 35 + 44] = 149/2 = 74.5
55 < Area < 74.5
PREV. 21 23 25 27 29 31 33 35 37 39 41 NEXT

4.5 Electricity *(Exercise 88, p. 307)*

4.4 The Speed of Sound *(Example 5, p. 286)*

left, TWStock/Shutterstock.com; right, APFootage/Alamy Stock Photo
Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322
Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

4.1 Antiderivatives and Indefinite Integration

GO DIGITAL

- **Write the general solution of a differential equation and use indefinite integral notation for antiderivatives.**
- **Use basic integration rules to find antiderivatives.**
- **Find a particular solution of a differential equation.**

Antiderivatives

To find a function F whose derivative is $f(x) = 3x^2$, you might use your knowledge of derivatives to conclude that

$$F(x) = x^3 \quad \text{because} \quad \frac{d}{dx}[x^3] = 3x^2.$$

The function F is an *antiderivative* of f.

Definition of Antiderivative

A function F is an **antiderivative** of f on an interval I when $F'(x) = f(x)$ for all x in I.

Note that F is called *an* antiderivative of f rather than *the* antiderivative of f. To see why, observe that

$$F_1(x) = x^3, \quad F_2(x) = x^3 - 5, \quad \text{and} \quad F_3(x) = x^3 + 97$$

are all antiderivatives of $f(x) = 3x^2$. In fact, for any constant C, the function $F(x) = x^3 + C$ is an antiderivative of f.

Exploration

Finding Antiderivatives

For each derivative, describe the original function F.

a. $F'(x) = 2x$

b. $F'(x) = x$

c. $F'(x) = x^2$

d. $F'(x) = \dfrac{1}{x^2}$

e. $F'(x) = \dfrac{1}{x^3}$

f. $F'(x) = \cos x$

What strategy did you use to find F?

THEOREM 4.1 Representation of Antiderivatives

If F is an antiderivative of f on an interval I, then G is an antiderivative of f on the interval I if and only if G is of the form $G(x) = F(x) + C$ for all x in I, where C is a constant.

Proof The proof of Theorem 4.1 in one direction is straightforward. That is, if $G(x) = F(x) + C$, $F'(x) = f(x)$, and C is a constant, then

$$G'(x) = \frac{d}{dx}[F(x) + C] = F'(x) + 0 = f(x).$$

To prove this theorem in the other direction, assume that G is an antiderivative of f. Define a function H such that

$$H(x) = G(x) - F(x).$$

For any two points a and b $(a < b)$ in the interval, H is continuous on $[a, b]$ and differentiable on (a, b). By the Mean Value Theorem,

$$H'(c) = \frac{H(b) - H(a)}{b - a}$$

for some c in (a, b). However, $H'(c) = 0$, so $H(a) = H(b)$. Because a and b are arbitrary points in the interval, you know that H is a constant function C. So, $G(x) - F(x) = C$ and it follows that $G(x) = F(x) + C$. ∎

Big Ideas of Calculus

In this chapter, you will study integration. Integration, like differentiation, is a major theme of calculus. Interestingly, as you will learn in the Fundamental Theorem of Calculus, these two major themes have an inverse relationship. As part of your study of integration, you will examine the areas of plane regions.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Using Theorem 4.1, you can represent the entire family of antiderivatives of a function by adding a constant to a *known* antiderivative. For example, knowing that

$$D_x[x^2] = 2x$$

you can represent the family of *all* antiderivatives of $f(x) = 2x$ by

$$G(x) = x^2 + C \qquad \text{Family of all antiderivatives of } f(x) = 2x$$

where C is a constant. The constant C is called the **constant of integration.** The family of functions represented by G is the **general antiderivative** of f, and $G(x) = x^2 + C$ is the **general solution** of the *differential equation*

$$G'(x) = 2x. \qquad \text{Differential equation}$$

A **differential equation** in x and y is an equation that involves x, y, and derivatives of y. For instance,

$$y' = 3x \quad \text{and} \quad y' = x^2 + 1$$

are examples of differential equations.



Functions of the form $y = 2x + C$
Figure 4.1

EXAMPLE 1 Solving a Differential Equation

Find the general solution of the differential equation $dy/dx = 2$.

Solution To begin, you need to find a function whose derivative is 2. One such function is

$$y = 2x. \qquad 2x \text{ is } \textit{an} \text{ antiderivative of } 2.$$

Now, use Theorem 4.1 to conclude that the general solution of the differential equation $dy/dx = 2$ is

$$y = 2x + C. \qquad \text{General solution}$$

The graphs of several functions of the form $y = 2x + C$ are shown in Figure 4.1. ■

When solving a differential equation of the form

$$\frac{dy}{dx} = f(x) \qquad \text{Differential equation}$$

it is convenient to write it in the equivalent differential form

$$dy = f(x)\,dx. \qquad \text{Equation in differential form}$$

The operation of finding all solutions of this equation is called **antidifferentiation** (or **indefinite integration**) and is denoted by an integral sign $\int$. The general solution is denoted by

Variable of integration — Constant of integration

$$y = \int f(x)\,dx = F(x) + C.$$

Integrand — An antiderivative of $f(x)$

REMARK In this text, the notation $\int f(x)\,dx = F(x) + C$ means that F is an antiderivative of f *on an interval*.

The expression $\int f(x)\,dx$ is read as the *antiderivative of f with respect to x*. So, the differential dx serves to identify x as the variable of integration. The term **indefinite integral** is a synonym for antiderivative.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Basic Integration Rules

The inverse nature of integration and differentiation can be verified by substituting $F'(x)$ for $f(x)$ in the indefinite integration definition to obtain

$$\int F'(x)\,dx = F(x) + C.$$ Integration is the "inverse" of differentiation.

Moreover, if $\int f(x)\,dx = F(x) + C$, then

$$\frac{d}{dx}\left[\int f(x)\,dx\right] = f(x).$$ Differentiation is the "inverse" of integration.

These two equations allow you to obtain integration formulas directly from differentiation formulas, as shown in the following summary.

Basic Integration Rules

Differentiation Formula	Integration Formula	
$\frac{d}{dx}[C] = 0$	$\int 0\,dx = C$	
$\frac{d}{dx}[kx] = k$	$\int k\,dx = kx + C$	
$\frac{d}{dx}[kf(x)] = kf'(x)$	$\int kf(x)\,dx = k\int f(x)\,dx$	
$\frac{d}{dx}[f(x) \pm g(x)] = f'(x) \pm g'(x)$	$\int [f(x) \pm g(x)]\,dx = \int f(x)\,dx \pm \int g(x)\,dx$	
$\frac{d}{dx}[x^n] = nx^{n-1}$	$\int x^n\,dx = \frac{x^{n+1}}{n+1} + C, \quad n \neq -1$	Power Rule
$\frac{d}{dx}[\sin x] = \cos x$	$\int \cos x\,dx = \sin x + C$	
$\frac{d}{dx}[\cos x] = -\sin x$	$\int \sin x\,dx = -\cos x + C$	
$\frac{d}{dx}[\tan x] = \sec^2 x$	$\int \sec^2 x\,dx = \tan x + C$	
$\frac{d}{dx}[\sec x] = \sec x \tan x$	$\int \sec x \tan x\,dx = \sec x + C$	
$\frac{d}{dx}[\cot x] = -\csc^2 x$	$\int \csc^2 x\,dx = -\cot x + C$	
$\frac{d}{dx}[\csc x] = -\csc x \cot x$	$\int \csc x \cot x\,dx = -\csc x + C$	

Note that the Power Rule for Integration has the restriction that $n \neq -1$. The integration formula for

$$\int \frac{1}{x}\,dx$$ Antiderivative of the reciprocal function

must wait until the introduction of the natural logarithmic function in Chapter 5.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

REMARK In Example 2, note that the general pattern of integration is similar to that of differentiation.

Original integral
⇩
Rewrite
⇩
Integrate
⇩
Simplify

EXAMPLE 2 Describing Antiderivatives

$$\int 3x\,dx = 3\int x\,dx \qquad \text{Constant Multiple Rule}$$
$$= 3\int x^1\,dx \qquad \text{Rewrite } x \text{ as } x^1.$$
$$= 3\left(\frac{x^2}{2}\right) + C \qquad \text{Power Rule } (n = 1)$$
$$= \frac{3}{2}x^2 + C \qquad \text{Simplify.}$$

The antiderivatives of $3x$ are of the form $\frac{3}{2}x^2 + C$, where C is any constant. ■

When finding indefinite integrals, a strict application of the basic integration rules tends to produce complicated constants of integration. For instance, in Example 2, the solution could have been written as

$$\int 3x\,dx = 3\int x\,dx = 3\left(\frac{x^2}{2} + C\right) = \frac{3}{2}x^2 + 3C.$$

Because C represents *any* constant, it is both cumbersome and unnecessary to write $3C$ as the constant of integration. So, $\frac{3}{2}x^2 + 3C$ is written in the simpler form $\frac{3}{2}x^2 + C$.

EXAMPLE 3 Rewriting Before Integrating

See LarsonCalculus.com for an interactive version of this type of example.

	Original Integral	Rewrite	Integrate	Simplify
a.	$\int \frac{1}{x^3}\,dx$	$\int x^{-3}\,dx$	$\frac{x^{-2}}{-2} + C$	$-\frac{1}{2x^2} + C$
b.	$\int \sqrt{x}\,dx$	$\int x^{1/2}\,dx$	$\frac{x^{3/2}}{3/2} + C$	$\frac{2}{3}x^{3/2} + C$
c.	$\int 2\sin x\,dx$	$2\int \sin x\,dx$	$2(-\cos x) + C$	$-2\cos x + C$

REMARK The basic integration rules allow you to integrate any polynomial function.

EXAMPLE 4 Integrating Polynomial Functions

a. $\int dx = \int 1\,dx$ Integrand is understood to be 1.

$= x + C$ Constant Rule

b. $\int (x + 2)\,dx = \int x\,dx + \int 2\,dx$ Sum Rule

$= \frac{x^2}{2} + C_1 + 2x + C_2$ Power and Constant Rules

$= \frac{x^2}{2} + 2x + C$ $C = C_1 + C_2$

The second line in the solution is usually omitted.

c. $\int (3x^4 - 5x^2 + x)\,dx = 3\left(\frac{x^5}{5}\right) - 5\left(\frac{x^3}{3}\right) + \frac{x^2}{2} + C$

$= \frac{3}{5}x^5 - \frac{5}{3}x^3 + \frac{1}{2}x^2 + C$ ■

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

One of the most important steps in integration is *rewriting the integrand* in a form that fits one of the basic integration rules. To further illustrate this point, note how the integrands are rewritten in the next three examples.

EXAMPLE 5 Rewriting Before Integrating

$$\int \frac{x+1}{\sqrt{x}}\,dx = \int \left(\frac{x}{\sqrt{x}} + \frac{1}{\sqrt{x}}\right) dx \qquad \text{Rewrite as two fractions.}$$

$$= \int (x^{1/2} + x^{-1/2})\,dx \qquad \text{Rewrite with rational exponents.}$$

$$= \frac{x^{3/2}}{3/2} + \frac{x^{1/2}}{1/2} + C \qquad \text{Integrate.}$$

$$= \frac{2}{3}x^{3/2} + 2x^{1/2} + C \qquad \text{Simplify.}$$

When integrating quotients, do not integrate the numerator and denominator separately. This is no more valid in integration than it is in differentiation. For instance, in Example 5, be sure you understand that

$$\int \frac{x+1}{\sqrt{x}}\,dx \neq \frac{\int (x+1)\,dx}{\int \sqrt{x}\,dx}.$$

EXAMPLE 6 Rewriting Before Integrating

$$\int \frac{\sin x}{\cos^2 x}\,dx = \int \left(\frac{1}{\cos x}\right)\left(\frac{\sin x}{\cos x}\right) dx \qquad \text{Rewrite as a product.}$$

$$= \int \sec x \tan x\,dx \qquad \text{Rewrite using trigonometric identities.}$$

$$= \sec x + C \qquad \text{Integrate.}$$

REMARK Recall from trigonometry that

$$\sec x = \frac{1}{\cos x}$$

and

$$\tan x = \frac{\sin x}{\cos x}.$$

EXAMPLE 7 Rewriting Before Integrating

	Original Integral	Rewrite	Integrate	Simplify
a.	$\int \frac{2}{\sqrt{x}}\,dx$	$2\int x^{-1/2}\,dx$	$2\left(\frac{x^{1/2}}{1/2}\right) + C$	$4x^{1/2} + C$
b.	$\int (t^2+1)^2\,dt$	$\int (t^4 + 2t^2 + 1)\,dt$	$\frac{t^5}{5} + 2\left(\frac{t^3}{3}\right) + t + C$	$\frac{1}{5}t^5 + \frac{2}{3}t^3 + t + C$
c.	$\int \frac{x^3+3}{x^2}\,dx$	$\int (x + 3x^{-2})\,dx$	$\frac{x^2}{2} + 3\left(\frac{x^{-1}}{-1}\right) + C$	$\frac{1}{2}x^2 - \frac{3}{x} + C$
d.	$\int \sqrt[3]{x}(x-4)\,dx$	$\int (x^{4/3} - 4x^{1/3})\,dx$	$\frac{x^{7/3}}{7/3} - 4\left(\frac{x^{4/3}}{4/3}\right) + C$	$\frac{3}{7}x^{7/3} - 3x^{4/3} + C$

As you do the exercises, note that you can check your answer to an antidifferentiation problem by differentiating. For instance, in Example 7(a), you can check that $4x^{1/2} + C$ is the correct antiderivative by differentiating the answer to obtain

$$D_x[4x^{1/2} + C] = 4\left(\frac{1}{2}\right)x^{-1/2} = \frac{2}{\sqrt{x}}. \qquad \text{Use differentiation to check antiderivative.}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The particular solution that satisfies the initial condition $F(2) = 4$ is $F(x) = x^3 - x - 2$.

Figure 4.2

GO DIGITAL



The particular solution that satisfies the initial condition $F(1) = 0$ is $F(x) = -(1/x) + 1, x > 0$.

Figure 4.3

Initial Conditions and Particular Solutions

You have already seen that the equation $y = \int f(x)\,dx$ has many solutions (each differing from the others by a constant). This means that the graphs of any two antiderivatives of f are vertical translations of each other. For example, Figure 4.2 shows the graphs of several antiderivatives of the form

$$y = \int (3x^2 - 1)\,dx = x^3 - x + C \qquad \text{General solution}$$

for various integer values of C. Each of these antiderivatives is a solution of the differential equation

$$\frac{dy}{dx} = 3x^2 - 1. \qquad \text{Differential equation}$$

In many applications of integration, you are given enough information to determine a **particular solution.** To do this, you need only know the value of $y = F(x)$ for one value of x. This information is called an **initial condition.** For example, in Figure 4.2, only one curve passes through the point $(2, 4)$. To find this curve, use the general solution

$$F(x) = x^3 - x + C \qquad \text{General solution}$$

and the initial condition

$$F(2) = 4. \qquad \text{Initial condition}$$

By using the initial condition in the general solution, you can determine that

$$F(2) = 8 - 2 + C = 4$$

which implies that $C = -2$. So, the particular solution that passes through $(2, 4)$ is

$$F(x) = x^3 - x - 2. \qquad \text{Particular solution}$$

EXAMPLE 8 Finding a Particular Solution

Find the general solution of

$$F'(x) = \frac{1}{x^2}, \quad x > 0$$

and find the particular solution that satisfies the initial condition $F(1) = 0$.

Solution To find the general solution, integrate to obtain

$$\begin{aligned} F(x) &= \int \frac{1}{x^2}\,dx && F(x) = \textstyle\int F'(x)\,dx \\ &= \int x^{-2}\,dx && \text{Rewrite as a power.} \\ &= \frac{x^{-1}}{-1} + C && \text{Integrate.} \\ &= -\frac{1}{x} + C, \quad x > 0. && \text{General solution} \end{aligned}$$

Using the initial condition $F(1) = 0$, you can solve for C as shown.

$$F(1) = -\frac{1}{1} + C = 0 \quad \Rightarrow \quad C = 1$$

So, the particular solution, as shown in Figure 4.3, is

$$F(x) = -\frac{1}{x} + 1, \quad x > 0. \qquad \text{Particular solution}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

So far in this section, you have been using x as the variable of integration. In applications, it is often convenient to use a different variable. For instance, in the next example, involving *time*, the variable of integration is t.

EXAMPLE 9 Solving a Vertical Motion Problem

A ball is thrown upward with an initial velocity of 64 feet per second from an initial height of 80 feet. [Assume the acceleration is $a(t) = -32$ feet per second per second.]

a. Find the position function giving the height s as a function of the time t.

b. When does the ball hit the ground?

Solution

a. Let $t = 0$ represent the initial time. The two given initial conditions can be written as shown.

$$s(0) = 80 \qquad \text{Initial height is 80 feet.}$$
$$s'(0) = 64 \qquad \text{Initial velocity is 64 feet per second.}$$

Recall that $a(t) = s''(t)$, so integrate $s''(t) = -32$ to find the velocity function.

$$s'(t) = \int s''(t)\,dt = \int -32\,dt = -32t + C_1$$

Using the initial velocity, you obtain $s'(0) = 64 = -32(0) + C_1$, which implies that $C_1 = 64$. Next, integrate the velocity function $s'(t)$ to find the position function.

$$s(t) = \int s'(t)\,dt = \int (-32t + 64)\,dt = -16t^2 + 64t + C_2$$

Using the initial height, you obtain

$$s(0) = 80 = -16(0^2) + 64(0) + C_2$$

which implies that $C_2 = 80$. So, the position function is

$$s(t) = -16t^2 + 64t + 80. \qquad \text{Position function}$$

The graph of s is shown in Figure 4.4.



Height of a ball at time t

Figure 4.4

b. Using the position function found in part (a), you can find the time at which the ball hits the ground by solving the equation $s(t) = 0$.

$$-16t^2 + 64t + 80 = 0 \qquad \text{Set } s(t) \text{ equal to 0.}$$
$$-16(t + 1)(t - 5) = 0 \qquad \text{Factor.}$$
$$t = -1, 5 \qquad t\text{-values for which } s(t) = 0$$

Because t must be positive, you can conclude that the ball hits the ground 5 seconds after it was thrown. ■

In Example 9, note that the position function has the form

$$s(t) = -\frac{1}{2}gt^2 + v_0t + s_0 \qquad \text{Position function}$$

where g is the acceleration due to gravity, v_0 is the initial velocity, and s_0 is the initial height, as presented in Section 2.2.

Example 9 shows how to use calculus to analyze vertical motion problems in which the acceleration is determined by a gravitational force. You can use a similar strategy to analyze other linear motion problems (vertical or horizontal) in which the acceleration (or deceleration) is the result of some other force, as you will see in Exercises 65–72.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

4.1 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain what it means for a function F to be an antiderivative of a function f on an interval I.
2. Can two different functions both be antiderivatives of the same function? Explain.
3. Explain how to find a particular solution of a differential equation.
4. Describe the difference between the general solution and a particular solution of a differential equation.

Integration and Differentiation **In Exercises 5 and 6, verify the statement by showing that the derivative of the right side equals the integrand on the left side.**

5. $\int \left(-\frac{6}{x^4}\right) dx = \frac{2}{x^3} + C$
6. $\int \left(8x^3 + \frac{1}{2x^2}\right) dx = 2x^4 - \frac{1}{2x} + C$

Solving a Differential Equation **In Exercises 7–10, find the general solution of the differential equation and check the result by differentiation.**

7. $\frac{dy}{dt} = 9t^2$
8. $\frac{dy}{dt} = 5$
9. $\frac{dy}{dx} = x^{3/2}$
10. $\frac{dy}{dx} = 2x^{-3}$

Rewriting Before Integrating **In Exercises 11–14, complete the table to find the indefinite integral.**

Original Integral	Rewrite	Integrate	Simplify
11. $\int \sqrt[3]{x}\, dx$			
12. $\int \frac{1}{4x^2}\, dx$			
13. $\int \frac{1}{x\sqrt{x}}\, dx$			
14. $\int \frac{1}{(3x)^2}\, dx$			

Finding an Indefinite Integral **In Exercises 15–36, find the indefinite integral and check the result by differentiation.**

15. $\int (x + 7)\, dx$
16. $\int (13 - x)\, dx$
17. $\int (x^5 + 1)\, dx$
18. $\int (9x^8 - 2x - 6)\, dx$
19. $\int (x^{3/2} + 2x + 1)\, dx$
20. $\int \left(\sqrt{x} + \frac{1}{2\sqrt{x}}\right) dx$
21. $\int \sqrt[3]{x^2}\, dx$
22. $\int \left(\sqrt[4]{x^3} + 1\right) dx$
23. $\int \frac{1}{x^5}\, dx$
24. $\int \left(2 - \frac{3}{x^{10}}\right) dx$
25. $\int \frac{x + 6}{\sqrt{x}}\, dx$
26. $\int \frac{x^4 - 3x^2 + 5}{x^4}\, dx$
27. $\int (x + 1)(3x - 2)\, dx$
28. $\int (4t^2 + 3)^2\, dt$
29. $\int (5\cos x + 4\sin x)\, dx$
30. $\int (\sin x - 6\cos x)\, dx$
31. $\int (\csc x \cot x - 2x)\, dx$
32. $\int (\theta^2 + \sec^2\theta)\, d\theta$
33. $\int (\sec^2\theta - \sin\theta)\, d\theta$
34. $\int (\sec y)(\tan y - \sec y)\, dy$
35. $\int (\tan^2 y + 1)\, dy$
36. $\int (4x - \csc^2 x)\, dx$

Finding a Particular Solution **In Exercises 37–44, find the particular solution of the differential equation that satisfies the initial condition(s).**

37. $f'(x) = 6x,\ f(0) = 8$
38. $g'(x) = 4x^2,\ g(-1) = 3$
39. $h'(x) = 7x^6 + 5,\ h(1) = -1$
40. $f'(s) = 10s - 12s^3,\ f(3) = 2$
41. $f''(x) = 2,\ f'(2) = 5,\ f(2) = 10$
42. $f''(x) = 3x^2,\ f'(-1) = -2,\ f(2) = 3$
43. $f''(x) = x^{-3/2},\ f'(4) = 2,\ f(0) = 0$
44. $f''(x) = \sin x,\ f'(0) = 1,\ f(0) = 6$

Slope Field **In Exercises 45 and 46, a differential equation, a point, and a slope field are given. A *slope field* (or *direction field*) consists of line segments with slopes given by the differential equation. These line segments give a visual perspective of the slopes of the solutions of the differential equation. (a) Sketch two approximate solutions of the differential equation on the slope field, one of which passes through the indicated point. (To print an enlarged copy of the graph, go to *MathGraphs.com*.) (b) Use integration and the given point to find the particular solution of the differential equation and use a graphing utility to graph the solution. Compare the result with the sketch in part (a) that passes through the given point.**

45. $\frac{dy}{dx} = x^2 - 1,\ (-1, 3)$
46. $\frac{dy}{dx} = -\frac{1}{x^2},\ x > 0,\ (1, 3)$





Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Slope Field **In Exercises 47 and 48, (a) use a graphing utility to graph a slope field for the differential equation, (b) use integration and the given point to find the particular solution of the differential equation, and (c) graph the particular solution and the slope field in the same viewing window.**

47. $\frac{dy}{dx} = 2x, (-2, -2)$

48. $\frac{dy}{dx} = 2\sqrt{x}, (4, 12)$

Exploring Concepts

In Exercises 49 and 50, the graph of the derivative of a function is given. Sketch the graphs of *two* functions that have the given derivative. (There is more than one correct answer.) To print an enlarged copy of the graph, go to *MathGraphs.com*.

49.



50.



51. Consider $f(x) = \tan^2 x$ and $g(x) = \sec^2 x$. What do you notice about the derivatives of f and g? What can you conclude about the relationship between f and g?

52. **HOW DO YOU SEE IT?** Use the graph of f' shown in the figure to answer the following.



(a) Approximate the slope of f at $x = 4$. Explain.

(b) Is $f(5) - f(4) > 0$? Explain.

(c) Approximate the value of x where f is maximum. Explain.

(d) Approximate any open intervals on which the graph of f is concave upward and any open intervals on which it is concave downward. Approximate the x-coordinates of any points of inflection.

53. **Horizontal Tangent** Find a function f such that the graph of f has a horizontal tangent at $(2, 0)$ and $f''(x) = 2x$.

54. **Sketching Graphs** The graphs of f and f' each pass through the origin. Use the graph of f'' shown in the figure to sketch the graphs of f and f'. To print an enlarged copy of the graph, go to *MathGraphs.com.*



55. **Tree Growth** An evergreen nursery usually sells a certain type of shrub after 6 years of growth and shaping. The growth rate during those 6 years is approximated by $dh/dt = 1.5t + 5$, where t is the time in years and h is the height in centimeters. The seedlings are 12 centimeters tall when planted ($t = 0$).

(a) Find the height after t years.

(b) How tall are the shrubs when they are sold?

56. **Population Growth** The rate of growth dP/dt of a population of bacteria is proportional to the square root of t, where P is the population size and t is the time in days ($0 \le t \le 10$). That is,

$$\frac{dP}{dt} = k\sqrt{t}.$$

The initial size of the population is 500. After 1 day, the population has grown to 600. Estimate the population after 7 days.

Vertical Motion **In Exercises 57–59, assume the acceleration of the object is $a(t) = -32$ feet per second per second. (Neglect air resistance.)**

57. A ball is launched vertically upward from a height of 6 feet with an initial velocity of 60 feet per second. Determine its maximum height.

58. With what initial velocity must an object be launched upward (from ground level) to reach the top of the Washington Monument (approximately 550 feet)?

59. A balloon, rising vertically with a velocity of 16 feet per second, releases a sandbag at the instant it is 64 feet above the ground.

(a) How many seconds after its release will the bag strike the ground?

(b) At what velocity will the bag hit the ground?

Vertical Motion **In Exercises 60–62, assume the acceleration of the object is $a(t) = -9.8$ meters per second per second. (Neglect air resistance.)**

60. A baseball is thrown upward from a height of 2 meters with an initial velocity of 10 meters per second. Determine its maximum height.

61. With what initial velocity must an object be launched upward (from a height of 2 meters) to reach a maximum height of 200 meters?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

62. Grand Canyon

The Grand Canyon is 1800 meters deep at its deepest point. A rock is dropped from the rim above this point. How long will it take the rock to hit the canyon floor?

63. Lunar Gravity On the moon, the acceleration of a free-falling object is $a(t) = -1.6$ meters per second per second. A stone is dropped from a cliff on the moon and hits the surface of the moon 20 seconds later. How far did it fall? What was its velocity at impact?

64. Escape Velocity The minimum velocity required for an object to escape Earth's gravitational pull is obtained from the solution of the equation

$$\int v\,dv = -GM\int \frac{1}{y^2}\,dy$$

where v is the velocity of the object projected from Earth, y is the distance from the center of Earth, G is the gravitational constant, and M is the mass of Earth. Show that v and y are related by the equation

$$v^2 = v_0^2 + 2GM\left(\frac{1}{y} - \frac{1}{R}\right)$$

where v_0 is the initial velocity of the object and R is the radius of Earth.

Rectilinear Motion **In Exercises 65–68, consider a particle moving along the x-axis, where $x(t)$ is the position of the particle at time t, $x'(t)$ is its velocity, and $x''(t)$ is its acceleration.**

65. $x(t) = t^3 - 6t^2 + 9t - 2, \quad 0 \le t \le 5$

(a) Find the velocity and acceleration of the particle.

(b) Find the open t-intervals on which the particle is moving to the right.

(c) Find the velocity of the particle when the acceleration is 0.

66. Repeat Exercise 65 for the position function $x(t) = (t-1)(t-3)^2, 0 \le t \le 5$.

67. A particle moves along the x-axis at a velocity of $v(t) = 1/\sqrt{t}$, $t > 0$. At time $t = 1$, its position is $x = 4$. Find the acceleration and position functions for the particle.

68. A particle, initially at rest, moves along the x-axis such that its acceleration at time $t > 0$ is given by $a(t) = \cos t$. At time $t = 0$, its position is $x = 3$.

(a) Find the velocity and position functions for the particle.

(b) Find the values of t for which the particle is at rest.

69. Acceleration A car dealership advertises that a car takes 13 seconds to accelerate from 25 kilometers per hour to 80 kilometers per hour. Assume the acceleration is constant.

(a) Find the acceleration in meters per second per second.

(b) Find the distance the car travels during the 13 seconds.

70. Deceleration A car traveling at 45 miles per hour is brought to a stop, at constant deceleration, 132 feet from where the brakes are applied.

(a) How far has the car moved when its speed has been reduced to 30 miles per hour?

(b) How far has the car moved when its speed has been reduced to 15 miles per hour?

(c) Draw the real number line from 0 to 132. Plot the points found in parts (a) and (b). What can you conclude?

71. Acceleration At the instant the traffic light turns green, a car that has been waiting at an intersection starts with a constant acceleration of 6 feet per second per second. At the same instant, a truck traveling with a constant velocity of 30 feet per second passes the car.

(a) How far beyond its starting point will the car pass the truck?

(b) How fast will the car be traveling when it passes the truck?

72. Acceleration A fully loaded plane starting from rest has a constant acceleration while moving down a runway. The plane requires 0.7 mile of runway and a speed of 160 miles per hour in order to lift off. What is the plane's acceleration?

True or False? **In Exercises 73–78, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

73. The antiderivative of $f(x)$ is unique.

74. Each antiderivative of an nth-degree polynomial function is an $(n+1)$th-degree polynomial function.

75. If $p(x)$ is a polynomial function, then p has exactly one antiderivative whose graph contains the origin.

76. If $F(x)$ and $G(x)$ are antiderivatives of $f(x)$, then

$$F(x) = G(x) + C.$$

77. If $f'(x) = g(x)$, then $\int g(x)\,dx = f(x) + C$.

78. $\int f(x)g(x)\,dx = \left(\int f(x)\,dx\right)\left(\int g(x)\,dx\right)$

79. Proof Let $s(x)$ and $c(x)$ be two functions satisfying $s'(x) = c(x)$ and $c'(x) = -s(x)$ for all x. If $s(0) = 0$ and $c(0) = 1$, prove that $[s(x)]^2 + [c(x)]^2 = 1$.

80. Think About It Find the general solution of

$$f'(x) = -2x\sin x^2.$$

PUTNAM EXAM CHALLENGE

81. Suppose f and g are non-constant, differentiable, real-valued functions defined on $(-\infty, \infty)$. Furthermore, suppose that for each pair of real numbers x and y,

$$f(x+y) = f(x)f(y) - g(x)g(y) \quad \text{and}$$
$$g(x+y) = f(x)g(y) + g(x)f(y).$$

If $f'(0) = 0$, prove that $(f(x))^2 + (g(x))^2 = 1$ for all x.

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Josemaria Toscano/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

4.2 Area

GO DIGITAL

- Use sigma notation to write and evaluate a sum.
- Describe the concept of area.
- Approximate the area of a plane region.
- Find the area of a plane region using limits.

Sigma Notation

In the preceding section, you studied antidifferentiation. In this section, you will look further into a problem introduced in Section 1.1—that of finding the area of a region in the plane. At first glance, these two ideas may seem unrelated, but you will discover in Section 4.4 that they are closely related by an extremely important theorem called the Fundamental Theorem of Calculus.

This section begins by introducing a concise notation for sums. This notation is called **sigma notation** because it uses the uppercase Greek letter sigma, written as Σ.

Sigma Notation

The sum of n terms $a_1, a_2, a_3, \ldots, a_n$ is written as

$$\sum_{i=1}^{n} a_i = a_1 + a_2 + a_3 + \cdots + a_n$$

where i is the **index of summation,** a_i is the ***i*th term** of the sum, and the **upper and lower bounds of summation** are n and 1.

REMARK The upper and lower bounds must be constant with respect to the index of summation. The lower bound, however, does not have to be 1. Any integer less than or equal to the upper bound is legitimate.

EXAMPLE 1 Using Sigma Notation

a. $\displaystyle\sum_{i=1}^{6} i = 1 + 2 + 3 + 4 + 5 + 6$

b. $\displaystyle\sum_{i=0}^{5} (i + 1) = 1 + 2 + 3 + 4 + 5 + 6$

c. $\displaystyle\sum_{j=3}^{7} j^2 = 3^2 + 4^2 + 5^2 + 6^2 + 7^2$

d. $\displaystyle\sum_{j=1}^{5} \frac{1}{\sqrt{j}} = \frac{1}{\sqrt{1}} + \frac{1}{\sqrt{2}} + \frac{1}{\sqrt{3}} + \frac{1}{\sqrt{4}} + \frac{1}{\sqrt{5}}$

e. $\displaystyle\sum_{k=1}^{n} \frac{1}{n}(k^2 + 1) = \frac{1}{n}(1^2 + 1) + \frac{1}{n}(2^2 + 1) + \cdots + \frac{1}{n}(n^2 + 1)$

f. $\displaystyle\sum_{i=1}^{n} f(x_i)\,\Delta x = f(x_1)\,\Delta x + f(x_2)\,\Delta x + \cdots + f(x_n)\,\Delta x$

From parts (a) and (b), notice that the same sum can be represented in different ways using sigma notation.

REMARK In Example 1(e), note that k is the variable and the factor $1/n$ is held constant. What factor is held constant in Example 1(f)?

Although any variable can be used as the index of summation, i, j, and k are often used. Notice in Example 1 that the index of summation does not appear in the terms of the expanded sum.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The properties of summation shown below can be derived using the Associative and Commutative Properties of Addition and the Distributive Property of Addition over Multiplication. (In the first property, k is a constant.)

1. $\sum_{i=1}^{n} ka_i = k\sum_{i=1}^{n} a_i$ **2.** $\sum_{i=1}^{n} (a_i \pm b_i) = \sum_{i=1}^{n} a_i \pm \sum_{i=1}^{n} b_i$

The next theorem lists some useful formulas for sums of powers.

THE SUM OF THE FIRST 100 INTEGERS

A teacher of Carl Friedrich Gauss (1777–1855) asked him to add all the integers from 1 to 100. When Gauss returned with the correct answer after only a few moments, the teacher could only look at him in astounded silence. This is what Gauss did.

$$\begin{array}{r} 1 + 2 + 3 + \cdots + 100 \\ 100 + 99 + 98 + \cdots + 1 \\ \hline 101 + 101 + 101 + \cdots + 101 \end{array}$$

$$\frac{100 \times 101}{2} = 5050$$

This is generalized by Theorem 4.2, Property 2, where

$$\sum_{i=1}^{100} i = \frac{100(101)}{2} = 5050.$$

THEOREM 4.2 Summation Formulas

1. $\sum_{i=1}^{n} c = cn$, c is a constant **2.** $\sum_{i=1}^{n} i = \frac{n(n+1)}{2}$

3. $\sum_{i=1}^{n} i^2 = \frac{n(n+1)(2n+1)}{6}$ **4.** $\sum_{i=1}^{n} i^3 = \frac{n^2(n+1)^2}{4}$

A proof of this theorem is given in Appendix A.

EXAMPLE 2 Evaluating a Sum

Evaluate $\sum_{i=1}^{n} \frac{i+1}{n^2}$ for $n = 10$, 100, 1000, and 10,000.

Solution Use algebra and Theorem 4.2 to simplify the sum.

$$\sum_{i=1}^{n} \frac{i+1}{n^2} = \frac{1}{n^2}\sum_{i=1}^{n} (i+1)$$ Factor the constant $1/n^2$ out of sum.

$$= \frac{1}{n^2}\left(\sum_{i=1}^{n} i + \sum_{i=1}^{n} 1\right)$$ Write as two sums.

$$= \frac{1}{n^2}\left[\frac{n(n+1)}{2} + n\right]$$ Apply Theorem 4.2.

$$= \frac{1}{n^2}\left(\frac{n^2+3n}{2}\right)$$ Simplify.

$$= \frac{n+3}{2n}$$ Simplify.

Next, use this formula to evaluate the sum for the appropriate values of n, as shown in the table below.

n	10	100	1000	10,000
$\sum_{i=1}^{n} \frac{i+1}{n^2} = \frac{n+3}{2n}$	0.65000	0.51500	0.50150	0.50015

FOR FURTHER INFORMATION

For a geometric interpretation of summation formulas, see the article "Looking at $\sum_{k=1}^{n} k$ and $\sum_{k=1}^{n} k^2$ Geometrically" by Eric Hegblom in *Mathematics Teacher*. To view this article, go to *MathArticles.com*.

In Example 2, note in the table that the sum appears to approach a limit as n increases. Although the discussion of limits at infinity in Section 3.5 applies to a variable x, where x can be any real number, many of the same results hold true for limits involving the variable n, where n is restricted to positive integer values. So, to find the limit of $(n+3)/2n$ as n approaches infinity, you can write

$$\lim_{n\to\infty} \frac{n+3}{2n} = \lim_{n\to\infty} \left(\frac{n}{2n} + \frac{3}{2n}\right) = \lim_{n\to\infty} \left(\frac{1}{2} + \frac{3}{2n}\right) = \frac{1}{2} + 0 = \frac{1}{2}.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Area

In Euclidean geometry, the simplest type of plane region is a rectangle. Although people often say that the *formula* for the area of a rectangle is

$$A = bh$$

it is actually more proper to say that this is the *definition* of the **area of a rectangle.**

From this definition, you can develop formulas for the areas of many other plane regions. For example, to determine the area of a triangle, you can form a rectangle whose area is twice that of the triangle, as shown in Figure 4.5. Once you know how to find the area of a triangle, you can determine the area of any polygon by subdividing the polygon into triangular regions, as shown in Figure 4.6.



Triangle: $A = \frac{1}{2}bh$

Figure 4.5



Parallelogram Hexagon Polygon

Figure 4.6



ARCHIMEDES (287–212 B.C.)

Archimedes used the method of exhaustion to derive formulas for the areas of ellipses, parabolic segments, and sectors of a spiral. He is considered to have been the greatest applied mathematician of antiquity.

See LarsonCalculus.com to read more of this biography.

Finding the areas of regions other than polygons is more difficult. The ancient Greeks were able to determine formulas for the areas of some general regions (principally those bounded by conics) by the *exhaustion* method. The clearest description of this method was given by Archimedes. Essentially, the method is a limiting process in which the area is squeezed between two polygons—one inscribed in the region and one circumscribed about the region.

For instance, in Figure 4.7, the area of a circular region is approximated by an n-sided inscribed polygon and an n-sided circumscribed polygon. For each value of n, the area of the inscribed polygon is less than the area of the circle, and the area of the circumscribed polygon is greater than the area of the circle. Moreover, as n increases, the areas of both polygons become better and better approximations of the area of the circle.



The exhaustion method for finding the area of a circular region

Figure 4.7

FOR FURTHER INFORMATION

For an alternative development of the formula for the area of a circle, see the article "Proof Without Words: Area of a Disk is πR^2" by Russell Jay Hendel in *Mathematics Magazine*. To view this article, go to *MathArticles.com*.

A process that is similar to that used by Archimedes to determine the area of a plane region is used in the remaining examples in this section.

Chronicle/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The Area of a Plane Region

Recall from Section 1.1 that the origins of calculus are connected to two classic problems: the tangent line problem and the area problem. Example 3 begins the investigation of the area problem.

EXAMPLE 3 Approximating the Area of a Plane Region

Use the five rectangles in Figures 4.8(a) and 4.8(b) to find *two* approximations of the area of the region lying between the graph of

$$f(x) = -x^2 + 5$$

and the x-axis between $x = 0$ and $x = 2$.



(a) The area of the parabolic region is greater than the area of the rectangles.



(b) The area of the parabolic region is less than the area of the rectangles.

Figure 4.8

Solution

a. The right endpoints of the five intervals are

$$\frac{2}{5}i \qquad \text{Right endpoints}$$

where $i = 1, 2, 3, 4, 5$. The width of each rectangle is $\frac{2}{5}$, and the height of each rectangle can be obtained by evaluating f at the right endpoint of each interval.

$$\left[0, \frac{2}{5}\right], \left[\frac{2}{5}, \frac{4}{5}\right], \left[\frac{4}{5}, \frac{6}{5}\right], \left[\frac{6}{5}, \frac{8}{5}\right], \left[\frac{8}{5}, \frac{10}{5}\right]$$

Evaluate f at the right endpoints of these intervals.

The sum of the areas of the five rectangles is

$$\overbrace{f\left(\frac{2i}{5}\right)}^{\text{Height}}\overbrace{\left(\frac{2}{5}\right)}^{\text{Width}} = \sum_{i=1}^{5} f\left(\frac{2i}{5}\right)\left(\frac{2}{5}\right) = \sum_{i=1}^{5}\left[-\left(\frac{2i}{5}\right)^2 + 5\right]\left(\frac{2}{5}\right) = \frac{162}{25} = 6.48.$$

Because each of the five rectangles lies inside the parabolic region, you can conclude that the area of the parabolic region is greater than 6.48.

b. The left endpoints of the five intervals are

$$\frac{2}{5}(i - 1) \qquad \text{Left endpoints}$$

where $i = 1, 2, 3, 4, 5$. The width of each rectangle is $\frac{2}{5}$, and the height of each rectangle can be obtained by evaluating f at the left endpoint of each interval. So, the sum is

$$\overbrace{f\left(\frac{2i-2}{5}\right)}^{\text{Height}}\overbrace{\left(\frac{2}{5}\right)}^{\text{Width}} = \sum_{i=1}^{5} f\left(\frac{2i-2}{5}\right)\left(\frac{2}{5}\right) = \sum_{i=1}^{5}\left[-\left(\frac{2i-2}{5}\right)^2 + 5\right]\left(\frac{2}{5}\right) = \frac{202}{25} = 8.08.$$

Because the parabolic region lies within the union of the five rectangular regions, you can conclude that the area of the parabolic region is less than 8.08.

By combining the results in parts (a) and (b), you can conclude that

$$6.48 < (\text{Area of region}) < 8.08.$$

By increasing the number of rectangles used in Example 3, you can obtain closer and closer approximations of the area of the region. For instance, using 25 rectangles of width $\frac{2}{25}$ each, you can conclude that

$$7.1712 < (\text{Area of region}) < 7.4912.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The region under a curve

Figure 4.9



The interval $[a, b]$ is divided into n subintervals of width $\Delta x = \dfrac{b - a}{n}$.

Figure 4.10

Finding Area by the Limit Definition

Think about the procedure used to find area in Example 3. Can this procedure be generalized to find areas under other curves? Consider the plane region shown in Figure 4.9. The upper boundary of the region is the graph of $y = f(x)$, the lower boundary is the x-axis, and the left and right boundaries are the vertical lines $x = a$ and $x = b$. Also, the function f is continuous and nonnegative on the closed interval $[a, b]$.

To approximate the area of the region, begin by subdividing the interval $[a, b]$ into n subintervals, each of width

$$\Delta x = \frac{b - a}{n}$$ Width of each subinterval

as shown in Figure 4.10. The endpoints of the intervals are

$$\overbrace{a = x_0}\quad \overbrace{x_1}\quad \overbrace{x_2}\quad \overbrace{x_n = b}$$
$$a + 0(\Delta x) < a + 1(\Delta x) < a + 2(\Delta x) < \cdots < a + n(\Delta x).$$

Because f is continuous, the Extreme Value Theorem guarantees the existence of a minimum and a maximum value of f on *each* subinterval.

$f(m_i)$ = Minimum value of f on ith subinterval

$f(M_i)$ = Maximum value of f on ith subinterval

Next, define an **inscribed rectangle** lying *inside* the ith subregion and a **circumscribed rectangle** extending *outside* the ith subregion. The height of the ith inscribed rectangle is $f(m_i)$ and the height of the ith circumscribed rectangle is $f(M_i)$. For *each* i, the area of the inscribed rectangle is less than or equal to the area of the circumscribed rectangle.

$$\begin{pmatrix}\text{Area of inscribed}\\ \text{rectangle}\end{pmatrix} = f(m_i)\,\Delta x \le f(M_i)\,\Delta x = \begin{pmatrix}\text{Area of circumscribed}\\ \text{rectangle}\end{pmatrix}$$

The sum of the areas of the inscribed rectangles is called a **lower sum,** and the sum of the areas of the circumscribed rectangles is called an **upper sum.**

$$\text{Lower sum} = s(n) = \sum_{i=1}^{n} f(m_i)\,\Delta x$$ Area of inscribed rectangles

$$\text{Upper sum} = S(n) = \sum_{i=1}^{n} f(M_i)\,\Delta x$$ Area of circumscribed rectangles

From Figure 4.11, note that the lower sum $s(n)$ is less than or equal to the upper sum $S(n)$. Moreover, the actual area of the region lies between these two sums.

$$s(n) \le (\text{Area of region}) \le S(n)$$



Area of inscribed rectangles is less than area of region.

Area of region

Area of circumscribed rectangles is greater than area of region.

Figure 4.11

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 4 Finding Upper and Lower Sums for a Region

Find the upper and lower sums for the region bounded by the graph of $f(x) = x^2$ and the x-axis between $x = 0$ and $x = 2$.

Solution To begin, partition the interval $[0, 2]$ into n subintervals, each of width

$$\Delta x = \frac{b - a}{n} = \frac{2 - 0}{n} = \frac{2}{n}.$$



Inscribed rectangles



Circumscribed rectangles

Figure 4.12

Figure 4.12 shows the endpoints of the subintervals and several inscribed and circumscribed rectangles. Because f is increasing on the interval $[0, 2]$, the minimum value on each subinterval occurs at the left endpoint, and the maximum value occurs at the right endpoint.

Left Endpoints

$$m_i = 0 + (i - 1)\left(\frac{2}{n}\right) = \frac{2(i - 1)}{n}$$

Right Endpoints

$$M_i = 0 + i\left(\frac{2}{n}\right) = \frac{2i}{n}$$

Using the left endpoints, the lower sum is

$$\begin{aligned}
s(n) &= \sum_{i=1}^{n} f(m_i)\,\Delta x && \text{Formula for lower sum}\\
&= \sum_{i=1}^{n} f\left[\frac{2(i-1)}{n}\right]\left(\frac{2}{n}\right) && \text{Substitute for } m_i.\\
&= \sum_{i=1}^{n} \left[\frac{2(i-1)}{n}\right]^2\left(\frac{2}{n}\right) && \text{Definition of } f(x)\\
&= \sum_{i=1}^{n} \left(\frac{8}{n^3}\right)(i^2 - 2i + 1) && \text{Evaluate power and factor.}\\
&= \frac{8}{n^3}\left(\sum_{i=1}^{n} i^2 - 2\sum_{i=1}^{n} i + \sum_{i=1}^{n} 1\right) && \text{Factor and write as three sums.}\\
&= \frac{8}{n^3}\left\{\frac{n(n+1)(2n+1)}{6} - 2\left[\frac{n(n+1)}{2}\right] + n\right\} && \text{Apply Theorem 4.2.}\\
&= \frac{4}{3n^3}(2n^3 - 3n^2 + n) && \text{Simplify.}\\
&= \frac{8}{3} - \frac{4}{n} + \frac{4}{3n^2}. && \text{Lower sum}
\end{aligned}$$

Using the right endpoints, the upper sum is

$$\begin{aligned}
S(n) &= \sum_{i=1}^{n} f(M_i)\,\Delta x && \text{Formula for upper sum}\\
&= \sum_{i=1}^{n} f\left(\frac{2i}{n}\right)\left(\frac{2}{n}\right) && \text{Substitute for } M_i.\\
&= \sum_{i=1}^{n} \left(\frac{2i}{n}\right)^2\left(\frac{2}{n}\right) && \text{Definition of } f(x)\\
&= \sum_{i=1}^{n} \left(\frac{8}{n^3}\right) i^2 && \text{Evaluate power and factor.}\\
&= \frac{8}{n^3}\left[\frac{n(n+1)(2n+1)}{6}\right] && \text{Apply Theorem 4.2.}\\
&= \frac{4}{3n^3}(2n^3 + 3n^2 + n) && \text{Simplify.}\\
&= \frac{8}{3} + \frac{4}{n} + \frac{4}{3n^2}. && \text{Upper sum}
\end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploration

For the region given in Example 4, evaluate the lower sum

$$s(n) = \frac{8}{3} - \frac{4}{n} + \frac{4}{3n^2}$$

and the upper sum

$$S(n) = \frac{8}{3} + \frac{4}{n} + \frac{4}{3n^2}$$

for $n = 10$, 100, and 1000. Use your results to determine the area of the region.

Example 4 illustrates some important things about lower and upper sums. First, notice that for any value of n, the lower sum is less than (or equal to) the upper sum.

$$s(n) = \frac{8}{3} - \frac{4}{n} + \frac{4}{3n^2} < \frac{8}{3} + \frac{4}{n} + \frac{4}{3n^2} = S(n) \qquad \text{(Lower sum) < (upper sum)}$$

Second, the difference between these two sums lessens as n increases. In fact, when you take the limits as $n \to \infty$, both the lower sum and the upper sum approach $\frac{8}{3}$.

$$\lim_{n\to\infty} s(n) = \lim_{n\to\infty} \left(\frac{8}{3} - \frac{4}{n} + \frac{4}{3n^2}\right) = \frac{8}{3} \qquad \text{Lower sum limit}$$

and

$$\lim_{n\to\infty} S(n) = \lim_{n\to\infty} \left(\frac{8}{3} + \frac{4}{n} + \frac{4}{3n^2}\right) = \frac{8}{3} \qquad \text{Upper sum limit}$$

The next theorem shows that the equivalence of the limits (as $n \to \infty$) of the upper and lower sums is not mere coincidence. It is true for all functions that are continuous and nonnegative on the closed interval $[a, b]$. The proof of this theorem is best left to a course in advanced calculus.

THEOREM 4.3 Limits of the Lower and Upper Sums

Let a function f be continuous and nonnegative on the interval $[a, b]$. The limits as $n \to \infty$ of both the lower and upper sums exist and are equal to each other. That is,

$$\lim_{n\to\infty} s(n) = \lim_{n\to\infty} \sum_{i=1}^{n} f(m_i)\,\Delta x \qquad \text{Limit of lower sum}$$

$$= \lim_{n\to\infty} \sum_{i=1}^{n} f(M_i)\,\Delta x$$

$$= \lim_{n\to\infty} S(n) \qquad \text{Limit of upper sum}$$

where $\Delta x = (b - a)/n$ and $f(m_i)$ and $f(M_i)$ are the minimum and maximum values of f on the ith subinterval.

In Theorem 4.3, the same limit is attained for both the minimum value $f(m_i)$ and the maximum value $f(M_i)$. So, it follows from the Squeeze Theorem (Theorem 1.8) that the choice of x in the ith subinterval does not affect the limit. This means that you are free to choose an *arbitrary* x-value in the ith subinterval, as shown in the *definition of the area of a region in the plane.*

Definition of the Area of a Region in the Plane

Let a function f be continuous and nonnegative on the interval $[a, b]$. (See Figure 4.13.) The area of the region bounded by the graph of f, the x-axis, and the vertical lines $x = a$ and $x = b$ is

$$\text{Area} = \lim_{n\to\infty} \sum_{i=1}^{n} f(c_i)\,\Delta x$$

where $x_{i-1} \le c_i \le x_i$ and

$$\Delta x = \frac{b - a}{n}.$$



The width of the ith subinterval is $\Delta x = x_i - x_{i-1}$.

Figure 4.13

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The area of the region bounded by the graph of f, the x-axis, $x = 0$, and $x = 1$ is $\frac{1}{4}$.
Figure 4.14

EXAMPLE 5 Finding Area by the Limit Definition

Find the area of the region bounded by the graph of $f(x) = x^3$, the x-axis, and the vertical lines $x = 0$ and $x = 1$, as shown in Figure 4.14.

Solution Note that the function f is continuous and nonnegative on the interval $[0, 1]$. So, begin by partitioning the interval $[0, 1]$ into n subintervals, each of width $\Delta x = 1/n$. According to the definition of area, you can choose any x-value in the ith subinterval. For this example, the right endpoints $c_i = i/n$ are convenient.

$$\begin{aligned}
\text{Area} &= \lim_{n\to\infty} \sum_{i=1}^{n} f(c_i)\,\Delta x && \text{Limit definition of area} \\
&= \lim_{n\to\infty} \sum_{i=1}^{n} \left(\frac{i}{n}\right)^3 \left(\frac{1}{n}\right) && \text{Right endpoints: } c_i = \frac{i}{n} \\
&= \lim_{n\to\infty} \frac{1}{n^4} \sum_{i=1}^{n} i^3 && \text{Factor constant } \frac{1}{n^4} \text{ out of sum.} \\
&= \lim_{n\to\infty} \frac{1}{n^4} \left[\frac{n^2(n+1)^2}{4}\right] && \text{Theorem 4.2, Property 4} \\
&= \lim_{n\to\infty} \left(\frac{1}{4} + \frac{1}{2n} + \frac{1}{4n^2}\right) && \text{Simplify.} \\
&= \frac{1}{4} && \text{Evaluate limit.}
\end{aligned}$$

The area of the region is $\frac{1}{4}$.

EXAMPLE 6 Finding Area by the Limit Definition

See LarsonCalculus.com for an interactive version of this type of example.



The area of the region bounded by the graph of f, the x-axis, $x = 1$, and $x = 2$ is $\frac{5}{3}$.
Figure 4.15

Find the area of the region bounded by the graph of $f(x) = 4 - x^2$, the x-axis, and the vertical lines $x = 1$ and $x = 2$, as shown in Figure 4.15.

Solution Note that the function f is continuous and nonnegative on the interval $[1, 2]$. So, begin by partitioning the interval into n subintervals, each of width $\Delta x = 1/n$. Choosing the right endpoint

$$c_i = a + i\Delta x = 1 + \frac{i}{n} \qquad \text{Right endpoints}$$

of each subinterval, you obtain

$$\begin{aligned}
\text{Area} &= \lim_{n\to\infty} \sum_{i=1}^{n} f(c_i)\,\Delta x && \text{Limit definition of area} \\
&= \lim_{n\to\infty} \sum_{i=1}^{n} \left[4 - \left(1 + \frac{i}{n}\right)^2\right]\left(\frac{1}{n}\right) && \text{Right endpoints: } c_i = 1 + \frac{i}{n} \\
&= \lim_{n\to\infty} \sum_{i=1}^{n} \left(3 - \frac{2i}{n} - \frac{i^2}{n^2}\right)\left(\frac{1}{n}\right) && \text{Simplify.} \\
&= \lim_{n\to\infty} \left(\frac{1}{n}\sum_{i=1}^{n} 3 - \frac{2}{n^2}\sum_{i=1}^{n} i - \frac{1}{n^3}\sum_{i=1}^{n} i^2\right) && \text{Factor and write as three sums.} \\
&= \lim_{n\to\infty} \left[3 - \left(1 + \frac{1}{n}\right) - \left(\frac{1}{3} + \frac{1}{2n} + \frac{1}{6n^2}\right)\right] && \text{Apply Theorem 4.2.} \\
&= 3 - 1 - \frac{1}{3} && \text{Evaluate limit.} \\
&= \frac{5}{3}.
\end{aligned}$$

The area of the region is $\frac{5}{3}$.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The next example looks at a region that is bounded by the y-axis (rather than by the x-axis).

EXAMPLE 7 A Region Bounded by the y-axis

Find the area of the region bounded by the graph of $f(y) = y^2$ and the y-axis for $0 \le y \le 1$, as shown in Figure 4.16.



The area of the region bounded by the graph of f and the y-axis for $0 \le y \le 1$ is $\frac{1}{3}$.
Figure 4.16

Solution When f is a continuous, nonnegative function of y, you can still use the same basic procedure shown in Examples 5 and 6. Begin by partitioning the interval $[0, 1]$ into n subintervals, each of width $\Delta y = 1/n$. Then, using the upper endpoints $c_i = i/n$, you obtain

$$\begin{aligned}
\text{Area} &= \lim_{n\to\infty} \sum_{i=1}^{n} f(c_i)\,\Delta y && \text{Limit definition of area} \\
&= \lim_{n\to\infty} \sum_{i=1}^{n} \left(\frac{i}{n}\right)^2\left(\frac{1}{n}\right) && \text{Upper endpoints: } c_i = \frac{i}{n} \\
&= \lim_{n\to\infty} \frac{1}{n^3}\sum_{i=1}^{n} i^2 && \text{Factor constant } \frac{1}{n^3} \text{ out of sum.} \\
&= \lim_{n\to\infty} \frac{1}{n^3}\left[\frac{n(n+1)(2n+1)}{6}\right] && \text{Theorem 4.2, Property 3} \\
&= \lim_{n\to\infty} \left(\frac{1}{3} + \frac{1}{2n} + \frac{1}{6n^2}\right) && \text{Simplify.} \\
&= \frac{1}{3}. && \text{Evaluate limit.}
\end{aligned}$$

The area of the region is $\frac{1}{3}$. ■

REMARK You will study other approximation methods in Section 8.6. One of the methods, the Trapezoidal Rule, is similar to the Midpoint Rule.

In Examples 5, 6, and 7, c_i is chosen to be a value that is convenient for calculating the limit. Because each limit gives the exact area for *any* c_i, there is no need to find values that give good approximations when n is small. For an *approximation*, however, you should try to find a value of c_i that gives a good approximation of the area of the ith subregion. In general, a good value to choose is the midpoint of the interval, $c_i = (x_{i-1} + x_i)/2$, and apply the **Midpoint Rule.**

$$\text{Area} \approx \sum_{i=1}^{n} f\left(\frac{x_{i-1} + x_i}{2}\right)\Delta x \qquad \text{Midpoint Rule}$$

EXAMPLE 8 Approximating Area with the Midpoint Rule

Use the Midpoint Rule with $n = 4$ to approximate the area of the region bounded by the graph of $f(x) = \sin x$ and the x-axis for $0 \le x \le \pi$, as shown in Figure 4.17.



The area of the region bounded by the graph of $f(x) = \sin x$ and the x-axis for $0 \le x \le \pi$ is about 2.052.
Figure 4.17

Solution For $n = 4$, $\Delta x = \pi/4$. The midpoints of the subregions are shown below.

$$c_1 = \frac{0 + (\pi/4)}{2} = \frac{\pi}{8} \qquad c_2 = \frac{(\pi/4) + (\pi/2)}{2} = \frac{3\pi}{8}$$

$$c_3 = \frac{(\pi/2) + (3\pi/4)}{2} = \frac{5\pi}{8} \qquad c_4 = \frac{(3\pi/4) + \pi}{2} = \frac{7\pi}{8}$$

So, the area is approximated by

$$\text{Area} \approx \sum_{i=1}^{n} f(c_i)\,\Delta x = \sum_{i=1}^{4} (\sin c_i)\left(\frac{\pi}{4}\right) = \frac{\pi}{4}\left(\sin\frac{\pi}{8} + \sin\frac{3\pi}{8} + \sin\frac{5\pi}{8} + \sin\frac{7\pi}{8}\right)$$

which is about 2.052. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

4.2 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Identify the index of summation, the upper bound of summation, and the lower bound of summation for $\sum_{i=3}^{8} (i - 4)$.
2. Find the value of n.

   (a) $\sum_{i=1}^{n} i = \frac{5(5 + 1)}{2}$ (b) $\sum_{i=1}^{n} i^2 = \frac{20(20 + 1)[2(20) + 1]}{6}$
3. Describe the methods of upper sums and lower sums in approximating the area of a region, using figures where appropriate.
4. Explain how to find the area of a plane region using limits.

Finding a Sum **In Exercises 5–10, find the sum by adding each term together. Use the summation capabilities of a graphing utility to verify your result.**

5. $\sum_{i=1}^{6} (3i + 2)$
6. $\sum_{k=3}^{9} (k^2 + 1)$
7. $\sum_{k=0}^{4} \frac{1}{k^2 + 1}$
8. $\sum_{j=2}^{5} \frac{1}{2j}$
9. $\sum_{k=0}^{7} c$
10. $\sum_{i=1}^{4} [(i - 1)^2 + (i + 1)^3]$

Using Sigma Notation **In Exercises 11–16, use sigma notation to write the sum.**

11. $\frac{1}{5(1)} + \frac{1}{5(2)} + \frac{1}{5(3)} + \cdots + \frac{1}{5(11)}$
12. $\frac{6}{2 + 1} + \frac{6}{2 + 2} + \frac{6}{2 + 3} + \cdots + \frac{6}{2 + 11}$
13. $\left[7\left(\frac{1}{6}\right) + 5\right] + \left[7\left(\frac{2}{6}\right) + 5\right] + \cdots + \left[7\left(\frac{6}{6}\right) + 5\right]$
14. $\left[1 - \left(\frac{1}{4}\right)^2\right] + \left[1 - \left(\frac{2}{4}\right)^2\right] + \cdots + \left[1 - \left(\frac{4}{4}\right)^2\right]$
15. $\left[\left(\frac{2}{n}\right)^3 - \frac{2}{n}\right]\left(\frac{2}{n}\right) + \cdots + \left[\left(\frac{2n}{n}\right)^3 - \frac{2n}{n}\right]\left(\frac{2}{n}\right)$
16. $\left[2\left(1 + \frac{3}{n}\right)^2\right]\left(\frac{3}{n}\right) + \cdots + \left[2\left(1 + \frac{3n}{n}\right)^2\right]\left(\frac{3}{n}\right)$

Evaluating a Sum **In Exercises 17–24, use the properties of summation and Theorem 4.2 to evaluate the sum. Use the summation capabilities of a graphing utility to verify your result.**

17. $\sum_{i=1}^{12} 7$
18. $\sum_{i=1}^{20} -8$
19. $\sum_{i=1}^{24} 4i$
20. $\sum_{i=1}^{16} (5i - 4)$
21. $\sum_{i=1}^{20} (i - 1)^2$
22. $\sum_{i=1}^{10} (i^2 - 1)$
23. $\sum_{i=1}^{7} i(i + 3)^2$
24. $\sum_{i=1}^{25} (i^3 - 2i)$

Evaluating a Sum **In Exercises 25–28, use the summation formulas to rewrite the expression without the summation notation. Use the result to find the sums for $n = 10$, 100, 1000, and 10,000.**

25. $\sum_{i=1}^{n} \frac{2i + 1}{n^2}$
26. $\sum_{j=1}^{n} \frac{7j + 4}{n^2}$
27. $\sum_{k=1}^{n} \frac{6k(k - 1)}{n^3}$
28. $\sum_{i=1}^{n} \frac{2i^3 - 3i}{n^4}$

Approximating the Area of a Plane Region **In Exercises 29–34, use left and right endpoints and the given number of rectangles to find two approximations of the area of the region between the graph of the function and the x-axis over the given interval.**

29. $f(x) = 2x + 5$, $[0, 2]$, 4 rectangles
30. $f(x) = 9 - x$, $[2, 4]$, 6 rectangles
31. $g(x) = 2x^2 - x - 1$, $[2, 5]$, 6 rectangles
32. $g(x) = x^2 + 1$, $[1, 3]$, 8 rectangles
33. $f(x) = \cos x$, $\left[0, \frac{\pi}{2}\right]$, 4 rectangles
34. $g(x) = \sin x$, $[0, \pi]$, 6 rectangles

Using Upper and Lower Sums **In Exercises 35 and 36, bound the area of the shaded region by approximating the upper and lower sums. Use rectangles of width 1.**

35.



36.



Finding Upper and Lower Sums for a Region **In Exercises 37–40, use upper and lower sums to approximate the area of the region using the given number of subintervals (of equal width).**

37. $y = \sqrt{x}$



38. $y = \sqrt{x} + 2$



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

39. $y = \frac{1}{x}$



40. $y = \sqrt{1 - x^2}$



Finding Upper and Lower Sums for a Region **In Exercises 41–44, find the upper and lower sums for the region bounded by the graph of the function and the x-axis on the given interval. Leave your answer in terms of n, the number of subintervals.**

	Function	Interval
41.	$f(x) = 3x$	$[0, 4]$
42.	$f(x) = 6 - 2x$	$[1, 2]$
43.	$f(x) = 5x^2$	$[0, 1]$
44.	$f(x) = 9 - x^2$	$[0, 2]$

45. Numerical Reasoning Consider a triangle of area 2 bounded by the graphs of $y = x$, $y = 0$, and $x = 2$.

(a) Sketch the region.

(b) Divide the interval $[0, 2]$ into n subintervals of equal width and show that the endpoints are

$$0 < 1\left(\frac{2}{n}\right) < \cdots < (n-1)\left(\frac{2}{n}\right) < n\left(\frac{2}{n}\right).$$

(c) Show that $s(n) = \sum_{i=1}^{n}\left[(i-1)\left(\frac{2}{n}\right)\right]\left(\frac{2}{n}\right)$.

(d) Show that $S(n) = \sum_{i=1}^{n}\left[i\left(\frac{2}{n}\right)\right]\left(\frac{2}{n}\right)$.

(e) Find $s(n)$ and $S(n)$ for $n = 5$, 10, 50, and 100.

(f) Show that $\lim_{n\to\infty} s(n) = \lim_{n\to\infty} S(n) = 2$.

46. Numerical Reasoning Consider a trapezoid of area 4 bounded by the graphs of $y = x$, $y = 0$, $x = 1$, and $x = 3$.

(a) Sketch the region.

(b) Divide the interval $[1, 3]$ into n subintervals of equal width and show that the endpoints are

$$1 < 1 + 1\left(\frac{2}{n}\right) < \cdots < 1 + (n-1)\left(\frac{2}{n}\right) < 1 + n\left(\frac{2}{n}\right).$$

(c) Show that $s(n) = \sum_{i=1}^{n}\left[1 + (i-1)\left(\frac{2}{n}\right)\right]\left(\frac{2}{n}\right)$.

(d) Show that $S(n) = \sum_{i=1}^{n}\left[1 + i\left(\frac{2}{n}\right)\right]\left(\frac{2}{n}\right)$.

(e) Find $s(n)$ and $S(n)$ for $n = 5$, 10, 50, and 100.

(f) Show that $\lim_{n\to\infty} s(n) = \lim_{n\to\infty} S(n) = 4$.

Finding Area by the Limit Definition **In Exercises 47–56, use the limit process to find the area of the region bounded by the graph of the function and the x-axis over the given interval. Sketch the region.**

47. $y = -4x + 5$, $[0, 1]$

48. $y = 3x - 2$, $[2, 5]$

49. $y = x^2 + 2$, $[0, 1]$

50. $y = 5x^2 + 1$, $[0, 2]$

51. $y = 25 - x^2$, $[1, 4]$

52. $y = 4 - x^2$, $[-2, 2]$

53. $y = 27 - x^3$, $[1, 3]$

54. $y = 2x - x^3$, $[0, 1]$

55. $y = x^2 - x^3$, $[-1, 1]$

56. $y = 2x^3 - x^2$, $[1, 2]$

Finding Area by the Limit Definition **In Exercises 57–62, use the limit process to find the area of the region bounded by the graph of the function and the y-axis over the given y-interval. Sketch the region.**

57. $f(y) = 4y$, $0 \le y \le 2$

58. $g(y) = \frac{1}{2}y$, $2 \le y \le 4$

59. $f(y) = y^2$, $0 \le y \le 5$

60. $y = 3y - y^2$, $2 \le y \le 3$

61. $g(y) = 4y^2 - y^3$, $1 \le y \le 3$

62. $h(y) = y^3 + 1$, $1 \le y \le 2$

Approximating Area with the Midpoint Rule **In Exercises 63–66, use the Midpoint Rule with $n = 4$ to approximate the area of the region bounded by the graph of the function and the x-axis over the given interval.**

63. $f(x) = x^2 + 3$, $[0, 2]$

64. $f(x) = x^2 + 4x$, $[0, 4]$

65. $f(x) = \tan x$, $\left[0, \frac{\pi}{4}\right]$

66. $f(x) = \cos x$, $\left[0, \frac{\pi}{2}\right]$

Exploring Concepts

67. Determine which value best approximates the area of the region bounded by the graph of $f(x) = 4 - x^2$ and the x-axis over the interval $[0, 2]$. Make your selection on the basis of a sketch of the region, not by performing calculations.

(a) -2 (b) 6 (c) 10 (d) 3 (e) 8

68. A function is continuous, nonnegative, concave upward, and decreasing on the interval $[0, a]$. Does using the right endpoints of the subintervals produce an overestimate or an underestimate of the area of the region bounded by the function and the x-axis?

69. Explain why the Midpoint Rule almost always results in a better area approximation in comparison to the endpoint method.

70. Does the Midpoint Rule ever give the exact area between a function and the x-axis? Explain.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

71. Graphical Reasoning Consider the region bounded by the graphs of $f(x) = 8x/(x + 1)$, $x = 0$, $x = 4$, and $y = 0$, as shown in the figure. To print an enlarged copy of the graph, go to *MathGraphs.com.*



(a) Redraw the figure, and complete and shade the rectangles representing the lower sum when $n = 4$. Find this lower sum.

(b) Redraw the figure, and complete and shade the rectangles representing the upper sum when $n = 4$. Find this upper sum.

(c) Redraw the figure, and complete and shade the rectangles whose heights are determined by the function values at the midpoint of each subinterval when $n = 4$. Find this sum using the Midpoint Rule.

(d) Verify the following formulas for approximating the area of the region using n subintervals of equal width.

$$\text{Lower sum: } s(n) = \sum_{i=1}^{n} f\left[(i-1)\frac{4}{n}\right]\left(\frac{4}{n}\right)$$

$$\text{Upper sum: } S(n) = \sum_{i=1}^{n} f\left[(i)\frac{4}{n}\right]\left(\frac{4}{n}\right)$$

$$\text{Midpoint Rule: } M(n) = \sum_{i=1}^{n} f\left[\left(i-\frac{1}{2}\right)\frac{4}{n}\right]\left(\frac{4}{n}\right)$$

(e) Use a graphing utility to create a table of values of $s(n)$, $S(n)$, and $M(n)$ for $n = 4$, 8, 20, 100, and 200.

(f) Explain why $s(n)$ increases and $S(n)$ decreases for increasing values of n, as shown in the table in part (e).

72. HOW DO YOU SEE IT? The function shown in the graph below is increasing on the interval $[1, 4]$. The interval is divided into 12 subintervals.



(a) Find the left endpoints of the first and last subintervals.

(b) Find the right endpoints of the first two subintervals.

(c) When using the right endpoints, do the rectangles lie above or below the graph of the function?

(d) What can you conclude about the heights of the rectangles when the function is constant on the given interval?

True or False? **In Exercises 73 and 74, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

73. The sum of the first n positive integers is $n(n + 1)/2$.

74. If f is continuous and nonnegative on $[a, b]$, then the limits as $n \to \infty$ of its lower sum $s(n)$ and upper sum $S(n)$ both exist and are equal.

75. Writing Use the figure to write a short paragraph explaining why the formula $1 + 2 + \cdots + n = \frac{1}{2}n(n + 1)$ is valid for all positive integers n.



Figure for 75



Figure for 76

76. Graphical Reasoning Consider an n-sided regular polygon inscribed in a circle of radius r. Join the vertices of the polygon to the center of the circle, forming n congruent triangles (see figure).

(a) Determine the central angle θ in terms of n.

(b) Show that the area of each triangle is $\frac{1}{2}r^2 \sin\theta$.

(c) Let A_n be the sum of the areas of the n triangles. Find $\lim_{n\to\infty} A_n$.

77. Seating Capacity

A teacher places n seats to form the back row of a classroom layout. Each successive row contains two fewer seats than the preceding row. Find a formula for the number of seats used in the layout. (Hint: The number of seats in the layout depends on whether n is odd or even.)

78. Proof Prove each formula by mathematical induction. (You may need to review the method of proof by induction from a precalculus text.)

(a) $\sum_{i=1}^{n} 2i = n(n + 1)$ (b) $\sum_{i=1}^{n} i^3 = \frac{n^2(n+1)^2}{4}$

PUTNAM EXAM CHALLENGE

79. A dart, thrown at random, hits a square target. Assuming that any two parts of the target of equal area are equally likely to be hit, find the probability that the point hit is nearer to the center than to any edge. Write your answer in the form $\left(a\sqrt{b} + c\right)/d$, where a, b, c, and d are integers.

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Bokeh Blur Background/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

4.3 Riemann Sums and Definite Integrals

GO DIGITAL

- **Describe a Riemann sum.**
- **Evaluate a definite integral using limits and geometric formulas.**
- **Evaluate a definite integral using properties of definite integrals.**

Riemann Sums

In the definition of area given in Section 4.2, the partitions have subintervals of *equal width*. This was done only for computational convenience. The next example shows that it is not necessary to have subintervals of equal width.

EXAMPLE 1 **A Partition with Subintervals of Unequal Widths**

Consider the region bounded by the graph of $f(x) = \sqrt{x}$ and the x-axis for $0 \le x \le 1$, as shown in Figure 4.18. Evaluate the limit

$$\lim_{n\to\infty} \sum_{i=1}^{n} f(c_i)\,\Delta x_i$$

where c_i is the right endpoint of the partition given by $c_i = i^2/n^2$ and Δx_i is the width of the ith interval.



The subintervals do not have equal widths.

Figure 4.18

Solution The left endpoint of the ith interval is $(i-1)^2/n^2$. So, the width of the ith interval is

$$\Delta x_i = \frac{i^2}{n^2} - \frac{(i-1)^2}{n^2}$$ Width = (right endpoint) − (left endpoint)

$$= \frac{i^2 - i^2 + 2i - 1}{n^2}$$ Subtract fractions and expand binomial.

$$= \frac{2i-1}{n^2}.$$ Simplify.

Now, evaluate the limit.

$$\lim_{n\to\infty} \sum_{i=1}^{n} f(c_i)\,\Delta x_i = \lim_{n\to\infty} \sum_{i=1}^{n} \sqrt{\frac{i^2}{n^2}}\left(\frac{2i-1}{n^2}\right)$$

$$= \lim_{n\to\infty} \frac{1}{n^3} \sum_{i=1}^{n} (2i^2 - i)$$

$$= \lim_{n\to\infty} \frac{1}{n^3}\left[2\left(\frac{n(n+1)(2n+1)}{6}\right) - \frac{n(n+1)}{2}\right]$$

$$= \lim_{n\to\infty} \frac{4n^3 + 3n^2 - n}{6n^3}$$

$$= \lim_{n\to\infty} \left(\frac{2}{3} + \frac{1}{2n} - \frac{1}{6n^2}\right)$$

$$= \frac{2}{3}$$ ■



The area of the region bounded by the graph of $x = y^2$ and the y-axis for $0 \le y \le 1$ is $\frac{1}{3}$.

Figure 4.19

From Example 7 in Section 4.2, you know that the region shown in Figure 4.19 has an area of $\frac{1}{3}$. Because the square bounded by $0 \le x \le 1$ and $0 \le y \le 1$ has an area of 1, you can conclude that the area of the region shown in Figure 4.18 has an area of $\frac{2}{3}$. This agrees with the limit found in Example 1, even though that example used a partition having subintervals of unequal widths. The reason this particular partition gave the proper area is that as n increases, the *width of the largest subinterval approaches zero.* This is a key feature of the development of definite integrals.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

In Section 4.2, the limit of a sum was used to define the area of a region in the plane. Finding area by this method is only one of *many* applications involving the limit of a sum. A similar approach can be used to determine quantities as diverse as arc lengths, average values, centroids, volumes, work, and surface areas. The next definition is named after Georg Friedrich Bernhard Riemann. Although the definite integral had been defined and used long before Riemann's time, he generalized the concept to cover a broader category of functions.

In the definition of a Riemann sum below, note that the function f has no restrictions other than being defined on the interval $[a, b]$. (In Section 4.2, the function f was assumed to be continuous and nonnegative because you were finding the area under a curve.)

GEORG FRIEDRICH BERNHARD RIEMANN (1826–1866)

German mathematician Riemann did his most famous work in the areas of non-Euclidean geometry, differential equations, and number theory. It was Riemann's results in physics and mathematics that formed the structure on which Einstein's General Theory of Relativity is based.

See LarsonCalculus.com to read more of this biography.

Definition of Riemann Sum

Let a function f be defined on the closed interval $[a, b]$, and let Δ be a partition of $[a, b]$ given by

$$a = x_0 < x_1 < x_2 < \cdots < x_{n-1} < x_n = b$$

where Δx_i is the width of the ith subinterval

$$[x_{i-1}, x_i]. \qquad i\text{th subinterval}$$

If c_i is *any* point in the ith subinterval, then the sum

$$\sum_{i=1}^{n} f(c_i)\,\Delta x_i, \quad x_{i-1} \le c_i \le x_i$$

is called a **Riemann sum** of f for the partition Δ. (The sums in Section 4.2 are examples of Riemann sums, but there are more general Riemann sums than those covered there.)

The width of the largest subinterval of a partition Δ is the **norm** of the partition and is denoted by $\|\Delta\|$. If every subinterval is of equal width, then the partition is **regular** and the norm is denoted by

$$\|\Delta\| = \Delta x = \frac{b-a}{n}. \qquad \text{Regular partition}$$

For a **general partition,** the norm is related to the number of subintervals of $[a, b]$ by the inequality

$$\frac{b-a}{\|\Delta\|} \le n. \qquad \text{General partition}$$

So, the number of subintervals in a partition approaches infinity as the norm of the partition approaches 0. That is, $\|\Delta\| \to 0$ implies that $n \to \infty$.

The converse of this statement is not true. For example, let Δ_n be the partition of the interval $[0, 1]$ given by

$$0 < \frac{1}{2^n} < \frac{1}{2^{n-1}} < \cdots < \frac{1}{8} < \frac{1}{4} < \frac{1}{2} < 1.$$

As shown in Figure 4.20, for any positive value of n, the norm of the partition Δ_n is $\frac{1}{2}$. So, letting n approach infinity does not force $\|\Delta\|$ to approach 0. In a regular partition, however, the statements

$$\|\Delta\| \to 0 \quad \text{and} \quad n \to \infty$$

are equivalent.



$n \to \infty$ does not imply that $\|\Delta\| \to 0$.

Figure 4.20

INTERFOTO/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Definite Integrals

To define the definite integral, consider the limit

$$\lim_{\|\Delta\|\to 0} \sum_{i=1}^{n} f(c_i)\,\Delta x_i = L.$$

To say that this limit exists means there exists a real number L such that for each $\varepsilon > 0$, there exists a $\delta > 0$ such that for every partition with $\|\Delta\| < \delta$, it follows that

$$\left| L - \sum_{i=1}^{n} f(c_i)\,\Delta x_i \right| < \varepsilon$$

regardless of the choice of c_i in the ith subinterval of each partition Δ.

Definition of Definite Integral

If a function f is defined on the closed interval $[a, b]$ and the limit of Riemann sums over partitions Δ

$$\lim_{\|\Delta\|\to 0} \sum_{i=1}^{n} f(c_i)\,\Delta x_i$$

exists (as described above), then f is said to be **integrable** on $[a, b]$ and the limit is denoted by

$$\lim_{\|\Delta\|\to 0} \sum_{i=1}^{n} f(c_i)\,\Delta x_i = \int_a^b f(x)\,dx.$$

The limit is called the **definite integral** of f from a to b. The number a is the **lower limit** of integration, and the number b is the **upper limit** of integration.

REMARK Later in this chapter, you will learn convenient methods for calculating $\int_a^b f(x)\,dx$ for continuous functions. For now, you must use the limit definition.

It is not a coincidence that the notation for definite integrals is similar to that used for indefinite integrals. You will see why in the next section when the Fundamental Theorem of Calculus is introduced. For now, it is important to see that definite integrals and indefinite integrals are different concepts. A definite integral is a *number*, whereas an indefinite integral is a *family of functions*.

Though Riemann sums were defined for functions with very few restrictions, a sufficient condition for a function f to be integrable on $[a, b]$ is that it is continuous on $[a, b]$. A proof of this theorem is beyond the scope of this text.

THEOREM 4.4 Continuity Implies Integrability

If a function f is continuous on the closed interval $[a, b]$, then f is integrable on $[a, b]$. That is, $\int_a^b f(x)\,dx$ exists.

FOR FURTHER INFORMATION For insight into the history of the definite integral, see the article "The Evolution of Integration" by A. Shenitzer and J. Steprāns in *The American Mathematical Monthly.* To view this article, go to *MathArticles.com.*

Exploration

The Converse of Theorem 4.4 Is the converse of Theorem 4.4 true? That is, when a function is integrable, does it have to be continuous? Explain your reasoning and give examples.

Describe the relationships among continuity, differentiability, and integrability. Which is the strongest condition? Which is the weakest? Which conditions imply other conditions?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 2 Evaluating a Definite Integral as a Limit

Evaluate the definite integral $\int_{-2}^{1} 2x\,dx$.

Solution The function $f(x) = 2x$ is integrable on the interval $[-2, 1]$ because it is continuous on $[-2, 1]$. Moreover, the definition of integrability implies that any partition whose norm approaches 0 can be used to determine the limit. For computational convenience, define Δ by subdividing $[-2, 1]$ into n subintervals of equal width

$$\Delta x_i = \Delta x = \frac{b-a}{n} = \frac{3}{n}. \qquad \text{Width of interval}$$

Choosing c_i as the right endpoint of each subinterval produces

$$c_i = a + i(\Delta x) = -2 + \frac{3i}{n}. \qquad \text{Right endpoint}$$

So, the definite integral is

$$\begin{aligned}
\int_{-2}^{1} 2x\,dx &= \lim_{\|\Delta\|\to 0} \sum_{i=1}^{n} f(c_i)\,\Delta x_i && \text{Definition of definite integral} \\
&= \lim_{n\to\infty} \sum_{i=1}^{n} f(c_i)\,\Delta x && n \to \infty \text{ as } \|\Delta\| \to 0 \\
&= \lim_{n\to\infty} \sum_{i=1}^{n} 2\left(-2 + \frac{3i}{n}\right)\left(\frac{3}{n}\right) && f(c_i) = 2c_i \text{ and } \Delta x = \frac{3}{n} \\
&= \lim_{n\to\infty} \frac{6}{n} \sum_{i=1}^{n} \left(-2 + \frac{3i}{n}\right) && \text{Factor out constant term.} \\
&= \lim_{n\to\infty} \frac{6}{n} \left(-2\sum_{i=1}^{n} 1 + \frac{3}{n}\sum_{i=1}^{n} i\right) && \text{Property of summation} \\
&= \lim_{n\to\infty} \frac{6}{n} \left\{-2n + \frac{3}{n}\left[\frac{n(n+1)}{2}\right]\right\} && \text{Apply Theorem 4.2.} \\
&= \lim_{n\to\infty} \frac{6}{n} \left(-2n + \frac{3n}{2} + \frac{3}{2}\right) \\
&= \lim_{n\to\infty} \left(-12 + 9 + \frac{9}{n}\right) \\
&= -3.
\end{aligned}$$



Because the definite integral is negative, it does not represent the area of the region.

Figure 4.21

Because the definite integral in Example 2 is negative, it *does not* represent the area of the region shown in Figure 4.21. Definite integrals can be positive, negative, or zero. For a definite integral to be interpreted as an area (as defined in Section 4.2), the function f must be continuous and nonnegative on $[a, b]$, as stated in the next theorem. The proof of this theorem is straightforward—you simply use the definition of area given in Section 4.2, because it is a Riemann sum.



You can use a definite integral to find the area of the region bounded by the graph of f, the x-axis, $x = a$, and $x = b$.

Figure 4.22

THEOREM 4.5 The Definite Integral as the Area of a Region

If a function f is continuous and nonnegative on the closed interval $[a, b]$, then the area of the region bounded by the graph of f, the x-axis, and the vertical lines $x = a$ and $x = b$ is

$$\text{Area} = \int_a^b f(x)\,dx.$$

(See Figure 4.22.)

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



$$\text{Area} = \int_0^4 (4x - x^2)\,dx$$

Figure 4.23

As an example of Theorem 4.5, consider the region bounded by the graph of

$$f(x) = 4x - x^2$$

and the x-axis, as shown in Figure 4.23. Because f is continuous and nonnegative on the closed interval $[0, 4]$, the area of the region is

$$\text{Area} = \int_0^4 (4x - x^2)\,dx.$$

A straightforward technique for evaluating a definite integral such as this will be discussed in Section 4.4. For now, however, you can evaluate a definite integral in two ways—you can use the limit definition *or* you can check to see whether the definite integral represents the area of a common geometric region, such as a rectangle, triangle, or semicircle.

EXAMPLE 3 Areas of Common Geometric Figures

Sketch the region corresponding to each definite integral. Then evaluate each integral using a geometric formula.

a. $\displaystyle\int_1^3 4\,dx$ **b.** $\displaystyle\int_0^3 (x + 2)\,dx$ **c.** $\displaystyle\int_{-2}^2 \sqrt{4 - x^2}\,dx$

Solution A sketch of each region is shown in Figure 4.24.

a. This region is a rectangle of height 4 and width 2.

$$\int_1^3 4\,dx = (\text{Area of rectangle}) = 4(2) = 8$$

b. This region is a trapezoid with an altitude of 3 and parallel bases of lengths 2 and 5. The formula for the area of a trapezoid is $\frac{1}{2}h(b_1 + b_2)$.

$$\int_0^3 (x + 2)\,dx = (\text{Area of trapezoid}) = \frac{1}{2}(3)(2 + 5) = \frac{21}{2}$$

c. This region is a semicircle of radius 2. The formula for the area of a semicircle is $\frac{1}{2}\pi r^2$.

$$\int_{-2}^2 \sqrt{4 - x^2}\,dx = (\text{Area of semicircle}) = \frac{1}{2}\pi(2^2) = 2\pi$$



(a) **(b)** **(c)**

Figure 4.24

The variable of integration in a definite integral is sometimes called a *dummy variable* because it can be replaced by any other variable without changing the value of the integral. For instance, the definite integrals

$$\int_0^3 (x + 2)\,dx \quad \text{and} \quad \int_0^3 (t + 2)\,dt$$

have the same value.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Properties of Definite Integrals

The definition of the definite integral of f on the interval $[a, b]$ specifies that $a < b$. Now, however, it is convenient to extend the definition to cover cases in which $a = b$ or $a > b$. Geometrically, the next two definitions seem reasonable. For instance, it makes sense to define the area of a region of zero width and finite height to be 0.

Definitions of Two Special Definite Integrals

1. If a function f is defined at $x = a$, then $\int_a^a f(x)\,dx = 0$.

2. If a function f is integrable on $[a, b]$, then $\int_b^a f(x)\,dx = -\int_a^b f(x)\,dx$.

EXAMPLE 4 Evaluating Definite Integrals

See LarsonCalculus.com for an interactive version of this type of example.

Evaluate (a) $\int_\pi^\pi \sin x\,dx$ and (b) $\int_3^0 (x + 2)\,dx$.

Solution

a. Because the sine function is defined at $x = \pi$, and the upper and lower limits of integration are equal, you can write

$$\int_\pi^\pi \sin x\,dx = 0.$$

b. The integral $\int_3^0 (x + 2)\,dx$ is the same as that given in Example 3(b) except that the upper and lower limits are interchanged. Because the integral in Example 3(b) has a value of $\frac{21}{2}$, you can write

$$\int_3^0 (x + 2)\,dx = -\int_0^3 (x + 2)\,dx = -\frac{21}{2}.$$



Figure 4.25

In Figure 4.25, the larger region can be divided at $x = c$ into two subregions whose intersection is a line segment. Because the line segment has zero area, it follows that the area of the larger region is equal to the sum of the areas of the two smaller regions.

THEOREM 4.6 Additive Interval Property

If a function f is integrable on the three closed intervals determined by a, b, and c, then

$$\int_a^b f(x)\,dx = \int_a^c f(x)\,dx + \int_c^b f(x)\,dx.$$

See Figure 4.25.

EXAMPLE 5 Using the Additive Interval Property

$$\int_{-1}^1 |x|\,dx = \int_{-1}^0 -x\,dx + \int_0^1 x\,dx \qquad \text{Theorem 4.6}$$

$$= \frac{1}{2} + \frac{1}{2} \qquad \text{Area of a triangle (See Figure 4.26.)}$$

$$= 1$$



Figure 4.26

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Because the definite integral is defined as the limit of a sum, it inherits the properties of summation given at the top of page 259.

THEOREM 4.7 Properties of Definite Integrals

If the functions f and g are integrable on $[a, b]$ and k is a constant, then the functions kf and $f \pm g$ are integrable on $[a, b]$, and

1. $\int_a^b kf(x)\,dx = k\int_a^b f(x)\,dx$

2. $\int_a^b [f(x) \pm g(x)]\,dx = \int_a^b f(x)\,dx \pm \int_a^b g(x)\,dx.$

REMARK Property 2 of Theorem 4.7 can be extended to cover any finite number of functions (see Example 6).

EXAMPLE 6 Evaluating a Definite Integral

Evaluate $\int_1^3 (-x^2 + 4x - 3)\,dx$ using the values shown below.

$$\int_1^3 x^2\,dx = \frac{26}{3}, \qquad \int_1^3 x\,dx = 4, \qquad \int_1^3 dx = 2$$

Solution

$$\begin{aligned}\int_1^3 (-x^2 + 4x - 3)\,dx &= \int_1^3 (-x^2)\,dx + \int_1^3 4x\,dx + \int_1^3 (-3)\,dx \\ &= -\int_1^3 x^2\,dx + 4\int_1^3 x\,dx - 3\int_1^3 dx \\ &= -\left(\frac{26}{3}\right) + 4(4) - 3(2) \\ &= \frac{4}{3}\end{aligned}$$



$\int_a^b f(x)\,dx \le \int_a^b g(x)\,dx$

Figure 4.27

If the functions f and g are continuous on the closed interval $[a, b]$ and $0 \le f(x) \le g(x)$ for $a \le x \le b$, then the following properties are true. First, the area of the region bounded by the graph of f and the x-axis (between a and b) must be nonnegative. Second, this area must be less than or equal to the area of the region bounded by the graph of g and the x-axis (between a and b), as shown in Figure 4.27. These two properties are generalized in Theorem 4.8.

THEOREM 4.8 Preservation of Inequality

1. If a function f is integrable and nonnegative on the closed interval $[a, b]$, then

$$0 \le \int_a^b f(x)\,dx.$$

2. If the functions f and g are integrable on the closed interval $[a, b]$ and $f(x) \le g(x)$ for every x in $[a, b]$, then

$$\int_a^b f(x)\,dx \le \int_a^b g(x)\,dx.$$

A proof of this theorem is given in Appendix A.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

4.3 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain what a Riemann sum represents.
2. Explain how to find the area of a region using a definite integral.

Evaluating a Limit **In Exercises 3 and 4, use Example 1 as a model to evaluate the limit**

$$\lim_{n\to\infty} \sum_{i=1}^{n} f(c_i)\,\Delta x_i$$

over the region bounded by the graphs of the equations.

3. $f(x) = \sqrt{x}, \quad y = 0, \quad x = 0, \quad x = 3 \quad \left(\textit{Hint: Let } c_i = \frac{3i^2}{n^2}.\right)$

4. $f(x) = \sqrt[3]{x}, \quad y = 0, \quad x = 0, \quad x = 1 \quad \left(\textit{Hint: Let } c_i = \frac{i^3}{n^3}.\right)$

Evaluating a Definite Integral as a Limit **In Exercises 5–10, evaluate the definite integral by the limit definition.**

5. $\int_2^6 8\,dx$
6. $\int_{-2}^{3} x\,dx$
7. $\int_{-1}^{1} x^3\,dx$
8. $\int_1^4 4x^2\,dx$
9. $\int_1^2 (x^2 + 1)\,dx$
10. $\int_{-2}^{1} (2x^2 + 3)\,dx$

Writing a Limit as a Definite Integral **In Exercises 11 and 12, write the limit as a definite integral on the given interval, where c_i is any point in the ith subinterval.**

	Limit	Interval
11.	$\lim_{\|\Delta\|\to 0} \sum_{i=1}^{n} (3c_i + 10)\,\Delta x_i$	$[-1, 5]$
12.	$\lim_{\|\Delta\|\to 0} \sum_{i=1}^{n} \sqrt{c_i^2 + 4}\,\Delta x_i$	$[0, 3]$

Writing a Definite Integral **In Exercises 13–22, write a definite integral that represents the area of the region. (Do not evaluate the integral.)**

13. $f(x) = 5$



14. $f(x) = 6 - 3x$



15. $f(x) = 4 - |x|$



16. $f(x) = x^2$



17. $f(x) = 25 - x^2$



18. $f(x) = \dfrac{4}{x^2 + 2}$



19. $f(x) = \cos x$



20. $f(x) = \tan x$



21. $g(y) = y^3$



22. $f(y) = (y - 2)^2$



Evaluating a Definite Integral Using a Geometric Formula **In Exercises 23–32, sketch the region whose area is given by the definite integral. Then use a geometric formula to evaluate the integral ($a > 0, r > 0$).**

23. $\int_0^3 4\,dx$
24. $\int_{-3}^{4} 9\,dx$
25. $\int_0^4 x\,dx$
26. $\int_0^8 \frac{x}{4}\,dx$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

27. $\int_0^2 (3x + 4)\,dx$ **28.** $\int_0^3 (8 - 2x)\,dx$

29. $\int_{-1}^1 (1 - |x|)\,dx$ **30.** $\int_{-a}^a (a - |x|)\,dx$

31. $\int_{-7}^7 \sqrt{49 - x^2}\,dx$ **32.** $\int_{-r}^r \sqrt{r^2 - x^2}\,dx$

Using Properties of Definite Integrals **In Exercises 33–40, evaluate the definite integral using the values below.**

$$\int_2^6 x^3\,dx = 320, \quad \int_2^6 x\,dx = 16, \quad \int_2^6 dx = 4$$

33. $\int_6^2 x^3\,dx$ **34.** $\int_2^2 x\,dx$

35. $\int_2^6 \frac{1}{4}x^3\,dx$ **36.** $\int_2^6 -3x\,dx$

37. $\int_2^6 (x - 14)\,dx$ **38.** $\int_2^6 \left(6x - \frac{1}{8}x^3\right)dx$

39. $\int_2^6 (2x^3 - 10x + 7)\,dx$ **40.** $\int_2^6 (21 - 5x - x^3)\,dx$

41. Using Properties of Definite Integrals Given

$$\int_0^5 f(x)\,dx = 10 \quad \text{and} \quad \int_5^7 f(x)\,dx = 3$$

evaluate

(a) $\int_0^7 f(x)\,dx$. (b) $\int_5^0 f(x)\,dx$.

(c) $\int_5^5 f(x)\,dx$. (d) $\int_0^5 3f(x)\,dx$.

42. Using Properties of Definite Integrals Given

$$\int_0^3 f(x)\,dx = 4 \quad \text{and} \quad \int_3^6 f(x)\,dx = -1$$

evaluate

(a) $\int_0^6 f(x)\,dx$. (b) $\int_6^3 f(x)\,dx$.

(c) $\int_3^3 f(x)\,dx$. (d) $\int_3^6 -5f(x)\,dx$.

43. Using Properties of Definite Integrals Given

$$\int_2^6 f(x)\,dx = 10 \quad \text{and} \quad \int_2^6 g(x)\,dx = -2$$

evaluate

(a) $\int_2^6 [f(x) + g(x)]\,dx$.

(b) $\int_2^6 [g(x) - f(x)]\,dx$.

(c) $\int_2^6 2g(x)\,dx$.

(d) $\int_2^6 3f(x)\,dx$.

44. Using Properties of Definite Integrals Given

$$\int_{-1}^1 f(x)\,dx = 0 \quad \text{and} \quad \int_0^1 f(x)\,dx = 5$$

evaluate

(a) $\int_{-1}^0 f(x)\,dx$. (b) $\int_0^1 f(x)\,dx - \int_{-1}^0 f(x)\,dx$.

(c) $\int_{-1}^1 3f(x)\,dx$. (d) $\int_0^1 3f(x)\,dx$.

45. Estimating a Definite Integral Use the table of values to find lower and upper estimates of

$$\int_0^{10} f(x)\,dx.$$

Assume that f is a decreasing function.

x	0	2	4	6	8	10
$f(x)$	32	24	12	−4	−20	−36

46. Estimating a Definite Integral Use the table of values to estimate

$$\int_0^6 f(x)\,dx.$$

Use three equal subintervals and the (a) left endpoints, (b) right endpoints, and (c) midpoints. When f is an increasing function, how does each estimate compare with the actual value? Explain your reasoning.

x	0	1	2	3	4	5	6
$f(x)$	−6	0	8	18	30	50	80

47. Think About It The graph of a function f consists of line segments and a semicircle, as shown in the figure. Evaluate each definite integral by using geometric formulas.



(a) $\int_0^2 f(x)\,dx$ (b) $\int_2^6 f(x)\,dx$

(c) $\int_{-4}^2 f(x)\,dx$

(d) $\int_{-4}^6 f(x)\,dx$

(e) $\int_{-4}^6 |f(x)|\,dx$

(f) $\int_{-4}^6 [f(x) + 2]\,dx$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

48. Think About It The graph of a function f consists of line segments, as shown in the figure. Evaluate each definite integral by using geometric formulas.



(a) $\int_0^1 -f(x)\,dx$ (b) $\int_3^4 3f(x)\,dx$

(c) $\int_0^7 f(x)\,dx$ (d) $\int_5^{11} f(x)\,dx$

(e) $\int_0^{11} f(x)\,dx$ (f) $\int_4^{10} f(x)\,dx$

49. Think About It Consider a function f that is continuous on the interval $[-5, 5]$ and for which

$$\int_0^5 f(x)\,dx = 4.$$

Evaluate each integral.

(a) $\int_0^5 [f(x) + 2]\,dx$ (b) $\int_{-2}^3 f(x + 2)\,dx$

(c) $\int_{-5}^5 f(x)\,dx$, f is even (d) $\int_{-5}^5 f(x)\,dx$, f is odd

50. HOW DO YOU SEE IT? Use the figure to fill in the blank with the symbol $<$, $>$, or $=$. Explain your reasoning.



(a) The interval $[1, 5]$ is partitioned into n subintervals of equal width Δx, and x_i is the left endpoint of the ith subinterval.

$$\sum_{i=1}^{n} f(x_i)\,\Delta x \quad \square \quad \int_1^5 f(x)\,dx$$

(b) The interval $[1, 5]$ is partitioned into n subintervals of equal width Δx, and x_i is the right endpoint of the ith subinterval.

$$\sum_{i=1}^{n} f(x_i)\,\Delta x \quad \square \quad \int_1^5 f(x)\,dx$$

51. Think About It A function f is defined below. Use geometric formulas to find $\int_0^8 f(x)\,dx$.

$$f(x) = \begin{cases} 4, & x < 4 \\ x, & x \geq 4 \end{cases}$$

52. Think About It A function f is defined below. Use geometric formulas to find $\int_0^{12} f(x)\,dx$.

$$f(x) = \begin{cases} 6, & x > 6 \\ -\frac{1}{2}x + 9, & x \leq 6 \end{cases}$$

Exploring Concepts

In Exercises 53 and 54, determine which value best approximates the definite integral. Make your selection on the basis of a sketch.

53. $\int_0^4 \sqrt{x}\,dx$

(a) 5 (b) -3 (c) 10 (d) 2 (e) 8

54. $\int_0^{1/2} 4\cos \pi x\,dx$

(a) 4 (b) $\frac{4}{3}$ (c) 16 (d) 2π (e) -6

55. Use a graph to explain why

$$\int_a^a f(x)\,dx = 0$$

if f is defined at $x = a$.

56. Use a graph to explain why

$$\int_a^b kf(x)\,dx = k\int_a^b f(x)\,dx$$

if f is integrable on $[a, b]$ and k is a constant.

57. Describe two ways to evaluate

$$\int_{-1}^3 (x + 2)\,dx.$$

Verify that each method gives the same result.

58. Give an example of a function that is integrable on the interval $[-1, 1]$ but not continuous on $[-1, 1]$.

Finding Values **In Exercises 59–62, find possible values of a and b that make the statement true. Use a graph to support your answer, when possible. (There may be more than one correct answer.)**

59. $\int_{-2}^1 f(x)\,dx + \int_1^5 f(x)\,dx = \int_a^b f(x)\,dx$

60. $\int_{-3}^3 f(x)\,dx + \int_3^6 f(x)\,dx - \int_a^b f(x)\,dx = \int_{-1}^6 f(x)\,dx$

61. $\int_a^b \sin x\,dx < 0$

62. $\int_a^b \cos x\,dx = 0$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

True or False? **In Exercises 63–68, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

63. $\int_a^b [f(x) + g(x)]\,dx = \int_a^b f(x)\,dx + \int_a^b g(x)\,dx$

64. $\int_a^b f(x)g(x)\,dx = \left[\int_a^b f(x)\,dx\right]\left[\int_a^b g(x)\,dx\right]$

65. If the norm of a partition approaches zero, then the number of subintervals approaches infinity.

66. If a function f is increasing on $[a, b]$, then the minimum value of f on $[a, b]$ is $f(a)$.

67. $\int_a^b f(x)\,dx \geq 0$

68. $\int_2^2 \sin x^2\,dx = 0$

69. Finding a Riemann Sum Find the Riemann sum for $f(x) = x^2 + 3x$ over the interval $[0, 8]$, where

$x_0 = 0, \quad x_1 = 1, \quad x_2 = 3, \quad x_3 = 7, \quad \text{and} \quad x_4 = 8$

and where

$c_1 = 1, \quad c_2 = 2, \quad c_3 = 5, \quad \text{and} \quad c_4 = 8.$



70. Finding a Riemann Sum Find the Riemann sum for $f(x) = \sin x$ over the interval $[0, 2\pi]$, where

$x_0 = 0, \quad x_1 = \frac{\pi}{4}, \quad x_2 = \frac{\pi}{3}, \quad x_3 = \pi, \quad \text{and} \quad x_4 = 2\pi$

and where

$c_1 = \frac{\pi}{6}, \quad c_2 = \frac{\pi}{3}, \quad c_3 = \frac{2\pi}{3}, \quad \text{and} \quad c_4 = \frac{3\pi}{2}.$



71. Proof Prove that $\int_a^b x\,dx = \frac{b^2 - a^2}{2}$.

72. Proof Prove that $\int_a^b x^2\,dx = \frac{b^3 - a^3}{3}$.

73. Think About It Determine whether the Dirichlet function

$$f(x) = \begin{cases} 1, & x \text{ is rational} \\ 0, & x \text{ is irrational} \end{cases}$$

is integrable on the interval $[0, 1]$. Explain.

74. Finding a Definite Integral The function

$$f(x) = \begin{cases} 0, & x = 0 \\ \dfrac{1}{x}, & 0 < x \leq 1 \end{cases}$$

is defined on $[0, 1]$, as shown in the figure. Show that

$\int_0^1 f(x)\,dx$

does not exist. Does this contradict Theorem 4.4? Why or why not?



75. Finding Values Find the constants a and b, where $a < b$, that maximize the value of

$\int_a^b (1 - x^2)\,dx.$

Explain your reasoning.

76. Finding Values Find the constants a and b, where $a < 4 < b$, such that

$\left|\int_a^b (x - 4)\,dx\right| = 16$ and $\int_a^b |x - 4|\,dx = 20.$

77. Think About It When is

$\int_a^b f(x)\,dx = \int_a^b |f(x)|\,dx?$

Explain.

78. Step Function Evaluate, if possible, the integral

$\int_0^2 [\![x]\!]\,dx.$

79. Using a Riemann Sum Determine

$\lim_{n\to\infty} \frac{1}{n^3}(1^2 + 2^2 + 3^2 + \cdots + n^2)$

by using an appropriate Riemann sum.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

4.4 The Fundamental Theorem of Calculus

GO DIGITAL

- **Evaluate a definite integral using the Fundamental Theorem of Calculus.**
- **Describe and use the Mean Value Theorem for Integrals.**
- **Find the average value of a function over a closed interval.**
- **Describe and use the Second Fundamental Theorem of Calculus.**
- **Describe and use the Net Change Theorem.**

The Fundamental Theorem of Calculus

You have now been introduced to the two major branches of calculus: differential calculus (introduced with the tangent line problem) and integral calculus (introduced with the area problem). So far, these two problems might seem unrelated—but there is a very close connection. The connection was discovered independently by Isaac Newton and Gottfried Leibniz and is stated in the **Fundamental Theorem of Calculus.**

Informally, the theorem states that differentiation and (definite) integration are inverse operations, in the same sense that division and multiplication are inverse operations. To see how Newton and Leibniz might have anticipated this relationship, consider the approximations shown in Figure 4.28. The slope of the tangent line was defined using the *quotient* $\Delta y/\Delta x$ (the slope of the secant line). Similarly, the area of a region under a curve was defined using the *product* $\Delta y \Delta x$ (the area of a rectangle). So, at least in the primitive approximation stage, the operations of differentiation and definite integration appear to have an inverse relationship in the same sense that division and multiplication are inverse operations. The Fundamental Theorem of Calculus states that the limit processes (used to define the derivative and definite integral) preserve this inverse relationship.



(a) Differentiation **(b)** Definite integration

Differentiation and definite integration have an "inverse" relationship.

Figure 4.28

ANTIDIFFERENTIATION AND DEFINITE INTEGRATION

Throughout this chapter, you have been using the integral sign to denote an antiderivative (a family of functions) and a definite integral (a number).

Antidifferentiation: $\int f(x)\,dx$ Definite integration: $\int_a^b f(x)\,dx$

The use of the same symbol for both operations makes it appear that they are related. In the early work with calculus, however, it was not known that the two operations were related. The symbol $\int$ was first applied to the definite integral by Leibniz and was derived from the letter *S*. (Leibniz calculated area as an infinite sum, thus, the letter *S*.)

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

THEOREM 4.9 The Fundamental Theorem of Calculus

If a function f is continuous on the closed interval $[a, b]$ and F is an antiderivative of f on the interval $[a, b]$, then

$$\int_a^b f(x)\,dx = F(b) - F(a).$$

Proof The key to the proof is writing the difference $F(b) - F(a)$ in a convenient form. Let Δ be any partition of $[a, b]$.

$$a = x_0 < x_1 < x_2 < \cdots < x_{n-1} < x_n = b$$

By pairwise subtraction and addition of like terms, you can write

$$\begin{aligned} F(b) - F(a) &= F(x_n) - F(x_{n-1}) + F(x_{n-1}) - \cdots - F(x_1) + F(x_1) - F(x_0) \\ &= \sum_{i=1}^{n} [F(x_i) - F(x_{i-1})]. \end{aligned}$$

By the Mean Value Theorem, there exists a number c_i in the ith subinterval such that

$$F'(c_i) = \frac{F(x_i) - F(x_{i-1})}{x_i - x_{i-1}}.$$

Because $F'(c_i) = f(c_i)$, let

$$\Delta x_i = x_i - x_{i-1}$$

and obtain

$$F(b) - F(a) = \sum_{i=1}^{n} f(c_i)\,\Delta x_i.$$

This important equation tells you that by repeatedly applying the Mean Value Theorem, you can always find a collection of c_i's such that the *constant* $F(b) - F(a)$ is a Riemann sum of f on $[a, b]$ for any partition. Theorem 4.4 guarantees that the limit of Riemann sums over the partition with $\|\Delta\| \to 0$ exists. So, taking the limit (as $\|\Delta\| \to 0$) produces

$$F(b) - F(a) = \int_a^b f(x)\,dx.$$

Guidelines for using The Fundamental Theorem of Calculus

1. *Provided you can find* an antiderivative of f, you now have a way to evaluate a definite integral without having to use the limit of a sum.
2. When applying the Fundamental Theorem of Calculus, the notation shown below is convenient.

$$\int_a^b f(x)\,dx = F(x)\Big]_a^b = F(b) - F(a)$$

For instance, to evaluate $\int_1^3 x^3\,dx$, you can write

$$\int_1^3 x^3\,dx = \frac{x^4}{4}\Big]_1^3 = \frac{3^4}{4} - \frac{1^4}{4} = \frac{81}{4} - \frac{1}{4} = 20.$$

3. It is not necessary to include a constant of integration C in the antiderivative.

$$\int_a^b f(x)\,dx = \Big[F(x) + C\Big]_a^b = [F(b) + C] - [F(a) + C] = F(b) - F(a)$$

REMARK Other common notations used when applying the Fundamental Theorem of Calculus are

$$\Big[F(x)\Big]_a^b \quad \text{and} \quad F(x)\Big|_a^b.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 1 Evaluating Definite Integrals

See LarsonCalculus.com for an interactive version of this type of example.

Evaluate each definite integral.

a. $\int_1^2 (x^2 - 3)\,dx$ **b.** $\int_1^4 3\sqrt{x}\,dx$ **c.** $\int_0^{\pi/4} \sec^2 x\,dx$

Solution

a. $\int_1^2 (x^2 - 3)\,dx = \left[\frac{x^3}{3} - 3x\right]_1^2 = \left(\frac{8}{3} - 6\right) - \left(\frac{1}{3} - 3\right) = -\frac{2}{3}$

b. $\int_1^4 3\sqrt{x}\,dx = 3\int_1^4 x^{1/2}\,dx = 3\left[\frac{x^{3/2}}{3/2}\right]_1^4 = 2(4)^{3/2} - 2(1)^{3/2} = 14$

c. $\int_0^{\pi/4} \sec^2 x\,dx = \tan x\Big]_0^{\pi/4} = \tan\frac{\pi}{4} - \tan 0 = 1 - 0 = 1$



The definite integral of y on $[0, 2]$ is $\frac{5}{2}$.
Figure 4.29

EXAMPLE 2 A Definite Integral Involving Absolute Value

Evaluate $\int_0^2 |2x - 1|\,dx$.

Solution Using Figure 4.29 and the definition of absolute value, you can rewrite the integrand as shown.

$$|2x - 1| = \begin{cases} -(2x - 1), & x < \frac{1}{2} \\ 2x - 1, & x \geq \frac{1}{2} \end{cases}$$ Rewrite using definition of absolute value.

Next, use this and Theorem 4.6 to rewrite the integral in two parts.

$$\begin{aligned} \int_0^2 |2x - 1|\,dx &= \int_0^{1/2} -(2x - 1)\,dx + \int_{1/2}^2 (2x - 1)\,dx \\ &= \left[-x^2 + x\right]_0^{1/2} + \left[x^2 - x\right]_{1/2}^2 \\ &= \left(-\frac{1}{4} + \frac{1}{2}\right) - (0 + 0) + (4 - 2) - \left(\frac{1}{4} - \frac{1}{2}\right) \\ &= \frac{5}{2} \end{aligned}$$



The area of the region bounded by the graph of y, the x-axis, $x = 0$, and $x = 2$ is $\frac{10}{3}$.
Figure 4.30

EXAMPLE 3 Using the Fundamental Theorem to Find Area

Find the area of the region bounded by the graph of

$$y = 2x^2 - 3x + 2$$

the x-axis, and the vertical lines $x = 0$ and $x = 2$, as shown in Figure 4.30.

Solution Note that $y > 0$ on the interval $[0, 2]$.

$$\begin{aligned} \text{Area} &= \int_0^2 (2x^2 - 3x + 2)\,dx && \text{Integrate between } x = 0 \text{ and } x = 2. \\ &= \left[\frac{2x^3}{3} - \frac{3x^2}{2} + 2x\right]_0^2 && \text{Find antiderivative.} \\ &= \left(\frac{16}{3} - 6 + 4\right) - (0 - 0 + 0) && \text{Apply Fundamental Theorem.} \\ &= \frac{10}{3} && \text{Simplify.} \end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Mean value rectangle:

$f(c)(b - a) = \int_a^b f(x)\,dx$

Figure 4.31

The Mean Value Theorem for Integrals

In Section 4.2, you saw that the area of a region under a curve is greater than the area of an inscribed rectangle and less than the area of a circumscribed rectangle. The Mean Value Theorem for Integrals states that somewhere "between" the inscribed and circumscribed rectangles, there is a rectangle whose area is precisely equal to the area of the region under the curve, as shown in Figure 4.31.

THEOREM 4.10 Mean Value Theorem for Integrals

If a function f is continuous on the closed interval $[a, b]$, then there exists a number c in the closed interval $[a, b]$ such that

$$\int_a^b f(x)\,dx = f(c)(b - a).$$

Proof

Case 1: If f is constant on the interval $[a, b]$, then the theorem is clearly valid because c can be any point in $[a, b]$.

Case 2: If f is not constant on $[a, b]$, then, by the Extreme Value Theorem, you can choose $f(m)$ and $f(M)$ to be the minimum and maximum values of f on $[a, b]$. Because

$$f(m) \le f(x) \le f(M)$$

for all x in $[a, b]$, you can apply Theorem 4.8 to write the double inequality below.

$$\int_a^b f(m)\,dx \le \int_a^b f(x)\,dx \le \int_a^b f(M)\,dx \qquad \text{See Figure 4.32.}$$

$$f(m)(b - a) \le \int_a^b f(x)\,dx \le f(M)(b - a) \qquad \text{Apply Fundamental Theorem.}$$

$$f(m) \le \frac{1}{b - a}\int_a^b f(x)\,dx \le f(M) \qquad \text{Divide by } b - a.$$

From the third inequality, you can apply the Intermediate Value Theorem to conclude that there exists some c in $[a, b]$ such that

$$f(c) = \frac{1}{b - a}\int_a^b f(x)\,dx \quad \text{or} \quad f(c)(b - a) = \int_a^b f(x)\,dx.$$



Inscribed rectangle (less than actual area)

$\int_a^b f(m)\,dx = f(m)(b - a)$

Mean value rectangle (equal to actual area)

$\int_a^b f(x)\,dx$

Circumscribed rectangle (greater than actual area)

$\int_a^b f(M)\,dx = f(M)(b - a)$

Figure 4.32

Notice that Theorem 4.10 does not specify how to determine c. It merely guarantees the existence of at least one number c in the interval.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Average value $= \frac{1}{b-a}\int_a^b f(x)\,dx$

Figure 4.33

GO DIGITAL

Average Value of a Function

The value of $f(c)$ given in the Mean Value Theorem for Integrals is called the **average value** of f on the interval $[a, b]$.

Definition of the Average Value of a Function on an Interval

If a function f is integrable on the closed interval $[a, b]$, then the **average value** of f on the interval is

$$\frac{1}{b-a}\int_a^b f(x)\,dx.$$ See Figure 4.33.

To see why the average value of f is defined in this way, partition $[a, b]$ into n subintervals of equal width $\Delta x = (b-a)/n$. If c_i is any point in the ith subinterval, then the arithmetic average (or mean) of the function values at the c_i's is

$$a_n = \frac{1}{n}[f(c_1) + f(c_2) + \cdots + f(c_n)].$$ Average of $f(c_1), \ldots, f(c_n)$

By writing the sum using summation notation and then multiplying and dividing by $(b-a)$, you can write the average as

$$\begin{aligned} a_n &= \frac{1}{n}\sum_{i=1}^{n} f(c_i) && \text{Rewrite using summation notation.} \\ &= \frac{1}{n}\sum_{i=1}^{n} f(c_i)\left(\frac{b-a}{b-a}\right) && \text{Multiply and divide by } (b-a). \\ &= \frac{1}{b-a}\sum_{i=1}^{n} f(c_i)\left(\frac{b-a}{n}\right) && \text{Rewrite.} \\ &= \frac{1}{b-a}\sum_{i=1}^{n} f(c_i)\,\Delta x. && \Delta x = \frac{b-a}{n} \end{aligned}$$

Finally, taking the limit as $n \to \infty$ produces the average value of f on the interval $[a, b]$, as given in the definition above. In Figure 4.33, notice that the area of the region under the graph of f is equal to the area of the rectangle whose height is the average value.

This development of the average value of a function on an interval is only one of many practical uses of definite integrals to represent summation processes. In Chapter 7, you will study other applications, such as volume, arc length, centers of mass, and work.

EXAMPLE 4 Finding the Average Value of a Function

Find the average value of $f(x) = 3x^2 - 2x$ on the interval $[1, 4]$.

Solution The average value is

$$\begin{aligned} \frac{1}{b-a}\int_a^b f(x)\,dx &= \frac{1}{4-1}\int_1^4 (3x^2 - 2x)\,dx \\ &= \frac{1}{3}\Big[x^3 - x^2\Big]_1^4 \\ &= \frac{1}{3}[64 - 16 - (1-1)] \\ &= \frac{48}{3} \\ &= 16. \end{aligned}$$ See Figure 4.34.



Figure 4.34

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

The first person to fly at a speed greater than the speed of sound was Charles Yeager. On October 14, 1947, Yeager was clocked at 295.9 meters per second at an altitude of 12.2 kilometers. If Yeager had been flying at an altitude below 11.275 kilometers, this speed would not have "broken the sound barrier." The photo shows an F/A-18F Super Hornet, a supersonic twin-engine strike fighter. A "green Hornet" using a 50/50 mixture of biofuel made from camelina oil became the first U.S. naval tactical aircraft to exceed 1 mach (the speed of sound).

EXAMPLE 5 The Speed of Sound

At different altitudes in Earth's atmosphere, sound travels at different speeds. The speed of sound $s(x)$, in meters per second, can be modeled by

$$s(x) = \begin{cases} -4x + 341, & 0 \le x < 11.5 \\ 295, & 11.5 \le x < 22 \\ \frac{3}{4}x + 278.5, & 22 \le x < 32 \\ \frac{3}{2}x + 254.5, & 32 \le x < 50 \\ -\frac{3}{2}x + 404.5, & 50 \le x \le 80 \end{cases}$$

where x is the altitude in kilometers (see figure). What is the average speed of sound over the interval $[0, 80]$?



Speed of sound depends on altitude.

Solution Begin by integrating $s(x)$ over the interval $[0, 80]$. To do this, break the integral into five parts.

$$\int_0^{11.5} s(x)\,dx = \int_0^{11.5} (-4x + 341)\,dx = \left[-2x^2 + 341x\right]_0^{11.5} = 3657$$

$$\int_{11.5}^{22} s(x)\,dx = \int_{11.5}^{22} 295\,dx = \left[295x\right]_{11.5}^{22} = 3097.5$$

$$\int_{22}^{32} s(x)\,dx = \int_{22}^{32} \left(\tfrac{3}{4}x + 278.5\right) dx = \left[\tfrac{3}{8}x^2 + 278.5x\right]_{22}^{32} = 2987.5$$

$$\int_{32}^{50} s(x)\,dx = \int_{32}^{50} \left(\tfrac{3}{2}x + 254.5\right) dx = \left[\tfrac{3}{4}x^2 + 254.5x\right]_{32}^{50} = 5688$$

$$\int_{50}^{80} s(x)\,dx = \int_{50}^{80} \left(-\tfrac{3}{2}x + 404.5\right) dx = \left[-\tfrac{3}{4}x^2 + 404.5x\right]_{50}^{80} = 9210$$

By adding the values of the five integrals, you have

$$\int_0^{80} s(x)\,dx = 24{,}640.$$

So, the average speed of sound from an altitude of 0 kilometers to an altitude of 80 kilometers is

$$\text{Average speed} = \frac{1}{80}\int_0^{80} s(x)\,dx = \frac{24{,}640}{80} = 308 \text{ meters per second.}$$

GO DIGITAL

APFootage/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The Second Fundamental Theorem of Calculus

Earlier you saw that the definite integral of f on the interval $[a, b]$ was defined using the constant b as the upper limit of integration and x as the variable of integration. However, a slightly different situation may arise in which the variable x is used in the upper limit of integration. To avoid the confusion of using x in two different ways, t is temporarily used as the variable of integration. (Remember that the definite integral is *not* a function of its variable of integration.)

The Definite Integral as a Number



The Definite Integral as a Function of x



Exploration

Use a graphing utility to graph the function

$$F(x) = \int_0^x \cos t\,dt$$

for $0 \le x \le 2\pi$. Do you recognize this graph? Explain.

EXAMPLE 6 **The Definite Integral as a Function**

Evaluate the function

$$F(x) = \int_0^x \cos t\,dt$$

at $x = 0$, $\pi/6$, $\pi/4$, $\pi/3$, and $\pi/2$.

Solution You could solve this problem by evaluating five different definite integrals, one for each of the given upper limits. It is much simpler, however, to fix x (as a constant) temporarily to obtain

$$\begin{aligned}\int_0^x \cos t\,dt &= \sin t\Big]_0^x \\ &= \sin x - \sin 0 \\ &= \sin x.\end{aligned}$$

Now, using $F(x) = \sin x$, you can obtain the results shown in Figure 4.35.



$F(x) = \int_0^x \cos t\,dt$ is the area under the curve $f(t) = \cos t$ from 0 to x.

Figure 4.35

You can think of the function $F(x)$ as *accumulating* the area under the curve $f(t) = \cos t$ from $t = 0$ to $t = x$. For $x = 0$, the area is 0 and $F(0) = 0$. For $x = \pi/2$, $F(\pi/2) = 1$ gives the accumulated area under the cosine curve on the entire interval $[0, \pi/2]$. This interpretation of an integral as an **accumulation function** is used often in applications of integration.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

In Example 6, note that the derivative of F is the original integrand (with only the variable changed). That is,

$$\frac{d}{dx}[F(x)] = \frac{d}{dx}[\sin x] = \frac{d}{dx}\left[\int_0^x \cos t\, dt\right] = \cos x.$$

This result is generalized in the next theorem, called the **Second Fundamental Theorem of Calculus.**

THEOREM 4.11 The Second Fundamental Theorem of Calculus

If a function f is continuous on an open interval I containing a, then, for every x in the interval,

$$\frac{d}{dx}\left[\int_a^x f(t)\, dt\right] = f(x).$$

Proof Begin by defining F as

$$F(x) = \int_a^x f(t)\, dt.$$

Then, by the definition of the derivative, you can write

$$\begin{aligned} F'(x) &= \lim_{\Delta x \to 0} \frac{F(x + \Delta x) - F(x)}{\Delta x} \\ &= \lim_{\Delta x \to 0} \frac{1}{\Delta x}\left[\int_a^{x+\Delta x} f(t)\, dt - \int_a^x f(t)\, dt\right] \\ &= \lim_{\Delta x \to 0} \frac{1}{\Delta x}\left[\int_a^{x+\Delta x} f(t)\, dt + \int_x^a f(t)\, dt\right] \\ &= \lim_{\Delta x \to 0} \frac{1}{\Delta x}\left[\int_x^{x+\Delta x} f(t)\, dt\right]. \end{aligned}$$

From the Mean Value Theorem for Integrals (assuming $\Delta x > 0$), there exists a number c in the interval $[x, x + \Delta x]$ such that the integral in the expression above is equal to $f(c)\,\Delta x$. Moreover, because $x \le c \le x + \Delta x$, it follows that $c \to x$ as $\Delta x \to 0$. So, you obtain

$$F'(x) = \lim_{\Delta x \to 0}\left[\frac{1}{\Delta x} f(c)\,\Delta x\right] = \lim_{\Delta x \to 0} f(c) = f(x).$$

A similar argument can be made for $\Delta x < 0$. ∎

Using the area model for definite integrals, the approximation

$$f(x)\,\Delta x \approx \int_x^{x+\Delta x} f(t)\, dt$$

can be viewed as saying that the area of the rectangle of height $f(x)$ and width Δx is approximately equal to the area of the region lying between the graph of f and the x-axis on the interval

$$[x, x + \Delta x]$$

as shown in the figure at the right.



$$f(x)\,\Delta x \approx \int_x^{x+\Delta x} f(t)\, dt$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Note that the Second Fundamental Theorem of Calculus tells you that when a function is continuous, you can be sure that it has an antiderivative. This antiderivative need not, however, be an elementary function. (Recall the discussion of elementary functions in Section P.3.)

EXAMPLE 7 The Second Fundamental Theorem of Calculus

Evaluate $\frac{d}{dx}\left[\int_0^x \sqrt{t^2 + 1}\, dt\right]$.

Solution Note that $f(t) = \sqrt{t^2 + 1}$ is continuous on the entire real number line. So, using the Second Fundamental Theorem of Calculus, you can write

$$\frac{d}{dx}\left[\int_0^x \sqrt{t^2 + 1}\, dt\right] = \sqrt{x^2 + 1}.$$

The differentiation shown in Example 7 is a straightforward application of the Second Fundamental Theorem of Calculus. The next example shows how this theorem can be combined with the Chain Rule to find the derivative of a function.

EXAMPLE 8 The Second Fundamental Theorem of Calculus

Find the derivative of $F(x) = \int_{\pi/2}^{x^3} \cos t\, dt$.

Solution Using $u = x^3$, apply the Second Fundamental Theorem of Calculus with the Chain Rule as shown.

$$\begin{aligned}
F'(x) &= \frac{dF}{du}\frac{du}{dx} && \text{Chain Rule} \\
&= \frac{d}{du}[F(x)]\frac{du}{dx} && \text{Definition of } \frac{dF}{du} \\
&= \frac{d}{du}\left[\int_{\pi/2}^{x^3} \cos t\, dt\right]\frac{du}{dx} && \text{Substitute } \int_{\pi/2}^{x^3} \cos t\, dt \text{ for } F(x). \\
&= \frac{d}{du}\left[\int_{\pi/2}^{u} \cos t\, dt\right]\frac{du}{dx} && \text{Substitute } u \text{ for } x^3. \\
&= (\cos u)(3x^2) && \text{Apply Second Fundamental Theorem of Calculus.} \\
&= (\cos x^3)(3x^2) && \text{Rewrite as function of } x.
\end{aligned}$$

Because the integrand in Example 8 is easily integrated, you can verify the derivative as shown below. First, rewrite F as

$$\begin{aligned}
F(x) &= \int_{\pi/2}^{x^3} \cos t\, dt \\
&= \sin t\Big]_{\pi/2}^{x^3} \\
&= \sin x^3 - \sin\frac{\pi}{2} \\
&= \sin x^3 - 1.
\end{aligned}$$

Then, in this form, apply the Chain Rule to verify that the derivative of F is the same as that obtained in Example 8.

$$\frac{d}{dx}[\sin x^3 - 1] = (\cos x^3)(3x^2) \qquad \text{Derivative of } F$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Net Change Theorem

The Fundamental Theorem of Calculus (Theorem 4.9) states that if a function f is continuous on the closed interval $[a, b]$ and F is an antiderivative of f on $[a, b]$, then

$$\int_a^b f(x)\,dx = F(b) - F(a).$$

But because $F'(x) = f(x)$, this statement can be rewritten as

$$\int_a^b F'(x)\,dx = F(b) - F(a)$$

where the quantity $F(b) - F(a)$ represents the *net change of* $F(x)$ on the interval $[a, b]$.

THEOREM 4.12 The Net Change Theorem

If $F'(x)$ is the rate of change of a quantity $F(x)$, then the definite integral of $F'(x)$ from a to b gives the total change, or **net change,** of $F(x)$ on the interval $[a, b]$.

$$\int_a^b F'(x)\,dx = F(b) - F(a) \qquad \text{Net change of } F(x)$$

EXAMPLE 9 Using the Net Change Theorem

A chemical flows into a storage tank at a rate of $(180 + 3t)$ liters per minute, where t is the time in minutes and $0 \le t \le 60$. Find the amount of the chemical that flows into the tank during the first 20 minutes.

Solution Let $c(t)$ be the amount of the chemical in the tank at time t. Then $c'(t)$ represents the rate at which the chemical flows into the tank at time t. During the first 20 minutes, the amount that flows into the tank is

$$\begin{aligned}\int_0^{20} c'(t)\,dt &= \int_0^{20} (180 + 3t)\,dt \\ &= \left[180t + \frac{3}{2}t^2\right]_0^{20} \\ &= 3600 + 600 \\ &= 4200.\end{aligned}$$

So, the amount of the chemical that flows into the tank during the first 20 minutes is 4200 liters. ■

A common application of the Net Change Theorem is a particle motion problem. Consider a particle moving along a straight line, where $s(t)$ is the position at time t. The velocity of the particle is $v(t) = s'(t)$ and

$$\int_a^b v(t)\,dt = s(b) - s(a) \qquad \text{Displacement on } [a, b]$$

is the net change in position, or **displacement,** of the particle on the time interval $a \le t \le b$.

goldenjack/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



A_1, A_2, and A_3 are the areas of the shaded regions.

Figure 4.36

To calculate the **total distance** the particle travels on the time interval $a \le t \le b$, you must consider the intervals where $v(t) < 0$ and the intervals where $v(t) > 0$. When $v(t) < 0$, the particle moves to the left. When $v(t) > 0$, the particle moves to the right. In both cases, the distance is found by integrating the **speed** of the particle, $|v(t)|$.

$$\text{Total distance traveled on } [a, b] = \int_a^b |v(t)|\, dt$$

Figure 4.36 shows how both displacement and total distance traveled can be interpreted as areas under a velocity curve.

$$\text{Displacement on } [a, b] = \int_a^b v(t)\, dt = A_1 - A_2 + A_3$$

$$\text{Total distance traveled on } [a, b] = \int_a^b |v(t)|\, dt = A_1 + A_2 + A_3$$

GO DIGITAL

EXAMPLE 10 Solving a Particle Motion Problem

The velocity (in feet per second) of a particle moving along a line is

$$v(t) = t^3 - 10t^2 + 29t - 20$$

where t is the time in seconds.

a. What is the displacement of the particle on the time interval $1 \le t \le 5$?

b. What is the total distance traveled by the particle on the time interval $1 \le t \le 5$?

Solution

a. The displacement of the particle on $1 \le t \le 5$ is

$$\begin{aligned}\int_1^5 v(t)\, dt &= \int_1^5 (t^3 - 10t^2 + 29t - 20)\, dt \\ &= \left[\frac{1}{4}t^4 - \frac{10}{3}t^3 + \frac{29}{2}t^2 - 20t\right]_1^5 \\ &= \frac{25}{12} - \left(-\frac{103}{12}\right) \\ &= \frac{32}{3} \text{ feet.}\end{aligned}$$

So, the particle moves about 10.667 feet to the right.

b. To find the total distance traveled, calculate $\int_1^5 |v(t)|\, dt$. Using Figure 4.37 and the fact that $v(t)$ can be factored as $(t - 1)(t - 4)(t - 5)$, you can determine that $v(t) > 0$ on the interval $(1, 4)$ and $v(t) < 0$ on the interval $(4, 5)$. So, the total distance traveled on $1 \le t \le 5$ is

$$\begin{aligned}\int_1^5 |v(t)|\, dt &= \int_1^4 v(t)\, dt + \int_4^5 -v(t)\, dt \\ &= \int_1^4 (t^3 - 10t^2 + 29t - 20)\, dt + \int_4^5 -(t^3 - 10t^2 + 29t - 20)\, dt \\ &= \left[\frac{1}{4}t^4 - \frac{10}{3}t^3 + \frac{29}{2}t^2 - 20t\right]_1^4 + \left[-\frac{1}{4}t^4 + \frac{10}{3}t^3 - \frac{29}{2}t^2 + 20t\right]_4^5 \\ &= \frac{45}{4} + \frac{7}{12} \\ &= \frac{71}{6} \text{ feet}\end{aligned}$$

or about 11.833 feet.



Figure 4.37

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

4.4 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain how to evaluate a definite integral using the Fundamental Theorem of Calculus.
2. Describe the Mean Value Theorem for Integrals.
3. Explain how to find the average value of a function on an interval.
4. Explain why

$$F(x) = \int_0^x f(t)\,dt$$

is considered an accumulation function.

Graphical Reasoning **In Exercises 5–8, use a graphing utility to graph the integrand. Use the graph to determine whether the definite integral is positive, negative, or zero.**

5. $\displaystyle\int_0^{\pi} \frac{4}{x^2+1}\,dx$
6. $\displaystyle\int_0^{\pi} \cos x\,dx$
7. $\displaystyle\int_{-2}^{2} x\sqrt{x^2+1}\,dx$
8. $\displaystyle\int_{-2}^{2} x\sqrt{2-x}\,dx$

Evaluating a Definite Integral **In Exercises 9–36, evaluate the definite integral. Use a graphing utility to verify your result.**

9. $\displaystyle\int_{-1}^{0} (2x-1)\,dx$
10. $\displaystyle\int_{-1}^{2} (7-3t)\,dt$
11. $\displaystyle\int_{-1}^{1} (t^2-5)\,dt$
12. $\displaystyle\int_{1}^{2} (6x^2-3x)\,dx$
13. $\displaystyle\int_{0}^{1} (2t-1)^2\,dt$
14. $\displaystyle\int_{1}^{4} (8x^3-x)\,dx$
15. $\displaystyle\int_{1}^{2} \left(\frac{3}{x^2}-1\right)dx$
16. $\displaystyle\int_{-2}^{-1} \left(u-\frac{1}{u^2}\right)du$
17. $\displaystyle\int_{1}^{4} \frac{u-2}{\sqrt{u}}\,du$
18. $\displaystyle\int_{-8}^{8} x^{1/3}\,dx$
19. $\displaystyle\int_{-1}^{1} \left(\sqrt[3]{t}-2\right)dt$
20. $\displaystyle\int_{1}^{8} \sqrt{\frac{2}{x}}\,dx$
21. $\displaystyle\int_{0}^{1} \frac{x-\sqrt{x}}{3}\,dx$
22. $\displaystyle\int_{0}^{2} (6-t)\sqrt{t}\,dt$
23. $\displaystyle\int_{-1}^{0} (t^{1/3}-t^{2/3})\,dt$
24. $\displaystyle\int_{-8}^{-1} \frac{x-x^2}{2\sqrt[3]{x}}\,dx$
25. $\displaystyle\int_{0}^{5} |2x-5|\,dx$
26. $\displaystyle\int_{1}^{4} (3-|x-3|)\,dx$
27. $\displaystyle\int_{0}^{4} |x^2-9|\,dx$
28. $\displaystyle\int_{0}^{4} |x^2-4x+3|\,dx$
29. $\displaystyle\int_{0}^{\pi} (\sin x-7)\,dx$
30. $\displaystyle\int_{0}^{\pi} (2+\cos x)\,dx$
31. $\displaystyle\int_{0}^{\pi/4} \frac{1-\sin^2\theta}{\cos^2\theta}\,d\theta$
32. $\displaystyle\int_{0}^{\pi/4} \frac{\sec^2\theta}{\tan^2\theta+1}\,d\theta$
33. $\displaystyle\int_{-\pi/6}^{\pi/6} \sec^2 x\,dx$
34. $\displaystyle\int_{\pi/4}^{\pi/2} (2-\csc^2 x)\,dx$
35. $\displaystyle\int_{-\pi/3}^{\pi/3} 4\sec\theta\tan\theta\,d\theta$
36. $\displaystyle\int_{-\pi/2}^{\pi/2} (2\theta+\cos\theta)\,d\theta$

Finding the Area of a Region **In Exercises 37–40, find the area of the given region.**

37. $y = x - x^2$



38. $y = \dfrac{1}{x^2}$



39. $y = \cos x$



40. $y = x + \sin x$



Finding the Area of a Region **In Exercises 41–46, find the area of the region bounded by the graphs of the equations.**

41. $y = 5x^2 + 2, \quad x = 0, \quad x = 2, \quad y = 0$
42. $y = x^3 + 6x, \quad x = 2, \quad y = 0$
43. $y = 1 + \sqrt[3]{x}, \quad x = 0, \quad x = 8, \quad y = 0$
44. $y = 2\sqrt{x} - x, \quad y = 0$
45. $y = -x^2 + 4x, \quad y = 0$
46. $y = 1 - x^4, \quad y = 0$

Using the Mean Value Theorem for Integrals **In Exercises 47–52, find the value(s) of c guaranteed by the Mean Value Theorem for Integrals for the function over the given interval.**

47. $f(x) = x^3, \quad [0, 3]$
48. $f(x) = \sqrt{x}, \quad [4, 9]$
49. $y = \dfrac{x^2}{4}, \quad [0, 6]$
50. $f(x) = \dfrac{9}{x^3}, \quad [1, 3]$
51. $f(x) = 2\sec^2 x, \quad \left[-\dfrac{\pi}{4}, \dfrac{\pi}{4}\right]$
52. $f(x) = \cos x, \quad \left[-\dfrac{\pi}{3}, \dfrac{\pi}{3}\right]$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding the Average Value of a Function **In Exercises 53–58, find the average value of the function over the given interval and all values of x in the interval for which the function equals its average value.**

53. $f(x) = 4 - x^2, \quad [-2, 2]$

54. $f(x) = \dfrac{4(x^2 + 1)}{x^2}, \quad [1, 3]$

55. $f(x) = x^4 + 7, \quad [0, 2]$

56. $f(x) = 4x^3 - 3x^2, \quad [0, 1]$

57. $f(x) = \sin x, \quad [0, \pi]$

58. $f(x) = \cos x, \quad \left[0, \dfrac{\pi}{2}\right]$

59. Force The force F (in newtons) of a hydraulic cylinder in a press is proportional to the square of $\sec x$, where x is the distance (in meters) that the cylinder is extended in its cycle. The domain of F is $[0, \pi/3]$, and $F(0) = 500$.

(a) Find F as a function of x.

(b) Find the average force exerted by the press over the interval $[0, \pi/3]$.

60. Respiratory Cycle The volume V, in liters, of air in the lungs during a five-second respiratory cycle is approximated by the model $V = 0.1729t + 0.1522t^2 - 0.0374t^3$, where t is the time in seconds. Approximate the average volume of air in the lungs during one cycle.

61. Buffon's Needle Experiment A horizontal plane is ruled with parallel lines 2 inches apart. A two-inch needle is tossed randomly onto the plane. The probability that the needle will touch a line is

$$P = \frac{2}{\pi}\int_0^{\pi/2} \sin\theta \, d\theta$$

where θ is the acute angle between the needle and any one of the parallel lines. Find this probability.



62. HOW DO YOU SEE IT? The graph of a function f is shown in the figure. The shaded region A has an area of 1.5, and $\int_0^6 f(x)\,dx = 3.5$. Use this information to fill in the blanks.



(a) $\displaystyle\int_0^2 f(x)\,dx =$ ____

(b) $\displaystyle\int_2^6 f(x)\,dx =$ ____

(c) $\displaystyle\int_0^6 |f(x)|\,dx =$ ____

(d) $\displaystyle\int_0^2 -2f(x)\,dx =$ ____

(e) $\displaystyle\int_0^6 [2 + f(x)]\,dx =$ ____

(f) The average value of f over the interval $[0, 6]$ is ____.

Evaluating a Definite Integral **In Exercises 63 and 64, find F as a function of x and evaluate it at $x = 2$, $x = 5$, and $x = 8$.**

63. $F(x) = \displaystyle\int_1^x \frac{20}{v^2}\,dv$

64. $F(x) = \displaystyle\int_2^x (t^3 + 2t - 2)\,dt$

Evaluating a Definite Integral **In Exercises 65 and 66, find F as a function of x and evaluate it at $x = 0$, $x = \pi/4$, and $x = \pi/2$.**

65. $F(x) = \displaystyle\int_0^x \cos\theta\,d\theta$

66. $F(x) = \displaystyle\int_{-\pi}^x \sin\theta\,d\theta$

67. Analyzing a Function Let

$$g(x) = \int_0^x f(t)\,dt$$

where f is the function whose graph is shown in the figure.

(a) Estimate $g(0)$, $g(2)$, $g(4)$, $g(6)$, and $g(8)$.

(b) Find the largest open interval on which g is increasing. Find the largest open interval on which g is decreasing.

(c) Identify any extrema of g.

(d) Sketch a rough graph of g.



Figure for 67



Figure for 68

68. Analyzing a Function Let

$$g(x) = \int_0^x f(t)\,dt$$

where f is the function whose graph is shown in the figure.

(a) Estimate $g(0)$, $g(2)$, $g(4)$, $g(6)$, and $g(8)$.

(b) Find the largest open interval on which g is increasing. Find the largest open interval on which g is decreasing.

(c) Identify any extrema of g.

(d) Sketch a rough graph of g.

Finding and Checking an Integral **In Exercises 69–74, (a) integrate to find F as a function of x, and (b) demonstrate the Second Fundamental Theorem of Calculus by differentiating the result in part (a).**

69. $F(x) = \displaystyle\int_0^x (t + 2)\,dt$

70. $F(x) = \displaystyle\int_0^x t(t^2 + 1)\,dt$

71. $F(x) = \displaystyle\int_8^x \sqrt[3]{t}\,dt$

72. $F(x) = \displaystyle\int_4^x t^{3/2}\,dt$

73. $F(x) = \displaystyle\int_{\pi/4}^x \sec^2 t\,dt$

74. $F(x) = \displaystyle\int_{\pi/3}^x \sec t \tan t\,dt$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Using the Second Fundamental Theorem of Calculus

In Exercises 75–80, use the Second Fundamental Theorem of Calculus to find $F'(x)$.

75. $F(x) = \int_{-2}^{x} (t^2 - 2t)\,dt$

76. $F(x) = \int_{1}^{x} \frac{t^2}{t^2 + 1}\,dt$

77. $F(x) = \int_{-1}^{x} \sqrt{t^4 + 1}\,dt$

78. $F(x) = \int_{1}^{x} \sqrt[4]{t}\,dt$

79. $F(x) = \int_{1}^{x} \sqrt{t}\csc t\,dt$

80. $F(x) = \int_{0}^{x} \sec^3 t\,dt$

Finding a Derivative

In Exercises 81–86, find $F'(x)$.

81. $F(x) = \int_{x}^{x+2} (4t + 1)\,dt$

82. $F(x) = \int_{-x}^{x} t^3\,dt$

83. $F(x) = \int_{0}^{\sin x} \sqrt{t}\,dt$

84. $F(x) = \int_{2}^{x^2} \frac{1}{t^3}\,dt$

85. $F(x) = \int_{0}^{x^3} \sin t^2\,dt$

86. $F(x) = \int_{0}^{2x} \cos t^4\,dt$

87. Graphical Analysis Sketch an approximate graph of g on the interval $0 \le x \le 4$, where

$$g(x) = \int_{0}^{x} f(t)\,dt.$$

Identify the x-coordinate of an extremum of g. To print an enlarged copy of the graph, go to *MathGraphs.com.*



88. Area The area A between the graph of the function

$$g(t) = 4 - \frac{4}{t^2}$$

and the t-axis over the interval $[1, x]$ is

$$A(x) = \int_{1}^{x} \left(4 - \frac{4}{t^2}\right) dt.$$

(a) Find the horizontal asymptote of the graph of g.

(b) Integrate to find A as a function of x. Does the graph of A have a horizontal asymptote? Explain.

89. Water Flow Water flows from a storage tank at a rate of $(500 - 5t)$ liters per minute. Find the amount of water that flows out of the tank during the first 18 minutes.

90. Oil Leak At 1:00 P.M., oil begins leaking from a tank at a rate of $(4 + 0.75t)$ gallons per hour.

(a) How much oil is lost from 1:00 P.M. to 4:00 P.M.?

(b) How much oil is lost from 4:00 P.M. to 7:00 P.M.?

(c) Compare your answers to parts (a) and (b). What do you notice?

91. Velocity The graph shows the velocity, in feet per second, of a car accelerating from rest. Use the graph to estimate the distance the car travels in 8 seconds.



92. Velocity The graph shows the velocity, in feet per second, of a decelerating car after the driver applies the brakes. Use the graph to estimate how far the car travels before it comes to a stop.



Particle Motion

In Exercises 93–98, the velocity function, in feet per second, is given for a particle moving along a straight line, where t is the time in seconds. Find (a) the displacement and (b) the total distance that the particle travels over the given interval.

93. $v(t) = 5t - 7, \quad 0 \le t \le 3$

94. $v(t) = t^2 - t - 12, \quad 1 \le t \le 5$

95. $v(t) = t^3 - 10t^2 + 27t - 18, \quad 1 \le t \le 7$

96. $v(t) = t^3 - 8t^2 + 15t, \quad 0 \le t \le 5$

97. $v(t) = \frac{1}{\sqrt{t}}, \quad 1 \le t \le 4$

98. $v(t) = \cos t, \quad 0 \le t \le 3\pi$

99. Average Sales A company fits a model to the monthly sales data for a seasonal product. The model is

$$S(t) = \frac{t}{4} + 1.8 + 0.5\sin\left(\frac{\pi t}{6}\right), \quad 0 \le t \le 24$$

where S is sales in thousands and t is time in months.

(a) Use a graphing utility to graph $f(t) = 0.5\sin(\pi t/6)$ for $0 \le t \le 24$. Use the graph to explain why the average value of $f(t)$ is 0 over the interval.

(b) Use a graphing utility to graph $S(t)$ and the line $g(t) = t/4 + 1.8$ in the same viewing window. Use the graph and the result of part (a) to explain why g is called the *trend line*.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

100. Average Value The average value of $g(x)$ on $[-1, 1]$ is 8, and the average value of $g(x)$ on $[1, 6]$ is 7. Find the average value of $g(x)$ on $[-1, 6]$.

Exploring Concepts

101. Describe a situation where the displacement and the total distance traveled for a particle are equal.

102. Let $r'(t)$ represent the rate of growth of a dog in pounds per year. What does $r(t)$ represent? What does $\int_2^6 r'(t)\,dt$ represent about the dog?

103. Explain why the Fundamental Theorem of Calculus cannot be used to integrate

$$f(x) = \frac{1}{x - c}$$

on any interval containing c.

104. Modeling Data An experimental vehicle is tested on a straight track. It starts from rest, and its velocity v (in meters per second) is recorded every 10 seconds for 1 minute (see table).

t	0	10	20	30	40	50	60
v	0	5	21	40	62	78	83

(a) Use a graphing utility to find a model of the form $v = at^3 + bt^2 + ct + d$ for the data.

(b) Use a graphing utility to plot the data and graph the model.

(c) Approximate the distance traveled by the vehicle during the test.

105. Particle Motion A particle is moving along the x-axis. The position of the particle at time t is given by

$$x(t) = t^3 - 6t^2 + 9t - 2, \quad 0 \le t \le 5.$$

Find the total distance the particle travels in 5 units of time.

106. Particle Motion Repeat Exercise 105 for the position function given by

$$x(t) = (t - 1)(t - 3)^2, \quad 0 \le t \le 5.$$

Error Analysis **In Exercises 107–110, describe why the statement is incorrect.**

107. $\displaystyle\int_{-1}^{1} x^{-2}\,dx = \left[-x^{-1}\right]_{-1}^{1} = (-1) - 1 = -2$ ✗

108. $\displaystyle\int_{-2}^{1} \frac{2}{x^3}\,dx = \left[-\frac{1}{x^2}\right]_{-2}^{1} = -\frac{3}{4}$ ✗

109. $\displaystyle\int_{\pi/4}^{3\pi/4} \sec^2 x\,dx = \left[\tan x\right]_{\pi/4}^{3\pi/4} = -2$ ✗

110. $\displaystyle\int_{\pi/2}^{3\pi/2} \csc x \cot x\,dx = \left[-\csc x\right]_{\pi/2}^{3\pi/2} = 2$ ✗

True or False? **In Exercises 111 and 112, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

111. If $F'(x) = G'(x)$ on the interval $[a, b]$, then

$$F(b) - F(a) = G(b) - G(a).$$

112. If $F(b) - F(a) = G(b) - G(a)$, then $F'(x) = G'(x)$ on the interval $[a, b]$.

113. Antiderivative Find an antiderivative of

$$f(x) = |x|.$$

114. Analyzing a Function Show that the function

$$f(x) = \int_0^{1/x} \frac{1}{t^2 + 1}\,dt + \int_0^{x} \frac{1}{t^2 + 1}\,dt$$

is constant for $x > 0$.

115. Finding a Function Find the function $f(x)$ and all values of c such that

$$\int_c^x f(t)\,dt = x^2 + x - 2.$$

116. Using a Function Let $L(x) = \displaystyle\int_1^x \frac{1}{t}\,dt$, $x > 0$.

(a) Find $L(1)$.

(b) Find $L'(x)$ and $L'(1)$.

(c) Use a graphing utility to approximate the value of x (to three decimal places) for which $L(x) = 1$.

(d) Prove that $L(x_1x_2) = L(x_1) + L(x_2)$ for all positive values of x_1 and x_2.

117. Finding Values Let

$$G(x) = \int_0^x \left[s \int_0^s f(t)\,dt \right] ds$$

where f is continuous for all real t. Find (a) $G(0)$, (b) $G'(0)$, (c) $G''(x)$, and (d) $G''(0)$.

118. Proof Prove that

$$\frac{d}{dx}\left[\int_{u(x)}^{v(x)} f(t)\,dt\right] = f(v(x))v'(x) - f(u(x))u'(x).$$

PUTNAM EXAM CHALLENGE

119. For each continuous function $f\colon [0, 1] \to \mathbb{R}$, let

$$I(f) = \int_0^1 x^2 f(x)\,dx$$

and

$$J(f) = \int_0^1 x(f(x))^2\,dx.$$

Find the maximum value of $I(f) - J(f)$ over all such functions f.

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

4.5 Integration by Substitution

GO DIGITAL

- **Use pattern recognition to find an indefinite integral.**
- **Use a change of variables to find an indefinite integral.**
- **Use the General Power Rule for Integration to find an indefinite integral.**
- **Use a change of variables to evaluate a definite integral.**
- **Evaluate a definite integral involving an even or odd function.**

Pattern Recognition

In this section, you will study techniques for integrating composite functions. The discussion is split into two parts—*pattern recognition* and *change of variables.* Both techniques involve a ***u*-substitution.** With pattern recognition, you perform the substitution mentally, and with change of variables, you write the substitution steps.

The role of substitution in integration is comparable to the role of the Chain Rule in differentiation. Recall that for the differentiable functions

$$y = F(u) \quad \text{and} \quad u = g(x)$$

the Chain Rule states that

$$\frac{d}{dx}[F(g(x))] = F'(g(x))g'(x).$$

From the definition of an antiderivative, it follows that

$$\int F'(g(x))g'(x)\,dx = F(g(x)) + C.$$

These results are summarized in the next theorem.

REMARK The statement of Theorem 4.13 does not tell how to distinguish between $f(g(x))$ and $g'(x)$ in the integrand. As you become more experienced at integration, your skill in doing this will improve. Of course, part of the key is familiarity with derivatives.

THEOREM 4.13 Antidifferentiation of a Composite Function

Let g be a function whose range is an interval I, and let f be a function that is continuous on I. If g is differentiable on its domain and F is an antiderivative of f on I, then

$$\int f(g(x))g'(x)\,dx = F(g(x)) + C.$$

Letting $u = g(x)$ gives $du = g'(x)\,dx$ and

$$\int f(u)\,du = F(u) + C.$$

Examples 1 and 2 show how to apply Theorem 4.13 *directly*, by recognizing the presence of $f(g(x))$ and $g'(x)$. Note that the composite function in the integrand has an *outside function* f and an *inside function* g. Moreover, the derivative $g'(x)$ is present as a factor of the integrand.



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 1 Recognizing the $f(g(x))g'(x)$ Pattern

Find $\int (x^2 + 1)^2(2x)\,dx$.

Solution Letting $g(x) = x^2 + 1$, you obtain

$$g'(x) = 2x$$ Derivative of g

and

$$f(g(x)) = f(x^2 + 1) = (x^2 + 1)^2.$$ Composition of f with g

From this, you can recognize that the integrand follows the $f(g(x))g'(x)$ pattern. Using the Power Rule for Integration and Theorem 4.13, you can write

$$\int \overbrace{(x^2 + 1)^2}^{f(g(x))}\overbrace{(2x)}^{g'(x)}\,dx = \frac{1}{3}(x^2 + 1)^3 + C.$$

Use the Chain Rule to check that the derivative of $\frac{1}{3}(x^2 + 1)^3 + C$ is the integrand of the original integral.

EXAMPLE 2 Recognizing the $f(g(x))g'(x)$ Pattern

Find $\int 5 \cos 5x\,dx$.

Solution Letting $g(x) = 5x$, you obtain

$$g'(x) = 5$$ Derivative of g

and

$$f(g(x)) = f(5x) = \cos 5x.$$ Composition of f with g

From this, you can recognize that the integrand follows the $f(g(x))g'(x)$ pattern. Using the Cosine Rule for Integration and Theorem 4.13, you can write

$$\int \overbrace{(\cos 5x)}^{f(g(x))}\overbrace{(5)}^{g'(x)}\,dx = \sin 5x + C.$$

Check this result by differentiating $\sin 5x + C$ to obtain the original integrand.

TECHNOLOGY

Use a graphing utility, such as *Maple*, *Mathematica*, or the *TI-Nspire*, to find the integrals given in Examples 1 and 2. Do you obtain the same antiderivatives that are listed in the examples?

Exploration

Recognizing Patterns The integrand in each of the integrals labeled (a)–(c) fits the pattern $f(g(x))g'(x)$. Identify the pattern and use the result to find the integral.

a. $\int 2x(x^2 + 1)^4\,dx$ **b.** $\int 3x^2\sqrt{x^3 + 1}\,dx$ **c.** $\int (\sec^2 x)(\tan x + 3)\,dx$

The integrals labeled (d)–(f) are similar to (a)–(c). Show how you can multiply and divide by a constant to find these integrals.

d. $\int x(x^2 + 1)^4\,dx$ **e.** $\int x^2\sqrt{x^3 + 1}\,dx$ **f.** $\int (2 \sec^2 x)(\tan x + 3)\,dx$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The integrands in Examples 1 and 2 fit the $f(g(x))g'(x)$ pattern exactly—you only had to recognize the pattern. You can extend this technique considerably with the Constant Multiple Rule

$$\int kf(x)\,dx = k\int f(x)\,dx.$$

Many integrands contain the essential part (the variable part) of $g'(x)$ but are missing a constant multiple. In such cases, you can multiply and divide by the necessary constant multiple, as shown in Example 3.

EXAMPLE 3 Multiplying and Dividing by a Constant

Find the indefinite integral.

$$\int x(x^2 + 1)^2\,dx$$

Solution This is similar to the integral given in Example 1, except that the integrand is missing a factor of 2. Recognizing that $2x$ is the derivative of $x^2 + 1$, let

$$g(x) = x^2 + 1.$$

To obtain a factor of 2, multiply and divide the integrand by the constant 2.

$$\int x(x^2 + 1)^2\,dx = \int (x^2 + 1)^2 \left(\frac{1}{2}\right)(2x)\,dx \qquad \text{Multiply and divide by 2.}$$

$$= \frac{1}{2}\int \overbrace{(x^2 + 1)^2}^{f(g(x))}\overbrace{(2x)}^{g'(x)}\,dx \qquad \text{Constant Multiple Rule}$$

$$= \frac{1}{2}\left[\frac{(x^2 + 1)^3}{3}\right] + C \qquad \text{Integrate.}$$

$$= \frac{1}{6}(x^2 + 1)^3 + C \qquad \text{Simplify.}$$

In practice, most people would not write as many steps as are shown in Example 3. For instance, you could evaluate the integral by writing

$$\int x(x^2 + 1)^2\,dx = \frac{1}{2}\int (x^2 + 1)^2\,(2x)\,dx$$

$$= \frac{1}{2}\left[\frac{(x^2 + 1)^3}{3}\right] + C$$

$$= \frac{1}{6}(x^2 + 1)^3 + C.$$

Be sure you see that the *Constant* Multiple Rule applies only to *constants*. You cannot multiply and divide by a variable and then move the variable outside the integral sign. For instance,

$$\int (x^2 + 1)^2\,dx \neq \frac{1}{2x}\int (x^2 + 1)^2\,(2x)\,dx.$$

After all, if it were legitimate to move variable quantities outside the integral sign, you could move the entire integrand out and simplify the whole process. But the result would be incorrect.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Change of Variables for Indefinite Integrals

With a formal **change of variables,** you completely rewrite the integral in terms of u and du (or any other convenient variable). Although this procedure can involve more written steps than the pattern recognition illustrated in Examples 1 through 3, it is useful for complicated integrands. The change of variables technique uses the Leibniz notation for the differential. That is, if $u = g(x)$, then $du = g'(x)\,dx$, and the integral in Theorem 4.13 takes the form

$$\int f(g(x))g'(x)\,dx = \int f(u)\,du = F(u) + C.$$

EXAMPLE 4 Change of Variables

Find $\int \sqrt{2x - 1}\,dx$.

Solution First, let u be the inner function, $u = 2x - 1$. Then calculate the differential du to be $du = 2\,dx$. Now, using $\sqrt{2x - 1} = \sqrt{u}$ and $dx = du/2$, substitute to obtain

$$\begin{aligned}
\int \sqrt{2x - 1}\,dx &= \int \sqrt{u}\left(\frac{du}{2}\right) && \text{Substitute.}\\
&= \frac{1}{2}\int u^{1/2}\,du && \text{Constant Multiple Rule}\\
&= \frac{1}{2}\left(\frac{u^{3/2}}{3/2}\right) + C && \text{Antiderivative in terms of } u\\
&= \frac{1}{3}u^{3/2} + C && \text{Simplify.}\\
&= \frac{1}{3}(2x - 1)^{3/2} + C. && \text{Antiderivative in terms of } x
\end{aligned}$$

REMARK Because integration is usually more difficult than differentiation, you should always check your answer to an integration problem by differentiating. For instance, in Example 4, differentiate $\frac{1}{3}(2x - 1)^{3/2} + C$ to verify that you obtain the original integrand.

EXAMPLE 5 Change of Variables

See LarsonCalculus.com for an interactive version of this type of example.

Find $\int x\sqrt{2x - 1}\,dx$.

Solution As in the previous example, let $u = 2x - 1$ and obtain $dx = du/2$. Because the integrand contains a factor of x, you must also solve for x in terms of u, as shown.

$$u = 2x - 1 \quad \Rightarrow \quad x = \frac{u + 1}{2} \qquad \text{Solve for } x \text{ in terms of } u.$$

Now, using substitution, you obtain

$$\begin{aligned}
\int x\sqrt{2x - 1}\,dx &= \int \left(\frac{u + 1}{2}\right)u^{1/2}\left(\frac{du}{2}\right) && \text{Substitute.}\\
&= \frac{1}{4}\int (u^{3/2} + u^{1/2})\,du\\
&= \frac{1}{4}\left(\frac{u^{5/2}}{5/2} + \frac{u^{3/2}}{3/2}\right) + C\\
&= \frac{1}{10}(2x - 1)^{5/2} + \frac{1}{6}(2x - 1)^{3/2} + C.
\end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

To complete the change of variables in Example 5, you solved for x in terms of u. Sometimes this is very difficult. Fortunately, it is not always necessary, as shown in the next example.

EXAMPLE 6 Change of Variables

Find $\int \sin^2 3x \cos 3x \, dx$.

Solution Because $\sin^2 3x = (\sin 3x)^2$, let $u = \sin 3x$. Then

$du = (\cos 3x)(3)\, dx.$ Differentiate each side.

Now, because $\cos 3x \, dx$ is part of the original integral, you can write

$\frac{du}{3} = \cos 3x \, dx.$ Divide each side by 3.

Substituting u and $du/3$ in the original integral yields

$$\int \sin^2 3x \cos 3x \, dx = \int u^2 \frac{du}{3}$$ Substitute.

$$= \frac{1}{3}\int u^2 \, du$$ Constant Multiple Rule

$$= \frac{1}{3}\left(\frac{u^3}{3}\right) + C$$ Antiderivative in terms of u

$$= \frac{1}{9}\sin^3 3x + C.$$ Antiderivative in terms of x

You can check this by differentiating.

$$\frac{d}{dx}\left[\frac{1}{9}\sin^3 3x + C\right] = \left(\frac{1}{9}\right)(3)(\sin 3x)^2(\cos 3x)(3)$$

$$= \sin^2 3x \cos 3x$$

Because differentiation produces the original integrand, you know that you have obtained the correct antiderivative. ■

REMARK When making a change of variables, be sure that your answer is written using the same variables as in the original integrand. For instance, in Example 6, you should not leave your answer as

$$\frac{1}{9}u^3 + C$$

but rather, you should replace u by $\sin 3x$.

The steps used for integration by substitution are summarized in the following guidelines.

Guidelines for Making a Change of Variables

1. Choose a substitution $u = g(x)$. Usually, it is best to choose the *inner* part of a composite function, such as a quantity raised to a power.
2. Compute $du = g'(x)\, dx$.
3. Rewrite the integral in terms of u and du.
4. Find the resulting integral in terms of u.
5. Replace u by $g(x)$ to obtain an antiderivative in terms of x.
6. Check your answer by differentiating.

So far, you have seen two techniques for applying substitution, and you will see more techniques in the remainder of this section. Each technique differs slightly from the others. You should remember, however, that the goal is the same with each technique—*you are trying to find an antiderivative of the integrand.*

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The General Power Rule for Integration

One of the most common u-substitutions involves quantities in the integrand that are raised to a power. Because of the importance of this type of substitution, it is given a special name—the **General Power Rule for Integration.** A proof of this rule follows directly from the (simple) Power Rule for Integration, together with Theorem 4.13.

THEOREM 4.14 The General Power Rule for Integration

If g is a differentiable function of x, then

$$\int [g(x)]^n g'(x)\,dx = \frac{[g(x)]^{n+1}}{n+1} + C, \quad n \neq -1.$$

Equivalently, if $u = g(x)$, then

$$\int u^n\,du = \frac{u^{n+1}}{n+1} + C, \quad n \neq -1.$$

EXAMPLE 7 Substitution and the General Power Rule

a. $\displaystyle\int 3(3x-1)^4\,dx = \int \overbrace{(3x-1)^4}^{u^4}\overbrace{(3)\,dx}^{du} = \overbrace{\frac{(3x-1)^5}{5}}^{u^5/5} + C$

b. $\displaystyle\int (2x+1)(x^2+x)\,dx = \int \overbrace{(x^2+x)^1}^{u^1}\overbrace{(2x+1)\,dx}^{du} = \overbrace{\frac{(x^2+x)^2}{2}}^{u^2/2} + C$

c. $\displaystyle\int 3x^2\sqrt{x^3-2}\,dx = \int \overbrace{(x^3-2)^{1/2}}^{u^{1/2}}\overbrace{(3x^2)\,dx}^{du} = \overbrace{\frac{(x^3-2)^{3/2}}{3/2}}^{u^{3/2}/(3/2)} + C = \frac{2}{3}(x^3-2)^{3/2} + C$

d. $\displaystyle\int \frac{-4x}{(1-2x^2)^2}\,dx = \int \overbrace{(1-2x^2)^{-2}}^{u^{-2}}\overbrace{(-4x)\,dx}^{du} = \overbrace{\frac{(1-2x^2)^{-1}}{-1}}^{u^{-1}/(-1)} + C = -\frac{1}{1-2x^2} + C$

e. $\displaystyle\int \cos^2 x \sin x\,dx = -\int \overbrace{(\cos x)^2}^{u^2}\overbrace{(-\sin x)\,dx}^{du} = -\overbrace{\frac{(\cos x)^3}{3}}^{u^3/3} + C$ ■

REMARK Example 7(b) illustrates a case of the General Power Rule that is sometimes overlooked—when the power is $n = 1$. In this case, the rule takes the form

$$\int u\,du = \frac{u^2}{2} + C.$$

Some integrals whose integrands involve quantities raised to powers cannot be found by the General Power Rule. Consider the two integrals

$$\int x(x^2+1)^2\,dx \quad \text{and} \quad \int (x^2+1)^2\,dx.$$

The substitution

$$u = x^2 + 1$$

works in the first integral but not in the second. In the second, the substitution fails because the integrand lacks the factor x needed for du. Fortunately, *for this particular integral*, you can expand the integrand as

$$(x^2+1)^2 = x^4 + 2x^2 + 1$$

and use the (simple) Power Rule to integrate each term.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Change of Variables for Definite Integrals

When using u-substitution with a definite integral, it is often convenient to determine the limits of integration for the variable u rather than to convert the antiderivative back to the variable x and evaluate at the original limits. This change of variables is stated explicitly in the next theorem. The proof follows from Theorem 4.13 combined with the Fundamental Theorem of Calculus.

THEOREM 4.15 Change of Variables for Definite Integrals

If the function $u = g(x)$ has a continuous derivative on the closed interval $[a, b]$ and the function f is continuous on the range of g, then

$$\int_a^b f(g(x))g'(x)\,dx = \int_{g(a)}^{g(b)} f(u)\,du.$$

EXAMPLE 8 Change of Variables

Evaluate $\int_0^1 x(x^2 + 1)^3\,dx$.

Solution To evaluate this integral, let $u = x^2 + 1$. Then, you obtain

$du = 2x\,dx.$ Differentiate each side.

Before substituting, determine the new upper and lower limits of integration.

Lower Limit	Upper Limit
When $x = 0$, $u = 0^2 + 1 = 1$.	When $x = 1$, $u = 1^2 + 1 = 2$.

Now, substitute to obtain

$$\int_0^1 x(x^2 + 1)^3\,dx = \frac{1}{2}\int_0^1 (x^2 + 1)^3(2x)\,dx$$ Integration limits for x

$$= \frac{1}{2}\int_1^2 u^3\,du$$ Integration limits for u

$$= \frac{1}{2}\left[\frac{u^4}{4}\right]_1^2$$ Antiderivative in terms of u

$$= \frac{1}{2}\left(4 - \frac{1}{4}\right)$$ Apply Fundamental Theorem of Calculus.

$$= \frac{15}{8}.$$ Simplify.

Notice that you obtain the same result when you rewrite the antiderivative $\frac{1}{2}(u^4/4)$ in terms of the variable x and evaluate the definite integral at the original limits of integration, as shown below.

$$\frac{1}{2}\left[\frac{u^4}{4}\right]_1^2 = \frac{1}{2}\left[\frac{(x^2 + 1)^4}{4}\right]_0^1$$ Rewrite in terms of x.

$$= \frac{1}{2}\left(4 - \frac{1}{4}\right)$$ Apply Fundamental Theorem of Calculus.

$$= \frac{15}{8}$$ Simplify. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 9 Change of Variables

Evaluate the definite integral.

$$\int_1^5 \frac{x}{\sqrt{2x-1}}\,dx$$

Solution To evaluate this integral, let $u = \sqrt{2x-1}$. Then, you obtain

$$\begin{aligned} u^2 &= 2x - 1 && \text{Square each side.}\\ u^2 + 1 &= 2x && \text{Add 1 to each side.}\\ \frac{u^2+1}{2} &= x && \text{Divide each side by 2.}\\ u\,du &= dx. && \text{Differentiate each side.} \end{aligned}$$

Before substituting, determine the new upper and lower limits of integration.

Lower Limit	Upper Limit
When $x = 1$, $u = \sqrt{2-1} = 1$.	When $x = 5$, $u = \sqrt{10-1} = 3$.

Now, substitute to obtain

$$\begin{aligned} \int_1^5 \frac{x}{\sqrt{2x-1}}\,dx &= \int_1^3 \frac{1}{u}\left(\frac{u^2+1}{2}\right)u\,du && \text{Substitute.}\\ &= \frac{1}{2}\int_1^3 (u^2+1)\,du && \text{Constant Multiple Rule}\\ &= \frac{1}{2}\left[\frac{u^3}{3} + u\right]_1^3 && \text{Antiderivative in terms of } u\\ &= \frac{1}{2}\left(9 + 3 - \frac{1}{3} - 1\right) && \text{Apply Fundamental Theorem of Calculus.}\\ &= \frac{16}{3}. && \text{Simplify.} \end{aligned}$$



The region before substitution has an area of $\frac{16}{3}$.

Figure 4.38



The region after substitution has an area of $\frac{16}{3}$.

Figure 4.39

Geometrically, you can interpret the equation

$$\int_1^5 \frac{x}{\sqrt{2x-1}}\,dx = \int_1^3 \frac{u^2+1}{2}\,du$$

to mean that the two *different* regions shown in Figures 4.38 and 4.39 have the *same* area.

When evaluating definite integrals by substitution, it is possible for the upper limit of integration of the u-variable form to be smaller than the lower limit. When this happens, do not rearrange the limits. Simply evaluate as usual. For example, after substituting $u = \sqrt{1-x}$ in the integral

$$\int_0^1 x^2(1-x)^{1/2}\,dx$$

you obtain $u = \sqrt{1-0} = 1$ when $x = 0$, and $u = \sqrt{1-1} = 0$ when $x = 1$. So, the correct u-variable form of this integral is

$$-2\int_1^0 (1-u^2)^2u^2\,du.$$

Expanding the integrand, you can evaluate this integral as shown.

$$-2\int_1^0 (u^2 - 2u^4 + u^6)\,du = -2\left[\frac{u^3}{3} - \frac{2u^5}{5} + \frac{u^7}{7}\right]_1^0 = -2\left(-\frac{1}{3} + \frac{2}{5} - \frac{1}{7}\right) = \frac{16}{105}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Even function



Odd function

Figure 4.40

Integration of Even and Odd Functions

Even with a change of variables, integration can be difficult. Occasionally, you can simplify the evaluation of a definite integral over an interval that is symmetric about the y-axis or about the origin by recognizing the integrand to be an even or odd function (see Figure 4.40).

THEOREM 4.16 Integration of Even and Odd Functions

Let a function f be integrable on the closed interval $[-a, a]$.

1. If f is an *even* function, then $\int_{-a}^{a} f(x)\,dx = 2\int_{0}^{a} f(x)\,dx$.
2. If f is an *odd* function, then $\int_{-a}^{a} f(x)\,dx = 0$.

Proof Here is the proof of the first property. (The proof of the second property is left to you [see Exercise 103].) Because f is even, you know that

$$f(x) = f(-x).$$ Definition of even function (See Section P.3.)

Using Theorem 4.13 with the substitution $u = -x$ produces

$$\int_{-a}^{0} f(x)\,dx = \int_{a}^{0} f(-u)(-du) = -\int_{a}^{0} f(u)\,du = \int_{0}^{a} f(u)\,du = \int_{0}^{a} f(x)\,dx.$$

Finally, using Theorem 4.6, you obtain

$$\begin{aligned}\int_{-a}^{a} f(x)\,dx &= \int_{-a}^{0} f(x)\,dx + \int_{0}^{a} f(x)\,dx \\ &= \int_{0}^{a} f(x)\,dx + \int_{0}^{a} f(x)\,dx \\ &= 2\int_{0}^{a} f(x)\,dx.\end{aligned}$$

EXAMPLE 10 Integration of an Odd Function

Evaluate the definite integral.

$$\int_{-\pi/2}^{\pi/2} (\sin^3 x \cos x + \sin x \cos x)\,dx$$

Solution Let $f(x) = \sin^3 x \cos x + \sin x \cos x$. This function is odd because

$$\begin{aligned}f(-x) &= \sin^3(-x)\cos(-x) + \sin(-x)\cos(-x) \\ &= -\sin^3 x \cos x - \sin x \cos x \\ &= -f(x).\end{aligned}$$

Also, the function f is symmetric about the origin over the interval $[-\pi/2, \pi/2]$. This means you can apply Property 2 of Theorem 4.16 to conclude that

$$\int_{-\pi/2}^{\pi/2} (\sin^3 x \cos x + \sin x \cos x)\,dx = 0.$$

Figure 4.41 shows that the two regions on either side of the y-axis have the same area. However, because one lies below the x-axis and one lies above it, integration produces a cancellation effect. (More will be said about areas below the x-axis in Section 7.1.)



Because f is an odd function, $\int_{-\pi/2}^{\pi/2} f(x)\,dx = 0$.

Figure 4.41

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

4.5 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain how to use the Constant Multiple Rule when finding an indefinite integral.
2. Summarize the guidelines for making a change of variables when finding an indefinite integral.
3. Describe the General Power Rule for Integration.
4. Without integrating, explain why
$$\int_{-2}^{2} x(x^2 + 1)^2\,dx = 0.$$

Recognizing Patterns In Exercises 5–8, complete the table by identifying u and du for the integral.

$\int f(g(x))g'(x)\,dx$	$u = g(x)$	$du = g'(x)\,dx$
5. $\int (5x^2 + 1)^2(10x)\,dx$		
6. $\int x^2\sqrt{x^3 + 1}\,dx$		
7. $\int \tan^2 x \sec^2 x\,dx$		
8. $\int \frac{\cos x}{\sin^2 x}\,dx$		

Finding an Indefinite Integral In Exercises 9–30, find the indefinite integral and check the result by differentiation.

9. $\int (1 + 6x)^4(6)\,dx$
10. $\int (x^2 - 9)^3(2x)\,dx$
11. $\int \sqrt{25 - x^2}\,(-2x)\,dx$
12. $\int \sqrt[3]{3 - 4x^2}(-8x)\,dx$
13. $\int x^3(x^4 + 3)^2\,dx$
14. $\int x^2(6 - x^3)^5\,dx$
15. $\int x^2(2x^3 - 1)^4\,dx$
16. $\int x(5x^2 + 4)^3\,dx$
17. $\int t\sqrt{t^2 + 2}\,dt$
18. $\int t^3\sqrt{2t^4 + 3}\,dt$
19. $\int 5x\sqrt[3]{1 - x^2}\,dx$
20. $\int 6u^6\sqrt{u^7 + 8}\,du$
21. $\int \frac{7x}{(1 - x^2)^3}\,dx$
22. $\int \frac{x^3}{(1 + x^4)^2}\,dx$
23. $\int \frac{x^2}{(1 + x^3)^2}\,dx$
24. $\int \frac{6x^2}{(4x^3 - 9)^3}\,dx$
25. $\int \frac{x}{\sqrt{1 - x^2}}\,dx$
26. $\int \frac{x^3}{\sqrt{1 + x^4}}\,dx$
27. $\int \left(1 + \frac{1}{t}\right)^3\left(\frac{1}{t^2}\right)dt$
28. $\int \left(8 - \frac{1}{t^4}\right)^2\left(\frac{1}{t^5}\right)dt$
29. $\int \frac{1}{\sqrt{2x}}\,dx$
30. $\int \frac{x}{\sqrt[3]{5x^2}}\,dx$

Differential Equation In Exercises 31–34, find the general solution of the differential equation.

31. $\frac{dy}{dx} = 4x + \frac{4x}{\sqrt{16 - x^2}}$
32. $\frac{dy}{dx} = \frac{10x^2}{\sqrt{1 + x^3}}$
33. $\frac{dy}{dx} = \frac{x + 1}{(x^2 + 2x - 3)^2}$
34. $\frac{dy}{dx} = \frac{18 - 6x^2}{\sqrt{x^3 - 9x + 7}}$

Slope Field In Exercises 35 and 36, a differential equation, a point, and a slope field are given. A *slope field* (or *direction field*) consists of line segments with slopes given by the differential equation. These line segments give a visual perspective of the slopes of the solutions of the differential equation. (a) Sketch two approximate solutions of the differential equation on the slope field, one of which passes through the given point. (To print an enlarged copy of the graph, go to *MathGraphs.com*.) (b) Use integration and the given point to find the particular solution of the differential equation and use a graphing utility to graph the solution. Compare the result with the sketch in part (a) that passes through the given point.

35. $\frac{dy}{dx} = x\sqrt{4 - x^2}$, $(2, 2)$
36. $\frac{dy}{dx} = x^2(x^3 - 1)^2$, $(1, 0)$





Differential Equation In Exercises 37 and 38, the graph of a function f is shown. Use the differential equation and the given point to find an equation of the function.

37. $\frac{dy}{dx} = 18x^2(2x^3 + 1)^2$
38. $\frac{dy}{dx} = \frac{-48}{(3x + 5)^3}$





Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding an Indefinite Integral **In Exercises 39–48, find the indefinite integral.**

39. $\int \pi \sin \pi x \, dx$

40. $\int \sin 4x \, dx$

41. $\int \cos 6x \, dx$

42. $\int \csc^2\left(\frac{x}{2}\right) dx$

43. $\int \frac{1}{\theta^2} \cos \frac{1}{\theta} \, d\theta$

44. $\int x \sin x^2 \, dx$

45. $\int \sin 2x \cos 2x \, dx$

46. $\int \sqrt[3]{\tan x} \sec^2 x \, dx$

47. $\int \frac{\csc^2 x}{\cot^3 x} \, dx$

48. $\int \frac{\sin x}{\cos^3 x} \, dx$

Finding an Equation **In Exercises 49–52, find an equation for the function f that has the given derivative and whose graph passes through the given point.**

Derivative	Point
49. $f'(x) = -\sin \frac{x}{2}$	$(0, 6)$
50. $f'(x) = \sec^2 2x$	$\left(\frac{\pi}{2}, 2\right)$
51. $f'(x) = 2x(4x^2 - 10)^2$	$(2, 10)$
52. $f'(x) = -2x\sqrt{8 - x^2}$	$(2, 7)$

Change of Variables **In Exercises 53–60, find the indefinite integral by making a change of variables.**

53. $\int x\sqrt{x + 6} \, dx$

54. $\int x\sqrt{3x - 4} \, dx$

55. $\int x^2\sqrt{1 - x} \, dx$

56. $\int (x + 1)\sqrt{2 - x} \, dx$

57. $\int \frac{x^2 - 1}{\sqrt{2x - 1}} \, dx$

58. $\int \frac{2x + 1}{\sqrt{x + 4}} \, dx$

59. $\int \cos^3 2x \sin 2x \, dx$

60. $\int \sec^5 7x \tan 7x \, dx$

Evaluating a Definite Integral **In Exercises 61–70, evaluate the definite integral. Use a graphing utility to verify your result.**

61. $\int_{-1}^{1} x(x^2 + 1)^3 \, dx$

62. $\int_{0}^{1} x^3(2x^4 + 1)^2 \, dx$

63. $\int_{1}^{2} 2x^2\sqrt{x^3 + 1} \, dx$

64. $\int_{-1}^{0} x\sqrt{1 - x^2} \, dx$

65. $\int_{0}^{4} \frac{1}{\sqrt{2x + 1}} \, dx$

66. $\int_{0}^{2} \frac{x}{\sqrt{1 + 2x^2}} \, dx$

67. $\int_{1}^{9} \frac{1}{\sqrt{x}\left(1 + \sqrt{x}\right)^2} \, dx$

68. $\int_{4}^{5} \frac{x}{\sqrt{2x - 6}} \, dx$

69. $2\pi \int_{0}^{1} (x + 1)\sqrt{1 - x} \, dx$

70. $2\pi \int_{-1}^{0} x^2\sqrt{x + 1} \, dx$

Finding the Area of a Region **In Exercises 71–74, find the area of the region. Use a graphing utility to verify your result.**

71. $\int_{0}^{7} x\sqrt[3]{x + 1} \, dx$



72. $\int_{-2}^{6} x^2\sqrt[3]{x + 2} \, dx$



73. $\int_{\pi/2}^{2\pi/3} \sec^2\left(\frac{x}{2}\right) dx$



74. $\int_{\pi/12}^{\pi/4} \csc 2x \cot 2x \, dx$



Even and Odd Functions **In Exercises 75–78, evaluate the integral using the properties of even and odd functions as an aid.**

75. $\int_{-2}^{2} x^2(x^2 + 1) \, dx$

76. $\int_{-2}^{2} x(x^2 + 1)^3 \, dx$

77. $\int_{-\pi/2}^{\pi/2} \sin x \cos x \, dx$

78. $\int_{-\pi/2}^{\pi/2} \sin^2 x \cos x \, dx$

79. Using an Even Function Use $\int_0^6 x^2 \, dx = 72$ to evaluate each definite integral without using the Fundamental Theorem of Calculus.

(a) $\int_{-6}^{6} x^2 \, dx$

(b) $\int_{-6}^{0} x^2 \, dx$

(c) $\int_{0}^{6} -2x^2 \, dx$

(d) $\int_{-6}^{6} 3x^2 \, dx$

80. Using Symmetry Use the symmetry of the graphs of the sine and cosine functions as an aid in evaluating each definite integral.

(a) $\int_{-\pi/4}^{\pi/4} \sin x \, dx$

(b) $\int_{-\pi/4}^{\pi/4} \cos x \, dx$

(c) $\int_{-\pi/2}^{\pi/2} \cos x \, dx$

(d) $\int_{-\pi/2}^{\pi/2} \sin x \cos x \, dx$

Even and Odd Functions **In Exercises 81 and 82, write the integral as the sum of the integral of an odd function and the integral of an even function. Use this simplification to evaluate the integral.**

81. $\int_{-3}^{3} (x^3 + 4x^2 - 3x - 6) \, dx$

82. $\int_{-\pi/2}^{\pi/2} (\sin 4x + \cos 4x) \, dx$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploring Concepts

83. You are asked to find one of the integrals. Which one would you choose? Explain.

(a) $\int \sqrt{x^3 + 1}\, dx$ or $\int x^2\sqrt{x^3 + 1}\, dx$

(b) $\int \cot 2x\, dx$ or $\int \cot^3 2x \csc^2 2x\, dx$

84. Find the indefinite integral in two ways. Explain any difference in the forms of the answers.

(a) $\int (2x - 1)^2\, dx$ (b) $\int \sin x \cos x\, dx$

85. Depreciation The rate of depreciation dV/dt of a machine is inversely proportional to the square of $(t + 1)$, where V is the value of the machine t years after it was purchased. The initial value of the machine was \$500,000, and its value decreased \$100,000 in the first year. Estimate its value after 4 years.

86. HOW DO YOU SEE IT? The graph shows the flow rate of water at a pumping station for one day.



(a) Approximate the maximum flow rate at the pumping station. At what time does this occur?

(b) Explain how you can find the amount of water used during the day.

(c) Approximate the two-hour period when the least amount of water is used. Explain your reasoning.

87. Sales The sales S (in thousands of units) of a seasonal product are given by the model

$$S = 74.50 + 43.75 \sin \frac{\pi t}{6}$$

where t is the time in months, with $t = 1$ corresponding to January. Find the average sales for each time period.

(a) The first quarter $(0 \le t \le 3)$

(b) The second quarter $(3 \le t \le 6)$

(c) The entire year $(0 \le t \le 12)$

88. Electricity

The oscillating current in an electrical circuit is

$$I = 2 \sin(60\pi t) + \cos(120\pi t)$$

where I is measured in amperes and t is measured in seconds. Find the average current for each time interval.

(a) $0 \le t \le \frac{1}{60}$

(b) $0 \le t \le \frac{1}{240}$

(c) $0 \le t \le \frac{1}{30}$

TWStock/Shutterstock.com

89. Graphical Analysis Consider the functions f and g, where

$$f(x) = 6 \sin x \cos^2 x \quad \text{and} \quad g(t) = \int_0^t f(x)\, dx.$$

(a) Use a graphing utility to graph f and g in the same viewing window.

(b) Explain why g is nonnegative.

(c) Identify the points on the graph of g that correspond to the extrema of f.

(d) Does each of the zeros of f correspond to an extremum of g? Explain.

(e) Consider the function

$$h(t) = \int_{\pi/2}^t f(x)\, dx.$$

Use a graphing utility to graph h. What is the relationship between g and h? Verify your conjecture.

90. Finding a Limit Using a Definite Integral Find

$$\lim_{n\to\infty} \sum_{i=1}^{n} \frac{\sin(i\pi/n)}{n}$$

by evaluating an appropriate definite integral over the interval $[0, 1]$.

91. Rewriting Integrals

(a) Show that $\int_0^1 x^3(1 - x)^8\, dx = \int_0^1 x^8(1 - x)^3\, dx$.

(b) Show that $\int_0^1 x^a(1 - x)^b\, dx = \int_0^1 x^b(1 - x)^a\, dx$.

92. Rewriting Integrals

(a) Show that $\int_0^{\pi/2} \sin^2 x\, dx = \int_0^{\pi/2} \cos^2 x\, dx$.

(b) Show that

$$\int_0^{\pi/2} \sin^n x\, dx = \int_0^{\pi/2} \cos^n x\, dx$$

where n is a positive integer.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

True or False? **In Exercises 93–98, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

93. $\int 3x^2(x^3 + 5)^{-2}\,dx = -(x^3 + 5)^{-1} + C$

94. $\int x(x^2 + 1)\,dx = \frac{1}{2}x^2\left(\frac{1}{3}x^3 + x\right) + C$

95. $\int_{-10}^{10} (ax^3 + bx^2 + cx + d)\,dx = 2\int_{0}^{10} (bx^2 + d)\,dx$

96. $\int_a^b \sin x\,dx = \int_a^{b+2\pi} \sin x\,dx$

97. $4\int \sin x \cos x\,dx = -\cos 2x + C$

98. $\int \sin^2 2x \cos 2x\,dx = \frac{1}{3}\sin^3 2x + C$

99. Rewriting Integrals Assume that the function f is continuous everywhere and that c is a constant. Show that

$$\int_{ca}^{cb} f(x)\,dx = c\int_a^b f(cx)\,dx.$$

100. Integration and Differentiation

(a) Verify that $\sin u - u\cos u + C = \int u \sin u\,du$.

(b) Use part (a) to show that $\int_0^{\pi^2} \sin\sqrt{x}\,dx = 2\pi$.

101. Proof Prove the second property of Theorem 4.16.

102. Rewriting Integrals Show that if the function f is continuous on the entire real number line, then

$$\int_a^b f(x + h)\,dx = \int_{a+h}^{b+h} f(x)\,dx.$$

PUTNAM EXAM CHALLENGE

103. If $a_0, a_1, \ldots, a_n$ are real numbers satisfying

$$\frac{a_0}{1} + \frac{a_1}{2} + \cdots + \frac{a_n}{n+1} = 0,$$

show that the equation

$$a_0 + a_1x + a_2x^2 + \cdots + a_nx^n = 0$$

has at least one real root.

104. Find all the continuous positive functions $f(x)$, for $0 \le x \le 1$, such that

$$\int_0^1 f(x)\,dx = 1$$

$$\int_0^1 f(x)x\,dx = \alpha$$

$$\int_0^1 f(x)x^2\,dx = \alpha^2$$

where α is a given real number.

These problems were composed by the Committee on the Putnam Prize Competition. © The Mathematical Association of America. All rights reserved.

SECTION PROJECT

Probability

The function $f(x) = kx^n(1 - x)^m$, where $0 \le x \le 1$, $n > 0$, $m > 0$, and k is a constant, can be used to represent various probability distributions. If k is chosen such that

$$\int_0^1 f(x)dx = 1$$

then the probability that x will fall between a and b $(0 \le a \le b \le 1)$ is

$$P_{a,b} = \int_a^b f(x)\,dx.$$

(a) The probability that a person will remember between $100a\%$ and $100b\%$ of material learned in an experiment is

$$P_{a,b} = \int_a^b \frac{15}{4}x\sqrt{1 - x}\,dx$$

where x represents the proportion remembered. (See figure.)



For a randomly chosen individual, what is the probability that they will recall between 50% and 75% of the material? What is the median percent recall? That is, for what value of b is it true that the probability of recalling 0 to b is 0.5?

(b) The probability that ore samples taken from a region contain between $100a\%$ and $100b\%$ iron is

$$P_{a,b} = \int_a^b \frac{1155}{32}x^3(1 - x)^{3/2}\,dx$$

where x represents the proportion of iron. (See figure.)



Find the probability that a sample will contain between 0% and 25% iron. Find the probability that a sample will contain between 50% and 100% iron.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Review Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Exploring Concepts

In Chapters 2 and 3, you studied the first major theme of calculus, the derivative. In this chapter, you studied the second major theme, integration. The relationship between these two concepts is stated in the most important theorem in all of calculus, the Fundamental Theorem of Calculus. The importance of the inverse relationship between differentiation and integration cannot be overstated.

$$\int_a^b f(x)\,dx = F(b) - F(a) \quad \text{and} \quad \frac{d}{dx}\left[\int_a^x f(t)\,dt\right] = f(x).$$

1. Consider the functions

$f(x) = \sin^2 x$ and $g(x) = \cos^2 x$.

(a) What do you notice about the derivatives of f and g?

(b) What can you conclude about the relationship between f and g?

2. Determine whether the function

$$f(x) = \frac{1}{x-4}$$

is integrable on the interval $[0, 5]$. Explain your reasoning.

3. Determine which value best approximates

$$\int_0^9 \left(1 + \sqrt{x}\right) dx.$$

Make your selection on the basis of a sketch.

(a) -3 (b) 9

(c) 27 (d) 3

4. Consider the function

$$F(x) = \int_{-3}^{x} (t^2 + 3t + 2)\,dt.$$

(a) Integrate to find F as a function of x.

(b) Demonstrate the Second Fundamental Theorem of Calculus by differentiating the result in part (a).

5. Let $v(t)$ represent the velocity (in feet per second) of a particle moving along a straight line at time t (in seconds). The graph of v is shown in the figure. Describe what each expression represents in the context of the situation.

(a) $v'(t)$ (b) $\displaystyle\int_a^c v(t)\,dt$

(c) $\displaystyle\int_a^c |v(t)|\,dt$ (d) $\displaystyle\frac{d}{dx}\left[\int_a^x v(t)\,dt\right]$

(e) $A - B$

(f) $\displaystyle\int_a^b v(t)\,dt + \int_b^c v(t)\,dt$



Figure for 5



Figure for 6

6. The graph of the derivative of f is shown in the figure. Sketch the graphs of *two* functions that have the given derivative. (There is more than one correct answer.) To print an enlarged copy of the graph, go to *MathGraphs.com*.

Finding an Indefinite Integral **In Exercises 7–10, find the indefinite integral and check the result by differentiation.**

7. $\displaystyle\int (x^3 + 4)\,dx$ **8.** $\displaystyle\int (4x^2 + x + 3)\,dx$

9. $\displaystyle\int \frac{6}{\sqrt[3]{x}}\,dx$ **10.** $\displaystyle\int (2\csc^2 x - 9\sin x)\,dx$

Finding a Particular Solution **In Exercises 11 and 12, find the particular solution of the differential equation that satisfies the initial condition(s).**

11. $f'(x) = -6x,\ f(1) = -2$

12. $f''(x) = 24x,\ f'(-1) = 7,\ f(1) = -4$

13. Vertical Motion A ball is launched vertically upward from ground level with an initial velocity of 96 feet per second. Assume the acceleration of the ball is $a(t) = -32$ feet per second per second. (Neglect air resistance.)

(a) How long will it take the ball to rise to its maximum height? What is the maximum height?

(b) After how many seconds is the velocity of the ball one-half the initial velocity?

(c) What is the height of the ball when its velocity is one-half the initial velocity?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

14. Vertical Motion With what initial velocity must an object be thrown upward (from a height of 3 meters) to reach a maximum height of 150 meters? Assume the acceleration of the object is $a(t) = 9.8$ meters per second per second. (Neglect air resistance.)

Finding a Sum **In Exercises 15 and 16, find the sum by adding each term together. Use the summation capabilities of a graphing utility to verify your result.**

15. $\sum_{i=1}^{5} (5i - 3)$

16. $\sum_{k=0}^{3} (k^2 + 1)$

Using Sigma Notation **In Exercises 17 and 18, use sigma notation to write the sum.**

17. $\frac{1}{5(3)} + \frac{2}{5(4)} + \frac{3}{5(5)} + \cdots + \frac{10}{5(12)}$

18. $\left(\frac{3}{n}\right)\left(\frac{1+1}{n}\right)^2 + \left(\frac{3}{n}\right)\left(\frac{2+1}{n}\right)^2 + \cdots + \left(\frac{3}{n}\right)\left(\frac{n+1}{n}\right)^2$

Evaluating a Sum **In Exercises 19–24, use the properties of summation and Theorem 4.2 to evaluate the sum. Use the summation capabilities of a graphing utility to verify your result.**

19. $\sum_{i=1}^{24} 8$

20. $\sum_{i=1}^{75} 5i$

21. $\sum_{i=1}^{20} 2i$

22. $\sum_{i=1}^{30} (3i - 4)$

23. $\sum_{i=1}^{20} (i + 1)^2$

24. $\sum_{i=1}^{12} i(i^2 - 1)$

Finding Upper and Lower Sums for a Region **In Exercises 25 and 26, use upper and lower sums to approximate the area of the region using the given number of subintervals (of equal width).**

25. $y = \frac{10}{x^2 + 1}$



26. $y = 9 - \frac{1}{4}x^2$



Finding Upper and Lower Sums for a Region **In Exercises 27 and 28, find the upper and lower sums for the region bounded by the graph of the function and the x-axis on the given interval. Leave your answer in terms of n, the number of subintervals.**

Function	Interval
27. $f(x) = 4x + 1$	$[2, 3]$
28. $f(x) = 7x^2$	$[0, 3]$

Finding Area by the Limit Definition **In Exercises 29–32, use the limit process to find the area of the region bounded by the graph of the function and the x-axis over the given interval. Sketch the region.**

29. $y = 8 - 2x, \quad [0, 3]$

30. $y = x^2 + 3, \quad [0, 2]$

31. $y = 5 - x^2, \quad [-2, 1]$

32. $y = \frac{1}{4}x^3, \quad [2, 4]$

Approximating Area with the Midpoint Rule **In Exercises 33 and 34, use the Midpoint Rule with $n = 4$ to approximate the area of the region bounded by the graph of the function and the x-axis over the given interval.**

33. $f(x) = 16 - x^2, \quad [0, 4]$

34. $f(x) = \sin \pi x, \quad [0, 1]$

Evaluating a Definite Integral as a Limit **In Exercises 35 and 36, evaluate the definite integral by the limit definition.**

35. $\int_{-3}^{5} 6x \, dx$

36. $\int_{0}^{3} (1 - 2x^2) \, dx$

Evaluating a Definite Integral Using a Geometric Formula **In Exercises 37 and 38, sketch the region whose area is given by the definite integral. Then use a geometric formula to evaluate the integral ($a > 0, r > 0$).**

37. $\int_{0}^{5} (5 - |x - 5|) \, dx$

38. $\int_{-6}^{6} \sqrt{36 - x^2} \, dx$

39. Using Properties of Definite Integrals Given $\int_4^8 f(x) \, dx = 12$ and $\int_4^8 g(x) \, dx = 5$, evaluate

(a) $\int_4^8 [f(x) + g(x)] \, dx$. (b) $\int_4^8 [f(x) - g(x)] \, dx$.

(c) $\int_4^8 [2f(x) - 3g(x)] \, dx$. (d) $\int_4^8 7f(x) \, dx$.

40. Using Properties of Definite Integrals Given $\int_0^2 f(x) \, dx = 2$ and $\int_2^5 f(x) = -5$, evaluate

(a) $\int_0^5 f(x) \, dx$. (b) $\int_5^2 f(x) \, dx$.

(c) $\int_3^5 f(x) \, dx$. (d) $\int_2^5 -8f(x) \, dx$.

Evaluating a Definite Integral **In Exercises 41–46, use the Fundamental Theorem of Calculus to evaluate the definite integral. Use a graphing utility to verify your result.**

41. $\int_0^6 (x - 1) \, dx$

42. $\int_{-2}^{1} (4x^4 - x) \, dx$

43. $\int_4^9 x\sqrt{x} \, dx$

44. $\int_1^4 \left(\frac{1}{x^3} + x\right) dx$

45. $\int_0^{3\pi/4} \sin\theta \, d\theta$

46. $\int_{-\pi/4}^{\pi/4} \sec^2 t \, dt$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding the Area of a Region **In Exercises 47 and 48, find the area of the region bounded by the function and the x-axis on the interval $[0, \pi/2]$.**

47. $y = \sin x$

48. $y = x + \cos x$

Finding the Area of a Region **In Exercises 49–52, find the area of the region bounded by the graphs of the equations.**

49. $y = 8 - x,\ x = 0,\ x = 6,\ y = 0$

50. $y = -x^2 + x + 6,\ y = 0$

51. $y = x - x^3,\ x = 0,\ x = 1,\ y = 0$

52. $y = \sqrt{x}(1 - x),\ y = 0$

Using the Mean Value Theorem for Integrals **In Exercises 53 and 54, find the value(s) of c guaranteed by the Mean Value Theorem for Integrals for the function over the given interval.**

53. $f(x) = 3x^2,\quad [1, 3]$

54. $f(x) = \sin x,\quad [0, \pi]$

Finding the Average Value of a Function **In Exercises 55 and 56, find the average value of the function over the given interval and all values of x in the interval for which the function equals its average value.**

55. $f(x) = \dfrac{1}{\sqrt{x}},\quad [4, 9]$ **56.** $f(x) = x^3,\quad [0, 2]$

Using the Second Fundamental Theorem of Calculus **In Exercises 57 and 58, use the Second Fundamental Theorem of Calculus to find $F'(x)$.**

57. $F(x) = \displaystyle\int_0^x t^2\sqrt{1 + t^3}\,dt$ **58.** $F(x) = \displaystyle\int_1^x \frac{1}{t^2}\,dt$

Finding an Indefinite Integral **In Exercises 59–66, find the indefinite integral.**

59. $\displaystyle\int x(1 - 3x^2)^4\,dx$ **60.** $\displaystyle\int 6x^3\sqrt{3x^4 + 2}\,dx$

61. $\displaystyle\int \sin^3 x \cos x\,dx$ **62.** $\displaystyle\int x \sin 3x^2\,dx$

63. $\displaystyle\int \frac{\cos\theta}{\sqrt{1 - \sin\theta}}\,d\theta$ **64.** $\displaystyle\int \frac{\sin x}{\sqrt{\cos x}}\,dx$

65. $\displaystyle\int x\sqrt{8 - x}\,dx$ **66.** $\displaystyle\int \sqrt{1 + \sqrt{x}}\,dx$

Evaluating a Definite Integral **In Exercises 67–70, evaluate the definite integral. Use a graphing utility to verify your result.**

67. $\displaystyle\int_0^1 (3x + 1)^5\,dx$ **68.** $\displaystyle\int_0^1 x^2(x^3 - 2)^3\,dx$

69. $\displaystyle\int_0^3 \frac{1}{\sqrt{1 + x}}\,dx$ **70.** $\displaystyle\int_3^6 \frac{x}{3\sqrt{x^2 - 8}}\,dx$

Finding the Area of a Region **In Exercises 71 and 72, find the area of the region under the curve by evaluating the definite integral with the given bounds. Use a graphing utility to verify your result.**

71. $\displaystyle\int_1^9 x\sqrt[3]{x - 1}\,dx$ **72.** $\displaystyle\int_0^{\pi/2} (\cos x + \sin 2x)\,dx$

Even and Odd Functions **In Exercises 73 and 74, evaluate the integral using the properties of even and odd functions as an aid.**

73. $\displaystyle\int_{-2}^{2} (x^3 - 2x)\,dx$ **74.** $\displaystyle\int_{-\pi}^{\pi} (\cos x + x^2)\,dx$

Building on Concepts

75. Consider the function

$$F(x) = \int_0^x \sin^2 t\,dt.$$

(a) Evaluate F at $x = 0, \pi/6, \pi/3, \pi/2, 2\pi/3, 5\pi/6$, and π. Are the values of F increasing or decreasing? Explain.

(b) Use the integration capabilities of a graphing utility to graph F and $y_1 = \sin^2 t$ on the interval $0 \le t \le \pi$.

(c) Use the differentiation capabilities of a graphing utility to graph F'. How is this graph related to the graph in part (b)?

(d) Verify that $\sin^2 t$ is the derivative of

$$y = \frac{1}{2}t - \frac{1}{4}\sin 2t.$$

Graph y and write a short paragraph about how this graph is related to those in parts (b) and (c).

76. Archimedes showed that the area of a parabolic arch is equal to $\frac{2}{3}$ the product of the base and the height (see figure).



(a) Graph the parabolic arch bounded by $y = 9 - x^2$ and the x-axis. Use an appropriate integral to find the area A.

(b) Find the base and height of the arch and verify Archimedes's formula.

(c) Prove Archimedes's formula for a general parabola.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.S. Problem Solving

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Evaluating a Sum and a Limit **In Exercises 1 and 2, (a) write the area under the graph of the given function defined on the given interval as a limit. Then (b) evaluate the sum in part (a), and (c) evaluate the limit using the result of part (b).**

1. $y = x^4 - 4x^3 + 4x^2, \quad [0, 2]$

$$\left(\textit{Hint: } \sum_{i=1}^{n} i^4 = \frac{n(n+1)(2n+1)(3n^2+3n-1)}{30}\right)$$

2. $y = \frac{1}{2}x^5 + 2x^3, \quad [0, 2]$

$$\left(\textit{Hint: } \sum_{i=1}^{n} i^5 = \frac{n^2(n+1)^2(2n^2+2n-1)}{12}\right)$$

3. Fresnel Function The **Fresnel function** S is defined by the integral

$$S(x) = \int_0^x \sin\frac{\pi t^2}{2}\,dt.$$

(a) Graph the function $y = \sin\dfrac{\pi x^2}{2}$ on the interval $[0, 3]$.

(b) Use the graph in part (a) to sketch the graph of S on the interval $[0, 3]$.

(c) Locate all relative extrema of S on the interval $(0, 3)$.

(d) Locate all points of inflection of S on the interval $(0, 3)$.

4. Approximation The **Two-Point Gaussian Quadrature Approximation** for f is

$$\int_{-1}^{1} f(x)\,dx \approx f\left(-\frac{1}{\sqrt{3}}\right) + f\left(\frac{1}{\sqrt{3}}\right).$$

(a) Use this formula to approximate

$$\int_{-1}^{1} \cos x\,dx.$$

Find the error of the approximation.

(b) Use this formula to approximate

$$\int_{-1}^{1} \frac{1}{1+x^2}\,dx.$$

(c) Prove that the Two-Point Gaussian Quadrature Approximation is exact for all polynomials of degree 3 or less.

5. Falling Objects Galileo Galilei (1564–1642) stated the following proposition concerning falling objects:

> *The time in which any space is traversed by a uniformly accelerating body is equal to the time in which that same space would be traversed by the same body moving at a uniform speed whose value is the mean of the highest speed of the accelerating body and the speed just before acceleration began.*

Use the techniques of this chapter to verify this proposition.

6. Extrema and Points of Inflection The graph of the function f consists of the three line segments joining the points $(0, 0)$, $(2, -2)$, $(6, 2)$, and $(8, 3)$. The function F is defined by the integral

$$F(x) = \int_0^x f(t)\,dt.$$

(a) Sketch the graph of f.

(b) Complete the table.

x	0	1	2	3	4	5	6	7	8
$F(x)$									

(c) Find the extrema of F on the interval $[0, 8]$.

(d) Determine all points of inflection of F on the interval $(0, 8)$.

7. Proof Prove $\displaystyle\int_0^x f(t)(x-t)\,dt = \int_0^x \left(\int_0^t f(v)\,dv\right) dt.$

8. Proof Prove $\displaystyle\int_a^b f(x)f'(x)\,dx = \tfrac{1}{2}([f(b)]^2 - [f(a)]^2).$

9. Riemann Sum Use an appropriate Riemann sum to evaluate the limit

$$\lim_{n\to\infty} \frac{\sqrt{1} + \sqrt{2} + \sqrt{3} + \cdots + \sqrt{n}}{n^{3/2}}.$$

10. Using a Continuous Function Let the function f be continuous on the interval $[0, b]$, where $f(x) + f(b - x) \neq 0$ on $[0, b]$.

(a) Show that $\displaystyle\int_0^b \frac{f(x)}{f(x) + f(b-x)}\,dx = \frac{b}{2}$.

(b) Use the result in part (a) to evaluate

$$\int_0^1 \frac{\sin x}{\sin(1-x) + \sin x}\,dx.$$

(c) Use the result in part (a) to evaluate

$$\int_0^3 \frac{\sqrt{x}}{\sqrt{x} + \sqrt{3-x}}\,dx.$$

11. Minimizing an Integral Determine the limits of integration where $a \leq b$ such that $\int_a^b (x^2 - 16)\,dx$ has minimal value.

12. Upper and Lower Sums Consider the region bounded by $y = mx$, $y = 0$, $x = 0$, and $x = b$.

(a) Find the upper and lower sums to approximate the area of the region when $\Delta x = b/4$.

(b) Find the upper and lower sums to approximate the area of the region when $\Delta x = b/n$.

(c) Find the area of the region by letting n approach infinity in both sums in part (b). Show that, in each case, you obtain the formula for the area of a triangle.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

5 Logarithmic, Exponential, and Other Transcendental Functions

GO DIGITAL

5.1 The Natural Logarithmic Function: Differentiation
5.2 The Natural Logarithmic Function: Integration
5.3 Inverse Functions
5.4 Exponential Functions: Differentiation and Integration
5.5 Bases Other than *e* and Applications
5.6 Indeterminate Forms and L'Hôpital's Rule
5.7 Inverse Trigonometric Functions: Differentiation
5.8 Inverse Trigonometric Functions: Integration
5.9 Hyperbolic Functions

CalcView®

CalcChat®



5.1 Sound Intensity *(Exercise 102, p. 323)*

5.5 Radioactive Half-Life Model *(Example 1, p. 352)*

left, William R. Sallaz/Getty Images; right, Alexander Rieber/EyeEm/Getty Images

This material is protected under all copyright laws as they currently exist. No portion of this material may be reproduced, modified or distributed in any form or by any means, or stored in a database or retrieval system, without the prior written permission of Cengage Learning, Inc. All rights reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

5.1 The Natural Logarithmic Function: Differentiation

GO DIGITAL

- **Define the natural logarithmic function and use its properties.**
- **Define the number *e*.**
- **Find derivatives of functions involving the natural logarithmic function.**

Big Ideas of Calculus

You can use calculus to define the natural logarithmic function $\ln x$ as an integral. Then, you can define the inverse of $\ln x$ as the natural exponential function e^x. The function e^x is one of the most interesting functions in calculus—its derivative and its integral are equal to itself! With these definitions and other properties, you will develop differentiation and integration rules for logarithmic, exponential, inverse trigonometric, and hyperbolic functions.

The Natural Logarithmic Function

Recall that the General Power Rule

$$\int x^n\,dx = \frac{x^{n+1}}{n+1} + C, \quad n \neq -1$$ General Power Rule

does not apply when $n = -1$. Consequently, you have not yet found an antiderivative for the function $f(x) = 1/x$. In this section, you will use the Second Fundamental Theorem of Calculus to *define* such a function. This antiderivative is a function that you have not encountered previously in the text. It is neither algebraic nor trigonometric but falls into a new class of functions called *logarithmic functions.* This particular function is the **natural logarithmic function.**

Definition of the Natural Logarithmic Function

The **natural logarithmic function** is defined by

$$\ln x = \int_1^x \frac{1}{t}\,dt, \quad x > 0.$$

The domain of the natural logarithmic function is the set of all positive real numbers.

In the definition of the natural logarithmic function, note that $\ln x$ is positive for $x > 1$ and negative for $0 < x < 1$, as shown in Figure 5.1. Moreover, $\ln 1 = 0$, because the upper and lower limits of integration are equal when $x = 1$.



If $x > 1$, then $\ln x > 0$.



If $0 < x < 1$, then $\ln x < 0$.

Figure 5.1

Exploration

Graphing the Natural Logarithmic Function Using *only* the definition of the natural logarithmic function, sketch a graph of the function. Explain your reasoning.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



JOHN NAPIER (1550–1617)

Logarithms were invented by the Scottish mathematician John Napier. Napier coined the term *logarithm*, from the two Greek words *logos* (or ratio) and *arithmos* (or number), to describe the theory that he spent 20 years developing and that first appeared in the book *Mirifici Logarithmorum Canonis Descriptio* (A Description of the Marvelous Rule of Logarithms). Although he did not introduce the *natural* logarithmic function, it is sometimes called the *Napierian* logarithm.

See LarsonCalculus.com to read more of this biography.

To sketch the graph of $y = \ln x$, you can think of the natural logarithmic function as an *antiderivative* given by the differential equation

$$\frac{dy}{dx} = \frac{1}{x}.$$ Differential equation

Figure 5.2 is a computer-generated graph, called a *slope field (or direction field)*, showing small line segments of slope $1/x$. The graph of $y = \ln x$ is the solution that passes through the point $(1, 0)$. (You will study slope fields in Section 6.1.)



Each small line segment has a slope of $\frac{1}{x}$.

Figure 5.2

THEOREM 5.1 Properties of the Natural Logarithmic Function

The natural logarithmic function has three important properties.

1. The domain is $(0, \infty)$ and the range is $(-\infty, \infty)$.
2. The function is continuous, increasing, and one-to-one.
3. The graph is concave downward.



The natural logarithmic function is increasing, and its graph is concave downward.

Figure 5.3

Proof The domain of $f(x) = \ln x$ is $(0, \infty)$ by definition. Moreover, the function is continuous because it is differentiable. It is increasing because its derivative

$$f'(x) = \frac{1}{x}$$ First derivative

is positive for $x > 0$, as shown in Figure 5.3. It is concave downward because its second derivative

$$f''(x) = -\frac{1}{x^2}$$ Second derivative

is negative for $x > 0$. The proof that f is one-to-one is given in Appendix A. The next two limits imply that the range of f is the entire real number line.

$$\lim_{x \to 0^+} \ln x = -\infty$$

and

$$\lim_{x \to \infty} \ln x = \infty$$

Verification of these two limits is given in Appendix A. ∎

Using the definition of the natural logarithmic function, you can prove several important properties involving operations with natural logarithms. If you are already familiar with logarithms, you will recognize that the properties listed on the next page are characteristic of all logarithms.

GO DIGITAL

Chronicle/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

THEOREM 5.2 Logarithmic Properties

If a and b are positive numbers and n is rational, then the four properties below are true.

1. $\ln 1 = 0$

2. $\ln(ab) = \ln a + \ln b$

3. $\ln(a^n) = n \ln a$

4. $\ln\left(\frac{a}{b}\right) = \ln a - \ln b$

Proof The first property has already been discussed. The proof of the second property follows from the fact that two antiderivatives of the same function differ at most by a constant. From the Second Fundamental Theorem of Calculus and the definition of the natural logarithmic function, you know that

$$\frac{d}{dx}[\ln x] = \frac{d}{dx}\left[\int_1^x \frac{1}{t}\,dt\right] = \frac{1}{x}.$$ Apply Second Fundamental Theorem of Calculus.

So, consider the two derivatives

$$\frac{d}{dx}[\ln(ax)] = \frac{a}{ax} = \frac{1}{x}$$

and

$$\frac{d}{dx}[\ln a + \ln x] = 0 + \frac{1}{x} = \frac{1}{x}.$$

Because $\ln(ax)$ and $(\ln a + \ln x)$ are both antiderivatives of $1/x$, they must differ at most by a constant, $\ln(ax) = \ln a + \ln x + C$. By letting $x = 1$, you can see that $C = 0$. The third property can be proved similarly by comparing the derivatives of $\ln(x^n)$ and $n \ln x$. Finally, use the second and third properties to prove the fourth property.

$$\ln\left(\frac{a}{b}\right) = \ln[a(b^{-1})] = \ln a + \ln(b^{-1}) = \ln a - \ln b$$ ■

EXAMPLE 1 Expanding Logarithmic Expressions

a. $\ln\frac{10}{9} = \ln 10 - \ln 9$ Property 4

b. $\ln\sqrt{3x+2} = \ln(3x+2)^{1/2}$ Rewrite with rational exponent.

$= \frac{1}{2}\ln(3x+2)$ Property 3

c. $\ln\frac{6x}{5} = \ln(6x) - \ln 5$ Property 4

$= \ln 6 + \ln x - \ln 5$ Property 2

d. $\ln\frac{(x^2+3)^2}{x\sqrt[3]{x^2+1}} = \ln(x^2+3)^2 - \ln\left(x\sqrt[3]{x^2+1}\right)$

$= 2\ln(x^2+3) - [\ln x + \ln(x^2+1)^{1/3}]$

$= 2\ln(x^2+3) - \ln x - \ln(x^2+1)^{1/3}$

$= 2\ln(x^2+3) - \ln x - \frac{1}{3}\ln(x^2+1)$ ■



Figure 5.4

When using the properties of logarithms to rewrite logarithmic functions, you must check to see whether the domain of the rewritten function is the same as the domain of the original. For instance, the domain of $f(x) = \ln x^2$ is all real numbers except $x = 0$, and the domain of $g(x) = 2 \ln x$ is all positive real numbers. (See Figure 5.4.)

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The Number e

It is likely that you have studied logarithms in an algebra course. There, without the benefit of calculus, logarithms would have been defined in terms of a **base** number. For example, common logarithms have a base of 10 and so $\log_{10} 10 = 1$. (You will learn more about this in Section 5.5.)

The **base for the natural logarithm** is defined using the fact that the natural logarithmic function is continuous, is one-to-one, and has a range of $(-\infty, \infty)$. So, there must be a unique real number x such that $\ln x = 1$, as shown in Figure 5.5. This number is denoted by the letter e. It can be shown that e is irrational and has the decimal approximation



e is the base for the natural logarithm because $\ln e = 1$.
Figure 5.5

$$e \approx 2.71828182846$$

when rounded to 11 decimal places.

THE NUMBER e

The symbol e was first used by mathematician Leonhard Euler to represent the base of natural logarithms in a letter to another mathematician, Christian Goldbach, in 1731.

Definition of e

The letter e denotes the positive real number such that

$$\ln e = \int_1^e \frac{1}{t}\,dt = 1.$$

Once you know that $\ln e = 1$, you can use logarithmic properties to evaluate the natural logarithms of several other numbers. For example, by using the property

$$\ln(e^n) = n \ln e = n(1) = n$$

you can evaluate $\ln(e^n)$ for various values of n, as shown in the table and in Figure 5.6. The logarithms shown in the table are convenient because the x-values are integer powers of e. Most logarithmic expressions are, however, best evaluated with a calculator. For example, $\ln 2 \approx 0.693$ and $\ln(0.1) \approx -2.303$.

FOR FURTHER INFORMATION
To learn more about the number e, see the article "Unexpected Occurrences of the Number e" by Harris S. Shultz and Bill Leonard in *Mathematics Magazine*. To view this article, go to *MathArticles.com*.

x	$\frac{1}{e^3} \approx 0.050$	$\frac{1}{e^2} \approx 0.135$	$\frac{1}{e} \approx 0.368$	$e^0 = 1$	$e \approx 2.718$	$e^2 \approx 7.389$
$\ln x$	-3	-2	-1	0	1	2



If $x = e^n$, then $\ln x = n$.
Figure 5.6

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The Derivative of the Natural Logarithmic Function

The derivative of the natural logarithmic function is given in Theorem 5.3. The first part of the theorem follows from the definition of the natural logarithmic function as an antiderivative. The second part of the theorem is simply the Chain Rule version of the first part.

THEOREM 5.3 Derivative of the Natural Logarithmic Function

Let u be a differentiable function of x.

1. $\dfrac{d}{dx}[\ln x] = \dfrac{1}{x}, \quad x > 0$
2. $\dfrac{d}{dx}[\ln u] = \dfrac{1}{u}\dfrac{du}{dx} = \dfrac{u'}{u}, \quad u > 0$

EXAMPLE 2 Differentiation of Logarithmic Functions

See LarsonCalculus.com for an interactive version of this type of example.

a. $\dfrac{d}{dx}[\ln 2x] = \dfrac{u'}{u} = \dfrac{2}{2x} = \dfrac{1}{x}$ $u = 2x$

b. $\dfrac{d}{dx}[\ln(x^2 + 1)] = \dfrac{u'}{u} = \dfrac{2x}{x^2 + 1}$ $u = x^2 + 1$

c. $\dfrac{d}{dx}[x \ln x] = x\left(\dfrac{d}{dx}[\ln x]\right) + (\ln x)\left(\dfrac{d}{dx}[x]\right)$ Product Rule

$= x\left(\dfrac{1}{x}\right) + (\ln x)(1)$

$= 1 + \ln x$

d. $\dfrac{d}{dx}[(\ln x)^3] = 3(\ln x)^2 \dfrac{d}{dx}[\ln x]$ Chain Rule

$= 3(\ln x)^2 \dfrac{1}{x}$ ■

Napier used logarithmic properties to simplify *calculations* involving products, quotients, and powers. Of course, given the availability of calculators, there is now little need for this particular application of logarithms. However, there is great value in using logarithmic properties to simplify *differentiation* involving products, quotients, and powers.

EXAMPLE 3 Logarithmic Properties as Aids to Differentiation

Differentiate $f(x) = \ln\sqrt{x + 1}$.

Solution To help with the differentiation, rewrite the radical with a rational exponent. Then use the logarithmic property $\ln x^z = z \ln x$ to rewrite the function as

$$f(x) = \ln\sqrt{x + 1} = \ln(x + 1)^{1/2} = \frac{1}{2}\ln(x + 1).$$ Rewrite before differentiating.

Next, find the first derivative of f with respect to x.

$$f'(x) = \frac{1}{2}\left(\frac{1}{x + 1}\right) = \frac{1}{2(x + 1)}$$ Differentiate. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 4 Logarithmic Properties as Aids to Differentiation

Differentiate $f(x) = \ln \dfrac{x(x^2 + 1)^2}{\sqrt{2x^3 - 1}}$.

Solution First, use logarithmic properties to rewrite the function.

$$f(x) = \ln \frac{x(x^2 + 1)^2}{\sqrt{2x^3 - 1}}$$ Write original function.

$$= \ln x + 2\ln(x^2 + 1) - \frac{1}{2}\ln(2x^3 - 1)$$ Rewrite before differentiating.

Next, find the first derivative of f with respect to x.

$$f'(x) = \frac{1}{x} + 2\left(\frac{2x}{x^2 + 1}\right) - \frac{1}{2}\left(\frac{6x^2}{2x^3 - 1}\right)$$ Differentiate.

$$= \frac{1}{x} + \frac{4x}{x^2 + 1} - \frac{3x^2}{2x^3 - 1}$$ Simplify.

REMARK In Example 4, notice how the logarithmic properties

$$\ln xy = \ln x + \ln y,$$

$$\ln \frac{x}{y} = \ln x - \ln y,$$

and

$$\ln x^z = z \ln x$$

are used to rewrite the function before differentiating.

In Examples 3 and 4, be sure you see the benefit of applying logarithmic properties *before* differentiating. Consider, for instance, the difficulty of direct differentiation of the function given in Example 4.

On occasion, it is convenient to use logarithms as aids in differentiating *nonlogarithmic* functions. This procedure is called **logarithmic differentiation.** In general, use logarithmic differentiation when differentiating (1) a function involving many factors or (2) a function having both a variable base and a variable exponent [see Section 5.5, Example 5(d)].

EXAMPLE 5 Logarithmic Differentiation

Find the derivative of $y = \dfrac{(x - 2)^2}{\sqrt{x^2 + 1}}, \quad x \neq 2.$

Solution Note that $y > 0$ for all $x \neq 2$. So, $\ln y$ is defined. Begin by taking the natural logarithm of each side of the equation. Then apply logarithmic properties and differentiate implicitly. Finally, solve for y'.

$$y = \frac{(x - 2)^2}{\sqrt{x^2 + 1}}, \quad x \neq 2$$ Write original equation.

$$\ln y = \ln \frac{(x - 2)^2}{\sqrt{x^2 + 1}}$$ Take natural log of each side.

$$\ln y = 2\ln(x - 2) - \frac{1}{2}\ln(x^2 + 1)$$ Logarithmic properties

$$\frac{y'}{y} = 2\left(\frac{1}{x - 2}\right) - \frac{1}{2}\left(\frac{2x}{x^2 + 1}\right)$$ Differentiate.

$$\frac{y'}{y} = \frac{x^2 + 2x + 2}{(x - 2)(x^2 + 1)}$$ Simplify.

$$y' = y\left[\frac{x^2 + 2x + 2}{(x - 2)(x^2 + 1)}\right]$$ Solve for y'.

$$y' = \frac{(x - 2)^2}{\sqrt{x^2 + 1}}\left[\frac{x^2 + 2x + 2}{(x - 2)(x^2 + 1)}\right]$$ Substitute for y.

$$y' = \frac{(x - 2)(x^2 + 2x + 2)}{(x^2 + 1)^{3/2}}$$ Simplify.

REMARK You could also solve the problem in Example 5 without using logarithmic differentiation by using the Power and Quotient Rules. Use these rules to find the derivative and show that the result is equivalent to the one in Example 5. Which method do you prefer?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Because the natural logarithm is undefined for negative numbers, you will often encounter expressions of the form $\ln|u|$. The next theorem states that you can differentiate functions of the form $y = \ln|u|$ as though the absolute value notation was not present.

THEOREM 5.4 Derivative Involving Absolute Value

If u is a differentiable function of x such that $u \neq 0$, then

$$\frac{d}{dx}[\ln|u|] = \frac{u'}{u}.$$

Proof If $u > 0$, then $|u| = u$, and the result follows from Theorem 5.3. If $u < 0$, then $|u| = -u$, and you have

$$\frac{d}{dx}[\ln|u|] = \frac{d}{dx}[\ln(-u)] \qquad \text{For } u < 0,\ |u| = -u.$$

$$= \frac{-u'}{-u} \qquad \text{Apply Theorem 5.3.}$$

$$= \frac{u'}{u}. \qquad \text{Simplify.}$$

EXAMPLE 6 Derivative Involving Absolute Value

Find the derivative of

$$f(x) = \ln|\cos x|.$$

Solution Using Theorem 5.4, let $u = \cos x$ and write

$$\frac{d}{dx}[\ln|\cos x|] = \frac{u'}{u} \qquad \frac{d}{dx}[\ln|u|] = \frac{u'}{u}$$

$$= \frac{-\sin x}{\cos x} \qquad u = \cos x$$

$$= -\tan x. \qquad \text{Simplify.}$$

The next example shows how to use the techniques of Chapter 3 to find the relative extrema of a logarithmic function.

EXAMPLE 7 Finding Relative Extrema

Locate the relative extrema of

$$y = \ln(x^2 + 2x + 3).$$

Solution Differentiating y, you obtain

$$\frac{dy}{dx} = \frac{2x + 2}{x^2 + 2x + 3}.$$

Because $dy/dx = 0$ when $x = -1$, you can apply the First Derivative Test and conclude that a relative minimum occurs at the point $(-1, \ln 2)$. Because there are no other critical points, it follows that this is the only relative extremum, as shown in the figure.



The derivative of y changes from negative to positive at $x = -1$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

5.1 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain why $\ln x$ is positive for $x > 1$ and negative for $0 < x < 1$.
2. Find the value of n.

   $\ln 4 + \ln(n^{-1}) = \ln 4 - \ln 7$
3. Define the number e.
4. State the Chain Rule version of the derivative of the natural logarithmic function.

Matching In Exercises 5–8, match the function with its graph. [The graphs are labeled (a), (b), (c), and (d).]

(a)



(b)



(c)



(d)



5. $f(x) = \ln x + 1$
6. $f(x) = -\ln x$
7. $f(x) = \ln(x - 1)$
8. $f(x) = -\ln(-x)$

Sketching a Graph In Exercises 9–14, sketch the graph of the function and state its domain.

9. $f(x) = 3 \ln x$
10. $f(x) = -2 \ln x$
11. $f(x) = \ln 2x$
12. $f(x) = \ln|x|$
13. $f(x) = \ln(x - 3)$
14. $f(x) = \ln x - 4$

Using Properties of Logarithms In Exercises 15 and 16, use the properties of logarithms to approximate the indicated logarithms, given that $\ln 2 \approx 0.6931$ and $\ln 3 \approx 1.0986$.

15. (a) $\ln 6$ (b) $\ln \frac{2}{3}$ (c) $\ln 81$ (d) $\ln \sqrt{3}$
16. (a) $\ln 0.25$ (b) $\ln 24$ (c) $\ln \sqrt[3]{12}$ (d) $\ln \frac{1}{72}$

Expanding a Logarithmic Expression In Exercises 17–26, use the properties of logarithms to expand the logarithmic expression.

17. $\ln \frac{x}{4}$
18. $\ln \sqrt{x^5}$
19. $\ln \frac{xy}{z}$
20. $\ln(xyz)$
21. $\ln\left(x\sqrt{x^2 + 5}\right)$
22. $x \ln \sqrt{x - 4}$
23. $\ln \sqrt{\frac{x - 1}{x}}$
24. $\ln(3e^2)$
25. $\ln z(z - 1)^2$
26. $\ln \frac{z}{e}$

Condensing a Logarithmic Expression In Exercises 27–32, write the expression as a logarithm of a single quantity.

27. $\ln(x - 2) - \ln(x + 2)$
28. $3 \ln x + 2 \ln y - 4 \ln z$
29. $\frac{1}{3}[2 \ln(x + 3) + \ln x - \ln(x^2 - 1)]$
30. $2[\ln x - \ln(x + 1) - \ln(x - 1)]$
31. $4 \ln 2 - \frac{1}{2} \ln(x^3 + 6x)$
32. $\frac{3}{2}[\ln(x^2 + 1) - \ln(x + 1) - \ln(x - 1)]$

Verifying Properties of Logarithms In Exercises 33 and 34, (a) verify that $f = g$ by using a graphing utility to graph f and g in the same viewing window and (b) verify that $f = g$ algebraically.

33. $f(x) = \ln \frac{x^2}{4}$, $x > 0$, $g(x) = 2 \ln x - \ln 4$
34. $f(x) = \ln \sqrt{x(x^2 + 1)}$, $g(x) = \frac{1}{2}[\ln x + \ln(x^2 + 1)]$

Finding a Limit In Exercises 35–38, find the limit.

35. $\lim_{x \to 3^+} \ln(x - 3)$
36. $\lim_{x \to 6^-} \ln(6 - x)$
37. $\lim_{x \to 2^-} \ln[x^2(3 - x)]$
38. $\lim_{x \to 5^+} \ln \frac{x}{\sqrt{x - 4}}$

Finding a Derivative In Exercises 39–62, find the derivative of the function.

39. $f(x) = \ln 3x$
40. $f(x) = \ln(x - 1)$
41. $f(x) = \ln(x^2 + 3)$
42. $h(x) = \ln(2x^2 + 1)$
43. $y = (\ln x)^4$
44. $y = x^2 \ln x$
45. $y = \ln(t + 1)^2$
46. $y = \ln \sqrt{x^2 - 4}$
47. $y = \ln\left(x\sqrt{x^2 - 1}\right)$
48. $y = \ln[t(t^2 + 3)^3]$
49. $f(x) = \ln \frac{x}{x^2 + 1}$
50. $f(x) = \ln \frac{2x}{x + 3}$
51. $g(t) = \frac{\ln t}{t^2}$
52. $h(t) = \frac{\ln t}{t^3 + 5}$
53. $y = \ln(\ln x^2)$
54. $y = \ln(\ln x)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

55. $y = \ln\sqrt{\dfrac{x+1}{x-1}}$ **56.** $y = \ln\sqrt[3]{\dfrac{x-1}{x+1}}$

57. $f(x) = \ln\dfrac{\sqrt{4+x^2}}{x}$ **58.** $f(x) = \ln\left(x + \sqrt{4+x^2}\right)$

59. $y = \ln|\sin x|$ **60.** $y = \ln|\csc x|$

61. $y = \ln\left|\dfrac{\cos x}{\cos x - 1}\right|$ **62.** $y = \ln|\sec x + \tan x|$

Finding an Equation of a Tangent Line **In Exercises 63–70, (a) find an equation of the tangent line to the graph of the function at the given point, (b) use a graphing utility to graph the function and its tangent line at the point, and (c) use the *tangent* feature of a graphing utility to verify your results.**

63. $y = \ln x^4, \quad (1, 0)$ **64.** $y = \ln x^{2/3}, \quad (-1, 0)$

65. $f(x) = 3x^2 - \ln x, \quad (1, 3)$

66. $f(x) = 4 - x^2 - \ln\left(\frac{1}{2}x + 1\right), \quad (0, 4)$

67. $f(x) = \ln\sqrt{1+\sin^2 x}, \quad \left(\dfrac{\pi}{4}, \ln\sqrt{\dfrac{3}{2}}\right)$

68. $f(x) = \sin 2x \ln x^2, \quad (1, 0)$

69. $y = x^3 \ln x^4, \quad (-1, 0)$

70. $f(x) = \dfrac{1}{2}x \ln x^2, \quad (-1, 0)$

Logarithmic Differentiation **In Exercises 71–76, use logarithmic differentiation to find dy/dx.**

71. $y = x\sqrt{x^2+1}, \quad x > 0$

72. $y = \sqrt{x^2(x+1)(x+2)}, \quad x > 0$

73. $y = \dfrac{x^2\sqrt{3x-2}}{(x+1)^2}, \quad x > \dfrac{2}{3}$ **74.** $y = \sqrt{\dfrac{x^2-1}{x^2+1}}, \quad x > 1$

75. $y = \dfrac{x(x-1)^{3/2}}{\sqrt{x+1}}, \quad x > 1$ **76.** $y = \dfrac{(x+1)(x-2)}{(x-1)(x+2)}, \quad x > 2$

Implicit Differentiation **In Exercises 77–80, use implicit differentiation to find dy/dx.**

77. $x^2 - 3\ln y + y^2 = 10$ **78.** $\ln xy + 5x = 30$

79. $4x^3 + \ln y^2 + 2y = 2x$ **80.** $4xy + \ln x^2 y = 7$

Differential Equation **In Exercises 81 and 82, verify that the function is a solution of the differential equation.**

Function	Differential Equation
81. $y = 2\ln x + 3$	$xy'' + y' = 0$
82. $y = x\ln x - 4x$	$x + y - xy' = 0$

Relative Extrema and Points of Inflection **In Exercises 83–88, locate any relative extrema and points of inflection. Use a graphing utility to confirm your results.**

83. $y = \dfrac{x^2}{2} - \ln x$ **84.** $y = 2x - \ln 2x$

85. $y = x\ln x$ **86.** $y = \dfrac{\ln x}{x}$

87. $y = \dfrac{x}{\ln x}$ **88.** $y = x^2 \ln\dfrac{x}{4}$

Using Newton's Method **In Exercises 89 and 90, use Newton's Method to approximate, to three decimal places, the x-coordinate of the point of intersection of the graphs of the two equations. Use a graphing utility to verify your result.**

89. $y = \ln x, \quad y = -x$ **90.** $y = \ln x, \quad y = 3 - x$

Exploring Concepts

In Exercises 91 and 92, let f be a function that is positive and differentiable on the entire real number line and let $g(x) = \ln f(x)$.

91. When g is increasing, must f be increasing? Explain.

92. When the graph of f is concave upward, must the graph of g be concave upward? Explain.

93. Is $\ln xy = \ln x \ln y$ a valid property of logarithms, where $x > 0$ and $y > 0$? Explain.

94. HOW DO YOU SEE IT? The graph shows the temperature T (in degrees Celsius) of an object h hours after it is removed from a furnace.



(a) Find $\lim_{h\to\infty} T$. What does this limit represent?

(b) When is the temperature changing most rapidly?

True or False? **In Exercises 95–98, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

95. $\ln(a^{n+m}) = n\ln a + m\ln a$, where $a > 0$ and m and n are rational.

96. $\dfrac{d}{dx}[\ln(cx)] = \dfrac{d}{dx}[\ln x]$, where $c > 0$

97. If $y = \ln\pi$, then $y' = 1/\pi$. **98.** If $y = \ln e$, then $y' = 1$.

99. Logarithmic Equation Solve for x.

$$\frac{\ln x}{x} = \frac{\ln 2}{2}$$

100. Proof Use a graphing utility to graph the equations $y_1 = x - 1$, $y_2 = \ln x$, and $y_3 = 1 - (1/x)$, $x > 0$. Note that $x - 1 \geq \ln x \geq 1 - (1/x)$. Prove this inequality by analyzing the functions $f(x) = x - 1 - \ln x$ and $g(x) = 1 - (1/x) - \ln x$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

101. Home Mortgage The term t (in years) of a \$200,000 home mortgage at 7.5% interest can be approximated by

$$t = 13.375 \ln\left(\frac{x}{x - 1250}\right), \quad x > 1250$$

where x is the monthly payment in dollars.

(a) Use a graphing utility to graph the model.

(b) Use the model to approximate the term of a home mortgage for which the monthly payment is \$1398.43. What is the total amount paid?

(c) Use the model to approximate the term of a home mortgage for which the monthly payment is \$1611.19. What is the total amount paid?

(d) Find the instantaneous rates of change of t with respect to x when $x = \$1398.43$ and $x = \$1611.19$.

(e) Write a short paragraph describing the benefit of the higher monthly payment.

102. Sound Intensity

The relationship between the number of decibels β and the intensity of a sound I in watts per centimeter squared is $\beta = \frac{10}{\ln 10} \ln\left(\frac{I}{10^{-16}}\right)$.

(a) Use the properties of logarithms to write the formula in simpler form.

(b) Determine the number of decibels of a sound with an intensity of 10^{-5} watt per square centimeter.

103. Modeling Data The table shows the temperatures T (in degrees Fahrenheit) at which water boils at selected pressures p (in pounds per square inch). (*Source: Standard Handbook of Mechanical Engineers*)

p	5	10	14.696 (1 atm)	20
T	162.24	193.21	212.00	227.96

p	30	40	60	80	100
T	250.33	267.25	292.71	312.03	327.81

A model that approximates the data is

$$T = 87.97 + 34.96 \ln p + 7.91\sqrt{p}.$$

(a) Use a graphing utility to plot the data and graph the model.

(b) Find the rates of change of T with respect to p when $p = 10$ and $p = 70$.

(c) Use a graphing utility to graph T'. Find $\lim_{p \to \infty} T'(p)$ and interpret the result in the context of the problem.

104. Modeling Data The atmospheric pressure decreases with increasing altitude. At sea level, the average air pressure is one atmosphere (1.033227 kilograms per square centimeter). The table shows the pressures p (in atmospheres) at selected altitudes h (in kilometers).

h	0	5	10	15	20	25
p	1	0.55	0.25	0.12	0.06	0.02

(a) Use a graphing utility to find a model of the form $p = a + b \ln h$ for the data. Explain why the result is an error message.

(b) Use a graphing utility to find the logarithmic model $h = a + b \ln p$ for the data.

(c) Use a graphing utility to plot the data and graph the model from part (b).

(d) Use the model to estimate the altitude when $p = 0.75$.

(e) Use the model to estimate the pressure when $h = 13$.

(f) Use the model to find the rates of change of pressure when $h = 5$ and $h = 20$. Interpret the results.

105. Tractrix A person walking along a dock drags a boat by a 10-meter rope. The boat travels along a path known as a *tractrix* (see figure). The equation of this path is

$$y = 10 \ln\left(\frac{10 + \sqrt{100 - x^2}}{x}\right) - \sqrt{100 - x^2}.$$

(a) Use a graphing utility to graph the function.

(b) What are the slopes of this path when $x = 5$ and $x = 9$?

(c) What does the slope of the path approach as x approaches 10 from the left?



106. Prime Number Theorem There are 25 prime numbers less than 100. The **Prime Number Theorem** states that the number of primes less than x approaches

$$p(x) \approx \frac{x}{\ln x}.$$

Use this approximation to estimate the rate (in primes per 100 integers) at which the prime numbers occur when

(a) $x = 1000$.

(b) $x = 1{,}000{,}000$.

(c) $x = 1{,}000{,}000{,}000$.

107. Conjecture Use a graphing utility to graph f and g in the same viewing window and determine which is increasing at the greater rate for large values of x. What can you conclude about the rate of growth of the natural logarithmic function?

(a) $f(x) = \ln x, \quad g(x) = \sqrt{x}$

(b) $f(x) = \ln x, \quad g(x) = \sqrt[4]{x}$

William R. Sallaz/Getty Images

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

5.2 The Natural Logarithmic Function: Integration

GO DIGITAL

- Use the Log Rule for Integration to integrate a rational function.
- Integrate trigonometric functions.

Log Rule for Integration

The differentiation rules

$$\frac{d}{dx}[\ln|x|] = \frac{1}{x} \quad \text{and} \quad \frac{d}{dx}[\ln|u|] = \frac{u'}{u}$$

that you studied in the preceding section produce the **Log Rule for Integration.**

THEOREM 5.5 Log Rule for Integration

Let u be a differentiable function of x.

1. $\displaystyle\int \frac{1}{x}\,dx = \ln|x| + C$
2. $\displaystyle\int \frac{1}{u}\,du = \ln|u| + C$

Because $du = u'\,dx$, the second formula can also be written as

$$\int \frac{u'}{u}\,dx = \ln|u| + C. \qquad \text{Alternative form of Log Rule}$$

EXAMPLE 1 Using the Log Rule for Integration

$$\begin{aligned}\int \frac{2}{x}\,dx &= 2\int \frac{1}{x}\,dx && \text{Constant Multiple Rule}\\ &= 2\ln|x| + C && \text{Log Rule for Integration}\\ &= \ln x^2 + C && \text{Property of logarithms}\end{aligned}$$

Because x^2 cannot be negative, the absolute value notation is unnecessary in the final form of the antiderivative.

EXAMPLE 2 Using the Log Rule with a Change of Variables

Find $\displaystyle\int \frac{1}{4x-1}\,dx$.

Solution If you let $u = 4x - 1$, then $du = 4\,dx$. To introduce the missing factor of 4 in the integrand, multiply and divide by 4.

$$\begin{aligned}\int \frac{1}{4x-1}\,dx &= \frac{1}{4}\int \left(\frac{1}{4x-1}\right)4\,dx && \text{Multiply and divide by 4.}\\ &= \frac{1}{4}\int \frac{1}{u}\,du && \text{Substitute: } u = 4x-1.\\ &= \frac{1}{4}\ln|u| + C && \text{Apply Log Rule.}\\ &= \frac{1}{4}\ln|4x-1| + C && \text{Back-substitute.}\end{aligned}$$

Exploration

Integrating Rational Functions

Early in Chapter 4, you learned rules that allowed you to integrate *any* polynomial function. The Log Rule presented in this section goes a long way toward enabling you to integrate rational functions. For instance, each function below can be integrated with the Log Rule.

$\frac{2}{x}$	Example 1
$\frac{1}{4x-1}$	Example 2
$\frac{x}{x^2+1}$	Example 3
$\frac{3x^2+1}{x^3+x}$	Example 4(a)
$\frac{x+1}{x^2+2x}$	Example 4(c)
$\frac{1}{3x+2}$	Example 4(d)
$\frac{x^2+x+1}{x^2+1}$	Example 5
$\frac{2x}{(x+1)^2}$	Example 6

There are still some rational functions that cannot be integrated using the Log Rule. Give examples of these functions and explain your reasoning.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Example 3 uses the alternative form of the Log Rule. To apply this rule, look for quotients in which the numerator is the derivative of the denominator.

EXAMPLE 3 Finding Area with the Log Rule

Find the area of the region bounded by the graph of

$$y = \frac{x}{x^2 + 1}$$

the x-axis, and the line $x = 3$.



Area $= \int_0^3 \frac{x}{x^2 + 1}\,dx$

The area of the region bounded by the graph of y, the x-axis, and $x = 3$ is $\frac{1}{2}\ln 10$.

Figure 5.7

Solution In Figure 5.7, you can see that the area of the region is given by the definite integral

$$\int_0^3 \frac{x}{x^2 + 1}\,dx. \qquad \text{Area of region}$$

If you let $u = x^2 + 1$, then $u' = 2x$. To apply the Log Rule, multiply and divide by 2 as shown.

$$\int_0^3 \frac{x}{x^2 + 1}\,dx = \frac{1}{2}\int_0^3 \frac{2x}{x^2 + 1}\,dx \qquad \text{Multiply and divide by 2.}$$

$$= \frac{1}{2}\Big[\ln(x^2 + 1)\Big]_0^3 \qquad \int \frac{u'}{u}\,dx = \ln|u| + C$$

$$= \frac{1}{2}(\ln 10 - \ln 1)$$

$$= \frac{1}{2}\ln 10 \qquad \ln 1 = 0$$

$$\approx 1.151$$

The area of the region is about 1.151 square units.

EXAMPLE 4 Recognizing Quotient Forms of the Log Rule

a. $\int \frac{3x^2 + 1}{x^3 + x}\,dx = \ln|x^3 + x| + C \qquad u = x^3 + x$

b. $\int \frac{\sec^2 x}{\tan x}\,dx = \ln|\tan x| + C \qquad u = \tan x$

c. $\int \frac{x + 1}{x^2 + 2x}\,dx = \frac{1}{2}\int \frac{2x + 2}{x^2 + 2x}\,dx \qquad u = x^2 + 2x$

$$= \frac{1}{2}\ln|x^2 + 2x| + C$$

d. $\int \frac{1}{3x + 2}\,dx = \frac{1}{3}\int \frac{3}{3x + 2}\,dx \qquad u = 3x + 2$

$$= \frac{1}{3}\ln|3x + 2| + C$$

With antiderivatives involving logarithms, it is easy to obtain forms that look quite different but are still equivalent. For instance, both

$$\ln|(3x + 2)^{1/3}| + C$$

and

$$\ln|3x + 2|^{1/3} + C$$

are equivalent to the antiderivative listed in Example 4(d).

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Integrals to which the Log Rule can be applied often appear in disguised form. For instance, when a rational function has a *numerator of degree greater than or equal to that of the denominator*, division may reveal a form to which you can apply the Log Rule. This is shown in Example 5.

EXAMPLE 5 Using Long Division Before Integrating

See LarsonCalculus.com for an interactive version of this type of example.

Find the indefinite integral.

$$\int \frac{x^2 + x + 1}{x^2 + 1}\,dx$$

Solution Begin by using long division to rewrite the integrand.

$$\frac{x^2 + x + 1}{x^2 + 1} \quad \Rightarrow \quad x^2 + 1\overline{)\,x^2 + x + 1}\;\begin{array}{r}1\\ x^2 + 1\\ \hline x\end{array} \quad \Rightarrow \quad 1 + \frac{x}{x^2 + 1}$$

Now, integrate to obtain

$$\begin{aligned}\int \frac{x^2 + x + 1}{x^2 + 1}\,dx &= \int \left(1 + \frac{x}{x^2 + 1}\right)dx && \text{Rewrite using long division.}\\ &= \int dx + \frac{1}{2}\int \frac{2x}{x^2 + 1}\,dx && \text{Rewrite as two integrals.}\\ &= x + \frac{1}{2}\ln(x^2 + 1) + C. && \text{Integrate.}\end{aligned}$$

Check this result by differentiating to obtain the original integrand. ■

The next example presents another instance in which the use of the Log Rule is disguised. In this case, a change of variables helps you recognize the Log Rule.

EXAMPLE 6 Change of Variables with the Log Rule

Find the indefinite integral.

$$\int \frac{2x}{(x + 1)^2}\,dx$$

Solution If you let $u = x + 1$, then $du = dx$ and $x = u - 1$.

$$\begin{aligned}\int \frac{2x}{(x + 1)^2}\,dx &= \int \frac{2(u - 1)}{u^2}\,du && \text{Substitute.}\\ &= 2\int \left(\frac{u}{u^2} - \frac{1}{u^2}\right)du && \text{Rewrite as two fractions.}\\ &= 2\int \frac{du}{u} - 2\int u^{-2}\,du && \text{Rewrite as two integrals.}\\ &= 2\ln|u| - 2\left(\frac{u^{-1}}{-1}\right) + C && \text{Integrate.}\\ &= 2\ln|u| + \frac{2}{u} + C && \text{Simplify.}\\ &= 2\ln|x + 1| + \frac{2}{x + 1} + C && \text{Back-substitute.}\end{aligned}$$

Check this result by differentiating to obtain the original integrand. ■

TECHNOLOGY Use a graphing utility to find the indefinite integrals in Examples 5 and 6. How does the form of the antiderivative that it gives you compare with that given in Examples 5 and 6?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

The methods shown in Examples 5 and 6 involve rewriting a disguised integrand so that it fits one or more of the basic integration formulas. Throughout the remaining sections of Chapter 5 and in Chapter 8, much time will be devoted to integration techniques. To master these techniques, you must recognize the "form-fitting" nature of integration. In this sense, integration is not nearly as straightforward as differentiation. Differentiation takes the form

"Here is the question; what is the answer?"

Integration is more like

"Here is the answer; what is the question?"

Below are some guidelines you can use for integration.

Guidelines for Integration

1. Learn a basic list of integration formulas.
2. Find an integration formula that resembles all or part of the integrand and, by trial and error, find a choice of u that will make the integrand conform to the formula.
3. When you cannot find a u-substitution that works, try altering the integrand. You might try a trigonometric identity, multiplication and division by the same quantity, addition and subtraction of the same quantity, or long division. Be creative.
4. If you have a graphing utility that finds antiderivatives symbolically, use it.
5. Check your result by differentiating to obtain the original integrand.

EXAMPLE 7 ***u*-Substitution and the Log Rule**

Solve the differential equation

$$\frac{dy}{dx} = \frac{1}{x \ln x}.$$

Solution The solution can be written as an indefinite integral.

$$y = \int \frac{1}{x \ln x}\, dx$$

Because the integrand is a quotient whose denominator is raised to the first power, you should try the Log Rule. There are three basic choices for u. Two of the choices,

$$u = x \quad \text{and} \quad u = x \ln x$$

fail to fit the u'/u form of the Log Rule. The third choice, $u = \ln x$, does fit. Letting $u = \ln x$ produces $u' = 1/x$. Now, find the indefinite integral.

$$\begin{aligned}
\int \frac{1}{x \ln x}\, dx &= \int \frac{1/x}{\ln x}\, dx && \text{Divide numerator and denominator by } x. \\
&= \int \frac{u'}{u}\, du && \text{Substitute: } u = \ln x. \\
&= \ln|u| + C && \text{Apply Log Rule.} \\
&= \ln|\ln x| + C && \text{Back-substitute.}
\end{aligned}$$

So, the solution of the differential equation is $y = \ln|\ln x| + C$. ■

REMARK Keep in mind that you can check your answer to an integration problem by differentiating the answer. For instance, in Example 7, the derivative of $y = \ln|\ln x| + C$ is $y' = 1/(x \ln x)$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Integrals of Trigonometric Functions

In Section 4.1, you studied six trigonometric integration rules—the six that correspond directly to differentiation rules. With the Log Rule, you can now complete the set of basic trigonometric integration formulas.

EXAMPLE 8 Using a Trigonometric Identity

Find $\int \tan x \, dx$.

Solution This integral does not seem to fit any formulas on the basic list. By using a trigonometric identity, however, you obtain

$$\int \tan x \, dx = \int \frac{\sin x}{\cos x} \, dx. \qquad \tan x = \frac{\sin x}{\cos x}$$

Knowing that $D_x[\cos x] = -\sin x$, let $u = \cos x$ and $u' = -\sin x$. So, you can conclude that

$$\begin{aligned} \int \tan x \, dx &= -\int \frac{-\sin x}{\cos x} \, dx && \text{Apply trigonometric identity and multiply and divide by } -1. \\ &= -\int \frac{u'}{u} \, du && \text{Substitute: } u = \cos x. \\ &= -\ln|u| + C && \text{Apply Log Rule.} \\ &= -\ln|\cos x| + C. && \text{Back-substitute.} \end{aligned}$$

Example 8 used a trigonometric identity to derive an integration rule for the tangent function. The next example takes a rather unusual step (multiplying and dividing by the same quantity) to derive an integration rule for the secant function.

EXAMPLE 9 Derivation of the Secant Formula

Find $\int \sec x \, dx$.

Solution Consider the procedure shown below.

$$\begin{aligned} \int \sec x \, dx &= \int (\sec x)\left(\frac{\sec x + \tan x}{\sec x + \tan x}\right) dx && \text{Multiply and divide by } \sec x + \tan x. \\ &= \int \frac{\sec^2 x + \sec x \tan x}{\sec x + \tan x} \, dx \end{aligned}$$

Letting u be the denominator of this quotient produces

$$u = \sec x + \tan x$$

and

$$u' = \sec x \tan x + \sec^2 x.$$

So, you can conclude that

$$\begin{aligned} \int \sec x \, dx &= \int \frac{\sec^2 x + \sec x \tan x}{\sec x + \tan x} \, dx && \text{Rewrite integrand.} \\ &= \int \frac{u'}{u} \, du && \text{Substitute: } u = \sec x + \tan x. \\ &= \ln|u| + C && \text{Apply Log Rule.} \\ &= \ln|\sec x + \tan x| + C. && \text{Back-substitute.} \end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

With the results of Examples 8 and 9, you now have integration formulas for $\sin x$, $\cos x$, $\tan x$, and $\sec x$. The integrals of the six basic trigonometric functions are summarized below. [The proofs of $\cot u$ and $\csc u$ are left as exercises (see Exercises 85 and 86).]

Integrals of the Six Basic Trigonometric Functions

$$\int \sin u\,du = -\cos u + C \qquad \int \cos u\,du = \sin u + C$$

$$\int \tan u\,du = -\ln|\cos u| + C \qquad \int \cot u\,du = \ln|\sin u| + C$$

$$\int \sec u\,du = \ln|\sec u + \tan u| + C \qquad \int \csc u\,du = -\ln|\csc u + \cot u| + C$$

REMARK Using trigonometric identities and properties of logarithms, you could rewrite these six integration rules in other forms. For instance, you could write

$$\int \csc u\,du = \ln|\csc u - \cot u| + C.$$

(See Exercises 87–90.)

EXAMPLE 10 Integrating a Trigonometric Function

Evaluate $\displaystyle\int_0^{\pi/4} \sqrt{1 + \tan^2 x}\,dx$.

Solution This integral does not fit any formulas on the basic list. To obtain an integrand involving only $\sec x$, use the trigonometric identity $1 + \tan^2 x = \sec^2 x$.

$$\begin{aligned}
\int_0^{\pi/4} \sqrt{1 + \tan^2 x}\,dx &= \int_0^{\pi/4} \sqrt{\sec^2 x}\,dx && \text{Apply trigonometric identity.}\\
&= \int_0^{\pi/4} \sec x\,dx && \sec x \geq 0 \text{ for } 0 \leq x \leq \frac{\pi}{4}.\\
&= \ln|\sec x + \tan x|\Big]_0^{\pi/4} && \text{Integrate.}\\
&= \ln\left(\sqrt{2} + 1\right) - \ln 1\\
&\approx 0.881.
\end{aligned}$$

EXAMPLE 11 Finding an Average Value

Find the average value of $f(x) = \tan x$ on the interval $\left[0, \frac{\pi}{4}\right]$.

Solution

$$\begin{aligned}
\text{Average value} &= \frac{1}{(\pi/4) - 0}\int_0^{\pi/4} \tan x\,dx && \text{Average value} = \frac{1}{b-a}\int_a^b f(x)\,dx\\
&= \frac{4}{\pi}\int_0^{\pi/4} \tan x\,dx && \text{Simplify.}\\
&= \frac{4}{\pi}\Big[-\ln|\cos x|\Big]_0^{\pi/4} && \text{Integrate.}\\
&= -\frac{4}{\pi}\left(\ln\frac{\sqrt{2}}{2} - \ln 1\right)\\
&= -\frac{4}{\pi}\ln\frac{\sqrt{2}}{2}\\
&\approx 0.441
\end{aligned}$$



Figure 5.8

The average value is about 0.441, as shown in Figure 5.8.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

5.2 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Can you use the Log Rule to find the integral below? Explain.

$$\int \frac{x}{(x^2 - 4)^3}\,dx$$

2. Explain when to use long division before applying the Log Rule.
3. Describe two ways to rewrite an integrand so that it fits an integration formula.
4. Integrating which trigonometric function results in $\ln|\sin x| + C$?

Finding an Indefinite Integral **In Exercises 5–28, find the indefinite integral.**

5. $\int \frac{5}{x}\,dx$
6. $\int \frac{1}{x - 5}\,dx$
7. $\int \frac{1}{2x + 5}\,dx$
8. $\int \frac{9}{5 - 4x}\,dx$
9. $\int \frac{x}{x^2 - 3}\,dx$
10. $\int \frac{x^2}{5 - x^3}\,dx$
11. $\int \frac{4x^3 + 3}{x^4 + 3x}\,dx$
12. $\int \frac{x^2 - 2x}{x^3 - 3x^2}\,dx$
13. $\int \frac{x^2 - 7}{7x}\,dx$
14. $\int \frac{x^3 - 8x}{x^2}\,dx$
15. $\int \frac{x^2 + 2x + 3}{x^3 + 3x^2 + 9x}\,dx$
16. $\int \frac{x^2 + 4x}{x^3 + 6x^2 + 5}\,dx$
17. $\int \frac{x^2 - 3x + 2}{x + 1}\,dx$
18. $\int \frac{2x^2 + 7x - 3}{x - 2}\,dx$
19. $\int \frac{x^3 - 3x^2 + 5}{x - 3}\,dx$
20. $\int \frac{x^3 - 6x - 20}{x + 5}\,dx$
21. $\int \frac{x^4 + x - 4}{x^2 + 2}\,dx$
22. $\int \frac{x^3 - 4x^2 - 4x + 20}{x^2 - 5}\,dx$
23. $\int \frac{(\ln x)^2}{x}\,dx$
24. $\int \frac{dx}{x(\ln x^2)^3}$
25. $\int \frac{1}{\sqrt{x}(1 - 3\sqrt{x})}\,dx$
26. $\int \frac{1}{x^{2/3}(1 + x^{1/3})}\,dx$
27. $\int \frac{6x}{(x - 5)^2}\,dx$
28. $\int \frac{x(x - 2)}{(x - 1)^3}\,dx$

Change of Variables **In Exercises 29–32, find the indefinite integral by making a change of variables. (*Hint:* Let u be the denominator of the integrand.)**

29. $\int \frac{1}{1 + \sqrt{2x}}\,dx$
30. $\int \frac{4}{1 + \sqrt{5x}}\,dx$
31. $\int \frac{\sqrt{x}}{\sqrt{x} - 3}\,dx$
32. $\int \frac{\sqrt[3]{x}}{\sqrt[3]{x} - 1}\,dx$

Finding an Indefinite Integral of a Trigonometric Function **In Exercises 33–42, find the indefinite integral.**

33. $\int \cot\frac{\theta}{3}\,d\theta$
34. $\int \theta \tan 2\theta^2\,d\theta$
35. $\int \csc 2x\,dx$
36. $\int \sec\frac{x}{2}\,dx$
37. $\int (5 - \cos 3\theta)\,d\theta$
38. $\int \left(2 - \tan\frac{\theta}{4}\right)d\theta$
39. $\int \frac{\cos t}{1 + \sin t}\,dt$
40. $\int \frac{\csc^2 t}{\cot t}\,dt$
41. $\int \frac{\sec x \tan x}{\sec x - 1}\,dx$
42. $\int (\sec 2x + \tan 2x)\,dx$

Differential Equation **In Exercises 43–46, find the general solution of the differential equation. Use a graphing utility to graph three solutions, one of which passes through the given point.**

43. $\frac{dy}{dx} = \frac{3}{2 - x}$, $(1, 0)$
44. $\frac{dy}{dx} = \frac{x - 2}{x}$, $(-1, 0)$
45. $\frac{dy}{dx} = \frac{2x}{x^2 - 9}$, $(0, 4)$
46. $\frac{dr}{dt} = \frac{\sec^2 t}{\tan t + 1}$, $(\pi, 4)$

Finding a Particular Solution **In Exercises 47 and 48, find the particular solution of the differential equation that satisfies the initial conditions.**

47. $f''(x) = \frac{2}{x^2}$, $f'(1) = 1$, $f(1) = 1$, $x > 0$
48. $f''(x) = -\frac{4}{(x - 1)^2} - 2$, $f'(2) = 0$, $f(2) = 3$, $x > 1$

Slope Field **In Exercises 49 and 50, a differential equation, a point, and a slope field are given. (a) Sketch two approximate solutions of the differential equation on the slope field, one of which passes through the given point. (To print an enlarged copy of the graph, go to *MathGraphs.com*.) (b) Use integration and the given point to find the particular solution of the differential equation and use a graphing utility to graph the solution. Compare the result with the sketch in part (a) that passes through the given point.**

49. $\frac{dy}{dx} = \frac{1}{x + 2}$, $(0, 1)$
50. $\frac{dy}{dx} = \frac{\ln x}{x}$, $(1, -2)$





Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Evaluating a Definite Integral **In Exercises 51–58, evaluate the definite integral. Use a graphing utility to verify your result.**

51. $\int_0^4 \frac{5}{3x+1}\,dx$

52. $\int_{-1}^1 \frac{1}{2x+3}\,dx$

53. $\int_1^e \frac{(1+\ln x)^2}{x}\,dx$

54. $\int_e^{e^2} \frac{1}{x \ln x}\,dx$

55. $\int_0^2 \frac{x^2-2}{x+1}\,dx$

56. $\int_0^1 \frac{x-1}{x+1}\,dx$

57. $\int_1^2 \frac{1-\cos\theta}{\theta-\sin\theta}\,d\theta$

58. $\int_{\pi/8}^{\pi/4} (\csc 2\theta - \cot 2\theta)\,d\theta$

Finding an Integral Using Technology **In Exercises 59 and 60, use a graphing utility to find or evaluate the integral.**

59. $\int \frac{1-\sqrt{x}}{1+\sqrt{x}}\,dx$

60. $\int_{-\pi/4}^{\pi/4} \frac{\sin^2 x - \cos^2 x}{\cos x}\,dx$

Finding a Derivative **In Exercises 61–64, find $F'(x)$.**

61. $F(x) = \int_1^x \frac{1}{t}\,dt$

62. $F(x) = \int_0^x \tan t\,dt$

63. $F(x) = \int_1^{4x} \cot t\,dt$

64. $F(x) = \int_0^{x^2} \frac{3}{t+1}\,dt$

Area **In Exercises 65–68, find the area of the given region. Use a graphing utility to verify your result.**

65. $y = \frac{6}{x}$



66. $y = \frac{1+\ln x^3}{x}$



67. $y = \csc(x+1)$



68. $y = \frac{\sin x}{1+\cos x}$



Area **In Exercises 69–72, find the area of the region bounded by the graphs of the equations. Use a graphing utility to verify your result.**

69. $y = \frac{x^2+4}{x}, \quad x = 1, \quad x = 4, \quad y = 0$

70. $y = \frac{5x}{x^2+2}, \quad x = 1, \quad x = 5, \quad y = 0$

71. $y = 2\sec\frac{\pi x}{6}, \quad x = 0, \quad x = 2, \quad y = 0$

72. $y = 2x - \tan 0.3x, \quad x = 1, \quad x = 4, \quad y = 0$

Finding the Average Value of a Function **In Exercises 73–76, find the average value of the function over the given interval.**

73. $f(x) = \frac{8}{x^2}, \quad [2, 4]$

74. $f(x) = \frac{4(x+1)}{x^2}, \quad [2, 4]$

75. $f(x) = \frac{2\ln x}{x}, \quad [1, e]$

76. $f(x) = \sec\frac{\pi x}{6}, \quad [0, 2]$

Midpoint Rule **In Exercises 77 and 78, use the Midpoint Rule with $n = 4$ to approximate the value of the definite integral. Use a graphing utility to verify your result.**

77. $\int_1^3 \frac{12}{x}\,dx$

78. $\int_0^{\pi/4} \sec x\,dx$

Exploring Concepts

In Exercises 79 and 80, determine which value best approximates the area of the region between the x-axis and the graph of the function over the given interval. Make your selection on the basis of a sketch of the region, not by performing calculations.

79. $f(x) = \sec x, \quad [0, 1]$

(a) 6 (b) -6 (c) $\frac{1}{2}$ (d) 1.25 (e) 3

80. $f(x) = \frac{2x}{x^2+1}, \quad [0, 4]$

(a) 3 (b) 7 (c) -2 (d) 5 (e) 1

81. Napier's Inequality For $0 < x < y$, use the Mean Value Theorem to show that

$$\frac{1}{y} < \frac{\ln y - \ln x}{y - x} < \frac{1}{x}.$$

82. Think About It Is the function

$$F(x) = \int_x^{2x} \frac{1}{t}\,dt$$

constant, increasing, or decreasing on the interval $(0, \infty)$? Explain.

83. Finding a Value Find a value of x such that

$$\int_1^x \frac{3}{t}\,dt = \int_{1/4}^x \frac{1}{t}\,dt.$$

84. Finding a Value Find a value of x such that

$$\int_1^x \frac{1}{t}\,dt$$

is equal to (a) $\ln 5$ and (b) 1.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

85. Proof Prove that

$$\int \cot u\, du = \ln|\sin u| + C.$$

86. Proof Prove that

$$\int \csc u\, du = -\ln|\csc u + \cot u| + C.$$

Using Properties of Logarithms and Trigonometric Identities **In Exercises 87–90, show that the two formulas are equivalent.**

87. $\int \tan x\, dx = -\ln|\cos x| + C$

$\int \tan x\, dx = \ln|\sec x| + C$

88. $\int \cot x\, dx = \ln|\sin x| + C$

$\int \cot x\, dx = -\ln|\csc x| + C$

89. $\int \sec x\, dx = \ln|\sec x + \tan x| + C$

$\int \sec x\, dx = -\ln|\sec x - \tan x| + C$

90. $\int \csc x\, dx = -\ln|\csc x + \cot x| + C$

$\int \csc x\, dx = \ln|\csc x - \cot x| + C$

91. Biology A population of bacteria P is changing at a rate of

$$\frac{dP}{dt} = \frac{3000}{1 + 0.25t}$$

where t is the time in days. The initial population (when $t = 0$) is 1000.

(a) Write an equation that gives the population at any time t.

(b) Find the population when $t = 3$ days.

92. Sales The rate of change in sales S is inversely proportional to time t ($t > 1$), measured in weeks. Find S as a function of t when the sales after 2 and 4 weeks are 200 units and 300 units, respectively.

93. Heat Transfer

Find the time required for an object to cool from 300°F to 250°F by evaluating

$$t = \frac{10}{\ln 2}\int_{250}^{300} \frac{1}{T - 100}\, dT$$

where t is time in minutes.

Benoit Daoust/Shutterstock.com

94. Average Price The demand equation for a product is

$$p = \frac{90{,}000}{400 + 3x}$$

where p is the price (in dollars) and x is the number of units (in thousands). Find the average price p on the interval $40 \le x \le 50$.

95. Area and Slope Graph the function

$$f(x) = \frac{x}{1 + x^2}$$

on the interval $[0, \infty)$.

(a) Find the area bounded by the graph of f and the line $y = \frac{1}{2}x$.

(b) Determine the values of the slope m such that the line $y = mx$ and the graph of f enclose a finite region.

(c) Calculate the area of this region as a function of m.

96. HOW DO YOU SEE IT? Use the graph of f' shown in the figure to answer the following.



(a) Approximate the slope of f at $x = -1$. Explain.

(b) Approximate any open intervals on which the graph of f is increasing and any open intervals on which it is decreasing. Explain.

True or False? **In Exercises 97–100, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

97. $\ln|x^4| = \ln x^4$

98. $\ln|\cos\theta^2| = \ln(\cos\theta^2)$

99. $\int \frac{1}{x}dx = \ln|cx|, \quad c \neq 0$

100. $\int_{-1}^{2} \frac{1}{x}dx = \left[\ln|x|\right]_{-1}^{2} = \ln 2 - \ln 1 = \ln 2$

PUTNAM EXAM CHALLENGE

101. Suppose that f is a function on the interval $[1, 3]$ such that $-1 \le f(x) \le 1$ for all x and $\int_1^3 f(x)\, dx = 0$. How large can $\int_1^3 \frac{f(x)}{x}dx$ be?

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

5.3 Inverse Functions

GO DIGITAL

- **Verify that one function is the inverse function of another function.**
- **Determine whether a function has an inverse function.**
- **Find the derivative of an inverse function.**

Inverse Functions

Recall from Section P.3 that a function can be represented by a set of ordered pairs. For instance, the function $f(x) = x + 3$ from $A = \{1, 2, 3, 4\}$ to $B = \{4, 5, 6, 7\}$ can be written as

$$f: \{(1, 4), (2, 5), (3, 6), (4, 7)\}.$$

By interchanging the first and second coordinates of each ordered pair, you can form the **inverse function** of f. This function is denoted by f^{-1}, which is read as "f inverse." It is a function from B to A and can be written as

$$f^{-1}: \{(4, 1), (5, 2), (6, 3), (7, 4)\}.$$

Note that the domain of f is equal to the range of f^{-1}, and vice versa, as shown in Figure 5.9. The functions f and f^{-1} have the effect of "undoing" each other. That is, when you form the composition of f with f^{-1} or the composition of f^{-1} with f, you obtain the identity function.

$$f(f^{-1}(x)) = x \quad \text{and} \quad f^{-1}(f(x)) = x$$



Domain of f = range of f^{-1}
Domain of f^{-1} = range of f
Figure 5.9

REMARK Although the notation used to denote an inverse function resembles *exponential notation*, it is a different use of -1 as a superscript. That is, in general,

$$f^{-1}(x) \neq \frac{1}{f(x)}.$$

Exploration

Finding Inverse Functions
Explain how to "undo" each of the functions below. Then use your explanation to write the inverse function of f.

a. $f(x) = x - 5$
b. $f(x) = 6x$
c. $f(x) = \frac{x}{2}$
d. $f(x) = 3x + 2$
e. $f(x) = x^3$
f. $f(x) = 4(x - 2)$

Use a graphing utility with a square setting to graph each function and its inverse function in the same viewing window. What observation can you make about each pair of graphs?

Definition of Inverse Function

A function g is the **inverse function** of the function f when

$$f(g(x)) = x \text{ for each } x \text{ in the domain of } g$$

and

$$g(f(x)) = x \text{ for each } x \text{ in the domain of } f.$$

The function g is denoted by f^{-1}.

Here are some important observations about inverse functions.

1. If g is the inverse function of f, then f is the inverse function of g.
2. The domain of f^{-1} is equal to the range of f, and the range of f^{-1} is equal to the domain of f.
3. A function need not have an inverse function, but when it does, the inverse function is unique (see Exercise 90).

You can think of f^{-1} as undoing what has been done by f. For example, subtraction can be used to undo addition, and division can be used to undo multiplication. So,

$$f(x) = x + c \quad \text{and} \quad f^{-1}(x) = x - c$$ Subtraction can be used to undo addition.

are inverse functions of each other and

$$f(x) = cx \quad \text{and} \quad f^{-1}(x) = \frac{x}{c}, \quad c \neq 0$$ Division can be used to undo multiplication.

are inverse functions of each other, where c is a constant.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

REMARK In Example 1, try comparing the functions f and g verbally.

For f: First cube x, then multiply by 2, then subtract 1.

For g: First add 1, then divide by 2, then take the cube root.

Do you see the "undoing pattern"?

EXAMPLE 1 Verifying Inverse Functions

Show that the functions are inverse functions of each other.

$$f(x) = 2x^3 - 1 \quad \text{and} \quad g(x) = \sqrt[3]{\frac{x+1}{2}}$$

Solution Because the domains and ranges of both f and g consist of all real numbers, you can conclude that both composite functions exist for all x. The composition of f with g is

$$\begin{aligned} f(g(x)) &= f\left(\sqrt[3]{\frac{x+1}{2}}\right) && \text{Substitute for } g(x). \\ &= 2\left(\sqrt[3]{\frac{x+1}{2}}\right)^3 - 1 && \text{Definition of } f(x) \\ &= 2\left(\frac{x+1}{2}\right) - 1 && \text{Property of radicals} \\ &= x + 1 - 1 && \text{Multiply.} \\ &= x. && \text{Simplify.} \end{aligned}$$

The composition of g with f is

$$g(f(x)) = \sqrt[3]{\frac{(2x^3 - 1) + 1}{2}} = \sqrt[3]{\frac{2x^3}{2}} = \sqrt[3]{x^3} = x.$$

Because $f(g(x)) = x$ and $g(f(x)) = x$, you can conclude that f and g are inverse functions of each other (see Figure 5.10).



f and g are inverse functions of each other.
Figure 5.10

In Figure 5.10, the graphs of f and $g = f^{-1}$ appear to be mirror images of each other with respect to the line $y = x$. The graph of f^{-1} is a **reflection** of the graph of f in the line $y = x$. This idea is generalized in the next theorem.

THEOREM 5.6 Reflective Property of Inverse Functions

The graph of f contains the point (a, b) if and only if the graph of f^{-1} contains the point (b, a).

Proof If (a, b) is on the graph of f, then $f(a) = b$, and you can write

$$f^{-1}(b) = f^{-1}(f(a)) = a.$$

So, (b, a) is on the graph of f^{-1}, as shown in Figure 5.11. A similar argument will prove the theorem in the other direction.



The graph of f^{-1} is a reflection of the graph of f in the line $y = x$.
Figure 5.11

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Existence of an Inverse Function

Not every function has an inverse function, and Theorem 5.6 suggests a graphical test for those that do—the **Horizontal Line Test** for an inverse function. This test states that a function f has an inverse function if and only if every horizontal line intersects the graph of f at most once (see Figure 5.12). The next theorem formally states why the Horizontal Line Test is valid. (Recall from Section 3.3 that a function is *strictly monotonic* when it is either increasing on its entire domain or decreasing on its entire domain.)



If a horizontal line intersects the graph of f twice, then f is not one-to-one.
Figure 5.12

THEOREM 5.7 The Existence of an Inverse Function

1. A function has an inverse function if and only if it is one-to-one.
2. If f is strictly monotonic on its entire domain, then it is one-to-one and therefore has an inverse function.

Proof The proof of the first part of the theorem is left as an exercise (see Exercise 91). To prove the second part of the theorem, recall from Section P.3 that f is one-to-one when for x_1 and x_2 in its domain

$$x_1 \neq x_2 \quad \Rightarrow \quad f(x_1) \neq f(x_2).$$

Now, choose x_1 and x_2 in the domain of f. If $x_1 \neq x_2$, then, because f is strictly monotonic, it follows that either $f(x_1) < f(x_2)$ or $f(x_1) > f(x_2)$. In either case, $f(x_1) \neq f(x_2)$. So, f is one-to-one on the interval. ■



(a) Because f is increasing over its entire domain, it has an inverse function.



(b) Because f is not one-to-one, it does not have an inverse function.
Figure 5.13

EXAMPLE 2 The Existence of an Inverse Function

a. From the graph of $f(x) = x^3 + x - 1$ shown in Figure 5.13(a), it appears that f is increasing over its entire domain. To verify this, note that the derivative, $f'(x) = 3x^2 + 1$, is positive for all real values of x. So, f is strictly monotonic, and it must have an inverse function.

b. From the graph of $f(x) = x^3 - x + 1$ shown in Figure 5.13(b), you can see that the function does not pass the Horizontal Line Test. In other words, it is not one-to-one. For instance, f has the same value when $x = -1$, 0, and 1.

$$f(-1) = f(1) = f(0) = 1 \qquad \text{Not one-to-one}$$

So, by Theorem 5.7, f does not have an inverse function. ■

Often, it is easier to prove that a function *has* an inverse function than to find the inverse function. For instance, it would be difficult algebraically to find the inverse function of the function in Example 2(a).

Guidelines for Finding an Inverse Function

1. Use Theorem 5.7 to determine whether the function $y = f(x)$ has an inverse function.
2. Solve for x as a function of y: $x = g(y) = f^{-1}(y)$.
3. Interchange x and y. The resulting equation is $y = f^{-1}(x)$.
4. Define the domain of f^{-1} as the range of f.
5. Verify that $f(f^{-1}(x)) = x$ and $f^{-1}(f(x)) = x$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The domain of f^{-1}, $[0, \infty)$, is the range of f.
Figure 5.14

GO DIGITAL

EXAMPLE 3 Finding an Inverse Function

Find the inverse function of $f(x) = \sqrt{2x - 3}$.

Solution From the graph of f in Figure 5.14, it appears that f is increasing over its entire domain, $[3/2, \infty)$. To verify this, note that

$$f'(x) = \frac{1}{\sqrt{2x - 3}} \qquad \text{Derivative of } f$$

is positive on the domain of f. So, f is strictly monotonic, and it must have an inverse function. To find an equation for the inverse function, let $y = f(x)$, and solve for x in terms of y.

$$\begin{aligned}
\sqrt{2x - 3} &= y && \text{Let } y = f(x).\\
2x - 3 &= y^2 && \text{Square each side.}\\
x &= \frac{y^2 + 3}{2} && \text{Solve for } x.\\
y &= \frac{x^2 + 3}{2} && \text{Interchange } x \text{ and } y.\\
f^{-1}(x) &= \frac{x^2 + 3}{2} && \text{Replace } y \text{ by } f^{-1}(x).
\end{aligned}$$

The domain of f^{-1} is the range of f, which is $[0, \infty)$. You can verify this result as shown.

$$f(f^{-1}(x)) = \sqrt{2\left(\frac{x^2 + 3}{2}\right) - 3} = \sqrt{x^2} = x, \quad x \geq 0$$

$$f^{-1}(f(x)) = \frac{\left(\sqrt{2x - 3}\right)^2 + 3}{2} = \frac{2x - 3 + 3}{2} = x, \quad x \geq \frac{3}{2}$$

Theorem 5.7 is useful in the next type of problem. You are given a function that is *not* one-to-one on its domain. By restricting the domain to an interval on which the function is strictly monotonic, you can conclude that the new function *is* one-to-one on the restricted domain.

EXAMPLE 4 Testing Whether a Function Is One-to-One

See LarsonCalculus.com for an interactive version of this type of example.

Show that the sine function

$$f(x) = \sin x$$

is not one-to-one on the entire real number line. Then show that $[-\pi/2, \pi/2]$ is the largest interval, centered at the origin, on which f is strictly monotonic.

Solution It is clear that f is not one-to-one, because many different x-values yield the same y-value. For instance,

$$\sin 0 = 0 = \sin \pi.$$

Moreover, f is increasing on the open interval $(-\pi/2, \pi/2)$, because its derivative

$$f'(x) = \cos x$$

is positive there. Finally, because the left and right endpoints correspond to relative extrema of the sine function, you can conclude that f is increasing on the closed interval $[-\pi/2, \pi/2]$ *and* that on any larger interval the function is not strictly monotonic (see Figure 5.15).



f is one-to-one on the interval $[-\pi/2, \pi/2]$.
Figure 5.15

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Derivative of an Inverse Function

The next two theorems discuss the derivative of an inverse function. The reasonableness of Theorem 5.8 follows from the reflective property of inverse functions, as shown in Figure 5.11.

THEOREM 5.8 Continuity and Differentiability of Inverse Functions

Let f be a function whose domain is an interval I. If f has an inverse function, then the following statements are true.

1. If f is continuous on its domain, then f^{-1} is continuous on its domain.
2. If f is increasing on its domain, then f^{-1} is increasing on its domain.
3. If f is decreasing on its domain, then f^{-1} is decreasing on its domain.
4. If f is differentiable on an interval containing c and $f'(c) \neq 0$, then f^{-1} is differentiable at $f(c)$.

A proof of this theorem is given in Appendix A.

Exploration

Graph the inverse functions $f(x) = x^3$ and $g(x) = x^{1/3}$. Calculate the slopes of f at (1, 1), (2, 8), and (3, 27), and the slopes of g at (1, 1), (8, 2), and (27, 3). What do you observe? What happens at (0, 0)?

THEOREM 5.9 The Derivative of an Inverse Function

Let f be a function that is differentiable on an interval I. If f has an inverse function g, then g is differentiable at any x for which $f'(g(x)) \neq 0$. Moreover,

$$g'(x) = \frac{1}{f'(g(x))}, \quad f'(g(x)) \neq 0.$$

A proof of this theorem is given in Appendix A.

EXAMPLE 5 Evaluating the Derivative of an Inverse Function

Let $f(x) = \frac{1}{4}x^3 + x - 1$, where $f(2) = 3$. Without writing a formula for $f^{-1}(x)$, find (a) $f^{-1}(3)$ and (b) $(f^{-1})'(3)$.

Solution Notice that the derivative, $f'(x) = (3/4)x^2 + 1$, is positive for all real values of x. So, f is strictly monotonic and must have an inverse function.

a. Because $f(2) = 3$, you know that $f^{-1}(3) = 2$.

b. Because the function f is differentiable and has an inverse function, you can apply Theorem 5.9 (with $g = f^{-1}$) to write

$$(f^{-1})'(3) = \frac{1}{f'(f^{-1}(3))} = \frac{1}{f'(2)}.$$

Moreover, using $f'(x) = (3/4)x^2 + 1$, you can conclude that

$$(f^{-1})'(3) = \frac{1}{f'(2)} = \frac{1}{(3/4)(2^2) + 1} = \frac{1}{4}.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The graphs of the inverse functions f and f^{-1} have reciprocal slopes at points (a, b) and (b, a).
Figure 5.16

In Example 5, note that at the point $(2, 3)$, the slope of the graph of f is $m = 4$, and at the point $(3, 2)$, the slope of the graph of f^{-1} is

$$m = \frac{1}{4}.$$ Slope of the graph of f^{-1} at $(3, 2)$

(See Figure 5.16.) In general, if $y = g(x) = f^{-1}(x)$, then $f(y) = x$ and $f'(y) = dx/dy$. It follows from Theorem 5.9 that

$$g'(x) = \frac{dy}{dx} = \frac{1}{f'(g(x))} = \frac{1}{f'(y)} = \frac{1}{(dx/dy)}.$$

This reciprocal relationship is sometimes written in Leibniz notation as

$$\frac{dy}{dx} = \frac{1}{dx/dy}.$$

EXAMPLE 6 Graphs of Inverse Functions Have Reciprocal Slopes

Let $f(x) = x^2$ (for $x \geq 0$), and let $f^{-1}(x) = \sqrt{x}$. Show that the slopes of the graphs of f and f^{-1} are reciprocals at each pair of points.

a. $(2, 4)$ and $(4, 2)$ **b.** $(3, 9)$ and $(9, 3)$

Solution The derivatives of f and f^{-1} are

$$f'(x) = 2x \quad \text{and} \quad (f^{-1})'(x) = \frac{1}{2\sqrt{x}}.$$ Find the derivatives of f and f^{-1}.

a. At $(2, 4)$, the slope of the graph of f is $f'(2) = 2(2) = 4$. At $(4, 2)$, the slope of the graph of f^{-1} is

$$(f^{-1})'(4) = \frac{1}{2\sqrt{4}} = \frac{1}{2(2)} = \frac{1}{4}.$$ Slope of the graph of f^{-1} at $(4, 2)$

b. At $(3, 9)$, the slope of the graph of f is $f'(3) = 2(3) = 6$. At $(9, 3)$, the slope of the graph of f^{-1} is

$$(f^{-1})'(9) = \frac{1}{2\sqrt{9}} = \frac{1}{2(3)} = \frac{1}{6}.$$ Slope of the graph of f^{-1} at $(9, 3)$

So, in both cases, the slopes of the graphs of f and f^{-1} are reciprocals, as shown in the figure below.



At $(0, 0)$, the derivative of f is 0, and the derivative of f^{-1} does not exist.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

5.3 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe what it means to say that the function g is the inverse function of the function f.
2. Describe the relationship between the graph of a function and the graph of its inverse function.
3. The function f has an inverse function, f^{-1}. Is the domain of f the same as the domain of f^{-1}? Explain.
4. The function f is decreasing on its domain and has an inverse function, f^{-1}. Is f^{-1} increasing, decreasing, or constant on its domain?

Verifying Inverse Functions **In Exercises 5–12, show that f and g are inverse functions (a) analytically and (b) graphically.**

5. $f(x) = 5x + 1$, $g(x) = \dfrac{x - 1}{5}$
6. $f(x) = 3 - 4x$, $g(x) = \dfrac{3 - x}{4}$
7. $f(x) = x^3$, $g(x) = \sqrt[3]{x}$
8. $f(x) = 1 - x^3$, $g(x) = \sqrt[3]{1 - x}$
9. $f(x) = \sqrt{x - 4}$, $g(x) = x^2 + 4, \quad x \geq 0$
10. $f(x) = 16 - x^2, \quad x \geq 0$, $g(x) = \sqrt{16 - x}$
11. $f(x) = \dfrac{1}{x}$, $g(x) = \dfrac{1}{x}$
12. $f(x) = \dfrac{1}{1 + x}, \quad x \geq 0$, $g(x) = \dfrac{1 - x}{x}, \quad 0 < x \leq 1$

Using the Horizontal Line Test **In Exercises 13–22, use a graphing utility to graph the function. Then use the Horizontal Line Test to determine whether the function is one-to-one on its entire domain and therefore has an inverse function.**

13. $f(x) = \frac{3}{4}x + 6$
14. $f(x) = 1 - x^3$
15. $f(\theta) = \sin\theta$
16. $f(x) = x\cos x$
17. $h(s) = \dfrac{1}{s - 2} - 3$
18. $g(t) = \dfrac{1}{\sqrt{t^2 + 1}}$
19. $f(x) = 5x\sqrt{x - 1}$
20. $g(x) = (x + 5)^3$
21. $f(x) = \ln x$
22. $h(x) = \ln x^2$

Determining Whether a Function Has an Inverse Function **In Exercises 23–28, use the derivative to determine whether the function is strictly monotonic on its entire domain and therefore has an inverse function.**

23. $f(x) = 2 - x - x^3$
24. $f(x) = x^3 - 6x^2 + 12x$
25. $f(x) = 8x^3 + x^2 - 1$
26. $f(x) = 1 - x^3 - 6x^5$
27. $f(x) = \ln(x - 3)$
28. $f(x) = \cos\dfrac{3x}{2}$

Matching **In Exercises 29–32, match the graph of the function with the graph of its inverse function. [The graphs of the inverse functions are labeled (a), (b), (c), and (d).]**

(a)



(b)



(c)



(d)



29.



30.



31.



32.



Verifying a Function Has an Inverse Function **In Exercises 33–38, show that f is strictly monotonic on the given interval and therefore has an inverse function on that interval.**

33. $f(x) = (x - 4)^2, \quad [4, \infty)$
34. $f(x) = |x + 2|, \quad [-2, \infty)$
35. $f(x) = \cot x, \quad (0, \pi)$
36. $f(x) = \dfrac{4}{x^2}, \quad (0, \infty)$
37. $f(x) = \cos x, \quad [0, \pi]$
38. $f(x) = \sec x, \quad \left[0, \dfrac{\pi}{2}\right)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding an Inverse Function **In Exercises 39–50, (a) find the inverse function of f, (b) graph f and f^{-1} on the same set of coordinate axes, (c) describe the relationship between the graphs, and (d) state the domains and ranges of f and f^{-1}.**

39. $f(x) = 2x - 3$

40. $f(x) = 9 - 5x$

41. $f(x) = x^5$

42. $f(x) = x^3 - 1$

43. $f(x) = \sqrt{x}$

44. $f(x) = x^4, \quad x \geq 0$

45. $f(x) = \sqrt{4 - x^2}, \quad 0 \leq x \leq 2$

46. $f(x) = \sqrt{x^2 - 4}, \quad x \geq 2$

47. $f(x) = \sqrt[3]{x - 1}$

48. $f(x) = x^{2/3}, \quad x \geq 0$

49. $f(x) = \dfrac{x}{\sqrt{x^2 + 7}}$

50. $f(x) = \dfrac{x + 2}{x}$

Finding an Inverse Function **In Exercises 51 and 52, use the graph of the function f to make a table of values for the given points. Then make a second table that can be used to find f^{-1} and sketch the graph of f^{-1}. To print an enlarged copy of the graph, go to *MathGraphs.com*.**

51.



52.



53. Cost You need a total of 50 pounds of two commodities costing \$1.25 and \$2.75 per pound.

(a) Verify that the total cost is $y = 1.25x + 2.75(50 - x)$, where x is the number of pounds of the less expensive commodity.

(b) Find the inverse function of the cost function. What does each variable represent in the inverse function?

(c) What is the domain of the inverse function? Validate or explain your answer using the context of the problem.

(d) Determine the number of pounds of the less expensive commodity purchased when the total cost is \$73.

54. Temperature The formula $C = \frac{5}{9}(F - 32)$, where $F \geq -459.6$, represents Celsius temperature C as a function of Fahrenheit temperature F.

(a) Find the inverse function of C.

(b) What does the inverse function represent?

(c) What is the domain of the inverse function? Validate or explain your answer using the context of the problem.

(d) The temperature is 22°C. What is the corresponding temperature in degrees Fahrenheit?

Testing Whether a Function Is One-to-One **In Exercises 55–58, determine whether the function is one-to-one. If it is, find its inverse function.**

55. $f(x) = \sqrt{x - 2}$

56. $f(x) = -3$

57. $f(x) = |x - 2|, \quad x \leq 2$

58. $f(x) = ax + b, \quad a \neq 0$

Making a Function One-to-One **In Exercises 59–62, the function is not one-to-one. Delete part of the domain so that the function that remains is one-to-one. Find the inverse function of the remaining function and give the domain of the inverse function. (*Note:* There is more than one correct answer.)**

59. $f(x) = (x - 3)^2$



60. $f(x) = |x - 3|$



61. $f(x) = |x + 3|$



62. $f(x) = 16 - x^4$



Think About It **In Exercises 63–66, decide whether the function has an inverse function. If so, describe what the inverse function represents.**

63. $g(t)$ is the volume of water that has passed through a water line t minutes after a control valve is opened.

64. $h(t)$ is the height of the tide t hours after midnight, where $0 \leq t < 24$.

65. $C(t)$ is the cost of a long-distance phone call lasting t minutes.

66. $A(r)$ is the area of a circle of radius r.

Evaluating the Derivative of an Inverse Function **In Exercises 67–72, verify that f has an inverse function. Then use the function f and the given function value $f(x) = a$ to find $(f^{-1})'(a)$. (*Hint:* See Example 5.)**

67. $f(x) = 5 - 2x^3, \quad f(-1) = 7$

68. $f(x) = \frac{1}{27}(x^5 + 2x^3), \quad f(-3) = -11$

69. $f(x) = \sqrt{x - 4}, \quad f(8) = 2$

70. $f(x) = \sin x, \quad -\dfrac{\pi}{2} \leq x \leq \dfrac{\pi}{2}, \quad f\left(\dfrac{\pi}{6}\right) = \dfrac{1}{2}$

71. $f(x) = \cos 2x, \quad 0 \leq x \leq \dfrac{\pi}{2}, \quad f(0) = 1$

72. $f(x) = \dfrac{x + 6}{x - 2}, \quad x > 2, \quad f(6) = 3$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Using Inverse Functions **In Exercises 73–76, (a) find the domains of f and f^{-1}, (b) find the ranges of f and f^{-1}, (c) graph f and f^{-1}, and (d) show that the slopes of the graphs of f and f^{-1} are reciprocals at the given points.**

Functions	Point
73. $f(x) = x^3$	$\left(\frac{1}{2}, \frac{1}{8}\right)$
$f^{-1}(x) = \sqrt[3]{x}$	$\left(\frac{1}{8}, \frac{1}{2}\right)$
74. $f(x) = 3 - 4x$	$(1, -1)$
$f^{-1}(x) = \dfrac{3 - x}{4}$	$(-1, 1)$
75. $f(x) = \sqrt{x - 4}$	$(5, 1)$
$f^{-1}(x) = x^2 + 4, \quad x \geq 0$	$(1, 5)$
76. $f(x) = \dfrac{4}{1 + x^2}, \quad x \geq 0$	$(1, 2)$
$f^{-1}(x) = \sqrt{\dfrac{4 - x}{x}}$	$(2, 1)$

Using Composite and Inverse Functions **In Exercises 77–80, use the functions $f(x) = \frac{1}{8}x - 3$ and $g(x) = x^3$ to find the given value or function.**

77. $(f^{-1} \circ g^{-1})(1)$ **78.** $(g^{-1} \circ g^{-1})(8)$

79. $g^{-1} \circ f^{-1}$ **80.** $(f \circ g)^{-1}$

Exploring Concepts

81. Consider the function $f(x) = x^n$, where n is odd. Does f^{-1} exist? Explain.

82. Does adding a constant term to a function affect the existence of an inverse function? Explain.

In Exercises 83 and 84, the derivative of the function has the same sign for all x in its domain, but the function is not one-to-one. Explain why the function is not one-to-one.

83. $f(x) = \tan x$ **84.** $f(x) = \dfrac{x}{x^2 - 4}$

True or False? **In Exercises 85 and 86, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

85. If f is an even function, then f^{-1} exists.

86. If the inverse function of f exists, then the y-intercept of f is an x-intercept of f^{-1}.

87. Making a Function One-to-One

(a) Show that $f(x) = 2x^3 + 3x^2 - 36x$ is not one-to-one on $(-\infty, \infty)$.

(b) Determine the greatest value c such that f is one-to-one on $(-c, c)$.

88. Proof Let f and g be one-to-one functions. Prove that

(a) $f \circ g$ is one-to-one.

(b) $(f \circ g)^{-1}(x) = (g^{-1} \circ f^{-1})(x)$.

89. Proof Prove that if f has an inverse function, then $(f^{-1})^{-1} = f$.

90. Proof Prove that if a function has an inverse function, then the inverse function is unique.

91. Proof Prove that a function has an inverse function if and only if it is one-to-one.

92. HOW DO YOU SEE IT? Use the information in the graph of f below.



(a) What is the slope of the tangent line to the graph of f^{-1} at the point $\left(-\frac{1}{2}, -1\right)$? Explain.

(b) What is the slope of the tangent line to the graph of f^{-1} at the point $(1, 2)$? Explain.

93. Inverse Function Let

$$f(x) = \frac{x - 2}{x - 1}.$$

Show that f is its own inverse function. What can you conclude about the graph of f? Explain.

94. Using Theorem 5.7 Is the converse of the second part of Theorem 5.7 true? That is, if a function is one-to-one (and therefore has an inverse function), then must the function be strictly monotonic? If so, prove it. If not, give a counterexample.

95. Derivative of an Inverse Function Show that

$$f(x) = \int_2^x \sqrt{1 + t^2}\, dt$$

is one-to-one and find $(f^{-1})'(0)$.

96. Derivative of an Inverse Function Show that

$$f(x) = \int_2^x \frac{dt}{\sqrt{1 + t^4}}$$

is one-to-one and find $(f^{-1})'(0)$.

97. Concavity Let f be twice-differentiable and one-to-one on an open interval I. Show that its inverse function g satisfies

$$g''(x) = -\frac{f''(g(x))}{[f'(g(x))]^3}.$$

When f is increasing and concave downward, what is the concavity of g?

98. Using a Function Let $f(x) = \dfrac{ax + b}{cx + d}$.

(a) Show that f is one-to-one if and only if $bc - ad \neq 0$.

(b) Given $bc - ad \neq 0$, find f^{-1}.

(c) Determine the values of a, b, c, and d such that $f = f^{-1}$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

5.4 Exponential Functions: Differentiation and Integration

GO DIGITAL

- **Develop properties of the natural exponential function.**
- **Differentiate natural exponential functions.**
- **Integrate natural exponential functions.**

The Natural Exponential Function

The function $f(x) = \ln x$ is increasing on its entire domain, and therefore it has an inverse function f^{-1}. The domain of f^{-1} is the set of all real numbers, and the range is the set of positive real numbers, as shown in Figure 5.17. So, for any real number x,

$$f(f^{-1}(x)) = \ln[f^{-1}(x)] = x. \qquad x \text{ is any real number.}$$

If x is rational, then

$$\ln(e^x) = x \ln e = x(1) = x. \qquad x \text{ is a rational number.}$$

Because the natural logarithmic function is one-to-one, you can conclude that $f^{-1}(x)$ and e^x agree for *rational* values of x. The next definition extends the meaning of e^x to include *all* real values of x.



The inverse function of the natural logarithmic function is the natural exponential function.

Figure 5.17

Definition of the Natural Exponential Function

The inverse function of the natural logarithmic function $f(x) = \ln x$ is called the **natural exponential function** and is denoted by

$$f^{-1}(x) = e^x.$$

That is, $y = e^x$ if and only if $x = \ln y$.

The inverse relationship between the natural logarithmic function and the natural exponential function can be summarized as shown.

$$\ln(e^x) = x \quad \text{and} \quad e^{\ln x} = x \qquad \text{Inverse relationship}$$

EXAMPLE 1 Solving an Exponential Equation

Solve $7 = e^{x+1}$.

Solution You can convert from exponential form to logarithmic form by *taking the natural logarithm of each side* of the equation.

$$\begin{aligned} 7 &= e^{x+1} && \text{Write original equation.} \\ \ln 7 &= \ln(e^{x+1}) && \text{Take natural logarithm of each side.} \\ \ln 7 &= x + 1 && \text{Apply inverse property.} \\ -1 + \ln 7 &= x && \text{Solve for } x. \end{aligned}$$

So, the solution is $-1 + \ln 7 \approx 0.946$. Figure 5.18, which shows the graphs of the left and right sides of the original equation, supports this result. An algebraic check of the answer is shown below.

$$\begin{aligned} 7 &= e^{x+1} && \text{Write original equation.} \\ 7 &\stackrel{?}{=} e^{(-1+\ln 7)+1} && \text{Substitute } -1 + \ln 7 \text{ for } x \text{ in original equation.} \\ 7 &\stackrel{?}{=} e^{\ln 7} && \text{Simplify.} \\ 7 &= 7 \ \checkmark && \text{Solution checks.} \end{aligned}$$



Figure 5.18

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

TECHNOLOGY

You can use a graphing utility to check a solution of an equation. One way to do this is to graph the left and right sides of the equation and then use the *intersect* feature. For instance, to check the solution to Example 2, enter $y_1 = \ln(2x - 3)$ and $y_2 = 5$. The solution of the original equation is the x-value of each point of intersection (see figure). So the solution of the original equation is $x \approx 75.707$.



EXAMPLE 2 Solving a Logarithmic Equation

Solve $\ln(2x - 3) = 5$.

Solution To convert from logarithmic form to exponential form, you can *exponentiate each side* of the logarithmic equation.

$$\ln(2x - 3) = 5 \qquad \text{Write original equation.}$$
$$e^{\ln(2x-3)} = e^5 \qquad \text{Exponentiate each side.}$$
$$2x - 3 = e^5 \qquad \text{Apply inverse property.}$$
$$x = \tfrac{1}{2}(e^5 + 3) \qquad \text{Solve for } x.$$
$$x \approx 75.707 \qquad \text{Use a calculator.}$$

The familiar rules for operating with rational exponents can be extended to the natural exponential function, as shown in the next theorem.

THEOREM 5.10 Operations with Exponential Functions

Let a and b be any real numbers.

1. $e^a e^b = e^{a+b}$
2. $\dfrac{e^a}{e^b} = e^{a-b}$

Proof To prove Property 1, consider $\ln(e^a e^b)$. Use Theorem 5.2 to write

$$\ln(e^a e^b) = \ln(e^a) + \ln(e^b) = a + b = \ln(e^{a+b}).$$

Because the natural logarithmic function is one-to-one, you can conclude that

$$e^a e^b = e^{a+b}.$$

The proof of the other property is given in Appendix A.

In Section 5.3, you learned that an inverse function f^{-1} shares many properties with f. So, the natural exponential function inherits the properties listed below from the natural logarithmic function.

Properties of the Natural Exponential Function

1. The domain of $f(x) = e^x$ is
   $$(-\infty, \infty)$$
   and the range is
   $$(0, \infty).$$
2. The function $f(x) = e^x$ is continuous, increasing, and one-to-one on its entire domain.
3. The graph of $f(x) = e^x$ is concave upward on its entire domain.
4. $\lim_{x \to -\infty} e^x = 0$
5. $\lim_{x \to \infty} e^x = \infty$



The natural exponential function is increasing, and its graph is concave upward.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Derivatives of Exponential Functions

One of the most intriguing (and useful) characteristics of the natural exponential function is that *it is its own derivative*. In other words, it is a solution of the differential equation $y' = y$. This result is stated in the next theorem.

REMARK You can interpret this theorem geometrically by saying that the slope of the graph of $f(x) = e^x$ at any point (x, e^x) is equal to the y-coordinate of the point.

THEOREM 5.11 Derivatives of the Natural Exponential Function

Let u be a differentiable function of x.

1. $\dfrac{d}{dx}[e^x] = e^x$
2. $\dfrac{d}{dx}[e^u] = e^u \dfrac{du}{dx}$

Proof To prove the first part of this theorem, use the fact that $\ln e^x = x$ and differentiate each side of the equation.

$$\ln e^x = x \qquad \text{Definition of exponential function}$$

$$\frac{d}{dx}[\ln e^x] = \frac{d}{dx}[x] \qquad \text{Differentiate each side with respect to } x.$$

$$\frac{1}{e^x}\frac{d}{dx}[e^x] = 1 \qquad \frac{d}{dx}[\ln u] = \frac{1}{u}\frac{du}{dx}$$

$$\frac{d}{dx}[e^x] = e^x \qquad \text{Multiply each side by } e^x.$$

The derivative of e^u follows from the Chain Rule. ∎

EXAMPLE 3 Differentiating Exponential Functions

a. $\dfrac{d}{dx}[e^{2x-1}] = e^u \dfrac{du}{dx} = 2e^{2x-1}$ $\qquad u = 2x - 1$

b. $\dfrac{d}{dx}[e^{-3/x}] = e^u \dfrac{du}{dx} = \left(\dfrac{3}{x^2}\right)e^{-3/x} = \dfrac{3e^{-3/x}}{x^2}$ $\qquad u = -\dfrac{3}{x}$

c. $\dfrac{d}{dx}[x^2e^x] = x^2(e^x) + e^x(2x) = xe^x(x + 2)$ $\qquad$ Product Rule and Theorem 5.11

d. $\dfrac{d}{dx}\left[\dfrac{e^{3x}}{e^x + 1}\right] = \dfrac{(e^x + 1)(3e^{3x}) - e^{3x}(e^x)}{(e^x + 1)^2} = \dfrac{3e^{4x} + 3e^{3x} - e^{4x}}{(e^x + 1)^2} = \dfrac{e^{3x}(2e^x + 3)}{(e^x + 1)^2}$

EXAMPLE 4 Locating Relative Extrema

Find the relative extrema of

$$f(x) = xe^x.$$

Solution The derivative of f is

$$f'(x) = x(e^x) + e^x(1) \qquad \text{Product Rule}$$

$$= e^x(x + 1). \qquad \text{Factor.}$$

Because e^x is never 0, the derivative is 0 only when $x = -1$. Moreover, by the First Derivative Test, you can determine that $x = -1$ corresponds to a relative minimum, as shown in Figure 5.19. Because the derivative $f'(x) = e^x(x + 1)$ is defined for all x, there are no other critical points. ∎



The derivative of f changes from negative to positive at $x = -1$.
Figure 5.19

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



Figure 5.20

EXAMPLE 5 Finding an Equation of a Tangent Line

Find an equation of the tangent line to the graph of $f(x) = 2 + e^{1-x}$ at the point $(1, 3)$.

Solution Begin by finding $f'(x)$.

$$f(x) = 2 + e^{1-x}$$ Write original function.

$$f'(x) = e^{1-x}(-1)$$ $u = 1 - x$

$$= -e^{1-x}$$ First derivative

To find the slope of the tangent line at $(1, 3)$, evaluate $f'(1)$.

$$f'(1) = -e^{1-1} = -e^0 = -1$$ Slope of tangent line at $(1, 3)$

Now, use the point-slope form of the equation of a line to write

$$y - y_1 = m(x - x_1)$$ Point-slope form

$$y - 3 = -1(x - 1)$$ Substitute for y_1, m, and x_1.

$$y = -x + 4.$$ Equation of tangent line at $(1, 3)$

The graph of f and its tangent line at $(1, 3)$ are shown in Figure 5.20.

EXAMPLE 6 The Standard Normal Probability Density Function

See LarsonCalculus.com for an interactive version of this type of example.

Show that the *standard normal probability density function*

$$f(x) = \frac{1}{\sqrt{2\pi}}e^{-x^2/2}$$

has points of inflection when $x = \pm 1$.

Solution To locate possible points of inflection, find the x-values for which the second derivative is 0.

$$f(x) = \frac{1}{\sqrt{2\pi}}e^{-x^2/2}$$ Write original function.

$$f'(x) = \frac{1}{\sqrt{2\pi}}(-x)e^{-x^2/2}$$ First derivative

$$f''(x) = \frac{1}{\sqrt{2\pi}}[(-x)(-x)e^{-x^2/2} + (-1)e^{-x^2/2}]$$ Product Rule

$$= \frac{1}{\sqrt{2\pi}}(e^{-x^2/2})(x^2 - 1)$$ Second derivative

So, $f''(x) = 0$ when $x = \pm 1$, and you can apply the techniques of Chapter 3 to conclude that these values yield the two points of inflection shown in the figure below.



The bell-shaped curve given by the standard normal probability density function

REMARK The general form of a normal probability density function (whose mean is 0) is

$$f(x) = \frac{1}{\sigma\sqrt{2\pi}}e^{-x^2/(2\sigma^2)}$$

where σ is the standard deviation (σ is the lowercase Greek letter sigma). This "bell-shaped curve" has points of inflection when $x = \pm\sigma$.

FOR FURTHER INFORMATION To learn about derivatives of exponential functions of order 1/2, see the article "A Child's Garden of Fractional Derivatives" by Marcia Kleinz and Thomas J. Osler in *The College Mathematics Journal*. To view this article, go to *MathArticles.com*.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Integrals of Exponential Functions

Each differentiation formula in Theorem 5.11 has a corresponding integration formula.

THEOREM 5.12 Integration Rules for Exponential Functions

Let u be a differentiable function of x.

1. $\int e^x\,dx = e^x + C$
2. $\int e^u\,du = e^u + C$

EXAMPLE 7 Integrating Exponential Functions

Find $\int e^{3x+1}\,dx$.

Solution If you let $u = 3x + 1$, then $du = 3\,dx$. To introduce the missing factor of 3 in the integrand, multiply and divide by 3.

$$\int e^{3x+1}\,dx = \frac{1}{3}\int e^{3x+1}(3)\,dx \qquad \text{Multiply and divide by 3.}$$

$$= \frac{1}{3}\int e^u\,du \qquad \text{Substitute: } u = 3x + 1.$$

$$= \frac{1}{3}e^u + C \qquad \text{Apply Exponential Rule.}$$

$$= \frac{e^{3x+1}}{3} + C \qquad \text{Back-substitute.}$$

REMARK In Example 7, the missing *constant* factor 3 was introduced to create $du = 3\,dx$. Remember, however, that you cannot introduce a missing *variable* factor in the integrand. For instance,

$$\int e^{-x^2}\,dx \neq \frac{1}{x}\int e^{-x^2}(x\,dx).$$

EXAMPLE 8 Integrating Exponential Functions

Find the indefinite integral.

$$\int 5xe^{-x^2}\,dx$$

Solution If you let $u = -x^2$, then $du = -2x\,dx$ or $x\,dx = -du/2$.

$$\int 5xe^{-x^2}\,dx = \int 5e^{-x^2}(x\,dx) \qquad \text{Regroup integrand.}$$

$$= \int 5e^u\left(-\frac{du}{2}\right) \qquad \text{Substitute: } u = -x^2.$$

$$= -\frac{5}{2}\int e^u\,du \qquad \text{Constant Multiple Rule}$$

$$= -\frac{5}{2}e^u + C \qquad \text{Apply Exponential Rule.}$$

$$= -\frac{5}{2}e^{-x^2} + C \qquad \text{Back-substitute.}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 9 Integrating Exponential Functions

Find each indefinite integral.

a. $\int \frac{e^{1/x}}{x^2}\,dx$ **b.** $\int \sin x\, e^{\cos x}\,dx$

Solution

a. $\int \frac{e^{1/x}}{x^2}\,dx = -\int \overbrace{e^{1/x}}^{e^u}\overbrace{\left(-\frac{1}{x^2}\right)\,dx}^{du}$ $u = \frac{1}{x}$

$= -e^{1/x} + C$

b. $\int \sin x\, e^{\cos x}\,dx = -\int \overbrace{e^{\cos x}}^{e^u}\overbrace{(-\sin x)\,dx}^{du}$ $u = \cos x$

$= -e^{\cos x} + C$

EXAMPLE 10 Finding Areas Bounded by Exponential Functions

Evaluate each definite integral.

a. $\int_0^1 e^{-x}\,dx$ **b.** $\int_0^1 \frac{e^x}{1+e^x}\,dx$ **c.** $\int_{-1}^0 e^x \cos(e^x)\,dx$

Solution

a. $\int_0^1 e^{-x}\,dx = -e^{-x}\Big]_0^1$ See Figure 5.21(a).

$= -e^{-1} - (-1)$

$= 1 - \frac{1}{e}$

≈ 0.632

b. $\int_0^1 \frac{e^x}{1+e^x}\,dx = \ln(1+e^x)\Big]_0^1$ See Figure 5.21(b).

$= \ln(1+e) - \ln 2$

≈ 0.620

c. $\int_{-1}^0 e^x \cos(e^x)\,dx = \sin(e^x)\Big]_{-1}^0$ See Figure 5.21(c).

$= \sin 1 - \sin(e^{-1})$

≈ 0.482

REMARK In Example 10, the integration rules

$$\int \frac{du}{u} = \ln|u| + C$$

$$\int \cos u\,du = \sin u + C$$

and

$$\int e^u\,du = e^u + C$$

were used to solve parts (a)–(c). In each case, what value of u was used?



(a) **(b)** **(c)**

Figure 5.21

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

5.4 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe the graph of $f(x) = e^x$.
2. Which of the following functions are their own derivative?
   $y = e^x + 4$ $\quad y = e^x$ $\quad y = e^{4x}$ $\quad y = 4e^x$

Solving an Exponential or Logarithmic Equation In Exercises 3–18, solve for x accurate to three decimal places.

3. $e^{\ln x} = 4$
4. $e^{\ln 3x} = 24$
5. $e^x = 12$
6. $5e^x = 36$
7. $9 - 2e^x = 7$
8. $8e^x - 12 = 7$
9. $50e^{-x} = 30$
10. $100e^{-2x} = 35$
11. $\dfrac{800}{100 - e^{x/2}} = 50$
12. $\dfrac{5000}{1 + e^{2x}} = 2$
13. $\ln x = 2$
14. $\ln x^2 = -8$
15. $\ln(x - 3) = 2$
16. $\ln 4x = 1$
17. $\ln\sqrt{x + 2} = 1$
18. $\ln(x - 2)^2 = 12$

Sketching a Graph In Exercises 19–24, sketch the graph of the function.

19. $y = e^{-x}$
20. $y = \frac{1}{3}e^x$
21. $y = e^x + 1$
22. $y = -e^{x-1}$
23. $y = e^{-x^2}$
24. $y = e^{-x/2}$

Matching In Exercises 25–28, match the equation with the correct graph. Assume that a and C are positive real numbers. [The graphs are labeled (a), (b), (c), and (d).]

(a)



(b)



(c)



(d)



25. $y = Ce^{ax}$
26. $y = Ce^{-ax}$
27. $y = C(1 - e^{-ax})$
28. $y = \dfrac{C}{1 + e^{-ax}}$

Inverse Functions In Exercises 29–32, illustrate that the functions are inverse functions of each other by sketching their graphs on the same set of coordinate axes.

29. $f(x) = e^{2x}$, $g(x) = \ln\sqrt{x}$
30. $f(x) = e^{x/3}$, $g(x) = \ln x^3$
31. $f(x) = e^x - 1$, $g(x) = \ln(x + 1)$
32. $f(x) = e^{x-1}$, $g(x) = 1 + \ln x$

Finding a Derivative In Exercises 33–54, find the derivative of the function.

33. $y = e^{5x}$
34. $y = e^{-8x}$
35. $y = e^{\sqrt{x}}$
36. $y = e^{-2x^3}$
37. $y = e^{x-4}$
38. $y = 5e^{x^2+5}$
39. $y = e^x \ln x$
40. $y = xe^{4x}$
41. $y = (x + 1)^2e^x$
42. $y = x^2e^{-x}$
43. $g(t) = (e^{-t} + e^t)^3$
44. $g(t) = e^{-3/t^2}$
45. $y = \ln(2 - e^{5x})$
46. $y = \ln\left(\dfrac{1 + e^x}{1 - e^x}\right)$
47. $y = \dfrac{2}{e^x + e^{-x}}$
48. $y = \dfrac{e^x - e^{-x}}{2}$
49. $y = \dfrac{e^x + 1}{e^x - 1}$
50. $y = \dfrac{e^{2x}}{e^{2x} + 1}$
51. $y = e^x(\sin x + \cos x)$
52. $y = e^{2x}\tan 2x$
53. $F(x) = \displaystyle\int_{\pi}^{\ln x} \cos e^t\, dt$
54. $F(x) = \displaystyle\int_{0}^{e^{2x}} \ln(t + 1)\, dt$

Finding an Equation of a Tangent Line In Exercises 55–62, find an equation of the tangent line to the graph of the function at the given point.

55. $f(x) = e^{3x}$, $(0, 1)$
56. $f(x) = e^{-x} - 6$, $(0, -5)$
57. $y = e^{3x-x^2}$, $(3, 1)$
58. $y = e^{-2x+x^2}$, $(2, 1)$
59. $f(x) = e^{-x}\ln x$, $(1, 0)$
60. $y = \ln\dfrac{e^x + e^{-x}}{2}$, $(0, 0)$
61. $y = x^2e^x - 2xe^x + 2e^x$, $(1, e)$
62. $y = xe^x - e^x$, $(1, 0)$

Implicit Differentiation In Exercises 63 and 64, use implicit differentiation to find dy/dx.

63. $xe^y - 10x + 3y = 0$
64. $e^{xy} + x^2 - y^2 = 10$

Finding the Equation of a Tangent Line In Exercises 65 and 66, use implicit differentiation to find an equation of the tangent line to the graph of the equation at the given point.

65. $xe^y + ye^x = 1$, $(0, 1)$
66. $1 + \ln xy = e^{x-y}$, $(1, 1)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding a Second Derivative **In Exercises 67 and 68, find the second derivative of the function.**

67. $f(x) = (3 + 2x)e^{-3x}$

68. $g(x) = \sqrt{x} + e^x \ln x$

Differential Equation **In Exercises 69 and 70, show that the function $y = f(x)$ is a solution of the differential equation.**

69. $y = 4e^{-x}$
$y'' - y = 0$

70. $y = e^{3x} + e^{-3x}$
$y'' - 9y = 0$

Relative Extrema and Points of Inflection **In Exercises 71–78, find the relative extrema and the points of inflection (if any exist) of the function. Use a graphing utility to graph the function and confirm your results.**

71. $f(x) = \dfrac{e^x + e^{-x}}{2}$

72. $f(x) = \dfrac{e^x - e^{-x}}{2}$

73. $g(x) = \dfrac{1}{\sqrt{2\pi}} e^{-(x-2)^2/2}$

74. $g(x) = \dfrac{1}{\sqrt{2\pi}} e^{-(x-3)^2/2}$

75. $f(x) = (2 - x)e^x$

76. $f(x) = xe^{-x}$

77. $g(t) = 1 + (2 + t)e^{-t}$

78. $f(x) = -2 + e^{3x}(4 - 2x)$

79. Area Find the area of the largest rectangle that can be inscribed under the curve $y = e^{-x^2}$ in the first and second quadrants.

80. Area Perform the following steps to find the maximum area of the rectangle shown in the figure.



(a) Solve for c in the equation $f(c) = f(c + x)$.

(b) Use the result in part (a) to write the area A as a function of x. [*Hint:* $A = xf(c)$]

(c) Use a graphing utility to graph the area function. Use the graph to approximate the dimensions of the rectangle of maximum area. Determine the maximum area.

(d) Use a graphing utility to graph the expression for c found in part (a). Use the graph to approximate

$$\lim_{x \to 0^+} c \quad \text{and} \quad \lim_{x \to \infty} c.$$

Use this result to describe the changes in dimensions and position of the rectangle for $0 < x < \infty$.

81. Finding an Equation of a Tangent Line Find the point on the graph of the function $f(x) = e^{2x}$ such that the tangent line to the graph at that point passes through the origin. Use a graphing utility to graph f and the tangent line in the same viewing window.

82. HOW DO YOU SEE IT? The figure shows the graphs of f and g, where a is a positive real number. Identify the open interval(s) on which the graphs of f and g are (a) increasing or decreasing and (b) concave upward or concave downward.



83. Depreciation The value V of an item t years after it is purchased is $V = 15{,}000e^{-0.6286t}$, $0 \le t \le 10$.

(a) Use a graphing utility to graph the function.

(b) Find the rates of change of V with respect to t when $t = 1$ and $t = 5$.

(c) Use a graphing utility to graph the tangent lines to the function when $t = 1$ and $t = 5$.

84. Harmonic Motion The displacement from equilibrium of a mass oscillating on the end of a spring suspended from a ceiling is $y = 1.56e^{-0.22t} \cos 4.9t$, where y is the displacement (in feet) and t is the time (in seconds). Use a graphing utility to graph the displacement function on the interval $[0, 10]$. Find a value of t past which the displacement is less than 3 inches from equilibrium.

85. Atmospheric Pressure

A meteorologist measures the atmospheric pressure P (in millibars) at altitude h (in kilometers). The data are shown below.

h	0	5	10	15	20
P	1013.2	547.5	233.0	121.6	50.7

(a) Use a graphing utility to plot the points $(h, \ln P)$. Use the regression capabilities of the graphing utility to find a linear model for the revised data points.

(b) The line in part (a) has the form $\ln P = ah + b$. Write the equation in exponential form.

(c) Use a graphing utility to plot the original data and graph the exponential model in part (b).

(d) Find the rates of change of the pressure when $h = 5$ and $h = 18$.

John Sirlin/EyeEm/Getty Images

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

86. Modeling Data The table lists the approximate values V of a mid-sized sedan for the years 2014 through 2020. The variable t represents the time (in years), with $t = 14$ corresponding to 2014.

t	14	15	16	17
V	\$23,046	\$20,596	\$18,851	\$17,001

t	18	19	20
V	\$15,226	\$14,101	\$12,841

(a) Use the regression capabilities of a graphing utility to fit linear and quadratic models to the data. Plot the data and graph the models.

(b) What does the slope represent in the linear model in part (a)?

(c) Use the regression capabilities of a graphing utility to fit an exponential model to the data.

(d) Determine the horizontal asymptote of the exponential model found in part (c). Interpret its meaning in the context of the problem.

(e) Use the exponential model to find the rates of decrease in the value of the sedan when $t = 16$ and $t = 19$.

Linear and Quadratic Approximation **In Exercises 87 and 88, use a graphing utility to graph the function. Then graph**

$$P_1(x) = f(0) + f'(0)(x - 0) \quad \text{and}$$

$$P_2(x) = f(0) + f'(0)(x - 0) + \tfrac{1}{2}f''(0)(x - 0)^2$$

in the same viewing window. Compare the values of f, P_1, P_2, and their first derivatives at $x = 0$.

87. $f(x) = e^x$ **88.** $f(x) = e^{x/2}$

Stirling's Formula **For large values of n,**

$$n! = 1 \cdot 2 \cdot 3 \cdot 4 \cdot \cdots (n - 1) \cdot n$$

can be approximated by Stirling's Formula,

$$n! \approx \left(\frac{n}{3}\right)^n \sqrt{2\pi n}.$$

In Exercises 89 and 90, find the exact value of $n!$ and then approximate $n!$ using Stirling's Formula.

89. $n = 12$ **90.** $n = 15$

Finding an Indefinite Integral **In Exercises 91–108, find the indefinite integral.**

91. $\int e^{5x}(5)\,dx$ **92.** $\int e^{-x^4}(-4x^3)\,dx$

93. $\int e^{5x-3}\,dx$ **94.** $\int e^{1-3x}\,dx$

95. $\int (2x + 1)e^{x^2+x}\,dx$ **96.** $\int e^x(e^x + 1)^2\,dx$

97. $\int \frac{e^{\sqrt{x}}}{\sqrt{x}}\,dx$ **98.** $\int \frac{e^{1/x^2}}{x^3}\,dx$

99. $\int \frac{e^{-x}}{1 + e^{-x}}\,dx$ **100.** $\int \frac{e^{2x}}{1 + e^{2x}}\,dx$

101. $\int e^x\sqrt{1 - e^x}\,dx$ **102.** $\int \frac{e^x - e^{-x}}{e^x + e^{-x}}\,dx$

103. $\int \frac{e^x + e^{-x}}{e^x - e^{-x}}\,dx$ **104.** $\int \frac{2e^x - 2e^{-x}}{(e^x + e^{-x})^2}\,dx$

105. $\int \frac{5 - e^x}{e^{2x}}\,dx$ **106.** $\int \frac{e^{-3x} + 2e^{2x} + 3}{e^x}\,dx$

107. $\int e^{-x}\tan(e^{-x})\,dx$ **108.** $\int e^{2x}\csc(e^{2x})\,dx$

Evaluating a Definite Integral **In Exercises 109–118, evaluate the definite integral. Use a graphing utility to verify your result.**

109. $\int_0^1 e^{-3x}\,dx$ **110.** $\int_{-1}^1 e^{1+4x}\,dx$

111. $\int_0^1 xe^{-x^2}\,dx$ **112.** $\int_{-2}^0 x^2e^{x^3/2}\,dx$

113. $\int_1^3 \frac{e^{3/x}}{x^2}\,dx$ **114.** $\int_0^{\sqrt{2}} xe^{-x^2/2}\,dx$

115. $\int_0^2 \frac{e^{4x}}{1 + e^{4x}}\,dx$ **116.** $\int_{-2}^0 \frac{e^{x+1}}{7 - e^{x+1}}\,dx$

117. $\int_0^{\pi/2} e^{\sin \pi x}\cos \pi x\,dx$ **118.** $\int_{\pi/3}^{\pi/2} e^{\sec 2x}\sec 2x \tan 2x\,dx$

Differential Equation **In Exercises 119 and 120, find the general solution of the differential equation.**

119. $\frac{dy}{dx} = xe^{9x^2}$

120. $\frac{dy}{dx} = (e^x - e^{-x})^2$

Differential Equation **In Exercises 121 and 122, find the particular solution of the differential equation that satisfies the initial conditions.**

121. $f''(x) = \frac{1}{2}(e^x + e^{-x})$, $f(0) = 1$, $f'(0) = 0$

122. $f''(x) = \sin x + e^{2x}$, $f(0) = \frac{1}{4}$, $f'(0) = \frac{1}{2}$

Area **In Exercises 123–126, find the area of the region bounded by the graphs of the equations. Use a graphing utility to verify your result.**

123. $y = e^x$, $y = 0$, $x = 0$, $x = 6$

124. $y = e^{-2x}$, $y = 0$, $x = -1$, $x = 3$

125. $y = xe^{-x^2/4}$, $y = 0$, $x = 0$, $x = \sqrt{6}$

126. $y = e^{-5x} + 2$, $y = 0$, $x = 0$, $x = 2$

Midpoint Rule **In Exercises 127 and 128, use the Midpoint Rule with $n = 12$ to approximate the value of the definite integral. Use a graphing utility to verify your result.**

127. $\int_0^4 \sqrt{x}\,e^x\,dx$ **128.** $\int_0^2 2xe^{-x}\,dx$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploring Concepts

129. Compare the asymptotes of the natural exponential function with those of the natural logarithmic function.

130. Use a graphing utility to graph $f(x) = e^x$ and the given function in the same viewing window. How are the two graphs related?

(a) $g(x) = e^{x-2}$ (b) $h(x) = -\frac{1}{2}e^x$

(c) $q(x) = e^{-x} + 3$ (d) $p(x) = 5e^x$

True or False? **In Exercises 131–134, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

131. If $f(x) = g(x)e^x$, then $f'(x) = g'(x)e^x$.

132. If $f(x) = \ln x$, then $f(e^{n+1}) - f(e^n) = 1$ for any value of n.

133. The graphs of $f(x) = e^x$ and $g(x) = e^{-x}$ meet at right angles.

134. If $f(x) = g(x)e^x$, then the only zeros of f are the zeros of g.

135. Probability A car battery has an average lifetime of 48 months with a standard deviation of 6 months. The battery lives are normally distributed. The probability that a given battery will last between 48 months and 60 months is

$$0.0065 \int_{48}^{60} e^{-0.0139(t-48)^2}\,dt.$$

Use the integration capabilities of a graphing utility to approximate the integral. Interpret the resulting probability.

136. Probability The median waiting time (in minutes) for people waiting for service in a convenience store is given by the solution of the equation

$$\int_0^x 0.3e^{-0.3t}\,dt = \frac{1}{2}.$$

What is the median waiting time?

137. Modeling Data A valve on a storage tank is opened for 4 hours to release a chemical in a manufacturing process. The flow rate R (in liters per hour) at time t (in hours) is given in the table.

t	0	1	2	3	4
R	425	240	118	71	36

(a) Use the regression capabilities of a graphing utility to find a linear model for the points $(t, \ln R)$. Write the resulting equation of the form $\ln R = at + b$ in exponential form.

(b) Use a graphing utility to plot the data and graph the exponential model.

(c) Use a definite integral to approximate the number of liters of chemical released during the 4 hours.

138. Using the Area of a Region Find the value of a such that the area bounded by $y = e^{-x}$, the x-axis, $x = -a$, and $x = a$ is $\frac{8}{3}$.

139. Analyzing a Graph Consider the function

$$f(x) = \frac{2}{1 + e^{1/x}}.$$

(a) Use a graphing utility to graph f.

(b) Write a short paragraph explaining why the graph has a horizontal asymptote at $y = 1$ and why the function has a nonremovable discontinuity at $x = 0$.

140. Horizontal Motion The position function of a particle moving along the x-axis is $x(t) = Ae^{kt} + Be^{-kt}$, where A, B, and k are positive constants.

(a) During what times t is the particle closest to the origin?

(b) Show that the acceleration of the particle is proportional to the position of the particle. What is the constant of proportionality?

141. Deriving an Inequality Given $e^x \geq 1$ for $x \geq 0$, it follows that

$$\int_0^x e^t\,dt \geq \int_0^x 1\,dt.$$

Perform this integration to derive the inequality

$$e^x \geq 1 + x$$

for $x \geq 0$.

142. Solving an Equation Find, to three decimal places, the value of x such that $e^{-x} = x$. (Use Newton's Method or the *zero* or *root* feature of a graphing utility.)

143. Analyzing a Graph Consider

$$f(x) = xe^{-kx}$$

for $k > 0$. Find the relative extrema and the points of inflection of the function.

144. Finding the Maximum Rate of Change Verify that the function

$$y = \frac{L}{1 + ae^{-x/b}}, \quad a > 0, \quad b > 0, \quad L > 0$$

increases at a maximum rate when $y = L/2$.

PUTNAM EXAM CHALLENGE

145. Let S be a class of functions from $[0, \infty)$ to $[0, \infty)$ that satisfies:

(i) The functions $f_1(x) = e^x - 1$ and $f_2(x) = \ln(x + 1)$ are in S;

(ii) If $f(x)$ and $g(x)$ are in S, the functions $f(x) + g(x)$ and $f(g(x))$ are in S;

(iii) If $f(x)$ and $g(x)$ are in S and $f(x) \geq g(x)$ for all $x \geq 0$, then the function $f(x) - g(x)$ is in S.

Prove that if $f(x)$ and $g(x)$ are in S, then the function $f(x)g(x)$ is also in S.

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

5.5 Bases Other than *e* and Applications

GO DIGITAL

- Define exponential functions that have bases other than e.
- Differentiate and integrate exponential functions that have bases other than e.
- Use exponential functions to model compound interest and exponential growth.

Bases Other than e

The **base** of the natural exponential function is e. This "natural" base can be used to assign a meaning to a general base a.

Definition of Exponential Function to Base *a*

If a is a positive real number ($a \neq 1$) and x is any real number, then the **exponential function to the base *a*** is denoted by a^x and is defined by

$$a^x = e^{(\ln a)x}.$$

If $a = 1$, then $y = 1^x = 1$ is a constant function.

REMARK Remember, base $a = 1$ is excluded because it yields $f(x) = 1^x = 1$. This is a *constant* function, not an *exponential* function.

Exponential functions obey the usual laws of exponents. For instance, here are some familiar properties.

1. $a^0 = 1$ **2.** $a^x a^y = a^{x+y}$ **3.** $\dfrac{a^x}{a^y} = a^{x-y}$ **4.** $(a^x)^y = a^{xy}$

When modeling the half-life of a radioactive sample, it is convenient to use $\frac{1}{2}$ as the base of the exponential model. (*Half-life* is the number of years required for half of the atoms in a sample of radioactive material to decay.)

Carbon dating uses the radioactive isotope carbon-14 to estimate the age of dead organic materials. The method is based on the decay rate of carbon-14 (see Example 1), a compound organisms take in when they are alive.

Alexander Rieber/EyeEm/Getty Images

EXAMPLE 1 **Radioactive Half-Life Model**

The half-life of carbon-14 is about 5715 years. A sample contains 1 gram of carbon-14. How much will be present in 10,000 years?

Solution Let $t = 0$ represent the present time and let y represent the amount (in grams) of carbon-14 in the sample. Using a base of $\frac{1}{2}$, you can model y by the equation

$$y = \left(\frac{1}{2}\right)^{t/5715}.$$

Notice that when $t = 5715$, the amount is reduced to half of the original amount.

$$y = \left(\frac{1}{2}\right)^{5715/5715} = \frac{1}{2} \text{ gram}$$

When $t = 11{,}430$, the amount is reduced to a quarter of the original amount and so on. To find the amount of carbon-14 after 10,000 years, substitute 10,000 for t.

$$y = \left(\frac{1}{2}\right)^{10{,}000/5715} \approx 0.30 \text{ gram}$$

The graph of y is shown at the right.



The half-life of carbon-14 is about 5715 years.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Logarithmic functions to bases other than e can be defined in much the same way as exponential functions to other bases are defined.

Definition of Logarithmic Function to Base *a*

If a is a positive real number ($a \neq 1$) and x is any positive real number, then the **logarithmic function to the base *a*** is denoted by $\log_a x$ and is defined as

$$\log_a x = \frac{1}{\ln a} \ln x.$$

REMARK In precalculus, you learned that $\log_a x$ is the value to which a must be raised to produce x. This agrees with the definition at the right because

$$\begin{aligned} a^{\log_a x} &= a^{(1/\ln a)\ln x} \\ &= (e^{\ln a})^{(1/\ln a)\ln x} \\ &= e^{(\ln a/\ln a)\ln x} \\ &= e^{\ln x} \\ &= x. \end{aligned}$$

Logarithmic functions to the base a have properties similar to those of the natural logarithmic function given in Theorem 5.2. (Assume x and y are positive numbers and n is rational.)

1. $\log_a 1 = 0$ Log of 1
2. $\log_a xy = \log_a x + \log_a y$ Log of a product
3. $\log_a x^n = n \log_a x$ Log of a power
4. $\log_a \frac{x}{y} = \log_a x - \log_a y$ Log of a quotient

GO DIGITAL

From the definitions of the exponential and logarithmic functions to the base a, it follows that $f(x) = a^x$ and $g(x) = \log_a x$ are inverse functions of each other.

Properties of Inverse Functions

1. $y = a^x$ if and only if $x = \log_a y$
2. $a^{\log_a x} = x$, for $x > 0$
3. $\log_a a^x = x$, for all x

The logarithmic function to the base 10 is called the **common logarithmic function.** So, for common logarithms,

$$y = 10^x \quad \text{if and only if} \quad x = \log_{10} y.$$ Property of inverse functions

EXAMPLE 2 Bases Other than *e*

Solve for x in each equation.

a. $3^x = \frac{1}{81}$ **b.** $\log_2 x = -4$

Solution

a. To solve this equation, you can apply the logarithmic function to the base 3 to each side of the equation.

$$\begin{aligned} 3^x &= \frac{1}{81} \\ \log_3 3^x &= \log_3 \frac{1}{81} \\ x &= \log_3 3^{-4} \\ x &= -4 \end{aligned}$$

b. To solve this equation, you can apply the exponential function to the base 2 to each side of the equation.

$$\begin{aligned} \log_2 x &= -4 \\ 2^{\log_2 x} &= 2^{-4} \\ x &= \frac{1}{2^4} \\ x &= \frac{1}{16} \end{aligned}$$

REMARK In Example 2, the strategy used to solve for x is to operate on each side of the equation with the *inverse* function. For instance, in part (a), the equation has an exponential function with base 3. So, to solve for x, apply the logarithmic function to the base 3 to each side of the equation.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Differentiation and Integration

To differentiate exponential and logarithmic functions to other bases, you have three options: (1) use the definitions of a^x and $\log_a x$ and differentiate using the rules for the natural exponential and logarithmic functions, (2) use logarithmic differentiation, or (3) use the differentiation rules for bases other than e given in the next theorem.

THEOREM 5.13 Derivatives for Bases Other than *e*

Let a be a positive real number $(a \neq 1)$, and let u be a differentiable function of x.

1. $\dfrac{d}{dx}[a^x] = (\ln a)a^x$
2. $\dfrac{d}{dx}[a^u] = (\ln a)a^u \dfrac{du}{dx}$
3. $\dfrac{d}{dx}[\log_a x] = \dfrac{1}{(\ln a)x}$
4. $\dfrac{d}{dx}[\log_a u] = \dfrac{1}{(\ln a)u}\dfrac{du}{dx}$

REMARK These differentiation rules are similar to those for the natural exponential function and the natural logarithmic function. In fact, they differ only by the constant factors $\ln a$ and $1/\ln a$. This points out one reason why, for calculus, e is the most convenient base.

Proof By definition, $a^x = e^{(\ln a)x}$. So, you can prove the first rule by letting $u = (\ln a)x$ and differentiating with base e to obtain

$$\frac{d}{dx}[a^x] = \frac{d}{dx}[e^{(\ln a)x}] = e^u\frac{du}{dx} = e^{(\ln a)x}(\ln a) = (\ln a)a^x.$$

To prove the third rule, you can write

$$\frac{d}{dx}[\log_a x] = \frac{d}{dx}\left[\frac{1}{\ln a}\ln x\right] = \frac{1}{\ln a}\left(\frac{1}{x}\right) = \frac{1}{(\ln a)x}.$$

The second and fourth rules are simply the Chain Rule versions of the first and third rules. ■

EXAMPLE 3 Differentiating Functions to Other Bases

Find the derivative of each function.

a. $y = 2^x$ **b.** $y = 2^{3x}$ **c.** $y = \log_{10}\cos x$ **d.** $y = \log_3 \dfrac{\sqrt{x}}{2x+5}$

Solution

a. $y' = \dfrac{d}{dx}[2^x] = (\ln 2)2^x$

b. $y' = \dfrac{d}{dx}[2^{3x}] = (\ln 2)2^{3x}(3) = (3\ln 2)2^{3x}$

REMARK Write 2^{3x} as 8^x and differentiate. Is the result the same as the one in Example 3(b)?

c. $y' = \dfrac{d}{dx}[\log_{10}\cos x] = \dfrac{-\sin x}{(\ln 10)\cos x} = -\dfrac{1}{\ln 10}\tan x$

d. Before differentiating, rewrite the function using logarithmic properties.

$$y = \log_3 \frac{\sqrt{x}}{2x+5} = \frac{1}{2}\log_3 x - \log_3(2x+5)$$

Next, apply Theorem 5.13 to differentiate the function.

$$y' = \frac{d}{dx}\left[\frac{1}{2}\log_3 x - \log_3(2x+5)\right]$$ Differentiate with respect to x.

$$= \frac{1}{2(\ln 3)x} - \frac{1}{(\ln 3)(2x+5)}(2)$$ Theorem 5.13, Properties 3 and 4

$$= \frac{5-2x}{2(\ln 3)x(2x+5)}$$ Simplify. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Occasionally, an integrand involves an exponential function to a base other than e. When this occurs, there are two options: (1) convert to base e using the formula $a^x = e^{(\ln a)x}$ and then integrate, or (2) integrate directly, using the integration formula

$$\int a^x\,dx = \left(\frac{1}{\ln a}\right)a^x + C$$

which follows from Theorem 5.13.

EXAMPLE 4 Integrating an Exponential Function to Another Base

Find $\int 2^x\,dx$.

Solution

$$\int 2^x\,dx = \frac{1}{\ln 2}2^x + C$$

When the Power Rule, $D_x[x^n] = nx^{n-1}$, was introduced in Chapter 2, the exponent n was required to be a rational number. Now the rule is extended to cover any real value of n. Try to prove this theorem using logarithmic differentiation.

THEOREM 5.14 The Power Rule for Real Exponents

Let n be any real number, and let u be a differentiable function of x.

1. $\dfrac{d}{dx}[x^n] = nx^{n-1}$ **2.** $\dfrac{d}{dx}[u^n] = nu^{n-1}\dfrac{du}{dx}$

The next example compares the derivatives of four types of functions. Each function uses a different differentiation formula, depending on whether the base and the exponent are constants or variables.

EXAMPLE 5 Comparing Variables and Constants

a. $\dfrac{d}{dx}[e^e] = 0$ Constant Rule

b. $\dfrac{d}{dx}[e^x] = e^x$ Exponential Rule

c. $\dfrac{d}{dx}[x^e] = ex^{e-1}$ Power Rule

d.

$y = x^x$	Use logarithmic differentiation.
$\ln y = \ln x^x$	Take natural log of each side.
$\ln y = x \ln x$	Property of logarithms
$\dfrac{y'}{y} = x\left(\dfrac{1}{x}\right) + (\ln x)(1)$	Differentiate.
$\dfrac{y'}{y} = 1 + \ln x$	Simplify.
$y' = y(1 + \ln x)$	Solve for y'.
$y' = x^x(1 + \ln x)$	Substitute for y.

REMARK Be sure you understand that there is no simple differentiation rule for calculating the derivative of $y = x^x$. In general, when $y = u(x)^{v(x)}$, you need to use logarithmic differentiation.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Applications of Exponential Functions

An amount of P dollars is deposited in an account at an annual interest rate r (in decimal form). What is the balance in the account at the end of 1 year? The answer depends on the number of times n the interest is compounded according to the formula

$$A = P\left(1 + \frac{r}{n}\right)^n.$$

For instance, the result for a deposit of \$1000 at 8% interest compounded n times a year is shown in the table at the right.

n	A
1	\$1080.00
2	\$1081.60
4	\$1082.43
12	\$1083.00
365	\$1083.28

As n increases, the balance A approaches a limit. To develop this limit, use the next theorem. To test the reasonableness of this theorem, try evaluating

$$\left(\frac{x + 1}{x}\right)^x$$

for several values of x, as shown in the table at the left.

x	$\left(\frac{x+1}{x}\right)^x$
10	2.59374
100	2.70481
1000	2.71692
10,000	2.71815
100,000	2.71827
1,000,000	2.71828

THEOREM 5.15 A Limit Involving e

$$\lim_{x\to\infty}\left(1 + \frac{1}{x}\right)^x = \lim_{x\to\infty}\left(\frac{x + 1}{x}\right)^x = e$$

A proof of this theorem is given in Appendix A.

Given Theorem 5.15, take another look at the formula for the balance A in an account in which the interest is compounded n times per year. By taking the limit as n approaches infinity, you obtain

$$\begin{aligned} A &= \lim_{n\to\infty} P\left(1 + \frac{r}{n}\right)^n && \text{Take limit as } n\to\infty. \\ &= P\lim_{n\to\infty}\left[\left(1 + \frac{1}{n/r}\right)^{n/r}\right]^r && \text{Rewrite.} \\ &= P\left[\lim_{x\to\infty}\left(1 + \frac{1}{x}\right)^x\right]^r && \text{Let } x = n/r. \text{ Then } x\to\infty \text{ as } n\to\infty. \\ &= Pe^r. && \text{Apply Theorem 5.15.} \end{aligned}$$

This limit produces the balance after 1 year of **continuous compounding.** So, for a deposit of \$1000 at 8% interest compounded continuously, the balance at the end of 1 year would be

$$A = 1000e^{0.08} \approx \$1083.29.$$

REMARK The interest rate r in the formulas for compound interest should be written in decimal form. For instance, an interest rate of 2.5% is written as $r = 0.025$.

Summary of Compound Interest Formulas

In the formulas below, P is the amount deposited, t is the number of years, A is the balance after t years, r is the annual interest rate (in decimal form), and n is the number of compoundings per year.

1. Compounded n times per year: $A = P\left(1 + \frac{r}{n}\right)^{nt}$
2. Compounded continuously: $A = Pe^{rt}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 6 Continuous, Quarterly, and Monthly Compounding

See LarsonCalculus.com for an interactive version of this type of example.

A deposit of \$2500 is made in an account that pays an annual interest rate of 5%. Find the balance in the account at the end of 5 years when the interest is compounded (a) quarterly, (b) monthly, and (c) continuously.

Solution

a. $A = P\left(1 + \frac{r}{n}\right)^{nt}$ Compounded quarterly

$= 2500\left(1 + \frac{0.05}{4}\right)^{4(5)}$

$= 2500(1.0125)^{20}$

$= \$3205.09$

b. $A = P\left(1 + \frac{r}{n}\right)^{nt}$ Compounded monthly

$= 2500\left(1 + \frac{0.05}{12}\right)^{12(5)}$

$\approx 2500(1.0041667)^{60}$

$= \$3208.40$

c. $A = Pe^{rt}$ Compounded continuously

$= 2500\left[e^{0.05(5)}\right]$

$= 2500e^{0.25}$

$= \$3210.06$

EXAMPLE 7 Bacterial Culture Growth

A bacterial culture is growing according to the *logistic growth function*

$$y = \frac{1.25}{1 + 0.25e^{-0.4t}}, \quad t \geq 0$$

where y is the weight of the culture in grams and t is the time in hours. Find the weight of the culture after (a) 0 hours, (b) 1 hour, and (c) 10 hours. (d) What is the limit as t approaches infinity?

Solution

a. When $t = 0$, $y = \frac{1.25}{1 + 0.25e^{-0.4(0)}}$

$= 1$ gram.

b. When $t = 1$, $y = \frac{1.25}{1 + 0.25e^{-0.4(1)}}$

≈ 1.071 grams.

c. When $t = 10$, $y = \frac{1.25}{1 + 0.25e^{-0.4(10)}}$

≈ 1.244 grams.

d. Taking the limit as t approaches infinity, you obtain

$$\lim_{t\to\infty} \frac{1.25}{1 + 0.25e^{-0.4t}} = \frac{1.25}{1 + 0} = 1.25 \text{ grams.}$$

The graph of the function is shown in Figure 5.22. In the figure, notice that the line $y = 1.25$ is a horizontal asymptote to the right.



The limit of the weight of the culture as $t \to \infty$ is 1.25 grams.

Figure 5.22

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

5.5 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Find the values of a and b.

$$\frac{d}{dx}[6^{4x}] = a(\ln b)6^{4x}.$$

2. Explain two different ways to find the indefinite integral below.

$$\int 5^t\,dt$$

3. Explain when it is necessary to use logarithmic differentiation to find the derivative of an exponential function.

4. Explain how to choose which compound interest formula to use to find the balance of a deposit.

Evaluating a Logarithmic Expression **In Exercises 5–10, evaluate the expression without using a calculator.**

5. $\log_2 \frac{1}{8}$
6. $\log_3 81$
7. $\log_7 1$
8. $\log_a \frac{1}{a}$
9. $\log_{64} 32$
10. $\log_{27} \frac{1}{9}$

Exponential and Logarithmic Forms of Equations **In Exercises 11–14, write the exponential equation as a logarithmic equation or vice versa.**

11. (a) $2^3 = 8$
    (b) $3^{-1} = \frac{1}{3}$
12. (a) $27^{2/3} = 9$
    (b) $16^{3/4} = 8$
13. (a) $\log_{10} 0.01 = -2$
    (b) $\log_{0.5} 8 = -3$
14. (a) $\log_3 \frac{1}{9} = -2$
    (b) $49^{1/2} = 7$

Sketching a Graph **In Exercises 15–20, sketch the graph of the function.**

15. $y = 2^x$
16. $y = 4^{x-1}$
17. $y = \left(\frac{1}{3}\right)^x$
18. $y = 2^{x^2}$
19. $h(x) = 5^{x-2}$
20. $y = 3^{-|x|}$

Solving an Equation **In Exercises 21–26, solve for x.**

21. (a) $\log_{10} 1000 = x$
    (b) $\log_{10} 0.1 = x$
22. (a) $\log_3 \frac{1}{81} = x$
    (b) $\log_6 36 = x$
23. (a) $\log_3 x = -1$
    (b) $\log_2 x = -4$
24. (a) $\log_4 x = -2$
    (b) $\log_5 x = 3$
25. (a) $x^2 - x = \log_5 25$
    (b) $3x + 5 = \log_2 64$
26. (a) $\log_3 x + \log_3(x - 2) = 1$
    (b) $\log_{10}(x + 3) - \log_{10} x = 1$

Solving an Equation **In Exercises 27–36, solve the equation accurate to three decimal places.**

27. $3^{2x} = 75$
28. $6^{-2x} = 74$
29. $2^{3-z} = 625$
30. $3(5^{x-1}) = 86$
31. $\left(1 + \frac{0.09}{12}\right)^{12t} = 3$
32. $\left(1 + \frac{0.10}{365}\right)^{365t} = 2$
33. $\log_2(x - 1) = 5$
34. $\log_{10}(t - 3) = 2.6$
35. $\log_7 x^3 = 1.9$
36. $\log_5 \sqrt{x - 4} = 3.2$

Inverse Functions **In Exercises 37 and 38, illustrate that the functions are inverse functions of each other by sketching their graphs on the same set of coordinate axes.**

37. $f(x) = 4^x$, $g(x) = \log_4 x$
38. $f(x) = 3^x$, $g(x) = \log_3 x$

Finding a Derivative **In Exercises 39–60, find the derivative of the function.**

39. $f(x) = 4^x$
40. $f(x) = 3^{4x}$
41. $y = 5^{-4x}$
42. $y = 6^{3x-4}$
43. $f(x) = x\,9^x$
44. $y = -7x(8^{-2x})$
45. $f(t) = \frac{-2t^2}{8^t}$
46. $f(t) = \frac{3^{2t}}{t}$
47. $h(\theta) = 2^{-\theta}\cos \pi\theta$
48. $g(\alpha) = 5^{-\alpha/2}\sin 2\alpha$
49. $y = \log_4(6x + 1)$
50. $y = \log_3(x^2 - 3x)$
51. $h(t) = \log_5(4 - t)^2$
52. $g(t) = \log_2(t^2 + 7)^3$
53. $y = \log_5 \sqrt{x^2 - 1}$
54. $f(x) = \log_2 \sqrt[3]{2x + 1}$
55. $f(x) = \log_2 \frac{x^2}{x - 1}$
56. $y = \log_{10} \frac{x^2 - 1}{x}$
57. $h(x) = \log_3 \frac{x\sqrt{x - 1}}{2}$
58. $g(x) = \log_5 \frac{4}{x^2\sqrt{1 - x}}$
59. $g(t) = \frac{10 \log_4 t}{t}$
60. $f(t) = t^{3/2}\log_2 \sqrt{t + 1}$

Finding an Equation of a Tangent Line **In Exercises 61–64, find an equation of the tangent line to the graph of the function at the given point.**

61. $y = 2^{-x}$, $(-1, 2)$
62. $y = 5^{x-2}$, $(2, 1)$
63. $y = \log_3 x$, $(27, 3)$
64. $y = \log_{10} 2x$, $(5, 1)$

Logarithmic Differentiation **In Exercises 65–68, use logarithmic differentiation to find dy/dx.**

65. $y = x^{2/x}$
66. $y = x^{x-1}$
67. $y = (x - 2)^{x+1}$
68. $y = (1 + x)^{1/x}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding an Indefinite Integral **In Exercises 69–76, find the indefinite integral.**

69. $\int 3^x\,dx$

70. $\int 2^{-x}\,dx$

71. $\int (x^2 + 2^{-x})\,dx$

72. $\int (x^4 + 5^x)\,dx$

73. $\int x(5^{-x^2})\,dx$

74. $\int (4 - x)6^{(4-x)^2}\,dx$

75. $\int \frac{3^{2x}}{1 + 3^{2x}}\,dx$

76. $\int 2^{\sin x}\cos x\,dx$

Evaluating a Definite Integral **In Exercises 77–80, evaluate the definite integral. Use a graphing utility to verify your result.**

77. $\int_{-1}^{2} 2^x\,dx$

78. $\int_{-4}^{4} 3^{x/4}\,dx$

79. $\int_{0}^{1} (5^x - 3^x)\,dx$

80. $\int_{1}^{3} (4^{x+1} + 2^x)\,dx$

Area **In Exercises 81 and 82, find the area of the region bounded by the graphs of the equations. Use a graphing utility to verify your result.**

81. $y = \dfrac{\log_4 x}{x}$, $y = 0$, $x = 1$, $x = 5$

82. $y = 3^{\cos x}\sin x$, $y = 0$, $x = 0$, $x = \pi$

Exploring Concepts

83. Explain how the rate of change of the exponential function $y = a^x$ is affected as a becomes larger.

84. Explain how the rate of change of the logarithmic function $y = \log_a x$ is affected as a becomes larger.

85. Analyzing a Logarithmic Equation Consider the function $f(x) = \log_{10} x$.

(a) What is the domain of f?

(b) Find f^{-1}.

(c) Let x be a real number between 1000 and 10,000. Determine the interval in which $f(x)$ will be found.

(d) Determine the interval in which x will be found if $f(x)$ is negative.

(e) When $f(x)$ is increased by one unit, x must have been increased by what factor?

(f) Find the ratio of x_1 to x_2 given that $f(x_1) = 3n$ and $f(x_2) = n$.

86. Comparing Rates of Growth Order the functions

$f(x) = \log_2 x$, $g(x) = x^x$, $h(x) = x^2$, and $k(x) = 2^x$

from the one with the greatest rate of growth to the one with the least rate of growth for large values of x.

87. Analyzing a Graph Use a graphing utility to determine whether (a) $y = (1/2)^x$ and $y = x$ intersect and (b) $y = 2^x$ and $y = x$ intersect.

88. Analyzing a Graph Use the results of Exercise 87 to find all positive values of a such that $y = a^x$ and $y = x$ intersect.

89. Inflation When the annual rate of inflation averages 5% over the next 10 years, the approximate cost C of goods or services during any year in that decade is

$$C(t) = P(1.05)^t$$

where t is the time in years and P is the present cost.

(a) The price of an oil change for your car is presently \$24.95. Estimate the price 10 years from now.

(b) Find the rates of change of C with respect to t when $t = 1$ and $t = 8$.

(c) Verify that the rate of change of C is proportional to C. What is the constant of proportionality?

90. Depreciation After t years, the value of a car purchased for \$25,000 is

$$V(t) = 25{,}000\left(\tfrac{3}{4}\right)^t.$$

(a) Use a graphing utility to graph the function and determine the value of the car 2 years after it was purchased.

(b) Find the rates of change of V with respect to t when $t = 1$ and $t = 4$.

(c) Use a graphing utility to graph $V'(t)$ and determine the horizontal asymptote of $V'(t)$. Interpret its meaning in the context of the problem.

Compound Interest **In Exercises 91–94, complete the table by determining the balance A for P dollars invested at rate r for t years and compounded n times per year.**

n	1	2	4	12	365	Continuous Compounding
A						

91. $P = \$1000$, $r = 3\frac{1}{2}\%$, $t = 10$ years

92. $P = \$2500$, $r = 6\%$, $t = 20$ years

93. $P = \$7500$, $r = 4.8\%$, $t = 30$ years

94. $P = \$4000$, $r = 4\%$, $t = 15$ years

Compound Interest **In Exercises 95–98, complete the table by determining the amount of money P (present value) that should be invested at rate r to produce a balance of \$100,000 in t years.**

t	1	10	20	30	40	50
P						

95. $r = 4\%$, Compounded continuously

96. $r = 0.6\%$, Compounded continuously

97. $r = 5\%$, Compounded monthly

98. $r = 2\%$, Compounded daily

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

99. Compound Interest Assume that you can earn 6% on an investment, compounded daily. Which of the following options would yield the greatest balance after 8 years?

(a) \$20,000 now (b) \$30,000 after 8 years

(c) \$8000 now and \$20,000 after 4 years

(d) \$9000 now, \$9000 after 4 years, and \$9000 after 8 years

100. Compound Interest Consider a deposit of \$100 placed in an account for 20 years at $r\%$ compounded continuously. Use a graphing utility to graph the exponential functions describing the growth of the investment over the 20 years for the following interest rates. Compare the ending balances.

(a) $r = 3\%$ (b) $r = 5\%$ (c) $r = 6\%$

101. Timber Yield The yield V (in millions of cubic feet per acre) for a stand of timber at age t is $V = 0.75e^{-48.1/0.5t}$, where t is measured in years.

(a) Find the limiting volume of wood per acre as t approaches infinity.

(b) Find the rates at which the yield is changing when $t = 20$ and $t = 60$.

102. HOW DO YOU SEE IT? The graph shows the proportion P of correct responses after n trials in a group project in learning theory.



(a) What is the limiting proportion of correct responses as n approaches infinity?

(b) What happens to the rate of change of the proportion in the long run?

103. Population Growth A lake is stocked with 500 fish, and the population p is growing according to the logistic curve

$$p(t) = \frac{10{,}000}{1 + 19e^{-t/5}}$$

where t is measured in months.

(a) Use a graphing utility to graph the function.

(b) Find the fish populations after 6 months, 12 months, 24 months, 36 months, and 48 months. What is the limiting size of the fish population?

(c) Find the rates at which the fish population is changing after 1 month and after 10 months.

(d) After how many months is the population increasing most rapidly?

104. Modeling Data

The breaking strengths B (in tons) of steel cables of various diameters d (in inches) are shown in the table.

d	0.50	0.75	1.00	1.25	1.50	1.75
B	9.85	21.8	38.3	59.2	84.4	114.0

(a) Use the regression capabilities of a graphing utility to fit an exponential model to the data.

(b) Use a graphing utility to plot the data and graph the model.

(c) Find the rates of growth of the model when $d = 0.8$ and $d = 1.5$.

105. Comparing Models The cumulative numbers of deaths from the Ebola virus during an outbreak in West Africa in 2014 are shown in the table, where x is the number of months after the beginning of the outbreak. *(Source: Centers for Disease Control and Prevention)*

x	1	2	3	4	5
y	147	183	338	660	1422

x	6	7	8	9	10
y	2909	4912	5674	7573	8626

(a) Use the regression capabilities of a graphing utility to find the following models for the data.

$y_1 = ax + b$ $y_2 = a + b \ln x$

$y_3 = ab^x$ $y_4 = ax^b$

(b) Use a graphing utility to plot the data and graph each of the models. Which model do you think best fits the data?

(c) Find the rate of change of each of the models in part (a) 5 months after the beginning of the outbreak. Which model is increasing at the greatest rate at this time?

106. An Approximation of e Complete the table to demonstrate that e can also be defined as

$$\lim_{x \to 0^+} (1 + x)^{1/x}.$$

x	1	10^{-1}	10^{-2}	10^{-4}	10^{-6}
$(1 + x)^{1/x}$					

Using Properties of Exponents **In Exercises 107–110, find the exact value of the expression.**

107. $5^{1/\ln 5}$ **108.** $6^{(\ln 10)/\ln 6}$

109. $9^{1/\ln 3}$ **110.** $32^{1/\ln 2}$

AdShooter/Getty Images

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Modeling Data **In Exercises 111 and 112, find an exponential function that fits the experimental data collected over time t.**

111.

t	0	1	2	3	4
y	1200.00	720.00	432.00	259.20	155.52

112.

t	0	1	2	3	4
y	600.00	630.00	661.50	694.58	729.30

113. Comparing Functions

(a) Show that $(2^3)^2 \neq 2^{(3^2)}$.

(b) Are $f(x) = (x^x)^x$ and $g(x) = x^{(x^x)}$ the same function? Why or why not?

(c) Find $f'(x)$ and $g'(x)$.

114. Finding an Inverse Function Let

$$f(x) = \frac{a^x - 1}{a^x + 1}$$

for $a > 0$, $a \neq 1$. Show that f has an inverse function. Then find f^{-1}.

115. Logistic Differential Equation Show that solving the logistic differential equation

$$\frac{dy}{dt} = \frac{8}{25}y\left(\frac{5}{4} - y\right), \quad y(0) = 1$$

results in the logistic growth function in Example 7.

$$\left[\textit{Hint: } \frac{1}{y\left(\frac{5}{4} - y\right)} = \frac{4}{5}\left(\frac{1}{y} + \frac{1}{\frac{5}{4} - y}\right)\right]$$

116. The Subtangent Let $P = (x_0, y_0)$ be a point on the graph of $y = f(x)$. Assume that the tangent line at P intersects the x-axis at A (see figure). If $B = (x_0, 0)$, then the line segment AB is the *subtangent* at P.



Let $y = x^x$, $x > 0$.

(a) Find $f'(x)$ and the length of the subtangent at $P = (x, y)$.

(b) Find the length of the subtangent when $x = e$.

(c) Explain why the subtangent is not defined at $x = 1/e$.

117. Tangent Lines

(a) Determine y' given $y^x = x^y$.

(b) Find the slope of the tangent line to the graph of $y^x = x^y$ at each of the following points.

(i) (c, c) (ii) $(2, 4)$ (iii) $(4, 2)$

(c) At what points on the graph of $y^x = x^y$ does the tangent line not exist?

118. Using Properties of Exponents Given the exponential function $f(x) = a^x$, show that

(a) $f(u + v) = f(u) \cdot f(v)$.

(b) $f(2x) = [f(x)]^2$.

PUTNAM EXAM CHALLENGE

119. Which is greater

$$\left(\sqrt{n}\right)^{\sqrt{n+1}} \quad \text{or} \quad \left(\sqrt{n+1}\right)^{\sqrt{n}}$$

where $n > 8$?

120. Show that if x is positive, then

$$\log_e\left(1 + \frac{1}{x}\right) > \frac{1}{1 + x}.$$

These problems were composed by the Committee on the Putnam Prize Competition. © The Mathematical Association of America. All rights reserved.

SECTION PROJECT

Using a Graphing Utility to Estimate Slope

Let $f(x) = \begin{cases} |x|^x, & x \neq 0 \\ 1, & x = 0. \end{cases}$

(a) Use a graphing utility to graph f in the viewing window $-3 \leq x \leq 3$, $-2 \leq y \leq 2$. What is the domain of f?

(b) Use the *zoom* and *trace* features of a graphing utility to estimate $\lim_{x \to 0} f(x)$.

(c) Write a short paragraph explaining why the function f is continuous for all real numbers.

(d) Visually estimate the slope of f at the point $(0, 1)$.

(e) Explain why the derivative of a function can be approximated by the formula

$$\frac{f(x + \Delta x) - f(x - \Delta x)}{2\Delta x}$$

for small values of Δx. Use this formula to approximate the slope of f at the point $(0, 1)$.

$$f'(0) \approx \frac{f(0 + \Delta x) - f(0 - \Delta x)}{2\Delta x}$$

$$= \frac{f(\Delta x) - f(-\Delta x)}{2\Delta x}$$

What do you think the slope of the graph of f is at $(0, 1)$?

(f) Find a formula for the derivative of f and determine $f'(0)$. Write a short paragraph explaining how a graphing utility might lead you to approximate the slope of a graph incorrectly.

(g) Use your formula for the derivative of f to find the relative extrema of f. Verify your answer using a graphing utility.

FOR FURTHER INFORMATION For more information on using a graphing utility to estimate slope, see the article "Computer-Aided Delusions" by Richard L. Hall in *The College Mathematics Journal*. To view this article, go to *MathArticles.com*.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

5.6 Indeterminate Forms and L'Hôpital's Rule

GO DIGITAL

- **Recognize limits that produce indeterminate forms.**
- **Apply L'Hôpital's Rule to evaluate a limit.**

Indeterminate Forms

Recall from Chapters 1 and 3 that the forms $0/0$ and ∞/∞ are called *indeterminate* because they do not guarantee that a limit exists, nor do they indicate what the limit is, if one does exist. When you encountered one of these indeterminate forms earlier in the text, you attempted to rewrite the expression by using various algebraic techniques.

Indeterminate Form	Limit	Algebraic Technique
$\frac{0}{0}$	$\lim_{x\to -1}\frac{2x^2-2}{x+1}=\lim_{x\to -1}2(x-1)=-4$	Divide numerator and denominator by $(x+1)$.
$\frac{\infty}{\infty}$	$\lim_{x\to \infty}\frac{3x^2-1}{2x^2+1}=\lim_{x\to \infty}\frac{3-(1/x^2)}{2+(1/x^2)}=\frac{3}{2}$	Divide numerator and denominator by x^2.

Occasionally, you can extend these algebraic techniques to find limits of transcendental functions. For instance, the limit

$$\lim_{x\to 0}\frac{e^{2x}-1}{e^x-1}$$

produces the indeterminate form $0/0$. Factoring and then dividing produces

$$\lim_{x\to 0}\frac{e^{2x}-1}{e^x-1}=\lim_{x\to 0}\frac{(e^x+1)(e^x-1)}{e^x-1}$$ Factor.

$$=\lim_{x\to 0}(e^x+1)$$ Divide out common factor.

$$=2.$$ Use direct substitution.

Not all indeterminate forms, however, can be evaluated by algebraic manipulation. This is often true when *both* algebraic and transcendental functions are involved. For instance, the limit

$$\lim_{x\to 0}\frac{e^{2x}-1}{x}$$

produces the indeterminate form $0/0$. Rewriting the expression to obtain

$$\lim_{x\to 0}\left(\frac{e^{2x}}{x}-\frac{1}{x}\right)$$ Rewrite as two fractions.

merely produces another indeterminate form, $\infty-\infty$. Of course, you could use technology to estimate the limit, as shown in the table and in Figure 5.23. From the table and the graph, the limit appears to be 2. (This limit will be verified in Example 1.)



The limit as x approaches 0 appears to be 2.

Figure 5.23

x	-1	-0.1	-0.01	-0.001	0	0.001	0.01	0.1	1
$\frac{e^{2x}-1}{x}$	0.865	1.813	1.980	1.998	?	2.002	2.020	2.214	6.389

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GUILLAUME L'HÔPITAL (1661–1704)

L'Hôpital's Rule is named after the French mathematician Guillaume François Antoine de L'Hôpital. L'Hôpital is credited with writing the first text on differential calculus (in 1696) in which the rule publicly appeared. It was recently discovered that the rule and its proof were written in a letter from John Bernoulli to L'Hôpital. "… I acknowledge that I owe very much to the bright minds of the Bernoulli brothers. … I have made free use of their discoveries …," said L'Hôpital.

See LarsonCalculus.com to read more of this biography.

L'Hôpital's Rule

To find the limit illustrated in Figure 5.23, you can use a theorem called **L'Hôpital's Rule.** This theorem states that under certain conditions, the limit of the quotient $f(x)/g(x)$ is determined by the limit of the quotient of the derivatives

$$\frac{f'(x)}{g'(x)}.$$ Differentiate numerator and denominator.

To prove this theorem, you can use a more general result called the **Extended Mean Value Theorem.**

THEOREM 5.16 The Extended Mean Value Theorem

If f and g are differentiable on an open interval (a, b) and continuous on $[a, b]$ such that $g'(x) \neq 0$ for any x in (a, b), then there exists a point c in (a, b) such that

$$\frac{f'(c)}{g'(c)} = \frac{f(b) - f(a)}{g(b) - g(a)}.$$

A proof of this theorem is given in Appendix A.

To see why Theorem 5.16 is called the Extended Mean Value Theorem, consider the special case in which $g(x) = x$. For this case, you obtain the "standard" Mean Value Theorem as presented in Section 3.2.

THEOREM 5.17 L'Hôpital's Rule

Let f and g be functions that are differentiable on an open interval (a, b) containing c, except possibly at c itself. Assume that $g'(x) \neq 0$ for all x in (a, b), except possibly at c itself. If the limit of $f(x)/g(x)$ as x approaches c produces the indeterminate form $0/0$, then

$$\lim_{x \to c} \frac{f(x)}{g(x)} = \lim_{x \to c} \frac{f'(x)}{g'(x)}$$

provided the limit on the right exists (or is infinite). This result also applies when the limit of $f(x)/g(x)$ as x approaches c produces any one of the indeterminate forms ∞/∞, $(-\infty)/\infty$, $\infty/(-\infty)$, or $(-\infty)/(-\infty)$.
A proof of this theorem is given in Appendix A.

People occasionally use L'Hôpital's Rule incorrectly by applying the Quotient Rule to $f(x)/g(x)$. Be sure you understand that the rule involves

$$\frac{f'(x)}{g'(x)}$$ Derivative of f divided by derivative of g

not the derivative of $f(x)/g(x)$.

L'Hôpital's Rule can also be applied to one-sided limits. For instance, if the limit of $f(x)/g(x)$ as x approaches c *from the right* produces the indeterminate form $0/0$, then

$$\lim_{x \to c^+} \frac{f(x)}{g(x)} = \lim_{x \to c^+} \frac{f'(x)}{g'(x)}$$

provided the limit exists (or is infinite).

FOR FURTHER INFORMATION

To enhance your understanding of the necessity of the restriction that $g'(x)$ be nonzero for all x in (a, b), except possibly at c, see the article "Counterexamples to L'Hôpital's Rule" by R. P. Boas in *The American Mathematical Monthly.* To view this article, go to *MathArticles.com.*

GO DIGITAL

Photo 12/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploration

Numerical and Graphical Approaches Use a numerical or a graphical approach to approximate each limit.

a. $\lim_{x\to 0}\dfrac{2^{2x}-1}{x}$

b. $\lim_{x\to 0}\dfrac{3^{2x}-1}{x}$

c. $\lim_{x\to 0}\dfrac{4^{2x}-1}{x}$

d. $\lim_{x\to 0}\dfrac{5^{2x}-1}{x}$

What pattern do you observe? Does an analytic approach have an advantage for determining these limits? If so, explain your reasoning.

EXAMPLE 1 Indeterminate Form 0/0

Evaluate $\lim_{x\to 0}\dfrac{e^{2x}-1}{x}$.

Solution Because direct substitution results in the indeterminate form $0/0$

$$\lim_{x\to 0}\frac{e^{2x}-1}{x}\quad\begin{cases}\lim_{x\to 0}(e^{2x}-1)=0\\ \lim_{x\to 0}x=0\end{cases}$$

apply L'Hôpital's Rule, as shown below.

$$\lim_{x\to 0}\frac{e^{2x}-1}{x}=\lim_{x\to 0}\frac{\frac{d}{dx}[e^{2x}-1]}{\frac{d}{dx}[x]}$$ Apply L'Hôpital's Rule.

$$=\lim_{x\to 0}\frac{2e^{2x}}{1}$$ Differentiate numerator and denominator.

$$=2$$ Evaluate the limit. ■

In the solution to Example 1, note that you actually do not know that the first limit is equal to the second limit until you have shown that the second limit exists. In other words, if the second limit had not existed, then it would not have been permissible to apply L'Hôpital's Rule.

Another form of L'Hôpital's Rule states that if the limit of $f(x)/g(x)$ as x approaches ∞ (or $-\infty$) produces the indeterminate form $0/0$ or ∞/∞, then

$$\lim_{x\to\infty}\frac{f(x)}{g(x)}=\lim_{x\to\infty}\frac{f'(x)}{g'(x)}$$

provided the limit on the right exists.

EXAMPLE 2 Indeterminate Form ∞/∞

Evaluate $\lim_{x\to\infty}\dfrac{\ln x}{x}$.

Solution Because direct substitution results in the indeterminate form ∞/∞, apply L'Hôpital's Rule to obtain

$$\lim_{x\to\infty}\frac{\ln x}{x}=\lim_{x\to\infty}\frac{\frac{d}{dx}[\ln x]}{\frac{d}{dx}[x]}$$ Apply L'Hôpital's Rule.

$$=\lim_{x\to\infty}\frac{1}{x}$$ Differentiate numerator and denominator.

$$=0.$$ Evaluate the limit. ■

TECHNOLOGY Use a graphing utility to graph $y_1=\ln x$ and $y_2=x$ in the same viewing window. Which function grows faster as x approaches ∞? How is this observation related to Example 2?

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Occasionally it is necessary to apply L'Hôpital's Rule more than once to remove an indeterminate form, as shown in Example 3.

EXAMPLE 3 Applying L'Hôpital's Rule More than Once

Evaluate $\lim_{x\to-\infty} \frac{x^2}{e^{-x}}$.

FOR FURTHER INFORMATION To read about the connection between Leonhard Euler and Guillaume L'Hôpital, see the article "When Euler Met l'Hôpital" by William Dunham in *Mathematics Magazine*. To view this article, go to *MathArticles.com*.

Solution Because direct substitution results in the indeterminate form ∞/∞, apply L'Hôpital's Rule.

$$\lim_{x\to-\infty} \frac{x^2}{e^{-x}} = \lim_{x\to-\infty} \frac{\frac{d}{dx}[x^2]}{\frac{d}{dx}[e^{-x}]} = \lim_{x\to-\infty} \frac{2x}{-e^{-x}}$$

This limit yields the indeterminate form $(-\infty)/(-\infty)$, so apply L'Hôpital's Rule again to obtain

$$\lim_{x\to-\infty} \frac{2x}{-e^{-x}} = \lim_{x\to-\infty} \frac{\frac{d}{dx}[2x]}{\frac{d}{dx}[-e^{-x}]} = \lim_{x\to-\infty} \frac{2}{e^{-x}} = 0.$$

In addition to the forms $0/0$ and ∞/∞, there are other indeterminate forms such as $0 \cdot \infty$, 1^∞, ∞^0, 0^0, and $\infty - \infty$. For example, consider the four limits that lead to the indeterminate form $0 \cdot \infty$.

$$\underbrace{\lim_{x\to0}\left(\frac{1}{x}\right)(x)}_{\text{Limit is 1.}}, \quad \underbrace{\lim_{x\to0}\left(\frac{2}{x}\right)(x)}_{\text{Limit is 2.}}, \quad \underbrace{\lim_{x\to\infty}\left(\frac{1}{e^x}\right)(x)}_{\text{Limit is 0.}}, \quad \underbrace{\lim_{x\to\infty}\left(\frac{1}{x}\right)(e^x)}_{\text{Limit is } \infty.}$$

Because each limit is different, it is clear that the form $0 \cdot \infty$ is indeterminate in the sense that it does not determine the value (or even the existence) of the limit. The remaining examples in this section show methods for evaluating some of the other indeterminate forms. Basically, you attempt to convert each form to $0/0$ or ∞/∞ so that L'Hôpital's Rule can be applied.

EXAMPLE 4 Indeterminate Form $0 \cdot \infty$

Evaluate $\lim_{x\to\infty} e^{-x}\sqrt{x}$.

Solution Because direct substitution produces the indeterminate form $0 \cdot \infty$, try to rewrite the limit to fit the form $0/0$ or ∞/∞. In this case, rewrite the limit to fit the second form.

$$\lim_{x\to\infty} e^{-x}\sqrt{x} = \lim_{x\to\infty} \frac{\sqrt{x}}{e^x}$$

Now, by L'Hôpital's Rule, you have

$$\lim_{x\to\infty} \frac{\sqrt{x}}{e^x} = \lim_{x\to\infty} \frac{1/(2\sqrt{x})}{e^x} \qquad \text{Differentiate numerator and denominator.}$$

$$= \lim_{x\to\infty} \frac{1}{2\sqrt{x}e^x} \qquad \text{Simplify.}$$

$$= 0. \qquad \text{Evaluate the limit.}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

When rewriting a limit in one of the forms $0/0$ or ∞/∞ does not seem to work, try the other form. For instance, in Example 4, you can write the limit as

$$\lim_{x\to\infty} e^{-x}\sqrt{x} = \lim_{x\to\infty} \frac{e^{-x}}{x^{-1/2}}$$

which yields the indeterminate form $0/0$. As it happens, applying L'Hôpital's Rule to this limit produces

$$\lim_{x\to\infty} \frac{e^{-x}}{x^{-1/2}} = \lim_{x\to\infty} \frac{-e^{-x}}{-1/(2x^{3/2})}$$

which also yields the indeterminate form $0/0$.

The indeterminate forms 1^∞, ∞^0, and 0^0 arise from limits of functions that have variable bases and variable exponents. When you previously encountered this type of function, you used logarithmic differentiation to find the derivative. You can use a similar procedure when taking limits, as shown in the next example.

EXAMPLE 5 Indeterminate Form 1^∞

Evaluate $\lim_{x\to\infty} \left(1 + \frac{1}{x}\right)^x$.

REMARK Note that the solution to Example 5 is an alternate proof of Theorem 5.15.

Solution Because direct substitution yields the indeterminate form 1^∞, you can proceed as follows. To begin, assume that the limit exists and is equal to y.

$$y = \lim_{x\to\infty} \left(1 + \frac{1}{x}\right)^x$$

Taking the natural logarithm of each side produces

$$\ln y = \ln\left[\lim_{x\to\infty} \left(1 + \frac{1}{x}\right)^x\right].$$

Because the natural logarithmic function is continuous, you can write

$$\begin{aligned}
\ln y &= \lim_{x\to\infty} \left[x \ln\left(1 + \frac{1}{x}\right)\right] && \text{Indeterminate form } \infty \cdot 0 \\
&= \lim_{x\to\infty} \left(\frac{\ln[1 + (1/x)]}{1/x}\right) && \text{Indeterminate form } 0/0 \\
&= \lim_{x\to\infty} \left(\frac{(-1/x^2)\{1/[1 + (1/x)]\}}{-1/x^2}\right) && \text{L'Hôpital's Rule} \\
&= \lim_{x\to\infty} \frac{1}{1 + (1/x)} && \text{Simplify.} \\
&= 1. && \text{Evaluate the limit.}
\end{aligned}$$

Now, because you have shown that

$$\ln y = 1$$

you can conclude that

$$y = e$$

and obtain

$$\lim_{x\to\infty} \left(1 + \frac{1}{x}\right)^x = e.$$

You can use a graphing utility to support this result, as shown in Figure 5.24.



The limit of $[1 + (1/x)]^x$ as x approaches infinity is e.
Figure 5.24

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

L'Hôpital's Rule can also be applied to one-sided limits, as demonstrated in Examples 6 and 7.

EXAMPLE 6 Indeterminate Form 0^0

See LarsonCalculus.com for an interactive version of this type of example.

Evaluate $\lim_{x\to 0^+} (\sin x)^x$.

Solution Because direct substitution produces the indeterminate form 0^0, you can proceed as shown below. To begin, assume that the limit exists and is equal to y.

$$\begin{aligned}
y &= \lim_{x\to 0^+} (\sin x)^x && \text{Indeterminate form } 0^0\\
\ln y &= \ln\left[\lim_{x\to 0^+} (\sin x)^x\right] && \text{Take natural log of each side.}\\
&= \lim_{x\to 0^+} \left[\ln(\sin x)^x\right] && \text{Continuity}\\
&= \lim_{x\to 0^+} \left[x \ln(\sin x)\right] && \text{Indeterminate form } 0 \cdot (-\infty)\\
&= \lim_{x\to 0^+} \frac{\ln(\sin x)}{1/x} && \text{Indeterminate form } -\infty/\infty\\
&= \lim_{x\to 0^+} \frac{\cot x}{-1/x^2} && \text{L'Hôpital's Rule}\\
&= \lim_{x\to 0^+} \frac{-x^2}{\tan x} && \text{Indeterminate form } 0/0\\
&= \lim_{x\to 0^+} \frac{-2x}{\sec^2 x} && \text{L'Hôpital's Rule}\\
&= 0 && \text{Evaluate the limit.}
\end{aligned}$$

Now, because $\ln y = 0$, you can conclude that $y = e^0 = 1$, and it follows that

$$\lim_{x\to 0^+} (\sin x)^x = 1.$$

TECHNOLOGY When evaluating complicated limits such as the one in Example 6, it is helpful to check the reasonableness of the solution with a graphing utility. For instance, the calculations in the table and the graph in the figure (see below) are consistent with the conclusion that $(\sin x)^x$ approaches 1 as x approaches 0 from the right.

x	1	0.1	0.01	0.001	0.0001	0.00001
$(\sin x)^x$	0.8415	0.7942	0.9550	0.9931	0.9991	0.9999



The limit of $(\sin x)^x$ is 1 as x approaches 0 from the right.

Use a graphing utility to estimate the limits $\lim_{x\to 0} (1 - \cos x)^x$ and $\lim_{x\to 0^+} (\tan x)^x$. Then try to verify your estimates analytically.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 7 Indeterminate Form $\infty - \infty$

Evaluate $\lim_{x \to 1^+} \left(\frac{1}{\ln x} - \frac{1}{x - 1} \right)$.

Solution Because direct substitution yields the indeterminate form $\infty - \infty$, try to rewrite the expression to produce a form to which you can apply L'Hôpital's Rule. In this case, you can combine the two fractions to obtain

$$\lim_{x \to 1^+} \left(\frac{1}{\ln x} - \frac{1}{x - 1} \right) = \lim_{x \to 1^+} \frac{x - 1 - \ln x}{(x - 1) \ln x}.$$

Now, because direct substitution produces the indeterminate form $0/0$, apply L'Hôpital's Rule to obtain

$$\begin{aligned} \lim_{x \to 1^+} \frac{x - 1 - \ln x}{(x - 1) \ln x} &= \lim_{x \to 1^+} \frac{\frac{d}{dx}[x - 1 - \ln x]}{\frac{d}{dx}[(x - 1) \ln x]} \\ &= \lim_{x \to 1^+} \frac{1 - (1/x)}{(x - 1)(1/x) + \ln x} \\ &= \lim_{x \to 1^+} \frac{x - 1}{x - 1 + x \ln x}. \end{aligned}$$

This limit also yields the indeterminate form $0/0$, so apply L'Hôpital's Rule again.

$$\lim_{x \to 1^+} \frac{x - 1}{x - 1 + x \ln x} = \lim_{x \to 1^+} \frac{1}{1 + x(1/x) + \ln x} = \frac{1}{2}$$

You can check the reasonableness of this solution using a table, as shown at the left.

Table for Example 7

x	$\frac{1}{\ln x} - \frac{1}{x - 1}$
2	0.44270
1.5	0.46630
1.1	0.49206
1.01	0.49917
1.001	0.49992
1.0001	0.49999
1.00001	0.50000

The forms $0/0$, ∞/∞, $\infty - \infty$, $0 \cdot \infty$, 0^0, 1^∞, and ∞^0 have been identified as *indeterminate*. There are similar forms that you should recognize as "determinate."

$\infty + \infty \to \infty$ Limit is positive infinity.

$-\infty - \infty \to -\infty$ Limit is negative infinity.

$0^\infty \to 0$ Limit is zero.

$0^{-\infty} \to \infty$ Limit is positive infinity.

REMARK You are asked to verify that 0^∞ and $0^{-\infty}$ are "determinate" in Exercises 112 and 113, respectively.

As a final comment, remember that L'Hôpital's Rule can be applied only to quotients leading to the indeterminate forms $0/0$ and ∞/∞. For instance, the application of L'Hôpital's Rule shown below is *incorrect*.

$$\lim_{x \to 0} \frac{e^x}{x} \overset{\text{(=)}}{=} \lim_{x \to 0} \frac{e^x}{1} = 1$$

Incorrect use of L'Hôpital's Rule

The reason this application is incorrect is that, even though the limit of the denominator is 0, the limit of the numerator is 1, which means that the hypotheses of L'Hôpital's Rule have not been satisfied.

Exploration

In each example in this section, L'Hôpital's Rule is used to find a limit that exists. It can also be used to conclude that a limit is infinite. For instance, use L'Hôpital's Rule to show that $\lim_{x \to \infty} e^x/x = \infty$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

5.6 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain the benefit of L'Hôpital's Rule.
2. For each limit, use direct substitution. Then identify the form of the limit as either indeterminate or not.

(a) $\lim_{x\to 0} \frac{x^2}{\sin 2x}$ (b) $\lim_{x\to\infty} (e^x + x^2)$

(c) $\lim_{x\to\infty} (\ln x - e^x)$ (d) $\lim_{x\to 0^+} \left(\ln x^2 - \frac{1}{x}\right)$

Numerical and Graphical Analysis **In Exercises 3–6, complete the table and use the result to estimate the limit. Use a graphing utility to graph the function to confirm your result.**

3. $\lim_{x\to 0} \frac{\sin 4x}{\sin 3x}$

x	-0.1	-0.01	-0.001	0	0.001	0.01	0.1
$f(x)$				?			

4. $\lim_{x\to 0} \frac{1 - e^x}{x}$

x	-0.1	-0.01	-0.001	0	0.001	0.01	0.1
$f(x)$				?			

5. $\lim_{x\to\infty} x^5 e^{-x/100}$

x	1	10	10^2	10^3	10^4	10^5
$f(x)$						

6. $\lim_{x\to\infty} \frac{6x}{\sqrt{3x^2 - 2x}}$

x	1	10	10^2	10^3	10^4	10^5
$f(x)$						

Using Two Methods **In Exercises 7–14, evaluate the limit (a) using techniques from Chapters 1 and 3 and (b) using L'Hôpital's Rule.**

7. $\lim_{x\to 4} \frac{3(x-4)}{x^2 - 16}$
8. $\lim_{x\to -4} \frac{2x^2 + 13x + 20}{x + 4}$
9. $\lim_{x\to 6} \frac{\sqrt{x+10} - 4}{x - 6}$
10. $\lim_{x\to -1} \left(\frac{1 - \sqrt{x+2}}{x+1}\right)$
11. $\lim_{x\to 0} \left(\frac{2 - 2\cos x}{6x}\right)$
12. $\lim_{x\to 0} \frac{\sin 6x}{4x}$
13. $\lim_{x\to\infty} \frac{5x^2 - 3x + 1}{3x^2 - 5}$
14. $\lim_{x\to\infty} \frac{x^3 + 2x}{4 - x}$

Evaluating a Limit **In Exercises 15–42, evaluate the limit, using L'Hôpital's Rule if necessary.**

15. $\lim_{x\to 3} \frac{x^2 - 2x - 3}{x - 3}$
16. $\lim_{x\to -2} \frac{x^2 - 3x - 10}{x + 2}$
17. $\lim_{x\to 0} \frac{\sqrt{25 - x^2} - 5}{x}$
18. $\lim_{x\to 5^-} \frac{\sqrt{25 - x^2}}{x - 5}$
19. $\lim_{x\to 0^+} \frac{e^x - (1 + x)}{x^3}$
20. $\lim_{x\to 1} \frac{\ln x^3}{x^2 - 1}$
21. $\lim_{x\to 1} \frac{x^{11} - 1}{x^4 - 1}$
22. $\lim_{x\to 1} \frac{x^a - 1}{x^b - 1}$, where $a, b \neq 0$
23. $\lim_{x\to 0} \frac{\sin 3x}{\sin 5x}$
24. $\lim_{x\to 0} \frac{\sin ax}{\sin bx}$, where $a, b \neq 0$
25. $\lim_{x\to\infty} \frac{7x^3 - 2x + 1}{6x^3 + 1}$
26. $\lim_{x\to\infty} \frac{8 - x}{x^3}$
27. $\lim_{x\to\infty} \frac{x^2 + 4x + 7}{x - 6}$
28. $\lim_{x\to\infty} \frac{x^3}{x + 2}$
29. $\lim_{x\to\infty} \frac{x^3}{e^{x/2}}$
30. $\lim_{x\to\infty} \frac{e^{x^2}}{1 - x^3}$
31. $\lim_{x\to\infty} \frac{x}{\sqrt{x^2 + 1}}$
32. $\lim_{x\to\infty} \frac{x^2}{\sqrt{x^2 + 1}}$
33. $\lim_{x\to\infty} \frac{\cos x}{x}$
34. $\lim_{x\to\infty} \frac{\sin x}{x - \pi}$
35. $\lim_{x\to\infty} \frac{\ln x}{x^2}$
36. $\lim_{x\to\infty} \frac{\ln x^4}{x^3}$
37. $\lim_{x\to\infty} \frac{e^x}{x^4}$
38. $\lim_{x\to\infty} \frac{e^{2x-9}}{3x}$
39. $\lim_{x\to 0} \frac{\sin 5x}{\tan 9x}$
40. $\lim_{x\to 1} \frac{\ln x}{\sin \pi x}$
41. $\lim_{x\to\infty} \frac{\int_1^x \ln(e^{4t-1})\, dt}{x}$
42. $\lim_{x\to 1^+} \frac{\int_1^x \cos\theta\, d\theta}{x - 1}$

Evaluating a Limit **In Exercises 43–62, (a) describe the type of indeterminate form (if any) that is obtained by direct substitution. (b) Evaluate the limit, using L'Hôpital's Rule if necessary. (c) Use a graphing utility to graph the function and verify the result in part (b).**

43. $\lim_{x\to\infty} x \ln x$
44. $\lim_{x\to 0^+} x^3 \cot x$
45. $\lim_{x\to\infty} x \sin \frac{1}{x}$
46. $\lim_{x\to\infty} x \tan \frac{1}{x}$
47. $\lim_{x\to 0^+} (e^x + x)^{2/x}$
48. $\lim_{x\to 0^+} \left(1 + \frac{1}{x}\right)^x$
49. $\lim_{x\to\infty} x^{1/x}$
50. $\lim_{x\to 0^+} x^{1/x}$
51. $\lim_{x\to 0^+} (1 + x)^{1/x}$
52. $\lim_{x\to\infty} (1 + x)^{1/x}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

53. $\lim_{x\to 0^+} 3x^{x/2}$

54. $\lim_{x\to 4^+} [3(x-4)]^{x-4}$

55. $\lim_{x\to 1^+} (\ln x)^{x-1}$

56. $\lim_{x\to 0^+} \left[\cos\left(\frac{\pi}{2} - x\right)\right]^x$

57. $\lim_{x\to 2^+} \left(\frac{8}{x^2-4} - \frac{x}{x-2}\right)$

58. $\lim_{x\to 2^+} \left(\frac{1}{x^2-4} - \frac{\sqrt{x-1}}{x^2-4}\right)$

59. $\lim_{x\to 1^+} \left(\frac{3}{\ln x} - \frac{2}{x-1}\right)$

60. $\lim_{x\to 0^+} \left(\frac{10}{x} - \frac{3}{x^2}\right)$

61. $\lim_{x\to \infty} (e^x - x)$

62. $\lim_{x\to \infty} \left(x - \sqrt{x^2+1}\right)$

Exploring Concepts

63. Find differentiable functions f and g that satisfy the specified condition such that

$$\lim_{x\to 5} f(x) = 0 \quad \text{and} \quad \lim_{x\to 5} g(x) = 0.$$

Explain how you obtained your answers. (*Note:* There are many correct answers.)

(a) $\lim_{x\to 5} \frac{f(x)}{g(x)} = 10$

(b) $\lim_{x\to 5} \frac{f(x)}{g(x)} = 0$

(c) $\lim_{x\to 5} \frac{f(x)}{g(x)} = \infty$

64. Find differentiable functions f and g such that

$$\lim_{x\to \infty} f(x) = \lim_{x\to \infty} g(x) = \infty \text{ and } \lim_{x\to \infty} [f(x) - g(x)] = 25.$$

Explain how you obtained your answers. (Note: There are many correct answers.)

65. Determine which of the following limits can be evaluated using L'Hôpital's Rule. Explain your reasoning. Do not evaluate the limit.

(a) $\lim_{x\to 2} \frac{x-2}{x^3-x-6}$

(b) $\lim_{x\to 0} \frac{x^2-4x}{2x-1}$

(c) $\lim_{x\to \infty} \frac{x^3}{e^x}$

(d) $\lim_{x\to 3} \frac{e^{x^2}-e^9}{x-3}$

(e) $\lim_{x\to 1} \frac{\cos \pi x}{\ln x}$

(f) $\lim_{x\to 1} \frac{1 + x(\ln x - 1)}{(x-1)\ln x}$

66. HOW DO YOU SEE IT? Use the graph of f to find each limit.



(a) $\lim_{x\to 1^-} f(x)$ (b) $\lim_{x\to 1^+} f(x)$ (c) $\lim_{x\to 1} f(x)$

67. Numerical Analysis Complete the table to show that x eventually "overpowers" $(\ln x)^4$.

x	10	10^2	10^4	10^6	10^8	10^{10}
$\frac{(\ln x)^4}{x}$						

68. Numerical Analysis Complete the table to show that e^x eventually "overpowers" x^5.

x	1	5	10	20	30	40	50	100
$\frac{e^x}{x^5}$								

Comparing Functions **In Exercises 69–74, use L'Hôpital's Rule to determine the comparative rates of increase of the functions $f(x) = x^m$, $g(x) = e^{nx}$, and $h(x) = (\ln x)^n$, where $n > 0$, $m > 0$, and $x \to \infty$.**

69. $\lim_{x\to \infty} \frac{x^2}{e^{5x}}$

70. $\lim_{x\to \infty} \frac{x^3}{e^{2x}}$

71. $\lim_{x\to \infty} \frac{(\ln x)^3}{x}$

72. $\lim_{x\to \infty} \frac{(\ln x)^2}{x^3}$

73. $\lim_{x\to \infty} \frac{(\ln x)^n}{x^m}$

74. $\lim_{x\to \infty} \frac{x^m}{e^{nx}}$

Asymptotes and Relative Extrema **In Exercises 75–78, find any asymptotes and relative extrema that may exist and use a graphing utility to graph the function.**

75. $y = x^{1/x}, \ x > 0$

76. $y = x^x, \ x > 0$

77. $y = 2xe^{-x}$

78. $y = \frac{\ln x}{x}$

Think About It **In Exercises 79–82, L'Hôpital's Rule is used incorrectly. Describe the error.**

79. $\lim_{x\to 2} \frac{3x^2+4x+1}{x^2-x-2} = \lim_{x\to 2} \frac{6x+4}{2x-1} = \lim_{x\to 2} \frac{6}{2} = 3$ ✗

80.
$$\lim_{x\to 0} \frac{e^{2x}-1}{e^x} = \lim_{x\to 0} \frac{2e^{2x}}{e^x}$$
$$= \lim_{x\to 0} 2e^x$$
$$= 2$$
✗

81.
$$\lim_{x\to 0} \frac{1-e^x}{x-x^2} = \lim_{x\to 0} \frac{-e^x}{1-2x}$$
$$= \lim_{x\to 0} \frac{-e^x}{-2}$$
$$= \frac{1}{2}$$
✗

82.
$$\lim_{x\to \infty} x \cos\frac{1}{x} = \lim_{x\to \infty} \frac{\cos(1/x)}{1/x}$$
$$= \lim_{x\to \infty} \frac{[-\sin(1/x)](1/x^2)}{-1/x^2}$$
$$= \lim_{x\to \infty} \sin\frac{1}{x}$$
$$= 0$$
✗

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Evaluating a Limit **In Exercises 83 and 84, evaluate the limit using L'Hôpital's Rule if necessary.**

83. $\lim_{x\to 0} \dfrac{e^x - 1 - x - \frac{x^2}{2}}{x^3}$

84. $\lim_{x\to 0} \dfrac{\ln(1+x) - x + \frac{x^2}{2}}{x^3}$

Analytic and Graphical Analysis **In Exercises 85 and 86, (a) explain why L'Hôpital's Rule cannot be used to find the limit, (b) find the limit analytically, and (c) use a graphing utility to graph the function and approximate the limit from the graph. Compare the result with that in part (b).**

85. $\lim_{x\to\infty} \dfrac{x}{\sqrt{x^2+1}}$

86. $\lim_{x\to \pi/2^-} \dfrac{\tan x}{\sec x}$

Graphical Analysis **In Exercises 87 and 88, graph $f(x)/g(x)$ and $f'(x)/g'(x)$ near $x = 0$. What do you notice about these ratios as $x \to 0$? How does this illustrate L'Hôpital's Rule?**

87. $f(x) = \sin 3x,\ g(x) = \sin 4x$

88. $f(x) = e^{3x} - 1,\ g(x) = x$

89. Electric Circuit The diagram shows a simple electric circuit consisting of a power source, a resistor, and an inductor. If voltage V is first applied at time $t = 0$, then the current I flowing through the circuit at time t is given by

$$I = \frac{V}{R}(1 - e^{-Rt/L})$$

where L is the inductance and R is the resistance. Use L'Hôpital's Rule to find the formula for the current by fixing V and L and letting R approach 0 from the right.



90. Velocity in a Resisting Medium The velocity v of an object falling through a resisting medium such as air or water is given by

$$v = \frac{32}{k}\left(1 - e^{-kt} + \frac{v_0 k e^{-kt}}{32}\right)$$

where v_0 is the initial velocity, t is the time in seconds, and k is the resistance constant of the medium. Use L'Hôpital's Rule to find the formula for the velocity of a falling body in a vacuum by fixing v_0 and t and letting k approach zero. (Assume that the downward direction is positive.)

91. The Gamma Function The gamma function $\Gamma(n)$ is defined in terms of the integral of the function given by $f(x) = x^{n-1}e^{-x}$, $n > 0$. Show that for any fixed value of n, the limit of $f(x)$ as x approaches infinity is zero.

92. Compound Interest The formula for the amount A in a savings account compounded n times per year for t years at an interest rate r and an initial deposit of P is given by

$$A = P\left(1 + \frac{r}{n}\right)^{nt}.$$

Use L'Hôpital's Rule to show that the limiting formula as the number of compoundings per year approaches infinity is given by $A = Pe^{rt}$.

Extended Mean Value Theorem **In Exercises 93–96, verify that the Extended Mean Value Theorem can be applied to the functions f and g on the closed interval $[a, b]$. Then find all values c in the open interval (a, b) such that**

$$\frac{f'(c)}{g'(c)} = \frac{f(b) - f(a)}{g(b) - g(a)}.$$

	Functions	Interval
93.	$f(x) = x^3,\ g(x) = x^2 + 1$	$[0, 1]$
94.	$f(x) = \dfrac{1}{x},\ g(x) = x^2 - 4$	$[1, 2]$
95.	$f(x) = \sin x,\ g(x) = \cos x$	$\left[0, \dfrac{\pi}{2}\right]$
96.	$f(x) = \ln x,\ g(x) = x^3$	$[1, 4]$

True or False? **In Exercises 97–102, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

97. A limit of the form $\infty/0$ is indeterminate.

98. A limit of the form $\infty \cdot \infty$ is indeterminate.

99. An indeterminate form does not guarantee the existence of a limit.

100. $\lim_{x\to 0} \dfrac{x^2 + x + 1}{x} = \lim_{x\to 0} \dfrac{2x + 1}{1} = 1$

101. If $p(x)$ is a polynomial, then $\lim_{x\to\infty} \dfrac{p(x)}{e^x} = 0$.

102. If $\lim_{x\to\infty} \dfrac{f(x)}{g(x)} = 1$, then $\lim_{x\to\infty} [f(x) - g(x)] = 0$.

103. Area Find the limit, as x approaches 0, of the ratio of the area of the triangle to the total shaded area in the figure.



104. Evaluating a Limit Evaluate the limit.

$$\lim_{x\to 0} \frac{\sin 5x \sin 7x}{x \sin 4x}$$

Use a graphing utility to verify the result.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Continuous Function **In Exercises 105 and 106, find the value of c that makes the function continuous at $x = 0$.**

105. $f(x) = \begin{cases} \dfrac{4x - 2\sin 2x}{2x^3}, & x \neq 0 \\ c, & x = 0 \end{cases}$

106. $f(x) = \begin{cases} (e^x + x)^{1/x}, & x \neq 0 \\ c, & x = 0 \end{cases}$

107. Finding Values Find the values of a and b such that

$$\lim_{x\to 0} \frac{a - \cos bx}{x^2} = 2.$$

108. Evaluating a Limit Use a graphing utility to graph

$$f(x) = \frac{x^k - 1}{k}$$

for $k = 1$, 0.1, and 0.01. Then evaluate the limit

$$\lim_{k\to 0^+} \frac{x^k - 1}{k}.$$

109. Finding a Derivative

(a) Let $f'(x)$ be continuous. Show that

$$\lim_{h\to 0} \frac{f(x + h) - f(x - h)}{2h} = f'(x).$$

(b) Explain the result of part (a) graphically.



110. Finding a Second Derivative Let $f''(x)$ be continuous. Show that

$$\lim_{h\to 0} \frac{f(x + h) - 2f(x) + f(x - h)}{h^2} = f''(x).$$

111. Evaluating a Limit Consider the limit

$$\lim_{x\to 0^+} (-x \ln x).$$

(a) Describe the type of indeterminate form that is obtained by direct substitution.

(b) Evaluate the limit. Use a graphing utility to verify the result.

FOR FURTHER INFORMATION For a geometric approach to this exercise, see the article "A Geometric Proof of $\lim_{d\to 0^+} (-d \ln d) = 0$" by John H. Mathews in *The College Mathematics Journal*. To view this article, go to *MathArticles.com*.

112. Proof Prove that if $f(x) \geq 0$, $\lim_{x\to a} f(x) = 0$, and $\lim_{x\to a} g(x) = \infty$, then $\lim_{x\to a} f(x)^{g(x)} = 0$.

113. Proof Prove that if $f(x) \geq 0$, $\lim_{x\to a} f(x) = 0$, and $\lim_{x\to a} g(x) = -\infty$, then $\lim_{x\to a} f(x)^{g(x)} = \infty$.

114. Think About It Use two different methods to find the limit

$$\lim_{x\to\infty} \frac{\ln x^m}{\ln x^n}$$

where $m > 0$, $n > 0$, and $x > 0$.

115. Indeterminate Forms Show that the indeterminate forms 0^0, ∞^0, and 1^∞ do not always have a value of 1 by evaluating each limit.

(a) $\lim_{x\to 0^+} x^{(\ln 2)/(1 + \ln x)}$

(b) $\lim_{x\to\infty} x^{(\ln 2)/(1 + \ln x)}$

(c) $\lim_{x\to 0} (x + 1)^{(\ln 2)/x}$

116. Calculus History In L'Hôpital's 1696 calculus textbook, he illustrated his rule using the limit of the function

$$f(x) = \frac{\sqrt{2a^3x - x^4} - a\sqrt[3]{a^2x}}{a - \sqrt[4]{ax^3}}$$

as x approaches a, $a > 0$. Find this limit.

117. Finding a Limit Consider the function

$$h(x) = \frac{x + \sin x}{x}.$$

(a) Use a graphing utility to graph the function. Then use the *zoom* and *trace* features to investigate $\lim_{x\to\infty} h(x)$.

(b) Find $\lim_{x\to\infty} h(x)$ analytically by writing

$$h(x) = \frac{x}{x} + \frac{\sin x}{x}.$$

(c) Can you use L'Hôpital's Rule to find $\lim_{x\to\infty} h(x)$? Explain your reasoning.

118. Evaluating a Limit Let $f(x) = x + x\sin x$ and $g(x) = x^2 - 4$.

(a) Show that $\lim_{x\to\infty} \frac{f(x)}{g(x)} = 0$.

(b) Show that $\lim_{x\to\infty} f(x) = \infty$ and $\lim_{x\to\infty} g(x) = \infty$.

(c) Evaluate the limit

$$\lim_{x\to\infty} \frac{f'(x)}{g'(x)}.$$

What do you notice?

(d) Do your answers to parts (a) through (c) contradict L'Hôpital's Rule? Explain your reasoning.

PUTNAM EXAM CHALLENGE

119. Evaluate $\lim_{x\to\infty} \left[\frac{1}{x} \cdot \frac{a^x - 1}{a - 1}\right]^{1/x}$ where $a > 0$, $a \neq 1$.

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

5.7 Inverse Trigonometric Functions: Differentiation

GO DIGITAL

- **Define the six inverse trigonometric functions and use their properties.**
- **Differentiate an inverse trigonometric function.**
- **Review the basic differentiation rules for elementary functions.**



The sine function is one-to-one on $[-\pi/2, \pi/2]$.
Figure 5.25

Inverse Trigonometric Functions

This section begins with a rather surprising statement: *None of the six basic trigonometric functions has an inverse function.* This statement is true because all six trigonometric functions are periodic and therefore are not one-to-one. In this section, you will examine these six functions to determine whether their domains can be redefined in such a way that they will have inverse functions on the *restricted domains.*

In Example 4 of Section 5.3, you learned that the sine function is increasing (and therefore is one-to-one) on the interval

$$\left[-\frac{\pi}{2}, \frac{\pi}{2}\right]$$

as shown in Figure 5.25. On this interval, the inverse of the *restricted* sine function is defined as

$$y = \arcsin x \quad \text{if and only if} \quad \sin y = x$$

where $-1 \le x \le 1$ and $-\pi/2 \le \arcsin x \le \pi/2$.

Under suitable restrictions, each of the six trigonometric functions is one-to-one and so has an inverse function, as shown in the next definition. (Note that the term "iff" is used to represent the phrase "if and only if.")

REMARK The notation $\arcsin x$ is read as "the arcsine of x" or sometimes "the angle whose sine is x." An alternative notation for the inverse sine function is $\sin^{-1} x$, which is consistent with the inverse function notation $f^{-1}(x)$.

Definitions of Inverse Trigonometric Functions

Function	Domain	Range
$y = \arcsin x$ iff $\sin y = x$	$-1 \le x \le 1$	$-\frac{\pi}{2} \le y \le \frac{\pi}{2}$
$y = \arccos x$ iff $\cos y = x$	$-1 \le x \le 1$	$0 \le y \le \pi$
$y = \arctan x$ iff $\tan y = x$	$-\infty < x < \infty$	$-\frac{\pi}{2} < y < \frac{\pi}{2}$
$y = \operatorname{arccot} x$ iff $\cot y = x$	$-\infty < x < \infty$	$0 < y < \pi$
$y = \operatorname{arcsec} x$ iff $\sec y = x$	$\lvert x\rvert \ge 1$	$0 \le y \le \pi, \quad y \ne \frac{\pi}{2}$
$y = \operatorname{arccsc} x$ iff $\csc y = x$	$\lvert x\rvert \ge 1$	$-\frac{\pi}{2} \le y \le \frac{\pi}{2}, \quad y \ne 0$

Exploration

The Inverse Secant Function In this text, the inverse secant function is defined by restricting the domain of the secant function to the intervals $[0, \pi/2) \cup (\pi/2, \pi]$. Most other texts and reference books use this domain, but some do not. What other domains might make sense? Explain your reasoning graphically. Some calculators do not have a key for the inverse secant function. In such cases, how can you use the calculator to evaluate the inverse secant function?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

The graphs of the six inverse trigonometric functions are shown in Figure 5.26.



Domain: $[-1, 1]$
Range: $[-\pi/2, \pi/2]$



Domain: $[-1, 1]$
Range: $[0, \pi]$



Domain: $(-\infty, \infty)$
Range: $(-\pi/2, \pi/2)$



Domain: $(-\infty, -1] \cup [1, \infty)$
Range: $[-\pi/2, 0) \cup (0, \pi/2]$



Domain: $(-\infty, -1] \cup [1, \infty)$
Range: $[0, \pi/2) \cup (\pi/2, \pi]$



Domain: $(-\infty, \infty)$
Range: $(0, \pi)$

Figure 5.26

When evaluating inverse trigonometric functions, remember that they denote angles in *radian measure*. (For a review of radian measure, see Section P.4.)

EXAMPLE 1 Evaluating Inverse Trigonometric Functions

Evaluate each function.

a. $\arcsin\left(-\frac{1}{2}\right)$ **b.** $\arccos 0$ **c.** $\arctan \sqrt{3}$ **d.** $\arcsin(0.3)$

Solution

a. By definition, $y = \arcsin\left(-\frac{1}{2}\right)$ implies that $\sin y = -\frac{1}{2}$. In the interval $[-\pi/2, \pi/2]$, the correct value of y is $-\pi/6$.

$$\arcsin\left(-\frac{1}{2}\right) = -\frac{\pi}{6}$$

b. By definition, $y = \arccos 0$ implies that $\cos y = 0$. In the interval $[0, \pi]$, you have $y = \pi/2$.

$$\arccos 0 = \frac{\pi}{2}$$

c. By definition, $y = \arctan \sqrt{3}$ implies that $\tan y = \sqrt{3}$. In the interval $(-\pi/2, \pi/2)$, you have $y = \pi/3$.

$$\arctan \sqrt{3} = \frac{\pi}{3}$$

d. Using a calculator set in *radian* mode produces

$$\arcsin(0.3) \approx 0.305.$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Inverse functions have the properties $f(f^{-1}(x)) = x$ and $f^{-1}(f(x)) = x$. When applying these properties to inverse trigonometric functions, remember that the trigonometric functions have inverse functions only in restricted domains. For x-values outside these domains, these two properties do not hold. For example, $\arcsin(\sin \pi)$ is equal to 0, not π.

REMARK When using these inverse properties, remember that the domains are restricted. For example,

$$\tan^{-1}\left(\tan \frac{3\pi}{4}\right) \neq \frac{3\pi}{4}$$

because $3\pi/4$ is not in the interval $(-\pi/2, \pi/2)$. Rather,

$$\tan^{-1}\left(\tan \frac{3\pi}{4}\right) = \tan^{-1}(-1) = -\frac{\pi}{4}.$$

Properties of Inverse Trigonometric Functions

If $-1 \leq x \leq 1$ and $-\pi/2 \leq y \leq \pi/2$, then

$$\sin(\arcsin x) = x \quad \text{and} \quad \arcsin(\sin y) = y.$$

If $-\pi/2 < y < \pi/2$, then

$$\tan(\arctan x) = x \quad \text{and} \quad \arctan(\tan y) = y.$$

If $|x| \geq 1$ and $0 \leq y < \pi/2$ or $\pi/2 < y \leq \pi$, then

$$\sec(\operatorname{arcsec} x) = x \quad \text{and} \quad \operatorname{arcsec}(\sec y) = y.$$

Similar properties hold for the other inverse trigonometric functions.

EXAMPLE 2 Solving an Equation

$$\arctan(2x - 3) = \frac{\pi}{4} \qquad \text{Original equation}$$

$$\tan[\arctan(2x - 3)] = \tan\frac{\pi}{4} \qquad \text{Take tangent of each side.}$$

$$2x - 3 = 1 \qquad \tan(\arctan x) = x$$

$$x = 2 \qquad \text{Solve for } x.$$

Some problems in calculus require that you evaluate expressions such as $\cos(\arcsin x)$, as shown in Example 3.

REMARK To review the right triangle definitions of trigonometric functions, see Section P.4.

EXAMPLE 3 Using Right Triangles

a. Given $y = \arcsin x$, where $0 < y < \pi/2$, find $\cos y$.

b. Given $y = \operatorname{arcsec}(\sqrt{5}/2)$, find $\tan y$.

Solution

a. Because $y = \arcsin x$, you know that $\sin y = x$. This relationship between x and y can be represented by a right triangle, as shown in the figure at the right.



$y = \arcsin x$

$$\cos y = \cos(\arcsin x) = \frac{\text{adj}}{\text{hyp}} = \sqrt{1 - x^2}$$

(This result is also valid for $-\pi/2 < y < 0$.)

b. Use the right triangle shown in the figure at the left.



$y = \operatorname{arcsec}\dfrac{\sqrt{5}}{2}$

$$\tan y = \tan\left(\operatorname{arcsec}\frac{\sqrt{5}}{2}\right) = \frac{\text{opp}}{\text{adj}} = \frac{1}{2}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Derivatives of Inverse Trigonometric Functions

In Section 5.1, you learned that the derivative of the *transcendental* function $f(x) = \ln x$ is the *algebraic* function $f'(x) = 1/x$. You will now learn that the derivatives of the inverse trigonometric functions also are algebraic (even though the inverse trigonometric functions are themselves transcendental).

The next theorem lists the derivatives of the six inverse trigonometric functions. Note that the derivatives of arccos u, arccot u, and arccsc u are the *negatives* of the derivatives of arcsin u, arctan u, and arcsec u, respectively.

REMARK There is no common agreement on the definition of arcsec x (or arccsc x) for negative values of x. For the definition of arcsec x in this text, the range was chosen to preserve the reciprocal identity

$$\operatorname{arcsec} x = \arccos \frac{1}{x}.$$

One consequence of this definition is that its graph has a positive slope at every x-value in its domain. (See Figure 5.26.) This accounts for the absolute value sign in the formula for the derivative of arcsec x.

THEOREM 5.18 Derivatives of Inverse Trigonometric Functions

Let u be a differentiable function of x.

$$\frac{d}{dx}[\arcsin u] = \frac{u'}{\sqrt{1-u^2}} \qquad \frac{d}{dx}[\arccos u] = \frac{-u'}{\sqrt{1-u^2}}$$

$$\frac{d}{dx}[\arctan u] = \frac{u'}{1+u^2} \qquad \frac{d}{dx}[\operatorname{arccot} u] = \frac{-u'}{1+u^2}$$

$$\frac{d}{dx}[\operatorname{arcsec} u] = \frac{u'}{|u|\sqrt{u^2-1}} \qquad \frac{d}{dx}[\operatorname{arccsc} u] = \frac{-u'}{|u|\sqrt{u^2-1}}$$

Proofs for arcsin u and arccos u are given in Appendix A. [The proofs for the other rules are left as an exercise (see Exercise 94).]

TECHNOLOGY Some graphing utilities do not have the arcsecant function. In such cases, use

$$f(x) = \operatorname{arcsec} x = \arccos \frac{1}{x}.$$

EXAMPLE 4 Differentiating Inverse Trigonometric Functions

a. $\dfrac{d}{dx}[\arcsin(2x)] = \dfrac{2}{\sqrt{1-(2x)^2}} = \dfrac{2}{\sqrt{1-4x^2}}$ $u = 2x$

b. $\dfrac{d}{dx}[\arctan(3x)] = \dfrac{3}{1+(3x)^2} = \dfrac{3}{1+9x^2}$ $u = 3x$

c. $\dfrac{d}{dx}[\arcsin\sqrt{x}] = \dfrac{(1/2)x^{-1/2}}{\sqrt{1-x}} = \dfrac{1}{2\sqrt{x}\sqrt{1-x}} = \dfrac{1}{2\sqrt{x-x^2}}$ $u = \sqrt{x} = x^{1/2}$

d. $\dfrac{d}{dx}[\operatorname{arcsec} e^{2x}] = \dfrac{2e^{2x}}{e^{2x}\sqrt{(e^{2x})^2-1}} = \dfrac{2}{\sqrt{e^{4x}-1}}$ $u = e^{2x}$

The absolute value sign is not necessary because $e^{2x} > 0$.

EXAMPLE 5 A Derivative That Can Be Simplified

$$\begin{aligned} y &= \arcsin x + x\sqrt{1-x^2} \\ y' &= \frac{1}{\sqrt{1-x^2}} + x\left(\frac{1}{2}\right)(-2x)(1-x^2)^{-1/2} + \sqrt{1-x^2} \\ &= \frac{1}{\sqrt{1-x^2}} - \frac{x^2}{\sqrt{1-x^2}} + \sqrt{1-x^2} \\ &= \sqrt{1-x^2} + \sqrt{1-x^2} \\ &= 2\sqrt{1-x^2} \end{aligned}$$

Example 5 shows one of the benefits of inverse trigonometric functions—they can be used to integrate common algebraic functions. For instance, from the result shown in the example, it follows that

$$\int \sqrt{1-x^2}\,dx = \frac{1}{2}\left(\arcsin x + x\sqrt{1-x^2}\right).$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



The graph of $y = (\arctan x)^2$ has a horizontal asymptote at $y = \pi^2/4$.
Figure 5.27

EXAMPLE 6 Analyzing an Inverse Trigonometric Graph

Analyze the graph of $y = (\arctan x)^2$.

Solution By examining the derivative of y with respect to x

$$y' = 2(\arctan x)\left(\frac{1}{1 + x^2}\right) \qquad \text{Differentiate with respect to } x.$$

$$= \frac{2 \arctan x}{1 + x^2} \qquad \text{Simplify.}$$

you can determine that the only critical number is $x = 0$. By the First Derivative Test, this value corresponds to a relative minimum at $(0, 0)$. From the first derivative, it follows that the graph is decreasing on the interval $(-\infty, 0)$ and increasing on $(0, \infty)$. From the second derivative

$$y'' = \frac{(1 + x^2)\left(\frac{2}{1 + x^2}\right) - (2 \arctan x)(2x)}{(1 + x^2)^2} \qquad \text{Differentiate with respect to } x.$$

$$= \frac{2(1 - 2x \arctan x)}{(1 + x^2)^2} \qquad \text{Simplify.}$$

it follows that points of inflection occur when $2x \arctan x = 1$. Using Newton's Method, these points occur when $x \approx \pm 0.765$. Finally, because

$$\lim_{x \to \pm\infty} (\arctan x)^2 = \frac{\pi^2}{4} \qquad \text{Limit as } x \text{ approaches } -\infty \text{ and } +\infty$$

it follows that the graph has a horizontal asymptote at $y = \pi^2/4$. The graph is shown in Figure 5.27.

EXAMPLE 7 Maximizing an Angle

See LarsonCalculus.com for an interactive version of this type of example.

A photographer is taking a picture of a painting hung in an art gallery. The height of the painting is 4 feet. The camera lens is 1 foot below the lower edge of the painting, as shown in the figure at the right. How far should the camera be from the painting to maximize the angle subtended by the camera lens?



Not drawn to scale

The camera should be 2.236 feet from the painting to maximize the angle β.

Solution In the figure, let β be the angle to be maximized.

$$\beta = \theta - \alpha = \operatorname{arccot} \frac{x}{5} - \operatorname{arccot} x$$

Differentiating with respect to x produces

$$\frac{d\beta}{dx} = \frac{-1/5}{1 + (x^2/25)} - \frac{-1}{1 + x^2}$$

$$= \frac{-5}{25 + x^2} + \frac{1}{1 + x^2}$$

$$= \frac{4(5 - x^2)}{(25 + x^2)(1 + x^2)}.$$

Because $d\beta/dx = 0$ when $x = \sqrt{5}$, you can conclude from the First Derivative Test that this distance yields a maximum value of β. So, the distance is $x \approx 2.236$ feet and the angle is $\beta \approx 0.7297$ radian $\approx 41.81°$.

REMARK In Example 7, you could also let $\theta = \operatorname{arctan}(5/x)$ and $\alpha = \operatorname{arctan}(1/x)$. Although these expressions are more difficult to use than those in Example 7, you should obtain the same answer. Try verifying this.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



GALILEO GALILEI (1564–1642)

Galileo's approach to science departed from the accepted Aristotelian view that nature had describable *qualities*, such as "fluidity" and "potentiality." He chose to describe the physical world in terms of measurable *quantities*, such as time, distance, force, and mass. *See LarsonCalculus.com to read more of this biography.*

GO DIGITAL

Review of Basic Differentiation Rules

In the 1600s, Europe was ushered into the scientific age by such great thinkers as Descartes, Galileo, Huygens, Newton, and Kepler. These men believed that nature is governed by basic laws—laws that can, for the most part, be written in terms of mathematical equations. One of the most influential publications of this period—*Dialogue on the Great World Systems*, by Galileo Galilei—has become a classic description of modern scientific thought.

As mathematics has developed during the past few hundred years, a small number of elementary functions have proven sufficient for modeling most* phenomena in physics, chemistry, biology, engineering, economics, and a variety of other fields. An **elementary function** is a function from the following list or one that can be formed as the sum, product, quotient, or composition of functions in the list.

Algebraic Functions	**Transcendental Functions**
Polynomial functions	Logarithmic functions
Rational functions	Exponential functions
Functions involving radicals	Trigonometric functions
	Inverse trigonometric functions

With the differentiation rules introduced so far in the text, you can differentiate *any* elementary function. For convenience, these differentiation rules are summarized below.

Basic Differentiation Rules for Elementary Functions

1. $\frac{d}{dx}[cu] = cu'$
2. $\frac{d}{dx}[u \pm v] = u' \pm v'$
3. $\frac{d}{dx}[uv] = uv' + vu'$
4. $\frac{d}{dx}\left[\frac{u}{v}\right] = \frac{vu' - uv'}{v^2}$
5. $\frac{d}{dx}[c] = 0$
6. $\frac{d}{dx}[u^n] = nu^{n-1}u'$
7. $\frac{d}{dx}[x] = 1$
8. $\frac{d}{dx}[|u|] = \frac{u}{|u|}(u'), \quad u \neq 0$
9. $\frac{d}{dx}[\ln u] = \frac{u'}{u}$
10. $\frac{d}{dx}[e^u] = e^u u'$
11. $\frac{d}{dx}[\log_a u] = \frac{u'}{(\ln a)u}$
12. $\frac{d}{dx}[a^u] = (\ln a)a^u u'$
13. $\frac{d}{dx}[\sin u] = (\cos u)u'$
14. $\frac{d}{dx}[\cos u] = -(\sin u)u'$
15. $\frac{d}{dx}[\tan u] = (\sec^2 u)u'$
16. $\frac{d}{dx}[\cot u] = -(\csc^2 u)u'$
17. $\frac{d}{dx}[\sec u] = (\sec u \tan u)u'$
18. $\frac{d}{dx}[\csc u] = -(\csc u \cot u)u'$
19. $\frac{d}{dx}[\arcsin u] = \frac{u'}{\sqrt{1 - u^2}}$
20. $\frac{d}{dx}[\arccos u] = \frac{-u'}{\sqrt{1 - u^2}}$
21. $\frac{d}{dx}[\arctan u] = \frac{u'}{1 + u^2}$
22. $\frac{d}{dx}[\operatorname{arccot} u] = \frac{-u'}{1 + u^2}$
23. $\frac{d}{dx}[\operatorname{arcsec} u] = \frac{u'}{|u|\sqrt{u^2 - 1}}$
24. $\frac{d}{dx}[\operatorname{arccsc} u] = \frac{-u'}{|u|\sqrt{u^2 - 1}}$

FOR FURTHER INFORMATION

For more on the derivative of the arctangent function, see the article "Differentiating the Arctangent Directly" by Eric Key in *The College Mathematics Journal*. To view this article, go to *MathArticles.com*.

* Some important functions used in engineering and science (such as Bessel functions and gamma functions) are not elementary functions.

Pictorial Press Ltd/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

5.7 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe the meaning of $\arccos x$.
2. Give the definition of a restricted domain. Why are restricted domains necessary to define inverse trigonometric functions?
3. Which inverse trigonometric function has a range of $0 < y < \pi$?
4. Find the missing value.

$$\frac{d}{dx}[\operatorname{arccsc} x^3] = \frac{\square}{|x^3|\sqrt{x^6 - 1}}$$

Finding Coordinates In Exercises 5 and 6, determine the missing coordinates of the points on the graph of the function.

5.



6.



Evaluating Inverse Trigonometric Functions In Exercises 7–14, evaluate the expression without using a calculator.

7. $\arcsin \frac{1}{2}$
8. $\arcsin 0$
9. $\arccos \frac{1}{2}$
10. $\arccos(-1)$
11. $\arctan \frac{\sqrt{3}}{3}$
12. $\operatorname{arccot}(-\sqrt{3})$
13. $\operatorname{arccsc}(-\sqrt{2})$
14. $\operatorname{arcsec} 2$

Approximating Inverse Trigonometric Functions In Exercises 15–18, use a calculator to approximate the value. Round your answer to two decimal places.

15. $\arccos(0.051)$
16. $\arcsin(-0.39)$
17. $\operatorname{arcsec} 1.269$
18. $\operatorname{arccsc}(-4.487)$

Using a Right Triangle In Exercises 19–24, use the figure to write the expression in algebraic form given $y = \arccos x$, where $0 < y < \pi/2$.

19. $\cos y$
20. $\sin y$
21. $\tan y$
22. $\cot y$
23. $\sec y$
24. $\csc y$



Evaluating an Expression In Exercises 25–28, evaluate each expression without using a calculator. (*Hint:* Sketch a right triangle, as demonstrated in Example 3.)

25. (a) $\sin\left(\arctan \frac{3}{4}\right)$ (b) $\sec\left(\arcsin \frac{4}{5}\right)$
26. (a) $\tan\left(\arccos \frac{\sqrt{2}}{2}\right)$ (b) $\cos\left(\arcsin \frac{5}{13}\right)$
27. (a) $\cot\left[\arcsin\left(-\frac{1}{2}\right)\right]$ (b) $\csc\left[\arctan\left(-\frac{5}{12}\right)\right]$
28. (a) $\sec\left[\arctan\left(-\frac{3}{5}\right)\right]$ (b) $\tan\left[\arcsin\left(-\frac{5}{6}\right)\right]$

Simplifying an Expression Using a Right Triangle In Exercises 29–36, write the expression in algebraic form. (*Hint:* Sketch a right triangle, as demonstrated in Example 3.)

29. $\cos(\arcsin 2x)$
30. $\sec(\arctan 6x)$
31. $\sin(\operatorname{arcsec} x)$
32. $\cos(\operatorname{arccot} x)$
33. $\tan\left(\operatorname{arcsec} \frac{x}{3}\right)$
34. $\sec[\arcsin(x - 1)]$
35. $\csc\left(\arctan \frac{x}{\sqrt{2}}\right)$
36. $\cos\left(\arcsin \frac{x - h}{r}\right)$

Solving an Equation In Exercises 37–40, solve the equation for x.

37. $\arcsin(3x - \pi) = \frac{1}{2}$
38. $\arctan(2x - 5) = -1$
39. $\arcsin \sqrt{2x} = \arccos \sqrt{x}$
40. $\arccos x = \operatorname{arcsec} x$

Finding a Derivative In Exercises 41–56, find the derivative of the function.

41. $f(x) = \arcsin(x - 1)$
42. $f(t) = \operatorname{arccsc}(-t^2)$
43. $g(x) = 3 \arccos \frac{x}{2}$
44. $f(x) = \operatorname{arcsec} 2x$
45. $f(x) = \arctan e^x$
46. $f(x) = \operatorname{arccot} \sqrt{x}$
47. $g(x) = \dfrac{\arcsin 3x}{x}$
48. $h(x) = x^2 \arctan 5x$
49. $h(t) = \sin(\arccos t)$
50. $f(x) = \arcsin x + \arccos x$
51. $y = 2x \arccos x - 2\sqrt{1 - x^2}$
52. $y = x \arctan 2x - \frac{1}{4}\ln(1 + 4x^2)$
53. $y = \frac{1}{2}\left(\frac{1}{2}\ln\dfrac{x + 1}{x - 1} + \arctan x\right)$
54. $y = \frac{1}{2}\left[x\sqrt{4 - x^2} + 4 \arcsin \frac{x}{2}\right]$
55. $y = 8 \arcsin \dfrac{x}{4} - \dfrac{x\sqrt{16 - x^2}}{2}$
56. $y = \arctan x + \dfrac{x}{1 + x^2}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding an Equation of a Tangent Line **In Exercises 57–62, find an equation of the tangent line to the graph of the function at the given point.**

57. $y = 2 \arcsin x, \quad \left(\frac{1}{2}, \frac{\pi}{3}\right)$

58. $y = -\frac{1}{4} \arccos x, \quad \left(-\frac{1}{2}, -\frac{\pi}{6}\right)$

59. $y = \arctan \frac{x}{2}, \quad \left(2, \frac{\pi}{4}\right)$

60. $y = \operatorname{arcsec} 4x, \quad \left(\frac{\sqrt{2}}{4}, \frac{\pi}{4}\right)$

61. $y = 4x \arccos(x - 1), \quad (1, 2\pi)$

62. $y = 3x \arcsin x, \quad \left(\frac{1}{2}, \frac{\pi}{4}\right)$

Finding Relative Extrema **In Exercises 63–66, find any relative extrema of the function.**

63. $f(x) = \operatorname{arcsec} x - x$

64. $f(x) = \arcsin x - 2x$

65. $f(x) = \arctan x - \arctan(x - 4)$

66. $h(x) = \arcsin x - 2 \arctan x$

Analyzing an Inverse Trigonometric Graph **In Exercises 67–70, analyze and sketch a graph of the function. Identify any relative extrema, points of inflection, and asymptotes. Use a graphing utility to verify your results.**

67. $f(x) = \arcsin(x - 1)$

68. $f(x) = \arctan x + \frac{\pi}{2}$

69. $f(x) = \operatorname{arcsec} 2x$

70. $f(x) = \arccos \frac{x}{4}$

Implicit Differentiation **In Exercises 71–74, use implicit differentiation to find an equation of the tangent line to the graph of the equation at the given point.**

71. $x^2 + x \arctan y = y - 1, \quad \left(-\frac{\pi}{4}, 1\right)$

72. $\arctan(xy) = \arcsin(x + y), \quad (0, 0)$

73. $\arcsin x + \arcsin y = \frac{\pi}{2}, \quad \left(\frac{\sqrt{2}}{2}, \frac{\sqrt{2}}{2}\right)$

74. $\arctan(x + y) = y^2 + \frac{\pi}{4}, \quad (1, 0)$

75. Finding Values

(a) Use a graphing utility to evaluate $\arcsin(\arcsin 0.5)$ and $\arcsin(\arcsin 1)$.

(b) Let

$$f(x) = \arcsin(\arcsin x).$$

Find the values of x in the interval $-1 \le x \le 1$ such that $f(x)$ is a real number.

76. HOW DO YOU SEE IT? The graph of $g(x) = \cos x$ is shown below. Explain whether the points

$$\left(-\frac{1}{2}, \frac{2\pi}{3}\right), \quad \left(0, \frac{\pi}{2}\right), \quad \text{and} \quad \left(\frac{1}{2}, -\frac{\pi}{3}\right)$$

lie on the graph of $y = \arccos x$.



Exploring Concepts

77. Determine whether

$$\frac{\arcsin x}{\arccos x} = \arctan x.$$

78. Determine whether each inverse trigonometric function can be defined as shown. Explain.

(a) $y = \operatorname{arcsec} x$, Domain: $x > 1$, Range: $-\frac{\pi}{2} < y < \frac{\pi}{2}$

(b) $y = \operatorname{arccsc} x$, Domain: $x > 1$, Range: $0 < y < \pi$

79. Explain why $\sin 2\pi = 0$ does not imply that $\arcsin 0 = 2\pi$.

80. Explain why $\tan \pi = 0$ does not imply that $\arctan 0 = \pi$.

Verifying Identities **In Exercises 81 and 82, verify each identity.**

81. (a) $\operatorname{arccsc} x = \arcsin \frac{1}{x}, \quad |x| \ge 1$

(b) $\arctan x + \arctan \frac{1}{x} = \frac{\pi}{2}, \quad x > 0$

82. (a) $\arcsin(-x) = -\arcsin x, \quad |x| \le 1$

(b) $\arccos(-x) = \pi - \arccos x, \quad |x| \le 1$

True or False? **In Exercises 83–86, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

83. The slope of the graph of the inverse tangent function is positive for all x.

84. The range of $y = \arcsin x$ is $[0, \pi]$.

85. $\frac{d}{dx}[\arctan(\tan x)] = 1$ for all x in the domain.

86. $\arcsin^2 x + \arccos^2 x = 1$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

87. Angular Rate of Change An airplane flies at an altitude of 5 miles toward a point directly over an observer. Consider θ and x as shown in the figure.



(a) Write θ as a function of x.

(b) The speed of the plane is 400 miles per hour. Find $d\theta/dt$ when $x = 10$ miles and $x = 3$ miles.

88. Writing Repeat Exercise 87 for an altitude of 3 miles and describe how the altitude affects the rate of change of θ.

89. Angular Rate of Change In a free-fall experiment, an object is dropped from a height of 256 feet. A camera on the ground 500 feet from the point of impact records the fall of the object (see figure).

(a) Find the position function that yields the height of the object at time t, assuming the object is released at time $t = 0$. At what time will the object reach ground level?

(b) Find the rates of change of the angle of elevation of the camera when $t = 1$ and $t = 2$.



Figure for 89



Figure for 90

90. Angular Rate of Change A television camera at ground level is filming the liftoff of a rocket at a point 800 meters from the launch pad. Let θ be the angle of elevation of the rocket and let s be the distance between the camera and the rocket (see figure). Write θ as a function of s for the period of time when the rocket is moving vertically. Differentiate the result to find $d\theta/dt$ in terms of s and ds/dt.

91. Maximizing an Angle A billboard 85 feet wide is perpendicular to a straight road and is 40 feet from the road (see figure). Find the point on the road at which the angle θ subtended by the billboard is a maximum.



Figure for 91



Figure for 92

92. Angular Speed A patrol car is parked 50 feet from a long warehouse (see figure). The revolving light on top of the car turns at a rate of 30 revolutions per minute. Write θ as a function of x. Use inverse trigonometric functions to find how fast the light beam is moving along the wall when the beam makes an angle of $\theta = 45°$ with the line perpendicular from the light to the wall.

93. Proof

Prove that $\arctan x + \arctan y = \arctan \dfrac{x + y}{1 - xy}$, $xy \neq 1$.

94. Proof Prove each differentiation formula.

(a) $\dfrac{d}{dx}[\arctan u] = \dfrac{u'}{1 + u^2}$

(b) $\dfrac{d}{dx}[\operatorname{arccot} u] = \dfrac{-u'}{1 + u^2}$

(c) $\dfrac{d}{dx}[\operatorname{arcsec} u] = \dfrac{u'}{|u|\sqrt{u^2 - 1}}$

(d) $\dfrac{d}{dx}[\operatorname{arccsc} u] = \dfrac{-u'}{|u|\sqrt{u^2 - 1}}$

95. Describing a Graph Use a graphing utility to graph the function $f(x) = \arccos x + \arcsin x$ on the interval $[-1, 1]$.

(a) Describe the graph of f.

(b) Verify the result of part (a) analytically.

96. Think About It Use a graphing utility to graph $f(x) = \sin x$ and $g(x) = \arcsin(\sin x)$.

(a) Explain why the graph of g is not the line $y = x$.

(b) Determine the extrema of g.

97. Maximizing an Angle In the figure, find the value of c in the interval $[0, 4]$ on the x-axis that maximizes angle θ.



Figure for 97



Figure for 98

98. Finding a Distance In the figure, find PR such that $0 \leq PR \leq 3$ and $m\angle\theta$ is a maximum.

99. Inverse Secant Function Some calculus textbooks define the inverse secant function using the range $[0, \pi/2) \cup [\pi, 3\pi/2)$.

(a) Sketch the graph $y = \operatorname{arcsec} x$ using this range.

(b) Show that $y' = \dfrac{1}{x\sqrt{x^2 - 1}}$.

100. Proof Prove that $\arcsin x = \arctan \dfrac{x}{\sqrt{1 - x^2}}$, $|x| < 1$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

5.8 Inverse Trigonometric Functions: Integration

GO DIGITAL

- Integrate functions whose antiderivatives involve inverse trigonometric functions.
- Use the method of completing the square to integrate a function.
- Review the basic integration rules involving elementary functions.

Integrals Involving Inverse Trigonometric Functions

The derivatives of the six inverse trigonometric functions fall into three pairs. In each pair, the derivative of one function is the negative of the other. For example,

$$\frac{d}{dx}[\arcsin x] = \frac{1}{\sqrt{1 - x^2}}$$

and

$$\frac{d}{dx}[\arccos x] = -\frac{1}{\sqrt{1 - x^2}}.$$

When listing the *antiderivative* that corresponds to each of the inverse trigonometric functions, you need to use only one member from each pair. It is conventional to use $\arcsin x$ as the antiderivative of $1/\sqrt{1 - x^2}$, rather than $-\arccos x$. The next theorem gives one antiderivative formula for each of the three pairs. The proofs of these integration rules are left to you (see Exercises 75–77).

FOR FURTHER INFORMATION
For a detailed proof of rule 2 of Theorem 5.19, see the article "A Direct Proof of the Integral Formula for Arctangent" by Arnold J. Insel in *The College Mathematics Journal*. To view this article, go to *MathArticles.com*.

THEOREM 5.19 Integrals Involving Inverse Trigonometric Functions

Let u be a differentiable function of x, and let $a > 0$.

1. $\displaystyle\int \frac{du}{\sqrt{a^2 - u^2}} = \arcsin\frac{u}{a} + C$
2. $\displaystyle\int \frac{du}{a^2 + u^2} = \frac{1}{a}\arctan\frac{u}{a} + C$
3. $\displaystyle\int \frac{du}{u\sqrt{u^2 - a^2}} = \frac{1}{a}\operatorname{arcsec}\frac{|u|}{a} + C$

EXAMPLE 1 Integration with Inverse Trigonometric Functions

a. $\displaystyle\int \frac{dx}{\sqrt{4 - x^2}} = \arcsin\frac{x}{2} + C$ $\quad u = x,\ a = 2$

b. $\displaystyle\int \frac{dx}{2 + 9x^2} = \frac{1}{3}\int \frac{3\,dx}{(\sqrt{2})^2 + (3x)^2}$ $\quad u = 3x,\ a = \sqrt{2}$

$$= \frac{1}{3\sqrt{2}}\arctan\frac{3x}{\sqrt{2}} + C$$

c. $\displaystyle\int \frac{dx}{x\sqrt{4x^2 - 9}} = \int \frac{2\,dx}{2x\sqrt{(2x)^2 - 3^2}}$ $\quad u = 2x,\ a = 3$

$$= \frac{1}{3}\operatorname{arcsec}\frac{|2x|}{3} + C$$

The integrals in Example 1 are fairly straightforward applications of integration formulas. Unfortunately, this is not typical. The integration formulas for inverse trigonometric functions can be disguised in many ways.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

EXAMPLE 2 **Integration by Substitution**

Find $\int \frac{dx}{\sqrt{e^{2x} - 1}}$.

Solution As it stands, this integral does not fit any of the three inverse trigonometric formulas. Using the substitution $u = e^x$, however, produces

$$u = e^x \quad \Rightarrow \quad du = e^x\,dx \quad \Rightarrow \quad dx = \frac{du}{e^x} = \frac{du}{u}.$$

With this substitution, you can integrate as shown.

$$\begin{aligned}
\int \frac{dx}{\sqrt{e^{2x} - 1}} &= \int \frac{dx}{\sqrt{(e^x)^2 - 1}} && \text{Write } e^{2x} \text{ as } (e^x)^2. \\
&= \int \frac{du/u}{\sqrt{u^2 - 1}} && \text{Substitute.} \\
&= \int \frac{du}{u\sqrt{u^2 - 1}} && \text{Rewrite to fit Arcsecant Rule.} \\
&= \operatorname{arcsec} \frac{|u|}{1} + C && \text{Apply Arcsecant Rule.} \\
&= \operatorname{arcsec} e^x + C && \text{Back-substitute.}
\end{aligned}$$

Note that the absolute value sign is not necessary in the final answer because $e^x > 0$.

TECHNOLOGY A graphing utility can be useful for integrating functions such as the one in Example 2. In some cases, the utility may fail to find an antiderivative, often for two reasons. First, some elementary functions do not have antiderivatives that are elementary functions. Second, every utility has limitations—you might have entered a function that the utility was not programmed to find. Also, remember that antiderivatives can be written in many different forms. For instance, one utility found the integral in Example 2 to be

$$\int \frac{dx}{\sqrt{e^{2x} - 1}} = \arctan \sqrt{e^{2x} - 1} + C.$$

Show that this antiderivative is equivalent to the one found in Example 2.

EXAMPLE 3 **Rewriting as the Sum of Two Quotients**

Find $\int \frac{x + 2}{\sqrt{4 - x^2}}\,dx$.

Solution This integral does not appear to fit any of the basic integration formulas. By splitting the integrand into two parts, however, notice that the first part can be found with the Power Rule and the second part yields an inverse sine function.

$$\begin{aligned}
\int \frac{x + 2}{\sqrt{4 - x^2}}\,dx &= \int \frac{x}{\sqrt{4 - x^2}}\,dx + \int \frac{2}{\sqrt{4 - x^2}}\,dx \\
&= -\frac{1}{2}\int (4 - x^2)^{-1/2}(-2x)\,dx + 2\int \frac{1}{\sqrt{4 - x^2}}\,dx \\
&= -\frac{1}{2}\left[\frac{(4 - x^2)^{1/2}}{1/2}\right] + 2 \arcsin \frac{x}{2} + C \\
&= -\sqrt{4 - x^2} + 2 \arcsin \frac{x}{2} + C
\end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Completing the Square

Completing the square helps when quadratic functions are involved in the integrand. For example, the quadratic $x^2 + bx + c$ can be written as the difference of two squares by adding and subtracting $(b/2)^2$.

$$x^2 + bx + c = x^2 + bx + \left(\frac{b}{2}\right)^2 - \left(\frac{b}{2}\right)^2 + c = \left(x + \frac{b}{2}\right)^2 - \left(\frac{b}{2}\right)^2 + c$$

EXAMPLE 4 Completing the Square

See LarsonCalculus.com for an interactive version of this type of example.

Find $\displaystyle\int \frac{dx}{x^2 - 4x + 7}$.

Solution First, rewrite the denominator as the sum of two squares, as shown.

$$x^2 - 4x + 7 = (x^2 - 4x + 4) - 4 + 7 = (x - 2)^2 + 3 = u^2 + a^2$$

Now, in this completed square form, let $u = x - 2$ and $a = \sqrt{3}$.

$$\int \frac{dx}{x^2 - 4x + 7} = \int \frac{dx}{(x - 2)^2 + 3} = \frac{1}{\sqrt{3}} \arctan \frac{x - 2}{\sqrt{3}} + C$$

When the leading coefficient is not 1, it helps to factor before completing the square. For example, to complete the square for $2x^2 - 8x + 10$, factor out 2 first.

$$2x^2 - 8x + 10 = 2(x^2 - 4x + 5) = 2(x^2 - 4x + 4 - 4 + 5) = 2\left[(x - 2)^2 + 1\right]$$

To complete the square when the coefficient of x^2 is negative, use the same factoring process shown above. For instance, you can complete the square for $3x - x^2$ as shown.

$$3x - x^2 = -(x^2 - 3x) = -\left[x^2 - 3x + \left(\frac{3}{2}\right)^2 - \left(\frac{3}{2}\right)^2\right] = \left(\frac{3}{2}\right)^2 - \left(x - \frac{3}{2}\right)^2$$

EXAMPLE 5 Completing the Square

Find the area of the region bounded by the graph of

$$f(x) = \frac{1}{\sqrt{3x - x^2}}$$

the x-axis, and the lines $x = \frac{3}{2}$ and $x = \frac{9}{4}$.



The area of the region bounded by the graph of f, the x-axis, $x = \frac{3}{2}$, and $x = \frac{9}{4}$ is $\pi/6$.

Figure 5.28

Solution In Figure 5.28, you can see that the area is

$$\begin{aligned}
\text{Area} &= \int_{3/2}^{9/4} \frac{1}{\sqrt{3x - x^2}}\,dx \\
&= \int_{3/2}^{9/4} \frac{dx}{\sqrt{(3/2)^2 - [x - (3/2)]^2}} && \text{Use completed square form derived above.} \\
&= \arcsin \frac{x - (3/2)}{3/2}\Bigg]_{3/2}^{9/4} \\
&= \arcsin \frac{1}{2} - \arcsin 0 \\
&= \frac{\pi}{6} \\
&\approx 0.524.
\end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Review of Basic Integration Rules

You have now completed the introduction of the **basic integration rules.** With enough practice, you will become more efficient at applying these rules.

Basic Integration Rules ($a > 0$)

1. $\int kf(u)\,du = k\int f(u)\,du$
2. $\int [f(u) \pm g(u)]\,du = \int f(u)\,du \pm \int g(u)\,du$
3. $\int du = u + C$
4. $\int u^n\,du = \frac{u^{n+1}}{n+1} + C, \quad n \neq -1$
5. $\int \frac{du}{u} = \ln|u| + C$
6. $\int e^u\,du = e^u + C$
7. $\int a^u\,du = \left(\frac{1}{\ln a}\right)a^u + C$
8. $\int \sin u\,du = -\cos u + C$
9. $\int \cos u\,du = \sin u + C$
10. $\int \tan u\,du = -\ln|\cos u| + C$
11. $\int \cot u\,du = \ln|\sin u| + C$
12. $\int \sec u\,du = \ln|\sec u + \tan u| + C$
13. $\int \csc u\,du = -\ln|\csc u + \cot u| + C$
14. $\int \sec^2 u\,du = \tan u + C$
15. $\int \csc^2 u\,du = -\cot u + C$
16. $\int \sec u \tan u\,du = \sec u + C$
17. $\int \csc u \cot u\,du = -\csc u + C$
18. $\int \frac{du}{\sqrt{a^2 - u^2}} = \arcsin\frac{u}{a} + C$
19. $\int \frac{du}{a^2 + u^2} = \frac{1}{a}\arctan\frac{u}{a} + C$
20. $\int \frac{du}{u\sqrt{u^2 - a^2}} = \frac{1}{a}\operatorname{arcsec}\frac{|u|}{a} + C$

You can learn a lot about the nature of integration by comparing this list with the summary of differentiation rules given in the preceding section. For differentiation, you now have rules that allow you to differentiate *any* elementary function. For integration, this is far from true.

The integration rules listed above are primarily those that were discovered during the development of differentiation rules. So far, you have not learned any rules or techniques for finding the antiderivative of a general product or quotient, the natural logarithmic function, or the inverse trigonometric functions. More important, you cannot apply any of the rules in this list unless you can create the proper du corresponding to the u in the formula. The point is that you need to work more on integration techniques, which you will do in Chapter 8. The next two examples should give you a better feeling for the integration problems that you *can* and *cannot* solve with the techniques and rules you now know.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 6 Comparing Integration Problems

Use the formulas and techniques you have studied so far in this text to find each integral, if possible.

a. $\int \frac{dx}{x\sqrt{x^2-4}}$ **b.** $\int \frac{x\,dx}{\sqrt{x^2-4}}$ **c.** $\int \frac{dx}{\sqrt{x^2-4}}$

Solution

a. You *can* find this integral (it fits the Arcsecant Rule).

$$\int \frac{dx}{x\sqrt{x^2-4}} = \frac{1}{2}\operatorname{arcsec}\left|\frac{x}{2}\right| + C \qquad u = x,\ a = 2$$

b. You *can* find this integral (it fits the Power Rule).

$$\begin{aligned}\int \frac{x\,dx}{\sqrt{x^2-4}} &= \frac{1}{2}\int (x^2-4)^{-1/2}(2x)\,dx \qquad u = x^2-4\\ &= \frac{1}{2}\left[\frac{(x^2-4)^{1/2}}{1/2}\right] + C\\ &= \sqrt{x^2-4} + C\end{aligned}$$

c. You *cannot* find this integral using the techniques you have studied so far. (You should scan the list of basic integration rules to verify this conclusion.)

EXAMPLE 7 Comparing Integration Problems

Use the formulas and techniques you have studied so far in this text to find each integral, if possible.

a. $\int \frac{dx}{x\ln x}$ **b.** $\int \frac{\ln x\,dx}{x}$ **c.** $\int \ln x\,dx$

Solution

a. You *can* find this integral (it fits the Log Rule).

$$\begin{aligned}\int \frac{dx}{x\ln x} &= \int \frac{1/x}{\ln x}\,dx \qquad u = \ln x\\ &= \ln|\ln x| + C\end{aligned}$$

b. You *can* find this integral (it fits the Power Rule).

$$\begin{aligned}\int \frac{\ln x\,dx}{x} &= \int \left(\frac{1}{x}\right)(\ln x)^1\,dx \qquad u = \ln x\\ &= \frac{(\ln x)^2}{2} + C\end{aligned}$$

c. You *cannot* find this integral using the techniques you have studied so far. ■

Note in Examples 6 and 7 that the *simplest* functions are those you cannot yet integrate. In Chapter 8, you will learn that the integral in Example 6(c) can be found using *trigonometric substitution* (see Section 8.4, Exercise 20). The integral in Example 7(c) can be found using *integration by parts* (see Section 8.2, Example 3), and the result is shown below. Verify this result by differentiating the antiderivative.

$$\int \ln x\,dx = x\ln x - x + C$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

5.8 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Decide whether you can find each integral using the formulas and techniques you have studied so far. Explain. Do not integrate.

(a) $\int \frac{2\,dx}{\sqrt{x^2+4}}$ (b) $\int \frac{dx}{x\sqrt{x^2-9}}$

2. Describe the process of completing the square of a quadratic function. Explain when completing the square is useful for finding an integral.

Finding an Indefinite Integral

In Exercises 3–22, find the indefinite integral.

3. $\int \frac{dx}{\sqrt{9-x^2}}$
4. $\int \frac{dx}{\sqrt{1-4x^2}}$
5. $\int \frac{1}{x\sqrt{4x^2-1}}\,dx$
6. $\int \frac{12}{1+9x^2}\,dx$
7. $\int \frac{1}{\sqrt{1-(x+1)^2}}\,dx$
8. $\int \frac{7}{4+(3-x)^2}\,dx$
9. $\int \frac{t}{\sqrt{1-t^4}}\,dt$
10. $\int \frac{1}{x\sqrt{x^4-4}}\,dx$
11. $\int \frac{t}{t^4+25}\,dt$
12. $\int \frac{1}{x\sqrt{1-(\ln x)^2}}\,dx$
13. $\int \frac{e^{2x}}{4+e^{4x}}\,dx$
14. $\int \frac{5}{x\sqrt{9x^2-11}}\,dx$
15. $\int \frac{-\csc x\cot x}{\sqrt{25-\csc^2 x}}\,dx$
16. $\int \frac{\sin x}{7+\cos^2 x}\,dx$
17. $\int \frac{1}{\sqrt{x}\sqrt{1-x}}\,dx$
18. $\int \frac{3}{2\sqrt{x}(1+x)}\,dx$
19. $\int \frac{x-3}{x^2+1}\,dx$
20. $\int \frac{x^2+8}{x\sqrt{x^2-4}}\,dx$
21. $\int \frac{x+5}{\sqrt{9-(x-3)^2}}\,dx$
22. $\int \frac{x-2}{(x+1)^2+4}\,dx$

Evaluating a Definite Integral

In Exercises 23–34, evaluate the definite integral.

23. $\int_0^{1/6} \frac{3}{\sqrt{1-9x^2}}\,dx$
24. $\int_0^{\sqrt{2}} \frac{1}{\sqrt{4-x^2}}\,dx$
25. $\int_0^{\sqrt{3}/2} \frac{1}{1+4x^2}\,dx$
26. $\int_{\sqrt{3}}^{3} \frac{1}{x\sqrt{4x^2-9}}\,dx$
27. $\int_1^7 \frac{1}{9+(x+2)^2}\,dx$
28. $\int_1^4 \frac{1}{x\sqrt{16x^2-5}}\,dx$
29. $\int_0^{\ln 5} \frac{e^x}{1+e^{2x}}\,dx$
30. $\int_{\ln 2}^{\ln 4} \frac{e^{-x}}{\sqrt{1-e^{-2x}}}\,dx$
31. $\int_{\pi/2}^{\pi} \frac{\sin x}{1+\cos^2 x}\,dx$
32. $\int_0^{\pi/2} \frac{\cos x}{1+\sin^2 x}\,dx$
33. $\int_0^{1/\sqrt{2}} \frac{\arcsin x}{\sqrt{1-x^2}}\,dx$
34. $\int_0^{1/\sqrt{2}} \frac{\arccos x}{\sqrt{1-x^2}}\,dx$

Completing the Square

In Exercises 35–44, find or evaluate the integral by completing the square.

35. $\int_0^2 \frac{dx}{x^2-2x+2}$
36. $\int_{-2}^3 \frac{dx}{x^2+4x+8}$
37. $\int \frac{2x}{x^2+6x+13}\,dx$
38. $\int \frac{2x-5}{x^2+2x+2}\,dx$
39. $\int \frac{dx}{\sqrt{-2x^2+8x+4}}$
40. $\int \frac{dx}{3x^2-6x+12}$
41. $\int \frac{1}{\sqrt{-x^2-4x}}\,dx$
42. $\int \frac{2}{\sqrt{-x^2+4x}}\,dx$
43. $\int_2^3 \frac{2x-3}{\sqrt{4x-x^2}}\,dx$
44. $\int_3^4 \frac{1}{(x-1)\sqrt{x^2-2x}}\,dx$

Integration by Substitution

In Exercises 45–48, use the specified substitution to find or evaluate the integral.

45. $\int \sqrt{e^t-3}\,dt$, $u=\sqrt{e^t-3}$
46. $\int \frac{\sqrt{x-2}}{x+1}\,dx$, $u=\sqrt{x-2}$
47. $\int_1^3 \frac{dx}{\sqrt{x}(1+x)}$, $u=\sqrt{x}$
48. $\int_0^1 \frac{dx}{2\sqrt{3-x}\sqrt{x+1}}$, $u=\sqrt{x+1}$

Comparing Integration Problems

In Exercises 49–52, find the indefinite integrals, if possible, using the formulas and techniques you have studied so far in the text.

49. (a) $\int \frac{1}{\sqrt{1-x^2}}\,dx$
(b) $\int \frac{x}{\sqrt{1-x^2}}\,dx$
(c) $\int \frac{1}{x\sqrt{1-x^2}}\,dx$

50. (a) $\int e^{x^2}\,dx$
(b) $\int xe^{x^2}\,dx$
(c) $\int \frac{1}{x^2}e^{1/x}\,dx$

51. (a) $\int \sqrt{x-1}\,dx$
(b) $\int x\sqrt{x-1}\,dx$
(c) $\int \frac{x}{\sqrt{x-1}}\,dx$

52. (a) $\int \frac{1}{1+x^4}\,dx$
(b) $\int \frac{x}{1+x^4}\,dx$
(c) $\int \frac{x^3}{1+x^4}\,dx$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploring Concepts

In Exercises 53 and 54, show that the antiderivatives are equivalent.

53. $\int \frac{3x^2}{\sqrt{1-x^6}}\,dx = \arcsin x^3 + C$ or $\arccos\sqrt{1-x^6} + C$

54. $\int \frac{6}{4+9x^2}\,dx = \arctan\frac{3x}{2} + C$ or $\operatorname{arccsc}\frac{\sqrt{4+9x^2}}{3x} + C$

55. The antiderivative of

$$\int \frac{1}{\sqrt{1-x^2}}\,dx$$

can be either $\arcsin x + C$ or $-\arccos x + C$. Does this mean that $\arcsin x = -\arccos x$? Explain.

56. HOW DO YOU SEE IT? Using the graph, which value best approximates the area of the region between the x-axis and the function over the interval $\left[-\frac{1}{2}, \frac{1}{2}\right]$? Explain.



(a) -3 (b) $\frac{1}{2}$ (c) 1 (d) 2 (e) 4

Slope Field **In Exercises 57 and 58, a differential equation, a point, and a slope field are given. (a) Sketch two approximate solutions of the differential equation on the slope field, one of which passes through the given point. (To print an enlarged copy of the graph, go to *MathGraphs.com*.) (b) Use integration and the given point to find the particular solution of the differential equation and use a graphing utility to graph the solution. Compare the result with the sketch in part (a) that passes through the given point.**

57. $\frac{dy}{dx} = \frac{2}{9+x^2}$, $(0, 2)$



58. $\frac{dy}{dx} = \frac{2}{\sqrt{25-x^2}}$, $(5, \pi)$



Slope Field **In Exercises 59–62, use a graphing utility to graph the slope field for the differential equation and graph the particular solution satisfying the specified initial condition.**

59. $\frac{dy}{dx} = \frac{10}{x\sqrt{x^2-1}}$, $y(3) = 0$

60. $\frac{dy}{dx} = \frac{1}{12+x^2}$, $y(4) = 2$

61. $\frac{dy}{dx} = \frac{2y}{\sqrt{16-x^2}}$, $y(0) = 2$

62. $\frac{dy}{dx} = \frac{\sqrt{y}}{1+x^2}$, $y(0) = 4$

Differential Equation **In Exercises 63 and 64, find the particular solution of the differential equation that satisfies the initial condition.**

63. $\frac{dy}{dx} = \frac{1}{\sqrt{4-x^2}}$, $y(0) = \pi$

64. $\frac{dy}{dx} = \frac{1}{4+x^2}$, $y(2) = \pi$

Area **In Exercises 65–68, find the area of the given region. Use a graphing utility to verify your result.**

65. $y = \frac{2}{\sqrt{4-x^2}}$



66. $y = \frac{1}{x\sqrt{x^2-1}}$



67. $y = \frac{3\cos x}{1+\sin^2 x}$



68. $y = \frac{4e^x}{1+e^{2x}}$



69. Area

(a) Sketch the region whose area is represented by

$$\int_0^1 \arcsin x\,dx.$$

(b) Use the integration capabilities of a graphing utility to approximate the area.

(c) Find the exact area analytically.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

70. Approximating Pi

(a) Show that

$$\int_0^1 \frac{4}{1+x^2}\,dx = \pi.$$

(b) Approximate the number π by using the integration capabilities of a graphing utility.

71. Investigation Consider the function

$$F(x) = \frac{1}{2}\int_x^{x+2} \frac{2}{t^2+1}\,dt.$$

(a) Write a short paragraph giving a geometric interpretation of the function $F(x)$ relative to the function

$$f(x) = \frac{2}{x^2+1}.$$

Use what you have written to guess the value of x that will make F maximum.

(b) Perform the specified integration to find an alternative form of $F(x)$. Use calculus to locate the value of x that will make F maximum and compare the result with your guess in part (a).

72. Comparing Integrals Consider the integral

$$\int \frac{1}{\sqrt{6x-x^2}}\,dx.$$

(a) Find the integral by completing the square of the radicand.

(b) Find the integral by making the substitution $u = \sqrt{x}$.

(c) The antiderivatives in parts (a) and (b) appear to be significantly different. Use a graphing utility to graph each antiderivative in the same viewing window and determine the relationship between them. Find the domain of each.

True or False? **In Exercises 73 and 74, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

73. $\displaystyle\int \frac{dx}{3x\sqrt{9x^2-16}} = \frac{1}{4}\operatorname{arcsec}\frac{3x}{4} + C$

74. $\displaystyle\int \frac{dx}{25+x^2} = \frac{1}{25}\arctan\frac{x}{25} + C$

Verifying an Integration Rule **In Exercises 75–77, verify the rule by differentiating. Let $a > 0$.**

75. $\displaystyle\int \frac{du}{\sqrt{a^2-u^2}} = \arcsin\frac{u}{a} + C$

76. $\displaystyle\int \frac{du}{a^2+u^2} = \frac{1}{a}\arctan\frac{u}{a} + C$

77. $\displaystyle\int \frac{du}{u\sqrt{u^2-a^2}} = \frac{1}{a}\operatorname{arcsec}\frac{|u|}{a} + C$

78. Proof Graph $y_1 = \dfrac{x}{1+x^2}$, $y_2 = \arctan x$, and $y_3 = x$ on $[0, 10]$. Prove that $\dfrac{x}{1+x^2} < \arctan x < x$ for $x > 0$.

79. Numerical Integration

(a) Write an integral that represents the area of the region in the figure.

(b) Use the Midpoint Rule with $n = 8$ to estimate the area of the region.

(c) Explain how you can use the results of parts (a) and (b) to estimate π.



80. Vertical Motion An object is projected upward from ground level with an initial velocity of 500 feet per second. In this exercise, the goal is to analyze the motion of the object during its upward flight.

(a) Find the velocity of the object as a function of time (neglect air resistance). Use a graphing utility to graph this function.

(b) Use the result of part (a) to find the position function and determine the maximum height attained by the object.

(c) When the air resistance is proportional to the square of the velocity, you obtain the equation

$$\frac{dv}{dt} = -(32 + kv^2)$$

where 32 feet per second per second is the acceleration due to gravity and k is a constant. Find the velocity as a function of time by solving the equation

$$\int \frac{dv}{32+kv^2} = -\int dt.$$

(d) Use a graphing utility to graph the velocity function $v(t)$ in part (c) for $k = 0.001$. Use the graph to approximate the time t_0 at which the object reaches its maximum height.

(e) Use the integration capabilities of a graphing utility to approximate the integral

$$\int_0^{t_0} v(t)\,dt$$

where $v(t)$ and t_0 are those found in part (d). This is the approximation of the maximum height of the object.

(f) Explain the difference between the results in parts (b) and (e).

FOR FURTHER INFORMATION For more information on this topic, see the article "What Goes Up Must Come Down; Will Air Resistance Make It Return Sooner, or Later?" by John Lekner in *Mathematics Magazine*. To view this article, go to *MathArticles.com*.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

5.9 Hyperbolic Functions

GO DIGITAL

- Develop properties of hyperbolic functions.
- Differentiate and integrate hyperbolic functions.
- Develop properties of inverse hyperbolic functions.
- Differentiate and integrate functions involving inverse hyperbolic functions.

JOHANN HEINRICH LAMBERT (1728–1777)

The first person to publish a comprehensive study on hyperbolic functions was Johann Heinrich Lambert, a Swiss-German mathematician and colleague of Euler. *See LarsonCalculus.com to read more of this biography.*

Hyperbolic Functions

In this section, you will look briefly at a special class of exponential functions called **hyperbolic functions.** The name *hyperbolic function* arose from comparison of the area of a semicircular region, as shown in Figure 5.29, with the area of a region under a hyperbola, as shown in Figure 5.30.



Circle: $x^2 + y^2 = 1$
Figure 5.29



Hyperbola: $-x^2 + y^2 = 1$
Figure 5.30

The integral for the semicircular region involves an inverse trigonometric (circular) function:

$$\int_{-1}^{1} \sqrt{1 - x^2}\, dx = \frac{1}{2}\left[x\sqrt{1 - x^2} + \arcsin x\right]_{-1}^{1} = \frac{\pi}{2} \approx 1.571.$$

The integral for the hyperbolic region involves an inverse hyperbolic function:

$$\int_{-1}^{1} \sqrt{1 + x^2}\, dx = \frac{1}{2}\left[x\sqrt{1 + x^2} + \sinh^{-1} x\right]_{-1}^{1} \approx 2.296.$$

This is only one of many ways in which the hyperbolic functions are similar to the trigonometric functions.

REMARK The notation $\sinh x$ is read as "the hyperbolic sine of x," $\cosh x$ as "the hyperbolic cosine of x," and so on.

Definitions of the Hyperbolic Functions

$$\sinh x = \frac{e^x - e^{-x}}{2} \qquad \operatorname{csch} x = \frac{1}{\sinh x}, \quad x \neq 0$$

$$\cosh x = \frac{e^x + e^{-x}}{2} \qquad \operatorname{sech} x = \frac{1}{\cosh x}$$

$$\tanh x = \frac{\sinh x}{\cosh x} \qquad \coth x = \frac{1}{\tanh x}, \quad x \neq 0$$

FOR FURTHER INFORMATION For more information on the development of hyperbolic functions, see the article "An Introduction to Hyperbolic Functions in Elementary Calculus" by Jerome Rosenthal in *Mathematics Teacher.* To view this article, go to *MathArticles.com.*

INTERFOTO/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

The graphs of the six hyperbolic functions and their domains and ranges are shown in Figure 5.31. Note that the graph of $\sinh x$ can be obtained by adding the corresponding y-coordinates of the exponential functions $f(x) = \frac{1}{2}e^x$ and $g(x) = -\frac{1}{2}e^{-x}$. Likewise, the graph of $\cosh x$ can be obtained by adding the corresponding y-coordinates of the exponential functions $f(x) = \frac{1}{2}e^x$ and $h(x) = \frac{1}{2}e^{-x}$.



Domain: $(-\infty, \infty)$
Range: $(-\infty, \infty)$



Domain: $(-\infty, \infty)$
Range: $[1, \infty)$



Domain: $(-\infty, \infty)$
Range: $(-1, 1)$



Domain: $(-\infty, 0) \cup (0, \infty)$
Range: $(-\infty, 0) \cup (0, \infty)$



Domain: $(-\infty, \infty)$
Range: $(0, 1]$



Domain: $(-\infty, 0) \cup (0, \infty)$
Range: $(-\infty, -1) \cup (1, \infty)$

Figure 5.31

Many of the trigonometric identities have corresponding *hyperbolic identities*. For instance,

$$\begin{aligned}\cosh^2 x - \sinh^2 x &= \left(\frac{e^x + e^{-x}}{2}\right)^2 - \left(\frac{e^x - e^{-x}}{2}\right)^2 \\ &= \frac{e^{2x} + 2 + e^{-2x}}{4} - \frac{e^{2x} - 2 + e^{-2x}}{4} \\ &= \frac{4}{4} \\ &= 1.\end{aligned}$$

Hyperbolic Identities

$$\cosh^2 x - \sinh^2 x = 1$$
$$\tanh^2 x + \operatorname{sech}^2 x = 1$$
$$\coth^2 x - \operatorname{csch}^2 x = 1$$

$$\sinh(x + y) = \sinh x \cosh y + \cosh x \sinh y$$
$$\sinh(x - y) = \sinh x \cosh y - \cosh x \sinh y$$
$$\cosh(x + y) = \cosh x \cosh y + \sinh x \sinh y$$
$$\cosh(x - y) = \cosh x \cosh y - \sinh x \sinh y$$

$$\sinh^2 x = \frac{-1 + \cosh 2x}{2}$$
$$\cosh^2 x = \frac{1 + \cosh 2x}{2}$$

$$\sinh 2x = 2 \sinh x \cosh x$$
$$\cosh 2x = \cosh^2 x + \sinh^2 x$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Differentiation and Integration of Hyperbolic Functions

Because the hyperbolic functions are written in terms of e^x and e^{-x}, you can easily derive rules for their derivatives. The next theorem lists these derivatives with the corresponding integration rules.

THEOREM 5.20 Derivatives and Integrals of Hyperbolic Functions

Let u be a differentiable function of x.

$$\frac{d}{dx}[\sinh u] = (\cosh u)u' \qquad \int \cosh u\,du = \sinh u + C$$

$$\frac{d}{dx}[\cosh u] = (\sinh u)u' \qquad \int \sinh u\,du = \cosh u + C$$

$$\frac{d}{dx}[\tanh u] = (\operatorname{sech}^2 u)u' \qquad \int \operatorname{sech}^2 u\,du = \tanh u + C$$

$$\frac{d}{dx}[\coth u] = -(\operatorname{csch}^2 u)u' \qquad \int \operatorname{csch}^2 u\,du = -\coth u + C$$

$$\frac{d}{dx}[\operatorname{sech} u] = -(\operatorname{sech} u \tanh u)u' \qquad \int \operatorname{sech} u \tanh u\,du = -\operatorname{sech} u + C$$

$$\frac{d}{dx}[\operatorname{csch} u] = -(\operatorname{csch} u \coth u)u' \qquad \int \operatorname{csch} u \coth u\,du = -\operatorname{csch} u + C$$

Proof Here is a proof of two of the differentiation rules. (You are asked to prove some of the other differentiation rules in Exercises 99–101.)

$$\frac{d}{dx}[\sinh x] = \frac{d}{dx}\left[\frac{e^x - e^{-x}}{2}\right] \qquad \text{Definition of sinh } x$$

$$= \frac{e^x + e^{-x}}{2} \qquad \frac{d}{dx}[e^u] = e^u u'$$

$$= \cosh x \qquad \text{Definition of cosh } x$$

$$\frac{d}{dx}[\tanh x] = \frac{d}{dx}\left[\frac{\sinh x}{\cosh x}\right] \qquad \text{Definition of tanh } x$$

$$= \frac{(\cosh x)(\cosh x) - (\sinh x)(\sinh x)}{\cosh^2 x} \qquad \text{Quotient Rule}$$

$$= \frac{1}{\cosh^2 x} \qquad \cosh^2 x - \sinh^2 x = 1$$

$$= \operatorname{sech}^2 x \qquad \text{Hyperbolic identity}$$

The derivatives of sinh u and tanh u follow from the Chain Rule. ■

EXAMPLE 1 Differentiation of Hyperbolic Functions

a. $\frac{d}{dx}[\sinh(x^2 - 3)] = 2x\cosh(x^2 - 3)$

b. $\frac{d}{dx}[\ln(\cosh x)] = \frac{\sinh x}{\cosh x} = \tanh x$

c. $\frac{d}{dx}[x\sinh x - \cosh x] = x\cosh x + \sinh x - \sinh x = x\cosh x$

d. $\frac{d}{dx}[(x-1)\cosh x - \sinh x] = (x-1)\sinh x + \cosh x - \cosh x = (x-1)\sinh x$

■

REMARK In Example 1, in addition to applying Theorem 5.20, note the use of the Log, Product, and Difference Rules for differentiation to find the derivatives in parts (b)–(d).

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



$f''(0) < 0$, so $(0, -1)$ is a relative maximum. $f''(1) > 0$, so $(1, -\sinh 1)$ is a relative minimum.
Figure 5.32

EXAMPLE 2 Finding Relative Extrema

Find the relative extrema of $f(x) = (x - 1)\cosh x - \sinh x$.

Solution From the result of Example 1(d), you know that $f'(x) = (x - 1)\sinh x$. Next, set the first derivative of f equal to 0.

$$(x - 1)\sinh x = 0$$

So, the critical numbers are $x = 1$ and $x = 0$. By the Second Derivative Test, the point $(0, -1)$ yields a relative maximum and the point $(1, -\sinh 1)$ yields a relative minimum, as shown in Figure 5.32. Use a graphing utility to check this result. If your graphing utility does not have hyperbolic functions, use the definitions of $\cosh x$ and $\sinh x$ to rewrite f with exponential functions, as shown.

$$\begin{aligned} f(x) &= (x - 1)\left(\frac{1}{2}\right)(e^x + e^{-x}) - \frac{1}{2}(e^x - e^{-x}) \\ &= \frac{1}{2}(xe^x + xe^{-x} - e^x - e^{-x} - e^x + e^{-x}) \\ &= \frac{1}{2}(xe^x + xe^{-x} - 2e^x) \end{aligned}$$

When a uniform flexible cable, such as a power cable, is suspended from two points, it takes the shape of a *catenary*, as discussed in Example 3.

EXAMPLE 3 Hanging Power Cables

See LarsonCalculus.com for an interactive version of this type of example.

Power cables are suspended between two towers, forming the catenary shown in Figure 5.33. The equation for this catenary is

$$y = a\cosh\frac{x}{a}.$$

The distance between the two towers is $2b$. Find the slope of the catenary at the point where the cable meets the right-hand tower.

Solution Differentiating produces

$$y' = a\left(\frac{1}{a}\right)\sinh\frac{x}{a} = \sinh\frac{x}{a}. \qquad \text{Differentiate with respect to } x.$$

At the point $(b, a\cosh(b/a))$, the slope (from the left) is $m = \sinh(b/a)$.



Catenary
Figure 5.33

FOR FURTHER INFORMATION
In Example 3, the cable is a catenary between two supports at the same height. To learn about the shape of a cable hanging between supports of different heights, see the article "Reexamining the Catenary" by Paul Cella in *The College Mathematics Journal*. To view this article, go to *MathArticles.com*.

EXAMPLE 4 Integrating a Hyperbolic Function

Find $\int \cosh 2x \sinh^2 2x\,dx$.

Solution

$$\begin{aligned} \int \cosh 2x \sinh^2 2x\,dx &= \frac{1}{2}\int (\sinh 2x)^2(2\cosh 2x)\,dx \qquad u = \sinh 2x \\ &= \frac{1}{2}\left[\frac{(\sinh 2x)^3}{3}\right] + C \\ &= \frac{\sinh^3 2x}{6} + C \end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Inverse Hyperbolic Functions

Unlike trigonometric functions, hyperbolic functions are not periodic. In fact, by looking back at Figure 5.31, notice that four of the six hyperbolic functions are actually one-to-one (the hyperbolic sine, tangent, cosecant, and cotangent). So, you can apply Theorem 5.7 to conclude that these four functions have inverse functions. The other two (the hyperbolic cosine and secant) are one-to-one when their domains are restricted to the positive real numbers, and for this restricted domain they also have inverse functions. Because the hyperbolic functions are defined in terms of exponential functions, it is not surprising to find that the inverse hyperbolic functions can be written in terms of logarithmic functions, as shown in the next theorem.

THEOREM 5.21 Inverse Hyperbolic Functions

Function	Domain
$\sinh^{-1} x = \ln\left(x + \sqrt{x^2 + 1}\right)$	$(-\infty, \infty)$
$\cosh^{-1} x = \ln\left(x + \sqrt{x^2 - 1}\right)$	$[1, \infty)$
$\tanh^{-1} x = \frac{1}{2} \ln \frac{1 + x}{1 - x}$	$(-1, 1)$
$\coth^{-1} x = \frac{1}{2} \ln \frac{x + 1}{x - 1}$	$(-\infty, -1) \cup (1, \infty)$
$\operatorname{sech}^{-1} x = \ln \frac{1 + \sqrt{1 - x^2}}{x}$	$(0, 1]$
$\operatorname{csch}^{-1} x = \ln\left(\frac{1}{x} + \frac{\sqrt{1 + x^2}}{\lvert x \rvert}\right)$	$(-\infty, 0) \cup (0, \infty)$

Proof The proof of this theorem is a straightforward application of the properties of the exponential and logarithmic functions. For example, for

$$f(x) = \sinh x = \frac{e^x - e^{-x}}{2}$$ Definition of $\sinh x$

and

$$g(x) = \ln\left(x + \sqrt{x^2 + 1}\right)$$

you can show that

$$f(g(x)) = x \quad \text{and} \quad g(f(x)) = x$$

which implies that g is the inverse function of f. ∎



Graphs of the hyperbolic tangent function and the inverse hyperbolic tangent function

Figure 5.34

TECHNOLOGY You can use a graphing utility to support the results of Theorem 5.21. For instance, to investigate the definition of $\tanh^{-1} x$, graph the four functions below.

$y_1 = \tanh x$ Hyperbolic tangent

$y_2 = \frac{e^x - e^{-x}}{e^x + e^{-x}}$ Definition of hyperbolic tangent

$y_3 = \tanh^{-1} x$ Inverse hyperbolic tangent

$y_4 = \frac{1}{2} \ln \frac{1 + x}{1 - x}$ Definition of inverse hyperbolic tangent

The resulting display is shown in Figure 5.34. Using the *trace* or *table* feature to investigate each function, notice that $y_1 = y_2$ and $y_3 = y_4$. Also, notice that the graph of y_1 is the reflection of the graph of y_3 in the line $y = x$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The graphs of the inverse hyperbolic functions are shown in Figure 5.35.



Domain: $(-\infty, \infty)$
Range: $(-\infty, \infty)$



Domain: $[1, \infty)$
Range: $[0, \infty)$



Domain: $(-1, 1)$
Range: $(-\infty, \infty)$



Domain: $(-\infty, 0) \cup (0, \infty)$
Range: $(-\infty, 0) \cup (0, \infty)$



Domain: $(0, 1]$
Range: $[0, \infty)$



Domain: $(-\infty, -1) \cup (1, \infty)$
Range: $(-\infty, 0) \cup (0, \infty)$

Figure 5.35

The inverse hyperbolic secant can be used to define a curve called a *tractrix* or *pursuit curve*, as discussed in Example 5.

EXAMPLE 5 A Tractrix

A person is holding a rope that is tied to a boat, as shown in Figure 5.36. As the person walks along the dock, the boat travels along a **tractrix,** given by the equation

$$y = a \operatorname{sech}^{-1} \frac{x}{a} - \sqrt{a^2 - x^2}$$

where a is the length of the rope. For $a = 20$ feet, find the distance the person must walk to bring the boat to a position 5 feet from the dock.

Solution In Figure 5.36, notice that the distance the person has walked is

$$\begin{aligned} y_1 &= y + \sqrt{20^2 - x^2} \\ &= \left(20 \operatorname{sech}^{-1} \frac{x}{20} - \sqrt{20^2 - x^2}\right) + \sqrt{20^2 - x^2} \\ &= 20 \operatorname{sech}^{-1} \frac{x}{20}. \end{aligned}$$

When $x = 5$, this distance is

$$y_1 = 20 \operatorname{sech}^{-1} \frac{5}{20} = 20 \ln \frac{1 + \sqrt{1 - (1/4)^2}}{1/4} = 20 \ln\left(4 + \sqrt{15}\right) \approx 41.27 \text{ feet.}$$

So, the person must walk about 41.27 feet to bring the boat to a position 5 feet from the dock. ■



A person must walk about 41.27 feet to bring the boat to a position 5 feet from the dock.

Figure 5.36

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Inverse Hyperbolic Functions: Differentiation and Integration

The derivatives of the inverse hyperbolic functions, which resemble the derivatives of the inverse trigonometric functions, are listed in Theorem 5.22 with the corresponding integration formulas (in logarithmic form). You can verify each of these formulas by applying the logarithmic definitions of the inverse hyperbolic functions. (See Exercises 102–104.)

THEOREM 5.22 Differentiation and Integration Involving Inverse Hyperbolic Functions

Let u be a differentiable function of x.

$$\frac{d}{dx}[\sinh^{-1} u] = \frac{u'}{\sqrt{u^2 + 1}} \qquad \frac{d}{dx}[\cosh^{-1} u] = \frac{u'}{\sqrt{u^2 - 1}}$$

$$\frac{d}{dx}[\tanh^{-1} u] = \frac{u'}{1 - u^2} \qquad \frac{d}{dx}[\coth^{-1} u] = \frac{u'}{1 - u^2}$$

$$\frac{d}{dx}[\operatorname{sech}^{-1} u] = \frac{-u'}{u\sqrt{1 - u^2}} \qquad \frac{d}{dx}[\operatorname{csch}^{-1} u] = \frac{-u'}{|u|\sqrt{1 + u^2}}$$

$$\int \frac{du}{\sqrt{u^2 \pm a^2}} = \ln\left(u + \sqrt{u^2 \pm a^2}\right) + C$$

$$\int \frac{du}{a^2 - u^2} = \frac{1}{2a} \ln\left|\frac{a + u}{a - u}\right| + C$$

$$\int \frac{du}{u\sqrt{a^2 \pm u^2}} = -\frac{1}{a} \ln \frac{a + \sqrt{a^2 \pm u^2}}{|u|} + C$$

EXAMPLE 6 Differentiation of Inverse Hyperbolic Functions

a. $\dfrac{d}{dx}[\sinh^{-1}(2x)] = \dfrac{2}{\sqrt{(2x)^2 + 1}}$ $\quad \frac{d}{dx}[\sinh^{-1} u]$ with $u = 2x$

$= \dfrac{2}{\sqrt{4x^2 + 1}}$

b. $\dfrac{d}{dx}[\tanh^{-1}(x^3)] = \dfrac{3x^2}{1 - (x^3)^2}$ $\quad \frac{d}{dx}[\tanh^{-1} u]$ with $u = x^3$

$= \dfrac{3x^2}{1 - x^6}$

EXAMPLE 7 Integration Using Inverse Hyperbolic Functions

a. $\displaystyle\int \frac{dx}{x\sqrt{4 - 9x^2}} = \int \frac{3\,dx}{(3x)\sqrt{2^2 - (3x)^2}}$ $\quad \int \frac{du}{u\sqrt{a^2 - u^2}}$ with $a = 2$ and $u = 3x$

$\displaystyle= -\frac{1}{2} \ln \frac{2 + \sqrt{4 - 9x^2}}{|3x|} + C$ $\quad -\frac{1}{a} \ln \frac{a + \sqrt{a^2 - u^2}}{|u|} + C$

b. $\displaystyle\int \frac{dx}{5 - 4x^2} = \frac{1}{2}\int \frac{2\,dx}{(\sqrt{5})^2 - (2x)^2}$ $\quad \int \frac{du}{a^2 - u^2}$ with $a = \sqrt{5}$ and $u = 2x$

$\displaystyle= \frac{1}{2}\left(\frac{1}{2\sqrt{5}} \ln\left|\frac{\sqrt{5} + 2x}{\sqrt{5} - 2x}\right|\right) + C$ $\quad \frac{1}{2a} \ln\left|\frac{a + u}{a - u}\right| + C$

$\displaystyle= \frac{1}{4\sqrt{5}} \ln\left|\frac{\sqrt{5} + 2x}{\sqrt{5} - 2x}\right| + C$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

5.9 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe how the name *hyperbolic function* arose.
2. Which hyperbolic functions have domains that are not all real numbers?
3. Give the hyperbolic identity that corresponds to the trigonometric identity
$$\sin^2 x = \frac{1 - \cos 2x}{2}.$$
4. Find the missing value.
$$\frac{d}{dx}[\operatorname{sech}^{-1}(3x)] = \frac{\square}{3x\sqrt{1 - 9x^2}}$$

Evaluating a Function **In Exercises 5–10, evaluate the function. If the value is not a rational number, round your answer to three decimal places.**

5. (a) $\sinh 3$ (b) $\tanh(-2)$
6. (a) $\cosh 0$ (b) $\operatorname{sech} 1$
7. (a) $\operatorname{csch}(\ln 2)$ (b) $\coth(\ln 5)$
8. (a) $\sinh^{-1} 0$ (b) $\tanh^{-1} 0$
9. (a) $\cosh^{-1} 2$ (b) $\operatorname{sech}^{-1} \frac{2}{3}$
10. (a) $\operatorname{csch}^{-1} 2$ (b) $\coth^{-1} 3$

Verifying an Identity **In Exercises 11–18, verify the identity.**

11. $\sinh x + \cosh x = e^x$
12. $\cosh x - \sinh x = e^{-x}$
13. $\tanh^2 x + \operatorname{sech}^2 x = 1$
14. $\coth^2 x - \operatorname{csch}^2 x = 1$
15. $\cosh^2 x = \dfrac{1 + \cosh 2x}{2}$
16. $\sinh^2 x = \dfrac{-1 + \cosh 2x}{2}$
17. $\sinh 2x = 2 \sinh x \cosh x$
18. $\sinh(x + y) = \sinh x \cosh y + \cosh x \sinh y$

Finding Values of Hyperbolic Functions **In Exercises 19 and 20, use the value of the given hyperbolic function to find the values of the other hyperbolic functions.**

19. $\sinh x = \dfrac{3}{2}$
20. $\tanh x = \dfrac{1}{2}$

Finding a Limit **In Exercises 21–24, find the limit.**

21. $\lim_{x \to \infty} \sinh x$
22. $\lim_{x \to -\infty} \tanh x$
23. $\lim_{x \to 0} \dfrac{\sinh x}{x}$
24. $\lim_{x \to 0^-} \coth x$

Finding a Derivative **In Exercises 25–34, find the derivative of the function.**

25. $f(x) = \sinh 9x$
26. $f(x) = \cosh(8x + 1)$
27. $y = \operatorname{sech} 5x^2$
28. $f(x) = \tanh(4x^2 + 3x)$
29. $f(x) = \ln(\sinh x)$
30. $y = \ln\left(\tanh \dfrac{x}{2}\right)$
31. $h(t) = \dfrac{t}{6} \sinh(-3t)$
32. $y = (x^2 + 1) \coth \dfrac{x}{3}$
33. $f(t) = \arctan(\sinh t)$
34. $g(x) = \operatorname{sech}^2 3x$

Finding an Equation of a Tangent Line **In Exercises 35–38, find an equation of the tangent line to the graph of the function at the given point.**

35. $y = \sinh(1 - x^2), \quad (1, 0)$
36. $y = x^{\cosh x}, \quad (1, 1)$
37. $y = (\cosh x - \sinh x)^2, \quad (0, 1)$
38. $y = e^{\sinh x}, \quad (0, 1)$

Finding Relative Extrema **In Exercises 39–42, find the relative extrema of the function. Use a graphing utility to confirm your result.**

39. $g(x) = x \operatorname{sech} x$
40. $h(x) = 2 \tanh x - x$
41. $f(x) = \sin x \sinh x - \cos x \cosh x, \quad -4 \le x \le 4$
42. $f(x) = x \sinh(x - 1) - \cosh(x - 1)$

Catenary **In Exercises 43 and 44, a model for a power cable suspended between two towers is given. (a) Graph the model. (b) Find the heights of the cable at the towers and at the midpoint between the towers. (c) Find the slope of the cable at the point where the cable meets the right-hand tower.**

43. $y = 10 + 15 \cosh \dfrac{x}{15}, \quad -15 \le x \le 15$
44. $y = 18 + 25 \cosh \dfrac{x}{25}, \quad -25 \le x \le 25$

Finding an Indefinite Integral **In Exercises 45–54, find the indefinite integral.**

45. $\displaystyle\int \cosh 4x \, dx$
46. $\displaystyle\int \operatorname{sech}^2 3x \, dx$
47. $\displaystyle\int \sinh(1 - 2x) \, dx$
48. $\displaystyle\int \frac{\cosh \sqrt{x}}{\sqrt{x}} \, dx$
49. $\displaystyle\int \cosh^2(x - 1) \sinh(x - 1) \, dx$
50. $\displaystyle\int \frac{\sinh x}{1 + \sinh^2 x} \, dx$
51. $\displaystyle\int \frac{\cosh x}{\sinh x} \, dx$
52. $\displaystyle\int \frac{\operatorname{csch}(1/x) \coth(1/x)}{x^2} \, dx$
53. $\displaystyle\int x \operatorname{csch}^2 \frac{x^2}{2} \, dx$
54. $\displaystyle\int \operatorname{sech}^3 x \tanh x \, dx$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Evaluating a Definite Integral **In Exercises 55–60, evaluate the definite integral.**

55. $\int_0^{\ln 2} \tanh x\,dx$

56. $\int_0^1 \cosh^2 x\,dx$

57. $\int_3^4 \operatorname{csch}^2(x-2)\,dx$

58. $\int_{1/2}^1 \operatorname{sech}^2(2x-1)\,dx$

59. $\int_{5/3}^2 \operatorname{csch}(3x-4)\coth(3x-4)\,dx$

60. $\int_0^{\ln 2} 2e^{-x}\cosh x\,dx$

Exploring Concepts

61. Explain graphically why the equation $\cosh x = \sinh x$ has no solution.

62. Use the graphs on page 391 to determine whether each hyperbolic function is even, odd, or neither.

63. Verify the results of Exercise 62 algebraically.

64. HOW DO YOU SEE IT? Use the graphs of f and g shown in the figures to answer the following.



(a) Identify the open interval(s) on which the graphs of f and g are increasing or decreasing.

(b) Identify the open interval(s) on which the graphs of f and g are concave upward or concave downward.

Finding a Derivative **In Exercises 65–74, find the derivative of the function.**

65. $y = \cosh^{-1}(3x)$

66. $y = \operatorname{csch}^{-1}(1-x)$

67. $y = \tanh^{-1}\sqrt{x}$

68. $f(x) = \coth^{-1}(x^2)$

69. $y = \sinh^{-1}(\tan x)$

70. $y = \tanh^{-1}(\sin 2x)$

71. $y = \operatorname{sech}^{-1}(\sin x),\ 0 < x < \pi/2$

72. $y = \coth^{-1}(e^{2x})$

73. $y = 2x\sinh^{-1}(2x) - \sqrt{1+4x^2}$

74. $y = x\tanh^{-1}x + \ln\sqrt{1-x^2}$

Finding an Indefinite Integral **In Exercises 75–82, find the indefinite integral using the formulas from Theorem 5.22.**

75. $\int \frac{1}{3-9x^2}\,dx$

76. $\int \frac{1}{2x\sqrt{1-4x^2}}\,dx$

77. $\int \frac{1}{\sqrt{1+e^{2x}}}\,dx$

78. $\int \frac{x}{9-x^4}\,dx$

79. $\int \frac{1}{\sqrt{x}\sqrt{1+x}}\,dx$

80. $\int \frac{\sqrt{x}}{\sqrt{1+x^3}}\,dx$

81. $\int \frac{-1}{4x-x^2}\,dx$

82. $\int \frac{dx}{(x+2)\sqrt{x^2+4x+8}}$

Evaluating a Definite Integral **In Exercises 83–86, evaluate the definite integral using the formulas from Theorem 5.22.**

83. $\int_3^7 \frac{1}{\sqrt{x^2-4}}\,dx$

84. $\int_1^3 \frac{1}{x\sqrt{4+x^2}}\,dx$

85. $\int_{-1}^1 \frac{1}{16-9x^2}\,dx$

86. $\int_0^1 \frac{1}{\sqrt{25x^2+1}}\,dx$

Differential Equation **In Exercises 87 and 88, find the general solution of the differential equation.**

87. $\frac{dy}{dx} = \frac{x^3-21x}{5+4x-x^2}$

88. $\frac{dy}{dx} = \frac{1-2x}{4x-x^2}$

Area **In Exercises 89–92, find the area of the given region.**

89. $y = \operatorname{sech}\frac{x}{2}$



90. $y = \tanh 2x$



91. $y = \frac{5x}{\sqrt{x^4+1}}$



92. $y = \frac{6}{x\sqrt{9-x^2}}$



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

93. Tractrix Consider the equation of a tractrix

$$y = a\,\text{sech}^{-1}\left(\frac{x}{a}\right) - \sqrt{a^2 - x^2}, \quad a > 0.$$

(a) Find dy/dx.

(b) Let L be the tangent line to the tractrix at the point P. When L intersects the y-axis at the point Q, show that the distance between P and Q is a.

94. Tractrix Show that the boat in Example 5 is always pointing toward the person.

95. Proof Prove that

$$\tanh^{-1} x = \frac{1}{2}\ln\left(\frac{1+x}{1-x}\right), \quad -1 < x < 1.$$

96. Proof Prove that $\sinh^{-1} t = \ln\left(t + \sqrt{t^2+1}\right)$.

97. Using a Right Triangle Show that

$$\arctan(\sinh x) = \arcsin(\tanh x).$$

98. Integration Let $x > 0$ and $b > 0$. Show that

$$\int_{-b}^{b} e^{xt}\,dt = \frac{2\sinh bx}{x}.$$

Proof **In Exercises 99–104, prove the differentiation formula.**

99. $\frac{d}{dx}[\cosh x] = \sinh x$ **100.** $\frac{d}{dx}[\coth x] = -\text{csch}^2 x$

101. $\frac{d}{dx}[\text{sech}\, x] = -\text{sech}\, x \tanh x$

102. $\frac{d}{dx}[\cosh^{-1} x] = \frac{1}{\sqrt{x^2-1}}$

103. $\frac{d}{dx}[\sinh^{-1} x] = \frac{1}{\sqrt{x^2+1}}$

104. $\frac{d}{dx}[\text{sech}^{-1} x] = \frac{-1}{x\sqrt{1-x^2}}$

105. Hyperbolic Identities Tell whether the identity is correct. If it is not correct, explain why or give an example to show that it is not correct. How does the identity compare to the corresponding trigonometric identity?

(a) $\cosh^2 x + \sinh^2 x = 1$

(b) $\cosh(x - y) = \cosh x \cosh y - \sinh x \sinh y$

PUTNAM EXAM CHALLENGE

106. From the vertex $(0, c)$ of the catenary $y = c\cosh(x/c)$ a line L is drawn perpendicular to the tangent to the catenary at point P. Prove that the length of L intercepted by the axes is equal to the ordinate y of the point P.

107. Prove or disprove: there is at least one straight line normal to the graph of $y = \cosh x$ at a point $(a, \cosh a)$ and also normal to the graph of $y = \sinh x$ at a point $(c, \sinh c)$.

[At a point on a graph, the normal line is the perpendicular to the tangent at that point. Also, $\cosh x = (e^x + e^{-x})/2$ and $\sinh x = (e^x - e^{-x})/2$.]

These problems were composed by the Committee on the Putnam Prize Competition. © The Mathematical Association of America. All rights reserved.

SECTION PROJECT

Mercator Map

When flying or sailing, pilots expect to be given a steady compass course to follow. On a standard flat map, this is difficult because a steady compass course results in a curved line, as shown below.



Globe: flight with constant 45° bearing



Standard flat map: flight with constant 45° bearing

For curved lines to appear as straight lines on a flat map, Flemish geographer Gerardus Mercator (1512-1594) realized that latitude lines must be stretched horizontally by a scaling factor of sec ϕ, where ϕ is the angle (in radians) of the latitude line. The Mercator map has latitude lines that are not equidistant, as shown at the right.



Mercator map: flight with constant 45° bearing

To calculate these vertical lengths, imagine a globe with radius R and latitude lines marked at angles of every $\Delta\phi$ radians, with $\Delta\phi = \phi_i - \phi_{i-1}$, as shown in the figure on the left below. The arc length of consecutive latitude lines is $R\Delta\phi$. On the corresponding Mercator map, the vertical distance between the ith and $(i-1)$st latitude lines is $R\Delta\phi \sec\phi_i$, and the total vertical distance from the equator to the nth latitude line is approximately $\sum_{i=1}^{n} R\Delta\phi \sec\phi_i$, as shown in the figure on the right below.





Mercator maps are still used by websites to display the world.

(a) Explain how to calculate the total vertical distance on a Mercator map from the equator to the nth latitude line using calculus.

(b) Using a globe radius of $R = 6$ inches, find the total vertical distances on a Mercator map from the equator to the latitude lines whose angles are 30°, 45°, and 60°.

(c) Explain what happens when you attempt to find the total vertical distance on a Mercator map from the equator to the North Pole.

(d) The *Gudermannian function* $\text{gd}(y) = \int_0^y \frac{dt}{\cosh t}$ expresses the latitude $\phi(y) = \text{gd}(y)$ in terms of the vertical position y on a Mercator map. Show that $\text{gd}(y) = \arctan(\sinh y)$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Review Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Exploring Concepts

This chapter presented several key definitions. First, the natural logarithmic function was defined as an integral.

$$\ln x = \int_1^x \frac{1}{t}\,dt,\ x > 0$$

By the Second Fundamental Theorem of Calculus, this definition leads directly to the derivative of $\ln x$. Second, by defining e^x as the inverse of $\ln x$ (see figure), you developed several important properties, such as

$$\ln e^x = x \quad \text{and} \quad e^{\ln x} = x.$$

You used these definitions and properties to develop the derivatives and integration rules for e^x. You then developed differentiation and integration rules for inverse trigonometric functions and hyperbolic functions.



1. Use a graphing utility to evaluate

$$y_1 = \ln x \quad \text{and} \quad y_2 = e^x$$

for $x = 0.1$, 0.5, 1, 2, and 10. Plot the points on the same set of axes and describe the relationship between y_1 and y_2. How do the domains and ranges of y_1 and y_2 compare? How do the asymptotes of y_1 and y_2 compare?

2. Use L'Hôpital's Rule to evaluate the important limit from Theorem 1.9 in Section 1.3,

$$\lim_{\theta \to 0} \frac{\sin \theta}{\theta}.$$

3. (a) Sketch the region whose area is represented by

$$\int_0^1 \arccos x\,dx.$$

(b) Use the integration capabilities of a graphing utility to approximate the area.

(c) Find the exact area analytically.

4. State the integration formula you would use to perform the integration. Do not integrate.

(a) $\displaystyle\int \sqrt[3]{x}\,dx$ (b) $\displaystyle\int \frac{x}{(x^2+4)^3}\,dx$

(c) $\displaystyle\int \frac{x}{x^2+4}\,dx$ (d) $\displaystyle\int \frac{\sec^2 x}{\tan x}\,dx$

5. Find the derivative of each function. (Assume c is a constant.)

(a) $y = x^c$

(b) $y = c^x$

(c) $y = x^x$

(d) $y = c^c$

6. Evaluate the integral in terms of (a) natural logarithms and (b) inverse hyperbolic functions.

$$\int_{-1/2}^{1/2} \frac{dx}{1-x^2}$$

Sketching a Graph

In Exercises 7 and 8, sketch the graph of the function and state its domain.

7. $f(x) = \ln x - 3$ **8.** $f(x) = \ln(x+3)$

Using Properties of Logarithms

In Exercises 9 and 10, use the properties of logarithms to approximate the indicated logarithms, given that $\ln 4 \approx 1.3863$ and $\ln 5 \approx 1.6094$.

9. (a) $\ln 20$ (b) $\ln \frac{4}{5}$ (c) $\ln 625$ (d) $\ln \sqrt{5}$

10. (a) $\ln 0.0625$ (b) $\ln \frac{5}{4}$ (c) $\ln 16$ (d) $\ln \sqrt[3]{80}$

Expanding a Logarithmic Expression

In Exercises 11 and 12, use the properties of logarithms to expand the logarithmic expression.

11. $\ln \sqrt[5]{\dfrac{4x^2-1}{4x^2+1}}$

12. $\ln[(x^2+1)(x-1)]$

Condensing a Logarithmic Expression

In Exercises 13 and 14, write the expression as the logarithm of a single quantity.

13. $\ln 3 + \frac{1}{3}\ln(4-x^2) - \ln x$

14. $3[\ln x - 2\ln(x^2+1)] + 2\ln 5$

Finding a Derivative

In Exercises 15–22, find the derivative of the function.

15. $g(x) = \ln\sqrt{2x}$ **16.** $f(x) = \ln(3x^2+2x)$

17. $f(x) = x\sqrt{\ln x}$ **18.** $f(x) = [\ln(2x)]^3$

19. $y = \ln\sqrt{\dfrac{x^2+4}{x^2-4}}$ **20.** $y = \ln\dfrac{4x}{x-6}$

21. $y = \dfrac{1}{\ln(1-7x)}$

22. $y = \dfrac{\ln 5x}{1-x}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding an Equation of a Tangent Line **In Exercises 23 and 24, find an equation of the tangent line to the graph of the function at the given point.**

23. $y = \ln(2 + x) + \dfrac{2}{2 + x}, \quad (-1, 2)$

24. $y = 2x^2 + \ln x^2, \quad (1, 2)$

Logarithmic Differentiation **In Exercises 25 and 26, use logarithmic differentiation to find dy/dx.**

25. $y = x^2\sqrt{x - 1}, \quad x > 1$

26. $y = \dfrac{x + 2}{\sqrt{3x - 2}}, \quad x > \dfrac{2}{3}$

Finding an Indefinite Integral **In Exercises 27–32, find the indefinite integral.**

27. $\displaystyle\int \frac{1}{7x - 2}\,dx$

28. $\displaystyle\int \frac{x^2}{x^3 + 1}\,dx$

29. $\displaystyle\int \frac{\sin x}{1 + \cos x}\,dx$

30. $\displaystyle\int \frac{\ln \sqrt{x}}{x}\,dx$

31. $\displaystyle\int \frac{x^2 - 6x + 1}{x^2 + 1}\,dx$

32. $\displaystyle\int \frac{dx}{\sqrt{x}\left(2\sqrt{x} + 5\right)}$

Evaluating a Definite Integral **In Exercises 33–36, evaluate the definite integral.**

33. $\displaystyle\int_1^4 \frac{2x + 1}{2x}\,dx$

34. $\displaystyle\int_1^e \frac{\ln x}{x}\,dx$

35. $\displaystyle\int_0^{\pi/3} \sec\theta\,d\theta$

36. $\displaystyle\int_0^{\pi} \tan\frac{\theta}{3}\,d\theta$

Area **In Exercises 37 and 38, find the area of the region bounded by the graphs of the equations. Use a graphing utility to verify your result.**

37. $y = \dfrac{6x^2}{x^3 - 2}, \ x = 3, \ x = 5, \ y = 0$

38. $y = x + \csc\dfrac{\pi x}{12}, \ x = 2, \ x = 6, \ y = 0$

Finding an Inverse Function **In Exercises 39–44, (a) find the inverse function of f, (b) graph f and f^{-1} on the same set of coordinate axes, (c) verify that $f^{-1}(f(x)) = x$ and $f(f^{-1}(x)) = x$, and (d) state the domains and ranges of f and f^{-1}.**

39. $f(x) = \frac{1}{2}x - 3$

40. $f(x) = 5x - 7$

41. $f(x) = \sqrt{x + 1}$

42. $f(x) = x^3 + 2$

43. $f(x) = \sqrt[3]{x + 1}$

44. $f(x) = x^2 - 5, \quad x \geq 0$

Evaluating the Derivative of an Inverse Function **In Exercises 45–48, verify that f has an inverse function. Then use the function f and the given function value $f(x) = a$ to find $(f^{-1})'(a)$. (*Hint:* Use Theorem 5.9.)**

45. $f(x) = x^3 + 2, \quad f\left(-\sqrt[3]{3}\right) = -1$

46. $f(x) = x\sqrt{x - 3}, \quad f(4) = 4$

47. $f(x) = \tan x, \quad -\dfrac{\pi}{4} \leq x \leq \dfrac{\pi}{4}, \quad f\left(\dfrac{\pi}{6}\right) = \dfrac{\sqrt{3}}{3}$

48. $f(x) = \cos x, \quad 0 \leq x \leq \pi, \quad f\left(\dfrac{\pi}{2}\right) = 0$

Solving an Exponential or Logarithmic Equation **In Exercises 49–52, solve for x accurate to three decimal places.**

49. $e^{3x} = 30$

50. $-4 + 3e^{-2x} = 6$

51. $\ln\sqrt{x + 1} = 2$

52. $\ln x + \ln(x - 3) = 0$

Finding a Derivative **In Exercises 53–58, find the derivative of the function.**

53. $g(t) = t^2e^t$

54. $g(x) = \ln\dfrac{e^x}{1 + e^x}$

55. $y = \sqrt{e^{2x} + e^{-2x}}$

56. $h(z) = e^{-z^2/2}$

57. $g(x) = \dfrac{x^3}{e^{2x}}$

58. $y = 3e^{-3/t}$

Finding an Equation of a Tangent Line **In Exercises 59 and 60, find an equation of the tangent line to the graph of the function at the given point.**

59. $f(x) = e^{6x}, \quad (0, 1)$

60. $h(x) = -xe^{2-x}, \quad (2, -2)$

Relative Extrema and Points of Inflection **In Exercises 61 and 62, find the relative extrema and points of inflection (if any exist) of the function. Use a graphing utility to graph the function and confirm your results.**

61. $f(x) = (x + 1)e^{-x}$

62. $g(x) = \dfrac{1}{\sqrt{2\pi}}e^{-(x-5)^2/2}$

Finding an Indefinite Integral **In Exercises 63–66, find the indefinite integral.**

63. $\displaystyle\int xe^{1-x^2}\,dx$

64. $\displaystyle\int x^2e^{x^3+1}\,dx$

65. $\displaystyle\int \frac{e^{4x} - e^{2x} + 1}{e^x}\,dx$

66. $\displaystyle\int \frac{e^{2x} - e^{-2x}}{e^{2x} + e^{-2x}}\,dx$

Evaluating a Definite Integral **In Exercises 67–70, evaluate the definite integral.**

67. $\displaystyle\int_0^1 xe^{-3x^2}\,dx$

68. $\displaystyle\int_{1/2}^2 \frac{e^{1/x}}{x^2}\,dx$

69. $\displaystyle\int_1^3 \frac{e^x}{e^x - 1}\,dx$

70. $\displaystyle\int_{1/4}^5 \frac{e^{4x} + 1}{4x + e^{4x}}\,dx$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

71. Area Find the area of the region bounded by the graphs of

$y = 2e^{-x}$, $y = 0$, $x = 0$, and $x = 2$.

72. Depreciation The value V of an item t years after it is purchased is

$V = 9000e^{-0.6t}, \quad 0 \le t \le 5.$

(a) Use a graphing utility to graph the function.

(b) Find the rates of change of V with respect to t when $t = 1$ and $t = 4$.

(c) Use a graphing utility to graph the tangent lines to the function when $t = 1$ and $t = 4$.

Sketching a Graph **In Exercises 73 and 74, sketch the graph of the function.**

73. $y = 3^{x/2}$

74. $y = \left(\frac{1}{4}\right)^x$

Solving an Equation **In Exercises 75–80, solve the equation accurate to three decimal places.**

75. $4^{1-x} = 52$

76. $2(3^{x+2}) = 17$

77. $\left(1 + \frac{0.03}{12}\right)^{12t} = 3$

78. $\left(1 + \frac{0.06}{365}\right)^{365t} = 2$

79. $\log_6(x + 1) = 2$

80. $\log_5 x^2 = 4.1$

Finding a Derivative **In Exercises 81–88, find the derivative of the function.**

81. $f(x) = 3^{x-1}$

82. $f(x) = 5^{3x}$

83. $g(t) = \frac{2^{3t}}{t^2}$

84. $f(x) = x(4^{-3x})$

85. $g(x) = \log_3 \sqrt{1 - x}$

86. $h(x) = \log_5 \frac{x}{x - 1}$

87. $y = x^{2x+1}$

88. $y = (3x + 5)^x$

Finding an Indefinite Integral **In Exercises 89 and 90, find the indefinite integral.**

89. $\int (x + 1)5^{(x+1)^2}\,dx$

90. $\int \frac{2^{-1/t}}{t^2}\,dt$

Evaluating a Definite Integral **In Exercises 91 and 92, evaluate the definite integral.**

91. $\int_1^2 6^x\,dx$

92. $\int_{-4}^0 9^{x/2}\,dx$

93. Compound Interest

(a) A deposit of \$550 is made in a savings account that pays an annual interest rate of 1% compounded monthly. What is the balance after 11 years?

(b) How large a deposit, at 5% interest compounded continuously, must be made to obtain a balance of \$10,000 in 15 years?

(c) A deposit earns interest at a rate of r percent compounded continuously and doubles in value in 10 years. Find r.

94. Climb Rate The time t (in minutes) for a small plane to climb to an altitude of h feet is

$t = 50 \log_{10} \frac{18{,}000}{18{,}000 - h}$

where 18,000 feet is as high as the plane can fly.

(a) Determine the domain of the function appropriate for the context of the problem.

(b) Use a graphing utility to graph the function and identify any asymptotes.

(c) Find the time when the altitude is increasing at the greatest rate.

Evaluating a Limit **In Exercises 95–102, use L'Hôpital's Rule to evaluate the limit.**

95. $\lim_{x \to 1} \frac{(\ln x)^2}{x - 1}$

96. $\lim_{x \to 0} \frac{\sin \pi x}{\sin 5\pi x}$

97. $\lim_{x \to \infty} \frac{e^{2x}}{x^2}$

98. $\lim_{x \to \infty} xe^{-x^2}$

99. $\lim_{x \to \infty} (\ln x)^{2/x}$

100. $\lim_{x \to 1^+} (x - 1)^{\ln x}$

101. $\lim_{n \to \infty} 1000\left(1 + \frac{0.09}{n}\right)^n$

102. $\lim_{x \to \infty} \left(1 + \frac{4}{x}\right)^x$

Evaluating an Expression **In Exercises 103 and 104, evaluate each expression without using a calculator. (*Hint:* Make a sketch of a right triangle.)**

103. (a) $\sin\left(\arcsin \frac{1}{2}\right)$

(b) $\cos\left(\arcsin \frac{1}{2}\right)$

104. (a) $\tan(\operatorname{arccot} 2)$

(b) $\cos\left(\operatorname{arcsec} \sqrt{5}\right)$

Finding a Derivative **In Exercises 105–110, find the derivative of the function.**

105. $y = \operatorname{arccsc} 2x^2$

106. $y = \frac{1}{2} \arctan e^{2x}$

107. $y = x \operatorname{arcsec} x$

108. $y = \sqrt{x^2 - 4} - 2 \operatorname{arcsec} \frac{x}{2}, \quad 2 < x < 4$

109. $y = x(\arcsin x)^2 - 2x + 2\sqrt{1 - x^2} \arcsin x$

110. $y = \tan(\arcsin x)$

Finding an Indefinite Integral **In Exercises 111–116, find the indefinite integral.**

111. $\int \frac{1}{e^{2x} + e^{-2x}}\,dx$

112. $\int \frac{1}{3 + 25x^2}\,dx$

113. $\int \frac{x}{\sqrt{1 - x^4}}\,dx$

114. $\int \frac{1}{x\sqrt{9x^2 - 49}}\,dx$

115. $\int \frac{\arctan(x/2)}{4 + x^2}\,dx$

116. $\int \frac{\arcsin 2x}{\sqrt{1 - 4x^2}}\,dx$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Evaluating a Definite Integral **In Exercises 117–120, evaluate the definite integral.**

117. $\displaystyle\int_0^{1/7} \frac{dx}{\sqrt{1-49x^2}}$

118. $\displaystyle\int_0^1 \frac{2x^2}{\sqrt{4-x^6}}\,dx$

119. $\displaystyle\int_{-1}^{2} \frac{10e^{2x}}{25+e^{4x}}\,dx$

120. $\displaystyle\int_{\pi/3}^{\pi/2} \frac{\cos x}{(\sin x)\sqrt{\sin^2 x-(1/4)}}\,dx$

Area **In Exercises 121 and 122, find the area of the given region.**

121. $y = \dfrac{4-x}{\sqrt{4-x^2}}$



122. $y = \dfrac{6}{16+x^2}$



Finding a Derivative **In Exercises 123–128, find the derivative of the function.**

123. $y = \operatorname{sech}(4x-1)$

124. $y = 2x - \cosh\sqrt{x}$

125. $y = \coth 8x^2$

126. $y = \ln(\coth x)$

127. $y = \sinh^{-1}(4x)$

128. $y = x\tanh^{-1}(2x)$

Finding an Indefinite Integral **In Exercises 129–134, find the indefinite integral.**

129. $\displaystyle\int x^2\operatorname{sech}^2 x^3\,dx$

130. $\displaystyle\int \sinh 6x\,dx$

131. $\displaystyle\int \frac{\operatorname{sech}^2 x}{\tanh x}\,dx$

132. $\displaystyle\int \operatorname{csch}^4 3x\coth 3x\,dx$

133. $\displaystyle\int \frac{1}{9-4x^2}\,dx$

134. $\displaystyle\int \frac{x}{\sqrt{x^4-1}}\,dx$

Evaluating a Definite Integral **In Exercises 135–138, evaluate the definite integral.**

135. $\displaystyle\int_1^2 \operatorname{sech} 2x\tanh 2x\,dx$

136. $\displaystyle\int_0^1 \sinh^2 x\,dx$

137. $\displaystyle\int_0^1 \frac{3}{\sqrt{9x^2+16}}\,dx$

138. $\displaystyle\int_{-1}^{0} \frac{2}{49-4x^2}\,dx$

Building on Concepts

139. Consider the function

$$f(x) = \sin(\ln x).$$

(a) Determine the domain of f.

(b) Find two values of x satisfying $f(x) = 1$.

(c) Find two values of x satisfying $f(x) = -1$.

(d) What is the range of f?

(e) Find $f'(x)$ and use calculus to find the maximum value of f on the interval $[1, 10]$.

(f) Use a graphing utility to graph f in the viewing window where $0 \le x \le 5$ and $-2 \le y \le 2$. Estimate $\lim_{x\to 0^+} f(x)$, if it exists.

(g) Determine $\lim_{x\to 0^+} f(x)$ analytically, if it exists.

140. (a) Use a graphing utility to compare the graph of the function $y = e^x$ with the graph of each function below.

(i) $y_1 = 1 + \dfrac{x}{1!}$

(ii) $y_2 = 1 + \dfrac{x}{1!} + \dfrac{x^2}{2!}$

(iii) $y_3 = 1 + \dfrac{x}{1!} + \dfrac{x^2}{2!} + \dfrac{x^3}{3!}$

(b) Identify the pattern of successive polynomials in part (a), extend the pattern one more term, and compare the graph of the resulting polynomial function with the graph of $y = e^x$.

(c) What do you think this pattern implies?

141. Consider the function

$$f(x) = \frac{\ln x}{x}.$$

(a) Use a graphing utility to graph f and show that f is strictly decreasing on (e, ∞).

(b) Show that if $e \le A < B$, then $A^B > B^A$.

(c) Use part (b) to show that $e^\pi > \pi^e$.

142. In Section 1.3, a geometric argument (see figure) was used to prove that

$$\lim_{\theta\to 0} \frac{\sin\theta}{\theta}.$$



(a) Write the area of $\triangle ABD$ in terms of θ.

(b) Write the area of the shaded region in terms of θ.

(c) Write the ratio R of the area of $\triangle ABD$ to that of the shaded region.

(d) Find $\lim_{\theta\to 0} R$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.S. Problem Solving

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

1. Approximation To approximate e^x, you can use a function of the form

$$f(x) = \frac{a + bx}{1 + cx}.$$

(This function is known as a **Padé approximation.**) The values of $f(0)$, $f'(0)$, and $f''(0)$ are equal to the corresponding values of e^x. Show that these values are equal to 1 and find the values of a, b, and c such that $f(0) = f'(0) = f''(0) = 1$. Then use a graphing utility to compare the graphs of f and e^x.

2. Area Consider the three regions A, B, and C determined by the graph of $f(x) = \arcsin x$, as shown in the figure.



(a) Calculate the areas of regions A and B.

(b) Use your answers in part (a) to evaluate the integral

$$\int_{1/2}^{\sqrt{2}/2} \arcsin x \, dx.$$

(c) Use the methods in part (a) to evaluate the integral

$$\int_{1}^{3} \ln x \, dx.$$

(d) Use the methods in part (a) to evaluate the integral

$$\int_{1}^{\sqrt{3}} \arctan x \, dx.$$

3. Finding a Value Find the value of the positive constant c such that

$$\lim_{x\to\infty} \left(\frac{x + c}{x - c}\right)^x = 9.$$

4. Finding Limits Use a graphing utility to estimate each limit. Then calculate each limit using L'Hôpital's Rule. What can you conclude about the form $0 \cdot \infty$?

(a) $\lim_{x\to 0^+} \left(\cot x + \frac{1}{x}\right)$

(b) $\lim_{x\to 0^+} \left(\cot x - \frac{1}{x}\right)$

(c) $\lim_{x\to 0^+} \left[\left(\cot x + \frac{1}{x}\right)\left(\cot x - \frac{1}{x}\right)\right]$

5. Distance Let L be the tangent line to the graph of the function $y = \ln x$ at the point (a, b), where c is the y-intercept of the tangent line, as shown in the figure. Show that the distance between b and c is always equal to 1.



Figure for 5



Figure for 6

6. Distance Let L be the tangent line to the graph of the function $y = e^x$ at the point (a, b), where c is the y-intercept of the tangent line, as shown in the figure. Show that the distance between a and c is always equal to 1.

7. Area Use integration by substitution to find the area under the curve

$$y = \frac{1}{\sin^2 x + 4\cos^2 x}$$

between $x = 0$ and $x = \frac{\pi}{4}$.

8. Areas and Angles

(a) Let $P(\cos t, \sin t)$ be a point on the unit circle $x^2 + y^2 = 1$ in the first quadrant (see figure). Show that t is equal to twice the area of the shaded circular sector AOP.



Figure for part (a)



Figure for part (b)

(b) Let $P(\cosh t, \sinh t)$ be a point on the unit hyperbola $x^2 - y^2 = 1$ in the first quadrant (see figure). Show that t is equal to twice the area of the shaded region AOP. Begin by showing that the area of the shaded region AOP is given by the formula

$$A(t) = \frac{1}{2}\cosh t \sinh t - \int_{1}^{\cosh t} \sqrt{x^2 - 1}\, dx.$$

9. Intersection Graph the exponential function $y = a^x$ for $a = 0.5$, 1.2, and 2.0. Which of these curves intersects the line $y = x$? Determine all positive numbers a for which the curve $y = a^x$ intersects the line $y = x$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

6 Differential Equations

GO DIGITAL

6.1 Slope Fields and Euler's Method
6.2 Growth and Decay
6.3 Separation of Variables and the Logistic Equation
6.4 First-Order Linear Differential Equations

CalcView®



CalcChat®



6.4 Intravenous Feeding *(Exercise 30, p. 437)*

6.3 Wildlife Population *(Example 4, p. 425)*

left, Numstocker/Shutterstock.com; right, W. Perry Conway/Getty Images
Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

6.1 Slope Fields and Euler's Method

GO DIGITAL

- Use initial conditions to find particular solutions of differential equations.
- Use slope fields to approximate solutions of differential equations.
- Use Euler's Method to approximate solutions of differential equations.

Big Ideas of Calculus

A differential equation is an equation involving a function and one or more of its derivatives. In many applications, the function represents a physical quantity, the derivatives represent the rates of changes, and the differential equation defines the relationship between the quantities. You will solve differential equations using three approaches—numerical, graphical, and analytic. Applications involving differential equations include velocities of falling objects, learning curves, chemical reactions, and population models.

General and Particular Solutions

In this text, you will learn that physical phenomena can be described by differential equations. Recall that a **differential equation** in x and y is an equation that involves x, y, and derivatives of y. For example,

$$2xy' - 3y = 0 \qquad \text{Differential equation}$$

is a differential equation. In Section 6.2, you will learn that problems involving radioactive decay, population growth, and Newton's Law of Cooling can be formulated in terms of differential equations.

A function $y = f(x)$ is called a **solution** of a differential equation if the equation is satisfied when y and its derivatives are replaced by $f(x)$ and its derivatives. For example, differentiation and substitution would show that $y = e^{-2x}$ is a solution of the differential equation $y' + 2y = 0$. It can be shown that every solution of this differential equation is of the form

$$y = Ce^{-2x} \qquad \text{General solution of } y' + 2y = 0$$

where C is any real number. This solution is called the **general solution.** Some differential equations have **singular solutions** that cannot be written as special cases of the general solution. Such solutions, however, are not considered in this text. The **order** of a differential equation is determined by the highest-order derivative in the equation. For instance, $y' = 4y$ is a first-order differential equation.

In Section 4.1, Example 9, you saw that the second-order differential equation $s''(t) = -32$ has the general solution

$$s(t) = -16t^2 + C_1t + C_2 \qquad \text{General solution of } s''(t) = -32$$

which contains two arbitrary constants. It can be shown that a differential equation of order n has a general solution with n arbitrary constants.

EXAMPLE 1 Determining Solutions

Determine whether each function is a solution of the differential equation $y'' - y = 0$.

a. $y = \sin x$ **b.** $y = 4e^{-x}$ **c.** $y = Ce^{x}$

Solution

a. Because $y = \sin x$, $y' = \cos x$, and $y'' = -\sin x$, it follows that

$$y'' - y = -\sin x - \sin x = -2\sin x \neq 0.$$

So, $y = \sin x$ is *not* a solution.

b. Because $y = 4e^{-x}$, $y' = -4e^{-x}$, and $y'' = 4e^{-x}$, it follows that

$$y'' - y = 4e^{-x} - 4e^{-x} = 0.$$

So, $y = 4e^{-x}$ is a solution.

c. Because $y = Ce^{x}$, $y' = Ce^{x}$, and $y'' = Ce^{x}$, it follows that

$$y'' - y = Ce^{x} - Ce^{x} = 0.$$

So, $y = Ce^{x}$ is a solution for any value of C. ■

REMARK Using techniques you will learn in Section 16.2, the general solution of the differential equation $y'' - y = 0$ in Example 1 is

$$y = C_1e^{x} + C_2e^{-x}.$$

Verify that this function is a solution of the differential equation.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Several solution curves for $y' + 2y = 0$
Figure 6.1

Geometrically, the general solution of a first-order differential equation represents a family of curves known as **solution curves,** one for each value assigned to the arbitrary constant. For instance, every function of the form

$$y = Ce^{-2x}$$ General solution of $y' + 2y = 0$

is a solution of the differential equation

$$y' + 2y = 0.$$

Figure 6.1 shows four of the solution curves corresponding to different values of C.

As discussed in Section 4.1, **particular solutions** of a differential equation are obtained from **initial conditions** that give the values of the dependent variable or one of its derivatives for particular values of the independent variable. The term "initial condition" stems from the fact that, often in problems involving time, the value of the dependent variable or one of its derivatives is known at the *initial* time $t = 0$. For instance, the second-order differential equation

$$s''(t) = -32$$

having the general solution

$$s(t) = -16t^2 + C_1t + C_2$$ General solution of $s''(t) = -32$

might have the following initial conditions.

$$s(0) = 80, \quad s'(0) = 64$$ Initial conditions

In this case, the initial conditions yield the particular solution

$$s(t) = -16t^2 + 64t + 80.$$ Particular solution

EXAMPLE 2 Finding a Particular Solution

See LarsonCalculus.com for an interactive version of this type of example.

For the differential equation

$$xy' - 3y = 0$$

verify that $y = Cx^3$ is a solution. (Assume $x > 0$.) Then find the particular solution determined by the initial condition $y = 2$ when $x = 3$.

Solution You know that $y = Cx^3$ is a solution because $y' = 3Cx^2$ and

$$xy' - 3y = x(3Cx^2) - 3(Cx^3) = 0.$$

Furthermore, the initial condition $y = 2$ when $x = 3$ yields

$$y = Cx^3$$ General solution

$$2 = C(3)^3$$ Substitute initial condition.

$$\frac{2}{27} = C$$ Solve for C.

and you can conclude that the particular solution is

$$y = \frac{2x^3}{27}, \quad x > 0$$ Particular solution

as shown in Figure 6.2. Try checking this solution by substituting for y and y' in the original differential equation. ■



For the initial condition $y = 2$ when $x = 3$, the particular solution of the differential equation $xy' - 3y = 0$, $x > 0$, is $y = (2x^3)/27$.
Figure 6.2

Note that to determine a particular solution, the number of initial conditions must match the number of constants in the general solution.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Slope Fields

Solving a differential equation analytically can be difficult or even impossible. However, there is a graphical approach you can use to learn a lot about the solution of a differential equation. Consider a differential equation of the form

$$y' = F(x, y) \qquad \text{Differential equation}$$

where $F(x, y)$ is some expression in x and y. At each point (x, y) in the xy-plane where F is defined, the differential equation determines the slope $y' = F(x, y)$ of the solution at that point. If you draw short line segments with slope $F(x, y)$ at selected points (x, y) in the domain of F, then these line segments form a **slope field,** or a *direction field*, for the differential equation $y' = F(x, y)$. Each line segment has the same slope as the solution curve through that point. A slope field shows the general shape of all the solutions and can be helpful in getting a visual perspective of the directions of the solutions of a differential equation.

EXAMPLE 3 Sketching a Slope Field

Sketch a slope field for the differential equation $y' = x - y$ for the points $(-1, 1)$, $(0, 1)$, and $(1, 1)$.

Solution The slope of the solution curve at any point (x, y) is

$$F(x, y) = x - y. \qquad \text{Slope at } (x, y)$$

So, the slope at each point can be found as shown.

Slope at $(-1, 1)$: $y' = -1 - 1 = -2$
Slope at $(0, 1)$: $y' = 0 - 1 = -1$
Slope at $(1, 1)$: $y' = 1 - 1 = 0$

Draw short line segments at the three points with their respective slopes, as shown in Figure 6.3.



Figure 6.3

EXAMPLE 4 Identifying Slope Fields for Differential Equations

Match each slope field with its differential equation.

a.



b.



c.



i. $y' = x + y$ **ii.** $y' = x$ **iii.** $y' = y$

Solution

a. The slope at any point along the y-axis is 0. The only equation that satisfies this condition is $y' = x$. So, the graph matches equation (ii).

b. The slope at the point $(1, -1)$ is 0. The only equation that satisfies this condition is $y' = x + y$. So, the graph matches equation (i).

c. The slope at any point along the x-axis is 0. The only equation that satisfies this condition is $y' = y$. So, the graph matches equation (iii). ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

A solution curve of a differential equation $y' = F(x, y)$ is simply a curve in the xy-plane whose tangent line at each point (x, y) has slope equal to $F(x, y)$. This is illustrated in Example 5.

EXAMPLE 5 Sketching a Solution Using a Slope Field

Sketch a slope field for the differential equation

$$y' = 2x + y.$$

Use the slope field to sketch the solution that passes through the point $(1, 1)$.

Solution Make a table showing the slopes at several points. The table shown is a small sample. The slopes at many other points should be calculated to get a representative slope field.

x	-2	-2	-1	-1	0	0	1	1	2	2
y	-1	1	-1	1	-1	1	-1	1	-1	1
$y' = 2x + y$	-5	-3	-3	-1	-1	1	1	3	3	5

Next, draw line segments at the points with their respective slopes, as shown in Figure 6.4.



Slope field for $y' = 2x + y$
Figure 6.4



Particular solution for $y' = 2x + y$ passing through $(1, 1)$
Figure 6.5

After the slope field is drawn, start at the initial point $(1, 1)$ and move to the right in the direction of the line segment. Continue to draw the solution curve so that it moves parallel to the nearby line segments. Do the same to the left of $(1, 1)$. The resulting solution is shown in Figure 6.5.

In Example 5, note that the slope field shows that y' increases to infinity as x increases.

TECHNOLOGY Sketching a slope field without a graphing utility is tedious. In practice, slope fields are usually drawn using a graphing utility. If you have access to a graphing utility that can graph slope fields, try graphing the slope field for the differential equation in Example 5. One example of a slope field drawn by a graphing utility is shown at the right.



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Euler's Method



Figure 6.6

Euler's Method is a numerical approach to approximating the particular solution of the differential equation

$$y' = F(x, y)$$

that passes through the point (x_0, y_0). From the given information, you know that the graph of the solution passes through the point (x_0, y_0) and has a slope of $F(x_0, y_0)$ at this point. This gives you a "starting point" for approximating the solution.

From this starting point, you can proceed in the direction indicated by the slope. Using a small step h, move along the tangent line until you arrive at the point (x_1, y_1), where

$$x_1 = x_0 + h \quad \text{and} \quad y_1 = y_0 + hF(x_0, y_0)$$

as shown in Figure 6.6. Then, using (x_1, y_1) as a new starting point, repeat the process to obtain a second point (x_2, y_2). The values of x_i and y_i are shown below.

$$\begin{aligned} x_1 &= x_0 + h & y_1 &= y_0 + hF(x_0, y_0) \\ x_2 &= x_1 + h & y_2 &= y_1 + hF(x_1, y_1) \\ &\vdots & &\vdots \\ x_n &= x_{n-1} + h & y_n &= y_{n-1} + hF(x_{n-1}, y_{n-1}) \end{aligned}$$

When using this method, note that you can obtain better approximations of the exact solution by choosing smaller and smaller step sizes.

EXAMPLE 6 Approximating a Solution Using Euler's Method

Use Euler's Method to approximate the particular solution of the differential equation

$$y' = x - y$$

passing through the point $(0, 1)$. Use a step of $h = 0.1$.

Solution Using $h = 0.1$, $x_0 = 0$, $y_0 = 1$, and $F(x, y) = x - y$, you have

$$x_0 = 0, \quad x_1 = 0.1, \quad x_2 = 0.2, \quad x_3 = 0.3$$

and the first three approximations are

$$\begin{aligned} y_1 &= y_0 + hF(x_0, y_0) = 1 + (0.1)(0 - 1) = 0.9 \\ y_2 &= y_1 + hF(x_1, y_1) = 0.9 + (0.1)(0.1 - 0.9) = 0.82 \\ y_3 &= y_2 + hF(x_2, y_2) = 0.82 + (0.1)(0.2 - 0.82) = 0.758. \end{aligned}$$

The first ten approximations are shown in the table. You can plot these values to see a graph of the approximate solution, as shown in Figure 6.7.



Figure 6.7

n	0	1	2	3	4	5	6	7	8	9	10
x_n	0	0.1	0.2	0.3	0.4	0.5	0.6	0.7	0.8	0.9	1
y_n	1	0.9	0.82	0.758	0.712	0.681	0.663	0.657	0.661	0.675	0.697

In Example 6, the exact solution of the differential equation $y' = x - y$ is

$$y = x - 1 + 2e^{-x}.$$

Figure 6.7 compares this exact solution with the approximate solution obtained in Example 6.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

6.1 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe how to determine whether a function $y = f(x)$ is a solution of a differential equation.
2. Explain what the general solution of a first-order differential equation represents geometrically.
3. Explain what the line segments on a slope field represent.
4. When is it appropriate to use Euler's Method?

Verifying a Solution **In Exercises 5–10, verify that the function is a solution of the differential equation.**

Function	Differential Equation
5. $y = Ce^{5x}$	$y' = 5y$
6. $y = e^{-2x}$	$3y' + 5y = -e^{-2x}$
7. $y = C_1 \sin x - C_2 \cos x$	$y'' + y = 0$
8. $y = C_1e^{-x} \cos x + C_2e^{-x} \sin x$	$y'' + 2y' + 2y = 0$
9. $y = (-\cos x) \ln\lvert\sec x + \tan x\rvert$	$y'' + y = \tan x$
10. $y = \frac{2}{5}(e^{-4x} + e^{x})$	$y'' + 4y' = 2e^{x}$

Verifying a Particular Solution **In Exercises 11–14, verify that the function is a particular solution of the differential equation.**

Function	Differential Equation and Initial Condition
11. $y = \sin x \cos x - \cos^2 x$	$2y + y' = 2 \sin 2x - 1$, $y\left(\frac{\pi}{4}\right) = 0$
12. $y = 6x - 4 \sin x + 1$	$y' = 6 - 4 \cos x$, $y(0) = 1$
13. $y = 4e^{-6x^2}$	$y' = -12xy$, $y(0) = 4$
14. $y = e^{-\cos x}$	$y' = y \sin x$, $y\left(\frac{\pi}{2}\right) = 1$

Determining a Solution **In Exercises 15–22, determine whether the function is a solution of the differential equation $y^{(4)} - 16y = 0$.**

15. $y = 3 \cos 2x$
16. $y = 3 \sin 2x$
17. $y = 3 \cos x$
18. $y = 2 \sin x$
19. $y = e^{-2x}$
20. $y = 5 \ln x$
21. $y = \ln x + e^{2x} + Cx^4$
22. $y = 3e^{2x} - 4 \sin 2x$

Determining a Solution **In Exercises 23–30, determine whether the function is a solution of the differential equation $xy' - 2y = x^3e^x$, $x > 0$.**

23. $y = x^2 + e^{x}$
24. $y = x^3 - e^{-x}$
25. $y = x^2e^{x}$
26. $y = x^2(2 + e^{x})$
27. $y = e^{x} - \sin x$
28. $y = x^2e^{x} + \sin x + \cos x$
29. $y = 2e^{x} \ln x$
30. $y = x^2e^{x} - 5x^2$

Finding a Particular Solution **In Exercises 31–34, some of the curves corresponding to different values of C in the general solution of the differential equation are shown in the graph. Find the particular solution that passes through the point shown on the graph.**

31. $y = Ce^{-x/2}$, $2y' + y = 0$



32. $y(x^2 + y) = C$, $2xy + (x^2 + 2y)y' = 0$



33. $y^2 = Cx^3$, $2xy' - 3y = 0, \quad x > 0$



34. $2x^2 - y^2 = C$, $yy' - 2x = 0$



Graphing Particular Solutions Using Technology **In Exercises 35 and 36, the general solution of the differential equation is given. Use a graphing utility to graph the particular solutions for the given values of C.**

35. $4yy' - x = 0$, $4y^2 - x^2 = C$, $C = 0, C = \pm 1, C = \pm 4$
36. $yy' + x = 0$, $x^2 + y^2 = C$, $C = 0, C = 1, C = 4$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding a Particular Solution **In Exercises 37–42, verify that the general solution satisfies the differential equation. Then find the particular solution that satisfies the initial condition(s).**

37. $y = Ce^{-6x}$

$y' + 6y = 0$

$y = 3$ when $x = 0$

38. $3x^2 + 2y^2 = C$

$3x + 2yy' = 0$

$y = 3$ when $x = 1$

39. $y = C_1 \sin 3x + C_2 \cos 3x$

$y'' + 9y = 0$

$y = 2$ when $x = \frac{\pi}{6}$

$y' = 1$ when $x = \frac{\pi}{6}$

40. $y = C_1 + C_2 \ln x$

$xy'' + y' = 0, x > 0$

$y = 0$ when $x = 2$

$y' = \frac{1}{2}$ when $x = 2$

41. $y = C_1x + C_2x^3$

$x^2y'' - 3xy' + 3y = 0, x > 0$

$y = 0$ when $x = 2$

$y' = 4$ when $x = 2$

42. $y = e^{2x/3}(C_1 + C_2x)$

$9y'' - 12y' + 4y = 0$

$y = 4$ when $x = 0$

$y = 0$ when $x = 3$

Finding a General Solution **In Exercises 43–52, use integration to find a general solution of the differential equation.**

43. $\frac{dy}{dx} = 12x^2$

44. $\frac{dy}{dx} = 3x^8 - 2x$

45. $\frac{dy}{dx} = \frac{x}{1 + x^2}$

46. $\frac{dy}{dx} = \frac{e^x}{4 + e^x}$

47. $\frac{dy}{dx} = \sin 2x$

48. $\frac{dy}{dx} = \tan^2 x$

49. $\frac{dy}{dx} = x\sqrt{x - 6}$

50. $\frac{dy}{dx} = 2x\sqrt{4x^2 + 1}$

51. $\frac{dy}{dx} = xe^{x^2}$

52. $\frac{dy}{dx} = 5(\sin x)e^{\cos x}$

Slope Field **In Exercises 53–56, a differential equation and its slope field are given. Complete the table by determining the slopes (if possible) in the slope field at the given points.**

x	-4	-2	0	2	4	8
y	2	0	4	4	6	8
dy/dx						

53. $\frac{dy}{dx} = \frac{2x}{y}$



54. $\frac{dy}{dx} = y - x$



55. $\frac{dy}{dx} = x \cos \frac{\pi y}{8}$



56. $\frac{dy}{dx} = \tan \frac{\pi y}{6}$



Matching **In Exercises 57–60, match the differential equation with its slope field. [The slope fields are labeled (a), (b), (c), and (d).]**

(a)



(b)



(c)



(d)



57. $\frac{dy}{dx} = \sin 2x$

58. $\frac{dy}{dx} = \frac{1}{2} \cos x$

59. $\frac{dy}{dx} = e^{-2x}$

60. $\frac{dy}{dx} = \frac{x}{x^2 + 1}$

Slope Field **In Exercises 61–64, (a) sketch the slope field for the differential equation, (b) use the slope field to sketch the solution that passes through the given point, and (c) discuss the graph of the solution as $x \to \infty$ and $x \to -\infty$. Use a graphing utility to verify your results. To print a blank coordinate plane, go to *MathGraphs.com*.**

61. $y' = 3 - x, \quad (4, 2)$

62. $y' = \frac{1}{3}x^2 - \frac{1}{2}x, \quad (1, 1)$

63. $y' = y - 4x, \quad (2, 2)$

64. $y' = y + xy, \quad (0, -4)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

65. Slope Field Use the slope field for the differential equation $y' = 1/x$, where $x > 0$, to sketch the graph of the solution that satisfies each given initial condition. Then make a conjecture about the behavior of a particular solution of $y' = 1/x$ as $x \to \infty$. To print an enlarged copy of the graph, go to *MathGraphs.com.*



(a) $(1, 0)$

(b) $(2, -1)$

66. Slope Field Use the slope field for the differential equation $y' = 1/y$, where $y > 0$, to sketch the graph of the solution that satisfies each given initial condition. Then make a conjecture about the behavior of a particular solution of $y' = 1/y$ as $x \to \infty$. To print an enlarged copy of the graph, go to *MathGraphs.com.*



(a) $(0, 1)$

(b) $(1, 1)$

Slope Field **In Exercises 67–72, use a computer algebra system to (a) graph the slope field for the differential equation and (b) graph the solution satisfying the specified initial condition.**

67. $\dfrac{dy}{dx} = 0.25y, \quad y(0) = 4$

68. $\dfrac{dy}{dx} = 4 - y, \quad y(0) = 6$

69. $\dfrac{dy}{dx} = 0.02y(10 - y), \quad y(0) = 2$

70. $\dfrac{dy}{dx} = 0.2x(2 - y), \quad y(0) = 9$

71. $\dfrac{dy}{dx} = 0.4y(3 - x), \quad y(0) = 1$

72. $\dfrac{dy}{dx} = \dfrac{1}{2}e^{-x/8} \sin \dfrac{\pi y}{4}, \quad y(0) = 2$

Euler's Method **In Exercises 73–78, use Euler's Method to make a table of values for the approximate solution of the differential equation with the specified initial value. Use n steps of size h.**

73. $y' = x + y, \quad y(0) = 2, \quad n = 10, \quad h = 0.1$

74. $y' = x + y, \quad y(0) = 2, \quad n = 20, \quad h = 0.05$

75. $y' = 3x - 2y, \quad y(0) = 3, \quad n = 10, \quad h = 0.05$

76. $y' = 0.5x(3 - y), \quad y(0) = 1, \quad n = 5, \quad h = 0.4$

77. $y' = e^{xy}, \quad y(0) = 1, \quad n = 10, \quad h = 0.1$

78. $y' = \cos x + \sin y, \quad y(0) = 5, \quad n = 10, \quad h = 0.1$

Euler's Method **In Exercises 79–81, complete the table using the exact solution of the differential equation and two approximations obtained using Euler's Method to approximate the particular solution of the differential equation. Use $h = 0.2$ and $h = 0.1$, and compute each approximation to four decimal places.**

x	0	0.2	0.4	0.6	0.8	1
$y(x)$ (exact)						
$y(x)$ ($h = 0.2$)						
$y(x)$ ($h = 0.1$)						

	Differential Equation	Initial Condition	Exact Solution
79.	$\dfrac{dy}{dx} = y$	$(0, 3)$	$y = 3e^x$
80.	$\dfrac{dy}{dx} = \dfrac{2x}{y}$	$(0, 2)$	$y = \sqrt{2x^2 + 4}$
81.	$\dfrac{dy}{dx} = y + \cos x$	$(0, 0)$	$y = \dfrac{1}{2}(\sin x - \cos x + e^x)$

82. Euler's Method Compare the values of the approximations in Exercises 79–81 with the values given by the exact solution. How does the error change as h increases?

83. Temperature At time $t = 0$ minutes, the temperature of an object is 140°F. The temperature of the object is changing at the rate given by the differential equation

$$\frac{dy}{dt} = -\frac{1}{2}(y - 72).$$

(a) Use a graphing utility and Euler's Method to approximate the particular solutions of this differential equation at $t = 1$, 2, and 3. Use a step size of $h = 0.1$. (A graphing utility program for Euler's Method is available at *LarsonCalculus.com.*)

(b) Compare your results with the exact solution

$$y = 72 + 68e^{-t/2}.$$

(c) Repeat parts (a) and (b) using a step size of $h = 0.05$. Compare the results.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

84. HOW DO YOU SEE IT? The graph shows a solution of one of the following differential equations. Which differential equation was used? Explain your reasoning.

(a) $y' = xy$

(b) $y' = \dfrac{4x}{y}$

(c) $y' = -4xy$

(d) $y' = 4 - xy$



Exploring Concepts

85. Explain when Euler's Method produces an exact particular solution of a differential equation.

86. It is known that $y = Ce^{kx}$ is a solution of the differential equation $y' = 0.07y$. Is it possible to determine C or k from the information given? Explain.

True or False? **In Exercises 87 and 88, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

87. If $y = f(x)$ is a solution of a first-order differential equation, then $y = f(x) + C$ is also a solution.

88. A slope field shows one particular solution of a differential equation.

89. Errors and Euler's Method The exact solution of the differential equation $y' = -2y$, where $y(0) = 4$, is

$y = 4e^{-2x}$.

(a) Use a graphing utility to complete the table, where y is the exact value of the solution, y_1 is the approximate solution using Euler's Method with $h = 0.1$, y_2 is the approximate solution using Euler's Method with $h = 0.2$, e_1 is the absolute error $|y - y_1|$, e_2 is the absolute error $|y - y_2|$, and r is the ratio e_1/e_2.

x	0	0.2	0.4	0.6	0.8	1
y						
y_1						
y_2						
e_1						
e_2						
r						

(b) What can you conclude about the ratio r as h changes?

(c) Predict the absolute error when $h = 0.05$.

90. Chebyshev Polynomials The **Chebyshev Polynomials** are defined recursively by

$T_0(x) = 1$, $T_1(x) = x$, and $T_{n+1}(x) = 2xT_n - T_{n-1}$,

$n = 1, 2, 3, \ldots$.

(a) Calculate $T_2(x)$, $T_3(x)$, and $T_4(x)$.

(b) It can be shown that $T_n(x)$ is a solution of the Chebyshev differential equation

$(1 - x^2)y'' - xy' + n^2y = 0, n = 0, 1, 2, \ldots$.

Show that $T_0(x)$, $T_1(x)$, and $T_2(x)$ are solutions of the Chebyshev differential equation.

91. Electric Circuit The diagram shows a simple electric circuit consisting of a power source, a resistor, and an inductor.



A model of the current I, in amperes (A), at time t is given by the first-order differential equation

$$L\frac{dI}{dt} + RI = E(t)$$

where $E(t)$ is the voltage (V) produced by the power source, R is the resistance, in ohms (Ω), and L is the inductance, in henrys (H). Suppose the electric circuit consists of a 24-V power source, a 12-Ω resistor, and a 4-H inductor.

(a) Sketch a slope field for the differential equation.

(b) What is the limiting value of the current? Explain.

92. Slope Field A slope field shows that the slope at the point $(1, 1)$ is 6. Does this slope field represent the family of solutions for the differential equation $y' = 4x + 2y$? Explain.

93. Think About It It is known that $y = A \sin \omega t$ is a solution of the differential equation $y'' + 16y = 0$. Find the value(s) of ω.

PUTNAM EXAM CHALLENGE

94. Let f be a twice-differentiable real-valued function satisfying $f(x) + f''(x) = -xg(x)f'(x)$, where $g(x) \geq 0$ for all real x. Prove that $|f(x)|$ is bounded.

95. Prove that if the family of integral curves of the differential equation

$$\frac{dy}{dx} + p(x)y = q(x), \quad p(x) \cdot q(x) \neq 0$$

is cut by the line $x = k$, the tangents at the points of intersection are concurrent.

These problems were composed by the Committee on the Putnam Prize Competition. © The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

6.2 Growth and Decay

GO DIGITAL

- Use separation of variables to solve a simple differential equation.
- Use exponential functions to model growth and decay in applied problems.

Differential Equations

In Section 6.1, you learned to analyze the solutions of differential equations visually using slope fields and to approximate solutions numerically using Euler's Method. Analytically, you have learned to solve only two types of differential equations—those of the forms $y' = f(x)$ and $y'' = f(x)$. In this section, you will learn how to solve a more general type of differential equation. The strategy is to rewrite the equation so that each variable occurs on only one side of the equation. This strategy is called *separation of variables*. (You will study this strategy in detail in Section 6.3.)

EXAMPLE 1 **Solving a Differential Equation**

$$y' = \frac{2x}{y}$$ Original equation

$$yy' = 2x$$ Multiply each side by y.

$$\int yy'\,dx = \int 2x\,dx$$ Integrate each side with respect to x.

$$\int y\,dy = \int 2x\,dx$$ $dy = y'\,dx$

$$\frac{1}{2}y^2 = x^2 + C_1$$ Apply Power Rule.

$$y^2 - 2x^2 = C$$ Rewrite, letting $C = 2C_1$.

So, the general solution is $y^2 - 2x^2 = C$. ■

REMARK You can use implicit differentiation to check the solution to Example 1.

When you integrate each side of the equation in Example 1, you do not need to add a constant of integration to each side. When you do, you still obtain the same result.

$$\int y\,dy = \int 2x\,dx$$

$$\frac{1}{2}y^2 + C_2 = x^2 + C_3$$

$$\frac{1}{2}y^2 = x^2 + (C_3 - C_2)$$

$$\frac{1}{2}y^2 = x^2 + C_1$$ Rewrite, letting $C_1 = C_3 - C_2$.

Some people prefer to use Leibniz notation and differentials when applying separation of variables. The solution to Example 1 is shown below using this notation.

$$\frac{dy}{dx} = \frac{2x}{y}$$

$$y\,dy = 2x\,dx$$

$$\int y\,dy = \int 2x\,dx$$

$$\frac{1}{2}y^2 = x^2 + C_1$$

$$y^2 - 2x^2 = C$$

Exploration

In Example 1, the general solution of the differential equation is

$$y^2 - 2x^2 = C.$$

Use a graphing utility to sketch the particular solutions for $C = \pm 2$, $C = \pm 1$, and $C = 0$. Describe the solutions graphically. Is the following statement true of each solution?

The slope of the graph at the point (x, y) is equal to twice the ratio of x and y.

Explain your reasoning. Are all curves for which this statement is true represented by the general solution?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Growth and Decay Models

In many applications, the rate of change of a variable y is proportional to the value of y. When y is a function of time t, the proportion can be written as shown.

Rate of change of y is proportional to y.

$$\frac{dy}{dt} = ky$$

The general solution of this differential equation is given in the next theorem.

THEOREM 6.1 Exponential Growth and Decay

If y is a differentiable function of t such that $y > 0$ and $dy/dt = ky$ for some constant k, then

$$y = Ce^{kt}$$

where C is the **initial value** of y, and k is the **proportionality constant.** **Exponential growth** occurs when $k > 0$, and **exponential decay** occurs when $k < 0$.

Proof

$$\frac{dy}{dt} = ky \qquad \text{Write original equation.}$$

$$\frac{dy}{y} = k\,dt \qquad \text{Separate variables.}$$

$$\int \frac{dy}{y} = \int k\,dt \qquad \text{Integrate each side.}$$

$$\ln y = kt + C_1 \qquad \text{Find antiderivative of each side.}$$

$$y = e^{kt + C_1} \qquad \text{Exponentiate each side.}$$

$$y = e^{kt}e^{C_1} \qquad \text{Property of exponents}$$

$$y = Ce^{kt} \qquad \text{Let } C = e^{C_1}.$$

So, all solutions of $y' = ky$ are of the form $y = Ce^{kt}$. Remember that you can differentiate the function $y = Ce^{kt}$ with respect to t to verify that $y' = ky$.

REMARK Notice that you do not need to write $\ln|y|$ because $y > 0$.

EXAMPLE 2 Using an Exponential Growth Model

The rate of change of y is proportional to y. When $t = 0$, $y = 2$, and when $t = 2$, $y = 4$. What is the value of y when $t = 3$?

Solution Because $y' = ky$, you know that y and t are related by the equation $y = Ce^{kt}$. You can find the values of the constants C and k by applying the initial conditions.

$$2 = Ce^0 \Rightarrow C = 2 \qquad \text{When } t = 0,\ y = 2.$$

$$4 = 2e^{2k} \Rightarrow k = \frac{1}{2}\ln 2 \approx 0.3466 \qquad \text{When } t = 2,\ y = 4.$$

So, the model is $y = 2e^{0.3466t}$. When $t = 3$, the value of y is $2e^{0.3466(3)} \approx 5.657$. See Figure 6.8.



If the rate of change of y is proportional to y, then y follows an exponential model.

Figure 6.8

Using logarithmic properties, the value of k in Example 2 can also be written as $\ln\sqrt{2}$. So, the model becomes $y = 2e^{(\ln\sqrt{2})t}$, which can be rewritten as $y = 2(\sqrt{2})^t$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

TECHNOLOGY Most graphing utilities have curve-fitting capabilities that can be used to find models that represent data. Use the *exponential regression* feature of a graphing utility and the information in Example 2 to find a model for the data. How does your model compare with the given model?

Radioactive decay is measured in terms of *half-life*—the number of years required for half of the atoms in a sample of radioactive material to decay. The rate of decay is proportional to the amount present. The half-lives of some common radioactive isotopes are listed below.

Uranium (^{238}U)	4,470,000,000 years
Plutonium (^{239}Pu)	24,100 years
Carbon (^{14}C)	5715 years
Radium (^{226}Ra)	1599 years
Einsteinium (^{254}Es)	276 days
Radon (^{222}Rn)	3.82 days
Nobelium (^{257}No)	25 seconds

EXAMPLE 3 Radioactive Decay

Ten grams of the plutonium isotope ^{239}Pu were released in a nuclear accident. How long will it take for the 10 grams to decay to 1 gram?

Solution Let y represent the mass (in grams) of the plutonium. Because the rate of decay is proportional to y, you know that $y = Ce^{kt}$, where t is the time in years. To find the values of the constants C and k, apply the initial conditions. Using the fact that $y = 10$ when $t = 0$, you can write

$$10 = Ce^{k(0)} \quad \Rightarrow \quad 10 = Ce^0$$

which implies that $C = 10$. Next, using the fact that the half-life of ^{239}Pu is 24,100 years, you have $y = 10/2 = 5$ when $t = 24{,}100$. So, you can write

$$5 = 10e^{k(24{,}100)} \qquad \text{Substitute.}$$

$$\frac{1}{2} = e^{24{,}100k} \qquad \text{Divide each side by 10.}$$

$$\ln\frac{1}{2} = \ln e^{24{,}100k} \qquad \text{Take natural log of each side.}$$

$$\ln\frac{1}{2} = 24{,}100k \qquad \text{Apply inverse property.}$$

$$\frac{1}{24{,}100}\ln\frac{1}{2} = k \qquad \text{Divide each side by 24,100.}$$

$$-0.000028761 \approx k. \qquad \text{Use a calculator.}$$

So, the model is

$$y = 10e^{-0.000028761t}. \qquad \text{Half-life model}$$

To find the time it would take for 10 grams to decay to 1 gram, solve for t in the equation $1 = 10e^{-0.000028761t}$. The solution is approximately 80,059 years. ■

From Example 3, notice that in an exponential growth or decay problem, it is easy to solve for C when you are given the value of y at $t = 0$. The next example demonstrates a procedure for solving for C and k when you do not know the value of y at $t = 0$.



In a conventional nuclear reactor, 1 kilogram of ^{239}Pu can generate enough electricity to power about 900 homes for a year. *(Source: World Nuclear Association, U.S. Energy Information Administration)*

iurii/Shutterstock.com

REMARK The exponential decay model in Example 3 can also be written as

$$y = 10\left(\frac{1}{2}\right)^{t/24{,}100}.$$

This model is much easier to derive, but for some applications it is not as convenient to use.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 4 Population Growth

See LarsonCalculus.com for an interactive version of this type of example.

An experimental population of fruit flies increases according to the law of exponential growth. There were 100 flies after the second day of the experiment and 300 flies after the fourth day. Approximately how many flies were in the original population?

Solution Let $y = Ce^{kt}$ be the number of flies at time t, where t is measured in days. Note that y is continuous, whereas the number of flies is discrete. Because $y = 100$ when $t = 2$ and $y = 300$ when $t = 4$, you can write

$$100 = Ce^{2k} \quad \text{and} \quad 300 = Ce^{4k}.$$

From the first equation, you know that

$$C = 100e^{-2k}.$$

Substituting this value into the second equation produces the following.

$300 = 100e^{-2k}e^{4k}$	Substitute.
$300 = 100e^{2k}$	Property of exponents
$3 = e^{2k}$	Divide each side by 100.
$\ln 3 = \ln e^{2k}$	Take natural log of each side.
$\ln 3 = 2k$	Apply inverse property.
$\frac{1}{2}\ln 3 = k$	Divide each side by 2.
$0.5493 \approx k$	Use a calculator.

So, the exponential growth model is $y = Ce^{0.5493t}$. To solve for C, reapply the condition $y = 100$ when $t = 2$ and obtain

$$100 = Ce^{0.5493(2)}$$
$$\frac{100}{e^{1.0986}} = C$$
$$33 \approx C.$$

So, the original population (when $t = 0$) consisted of approximately $y = C = 33$ flies, as shown in Figure 6.9.



Figure 6.9

EXAMPLE 5 Declining Sales

Four months after it stops advertising, a manufacturing company notices that its sales have dropped from 100,000 units per month to 80,000 units per month. The sales follow an exponential pattern of decline. What will the sales be after another 2 months?

Solution Use the exponential decay model $y = Ce^{kt}$, where t is measured in months. From the initial condition ($t = 0$), you know that $C = 100{,}000$. Moreover, because $y = 80{,}000$ when $t = 4$, you have

$80{,}000 = 100{,}000e^{4k}$	Substitute.
$0.8 = e^{4k}$	Divide each side by 100,000.
$\ln(0.8) = \ln e^{4k}$	Take natural log of each side.
$\ln(0.8) = 4k$	Apply inverse property.
$-0.0558 \approx k.$	Divide each side by 4. The use a calculator.

So, after 2 more months ($t = 6$), you can expect the monthly sales to be

$$y = 100{,}000e^{-0.0558(6)}$$
$$\approx 71{,}500 \text{ units.}$$ See Figure 6.10.



Figure 6.10

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

In Examples 2 through 5, you did not actually have to solve the differential equation $dy/dt = ky$. (This was done once in the proof of Theorem 6.1.) The next example demonstrates a problem whose solution involves the separation of variables technique. The example concerns **Newton's Law of Cooling,** which states that the rate of change of the temperature of an object is proportional to the difference between the object's temperature and the temperature of the surrounding medium.

EXAMPLE 6 Newton's Law of Cooling

Let y represent the temperature (in °F) of an object in a room whose temperature is kept at a constant 60°F. The object cools from 100°F to 90°F in 10 minutes. How much longer will it take for the temperature of the object to decrease to 80°F?

Solution From Newton's Law of Cooling, you know that the rate of change of y is proportional to the difference between y and 60. This can be written as

$$\frac{dy}{dt} = k(y - 60), \quad 80 \le y \le 100.$$

To solve this differential equation, use separation of variables, as shown.

$$\frac{dy}{dt} = k(y - 60) \qquad \text{Differential equation}$$

$$\left(\frac{1}{y - 60}\right) dy = k\,dt \qquad \text{Separate variables.}$$

$$\int \frac{1}{y - 60}\,dy = \int k\,dt \qquad \text{Integrate each side.}$$

$$\ln|y - 60| = kt + C_1 \qquad \text{Find antiderivative of each side.}$$

Because $y > 60$, $|y - 60| = y - 60$, and you can omit the absolute value signs. Using exponential notation and letting $C = e^{C_1}$, you have

$$y - 60 = e^{kt + C_1} \quad \Rightarrow \quad y = 60 + Ce^{kt}.$$

Using $y = 100$ when $t = 0$, you obtain

$$100 = 60 + Ce^{k(0)} \quad \Rightarrow \quad 100 = 60 + C \quad \Rightarrow \quad 40 = C.$$

Because $y = 90$ when $t = 10$, the value of k is

$$90 = 60 + 40e^{k(10)} \qquad \text{Substitute.}$$

$$30 = 40e^{10k} \qquad \text{Subtract 60 from each side.}$$

$$\ln\frac{3}{4} = \ln e^{10k} \qquad \text{Divide each side by 40. Then take natural log of each side.}$$

$$\frac{1}{10}\ln\frac{3}{4} = k. \qquad \text{Apply inverse property and divide each side by 10.}$$

So, $k \approx -0.02877$ and the model is $y = 60 + 40e^{-0.02877t}$. When $y = 80$, you obtain

$$80 = 60 + 40e^{-0.02877t} \qquad \text{Substitute.}$$

$$20 = 40e^{-0.02877t} \qquad \text{Subtract 60 from each side.}$$

$$\ln\frac{1}{2} = \ln e^{-0.02877t} \qquad \text{Divide each side by 40. Then take natural log of each side.}$$

$$\ln\frac{1}{2} = -0.02877t \qquad \text{Apply inverse property.}$$

$$24.09 \approx t. \qquad \text{Divide each side by } -0.02877 \text{ and simplify.}$$

So, it will require about 14.09 *more* minutes for the object to cool to a temperature of 80°F. See Figure 6.11. ■



Figure 6.11

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

6.2 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe what the values of C and k represent in the exponential growth and decay model $y = Ce^{kt}$.
2. For $y = Ce^{kt}$, explain why exponential growth occurs when $k > 0$ and exponential decay occurs when $k < 0$.

Solving a Differential Equation **In Exercises 3–12, find the general solution of the differential equation.**

3. $\frac{dy}{dx} = x + 3$
4. $\frac{dy}{dx} = 5 - 8x$
5. $\frac{dy}{dx} = y + 3$
6. $\frac{dy}{dx} = 6 - y$
7. $y' = \frac{5x}{y}$
8. $y' = -\frac{\sqrt{x}}{4y}$
9. $y' = \sqrt{x}\,y$
10. $y' = x(1 + y)$
11. $(1 + x^2)y' - 2xy = 0$
12. $xy + y' = 100x$

Writing and Solving a Differential Equation **In Exercises 13–16, write and find the general solution of the differential equation that models the verbal statement.**

13. The rate of change of Q with respect to t is inversely proportional to the square of t.
14. The rate of change of P with respect to t is proportional to $25 - t$.
15. The rate of change of N with respect to s is proportional to $500 - s$.
16. The rate of change of y with respect to x varies jointly as x and $L - y$.

Slope Field **In Exercises 17 and 18, a differential equation, a point, and a slope field are given. (a) Sketch two approximate solutions of the differential equation on the slope field, one of which passes through the given point. (To print an enlarged copy of the graph, go to *MathGraphs.com*.) (b) Use integration and the given point to find the particular solution of the differential equation and use a graphing utility to graph the solution. Compare the result with the sketch in part (a) that passes through the given point.**

17. $\frac{dy}{dx} = x(6 - y)$, $(0, 0)$



18. $\frac{dy}{dx} = xy$, $\left(0, \frac{1}{2}\right)$



Finding a Particular Solution **In Exercises 19–22, find the function $y = f(t)$ passing through the point $(0, 10)$ with the given differential equation. Use a graphing utility to graph the solution.**

19. $\frac{dy}{dt} = \frac{1}{2}t$
20. $\frac{dy}{dt} = -9\sqrt{t}$
21. $\frac{dy}{dt} = -\frac{1}{2}y$
22. $\frac{dy}{dt} = \frac{3}{4}y$

Writing and Solving a Differential Equation **In Exercises 23–26, write and find the general solution of the differential equation that models the verbal statement. Evaluate the solution at the specified value of the independent variable.**

23. The rate of change of N is proportional to N. When $t = 0$, $N = 250$, and when $t = 1$, $N = 400$. What is the value of N when $t = 4$?
24. The rate of change of y is proportional to y. When $x = 0$, $y = 6$, and when $x = 4$, $y = 15$. What is the value of y when $x = 8$?
25. The rate of change of V is proportional to V. When $t = 0$, $V = 20{,}000$, and when $t = 4$, $V = 12{,}500$. What is the value of V when $t = 6$?
26. The rate of change of P is proportional to P. When $t = 0$, $P = 5000$, and when $t = 1$, $P = 4750$. What is the value of P when $t = 5$?

Finding an Exponential Function **In Exercises 27–30, find the exponential function $y = Ce^{kt}$ that passes through the two given points.**

27.



28.



29.



30.



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploring Concepts

In Exercises 31 and 32, determine the quadrants in which the solution of the differential equation is an increasing function. Explain. (Do not solve the differential equation.)

31. $\frac{dy}{dx} = \frac{1}{2}xy$ **32.** $\frac{dy}{dx} = \frac{1}{2}x^2y$

Radioactive Decay **In Exercises 33–40, complete the table for the radioactive isotope.**

	Isotope	Half-life (in years)	Initial Quantity	Amount After 1000 Years	Amount After 10,000 Years
33.	^{226}Ra	1599	20 g		
34.	^{226}Ra	1599		1.5 g	
35.	^{226}Ra	1599			0.1 g
36.	^{14}C	5715			3 g
37.	^{14}C	5715	5 g		
38.	^{14}C	5715		1.6 g	
39.	^{239}Pu	24,100		2.1 g	
40.	^{239}Pu	24,100			0.4 g

41. Radioactive Decay Radioactive radium has a half-life of approximately 1599 years. What percent of a given amount remains after 100 years?

42. Carbon Dating Carbon-14 dating assumes that the carbon dioxide on Earth today has the same radioactive content as it did centuries ago. If this is true, the amount of ^{14}C absorbed by a tree that grew several centuries ago should be the same as the amount of ^{14}C absorbed by a tree growing today. A piece of ancient charcoal contains only 15% as much of the radioactive carbon as a piece of modern charcoal. How long ago was the tree burned to make the ancient charcoal? (The half-life of ^{14}C is 5715 years.)

Compound Interest **In Exercises 43–48, complete the table for a savings account in which interest is compounded continuously.**

	Initial Investment	Annual Rate	Time to Double	Amount After 10 Years
43.	$1000	12%		
44.	$28,000	2.5%		
45.	$150		15 yr	
46.	$31,000		8 yr	
47.	$900			$1845.25
48.	$6000			$6840

Compound Interest **In Exercises 49–52, find the principal P that must be invested at rate r, compounded monthly, so that $1,000,000 will be available for retirement in t years.**

49. $r = 7\frac{1}{2}\%, \quad t = 20$ **50.** $r = 6\%, \quad t = 40$

51. $r = 8\%, \quad t = 35$ **52.** $r = 9\%, \quad t = 25$

Compound Interest **In Exercises 53 and 54, find the time necessary for $1000 to double when it is invested at rate r and compounded (a) annually, (b) monthly, (c) daily, and (d) continuously.**

53. $r = 7\%$ **54.** $r = 5.5\%$

Population **In Exercises 55–58, the population (in millions) of a country in 2019 and the expected continuous annual rate of change k of the population are given. (*Source: U.S. Census Bureau, International Data Base*)**

(a) Find the exponential growth model

$$P = Ce^{kt}$$

for the population by letting $t = 9$ correspond to 2019.

(b) Use the model to predict the population of the country in 2040.

(c) Discuss the relationship between the sign of k and the change in population for the country.

	Country	2019 Population	k
55.	Latvia	1.9	−0.011
56.	Canada	37.4	0.008
57.	Paraguay	7.1	0.012
58.	Ukraine	44.0	0.0

59. Modeling Data One hundred bacteria are started in a culture, and the number N of bacteria is counted each hour for 5 hours. The results are shown in the table, where t is the time in hours.

t	0	1	2	3	4	5
N	100	126	151	198	243	297

(a) Use the regression capabilities of a graphing utility to find an exponential model for the data.

(b) Use the model to estimate the time required for the population to quadruple in size.

60. Bacteria Growth The number of bacteria in a culture is increasing according to the law of exponential growth. There are 125 bacteria in the culture after 2 hours and 350 bacteria after 4 hours.

(a) Find the initial population.

(b) Write an exponential growth model for the bacteria population. Let t represent the time in hours.

(c) Use the model to determine the number of bacteria after 8 hours.

(d) After how many hours will the bacteria count be 25,000?

61. Insect Population

(a) Suppose an insect population increases by a constant number each month. Explain why the number of insects can be represented by a linear function.

(b) Suppose an insect population increases by a constant percentage each month. Explain why the number of insects can be represented by an exponential function.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

62. HOW DO YOU SEE IT? The functions f and g are both of the form $y = Ce^{kt}$.



(a) Do the functions f and g represent exponential growth or exponential decay? Explain.

(b) Assume both functions have the same value of C. Which function has a greater value of k? Explain.

63. Modeling Data The table shows the cost of tuition and fees M (in 2020 dollars) at public four-year universities for selected years. (*Source: The College Board*)

Year	1985	1990	1995	2000
Cost, M	3170	3800	4770	5260

Year	2005	2010	2015	2020
Cost, M	7280	9070	10,240	10,560

(a) Use a graphing utility to find an exponential model M_1 for the data. Let $t = 5$ represent 1985.

(b) Use a graphing utility to find a linear model M_2 for the data. Let $t = 5$ represent 1985.

(c) Which model fits the data better? Explain.

(d) Use the exponential model to predict when the cost of tuition and fees will be \$15,000. Does the result seem reasonable? Explain.

64. Forestry

The value of a tract of timber is

$$V(t) = 100{,}000e^{0.8\sqrt{t}}$$

where t is the time in years, with $t = 0$ corresponding to 2020. If money earns interest continuously at 10%, then the present value of the timber at any time t is

$$A(t) = V(t)e^{-0.10t}.$$

Find the year in which the timber should be harvested to maximize the present value function.

65. Sound Intensity The level of sound β (in decibels) with an intensity of I is

$$\beta(I) = 10 \log_{10} \frac{I}{I_0}$$

where I_0 is an intensity of 10^{-16} watt per square centimeter, corresponding roughly to the faintest sound that can be heard. Determine $\beta(I)$ for the following.

(a) $I = 10^{-14}$ watt per square centimeter (whisper)

(b) $I = 10^{-9}$ watt per square centimeter (busy street corner)

(c) $I = 10^{-4}$ watt per square centimeter (threshold of pain)

66. Noise Level With the installation of noise suppression materials, the noise level in an auditorium was reduced from 93 to 80 decibels. Use the function in Exercise 65 to find the percent decrease in the intensity level of the noise as a result of the installation of these materials.

67. Newton's Law of Cooling When an object is removed from a furnace and placed in an environment with a constant temperature of 80°F, its core temperature is 1500°F. One hour after it is removed, the core temperature is 1120°F.

(a) Write an equation for the core temperature y of the object t hours after it is removed from the furnace.

(b) What is the core temperature of the object 6 hours after it is removed from the furnace?

68. Newton's Law of Cooling A container of hot liquid is placed in a freezer that is kept at a constant temperature of 20°F. The initial temperature of the liquid is 160°F. After 5 minutes, the liquid's temperature is 60°F.

(a) Write an equation for the temperature y of the liquid t minutes after it is placed in the freezer.

(b) How much longer will it take for the temperature of the liquid to decrease to 25°F?

True or False? In Exercises 69 and 70, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.

69. Half of the atoms in a sample of radioactive radium decay in 799.5 years.

70. If prices are rising at a rate of 0.5% per month, then they are rising at a rate of 6% per year.

71. Earthquake Intensity On the Richter scale, the magnitude R of an earthquake of intensity I is

$$R = \frac{\ln I - \ln I_0}{\ln 10}$$

where I_0 is the minimum intensity used for comparison. Assume that $I_0 = 1$.

(a) Find the intensity of the 1906 San Francisco earthquake ($R = 8.3$).

(b) Find the factor by which the intensity is increased if the Richter scale measurement is doubled.

(c) Find dR/dI.

Schon/Getty Images

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

6.3 Separation of Variables and the Logistic Equation

GO DIGITAL

- **Recognize and solve differential equations that can be solved by separation of variables.**
- **Use differential equations to model and solve applied problems.**
- **Solve and analyze logistic differential equations.**

Separation of Variables

Consider a differential equation that can be written in the form

$$M(x) + N(y)\frac{dy}{dx} = 0$$

where M is a continuous function of x alone and N is a continuous function of y alone. As you learned in Section 6.2, for this type of equation, all x-terms can be collected with dx and all y-terms with dy, and a solution can be obtained by integration. Such equations are said to be **separable,** and the solution procedure is called **separation of variables.** Below are some examples of differential equations that are separable.

Original Differential Equation	Rewritten with Variables Separated
$x^2 + 3y\frac{dy}{dx} = 0$	$3y\,dy = -x^2\,dx$
$(\sin x)y' = \cos x$	$dy = \cot x\,dx$
$\frac{xy'}{e^y + 1} = 2$	$\frac{1}{e^y + 1}dy = \frac{2}{x}dx$

EXAMPLE 1 Separation of Variables

See LarsonCalculus.com for an interactive version of this type of example.

Find the general solution of $(x^2 + 4)\frac{dy}{dx} = xy$.

Solution To begin, note that $y = 0$ is a solution. To find other solutions, assume that $y \neq 0$ and separate variables as shown.

$$(x^2 + 4)\,dy = xy\,dx \qquad \text{Differential form}$$

$$\frac{dy}{y} = \frac{x}{x^2 + 4}dx \qquad \text{Separate variables.}$$

Now, integrate to obtain

$$\int \frac{dy}{y} = \int \frac{x}{x^2 + 4}dx \qquad \text{Integrate each side.}$$

$$\ln|y| = \frac{1}{2}\ln(x^2 + 4) + C_1 \qquad \text{Find antiderivative of each side.}$$

$$\ln|y| = \ln\sqrt{x^2 + 4} + C_1 \qquad \text{Logarithmic property}$$

$$|y| = e^{\ln\sqrt{x^2+4}+C_1} \qquad \text{Exponentiate each side.}$$

$$|y| = e^{C_1}e^{\ln\sqrt{x^2+4}} \qquad \text{Property of exponents}$$

$$|y| = e^{C_1}\sqrt{x^2 + 4} \qquad \text{Apply inverse property.}$$

$$y = \pm e^{C_1}\sqrt{x^2 + 4}. \qquad \text{Definition of absolute value}$$

Because $y = 0$ is also a solution, you can write the general solution as

$$y = C\sqrt{x^2 + 4}. \qquad \text{General solution}$$

REMARK In Example 1, you can check the solution

$$y = C\sqrt{x^2 + 4}$$

by differentiating and substituting into the original equation.

$$(x^2 + 4)\frac{dy}{dx} = xy$$

$$(x^2 + 4)\frac{Cx}{\sqrt{x^2 + 4}} \stackrel{?}{=} x\left(C\sqrt{x^2 + 4}\right)$$

$$Cx\sqrt{x^2 + 4} = Cx\sqrt{x^2 + 4}$$

So, the solution checks.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

In some cases, it is not feasible to write the general solution in the explicit form $y = f(x)$. The next example illustrates such a solution.

EXAMPLE 2 Finding a Particular Solution

Find the particular solution of $xy\,dx + e^{-x^2}(y^2 - 1)\,dy = 0$ that satisfies the initial condition $y(0) = 1$.

Solution Note that $y = 0$ is a solution of the differential equation—but this solution does not satisfy the initial condition. So, assume that $y \neq 0$. To separate variables, you must rid the first term of y and the second term of e^{-x^2}. So, you should multiply by e^{x^2}/y and obtain the following.

$$xy\,dx + e^{-x^2}(y^2 - 1)\,dy = 0 \qquad \text{Write original equation.}$$

$$e^{-x^2}(y^2 - 1)\,dy = -xy\,dx \qquad \text{Subtract } xy\,dx \text{ from each side.}$$

$$\left(y - \frac{1}{y}\right)dy = -xe^{x^2}\,dx \qquad \text{Separate variables.}$$

$$\int \left(y - \frac{1}{y}\right)dy = \int -xe^{x^2}\,dx \qquad \text{Integrate each side.}$$

$$\frac{y^2}{2} - \ln|y| = -\frac{1}{2}e^{x^2} + C \qquad \text{Find antiderivative of each side.}$$

From the initial condition $y(0) = 1$, you have

$$\frac{1^2}{2} - \ln|1| = -\frac{1}{2}e^{0^2} + C \quad \Rightarrow \quad \frac{1}{2} - 0 = -\frac{1}{2} + C$$

which implies that $C = 1$. So, the particular solution has the implicit form

$$\frac{y^2}{2} - \ln|y| = -\frac{1}{2}e^{x^2} + 1 \quad \text{or} \quad y^2 - \ln y^2 + e^{x^2} = 2.$$

Check this by differentiating implicitly and rewriting to get the original equation.

EXAMPLE 3 Finding a Particular Solution Curve

Find the equation of the curve that passes through the point $(1, 3)$ and has a slope of y/x^2 at any point (x, y).

Solution Because the slope of the curve is y/x^2, you have

$$\frac{dy}{dx} = \frac{y}{x^2}$$

with the initial condition $y(1) = 3$. Because the initial condition occurs in Quadrant I, assume $x > 0$. Then, separating variables and integrating produce

$$\int \frac{dy}{y} = \int \frac{dx}{x^2}, \quad y \neq 0, x > 0 \qquad \text{Separate variables and integrate each side.}$$

$$\ln|y| = -\frac{1}{x} + C_1 \qquad \text{Find antiderivative of each side.}$$

$$y = e^{-(1/x)+C_1} \qquad \text{Exponentiate each side.}$$

$$y = Ce^{-1/x}. \qquad \text{Rewrite, letting } C = e^{C_1}.$$

Because $y = 3$ when $x = 1$, it follows that $3 = Ce^{-1}$ and $C = 3e$. So, the equation of the specified curve is

$$y = (3e)e^{-1/x} \quad \Rightarrow \quad y = 3e^{(x-1)/x}, \quad x > 0.$$

See Figure 6.12. ■



Figure 6.12

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Applications

EXAMPLE 4 Wildlife Population

The rate of change of the number of coyotes $N(t)$ in a population is directly proportional to $650 - N(t)$, where t is the time in years. When $t = 0$, the population is 300, and when $t = 2$, the population has increased to 500. Find the population when $t = 3$.

Solution Because the rate of change of the population is proportional to $650 - N(t)$, or $650 - N$, you can write the differential equation

$$\frac{dN}{dt} = k(650 - N).$$

You can solve this equation using separation of variables.

$$dN = k(650 - N)\,dt \qquad \text{Differential form}$$

$$\frac{dN}{650 - N} = k\,dt \qquad \text{Separate variables.}$$

$$-\ln|650 - N| = kt + C_1 \qquad \text{Integrate each side.}$$

$$\ln|650 - N| = -kt - C_1 \qquad \text{Multiply each side by } -1.$$

$$650 - N = e^{-kt - C_1} \qquad \text{Exponentiate each side. (Assume } N < 650.\text{)}$$

$$650 - N = e^{-C_1}e^{-kt} \qquad \text{Property of exponents}$$

$$N = 650 - Ce^{-kt} \qquad \text{General solution}$$

Using $N = 300$ when $t = 0$, you can conclude that $C = 350$, which produces

$$N = 650 - 350e^{-kt}.$$

Then, using $N = 500$ when $t = 2$, it follows that

$$500 = 650 - 350e^{-2k} \quad \Rightarrow \quad e^{-2k} = \frac{3}{7} \quad \Rightarrow \quad k \approx 0.4236.$$

So, the model for the coyote population is

$$N = 650 - 350e^{-0.4236t}. \qquad \text{Model for population}$$

When $t = 3$, you can approximate the population to be

$$N = 650 - 350e^{-0.4236(3)}$$
$$\approx 552 \text{ coyotes.}$$

The model for the population is shown in Figure 6.13. Note that $N = 650$ is the horizontal asymptote of the graph and is the *carrying capacity* of the model. You will learn more about carrying capacity later in this section.

FOR FURTHER INFORMATION
For an example (from engineering) of a differential equation that is separable, see the article "Designing a Rose Cutter" by J. S. Hartzler in *The College Mathematics Journal*. To view this article, go to *MathArticles.com*.



Figure 6.13

W. Perry Conway/Getty Images

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

A common problem in electrostatics, thermodynamics, and hydrodynamics involves finding a family of curves, each of which is *orthogonal* to all members of a given family of curves. For example, Figure 6.14 shows a family of circles

$$x^2 + y^2 = C \qquad \text{Family of circles}$$

each of which intersects the lines in the family

$$y = Kx \qquad \text{Family of lines}$$

at right angles. Two such families of curves are said to be **mutually orthogonal,** and each curve in one of the families is called an **orthogonal trajectory** of the other family. In electrostatics, lines of force are orthogonal to the *equipotential curves*. In thermodynamics, the flow of heat across a plane surface is orthogonal to the *isothermal curves*. In hydrodynamics, the flow (stream) lines are orthogonal trajectories of the *velocity potential curves*.



Each line $y = Kx$ is an orthogonal trajectory of the family of circles.
Figure 6.14

EXAMPLE 5 Finding Orthogonal Trajectories

Describe the orthogonal trajectories for the family of curves given by

$$y = \frac{C}{x}$$

for $C \neq 0$. Sketch several members of each family.

Solution First, solve the given equation for C and write $xy = C$. Then, by differentiating implicitly with respect to x, you obtain the differential equation

$$x\frac{dy}{dx} + y = 0 \qquad \text{Differential equation}$$

$$x\frac{dy}{dx} = -y$$

$$\frac{dy}{dx} = -\frac{y}{x}. \qquad \text{Slope of given family}$$

Because dy/dx represents the slope of the given family of curves at (x, y), it follows that the orthogonal family has the negative reciprocal slope x/y. So,

$$\frac{dy}{dx} = \frac{x}{y}. \qquad \text{Slope of orthogonal family}$$

Now you can find the orthogonal family by separating variables and integrating.

$$\int y\,dy = \int x\,dx \qquad \text{Separate variables and integrate each side.}$$

$$\frac{y^2}{2} = \frac{x^2}{2} + C_1 \qquad \text{Find antiderivative of each side.}$$

$$y^2 - x^2 = K \qquad \text{Rewrite, letting } K = 2C_1.$$

So, the orthogonal trajectories for the family of curves given by $y = C/x$ is the family of curves given by $y^2 - x^2 = K$. When $K \neq 0$, the orthogonal trajectories are hyperbolas with centers at the origin, and the transverse axes are vertical for $K > 0$ and horizontal for $K < 0$. When $K = 0$, the orthogonal trajectories are the lines $y = \pm x$. Several trajectories are shown in Figure 6.15.



Orthogonal trajectories
Figure 6.15

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



Note that as $t \to \infty$, $y \to L$.
Figure 6.16

Logistic Differential Equation

In Section 6.2, the exponential growth model was derived from the fact that the rate of change of a variable y is proportional to the value of y. You observed that the differential equation $dy/dt = ky$ has the general solution $y = Ce^{kt}$. Exponential growth is unlimited, but when describing a population, there often exists some upper limit L past which growth cannot occur. This upper limit L is called the **carrying capacity,** which is the maximum population $y(t)$ that can be sustained or supported as time t increases. A model that is often used to describe this type of growth is the **logistic differential equation**

$$\frac{dy}{dt} = ky\left(1 - \frac{y}{L}\right) \qquad \text{Logistic differential equation}$$

where k and L are positive constants. A population that satisfies this equation does not grow without bound but approaches the carrying capacity L as t increases.

In the logistic differential equation, if y is between 0 and the carrying capacity L, then $dy/dt > 0$, and the population increases. If y is greater than L, then $dy/dt < 0$, and the population decreases. The graph of the function y is called the *logistic curve*, as shown in Figure 6.16.

EXAMPLE 6 Deriving the General Solution

Solve the logistic differential equation

$$\frac{dy}{dt} = ky\left(1 - \frac{y}{L}\right).$$

Solution Begin by separating variables.

$$\frac{dy}{dt} = ky\left(1 - \frac{y}{L}\right) \qquad \text{Write differential equation.}$$

$$\frac{1}{y(1 - y/L)}\,dy = k\,dt \qquad \text{Separate variables.}$$

$$\int \frac{1}{y(1 - y/L)}\,dy = \int k\,dt \qquad \text{Integrate each side.}$$

$$\int \left(\frac{1}{y} + \frac{1}{L - y}\right)dy = \int k\,dt \qquad \text{Rewrite left side using partial fractions.}$$

$$\ln|y| - \ln|L - y| = kt + C \qquad \text{Find antiderivative of each side.}$$

$$\ln\left|\frac{L - y}{y}\right| = -kt - C \qquad \text{Multiply each side by } -1 \text{ and simplify.}$$

$$\left|\frac{L - y}{y}\right| = e^{-kt - C} \qquad \text{Exponentiate each side.}$$

$$\left|\frac{L - y}{y}\right| = e^{-C}e^{-kt} \qquad \text{Property of exponents}$$

$$\frac{L - y}{y} = be^{-kt} \qquad \text{Let } \pm e^{-C} = b.$$

Solving this equation for y produces $y = \dfrac{L}{1 + be^{-kt}}$. ■

From Example 6, you can conclude that all solutions of the logistic differential equation are of the general form

$$y = \frac{L}{1 + be^{-kt}}.$$

REMARK A review of the method of partial fractions is given in Section 8.5.

Exploration

Use a graphing utility to investigate the effects of the values of L, b, and k on the graph of

$$y = \frac{L}{1 + be^{-kt}}.$$

Include some examples to support your results.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 7 Solving a Logistic Differential Equation

A state game commission releases 40 elk into a game refuge. After 5 years, the elk population is 104. The commission believes that the environment can support no more than 4000 elk. The growth rate of the elk population p is

$$\frac{dp}{dt} = kp\left(1 - \frac{p}{4000}\right), \quad 40 \le p \le 4000$$

where t is the number of years.

a. Write a model for the elk population in terms of t.

b. Graph the slope field for the differential equation and the solution that passes through the point $(0, 40)$.

c. Use the model to estimate the elk population after 15 years.

d. Find the limit of the model as $t \to \infty$.

Solution

a. You know that $L = 4000$. So, the solution of the equation is of the form

$$p = \frac{4000}{1 + be^{-kt}}.$$

Because $p(0) = 40$, you can solve for b as follows.

$$40 = \frac{4000}{1 + be^{-k(0)}} \quad \Rightarrow \quad 40 = \frac{4000}{1 + b} \quad \Rightarrow \quad b = 99$$

Then, because $p = 104$ when $t = 5$, you can solve for k.

$$104 = \frac{4000}{1 + 99e^{-k(5)}} \quad \Rightarrow \quad k \approx 0.194$$

So, a model for the elk population is

$$p = \frac{4000}{1 + 99e^{-0.194t}}.$$



Slope field for

$$\frac{dp}{dt} = 0.194p\left(1 - \frac{p}{4000}\right)$$

and the solution passing through $(0, 40)$

Figure 6.17

b. Using a graphing utility, you can graph the slope field for

$$\frac{dp}{dt} = 0.194p\left(1 - \frac{p}{4000}\right)$$

and the solution that passes through $(0, 40)$, as shown in Figure 6.17.

c. To estimate the elk population after 15 years, substitute 15 for t in the model.

$$p = \frac{4000}{1 + 99e^{-0.194(15)}} \qquad \text{Substitute 15 for } t.$$

$$= \frac{4000}{1 + 99e^{-2.91}} \qquad \text{Simplify.}$$

$$\approx 626$$

d. As t increases without bound, the denominator of

$$\frac{4000}{1 + 99e^{-0.194t}}$$

gets closer and closer to 1. So,

$$\lim_{t \to \infty} \frac{4000}{1 + 99e^{-0.194t}} = 4000.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

6.3 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Determine whether each differential equation is separable.
   (a) $y = 2x^5y' - y'$ (b) $y'/x = x^2y + 1$
2. Explain what it means for two families of curves to be mutually orthogonal.
3. Describe carrying capacity.
4. Describe a real-life application that can be modeled by the logistic differential equation.

Finding a General Solution **In Exercises 5–18, find the general solution of the differential equation.**

5. $\frac{dy}{dx} = \frac{x}{y}$
6. $\frac{dy}{dx} = \frac{3x^2}{y^2}$
7. $\frac{dy}{dx} = \frac{x-1}{y^3}$
8. $\frac{dy}{dx} = \frac{6-x^2}{2y^3}$
9. $\frac{dr}{ds} = \frac{4}{9}r$
10. $\frac{dr}{ds} = \frac{9}{4}s$
11. $(2+x)y' = 3y$
12. $xy' = y$
13. $y^2y' = \sin 9x$
14. $yy' = -8\cos(\pi x)$
15. $\sqrt{1-4x^2}\,y' = x$
16. $\sqrt{x^3-5}\,y' = x^2$
17. $y\ln x - xy' = 0, \quad x > 0$
18. $12yy' - 7e^x = 0$

Finding a Particular Solution **In Exercises 19–28, find the particular solution of the differential equation that satisfies the initial condition.**

Differential Equation	Initial Condition
19. $yy' - 2e^x = 0$	$y(0) = 6$
20. $\sqrt{x} + \sqrt{y}\,y' = 0$	$y(1) = 9$
21. $y(x+1) + y' = 0$	$y(-2) = 1$
22. $2xy' - \ln x^2 = 0, \quad x > 0$	$y(1) = 2$
23. $y(1+x^2)y' - x(1+y^2) = 0$	$y(0) = \sqrt{3}$
24. $y\sqrt{1-x^2}\,y' - x\sqrt{1-y^2} = 0$	$y(\frac{1}{2}) = \frac{1}{2}$
25. $\frac{du}{dv} = uv\sin v^2$	$u(0) = e^2$
26. $\frac{dr}{ds} = e^{r-2s}$	$r(0) = 0$
27. $dP - kP\,dt = 0$	$P(0) = P_0$
28. $dT + k(T-70)\,dt = 0$	$T(0) = 140$

Finding a Particular Solution Curve **In Exercises 29–32, find an equation of the curve that passes through the point and has the given slope.**

29. $(0, 2), \quad y' = \frac{x}{4y}$
30. $(1, 1), \quad y' = -\frac{9x}{16y}$
31. $(3, 1), \quad y' = -\frac{y}{5x}$
32. $(8, 2), \quad y' = \frac{2y}{3x}$

Finding Functions **In Exercises 33 and 34, find all functions f having the indicated property.**

33. The tangent to the graph of f at the point (x, y) intersects the x-axis at $(x+2, 0)$.
34. All tangents to the graph of f pass through the origin.

Slope Field **In Exercises 35 and 36, sketch a few solutions of the differential equation on the slope field and then find the general solution analytically. To print an enlarged copy of the graph, go to *MathGraphs.com*.**

35. $\frac{dy}{dx} = x$



36. $\frac{dy}{dx} = -\frac{x}{y}$



Slope Field **In Exercises 37–40, (a) write a differential equation for the statement, (b) match the differential equation with a possible slope field, and (c) verify your result by using a graphing utility to graph a slope field for the differential equation. [The slope fields are labeled (i), (ii), (iii), and (iv).]**

(i)



(ii)



(iii)



(iv)



37. The rate of change of y with respect to x is proportional to the difference between y and 4.
38. The rate of change of y with respect to x is proportional to the difference between x and 4.
39. The rate of change of y with respect to x is proportional to the product of y and the difference between y and 4.
40. The rate of change of y with respect to x is proportional to y^2.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Euler's Method **In Exercises 41–44, (a) use Euler's Method with a step size of $h = 0.1$ to approximate the particular solution of the initial value problem at the given x-value, (b) find the exact solution of the differential equation analytically, and (c) compare the solutions at the given x-value.**

	Differential Equation	Initial Condition	x-value
41.	$\frac{dy}{dx} = -6xy$	$(0, 5)$	$x = 1$
42.	$\frac{dy}{dx} + 6xy^2 = 0$	$(0, 3)$	$x = 1$
43.	$\frac{dy}{dx} = \frac{2x + 12}{3y^2 - 4}$	$(1, 2)$	$x = 2$
44.	$\frac{dy}{dx} = 2x(1 + y^2)$	$(1, 0)$	$x = 1.5$

45. Radioactive Decay The rate of decomposition of radioactive radium is proportional to the amount present at any time. The half-life of radioactive radium is 1599 years. What percent of a present amount will remain after 50 years?

46. Chemical Reaction In a chemical reaction, a certain compound changes into another compound at a rate proportional to the unchanged amount. There is 40 grams of the original compound initially and 35 grams after 1 hour. When will 75 percent of the compound be changed?

47. Weight Gain A calf that weighs 60 pounds at birth gains weight at the rate

$$\frac{dw}{dt} = k(1200 - w)$$

where w is the weight in pounds and t is the time in years.

(a) Find the general solution of the differential equation.

(b) Use a graphing utility to graph the particular solutions for $k = 0.8$, 0.9, and 1.

(c) The animal is sold when its weight reaches 800 pounds. Find the time of sale for each of the models in part (b).

(d) What is the maximum weight of the animal for each of the models in part (b)?

48. Weight Gain A goat that weighs 7 pounds at birth gains weight at the rate

$$\frac{dw}{dt} = k(250 - w)$$

where w is the weight in pounds and t is the time in years. Repeat Exercise 47 assuming that the goat is sold when its weight reaches 175 pounds.

Finding Orthogonal Trajectories **In Exercises 49–54, find the orthogonal trajectories for the family of curves. Use a graphing utility to graph several members of each family.**

49. $3x^2 - y^2 = C$

50. $x^2 - 2y^2 = C$

51. $x^2 = Cy$

52. $y^2 = 2Cx$

53. $y^2 = Cx^3$

54. $y = Ce^x$

Matching **In Exercises 55–58, match the logistic equation with its graph. [The graphs are labeled (a), (b), (c), and (d).]**

(a)



(b)



(c)



(d)



55. $y = \frac{12}{1 + e^{-x}}$

56. $y = \frac{12}{1 + 3e^{-x}}$

57. $y = \frac{12}{1 + \frac{1}{2}e^{-x}}$

58. $y = \frac{12}{1 + e^{-2x}}$

Using a Logistic Equation **In Exercises 59 and 60, the logistic equation models the growth of a population. Use the equation to (a) find the value of k, (b) find the carrying capacity, (c) find the initial population, (d) determine when the population will reach 50% of its carrying capacity, and (e) write a logistic differential equation that has the solution $P(t)$.**

59. $P(t) = \frac{2100}{1 + 29e^{-0.75t}}$

60. $P(t) = \frac{5000}{1 + 39e^{-0.2t}}$

Using a Logistic Differential Equation **In Exercises 61 and 62, the logistic differential equation models the growth rate of a population. Use the equation to (a) find the value of k, (b) find the carrying capacity, (c) graph a slope field using a computer algebra system, and (d) determine the value of P at which the population growth rate is the greatest.**

61. $\frac{dP}{dt} = 3P\left(1 - \frac{P}{100}\right)$

62. $\frac{dP}{dt} = 0.1P - 0.0004P^2$

Solving a Logistic Differential Equation **In Exercises 63–66, find the logistic equation that passes through the given point.**

63. $\frac{dy}{dt} = y\left(1 - \frac{y}{36}\right)$, $(0, 4)$

64. $\frac{dy}{dt} = 4.2y\left(1 - \frac{y}{21}\right)$, $(0, 9)$

65. $\frac{dy}{dt} = \frac{4y}{5} - \frac{y^2}{150}$, $(0, 8)$

66. $\frac{dy}{dt} = \frac{3y}{20} - \frac{y^2}{1600}$, $(0, 15)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

67. Endangered Species A conservation organization releases 25 Florida panthers into a game preserve. After 2 years, there are 39 panthers in the preserve. The Florida preserve has a carrying capacity of 200 panthers.

(a) Write a logistic equation that models the population of panthers in the preserve.

(b) Find the population after 5 years.

(c) When will the population reach 100?

(d) Write a logistic differential equation that models the growth rate of the panther population. Then repeat part (b) using Euler's Method with a step size of $h = 1$. Compare the approximation with the exact answer.

(e) At what time is the panther population growing most rapidly? Explain.

68. Bacteria Growth At time $t = 0$, a bacterial culture weighs 1 gram. Two hours later, the culture weighs 4 grams. The maximum weight of the culture is 20 grams.

(a) Write a logistic equation that models the weight of the bacterial culture.

(b) Find the culture's weight after 5 hours.

(c) When will the culture's weight reach 18 grams?

(d) Write a logistic differential equation that models the growth rate of the culture's weight. Then repeat part (b) using Euler's Method with a step size of $h = 1$. Compare the approximation with the exact answer.

(e) At what time is the culture's weight increasing most rapidly? Explain.

Exploring Concepts

69. Determine whether an equation of the form

$$\frac{dy}{dx} = f(x)g(y) - f(x)h(y), \quad g(y) \neq h(y)$$

is separable. Explain.

70. Describe the slope field for a logistic differential equation. Explain your reasoning.

71. Finding a Derivative Show that if

$$y = \frac{1}{1 + be^{-kt}}$$

then

$$\frac{dy}{dt} = ky(1 - y).$$

72. Point of Inflection For any logistic equation, show that the point of inflection occurs at

$$y = \frac{L}{2}$$

when the solution starts below the carrying capacity L.

73. Sailing

Ignoring resistance, a sailboat starting from rest accelerates (dv/dt) at a rate proportional to the difference between the velocities of the wind and the boat.

(a) The wind is blowing at 20 knots, and after a half-hour, the boat is moving at 10 knots. Write the velocity v as a function of time t.

(b) Use the result of part (a) to write the distance traveled by the boat as a function of time.

74. HOW DO YOU SEE IT? The growth of a population is modeled by a logistic equation, as shown in the graph below. What happens to the rate of growth as the population increases? What do you think causes this to occur in real-life situations, such as animal or human populations?



True or False? In Exercises 75–77, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.

75. The function $y = 0$ is always a solution of a differential equation that can be solved by separation of variables.

76. The differential equation $y' = xy - 2y + x - 2$ is separable.

77. The families

$$x^2 + y^2 = 2Cy \quad \text{and} \quad x^2 + y^2 = 2Kx$$

are mutually orthogonal.

PUTNAM EXAM CHALLENGE

78. A not uncommon calculus mistake is to believe that the product rule for derivatives says that $(fg)' = f'g'$. If

$$f(x) = e^{x^2}$$

determine, with proof, whether there exists an open interval (a, b) and a nonzero function g defined on (a, b) such that this wrong product rule is true for x in (a, b).

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Giovanni Rinaldi/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

6.4 First-Order Linear Differential Equations

GO DIGITAL

Solve a first-order linear differential equation, and use linear differential equations to solve applied problems.

ANNA JOHNSON PELL WHEELER (1883–1966)

Anna Johnson Pell Wheeler was awarded a master's degree in 1904 from the University of Iowa for her thesis *The Extension of Galois Theory to Linear Differential Equations*. Influenced by David Hilbert, she worked on integral equations while studying infinite linear spaces.

See LarsonCalculus.com to read more of this biography.

First-Order Linear Differential Equations

In this section, you will learn how to solve a very important class of first-order differential equations—first-order linear differential equations.

Definition of First-Order Linear Differential Equation

A **first-order linear differential equation** is an equation of the form

$$\frac{dy}{dx} + P(x)y = Q(x)$$

where P and Q are continuous functions of x. This first-order linear differential equation is said to be in **standard form.**

To solve a linear differential equation, write it in standard form to identify the functions $P(x)$ and $Q(x)$. Then integrate $P(x)$ and form the expression

$$u(x) = e^{\int P(x)\,dx}$$ Integrating factor

which is called an **integrating factor.** The general solution of the equation is

$$y = \frac{1}{u(x)}\int Q(x)u(x)\,dx.$$ General solution

It is instructive to see why the integrating factor helps solve a linear differential equation of the form $y' + P(x)y = Q(x)$. When each side of the equation is multiplied by the integrating factor $u(x) = e^{\int P(x)\,dx}$, the left side becomes the derivative of a product.

$$y'e^{\int P(x)\,dx} + P(x)ye^{\int P(x)\,dx} = Q(x)e^{\int P(x)\,dx}$$
$$\left[ye^{\int P(x)\,dx}\right]' = Q(x)e^{\int P(x)\,dx}$$

Integrating each side of this second equation and dividing by $u(x)$ produces the general solution.

EXAMPLE 1 Solving a Linear Differential Equation

Find the general solution of $y' + y = e^x$.

Solution For this equation, $P(x) = 1$ and $Q(x) = e^x$. So, the integrating factor is

$$u(x) = e^{\int P(x)\,dx} = e^{\int dx} = e^x.$$ Integrating factor

This implies that the general solution is

$$y = \frac{1}{u(x)}\int Q(x)u(x)\,dx$$ Form of general solution
$$= \frac{1}{e^x}\int e^x(e^x)\,dx$$ Substitute.
$$= e^{-x}\left(\frac{1}{2}e^{2x} + C\right)$$ Integrate.
$$= \frac{1}{2}e^x + Ce^{-x}.$$ General solution

REMARK Check the answer to Example 1 by showing that the general solution satisfies the differential equation $y' + y = e^x$.

Photo from MacTutor by JOC/EFR

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

REMARK Rather than memorizing the formula in Theorem 6.2, just remember that multiplication by the integrating factor $e^{\int P(x)\,dx}$ converts the left side of the differential equation into the derivative of the product $ye^{\int P(x)\,dx}$.

THEOREM 6.2 Solution of a First-Order Linear Differential Equation

An integrating factor for the first-order linear differential equation

$$y' + P(x)y = Q(x)$$

is $u(x) = e^{\int P(x)\,dx}$. The solution of the differential equation is

$$ye^{\int P(x)\,dx} = \int Q(x)e^{\int P(x)\,dx}\,dx + C.$$

EXAMPLE 2 Solving a First-Order Linear Differential Equation

See LarsonCalculus.com for an interactive version of this type of example.

Find the general solution of $xy' - 2y = x^2$, where $x > 0$.

Solution First, divide by x to write the equation in the form $y' + P(x)y = Q(x)$.

$$y' + \left(-\frac{2}{x}\right)y = x, \quad x > 0 \qquad \text{Standard form}$$

So, $P(x) = -2/x$, and you have

$$\int P(x)\,dx = -\int \frac{2}{x}\,dx = -\ln x^2$$

which implies that the integrating factor is

$$e^{\int P(x)\,dx} = e^{-\ln x^2} = \frac{1}{e^{\ln x^2}} = \frac{1}{x^2}. \qquad \text{Integrating factor}$$

So, multiplying each side of the standard form by $1/x^2$ yields

$$\frac{y'}{x^2} - \frac{2y}{x^3} = \frac{1}{x} \qquad \text{Multiply each side of the standard form by } \frac{1}{x^2}.$$

$$\frac{d}{dx}\left[\frac{y}{x^2}\right] = \frac{1}{x} \qquad \text{Use Product Rule to rewrite left side.}$$

$$\frac{y}{x^2} = \int \frac{1}{x}\,dx \qquad \text{Integrate each side.}$$

$$\frac{y}{x^2} = \ln x + C$$

$$y = x^2(\ln x + C). \qquad \text{General solution}$$

Several solution curves (for $C = -2, -1, 0, 1, 2, 3,$ and 4) are shown in Figure 6.18.



Figure 6.18

In most falling-body problems discussed so far in the text, air resistance has been neglected. The next example includes this factor. In the example, the air resistance on the falling object is assumed to be proportional to its velocity v. If g is the acceleration due to gravity, the downward force F on a falling object of mass m is given by $-mg - kv$. If a is the acceleration of the object, then by Newton's Second Law of Motion,

$$F = ma = m\frac{dv}{dt} \qquad \text{Newton's Second Law of Motion}$$

which yields the following differential equation.

$$m\frac{dv}{dt} = -mg - kv \quad \Rightarrow \quad \frac{dv}{dt} + \frac{kv}{m} = -g$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 3 A Falling Object with Air Resistance

An object of mass m is dropped from a hovering helicopter. The air resistance is proportional to the velocity of the object. Find the velocity of the object as a function of time t.

Solution The velocity v satisfies the equation

$$\frac{dv}{dt} + \frac{kv}{m} = -g.$$

g = acceleration due to gravity, k = constant of proportionality

Letting $b = k/m$, you can *separate variables* to obtain

$$dv = -(g + bv)\,dt \qquad \text{Separate variables.}$$

$$\int \frac{dv}{g + bv} = -\int dt \qquad \text{Integrate each side.}$$

$$\frac{1}{b}\ln|g + bv| = -t + C_1 \qquad \text{Find antiderivative of each side.}$$

$$\ln|g + bv| = -bt + bC_1$$

$$g + bv = Ce^{-bt}. \qquad C = e^{bC_1}$$

Because the object was dropped, $v = 0$ when $t = 0$; so $g = C$, and it follows that

$$bv = -g + ge^{-bt} \quad \Rightarrow \quad v = \frac{-g(1 - e^{-bt})}{b} = -\frac{mg}{k}(1 - e^{-kt/m}).$$

REMARK Notice in Example 3 that the velocity approaches a limit of $-mg/k$ as a result of the air resistance. For falling-body problems in which air resistance is neglected, the velocity increases without bound.



Figure 6.19

A simple electric circuit consists of an electric current I (in amperes), a resistance R (in ohms), an inductance L (in henrys), and a constant electromotive force E (in volts), as shown in Figure 6.19. According to Kirchhoff's Second Law, if the switch S is closed when $t = 0$, then the applied electromotive force (voltage) is equal to the sum of the voltage drops in the rest of the circuit. This, in turn, means that the current I satisfies the differential equation

$$L\frac{dI}{dt} + RI = E.$$

EXAMPLE 4 An Electric Circuit Problem

Find the current I as a function of time t (in seconds), given that I satisfies the differential equation $L(dI/dt) + RI = \sin 2t$, where R and L are nonzero constants.

Solution In standard form, the given linear equation is

$$\frac{dI}{dt} + \frac{R}{L}I = \frac{1}{L}\sin 2t.$$

Let $P(t) = R/L$, so that $e^{\int P(t)\,dt} = e^{(R/L)t}$, and by Theorem 6.2,

$$Ie^{(R/L)t} = \frac{1}{L}\int e^{(R/L)t}\sin 2t\,dt$$

$$= \frac{1}{4L^2 + R^2}e^{(R/L)t}(R\sin 2t - 2L\cos 2t) + C.$$

So, the general solution is

$$I = e^{-(R/L)t}\left[\frac{1}{4L^2 + R^2}e^{(R/L)t}(R\sin 2t - 2L\cos 2t) + C\right]$$

$$= \frac{1}{4L^2 + R^2}(R\sin 2t - 2L\cos 2t) + Ce^{-(R/L)t}.$$

REMARK The integral in Example 4 was found using a graphing utility. In Chapter 8, you will learn how to integrate functions of this type using integration by parts.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

One type of problem that can be described in terms of a differential equation involves chemical mixtures, as illustrated in the next example.

EXAMPLE 5 A Mixture Problem

A tank contains 50 gallons of a solution composed of 90% water and 10% alcohol. A second solution containing 50% water and 50% alcohol is added to the tank at a rate of 4 gallons per minute. As the second solution is being added, the tank is being drained at a rate of 5 gallons per minute, as shown in Figure 6.20. The solution in the tank is stirred constantly. How much alcohol is in the tank after 10 minutes?



Figure 6.20

Solution Let y be the number of gallons of alcohol in the tank at any time t. You know that $y = 5$ when $t = 0$. Because the number of gallons of solution in the tank at any time is $50 - t$, and the tank loses 5 gallons of solution per minute, it must lose

$$\left(\frac{5}{50 - t}\right)y$$

gallons of alcohol per minute. Furthermore, because the tank is gaining 2 gallons of alcohol per minute, the rate of change of alcohol in the tank is

$$\frac{dy}{dt} = 2 - \left(\frac{5}{50 - t}\right)y \quad \Rightarrow \quad \frac{dy}{dt} + \left(\frac{5}{50 - t}\right)y = 2.$$

To solve this linear differential equation, let

$$P(t) = \frac{5}{50 - t}$$

and obtain

$$\int P(t)\,dt = \int \frac{5}{50 - t}\,dt = -5\ln|50 - t|.$$

Because $t < 50$, you can drop the absolute value signs and conclude that

$$e^{\int P(t)\,dt} = e^{-5\ln(50 - t)} = \frac{1}{(50 - t)^5}. \qquad \text{Integrating factor}$$

So, the general solution is

$$\frac{y}{(50 - t)^5} = \int \frac{2}{(50 - t)^5}\,dt$$

$$\frac{y}{(50 - t)^5} = \frac{1}{2(50 - t)^4} + C$$

$$y = \frac{50 - t}{2} + C(50 - t)^5. \qquad \text{General solution}$$

Because $y = 5$ when $t = 0$, you have

$$5 = \frac{50}{2} + C(50)^5 \quad \Rightarrow \quad -\frac{20}{50^5} = C$$

which means that the particular solution is

$$y = \frac{50 - t}{2} - 20\left(\frac{50 - t}{50}\right)^5. \qquad \text{Particular solution}$$

Finally, when $t = 10$, the amount of alcohol in the tank is

$$y = \frac{50 - 10}{2} - 20\left(\frac{50 - 10}{50}\right)^5 \approx 13.45 \text{ gal}$$

which represents a solution containing 33.6% alcohol.

EVANGELISTA TORRICELLI (1608–1647)

Torricelli was an Italian mathematician and physicist. He is probably most famous for being the first person to create a sustained vacuum and inventing the barometer. His work in geometry aided in the eventual development of integral calculus. He also developed a theorem used in fluid dynamics called Torricelli's Law. (See page 442, Exercises 3–5.)

See LarsonCalculus.com to read more of this biography.

Popperfoto/Getty Images

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

6.4 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain what the term "first-order" refers to in a first-order linear differential equation.
2. Describe how to solve a first-order linear differential equation.

Determining Whether a Differential Equation Is Linear **In Exercises 3–6, determine whether the differential equation is linear. Explain your reasoning.**

3. $x^3y' + xy = e^x + 1$
4. $2xy - y' \ln x = y$
5. $y' - y \sin x = xy^2$
6. $\dfrac{2 - y'}{y} = 5x$

Solving a First-Order Linear Differential Equation **In Exercises 7–14, find the general solution of the first-order linear differential equation for $x > 0$.**

7. $\dfrac{dy}{dx} + \left(\dfrac{1}{x}\right)y = 6x + 2$
8. $\dfrac{dy}{dx} + \left(\dfrac{2}{x}\right)y = 3x - 5$
9. $y' + 2xy = 10x$
10. $y' + 3x^2y = 6x^2$
11. $(y + 1)\cos x\,dx - dy = 0$
12. $(y - 1)\sin x\,dx - dy = 0$
13. $y' + 3y = e^{3x}$
14. $xy' + y = x^2 \ln x$

Slope Field **In Exercises 15 and 16, (a) sketch an approximate solution of the differential equation satisfying the given initial condition on the slope field, (b) find the particular solution that satisfies the given initial condition, and (c) use a graphing utility to graph the particular solution. Compare the graph with the sketch in part (a). To print an enlarged copy of the graph, go to *MathGraphs.com*.**

15. $\dfrac{dy}{dx} = e^x - y$, $(0, 1)$



16. $y' + \left(\dfrac{1}{x}\right)y = \sin x^2$, $\left(\sqrt{\pi}, 0\right)$



Finding a Particular Solution **In Exercises 17–24, find the particular solution of the first-order linear differential equation for $x > 0$ that satisfies the initial condition.**

Differential Equation	Initial Condition
17. $y' + y = 6e^x$	$y(0) = 3$
18. $x^3y' + 2y = e^{1/x^2}$	$y(1) = e$
19. $y' + y \tan x = \sec x + \cos x$	$y(0) = 1$
20. $y' + y \sec x = \sec x$	$y(0) = 4$
21. $y' + \left(\dfrac{1}{x}\right)y = 0$	$y(2) = 2$
22. $y' + (2x - 1)y = 0$	$y(1) = 2$
23. $x\,dy = (x + y + 2)\,dx$	$y(1) = 10$
24. $2xy' - y = x^3 - x$	$y(4) = 2$

25. **Population Growth** When predicting population growth, demographers must consider birth and death rates as well as the net change caused by the difference between the rates of immigration and emigration. Let P be the population at time t and let N be the net increase per unit time resulting from the difference between immigration and emigration. So, the rate of growth of the population is given by

$$\frac{dP}{dt} = kP + N$$

where N is constant. Solve this differential equation to find P as a function of time, when at time $t = 0$ the size of the population is P_0.

26. **Investment Growth** A large corporation starts at time $t = 0$ to invest part of its receipts continuously at a rate of P dollars per year in a fund for future corporate expansion. Assume that the fund earns r percent interest per year compounded continuously. So, the rate of growth of the amount A in the fund is given by $dA/dt = rA + P$, where $A = 0$ when $t = 0$. Solve this differential equation for A as a function of t.

Investment Growth **In Exercises 27 and 28, use the result of Exercise 26.**

27. Find A for the following.
    (a) $P = \$275{,}000$, $r = 8\%$, $t = 10$ years
    (b) $P = \$550{,}000$, $r = 5.9\%$, $t = 25$ years
28. Find t if the corporation needs $1,000,000 and it can invest $125,000 per year in a fund earning 8% interest compounded continuously.

29. **Learning Curve** The management at a certain factory has found that the maximum number of units a worker can produce in a day is 75. The rate of increase in the number of units N produced with respect to time t in days by a new employee is proportional to $75 - N$.
    (a) Determine the differential equation describing the rate of change of performance with respect to time.
    (b) Solve the differential equation from part (a).
    (c) Find the particular solution for a new employee who produced 20 units on the first day at the factory and 35 units on the twentieth day.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

30. Intravenous Feeding

Glucose is added intravenously to the bloodstream at the rate of q units per minute, and the body removes glucose from the bloodstream at a rate proportional to the amount present. Assume that $Q(t)$ is the amount of glucose in the bloodstream at time t.

(a) Determine the differential equation describing the rate of change of glucose in the bloodstream with respect to time.

(b) Solve the differential equation from part (a), letting $Q = Q_0$ when $t = 0$.

(c) Find the limit of $Q(t)$ as $t \to \infty$.

Falling Object **In Exercises 31 and 32, consider an object with a mass of 4 kilograms dropped from a height of 1500 meters, where the air resistance is proportional to the velocity.**

31. Write the velocity of the object as a function of time t when the velocity after 5 seconds is approximately -31 meters per second. What is the limiting value of the velocity function?

32. Use the result of Exercise 31 to write the position of the object as a function of time t. Approximate the velocity of the object when it reaches ground level.

Electric Circuits **In Exercises 33 and 34, use the differential equation for electric circuits given by**

$$L\frac{dI}{dt} + RI + E.$$

In this equation, I is the current, R is the resistance, L is the inductance, and E is the electromotive force (voltage).

33. Solve the differential equation for the current given a constant voltage E_0.

34. Use the result of Exercise 33 to find the equation for the current when $I(0) = 0$, $E_0 = 120$ volts, $R = 600$ ohms, and $L = 4$ henrys. When does the current reach 90% of its limiting value?

Mixture **In Exercises 35–38, consider a tank that at time $t = 0$ contains v_0 gallons of a solution of which, by weight, q_0 pounds is soluble concentrate. Another solution containing q_1 pounds of the concentrate per gallon is running into the tank at the rate of r_1 gallons per minute. The solution in the tank is kept well stirred and is withdrawn at the rate of r_2 gallons per minute.**

35. Let Q be the amount of concentrate (in pounds) in the solution at any time t. Show that

$$\frac{dQ}{dt} + \frac{r_2 Q}{v_0 + (r_1 - r_2)t} = q_1 r_1.$$

36. Let Q be the amount of concentrate (in pounds) in the solution at any time t. Write the differential equation for the rate of change of Q with respect to t when $r_1 = r_2 = r$.

37. A 200-gallon tank is full of a solution containing 25 pounds of concentrate. Starting at time $t = 0$, distilled water is admitted to the tank at a rate of 10 gallons per minute, and the well-stirred solution is withdrawn at the same rate.

(a) Find the amount of concentrate Q (in pounds) in the solution as a function of t.

(b) Find the time at which the amount of concentrate in the tank reaches 15 pounds.

(c) Find the amount of concentrate (in pounds) in the solution as $t \to \infty$.

38. A 200-gallon tank is half full of distilled water. Starting at time $t = 0$, a solution containing 0.5 pound of concentrate per gallon is admitted to the tank at a rate of 5 gallons per minute, and the well-stirred mixture is withdrawn at a rate of 3 gallons per minute.

(a) At what time will the tank be full?

(b) At the time the tank is full, how many pounds of concentrate will it contain?

(c) Repeat parts (a) and (b), assuming that the solution entering the tank contains 1 pound of concentrate per gallon.

39. Using an Integrating Factor The expression $u(x)$ is an integrating factor for $y' + P(x)y = Q(x)$. Which of the following is equal to $u'(x)$? Verify your answer.

(a) $P(x)u(x)$ (b) $P'(x)u(x)$

(c) $Q(x)u(x)$ (d) $Q'(x)u(x)$

40. HOW DO YOU SEE IT? The graph shows the amount of concentrate Q (in pounds) in a solution in a tank at time t (in minutes) as a solution with concentrate enters the tank, is well stirred, and is withdrawn from the tank.



(a) How much concentrate is in the tank at time $t = 0$?

(b) Which is greater, the rate of solution into the tank or the rate of solution withdrawn from the tank? Explain.

(c) At what time is there no concentrate in the tank? Explain what this means.

Numstocker/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploring Concepts

41. Describe two ways to find the general solution of

$$\frac{dy}{dx} + 3xy = x.$$

Verify that each method gives the same result.

42. Explain why you can omit the constant of integration when finding an integrating factor.

Matching **In Exercises 43–46, match the differential equation with its solution.**

Differential Equation	Solution
43. $y' - 2x = 0$	(a) $y = Ce^{x^2}$
44. $y' - 2y = 0$	(b) $y = -\frac{1}{2} + Ce^{x^2}$
45. $y' - 2xy = 0$	(c) $y = x^2 + C$
46. $y' - 2xy = x$	(d) $y = Ce^{2x}$

Slope Field **In Exercises 47 and 48, (a) use a graphing utility to graph the slope field for the differential equation, (b) find the particular solutions of the differential equation passing through the given points, and (c) use a graphing utility to graph the particular solutions on the slope field in part (a).**

Differential Equation	Points
47. $\frac{dy}{dx} - \frac{1}{x}y = x^2, \quad x > 0$	$(-2, 4), (2, 8)$
48. $\frac{dy}{dx} + 4x^3y = x^3$	$\left(0, \frac{7}{2}\right), \left(0, -\frac{1}{2}\right)$

Solving a First-Order Differential Equation **In Exercises 49–56, find the general solution of the first-order differential equation for $x > 0$ by any appropriate method.**

49. $\frac{dy}{dx} = \frac{e^{2x+y}}{e^{x-y}}$

50. $y' \cos x^2 + \frac{y \cos x^2}{x} = \sec x^2$

51. $y \cos x - \cos x + \frac{dy}{dx} = 0$

52. $y' = 2x\sqrt{1 - y^2}$

53. $(2y - e^x)\,dx + x\,dy = 0$

54. $(x + y)\,dx - x\,dy = 0$

55. $3(y - 4x^2)\,dx + x\,dy = 0$

56. $x\,dx + (y + e^y)(x^2 + 1)\,dy = 0$

Solving a Bernoulli Differential Equation **In Exercises 57–64, solve the Bernoulli differential equation. The *Bernoulli equation* is a well-known nonlinear equation of the form**

$$y' + P(x)y = Q(x)y^n$$

that can be reduced to a linear form by a substitution. The general solution of a Bernoulli equation is

$$y^{1-n}e^{\int(1-n)P(x)\,dx} = \int (1-n)Q(x)e^{\int(1-n)P(x)\,dx}\,dx + C.$$

57. $y' + 3x^2y = x^2y^3$

58. $y' + xy = xy^{-1}$

59. $y' + \left(\frac{1}{x}\right)y = xy^2, \quad x > 0$

60. $y' + \left(\frac{1}{x}\right)y = x\sqrt{y}, \quad x > 0$

61. $xy' + y = xy^3, \quad x > 0$

62. $y' - y = y^3$

63. $y' - y = e^x\sqrt[3]{y}$

64. $yy' - 2y^2 = e^x$

True or False? **In Exercises 65 and 66, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

65. $y' + x\sqrt{y} = x^2$ is a first-order linear differential equation.

66. $y' + xy = e^xy$ is a first-order linear differential equation.

SECTION PROJECT

Weight Loss

A person's weight depends on both the number of calories consumed and the energy used. Moreover, the amount of energy used depends on a person's weight—the average amount of energy used by a person is 17.5 calories per pound per day. So, the more weight a person loses, the less energy a person uses (assuming that the person maintains a constant level of activity). An equation that can be used to model weight loss is

$$\frac{dw}{dt} = \frac{C}{3500} - \frac{17.5}{3500}w$$

where w is the person's weight (in pounds), t is the time in days, and C is the constant daily calorie consumption.

(a) Find the general solution of the differential equation.

(b) Consider a person who weighs 180 pounds and begins a diet of 2500 calories per day. How long will it take the person to lose 10 pounds? How long will it take the person to lose 35 pounds?

(c) Use a graphing utility to graph the particular solution from part (b). What is the "limiting" weight of the person?

(d) Repeat parts (b) and (c) for a person who weighs 200 pounds when the diet is started.

FOR FURTHER INFORMATION For more information on modeling weight loss, see the article "A Linear Diet Model" by Arthur C. Segal in *The College Mathematics Journal.*

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Review Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Exploring Concepts

In this chapter, you studied differential equations, one of the most important areas of applied mathematics. Solving differential equations analytically can be difficult, so you studied how to solve differential equations using numerical and graphical approaches as well. (Note how this three-pronged approach to problem solving is used in Exercise 5.)

1. **Numerical approach** Euler's Method, an approximation technique for initial value problems
2. **Graphical approach** Slope fields (see figure)
3. **Analytic approach** Separation of variables; integrating factor and first-order linear differential equation in standard form

Using these approaches, you solved a variety of applications involving differential equations, including growth and decay models and logistic models.



Slope field for $y' = 2x + y$

1. Determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.

(a) In exponential growth, the rate of growth is constant.

(b) In linear growth, the rate of growth is constant.

(c) A differential equation can have more than one solution.

2. When determining a particular solution, how do you determine how many initial conditions are required?

3. Explain how you can find a particular solution of the differential equation $y'' + 4y' + 6y = 30$ by observation.

4. Explain how to use separation of variables to solve a differential equation.

5. Consider the differential equation $y' = -x/y$ that satisfies the initial condition $y(3) = 4$.

(a) Use Euler's Method with $h = 0.1$ to approximate the solutions at $x = 3.1$ and $x = 3.2$.

(b) Sketch a slope field for the differential equation. Then sketch the solution that passes through the point $(3, 4)$.

(c) Solve the differential equation.

(d) Explain how you can check your answer to part (c).

6. The differential equation

$$\frac{dN}{dt} = k(30 - N)$$

represents the rate of change of the number of units produced per day by a new employee, where N is the number of units and t is the time in days. The general solution of this differential equation is

$$N = 30 - 30e^{-kt}.$$

The figure shows the particular solutions for $k = 0.3$, 0.6, and 1. Match the value of k with each solution. (The solutions are labeled A, B, and C.) Explain your reasoning.



7. Determining a Solution Determine whether the function $y = x^3$ is a solution of the differential equation $2xy' + 4y = 10x^3$.

8. Determining a Solution Determine whether the function $y = 2 \sin 2x$ is a solution of the differential equation $y''' - 8y = 0$.

Finding a General Solution **In Exercises 9–14, use integration to find a general solution of the differential equation.**

9. $\dfrac{dy}{dx} = 4x^2 + 7$

10. $\dfrac{dy}{dx} = \dfrac{6 - x}{3x}, \quad x > 0$

11. $\dfrac{dy}{dx} = \cos 2x$

12. $\dfrac{dy}{dx} = 8 \csc x \cot x$

13. $\dfrac{dy}{dx} = e^{2-x}$

14. $\dfrac{dy}{dx} = 2e^{3x}$

Slope Field **In Exercises 15 and 16, (a) sketch the slope field for the differential equation, and (b) use the slope field to sketch the solution that passes through the given point. Use a graphing utility to verify your results. To print a blank coordinate plane, go to *MathGraphs.com*.**

15. $y' = 2x^2 - x, \quad (0, 2)$

16. $y' = y + 4x, \quad (-1, 1)$

Euler's Method **In Exercises 17 and 18, use Euler's Method to make a table of values for the approximate solution of the differential equation with the specified initial value. Use n steps of size h.**

17. $y' = x - y, \quad y(0) = 4, \quad n = 10, \quad h = 0.05$

18. $y' = 5x - 2y, \quad y(0) = 2, \quad n = 10, \quad h = 0.1$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Slope Field **In Exercises 19 and 20, a differential equation and its slope field are given. Complete the table by determining the slopes (if possible) in the slope field at the given points.**

x	-4	-2	0	2	4	8
y	2	0	4	4	6	8
dy/dx						

19. $\dfrac{dy}{dx} = 2x - y$



20. $\dfrac{dy}{dx} = x \sin \dfrac{\pi y}{4}$



Solving a Differential Equation **In Exercises 21–28, find the general solution of the differential equation.**

21. $\dfrac{dy}{dx} = 6x - x^3$

22. $\dfrac{dy}{dx} = 3y + 5$

23. $\dfrac{dy}{dx} = (y - 1)^2$

24. $\dfrac{dy}{dx} = \dfrac{x}{x^2 + 2}$

25. $(2 + x)y' - xy = 0$

26. $xy' - (x + 1)y = 0$

27. $\sqrt{x + 1}\,y' - y = 0$

28. $y' + \sqrt{x}y = 9\sqrt{x}$

Writing and Solving a Differential Equation **In Exercises 29 and 30, write and find the general solution of the differential equation that models the verbal statement.**

29. The rate of change of y with respect to t is inversely proportional to the cube of t.

30. The rate of change of y with respect to t is proportional to $50 - t$.

Finding an Exponential Function **In Exercises 31–34, find the exponential function $y = Ce^{kt}$ that passes through the two given points.**

31.



32.



33.



34.



35. Air Pressure Under ideal conditions, air pressure decreases continuously with the height above sea level at a rate proportional to the pressure at that height. The barometer reads 30 inches at sea level and 15 inches at 18,000 feet. Find the barometric pressure at 35,000 feet.

36. Radioactive Decay Radioactive radium has a half-life of approximately 1599 years. The initial quantity is 15 grams. How much remains after 750 years?

37. Population Growth A population grows exponentially at the rate of 1.85%. How long will it take the population to double?

38. Compound Interest Find the balance in an account when \$400 is deposited for 11 years at an interest rate of 2% compounded continuously.

39. Sales The sales S (in thousands of units) of a new product after it has been on the market for t years is given by

$$S = Ce^{k/t}.$$

(a) Find S as a function of t when 5000 units have been sold after 1 year and the saturation point for the market is 30,000 units (that is, $\lim_{t\to\infty} S = 30$).

(b) How many units will have been sold after 5 years?

40. Sales The sales S (in thousands of units) of a new product after it has been on the market for t years is given by

$$S = 25(1 - e^{kt}).$$

(a) Find S as a function of t when 4000 units have been sold after 1 year.

(b) How many units will saturate this market?

Finding a General Solution Using Separation of Variables **In Exercises 41–44, find the general solution of the differential equation.**

41. $\dfrac{dy}{dx} = \dfrac{5x}{y}$

42. $\dfrac{dy}{dx} = \dfrac{x^3}{2y^2}$

43. $y'e^{y-3x} = e^{x+2y}$

44. $y' - e^y \sin x = 0$

Finding a Particular Solution Using Separation of Variables **In Exercises 45–48, find the particular solution of the differential equation that satisfies the initial condition.**

Differential Equation	Initial Condition
45. $y^3y' - 3x = 0$	$y(2) = 2$
46. $yy' - 5e^{2x} = 0$	$y(0) = -3$
47. $y^3(x^4 + 1)y' - x^3(y^4 + 1) = 0$	$y(0) = 1$
48. $y' + \sin x \cos x = 0$	$y(\pi) = -2$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding a Particular Solution Curve **In Exercises 49 and 50, find an equation of the curve that passes through the point and has the given slope.**

49. $(1, 3), \quad y' = \dfrac{2x}{y}$

50. $(1, -2), \quad y' = \dfrac{y}{8x}$

Finding Orthogonal Trajectories **In Exercises 51 and 52, find the orthogonal trajectories for the family of curves. Use a graphing utility to graph several members of each family.**

51. $5x^2 - 4y^2 = C$

52. $x^3 = Cy$

Using a Logistic Equation **In Exercises 53 and 54, the logistic equation models the growth of a population. Use the equation to (a) find the value of k, (b) find the carrying capacity, (c) find the initial population, (d) determine when the population will reach 50% of its carrying capacity, and (e) write a logistic differential equation that has the solution $P(t)$.**

53. $P(t) = \dfrac{5250}{1 + 34e^{-0.55t}}$

54. $P(t) = \dfrac{4800}{1 + 14e^{-0.15t}}$

Solving a Logistic Differential Equation **In Exercises 55 and 56, find the logistic equation that passes through the given point.**

55. $\dfrac{dy}{dt} = y\left(1 - \dfrac{y}{80}\right), \quad (0, 8)$

56. $\dfrac{dy}{dt} = 1.76y\left(1 - \dfrac{y}{8}\right), \quad (0, 3)$

57. Wildlife Population The rate of change of the number of raccoons $N(t)$ in a population is directly proportional to $380 - N(t)$, where t is the time in years. When $t = 0$, the population is 110, and when $t = 4$, the population has increased to 150. Find the population when $t = 8$.

58. Environment A conservation department releases 1200 brook trout into a lake. It is estimated that the carrying capacity of the lake for the species is 20,400. After the first year, there are 2000 brook trout in the lake.

(a) Write a logistic equation that models the number of brook trout in the lake.

(b) Find the number of brook trout in the lake after 8 years.

(c) When will the number of brook trout reach 10,000?

(d) Write a logistic differential equation that models the growth rate of the brook trout population. Then repeat part (b) using Euler's method with a step size of $h = 1$. Compare the approximation with the exact answer.

(e) At what time is the brook trout population growing most rapidly? Explain.

Solving a First-Order Linear Differential Equation **In Exercises 59–64, find the general solution of the first-order linear differential equation.**

59. $y' - y = 10$

60. $e^x y' + 4e^x y = 1$

61. $4y' = e^{x/4} + y$

62. $\dfrac{dy}{dx} - \dfrac{5y}{x^2} = \dfrac{1}{x^2}, \quad x > 0$

63. $(x - 2)y' + y = 1, \quad x > 2$

64. $(x + 3)y' + 2y = 2(x + 3)^2, \quad x > -3$

Finding a Particular Solution **In Exercises 65–68, find the particular solution of the first-order linear differential equation that satisfies the initial condition.**

Differential Equation	Initial Condition
65. $y' + 5y = e^{5x}$	$y(0) = 3$
66. $y' - \left(\dfrac{3}{x}\right)y = 2x^3$	$y(1) = 1$
67. $(3y + 5)\cos x\, dx = dy$	$y(\pi) = 0$
68. $y' - 8x^3 y = e^{2x^4}$	$y(0) = 2$

Building on Concepts

69. Although it is true for some functions f and g, a common mistake in calculus is to believe that the Product Rule for derivatives is $(fg)' = f'g'$.

(a) Given $g(x) = x$, find f such that $(fg)' = f'g'$.

(b) Given an arbitrary function g, find a function f such that $(fg)' = f'g'$.

(c) Describe what happens when $g(x) = e^x$.

70. In a disease outbreak, carriers are individuals who can transmit a disease but who exhibit no apparent symptoms. Let y represent the proportion of carriers in a population at any time t. Suppose that carriers are quarantined at a rate r. Then the change in the proportion of carriers can be modeled by

$$\frac{dy}{dt} = -ry.$$

Find the general solution of the differential equation given that 40% of the population are carriers at the beginning of an outbreak.

71. A function $f(x, y)$ is **homogeneous of degree n** if

$$f(tx, ty) = t^n f(x, y)$$

for all t, where n is an integer. Determine whether each function is homogeneous, and if it is, determine its degree.

(a) $f(x, y) = x^3 + 4xy^2 + y^3$ (b) $f(x, y) = e^{x/y}$

(c) $f(x, y) = 2 \ln xy$ (d) $f(x, y) = \tan(x + y)$

72. A **homogeneous differential equation** is an equation of the form $M(x, y)\, dx + N(x, y)\, dy = 0$, where M and N are homogeneous functions of the same degree. To solve an equation of this form by the method of separation of variables, use the substitutions $y = vx$ and $dy = x\, dv + v\, dx$, where v is a differentiable function of x. Solve each homogeneous differential equation in terms of x and y.

(a) $(x + y)\, dx - 2x\, dy = 0$

(b) $(x^3 + y^3)\, dx - xy^2\, dy = 0$

(c) $(x - y)\, dx - (x + y)\, dy = 0$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.S. Problem Solving

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

1. Doomsday Equation The differential equation

$$\frac{dy}{dt} = ky^{1+\varepsilon}$$

where k and ε are positive constants, is called the **doomsday equation.**

(a) Solve the doomsday equation

$$\frac{dy}{dt} = y^{1.01}$$

given that $y(0) = 1$. Find the time T at which

$$\lim_{t \to T^-} y(t) = \infty.$$

(b) Solve the doomsday equation

$$\frac{dy}{dt} = ky^{1+\varepsilon}$$

given that $y(0) = y_0$. Explain why this equation is called the doomsday equation.

2. Rewriting the Logistic Equation Show that the logistic equation

$$y = \frac{L}{1 + be^{-kt}}$$

can be written as

$$y = \frac{1}{2}L\left[1 + \tanh\left(\frac{1}{2}k\left(t - \frac{\ln b}{k}\right)\right)\right].$$

What can you conclude about the graph of the logistic equation?

3. Torricelli's Law **Torricelli's Law** states that water will flow from an opening at the bottom of a tank with the same speed that it would attain falling from the surface of the water to the opening. One of the forms of Torricelli's Law is

$$A(h)\frac{dh}{dt} = -k\sqrt{2gh}$$

where h is the height of the water in the tank, k is the area of the opening at the bottom of the tank, $A(h)$ is the horizontal cross-sectional area at height h, and g is the acceleration due to gravity ($g \approx 32$ feet per second per second). A hemispherical water tank has a radius of 6 feet. When the tank is full, a circular valve with a radius of 1 inch is opened at the bottom (see figure). How long will it take for the tank to drain completely?



4. Torricelli's Law The cylindrical water tank shown in the figure has a height of 18 feet. When the tank is full, a circular valve is opened at the bottom of the tank. After 30 minutes, the depth of the water is 12 feet.



(a) Using Torricelli's Law, how long will it take for the tank to drain completely?

(b) What is the depth of the water in the tank after 1 hour?

5. Torricelli's Law Suppose the tank in Exercise 4 has a height of 20 feet and a radius of 8 feet, and the valve is circular with a radius of 2 inches. The tank is full when the valve is opened. How long will it take for the tank to drain completely?

6. Gompertz Equation Another model that can be used to represent population growth is the **Gompertz equation,** which is the solution of the differential equation

$$\frac{dy}{dt} = ky \ln \frac{L}{y}$$

where k is a constant and L is the carrying capacity.

(a) Find the general solution of the differential equation.

(b) Use a graphing utility to graph the slope field for the differential equation when $k = 0.05$ and $L = 1000$.

(c) Describe the behavior of the graph in part (b) as $t \to \infty$.

(d) Use a graphing utility to graph the equation you found in part (a) for $L = 5000$, $y(0) = 500$, and $k = 0.02$. Determine the concavity of the graph and how it compares with the general solution of the logistic differential equation.

7. Biomass Biomass is a measure of the amount of living matter in an ecosystem. Suppose the biomass $s(t)$ in a given ecosystem increases at a rate of about 3.5 tons per year and decreases by about 1.9% per year. This situation can be modeled by the differential equation

$$\frac{ds}{dt} = 3.5 - 0.019s.$$

(a) Find the general solution of the differential equation.

(b) Use a graphing utility to graph the slope field for the differential equation. What do you notice?

(c) Explain what happens to the biomass as $t \to \infty$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

7 Applications of Integration

GO DIGITAL

7.1 Area of a Region Between Two Curves
7.2 Volume: The Disk Method
7.3 Volume: The Shell Method
7.4 Arc Length and Surfaces of Revolution
7.5 Work
7.6 Moments, Centers of Mass, and Centroids
7.7 Fluid Pressure and Fluid Force

CalcView®



CalcChat®


Chapter 7
Section 1
Exercise 23
GO
The points of intersection are given by:
$y^2 = y + 2$
$(y - 2)(y + 1) = 0$ when $y = -1, 2$
$A = \int_{-1}^{2} [g(y) - f(y)]\,dy$
$= \int_{-1}^{2} [(y + 2) - y^2]\,dy$
$= \left[2y + \frac{y^2}{2} - \frac{y^3}{3}\right]_{-1}^{2} = \frac{9}{2}$
(4, 2)
(1, −1)
PREV. 13 15 17 19 21 23 25 27 29 31 33 NEXT

7.2 3D Printing *(Exercise 68, p. 463)*

7.3 Saturn *(Section Project, p. 473)*

left, guteksk7/Shutterstock.com; right, NASA
© Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322
Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

7.1 Area of a Region Between Two Curves

GO DIGITAL

- Find the area of a region between two curves using integration.
- Find the area of a region between intersecting curves using integration.
- Describe integration as an accumulation process.

Area of a Region Between Two Curves

With a few modifications, you can extend the application of definite integrals from the area of a region *under* a curve to the area of a region *between* two curves. Consider two functions f and g that are continuous on the interval $[a, b]$. Also, the graphs of both f and g lie above the x-axis, and the graph of g lies below the graph of f, as shown in Figure 7.1. You can geometrically interpret the area of the region between the graphs as the area of the region under the graph of g subtracted from the area of the region under the graph of f, as shown in Figure 7.2.



Figure 7.1



Area of region between f and g	=	Area of region under f	−	Area of region under g
$\int_a^b [f(x) - g(x)]\,dx$	=	$\int_a^b f(x)\,dx$	−	$\int_a^b g(x)\,dx$

Figure 7.2

To verify the reasonableness of the result shown in Figure 7.2, you can partition the interval $[a, b]$ into n subintervals, each of width Δx. Then, as shown in Figure 7.3, sketch a **representative rectangle** of width Δx and height $f(x_i) - g(x_i)$, where x_i is in the ith subinterval. The area of this representative rectangle is

$$\Delta A_i = (\text{height})(\text{width}) = [f(x_i) - g(x_i)]\Delta x.$$

By adding the areas of the n rectangles and taking the limit as $\|\Delta\| \to 0$ $(n \to \infty)$, you obtain

$$\lim_{n\to\infty} \sum_{i=1}^{n} [f(x_i) - g(x_i)]\Delta x.$$



Figure 7.3

Because f and g are continuous on $[a, b]$, $f - g$ is also continuous on $[a, b]$ and the limit exists. So, the area of the region is

$$\begin{aligned} \text{Area} &= \lim_{n\to\infty} \sum_{i=1}^{n} [f(x_i) - g(x_i)]\Delta x \\ &= \int_a^b [f(x) - g(x)]\,dx. \end{aligned}$$

Area between f and g

Big Ideas of Calculus

In this chapter, you will study some applications of the integral. These applications include

- finding the area of a region between two curves,
- finding the volume of a solid, and
- the work done by a force.

In many of these applications, you begin with a known formula. Then you will investigate how the limit of a sum yields a new formula that involves integration.

REMARK Recall from Section 4.3 that $\|\Delta\|$ is the norm of the partition. In a regular partition, the statements $\|\Delta\| \to 0$ and $n \to \infty$ are equivalent.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Area of a Region Between Two Curves

If f and g are continuous functions on $[a, b]$ and $g(x) \le f(x)$ for all x in $[a, b]$, then the area of the region bounded by the graphs of f and g and the vertical lines $x = a$ and $x = b$ is

$$A = \int_a^b [f(x) - g(x)]\,dx.$$

In Figure 7.1, the graphs of f and g are shown above the x-axis. This, however, is not necessary. The same integrand $[f(x) - g(x)]$ can be used as long as f and g are continuous and $g(x) \le f(x)$ for all x in the interval $[a, b]$. This is summarized graphically in Figure 7.4. Notice in Figure 7.4 that the height of a representative rectangle is $f(x) - g(x)$ regardless of the relative position of the x-axis.



Figure 7.4

Representative rectangles are used throughout this chapter in various applications of integration. A vertical rectangle (of width Δx) implies integration with respect to x, whereas a horizontal rectangle (of width Δy) implies integration with respect to y.

EXAMPLE 1 Finding the Area of a Region Between Two Curves

Find the area of the region bounded by the graphs of $y = x^2 + 2$, $y = -x$, $x = 0$, and $x = 1$.

Solution Begin by sketching the graphs of both functions, as shown in Figure 7.5. From the figure, note that $-x \le x^2 + 2$ for all x in $[0, 1]$. So, let $f(x) = x^2 + 2$ and $g(x) = -x$. The area of the representative rectangle is

$$\Delta A = [f(x) - g(x)]\Delta x = [(x^2 + 2) - (-x)]\Delta x$$

and the area of the region is

$$\begin{aligned} A &= \int_a^b [f(x) - g(x)]\,dx && \text{Area between } f \text{ and } g \\ &= \int_0^1 [(x^2 + 2) - (-x)]\,dx && \text{Substitute for } f \text{ and } g. \\ &= \left[\frac{x^3}{3} + \frac{x^2}{2} + 2x\right]_0^1 && \text{Integrate.} \\ &= \frac{1}{3} + \frac{1}{2} + 2 && \text{Apply Fundamental Theorem of Calculus.} \\ &= \frac{17}{6}. && \text{Simplify.} \end{aligned}$$



Region bounded by the graph of f, the graph of g, $x = 0$, and $x = 1$

Figure 7.5

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Area of a Region Between Intersecting Curves

In Example 1, the graphs of $f(x) = x^2 + 2$ and $g(x) = -x$ do not intersect, and the values of a and b are given explicitly. A more common problem involves the area of a region bounded by two *intersecting* graphs, where the values of a and b must be calculated.

EXAMPLE 2 A Region Lying Between Two Intersecting Graphs

Find the area of the region bounded by the graphs of $f(x) = 2 - x^2$ and $g(x) = x$.

Solution In Figure 7.6, notice that the graphs of f and g have two points of intersection. To find the x-coordinates of these points, set $f(x)$ and $g(x)$ equal to each other and solve for x.

$$\begin{aligned} 2 - x^2 &= x && \text{Set } f(x) \text{ equal to } g(x). \\ -x^2 - x + 2 &= 0 && \text{Write in general form.} \\ -(x + 2)(x - 1) &= 0 && \text{Factor.} \\ x &= -2 \text{ or } 1 && \text{Solve for } x. \end{aligned}$$

So, $a = -2$ and $b = 1$. Because $g(x) \le f(x)$ for all x in the interval $[-2, 1]$, the representative rectangle has an area of

$$\Delta A = [f(x) - g(x)]\Delta x = [(2 - x^2) - x]\Delta x$$

and the area of the region is

$$\begin{aligned} A &= \int_{-2}^{1} [(2 - x^2) - x]\,dx && \text{Area between } f \text{ and } g \\ &= \left[-\frac{x^3}{3} - \frac{x^2}{2} + 2x \right]_{-2}^{1} && \text{Integrate.} \\ &= \frac{9}{2}. \end{aligned}$$



Region bounded by the graph of f and the graph of g
Figure 7.6

EXAMPLE 3 A Region Lying Between Two Intersecting Graphs

The sine and cosine curves intersect infinitely many times, bounding regions of equal areas, as shown in Figure 7.7. Find the area of one of these regions.

Solution Consider the interval corresponding to the shaded region in Figure 7.7. For all x in this interval, $\cos x \le \sin x$. So, let $g(x) = \cos x$ and $f(x) = \sin x$. To find the two points of intersection on this interval, set $f(x)$ and $g(x)$ equal to each other and solve for x.

$$\begin{aligned} \sin x &= \cos x && \text{Set } f(x) \text{ equal to } g(x). \\ \frac{\sin x}{\cos x} &= 1 && \text{Divide each side by } \cos x. \\ \tan x &= 1 && \text{Trigonometric identity} \\ x &= \frac{\pi}{4} \text{ or } \frac{5\pi}{4}, \quad 0 \le x \le 2\pi && \text{Solve for } x. \end{aligned}$$

So, $a = \pi/4$ and $b = 5\pi/4$. Because $\cos x \le \sin x$ for all x in the interval $[\pi/4, 5\pi/4]$, the area of the region is

$$\begin{aligned} A &= \int_{\pi/4}^{5\pi/4} [\sin x - \cos x]\,dx && \text{Area between } f \text{ and } g \\ &= \left[-\cos x - \sin x \right]_{\pi/4}^{5\pi/4} && \text{Integrate.} \\ &= 2\sqrt{2}. \end{aligned}$$



One of the regions bounded by the graphs of the sine and cosine functions
Figure 7.7

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

To find the area of the region between two curves that intersect at *more* than two points, first determine all points of intersection. Then check to see which curve is above the other in each interval determined by these points, as shown in Example 4.

EXAMPLE 4 Curves That Intersect at More than Two Points

See LarsonCalculus.com for an interactive version of this type of example.

Find the area of the region between the graphs of

$$f(x) = 3x^3 - x^2 - 10x \quad \text{and} \quad g(x) = -x^2 + 2x.$$



On $[-2, 0]$, $g(x) \leq f(x)$, and on $[0, 2]$, $f(x) \leq g(x)$.
Figure 7.8

Solution Begin by setting $f(x)$ and $g(x)$ equal to each other and solving for x. This yields the x-values at all points of intersection of the two graphs.

$$\begin{aligned} 3x^3 - x^2 - 10x &= -x^2 + 2x && \text{Set } f(x) \text{ equal to } g(x). \\ 3x^3 - 12x &= 0 && \text{Write in general form.} \\ 3x(x-2)(x+2) &= 0 && \text{Factor.} \\ x &= -2, 0, 2 && \text{Solve for } x. \end{aligned}$$

So, the two graphs intersect when $x = -2$, 0, and 2. In Figure 7.8, notice that $g(x) \leq f(x)$ on the interval $[-2, 0]$. The two graphs switch at the origin, however, and $f(x) \leq g(x)$ on the interval $[0, 2]$. So, you need two integrals—one for the interval $[-2, 0]$ and one for the interval $[0, 2]$.

$$\begin{aligned} A &= \overbrace{\int_{-2}^{0} [f(x) - g(x)]\,dx}^{\text{Area on } [-2,0]} + \overbrace{\int_{0}^{2} [g(x) - f(x)]\,dx}^{\text{Area on } [0,2]} \\ &= \int_{-2}^{0} (3x^3 - 12x)\,dx + \int_{0}^{2} (-3x^3 + 12x)\,dx && \text{Substitute for } f \text{ and } g \text{ and simplify.} \\ &= \left[\frac{3x^4}{4} - 6x^2\right]_{-2}^{0} + \left[\frac{-3x^4}{4} + 6x^2\right]_{0}^{2} && \text{Integrate.} \\ &= -(12 - 24) + (-12 + 24) \\ &= 24 \end{aligned}$$

REMARK In Example 4, notice that you obtain an incorrect result when you integrate from -2 to 2. Such integration produces

$$\int_{-2}^{2} [f(x) - g(x)]\,dx = \int_{-2}^{2} (3x^3 - 12x)\,dx = 0.$$

When the graph of a function of y is a boundary of a region, it is often convenient to use representative rectangles that are *horizontal* and find the area by integrating with respect to y. In general, to determine the area between two curves, you can use

$$A = \int_{x_1}^{x_2} \underbrace{[(\text{top curve}) - (\text{bottom curve})]}_{\text{in variable } x}\,dx \qquad \text{Vertical rectangles}$$

or

$$A = \int_{y_1}^{y_2} \underbrace{[(\text{right curve}) - (\text{left curve})]}_{\text{in variable } y}\,dy \qquad \text{Horizontal rectangles}$$

where (x_1, y_1) and (x_2, y_2) are either adjacent points of intersection of the two curves involved or points on the specified boundary lines.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 5 Horizontal Representative Rectangles

Find the area of the region bounded by the graphs of $x = 3 - y^2$ and $x = y + 1$.

Solution Begin by sketching the graphs of both functions, as shown in Figure 7.9. From the figure, note that the two curves intersect when $y = -2$ and $y = 1$. Because $y + 1 \leq 3 - y^2$ for all y in $[-2, 1]$, let $g(y) = 3 - y^2$ and $f(y) = y + 1$. The area of the representative rectangle is

$$\Delta A = \overbrace{[g(y)}^{\text{Right curve}} - \overbrace{f(y)]}^{\text{Left curve}}\Delta y = [(3 - y^2) - (y + 1)]\Delta y.$$

So, the area is

$$\begin{aligned} A &= \int_{-2}^{1} [(3 - y^2) - (y + 1)]\, dy && \text{Area between } g \text{ and } f \\ &= \int_{-2}^{1} (-y^2 - y + 2)\, dy && \text{Simplify.} \\ &= \left[\frac{-y^3}{3} - \frac{y^2}{2} + 2y\right]_{-2}^{1} && \text{Integrate.} \\ &= \left(-\frac{1}{3} - \frac{1}{2} + 2\right) - \left(\frac{8}{3} - 2 - 4\right) \\ &= \frac{9}{2}. \end{aligned}$$



Horizontal rectangles (integration with respect to y)
Figure 7.9



Vertical rectangles (integration with respect to x)
Figure 7.10

In Example 5, notice that by integrating with respect to y, you need only one integral. To integrate with respect to x, you would need two integrals because the upper boundary changes at $x = 2$, as shown in Figure 7.10.

$$\begin{aligned} A &= \int_{-1}^{2} \left[(x - 1) + \sqrt{3 - x}\right] dx + \int_{2}^{3} \left(\sqrt{3 - x} + \sqrt{3 - x}\right) dx \\ &= \int_{-1}^{2} [x - 1 + (3 - x)^{1/2}]\, dx + 2\int_{2}^{3} (3 - x)^{1/2}\, dx \\ &= \left[\frac{x^2}{2} - x - \frac{(3 - x)^{3/2}}{3/2}\right]_{-1}^{2} - 2\left[\frac{(3 - x)^{3/2}}{3/2}\right]_{2}^{3} \\ &= \left(2 - 2 - \frac{2}{3}\right) - \left(\frac{1}{2} + 1 - \frac{16}{3}\right) - 2(0) + 2\left(\frac{2}{3}\right) \\ &= \frac{9}{2} \end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Integration as an Accumulation Process

In this section, the integration formula for the area between two curves was developed by using a rectangle as the *representative element.* For each new application of integration in the remaining sections of this chapter, an appropriate representative element will be constructed using known precalculus formulas. Each integration formula will then be obtained by summing or accumulating these representative elements.

Known precalculus formula ⇨ Representative element ⇨ New integration formula

For example, the area formula in this section was developed as follows.

$A = (\text{height})(\text{width})$ ⇨ $\Delta A = [f(x) - g(x)]\Delta x$ ⇨ $A = \int_a^b [f(x) - g(x)]\,dx$

EXAMPLE 6 **Integration as an Accumulation Process**

Find the area of the region bounded by the graph of $y = 4 - x^2$ and the x-axis. Describe the integration as an accumulation process.

Solution The area of the region is

$$A = \int_{-2}^{2} (4 - x^2)\,dx.$$

You can think of the integration as an accumulation of the areas of the rectangles formed as the representative rectangle slides from $x = -2$ to $x = 2$, as shown in Figure 7.11.



$$A = \int_{-2}^{-2} (4 - x^2)\,dx = 0$$



$$A = \int_{-2}^{-1} (4 - x^2)\,dx = \frac{5}{3}$$



$$A = \int_{-2}^{0} (4 - x^2)\,dx = \frac{16}{3}$$



$$A = \int_{-2}^{1} (4 - x^2)\,dx = 9$$



$$A = \int_{-2}^{2} (4 - x^2)\,dx = \frac{32}{3}$$

Figure 7.11

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

7.1 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Give the geometric interpretation of the area of the region between two curves.
2. Describe how to find the area of the region bounded by the graphs of $f(x)$ and $g(x)$ and the vertical lines $x = a$ and $x = b$, where f and g do not intersect on $[a, b]$.
3. Explain why it is important to determine all points of intersection of two curves when finding the area of the region between the curves.
4. Sketch a region for which integration with respect to y is easier than integration with respect to x.

Writing a Definite Integral **In Exercises 5–10, write a definite integral that represents the area of the region. (Do not evaluate the integral.)**

5. $y_1 = x^2 - 6x$, $y_2 = 0$



6. $y_1 = x^2 + 2x + 1$, $y_2 = 2x + 5$



7. $y_1 = x^2 - 4x + 3$, $y_2 = -x^2 + 2x + 3$



8. $y_1 = x^2$, $y_2 = x^3$



9. $y_1 = 3(x^3 - x)$, $y_2 = 0$



10. $y_1 = (x - 1)^3$, $y_2 = x - 1$



Finding a Region **In Exercises 11–14, the integrand of the definite integral is a difference of two functions. Sketch the graph of each function and shade the region whose area is represented by the integral.**

11. $\int_0^4 \left[(x + 1) - \frac{x}{2}\right] dx$

12. $\int_2^3 \left[\left(\frac{x^3}{3} - x\right) - \frac{x}{3}\right] dx$

13. $\int_{-2}^1 [(2 - y) - y^2] \, dy$

14. $\int_0^4 \left(2\sqrt{y} - y\right) dy$

Finding the Area of a Region **In Exercises 15–28, sketch the region bounded by the graphs of the equations and find the area of the region.**

15. $y = x^2 - 1, \quad y = -x + 2, \quad x = 0, \quad x = 1$

16. $y = -x^3 + 2, \quad y = x - 3, \quad x = -1, \quad x = 1$

17. $f(x) = x^2 + 2x, \quad g(x) = x + 2$

18. $y = -x^2 + 3x + 1, \quad y = -x + 1$

19. $f(x) = \frac{1}{9x^2}, \quad y = 1, \quad x = 1, \quad x = 2$

20. $f(x) = -\frac{4}{x^3}, \quad y = 0, \quad x = -3, \quad x = -1$

21. $f(x) = x^5 + 2, \quad g(x) = x + 2$

22. $f(x) = \sqrt[3]{x - 1}, \quad g(x) = x - 1$

23. $f(y) = y^2, \quad g(y) = y + 2$

24. $f(y) = y(2 - y), \quad g(y) = -y$

25. $f(y) = y^2 + 1, \quad g(y) = 0, \quad y = -1, \quad y = 2$

26. $f(y) = \frac{y}{\sqrt{16 - y^2}}, \quad g(y) = 0, \quad y = 3$

27. $f(x) = \frac{10}{x}, \quad x = 0, \quad y = 2, \quad y = 10$

28. $g(x) = \frac{4}{2 - x}, \quad y = 4, \quad x = 0$

Comparing Methods **In Exercises 29 and 30, find the area of the region by integrating (a) with respect to x and (b) with respect to y. (c) Compare your results. Which method is simpler? In general, will this method always be simpler than the other one? Why or why not?**

29. $x = 4 - y^2$, $x = y - 2$



30. $y = x^2$, $y = 6 - x$



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding the Area of a Region **In Exercises 31–36, (a) use a graphing utility to graph the region bounded by the graphs of the functions, (b) find the area of the region analytically, and (c) use the integration capabilities of the graphing utility to verify your results.**

31. $f(x) = x(x^2 - 3x + 3), \quad g(x) = x^2$

32. $y = x^4 - 2x^2, \quad y = 2x^2$

33. $f(x) = x^4 - 4x^2, \quad g(x) = x^2 - 4$

34. $f(x) = x^4 - 9x^2, \quad g(x) = x^3 - 9x$

35. $f(x) = \dfrac{1}{1 + x^2}, \quad g(x) = \dfrac{1}{2}x^2$

36. $f(x) = \dfrac{6x}{x^2 + 1}, \quad y = 0, \quad 0 \le x \le 3$

Finding the Area of a Region **In Exercises 37–42, sketch the region bounded by the graphs of the equations and find the area of the region.**

37. $f(x) = \cos x, \quad g(x) = 2 - \cos x, \quad 0 \le x \le 2\pi$

38. $f(x) = \sin x, \quad g(x) = \cos 2x, \quad -\dfrac{\pi}{2} \le x \le \dfrac{\pi}{6}$

39. $f(x) = 2 \sin x, \quad g(x) = \tan x, \quad -\dfrac{\pi}{3} \le x \le \dfrac{\pi}{3}$

40. $f(x) = \sec \dfrac{\pi x}{4} \tan \dfrac{\pi x}{4}, \quad g(x) = \left(\sqrt{2} - 4\right)x + 4, \quad x = 0$

41. $f(x) = xe^{-x^2}, \quad y = 0, \quad 0 \le x \le 1$

42. $f(x) = -2^x, \quad g(x) = 1 - 3x$

Finding the Area of a Region **In Exercises 43–46, (a) use a graphing utility to graph the region bounded by the graphs of the equations, (b) find the area of the region analytically, and (c) use the integration capabilities of the graphing utility to verify your results.**

43. $f(x) = 2 \sin x + \sin 2x, \quad y = 0, \quad 0 \le x \le \pi$

44. $f(x) = 2 \sin x + \cos 2x, \quad y = 0, \quad 0 < x \le \pi$

45. $f(x) = \dfrac{1}{x^2}e^{1/x}, \quad y = 0, \quad 1 \le x \le 3$

46. $g(x) = \dfrac{4 \ln x}{x}, \quad y = 0, \quad x = 5$

Finding the Area of a Region **In Exercises 47–50, (a) use a graphing utility to graph the region bounded by the graphs of the equations, (b) explain why the area of the region is difficult to find analytically, and (c) use the integration capabilities of the graphing utility to approximate the area of the region to four decimal places.**

47. $y = \sqrt{\dfrac{x^3}{4 - x}}, \quad y = 0, \quad x = 3$

48. $y = \sqrt{x}\, e^x, \quad y = 0, \quad x = 0, \quad x = 1$

49. $y = x^2, \quad y = 4 \cos x$

50. $y = x^2, \quad y = \sqrt{3 + x}$

51. Finding the Area of a Region Find the area of the given region bounded by the graphs of y_1, y_2, and y_3, as shown in the figure.

$y_1 = x^2 + 2, \quad y_2 = 4 - x^2, \quad y_3 = 2 - x$



Figure for 51



Figure for 52

52. Finding the Area of a Region Find the area of the given region bounded by the graphs of y_1, y_2, and y_3, as shown in the figure.

$y_1 = \sin x, \quad y_2 = \cos x, \quad y_3 = \sin x + \cos x$

Integration as an Accumulation Process **In Exercises 53–56, find the accumulation function F. Then evaluate F at each value of the independent variable and graphically show the area given by each value of the independent variable.**

53. $F(x) = \displaystyle\int_0^x \left(\frac{1}{2}t + 1\right) dt$ (a) $F(0)$ (b) $F(2)$ (c) $F(6)$

54. $F(x) = \displaystyle\int_0^x \left(\frac{1}{2}t^2 + 2\right) dt$ (a) $F(0)$ (b) $F(4)$ (c) $F(6)$

55. $F(\alpha) = \displaystyle\int_{-1}^{\alpha} \cos \frac{\pi\theta}{2}\, d\theta$ (a) $F(-1)$ (b) $F(0)$ (c) $F\left(\frac{1}{2}\right)$

56. $F(y) = \displaystyle\int_{-1}^{y} 4e^{x/2}\, dx$ (a) $F(-1)$ (b) $F(0)$ (c) $F(4)$

Finding the Area of a Figure **In Exercises 57–60, use integration to find the area of the figure having the given vertices.**

57. $(-1, -1), (1, 1), (2, -1)$

58. $(0, 0), (6, 0), (4, 3)$

59. $(0, 2), (4, 2), (0, -2), (-4, -2)$

60. $(0, 0), (1, 2), (3, -2), (1, -3)$

Using a Tangent Line **In Exercises 61–64, write and evaluate the definite integral that represents the area of the region bounded by the graph of the function and the tangent line to the graph at the given point.**

61. $f(x) = 2x^3 - 1, \quad (1, 1)$

62. $f(x) = x - x^3, \quad (-1, 0)$

63. $f(x) = \dfrac{1}{x^2 + 1}, \quad \left(1, \dfrac{1}{2}\right)$

64. $y = \dfrac{2}{1 + 4x^2}, \quad \left(\dfrac{1}{2}, 1\right)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploring Concepts

65. The graphs of $y = 1 - x^2$ and $y = x^4 - 2x^2 + 1$ intersect at three points. However, the area between the curves *can* be found by a single integral. Explain why this is so, and write an integral that represents this area. (Do not integrate.)

66. The area of the region bounded by the graphs of $y = x^3$ and $y = x$ *cannot* be found by the single integral $\int_{-1}^{1} (x^3 - x)\,dx$. Explain why this is so. Use symmetry to write a single integral that does represent the area. (Do not integrate.)

67. Two cars with velocities $v_1(t)$ and $v_2(t)$ (in meters per second) are tested on a straight track. Consider the following integrals.

$$\int_0^5 [v_1(t) - v_2(t)]\,dt = 10 \qquad \int_0^{10} [v_1(t) - v_2(t)]\,dt = 30$$

$$\int_{20}^{30} [v_1(t) - v_2(t)]\,dt = -5$$

(a) Write a verbal interpretation of each integral.

(b) Determine whether it is possible to find the distance between the two cars when $t = 5$ seconds. Explain.

(c) Assume both cars start at the same time and place. Which car is ahead when $t = 10$ seconds? How far ahead is the car?

(d) Suppose Car 1 has velocity v_1 and is ahead of Car 2 by 13 meters when $t = 20$ seconds. How far ahead or behind is Car 1 when $t = 30$ seconds?

68. **HOW DO YOU SEE IT?** A state legislature is debating two proposals for eliminating the annual budget deficits after 10 years. The figure shows the rate of decrease of the deficits for each proposal.



(a) What does the area between the two curves represent?

(b) From the viewpoint of minimizing the cumulative state deficit, which is the better proposal? Explain.

Dividing a Region **In Exercises 69 and 70, find b such that the line $y = b$ divides the region bounded by the graphs of the equations into two regions of equal area.**

69. $y = 9 - x^2, \quad y = 0$

70. $y = 9 - |x|, \quad y = 0$

Dividing a Region **In Exercises 71 and 72, find a such that the line $x = a$ divides the region bounded by the graphs of the equations into two regions of equal area.**

71. $y = x, \quad y = 4, \quad x = 0$

72. $y^2 = 4 - x, \quad x = 0$

Limits and Integrals **In Exercises 73 and 74, evaluate the limit and sketch the graph of the region whose area is represented by the limit.**

73. $\lim_{\|\Delta\| \to 0} \sum_{i=1}^{n} (x_i - x_i^2)\Delta x$, where $x_i = \frac{i}{n}$ and $\Delta x = \frac{1}{n}$

74. $\lim_{\|\Delta\| \to 0} \sum_{i=1}^{n} (4 - x_i^2)\Delta x$, where $x_i = -2 + \frac{4i}{n}$ and $\Delta x = \frac{4}{n}$

Revenue **In Exercises 75 and 76, two models R_1 and R_2 are given for revenue (in millions of dollars) for a corporation. Both models are estimates of revenues from 2030 through 2035, with $t = 0$ corresponding to 2030. Which model projects the greater revenue? How much more total revenue does that model project over the six-year period?**

75. $R_1 = 7.21 + 0.58t$

$R_2 = 7.21 + 0.45t$

76. $R_1 = 7.21 + 0.26t + 0.02t^2$

$R_2 = 7.21 + 0.1t + 0.01t^2$

77. **Lorenz Curve** Economists use *Lorenz curves* to illustrate the distribution of income in a country. A Lorenz curve, $y = f(x)$, represents the actual income distribution in the country. In this model, x represents percents of families in the country from the poorest to the wealthiest and y represents percents of total income. The model $y = x$ represents a country in which each family has the same income. The area between these two models, where $0 \le x \le 100$, indicates a country's "income inequality." The table lists percents of income y for selected percents of families x in a country.

x	10	20	30	40	50
y	3.35	6.07	9.17	13.39	19.45

x	60	70	80	90
y	28.03	39.77	55.28	75.12

(a) Use a graphing utility to find a quadratic model for the Lorenz curve.

(b) Plot the data and graph the model.

(c) Graph the model $y = x$. How does this model compare with the model in part (a)?

(d) Use the integration capabilities of a graphing utility to approximate the "income inequality."

78. **Profit** The chief financial officer of a company reports that profits for the past fiscal year were \$15.9 million. The officer predicts that profits for the next 5 years will grow at a continuous annual rate somewhere between $3\frac{1}{2}\%$ and 5%. Estimate the cumulative difference in total profit over the 5 years based on the predicted range of growth rates.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

79. Building Design

Concrete sections for a new building have the dimensions (in meters) and shape shown in the figure.



(a) Find the area of the face of the section superimposed on the rectangular coordinate system.

(b) Find the volume of concrete in one of the sections by multiplying the area in part (a) by 2 meters.

(c) One cubic meter of concrete weighs 5000 pounds. Find the weight of the section.

80. Mechanical Design The surface of a machine part is the region between the graphs of $y_1 = |x|$ and $y_2 = 0.08x^2 + k$ (see figure).



(a) Find k such that the parabola is tangent to the graph of y_1.

(b) Find the area of the surface of the machine part.

81. Area Find the area between the graph of $y = \sin x$ and the line segment joining the points $(0, 0)$ and $\left(\frac{7\pi}{6}, -\frac{1}{2}\right)$, as shown in the figure.



82. Area Let $a > 0$ and $b > 0$. Show that the area of the ellipse $\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$ is πab (see figure).



True or False? **In Exercises 83–86, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

83. If the area of the region bounded by the graphs of f and g is 1, then the area of the region bounded by the graphs of $h(x) = f(x) + C$ and $k(x) = g(x) + C$ is also 1.

84. If

$$\int_a^b [f(x) - g(x)]\,dx = A$$

then

$$\int_a^b [g(x) - f(x)]\,dx = -A.$$

85. If the graphs of f and g intersect midway between $x = a$ and $x = b$, then

$$\int_a^b [f(x) - g(x)]\,dx = 0.$$

86. The line

$$y = \left(1 - \sqrt[3]{0.5}\right)x$$

divides the region under the curve

$$f(x) = x(1 - x)$$

on $[0, 1]$ into two regions of equal area.

PUTNAM EXAM CHALLENGE

87. The horizontal line $y = c$ intersects the curve $y = 2x - 3x^3$ in the first quadrant as shown in the figure. Find c so that the areas of the two shaded regions are equal.



This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

synel/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

7.2 Volume: The Disk Method

GO DIGITAL

- **Find the volume of a solid of revolution using the disk method.**
- **Find the volume of a solid of revolution using the washer method.**
- **Find the volume of a solid with known cross sections.**

The Disk Method

You have already learned that area is only one of the *many* applications of the definite integral. Another important application is its use in finding the volume of a three-dimensional solid. In this section, you will study a particular type of three-dimensional solid—one whose cross sections are similar. Solids of revolution are used commonly in engineering and manufacturing. Some examples are axles, funnels, pills, bottles, and pistons, as shown in Figure 7.12.



Solids of revolution
Figure 7.12





Volume of a disk: $\pi R^2 w$
Figure 7.13

When a region in the plane is revolved about a line, the resulting solid is a **solid of revolution,** and the line is called the **axis of revolution.** The simplest such solid is a right circular cylinder or **disk,** which is formed by revolving a rectangle about an axis adjacent to one side of the rectangle, as shown in Figure 7.13. The volume of such a disk is

$$\begin{aligned}\text{Volume of disk} &= (\text{area of disk})(\text{width of disk}) \\ &= \pi R^2 w\end{aligned}$$

where R is the radius of the disk and w is the width.

To use the volume of a disk to find the volume of a general solid of revolution, consider a solid of revolution formed by revolving the plane region in Figure 7.14 (see next page) about the indicated axis. To determine the volume of this solid, consider a representative rectangle in the plane region. When this rectangle is revolved about the axis of revolution, it generates a representative disk whose volume is

$$\Delta V = \pi R^2 \Delta x.$$

Approximating the volume of the solid by n such disks of width Δx and radius $R(x_i)$ produces

$$\begin{aligned}\text{Volume of solid} &\approx \sum_{i=1}^{n} \pi[R(x_i)]^2 \Delta x \\ &= \pi \sum_{i=1}^{n} [R(x_i)]^2 \Delta x.\end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Disk method
Figure 7.14

This approximation appears to become better and better as $\|\Delta\| \to 0$ $(n \to \infty)$. So, you can define the volume of the solid as

$$\text{Volume of solid} = \lim_{\|\Delta\|\to 0} \pi \sum_{i=1}^{n} [R(x_i)]^2 \, \Delta x = \pi \int_a^b [R(x)]^2 \, dx.$$

Schematically, the disk method looks like this.

Known Precalculus Formula		**Representative Element**		**New Integration Formula**
Volume of disk $V = \pi R^2 w$	⇨	$\Delta V = \pi[R(x_i)]^2 \Delta x$	⇨	Solid of revolution $V = \pi \int_a^b [R(x)]^2 \, dx$

A similar formula can be derived when the axis of revolution is vertical.

The Disk Method

To find the volume of a solid of revolution with the **disk method,** use one of the formulas below. (See Figure 7.15.)

Horizontal Axis of Revolution

$$\text{Volume} = V = \pi \int_a^b [R(x)]^2 \, dx$$

Vertical Axis of Revolution

$$\text{Volume} = V = \pi \int_c^d [R(y)]^2 \, dy$$

REMARK In Figure 7.15, note that you can determine the variable of integration by placing a representative rectangle in the plane region "perpendicular" to the axis of revolution. When the width of the rectangle is Δx, integrate with respect to x, and when the width of the rectangle is Δy, integrate with respect to y.



Horizontal axis of revolution
Vertical axis of revolution
Figure 7.15

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The simplest application of the disk method involves a plane region bounded by the graph of f and the x-axis. When the axis of revolution is the x-axis, the radius $R(x)$ is simply $f(x)$.

EXAMPLE 1 Using the Disk Method

Find the volume of the solid formed by revolving the region bounded by the graph of $f(x) = \sqrt{\sin x}$ and the x-axis $(0 \le x \le \pi)$ about the x-axis, as shown in Figure 7.16.

Solution From the representative rectangle in the upper graph in Figure 7.16, you can see that the radius of this solid is $R(x) = f(x) = \sqrt{\sin x}$. The volume of the solid of revolution is

$$
\begin{aligned}
V &= \pi \int_a^b [R(x)]^2 \, dx && \text{Apply disk method.} \\
&= \pi \int_0^\pi \left(\sqrt{\sin x}\right)^2 dx && \text{Substitute } \sqrt{\sin x} \text{ for } R(x). \\
&= \pi \int_0^\pi \sin x \, dx && \text{Simplify.} \\
&= \pi \Big[-\cos x \Big]_0^\pi && \text{Integrate.} \\
&= \pi(1 + 1) && \text{Apply Fundamental Theorem of Calculus.} \\
&= 2\pi. && \text{Simplify.}
\end{aligned}
$$



Figure 7.16

Note in Example 1 that the problem was solved *without* referring to the three-dimensional sketch in Figure 7.16. In general, to set up an integral to find the volume of a solid of revolution, a sketch of the plane region is more useful than a sketch of the solid because the radius is more readily visualized in the plane region.

EXAMPLE 2 Using a Line That Is Not a Coordinate Axis

Find the volume of the solid formed by revolving the region bounded by the graphs of $f(x) = 2 - x^2$ and $g(x) = 1$ about the line $y = 1$, as shown in Figure 7.17.

Solution By equating $f(x)$ and $g(x)$, you can determine that the two graphs intersect when $x = \pm 1$. To find the radius, subtract $g(x)$ from $f(x)$.

$$
\begin{aligned}
R(x) &= f(x) - g(x) \\
&= (2 - x^2) - 1 \\
&= 1 - x^2
\end{aligned}
$$

To find the volume, integrate between -1 and 1.

$$
\begin{aligned}
V &= \pi \int_a^b [R(x)]^2 \, dx && \text{Apply disk method.} \\
&= \pi \int_{-1}^1 (1 - x^2)^2 \, dx && \text{Substitute } 1 - x^2 \text{ for } R(x). \\
&= \pi \int_{-1}^1 (1 - 2x^2 + x^4) \, dx && \text{Simplify.} \\
&= \pi \left[x - \frac{2x^3}{3} + \frac{x^5}{5} \right]_{-1}^1 && \text{Integrate.} \\
&= \frac{16\pi}{15}
\end{aligned}
$$



Figure 7.17

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 7.18

GO DIGITAL

The Washer Method

The disk method can be extended to cover solids of revolution with holes by replacing the representative disk with a representative **washer.** The washer is formed by revolving a rectangle about an axis, as shown in Figure 7.18. If r and R are the inner and outer radii of the washer, respectively, and w is the width of the washer, then the volume is

$$\text{Volume of washer} = \pi(R^2 - r^2)w.$$

To use this concept to find the volume of a solid of revolution, consider a region bounded by an **outer radius** $R(x)$ and an **inner radius** $r(x)$, as shown in Figure 7.19. If the region is revolved about its axis of revolution, then the volume of the resulting solid is

$$V = \pi \int_a^b \left([R(x)]^2 - [r(x)]^2\right) dx. \qquad \text{Washer method}$$

Note that the integral involving the inner radius represents the volume of the hole and is *subtracted* from the integral involving the outer radius.



Figure 7.19



Solid of revolution

Figure 7.20

EXAMPLE 3 Using the Washer Method

Find the volume of the solid formed by revolving the region bounded by the graphs of

$$y = \sqrt{x} \quad \text{and} \quad y = x^2$$

about the x-axis, as shown in Figure 7.20.

Solution The upper graph in Figure 7.20 shows that the two curves intersect when $x = 0$ and $x = 1$. Also, notice that the outer and inner radii are

$$R(x) = \sqrt{x} \quad \text{and} \quad r(x) = x^2$$

respectively. Integrating between 0 and 1 produces

$$V = \pi \int_a^b \left([R(x)]^2 - [r(x)]^2\right) dx \qquad \text{Apply washer method.}$$

$$= \pi \int_0^1 \left[\left(\sqrt{x}\right)^2 - (x^2)^2\right] dx \qquad \text{Substitute } \sqrt{x} \text{ for } R(x) \text{ and } x^2 \text{ for } r(x).$$

$$= \pi \int_0^1 (x - x^4)\, dx \qquad \text{Simplify.}$$

$$= \pi \left[\frac{x^2}{2} - \frac{x^5}{5}\right]_0^1 \qquad \text{Integrate.}$$

$$= \frac{3\pi}{10}.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

In each example so far, the axis of revolution has been *horizontal* and you have integrated with respect to x. In the next example, the axis of revolution is *vertical* and you integrate with respect to y. In this example, you need two separate integrals to compute the volume.

EXAMPLE 4 Integrating with Respect to y: Two-Integral Case

Find the volume of the solid formed by revolving the region bounded by the graphs of

$$y = x^2 + 1, \quad y = 0, \quad x = 0, \quad \text{and} \quad x = 1$$

about the y-axis, as shown in Figure 7.21.



Figure 7.21

Solution For the region shown in Figure 7.21, the outer radius is simply $R = 1$. There is, however, no convenient formula that represents the inner radius. When $0 \le y \le 1$, $r = 0$, but when $1 \le y \le 2$, r is determined by the equation $y = x^2 + 1$, which implies that $r = \sqrt{y - 1}$.

$$r(y) = \begin{cases} 0, & 0 \le y \le 1 \\ \sqrt{y - 1}, & 1 \le y \le 2 \end{cases}$$

Using this definition of the inner radius, you can use two integrals to find the volume.

$$\begin{aligned} V &= \pi \int_0^1 (1^2 - 0^2)\, dy + \pi \int_1^2 \left[1^2 - \left(\sqrt{y - 1}\right)^2\right] dy && \text{Apply washer method.} \\ &= \pi \int_0^1 1\, dy + \pi \int_1^2 (2 - y)\, dy && \text{Simplify.} \\ &= \pi \Big[y\Big]_0^1 + \pi \Big[2y - \frac{y^2}{2}\Big]_1^2 && \text{Integrate.} \\ &= \pi + \pi\left(4 - 2 - 2 + \frac{1}{2}\right) \\ &= \frac{3\pi}{2} \end{aligned}$$

Note that the first integral $\pi \int_0^1 1\, dy$ represents the volume of a right circular cylinder of radius 1 and height 1. This portion of the volume could have been determined without using calculus. ■



Generated by Mathematica

Figure 7.22

TECHNOLOGY Some graphing utilities can generate a solid of revolution. If you have access to such a utility, use it to graph some of the solids of revolution described in this section. For instance, the solid in Example 4 might appear like that shown in Figure 7.22.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Solid of revolution

(a)



Plane region

(b)

Figure 7.23

EXAMPLE 5 Manufacturing

See LarsonCalculus.com for an interactive version of this type of example.

A manufacturer drills a hole through the center of a metal sphere of radius 5 inches, as shown in Figure 7.23(a). The hole has a radius of 3 inches. What is the volume of the resulting metal ring?

Solution The ring is generated by a segment of the circle whose equation is $x^2 + y^2 = 25$, as shown in Figure 7.23(b). Because the radius of the hole is 3 inches, let $y = 3$ and solve the equation $x^2 + y^2 = 25$ to determine that the limits of integration are $x = \pm 4$. So, the inner and outer radii are $r(x) = 3$ and $R(x) = \sqrt{25 - x^2}$, and the volume is

$$V = \pi \int_a^b \left([R(x)]^2 - [r(x)]^2 \right) dx \qquad \text{Apply washer method.}$$

$$= \pi \int_{-4}^{4} \left[\left(\sqrt{25 - x^2} \right)^2 - (3)^2 \right] dx \qquad \text{Substitute } \sqrt{25 - x^2} \text{ for } R(x) \text{ and 3 for } r(x).$$

$$= \pi \int_{-4}^{4} (16 - x^2)\, dx \qquad \text{Simplify.}$$

$$= \pi \left[16x - \frac{x^3}{3} \right]_{-4}^{4} \qquad \text{Integrate.}$$

$$= \frac{256\pi}{3} \text{ cubic inches.} \qquad \text{Volume of metal ring}$$

Solids with Known Cross Sections

With the disk method, you can find the volume of a solid having a circular cross section whose area is $A = \pi R^2$. This method can be generalized to solids of any shape, as long as you know a formula for the area of an arbitrary cross section. Some common cross sections are squares, rectangles, triangles, semicircles, and trapezoids.

BONAVENTURA CAVALIERI (1598–1647)

Cavalieri made many contributions to trigonometry, geometry, optics, and astronomy. He discovered that if two solids have equal altitudes and all cross sections parallel to their bases and at equal distances from their bases have equal areas, then the solids have the same volume. (See Exercise 72.)

See LarsonCalculus.com to read more of this biography.

Volumes of Solids with Known Cross Sections

1. For cross sections of area $A(x)$ taken perpendicular to the x-axis,

$$\text{Volume} = \int_a^b A(x)\, dx. \qquad \text{See Figure 7.24(a).}$$

2. For cross sections of area $A(y)$ taken perpendicular to the y-axis,

$$\text{Volume} = \int_c^d A(y)\, dy. \qquad \text{See Figure 7.24(b).}$$



(a) Cross sections perpendicular to x-axis



(b) Cross sections perpendicular to y-axis

Figure 7.24

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Cross sections are equilateral triangles.



Triangular base in xy-plane

Figure 7.25

EXAMPLE 6 Triangular Cross Sections

Find the volume of the solid shown in Figure 7.25. The base of the solid is the region bounded by the lines

$$f(x) = 1 - \frac{x}{2}, \quad g(x) = -1 + \frac{x}{2}, \quad \text{and} \quad x = 0.$$

The cross sections perpendicular to the x-axis are equilateral triangles.

Solution The base and area of each triangular cross section are as follows.

$$\text{Base} = \left(1 - \frac{x}{2}\right) - \left(-1 + \frac{x}{2}\right) = 2 - x \qquad \text{Length of base}$$

$$\text{Area} = \frac{\sqrt{3}}{4}(\text{base})^2 \qquad \text{Area of equilateral triangle}$$

$$A(x) = \frac{\sqrt{3}}{4}(2 - x)^2 \qquad \text{Area of cross section}$$

Because x ranges from 0 to 2, the volume of the solid is

$$V = \int_a^b A(x)\,dx = \int_0^2 \frac{\sqrt{3}}{4}(2 - x)^2\,dx = -\frac{\sqrt{3}}{4}\left[\frac{(2 - x)^3}{3}\right]_0^2 = \frac{2\sqrt{3}}{3}.$$

EXAMPLE 7 An Application to Geometry

Prove that the volume of a pyramid with a square base is

$$V = \frac{1}{3}hB$$

where h is the height of the pyramid and B is the area of the base.

Solution As shown in Figure 7.26, you can intersect the pyramid with a plane parallel to the base at height y to form a square cross section whose sides are of length b'. Using similar triangles, you can show that

$$\frac{b'}{b} = \frac{h - y}{h} \quad \text{or} \quad b' = \frac{b}{h}(h - y)$$

where b is the length of the sides of the base of the pyramid. So,

$$A(y) = (b')^2 = \frac{b^2}{h^2}(h - y)^2.$$

Integrating between 0 and h produces

$$V = \int_0^h A(y)\,dy \qquad \text{Cross sections perpendicular to } y\text{-axis}$$

$$= \int_0^h \frac{b^2}{h^2}(h - y)^2\,dy \qquad \text{Substitute.}$$

$$= \frac{b^2}{h^2}\int_0^h (h - y)^2\,dy \qquad \text{Constant Multiple Rule}$$

$$= -\left(\frac{b^2}{h^2}\right)\left[\frac{(h - y)^3}{3}\right]_0^h \qquad \text{Integrate.}$$

$$= \frac{b^2}{h^2}\left(\frac{h^3}{3}\right)$$

$$= \frac{1}{3}hB. \qquad B = b^2$$





Figure 7.26

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

7.2 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain how to use the disk method to find the volume of a solid of revolution.
2. Explain the relationship between the disk method and the washer method.
3. Describe when it is necessary to use more than one integral to find the volume of a solid of revolution.
4. Explain how to find the volume of a solid with a known cross section.

Finding the Volume of a Solid In Exercises 5–8, write and evaluate the definite integral that represents the volume of the solid formed by revolving the region about the x-axis.

5. $y = \sqrt{x}$



6. $y = -x + 1$



7. $y = x^2, \quad y = x^5$



8. $y = 2, \quad y = 4 - \frac{x^2}{4}$



Finding the Volume of a Solid In Exercises 9–12, write and evaluate the definite integral that represents the volume of the solid formed by revolving the region about the y-axis.

9. $y = x^2$



10. $y = \sqrt{16 - x^2}$



11. $y = x^{2/3}$



12. $x = -y^2 + 4y$



Finding the Volume of a Solid In Exercises 13–16, find the volumes of the solids generated by revolving the region bounded by the graphs of the equations about the given lines.

13. $y = \sqrt{x}, \quad y = 0, \quad x = 3$

(a) x-axis (b) y-axis

(c) $x = 3$ (d) $x = 6$

14. $y = 2x^2, \quad y = 0, \quad x = 2$

(a) y-axis

(b) x-axis

(c) $y = 8$

(d) $x = 2$

15. $y = x^2, \quad y = 4x - x^2$

(a) x-axis

(b) $y = 6$

16. $y = 4 + 2x - x^2, \quad y = 4 - x$

(a) x-axis

(b) $y = 1$

Finding the Volume of a Solid In Exercises 17–20, find the volume of the solid generated by revolving the region bounded by the graphs of the equations about the line $y = 4$.

17. $y = x, \quad y = 3, \quad x = 0$

18. $y = \frac{1}{2}x^3, \quad y = 4, \quad x = 0$

19. $y = \dfrac{2}{1 + x}, \quad y = 0, \quad x = 0, \quad x = 4$

20. $y = \sqrt{1 - x}, \quad x = 0, \quad y = 0$

Finding the Volume of a Solid In Exercises 21–24, find the volume of the solid generated by revolving the region bounded by the graphs of the equations about the line $x = 5$.

21. $y = x, \quad y = 0, \quad y = 4, \quad x = 5$

22. $y = 2 - \dfrac{x}{2}, \quad y = 0, \quad y = 1, \quad x = 0$

23. $x = y^2, \quad x = 4$

24. $xy = 3, \quad y = 1, \quad y = 4, \quad x = 5$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding the Volume of a Solid **In Exercises 25–32, find the volume of the solid generated by revolving the region bounded by the graphs of the equations about the x-axis.**

25. $y = \dfrac{1}{\sqrt{3x + 5}}, \quad y = 0, \quad x = 0, \quad x = 2$

26. $y = x\sqrt{4 - x^2}, \quad y = 0$

27. $y = \dfrac{6}{x}, \quad y = 0, \quad x = 1, \quad x = 3$

28. $y = \dfrac{2}{x + 1}, \quad y = 0, \quad x = 0, \quad x = 6$

29. $y = e^{-3x}, \quad y = 0, \quad x = 0, \quad x = 2$

30. $y = e^{x/4}, \quad y = 0, \quad x = 0, \quad x = 6$

31. $y = x^2 + 1, \quad y = -x^2 + 2x + 5, \quad x = 0, \quad x = 3$

32. $y = \sqrt{x}, \quad y = -\frac{1}{2}x + 4, \quad x = 0, \quad x = 8$

Finding the Volume of a Solid **In Exercises 33–36, find the volume of the solid generated by revolving the region bounded by the graphs of the equations about the y-axis.**

33. $y = 3(2 - x), \quad y = 0, \quad x = 0$

34. $y = \sqrt{3x - 2}, \quad x = 0, \quad y = 0, \quad y = 1$

35. $y = 9 - x^2, \quad y = 0, \quad x = 2, \quad x = 3$

36. $y = \dfrac{x^3}{8}, \quad y = 0, \quad x = 4$

Finding the Volume of a Solid **In Exercises 37–40, find the volume of the solid generated by revolving the region bounded by the graphs of the equations about the x-axis. Verify your results using the integration capabilities of a graphing utility.**

37. $y = \sin x, \quad y = 0, \quad x = 0, \quad x = \pi$

38. $y = \cos 2x, \quad y = 0, \quad x = 0, \quad x = \dfrac{\pi}{4}$

39. $y = e^{x-1}, \quad y = 0, \quad x = 1, \quad x = 2$

40. $y = e^{x/2} + e^{-x/2}, \quad y = 0, \quad x = -1, \quad x = 2$

Finding the Volume of a Solid **In Exercises 41–48, find the volume of the solid generated by revolving the specified region about the given line.**



41. R_1 about $y = 0$

42. R_1 about $x = 1$

43. R_1 about $x = 0$

44. R_2 about $y = 1$

45. R_2 about $y = 0$

46. R_3 about $x = 1$

47. R_3 about $x = 0$

48. R_3 about $y = 1$

Finding the Volume of a Solid Using Technology **In Exercises 49–52, use the integration capabilities of a graphing utility to approximate the volume of the solid generated by revolving the region bounded by the graphs of the equations about the x-axis.**

49. $y = e^{-x^2}, \quad y = 0, \quad x = 0, \quad x = 2$

50. $y = \ln x, \quad y = 0, \quad x = 1, \quad x = 3$

51. $y = 2 \arctan(0.2x), \quad y = 0, \quad x = 0, \quad x = 5$

52. $y = \sqrt{2x}, \quad y = x^2$

Exploring Concepts

53. Each integral represents the volume of a solid. Describe each solid.

(a) $\pi \displaystyle\int_0^{\pi/2} \sin^2 x \, dx$ (b) $\pi \displaystyle\int_2^4 y^4 \, dy$

54. A region bounded by the parabola $y = 4x - x^2$ and the x-axis is revolved about the x-axis. A second region bounded by the parabola $y = 4 - x^2$ and the x-axis is revolved about the x-axis. Without integrating, how do the volumes of the two solids compare? Explain.

55. Comparing Volumes The region in the figure is revolved about the indicated axes and line. Order the volumes of the resulting solids from least to greatest. Explain your reasoning.



(a) x-axis

(b) y-axis

(c) $x = 3$

56. HOW DO YOU SEE IT? Use the graph to match the integral for the volume with the axis of rotation.



(a) $V = \pi \displaystyle\int_0^b (a^2 - [f(y)]^2) \, dy$ (i) x-axis

(b) $V = \pi \displaystyle\int_0^a (b^2 - [b - f(x)]^2) \, dx$ (ii) y-axis

(c) $V = \pi \displaystyle\int_0^a [f(x)]^2 \, dx$ (iii) $x = a$

(d) $V = \pi \displaystyle\int_0^b [a - f(y)]^2 \, dy$ (iv) $y = b$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Dividing a Solid **In Exercises 57 and 58, consider the solid formed by revolving the region bounded by $y = \sqrt{x}$, $y = 0$, $x = 1$, and $x = 3$ about the x-axis.**

57. Find the value of x in the interval $[1, 3]$ that divides the solid into two parts of equal volume.

58. Find the values of x in the interval $[1, 3]$ that divide the solid into three parts of equal volume.

59. Manufacturing A manufacturer drills a hole through the center of a metal sphere of radius R. The hole has a radius r. Find the volume of the resulting ring.

60. Manufacturing For the metal sphere in Exercise 59, let $R = 6$. What value of r will produce a ring whose volume is exactly half the volume of the sphere?

61. Volume of a Cone Use the disk method to verify that the volume of a right circular cone is $\frac{1}{3}\pi r^2 h$, where r is the radius of the base and h is the height.

62. Volume of a Sphere Use the disk method to verify that the volume of a sphere is $\frac{4}{3}\pi r^3$, where r is the radius.

63. Using a Cone A cone of height H with a base of radius r is cut by a plane parallel to and h units above the base, where $h < H$. Find the volume of the solid (frustum of a cone) below the plane.

64. Using a Sphere A sphere of radius r is cut by a plane h units above the equator, where $h < r$. Find the volume of the solid (spherical segment) above the plane.

65. Volume of a Fuel Tank A tank on the wing of a jet aircraft is formed by revolving the region bounded by the graph of $y = \frac{1}{4}x^2\sqrt{2 - x}$ and the x-axis $(0 \le x \le 2)$ about the x-axis, where x and y are measured in meters. Use a graphing utility to graph the function. Find the volume of the tank analytically.

66. Volume of a Container A container can be modeled by revolving the graph of

$$y = \begin{cases} \sqrt{0.1x^3 - 2.2x^2 + 10.9x + 22.2}, & 0 \le x \le 11.5 \\ 2.95, & 11.5 < x \le 15 \end{cases}$$

about the x-axis, where x and y are measured in centimeters. Use a graphing utility to graph the function. Find the volume of the container analytically.

67. Finding Volumes of Solids Find the volumes of the solids (see figures) generated if the upper half of the ellipse $9x^2 + 25y^2 = 225$ is revolved about (a) the x-axis to form a prolate spheroid (shaped like a football) and (b) the y-axis to form an oblate spheroid (shaped like half of a candy).



Figure for 67(a)



Figure for 67(b)

68. 3D Printing

A 3D printer is used to create a plastic drinking glass. The equations given to the printer for the inside of the glass are

$$x = \left(\frac{y}{4}\right)^{1/32} \quad \text{and} \quad y = 5$$

where x and y are measured in inches. What is the total volume that the drinking glass can hold when the region bounded by the graphs of the equations is revolved about the y-axis?

69. Minimum Volume The function $y = 4 - (x^2/4)$ on the interval $[0, 4]$ is revolved about the line $y = b$ (see figure).

(a) Find the volume of the resulting solid as a function of b.

(b) Use a graphing utility to graph the function in part (a), and use the graph to approximate the value of b that minimizes the volume of the solid.

(c) Use calculus to find the value of b that minimizes the volume of the solid, and compare the result with the answer to part (b).



Figure for 69

Figure for 70

70. Modeling Data A draftsman is asked to determine the amount of material required to produce a machine part (see figure). The diameters d of the part at equally spaced points x are listed in the table. The measurements are listed in centimeters.

x	0	1	2	3	4	5
d	4.2	3.8	4.2	4.7	5.2	5.7

x	6	7	8	9	10
d	5.8	5.4	4.9	4.4	4.6

(a) Use the regression capabilities of a graphing utility to find a fourth-degree polynomial through the points representing the radius of the machine part. Plot the data and graph the model.

(b) Use the integration capabilities of a graphing utility to approximate the volume of the machine part.

guteksk7/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

71. Think About It Match each integral with the solid whose volume it represents, and give the dimensions of each solid.

(a) Right circular cylinder (b) Ellipsoid

(c) Sphere (d) Right circular cone (e) Torus

(i) $\pi \int_0^h \left(\frac{rx}{h}\right)^2 dx$ (ii) $\pi \int_0^h r^2\, dx$

(iii) $\pi \int_{-r}^{r} \left(\sqrt{r^2 - x^2}\right)^2 dx$

(iv) $\pi \int_{-b}^{b} \left(a\sqrt{1 - \frac{x^2}{b^2}}\right)^2 dx$

(v) $\pi \int_{-r}^{r} \left[\left(R + \sqrt{r^2 - x^2}\right)^2 - \left(R - \sqrt{r^2 - x^2}\right)^2\right] dx$

72. Cavalieri's Theorem Prove that if two solids have equal altitudes and all cross sections parallel to their bases and at equal distances from their bases have equal areas, then the solids have the same volume (see figure).



Area of R_1 = area of R_2

73. Using Cross Sections Find the volumes of the solids whose bases are bounded by the graphs of $y = x + 1$ and $y = x^2 - 1$, with the indicated cross sections taken perpendicular to the x-axis.

(a) Squares (b) Rectangles of height 1





74. Using Cross Sections Find the volumes of the solids whose bases are bounded by the circle $x^2 + y^2 = 4$, with the indicated cross sections taken perpendicular to the x-axis.

(a) Squares (b) Equilateral triangles





(c) Semicircles (d) Isosceles right triangles



75. Using Cross Sections Find the volume of the solid of intersection (the solid common to both) of the two right circular cylinders of radius r whose axes meet at right angles (see figure).



Two intersecting cylinders

Solid of intersection

FOR FURTHER INFORMATION For more information on this problem, see the article "Estimating the Volumes of Solid Figures with Curved Surfaces" by Donald Cohen in *Mathematics Teacher*. To view this article, go to *MathArticles.com*.

76. Using Cross Sections The solid shown in the figure has cross sections bounded by the graph of $|x|^a + |y|^a = 1$, where $1 \le a \le 2$.

(a) Describe the cross section when $a = 1$ and $a = 2$.

(b) Describe a procedure for approximating the volume of the solid.



77. Volume of a Wedge Two planes cut a right circular cylinder to form a wedge. One plane is perpendicular to the axis of the cylinder and the second makes an angle of θ degrees with the first (see figure).

(a) Find the volume of the wedge if $\theta = 45°$.

(b) Find the volume of the wedge for an arbitrary angle θ. Assuming that the cylinder has sufficient length, how does the volume of the wedge change as θ increases from 0° to 90°?



Figure for 77



Figure for 78

78. Volume of a Torus

(a) Show that the volume of the torus shown in the figure is given by the integral $8\pi R \int_0^r \sqrt{r^2 - y^2}\, dy$, where $R > r > 0$.

(b) Find the volume of the torus.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

7.3 Volume: The Shell Method

GO DIGITAL

- **Find the volume of a solid of revolution using the shell method.**
- **Compare the uses of the disk method and the shell method.**

The Shell Method

In this section, you will study an alternative method for finding the volume of a solid of revolution. This method is called the **shell method** because it uses cylindrical shells. A comparison of the advantages of the disk and shell methods is given later in this section.

To begin, consider a representative rectangle as shown in Figure 7.27, where w is the width of the rectangle, h is the height of the rectangle, and p is the distance between the axis of revolution and the *center* of the rectangle. When this rectangle is revolved about its axis of revolution, it forms a cylindrical shell (or tube) of thickness w. To find the volume of this shell, consider two cylinders. The radius of the larger cylinder corresponds to the outer radius of the shell, and the radius of the smaller cylinder corresponds to the inner radius of the shell. Because p is the average radius of the shell, you know the outer radius is



Figure 7.27

$$p + \frac{w}{2}$$ Outer radius

and the inner radius is

$$p - \frac{w}{2}.$$ Inner radius

So, the volume of the shell is

$$\begin{aligned}\text{Volume of shell} &= (\text{volume of cylinder}) - (\text{volume of hole})\\ &= \pi\left(p + \frac{w}{2}\right)^2 h - \pi\left(p - \frac{w}{2}\right)^2 h\\ &= 2\pi phw\\ &= 2\pi(\text{average radius})(\text{height})(\text{thickness}).\end{aligned}$$

You can use this formula to find the volume of a solid of revolution. For instance, the plane region in Figure 7.28 is revolved about a line to form the indicated solid. Consider a horizontal rectangle of width Δy. As the plane region is revolved about a line parallel to the x-axis, the rectangle generates a representative shell whose volume is





Figure 7.28

$$\Delta V = 2\pi[p(y)h(y)]\Delta y.$$

You can approximate the volume of the solid by n such shells of thickness Δy, height $h(y_i)$, and average radius $p(y_i)$.

$$\text{Volume of solid} \approx \sum_{i=1}^{n} 2\pi[p(y_i)h(y_i)]\Delta y = 2\pi\sum_{i=1}^{n}[p(y_i)h(y_i)]\Delta y$$

This approximation appears to become better and better as $\|\Delta\| \to 0$ $(n \to \infty)$. So, the volume of the solid is

$$\begin{aligned}\text{Volume of solid} &= \lim_{\|\Delta\|\to 0} 2\pi\sum_{i=1}^{n}[p(y_i)h(y_i)]\Delta y\\ &= 2\pi\int_c^d [p(y)h(y)]\,dy.\end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The Shell Method

To find the volume of a solid of revolution with the **shell method,** use one of the formulas below. (See Figure 7.29.)

Horizontal Axis of Revolution

$$\text{Volume} = V = 2\pi \int_c^d p(y)h(y)\,dy$$

Vertical Axis of Revolution

$$\text{Volume} = V = 2\pi \int_a^b p(x)h(x)\,dx$$



Horizontal axis of revolution



Vertical axis of revolution

Figure 7.29

REMARK Be sure you understand that with the shell method, the representative rectangle is *parallel* to the axis of revolution.

EXAMPLE 1 Using the Shell Method to Find Volume

Find the volume of the solid formed by revolving the region bounded by

$$y = x - x^3$$

and the x-axis $(0 \le x \le 1)$ about the y-axis.

Solution Because the axis of revolution is vertical, use a vertical representative rectangle, as shown in Figure 7.30. The width Δx indicates that x is the variable of integration. The distance from the center of the rectangle to the axis of revolution is $p(x) = x$, and the height of the rectangle is

$$h(x) = x - x^3.$$

Because x ranges from 0 to 1, apply the shell method to find the volume of the solid.



Figure 7.30

$$V = 2\pi \int_a^b p(x)h(x)\,dx \qquad \text{Apply shell method.}$$

$$= 2\pi \int_0^1 x(x - x^3)\,dx \qquad \text{Substitute } x \text{ for } p(x) \text{ and } x - x^3 \text{ for } h(x).$$

$$= 2\pi \int_0^1 (-x^4 + x^2)\,dx \qquad \text{Simplify.}$$

$$= 2\pi \left[-\frac{x^5}{5} + \frac{x^3}{3} \right]_0^1 \qquad \text{Integrate.}$$

$$= 2\pi \left(-\frac{1}{5} + \frac{1}{3} \right) \qquad \text{Apply Fundamental Theorem of Calculus.}$$

$$= \frac{4\pi}{15} \qquad \text{Simplify.}$$

■

Exploration

Suppose you were asked to use the disk method to find the volume in Example 1. What would the representative rectangle look like? Is the disk method a good way to find the volume? Why or why not?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 2 Using the Shell Method to Find Volume

Find the volume of the solid formed by revolving the region bounded by the graph of

$$x = e^{-y^2}$$

and the y-axis $(0 \le y \le 1)$ about the x-axis.

Solution Because the axis of revolution is horizontal, use a horizontal representative rectangle, as shown in Figure 7.31. The width Δy indicates that y is the variable of integration. The distance from the center of the rectangle to the axis of revolution is $p(y) = y$, and the height of the rectangle is $h(y) = e^{-y^2}$. Because y ranges from 0 to 1, the volume of the solid is

$$V = 2\pi \int_c^d p(y)h(y)\,dy \qquad \text{Apply shell method.}$$

$$= 2\pi \int_0^1 ye^{-y^2}\,dy \qquad \text{Substitute } y \text{ for } p(y) \text{ and } e^{-y^2} \text{ for } h(y).$$

$$= -\pi\left[e^{-y^2}\right]_0^1 \qquad \text{Integrate.}$$

$$= \pi\left(1 - \frac{1}{e}\right) \qquad \text{Apply Fundamental Theorem of Calculus.}$$

$$\approx 1.986. \qquad \text{Use a calculator.}$$



Figure 7.31

Check this result using a graphing utility, as shown below.



Comparison of Disk and Shell Methods

The disk and shell methods can be distinguished as follows. For the disk method, the representative rectangle is always *perpendicular* to the axis of revolution, whereas for the shell method, the representative rectangle is always *parallel* to the axis of revolution, as shown in Figure 7.32.


$V = \pi \int_c^d (R^2 - r^2)\,dy$
$V = \pi \int_a^b (R^2 - r^2)\,dx$
$V = 2\pi \int_a^b ph\,dx$
$V = 2\pi \int_c^d ph\,dy$
Vertical axis of revolution
Horizontal axis of revolution
Vertical axis of revolution
Horizontal axis of revolution
Disk method: Representative rectangle is perpendicular to the axis of revolution.
Shell method: Representative rectangle is parallel to the axis of revolution.

Figure 7.32

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Often, one method is more convenient to use than the other. The next example illustrates a case in which the shell method is preferable.

EXAMPLE 3 Comparing Methods

See LarsonCalculus.com for an interactive version of this type of example.

Find the volume of the solid formed by revolving the region bounded by the graphs of $y = x^2 + 1$, $y = 0$, $x = 0$, and $x = 1$ about the y-axis.

Solution In Example 4 in Section 7.2, you saw that the washer method requires two integrals to determine the volume of this solid. See Figure 7.33(a).

$$V = \pi \int_0^1 (1^2 - 0^2)\, dy + \pi \int_1^2 \left[1^2 - \left(\sqrt{y-1}\right)^2\right] dy \qquad \text{Apply washer method.}$$

$$= \pi \int_0^1 1\, dy + \pi \int_1^2 (2 - y)\, dy \qquad \text{Simplify.}$$

$$= \pi \left[y \right]_0^1 + \pi \left[2y - \frac{y^2}{2} \right]_1^2 \qquad \text{Integrate.}$$

$$= \pi + \pi\left(4 - 2 - 2 + \frac{1}{2}\right)$$

$$= \frac{3\pi}{2}$$



(a) Washer method



(b) Shell method

Figure 7.33

Notice in Figure 7.33(b) that the shell method requires only one integral to find the volume. The distance from the center of the rectangle to the axis of revolution is $p(x) = x$, the height of the rectangle is $h(x) = x^2 + 1$, and x ranges from 0 to 1.

$$V = 2\pi \int_a^b p(x)h(x)\, dx \qquad \text{Apply shell method.}$$

$$= 2\pi \int_0^1 x(x^2 + 1)\, dx \qquad \text{Substitute.}$$

$$= 2\pi \int_0^1 (x^3 + x)\, dx \qquad \text{Simplify.}$$

$$= 2\pi \left[\frac{x^4}{4} + \frac{x^2}{2} \right]_0^1 \qquad \text{Integrate.}$$

$$= 2\pi\left(\frac{3}{4}\right)$$

$$= \frac{3\pi}{2}$$

Consider the solid formed by revolving the region in Example 3 about the vertical line $x = 1$. Would the resulting solid of revolution have a greater volume or a smaller volume than the solid in Example 3? Without integrating, you should be able to reason that the resulting solid would have a smaller volume because "more" of the revolved region would be closer to the axis of revolution. To confirm this, try solving the integral

$$V = 2\pi \int_0^1 (1 - x)(x^2 + 1)\, dx \qquad p(x) = 1 - x$$

which gives the volume of the solid.

FOR FURTHER INFORMATION To learn more about the disk and shell methods, see the article "The Disk and Shell Method" by Charles A. Cable in *The American Mathematical Monthly*. To view this article, go to *MathArticles.com*.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 7.34



Disk method

Figure 7.35

GO DIGITAL

EXAMPLE 4 Volume of a Pontoon

A pontoon is to be made in the shape shown in Figure 7.34. The pontoon is designed by revolving the graph of

$$y = 1 - \frac{x^2}{16}, \quad -4 \le x \le 4$$

about the x-axis, where x and y are measured in feet. Find the volume of the pontoon.

Solution Refer to Figure 7.35 and use the disk method as shown.

$$V = \pi \int_{-4}^{4} \left(1 - \frac{x^2}{16}\right)^2 dx \qquad \text{Apply disk method.}$$

$$= \pi \int_{-4}^{4} \left(1 - \frac{x^2}{8} + \frac{x^4}{256}\right) dx \qquad \text{Simplify.}$$

$$= \pi \left[x - \frac{x^3}{24} + \frac{x^5}{1280}\right]_{-4}^{4} \qquad \text{Integrate.}$$

$$= \frac{64\pi}{15}$$

$$\approx 13.4 \text{ cubic feet}$$

To use the shell method in Example 4, you would have to solve for x in terms of y in the equation

$$y = 1 - \frac{x^2}{16}$$

and then evaluate an integral that requires a u-substitution.

Sometimes, solving for x is very difficult (or even impossible). In such cases, you must use a vertical rectangle (of width Δx), making x the variable of integration. The position (horizontal or vertical) of the axis of revolution then determines the method to be used. This is shown in Example 5.

EXAMPLE 5 Shell Method Necessary

Find the volume of the solid formed by revolving the region bounded by the graphs of $y = x^3 + x + 1$, $y = 1$, and $x = 1$ about the line $x = 2$, as shown in Figure 7.36.



Figure 7.36

Solution In the equation $y = x^3 + x + 1$, you cannot easily solve for x in terms of y. (See the discussion at the end of Section 3.8.) So, the variable of integration must be x, and you should choose a vertical representative rectangle. Because the rectangle is parallel to the axis of revolution, use the shell method.

$$V = 2\pi \int_a^b p(x)h(x)\,dx \qquad \text{Apply shell method.}$$

$$= 2\pi \int_0^1 (2 - x)(x^3 + x + 1 - 1)\,dx \qquad \text{Substitute. (See Figure 7.36.)}$$

$$= 2\pi \int_0^1 (-x^4 + 2x^3 - x^2 + 2x)\,dx \qquad \text{Simplify.}$$

$$= 2\pi \left[-\frac{x^5}{5} + \frac{x^4}{2} - \frac{x^3}{3} + x^2\right]_0^1 \qquad \text{Integrate.}$$

$$= 2\pi \left(-\frac{1}{5} + \frac{1}{2} - \frac{1}{3} + 1\right)$$

$$= \frac{29\pi}{15}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

7.3 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain how to use the shell method to find the volume of a solid of revolution.
2. Compare the representative rectangles for the disk and shell methods.

Finding the Volume of a Solid **In Exercises 3–12, use the shell method to write and evaluate the definite integral that represents the volume of the solid generated by revolving the plane region about the *y*-axis.**

3. $y = x$



4. $y = 1 - x$



5. $y = \sqrt{x}$



6. $y = \frac{1}{2}x^2 + 1$



7. $y = \frac{1}{4}x^2, \quad y = 0, \quad x = 4$

8. $y = \frac{1}{2}x^3, \quad y = 0, \quad x = 3$

9. $y = x^2, \quad y = 4x - x^2$

10. $y = x^3, \quad y = 8, \quad x = 0$

11. $y = \sqrt{2x - 5}, \quad y = 0, \quad x = 4$

12. $y = x^{3/2}, \quad y = 8, \quad x = 0$

Finding the Volume of a Solid **In Exercises 13–22, use the shell method to write and evaluate the definite integral that represents the volume of the solid generated by revolving the plane region about the *x*-axis.**

13. $y = x$



14. $y = 1 - x$



15. $y = \frac{1}{x}$



16. $x + y^2 = 4$



17. $y = x^3, \quad x = 0, \quad y = 8$

18. $y = 4x^2, \quad x = 0, \quad y = 4$

19. $x + y = 4, \quad y = x, \quad y = 0$

20. $y = 3 - x, \quad y = 0, \quad x = 6$

21. $y = 1 - \sqrt{x}, \quad y = x + 1, \quad y = 0$

22. $y = \sqrt{x + 2}, \quad y = x, \quad y = 0$

Finding the Volume of a Solid **In Exercises 23–26, use the shell method to find the volume of the solid generated by revolving the region bounded by the graphs of the equations about the given line.**

23. $y = 2x - x^2, \quad y = 0,$ about the line $x = 4$

24. $y = \sqrt{x}, \quad y = 0, \quad x = 4,$ about the line $x = 6$

25. $y = 3x - x^2, \quad y = x^2,$ about the line $x = 2$

26. $y = \frac{1}{3}x^3, \quad y = 6x - x^2,$ about the line $x = 3$

Choosing a Method **In Exercises 27 and 28, decide whether it is more convenient to use the disk method or the shell method to find the volume of the solid of revolution. Explain your reasoning. (Do not find the volume.)**

27. $(y - 2)^2 = 4 - x$



28. $y = 4 - e^x$



Choosing a Method **In Exercises 29–32, use the disk method *or* the shell method to find the volumes of the solids generated by revolving the region bounded by the graphs of the equations about the given lines.**

29. $y = x^3, \quad y = 0, \quad x = 2$

(a) *x*-axis (b) *y*-axis (c) $x = 4$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

30. $y = \dfrac{10}{x^2}, \quad y = 0, \quad x = 1, \quad x = 5$

(a) x-axis (b) y-axis (c) $y = 10$

31. $x^{1/2} + y^{1/2} = a^{1/2}, \quad x = 0, \quad y = 0$

(a) x-axis (b) y-axis (c) $x = a$

32. $x^{2/3} + y^{2/3} = a^{2/3}, \quad a > 0$ (hypocycloid)

(a) x-axis (b) y-axis

Finding the Volume of a Solid Using Technology **In Exercises 33–36, (a) use a graphing utility to graph the region bounded by the graphs of the equations, and (b) use the integration capabilities of the graphing utility to approximate the volume of the solid generated by revolving the region about the y-axis.**

33. $x^{4/3} + y^{4/3} = 1, \quad x = 0, \quad y = 0,$ first quadrant

34. $y = \sqrt{1 - x^3}, \quad y = 0, \quad x = 0$

35. $y = \sqrt[3]{(x - 2)^2(x - 6)^2}, \quad y = 0, \quad x = 2, \quad x = 6$

36. $y = \dfrac{2}{1 + e^{1/x}}, \quad y = 0, \quad x = 1, \quad x = 3$

Exploring Concepts

37. Consider the plane region bounded by the graphs of $y = k$, $y = 0$, $x = 0$, and $x = b$, where $k > 0$ and $b > 0$. Find the heights and radii of the cylinders generated when this region is revolved about (a) the x-axis and (b) the y-axis.

38. A solid is generated by revolving the region bounded by $y = 9 - x^2$ and $x = 0$ about the y-axis. Explain why you can use the shell method with limits of integration $x = 0$ and $x = 3$ to find the volume of the solid.

In Exercises 39 and 40, give a geometric argument that explains why the integrals have equal values.

39. $\pi \displaystyle\int_1^5 (x - 1)\,dx = 2\pi \int_0^2 y[5 - (y^2 + 1)]\,dy$

40. $\pi \displaystyle\int_0^2 [16 - (2y)^2]\,dy = 2\pi \int_0^4 x\left(\frac{x}{2}\right)dx$

41. Comparing Volumes The region in the figure is revolved about the indicated axes and line. Order the volumes of the resulting solids from least to greatest. Explain your reasoning.

(a) x-axis (b) y-axis (c) $x = 4$



42. HOW DO YOU SEE IT? Use the graph to answer the following.



(a) Describe the figure generated by revolving segment AB about the y-axis.

(b) Describe the figure generated by revolving segment BC about the y-axis.

(c) Assume the curve in the figure can be described as $y = f(x)$ or $x = g(y)$. A solid is generated by revolving the region bounded by the curve, $y = 0$, and $x = 0$ about the y-axis. Set up integrals to find the volume of this solid using the disk method and the shell method. (Do not integrate.)

Analyzing an Integral **In Exercises 43–46, the integral represents the volume of a solid of revolution. Identify (a) the plane region that is revolved and (b) the axis of revolution.**

43. $2\pi \displaystyle\int_0^2 x^3\,dx$

44. $2\pi \displaystyle\int_0^1 (y - y^{3/2})\,dy$

45. $2\pi \displaystyle\int_0^6 (y + 2)\sqrt{6 - y}\,dy$

46. $2\pi \displaystyle\int_0^1 (4 - x)e^x\,dx$

47. Machine Part A solid is generated by revolving the region bounded by $y = \frac{1}{2}x^2$ and $y = 2$ about the y-axis. A hole, centered along the axis of revolution, is drilled through this solid so that one-fourth of the volume is removed. Find the diameter of the hole.

48. Machine Part A solid is generated by revolving the region bounded by $y = \sqrt{9 - x^2}$ and $y = 0$ about the y-axis. A hole, centered along the axis of revolution, is drilled through this solid so that one-third of the volume is removed. Find the diameter of the hole.

49. Volume of a Torus A torus is formed by revolving the region bounded by the circle $x^2 + y^2 = 1$ about the line $x = 2$ (see figure). Find the volume of this "doughnut-shaped" solid. (*Hint:* The integral $\int_{-1}^{1} \sqrt{1 - x^2}\,dx$ represents the area of a semicircle.)



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

50. Volume of a Torus Repeat Exercise 49 for a torus formed by revolving the region bounded by the circle $x^2 + y^2 = r^2$ about the line $x = R$, where $r < R$.

51. Finding Volumes of Solids

(a) Use differentiation to verify that

$$\int x \sin x \, dx = \sin x - x \cos x + C.$$

(b) Use the result of part (a) to find the volume of the solid generated by revolving each plane region about the y-axis.

(i)



(ii)



52. Finding Volumes of Solids

(a) Use differentiation to verify that

$$\int x \cos x \, dx = \cos x + x \sin x + C.$$

(b) Use the result of part (a) to find the volume of the solid generated by revolving each plane region about the y-axis. (*Hint:* Begin by approximating the points of intersection.)

(i)



(ii)



53. Volume of a Segment of a Sphere Let a sphere of radius r be cut by a plane, thereby forming a segment of height h. Show that the volume of this segment is

$$\frac{1}{3}\pi h^2(3r - h).$$

54. Volume of an Ellipsoid Consider the plane region bounded by the graph of the ellipse

$$\left(\frac{x}{a}\right)^2 + \left(\frac{y}{b}\right)^2 = 1$$

where $a > 0$ and $b > 0$. Show that the volume of the ellipsoid formed when this region is revolved about the y-axis is

$$\frac{4}{3}\pi a^2 b.$$

What is the volume when the region is revolved about the x-axis?

55. Exploration Consider the region bounded by the graphs of $y = ax^n$, $y = ab^n$, and $x = 0$, as shown in the figure.



(a) Find the ratio $R_1(n)$ of the area of the region to the area of the circumscribed rectangle.

(b) Find $\lim_{n\to\infty} R_1(n)$ and compare the result with the area of the circumscribed rectangle.

(c) Find the volume of the solid of revolution formed by revolving the region about the y-axis. Find the ratio $R_2(n)$ of this volume to the volume of the circumscribed right circular cylinder.

(d) Find $\lim_{n\to\infty} R_2(n)$ and compare the result with the volume of the circumscribed cylinder.

(e) Use the results of parts (b) and (d) to make a conjecture about the shape of the graph of $y = ax^n$, $0 \le x \le b$, as $n \to \infty$.

56. Think About It Match each integral with the solid whose volume it represents and give the dimensions of each solid.

(a) Right circular cone (b) Torus (c) Sphere

(d) Right circular cylinder (e) Ellipsoid

(i) $2\pi \int_0^r hx \, dx$

(ii) $2\pi \int_0^r hx\left(1 - \frac{x}{r}\right) dx$

(iii) $2\pi \int_0^r 2x\sqrt{r^2 - x^2} \, dx$

(iv) $2\pi \int_0^b 2ax\sqrt{1 - \frac{x^2}{b^2}} \, dx$

(v) $2\pi \int_{-r}^r (R - x)\left(2\sqrt{r^2 - x^2}\right) dx$

57. Volume of a Storage Shed A storage shed has a circular base of diameter 80 feet. Starting at the center, the interior height is measured every 10 feet and recorded in the table (see figure). Find the volume of the shed.

x	Height
0	50
10	45
20	40
30	20
40	0



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

58. Modeling Data A pond is approximately circular, with a diameter of 400 feet. Starting at the center, the depth of the water is measured every 25 feet and recorded in the table (see figure).

x	0	25	50
Depth	20	19	19

x	75	100	125
Depth	17	15	14

x	150	175	200
Depth	10	6	0



(a) Use the regression capabilities of a graphing utility to find a quadratic model for the depths recorded in the table. Use the graphing utility to plot the depths and graph the model.

(b) Use the integration capabilities of a graphing utility and the model in part (a) to approximate the volume of water in the pond.

(c) Use the result of part (b) to approximate the number of gallons of water in the pond. (*Hint:* 1 cubic foot of water is approximately 7.48 gallons.)

59. Equal Volumes Let V_1 and V_2 be the volumes of the solids that result when the plane region bounded by

$$y = \frac{1}{x}, \quad y = 0, \quad x = \frac{1}{4}, \quad \text{and} \quad x = c, \quad c > \frac{1}{4}$$

is revolved about the x-axis and the y-axis, respectively. Find the value of c for which $V_1 = V_2$.

60. Volume of a Segment of a Paraboloid The region bounded by $y = r^2 - x^2$, $y = 0$, and $x = 0$ is revolved about the y-axis to form a paraboloid. A hole, centered along the axis of revolution, is drilled through this solid. The hole has a radius k, $0 < k < r$. Find the volume of the resulting ring (a) by integrating with respect to x and (b) by integrating with respect to y.

61. Finding Volumes of Solids Consider the graph of $y^2 = x(4 - x)^2$, as shown in the figure. Find the volumes of the solids that are generated when the loop of this graph is revolved about (a) the x-axis, (b) the y-axis, and (c) the line $x = 4$.



SECTION PROJECT

Saturn

The Oblateness of Saturn Saturn is the most oblate of the planets in our solar system. Its equatorial radius is 60,268 kilometers and its polar radius is 54,364 kilometers. The color-enhanced photograph of Saturn was taken by Voyager 1. In the photograph, the oblateness of Saturn is clearly visible.

(a) Find the ratio of the volumes of the sphere and the oblate ellipsoid shown below.

(b) If a planet were spherical and had the same volume as Saturn, what would its radius be?

Computer model of "spherical Saturn," whose equatorial radius is equal to its polar radius. The equation of the cross section passing through the pole is

$x^2 + y^2 = 60{,}268^2$.



Computer model of "oblate Saturn," whose equatorial radius is greater than its polar radius. The equation of the cross section passing through the pole is

$$\frac{x^2}{60{,}268^2} + \frac{y^2}{54{,}364^2} = 1.$$



NASA

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

7.4 Arc Length and Surfaces of Revolution

GO DIGITAL

- **Find the arc length of a smooth curve.**
- **Find the area of a surface of revolution.**

Arc Length

In this section, definite integrals are used to find the arc lengths of curves and the areas of surfaces of revolution. In either case, an arc (a segment of a curve) is approximated by straight line segments whose lengths are given by the familiar Distance Formula

$$d = \sqrt{(x_2 - x_1)^2 + (y_2 - y_1)^2}.$$ See Appendix C.2.

A **rectifiable** curve is one that has a finite arc length. You will learn that a sufficient condition for the graph of a function f to be rectifiable between $(a, f(a))$ and $(b, f(b))$ is that f' be continuous on $[a, b]$. Such a function is **continuously differentiable** on $[a, b]$, and its graph on the interval $[a, b]$ is a **smooth curve.**

Consider a function $y = f(x)$ that is continuously differentiable on the interval $[a, b]$. You can approximate the graph of f by n line segments whose endpoints are determined by the partition

$$a = x_0 < x_1 < x_2 < \cdots < x_n = b$$

as shown in Figure 7.37. By letting $\Delta x_i = x_i - x_{i-1}$ and $\Delta y_i = y_i - y_{i-1}$, the approximate length of the graph is

$$\begin{aligned} s &\approx \sum_{i=1}^{n} \sqrt{(x_i - x_{i-1})^2 + (y_i - y_{i-1})^2} \\ &= \sum_{i=1}^{n} \sqrt{(\Delta x_i)^2 + (\Delta y_i)^2} && \Delta x_i = x_i - x_{i-1} \text{ and } \Delta y_i = y_i - y_{i-1} \\ &= \sum_{i=1}^{n} \sqrt{(\Delta x_i)^2 + \left(\frac{\Delta y_i}{\Delta x_i}\right)^2 (\Delta x_i)^2} && \text{Multiply and divide } (\Delta y_i)^2 \text{ by } (\Delta x_i)^2. \\ &= \sum_{i=1}^{n} \sqrt{1 + \left(\frac{\Delta y_i}{\Delta x_i}\right)^2} (\Delta x_i). && \Delta x_i > 0 \end{aligned}$$

This approximation appears to become better and better as $\|\Delta\| \to 0$ $(n \to \infty)$. So, the length of the graph is

$$s = \lim_{\|\Delta\| \to 0} \sum_{i=1}^{n} \sqrt{1 + \left(\frac{\Delta y_i}{\Delta x_i}\right)^2} (\Delta x_i).$$

Because $f'(x)$ exists for each x in (x_{i-1}, x_i), the Mean Value Theorem guarantees the existence of c_i in (x_{i-1}, x_i) such that

$$\frac{f(x_i) - f(x_{i-1})}{x_i - x_{i-1}} = f'(c_i)$$

$$\frac{\Delta y_i}{\Delta x_i} = f'(c_i).$$

Because f' is continuous on $[a, b]$, it follows that $\sqrt{1 + [f'(x)]^2}$ is also continuous (and therefore integrable) on $[a, b]$, which implies that

$$\begin{aligned} s &= \lim_{\|\Delta\| \to 0} \sum_{i=1}^{n} \sqrt{1 + [f'(c_i)]^2}\, (\Delta x_i) \\ &= \int_a^b \sqrt{1 + [f'(x)]^2}\, dx \end{aligned}$$

where s is called the **arc length** of f between a and b.



Figure 7.37

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

CHRISTIAN HUYGENS (1629–1695)

The Dutch mathematician Christian Huygens, who invented the pendulum clock, and James Gregory (1638–1675), a Scottish mathematician, both made early contributions to the problem of finding the length of a rectifiable curve.

See LarsonCalculus.com to read more of this biography.

Definition of Arc Length

Let the function $y = f(x)$ represent a smooth curve on the interval $[a, b]$. The **arc length** of f between a and b is

$$s = \int_a^b \sqrt{1 + [f'(x)]^2}\, dx.$$ y is a function of x.

Similarly, for a smooth curve $x = g(y)$, the **arc length** of g between c and d is

$$s = \int_c^d \sqrt{1 + [g'(y)]^2}\, dy.$$ x is a function of y.

FOR FURTHER INFORMATION To learn how arc length can be used to define trigonometric functions, see the article "Trigonometry Requires Calculus, Not Vice Versa" by Yves Nievergelt in *UMAP Modules*.

Because the definition of arc length can be applied to a linear function, you can check that this new definition agrees with the Distance Formula for the length of a line segment. This is shown in Example 1.

EXAMPLE 1 The Length of a Line Segment

Find the arc length from (x_1, y_1) to (x_2, y_2) on the graph of

$$f(x) = mx + b.$$

Solution Because

$$f'(x) = m = \frac{y_2 - y_1}{x_2 - x_1}$$ First derivative

it follows that

$$s = \int_{x_1}^{x_2} \sqrt{1 + [f'(x)]^2}\, dx$$ Formula for arc length

$$= \int_{x_1}^{x_2} \sqrt{1 + \left(\frac{y_2 - y_1}{x_2 - x_1}\right)^2}\, dx$$ $f'(x) = \frac{y_2 - y_1}{x_2 - x_1}$

$$= \sqrt{\frac{(x_2 - x_1)^2 + (y_2 - y_1)^2}{(x_2 - x_1)^2}}(x)\Bigg]_{x_1}^{x_2}$$ Integrate and simplify.

$$= \sqrt{\frac{(x_2 - x_1)^2 + (y_2 - y_1)^2}{(x_2 - x_1)^2}}(x_2 - x_1)$$ Apply Fundamental Theorem of Calculus.

$$= \sqrt{(x_2 - x_1)^2 + (y_2 - y_1)^2}$$ Simplify.

which is the formula for the distance between two points in the plane, as shown in Figure 7.38.



The formula for the arc length of the graph of f from (x_1, y_1) to (x_2, y_2) is the same as the standard Distance Formula.
Figure 7.38

TECHNOLOGY Definite integrals representing arc length often are very difficult to evaluate. In this section, a few examples are presented. In the next chapter, with more advanced integration techniques, you will be able to tackle more difficult arc length problems. In the meantime, remember that you can always use a numerical integration program to approximate an arc length. For instance, use the *numerical integration* feature of a graphing utility to approximate the arc lengths in Examples 2 and 3.

GO DIGITAL

Science & Society Picture Library/Getty Images

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The arc length of the graph of y on $\left[\frac{1}{2}, 2\right]$

Figure 7.39

EXAMPLE 2 Finding Arc Length

Find the arc length of the graph of $y = x^3/6 + 1/(2x)$ on the interval $[1/2, 2]$, as shown in Figure 7.39.

Solution Using

$$\frac{dy}{dx} = \frac{3x^2}{6} - \frac{1}{2x^2} = \frac{1}{2}\left(x^2 - \frac{1}{x^2}\right)$$ First derivative

yields an arc length of

$$s = \int_a^b \sqrt{1 + \left(\frac{dy}{dx}\right)^2}\, dx$$ Formula for arc length

$$= \int_{1/2}^{2} \sqrt{1 + \left[\frac{1}{2}\left(x^2 - \frac{1}{x^2}\right)\right]^2}\, dx$$ $\frac{dy}{dx} = \frac{1}{2}\left(x^2 - \frac{1}{x^2}\right)$

$$= \int_{1/2}^{2} \sqrt{\frac{1}{4}\left(x^4 + 2 + \frac{1}{x^4}\right)}\, dx$$

$$= \frac{1}{2}\int_{1/2}^{2} \left(x^2 + \frac{1}{x^2}\right) dx$$ Simplify.

$$= \frac{1}{2}\left[\frac{x^3}{3} - \frac{1}{x}\right]_{1/2}^{2}$$ Integrate.

$$= \frac{1}{2}\left(\frac{13}{6} + \frac{47}{24}\right)$$ Apply Fundamental Theorem of Calculus.

$$= \frac{33}{16}.$$ Simplify.



The arc length of the graph of y on $[0, 8]$

Figure 7.40

EXAMPLE 3 Finding Arc Length

Find the arc length of the graph of $(y - 1)^3 = x^2$ on the interval $[0, 8]$, as shown in Figure 7.40. Round your answer to three decimal places.

Solution Solving for y yields $y = x^{2/3} + 1$ and $dy/dx = 2/(3x^{1/3})$. Because dy/dx is undefined when $x = 0$, the arc length formula with respect to x cannot be used. Solving for x in terms of y yields $x = \pm(y - 1)^{3/2}$. Choosing the positive value of x produces

$$\frac{dx}{dy} = \frac{3}{2}(y - 1)^{1/2}.$$ First derivative

The x-interval $[0, 8]$ corresponds to the y-interval $[1, 5]$, and the arc length is

$$s = \int_c^d \sqrt{1 + \left(\frac{dx}{dy}\right)^2}\, dy$$ Formula for arc length

$$= \int_1^5 \sqrt{1 + \left[\frac{3}{2}(y - 1)^{1/2}\right]^2}\, dy$$ $\frac{dx}{dy} = \frac{3}{2}(y - 1)^{1/2}$

$$= \int_1^5 \sqrt{\frac{9}{4}y - \frac{5}{4}}\, dy$$

$$= \frac{1}{2}\int_1^5 \sqrt{9y - 5}\, dy$$ Simplify.

$$= \frac{1}{18}\left[\frac{(9y - 5)^{3/2}}{3/2}\right]_1^5$$ Integrate.

$$= \frac{1}{27}(40^{3/2} - 4^{3/2})$$ Apply Fundamental Theorem of Calculus.

$$\approx 9.073.$$ Use a calculator.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The arc length of the graph of y on $\left[0, \frac{\pi}{4}\right]$

Figure 7.41

EXAMPLE 4 Finding Arc Length

See LarsonCalculus.com for an interactive version of this type of example.

Find the arc length of the graph of

$$y = \ln(\cos x)$$

from $x = 0$ to $x = \pi/4$, as shown in Figure 7.41. Round your answer to three decimal places.

Solution Using

$$\frac{dy}{dx} = -\frac{\sin x}{\cos x} = -\tan x \qquad \text{First derivative}$$

yields an arc length of

$$\begin{aligned}
s &= \int_a^b \sqrt{1 + \left(\frac{dy}{dx}\right)^2}\, dx && \text{Formula for arc length} \\
&= \int_0^{\pi/4} \sqrt{1 + \tan^2 x}\, dx && \frac{dy}{dx} = -\tan x \\
&= \int_0^{\pi/4} \sqrt{\sec^2 x}\, dx && \text{Trigonometric identity} \\
&= \int_0^{\pi/4} \sec x\, dx && \text{Simplify.} \\
&= \Big[\ln|\sec x + \tan x|\Big]_0^{\pi/4} && \text{Integrate.} \\
&= \ln\left(\sqrt{2} + 1\right) - \ln 1 && \text{Apply Fundamental Theorem of Calculus.} \\
&\approx 0.881. && \text{Use a calculator.}
\end{aligned}$$

EXAMPLE 5 Length of a Cable

An electric cable is hung between two towers that are 200 feet apart, as shown in Figure 7.42. The cable takes the shape of a catenary whose equation is

$$y = 75(e^{x/150} + e^{-x/150}) = 150 \cosh \frac{x}{150}.$$



Figure 7.42

Find the arc length of the cable between the two towers to the nearest foot.

Solution Because $y' = \frac{1}{2}(e^{x/150} - e^{-x/150})$, you can square each side to obtain

$$(y')^2 = \frac{1}{4}(e^{x/75} - 2 + e^{-x/75}).$$

Then add 1 to each side and simplify to obtain

$$1 + (y')^2 = \frac{1}{4}(e^{x/75} + 2 + e^{-x/75}) = \left[\frac{1}{2}(e^{x/150} + e^{-x/150})\right]^2.$$

Therefore, the arc length of the cable is

$$\begin{aligned}
s &= \int_a^b \sqrt{1 + (y')^2}\, dx && \text{Formula for arc length} \\
&= \frac{1}{2}\int_{-100}^{100} (e^{x/150} + e^{-x/150})\, dx \\
&= 75\Big[e^{x/150} - e^{-x/150}\Big]_{-100}^{100} && \text{Integrate.} \\
&= 150(e^{2/3} - e^{-2/3}) && \text{Apply Fundamental Theorem of Calculus.} \\
&\approx 215 \text{ feet.} && \text{Use a calculator.}
\end{aligned}$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Area of a Surface of Revolution

In Sections 7.2 and 7.3, integration was used to calculate the volume of a solid of revolution. You will now learn a procedure for finding the area of a surface of revolution.

Definition of Surface of Revolution

When the graph of a continuous function is revolved about a line, the resulting surface is a **surface of revolution.**

The area of a surface of revolution is derived from the formula for the lateral surface area of the frustum of a right circular cone. Consider the line segment in the figure at the right, where L is the length of the line segment, r_1 is the radius at the left end of the line segment, and r_2 is the radius at the right end of the line segment. When the line segment is revolved about its axis of revolution, it forms a frustum of a right circular cone, with



$$S = 2\pi rL \qquad \text{Lateral surface area of frustum}$$

where

$$r = \frac{1}{2}(r_1 + r_2). \qquad \text{Average radius of frustum}$$

(In Exercise 56, you are asked to verify the formula for S.)

Consider a function f that has a continuous derivative on the interval $[a, b]$. The graph of f is revolved about the x-axis to form a surface of revolution, as shown in Figure 7.43. Let Δ be a partition of $[a, b]$, with subintervals of width Δx_i. Then the line segment of length

$$\Delta L_i = \sqrt{(\Delta x_i)^2 + (\Delta y_i)^2}$$

generates a frustum of a cone. Let r_i be the average radius of this frustum. By the Intermediate Value Theorem, a number d_i exists (in the ith subinterval) such that

$$r_i = f(d_i).$$

The lateral surface area ΔS_i of the frustum is

$$\begin{aligned}\Delta S_i &= 2\pi r_i \Delta L_i \\ &= 2\pi f(d_i)\sqrt{(\Delta x_i)^2 + (\Delta y_i)^2} \\ &= 2\pi f(d_i)\sqrt{1 + \left(\frac{\Delta y_i}{\Delta x_i}\right)^2}\Delta x_i.\end{aligned}$$



Figure 7.43

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 7.44

By the Mean Value Theorem, a number c_i exists in (x_{i-1}, x_i) such that

$$f'(c_i) = \frac{f(x_i) - f(x_{i-1})}{x_i - x_{i-1}} = \frac{\Delta y_i}{\Delta x_i}.$$

So, $\Delta S_i = 2\pi f(d_i)\sqrt{1 + [f'(c_i)]^2}\,\Delta x_i$, and the total surface area can be approximated by

$$S \approx 2\pi \sum_{i=1}^{n} f(d_i)\sqrt{1 + [f'(c_i)]^2}\,\Delta x_i.$$

It can be shown that the limit of the right side as $\|\Delta\| \to 0$ $(n \to \infty)$ is

$$S = 2\pi \int_a^b f(x)\sqrt{1 + [f'(x)]^2}\,dx. \qquad f \text{ is revolved about the } x\text{-axis.}$$

In a similar manner, if the graph of f is revolved about the y-axis, then S is

$$S = 2\pi \int_a^b x\sqrt{1 + [f'(x)]^2}\,dx. \qquad f \text{ is revolved about the } y\text{-axis.}$$

In these two formulas for S, you can regard the products $2\pi f(x)$ and $2\pi x$ as the circumferences of the circles traced by a point (x, y) on the graph of f as it is revolved about the x-axis and the y-axis (see Figure 7.44). In one case, the radius is $r = f(x)$, and in the other case, the radius is $r = x$. Moreover, by appropriately adjusting r, you can generalize the formula for surface area to cover *any* horizontal or vertical axis of revolution, as indicated in the next definition.

Definition of the Area of a Surface of Revolution

Let $y = f(x)$ have a continuous derivative on the interval $[a, b]$. The area S of the surface of revolution formed by revolving the graph of f about a horizontal or vertical axis is

$$S = 2\pi \int_a^b r(x)\sqrt{1 + [f'(x)]^2}\,dx \qquad y \text{ is a function of } x.$$

where $r(x)$ is the distance between the graph of f and the axis of revolution. If $x = g(y)$ on the interval $[c, d]$, then the surface area is

$$S = 2\pi \int_c^d r(y)\sqrt{1 + [g'(y)]^2}\,dy \qquad x \text{ is a function of } y.$$

where $r(y)$ is the distance between the graph of g and the axis of revolution.

The formulas in this definition are sometimes written as

$$S = 2\pi \int_a^b r(x)\,ds \qquad y \text{ is a function of } x.$$

and

$$S = 2\pi \int_c^d r(y)\,ds \qquad x \text{ is a function of } y.$$

where

$$ds = \sqrt{1 + [f'(x)]^2}\,dx \quad \text{and} \quad ds = \sqrt{1 + [g'(y)]^2}\,dy$$

respectively.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 7.45

EXAMPLE 6 The Area of a Surface of Revolution

Find the area of the surface formed by revolving the graph of $f(x) = x^3$ on the interval $[0, 1]$ about the x-axis (see Figure 7.45). Round your answer to three decimal places.

Solution The distance between the x-axis and the graph of f is $r(x) = f(x)$, and because $f'(x) = 3x^2$, the surface area is

$$\begin{aligned}
S &= 2\pi \int_a^b r(x)\sqrt{1 + [f'(x)]^2}\,dx && \text{Formula for surface area} \\
&= 2\pi \int_0^1 x^3\sqrt{1 + (3x^2)^2}\,dx && f'(x) = 3x^2 \\
&= \frac{2\pi}{36}\int_0^1 (36x^3)(1 + 9x^4)^{1/2}\,dx && \text{Simplify.} \\
&= \frac{\pi}{18}\left[\frac{(1 + 9x^4)^{3/2}}{3/2}\right]_0^1 && \text{Integrate.} \\
&= \frac{\pi}{27}(10^{3/2} - 1) && \text{Apply Fundamental Theorem of Calculus.} \\
&\approx 3.563. && \text{Use a calculator.}
\end{aligned}$$

EXAMPLE 7 The Area of a Surface of Revolution

Find the area of the surface formed by revolving the graph of $f(x) = x^2$ on the interval $[0, \sqrt{2}]$ about the y-axis (see figure). Round your answer to three decimal places.



Solution In this case, the distance between the graph of f and the y-axis is $r(x) = x$. Using $f'(x) = 2x$ and the formula for surface area, you can determine that

$$\begin{aligned}
S &= 2\pi \int_a^b r(x)\sqrt{1 + [f'(x)]^2}\,dx && \text{Formula for surface area} \\
&= 2\pi \int_0^{\sqrt{2}} x\sqrt{1 + (2x)^2}\,dx && f'(x) = 2x \\
&= \frac{2\pi}{8}\int_0^{\sqrt{2}} (1 + 4x^2)^{1/2}(8x)\,dx && \text{Simplify.} \\
&= \frac{\pi}{4}\left[\frac{(1 + 4x^2)^{3/2}}{3/2}\right]_0^{\sqrt{2}} && \text{Integrate.} \\
&= \frac{\pi}{6}[(1 + 8)^{3/2} - 1] && \text{Apply Fundamental Theorem of Calculus.} \\
&= \frac{13\pi}{3} \\
&\approx 13.614. && \text{Use a calculator.}
\end{aligned}$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

7.4 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe the condition for a curve to be rectifiable between two points.
2. Explain how to find the arc length of a function that is a smooth curve on the interval $[a, b]$.
3. Name a function for which the integral below represents the arc length of the function on the interval $[0, 2]$.

$$\int_0^2 \sqrt{1 + (4x)^2}\, dx$$

4. Describe a surface of revolution.

Finding Distance Using Two Methods **In Exercises 5 and 6, find the distance between the points using (a) the Distance Formula and (b) integration.**

5. $(2, 1), (5, 3)$
6. $(-2, 2), (4, -6)$

Finding Arc Length **In Exercises 7–20, find the arc length of the graph of the function over the indicated interval.**

7. $y = \frac{2}{3}(x^2 + 1)^{3/2}$



8. $y = \frac{x^4}{8} + \frac{1}{4x^2}, \quad [2, 3]$



9. $y = \frac{2}{3}x^{3/2} + 1$



10. $y = 2x^{3/2} + 3$



11. $y = \frac{3}{2}x^{2/3}, \quad [1, 8]$
12. $y = \frac{3}{2}x^{2/3} + 4, \quad [1, 27]$
13. $y = \frac{x^5}{10} + \frac{1}{6x^3}, \quad [2, 5]$
14. $y = \frac{x^7}{14} + \frac{1}{10x^5}, \quad [1, 2]$
15. $y = \ln(\sin x), \quad \left[\frac{\pi}{4}, \frac{3\pi}{4}\right]$
16. $y = \ln(\cos x), \quad \left[0, \frac{\pi}{3}\right]$
17. $y = \frac{1}{2}(e^x + e^{-x}), \quad [0, 2]$
18. $y = \ln\left(\frac{e^x + 1}{e^x - 1}\right), \quad [\ln 6, \ln 8]$
19. $x = \frac{1}{3}(y^2 + 2)^{3/2}, \quad 0 \le y \le 4$
20. $x = \frac{1}{3}\sqrt{y}(y - 3), \quad 1 \le y \le 4$

Finding Arc Length **In Exercises 21–30, (a) sketch the graph of the function, highlighting the part indicated by the given interval, (b) write a definite integral that represents the arc length of the curve over the indicated interval and observe that the integral cannot be evaluated with the techniques studied so far, and (c) use the integration capabilities of a graphing utility to approximate the arc length.**

21. $y = 4 - x^2, \quad [0, 2]$
22. $y = x^2 + x - 2, \quad [-2, 1]$
23. $y = \frac{1}{x}, \quad [1, 3]$
24. $y = \frac{1}{x + 1}, \quad [0, 1]$
25. $y = \sin x, \quad [0, \pi]$
26. $y = \cos x, \quad \left[-\frac{\pi}{2}, \frac{\pi}{2}\right]$
27. $y = 2 \arctan x, \quad [0, 1]$
28. $y = \ln x, \quad [1, 5]$
29. $x = e^{-y}, \quad 0 \le y \le 2$
30. $x = \sqrt{36 - y^2}, \quad 0 \le y \le 3$

Approximation **In Exercises 31 and 32, approximate the arc length of the graph of the function over the interval $[0, 4]$ in three ways. (a) Use the Distance Formula to find the distance between the endpoints of the arc. (b) Use the Distance Formula to find the lengths of the four line segments connecting the points on the arc when $x = 0$, $x = 1$, $x = 2$, $x = 3$, and $x = 4$. Find the sum of the four lengths. (c) Use the integration capabilities of a graphing utility to approximate the integral yielding the indicated arc length.**

31. $f(x) = x^3$
32. $f(x) = (x^2 - 4)^2$

33. **Length of a Cable** An electric cable is hung between two towers that are 40 meters apart (see figure). The cable takes the shape of a catenary whose equation is

$$y = 10(e^{x/20} + e^{-x/20}), \quad -20 \le x \le 20$$

where x and y are measured in meters. Find the arc length of the cable between the two towers.



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

34. Roof Area A barn is 100 feet long and 40 feet wide (see figure). A cross section of the roof is the inverted catenary $y = 31 - 10(e^{x/20} + e^{-x/20})$. Find the number of square feet of roofing on the barn.



35. Length of Gateway Arch The Gateway Arch in St. Louis, Missouri, is modeled by the inverted catenary

$$y = 693.8597 - 68.7672 \cosh(0.0100333x)$$

where $-299.2239 \le x \le 299.2239$. Use the integration capabilities of a graphing utility to approximate the length of this curve (see figure).



Figure for 35



Figure for 36

36. Astroid Find the total length of the graph of the astroid $x^{2/3} + y^{2/3} = 4$ (see figure).

37. Arc Length of a Sector of a Circle Find the arc length from $(0, 3)$ clockwise to $(2, \sqrt{5})$ along the circle $x^2 + y^2 = 9$.

38. Arc Length of a Sector of a Circle Find the arc length from $(-3, 4)$ clockwise to $(4, 3)$ along the circle $x^2 + y^2 = 25$. Show that the result is one-fourth the circumference of the circle.

Finding the Area of a Surface of Revolution **In Exercises 39–44, write and evaluate the definite integral that represents the area of the surface generated by revolving the curve on the indicated interval about the *x*-axis.**

39. $y = \frac{1}{3}x^3$



40. $y = 2\sqrt{x}$



41. $y = \frac{x^3}{6} + \frac{1}{2x}, \quad 1 \le x \le 2$

42. $y = 3x, \quad 0 \le x \le 3$

43. $y = \sqrt{4 - x^2}, \quad -1 \le x \le 1$

44. $y = \sqrt{9 - x^2}, \quad -2 \le x \le 2$

Finding the Area of a Surface of Revolution **In Exercises 45–48, write and evaluate the definite integral that represents the area of the surface generated by revolving the curve on the indicated interval about the *y*-axis.**

45. $y = \sqrt[3]{x} + 2, \quad 1 \le x \le 8$

46. $y = 9 - x^2, \quad 0 \le x \le 3$

47. $y = 1 - \frac{x^2}{4}, \quad 0 \le x \le 2$

48. $y = \frac{x}{2} + 3, \quad 1 \le x \le 5$

Finding the Area of a Surface of Revolution Using Technology **In Exercises 49 and 50, use the integration capabilities of a graphing utility to approximate the area of the surface of revolution.**

Function	Interval	Axis of Revolution
49. $y = \sin x$	$[0, \pi]$	x-axis
50. $y = \ln x$	$[1, e]$	y-axis

Exploring Concepts

In Exercises 51 and 52, determine which value best approximates the length of the arc represented by the integral. Make your selection on the basis of a sketch of the arc, not by performing calculations.

51. $\displaystyle\int_0^2 \sqrt{1 + \left[\frac{d}{dx}\left(\frac{5}{x^2 + 1}\right)\right]^2}\, dx$

(a) 25 (b) 5 (c) 2 (d) -4 (e) 3

52. $\displaystyle\int_0^{\pi/4} \sqrt{1 + \left[\frac{d}{dx}(\tan x)\right]^2}\, dx$

(a) 3 (b) -2 (c) 4 (d) $\frac{4\pi}{3}$ (e) 1

53. Consider the function

$$f(x) = \frac{1}{4}e^x + e^{-x}.$$

Compare the definite integral of f on the interval $[a, b]$ with the arc length of f over the interval $[a, b]$.

54. HOW DO YOU SEE IT? The graphs of the functions f_1 and f_2 on the interval $[a, b]$ are shown in the figure. The graph of each function is revolved about the x-axis. Which surface of revolution has the greater surface area? Explain.



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

55. Think About It The figure shows the graphs of the functions $y_1 = x$, $y_2 = \frac{1}{2}x^{3/2}$, $y_3 = \frac{1}{4}x^2$, and $y_4 = \frac{1}{8}x^{5/2}$ on the interval $[0, 4]$. To print an enlarged copy of the graph, go to *MathGraphs.com.*



(a) Label the functions.

(b) Without calculating, list the functions in order of increasing arc length.

(c) Verify your answer in part (b) by using the integration capabilities of a graphing utility to approximate each arc length accurate to three decimal places.

56. Verifying a Formula

(a) Given a circular sector with radius L and central angle θ (see figure), show that the area of the sector is given by

$$S = \frac{1}{2}L^2\theta.$$

(b) By joining the straight-line edges of the sector in part (a), a right circular cone is formed (see figure) and the lateral surface area of the cone is the same as the area of the sector. Show that the area is $S = \pi rL$, where r is the radius of the base of the cone. (*Hint:* The arc length of the sector equals the circumference of the base of the cone.)



Figure for 56(a)



Figure for 56(b)

(c) Use the result of part (b) to verify that the formula for the lateral surface area of the frustum of a cone with slant height L and radii r_1 and r_2 (see figure) is $S = \pi(r_1 + r_2)L$. (*Note:* This formula was used to develop the integral for finding the surface area of a surface of revolution.)



57. Lateral Surface Area of a Cone A right circular cone is generated by revolving the region bounded by $y = 3x/4$, $y = 3$, and $x = 0$ about the y-axis. Find the lateral surface area of the cone.

58. Lateral Surface Area of a Cone A right circular cone is generated by revolving the region bounded by $y = hx/r$, $y = h$, and $x = 0$ about the y-axis. Verify that the lateral surface area of the cone is $S = \pi r\sqrt{r^2 + h^2}$.

59. Using a Sphere Find the area of the segment of a sphere formed by revolving the graph of $y = \sqrt{9 - x^2}$, $0 \le x \le 2$, about the y-axis.

60. Using a Sphere Find the area of the segment of a sphere formed by revolving the graph of $y = \sqrt{r^2 - x^2}$, $0 \le x \le a$, about the y-axis. Assume that $a < r$.

61. Modeling Data The circumference C (in inches) of a vase is measured at three-inch intervals starting at its base. The measurements are shown in the table, where y is the vertical distance in inches from the base.

y	0	3	6	9	12	15	18
C	50	65.5	70	66	58	51	48

(a) Use the data to approximate the volume of the vase by summing the volumes of approximating disks.

(b) Use the data to approximate the outside surface area (excluding the base) of the vase by summing the outside surface areas of approximating frustums of right circular cones.

(c) Use the regression capabilities of a graphing utility to find a cubic model for the points (y, r), where $r = C/(2\pi)$. Use the graphing utility to plot the points and graph the model.

(d) Use the model in part (c) and the integration capabilities of a graphing utility to approximate the volume and outside surface area of the vase. Compare the results with your answers in parts (a) and (b).

62. Modeling Data Property bounded by two perpendicular roads and a stream is shown in the figure. All distances are measured in feet.



(a) Use the regression capabilities of a graphing utility to fit a fourth-degree polynomial to the path of the stream.

(b) Use the model in part (a) to approximate the area of the property in acres.

(c) Use the integration capabilities of a graphing utility to find the length of the stream that bounds the property.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

63. Volume and Surface Area Let R be the region bounded by $y = 1/x$, the x-axis, $x = 1$, and $x = b$, where $b > 1$. Let D be the solid formed when R is revolved about the x-axis.

(a) Find the volume V of D.

(b) Write a definite integral that represents the surface area S of D.

(c) Show that V approaches a finite limit as $b \to \infty$.

(d) Show that $S \to \infty$ as $b \to \infty$.

64. Arc Length Show that

$$\int_{-1}^{1} \frac{1}{\sqrt{1 - x^2}}\,dx = \pi$$

without evaluating the antiderivative of

$$\frac{1}{\sqrt{1 - x^2}}.$$

Approximating Arc Length or Surface Area **In Exercises 65–68, (a) write the definite integral for finding the indicated arc length or surface area, (b) explain why the integral does not satisfy the definition of a definite integral, and (c) use the integration capabilities of a graphing utility to approximate the arc length or surface area. (You will learn how to evaluate this type of integral in Section 8.8.)**

65. Length of Pursuit A fleeing object leaves the origin and moves up the y-axis (see figure). At the same time, a pursuer leaves the point $(1, 0)$ and always moves toward the fleeing object. The pursuer's speed is twice that of the fleeing object. The equation of the path is modeled by

$$y = \frac{1}{3}(x^{3/2} - 3x^{1/2} + 2).$$

How far has the fleeing object traveled when it is caught? Show that the pursuer has traveled twice as far.



Figure for 65



Figure for 66

66. Bulb Design An ornamental light bulb is designed by revolving the graph of

$$y = \frac{1}{3}x^{1/2} - x^{3/2}, \quad 0 \le x \le \frac{1}{3}$$

about the x-axis, where x and y are measured in feet (see figure). Find the surface area of the bulb and use the result to approximate the amount of glass needed to make the bulb. Assume that the thickness of the glass is 0.015 inch.

67. Astroid Find the area of the surface formed by revolving the portion in the first quadrant of the graph of $x^{2/3} + y^{2/3} = 4$, $0 \le y \le 8$, about the y-axis.



Figure for 67



Figure for 68

68. Using a Loop Consider the graph of

$$y^2 = \frac{1}{12}x(4 - x)^2$$

shown in the figure. Find the area of the surface formed when the loop of this graph is revolved about the x-axis.

69. Suspension Bridge A cable for a suspension bridge has the shape of a parabola with equation $y = kx^2$. Let h represent the height of the cable from its lowest point to its highest point and let $2w$ represent the total span of the bridge (see figure). Show that the length C of the cable is given by

$$C = 2\int_0^w \sqrt{1 + \left(\frac{4h^2}{w^2}\right)x^2}\,dx.$$



70. Suspension Bridge The Humber Bridge, located in the United Kingdom and opened in 1981, has a main span of about 1400 meters. Each of its towers has a height of about 155 meters. Use these dimensions, the integral in Exercise 69, and the integration capabilities of a graphing utility to approximate the length of a parabolic cable along the main span.

71. Arc Length and Area Let C be the curve given by $f(x) = \cosh x$ for $0 \le x \le t$, where $t > 0$. Show that the arc length of C is equal to the area bounded by C and the x-axis. Identify another curve on the interval $0 \le x \le t$ with this property.

PUTNAM EXAM CHALLENGE

72. Find the length of the curve $y^2 = x^3$ from the origin to the point where the tangent makes an angle of 45° with the x-axis.

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

7.5 Work

GO DIGITAL

- Find the work done by a constant force.
- Find the work done by a variable force.

Work Done by a Constant Force

The concept of work is important to scientists and engineers for determining the energy needed to perform various jobs. For instance, it is useful to know the amount of work done when a crane lifts a steel girder, when a spring is compressed, when a rocket is propelled into the air, or when a truck pulls a load along a highway.

In general, **work** is done by a force when it moves an object. If the force applied to the object is *constant,* then the work done is a product of the force and the distance the object moves in the direction of the force.

Definition of Work Done by a Constant Force

If an object is moved a distance D in the direction of an applied constant force F, then the **work** W done by the force is defined as $W = FD$.

There are four fundamental types of forces—gravitational, electromagnetic, strong nuclear, and weak nuclear. A **force** can be thought of as a *push* or a *pull*; a force changes the state of rest or state of motion of a body. For gravitational forces on Earth, it is common to use units of measure corresponding to the weight of an object.

EXAMPLE 1 **Lifting an Object**

Determine the work done in lifting a 50-pound object 4 feet.

Solution The magnitude of the required force F is the weight of the object, as shown in Figure 7.46. So, the work done in lifting the object 4 feet is

$$W = FD = 50(4) = 200 \text{ foot-pounds.}$$



The work done in lifting a 50-pound object 4 feet is 200 foot-pounds.

Figure 7.46

In the U.S. measurement system, work is typically expressed in foot-pounds (ft-lb), inch-pounds, or foot-tons. In the International System of Units (SI), the basic unit of force is the **newton**—the force required to produce an acceleration of 1 meter per second per second on a mass of 1 kilogram. In this system, work is typically expressed in newton-meters, also called joules. In another system, the centimeter-gram-second (C-G-S) system, the basic unit of force is the **dyne**—the force required to produce an acceleration of 1 centimeter per second per second on a mass of 1 gram. In this system, work is typically expressed in dyne-centimeters, also called ergs, or in joules. The table below summarizes the units of measure that are commonly used to express the work done and lists several conversion factors.

System of Measurement	Measure of Work	Measure of Force	Measure of Distance
U.S.	foot-pound (ft-lb)	pound (lb)	foot (ft)
International	joule (J)	newton (N)	meter (m)
C-G-S	erg	dyne (dyn)	centimeter (cm)
Conversions: 1 ft-lb $\approx$ 1.35582 J $= 1.35582 \times 10^7$ ergs 1 J $= 10^7$ ergs $\approx$ 0.73756 ft-lb		1 N $= 10^5$ dyn $\approx$ 0.22481 lb 1 lb $\approx$ 4.44822 N	

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Work Done by a Variable Force

In Example 1, the force involved was *constant*. When a *variable* force is applied to an object, calculus is needed to determine the work done, because the amount of force changes as the object changes position. For instance, the force required to compress a spring increases as the spring is compressed.

Consider an object that is moved along a straight line from $x = a$ to $x = b$ by a continuously varying force $F(x)$. Let Δ be a partition that divides the interval $[a, b]$ into n subintervals determined by

$$a = x_0 < x_1 < x_2 < \cdots < x_n = b$$

and let $\Delta x_i = x_i - x_{i-1}$. For each i, choose c_i such that

$$x_{i-1} \le c_i \le x_i.$$

Then at c_i, the force is $F(c_i)$. Because F is continuous, you can approximate the work done in moving the object through the ith subinterval by the increment

$$\Delta W_i = F(c_i)\Delta x_i$$

as shown in Figure 7.47. So, the total work done as the object moves from $x = a$ to $x = b$ is approximated by

$$W \approx \sum_{i=1}^{n} \Delta W_i = \sum_{i=1}^{n} F(c_i)\Delta x_i.$$

This approximation appears to become better and better as $\|\Delta\| \to 0$ $(n \to \infty)$. So, the work done is

$$W = \lim_{\|\Delta\|\to 0} \sum_{i=1}^{n} F(c_i)\Delta x_i = \int_a^b F(x)\,dx.$$



The amount of force changes as an object changes position (Δx).
Figure 7.47

Definition of Work Done by a Variable Force

If an object is moved along a straight line by a continuously varying force $F(x)$, then the **work** W done by the force as the object is moved from

$$x = a \quad \text{to} \quad x = b$$

is given by

$$W = \lim_{\|\Delta\|\to 0} \sum_{i=1}^{n} \Delta W_i = \int_a^b F(x)\,dx.$$

EMILIE DE BRETEUIL (1706–1749)

A major work by Breteuil was the translation of Newton's "Philosophiae Naturalis Principia Mathematica" into French. Her translation and commentary greatly contributed to the acceptance of Newtonian science in Europe.

See LarsonCalculus.com to read more of this biography.

The remaining examples in this section use some well-known physical laws. The discoveries of many of these laws occurred during the same period in which calculus was being developed. In fact, during the seventeenth and eighteenth centuries, there was little difference between physicists and mathematicians. One such physicist-mathematician was Emilie de Breteuil. Breteuil was instrumental in synthesizing the work of many other scientists, including Newton, Leibniz, Huygens, Kepler, and Descartes. Her physics text *Institutions* was widely used for many years.

Bettmann/Getty Images

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The three laws of physics listed below were developed by Robert Hooke (1635–1703), Isaac Newton (1642–1727), and Charles Coulomb (1736–1806).

1. **Hooke's Law:** The force F required to compress or stretch a spring (within its elastic limits) is proportional to the distance d that the spring is compressed or stretched from its original length. That is,

$$F = kd$$

where the constant of proportionality k (the spring constant) depends on the specific nature of the spring.

2. **Newton's Law of Universal Gravitation:** The force F of attraction between two particles of masses m_1 and m_2 is proportional to the product of the masses and inversely proportional to the square of the distance d between the two particles. That is,

$$F = G\frac{m_1 m_2}{d^2}.$$

When m_1 and m_2 are in kilograms and d in meters, F will be in newtons for a value of $G = 6.67 \times 10^{-11}$ cubic meter per kilogram-second squared, where G is the **gravitational constant.**

3. **Coulomb's Law:** The force F between two charges q_1 and q_2 in a vacuum is proportional to the product of the charges and inversely proportional to the square of the distance d between the two charges. That is,

$$F = k\frac{q_1 q_2}{d^2}.$$

When q_1 and q_2 are given in electrostatic units and d in centimeters, F will be in dynes for a value of $k = 1$.

EXAMPLE 2 Compressing a Spring

See LarsonCalculus.com for an interactive version of this type of example.

A force of 30 newtons compresses a spring 0.3 meter from its natural length of 1.5 meters. Find the work done in compressing the spring an additional 0.3 meter.

Solution By Hooke's Law, the force $F(x)$ required to compress the spring x units (from its natural length) is $F(x) = kx$. Because $F(0.3) = 30$, it follows that

$$F(0.3) = (k)(0.3) \quad \Rightarrow \quad 30 = 0.3k \quad \Rightarrow \quad 100 = k.$$

So, $F(x) = 100x$, as shown in Figure 7.48. To find the increment of work, assume that the force required to compress the spring over a small increment Δx is nearly constant. So, the increment of work is

$$\Delta W = (\text{force})(\text{distance increment}) = (100x)\Delta x.$$

Because the spring is compressed from $x = 0.3$ to $x = 0.6$ meter less than its natural length, the work required is

$$W = \int_a^b F(x)\,dx = \int_{0.3}^{0.6} 100x\,dx = 50x^2\Big]_{0.3}^{0.6} = 18 - 4.5 = 13.5 \text{ joules}.$$

Note that you do *not* integrate from $x = 0$ to $x = 0.6$ because you were asked to determine the work done in compressing the spring an *additional* 0.3 meter (not including the first 0.3 meter). ■



Figure 7.48

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 3 Moving a Space Module into Orbit

A space module weighs 15 tons on the surface of Earth. How much work is done in propelling the module to a height of 800 miles above Earth, as shown in Figure 7.49? (Use 4000 miles as the radius of Earth. Do not consider the effect of air resistance or the weight of the propellant.)



Figure 7.49

Solution Because the weight of a body varies inversely as the square of its distance from the center of Earth, the force $F(x)$ exerted by gravity is

$$F(x) = \frac{C}{x^2}$$

where C is the constant of proportionality. Because the module weighs 15 tons on the surface of Earth and the radius of Earth is approximately 4000 miles, you have

$$15 = \frac{C}{(4000)^2} \quad \Rightarrow \quad 240{,}000{,}000 = C.$$

So, the increment of work is

$$\Delta W = (\text{force})(\text{distance increment}) = \frac{240{,}000{,}000}{x^2}\,\Delta x.$$

Finally, because the module is propelled from $x = 4000$ to $x = 4800$ miles, the total work done is

$$\begin{aligned} W &= \int_a^b F(x)\,dx && \text{Formula for work} \\ &= \int_{4000}^{4800} \frac{240{,}000{,}000}{x^2}\,dx \\ &= \frac{-240{,}000{,}000}{x}\Bigg]_{4000}^{4800} && \text{Integrate.} \\ &= -50{,}000 + 60{,}000 \\ &= 10{,}000 \text{ mile-tons} \\ &= 1.056 \times 10^{11} \text{ foot-pounds.} && \text{1 mile} = \text{5280 feet; 1 ton} = \text{2000 pounds} \end{aligned}$$

In SI units, using a conversion factor of 1 foot-pound ≈ 1.35582 joules, the work done is

$$W \approx 1.432 \times 10^{11} \text{ joules.}$$

The solutions to Examples 2 and 3 conform to our development of work as the summation of increments in the form

$$\Delta W = (\text{force})(\text{distance increment}) = (F)(\Delta x).$$

Another way to formulate the increment of work is

$$\Delta W = (\text{force increment})(\text{distance}) = (\Delta F)(x).$$

This second interpretation of ΔW is useful in problems involving the movement of nonrigid substances such as fluids and chains.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 4 Emptying a Tank of Oil

A spherical tank of radius 8 feet is half full of oil that weighs 50 pounds per cubic foot. Find the work required to pump all of the oil out through a hole in the top of the tank.



Figure 7.50

Solution Consider the oil to be subdivided into disks of thickness Δy and radius x, as shown in Figure 7.50. Because the increment of force for each disk is given by its weight, you have

$$\begin{aligned}\Delta F &= \text{weight} \\ &= \left(\frac{50 \text{ pounds}}{\text{cubic foot}}\right)(\text{volume}) \\ &= 50(\pi x^2 \Delta y) \text{ pounds.}\end{aligned}$$

For a circle of radius 8 and center at (0, 8), you have

$$\begin{aligned}x^2 + (y - 8)^2 &= 8^2 \\ x^2 &= 16y - y^2\end{aligned}$$

and you can write the force increment as

$$\begin{aligned}\Delta F &= 50(\pi x^2 \Delta y) \\ &= 50\pi(16y - y^2)\Delta y.\end{aligned}$$

In Figure 7.50, note that a disk y feet from the bottom of the tank must be moved a distance of $(16 - y)$ feet. So, the increment of work is

$$\begin{aligned}\Delta W &= (\Delta F)(16 - y) \\ &= [50\pi(16y - y^2)\Delta y](16 - y) \\ &= 50\pi(256y - 32y^2 + y^3)\Delta y.\end{aligned}$$

Because the tank is half full, y ranges from 0 to 8 feet, and the work required to empty the tank is

$$\begin{aligned}W &= \int_0^8 50\pi(256y - 32y^2 + y^3)\, dy \\ &= 50\pi\left[128y^2 - \frac{32}{3}y^3 + \frac{y^4}{4}\right]_0^8 \\ &= 50\pi\left(\frac{11{,}264}{3}\right) \\ &\approx 589{,}782 \text{ foot-pounds.}\end{aligned}$$

To estimate the reasonableness of the result in Example 4, consider that the weight of the oil in the tank is

$$\left(\frac{1}{2}\right)(\text{volume})(\text{density}) = \frac{1}{2}\left(\frac{4}{3}\pi 8^3\right)(50) \approx 53{,}616.5 \text{ pounds.}$$

Lifting the entire half-tank of oil 8 feet would involve work of

$$\begin{aligned}W &= FD \qquad \text{Formula for work done by a constant force} \\ &\approx (53{,}616.5)(8) \\ &= 428{,}932 \text{ foot-pounds.}\end{aligned}$$

Because the oil is actually lifted between 8 and 16 feet, it seems reasonable that the work done is about 589,782 foot-pounds.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Work required to raise one end of the chain

Figure 7.51

EXAMPLE 5 Lifting a Chain

A 20-foot chain weighing 5 pounds per foot is lying coiled on the ground. How much work is required to raise one end of the chain to a height of 20 feet so that it is fully extended, as shown in Figure 7.51?

Solution Imagine that the chain is divided into small sections, each of length Δy. Then the weight of each section is the increment of force

$$\Delta F = (\text{weight}) = \left(\frac{5 \text{ pounds}}{\text{foot}}\right)(\text{length}) = 5\,\Delta y.$$

Because a typical section (initially on the ground) is raised to a height of y, the increment of work is

$$\Delta W = (\text{force increment})(\text{distance}) = (5\,\Delta y)y = 5y\,\Delta y.$$

Because y ranges from 0 to 20 feet, the total work required to raise the chain is

$$W = \int_0^{20} 5y\,dy = \frac{5y^2}{2}\Big]_0^{20} = \frac{5(400)}{2} = 1000 \text{ foot-pounds.}$$



Work done by expanding gas

Figure 7.52

In the next example, you will consider a piston of radius r in a cylindrical casing, as shown in Figure 7.52. As the gas in the cylinder expands, the piston moves, and work is done. If p represents the pressure of the gas (in pounds per square foot) against the piston head and V represents the volume of the gas (in cubic feet), then the work increment involved in moving the piston Δx feet is

$$\Delta W = (\text{force})(\text{distance increment}) = F\,\Delta x = p(\pi r^2)\Delta x = p\,\Delta V.$$

So, as the volume of the gas expands from V_0 to V_1, the work done in moving the piston is

$$W = \int_{V_0}^{V_1} p\,dV.$$

Assuming the pressure of the gas to be inversely proportional to its volume, you have $p = k/V$ and the integral for work becomes

$$W = \int_{V_0}^{V_1} \frac{k}{V}\,dV.$$

EXAMPLE 6 Work Done by an Expanding Gas

A quantity of gas with an initial volume of 1 cubic foot and a pressure of 500 pounds per square foot expands to a volume of 2 cubic feet. Find the work done by the gas. (Assume that the pressure is inversely proportional to the volume.)

Solution Because $p = k/V$ and $p = 500$ when $V = 1$, you have $k = 500$. So, the work done by the gas is

$$\begin{aligned} W &= \int_{V_0}^{V_1} \frac{k}{V}\,dV \\ &= \int_1^2 \frac{500}{V}\,dV \\ &= 500 \ln|V|\Big]_1^2 \\ &\approx 346.6 \text{ foot-pounds.} \end{aligned}$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

7.5 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain how you know when work is done by a force.
2. Describe the difference between finding the work done by a constant force and finding the work done by a variable force.
3. Explain what each variable in Hooke's Law represents.

   $F = kd$

4. Explain two ways to write the increment of work.

Constant Force **In Exercises 5–8, determine the work done by the constant force.**

5. A 1200-pound steel beam is lifted 40 feet.
6. An electric hoist lifts a 3000-pound car 6 feet.
7. A force of 112 newtons is required to slide a cement block 8 meters in a construction project.
8. The locomotive of a freight train pulls its cars with a constant force of 7 tons for a distance of one-quarter mile.

Hooke's Law **In Exercises 9–14, use Hooke's Law to determine the work done by the variable force in the spring problem.**

9. A force of 5 pounds compresses a 15-inch spring a total of 3 inches. How much work is done in compressing the spring 7 inches?
10. A force of 250 newtons stretches a spring 30 centimeters. How much work is done in stretching the spring from 20 centimeters to 50 centimeters?
11. A force of 20 pounds stretches a spring 9 inches in an exercise machine. Find the work done in stretching the spring 1 foot from its natural position.
12. An overhead garage door has two springs, one on each side of the door. A force of 15 pounds is required to stretch each spring 1 foot. Because of the pulley system, the springs stretch only one-half the distance the door travels. The door moves a total of 8 feet, and the springs are at their natural length when the door is open. Find the work done by the pair of springs.
13. Eighteen foot-pounds of work is required to stretch a spring 4 inches from its natural length. Find the work required to stretch the spring an additional 3 inches.
14. Six joules of work is required to stretch a spring 0.5 meter from its natural length. Find the work required to stretch the spring an additional 0.25 meter.
15. **Propulsion** Neglecting air resistance and the weight of the propellant, determine the work done in propelling a five-ton satellite to a height of (a) 100 miles above Earth and (b) 300 miles above Earth.
16. **Propulsion** Use the information in Exercise 15 to write the work W of the propulsion system as a function of the height h of the satellite above Earth. Find the limit (if it exists) of W as h approaches infinity.
17. **Propulsion** Neglecting air resistance and the weight of the propellant, determine the work done in propelling a 10-ton satellite to a height of (a) 11,000 miles above Earth and (b) 22,000 miles above Earth.
18. **Propulsion** A lunar module weighs 12 tons on the surface of Earth. How much work is done in propelling the module from the surface of the moon to a height of 50 miles? Consider the radius of the moon to be 1100 miles and its force of gravity to be one-sixth that of Earth.
19. **Pumping Water** A rectangular tank with a base 4 feet by 5 feet and a height of 4 feet is full of water (see figure). The water weighs 62.4 pounds per cubic foot. How much work is done in pumping water out over the top edge in order to empty (a) half of the tank and (b) all of the tank?



20. **Think About It** Explain why the answer in part (b) of Exercise 19 is not twice the answer in part (a).
21. **Pumping Water** A cylindrical water tank 4 meters high with a radius of 2 meters is buried so that the top of the tank is 1 meter below ground level (see figure). How much work is done in pumping a full tank of water up to ground level? The water weighs 9800 newtons per cubic meter.



Figure for 21



Figure for 22

22. **Pumping Water** Suppose the tank in Exercise 21 is located on a tower so that the bottom of the tank is 10 meters above a stream (see figure). How much work is done in filling the tank half full of water through a hole in the bottom, using water from the stream?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

23. Pumping Water An open tank has the shape of a right circular cone (see figure). The tank is 8 feet across the top and 6 feet high. How much work is done in emptying the tank by pumping the water over the top edge?



24. Pumping Water Water is pumped in through the bottom of the tank in Exercise 23. How much work is done to fill the tank

(a) to a depth of 2 feet?

(b) from a depth of 4 feet to a depth of 6 feet?

25. Pumping Water A hemispherical tank of radius 6 feet is positioned so that its base is circular. How much work is required to fill the tank with water through a hole in the base when the water source is at the base?

26. Pumping Diesel Fuel The fuel tank on a truck has trapezoidal cross sections with the dimensions (in feet) shown in the figure. Assume that the engine is approximately 3 feet above the top of the fuel tank and that diesel fuel weighs approximately 53.1 pounds per cubic foot. Find the work done by the fuel pump in raising a full tank of fuel to the level of the engine.



Pumping Gasoline **In Exercises 27 and 28, find the work done in pumping gasoline that weighs 42 pounds per cubic foot.**

27. A cylindrical gasoline tank 3 feet in diameter and 4 feet long is carried on the back of a truck and is used to fuel tractors. The axis of the tank is horizontal. The opening on the tractor tank is 5 feet above the top of the tank in the truck. Find the work done in pumping the entire contents of the fuel tank into the tractor.

28. The top of a cylindrical gasoline storage tank at a service station is 4 feet below ground level. The axis of the tank is horizontal and its diameter and length are 5 feet and 12 feet, respectively. Find the work done in pumping the entire contents of the full tank to a height of 3 feet above ground level.

Winding a Chain **In Exercises 29–32, consider a 20-foot chain that weighs 3 pounds per foot hanging from a winch 20 feet above ground level. Find the work done by the winch in winding up the specified amount of chain.**

29. Wind up the entire chain.

30. Wind up one-third of the chain.

31. Run the winch until the bottom of the chain is at the 10-foot level.

32. Wind up the entire chain with a 500-pound load attached to it.

Lifting a Chain **In Exercises 33 and 34, consider a 15-foot hanging chain that weighs 3 pounds per foot. Find the work done in lifting the chain vertically to the indicated position.**

33. Take the bottom of the chain and raise it to the 15-foot level, leaving the chain doubled and still hanging vertically (see figure).



34. Repeat Exercise 33 raising the bottom of the chain to the 12-foot level.

Exploring Concepts

35. Does it take any work to push an object that does not move? Explain.

36. In Example 1, 200 foot-pounds of work was needed to lift the 50-pound object 4 feet vertically off the ground. Does it take an additional 200 foot-pounds of work to lift the object another 4 feet vertically? Explain your reasoning.

37. Newton's Law of Universal Gravitation Consider two particles of masses m_1 and m_2. The position of the first particle is fixed, and the distance between the particles is a units. Using Newton's Law of Universal Gravitation, find the work needed to move the second particle so that the distance between the particles increases to b units.

38. Conjecture Use Newton's Law of Universal Gravitation to make a conjecture about what happens to the force of attraction between two particles when the distance between them is multiplied by a positive number n.

39. Electric Force Two electrons repel each other with a force that varies inversely as the square of the distance between them. One electron is fixed at the point $(2, 4)$. Find the work done in moving the second electron from $(-2, 4)$ to $(1, 4)$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

40. HOW DO YOU SEE IT? The graphs show the force F_i (in pounds) required to move an object 9 feet along the x-axis. Order the force functions from the one that yields the least work to the one that yields the most work without doing any calculations. Explain your reasoning.

(a)



(b)



(c)



(d)



41. Ordering Forces Verify your answer to Exercise 40 by calculating the work for each force function.

42. Comparing Work Order the following from least to greatest in terms of total work done.

(a) A 60-pound box of books is lifted 3 feet.

(b) An 80-pound box of books is lifted 1 foot, and then a 40-pound box of books is lifted 1 foot.

(c) A 60-pound box is held 3 feet in the air for 3 minutes.

Boyle's Law **In Exercises 43 and 44, find the work done by the gas for the given volume and pressure. Assume that the pressure is inversely proportional to the volume. (See Example 6.)**

43. A quantity of gas with an initial volume of 2 cubic feet and a pressure of 1000 pounds per square foot expands to a volume of 3 cubic feet.

44. A quantity of gas with an initial volume of 1 cubic foot and a pressure of 2500 pounds per square foot expands to a volume of 3 cubic feet.

Hydraulic Press **In Exercises 45–48, use the integration capabilities of a graphing utility to approximate the work done by a press in a manufacturing process. A model for the variable force F (in pounds) and the distance x (in feet) over which the press moves are given.**

	Force	Interval
45.	$F(x) = 1000[1.8 - \ln(x + 1)]$	$0 \le x \le 5$
46.	$F(x) = \dfrac{e^{x^2} - 1}{100}$	$0 \le x \le 4$
47.	$F(x) = 100x\sqrt{125 - x^3}$	$0 \le x \le 5$
48.	$F(x) = 1000 \sinh x$	$0 \le x \le 2$

49. Modeling Data The hydraulic cylinder on a woodsplitter has a 4-inch bore (diameter) and a stroke of 2 feet. The hydraulic pump creates a maximum pressure of 2000 pounds per square inch. Therefore, the maximum force created by the cylinder is $2000(\pi \cdot 2^2) = 8000\pi$ pounds.

(a) Find the work done through one extension of the cylinder, given that the maximum force is required.

(b) The force exerted in splitting a piece of wood is variable. Measurements of the force obtained in splitting a piece of wood are shown in the table. The variable x measures the extension of the cylinder in feet, and F is the force in pounds. Use the regression capabilities of a graphing utility to find a fourth-degree polynomial model for the data. Plot the data and graph the model.

x	0	$\frac{1}{3}$	$\frac{2}{3}$	1	$\frac{4}{3}$	$\frac{5}{3}$	2
$F(x)$	0	20,000	22,000	15,000	10,000	5000	0

(c) Use the model in part (b) to approximate the extension of the cylinder when the force is maximum.

(d) Use the model in part (b) to approximate the work done in splitting the piece of wood.

SECTION PROJECT

Pyramid of Khufu

The Pyramid of Khufu (also known as the Great Pyramid of Giza) is the oldest of the Seven Wonders of the Ancient World. It is also the tallest of the three Giza pyramids in Egypt. The pyramid took 20 years to construct, ending around 2560 B.C. When it was built, it had a height of 481 feet and a square base with side lengths of 756 feet. Assume that the stone used to build it weighed 150 pounds per cubic foot.

(a) How much work was required to build the pyramid? Consider only vertical distance.

(b) Suppose that the pyramid builders worked 12 hours each day for 330 days a year for 20 years and that each worker did 200 foot-pounds of work per hour. Approximately how many workers were needed to build the pyramid?

Dan Oldenburg/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

7.6 Moments, Centers of Mass, and Centroids

GO DIGITAL

- Define mass.
- Find the center of mass in a one-dimensional system.
- Find the center of mass in a two-dimensional system.
- Find the center of mass of a planar lamina.
- Use the Theorem of Pappus to find the volume of a solid of revolution.

Mass

In this section, you will study several important applications of integration that are related to mass. Mass is a measure of a body's resistance to changes in motion, and it is independent of the particular gravitational system in which the body is located. However, because so many applications involving mass occur on Earth's surface, an object's mass is sometimes equated with its weight. This is not technically correct. Weight is a type of force and as such is dependent on gravity. Force and mass are related by the equation

$$\text{Force} = (\text{mass})(\text{acceleration}).$$

The table below lists some commonly used measures of mass and force, together with their conversion factors.

System of Measurement	Measure of Mass	Measure of Force
U.S.	Slug	Pound $=$ (slug)(ft/sec^2)
International	Kilogram	Newton $=$ (kilogram)(m/sec^2)
C-G-S	Gram	Dyne $=$ (gram)(cm/sec^2)
Conversions:		
1 pound $\approx$ 4.44822 newtons		1 slug $\approx$ 14.59390 kilogram
1 newton $\approx$ 0.22481 pound		1 kilogram $\approx$ 0.0685218 slug
1 dyne $\approx$ 0.0000022481 pound		1 gram $\approx$ 0.0000685218 slug
1 dyne $=$ 0.00001 newton		1 foot $=$ 0.3048 meter

EXAMPLE 1 Mass on the Surface of Earth

Find the mass (in slugs) of an object whose weight at sea level is 1 pound.

Solution Use 32 feet per second per second as the acceleration due to gravity.

$$\text{Mass} = \frac{\text{force}}{\text{acceleration}} \qquad \text{Force} = (\text{mass})(\text{acceleration})$$

$$= \frac{1 \text{ pound}}{32 \text{ feet per second per second}}$$

$$= 0.03125 \frac{\text{pound}}{\text{foot per second per second}}$$

$$= 0.03125 \text{ slug}$$

Because many applications involving mass occur on Earth's surface, this amount of mass is called a **pound mass.** ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Center of Mass in a One-Dimensional System

You will now consider two types of moments of a mass—the **moment about a point** and the **moment about a line.** To define these two moments, consider an idealized situation in which a mass m is concentrated at a point. If x is the distance between this point mass and another point P, then the **moment of m about the point P** is

$$\text{Moment} = mx$$

and x is the **length of the moment arm.**



The seesaw will balance when the left and the right moments are equal.
Figure 7.53

The concept of moment can be demonstrated simply by a seesaw, as shown in Figure 7.53. A child of mass 20 kilograms sits 2 meters to the left of fulcrum P, and an older child of mass 30 kilograms sits 2 meters to the right of P. From experience, you know that the seesaw will begin to rotate clockwise, moving the larger child down. This rotation occurs because the moment produced by the child on the left is less than the moment produced by the child on the right.

$$\text{Left moment} = (20)(2) = 40 \text{ kilogram-meters}$$
$$\text{Right moment} = (30)(2) = 60 \text{ kilogram-meters}$$

To balance the seesaw, the two moments must be equal. For example, if the larger child moved to a position $\frac{4}{3}$ meters from the fulcrum, then the seesaw would balance, because each child would produce a moment of 40 kilogram-meters.

To generalize this, you can introduce a coordinate line on which the origin corresponds to the fulcrum, as shown in Figure 7.54. Several point masses are located on the x-axis. The measure of the tendency of this system to rotate about the origin is the **moment about the origin,** and it is defined as the sum of the n products $m_i x_i$. The moment about the origin is denoted by M_0 and can be written as

$$M_0 = m_1x_1 + m_2x_2 + \cdots + m_nx_n.$$

If M_0 is 0, then the system is said to be in **equilibrium.**



If $m_1x_1 + m_2x_2 + \cdots + m_nx_n = 0$, then the system is in equilibrium.
Figure 7.54

REMARK Note the use of the summation properties

$$\sum_{i=1}^{n} ka_i = k\sum_{i=1}^{n} a_i$$

where k is a constant, and

$$\sum_{i=1}^{n} (a_i \pm b_i) = \sum_{i=1}^{n} a_i \pm \sum_{i=1}^{n} b_i$$

to rewrite and solve for $\bar{x}$.

For a system that is not in equilibrium, the **center of mass** is defined as the point $\bar{x}$ at which the fulcrum could be relocated to attain equilibrium. If the system were translated $\bar{x}$ units, then each coordinate x_i would become

$$(x_i - \bar{x}) \qquad \text{Translate each } x\text{-coordinate } \bar{x} \text{ units.}$$

and because the moment of the translated system is 0, you have

$$\sum_{i=1}^{n} m_i(x_i - \bar{x}) = 0 \quad \Rightarrow \quad \sum_{i=1}^{n} m_ix_i - \sum_{i=1}^{n} m_i\bar{x} = 0.$$

Solving for $\bar{x}$ produces

$$\bar{x} = \frac{\sum_{i=1}^{n} m_ix_i}{\sum_{i=1}^{n} m_i} = \frac{\text{moment of system about origin}}{\text{total mass of system}}.$$

When $m_1x_1 + m_2x_2 + \cdots + m_nx_n = 0$, the system is in equilibrium.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Moment and Center of Mass: One-Dimensional System

Let the point masses $m_1, m_2, \ldots, m_n$ be located at $x_1, x_2, \ldots, x_n$.

1. The **moment about the origin** is

$$M_0 = m_1x_1 + m_2x_2 + \cdots + m_nx_n.$$

2. The **center of mass** is

$$\bar{x} = \frac{M_0}{m}$$

where $m = m_1 + m_2 + \cdots + m_n$ is the **total mass** of the system.

EXAMPLE 2 The Center of Mass of a Linear System

Find the center of mass of the linear system shown in Figure 7.55.



Figure 7.55

Solution The moment about the origin is

$$\begin{aligned} M_0 &= m_1x_1 + m_2x_2 + m_3x_3 + m_4x_4 \\ &= 10(-5) + 15(0) + 5(4) + 10(7) && \text{See Figure 7.55.} \\ &= -50 + 0 + 20 + 70 \\ &= 40. && \text{Moment about origin} \end{aligned}$$

Because the total mass of the system is

$$m = 10 + 15 + 5 + 10 = 40 \qquad \text{Total mass}$$

the center of mass is

$$\bar{x} = \frac{M_0}{m} = \frac{40}{40} = 1. \qquad \text{Center of mass}$$

Note that the point masses will be in equilibrium when the fulcrum is located at $x = 1$. ■

Rather than defining the moment of a mass, you could define the moment of a *force*. In this context, the center of mass is called the **center of gravity.** Consider a system of point masses $m_1, m_2, \ldots, m_n$ that is located at $x_1, x_2, \ldots, x_n$. Then, because

$$\text{force} = (\text{mass})(\text{acceleration})$$

the total force of the system is

$$F = m_1a + m_2a + \cdots + m_na = ma.$$

The **torque** (moment) about the origin is

$$T_0 = (m_1a)x_1 + (m_2a)x_2 + \cdots + (m_na)x_n = M_0a$$

and the **center of gravity** is

$$\frac{T_0}{F} = \frac{M_0a}{ma} = \frac{M_0}{m} = \bar{x}.$$

So, the center of gravity and the center of mass have the same location.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Center of Mass in a Two-Dimensional System

To extend the concept of moment to two dimensions, consider a system of masses located in the xy-plane at the points

$$(x_1, y_1), (x_2, y_2), \ldots, (x_n, y_n)$$

as shown in Figure 7.56. Rather than defining a single moment (with respect to the origin), two moments are defined—one with respect to the x-axis and one with respect to the y-axis.



In a two-dimensional system, there is a moment about the y-axis M_y and a moment about the x-axis M_x.
Figure 7.56

Moments and Center of Mass: Two-Dimensional System

Let the point masses $m_1, m_2, \ldots, m_n$ be located at $(x_1, y_1), (x_2, y_2), \ldots, (x_n, y_n)$.

1. The **moment about the y-axis** is
$$M_y = m_1x_1 + m_2x_2 + \cdots + m_nx_n.$$
2. The **moment about the x-axis** is
$$M_x = m_1y_1 + m_2y_2 + \cdots + m_ny_n.$$
3. The **center of mass** $(\bar{x}, \bar{y})$, or **center of gravity,** is
$$\bar{x} = \frac{M_y}{m} \quad \text{and} \quad \bar{y} = \frac{M_x}{m}$$
where
$$m = m_1 + m_2 + \cdots + m_n$$
is the **total mass** of the system.

The moment of a system of masses in the plane can be taken about any horizontal or vertical line. In general, the moment about a line is the sum of the product of the masses and the *directed distances* from the points to the line.

$$\text{Moment} = m_1(y_1 - b) + m_2(y_2 - b) + \cdots + m_n(y_n - b) \quad \text{Horizontal line } y = b$$
$$\text{Moment} = m_1(x_1 - a) + m_2(x_2 - a) + \cdots + m_n(x_n - a) \quad \text{Vertical line } x = a$$



Figure 7.57

EXAMPLE 3 The Center of Mass of a Two-Dimensional System

Find the center of mass of a system of point masses $m_1 = 6$, $m_2 = 3$, $m_3 = 2$, and $m_4 = 9$, located at $(3, -2)$, $(0, 0)$, $(-5, 3)$, and $(4, 2)$, respectively. (See Figure 7.57.)

Solution First, find m, M_y, and M_x.

$$m = 6 + 3 + 2 + 9 = 20 \quad \text{Total mass of system}$$
$$M_y = 6(3) + 3(0) + 2(-5) + 9(4) = 44 \quad \text{Moment about } y\text{-axis}$$
$$M_x = 6(-2) + 3(0) + 2(3) + 9(2) = 12 \quad \text{Moment about } x\text{-axis}$$

Next, use these values to find

$$\bar{x} = \frac{M_y}{m} = \frac{44}{20} = \frac{11}{5}$$

and

$$\bar{y} = \frac{M_x}{m} = \frac{12}{20} = \frac{3}{5}.$$

So, the center of mass is $\left(\frac{11}{5}, \frac{3}{5}\right)$.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



You can think of the center of mass $(\bar{x}, \bar{y})$ of a lamina as its balancing point. For a circular lamina, the center of mass is the center of the circle. For a rectangular lamina, the center of mass is the center of the rectangle.

Figure 7.58

Center of Mass of a Planar Lamina

So far in this section, you have assumed the total mass of a system to be distributed at discrete points in a plane or on a line. Now consider a thin, flat plate of material of constant density called a **planar lamina** (see Figure 7.58). **Density** is a measure of mass per unit of volume, such as grams per cubic centimeter. For planar laminas, however, density is considered to be a measure of mass per unit of area. Density is denoted by ρ, the lowercase Greek letter rho.

Consider an irregularly shaped planar lamina of uniform density ρ, bounded by the graphs of $y = f(x)$, $y = g(x)$, and $a \le x \le b$, as shown in Figure 7.59. The mass of this region is

$$\begin{aligned} m &= (\text{density})(\text{area}) \\ &= \rho \int_a^b [f(x) - g(x)]\,dx \\ &= \rho A \end{aligned}$$

where A is the area of the region. To find the center of mass of this lamina, partition the interval $[a, b]$ into n subintervals of equal width Δx. Let x_i be the center of the ith subinterval. You can approximate the portion of the lamina lying in the ith subinterval by a rectangle whose height is $h = f(x_i) - g(x_i)$. Because the density of the rectangle is ρ, its mass is

$$m_i = (\text{density})(\text{area}) = \rho[f(x_i) - g(x_i)]\,\Delta x.$$

Density Height Width



Planar lamina of uniform density ρ

Figure 7.59

Now, considering this mass to be located at the center (x_i, y_i) of the rectangle, the directed distance from the x-axis to (x_i, y_i) is $y_i = [f(x_i) + g(x_i)]/2$. So, the moment of m_i about the x-axis is

$$\begin{aligned} \text{Moment} &= (\text{mass})(\text{distance}) \\ &= m_i y_i \\ &= \rho[f(x_i) - g(x_i)]\Delta x\left[\frac{f(x_i) + g(x_i)}{2}\right]. \end{aligned}$$

Summing the moments and taking the limit as $n \to \infty$ suggest the definitions below.

Moments and Center of Mass of a Planar Lamina

Let f and g be continuous functions such that $f(x) \ge g(x)$ on $[a, b]$, and consider the planar lamina of uniform density ρ bounded by the graphs of $y = f(x)$, $y = g(x)$, and $a \le x \le b$.

1. **Moment about the x-axis:** $M_x = \rho \displaystyle\int_a^b \left[\frac{f(x) + g(x)}{2}\right][f(x) - g(x)]\,dx$

   Moment about the y-axis: $M_y = \rho \displaystyle\int_a^b x[f(x) - g(x)]\,dx$

2. **Center of mass** $(\bar{x}, \bar{y})$: $\bar{x} = \dfrac{M_y}{m}$ and $\bar{y} = \dfrac{M_x}{m}$

   Mass of the lamina: $m = \rho \displaystyle\int_a^b [f(x) - g(x)]\,dx$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 4 The Center of Mass of a Planar Lamina

See LarsonCalculus.com for an interactive version of this type of example.

Find the center of mass of the lamina of uniform density ρ bounded by the graph of $f(x) = 4 - x^2$ and the x-axis.

Solution Because the center of mass lies on the axis of symmetry, you know that $\bar{x} = 0$. Moreover, the mass of the lamina is

$$\begin{aligned} m &= \rho \int_{-2}^{2} (4 - x^2)\, dx \\ &= \rho \left[4x - \frac{x^3}{3} \right]_{-2}^{2} \\ &= \frac{32\rho}{3}. \end{aligned}$$

Mass of the lamina

To find the moment about the x-axis, place a representative rectangle in the region, as shown in the figure at the right. The distance from the x-axis to the center of this rectangle is

$$y_i = \frac{f(x)}{2} = \frac{4 - x^2}{2}.$$



Because the mass of the representative rectangle is

$$\rho f(x)\, \Delta x = \rho(4 - x^2)\, \Delta x$$

you have

$$\begin{aligned} M_x &= \rho \int_{-2}^{2} \frac{4 - x^2}{2}(4 - x^2)\, dx \\ &= \frac{\rho}{2} \int_{-2}^{2} (16 - 8x^2 + x^4)\, dx \\ &= \frac{\rho}{2} \left[16x - \frac{8x^3}{3} + \frac{x^5}{5} \right]_{-2}^{2} \\ &= \frac{256\rho}{15}. \end{aligned}$$

Moment about x-axis

Now, use M_x and m to find $\bar{y}$.

$$\bar{y} = \frac{M_x}{m} = \frac{256\rho/15}{32\rho/3} = \frac{8}{5}$$

So, the center of mass (the balancing point) of the lamina is $\left(0, \frac{8}{5}\right)$, as shown in Figure 7.60. ■



The center of mass is the balancing point.

Figure 7.60

The density ρ in Example 4 is a common factor of both the moments and the mass, and as such it divides out of the quotients representing the coordinates of the center of mass. So, the center of mass of a lamina of *uniform* density depends only on the shape of the lamina and not on its density. For this reason, the point

$$(\bar{x}, \bar{y})$$

Center of mass or centroid

is sometimes called the center of mass of a *region* in the plane, or the **centroid** of the region. In other words, to find the centroid of a region in the plane, assume that the region has a constant density of $\rho = 1$ and therefore the mass of the region is equal to the area A, or $m = A$. Then calculate the corresponding center of mass, as shown in the next two examples.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 7.61

GO DIGITAL

EXAMPLE 5 The Centroid of a Plane Region

Find the centroid of the region bounded by the graphs of $f(x) = 4 - x^2$ and $g(x) = x + 2$.

Solution The two graphs intersect at the points $(-2, 0)$ and $(1, 3)$, as shown in Figure 7.61. So, the area of the region is

$$A = \int_{-2}^{1} [f(x) - g(x)]\,dx = \int_{-2}^{1} (2 - x - x^2)\,dx = \frac{9}{2}.$$

Now, find the coordinates of the centroid $(\bar{x}, \bar{y})$.

$$\begin{aligned}
\bar{x} &= \frac{1}{A}\int_{-2}^{1} x[(4 - x^2) - (x + 2)]\,dx \\
&= \frac{2}{9}\int_{-2}^{1} (-x^3 - x^2 + 2x)\,dx \\
&= \frac{2}{9}\left[-\frac{x^4}{4} - \frac{x^3}{3} + x^2\right]_{-2}^{1} \\
&= -\frac{1}{2} \\
\bar{y} &= \frac{1}{A}\int_{-2}^{1} \left[\frac{(4 - x^2) + (x + 2)}{2}\right][(4 - x^2) - (x + 2)]\,dx \\
&= \frac{2}{9}\left(\frac{1}{2}\right)\int_{-2}^{1} (-x^2 + x + 6)(-x^2 - x + 2)\,dx \\
&= \frac{1}{9}\int_{-2}^{1} (x^4 - 9x^2 - 4x + 12)\,dx \\
&= \frac{1}{9}\left[\frac{x^5}{5} - 3x^3 - 2x^2 + 12x\right]_{-2}^{1} \\
&= \frac{12}{5}
\end{aligned}$$

So, the centroid of the region is $(\bar{x}, \bar{y}) = \left(-\frac{1}{2}, \frac{12}{5}\right)$. ■

For simple plane regions, you may be able to find the centroids without resorting to integration.



(a) Original region



(b) The centroids of the three rectangles

Figure 7.62

EXAMPLE 6 The Centroid of a Simple Plane Region

Find the centroid of the region shown in Figure 7.62(a).

Solution First, superimpose a coordinate system on the region, as shown in Figure 7.62(b). Notice in the figure that the centroids are located at

$$\left(\frac{1}{2}, \frac{3}{2}\right), \quad \left(\frac{5}{2}, \frac{1}{2}\right), \quad \text{and} \quad (5, 1).$$

Next, use these three points to find the centroid of the region.

$$\begin{aligned}
A &= \text{area of region} = 3 + 3 + 4 = 10 \\
\bar{x} &= \frac{(1/2)(3) + (5/2)(3) + (5)(4)}{10} = \frac{29}{10} = 2.9 \\
\bar{y} &= \frac{(3/2)(3) + (1/2)(3) + (1)(4)}{10} = \frac{10}{10} = 1
\end{aligned}$$

So, the centroid of the region is $(2.9, 1)$. Notice that $(2.9, 1)$ is not the "average" of $\left(\frac{1}{2}, \frac{3}{2}\right)$, $\left(\frac{5}{2}, \frac{1}{2}\right)$, and $(5, 1)$. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Theorem of Pappus

The final topic in this section is a useful theorem credited to Pappus of Alexandria (ca. 300 A.D.), a Greek mathematician whose eight-volume *Mathematical Collection* is a record of much of classical Greek mathematics. You are asked to prove this theorem in Section 14.4.



The volume V is $2\pi rA$, where A is the area of region R.

Figure 7.63

THEOREM 7.1 The Theorem of Pappus

Let R be a region in a plane and let L be a line in the same plane such that L does not intersect the interior of R, as shown in Figure 7.63. If r is the distance between the centroid of R and the line, then the volume V of the solid of revolution formed by revolving R about the line is

$$V = 2\pi rA$$

where A is the area of R. (Note that $2\pi r$ is the distance traveled by the centroid as the region is revolved about the line.)

The Theorem of Pappus can be used to find the volume of a torus, as shown in the next example. Recall that a torus is a doughnut-shaped solid formed by revolving a circular region about a line that lies in the same plane as the circle (but does not intersect the circle).

EXAMPLE 7 Finding Volume by the Theorem of Pappus

Find the volume of the torus shown in Figure 7.64(a), which was formed by revolving the circular region bounded by

$$(x - 2)^2 + y^2 = 1$$

about the y-axis, as shown in Figure 7.64(b).



Torus

(a)



(b)

Figure 7.64

Solution Notice in Figure 7.64(b) that the centroid of the circular region is $(2, 0)$. So, the distance between the centroid and the axis of revolution is

$$r = 2.$$

Because the area of the circular region is $A = \pi$, the volume of the torus is

$$\begin{aligned} V &= 2\pi rA \\ &= 2\pi(2)(\pi) \\ &= 4\pi^2 \\ &\approx 39.5. \end{aligned}$$

■

Exploration

Use the shell method to show that the volume of the torus in Example 7 is

$$V = \int_1^3 4\pi x\sqrt{1 - (x - 2)^2}\,dx.$$

Evaluate this integral using a graphing utility. Does your answer agree with the one in Example 7?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

7.6 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain how mass and weight are related.
2. The equation for the moment about the origin of a one-dimensional system is

   $M_0 = 5(-3) + 2(-1) + 1(1) + 5(2) + 1(6)$.

   Is the system in equilibrium? Explain.
3. Give the definition of a planar lamina. Describe what the center of mass of a lamina represents.
4. Explain why the Theorem of Pappus is useful.

Center of Mass of a Linear System

In Exercises 5–8, find the center of mass of the given system of point masses lying on the x-axis.

5. $m_1 = 7, m_2 = 3, m_3 = 5$
   $x_1 = -5, x_2 = 0, x_3 = 3$
6. $m_1 = 0.1, m_2 = 0.2, m_3 = 0.2, m_4 = 0.5$
   $x_1 = 1, x_2 = 2, x_3 = 3, x_4 = 4$
7. $m_1 = 1, m_2 = 3, m_3 = 2, m_4 = 9, m_5 = 5$
   $x_1 = 6, x_2 = 10, x_3 = 3, x_4 = 2, x_5 = 4$
8. $m_1 = 8, m_2 = 5, m_3 = 5, m_4 = 12, m_5 = 2$
   $x_1 = -2, x_2 = 6, x_3 = 0, x_4 = 3, x_5 = -5$

Equilibrium of a Linear System

In Exercises 9 and 10, consider a beam of length L with a fulcrum x feet from one end (see figure). There are objects with weights W_1 and W_2 placed on opposite ends of the beam, where $W_1 < W_2$. Find x such that the system is in equilibrium.



9. Two children weighing 48 pounds and 72 pounds are going to play on a seesaw that is 10 feet long.
10. In order to move a 600-pound rock, a person weighing 200 pounds wants to balance it on a beam that is 5 feet long.

Center of Mass of a Two-Dimensional System

In Exercises 11–14, find the center of mass of the given system of point masses.

11.

m_i	5	1	3
(x_i, y_i)	$(2, 2)$	$(-3, 1)$	$(1, -4)$

12.

m_i	8	1	4
(x_i, y_i)	$(-3, -1)$	$(0, 0)$	$(-1, 2)$

13.

m_i	12	6	4.5	15
(x_i, y_i)	$(2, 3)$	$(-1, 5)$	$(6, 8)$	$(2, -2)$

14.

m_i	3	4	2	1	6
(x_i, y_i)	$(-2, -3)$	$(5, 5)$	$(7, 1)$	$(0, 0)$	$(-3, 0)$

Center of Mass of a Planar Lamina

In Exercises 15–28, find M_x, M_y, and $(\bar{x}, \bar{y})$ for the lamina of uniform density ρ bounded by the graphs of the equations.

15. $y = \frac{1}{2}x, y = 0, x = 2$
16. $y = 6 - x, y = 0, x = 0$
17. $y = \sqrt{x}, y = 0, x = 4$
18. $y = \frac{1}{3}x^2, y = 0, x = 2$
19. $y = x^2, y = x^3$
20. $y = \sqrt{x}, y = \frac{1}{2}x$
21. $y = -x^2 + 4x + 2, y = x + 2$
22. $y = \sqrt{x} + 1, y = \frac{1}{3}x + 1$
23. $y = x^{2/3}, y = 0, x = 8$
24. $y = x^{2/3}, y = 4$
25. $x = 4 - y^2, x = 0$
26. $x = 3y - y^2, x = 0$
27. $x = -y, x = 2y - y^2$
28. $x = y + 2, x = y^2$

Approximating a Centroid Using Technology

In Exercises 29 and 30, use a graphing utility to graph the region bounded by the graphs of the equations. Use the integration capabilities of the graphing utility to approximate the centroid of the region.

29. $y = 5\sqrt[3]{400 - x^2}, y = 0$
30. $y = \dfrac{8}{x^2 + 4}, y = 0, x = -2, x = 2$

Finding the Center of Mass

In Exercises 31–34, introduce an appropriate coordinate system and find the center of mass of the planar lamina. (The answer depends on the position of the coordinate system.)

31.



32.



33.



34.



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

35. Finding the Center of Mass Find the center of mass of the lamina in Exercise 31 when the circular portion of the lamina has twice the density of the square portion of the lamina.

36. Finding the Center of Mass Find the center of mass of the lamina in Exercise 31 when the square portion of the lamina has twice the density of the circular portion of the lamina.

Finding Volume by the Theorem of Pappus **In Exercises 37–40, use the Theorem of Pappus to find the volume of the solid of revolution.**

37. The torus formed by revolving the circular region bounded by

$(x - 5)^2 + y^2 = 16$

about the y-axis

38. The torus formed by revolving the circular region bounded by

$x^2 + (y - 3)^2 = 4$

about the x-axis

39. The solid formed by revolving the region bounded by the graphs of $y = x$, $y = 4$, and $x = 0$ about the x-axis

40. The solid formed by revolving the region bounded by the graphs of $y = 2\sqrt{x - 2}$, $y = 0$, and $x = 6$ about the y-axis

Exploring Concepts

41. Explain what happens to the center of mass of a linear system when each point mass is translated k units horizontally.

42. Explain why the centroid of a rectangle is the center of a rectangle.

43. Use rectangles to create a region such that the center of mass lies outside of the region. Verify algebraically that the center of mass lies outside of the region.

44. HOW DO YOU SEE IT? The centroid of the plane region bounded by the graphs of $y = f(x)$, $y = 0$, $x = 0$, and $x = 3$ is $(1.2, 1.4)$. Without integrating, find the centroid of each of the regions bounded by the graphs of the following sets of equations. Explain your reasoning.



(a) $y = f(x) + 2$, $y = 2$, $x = 0$, and $x = 3$

(b) $y = f(x - 2)$, $y = 0$, $x = 2$, and $x = 5$

(c) $y = -f(x)$, $y = 0$, $x = 0$, and $x = 3$

Centroid of a Common Region **In Exercises 45–50, find and/or verify the centroid of the common region used in engineering.**

45. Triangle Show that the centroid of the triangle with vertices $(-a, 0)$, $(a, 0)$, and (b, c) is the point of intersection of the medians (see figure).



Figure for 45



Figure for 46

46. Parallelogram Show that the centroid of the parallelogram with vertices $(0, 0)$, $(a, 0)$, (b, c), and $(a + b, c)$ is the point of intersection of the diagonals (see figure).

47. Trapezoid Find the centroid of the trapezoid with vertices $(0, 0)$, $(0, a)$, (c, b), and $(c, 0)$. Show that it is the intersection of the line connecting the midpoints of the parallel sides and the line connecting the extended parallel sides, as shown in the figure.



Figure for 47



Figure for 48

48. Semicircle Find the centroid of the region bounded by the graphs of

$y = \sqrt{r^2 - x^2}$ and $y = 0$ (see figure).

49. Semiellipse Find the centroid of the region bounded by the graphs of

$y = \frac{b}{a}\sqrt{a^2 - x^2}$ and $y = 0$ (see figure).



Figure for 49



Figure for 50

50. Parabolic Spandrel Find the centroid of the **parabolic spandrel** shown in the figure.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

51. Graphical Reasoning Consider the region bounded by the graphs of $y = x^2$ and $y = b$, where $b > 0$.

(a) Sketch a graph of the region.

(b) Set up the integral for finding M_y. Because of the form of the integrand, the value of the integral can be obtained without integrating. What is the form of the integrand? What is the value of the integral and what is the value of $\bar{x}$?

(c) Use the graph in part (a) to determine whether $\bar{y} > \frac{b}{2}$ or $\bar{y} < \frac{b}{2}$. Explain.

(d) Use integration to verify your answer in part (c).

52. Graphical and Numerical Reasoning Consider the region bounded by the graphs of $y = x^{2n}$ and $y = b$, where $b > 0$ and n is a positive integer.

(a) Sketch a graph of the region.

(b) Set up the integral for finding M_y. Because of the form of the integrand, the value of the integral can be obtained without integrating. What is the form of the integrand? What is the value of the integral and what is the value of $\bar{x}$?

(c) Use the graph in part (a) to determine whether $\bar{y} > \frac{b}{2}$ or $\bar{y} < \frac{b}{2}$. Explain.

(d) Use integration to find $\bar{y}$ as a function of n.

(e) Use the result of part (d) to complete the table.

n	1	2	3	4
$\bar{y}$				

(f) Find $\lim_{n\to\infty} \bar{y}$.

(g) Give a geometric explanation of the result in part (f).

53. Modeling Data The manufacturer of glass for a window in a conversion van needs to approximate the center of mass of the glass. A coordinate system is superimposed on a prototype of the glass (see figure). The measurements (in centimeters) for the right half of the symmetric piece of glass are listed in the table.



x	0	10	20	30	40
y	30	29	26	20	0

(a) Use the regression capabilities of a graphing utility to find a fourth-degree polynomial model for the glass.

(b) Use the integration capabilities of a graphing utility and the model to approximate the center of mass of the glass.

54. Modeling Data The manufacturer of a boat needs to approximate the center of mass of a section of the hull. A coordinate system is superimposed on a prototype (see figure). The measurements (in feet) for the right half of the symmetric prototype are listed in the table.



x	0	0.5	1.0	1.5	2
h	1.50	1.45	1.30	0.99	0
d	0.50	0.48	0.43	0.33	0

(a) Use the regression capabilities of a graphing utility to find fourth-degree polynomial models for both curves shown in the figure.

(b) Use the integration capabilities of a graphing utility and the models to approximate the center of mass of the hull section.

Second Theorem of Pappus **In Exercises 55 and 56, use the *Second Theorem of Pappus*, which is stated as follows. If a segment of a plane curve C is revolved about an axis that does not intersect the curve (except possibly at its endpoints), then the area S of the resulting surface of revolution is equal to the product of the length of C times the distance d traveled by the centroid of C.**

55. Find the area of the surface formed by revolving the graph of $y = 3 - x$, $0 \le x \le 3$, about the y-axis.

56. A torus is formed by revolving the graph of $(x - 1)^2 + y^2 = 1$ about the y-axis. Find the surface area of the torus.

57. Finding a Centroid Let $n \ge 1$ be constant, and consider the region bounded by $f(x) = x^n$, the x-axis, and $x = 1$. Find the centroid of this region. As $n \to \infty$, what does the region look like, and where is its centroid?

58. Finding a Centroid Consider the functions

$$f(x) = x^n \quad \text{and} \quad g(x) = x^m$$

on the interval $[0, 1]$, where m and n are positive integers and $n > m$. Find the centroid of the region bounded by f and g.

PUTNAM EXAM CHALLENGE

59. Let V be the region in the cartesian plane consisting of all points (x, y) satisfying the simultaneous conditions $|x| \le y \le |x| + 3$ and $y \le 4$. Find the centroid $(\bar{x}, \bar{y})$ of V.

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

7.7 Fluid Pressure and Fluid Force

GO DIGITAL

Find fluid pressure and fluid force.

Fluid Pressure and Fluid Force

Swimmers know that the deeper an object is submerged in a fluid, the greater the pressure on the object. **Pressure** is defined as the force per unit of area over the surface of a body. For example, because a column of water that is 10 feet in height and 1 inch square weighs 4.3 pounds, the *fluid pressure* at a depth of 10 feet of water is 4.3 pounds per square inch.* At 20 feet, this would increase to 8.6 pounds per square inch, and in general the pressure is proportional to the depth of the object in the fluid.

BLAISE PASCAL (1623–1662)

Pascal is well known for his work in many areas of mathematics and physics, and also for his influence on Leibniz. Although much of Pascal's work in calculus was intuitive and lacked the rigor of modern mathematics, he nevertheless anticipated many important results.

See LarsonCalculus.com to read more of this biography.

Definition of Fluid Pressure

The **pressure** P on an object at depth h in a liquid is

$$P = wh$$

where w is the weight-density of the liquid per unit of volume.

Below are some common weight-densities of fluids in pounds per cubic foot.

Ethyl alcohol	49.4
Gasoline	41.0–43.0
Glycerin	78.6
Kerosene	51.2
Mercury	849.0
Seawater	64.0
Water	62.4

When calculating fluid pressure, you can use an important (and rather surprising) physical law called **Pascal's Principle,** named after the French mathematician Blaise Pascal. Pascal's Principle states that the pressure exerted by a fluid at a depth h is transmitted equally *in all directions.* For example, in Figure 7.65, the pressure at the indicated depth is the same for all three objects. Because fluid pressure is given in terms of force per unit area ($P = F/A$), the fluid force on a *submerged horizontal* surface of area A is

$$\text{Fluid force} = F = PA = (\text{pressure})(\text{area}).$$



The pressure at h is the same for all three objects.
Figure 7.65

* The total pressure on an object in 10 feet of water would also include the pressure due to Earth's atmosphere. At sea level, atmospheric pressure is approximately 14.7 pounds per square inch.

The Print Collector/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The fluid force on a horizontal metal sheet is equal to the fluid pressure times the area.
Figure 7.66

EXAMPLE 1 Fluid Force on a Submerged Sheet

Find the fluid force on a rectangular metal sheet measuring 3 feet by 4 feet that is submerged in 6 feet of water, as shown in Figure 7.66.

Solution Because the weight-density of water is 62.4 pounds per cubic foot and the sheet is submerged in 6 feet of water, the fluid pressure is

$$P = (62.4)(6) \qquad P = wh$$
$$= 374.4 \text{ pounds per square foot.}$$

Because the total area of the sheet is $A = (3)(4) = 12$ square feet, the fluid force is

$$F = PA$$
$$= \left(374.4 \frac{\text{pounds}}{\text{square foot}}\right)(12 \text{ square feet})$$
$$= 4492.8 \text{ pounds.}$$

This result is independent of the size of the body of water. The fluid force would be the same in a swimming pool or lake. ■

In Example 1, the fact that the sheet is rectangular and horizontal means that you do not need the methods of calculus to solve the problem. Consider a surface that is submerged vertically in a fluid. This problem is more difficult because the pressure is not constant over the surface.

Consider a vertical plate that is submerged in a fluid of weight-density w (per unit of volume), as shown in Figure 7.67. To determine the total force against *one side* of the region from depth c to depth d, subdivide the interval $[c, d]$ into n subintervals, each of width Δy. Next, consider the representative rectangle of width Δy and length $L(y_i)$, where y_i is in the ith subinterval. The force against this representative rectangle is

$$\Delta F_i = w(\text{depth})(\text{area})$$
$$= wh(y_i)L(y_i)\Delta y.$$



Calculus methods must be used to find the fluid force on a vertical metal plate.
Figure 7.67

The force against n such rectangles is

$$\sum_{i=1}^{n} \Delta F_i = w \sum_{i=1}^{n} h(y_i)L(y_i)\Delta y.$$

Note that w is considered to be constant and is factored out of the summation. So, taking the limit as $\|\Delta\| \to 0$ $(n \to \infty)$ suggests the next definition.

Definition of Force Exerted by a Fluid

The **force F exerted by a fluid** of constant weight-density w (per unit of volume) against a submerged vertical plane region from $y = c$ to $y = d$ is

$$F = w \lim_{\|\Delta\| \to 0} \sum_{i=1}^{n} h(y_i)L(y_i)\Delta y$$
$$= w \int_c^d h(y)L(y)\, dy$$

where $h(y)$ is the depth of the fluid at y and $L(y)$ is the horizontal length of the region at y.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 2 Fluid Force on a Vertical Surface

See LarsonCalculus.com for an interactive version of this type of example.

A vertical gate in a dam has the shape of an isosceles trapezoid 8 feet across the top and 6 feet across the bottom, with a height of 5 feet, as shown in Figure 7.68(a). What is the fluid force on the gate when the top of the gate is 4 feet below the surface of the water?



(a) Water gate in a dam

Solution In setting up a mathematical model for this problem, you are at liberty to locate the x- and y-axes in several different ways. A convenient approach is to let the y-axis bisect the gate and place the x-axis at the surface of the water, as shown in Figure 7.68(b). So, the depth of the water at y in feet is

$$\text{Depth} = h(y) = -y.$$

To find the length $L(y)$ of the region at y, find the equation of the line forming the right side of the gate. Because this line passes through the points $(3, -9)$ and $(4, -4)$, its equation is

$$\begin{aligned} y - (-9) &= \frac{-4 - (-9)}{4 - 3}(x - 3) \\ y + 9 &= 5(x - 3) \\ y &= 5x - 24 \\ x &= \frac{y + 24}{5}. \end{aligned}$$



(b) The fluid force against the gate

Figure 7.68

In Figure 7.68(b), notice that the length of the region at y is

$$\text{Length} = 2x = \frac{2}{5}(y + 24) = L(y).$$

Finally, integrate from $y = -9$ to $y = -4$ to calculate the fluid force.

$$\begin{aligned} F &= w\int_c^d h(y)L(y)\,dy && \text{Definition of force exerted by a fluid} \\ &= 62.4\int_{-9}^{-4}(-y)\left(\frac{2}{5}\right)(y + 24)\,dy && \text{Substitute.} \\ &= -62.4\left(\frac{2}{5}\right)\int_{-9}^{-4}(y^2 + 24y)\,dy \\ &= -62.4\left(\frac{2}{5}\right)\left[\frac{y^3}{3} + 12y^2\right]_{-9}^{-4} && \text{Integrate.} \\ &= -62.4\left(\frac{2}{5}\right)\left(\frac{-1675}{3}\right) \\ &= 13{,}936 \text{ pounds} \end{aligned}$$

In Example 2, the x-axis coincided with the surface of the water. This was convenient but arbitrary. In choosing a coordinate system to represent a physical situation, you should consider various possibilities. Often you can simplify the calculations in a problem by locating the coordinate system to take advantage of special characteristics of the problem, such as symmetry.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 3 Fluid Force on a Vertical Surface

A circular observation window at a seawater aquarium has a radius of 1 foot, and the center of the window is 8 feet below water level, as shown in Figure 7.69. What is the fluid force on the window?



The fluid force on the window

Figure 7.69

Solution To take advantage of symmetry, locate a coordinate system such that the origin coincides with the center of the window, as shown in Figure 7.69. The depth at y is then

$$\text{Depth} = h(y) = 8 - y.$$

The horizontal length of the window is $2x$, and you can use the equation for the circle, $x^2 + y^2 = 1$, to solve for x as shown.

$$\text{Length} = 2x = 2\sqrt{1 - y^2} = L(y)$$

Finally, because y ranges from -1 to 1, and using 64 pounds per cubic foot as the weight-density of seawater, you have

$$F = w\int_c^d h(y)L(y)\,dy = 64\int_{-1}^{1}(8 - y)(2)\sqrt{1 - y^2}\,dy.$$

Initially it looks as though this integral would be difficult to solve. However, when you break the integral into two parts and apply symmetry, the solution is simpler.

$$F = 64(16)\int_{-1}^{1}\sqrt{1 - y^2}\,dy - 64(2)\int_{-1}^{1} y\sqrt{1 - y^2}\,dy$$

The second integral is 0 (because the integrand is odd and the limits of integration are symmetric with respect to the origin). Moreover, by recognizing that the first integral represents the area of a semicircle of radius 1, you obtain

$$\begin{aligned} F &= 64(16)\left(\frac{\pi}{2}\right) - 64(2)(0) \\ &= 512\pi \\ &\approx 1608.5 \text{ pounds.} \end{aligned}$$

So, the fluid force on the window is about 1608.5 pounds. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

7.7 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe fluid pressure.
2. Does fluid pressure change with depth? Explain.

Force on a Submerged Sheet **In Exercises 3–6, the area of the top side of a piece of sheet metal is given. The sheet metal is submerged horizontally in 8 feet of water. Find the fluid force on the top side.**

3. 3 square feet
4. 8 square feet
5. 10 square feet
6. 25 square feet

Force on a Submerged Sheet **In Exercises 7 and 8, the area of the top side of a piece of sheet metal is given. The sheet metal is submerged horizontally in 5 feet of ethyl alcohol. Find the fluid force on the top side.**

7. 9 square feet
8. 14 square feet

Fluid Force on a Tank Wall **In Exercises 9–14, the figure is the vertical side of a tank filled with water, where the dimensions are given in feet. Find the fluid force on this side of the tank.**

9. Rectangle



10. Triangle



11. Trapezoid



12. Semicircle



13. Parabola, $y = x^2$



14. Semiellipse, $y = -\frac{1}{2}\sqrt{36 - 9x^2}$



Fluid Force of Water **In Exercises 15–18, find the fluid force on the vertical plate submerged in water, where the dimensions are given in meters and the weight-density of water is 9800 newtons per cubic meter.**

15. Square



16. Rectangle



17. Triangle



18. Square



Force on a Concrete Form **In Exercises 19–22, the figure is the vertical side of a form for poured concrete that weighs 140.7 pounds per cubic foot. Determine the force on this part of the concrete form.**

19. Rectangle



20. Semiellipse, $y = -\frac{3}{4}\sqrt{16 - x^2}$



21. Rectangle



22. Triangle



23. **Fluid Force of Gasoline** A cylindrical gasoline tank is placed so that the axis of the cylinder is horizontal. Find the fluid force on a circular end of the tank when the tank is half full, where the diameter is 3 feet and the gasoline weighs 42 pounds per cubic foot.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

24. Fluid Force of Gasoline Repeat Exercise 23 for a tank that is full. (Evaluate one integral by a geometric formula and the other by observing that the integrand is an odd function.)

Exploring Concepts

25. Explain why fluid pressure on a surface is calculated using horizontal representative rectangles instead of vertical representative rectangles.

26. Buoyant force is the difference between the fluid forces on the top and bottom sides of a solid. Find an expression for the buoyant force of a rectangular solid submerged in a fluid with its top side parallel to the surface of the fluid.

27. Approximate the depth of the water in the tank in Exercise 9 if the fluid force is one-half as great as when the tank is full. Explain why the answer is not $\frac{3}{2}$.

28. HOW DO YOU SEE IT? Two identical semicircular windows are placed at the same depth in the vertical wall of an aquarium (see figure). Which is subjected to the greater fluid force? Explain.



29. Fluid Force on a Circular Plate A circular plate of radius r feet is submerged vertically in a tank of fluid that weighs w pounds per cubic foot. The center of the circle is k feet below the surface of the fluid, where $k > r$. Show that the fluid force on the surface of the plate is

$$F = wk(\pi r^2).$$

(Evaluate one integral by a geometric formula and the other by observing that the integrand is an odd function.)

30. Fluid Force on a Circular Plate Use the result of Exercise 29 to find the fluid force on the circular plate shown in each figure. Assume that the tank is filled with water and the measurements are given in feet.

(a)



(b)



31. Fluid Force on a Rectangular Plate A rectangular plate of height h feet and base b feet is submerged vertically in a tank of fluid that weighs w pounds per cubic foot. The center of the rectangle is k feet below the surface of the fluid, where $k > h/2$. Show that the fluid force on the surface of the plate is

$$F = wkhb.$$

32. Fluid Force on a Rectangular Plate Use the result of Exercise 31 to find the fluid force on the rectangular plate shown in each figure. Assume that the tank is filled with water and the measurements are given in feet.

(a)



(b)



33. Submarine Porthole A square porthole on a vertical side of a submarine (submerged in seawater) has an area of 1 square foot. Find the fluid force on the porthole, assuming that the center of the square is 15 feet below the surface.

34. Submarine Porthole Repeat Exercise 33 for a circular porthole that has a diameter of 1 foot. The center of the circle is 15 feet below the surface.

35. Modeling Data The vertical stern of a boat partially submerged in seawater with a superimposed coordinate system is shown in the figure. The table shows the widths w of the stern (in feet) at indicated values of y. Use the Midpoint Rule with $n = 4$ to approximate the fluid force against the stern.

y	0	1	2	3	4
w	0	5	9	10.25	10.5



36. Irrigation Canal Gate The vertical cross section of an irrigation canal is modeled by

$$f(x) = \frac{5x^2}{x^2 + 4}$$

where x is measured in feet and $x = 0$ corresponds to the center of the canal. Use the integration capabilities of a graphing utility to approximate the fluid force against a vertical gate used to stop the flow of water when the water is 3 feet deep.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Review Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Exploring Concepts

In this chapter, you studied several applications of integration. To develop an integration formula for these applications, you began with a known precalculus formula. Then, using that formula to construct a representative element, you developed an integration formula by summing, or accumulating, these elements. For example, consider how the formula for the area of a region between two curves was developed.

Known Precalculus Formula		Representative Element		New Integration Formula
$A = (\text{height})(\text{width})$	⇨	$\Delta A = [f(x) - g(x)]\Delta x$	⇨	$A = \int_a^b [f(x) - g(x)]\,dx$

1. Identify the precalculus formula and representative element used to develop the integration formula for each application.

(a) Disk method

(b) Washer method

(c) Shell method

(d) Area of a surface of revolution

2. Let f and g be continuous functions on $[a, b]$ and let $g(x) \le f(x)$ for all x in $[a, b]$. Write in words the area given by

$$\int_a^b [f(x) - g(x)]\,dx.$$

Does the area interpretation of this integral change when $f(x) \ge 0$ and $g(x) \le 0$?

3. Determine which value best approximates the area of the region bounded by the graphs of

$f(x) = x + 1$ and $g(x) = (x - 1)^2$.

Make your selection on the basis of a sketch of the region and not by performing any calculations.

(a) -2 (b) 2 (c) 10 (d) 4 (e) 8

4. Determine which value best approximates the volume of the solid generated by revolving the region bounded by the graphs of

$y = \arctan x$, $y = 0$, $x = 0$, and $x = 1$

about the x-axis. Make your selection on the basis of a sketch of the region and not by performing any calculations.

(a) 10 (b) $\frac{3}{4}$ (c) 5 (d) -6 (e) 15

5. Explain why the two integrals are equal.

$$\int_1^e \sqrt{1 + \frac{1}{x^2}}\,dx = \int_0^1 \sqrt{1 + e^{2x}}\,dx$$

Use the integration capabilities of a graphing utility to verify that the integrals are equal.

6. Let the point masses $m_1, m_2, \ldots, m_n$ be located at

$(x_1, y_1), (x_2, y_2), \ldots, (x_n, y_n)$.

Define the center of mass $(\bar{x}, \bar{y})$.

Finding the Area of a Region

In Exercises 7–16, sketch the region bounded by the graphs of the equations and find the area of the region.

7. $y = 6 - \frac{1}{2}x^2$, $y = \frac{3}{4}x$, $x = -2$, $x = 2$

8. $y = \frac{1}{x^2}$, $y = 4$, $x = 5$

9. $y = \frac{1}{x^2 + 1}$, $y = 0$, $x = -1$, $x = 1$

10. $x = y^2 - 2y$, $x = -1$, $y = 0$

11. $y = x$, $y = x^3$

12. $x = y^2 + 1$, $x = y + 3$

13. $y = e^x$, $y = e^2$, $x = 0$

14. $y = \csc x$, $y = 2$, $\frac{\pi}{6} \le x \le \frac{5\pi}{6}$

15. $y = \sin x$, $y = \cos x$, $\frac{\pi}{4} \le x \le \frac{5\pi}{4}$

16. $x = \cos y$, $x = \frac{1}{2}$, $\frac{\pi}{3} \le y \le \frac{7\pi}{3}$

Finding the Area of a Region

In Exercises 17–20, (a) use a graphing utility to graph the region bounded by the graphs of the equations and (b) use the integration capabilities of the graphing utility to approximate the area of the region to four decimal places.

17. $y = x^2 - 8x + 3$, $y = 3 + 8x - x^2$

18. $y = x^2 - 4x + 3$, $y = x^3$, $x = 0$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

19. $\sqrt{x} + \sqrt{y} = 1, \quad y = 0, \quad x = 0$

20. $y = x^4 - 2x^2, \quad y = 2x^2$

Integration as an Accumulation Process **In Exercises 21 and 22, find the accumulation function F. Then evaluate F at each value of the independent variable and graphically show the area given by each value of the independent variable.**

21. $F(x) = \int_0^x (3t + 1)\, dt$

(a) $F(0)$ (b) $F(2)$ (c) $F(6)$

22. $F(x) = \int_{-\pi}^x (2 + \sin t)\, dt$

(a) $F(-\pi)$ (b) $F(0)$ (c) $F(2\pi)$

Revenue **In Exercises 23 and 24, two models R_1 and R_2 are given for revenue (in millions of dollars) for a corporation. Both models are estimates of revenues from 2030 through 2035, with $t = 0$ corresponding to 2030. Which model projects the greater revenue? How much more total revenue does that model project over the six-year period?**

23. $R_1 = 2.98 + 0.65t$

$R_2 = 2.98 + 0.56t$

24. $R_1 = 4.87 + 0.55t + 0.01t^2$

$R_2 = 4.87 + 0.61t + 0.07t^2$

Finding the Volume of a Solid **In Exercises 25 and 26, use the disk method to find the volume of the solid generated by revolving the region bounded by the graphs of the equations about the x-axis.**

25. $y = \dfrac{1}{\sqrt{1 + x^2}}, \quad y = 0, \quad x = -1, \quad x = 1$

26. $y = e^{-x}, \quad y = 0, \quad x = 0, \quad x = 1$

Finding the Volume of a Solid **In Exercises 27 and 28, use the shell method to find the volume of the solid generated by revolving the region bounded by the graphs of the equations about the y-axis.**

27. $y = \dfrac{1}{x^4 + 1}, \quad y = 0, \quad x = 0, \quad x = 1$

28. $y = \dfrac{1}{x^2}, \quad y = 0, \quad x = 2, \quad x = 5$

Finding the Volume of a Solid **In Exercises 29 and 30, use the disk method *or* the shell method to find the volumes of the solids generated by revolving the region bounded by the graphs of the equations about the given lines.**

29. $y = x, \quad y = 0, \quad x = 3$

(a) the x-axis

(b) the y-axis

(c) the line $x = 3$

(d) the line $x = 6$

30. $y = \sqrt{x}, \quad y = 2, \quad x = 0$

(a) the x-axis

(b) the line $y = 2$

(c) the y-axis

(d) the line $x = -1$

31. Gasoline Tank A gasoline tank is an oblate spheroid generated by revolving the region bounded by the graph of

$$\frac{x^2}{16} + \frac{y^2}{9} = 1$$

about the y-axis, where x and y are measured in feet. How much gasoline can the tank hold?

32. Using Cross Sections Find the volume of the solid whose base is bounded by the circle $x^2 + y^2 = 9$ and whose cross sections perpendicular to the x-axis are equilateral triangles.

Finding Arc Length **In Exercises 33 and 34, find the arc length of the graph of the function over the indicated interval.**

33. $f(x) = \dfrac{4}{5}x^{5/4}, \quad [0, 4]$

34. $y = \dfrac{1}{3}x^{3/2} - 1, \quad [2, 6]$

Finding the Area of a Surface of Revolution **In Exercises 35 and 36, write and evaluate the definite integral that represents the area of the surface generated by revolving the curve on the indicated interval about the x-axis.**

35. $y = \dfrac{x^3}{18}, \quad 3 \le x \le 6$

36. $y = \sqrt{25 - x^2}, \quad -4 \le x \le 4$

Finding the Area of a Surface of Revolution **In Exercises 37 and 38, write and evaluate the definite integral that represents the area of the surface generated by revolving the curve on the indicated interval about the y-axis.**

37. $y = \dfrac{x^2}{2} + 4, \quad 0 \le x \le 2$

38. $y = \sqrt[3]{x}, \quad 1 \le x \le 2$

39. Hooke's Law A force of 5 pounds stretches a spring 1 inch from its natural position. Find the work done in stretching the spring from its natural length of 10 inches to a length of 15 inches.

40. Hooke's Law A force of 50 pounds stretches a spring 1 inch from its natural position. Find the work done in stretching the spring from its natural length of 10 inches to double that length.

41. Propulsion Neglecting air resistance and the weight of the propellant, determine the work done in propelling a five-ton satellite to a height of 200 miles above Earth.

42. Pumping Water A water well has an 8-inch diameter and is 190 feet deep. The water is 25 feet from the top of the well. Determine the amount of work done in pumping the well dry.

43. Winding a Chain A chain 10 feet long weighs 4 pounds per foot and is hung from a platform 20 feet above the ground. How much work is required to raise the entire chain to the 20-foot level?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

44. Winding a Cable A 200-foot cable weighing 5 pounds per foot is hanging from a winch 200 feet above ground level. Find the work done in winding up the cable when there is a 300-pound load attached to the end of the cable.

45. Boyle's Law A quantity of gas with an initial volume of 1 cubic foot and a pressure of 500 pounds per square foot expands to a volume of 4 cubic feet. Find the work done by the gas. Assume that the pressure is inversely proportional to the volume.

46. Boyle's Law A quantity of gas with an initial volume of 2 cubic feet and a pressure of 800 pounds per square foot expands to a volume of 3 cubic feet. Find the work done by the gas. Assume that the pressure is inversely proportional to the volume.

47. Center of Mass of a Linear System Find the center of mass of the given system of point masses lying on the x-axis.

$m_1 = 8, \quad m_2 = 12, \quad m_3 = 6, \quad m_4 = 14$

$x_1 = -1, \quad x_2 = 2, \quad x_3 = 5, \quad x_4 = 7$

48. Center of Mass of a Two-Dimensional System Find the center of mass of the given system of point masses.

m_i	3	2	6	9
(x_i, y_i)	$(2, 1)$	$(-3, 2)$	$(4, -1)$	$(6, 5)$

Center of Mass of a Planar Lamina **In Exercises 49 and 50, find M_x, M_y, and $(\bar{x}, \bar{y})$ for the lamina of uniform density ρ bounded by the graphs of the equations.**

49. $y = x^2, \quad y = 2x + 3$

50. $y = x^{2/3}, \quad y = \frac{1}{2}x$

51. Finding Volume Use the Theorem of Pappus to find the volume of the torus formed by revolving the circular region bounded by

$(x - 4)^2 + y^2 = 4$

about the y-axis.

52. Finding the Center of Mass Introduce an appropriate coordinate system and find the center of mass of the planar lamina. (The answer depends on the position of the coordinate system.)



Force on a Submerged Sheet **In Exercises 53 and 54, the area of the top side of a piece of sheet metal is given. The sheet metal is submerged horizontally in 3 feet of water. Find the fluid force on the top side.**

53. 2 square feet

54. 15 square feet

55. Fluid Force of Seawater Find the fluid force on the vertical plate submerged in seawater (see figure).



Figure for 55



Figure for 56

56. Force on a Concrete Form The vertical side of a form for poured concrete that weighs 140.7 pounds per cubic foot is shown in the figure. Determine the force on this part of the concrete form.

57. Submarine Porthole A circular porthole on a vertical side of a submarine (submerged in seawater) has a diameter of 3 feet. Find the fluid force on the porthole, assuming that the center of the circle is 1600 feet below the surface.

Building on Concepts

58. The graph of $y = f(x)$ passes through the origin. The arc length of the curve from $(0, 0)$ to $(x, f(x))$ is given by

$$s(x) = \int_0^x \sqrt{1 + e^t}\, dt.$$

Identify the function f.

59. Let f be rectifiable on the interval $[a, b]$, and let

$$s(x) = \int_a^x \sqrt{1 + [f'(t)]^2}\, dt.$$

(a) Find ds/dx.

(b) Find ds and $(ds)^2$.

(c) Find $s(x)$ on $[1, 3]$ when $f(t) = t^{3/2}$.

(d) Use the function and interval in part (c) to calculate $s(2)$ and describe what it signifies.

60. Let R be the area of the region in the first quadrant bounded by the parabola $y = x^2$ and the line $y = cx$, $c > 0$, as shown in the figure. Let T be the area of triangle AOB. Find the limit

$$\lim_{c \to 0^+} \frac{T}{R}.$$



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.S. Problem Solving

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

1. Center of Mass of a Lamina Let L be the lamina of uniform density $\rho = 1$ obtained by removing circle A of radius r from circle B of radius $2r$ (see figure).



(a) Show that $M_x = 0$ for L.

(b) Show that M_y for L is equal to (M_y for B) $-$ (M_y for A).

(c) Find M_y for B and M_y for A. Then use part (b) to compute M_y for L.

(d) What is the center of mass of L?

2. Dividing a Region Let R be the region bounded by the parabola $y = x - x^2$ and the x-axis (see figure). Find the equation of the line $y = mx$ that divides this region into two regions of equal area.



3. Archimedes' Principle **Archimedes' Principle** states that the upward, or buoyant, force on an object within a fluid is equal to the weight of the fluid that the object displaces. For a partially submerged object, you can obtain information about the relative densities of the floating object and the fluid by observing how much of the object is above and below the surface. You can also determine the size of a floating object if you know the amount that is above the surface and the relative densities. You can see the top of a floating iceberg (see figure). The density of ocean water is 1.03×10^3 kilograms per cubic meter, and that of ice is 0.92×10^3 kilograms per cubic meter. What percent of the total iceberg is below the surface?



4. Surface Area Graph the curve $8y^2 = x^2(1 - x^2)$. Use a graphing utility to find the surface area of the solid of revolution obtained by revolving the curve about the y-axis.

5. Centroid A blade on an industrial fan has the configuration of a semicircle attached to a trapezoid (see figure). Find the centroid of the blade.



6. Work Find the work done by each force F.



7. Volume A rectangle R of length ℓ and width w is revolved about the line L (see figure). Find the volume of the resulting solid of revolution.



Figure for 7



Figure for 8

8. Comparing Areas of Regions

(a) The tangent line to the curve $y = x^3$ at the point $A(1, 1)$ intersects the curve at another point B. Let R be the area of the region bounded by the curve and the tangent line. The tangent line at B intersects the curve at another point C (see figure). Let S be the area of the region bounded by the curve and this second tangent line. How are the areas R and S related?

(b) Repeat the construction in part (a) by selecting an arbitrary point A on the curve $y = x^3$. Show that the two areas R and S are always related in the same way.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

8 Integration Techniques and Improper Integrals

GO DIGITAL

8.1 Basic Integration Rules
8.2 Integration by Parts
8.3 Trigonometric Integrals
8.4 Trigonometric Substitution
8.5 Partial Fractions
8.6 Numerical Integration
8.7 Integration by Tables and Other Integration Techniques
8.8 Improper Integrals

CalcView®



CalcChat®



8.5 Chemical Reaction *(Exercise 50, p. 558)*

8.3 The Wallis Product *(Section Project, p. 540)*

left, biDaala_studio/Shutterstock.com; right, agsandrew/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

8.1 Basic Integration Rules

GO DIGITAL

Review of Basic Integration Rules ($a > 0$)

1. $\int kf(u)\,du = k\int f(u)\,du$
2. $\int [f(u) \pm g(u)]\,du = \int f(u)\,du \pm \int g(u)\,du$
3. $\int du = u + C$
4. $\int u^n\,du = \frac{u^{n+1}}{n+1} + C, \quad n \neq -1$
5. $\int \frac{du}{u} = \ln|u| + C$
6. $\int e^u\,du = e^u + C$
7. $\int a^u\,du = \left(\frac{1}{\ln a}\right)a^u + C$
8. $\int \sin u\,du = -\cos u + C$
9. $\int \cos u\,du = \sin u + C$
10. $\int \tan u\,du = -\ln|\cos u| + C$
11. $\int \cot u\,du = \ln|\sin u| + C$
12. $\int \sec u\,du = \ln|\sec u + \tan u| + C$
13. $\int \csc u\,du = -\ln|\csc u + \cot u| + C$
14. $\int \sec^2 u\,du = \tan u + C$
15. $\int \csc^2 u\,du = -\cot u + C$
16. $\int \sec u \tan u\,du = \sec u + C$
17. $\int \csc u \cot u\,du = -\csc u + C$
18. $\int \frac{du}{\sqrt{a^2 - u^2}} = \arcsin\frac{u}{a} + C$
19. $\int \frac{du}{a^2 + u^2} = \frac{1}{a}\arctan\frac{u}{a} + C$
20. $\int \frac{du}{u\sqrt{u^2 - a^2}} = \frac{1}{a}\operatorname{arcsec}\frac{|u|}{a} + C$

Review procedures for fitting an integrand to one of the basic integration rules.

Fitting Integrands to Basic Integration Rules

In this chapter, you will study several integration techniques that greatly expand the set of integrals to which the basic integration rules can be applied. These rules are reviewed at the left. A major step in solving any integration problem is recognizing which basic integration rule to use.

EXAMPLE 1 A Comparison of Three Similar Integrals

See LarsonCalculus.com for an interactive version of this type of example.

Find each integral.

a. $\int \frac{4}{x^2 + 9}\,dx$ **b.** $\int \frac{4x}{x^2 + 9}\,dx$ **c.** $\int \frac{4x^2}{x^2 + 9}\,dx$

Solution

a. Use the Arctangent Rule and let $u = x$ and $a = 3$.

$$\int \frac{4}{x^2 + 9}\,dx = 4\int \frac{1}{x^2 + 3^2}\,dx \qquad \text{Constant Multiple Rule}$$

$$= 4\left(\frac{1}{3}\arctan\frac{x}{3}\right) + C \qquad \text{Arctangent Rule}$$

$$= \frac{4}{3}\arctan\frac{x}{3} + C \qquad \text{Simplify.}$$

b. The Arctangent Rule does not apply because the numerator contains a factor of x. Consider the Log Rule and let $u = x^2 + 9$. Then $du = 2x\,dx$, and you have

$$\int \frac{4x}{x^2 + 9}\,dx = 2\int \frac{2x\,dx}{x^2 + 9} \qquad \text{Constant Multiple Rule}$$

$$= 2\int \frac{du}{u} \qquad \text{Substitute: } u = x^2 + 9.$$

$$= 2\ln|u| + C \qquad \text{Log Rule}$$

$$= 2\ln(x^2 + 9) + C. \qquad \text{Rewrite as a function of } x.$$

c. Because the degree of the numerator is equal to the degree of the denominator, use long division to rewrite the improper rational function as the sum of a polynomial and a proper rational function.

$$\int \frac{4x^2}{x^2 + 9}\,dx = \int \left(4 + \frac{-36}{x^2 + 9}\right)dx \qquad \text{Rewrite using long division.}$$

$$= \int 4\,dx - 36\int \frac{1}{x^2 + 9}\,dx \qquad \text{Rewrite as two integrals.}$$

$$= 4x - 36\left(\frac{1}{3}\arctan\frac{x}{3}\right) + C \qquad \text{Integrate.}$$

$$= 4x - 12\arctan\frac{x}{3} + C \qquad \text{Simplify.}$$

Note in Example 1(c) that some algebra is required before applying any integration rules, and more than one rule is needed to find the resulting integral.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The area of the region is approximately 1.839.

Figure 8.1

EXAMPLE 2 Using Two Basic Rules to Solve a Single Integral

Evaluate $\int_0^1 \frac{x+3}{\sqrt{4-x^2}}\,dx$.

Solution Begin by writing the integral as the sum of two integrals. Then apply the Power Rule and the Arcsine Rule.

$$\begin{aligned}\int_0^1 \frac{x+3}{\sqrt{4-x^2}}\,dx &= \int_0^1 \frac{x}{\sqrt{4-x^2}}\,dx + \int_0^1 \frac{3}{\sqrt{4-x^2}}\,dx \\ &= -\frac{1}{2}\int_0^1 (4-x^2)^{-1/2}(-2x)\,dx + 3\int_0^1 \frac{1}{\sqrt{2^2-x^2}}\,dx \\ &= \left[-(4-x^2)^{1/2} + 3\arcsin\frac{x}{2}\right]_0^1 \\ &= \left(-\sqrt{3} + \frac{\pi}{2}\right) - (-2+0) \\ &\approx 1.839\end{aligned}$$

See Figure 8.1. ■

TECHNOLOGY The Midpoint Rule can be used to give a good approximation of the value of the integral in Example 2 (for $n = 5$, the approximation is 1.837). When using numerical integration, however, you should be aware that the Midpoint Rule does not always give good approximations when one or both of the limits of integration are near a vertical asymptote. For instance, using the Fundamental Theorem of Calculus, you can obtain

$$\int_0^{1.99} \frac{x+3}{\sqrt{4-x^2}}\,dx \approx 6.213.$$

For $n = 5$, the Midpoint Rule gives an approximation of 5.667.

Rules 18, 19, and 20 of the basic integration rules on the preceding page all have expressions involving the sum or difference of two squares:

$$a^2 - u^2, \quad a^2 + u^2, \quad \text{and} \quad u^2 - a^2.$$

These expressions are often apparent after a u-substitution, as shown in Example 3.

EXAMPLE 3 A Substitution Involving $a^2 - u^2$

Find $\int \frac{x^2}{\sqrt{16-x^6}}\,dx$.

Solution Because the radical in the denominator can be written in the form

$$\sqrt{a^2-u^2} = \sqrt{4^2-(x^3)^2}$$

try the substitution $u = x^3$. Then $du = 3x^2\,dx$, and you have

$$\begin{aligned}\int \frac{x^2}{\sqrt{16-x^6}}\,dx &= \frac{1}{3}\int \frac{3x^2\,dx}{\sqrt{4^2-(x^3)^2}} && \text{Rewrite integral.} \\ &= \frac{1}{3}\int \frac{du}{\sqrt{4^2-u^2}} && \text{Substitute: } u = x^3. \\ &= \frac{1}{3}\arcsin\frac{u}{4} + C && \text{Arcsine Rule} \\ &= \frac{1}{3}\arcsin\frac{x^3}{4} + C. && \text{Rewrite as a function of } x.\end{aligned}$$

■

Exploration

A Comparison of Three Similar Integrals Which, if any, of the integrals listed below can be found using the 20 basic integration rules? For any that can be found, do so. For any that cannot, explain why not.

a. $\int \frac{3}{\sqrt{1-x^2}}\,dx$

b. $\int \frac{3x}{\sqrt{1-x^2}}\,dx$

c. $\int \frac{3x^2}{\sqrt{1-x^2}}\,dx$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Two of the most commonly overlooked integration rules are the Log Rule and the Power Rule. Notice in the next two examples how these two integration rules can be disguised.

EXAMPLE 4 A Disguised Form of the Log Rule

Find $\int \frac{1}{1 + e^x}\,dx$.

Solution The integral does not appear to fit any of the basic rules. The quotient form, however, suggests the Log Rule. If you let $u = 1 + e^x$, then $du = e^x\,dx$. To obtain the required du, add and subtract e^x in the numerator.

$$\int \frac{1}{1 + e^x}\,dx = \int \frac{1 + e^x - e^x}{1 + e^x}\,dx \qquad \text{Add and subtract } e^x \text{ in numerator.}$$

$$= \int \left(\frac{1 + e^x}{1 + e^x} - \frac{e^x}{1 + e^x}\right) dx \qquad \text{Rewrite as two fractions.}$$

$$= \int dx - \int \frac{e^x\,dx}{1 + e^x} \qquad \text{Rewrite as two integrals.}$$

$$= x - \ln(1 + e^x) + C \qquad \text{Integrate.}$$

REMARK Remember that you can separate numerators but not denominators. Watch out for this common error when fitting integrands to basic rules. For instance, you cannot separate denominators in Example 4.

$$\frac{1}{1 + e^x} \neq \frac{1}{1} + \frac{1}{e^x}$$

There is usually more than one way to solve an integration problem. For instance, in Example 4, try integrating by multiplying the numerator and denominator by e^{-x} to obtain an integral of the form $-\int du/u$. Show that this procedure produces the same answer. (Be careful: the answer will appear in a different form.)

EXAMPLE 5 A Disguised Form of the Power Rule

Find $\int (\cot x)[\ln(\sin x)]\,dx$.

Solution Again, the integral does not appear to fit any of the basic rules. However, considering the two primary choices for u

$$u = \cot x \quad \text{or} \quad u = \ln(\sin x)$$

you can determine that the second choice is the appropriate one because

$$u = \ln(\sin x) \quad \text{and} \quad du = \frac{\cos x}{\sin x}\,dx = \cot x\,dx.$$

Using this substitution to find the integral produces

$$\int (\cot x)[\ln(\sin x)]\,dx = \int u\,du \qquad \text{Substitute: } u = \ln(\sin x).$$

$$= \frac{u^2}{2} + C \qquad \text{Integrate.}$$

$$= \frac{1}{2}[\ln(\sin x)]^2 + C. \qquad \text{Rewrite as a function of } x.$$

In Example 5, try checking that the derivative of

$$\frac{1}{2}[\ln(\sin x)]^2 + C$$

is the integrand of the original integral.

Big Ideas of Calculus

How do you find integrals such as

$$\int x^2 \ln x\,dx$$

or

$$\int \sin^3 x \cos^4 x\,dx?$$

When you try using the basic integration techniques you have learned so far, you may discover that they do not work. In this chapter, you will study several advanced integration techniques that you can use to evaluate integrals such as these.

Additionally, you will study how to use limits to evaluate integrals in which either one or both of the limits of integration are infinite or the integrand has a finite number of infinite discontinuities. Such integrals are called improper integrals.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Trigonometric identities can often be used to fit integrals to one of the basic integration rules.

EXAMPLE 6 Using Trigonometric Identities

Find $\int \tan^2 2x\,dx$.

TECHNOLOGY

Use a graphing utility to find the integrals in this section. Compare the *forms* of the antiderivatives given by the utility with the forms obtained in the text. Sometimes the forms will be the same, but often they will differ. For instance, why is the antiderivative $\ln 2x + C$ equivalent to the antiderivative $\ln x + C$?

Solution Note that $\tan^2 u$ is not in the list of basic integration rules. However, $\sec^2 u$ is in the list. This suggests the trigonometric identity $\tan^2 u = \sec^2 u - 1$. If you let $u = 2x$, then $du = 2\,dx$. Using this substitution to find the integral produces

$$\int \tan^2 2x\,dx = \frac{1}{2}\int \tan^2 u\,du \qquad \text{Substitute: } u = 2x.$$

$$= \frac{1}{2}\int (\sec^2 u - 1)\,du \qquad \text{Trigonometric identity}$$

$$= \frac{1}{2}\int \sec^2 u\,du - \frac{1}{2}\int du \qquad \text{Rewrite as two integrals.}$$

$$= \frac{1}{2}\tan u - \frac{u}{2} + C \qquad \text{Integrate.}$$

$$= \frac{1}{2}\tan 2x - x + C. \qquad \text{Rewrite as a function of } x.$$

This section concludes with a summary of the common procedures for fitting integrands to the basic integration rules.

Procedures for Fitting Integrands to Basic Integration Rules

Technique	Example
Expand (numerator).	$(1 + e^x)^2 = 1 + 2e^x + e^{2x}$
Separate numerator.	$\dfrac{1 + x}{x^2 + 1} = \dfrac{1}{x^2 + 1} + \dfrac{x}{x^2 + 1}$
Complete the square.	$\dfrac{1}{\sqrt{2x - x^2}} = \dfrac{1}{\sqrt{1 - (x - 1)^2}}$
Divide improper rational function.	$\dfrac{x^2}{x^2 + 1} = 1 - \dfrac{1}{x^2 + 1}$
Add and subtract terms in numerator.	$\dfrac{2x}{x^2 + 2x + 1} = \dfrac{2x + 2 - 2}{x^2 + 2x + 1} = \dfrac{2x + 2}{x^2 + 2x + 1} - \dfrac{2}{(x + 1)^2}$
Use trigonometric identities.	$\cot^2 x = \csc^2 x - 1$
Multiply and divide by Pythagorean conjugate.	$\dfrac{1}{1 + \sin x} = \left(\dfrac{1}{1 + \sin x}\right)\left(\dfrac{1 - \sin x}{1 - \sin x}\right) = \dfrac{1 - \sin x}{1 - \sin^2 x} = \dfrac{1 - \sin x}{\cos^2 x} = \sec^2 x - \dfrac{\sin x}{\cos^2 x}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

8.1 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain how to integrate a rational function with a numerator and denominator of the same degree.
2. State the procedure you should use to fit each integrand to the basic integration rules. Do not integrate.

(a) $\int \frac{2+x}{x^2+9}\,dx$ (b) $\int \cot^2 x\,dx$

Choosing an Antiderivative **In Exercises 3 and 4, select the correct antiderivative.**

3. $\int \frac{x}{\sqrt{x^2+1}}\,dx$

(a) $2\sqrt{x^2+1}+C$ (b) $\sqrt{x^2+1}+C$

(c) $\frac{1}{2}\sqrt{x^2+1}+C$ (d) $\ln(x^2+1)+C$

4. $\int \frac{1}{x^2+1}\,dx$

(a) $\ln\sqrt{x^2+1}+C$ (b) $\frac{2x}{(x^2+1)^2}+C$

(c) $\arctan x+C$ (d) $\ln(x^2+1)+C$

Choosing a Formula **In Exercises 5–14, state the basic integration formula you can use to find the indefinite integral, and identify u and a when appropriate. Do not integrate.**

5. $\int (5x-3)^4\,dx$
6. $\int \frac{2t+1}{t^2+t-4}\,dt$
7. $\int \frac{1}{\sqrt{x}(1-2\sqrt{x})}\,dx$
8. $\int \frac{2}{(2t-1)^2+4}\,dt$
9. $\int \frac{3}{\sqrt{1-t^2}}\,dt$
10. $\int \frac{-2x}{\sqrt{x^2-4}}\,dx$
11. $\int t\sin t^2\,dt$
12. $\int \sec 5x\tan 5x\,dx$
13. $\int (\cos x)e^{\sin x}\,dx$
14. $\int \frac{1}{x\sqrt{x^2-4}}\,dx$

Finding an Indefinite Integral **In Exercises 15–46, find the indefinite integral.**

15. $\int 14(x-5)^6\,dx$
16. $\int \frac{5}{(t+6)^3}\,dt$
17. $\int \frac{7}{(z-10)^7}\,dz$
18. $\int t^3\sqrt{t^4+1}\,dt$
19. $\int \left[z^2+\frac{1}{(1-z)^6}\right]dz$
20. $\int \left[4x-\frac{2}{(2x+3)^2}\right]dx$
21. $\int \frac{t^2-3}{-t^3+9t+1}\,dt$
22. $\int \frac{x+1}{\sqrt{3x^2+6x}}\,dx$
23. $\int \frac{x^2}{x-1}\,dx$
24. $\int \frac{3x}{x+4}\,dx$
25. $\int \frac{x+2}{x+1}\,dx$
26. $\int \left(\frac{1}{9z-5}-\frac{1}{9z+5}\right)dz$
27. $\int (5+4x^2)^2\,dx$
28. $\int x\left(3+\frac{2}{x}\right)^2\,dx$
29. $\int x\cos 2\pi x^2\,dx$
30. $\int \csc \pi x\cot \pi x\,dx$
31. $\int \frac{\sin x}{\sqrt{\cos x}}\,dx$
32. $\int \frac{\csc^2 3t}{\cot 3t}\,dt$
33. $\int \frac{2}{e^{-x}+1}\,dx$
34. $\int \frac{4}{3-e^x}\,dx$
35. $\int \frac{\ln x^2}{x}\,dx$
36. $\int (\tan x)[\ln(\cos x)]\,dx$
37. $\int \frac{1+\cos\alpha}{\sin\alpha}\,d\alpha$
38. $\int \frac{1}{\cos\theta-1}\,d\theta$
39. $\int \frac{-1}{\sqrt{1-(4t+1)^2}}\,dt$
40. $\int \frac{1}{25+4x^2}\,dx$
41. $\int \frac{\tan(2/t)}{t^2}\,dt$
42. $\int \frac{e^{-1/t^3}}{t^4}\,dt$
43. $\int \frac{6}{z\sqrt{9z^2-25}}\,dz$
44. $\int \frac{1}{(x-1)\sqrt{4x^2-8x+3}}\,dx$
45. $\int \frac{4}{4x^2+4x+65}\,dx$
46. $\int \frac{1}{x^2-4x+9}\,dx$

Slope Field **In Exercises 47 and 48, a differential equation, a point, and a slope field are given. (a) Sketch two approximate solutions of the differential equation on the slope field, one of which passes through the given point. (To print an enlarged copy of the graph, go to *MathGraphs.com*.) (b) Use integration and the given point to find the particular solution of the differential equation and use a graphing utility to graph the solution. Compare the result with the sketch in part (a) that passes through the given point.**

47. $\frac{ds}{dt}=\frac{t}{\sqrt{1-t^4}}$, $\left(0,-\frac{1}{2}\right)$



48. $\frac{dy}{dx}=\frac{1}{\sqrt{4x-x^2}}$, $\left(2,\frac{1}{2}\right)$



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Slope Field **In Exercises 49 and 50, use a graphing utility to graph the slope field for the differential equation and graph the solution satisfying the specified initial condition.**

49. $\frac{dy}{dx} = 0.8y,\ y(0) = 4$

50. $\frac{dy}{dx} = 5 - y,\ y(0) = 1$

Differential Equation **In Exercises 51–56, find the general solution of the differential equation.**

51. $\frac{dy}{dx} = (e^x + 5)^2$

52. $\frac{dy}{dx} = (4 - e^{2x})^2$

53. $\frac{dr}{dt} = \frac{10e^t}{\sqrt{1 - e^{2t}}}$

54. $\frac{dr}{dt} = \frac{(1 + e^t)^2}{e^{3t}}$

55. $(4 + \tan^2 x)y' = \sec^2 x$

56. $y' = \frac{1}{x\sqrt{4x^2 - 9}}$

Evaluating a Definite Integral **In Exercises 57–72, evaluate the definite integral. Use a graphing utility to verify your result.**

57. $\int_{2/3}^{1} (2 - 3t)^4\,dt$

58. $\int_{-1}^{0} \frac{5}{(t + 2)^{11}}\,dt$

59. $\int_{0}^{\pi/4} \cos 2x\,dx$

60. $\int_{0}^{\pi} \sin^2 t \cos t\,dt$

61. $\int_{0}^{1} xe^{-x^2}\,dx$

62. $\int_{1}^{e} \frac{1 - \ln x}{x}\,dx$

63. $\int_{2}^{3} \frac{\ln(x + 1)^3}{x + 1}\,dx$

64. $\int_{-3}^{1} \frac{e^x}{e^{2x} + 2e^x + 1}\,dx$

65. $\int_{0}^{8} \frac{2x}{\sqrt{x^2 + 36}}\,dx$

66. $\int_{1}^{3} \frac{2x^2 + 3x - 2}{x}\,dx$

67. $\int_{3}^{5} \frac{2t}{t^2 - 4t + 4}\,dt$

68. $\int_{2}^{4} \frac{4x^3}{x^4 - 6x^2 + 9}\,dx$

69. $\int_{0}^{2/\sqrt{3}} \frac{1}{4 + 9x^2}\,dx$

70. $\int_{0}^{7} \frac{1}{\sqrt{100 - x^2}}\,dx$

71. $\int_{-4}^{0} 3^{1-x}\,dx$

72. $\int_{0}^{1} 7^{x^2+2x}(x + 1)\,dx$

Finding an Integral Using Technology **In Exercises 73–76, use a graphing utility to find the integral. Use the graphing utility to graph two antiderivatives. Describe the relationship between the graphs of the two antiderivatives.**

73. $\int \frac{1}{x^2 + 4x + 13}\,dx$

74. $\int \frac{x - 2}{x^2 + 4x + 13}\,dx$

75. $\int \frac{1}{1 + \sin\theta}\,d\theta$

76. $\int \left(\frac{e^x + e^{-x}}{2}\right)^3 dx$

Area **In Exercises 77–80, find the area of the given region.**

77. $y = (-4x + 6)^{3/2}$



78. $y = \frac{3x + 2}{x^2 + 9}$



79. $y^2 = x^2(1 - x^2)$



80. $y = \sin 2x$



Exploring Concepts

81. When evaluating

$$\int_{-1}^{1} x^2\,dx$$

is it appropriate to substitute

$$u = x^2, \quad x = \sqrt{u}, \quad \text{and} \quad dx = \frac{du}{2\sqrt{u}}$$

to obtain

$$\frac{1}{2}\int_{1}^{1} \sqrt{u}\,du = 0?$$ Explain.

82. Show that

$$\sec x = \frac{\sin x}{\cos x} + \frac{\cos x}{1 + \sin x}.$$

Then use this identity to derive the basic integration rule

$$\int \sec x\,dx = \ln|\sec x + \tan x| + C.$$

83. Finding Constants Determine the constants a and b such that $\sin x + \cos x = a\sin(x + b)$. Use this result to integrate

$$\int \frac{dx}{\sin x + \cos x}.$$

84. Area The graphs of $f(x) = x$ and $g(x) = ax^2$ intersect at the points $(0, 0)$ and $(1/a, 1/a)$. Find a $(a > 0)$ such that the area of the region bounded by the graphs of these two functions is $\frac{2}{3}$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

85. Comparing Antiderivatives

(a) Explain why the antiderivative $y_1 = e^{x+C_1}$ is equivalent to the antiderivative $y_2 = Ce^x$.

(b) Explain why the antiderivative $y_1 = \sec^2 x + C_1$ is equivalent to the antiderivative $y_2 = \tan^2 x + C$.

86. HOW DO YOU SEE IT? Using the graph, is $\int_0^5 f(x)\,dx$ positive or negative? Explain.



Approximation **In Exercises 87 and 88, determine which value best approximates the area of the region between the x-axis and the graph of the function over the given interval. Make your selection on the basis of a sketch of the region, not by performing calculations.**

87. $f(x) = \dfrac{4x}{x^2 + 1}$, $[0, 2]$

(a) 3 (b) 1 (c) -8 (d) 8 (e) 10

88. $f(x) = \dfrac{4}{x^2 + 1}$, $[0, 2]$

(a) 3 (b) 1 (c) -4 (d) 4 (e) 10

Interpreting Integrals **In Exercises 89 and 90, (a) sketch the region whose area is given by the integral, (b) sketch the solid whose volume is given by the integral when the disk method is used, and (c) sketch the solid whose volume is given by the integral when the shell method is used. (There is more than one correct answer for each part.)**

89. $\int_0^2 2\pi x^2\,dx$ **90.** $\int_0^4 \pi y\,dy$

91. Volume The region bounded by $y = e^{-x^2}$, $y = 0$, $x = 0$, and $x = b$ $(b > 0)$ is revolved about the y-axis.

(a) Find the volume of the solid generated when $b = 1$.

(b) Find b such that the volume of the solid generated is $\frac{4}{3}$ cubic units.

92. Volume Consider the region bounded by the graphs of $x = 0$, $y = \cos x^2$, $y = \sin x^2$, and $x = \sqrt{x}/2$. Find the volume of the solid generated by revolving the region about the y-axis.

93. Arc Length Find the arc length of the graph of $y = \ln(\sin x)$ from $x = \pi/4$ to $x = \pi/2$.

94. Arc Length Find the arc length of the graph of $y = \ln(\cos x)$ from $x = 0$ to $x = \pi/3$.

95. Surface Area Find the area of the surface formed by revolving the graph of $y = 2\sqrt{x}$ on the interval $[0, 9]$ about the x-axis.

96. Centroid Find the centroid of the region bounded by the graphs of

$$y = \frac{1}{2x + 1}, \quad y = 0, \quad x = 0, \quad \text{and} \quad x = 2.$$

Average Value of a Function **In Exercises 97 and 98, find the average value of the function over the given interval.**

97. $f(x) = \dfrac{1}{1 + x^2}$, $-3 \le x \le 3$

98. $f(x) = \sin nx$, $0 \le x \le \pi/n$, n is a positive integer.

Arc Length **In Exercises 99 and 100, use the integration capabilities of a graphing utility to approximate the arc length of the curve over the given interval.**

99. $y = \tan \pi x$, $\left[0, \frac{1}{4}\right]$ **100.** $y = x^{2/3}$, $[1, 8]$

101. Finding a Pattern

(a) Find $\int \cos^3 x\,dx$.

(b) Find $\int \cos^5 x\,dx$.

(c) Find $\int \cos^7 x\,dx$.

(d) Explain how to find $\int \cos^{15} x\,dx$ without actually integrating.

102. Finding a Pattern

(a) Write $\int \tan^3 x\,dx$ in terms of $\int \tan x\,dx$. Then find $\int \tan^3 x\,dx$.

(b) Write $\int \tan^5 x\,dx$ in terms of $\int \tan^3 x\,dx$.

(c) Write $\int \tan^{2k+1} x\,dx$, where k is a positive integer, in terms of $\int \tan^{2k-1} x\,dx$.

(d) Explain how to find $\int \tan^{15} x\,dx$ without actually integrating.

103. Methods of Integration Show that the following results are equivalent. (You will learn about integration by tables in Section 8.7.)

Integration by tables:

$$\int \sqrt{x^2 + 1}\,dx = \frac{1}{2}\left(x\sqrt{x^2 + 1} + \ln\left|x + \sqrt{x^2 + 1}\right|\right) + C$$

Integration by graphing utility:

$$\int \sqrt{x^2 + 1}\,dx = \frac{1}{2}\left[x\sqrt{x^2 + 1} + \operatorname{arcsinh}(x)\right] + C$$

PUTNAM EXAM CHALLENGE

104. Evaluate $\displaystyle\int_2^4 \frac{\sqrt{\ln(9 - x)}\,dx}{\sqrt{\ln(9 - x)} + \sqrt{\ln(x + 3)}}$.

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

8.2 Integration by Parts

Find an antiderivative using integration by parts.

Integration by Parts

In this section, you will study an important integration technique called **integration by parts.** This technique can be applied to a wide variety of functions and is particularly useful for integrands involving *products* of algebraic and transcendental functions. For instance, integration by parts works well with integrals such as

$$\int x \ln x \, dx, \quad \int x^2 e^x \, dx, \quad \text{and} \quad \int e^x \sin x \, dx.$$

Integration by parts is based on the formula for the derivative of a product

$$\frac{d}{dx}[uv] = u\frac{dv}{dx} + v\frac{du}{dx} \qquad \text{Product Rule}$$

$$= uv' + vu' \qquad \text{Rewrite using prime notation.}$$

where both u and v are differentiable functions of x. When u' and v' are continuous, you can integrate each side of this equation to obtain

$$uv = \int uv' \, dx + \int vu' \, dx \qquad \text{Integrate each side.}$$

$$= \int u \, dv + \int v \, du. \qquad \text{Write in differential form.}$$

By rewriting this equation, you obtain the next theorem.

THEOREM 8.1 Integration by Parts

If u and v are functions of x and have continuous derivatives, then

$$\int u \, dv = uv - \int v \, du.$$

This formula expresses the original integral in terms of another integral. Depending on the choices of u and dv, it may be easier to find the second integral than the original one. Because the choices of u and dv are critical in the integration by parts process, the guidelines below are provided.

Guidelines for Integration by Parts

1. Try letting dv be the most complicated portion of the integrand that fits a basic integration rule. Then u will be the remaining portion of the integrand.
2. Try letting u be the portion of the integrand whose derivative is a function simpler than u. Then dv will be the remaining portion of the integrand.

Note that dv always includes the dx of the original integrand.

When using integration by parts, note that you can first choose dv or first choose u. After you choose, however, the choice of the other factor is determined—it must be the remaining portion of the integrand. Also note that dv must contain the differential dx of the original integral.

Exploration

Proof Without Words

Here is a different approach to proving the formula for integration by parts. This approach is from "Proof Without Words: Integration by Parts" by Roger B. Nelsen, *Mathematics Magazine,* 64, No. 2, April 1991, p. 130, by permission of the author.



Area + Area $= qs - pr$

$$\int_r^s u \, dv + \int_q^p v \, du = \Big[uv\Big]_{(p,\,r)}^{(q,\,s)}$$

$$\int_r^s u \, dv = \Big[uv\Big]_{(p,\,r)}^{(q,\,s)} - \int_q^p v \, du$$

Explain how this graph proves the theorem. Which notation in this proof is unfamiliar? What do you think it means?

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 1 Integration by Parts

Find $\int xe^x\,dx$.

Solution To apply integration by parts, you need to write the integral in the form $\int u\,dv$. There are several ways to do this.

$$\int \underbrace{(x)}_{u}\underbrace{(e^x\,dx)}_{dv}, \quad \int \underbrace{(e^x)}_{u}\underbrace{(x\,dx)}_{dv}, \quad \int \underbrace{(1)}_{u}\underbrace{(xe^x\,dx)}_{dv}, \quad \int \underbrace{(xe^x)}_{u}\underbrace{(dx)}_{dv}$$

The guidelines on the preceding page suggest the first option because the derivative of $u = x$ is simpler than x, and $dv = e^x\,dx$ is the most complicated portion of the integrand that fits a basic integration formula.

$$dv = e^x\,dx \quad \Rightarrow \quad v = \int dv = \int e^x\,dx = e^x$$
$$u = x \quad \Rightarrow \quad du = dx$$

Now, integration by parts produces

$$\int u\,dv = uv - \int v\,du \qquad \text{Integration by parts formula}$$
$$\int xe^x\,dx = xe^x - \int e^x\,dx \qquad \text{Substitute.}$$
$$= xe^x - e^x + C. \qquad \text{Integrate.}$$

Use differentiation to check that $xe^x - e^x + C$ is the integrand of the *original* integral.

REMARK In Example 1, note that it is not necessary to include a constant of integration when solving

$$v = \int e^x\,dx = e^x + C_1.$$

To illustrate this, replace $v = e^x$ by $v = e^x + C_1$ and apply integration by parts. Do you obtain the same result?

EXAMPLE 2 Integration by Parts

Find $\int x^2 \ln x\,dx$.

Solution In this case, x^2 is easier to integrate than $\ln x$. Furthermore, the derivative of $\ln x$ is simpler than $\ln x$. So, let $dv = x^2\,dx$ and let $u = \ln x$.

$$dv = x^2\,dx \quad \Rightarrow \quad v = \int x^2\,dx = \frac{x^3}{3}$$
$$u = \ln x \quad \Rightarrow \quad du = \frac{1}{x}\,dx$$

Integration by parts produces

$$\int u\,dv = uv - \int v\,du \qquad \text{Integration by parts formula}$$
$$\int x^2 \ln x\,dx = \frac{x^3}{3}\ln x - \int \left(\frac{x^3}{3}\right)\left(\frac{1}{x}\right)dx \qquad \text{Substitute.}$$
$$= \frac{x^3}{3}\ln x - \frac{1}{3}\int x^2\,dx \qquad \text{Simplify.}$$
$$= \frac{x^3}{3}\ln x - \frac{x^3}{9} + C. \qquad \text{Integrate.}$$

You can check this result by differentiating.

$$\frac{d}{dx}\left[\frac{x^3}{3}\ln x - \frac{x^3}{9} + C\right] = \frac{x^3}{3}\left(\frac{1}{x}\right) + (\ln x)(x^2) - \frac{x^2}{3} = x^2 \ln x$$

TECHNOLOGY Use a graphing utility to graph

$$f(x) = \int x^2 \ln x\,dx$$

and

$$g(x) = \frac{x^3}{3}\ln x - \frac{x^3}{9}$$

in the same viewing window. Does this graph support the solution to Example 2? Explain.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

One surprising application of integration by parts involves integrands consisting of single terms, such as

$$\int \ln x\,dx \quad \text{or} \quad \int \arcsin x\,dx.$$

In these cases, try letting $dv = dx$, as shown in the next two examples.

FOR FURTHER INFORMATION To learn how integration by parts is used to prove Stirling's approximation

$$\ln(n!) = n \ln n - n$$

see the article "The Validity of Stirling's Approximation: A Physical Chemistry Project" by A. S. Wallner and K. A. Brandt in *Journal of Chemical Education.*

EXAMPLE 3 An Integrand with a Single Term

Find $\int \ln x\,dx$.

Solution The integrand is not a product, so let $dv = dx$ and let $u = \ln x$.

$$dv = dx \quad \Rightarrow \quad v = \int dx = x$$

$$u = \ln x \quad \Rightarrow \quad du = \frac{1}{x}\,dx$$

Next, apply the integration by parts formula.

$$\int u\,dv = uv - \int v\,du \qquad \text{Integration by parts formula}$$

$$\int \ln x\,dx = (\ln x)(x) - \int x\left(\frac{1}{x}\right) dx \qquad \text{Substitute.}$$

$$= x \ln x - \int dx \qquad \text{Simplify.}$$

$$= x \ln x - x + C \qquad \text{Integrate.}$$

EXAMPLE 4 An Integrand with a Single Term

Evaluate $\int_0^1 \arcsin x\,dx$.

Solution Let $dv = dx$ and let $u = \arcsin x$.

$$dv = dx \quad \Rightarrow \quad v = \int dx = x$$

$$u = \arcsin x \quad \Rightarrow \quad du = \frac{1}{\sqrt{1 - x^2}}\,dx$$

Next, find the antiderivative.

$$\int u\,dv = uv - \int v\,du \qquad \text{Integration by parts formula}$$

$$\int \arcsin x\,dx = x \arcsin x - \int \frac{x}{\sqrt{1 - x^2}}\,dx \qquad \text{Substitute.}$$

$$= x \arcsin x + \frac{1}{2}\int (1 - x^2)^{-1/2}(-2x)\,dx \qquad \text{Rewrite.}$$

$$= x \arcsin x + \sqrt{1 - x^2} + C \qquad \text{Integrate.}$$

Finally, use this antiderivative to evaluate the definite integral.

$$\int_0^1 \arcsin x\,dx = \left[x \arcsin x + \sqrt{1 - x^2}\right]_0^1 = \frac{\pi}{2} - 1 \approx 0.571$$

The area represented by this definite integral is shown in Figure 8.2.



The area of the region is approximately 0.571.

Figure 8.2

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Some integrals require repeated use of the integration by parts formula, as shown in the next example.

EXAMPLE 5 Repeated Use of Integration by Parts

Find $\int x^2 \sin x \, dx$.

Solution The factors x^2 and $\sin x$ are equally easy to integrate. Notice, however, that the derivative of x^2 becomes simpler, whereas the derivative of $\sin x$ does not. So, let $dv = \sin x \, dx$ and let $u = x^2$.

$$dv = \sin x \, dx \quad \Rightarrow \quad v = \int \sin x \, dx = -\cos x$$
$$u = x^2 \quad \Rightarrow \quad du = 2x \, dx$$

Now, integration by parts produces

$$\int x^2 \sin x \, dx = -x^2 \cos x + \int 2x \cos x \, dx. \qquad \text{First use of integration by parts}$$

This first use of integration by parts has succeeded in simplifying the original integral, but the integral on the right still does not fit a basic integration rule. To find that integral, you can apply integration by parts again. This time, let $dv = \cos x \, dx$ and let $u = 2x$.

$$dv = \cos x \, dx \quad \Rightarrow \quad v = \int \cos x \, dx = \sin x$$
$$u = 2x \quad \Rightarrow \quad du = 2 \, dx$$

Now, integration by parts produces

$$\int 2x \cos x \, dx = 2x \sin x - \int 2 \sin x \, dx \qquad \text{Second use of integration by parts}$$
$$= 2x \sin x + 2 \cos x + C.$$

Combining these two results, you have

$$\int x^2 \sin x \, dx = -x^2 \cos x + 2x \sin x + 2 \cos x + C.$$

TECHNOLOGY

Remember that there are several ways to use technology to evaluate a definite integral: (1) use a numerical approximation such as the Midpoint Rule, (2) use a graphing utility to find the antiderivative and then apply the Fundamental Theorem of Calculus, or (3) use the *numerical integration* feature of a graphing utility. These methods, however, have shortcomings. To apply the Fundamental Theorem of Calculus, the graphing utility must be able to find the antiderivative. Often, for the *numerical integration* feature of a graphing utility, you are given no indication of the degree of accuracy of the approximation.

When making repeated applications of integration by parts, you need to be careful not to interchange the substitutions in successive applications. For instance, in Example 5, the first substitution was $u = x^2$ and $dv = \sin x \, dx$. If, in the second application, you had switched the substitution to $u = \cos x$ and $dv = 2x \, dx$, you would have obtained

$$\int x^2 \sin x \, dx = -x^2 \cos x + \int 2x \cos x \, dx$$
$$= -x^2 \cos x + x^2 \cos x + \int x^2 \sin x \, dx$$
$$= \int x^2 \sin x \, dx$$

thereby undoing the previous integration and returning to the *original* integral. When making repeated applications of integration by parts, you should also watch for the appearance of a *constant multiple* of the original integral. For instance, this occurs when you use integration by parts to find $\int e^x \cos 2x \, dx$, and it also occurs in Example 6 on the next page.

The integral in Example 6 is an important one. In Section 8.4 (Example 6), you will learn that it is used to find the arc length of a parabolic segment.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 6 Integration by Parts

Find $\int \sec^3 x\,dx$.

Solution The most complicated portion of the integrand that can be easily integrated is $\sec^2 x$, so let $dv = \sec^2 x\,dx$ and $u = \sec x$.

$$dv = \sec^2 x\,dx \quad \Rightarrow \quad v = \int \sec^2 x\,dx = \tan x$$

$$u = \sec x \quad \Rightarrow \quad du = \sec x \tan x\,dx$$

Integration by parts produces

$$\int u\,dv = uv - \int v\,du \qquad \text{Integration by parts formula}$$

$$\int \sec^3 x\,dx = \sec x \tan x - \int \sec x \tan^2 x\,dx \qquad \text{Substitute.}$$

$$\int \sec^3 x\,dx = \sec x \tan x - \int (\sec x)(\sec^2 x - 1)\,dx \qquad \text{Trigonometric identity}$$

$$\int \sec^3 x\,dx = \sec x \tan x - \int \sec^3 x\,dx + \int \sec x\,dx \qquad \text{Rewrite.}$$

$$2\int \sec^3 x\,dx = \sec x \tan x + \int \sec x\,dx \qquad \text{Collect like integrals.}$$

$$2\int \sec^3 x\,dx = \sec x \tan x + \ln|\sec x + \tan x| + C \qquad \text{Integrate.}$$

$$\int \sec^3 x\,dx = \frac{1}{2}\sec x \tan x + \frac{1}{2}\ln|\sec x + \tan x| + C. \qquad \text{Divide by 2.}$$

EXAMPLE 7 Finding a Centroid

A machine part is modeled by the region bounded by the graph of $y = \sin x$ and the x-axis, $0 \le x \le \pi/2$, as shown in Figure 8.3. Find the centroid of this region.



Figure 8.3

Solution Begin by finding the area of the region.

$$A = \int_0^{\pi/2} \sin x\,dx = \Big[-\cos x\Big]_0^{\pi/2} = 1$$

Now, you can find the coordinates of the centroid. To evaluate the integral for $\bar{y}$, first rewrite the integrand using the trigonometric identity $\sin^2 x = (1 - \cos 2x)/2$.

$$\bar{y} = \frac{1}{A}\int_0^{\pi/2} \frac{\sin x}{2}(\sin x)\,dx = \frac{1}{4}\int_0^{\pi/2} (1 - \cos 2x)\,dx = \frac{1}{4}\Big[x - \frac{\sin 2x}{2}\Big]_0^{\pi/2} = \frac{\pi}{8}$$

You can evaluate the integral for $\bar{x}$, $(1/A)\int_0^{\pi/2} x \sin x\,dx$, with integration by parts. To do this, let $dv = \sin x\,dx$ and $u = x$. This produces $v = -\cos x$ and $du = dx$, and you have

$$\int x \sin x\,dx = -x\cos x + \int \cos x\,dx = -x\cos x + \sin x + C.$$

Finally, you can determine $\bar{x}$ to be

$$\bar{x} = \frac{1}{A}\int_0^{\pi/2} x \sin x\,dx = \Big[-x\cos x + \sin x\Big]_0^{\pi/2} = 1.$$

So, the centroid of the region is $(1, \pi/8)$. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

As you gain experience in using integration by parts, your skill in determining u and dv will increase. The next summary lists several common integrals with suggestions for the choices of u and dv.

REMARK You can use the acronym LIATE as a guideline for choosing u in integration by parts. In order, check the integrand for the following.

Is there a Logarithmic part?

Is there an Inverse trigonometric part?

Is there an Algebraic part?

Is there a Trigonometric part?

Is there an Exponential part?

Common Integrals Using Integration by Parts

1. For integrals of the form

$$\int x^n e^{ax}\,dx, \quad \int x^n \sin ax\,dx, \quad \text{or} \quad \int x^n \cos ax\,dx$$

let $u = x^n$ and let $dv = e^{ax}\,dx$, $\sin ax\,dx$, or $\cos ax\,dx$.

2. For integrals of the form

$$\int x^n \ln x\,dx, \quad \int x^n \arcsin ax\,dx, \quad \text{or} \quad \int x^n \arctan ax\,dx$$

let $u = \ln x$, $\arcsin ax$, or $\arctan ax$ and let $dv = x^n\,dx$.

3. For integrals of the form

$$\int e^{ax} \sin bx\,dx \quad \text{or} \quad \int e^{ax} \cos bx\,dx$$

let $u = \sin bx$ or $\cos bx$ and let $dv = e^{ax}\,dx$.

In problems involving repeated applications of integration by parts, a tabular method can help organize the work, as shown in Example 8. This method works well for integrals of the forms

$$\int x^n \sin ax\,dx, \quad \int x^n \cos ax\,dx, \quad \text{and} \quad \int x^n e^{ax}\,dx.$$

EXAMPLE 8 Using the Tabular Method

See LarsonCalculus.com for an interactive version of this type of example.

Find $\int x^2 \sin 4x\,dx$.

Solution Begin as usual by letting $u = x^2$ and $dv = v'\,dx = \sin 4x\,dx$. Next, create a table consisting of three columns, as shown.

Alternate Signs	u and Its Derivatives	v' and Its Antiderivatives
+	x^2	$\sin 4x$
−	$2x$	$-\frac{1}{4}\cos 4x$
+	2	$-\frac{1}{16}\sin 4x$
−	0	$\frac{1}{64}\cos 4x$

Differentiate until you obtain 0 as a derivative.

To obtain the solution, add the signed products of the diagonal entries.

$$\int x^2 \sin 4x\,dx = x^2\left(-\frac{1}{4}\cos 4x\right) - 2x\left(-\frac{1}{16}\sin 4x\right) + 2\left(\frac{1}{64}\cos 4x\right) + C$$

$$= -\frac{1}{4}x^2 \cos 4x + \frac{1}{8}x \sin 4x + \frac{1}{32}\cos 4x + C$$

FOR FURTHER INFORMATION For more information on the tabular method, see the article "Tabular Integration by Parts" by David Horowitz in *The College Mathematics Journal*, and the article "More on Tabular Integration by Parts" by Leonard Gillman in *The College Mathematics Journal*. To view these articles, go to *MathArticles.com*.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

8.2 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Integration by parts is based on what formula?
2. Describe how to choose u and dv when using integration by parts.
3. How can you use integration by parts on an integrand with a single term that does not fit any of the basic integration rules?
4. Explain when integrating using the tabular method is useful.

Setting Up Integration by Parts **In Exercises 5–10, identify u and dv for finding the integral using integration by parts. Do not integrate.**

5. $\int xe^{9x}\,dx$
6. $\int x^2e^{2x}\,dx$
7. $\int (\ln x)^2\,dx$
8. $\int \ln 5x\,dx$
9. $\int x\sec^2 x\,dx$
10. $\int x^2\cos x\,dx$

Using Integration by Parts **In Exercises 11–14, find the indefinite integral using integration by parts with the given choices of u and dv.**

11. $\int x^3\ln x\,dx;\ u = \ln x,\ dv = x^3\,dx$
12. $\int (7 - x)e^{x/2}\,dx;\ u = 7 - x,\ dv = e^{x/2}\,dx$
13. $\int (2x + 1)\sin 4x\,dx;\ u = 2x + 1,\ dv = \sin 4x\,dx$
14. $\int x\cos 4x\,dx;\ u = x,\ dv = \cos 4x\,dx$

Finding an Indefinite Integral **In Exercises 15–34, find the indefinite integral. (*Note:* Solve by the most convenient method—not all require integration by parts.)**

15. $\int xe^{4x}\,dx$
16. $\int \frac{5x}{e^{2x}}\,dx$
17. $\int x^3e^x\,dx$
18. $\int \frac{e^{1/t}}{t^2}\,dt$
19. $\int t\ln(t + 1)\,dt$
20. $\int x^5\ln 3x\,dx$
21. $\int \frac{(\ln x)^2}{x}\,dx$
22. $\int \frac{\ln x}{x^3}\,dx$
23. $\int \frac{xe^{2x}}{(2x + 1)^2}\,dx$
24. $\int \frac{x^3e^{x^2}}{(x^2 + 1)^2}\,dx$
25. $\int x\sqrt{x - 5}\,dx$
26. $\int \frac{2x}{\sqrt{1 - 6x}}\,dx$
27. $\int x\csc^2 x\,dx$
28. $\int t\csc t\cot t\,dt$
29. $\int x^3\sin x\,dx$
30. $\int x^2\cos x\,dx$
31. $\int \arctan x\,dx$
32. $\int 4\arccos x\,dx$
33. $\int e^{-3x}\sin 5x\,dx$
34. $\int e^{4x}\cos 2x\,dx$

Differential Equation **In Exercises 35–38, find the general solution of the differential equation.**

35. $y' = \ln x$
36. $y' = \arctan\frac{x}{2}$
37. $\frac{dy}{dt} = \frac{t^2}{\sqrt{3 + 5t}}$
38. $\frac{dy}{dx} = x^2\sqrt{x - 3}$

Slope Field **In Exercises 39 and 40, a differential equation, a point, and a slope field are given. (a) Sketch two approximate solutions of the differential equation on the slope field, one of which passes through the given point. (To print an enlarged copy of the graph, go to *MathGraphs.com*.) (b) Use integration and the given point to find the particular solution of the differential equation and use a graphing utility to graph the solution. Compare the result with the sketch in part (a) that passes through the given point.**

39. $\frac{dy}{dx} = x\sqrt{y}\cos x,\ (0, 4)$
40. $\frac{dy}{dx} = e^{-x/3}\sin 2x,\ \left(0, -\frac{18}{37}\right)$





Slope Field **In Exercises 41 and 42, use a graphing utility to graph the slope field for the differential equation and graph the solution satisfying the specified initial condition.**

41. $\frac{dy}{dx} = \frac{x}{y}e^{x/8},\ y(0) = 2$
42. $\frac{dy}{dx} = \frac{x}{y}\sin x,\ y(0) = 4$

Evaluating a Definite Integral **In Exercises 43–52, evaluate the definite integral. Use a graphing utility to verify your result.**

43. $\int_0^3 xe^{x/2}\,dx$
44. $\int_0^2 x^2e^{-2x}\,dx$
45. $\int_0^{\pi/4} x\cos 2x\,dx$
46. $\int_0^{\pi} x\sin 2x\,dx$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

47. $\int_0^{1/2} \arccos x\, dx$

48. $\int_0^1 x \arcsin x^2\, dx$

49. $\int_0^1 e^x \sin x\, dx$

50. $\int_0^1 \ln(4 + x^2)\, dx$

51. $\int_2^4 x \operatorname{arcsec} x\, dx$

52. $\int_0^{\pi/8} x \sec^2 2x\, dx$

Using the Tabular Method **In Exercises 53–58, use the tabular method to find the indefinite integral.**

53. $\int x^2 e^{2x}\, dx$

54. $\int (1 - x)(e^{-x} + 1)\, dx$

55. $\int (x + 2)^2 \sin x\, dx$

56. $\int x^3 \cos 2x\, dx$

57. $\int (6 + x)\sqrt{4x + 9}\, dx$

58. $\int x^2(x - 2)^{3/2}\, dx$

Exploring Concepts

59. Write an integral that requires three applications of integration by parts. Explain why three applications are needed.

60. When finding $\int x \sin x\, dx$, explain how letting $u = \sin x$ and $dv = x\, dx$ makes the solution more difficult to find.

61. State whether you would use integration by parts to find each integral. If so, identify what you would use for u and dv. Explain your reasoning.

(a) $\int \frac{\ln x}{x}\, dx$ (b) $\int x \ln x\, dx$ (c) $\int x^2 e^{-3x}\, dx$

(d) $\int 2xe^{x^2}\, dx$ (e) $\int \frac{x}{\sqrt{x + 1}}\, dx$ (f) $\int \frac{x}{\sqrt{x^2 + 1}}\, dx$

62. HOW DO YOU SEE IT? Use the graph of f' shown in the figure to answer the following.



(a) Approximate the slope of f at $x = 2$. Explain.

(b) Approximate any open intervals on which the graph of f is increasing and any open intervals on which it is decreasing. Explain.

Using Two Methods Together **In Exercises 63–66, find the indefinite integral by using substitution followed by integration by parts.**

63. $\int \sin\sqrt{x}\, dx$

64. $\int 2x^3 \cos x^2\, dx$

65. $\int x^5 e^{x^2}\, dx$

66. $\int e^{\sqrt{2x}}\, dx$

67. Using Two Methods Integrate $\int \frac{x^3}{\sqrt{4 + x^2}}\, dx$

(a) by parts, letting $dv = \frac{x}{\sqrt{4 + x^2}}\, dx$.

(b) by substitution, letting $u = 4 + x^2$.

68. Using Two Methods Integrate $\int_0^a x^2\sqrt{a - x}\, dx$

(a) by parts, letting $dv = (a - x)^{1/2}\, dx$.

(b) by substitution, letting $u = \sqrt{a - x}$.

Finding a General Rule **In Exercises 69 and 70, use a graphing utility to find the integrals for $n = 0$, 1, 2, and 3. Use the result to obtain a general rule for the integrals for any positive integer n and test your results for $n = 4$.**

69. $\int x^n \ln x\, dx$

70. $\int x^n e^x\, dx$

Proof **In Exercises 71–76, use integration by parts to prove the formula. (For Exercises 71–74, assume that n is a positive integer.)**

71. $\int x^n \sin x\, dx = -x^n \cos x + n \int x^{n-1} \cos x\, dx$

72. $\int x^n \cos x\, dx = x^n \sin x - n \int x^{n-1} \sin x\, dx$

73. $\int x^n \ln x\, dx = \frac{x^{n+1}}{(n + 1)^2}[-1 + (n + 1) \ln x] + C$

74. $\int x^n e^{ax}\, dx = \frac{x^n e^{ax}}{a} - \frac{n}{a} \int x^{n-1} e^{ax}\, dx$

75. $\int e^{ax} \sin bx\, dx = \frac{e^{ax}(a \sin bx - b \cos bx)}{a^2 + b^2} + C$

76. $\int e^{ax} \cos bx\, dx = \frac{e^{ax}(a \cos bx + b \sin bx)}{a^2 + b^2} + C$

Using Formulas **In Exercises 77–82, find the indefinite integral by using the appropriate formula from Exercises 71–76.**

77. $\int x^2 \sin x\, dx$

78. $\int x^2 \cos x\, dx$

79. $\int x^5 \ln x\, dx$

80. $\int x^3 e^{2x}\, dx$

81. $\int e^{-3x} \sin 4x\, dx$

82. $\int e^{2x} \cos 3x\, dx$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Area **In Exercises 83–86, use a graphing utility to graph the region bounded by the graphs of the equations. Then find the area of the region analytically.**

83. $y = 2xe^{-x},\ y = 0,\ x = 3$

84. $y = \frac{1}{10}xe^{3x},\ y = 0,\ x = 0,\ x = 2$

85. $y = e^{-x}\sin \pi x,\ y = 0,\ x = 1$

86. $y = x^3 \ln x,\ y = 0,\ x = 1,\ x = 3$

87. Area, Volume, and Centroid Given the region bounded by the graphs of $y = \ln x$, $y = 0$, and $x = e$, find

(a) the area of the region.

(b) the volume of the solid generated by revolving the region about the x-axis.

(c) the volume of the solid generated by revolving the region about the y-axis.

(d) the centroid of the region.

88. Area, Volume, and Centroid Given the region bounded by the graphs of $y = x \sin x$, $y = 0$, $x = 0$, and $x = \pi$, find

(a) the area of the region.

(b) the volume of the solid generated by revolving the region about the x-axis.

(c) the volume of the solid generated by revolving the region about the y-axis.

(d) the centroid of the region.

89. Centroid Find the centroid of the region bounded by the graphs of $y = \arcsin x$, $x = 0$, and $y = \pi/2$. How is this problem related to Example 7 in this section?

90. Centroid Find the centroid of the region bounded by the graphs of $f(x) = x^2$, $g(x) = 2^x$, $x = 2$, and $x = 4$.

91. Average Displacement A damping force affects the vibration of a spring so that the displacement of the spring is given by

$$y = e^{-4t}(\cos 2t + 5 \sin 2t).$$

Find the average value of y on the interval from $t = 0$ to $t = \pi$.

92. Memory Model

A model for the ability M of a child to memorize, measured on a scale from 0 to 10, is given by

$$M = 1 + 1.6t \ln t, \quad 0 < t \le 4$$

where t is the child's age in years. Find the average value of this model

(a) between the child's first and second birthdays.

(b) between the child's third and fourth birthdays.

TY Lim/Shutterstock.com

Present Value **In Exercises 93 and 94, find the present value P of a continuous income flow of $c(t)$ dollars per year using**

$$P = \int_0^{t_1} c(t)e^{-rt}\,dt$$

where t_1 is the time in years and r is the annual interest rate compounded continuously.

93. $c(t) = 100{,}000 + 4000t,\ r = 5\%,\ t_1 = 10$

94. $c(t) = 1000 + 120t,\ r = 2\%,\ t_1 = 30$

Integrals Used to Find Fourier Coefficients **In Exercises 95 and 96, verify the value of the definite integral, where n is a positive integer.**

95. $$\int_{-\pi}^{\pi} x \sin nx\,dx = \begin{cases} \frac{2\pi}{n}, & n \text{ is odd} \\ -\frac{2\pi}{n}, & n \text{ is even} \end{cases}$$

96. $$\int_{-\pi}^{\pi} x^2 \cos nx\,dx = \frac{(-1)^n 4\pi}{n^2}$$

97. Vibrating String A string stretched between the two points $(0, 0)$ and $(2, 0)$ is plucked by displacing the string h units at its midpoint. The motion of the string is modeled by a **Fourier Sine Series** whose coefficients are given by

$$b_n = h\int_0^1 x \sin\frac{n\pi x}{2}\,dx + h\int_1^2 (-x + 2)\sin\frac{n\pi x}{2}\,dx.$$

Find b_n.

98. Finding a Pattern Find the area bounded by the graphs of $y = x \sin x$ and $y = 0$ over each interval.

(a) $[0, \pi]$ (b) $[\pi, 2\pi]$ (c) $[2\pi, 3\pi]$

Describe any patterns that you notice. What is the area between the graphs of $y = x \sin x$ and $y = 0$ over the interval $[n\pi, (n + 1)\pi]$, where n is any nonnegative integer? Explain.

99. Finding an Error Find the fallacy in the following argument that $0 = 1$.

$$dv = dx \Rightarrow v = \int dx = x$$

$$u = \frac{1}{x} \Rightarrow du = -\frac{1}{x^2}dx$$

$$0 + \int \frac{dx}{x} = \left(\frac{1}{x}\right)(x) - \int\left(-\frac{1}{x^2}\right)(x)\,dx$$

$$= 1 + \int \frac{dx}{x}$$

So, $0 = 1$.

PUTNAM EXAM CHALLENGE

100. Find a real number c and a positive number L for which

$$\lim_{r\to\infty} \frac{r^c \int_0^{\pi/2} x^r \sin x\,dx}{\int_0^{\pi/2} x^r \cos x\,dx} = L.$$

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

8.3 Trigonometric Integrals

GO DIGITAL

- **Solve trigonometric integrals involving powers of sine and cosine.**
- **Solve trigonometric integrals involving powers of secant and tangent.**
- **Solve trigonometric integrals involving sines and cosines of two angles.**

SHEILA SCOTT MACINTYRE (1910–1960)

Sheila Scott Macintyre published her first paper on the asymptotic periods of integral functions in 1935. She completed her doctorate work at Aberdeen University, where she taught. In 1958, she accepted a visiting research fellowship at the University of Cincinnati.

See LarsonCalculus.com to read more of this biography.

Integrals Involving Powers of Sine and Cosine

In this section, you will study techniques for finding integrals of the form

$$\int \sin^m x \cos^n x\, dx \quad \text{and} \quad \int \sec^m x \tan^n x\, dx$$

where either m or n is a positive integer. To find antiderivatives for these forms, try to break them into combinations of trigonometric integrals to which you can apply the Power Rule.

For instance, you can find

$$\int \sin^5 x \cos x\, dx$$

with the Power Rule by letting $u = \sin x$. Then, $du = \cos x\, dx$ and you have

$$\int \sin^5 x \cos x\, dx = \int u^5\, du = \frac{u^6}{6} + C = \frac{\sin^6 x}{6} + C.$$

To break up $\int \sin^m x \cos^n x\, dx$ into forms to which you can apply the Power Rule, use the relationships listed below.

$$\sin^2 x + \cos^2 x = 1 \qquad \text{Pythagorean identity}$$

$$\sin^2 x = \frac{1 - \cos 2x}{2} \qquad \text{Power-reducing formula for } \sin^2 x$$

$$\cos^2 x = \frac{1 + \cos 2x}{2} \qquad \text{Power-reducing formula for } \cos^2 x$$

Guidelines for Finding Integrals Involving Powers of Sine and Cosine

1. When the power of the sine is odd and positive, save one sine factor and convert the remaining factors to cosines. Then expand and integrate.

$$\int \sin^{\overbrace{2k+1}^{\text{Odd}}} x \cos^n x\, dx = \int \overbrace{(\sin^2 x)^k}^{\text{Convert to cosines.}} \cos^n x \overbrace{\sin x\, dx}^{\text{Save for } du.} = \int (1 - \cos^2 x)^k \cos^n x \sin x\, dx$$

2. When the power of the cosine is odd and positive, save one cosine factor and convert the remaining factors to sines. Then expand and integrate.

$$\int \sin^m x \cos^{\overbrace{2k+1}^{\text{Odd}}} x\, dx = \int (\sin^m x)\overbrace{(\cos^2 x)^k}^{\text{Convert to sines.}} \overbrace{\cos x\, dx}^{\text{Save for } du.} = \int (\sin^m x)(1 - \sin^2 x)^k \cos x\, dx$$

3. When the powers of both the sine and cosine are even and nonnegative, make repeated use of the formulas

$$\sin^2 x = \frac{1 - \cos 2x}{2} \quad \text{and} \quad \cos^2 x = \frac{1 + \cos 2x}{2}$$

to convert the integrand to odd powers of the cosine. Then proceed as in the second guideline.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 1 Power of Sine Is Odd and Positive

Find $\int \sin^3 x \cos^4 x \, dx$.

Solution Because you expect to use the Power Rule with $u = \cos x$, *save one sine factor* to form du and convert the remaining sine factors to cosines.

$$\begin{aligned}
\int \sin^3 x \cos^4 x \, dx &= \int (\sin^2 x \cos^4 x)(\sin x) \, dx && \text{Rewrite.} \\
&= \int (1 - \cos^2 x) \cos^4 x \sin x \, dx && \text{Trigonometric identity} \\
&= \int (\cos^4 x - \cos^6 x) \sin x \, dx && \text{Multiply.} \\
&= \int \cos^4 x \sin x \, dx - \int \cos^6 x \sin x \, dx && \text{Rewrite.} \\
&= -\int (\cos^4 x)(-\sin x) \, dx + \int (\cos^6 x)(-\sin x) \, dx \\
&= -\frac{\cos^5 x}{5} + \frac{\cos^7 x}{7} + C && \text{Integrate.}
\end{aligned}$$

TECHNOLOGY A graphing utility used to find the integral in Example 1 yielded

$$\int \sin^3 x \cos^4 x \, dx = (-\cos^5 x)\left(\frac{1}{7}\sin^2 x + \frac{2}{35}\right) + C.$$

Is this equivalent to the result obtained in Example 1?

In Example 1, *both* of the powers m and n happened to be positive integers. This strategy will work as long as either m or n is odd and positive. For instance, in the next example, the power of the cosine is 3, but the power of the sine is $-\frac{1}{2}$.

EXAMPLE 2 Power of Cosine Is Odd and Positive

See LarsonCalculus.com for an interactive version of this type of example.

Evaluate $\displaystyle\int_{\pi/6}^{\pi/3} \frac{\cos^3 x}{\sqrt{\sin x}} \, dx$.

Solution Because you expect to use the Power Rule with $u = \sin x$, *save one cosine factor* to form du and convert the remaining cosine factors to sines.

$$\begin{aligned}
\int_{\pi/6}^{\pi/3} \frac{\cos^3 x}{\sqrt{\sin x}} \, dx &= \int_{\pi/6}^{\pi/3} \frac{\cos^2 x \cos x}{\sqrt{\sin x}} \, dx && \text{Rewrite.} \\
&= \int_{\pi/6}^{\pi/3} \frac{(1 - \sin^2 x)(\cos x)}{\sqrt{\sin x}} \, dx && \text{Trigonometric identity} \\
&= \int_{\pi/6}^{\pi/3} \left[(\sin x)^{-1/2} - (\sin x)^{3/2}\right] \cos x \, dx && \text{Divide.} \\
&= \left[\frac{(\sin x)^{1/2}}{1/2} - \frac{(\sin x)^{5/2}}{5/2}\right]_{\pi/6}^{\pi/3} && \text{Integrate.} \\
&= 2\left(\frac{\sqrt{3}}{2}\right)^{1/2} - \frac{2}{5}\left(\frac{\sqrt{3}}{2}\right)^{5/2} - \sqrt{2} + \frac{\sqrt{32}}{80} \\
&\approx 0.239
\end{aligned}$$

Figure 8.4 shows the region whose area is represented by this integral.



The area of the region is approximately 0.239.

Figure 8.4

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 3 Power of Cosine Is Even and Nonnegative

Find $\int \cos^4 x\,dx$.

Solution Because m and n are both even and nonnegative ($m = 0$), you can replace $\cos^4 x$ by

$$\left(\frac{1 + \cos 2x}{2}\right)^2.$$

So, you can integrate as shown.

$$\begin{aligned}
\int \cos^4 x\,dx &= \int \left(\frac{1 + \cos 2x}{2}\right)^2 dx && \text{Power-reducing formula} \\
&= \int \left(\frac{1}{4} + \frac{\cos 2x}{2} + \frac{\cos^2 2x}{4}\right) dx && \text{Expand.} \\
&= \int \left[\frac{1}{4} + \frac{\cos 2x}{2} + \frac{1}{4}\left(\frac{1 + \cos 4x}{2}\right)\right] dx && \text{Power-reducing formula} \\
&= \frac{3}{8}\int dx + \frac{1}{4}\int 2\cos 2x\,dx + \frac{1}{32}\int 4\cos 4x\,dx && \text{Rewrite.} \\
&= \frac{3x}{8} + \frac{\sin 2x}{4} + \frac{\sin 4x}{32} + C && \text{Integrate.}
\end{aligned}$$

Use a graphing utility to verify this. Can you simplify the derivative to obtain the original integrand?

In Example 3, when you evaluate the definite integral from 0 to $\pi/2$, you obtain

$$\begin{aligned}
\int_0^{\pi/2} \cos^4 x\,dx &= \left[\frac{3x}{8} + \frac{\sin 2x}{4} + \frac{\sin 4x}{32}\right]_0^{\pi/2} \\
&= \left(\frac{3\pi}{16} + 0 + 0\right) - (0 + 0 + 0) \\
&= \frac{3\pi}{16}.
\end{aligned}$$

Note that the only term that contributes to the solution is

$$\frac{3x}{8}.$$

This observation is generalized in the following formulas developed by John Wallis (1616–1703). Note the restrictions on the positive integer n.

Wallis's Formulas

1. If n is odd ($n \geq 3$), then

$$\int_0^{\pi/2} \cos^n x\,dx = \left(\frac{2}{3}\right)\left(\frac{4}{5}\right)\left(\frac{6}{7}\right)\cdots\left(\frac{n-1}{n}\right).$$

2. If n is even ($n \geq 2$), then

$$\int_0^{\pi/2} \cos^n x\,dx = \left(\frac{1}{2}\right)\left(\frac{3}{4}\right)\left(\frac{5}{6}\right)\cdots\left(\frac{n-1}{n}\right)\left(\frac{\pi}{2}\right).$$

These formulas are also valid when $\cos^n x$ is replaced by $\sin^n x$. (You are asked to prove both formulas in Exercise 87.)

JOHN WALLIS (1616–1703)

Wallis did much of his work in calculus prior to Newton and Leibniz, and he influenced the thinking of both of these men. Wallis is also credited with introducing the present symbol (∞) for infinity.

See LarsonCalculus.com to read more of this biography.

Bettmann/Getty Images

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Integrals Involving Powers of Secant and Tangent

The guidelines below can help you find integrals of the form

$$\int \sec^m x \tan^n x \, dx.$$ Either m or n is a positive integer.

Guidelines for Finding Integrals Involving Powers of Secant and Tangent

1. When the power of the secant is even and positive, save a secant-squared factor and convert the remaining factors to tangents. Then expand and integrate.

$$\int \sec^{\overbrace{2k}^{\text{Even}}} x \tan^n x \, dx = \int \overbrace{(\sec^2 x)^{k-1}}^{\text{Convert to tangents.}} \tan^n x \overbrace{\sec^2 x \, dx}^{\text{Save for } du.} = \int (1 + \tan^2 x)^{k-1} \tan^n x \sec^2 x \, dx$$

2. When the power of the tangent is odd and positive, save a secant-tangent factor and convert the remaining factors to secants. Then expand and integrate.

$$\int \sec^m x \tan^{\overbrace{2k+1}^{\text{Odd}}} x \, dx = \int (\sec^{m-1} x)\overbrace{(\tan^2 x)^k}^{\text{Convert to secants.}} \overbrace{\sec x \tan x \, dx}^{\text{Save for } du.} = \int (\sec^{m-1} x)(\sec^2 x - 1)^k \sec x \tan x \, dx$$

3. When there are no secant factors and the power of the tangent is even and positive, convert a tangent-squared factor to a secant-squared factor, then expand and repeat if necessary.

$$\int \tan^n x \, dx = \int (\tan^{n-2} x)\overbrace{(\tan^2 x)}^{\text{Convert to secants.}} \, dx = \int (\tan^{n-2} x)(\sec^2 x - 1) \, dx$$

4. When the integral is of the form

$$\int \sec^m x \, dx$$

where m is odd and positive, use integration by parts, as illustrated in Example 6 in Section 8.2.

5. When the first four guidelines do not apply, try converting to sines and cosines.

EXAMPLE 4 Power of Tangent Is Odd and Positive

Find $\displaystyle\int \frac{\tan^3 x}{\sqrt{\sec x}} \, dx.$

Solution Because you expect to use the Power Rule with $u = \sec x$, *save a factor of (sec x tan x)* to form du and convert the remaining tangent factors to secants.

$$\begin{aligned}
\int \frac{\tan^3 x}{\sqrt{\sec x}} \, dx &= \int (\sec x)^{-1/2} \tan^3 x \, dx && \text{Rewrite.} \\
&= \int (\sec x)^{-3/2}(\tan^2 x)(\sec x \tan x) \, dx && \text{Rewrite.} \\
&= \int (\sec x)^{-3/2}(\sec^2 x - 1)(\sec x \tan x) \, dx && \text{Trigonometric identity} \\
&= \int [(\sec x)^{1/2} - (\sec x)^{-3/2}](\sec x \tan x) \, dx && \text{Multiply.} \\
&= \frac{2}{3}(\sec x)^{3/2} + 2(\sec x)^{-1/2} + C && \text{Integrate.}
\end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 5 Power of Secant Is Even and Positive

Find $\int \sec^4 3x \tan^3 3x\, dx$.

Solution Let $u = \tan 3x$. Then $du = 3 \sec^2 3x\, dx$ and you can write

$$\begin{aligned}
\int \sec^4 3x \tan^3 3x\, dx &= \int (\sec^2 3x \tan^3 3x)(\sec^2 3x)\, dx && \text{Rewrite.}\\
&= \int (1 + \tan^2 3x)(\tan^3 3x)(\sec^2 3x)\, dx && \text{Trigonometric identity}\\
&= \frac{1}{3}\int (\tan^3 3x + \tan^5 3x)(3 \sec^2 3x)\, dx && \text{Multiply.}\\
&= \frac{1}{3}\left(\frac{\tan^4 3x}{4} + \frac{\tan^6 3x}{6}\right) + C && \text{Integrate.}\\
&= \frac{\tan^4 3x}{12} + \frac{\tan^6 3x}{18} + C.
\end{aligned}$$

In Example 5, the power of the tangent is odd and positive. So, you could also find the integral using the procedure described in the second guideline on the preceding page. In Exercises 67 and 68, you are asked to show that the results obtained by these two procedures differ only by a constant.

EXAMPLE 6 Power of Tangent Is Even

Evaluate $\int_0^{\pi/4} \tan^4 x\, dx$.

Solution Because there are no secant factors, begin by converting a tangent-squared factor to a secant-squared factor.

$$\begin{aligned}
\int \tan^4 x\, dx &= \int (\tan^2 x)(\tan^2 x)\, dx && \text{Rewrite.}\\
&= \int (\tan^2 x)(\sec^2 x - 1)\, dx && \text{Trigonometric identity}\\
&= \int \tan^2 x \sec^2 x\, dx - \int \tan^2 x\, dx && \text{Rewrite.}\\
&= \int \tan^2 x \sec^2 x\, dx - \int (\sec^2 x - 1)\, dx && \text{Trigonometric identity}\\
&= \frac{\tan^3 x}{3} - \tan x + x + C && \text{Integrate.}
\end{aligned}$$

Next, evaluate the definite integral.

$$\begin{aligned}
\int_0^{\pi/4} \tan^4 x\, dx &= \left[\frac{\tan^3 x}{3} - \tan x + x\right]_0^{\pi/4}\\
&= \frac{1}{3} - 1 + \frac{\pi}{4}\\
&\approx 0.119
\end{aligned}$$



The area of the region is approximately 0.119.
Figure 8.5

The area represented by the definite integral is shown in Figure 8.5. Use the Midpoint Rule to approximate this integral. With $n = 15$, you should obtain an approximation that is within 0.001 of the actual value.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

For integrals involving powers of cotangents and cosecants, you can follow a strategy similar to that used for powers of tangents and secants. Also, when integrating trigonometric functions, remember that it sometimes helps to convert the entire integrand to powers of sines and cosines.

EXAMPLE 7 Converting to Sines and Cosines

Find $\int \frac{\sec x}{\tan^2 x}\,dx$.

Solution Because the first four guidelines on page 535 do not apply, try converting the integrand to sines and cosines. In this case, you are able to integrate the resulting powers of sine and cosine as shown.

$$\begin{aligned}
\int \frac{\sec x}{\tan^2 x}\,dx &= \int \sec x \cot^2 x\,dx && \text{Trigonometric identity}\\
&= \int \left(\frac{1}{\cos x}\right)\left(\frac{\cos x}{\sin x}\right)^2 dx && \text{Convert to sines and cosines.}\\
&= \int (\sin x)^{-2}(\cos x)\,dx && \text{Rewrite.}\\
&= -(\sin x)^{-1} + C && \text{Integrate.}\\
&= -\csc x + C && \text{Trigonometric identity}
\end{aligned}$$

Integrals Involving Sines and Cosines of Two Angles

Integrals involving the products of sines and cosines of two angles occur in many applications. You can evaluate these integrals using integration by parts. However, you may find it simpler to use the product-to-sum formulas below.

$$\sin mx \sin nx = \frac{1}{2}(\cos[(m-n)x] - \cos[(m+n)x])$$

$$\sin mx \cos nx = \frac{1}{2}(\sin[(m-n)x] + \sin[(m+n)x])$$

$$\cos mx \cos nx = \frac{1}{2}(\cos[(m-n)x] + \cos[(m+n)x])$$

EXAMPLE 8 Using a Product-to-Sum Formula

Find $\int \sin 5x \cos 4x\,dx$.

Solution The integrand has the product form $\sin mx \cos nx$. So, by the second product-to-sum formula above, you can write

$$\begin{aligned}
\int \sin 5x \cos 4x\,dx &= \frac{1}{2}\int (\sin x + \sin 9x)\,dx && \text{Product-to-sum formula}\\
&= \frac{1}{2}\left(-\cos x - \frac{\cos 9x}{9}\right) + C && \text{Integrate.}\\
&= -\frac{\cos x}{2} - \frac{\cos 9x}{18} + C. && \text{Multiply.}
\end{aligned}$$

FOR FURTHER INFORMATION To learn more about integrals involving sine-cosine products with different angles, see the article "Integrals of Products of Sine and Cosine with Different Arguments" by Sherrie J. Nicol in *The College Mathematics Journal*. To view this article, go to *MathArticles.com*.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

8.3 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Which integral requires more steps to find? Explain. Do not integrate.

$\int \sin^8 x\,dx$ $\int \sin^8 x \cos x\,dx$

2. Describe the technique for finding $\int \sec^5 x \tan^7 x\,dx$. Do not integrate.

Finding an Indefinite Integral Involving Sine and Cosine

In Exercises 3–14, find the indefinite integral.

3. $\int \cos^5 x \sin x\,dx$
4. $\int \sin^7 2x \cos 2x\,dx$
5. $\int \cos^3 x \sin^4 x\,dx$
6. $\int \sin^3 3x\,dx$
7. $\int \sin^3 x \cos^2 x\,dx$
8. $\int \cos^3 \frac{x}{3}\,dx$
9. $\int \sin^3 2\theta \sqrt{\cos 2\theta}\,d\theta$
10. $\int \frac{\cos^5 t}{\sqrt{\sin t}}\,dt$
11. $\int \cos^2 3x\,dx$
12. $\int \sin^4 6\theta\,d\theta$
13. $\int 8x \cos^2 x\,dx$
14. $\int x^2 \sin^2 x\,dx$

Using Wallis's Formulas

In Exercises 15–20, use Wallis's Formulas to evaluate the integral.

15. $\int_0^{\pi/2} \cos^3 x\,dx$
16. $\int_0^{\pi/2} \cos^6 x\,dx$
17. $\int_0^{\pi/2} \sin^2 x\,dx$
18. $\int_0^{\pi/2} \sin^9 x\,dx$
19. $\int_0^{\pi/2} \sin^{10} x\,dx$
20. $\int_0^{\pi/2} \cos^{11} x\,dx$

Finding an Indefinite Integral Involving Secant and Tangent

In Exercises 21–34, find the indefinite integral.

21. $\int \sec 4x\,dx$
22. $\int \sec^4 x\,dx$
23. $\int \sec^3 \pi x\,dx$
24. $\int \tan^6 3x\,dx$
25. $\int \tan^5 \frac{x}{2}\,dx$
26. $\int \tan^3 \frac{\pi x}{2} \sec^2 \frac{\pi x}{2}\,dx$
27. $\int \tan^3 2t \sec^3 2t\,dt$
28. $\int \tan^5 x \sec^4 x\,dx$
29. $\int \sec^6 4x \tan 4x\,dx$
30. $\int \sec^2 \frac{x}{2} \tan \frac{x}{2}\,dx$
31. $\int \sec^5 x \tan^3 x\,dx$
32. $\int \tan^3 3x\,dx$
33. $\int \frac{\tan^2 x}{\sec x}\,dx$
34. $\int \frac{\tan^2 x}{\sec^5 x}\,dx$

Differential Equation

In Exercises 35–38, find the general solution of the differential equation.

35. $\frac{dr}{d\theta} = \sin^4 \pi\theta$
36. $\frac{ds}{d\alpha} = \sin^2 \frac{\alpha}{2} \cos^2 \frac{\alpha}{2}$
37. $y' = \tan^3 3x \sec 3x$
38. $y' = \sqrt{\tan x} \sec^4 x$

Slope Field

In Exercises 39 and 40, a differential equation, a point, and a slope field are given. (a) Sketch two approximate solutions of the differential equation on the slope field, one of which passes through the given point. (To print an enlarged copy of the graph, go to *MathGraphs.com*.) (b) Use integration and the given point to find the particular solution of the differential equation and use a graphing utility to graph the solution. Compare the result with the sketch in part (a) that passes through the given point.

39. $\frac{dy}{dx} = \sin^2 x,\ (0, 0)$
40. $\frac{dy}{dx} = \sec^2 x \tan^2 x,\ \left(0, -\frac{1}{4}\right)$





Slope Field

In Exercises 41 and 42, use a graphing utility to graph the slope field for the differential equation and graph the solution satisfying the specified initial condition.

41. $\frac{dy}{dx} = \frac{3 \sin x}{y},\ y(0) = 2$
42. $\frac{dy}{dx} = 3\sqrt{y} \tan^2 x,\ y(0) = 3$

Using a Product-to-Sum Formula

In Exercises 43–48, find the indefinite integral.

43. $\int \cos 2x \cos 6x\,dx$
44. $\int \cos 5\theta \cos 3\theta\,d\theta$
45. $\int \sin 2t \cos 9t\,dt$
46. $\int \sin 8x \cos 7x\,dx$
47. $\int \sin \theta \sin 3\theta\,d\theta$
48. $\int \sin 5x \sin 4x\,dx$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding an Indefinite Integral **In Exercises 49–58, find the indefinite integral. Use a graphing utility to confirm your result.**

49. $\int \cot^3 2x\,dx$

50. $\int \tan^5 \frac{x}{4} \sec^4 \frac{x}{4}\,dx$

51. $\int \csc^4 3x\,dx$

52. $\int \cot^3 \frac{x}{2} \csc^4 \frac{x}{2}\,dx$

53. $\int \frac{\cot^2 t}{\csc t}\,dt$

54. $\int \frac{\cot^3 t}{\csc t}\,dt$

55. $\int \frac{1}{\sec x \tan x}\,dx$

56. $\int \frac{\sin^2 x - \cos^2 x}{\cos x}\,dx$

57. $\int (\tan^4 t - \sec^4 t)\,dt$

58. $\int \frac{1 - \sec t}{\cos t - 1}\,dt$

Evaluating a Definite Integral **In Exercises 59–66, evaluate the definite integral.**

59. $\int_{-\pi}^{\pi} \sin^2 x\,dx$

60. $\int_{0}^{\pi/3} \tan^2 x\,dx$

61. $\int_{0}^{\pi/4} 6 \tan^3 x\,dx$

62. $\int_{0}^{\pi/3} \sec^{3/2} x \tan x\,dx$

63. $\int_{0}^{\pi/2} \frac{\cot t}{1 + \sin t}\,dt$

64. $\int_{\pi/6}^{\pi/3} \sin 6x \cos 4x\,dx$

65. $\int_{-\pi/2}^{\pi/2} 3 \cos^3 x\,dx$

66. $\int_{0}^{\pi} \sin^5 x\,dx$

Exploring Concepts

In Exercises 67 and 68, (a) find the indefinite integral in two different ways, (b) use a graphing utility to graph the antiderivative (without the constant of integration) obtained by each method to show that the results differ only by a constant, and (c) verify analytically that the results differ only by a constant.

67. $\int \sec^4 3x \tan^3 3x\,dx$

68. $\int \sec^2 x \tan x\,dx$

69. Find the indefinite integral

$$\int \sin x \cos x\,dx$$

using the given method. Explain how your answers differ for each method.

(a) Substitution where $u = \sin x$

(b) Substitution where $u = \cos x$

(c) Integration by parts

(d) Using the identity $\sin 2x = 2 \sin x \cos x$

70. HOW DO YOU SEE IT? Use the graph of f' shown in the figure to answer the following.



(a) Using the interval shown in the graph, approximate the value(s) of x where f is maximum. Explain.

(b) Using the interval shown in the graph, approximate the value(s) of x where f is minimum. Explain.

Area **In Exercises 71 and 72, find the area of the given region.**

71. $y = \sin x,\ y = \sin^3 x$



72. $y = \sin^2 \pi x$



Area **In Exercises 73 and 74, find the area of the region bounded by the graphs of the equations.**

73. $y = \cos^2 x,\quad y = \sin^2 x,\quad x = -\frac{\pi}{4},\quad x = \frac{\pi}{4}$

74. $y = \cos^2 x,\quad y = \sin x \cos x,\quad x = -\frac{\pi}{2},\quad x = \frac{\pi}{4}$

Volume **In Exercises 75 and 76, find the volume of the solid generated by revolving the region bounded by the graphs of the equations about the x-axis.**

75. $y = \tan x,\quad y = 0,\quad x = -\frac{\pi}{4},\quad x = \frac{\pi}{4}$

76. $y = \cos \frac{x}{2},\quad y = \sin \frac{x}{2},\quad x = 0,\quad x = \frac{\pi}{2}$

Volume and Centroid **In Exercises 77 and 78, for the region bounded by the graphs of the equations, find (a) the volume of the solid generated by revolving the region about the x-axis and (b) the centroid of the region.**

77. $y = \sin x,\quad y = 0,\quad x = 0,\quad x = \pi$

78. $y = \cos x,\quad y = 0,\quad x = 0,\quad x = \frac{\pi}{2}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Verifying a Reduction Formula **In Exercises 79–82, use integration by parts to verify the reduction formula. (A *reduction formula* reduces a given integral to the sum of a function and a simpler integral.)**

79. $\int \sin^n x\,dx = -\frac{\sin^{n-1} x \cos x}{n} + \frac{n-1}{n}\int \sin^{n-2} x\,dx$

80. $\int \cos^n x\,dx = \frac{\cos^{n-1} x \sin x}{n} + \frac{n-1}{n}\int \cos^{n-2} x\,dx$

81. $\int \cos^m x \sin^n x\,dx$

$$= -\frac{\cos^{m+1} x \sin^{n-1} x}{m+n} + \frac{n-1}{m+n}\int \cos^m x \sin^{n-2} x\,dx$$

82. $\int \sec^n x\,dx = \frac{\sec^{n-2} x \tan x}{n-1} + \frac{n-2}{n-1}\int \sec^{n-2} x\,dx$

Using Formulas **In Exercises 83–86, find the indefinite integral by using the appropriate formula from Exercises 79–82.**

83. $\int \sin^5 x\,dx$

84. $\int \cos^4 x\,dx$

85. $\int \cos^2 x \sin^4 x\,dx$

86. $\int \sec^4 \frac{2\pi x}{5}\,dx$

87. Wallis's Formulas Use the result of Exercise 80 to prove the following versions of Wallis's Formulas.

(a) If n is odd $(n \geq 3)$, then

$$\int_0^{\pi/2} \cos^n x\,dx = \left(\frac{2}{3}\right)\left(\frac{4}{5}\right)\left(\frac{6}{7}\right)\cdots\left(\frac{n-1}{n}\right).$$

(b) If n is even $(n \geq 2)$, then

$$\int_0^{\pi/2} \cos^n x\,dx = \left(\frac{1}{2}\right)\left(\frac{3}{4}\right)\left(\frac{5}{6}\right)\cdots\left(\frac{n-1}{n}\right)\left(\frac{\pi}{2}\right).$$

88. Arc Length Find the arc length of the graph of the function $y = \ln(1 - x^2)$ on the interval $0 \leq x \leq \frac{1}{2}$ (see figure).



89. Proof Suppose that $f(a) = f(b) = g(a) = g(b) = 0$ and the second derivatives of f and g are continuous on the closed interval $[a, b]$. Prove that

$$\int_a^b f(x)g''(x)\,dx = \int_a^b f''(x)g(x)\,dx.$$

SECTION PROJECT

The Wallis Product

The formula for π as an infinite product was derived by English mathematician John Wallis in 1655. This product, called the **Wallis Product,** appeared in his book *Arithmetica Infinitorum.*

$$\frac{\pi}{2} = \left(\frac{2 \cdot 2}{1 \cdot 3}\right)\left(\frac{4 \cdot 4}{3 \cdot 5}\right)\left(\frac{6 \cdot 6}{5 \cdot 7}\right)\cdots\left(\frac{(2n) \cdot (2n)}{(2n-1) \cdot (2n+1)}\right)\cdots$$

In 2015, physicists Carl Hagen and Tamar Friedmann (also a mathematician) stumbled upon a connection between quantum mechanics and the Wallis Product when they applied the variational principle to higher energy states of the hydrogen atom. This principle was previously used only on the ground energy state. The Wallis Product appeared naturally in the midst of their calculations involving gamma functions.

Quantum mechanics is the study of matter and light on the atomic and subatomic scale.

Consider Wallis's method of finding a formula for π. Let

$$I(n) = \int_0^{\pi/2} \sin^n x\,dx.$$

From Wallis's Formulas,

$$I(n) = \left(\frac{1}{2}\right)\left(\frac{3}{4}\right)\left(\frac{5}{6}\right)\cdots\left(\frac{n-1}{n}\right)\left(\frac{\pi}{2}\right),\ n \text{ is even } (n \geq 2)$$

or

$$I(n) = \left(\frac{2}{3}\right)\left(\frac{4}{5}\right)\left(\frac{6}{7}\right)\cdots\left(\frac{n-1}{n}\right),\ n \text{ is odd } (n \geq 3).$$

(a) Find $I(n)$ for $n = 2$, 3, 4, and 5. What do you observe?

(b) Show that $I(n+1) \leq I(n)$ for $n \geq 2$.

(c) Show that

$$\lim_{n\to\infty} \frac{I(2n+1)}{I(2n)} = 1.$$

(Hint: Use the Squeeze Theorem.)

(d) Verify the Wallis Product using the limit in part (c).

FOR FURTHER INFORMATION For an alternative proof of the Wallis Product, see the article "An Elementary Proof of the Wallis Product Formula for pi" by Johan Wästlund in *The American Mathematical Monthly*. To view this article, go to *MathArticles.com*.

agsandrew/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

8.4 Trigonometric Substitution

GO DIGITAL

- **Use trigonometric substitution to find an integral.**
- **Use integrals to model and solve real-life applications.**

Exploration

Finding an Integral Involving a Radical Up to this point in the text, you have not evaluated the integral

$$\int_{-1}^{1} \sqrt{1 - x^2}\, dx.$$

From geometry, you should be able to find the exact value of this integral—what is it? Try finding the exact value using the substitution

$$x = \sin\theta$$

and

$$dx = \cos\theta\, d\theta.$$

Does your answer agree with the value you obtained using geometry?

Trigonometric Substitution

Now that you can find integrals involving powers of trigonometric functions, you can use **trigonometric substitution** to find integrals involving the radicals

$$\sqrt{a^2 - u^2}, \quad \sqrt{a^2 + u^2}, \quad \text{and} \quad \sqrt{u^2 - a^2}.$$

The objective with trigonometric substitution is to eliminate the radical in the integrand. You do this by using the Pythagorean identities.

$$\cos^2\theta = 1 - \sin^2\theta$$
$$\sec^2\theta = 1 + \tan^2\theta$$
$$\tan^2\theta = \sec^2\theta - 1$$

For example, for $a > 0$, let $u = a\sin\theta$, where $-\pi/2 \le \theta \le \pi/2$. Then

$$\begin{aligned}
\sqrt{a^2 - u^2} &= \sqrt{a^2 - a^2\sin^2\theta} && \text{Substitute for } u.\\
&= \sqrt{a^2(1 - \sin^2\theta)} && \text{Factor.}\\
&= \sqrt{a^2\cos^2\theta} && \text{Pythagorean identity}\\
&= a\cos\theta. && \text{Simplify.}
\end{aligned}$$

Note that $\cos\theta \ge 0$, because $-\pi/2 \le \theta \le \pi/2$.

Trigonometric Substitution ($a > 0$)

1. For integrals involving $\sqrt{a^2 - u^2}$, let

$$u = a\sin\theta.$$

Then $\sqrt{a^2 - u^2} = a\cos\theta$, where

$$-\pi/2 \le \theta \le \pi/2.$$



2. For integrals involving $\sqrt{a^2 + u^2}$, let

$$u = a\tan\theta.$$

Then $\sqrt{a^2 + u^2} = a\sec\theta$, where

$$-\pi/2 < \theta < \pi/2.$$



3. For integrals involving $\sqrt{u^2 - a^2}$, let

$$u = a\sec\theta.$$

Then



$$\sqrt{u^2 - a^2} = \begin{cases} a\tan\theta \text{ for } u > a, \text{ where } 0 \le \theta < \pi/2 \\ -a\tan\theta \text{ for } u < -a, \text{ where } \pi/2 < \theta \le \pi. \end{cases}$$

The restrictions on θ ensure that the function that defines the substitution is one-to-one. In fact, these are the same intervals over which the arcsine, arctangent, and arcsecant are defined.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 1 Trigonometric Substitution: $u = a \sin\theta$

Find $\displaystyle\int \frac{dx}{x^2\sqrt{9 - x^2}}$.

Solution First, note that the basic integration rules do not apply. To use trigonometric substitution, notice that

$$\sqrt{9 - x^2}$$

is of the form $\sqrt{a^2 - u^2}$. So, you can use the substitution

$$x = a \sin\theta = 3 \sin\theta.$$

Using differentiation and the right triangle shown in Figure 8.6, you obtain

$$dx = 3\cos\theta\, d\theta, \quad \sqrt{9 - x^2} = 3\cos\theta, \quad \text{and} \quad x^2 = 9\sin^2\theta.$$



$\sin\theta = \frac{x}{3}$, $\cot\theta = \frac{\sqrt{9 - x^2}}{x}$

Figure 8.6

So, trigonometric substitution yields

$$\begin{aligned}
\int \frac{dx}{x^2\sqrt{9 - x^2}} &= \int \frac{3\cos\theta\, d\theta}{(9\sin^2\theta)(3\cos\theta)} && \text{Substitute.}\\
&= \frac{1}{9}\int \frac{d\theta}{\sin^2\theta} && \text{Simplify.}\\
&= \frac{1}{9}\int \csc^2\theta\, d\theta && \text{Trigonometric identity}\\
&= -\frac{1}{9}\cot\theta + C && \text{Apply Cosecant Rule.}\\
&= -\frac{1}{9}\left(\frac{\sqrt{9 - x^2}}{x}\right) + C && \text{Substitute for } \cot\theta.\\
&= -\frac{\sqrt{9 - x^2}}{9x} + C.
\end{aligned}$$

Note that the triangle in Figure 8.6 can be used to convert the θ's back to x's, as shown.

$$\begin{aligned}
\cot\theta &= \frac{\text{adj}}{\text{opp}} && \text{Right triangle definition of cotangent}\\
&= \frac{\sqrt{9 - x^2}}{x} && \text{Substitute.}
\end{aligned}$$

REMARK To review the right triangle definitions of trigonometric functions, see Section P.4.

TECHNOLOGY Use a graphing utility to find each indefinite integral.

$$\int \frac{dx}{\sqrt{9 - x^2}} \qquad \int \frac{dx}{x\sqrt{9 - x^2}}$$

$$\int \frac{dx}{x^2\sqrt{9 - x^2}} \qquad \int \frac{dx}{x^3\sqrt{9 - x^2}}$$

Then use trigonometric substitution to duplicate the results obtained with the graphing utility.

In Chapter 5, inverse hyperbolic functions were used to find integrals of the forms

$$\int \frac{du}{\sqrt{u^2 \pm a^2}}, \quad \int \frac{du}{a^2 - u^2}, \quad \text{and} \quad \int \frac{du}{u\sqrt{a^2 \pm u^2}}.$$

You can also find these integrals using trigonometric substitution. This is shown in the next example.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



$\tan\theta = 2x$, $\sec\theta = \sqrt{4x^2+1}$

Figure 8.7

EXAMPLE 2 Trigonometric Substitution: $u = a\tan\theta$

Find $\displaystyle\int \frac{dx}{\sqrt{4x^2+1}}$.

Solution Let $u = 2x$, $a = 1$, and $2x = \tan\theta$, as shown in Figure 8.7. Then,

$$dx = \frac{1}{2}\sec^2\theta\,d\theta \quad \text{and} \quad \sqrt{4x^2+1} = \sec\theta.$$

Trigonometric substitution produces

$$\begin{aligned}
\int \frac{dx}{\sqrt{4x^2+1}} &= \frac{1}{2}\int \frac{\sec^2\theta\,d\theta}{\sec\theta} && \text{Substitute.}\\
&= \frac{1}{2}\int \sec\theta\,d\theta && \text{Simplify.}\\
&= \frac{1}{2}\ln|\sec\theta + \tan\theta| + C && \text{Apply Secant Rule.}\\
&= \frac{1}{2}\ln\left|\sqrt{4x^2+1} + 2x\right| + C. && \text{Back-substitute.}
\end{aligned}$$

Use a graphing utility to check this result. Is the result given in this form or in the form of an inverse hyperbolic function? ■

To use trigonometric substitution for integrals involving expressions such as $(a^2 - u^2)^{n/2}$, try writing the expression as $(a^2 - u^2)^{n/2} = \left(\sqrt{a^2 - u^2}\right)^n$.

EXAMPLE 3 Trigonometric Substitution: Rational Powers

See LarsonCalculus.com for an interactive version of this type of example.

Find $\displaystyle\int \frac{dx}{(x^2+1)^{3/2}}$.

Solution First, write $(x^2+1)^{3/2}$ as $\left(\sqrt{x^2+1}\right)^3$. Then let $a = 1$ and $u = x = \tan\theta$, as shown in Figure 8.8. Using

$$dx = \sec^2\theta\,d\theta \quad \text{and} \quad \sqrt{x^2+1} = \sec\theta$$

you can apply trigonometric substitution, as shown.

$$\begin{aligned}
\int \frac{dx}{(x^2+1)^{3/2}} &= \int \frac{dx}{\left(\sqrt{x^2+1}\right)^3} && \text{Rewrite denominator.}\\
&= \int \frac{\sec^2\theta\,d\theta}{\sec^3\theta} && \text{Substitute.}\\
&= \int \frac{d\theta}{\sec\theta} && \text{Simplify.}\\
&= \int \cos\theta\,d\theta && \text{Trigonometric identity}\\
&= \sin\theta + C && \text{Apply Cosine Rule.}\\
&= \frac{x}{\sqrt{x^2+1}} + C && \text{Back-substitute.}
\end{aligned}$$

■



$\tan\theta = x$, $\sin\theta = \dfrac{x}{\sqrt{x^2+1}}$

Figure 8.8

For definite integrals, it is often convenient to determine integration limits for θ that avoid converting back to x. (See Example 4 on the next page.) You might want to review this procedure in Section 4.5, Examples 8 and 9.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



$\sec\theta = \frac{x}{\sqrt{3}}$, $\tan\theta = \frac{\sqrt{x^2-3}}{\sqrt{3}}$

Figure 8.9

EXAMPLE 4 Converting the Limits of Integration

Evaluate $\int_{\sqrt{3}}^{2} \frac{\sqrt{x^2-3}}{x}\,dx$.

Solution Because $\sqrt{x^2-3}$ has the form $\sqrt{u^2-a^2}$, you can consider

$$u = x, \quad a = \sqrt{3}, \quad \text{and} \quad x = \sqrt{3}\sec\theta$$

as shown in Figure 8.9. Then

$$dx = \sqrt{3}\sec\theta\tan\theta\,d\theta \quad \text{and} \quad \sqrt{x^2-3} = \sqrt{3}\tan\theta.$$

To determine the upper and lower limits of integration, use the substitution $x = \sqrt{3}\sec\theta$, as shown.

Lower Limit

When $x = \sqrt{3}$, $\sec\theta = 1$ and $\theta = 0$.

Upper Limit

When $x = 2$, $\sec\theta = \frac{2}{\sqrt{3}}$ and $\theta = \frac{\pi}{6}$.

So, you have

Integration limits for x / Integration limits for θ

$$\begin{aligned}
\int_{\sqrt{3}}^{2} \frac{\sqrt{x^2-3}}{x}\,dx &= \int_{0}^{\pi/6} \frac{(\sqrt{3}\tan\theta)(\sqrt{3}\sec\theta\tan\theta)}{\sqrt{3}\sec\theta}\,d\theta \\
&= \int_{0}^{\pi/6} \sqrt{3}\tan^2\theta\,d\theta \\
&= \sqrt{3}\int_{0}^{\pi/6} (\sec^2\theta - 1)\,d\theta \\
&= \sqrt{3}\Big[\tan\theta - \theta\Big]_{0}^{\pi/6} \\
&= \sqrt{3}\left(\frac{1}{\sqrt{3}} - \frac{\pi}{6}\right) \\
&= 1 - \frac{\sqrt{3}\pi}{6} \\
&\approx 0.0931.
\end{aligned}$$

REMARK In Example 4, convert back to the variable x and evaluate the antiderivative at the original limits of integration. Do you obtain the same result?

When using trigonometric substitution to evaluate definite integrals, you must be careful to check that the values of θ lie in the intervals discussed at the beginning of this section. For instance, if in Example 4 you had been asked to evaluate the definite integral

$$\int_{-2}^{-\sqrt{3}} \frac{\sqrt{x^2-3}}{x}\,dx$$

then using $u = x$ and $a = \sqrt{3}$ in the interval $[-2, -\sqrt{3}]$ would imply that $u < -a$. So, when determining the upper and lower limits of integration, you would have to choose θ such that $\pi/2 < \theta \leq \pi$. In this case, you can rewrite the integral as

$$\int_{-2}^{-\sqrt{3}} \frac{\sqrt{x^2-3}}{x}\,dx = \int_{5\pi/6}^{\pi} \frac{(-\sqrt{3}\tan\theta)(\sqrt{3}\sec\theta\tan\theta)\,d\theta}{\sqrt{3}\sec\theta}.$$

Complete this integration and show that the result is equivalent to the one in Example 4. (See Exercise 66.)

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

REMARK Recall from Chapter 5 that you used completing the square for integrands involving quadratic functions.

Trigonometric substitution can be used with completing the square. For instance, try finding the integral

$$\int \sqrt{x^2 - 2x}\, dx.$$

To begin, you could complete the square for $x^2 - 2x$ and write the integral as

$$\int \sqrt{(x - 1)^2 - 1^2}\, dx.$$

Because the integrand has the form

$$\sqrt{u^2 - a^2}$$

with $u = x - 1$ and $a = 1$, you can now use trigonometric substitution to find the integral.

Trigonometric substitution can be used to find the three integrals listed in the next theorem. These integrals will be encountered several times in the remainder of the text. When this happens, there will be a reference to Theorem 8.2. (In Exercise 65, you are asked to verify the formulas in Theorem 8.2.)

THEOREM 8.2 Special Integration Formulas ($a > 0$)

1. $\displaystyle\int \sqrt{a^2 - u^2}\, du = \frac{1}{2}\left(u\sqrt{a^2 - u^2} + a^2 \arcsin\frac{u}{a}\right) + C$
2. $\displaystyle\int \sqrt{u^2 - a^2}\, du = \frac{1}{2}\left(u\sqrt{u^2 - a^2} - a^2 \ln\left|u + \sqrt{u^2 - a^2}\right|\right) + C$
3. $\displaystyle\int \sqrt{u^2 + a^2}\, du = \frac{1}{2}\left(u\sqrt{u^2 + a^2} + a^2 \ln\left|u + \sqrt{u^2 + a^2}\right|\right) + C$

EXAMPLE 5 Area of an Ellipse

Find the area enclosed by the ellipse

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1.$$



The area bounded by the ellipse in Quadrant I is one-fourth the total area enclosed by the ellipse.
Figure 8.10

Solution The ellipse is symmetric with respect to both axes, so find the area of the region bounded by the ellipse in Quadrant I and multiply by 4 to obtain the total area of the ellipse (see Figure 8.10). In Quadrant I, the equation of the ellipse is

$$y = b\sqrt{1 - \left(\frac{x}{a}\right)^2}, \qquad 0 \le x \le a.$$

So, the total area of the ellipse is

$$\begin{aligned} A &= 4\int_0^a b\sqrt{1 - \left(\frac{x}{a}\right)^2}\, dx \\ &= \frac{4b}{a}\int_0^a \sqrt{a^2 - x^2}\, dx \\ &= \left(\frac{4b}{a}\right)\left(\frac{1}{2}\right)\left[x\sqrt{a^2 - x^2} + a^2 \arcsin\frac{x}{a}\right]_0^a \qquad \text{Apply Theorem 8.2.} \\ &= \left(\frac{2b}{a}\right)\left[a^2\left(\frac{\pi}{2}\right)\right] \\ &= \pi ab. \end{aligned}$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



The arc length of the curve from (0, 0) to $(1, \frac{1}{2})$

Figure 8.11

Applications

EXAMPLE 6 Finding Arc Length

Find the arc length of the graph of $f(x) = \frac{1}{2}x^2$ from $x = 0$ to $x = 1$. (See Figure 8.11.)

Solution Refer to the arc length formula in Section 7.4.

$$s = \int_0^1 \sqrt{1 + [f'(x)]^2}\, dx \qquad \text{Formula for arc length}$$

$$= \int_0^1 \sqrt{1 + x^2}\, dx \qquad f'(x) = x$$

$$= \int_0^{\pi/4} \sec^3\theta\, d\theta \qquad \text{Let } a = 1 \text{ and } x = \tan\theta.$$

$$= \frac{1}{2}\Big[\sec\theta\tan\theta + \ln|\sec\theta + \tan\theta|\Big]_0^{\pi/4} \qquad \text{Example 6, Section 8.2}$$

$$= \frac{1}{2}\Big[\sqrt{2} + \ln\big(\sqrt{2} + 1\big)\Big]$$

$$\approx 1.148$$



The barrel is not quite full of oil—the top 0.2 foot of the barrel is empty.

Figure 8.12

EXAMPLE 7 Comparing Two Fluid Forces

A sealed barrel of oil (weighing 48 pounds per cubic foot) is floating in seawater (weighing 64 pounds per cubic foot), as shown in Figures 8.12 and 8.13. (The barrel is not completely full of oil. With the barrel lying on its side, the top 0.2 foot of the barrel is empty.) Compare the fluid forces against one end of the barrel from the inside and from the outside. (Assume the radius of the barrel is 1 foot and, with the barrel lying on its side, the top 0.6 foot of the barrel is above the water.)

Solution In Figure 8.13, locate the coordinate system with the origin at the center of the circle

$$x^2 + y^2 = 1.$$

To find the fluid force against an end of the barrel *from the inside,* integrate between -1 and 0.8 (using a weight of $w = 48$).

$$F = w\int_c^d h(y)L(y)\, dy \qquad \text{General equation (See Section 7.7.)}$$

$$F_{\text{inside}} = 48\int_{-1}^{0.8} (0.8 - y)(2)\sqrt{1 - y^2}\, dy$$

$$= 76.8\int_{-1}^{0.8} \sqrt{1 - y^2}\, dy - 96\int_{-1}^{0.8} y\sqrt{1 - y^2}\, dy$$



Figure 8.13

To find the fluid force *from the outside,* integrate between -1 and 0.4 (using a weight of $w = 64$).

$$F_{\text{outside}} = 64\int_{-1}^{0.4} (0.4 - y)(2)\sqrt{1 - y^2}\, dy$$

$$= 51.2\int_{-1}^{0.4} \sqrt{1 - y^2}\, dy - 128\int_{-1}^{0.4} y\sqrt{1 - y^2}\, dy$$

The details of integration are left for you to complete in Exercise 64. Intuitively, would you say that the force from the oil (the inside) or the force from the seawater (the outside) is greater? By evaluating these two integrals, you can determine that

$$F_{\text{inside}} \approx 121.3 \text{ pounds} \quad \text{and} \quad F_{\text{outside}} \approx 93.0 \text{ pounds.}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

8.4 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. State the trigonometric substitution you would use to find the indefinite integral. Do not integrate.

(a) $\int (9 + x^2)^{-2}\,dx$ (b) $\int \sqrt{4 - x^2}\,dx$

(c) $\int \frac{x^2}{\sqrt{25 - x^2}}\,dx$ (d) $\int x^2(x^2 - 25)^{3/2}\,dx$

2. Explain why completing the square is useful when you are considering integration by trigonometric substitution.

Using Trigonometric Substitution In Exercises 3–6, find the indefinite integral using the substitution $x = 4 \sin \theta$.

3. $\int \frac{1}{(16 - x^2)^{3/2}}\,dx$
4. $\int \frac{4}{x^2\sqrt{16 - x^2}}\,dx$
5. $\int \frac{\sqrt{16 - x^2}}{x}\,dx$
6. $\int \frac{x^3}{\sqrt{16 - x^2}}\,dx$

Using Trigonometric Substitution In Exercises 7–10, find the indefinite integral using the substitution $x = 5 \sec \theta$.

7. $\int \frac{1}{\sqrt{x^2 - 25}}\,dx$
8. $\int \frac{\sqrt{x^2 - 25}}{x}\,dx$
9. $\int x^3\sqrt{x^2 - 25}\,dx$
10. $\int \frac{x^3}{\sqrt{x^2 - 25}}\,dx$

Using Trigonometric Substitution In Exercises 11–14, find the indefinite integral using the substitution $x = 2 \tan \theta$.

11. $\int \frac{x}{2}\sqrt{4 + x^2}\,dx$
12. $\int \frac{x^3}{4\sqrt{4 + x^2}}\,dx$
13. $\int \frac{4}{(4 + x^2)^2}\,dx$
14. $\int \frac{2x^2}{(4 + x^2)^2}\,dx$

Special Integration Formulas In Exercises 15–18, use the Special Integration Formulas (Theorem 8.2) to find the indefinite integral.

15. $\int \sqrt{49 - 16x^2}\,dx$
16. $\int \sqrt{5x^2 - 1}\,dx$
17. $\int \sqrt{36 - 5x^2}\,dx$
18. $\int \sqrt{9 + 4x^2}$

Finding an Indefinite Integral In Exercises 19–32, find the indefinite integral.

19. $\int \sqrt{16 - 4x^2}\,dx$
20. $\int \frac{1}{\sqrt{x^2 - 4}}\,dx$
21. $\int \frac{\sqrt{1 - x^2}}{x^4}\,dx$
22. $\int \frac{\sqrt{25x^2 + 4}}{x^4}\,dx$
23. $\int \frac{1}{x\sqrt{4x^2 + 9}}\,dx$
24. $\int \frac{1}{x\sqrt{9x^2 + 1}}\,dx$
25. $\int \frac{-3}{(x^2 + 3)^{3/2}}\,dx$
26. $\int \frac{1}{(x^2 + 5)^{3/2}}\,dx$
27. $\int e^x\sqrt{1 - e^{2x}}\,dx$
28. $\int \frac{\sqrt{1 - x}}{\sqrt{x}}\,dx$
29. $\int \frac{1}{4 + 4x^2 + x^4}\,dx$
30. $\int \frac{x^3 + x + 1}{x^4 + 2x^2 + 1}\,dx$
31. $\int \operatorname{arcsec} 2x\,dx, \quad x > \frac{1}{2}$
32. $\int x \arcsin x\,dx$

Completing the Square In Exercises 33–36, complete the square and find the indefinite integral.

33. $\int \frac{x}{\sqrt{4x - x^2}}\,dx$
34. $\int \frac{x^2}{\sqrt{2x - x^2}}\,dx$
35. $\int \frac{x}{\sqrt{x^2 + 6x + 12}}\,dx$
36. $\int \frac{x}{\sqrt{x^2 - 6x + 5}}\,dx$

Converting the Limits of Integration In Exercises 37–42, evaluate the definite integral using (a) the given integration limits and (b) the limits obtained by trigonometric substitution.

37. $\int_0^{\sqrt{3}/2} \frac{t^2}{(1 - t^2)^{3/2}}\,dt$
38. $\int_0^{\sqrt{3}/2} \frac{1}{(1 - t^2)^{5/2}}\,dt$
39. $\int_0^3 \frac{x^3}{\sqrt{x^2 + 9}}\,dx$
40. $\int_0^{3/5} \sqrt{9 - 25x^2}\,dx$
41. $\int_4^6 \frac{x^2}{\sqrt{x^2 - 9}}\,dx$
42. $\int_4^8 \frac{\sqrt{x^2 - 16}}{x^2}\,dx$

True or False? In Exercises 43–46, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.

43. If $x = \sin \theta$, then
$$\int \frac{dx}{\sqrt{1 - x^2}} = \int d\theta.$$

44. If $x = \sec \theta$, then
$$\int \frac{\sqrt{x^2 - 1}}{x}\,dx = \int \sec \theta \tan \theta\,d\theta.$$

45. If $x = \tan \theta$, then
$$\int_0^{\sqrt{3}} \frac{dx}{(1 + x^2)^{3/2}} = \int_0^{4\pi/3} \cos \theta\,d\theta.$$

46. If $x = \sin \theta$, then
$$\int_{-1}^{1} x^2\sqrt{1 - x^2}\,dx = 2\int_0^{\pi/2} \sin^2 \theta \cos^2 \theta\,d\theta.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploring Concepts

In Exercises 47 and 48, state the method of integration you would use to find each integral. Explain why you chose that method. Do not integrate.

47. $\int x\sqrt{x^2+1}\,dx$ **48.** $\int x^2\sqrt{x^2-1}\,dx$

49. (a) Find the integral $\int \frac{x}{\sqrt{1-x^2}}\,dx$ using u-substitution. Then find the integral using trigonometric substitution. Discuss the results.

(b) Find the integral $\int \frac{x^2}{x^2+9}\,dx$ algebraically using $x^2 = (x^2+9) - 9$. Then find the integral using trigonometric substitution. Discuss the results.

50. HOW DO YOU SEE IT? Use the graph of f' shown in the figure to answer the following.



(a) Identify the open interval(s) on which the graph of f is increasing or decreasing. Explain.

(b) Identify the open interval(s) on which the graph of f is concave upward or concave downward. Explain.

51. Area Find the area enclosed by the ellipse

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$$

shown in the figure.



Figure for 51



Figure for 52

52. Area Find the area of the shaded region of the circle of radius a when the chord is h units ($0 < h < a$) from the center of the circle (see figure).

Arc Length **In Exercises 53 and 54, find the arc length of the graph of the function over the given interval.**

53. $y = \ln x,\ [1, 5]$ **54.** $y = \frac{x^2}{4} - 2x,\ [4, 8]$

Volume of a Torus **In Exercises 55 and 56, find the volume of the torus generated by revolving the region bounded by the graph of the circle about the y-axis.**

55. $(x-3)^2 + y^2 = 1$

56. $(x-h)^2 + y^2 = r^2,\quad h > r$

Centroid **In Exercises 57 and 58, find the centroid of the region bounded by the graphs of the inequalities.**

57. $y \le \frac{3}{\sqrt{x^2+9}},\ y \ge 0,\ x \ge -4,\ x \le 4$

58. $y \le \frac{1}{4}x^2,\ (x-4)^2 + y^2 \le 16,\ y \ge 0$

59. Volume The axis of a storage tank in the form of a right circular cylinder is horizontal (see figure). The radius and length of the tank are 1 meter and 3 meters, respectively.



(a) Determine the volume of fluid in the tank as a function of its depth d.

(b) Use a graphing utility to graph the function in part (a).

(c) Design a dipstick for the tank with markings of $\frac{1}{4}$, $\frac{1}{2}$, and $\frac{3}{4}$.

(d) Fluid is entering the tank at a rate of $\frac{1}{4}$ cubic meter per minute. Determine the rate of change of the depth of the fluid as a function of its depth d.

(e) Use a graphing utility to graph the function in part (d). When will the rate of change of the depth be minimum? Does this agree with your intuition? Explain.

60. Field Strength The field strength H of a magnet of length $2L$ on a particle r units from the center of the magnet is

$$H = \frac{2mL}{(r^2 + L^2)^{3/2}}$$

where $\pm m$ are the poles of the magnet (see figure). Find the average field strength as the particle moves from 0 to R units from the center by evaluating the integral

$$\frac{1}{R}\int_0^R \frac{2mL}{(r^2 + L^2)^{3/2}}\,dr.$$



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

61. Tractrix A tugboat is moving directly away from the shore pulling a fishing boat at the end of a 12-meter rope (see figure). Initially, the fishing boat is located 12 meters away from the tugboat.



(a) Show that the slope of the tangent line of the path of the fishing boat is

$$\frac{dy}{dx} = -\frac{\sqrt{144 - x^2}}{x}.$$

(b) Use the result of part (a) to find the equation of the path of the fishing boat. Use a graphing utility to graph the path and compare it with the figure.

(c) Find any vertical asymptotes of the graphs in part (b).

(d) When the tugboat is 12 meters from the shore, how far has the fishing boat moved?

62. Conjecture

(a) Find formulas for the distances between $(0, 0)$ and (a, a^2), $a > 0$, along the line between these points and along the parabola $y = x^2$.

(b) Use the formulas from part (a) to find the distances for $a = 1$, $a = 10$, and $a = 100$.

(c) Make a conjecture about the difference between the two distances as a increases.

63. Fluid Force

Find the fluid force on a circular observation window of radius 1 foot in a vertical wall of a large water-filled tank at a fish hatchery when the center of the window is (a) 3 feet and (b) d feet ($d > 1$) below the water's surface (see figure). Use trigonometric substitution to evaluate the one integral. Water weighs 62.4 pounds per cubic foot. (Recall that in Section 7.7 in a similar problem, you evaluated one integral by a geometric formula and the other by observing that the integrand was odd.)



64. Fluid Force Evaluate the following two integrals, which yield the fluid forces given in Example 7.

(a) $F_{\text{inside}} = 48\int_{-1}^{0.8} (0.8 - y)(2)\sqrt{1 - y^2}\, dy$

(b) $F_{\text{outside}} = 64\int_{-1}^{0.4} (0.4 - y)(2)\sqrt{1 - y^2}\, dy$

65. Verifying Formulas Use trigonometric substitution to verify the integration formulas given in Theorem 8.2.

66. Finding a Definite Integral Complete the integration shown below (see page 544). Is the result equivalent to the one in Example 4? Explain.

$$\int_{-2}^{-\sqrt{3}} \frac{\sqrt{x^2 - 3}}{x}\, dx = \int_{5\pi/6}^{\pi} \frac{\left(-\sqrt{3}\tan\theta\right)\left(\sqrt{3}\sec\theta\tan\theta\right)}{\sqrt{3}\sec\theta}\, d\theta$$

67. Area of a Lune The crescent-shaped region bounded by two circles forms a *lune* (see figure). Find the area of the lune given that the radius of the smaller circle is 3 and the radius of the larger circle is 5.



Figure for 67



Figure for 68

68. Area Two circles of radius 3, with centers at $(-2, 0)$ and $(2, 0)$, intersect (see figure). Find the area of the shaded region.

69. Arc Length Show that the arc length of the graph of $y = \sin x$ on the interval $[0, 2\pi]$ is equal to the circumference of the ellipse

$x^2 + 2y^2 = 2$ (see figure).



PUTNAM EXAM CHALLENGE

70. Evaluate

$$\int_0^1 \frac{\ln(x + 1)}{x^2 + 1}\, dx.$$

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Johnny Adolphson/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

8.5 Partial Fractions

GO DIGITAL

- **Describe the concept of partial fraction decomposition.**
- **Use partial fraction decomposition with linear factors to integrate rational functions.**
- **Use partial fraction decomposition with quadratic factors to integrate rational functions.**

Partial Fractions

This section examines a procedure for decomposing a rational function into simpler rational functions to which you can apply the basic integration formulas. This procedure is called the **method of partial fractions.** To see the benefit of the method of partial fractions, consider the integral

$$\int \frac{1}{x^2 - 5x + 6}\,dx.$$

To find this integral *without* partial fractions, you can complete the square for $x^2 - 5x + 6$ and use trigonometric substitution (see Figure 8.14) to obtain



$\sec\theta = 2x - 5$

Figure 8.14

$$\begin{aligned}
\int \frac{1}{x^2 - 5x + 6}\,dx &= \int \frac{dx}{(x - 5/2)^2 - (1/2)^2} && a = \tfrac{1}{2},\ x - \tfrac{5}{2} = \tfrac{1}{2}\sec\theta \\
&= \int \frac{(1/2)\sec\theta\tan\theta\,d\theta}{(1/4)\tan^2\theta} && dx = \tfrac{1}{2}\sec\theta\tan\theta\,d\theta \\
&= 2\int \csc\theta\,d\theta \\
&= 2\ln\left|\csc\theta - \cot\theta\right| + C \\
&= 2\ln\left|\frac{2x - 5}{2\sqrt{x^2 - 5x + 6}} - \frac{1}{2\sqrt{x^2 - 5x + 6}}\right| + C \\
&= 2\ln\left|\frac{x - 3}{\sqrt{x^2 - 5x + 6}}\right| + C \\
&= \ln\left|\frac{(x - 3)^2}{x^2 - 5x + 6}\right| + C \\
&= \ln\left|\frac{(x - 3)^2}{(x - 2)(x - 3)}\right| + C \\
&= \ln\left|\frac{x - 3}{x - 2}\right| + C \\
&= \ln|x - 3| - \ln|x - 2| + C.
\end{aligned}$$

Now, suppose you had observed that

$$\frac{1}{x^2 - 5x + 6} = \frac{1}{x - 3} - \frac{1}{x - 2}.$$ Partial fraction decomposition

Then you could find the integral, as shown.

$$\int \frac{1}{x^2 - 5x + 6}\,dx = \int \left(\frac{1}{x - 3} - \frac{1}{x - 2}\right)dx = \ln|x - 3| - \ln|x - 2| + C$$

This method is clearly preferable to trigonometric substitution. Its use, however, depends on the ability to factor the denominator, $x^2 - 5x + 6$, and to find the **partial fractions**

$$\frac{1}{x - 3} \quad \text{and} \quad -\frac{1}{x - 2}.$$

In this section, you will study techniques for finding partial fraction decompositions.

JOHN BERNOULLI (1667–1748)

The method of partial fractions was introduced by John Bernoulli, a Swiss mathematician who was instrumental in the early development of calculus. John Bernoulli was a professor at the University of Basel and taught many outstanding students, the most famous of whom was Leonhard Euler. *See LarsonCalculus.com to read more of this biography.*

Mary Evans Library/Adobe Stock

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Recall from algebra that every polynomial with real coefficients can be factored into linear and irreducible quadratic factors.* For instance, the polynomial

$$x^5 + x^4 - x - 1$$

can be written as

$$\begin{aligned} x^5 + x^4 - x - 1 &= x^4(x + 1) - (x + 1) \\ &= (x^4 - 1)(x + 1) \\ &= (x^2 + 1)(x^2 - 1)(x + 1) \\ &= (x^2 + 1)(x + 1)(x - 1)(x + 1) \\ &= (x - 1)(x + 1)^2(x^2 + 1) \end{aligned}$$

where $(x - 1)$ is a linear factor, $(x + 1)^2$ is a repeated linear factor, and $(x^2 + 1)$ is an irreducible quadratic factor. Using this factorization, you can write the partial fraction decomposition of the rational expression

$$\frac{N(x)}{x^5 + x^4 - x - 1}$$

where $N(x)$ is a polynomial of degree less than 5, as shown.

$$\frac{N(x)}{(x - 1)(x + 1)^2(x^2 + 1)} = \frac{A}{x - 1} + \frac{B}{x + 1} + \frac{C}{(x + 1)^2} + \frac{Dx + E}{x^2 + 1}$$

REMARK In precalculus, you learned how to combine fractions such as

$$\frac{1}{x - 2} + \frac{-1}{x + 3} = \frac{5}{(x - 2)(x + 3)}.$$

The method of partial fractions shows you how to reverse this process.

$$\frac{5}{(x - 2)(x + 3)} = \frac{?}{x - 2} + \frac{?}{x + 3}$$

Decomposition of $N(x)/D(x)$ into Partial Fractions

1. **Divide when improper:** When $N(x)/D(x)$ is an improper fraction (that is, when the degree of the numerator is greater than or equal to the degree of the denominator), divide the denominator into the numerator to obtain

   $$\frac{N(x)}{D(x)} = (\text{a polynomial}) + \frac{N_1(x)}{D(x)}$$

   where the degree of $N_1(x)$ is less than the degree of $D(x)$. Then apply Steps 2, 3, and 4 to the proper rational expression

   $$\frac{N_1(x)}{D(x)}.$$

2. **Factor denominator:** Completely factor the denominator into factors of the form

   $$(px + q)^m \quad \text{and} \quad (ax^2 + bx + c)^n$$

   where $ax^2 + bx + c$ is irreducible.

3. **Linear factors:** For each factor of the form $(px + q)^m$, the partial fraction decomposition must include the following sum of m fractions.

   $$\frac{A_1}{(px + q)} + \frac{A_2}{(px + q)^2} + \cdots + \frac{A_m}{(px + q)^m}$$

4. **Quadratic factors:** For each factor of the form $(ax^2 + bx + c)^n$, the partial fraction decomposition must include the following sum of n fractions.

   $$\frac{B_1x + C_1}{ax^2 + bx + c} + \frac{B_2x + C_2}{(ax^2 + bx + c)^2} + \cdots + \frac{B_nx + C_n}{(ax^2 + bx + c)^n}$$

* For a review of factorization techniques, see *Precalculus*, 11th edition, by Ron Larson (Boston, Massachusetts: Cengage, 2022).

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Linear Factors

Algebraic techniques for determining the constants in the numerators of a partial fraction decomposition with linear or repeated linear factors are shown in Examples 1 and 2.

EXAMPLE 1 Distinct Linear Factors

Write the partial fraction decomposition for

$$\frac{1}{x^2 - 5x + 6}.$$

Solution Because the denominator factors as $x^2 - 5x + 6 = (x - 3)(x - 2)$, you should include one partial fraction for each factor and write

$$\frac{1}{x^2 - 5x + 6} = \frac{A}{x - 3} + \frac{B}{x - 2}$$

where A and B are to be determined. Multiplying this equation by the least common denominator $(x - 3)(x - 2)$ yields the **basic equation**

$$1 = A(x - 2) + B(x - 3). \qquad \text{Basic equation}$$

This equation is true for all x, so you can substitute any *convenient* values for x to obtain equations in A and B. The most convenient values are the ones that make particular factors equal to 0. To solve for A, let $x = 3$.

$$\begin{aligned} 1 &= A(3 - 2) + B(3 - 3) && \text{Let } x = 3 \text{ in basic equation.} \\ 1 &= A(1) + B(0) \\ 1 &= A \end{aligned}$$

To solve for B, let $x = 2$.

$$\begin{aligned} 1 &= A(2 - 2) + B(2 - 3) && \text{Let } x = 2 \text{ in basic equation.} \\ 1 &= A(0) + B(-1) \\ -1 &= B \end{aligned}$$

So, the decomposition is

$$\frac{1}{x^2 - 5x + 6} = \frac{1}{x - 3} - \frac{1}{x - 2}$$

as shown at the beginning of this section. ■

REMARK Note that the substitutions for x in Example 1 are chosen for their convenience in determining values for A and B; $x = 3$ is chosen to eliminate the term $B(x - 3)$, and $x = 2$ is chosen to eliminate the term $A(x - 2)$. The goal is to make *convenient* substitutions whenever possible.

FOR FURTHER INFORMATION To learn a different method for finding partial fraction decompositions, called the Heaviside Method, see the article "Calculus to Algebra Connections in Partial Fraction Decomposition" by Joseph Wiener and Will Watkins in *The AMATYC Review*.

Be sure you understand that the method of partial fractions is practical only for integrals of rational functions whose denominators factor "nicely." For instance, when the denominator in Example 1 is changed to

$$x^2 - 5x + 5$$

its factorization as

$$x^2 - 5x + 5 = \left(x - \frac{5 + \sqrt{5}}{2}\right)\left(x - \frac{5 - \sqrt{5}}{2}\right)$$

would be too cumbersome to use with partial fractions. In such cases, you should use completing the square or a graphing utility to perform the integration. When you do this, you should obtain

$$\int \frac{1}{x^2 - 5x + 5}\,dx = \frac{\sqrt{5}}{5}\ln\left|2x - \sqrt{5} - 5\right| - \frac{\sqrt{5}}{5}\ln\left|2x + \sqrt{5} - 5\right| + C.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 2 Repeated Linear Factors

Find $\int \frac{5x^2 + 20x + 6}{x^3 + 2x^2 + x}\,dx$.

Solution Because the denominator factors as

$$x^3 + 2x^2 + x = x(x^2 + 2x + 1) = x(x + 1)^2$$

you should include one partial fraction for *each power* of x and $(x + 1)$ and write

$$\frac{5x^2 + 20x + 6}{x(x + 1)^2} = \frac{A}{x} + \frac{B}{x + 1} + \frac{C}{(x + 1)^2}.$$

Multiplying by the least common denominator $x(x + 1)^2$ yields the basic equation

$$5x^2 + 20x + 6 = A(x + 1)^2 + Bx(x + 1) + Cx. \qquad \text{Basic equation}$$

To solve for A, let $x = 0$. This eliminates the B and C terms and yields

$$\begin{aligned} 5(0)^2 + 20(0) + 6 &= A(0 + 1)^2 + B(0)(0 + 1) + C(0) \\ 6 &= A(1) + 0 + 0 \\ 6 &= A. \end{aligned}$$

To solve for C, let $x = -1$. This eliminates the A and B terms and yields

$$\begin{aligned} 5(-1)^2 + 20(-1) + 6 &= A(-1 + 1)^2 + B(-1)(-1 + 1) + C(-1) \\ 5 - 20 + 6 &= 0 + 0 - C \\ 9 &= C. \end{aligned}$$

The most convenient choices for x have been used. So, to find the value of B, use *any other value* of x along with the calculated values of A and C. Using $x = 1$, $A = 6$, and $C = 9$ produces

$$\begin{aligned} 5(1)^2 + 20(1) + 6 &= 6(1 + 1)^2 + B(1)(1 + 1) + 9(1) \\ 31 &= 6(4) + 2B + 9 \\ -2 &= 2B \\ -1 &= B. \end{aligned}$$

So, the decomposition is

$$\frac{5x^2 + 20x + 6}{x(x + 1)^2} = \frac{6}{x} - \frac{1}{x + 1} + \frac{9}{(x + 1)^2}.$$

Now, use the decomposition to rewrite the original integrand and find the integral.

$$\begin{aligned} \int \frac{5x^2 + 20x + 6}{x(x + 1)^2}\,dx &= \int \left(\frac{6}{x} - \frac{1}{x + 1} + \frac{9}{(x + 1)^2} \right) dx \\ &= 6 \ln|x| - \ln|x + 1| + 9\frac{(x + 1)^{-1}}{-1} + C \\ &= \ln\left| \frac{x^6}{x + 1} \right| - \frac{9}{x + 1} + C \end{aligned}$$

Check this result by differentiating. Include algebra in your check, simplifying the derivative until you have obtained the original integrand. ■

FOR FURTHER INFORMATION For an alternative approach to using partial fractions, see the article "A Shortcut in Partial Fractions" by Xun-Cheng Huang in *The College Mathematics Journal.*

TECHNOLOGY Some graphing utilities can be used to convert a rational function to its partial fraction decomposition. If you have access to such a utility, use it to find the partial fraction decompositions for the fractions in Examples 1 and 2. Then compare the results with those given in the examples.

It is necessary to make as many substitutions for x as there are unknowns $(A, B, C, \ldots)$ to be determined. For instance, in Example 2, three substitutions $(x = 0, x = -1, \text{and } x = 1)$ were made to solve for A, B, and C.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Quadratic Factors

When using the method of partial fractions with *linear* factors, a convenient choice of x immediately yields a value for one of the coefficients. With *quadratic* factors, a system of linear equations usually has to be solved, regardless of the choice of x.

EXAMPLE 3 Distinct Linear and Quadratic Factors

See LarsonCalculus.com for an interactive version of this type of example.

Find $\int \frac{2x^3 - 4x - 8}{(x^2 - x)(x^2 + 4)}\,dx$.

Solution Because the denominator factors as

$$(x^2 - x)(x^2 + 4) = x(x - 1)(x^2 + 4)$$

you should include one partial fraction for each factor and write

$$\frac{2x^3 - 4x - 8}{x(x - 1)(x^2 + 4)} = \frac{A}{x} + \frac{B}{x - 1} + \frac{Cx + D}{x^2 + 4}.$$

Multiplying by the least common denominator $x(x - 1)(x^2 + 4)$ yields the basic equation

$$2x^3 - 4x - 8 = A(x - 1)(x^2 + 4) + Bx(x^2 + 4) + (Cx + D)(x)(x - 1).$$

To solve for A, let $x = 0$ and obtain

$$\begin{aligned} -8 &= A(-1)(4) + B(0)(4) + D(0)(-1) \\ -8 &= -4A + 0 + 0 \\ 2 &= A. \end{aligned}$$

To solve for B, let $x = 1$ and obtain

$$\begin{aligned} -10 &= A(0)(5) + B(5) + (C + D)(1)(0) \\ -10 &= 0 + 5B + 0 \\ -2 &= B. \end{aligned}$$

At this point, C and D are yet to be determined. To find these remaining constants, choose two other values for x and solve the resulting system of linear equations. First, choose $x = -1$. With $A = 2$ and $B = -2$, you can write

$$\begin{aligned} -6 &= (2)(-2)(5) + (-2)(-1)(5) + (-C + D)(-1)(-2) \\ 2 &= -C + D. \end{aligned}$$

Next, choose $x = 2$. With $A = 2$ and $B = -2$, you can write

$$\begin{aligned} 0 &= (2)(1)(8) + (-2)(2)(8) + (2C + D)(2)(1) \\ 8 &= 2C + D. \end{aligned}$$

Solving the linear system by subtracting the first equation from the second

$$\begin{aligned} -C + D &= 2 \\ 2C + D &= 8 \end{aligned}$$

yields $C = 2$. Consequently, $D = 4$, and it follows that

$$\begin{aligned} \int \frac{2x^3 - 4x - 8}{x(x - 1)(x^2 + 4)}\,dx &= \int \left(\frac{2}{x} - \frac{2}{x - 1} + \frac{2x}{x^2 + 4} + \frac{4}{x^2 + 4} \right) dx \\ &= 2\ln|x| - 2\ln|x - 1| + \ln(x^2 + 4) + 2\arctan\frac{x}{2} + C. \end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

In Examples 1, 2, and 3, the solution of the basic equation began with substituting values of x that made the linear factors equal to 0. This method works well when the partial fraction decomposition involves linear factors. When the decomposition involves only quadratic factors, however, an alternative procedure is often more convenient. For instance, try writing the right side of the basic equation in polynomial form and *equating the coefficients* of like terms. This method is shown in Example 4.

EXAMPLE 4 Repeated Quadratic Factors

Find $\int \frac{8x^3 + 13x}{(x^2 + 2)^2}\,dx$.

Solution Include one partial fraction for each power of $(x^2 + 2)$ and write

$$\frac{8x^3 + 13x}{(x^2 + 2)^2} = \frac{Ax + B}{x^2 + 2} + \frac{Cx + D}{(x^2 + 2)^2}.$$

Multiplying by the least common denominator $(x^2 + 2)^2$ yields the basic equation

$$8x^3 + 13x = (Ax + B)(x^2 + 2) + Cx + D. \qquad \text{Basic equation}$$

Next, expand the basic equation and then collect like terms.

$$8x^3 + 13x = Ax^3 + 2Ax + Bx^2 + 2B + Cx + D \qquad \text{Expand.}$$
$$8x^3 + 13x = Ax^3 + Bx^2 + (2A + C)x + (2B + D) \qquad \text{Collect like terms.}$$

Now, equate the coefficients of like terms on opposite sides of the equation.

$$8 = A \qquad 0 = 2B + D$$
$$8x^3 + 0x^2 + 13x + 0 = Ax^3 + Bx^2 + (2A + C)x + (2B + D)$$
$$0 = B$$
$$13 = 2A + C$$

Note that $A = 8$, $B = 0$, $13 = 2A + C$, and $0 = 2B + D$. Use the values for A and B to solve for C and D.

$$13 = 2A + C \Rightarrow 13 = 2(8) + C \Rightarrow -3 = C$$
$$0 = 2B + D \Rightarrow 0 = 2(0) + D \Rightarrow 0 = D$$

Finally, you can conclude that

$$\int \frac{8x^3 + 13x}{(x^2 + 2)^2}\,dx = \int \left(\frac{8x}{x^2 + 2} + \frac{-3x}{(x^2 + 2)^2} \right) dx$$
$$= 4 \ln(x^2 + 2) + \frac{3}{2(x^2 + 2)} + C.$$

TECHNOLOGY You can use a graphing utility to support the decomposition found in Example 4. To do this, graph

$$y_1 = \frac{8x^3 + 13x}{(x^2 + 2)^2}$$

and

$$y_2 = \frac{8x}{x^2 + 2} + \frac{-3x}{(x^2 + 2)^2}$$

in the same viewing window. The graphs should appear to be identical (see figure).



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

When integrating rational expressions, keep in mind that for *improper* rational expressions such as

$$\frac{N(x)}{D(x)} = \frac{2x^3 + x^2 - 7x + 7}{x^2 + x - 2}$$

you must first divide to obtain

$$\frac{N(x)}{D(x)} = 2x - 1 + \frac{-2x + 5}{x^2 + x - 2}.$$

The proper rational expression is then decomposed into its partial fractions by the usual methods.

Guidelines for solving the basic equation that is obtained in a partial fraction decomposition are given below.

Guidelines for Solving the Basic Equation

Linear Factors

1. Substitute the roots of the distinct linear factors in the basic equation.
2. For repeated linear factors, use the coefficients determined in the first guideline to rewrite the basic equation. Then substitute other convenient values of x and solve for the remaining coefficients.

Quadratic Factors

1. Expand the basic equation.
2. Collect terms according to powers of x.
3. Equate the coefficients of like powers to obtain a system of linear equations involving A, B, C, and so on.
4. Solve the system of linear equations.

FOR FURTHER INFORMATION
To read about another method of evaluating integrals of rational functions, see the article "Alternate Approach to Partial Fractions to Evaluate Integrals of Rational Functions" by N. R. Nandakumar and Michael J. Bossé in *The Pi Mu Epsilon Journal.* To view this article, go to *MathArticles.com.*

Before concluding this section, here are a few things you should remember. First, it is not necessary to use the partial fractions technique on all rational functions. For instance, the next integral is found more easily by the Log Rule.

$$\int \frac{x^2 + 1}{x^3 + 3x - 4}\,dx = \frac{1}{3}\int \frac{3x^2 + 3}{x^3 + 3x - 4}\,dx \qquad \text{Multiply and divide by 3.}$$

$$= \frac{1}{3}\ln|x^3 + 3x - 4| + C \qquad \text{Apply Log Rule.}$$

Second, when the integrand is not in reduced form, reducing it may eliminate the need for partial fractions, as shown in the next integral.

$$\int \frac{x^2 - x - 2}{x^3 - 2x - 4}\,dx = \int \frac{(x + 1)(x - 2)}{(x - 2)(x^2 + 2x + 2)}\,dx \qquad \text{Factor.}$$

$$= \int \frac{x + 1}{x^2 + 2x + 2}\,dx \qquad \text{Divide out common factor.}$$

$$= \frac{1}{2}\ln|x^2 + 2x + 2| + C \qquad \text{Apply Log Rule.}$$

Finally, partial fractions can be used with some quotients involving transcendental functions. For instance, the substitution $u = \sin x$ allows you to write

$$\int \frac{\cos x}{(\sin x)(\sin x - 1)}\,dx = \int \frac{du}{u(u - 1)}. \qquad u = \sin x,\ du = \cos x\,dx$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

8.5 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Write the form of the partial fraction decomposition of each rational expression. Do not solve for the constants.

(a) $\dfrac{4}{x^2 - 8x}$ (b) $\dfrac{2x^2 + 1}{(x - 3)^3}$

(c) $\dfrac{2x - 3}{x^3 + 10x}$ (d) $\dfrac{2x - 1}{x(x^2 + 1)^2}$

2. Explain how to solve a basic equation obtained in a partial fraction decomposition that involves quadratic factors.

Using Partial Fractions **In Exercises 3–20, use partial fractions to find the indefinite integral.**

3. $\displaystyle\int \frac{1}{x^2 - 9}\,dx$

4. $\displaystyle\int \frac{2}{9x^2 - 1}\,dx$

5. $\displaystyle\int \frac{5}{x^2 + 3x - 4}\,dx$

6. $\displaystyle\int \frac{3 - x}{3x^2 - 2x - 1}\,dx$

7. $\displaystyle\int \frac{x^2 + 12x + 12}{x^3 - 4x}\,dx$

8. $\displaystyle\int \frac{x^3 - x + 3}{x^2 + x - 2}\,dx$

9. $\displaystyle\int \frac{2x^3 - 4x^2 - 15x + 5}{x^2 - 2x - 8}\,dx$

10. $\displaystyle\int \frac{x + 2}{x^2 + 5x}\,dx$

11. $\displaystyle\int \frac{4x^2 + 2x - 1}{x^3 + x^2}\,dx$

12. $\displaystyle\int \frac{5x - 2}{(x - 2)^2}\,dx$

13. $\displaystyle\int \frac{x^2 - 6x + 2}{x^3 + 2x^2 + x}\,dx$

14. $\displaystyle\int \frac{8x}{x^3 + x^2 - x - 1}\,dx$

15. $\displaystyle\int \frac{9 - x^2}{7x^3 + x}\,dx$

16. $\displaystyle\int \frac{6x}{x^3 - 8}\,dx$

17. $\displaystyle\int \frac{x^2}{x^4 - 2x^2 - 8}\,dx$

18. $\displaystyle\int \frac{x}{16x^4 - 1}\,dx$

19. $\displaystyle\int \frac{x^2 + 5}{x^3 - x^2 + x + 3}\,dx$

20. $\displaystyle\int \frac{x^2 + 6x + 4}{x^4 + 8x^2 + 16}\,dx$

Evaluating a Definite Integral **In Exercises 21–24, use partial fractions to evaluate the definite integral. Use a graphing utility to verify your result.**

21. $\displaystyle\int_0^2 \frac{3}{4x^2 + 5x + 1}\,dx$

22. $\displaystyle\int_1^5 \frac{x - 1}{x^2(x + 1)}\,dx$

23. $\displaystyle\int_1^2 \frac{x + 1}{x(x^2 + 1)}\,dx$

24. $\displaystyle\int_0^1 \frac{x^2 - x}{x^2 + x + 1}\,dx$

Finding an Indefinite Integral **In Exercises 25–32, use substitution and partial fractions to find the indefinite integral.**

25. $\displaystyle\int \frac{\sin x}{\cos x + \cos^2 x}\,dx$

26. $\displaystyle\int \frac{5\cos x}{\sin^2 x + 3\sin x - 4}\,dx$

27. $\displaystyle\int \frac{\sec^2 x}{\tan^2 x + 5\tan x + 6}\,dx$

28. $\displaystyle\int \frac{\sec^2 x}{(\tan x)(\tan x + 1)}\,dx$

29. $\displaystyle\int \frac{e^x}{(e^x - 1)(e^x + 4)}\,dx$

30. $\displaystyle\int \frac{e^x}{(e^{2x} + 1)(e^x - 1)}\,dx$

31. $\displaystyle\int \frac{\sqrt{x}}{x - 4}\,dx$

32. $\displaystyle\int \frac{1}{x\left(\sqrt{3} - \sqrt{x}\right)}\,dx$

Verifying a Formula **In Exercises 33–36, use the method of partial fractions to verify the integration formula.**

33. $\displaystyle\int \frac{1}{x(a + bx)}\,dx = \frac{1}{a}\ln\left|\frac{x}{a + bx}\right| + C$

34. $\displaystyle\int \frac{1}{a^2 - x^2}\,dx = \frac{1}{2a}\ln\left|\frac{a + x}{a - x}\right| + C$

35. $\displaystyle\int \frac{x}{(a + bx)^2}\,dx = \frac{1}{b^2}\left(\frac{a}{a + bx} + \ln|a + bx|\right) + C$

36. $\displaystyle\int \frac{1}{x^2(a + bx)}\,dx = -\frac{1}{ax} - \frac{b}{a^2}\ln\left|\frac{x}{a + bx}\right| + C$

Area **In Exercises 37–40, use partial fractions to find the area of the given region.**

37. $y = \dfrac{12}{x^2 + 5x + 6}$



38. $y = \dfrac{15}{x^2 + 7x + 12}$



39. $y = \dfrac{15}{9 - x^2}$



40. $y = \dfrac{7}{16 - x^2}$



Exploring Concepts

In Exercises 41–43, state the method of integration you would use to find each integral. Explain why you chose that method. Do not integrate.

41. $\displaystyle\int \frac{x + 1}{x^2 + 2x - 8}\,dx$

42. $\displaystyle\int \frac{7x + 4}{x^2 + 2x - 8}\,dx$

43. $\displaystyle\int \frac{4}{x^2 + 2x + 5}\,dx$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

44. HOW DO YOU SEE IT? Use the graph of f' shown in the figure to answer the following.



(a) Is $f(3) - f(2) > 0$? Explain.

(b) Which is greater, the area under the graph of f' from 1 to 2 or the area under the graph of f' from 3 to 4?

45. Modeling Data The predicted cost C (in hundreds of thousands of dollars) for a company to remove $p\%$ of a chemical from its waste water is shown in the table.

P	0	10	20	30	40
C	0	0.7	1.0	1.3	1.7

P	50	60	70	80	90
C	2.0	2.7	3.6	5.5	11.2

A model for the data is given by

$$C = \frac{124p}{(10 + p)(100 - p)}$$

for $0 \le p < 100$. Use the model to find the average cost of removing between 75% and 80% of the chemical.

46. Average Value of a Function Find the average value of

$$f(x) = \frac{1}{4x^2 - 1}$$

from $x = 1$ to $x = 4$.

47. Volume and Centroid Consider the region bounded by the graphs of

$$y = \frac{2x}{x^2 + 1}, \quad y = 0, \quad x = 0, \quad \text{and} \quad x = 3.$$

(a) Find the volume of the solid generated by revolving the region about the x-axis.

(b) Find the centroid of the region.

48. Volume Consider the region bounded by the graph of

$$y^2 = \frac{(2 - x)^2}{(1 + x)^2}$$

on the interval $[0, 1]$. Find the volume of the solid generated by revolving this region about the x-axis.

49. Epidemic Model A single infected individual enters a community of n susceptible individuals. Let x be the number of newly infected individuals at time t. The common epidemic model assumes that the disease spreads at a rate proportional to the product of the total number infected and the number not yet infected. So,

$$\frac{dx}{dt} = k(x + 1)(n - x)$$

and you obtain

$$\int \frac{1}{(x + 1)(n - x)}\,dx = \int k\,dt.$$

Solve for x as a function of t.

50. Chemical Reaction

In a chemical reaction, one unit of compound Y and one unit of compound Z are converted into a single unit of compound X. Let x be the amount of compound X formed. The rate of formation of X is proportional to the product of the amounts of unconverted compounds Y and Z. So, $dx/dt = k(y_0 - x)(z_0 - x)$, where y_0 and z_0 are the initial amounts of compounds Y and Z. From this equation, you obtain

$$\int \frac{1}{(y_0 - x)(z_0 - x)}\,dx = \int k\,dt.$$

(a) Solve for x as a function of t.

(b) Use the result of part (a) to find x as $t \to \infty$ for (1) $y_0 < z_0$, (2) $y_0 > z_0$, and (3) $y_0 = z_0$.

51. Using Two Methods Evaluate

$$\int_0^1 \frac{x}{1 + x^4}\,dx$$

in two different ways, one of which is partial fractions.

PUTNAM EXAM CHALLENGE

52. Prove $\frac{22}{7} - \pi = \int_0^1 \frac{x^4(1 - x)^4}{1 + x^2}\,dx$.

53. Let $p(x)$ be a nonzero polynomial of degree less than 1992 having no nonconstant factor in common with $x^3 - x$. Let

$$\frac{d^{1992}}{dx^{1992}}\left(\frac{p(x)}{x^3 - x}\right) = \frac{f(x)}{g(x)}$$

for polynomials $f(x)$ and $g(x)$. Find the smallest possible degree of $f(x)$.

These problems were composed by the Committee on the Putnam Prize Competition. © The Mathematical Association of America. All rights reserved.

biDaala_studio/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

8.6 Numerical Integration

GO DIGITAL

- Approximate a definite integral using the Trapezoidal Rule.
- Approximate a definite integral using Simpson's Rule.
- Analyze the approximate errors in the Trapezoidal Rule and Simpson's Rule.

The Trapezoidal Rule

Some elementary functions do not have antiderivatives that are elementary functions. For example, consider the functions below. There is no elementary function that has any of these functions as its derivative.

$$\sqrt[3]{x}\sqrt{1-x}, \qquad \sqrt{x}\cos x, \qquad \frac{\cos x}{x}, \qquad \sqrt{1-x^3}, \qquad \sin x^2$$

How can you evaluate a definite integral involving a function whose antiderivative cannot be found? While the Fundamental Theorem of Calculus is still true, it cannot be easily applied. In this case, it is easier to resort to an approximation technique, such as the Midpoint Rule (see Section 4.2). Two other techniques are described in this section.

One way to approximate a definite integral is to use n trapezoids, as shown in Figure 8.15. In the development of this method, assume that f is continuous and positive on the interval $[a, b]$. So, the definite integral

$$\int_a^b f(x)\,dx$$

represents the area of the region bounded by the graph of f and the x-axis, from $x = a$ to $x = b$. First, partition the interval $[a, b]$ into n subintervals, each of width $\Delta x = (b - a)/n$, such that

$$a = x_0 < x_1 < x_2 < \cdots < x_n = b.$$



The area of the region can be approximated using four trapezoids.

Figure 8.15

Then form a trapezoid for each subinterval (see Figure 8.16). The area of the ith trapezoid is

$$\text{Area of } i\text{th trapezoid} = \left[\frac{f(x_{i-1}) + f(x_i)}{2}\right]\left(\frac{b-a}{n}\right).$$

This implies that the sum of the areas of the n trapezoids is

$$\begin{aligned}\text{Area} &= \left(\frac{b-a}{n}\right)\left[\frac{f(x_0)+f(x_1)}{2} + \cdots + \frac{f(x_{n-1})+f(x_n)}{2}\right] \\ &= \left(\frac{b-a}{2n}\right)[f(x_0) + f(x_1) + f(x_1) + f(x_2) + \cdots + f(x_{n-1}) + f(x_n)] \\ &= \left(\frac{b-a}{2n}\right)[f(x_0) + 2f(x_1) + 2f(x_2) + \cdots + 2f(x_{n-1}) + f(x_n)].\end{aligned}$$

Letting $\Delta x = (b - a)/n$, take the limit as $n \to \infty$ to obtain

$$\begin{aligned}&\lim_{n\to\infty}\left(\frac{b-a}{2n}\right)[f(x_0) + 2f(x_1) + \cdots + 2f(x_{n-1}) + f(x_n)] \\ &= \lim_{n\to\infty}\left[\frac{[f(a) - f(b)]\,\Delta x}{2} + \sum_{i=1}^{n} f(x_i)\,\Delta x\right] \\ &= \lim_{n\to\infty}\frac{[f(a) - f(b)](b-a)}{2n} + \lim_{n\to\infty}\sum_{i=1}^{n} f(x_i)\,\Delta x \\ &= 0 + \int_a^b f(x)\,dx.\end{aligned}$$

The result is summarized in the next theorem.



The area of the first trapezoid is $\left[\frac{f(x_0) + f(x_1)}{2}\right]\left(\frac{b-a}{n}\right)$.

Figure 8.16

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

THEOREM 8.3 The Trapezoidal Rule

Let a function f be continuous on $[a, b]$. The Trapezoidal Rule for approximating $\int_a^b f(x)\,dx$ is

$$\int_a^b f(x)\,dx \approx \frac{b-a}{2n}[f(x_0) + 2f(x_1) + 2f(x_2) + \cdots + 2f(x_{n-1}) + f(x_n)].$$

Moreover, as $n \to \infty$, the right side approaches $\int_a^b f(x)\,dx$.

REMARK Observe that the coefficients in the Trapezoidal Rule have the pattern shown below.

1 2 2 2 . . . 2 2 1

EXAMPLE 1 Approximation with the Trapezoidal Rule

Use the Trapezoidal Rule to approximate

$$\int_0^{\pi} \sin x\,dx.$$

Compare the results for $n = 4$ and $n = 8$, as shown in Figure 8.17.



Four subintervals



Eight subintervals

Trapezoidal approximations

Figure 8.17

Solution When $n = 4$, $\Delta x = \pi/4$, and you obtain

$$\int_0^{\pi} \sin x\,dx \approx \frac{\pi}{8}\left(\sin 0 + 2\sin\frac{\pi}{4} + 2\sin\frac{\pi}{2} + 2\sin\frac{3\pi}{4} + \sin\pi\right)$$

$$= \frac{\pi}{8}\left(0 + \sqrt{2} + 2 + \sqrt{2} + 0\right)$$

$$= \frac{\pi\left(1 + \sqrt{2}\right)}{4}$$

$$\approx 1.896.$$ Approximation using $n = 4$

When $n = 8$, $\Delta x = \pi/8$, and you obtain

$$\int_0^{\pi} \sin x\,dx \approx \frac{\pi}{16}\left(\sin 0 + 2\sin\frac{\pi}{8} + 2\sin\frac{\pi}{4} + 2\sin\frac{3\pi}{8} + 2\sin\frac{\pi}{2} + 2\sin\frac{5\pi}{8} + 2\sin\frac{3\pi}{4} + 2\sin\frac{7\pi}{8} + \sin\pi\right)$$

$$= \frac{\pi}{16}\left(2 + 2\sqrt{2} + 4\sin\frac{\pi}{8} + 4\sin\frac{3\pi}{8}\right)$$

$$\approx 1.974.$$ Approximation using $n = 8$

Of course, for *this particular* integral, you can find an antiderivative and use the Fundamental Theorem of Calculus to find the exact value of the definite integral.

$$\int_0^{\pi} \sin x\,dx = -\cos x\Big]_0^{\pi} = 1 + 1 = 2$$ Exact value

So, the approximation using $n = 8$ is closer to the exact value than the one using $n = 4$.

TECHNOLOGY Most graphing utilities have a *numerical integration* feature for approximating the value of a definite integral. Use this feature to approximate the integral in Example 1. How close is the approximation? When you use this feature, you need to be aware of its limitations. Often, you are given no indication of the degree of accuracy of the approximation.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

It is interesting to compare the Trapezoidal Rule with the Midpoint Rule given in Section 4.2. For the Trapezoidal Rule, you average the function values at the endpoints of the subintervals, but for the Midpoint Rule, you take the function values of the subinterval midpoints.

$$\int_a^b f(x)\,dx \approx \sum_{i=1}^{n} f\left(\frac{x_{i-1} + x_i}{2}\right)\Delta x \qquad \text{Midpoint Rule}$$

$$\int_a^b f(x)\,dx \approx \sum_{i=1}^{n} \left(\frac{f(x_{i-1}) + f(x_i)}{2}\right)\Delta x \qquad \text{Trapezoidal Rule}$$

There are two important points that should be made concerning the Trapezoidal Rule (or the Midpoint Rule). First, the approximation tends to become more accurate as n increases. For instance, in Example 1, when $n = 16$, the Trapezoidal Rule yields an approximation of 1.994. Second, although you could have used the Fundamental Theorem of Calculus to evaluate the integral in Example 1, this theorem cannot be used to evaluate an integral as simple as $\int_0^{\pi} \sin x^2\,dx$ because $\sin x^2$ has no elementary antiderivative. Yet the Trapezoidal Rule can be applied to estimate this integral.

Simpson's Rule

One way to view the trapezoidal approximation of a definite integral is to say that on each subinterval, you approximate f by a *first*-degree polynomial. In Simpson's Rule, named after the English mathematician Thomas Simpson (1710–1761), you take this procedure one step further and approximate f by *second*-degree polynomials.

Before presenting Simpson's Rule, consider the next theorem for evaluating integrals of polynomials of degree 2 (or less).

THEOREM 8.4 Integral of $p(x) = Ax^2 + Bx + C$

If $p(x) = Ax^2 + Bx + C$, then

$$\int_a^b p(x)\,dx = \left(\frac{b-a}{6}\right)\left[p(a) + 4p\left(\frac{a+b}{2}\right) + p(b)\right].$$

Proof

$$\begin{aligned}\int_a^b p(x)\,dx &= \int_a^b (Ax^2 + Bx + C)\,dx \\ &= \left[\frac{Ax^3}{3} + \frac{Bx^2}{2} + Cx\right]_a^b \\ &= \frac{A(b^3 - a^3)}{3} + \frac{B(b^2 - a^2)}{2} + C(b-a) \\ &= \left(\frac{b-a}{6}\right)[2A(a^2 + ab + b^2) + 3B(b+a) + 6C]\end{aligned}$$

By expanding and collecting terms, the expression inside the brackets becomes

$$\underbrace{(Aa^2 + Ba + C)}_{p(a)} + \underbrace{4\left[A\left(\frac{b+a}{2}\right)^2 + B\left(\frac{b+a}{2}\right) + C\right]}_{4p\left(\frac{a+b}{2}\right)} + \underbrace{(Ab^2 + Bb + C)}_{p(b)}$$

and you can write

$$\int_a^b p(x)\,dx = \left(\frac{b-a}{6}\right)\left[p(a) + 4p\left(\frac{a+b}{2}\right) + p(b)\right].$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



$$\int_{x_0}^{x_2} p(x)\,dx \approx \int_{x_0}^{x_2} f(x)\,dx$$

Figure 8.18

To develop Simpson's Rule for approximating a definite integral, you again partition the interval $[a, b]$ into n subintervals, each of width $\Delta x = (b - a)/n$. This time, however, n is required to be even, and the subintervals are grouped in pairs such that

$$a = \underbrace{x_0 < x_1 < x_2}_{[x_0, x_2]} < \underbrace{x_3 < x_4}_{[x_2, x_4]} < \cdots < \underbrace{x_{n-2} < x_{n-1} < x_n}_{[x_{n-2}, x_n]} = b.$$

On each (double) subinterval $[x_{i-2}, x_i]$, you can approximate f by a polynomial p of degree less than or equal to 2. (See Exercise 47.) For example, on the subinterval $[x_0, x_2]$, choose the polynomial of least degree passing through the points (x_0, y_0), (x_1, y_1), and (x_2, y_2), as shown in Figure 8.18. Now, using p as an approximation of f on this subinterval, you have, by Theorem 8.4,

$$\begin{aligned}\int_{x_0}^{x_2} f(x)\,dx &\approx \int_{x_0}^{x_2} p(x)\,dx \\ &= \frac{x_2 - x_0}{6}\left[p(x_0) + 4p\left(\frac{x_0 + x_2}{2}\right) + p(x_2)\right] \\ &= \frac{2[(b-a)/n]}{6}[p(x_0) + 4p(x_1) + p(x_2)] \\ &= \frac{b-a}{3n}[f(x_0) + 4f(x_1) + f(x_2)].\end{aligned}$$

Repeating this procedure on the entire interval $[a, b]$ produces the next theorem.

REMARK Observe that the coefficients in Simpson's Rule have the pattern shown below.

1 4 2 4 2 4 . . . 4 2 4 1

THEOREM 8.5 Simpson's Rule

Let a function f be continuous on $[a, b]$ and let n be an even integer. Simpson's Rule for approximating $\int_a^b f(x)\,dx$ is

$$\begin{aligned}\int_a^b f(x)\,dx \approx \frac{b-a}{3n}[&f(x_0) + 4f(x_1) + 2f(x_2) + 4f(x_3) + \cdots \\ &+ 2f(x_{n-2}) + 4f(x_{n-1}) + f(x_n)].\end{aligned}$$

Moreover, as $n \to \infty$, the right side approaches $\int_a^b f(x)\,dx$.

In Example 1, the Trapezoidal Rule was used to estimate $\int_0^\pi \sin x\,dx$. In the next example, Simpson's Rule is applied to the same integral.

REMARK In Section 4.2, Example 8, the Midpoint Rule with $n = 4$ approximates this definite integral as 2.052. In Example 1, the Trapezoidal Rule with $n = 4$ gives an approximation of 1.896. In Example 2, Simpson's Rule with $n = 4$ gives an approximation of 2.005. The antiderivative would produce the exact value of 2.

EXAMPLE 2 Approximation with Simpson's Rule

See LarsonCalculus.com for an interactive version of this type of example.

Use Simpson's Rule to approximate

$$\int_0^\pi \sin x\,dx.$$

Compare the results for $n = 4$ and $n = 8$.

Solution When $n = 4$, you have

$$\int_0^\pi \sin x\,dx \approx \frac{\pi}{12}\left(\sin 0 + 4\sin\frac{\pi}{4} + 2\sin\frac{\pi}{2} + 4\sin\frac{3\pi}{4} + \sin\pi\right) \approx 2.005.$$

When $n = 8$, and using a graphing utility, the approximation is 2.0003. As shown in Example 1, the exact value of the definite integral is 2. So, the approximation using $n = 8$ is closer to the exact value than the one using $n = 4$. ■

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Error Analysis

It is important to know the accuracy of an approximation. The next theorem, which is listed without proof, gives the formulas for estimating the errors involved in the use of Simpson's Rule and the Trapezoidal Rule. In general, you can think of the error E as the difference between $\int_a^b f(x)\,dx$ and the approximation.

FOR FURTHER INFORMATION
For proofs of the formulas used for estimating the errors involved in the use of the Midpoint Rule and Simpson's Rule, see the article "Elementary Proofs of Error Estimates for the Midpoint and Simpson's Rules" by Edward C. Fazekas, Jr. and Peter R. Mercer in *Mathematics Magazine*. To view this article, go to *MathArticles.com*.

THEOREM 8.6 Errors in the Trapezoidal Rule and Simpson's Rule

If a function f has a continuous second derivative on $[a, b]$, then the error E in approximating $\int_a^b f(x)\,dx$ by the Trapezoidal Rule is

$$|E| \le \frac{(b-a)^3}{12n^2}[\max |f''(x)|], \quad a \le x \le b. \qquad \text{Trapezoidal Rule}$$

Moreover, if f has a continuous fourth derivative on $[a, b]$, then the error E in approximating $\int_a^b f(x)\,dx$ by Simpson's Rule is

$$|E| \le \frac{(b-a)^5}{180n^4}[\max |f^{(4)}(x)|], \quad a \le x \le b. \qquad \text{Simpson's Rule}$$

Theorem 8.6 states that the errors generated by the Trapezoidal Rule and Simpson's Rule have upper bounds dependent on the extreme values of $f''(x)$ and $f^{(4)}(x)$ in the interval $[a, b]$. Furthermore, these errors can be made arbitrarily small by *increasing* n, provided that f'' and $f^{(4)}$ are continuous and therefore bounded on $[a, b]$.

TECHNOLOGY
Use a graphing utility to evaluate the definite integral in Example 3. You should obtain a value equivalent to

$$\frac{1}{2}\left[\sqrt{2} + \ln\left(1 + \sqrt{2}\right)\right] \approx 1.14779.$$

EXAMPLE 3 The Approximate Error in the Trapezoidal Rule

Determine a value of n such that the Trapezoidal Rule will approximate the value of

$$\int_0^1 \sqrt{1 + x^2}\,dx$$

with an error that is less than or equal to 0.01.

Solution Begin by letting $f(x) = \sqrt{1 + x^2} = (1 + x^2)^{1/2}$. The first two derivatives of f are

$$f'(x) = x(1 + x^2)^{-1/2} \quad \text{and} \quad f''(x) = (1 + x^2)^{-3/2}.$$

The maximum value of $|f''(x)|$ on the interval $[0, 1]$ is $|f''(0)| = 1$. So, by Theorem 8.6,

$$|E| \le \frac{(b-a)^3}{12n^2}|f''(0)| = \frac{1}{12n^2}(1) = \frac{1}{12n^2}.$$

To obtain an error E that is less than or equal to 0.01, you must choose n such that $1/(12n^2) \le 1/100$. This implies that $100 \le 12n^2$, or $n \ge \sqrt{100/12} \approx 2.89$. So, you can choose $n = 3$ (because n must be greater than or equal to 2.89) and apply the Trapezoidal Rule, as shown in Figure 8.19, to obtain

$$\int_0^1 \sqrt{1 + x^2}\,dx \approx \frac{1}{6}\left[\sqrt{1 + 0^2} + 2\sqrt{1 + \left(\frac{1}{3}\right)^2} + 2\sqrt{1 + \left(\frac{2}{3}\right)^2} + \sqrt{1 + 1^2}\right] \approx 1.154.$$

By adding and subtracting the error from this estimate, you know that

$$1.144 \le \int_0^1 \sqrt{1 + x^2}\,dx \le 1.164.$$



$1.144 \le \int_0^1 \sqrt{1 + x^2}\,dx \le 1.164$

Figure 8.19

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

8.6 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain whether you would use numerical integration to evaluate $\int_0^2 (e^x + 5x)\,dx$.
2. Describe how to decrease the error between an approximation and the exact value of an integral using the Trapezoidal Rule and Simpson's Rule.

Using the Trapezoidal Rule and Simpson's Rule **In Exercises 3–14, use the Trapezoidal Rule and Simpson's Rule to approximate the value of the definite integral for the given value of n. Round your answer to four decimal places and compare the results with the exact value of the definite integral.**

3. $\int_0^2 x^2\,dx, \quad n = 4$
4. $\int_1^2 \left(\frac{x^2}{4} + 1\right) dx, \quad n = 4$
5. $\int_3^4 \frac{1}{x-2}\,dx, \quad n = 4$
6. $\int_2^3 \frac{2}{x^2}\,dx, \quad n = 4$
7. $\int_1^3 x^3\,dx, \quad n = 6$
8. $\int_0^8 \sqrt[3]{x}\,dx, \quad n = 8$
9. $\int_4^9 \sqrt{x}\,dx, \quad n = 8$
10. $\int_1^4 (4 - x^2)\,dx, \quad n = 6$
11. $\int_0^1 \frac{2}{(x+2)^2}\,dx, \quad n = 4$
12. $\int_0^2 x\sqrt{x^2+1}\,dx, \quad n = 4$
13. $\int_0^2 xe^{-x}\,dx, \quad n = 4$
14. $\int_0^2 x\ln(x+1)\,dx, \quad n = 4$

Using the Trapezoidal Rule and Simpson's Rule **In Exercises 15–24, approximate the definite integral using the Trapezoidal Rule and Simpson's Rule with $n = 4$. Compare these results with the approximation of the integral using a graphing utility.**

15. $\int_0^2 \sqrt{1+x^3}\,dx$
16. $\int_0^1 \sqrt{x}\sqrt{1-x}\,dx$
17. $\int_0^1 \frac{1}{1+x^2}\,dx$
18. $\int_0^2 \frac{1}{\sqrt{1+x^3}}\,dx$
19. $\int_0^4 \sqrt{x}e^x\,dx$
20. $\int_1^3 \ln x\,dx$
21. $\int_0^{\sqrt{\pi/2}} \sin x^2\,dx$
22. $\int_{\pi/2}^{\pi} \sqrt{x}\sin x\,dx$
23. $\int_0^{\pi/4} x\tan x\,dx$
24. $\int_0^{\pi} f(x)\,dx, \quad f(x) = \begin{cases} \frac{\sin x}{x}, & x > 0 \\ 1, & x = 0 \end{cases}$

Estimating Errors **In Exercises 25–28, use the error formulas in Theorem 8.6 to estimate the errors in approximating the integral, with $n = 4$, using (a) the Trapezoidal Rule and (b) Simpson's Rule.**

25. $\int_0^2 (x^2 + 2x)\,dx$
26. $\int_1^3 2x^3\,dx$
27. $\int_2^4 \frac{1}{(x-1)^2}\,dx$
28. $\int_0^1 e^{x^3}\,dx$

Estimating Errors **In Exercises 29–32, use the error formulas in Theorem 8.6 to find n such that the error in the approximation of the definite integral is less than or equal to 0.00001 using (a) the Trapezoidal Rule and (b) Simpson's Rule.**

29. $\int_1^3 \frac{1}{x}\,dx$
30. $\int_0^1 \frac{1}{1+x}\,dx$
31. $\int_0^2 \sqrt{x+2}\,dx$
32. $\int_1^3 e^{2x}\,dx$

Estimating Errors Using Technology **In Exercises 33 and 34, use a graphing utility and the error formulas to find n such that the error in the approximation of the definite integral is less than or equal to 0.00001 using (a) the Trapezoidal Rule and (b) Simpson's Rule.**

33. $\int_0^1 \tan x^2\,dx$
34. $\int_0^2 (x+1)^{2/3}\,dx$

35. **Finding the Area of a Region** Approximate the area of the shaded region using the Trapezoidal Rule and Simpson's Rule with $n = 4$.



Figure for 35



Figure for 36

36. **Finding the Area of a Region** Approximate the area of the shaded region using the Trapezoidal Rule and Simpson's Rule with $n = 8$.
37. **Area** Use Simpson's Rule with $n = 14$ to approximate the area of the region bounded by the graphs of $y = \sqrt{x}\cos x$, $y = 0$, $x = 0$, and $x = \pi/2$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

38. HOW DO YOU SEE IT? The function f is concave upward on the interval $[0, 2]$ and the function g is concave downward on the interval $[0, 2]$, as shown in the figure.



(a) Using the Trapezoidal Rule with $n = 4$, which integral would be overestimated, $\int_0^2 f(x)\,dx$ or $\int_0^2 g(x)\,dx$? Which integral would be underestimated? Explain your reasoning.

(b) Which rule would you use for more accurate approximations of $\int_0^2 f(x)\,dx$ and $\int_0^2 g(x)\,dx$, the Trapezoidal Rule or Simpson's Rule? Explain your reasoning.

Exploring Concepts

39. Explain how the Trapezoidal Rule is related to the approximations using left and right Riemann sums.

40. Describe the size of the error when the Trapezoidal Rule is used to approximate $\int_a^b f(x)\,dx$ when $f(x)$ is a linear function. Use a graph to explain your answer.

41. Surveying Use the Trapezoidal Rule to estimate the number of square meters of land, where x and y are measured in meters, as shown in the figure. The land is bounded by a stream and two straight roads that meet at right angles.

x	0	100	200	300	400	500
y	125	125	120	112	90	90

x	600	700	800	900	1000
y	95	88	75	35	0



42. Circumference The **elliptic integral**

$$8\sqrt{3}\int_0^{\pi/2}\sqrt{1-\tfrac{2}{3}\sin^2\theta}\,d\theta$$

gives the circumference of an ellipse. Use Simpson's Rule with $n = 8$ to approximate the circumference.

43. Work To determine the size of the motor required to operate a press, a company must know the amount of work done when the press moves an object linearly 5 feet. The variable force to move the object is

$$F(x) = 100x\sqrt{125 - x^3}$$

where F is given in pounds and x gives the position of the unit in feet. Use Simpson's Rule with $n = 12$ to approximate the work W (in foot-pounds) done through one cycle when

$$W = \int_0^5 F(x)\,dx.$$

44. Approximating a Function The table lists several measurements gathered in an experiment to approximate an unknown continuous function $y = f(x)$.

x	0.00	0.25	0.50	0.75	1.00
y	4.32	4.36	4.58	5.79	6.14

x	1.25	1.50	1.75	2.00
y	7.25	7.64	8.08	8.14

(a) Approximate the integral

$$\int_0^2 f(x)\,dx$$

using the Trapezoidal Rule and Simpson's Rule.

(b) Use a graphing utility to find a model of the form $y = ax^3 + bx^2 + cx + d$ for the data. Integrate the resulting polynomial over $[0, 2]$ and compare the result with the integral from part (a).

45. Using Simpson's Rule Use Simpson's Rule with $n = 10$ and a graphing utility to approximate t in the integral equation

$$\int_0^t \sin\sqrt{x}\,dx = 2.$$

46. Proof Prove that Simpson's Rule is exact when approximating the integral of a cubic polynomial function, and demonstrate the result with $n = 4$ for

$$\int_0^1 x^3\,dx.$$

47. Proof Prove that you can find a polynomial

$$p(x) = Ax^2 + Bx + C$$

that passes through any three points (x_1, y_1), (x_2, y_2), and (x_3, y_3), where the x_i's are distinct.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

8.7 Integration by Tables and Other Integration Techniques

GO DIGITAL

- **Find an indefinite integral using a table of integrals.**
- **Find an indefinite integral using reduction formulas.**
- **Find an indefinite integral involving fractional expressions of sine and cosine.**

Integration by Tables

So far in this chapter, you have studied several integration techniques that can be used with the basic integration rules. But merely knowing *how* to use the various techniques is not enough. You also need to know *when* to use them. Integration is first and foremost a problem of recognition. That is, you must recognize which rule or technique to apply to obtain an antiderivative. Frequently, a slight alteration of an integrand will require a different integration technique (or produce a function whose antiderivative is not an elementary function), as shown below.

$$\int x \ln x \, dx = \frac{x^2}{2} \ln x - \frac{x^2}{4} + C \qquad \text{Integration by parts}$$

$$\int \frac{\ln x}{x} \, dx = \frac{(\ln x)^2}{2} + C \qquad \text{Power Rule}$$

$$\int \frac{1}{x \ln x} \, dx = \ln|\ln x| + C \qquad \text{Log Rule}$$

$$\int \frac{x}{\ln x} \, dx = ? \qquad \text{Not an elementary function}$$

TECHNOLOGY

A graphing utility that performs symbolic integration consists, in part, of a database of integration formulas. The primary difference between using a graphing utility and using tables of integrals is that the utility searches through the database to find a fit. With integration tables, *you* must do the searching.

Many people find tables of integrals to be a valuable supplement to the integration techniques discussed in this chapter. Tables of common integrals can be found in Appendix B. **Integration by tables** is not a "cure-all" for all of the difficulties that can accompany integration—using tables of integrals requires considerable thought and insight and often involves substitution.

Each integration formula in Appendix B can be developed using one or more of the techniques in this chapter. You should try to verify several of the formulas. For instance, Formula 4

$$\int \frac{u}{(a + bu)^2} \, du = \frac{1}{b^2}\left(\frac{a}{a + bu} + \ln|a + bu|\right) + C \qquad \text{Formula 4}$$

can be verified using the method of partial fractions, Formula 19

$$\int \frac{\sqrt{a + bu}}{u} \, du = 2\sqrt{a + bu} + a \int \frac{1}{u\sqrt{a + bu}} \, du \qquad \text{Formula 19}$$

can be verified using integration by parts, and Formula 84

$$\int \frac{1}{1 + e^u} \, du = u - \ln(1 + e^u) + C \qquad \text{Formula 84}$$

can be verified using substitution. Note that the integrals in Appendix B are classified according to the form of the integrand. Several of the forms are listed below.

u^n	$(a + bu)$
$(a + bu + cu^2)$	$\sqrt{a + bu}$
$(a^2 \pm u^2)$	$\sqrt{u^2 \pm a^2}$
$\sqrt{a^2 - u^2}$	Trigonometric functions
Inverse trigonometric functions	Exponential functions
Logarithmic functions	

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploration

Use the tables of integrals in Appendix B and the substitution

$$u = \sqrt{x - 1}$$

to find the integral in Example 1. When you do this, you should obtain

$$\int \frac{dx}{x\sqrt{x - 1}} = \int \frac{2\,du}{u^2 + 1}.$$

Does this produce the same result as that obtained in Example 1?

GO DIGITAL

EXAMPLE 1 Integration by Tables

Find $\displaystyle\int \frac{dx}{x\sqrt{x - 1}}$.

Solution Because the expression inside the radical is linear, you should consider forms involving $\sqrt{a + bu}$.

$$\int \frac{1}{u\sqrt{a + bu}}\,du = \frac{2}{\sqrt{-a}} \arctan \sqrt{\frac{a + bu}{-a}} + C \qquad \text{Formula 17 } (a < 0)$$

Let $a = -1$, $b = 1$, and $u = x$. Then $du = dx$, and you can write

$$\int \frac{dx}{x\sqrt{x - 1}} = 2 \arctan \sqrt{x - 1} + C.$$

EXAMPLE 2 Integration by Tables

See LarsonCalculus.com for an interactive version of this type of example.

Find $\displaystyle\int x\sqrt{x^4 - 9}\,dx$.

Solution Because the radical has the form $\sqrt{u^2 - a^2}$, you should consider Formula 26.

$$\int \sqrt{u^2 - a^2}\,du = \frac{1}{2}\left(u\sqrt{u^2 - a^2} - a^2 \ln\left|u + \sqrt{u^2 - a^2}\right|\right) + C$$

Let $u = x^2$ and $a = 3$. Then $du = 2x\,dx$, and you have

$$\int x\sqrt{x^4 - 9}\,dx = \frac{1}{2}\int \sqrt{(x^2)^2 - 3^2}(2x)\,dx \qquad \text{Multiply and divide by 2.}$$

$$= \frac{1}{4}\left(x^2\sqrt{x^4 - 9} - 9 \ln\left|x^2 + \sqrt{x^4 - 9}\right|\right) + C.$$

EXAMPLE 3 Integration by Tables

Evaluate $\displaystyle\int_0^2 \frac{x}{1 + e^{-x^2}}\,dx$.

Solution Of the forms involving e^u, consider the formula

$$\int \frac{1}{1 + e^u}\,du = u - \ln(1 + e^u) + C. \qquad \text{Formula 84}$$

Let $u = -x^2$. Then $du = -2x\,dx$, and you have

$$\int \frac{x}{1 + e^{-x^2}}\,dx = -\frac{1}{2}\int \frac{-2x\,dx}{1 + e^{-x^2}} \qquad \text{Multiply and divide by } -2.$$

$$= -\frac{1}{2}\left[-x^2 - \ln\left(1 + e^{-x^2}\right)\right] + C \qquad \text{Apply Formula 84.}$$

$$= \frac{1}{2}\left[x^2 + \ln\left(1 + e^{-x^2}\right)\right] + C. \qquad \text{Simplify.}$$

So, the value of the definite integral is

$$\int_0^2 \frac{x}{1 + e^{-x^2}}\,dx = \frac{1}{2}\left[x^2 + \ln\left(1 + e^{-x^2}\right)\right]_0^2 = \frac{1}{2}[4 + \ln(1 + e^{-4}) - \ln 2] \approx 1.66.$$



Figure 8.20

Figure 8.20 shows the region whose area is represented by this integral.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Reduction Formulas

Several of the integrals in the integration tables have the form

$$\int f(x)\,dx = g(x) + \int h(x)\,dx.$$

Such integration formulas are called **reduction formulas** because they reduce a given integral to the sum of a function and a simpler integral.

EXAMPLE 4 Using a Reduction Formula

Find $\int x^3 \sin x\,dx$.

Solution Consider the three formulas listed below.

$$\int u \sin u\,du = \sin u - u\cos u + C \qquad \text{Formula 52}$$

$$\int u^n \sin u\,du = -u^n \cos u + n\int u^{n-1}\cos u\,du \qquad \text{Formula 54}$$

$$\int u^n \cos u\,du = u^n \sin u - n\int u^{n-1}\sin u\,du \qquad \text{Formula 55}$$

Using Formula 54, Formula 55, and then Formula 52 produces

$$\begin{aligned}\int x^3 \sin x\,dx &= -x^3\cos x + 3\int x^2\cos x\,dx \\ &= -x^3\cos x + 3\left(x^2\sin x - 2\int x\sin x\,dx\right) \\ &= -x^3\cos x + 3x^2\sin x + 6x\cos x - 6\sin x + C.\end{aligned}$$

REMARK Recall that integrals like the one in Example 4 can be evaluated using the tabular method shown in Example 8 of Section 8.2. Use this method to evaluate the integral in Example 4. Do you obtain the same result?

EXAMPLE 5 Using a Reduction Formula

Find $\int \frac{\sqrt{3-5x}}{2x}\,dx$.

Solution Consider the two formulas listed below.

$$\int \frac{1}{u\sqrt{a+bu}}\,du = \frac{1}{\sqrt{a}}\ln\left|\frac{\sqrt{a+bu}-\sqrt{a}}{\sqrt{a+bu}+\sqrt{a}}\right| + C \qquad \text{Formula 17 } (a>0)$$

$$\int \frac{\sqrt{a+bu}}{u}\,du = 2\sqrt{a+bu} + a\int \frac{1}{u\sqrt{a+bu}}\,du \qquad \text{Formula 19}$$

Using Formula 19, with $a = 3$, $b = -5$, and $u = x$, produces

$$\begin{aligned}\frac{1}{2}\int \frac{\sqrt{3-5x}}{x}\,dx &= \frac{1}{2}\left(2\sqrt{3-5x} + 3\int \frac{dx}{x\sqrt{3-5x}}\right) \\ &= \sqrt{3-5x} + \frac{3}{2}\int \frac{dx}{x\sqrt{3-5x}}.\end{aligned}$$

Using Formula 17, with $a = 3$, $b = -5$, and $u = x$, produces

$$\begin{aligned}\int \frac{\sqrt{3-5x}}{2x}\,dx &= \sqrt{3-5x} + \frac{3}{2}\left(\frac{1}{\sqrt{3}}\ln\left|\frac{\sqrt{3-5x}-\sqrt{3}}{\sqrt{3-5x}+\sqrt{3}}\right|\right) + C \\ &= \sqrt{3-5x} + \frac{\sqrt{3}}{2}\ln\left|\frac{\sqrt{3-5x}-\sqrt{3}}{\sqrt{3-5x}+\sqrt{3}}\right| + C.\end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Fractional Expressions of Sine and Cosine

EXAMPLE 6 **Integration by Tables**

Find $\int \frac{\sin 2x}{2 + \cos x}\,dx$.

Solution Use the trigonometric identity $\sin 2x = 2 \sin x \cos x$ and the Constant Multiple Rule to rewrite the integral.

$$\int \frac{\sin 2x}{2 + \cos x}\,dx = 2\int \frac{\sin x \cos x}{2 + \cos x}\,dx$$

A check of the forms involving $\sin u$ or $\cos u$ in Appendix B shows that those listed do not apply. So, you can consider forms involving $a + bu$. For example,

$$\int \frac{u}{a + bu}\,du = \frac{1}{b^2}(bu - a \ln|a + bu|) + C. \qquad \text{Formula 3}$$

Let $a = 2$, $b = 1$, and $u = \cos x$. Then $du = -\sin x\,dx$, and you have

$$\begin{aligned} 2\int \frac{\sin x \cos x}{2 + \cos x}\,dx &= -2\int \frac{(\cos x)(-\sin x\,dx)}{2 + \cos x} \qquad \text{Multiply and divide by } -1. \\ &= -2(\cos x - 2 \ln|2 + \cos x|) + C \\ &= -2 \cos x + 4 \ln|2 + \cos x| + C. \end{aligned}$$

Example 6 involves a fractional expression of $\sin x$ and $\cos x$. When you cannot find an integral of this form in the integration tables, try using the following special substitution to convert the trigonometric expression to a standard rational expression.

Substitution for Fractional Expressions of Sine and Cosine

For integrals involving fractional expressions of sine and cosine, the substitution

$$u = \frac{\sin x}{1 + \cos x} = \tan\frac{x}{2}$$

yields

$$\cos x = \frac{1 - u^2}{1 + u^2}, \quad \sin x = \frac{2u}{1 + u^2}, \quad \text{and} \quad dx = \frac{2\,du}{1 + u^2}.$$

Proof From the substitution for u, it follows that

$$u^2 = \frac{\sin^2 x}{(1 + \cos x)^2} = \frac{1 - \cos^2 x}{(1 + \cos x)^2} = \frac{1 - \cos x}{1 + \cos x}.$$

Solving for $\cos x$ produces

$$\cos x = \frac{1 - u^2}{1 + u^2}.$$

To find $\sin x$, write $u = (\sin x)/(1 + \cos x)$ as

$$\sin x = u(1 + \cos x) = u\left(1 + \frac{1 - u^2}{1 + u^2}\right) = \frac{2u}{1 + u^2}.$$

Finally, to find dx, consider $u = \tan(x/2)$. Then you have $\arctan u = x/2$ and

$$dx = \frac{2\,du}{1 + u^2}.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

8.7 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Which formula from the table of integrals would you use to find the integral below? Explain.

$$\int \frac{\sqrt{5 - 9x^2}}{x^2}\,dx$$

2. Describe what is meant by a reduction formula. Give an example.

Integration by Tables In Exercises 3 and 4, use a table of integrals with forms involving $a + bu$ to find the indefinite integral.

3. $\int \frac{x^2}{5 + x}\,dx$

4. $\int \frac{2}{x^2(4 + 3x)^2}\,dx$

Integration by Tables In Exercises 5 and 6, use a table of integrals with forms involving $\sqrt{a^2 - u^2}$ to find the indefinite integral.

5. $\int \frac{1}{x^2\sqrt{1 - x^2}}\,dx$

6. $\int \frac{\sqrt{64 - x^4}}{x}\,dx$

Integration by Tables In Exercises 7–10, use a table of integrals with forms involving the trigonometric functions to find the indefinite integral.

7. $\int \cos^4 3x\,dx$

8. $\int \frac{\sin^4 \sqrt{x}}{\sqrt{x}}\,dx$

9. $\int \frac{1}{\sqrt{x}(1 - \cos \sqrt{x})}\,dx$

10. $\int \frac{1}{1 + \cot 4x}\,dx$

Integration by Tables In Exercises 11 and 12, use a table of integrals with forms involving e^u to find the indefinite integral.

11. $\int \frac{1}{1 + e^{2x}}\,dx$

12. $\int e^{-4x} \sin 3x\,dx$

Integration by Tables In Exercises 13 and 14, use a table of integrals with forms involving $\ln u$ to find the indefinite integral.

13. $\int x^6 \ln x\,dx$

14. $\int (\ln x)^3\,dx$

Using Two Methods In Exercises 15–18, find the indefinite integral (a) using a table of integrals and (b) using the given method.

	Integral	Method
15.	$\int \ln \frac{x}{3}\,dx$	Integration by parts
16.	$\int \sin^2 3x\,dx$	Power-reducing formula
17.	$\int \frac{1}{x^2(x - 1)}\,dx$	Partial fractions
18.	$\int \frac{dx}{(4 + x^2)^{3/2}}$	Trigonometric substitution

Finding an Indefinite Integral In Exercises 19–40, use a table of integrals to find the indefinite integral.

19. $\int x \operatorname{arccsc}(x^2 + 1)\,dx$

20. $\int \operatorname{arccot}(4x - 5)\,dx$

21. $\int \frac{2}{x^3\sqrt{x^4 - 1}}\,dx$

22. $\int \frac{1}{x^2 + 4x + 8}\,dx$

23. $\int \frac{x}{(7 - 6x)^2}\,dx$

24. $\int \frac{\theta^3}{1 + \sin \theta^4}\,d\theta$

25. $\int e^x \arccos e^x\,dx$

26. $\int \frac{e^x}{1 - \tan e^x}\,dx$

27. $\int \frac{x}{1 - \sec x^2}\,dx$

28. $\int \frac{1}{t[1 + (\ln t)^2]}\,dt$

29. $\int \frac{\cos \theta}{3 + 2 \sin \theta + \sin^2 \theta}\,d\theta$

30. $\int x^2\sqrt{3 + 25x^2}\,dx$

31. $\int \frac{1}{x^2\sqrt{2 + 9x^2}}\,dx$

32. $\int \sqrt{x} \arctan x^{3/2}\,dx$

33. $\int \frac{\ln x}{x(3 + 2 \ln x)}\,dx$

34. $\int \frac{e^x}{(1 - e^{2x})^{3/2}}\,dx$

35. $\int \frac{x}{(x^2 - 6x + 10)^2}\,dx$

36. $\int \sqrt{\frac{5 - x}{5 + x}}\,dx$

37. $\int \frac{x}{\sqrt{x^4 - 6x^2 + 5}}\,dx$

38. $\int \frac{\cos x}{\sqrt{\sin^2 x + 1}}\,dx$

39. $\int \frac{e^{3x}}{(1 + e^x)^3}\,dx$

40. $\int \cot^4 \theta\,d\theta$

Evaluating a Definite Integral In Exercises 41–48, use a table of integrals to evaluate the definite integral.

41. $\int_0^1 \frac{x}{\sqrt{1 + x}}\,dx$

42. $\int_0^1 2x^3e^{x^2}\,dx$

43. $\int_1^2 x^4 \ln x\,dx$

44. $\int_0^{\pi/2} x \sin 2x\,dx$

45. $\int_{-\pi/2}^{\pi/2} \frac{\cos x}{1 + \sin^2 x}\,dx$

46. $\int_0^5 \frac{x^2}{(5 + 2x)^2}\,dx$

47. $\int_0^{\pi/2} t^3 \cos t\,dt$

48. $\int_0^3 \sqrt{x^2 + 16}\,dx$

Verifying a Formula In Exercises 49–54, verify the integration formula.

49. $\int \frac{u^2}{(a + bu)^2}\,du = \frac{1}{b^3}\left(bu - \frac{a^2}{a + bu} - 2a \ln|a + bu|\right) + C$

50. $\int \frac{u^n}{\sqrt{a + bu}}\,du = \frac{2}{(2n + 1)b}\left(u^n\sqrt{a + bu} - na\int \frac{u^{n-1}}{\sqrt{a + bu}}\,du\right)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

51. $\displaystyle\int \frac{1}{(u^2 \pm a^2)^{3/2}}\,du = \frac{\pm u}{a^2\sqrt{u^2 \pm a^2}} + C$

52. $\displaystyle\int u^n \cos u\,du = u^n \sin u - n\int u^{n-1} \sin u\,du$

53. $\displaystyle\int \arctan u\,du = u \arctan u - \ln\sqrt{1+u^2} + C$

54. $\displaystyle\int (\ln u)^n\,du = u(\ln u)^n - n\int (\ln u)^{n-1}\,du$

Finding or Evaluating an Integral **In Exercises 55–62, find or evaluate the integral.**

55. $\displaystyle\int \frac{1}{2 - 3\sin\theta}\,d\theta$

56. $\displaystyle\int \frac{\sin\theta}{1 + \cos^2\theta}\,d\theta$

57. $\displaystyle\int_0^{\pi/2} \frac{1}{1 + \sin\theta + \cos\theta}\,d\theta$

58. $\displaystyle\int_0^{\pi/2} \frac{1}{3 - 2\cos\theta}\,d\theta$

59. $\displaystyle\int \frac{\sin\theta}{3 - 2\cos\theta}\,d\theta$

60. $\displaystyle\int \frac{\cos\theta}{1 + \cos\theta}\,d\theta$

61. $\displaystyle\int \frac{\sin\sqrt{\theta}}{\sqrt{\theta}}\,d\theta$

62. $\displaystyle\int \frac{4}{\csc\theta - \cot\theta}\,d\theta$

Area **In Exercises 63 and 64, find the area of the region bounded by the graphs of the equations.**

63. $y = \dfrac{x}{\sqrt{x+3}}$, $y = 0$, $x = 6$

64. $y = \dfrac{x}{1 + e^{x^2}}$, $y = 0$, $x = 2$

Exploring Concepts

65. (a) Find $\int x^n \ln x\,dx$ for $n = 1$, 2, and 3. Describe any patterns you notice.

(b) Write a general rule for evaluating the integral in part (a) for an integer $n \geq 1$.

(c) Verify your rule from part (b) using integration by parts.

66. State the method or integration formula you would use to find the antiderivative. Explain why you chose that method or formula. Do not integrate.

(a) $\displaystyle\int \frac{e^x}{e^{2x}+1}\,dx$ (b) $\displaystyle\int \frac{e^x}{e^x+1}\,dx$ (c) $\displaystyle\int xe^{x^2}\,dx$

(d) $\displaystyle\int xe^x\,dx$ (e) $\displaystyle\int e^{2x}\sqrt{e^{2x}+1}\,dx$

67. **Work** A hydraulic cylinder on an industrial machine pushes a steel block a distance of x feet ($0 \leq x \leq 5$), where the variable force required is $F(x) = 2000xe^{-x}$ pounds. Find the work done in pushing the block the full 5 feet through the machine.

68. **Work** Repeat Exercise 67, using $F(x) = \dfrac{500x}{\sqrt{26 - x^2}}$ pounds.

69. **Population** A population is growing according to the logistic model

$$N = \frac{5000}{1 + e^{4.8 - 1.9t}}$$

where t is the time in days. Find the average population over the interval $[0, 2]$.

70. **HOW DO YOU SEE IT?** Use the graph of f' shown in the figure to answer the following.



(a) Approximate the slope of f at $x = -1$. Explain.

(b) Approximate any open intervals on which the graph of f is increasing and any open intervals on which it is decreasing. Explain.

71. **Volume** Consider the region bounded by the graphs of

$$y = x\sqrt{16 - x^2},\ y = 0,\ x = 0,\ \text{and}\ x = 4.$$

Find the volume of the solid generated by revolving the region about the y-axis.

72. **Building Design** The cross section of a precast concrete beam for a building is bounded by the graphs of the equations

$$x = \frac{2}{\sqrt{1+y^2}},\ x = \frac{-2}{\sqrt{1+y^2}},\ y = 0,\ \text{and}\ y = 3$$

where x and y are measured in feet. The length of the beam is 20 feet (see figure).



(a) Find the volume V and the weight W of the beam. Assume the concrete weighs 148 pounds per cubic foot.

(b) Find the centroid of a cross section of the beam.

PUTNAM EXAM CHALLENGE

73. Evaluate $\displaystyle\int_0^{\pi/2} \frac{dx}{1 + (\tan x)^{\sqrt{2}}}$.

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

8.8 Improper Integrals

GO DIGITAL

- Evaluate an improper integral that has an infinite limit of integration.
- Evaluate an improper integral that has an infinite discontinuity.

Improper Integrals with Infinite Limits of Integration

The definition of a definite integral

$$\int_a^b f(x)\,dx$$

requires that the interval $[a, b]$ be finite. Furthermore, the Fundamental Theorem of Calculus, by which you have been evaluating definite integrals, requires that f be continuous on $[a, b]$. In this section, you will study a procedure for evaluating integrals that do not satisfy these requirements—usually because either one or both of the limits of integration are infinite or because f has a finite number of infinite discontinuities in the interval $[a, b]$. Integrals that possess either property are **improper integrals.** Note that a function f is said to have an **infinite discontinuity** at c when, *from the right or left,*

$$\lim_{x\to c} f(x) = \infty \quad \text{or} \quad \lim_{x\to c} f(x) = -\infty.$$

To get an idea of how to evaluate an improper integral, consider the integral

$$\int_1^b \frac{dx}{x^2} = -\frac{1}{x}\Big]_1^b = -\frac{1}{b} + 1 = 1 - \frac{1}{b}$$

which can be interpreted as the area of the shaded region shown in Figure 8.21. Taking the limit as $b \to \infty$ produces

$$\int_1^\infty \frac{dx}{x^2} = \lim_{b\to\infty}\left(\int_1^b \frac{dx}{x^2}\right) = \lim_{b\to\infty}\left(1 - \frac{1}{b}\right) = 1.$$

This improper integral can be interpreted as the area of the *unbounded* region between the graph of $f(x) = 1/x^2$ and the x-axis (to the right of $x = 1$).



The unbounded region has an area of 1.
Figure 8.21

Definition of Improper Integrals with Infinite Integration Limits

1. If a function f is continuous on the interval $[a, \infty)$, then

$$\int_a^\infty f(x)\,dx = \lim_{b\to\infty}\int_a^b f(x)\,dx.$$

2. If a function f is continuous on the interval $(-\infty, b]$, then

$$\int_{-\infty}^b f(x)\,dx = \lim_{a\to-\infty}\int_a^b f(x)\,dx.$$

3. If a function f is continuous on the interval $(-\infty, \infty)$, then

$$\int_{-\infty}^\infty f(x)\,dx = \int_{-\infty}^c f(x)\,dx + \int_c^\infty f(x)\,dx$$

where c is any real number (see Exercise 107).

In the first two cases, the improper integral **converges** when the limit exists—otherwise, the improper integral **diverges**. In the third case, the improper integral on the left diverges when either of the improper integrals on the right diverges.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



This unbounded region has an infinite area.

Figure 8.22

EXAMPLE 1 An Improper Integral That Diverges

Evaluate $\int_1^b \frac{dx}{x}$.

Solution

$$\begin{aligned}\int_1^\infty \frac{dx}{x} &= \lim_{b\to\infty} \int_1^b \frac{dx}{x} && \text{Take limit as } b\to\infty.\\ &= \lim_{b\to\infty} \Big[\ln x\Big]_1^b && \text{Apply Log Rule.}\\ &= \lim_{b\to\infty} (\ln b - 0) && \text{Apply Fundamental Theorem of Calculus.}\\ &= \infty && \text{Evaluate limit.}\end{aligned}$$

The limit does not exist. So, you can conclude that the improper integral diverges. See Figure 8.22.

Compare the regions shown in Figures 8.21 and 8.22. They look similar, yet the region in Figure 8.21 has a finite area of 1 and the region in Figure 8.22 has an infinite area.

EXAMPLE 2 Improper Integrals That Converge

Evaluate each improper integral.

a. $\int_0^\infty e^{-x}\,dx$

b. $\int_0^\infty \frac{1}{x^2+1}\,dx$

Solution

a. $$\begin{aligned}\int_0^\infty e^{-x}\,dx &= \lim_{b\to\infty} \int_0^b e^{-x}\,dx\\ &= \lim_{b\to\infty} \Big[-e^{-x}\Big]_0^b\\ &= \lim_{b\to\infty} (-e^{-b}+1)\\ &= 1\end{aligned}$$

See Figure 8.23(a).

b. $$\begin{aligned}\int_0^\infty \frac{1}{x^2+1}\,dx &= \lim_{b\to\infty} \int_0^b \frac{1}{x^2+1}\,dx\\ &= \lim_{b\to\infty} \Big[\arctan x\Big]_0^b\\ &= \lim_{b\to\infty} \arctan b\\ &= \frac{\pi}{2}\end{aligned}$$

See Figure 8.23(b).



(a) The area of the unbounded region is 1.



(b) The area of the unbounded region is $\pi/2$.

Figure 8.23

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

In the next example, note how L'Hôpital's Rule can be used to evaluate an improper integral.

EXAMPLE 3 Using L'Hôpital's Rule with an Improper Integral

Evaluate $\int_1^\infty (1 - x)e^{-x}\,dx$.

Solution Use integration by parts, with $dv = e^{-x}\,dx$ and $u = (1 - x)$.

$$\begin{aligned}\int (1 - x)e^{-x}\,dx &= -e^{-x}(1 - x) - \int e^{-x}\,dx \\ &= -e^{-x} + xe^{-x} + e^{-x} + C \\ &= xe^{-x} + C\end{aligned}$$

Now, apply the definition of an improper integral.

$$\begin{aligned}\int_1^\infty (1 - x)e^{-x}\,dx &= \lim_{b\to\infty} \left[xe^{-x}\right]_1^b \\ &= \lim_{b\to\infty} \left(\frac{b}{e^b} - \frac{1}{e}\right) \\ &= \lim_{b\to\infty} \frac{b}{e^b} - \lim_{b\to\infty} \frac{1}{e}\end{aligned}$$



The area of the unbounded region is $|-1/e|$.
Figure 8.24

For the first limit, use L'Hôpital's Rule.

$$\lim_{b\to\infty} \frac{b}{e^b} = \lim_{b\to\infty} \frac{1}{e^b} = 0$$

So, you can conclude that

$$\begin{aligned}\int_1^\infty (1 - x)e^{-x}\,dx &= \lim_{b\to\infty} \frac{b}{e^b} - \lim_{b\to\infty} \frac{1}{e} \\ &= 0 - \frac{1}{e} \\ &= -\frac{1}{e}.\end{aligned}$$

See Figure 8.24.

EXAMPLE 4 Infinite Upper and Lower Limits of Integration

Evaluate $\int_{-\infty}^\infty \frac{e^x}{1 + e^{2x}}\,dx$.

Solution Note that the integrand is continuous on $(-\infty, \infty)$. To evaluate the integral, you can break it into two parts, choosing $c = 0$ as a convenient value.

$$\begin{aligned}\int_{-\infty}^\infty \frac{e^x}{1 + e^{2x}}\,dx &= \int_{-\infty}^0 \frac{e^x}{1 + e^{2x}}\,dx + \int_0^\infty \frac{e^x}{1 + e^{2x}}\,dx \\ &= \lim_{a\to-\infty} \left[\arctan e^x\right]_a^0 + \lim_{b\to\infty} \left[\arctan e^x\right]_0^b \\ &= \lim_{a\to-\infty} \left(\frac{\pi}{4} - \arctan e^a\right) + \lim_{b\to\infty} \left(\arctan e^b - \frac{\pi}{4}\right) \\ &= \frac{\pi}{4} - 0 + \frac{\pi}{2} - \frac{\pi}{4} \\ &= \frac{\pi}{2}\end{aligned}$$

See Figure 8.25.



The area of the unbounded region is $\pi/2$.
Figure 8.25

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 5 **Sending a Space Module into Orbit**

In Example 3 in Section 7.5, you found that it would require 10,000 mile-tons of work to propel a 15-ton space module to a height of 800 miles above Earth. How much work is required to propel the module an unlimited distance away from Earth's surface?

Solution At first you might think that an infinite amount of work would be required. But if this were the case, it would be impossible to send rockets into outer space. Because this has been done, the work required must be finite. You can determine the work in the following manner. Using the integral in Example 3, Section 7.5, replace the upper bound of 4800 miles by ∞ and write

$$W = \int_{4000}^{\infty} \frac{240{,}000{,}000}{x^2}\,dx$$

$$= \lim_{b\to\infty} \left[-\frac{240{,}000{,}000}{x} \right]_{4000}^{b} \qquad \text{Integrate.}$$

$$= \lim_{b\to\infty} \left(-\frac{240{,}000{,}000}{b} + \frac{240{,}000{,}000}{4000} \right)$$

$$= 60{,}000 \text{ mile-tons}$$

$$= 6.336 \times 10^{11} \text{ foot-pounds.} \qquad \text{1 mile} = 5280 \text{ feet; 1 ton} = 2000 \text{ pounds}$$

In SI units, using a conversion factor of

$$1 \text{ foot-pound} \approx 1.35582 \text{ joules}$$

the work done is $W \approx 8.59 \times 10^{11}$ joules. ■

Improper Integrals with Infinite Discontinuities

The second basic type of improper integral is one that has an infinite discontinuity *at or between* the limits of integration.

Definition of Improper Integrals with Infinite Discontinuities

1. If a function f is continuous on the interval $[a, b)$ and has an infinite discontinuity at b, then

$$\int_a^b f(x)\,dx = \lim_{c\to b^-} \int_a^c f(x)\,dx.$$

2. If a function f is continuous on the interval $(a, b]$ and has an infinite discontinuity at a, then

$$\int_a^b f(x)\,dx = \lim_{c\to a^+} \int_c^b f(x)\,dx.$$

3. If a function f is continuous on the interval $[a, b]$, except for some c in (a, b) at which f has an infinite discontinuity, then

$$\int_a^b f(x)\,dx = \int_a^c f(x)\,dx + \int_c^b f(x)\,dx.$$

In the first two cases, the improper integral **converges** when the limit exists—otherwise, the improper integral **diverges**. In the third case, the improper integral on the left diverges when either of the improper integrals on the right diverges.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 6 An Improper Integral with an Infinite Discontinuity

Evaluate $\int_0^1 \frac{dx}{\sqrt[3]{x}}$.

Solution The integrand has an infinite discontinuity at $x = 0$, as shown in the figure at the right. You can evaluate this integral as shown below.

$$\begin{aligned}\int_0^1 x^{-1/3}\,dx &= \lim_{b\to 0^+}\left[\frac{x^{2/3}}{2/3}\right]_b^1 \\ &= \lim_{b\to 0^+}\frac{3}{2}(1 - b^{2/3}) \\ &= \frac{3}{2}\end{aligned}$$



Infinite discontinuity at $x = 0$

EXAMPLE 7 An Improper Integral That Diverges

Evaluate $\int_0^2 \frac{dx}{x^3}$.

Solution Because the integrand has an infinite discontinuity at $x = 0$, you can write

$$\begin{aligned}\int_0^2 \frac{dx}{x^3} &= \lim_{b\to 0^+}\left[-\frac{1}{2x^2}\right]_b^2 \\ &= \lim_{b\to 0^+}\left(-\frac{1}{8} + \frac{1}{2b^2}\right) \\ &= \infty.\end{aligned}$$

So, you can conclude that the improper integral diverges.

EXAMPLE 8 An Improper Integral with an Interior Discontinuity

Evaluate $\int_{-1}^2 \frac{dx}{x^3}$.

Solution This integral is improper because the integrand has an infinite discontinuity at the interior point $x = 0$, as shown in Figure 8.26. So, you can write

$$\int_{-1}^2 \frac{dx}{x^3} = \int_{-1}^0 \frac{dx}{x^3} + \int_0^2 \frac{dx}{x^3}.$$

From Example 7, you know that the second integral diverges. So, the original improper integral also diverges. ■



The improper integral $\int_{-1}^2 \frac{dx}{x^3}$ diverges.

Figure 8.26

Remember to check for infinite discontinuities at interior points as well as at endpoints when determining whether an integral is improper. For instance, if you had not recognized that the integral in Example 8 was improper, you would have obtained the *incorrect* result

$$\int_{-1}^2 \frac{dx}{x^3} = \frac{-1}{2x^2}\Big]_{-1}^2 = -\frac{1}{8} + \frac{1}{2} = \frac{3}{8}.$$

Incorrect evaluation

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The integral in the next example is improper for *two* reasons. One limit of integration is infinite, and the integrand has an infinite discontinuity at the other limit of integration.

EXAMPLE 9 A Doubly Improper Integral

See LarsonCalculus.com for an interactive version of this type of example.

Evaluate $\int_0^\infty \frac{dx}{\sqrt{x}(x+1)}$.



The area of the unbounded region is π.
Figure 8.27

Solution To evaluate this integral, split it at a convenient point (say, $x = 1$) and write

$$\begin{aligned}\int_0^\infty \frac{dx}{\sqrt{x}(x+1)} &= \int_0^1 \frac{dx}{\sqrt{x}(x+1)} + \int_1^\infty \frac{dx}{\sqrt{x}(x+1)} \\ &= \lim_{b\to 0^+} \left[2\arctan\sqrt{x}\right]_b^1 + \lim_{c\to\infty}\left[2\arctan\sqrt{x}\right]_1^c \\ &= \lim_{b\to 0^+}\left(2\arctan 1 - 2\arctan\sqrt{b}\right) + \lim_{c\to\infty}\left(2\arctan\sqrt{c} - 2\arctan 1\right) \\ &= 2\left(\frac{\pi}{4}\right) - 0 + 2\left(\frac{\pi}{2}\right) - 2\left(\frac{\pi}{4}\right) \\ &= \pi.\end{aligned}$$

See Figure 8.27.

EXAMPLE 10 An Application Involving Arc Length

Use the formula for arc length to show that the circumference of the circle $x^2 + y^2 = 1$ is 2π.

Solution To simplify the work, consider the quarter circle given by $y = \sqrt{1 - x^2}$, where $0 \le x \le 1$. The function y is differentiable for any x in this interval except $x = 1$. So, the arc length of the quarter circle is given by the improper integral

$$\begin{aligned}s &= \int_0^1 \sqrt{1 + (y')^2}\,dx \\ &= \int_0^1 \sqrt{1 + \left(\frac{-x}{\sqrt{1-x^2}}\right)^2}\,dx \\ &= \int_0^1 \frac{dx}{\sqrt{1-x^2}}.\end{aligned}$$

This integral is improper because it has an infinite discontinuity at $x = 1$. So, you can write

$$\begin{aligned}s &= \int_0^1 \frac{dx}{\sqrt{1-x^2}} \\ &= \lim_{b\to 1^-}\left[\arcsin x\right]_0^b \\ &= \lim_{b\to 1^-}(\arcsin b - \arcsin 0) \\ &= \frac{\pi}{2} - 0 \\ &= \frac{\pi}{2}.\end{aligned}$$



The circumference of the circle is 2π.
Figure 8.28

Finally, multiplying by 4, you can conclude that the circumference of the circle is $4s = 2\pi$, as shown in Figure 8.28. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

This section concludes with a useful theorem describing the convergence or divergence of a common type of improper integral. The proof of this theorem is left as an exercise (see Exercise 49).

THEOREM 8.7 A Special Type of Improper Integral

$$\int_1^\infty \frac{dx}{x^p} = \begin{cases} \dfrac{1}{p-1}, & p > 1 \\ \text{diverges}, & p \le 1 \end{cases}$$

EXAMPLE 11 An Application Involving a Solid of Revolution

FOR FURTHER INFORMATION
For further investigation of solids that have finite volumes and infinite surface areas, see the article "Supersolids: Solids Having Finite Volume and Infinite Surfaces" by William P. Love in *Mathematics Teacher*. To view this article, go to *MathArticles.com*.

The solid formed by revolving (about the x-axis) the *unbounded* region lying between the graph of $f(x) = 1/x$ and the x-axis ($x \ge 1$) is called **Gabriel's Horn.** (See Figure 8.29.) Show that this solid has a finite volume and an infinite surface area.

Solution Using the disk method and Theorem 8.7, you can determine that the volume is

$$\begin{aligned} V &= \pi \int_1^\infty \left(\frac{1}{x}\right)^2 dx \qquad \text{Theorem 8.7, } p = 2 > 1 \\ &= \pi\left(\frac{1}{2-1}\right) \\ &= \pi. \end{aligned}$$

The surface area is given by

$$S = 2\pi \int_1^\infty f(x)\sqrt{1 + [f'(x)]^2}\, dx = 2\pi \int_1^\infty \frac{1}{x}\sqrt{1 + \frac{1}{x^4}}\, dx.$$

Because

$$\sqrt{1 + \frac{1}{x^4}} > 1$$

on the interval $[1, \infty)$, and the improper integral

$$\int_1^\infty \frac{1}{x}\, dx$$

diverges, you can conclude that the improper integral

$$\int_1^\infty \frac{1}{x}\sqrt{1 + \frac{1}{x^4}}\, dx$$

also diverges. (See Exercise 52.) So, the surface area is infinite.

FOR FURTHER INFORMATION
To learn about another function that has a finite volume and an infinite surface area, see the article "Gabriel's Wedding Cake" by Julian F. Fleron in *The College Mathematics Journal*. To view this article, go to *MathArticles.com*.



Gabriel's Horn has a finite volume and an infinite surface area.
Figure 8.29

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

8.8 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe three ways for an integral to be improper.
2. Explain what it means for an improper integral to converge.
3. Explain how to evaluate an improper integral that has an infinite limit of integration.
4. For what values of a is each integral improper? Explain.

(a) $\int_a^5 \frac{1}{x+2}\,dx$ (b) $\int_a^4 \frac{x}{3x-1}\,dx$

Determining Whether an Integral Is Improper In Exercises 5–12, decide whether the integral is improper. Explain your reasoning.

5. $\int_0^1 \frac{dx}{5x-3}$
6. $\int_1^2 \frac{dx}{x^3}$
7. $\int_0^1 \frac{2x-5}{x^2-5x+6}\,dx$
8. $\int_1^\infty \ln x^2\,dx$
9. $\int_0^2 e^{-x}\,dx$
10. $\int_0^\infty \cos x\,dx$
11. $\int_{-\infty}^\infty \frac{\sin x}{4+x^2}\,dx$
12. $\int_0^{\pi/4} \csc x\,dx$

Evaluating an Improper Integral In Exercises 13–16, explain why the integral is improper and determine whether it diverges or converges. Evaluate the integral if it converges.

13. $\int_0^4 \frac{1}{\sqrt{x}}\,dx$



14. $\int_3^4 \frac{1}{(x-3)^{3/2}}\,dx$



15. $\int_0^2 \frac{1}{(x-1)^2}\,dx$



16. $\int_{-\infty}^0 e^{3x}\,dx$



Evaluating an Improper Integral In Exercises 17–32, determine whether the improper integral diverges or converges. Evaluate the integral if it converges.

17. $\int_2^\infty \frac{1}{x^3}\,dx$
18. $\int_3^\infty \frac{1}{(x-1)^4}\,dx$
19. $\int_1^\infty \frac{3}{\sqrt[3]{x}}\,dx$
20. $\int_1^\infty \frac{4}{\sqrt[4]{x}}\,dx$
21. $\int_0^\infty e^{x/3}\,dx$
22. $\int_{-\infty}^0 xe^{-4x}\,dx$
23. $\int_0^\infty x^2e^{-x}\,dx$
24. $\int_0^\infty e^{-x}\cos x\,dx$
25. $\int_4^\infty \frac{1}{x(\ln x)^3}\,dx$
26. $\int_1^\infty \frac{\ln x}{x}\,dx$
27. $\int_{-\infty}^\infty \frac{4}{16+x^2}\,dx$
28. $\int_0^\infty \frac{x^3}{(x^2+1)^2}\,dx$
29. $\int_0^\infty \frac{1}{e^x+e^{-x}}\,dx$
30. $\int_0^\infty \frac{e^x}{1+e^x}\,dx$
31. $\int_0^\infty \cos \pi x\,dx$
32. $\int_0^\infty \sin \frac{x}{2}\,dx$

Evaluating an Improper Integral In Exercises 33–48, determine whether the improper integral diverges or converges. Evaluate the integral if it converges, and check your results with the results obtained by using the integration capabilities of a graphing utility.

33. $\int_0^1 \frac{1}{x^2}\,dx$
34. $\int_0^5 \frac{10}{x}\,dx$
35. $\int_0^2 \frac{1}{\sqrt[3]{x-1}}\,dx$
36. $\int_0^8 \frac{3}{\sqrt{8-x}}\,dx$
37. $\int_0^1 x\ln x\,dx$
38. $\int_0^e \ln x^2\,dx$
39. $\int_0^{\pi/2} \tan\theta\,d\theta$
40. $\int_0^{\pi/2} \sec\theta\,d\theta$
41. $\int_2^4 \frac{2}{x\sqrt{x^2-4}}\,dx$
42. $\int_3^6 \frac{1}{\sqrt{36-x^2}}\,dx$
43. $\int_3^5 \frac{1}{\sqrt{x^2-9}}\,dx$
44. $\int_0^5 \frac{1}{25-x^2}\,dx$
45. $\int_3^\infty \frac{1}{x\sqrt{x^2-9}}\,dx$
46. $\int_4^\infty \frac{\sqrt{x^2-16}}{x^2}\,dx$
47. $\int_0^\infty \frac{4}{\sqrt{x}(x+6)}\,dx$
48. $\int_1^\infty \frac{1}{x\ln x}\,dx$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding Values **In Exercises 49 and 50, determine all values of p for which the improper integral converges.**

49. $\int_1^\infty \frac{1}{x^p}\,dx$ **50.** $\int_0^1 \frac{1}{x^p}\,dx$

51. Mathematical Induction Use mathematical induction to verify that the following integral converges for any positive integer n.

$$\int_0^\infty x^n e^{-x}\,dx$$

52. Comparison Test for Improper Integrals In some cases, it is impossible to find the exact value of an improper integral, but it is important to determine whether the integral converges or diverges. Suppose the functions f and g are continuous and $0 \le g(x) \le f(x)$ on the interval $[a, \infty)$. It can be shown that if $\int_a^\infty f(x)\,dx$ converges, then $\int_a^\infty g(x)\,dx$ also converges, and if $\int_a^\infty g(x)\,dx$ diverges, then $\int_a^\infty f(x)\,dx$ also diverges. This is known as the Comparison Test for improper integrals.

(a) Use the Comparison Test to determine whether $\int_1^\infty e^{-x^2}\,dx$ converges or diverges. (*Hint:* Use the fact that $e^{-x^2} \le e^{-x}$ for $x \ge 1$.)

(b) Use the Comparison Test to determine whether $\int_1^\infty \frac{1}{x^5+1}\,dx$ converges or diverges. (*Hint:* Use the fact that $\frac{1}{x^5+1} \le \frac{1}{x^5}$ for $x \ge 1$.)

Convergence or Divergence **In Exercises 53–60, use the results of Exercises 49–52 to determine whether the improper integral converges or diverges.**

53. $\int_0^1 \frac{1}{\sqrt[6]{x}}\,dx$ **54.** $\int_0^1 \frac{1}{x^9}\,dx$

55. $\int_1^\infty \frac{1}{x^5}\,dx$ **56.** $\int_0^\infty x^4 e^{-x}\,dx$

57. $\int_1^\infty \frac{1}{x^2+5}\,dx$ **58.** $\int_2^\infty \frac{1}{\sqrt{x-1}}\,dx$

59. $\int_1^\infty \frac{1-\sin x}{x^2}\,dx$ **60.** $\int_0^\infty \frac{1}{e^x+x}\,dx$

Exploring Concepts

61. Explain why $\int_{-1}^1 \frac{1}{x^3}\,dx \ne 0$.

62. Consider the integral

$$\int_0^3 \frac{10}{x^2-2x}\,dx.$$

To determine the convergence or divergence of the integral, how many improper integrals must be analyzed? What must be true of each of these integrals for the given integral to converge?

Area **In Exercises 63–66, find the area of the unbounded shaded region.**

63. $y = -\frac{7}{(x-1)^3}$, $-\infty < x \le -1$



64. $y = -\ln x$



65. Witch of Agnesi: $y = \frac{1}{x^2+1}$



66. Witch of Agnesi: $y = \frac{8}{x^2+4}$



Area and Volume **In Exercises 67 and 68, consider the region satisfying the inequalities. (a) Find the area of the region. (b) Find the volume of the solid generated by revolving the region about the x-axis. (c) Find the volume of the solid generated by revolving the region about the y-axis.**

67. $y \le e^{-x}$, $y \ge 0$, $x \ge 0$

68. $y \le \frac{1}{x^2}$, $y \ge 0$, $x \ge 1$

69. Arc Length Find the arc length of the graph of $y = \sqrt{16-x^2}$ over the interval $[0, 4]$.

70. Surface Area Find the area of the surface formed by revolving the graph of $y = 2e^{-x}$ on the interval $[0, \infty)$ about the x-axis.

Propulsion **In Exercises 71 and 72, use the weight of the rocket to answer each question. (Use 4000 miles as the radius of Earth and do not consider the effect of air resistance.)**

(a) How much work is required to propel the rocket an unlimited distance away from Earth's surface?

(b) How far has the rocket traveled when half of the total work has occurred?

71. 5-ton rocket

72. 10-ton rocket

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Probability **A nonnegative function f is called a *probability density function* if**

$$\int_{-\infty}^{\infty} f(t)\,dt = 1.$$

The probability that x lies between a and b is given by

$$P(a \le x \le b) = \int_a^b f(t)\,dt.$$

In Exercises 73 and 74, (a) show that the nonnegative function is a probability density function, and (b) find $P(0 \le x \le 6)$.

73. $f(t) = \begin{cases} \frac{1}{9}e^{-t/9}, & t \ge 0 \\ 0, & t < 0 \end{cases}$

74. $f(t) = \begin{cases} \frac{5}{6}e^{-5t/6}, & t \ge 0 \\ 0, & t < 0 \end{cases}$

75. Normal Probability The mean height of American men between 20 and 29 years old is 69 inches, and the standard deviation is 3 inches. A 20- to 29-year-old man is chosen at random from the population. The probability that he is 6 feet tall or taller is

$$P(72 \le x < \infty) = \int_{72}^{\infty} \frac{1}{3\sqrt{2\pi}} e^{-(x-69)^2/18}\,dx.$$

(*Source: National Center for Health Statistics*)

(a) Use a graphing utility to graph the integrand. Use the graphing utility to convince yourself that the area between the x-axis and the integrand is 1.

(b) Use a graphing utility to approximate $P(72 \le x < \infty)$.

(c) Approximate $0.5 - P(69 \le x \le 72)$ using a graphing utility. Use the graph in part (a) to explain why this result is the same as the answer in part (b).

76. HOW DO YOU SEE IT? The graph shows the probability density function for a car brand that has a mean fuel efficiency of 26 miles per gallon and a standard deviation of 2.4 miles per gallon.



(a) Which is greater, the probability of choosing a car at random that gets between 26 and 28 miles per gallon or the probability of choosing a car at random that gets between 22 and 24 miles per gallon?

(b) Which is greater, the probability of choosing a car at random that gets between 20 and 22 miles per gallon or the probability of choosing a car at random that gets at least 30 miles per gallon?

Capitalized Cost **In Exercises 77 and 78, find the capitalized cost C of an asset (a) for $n = 5$ years, (b) for $n = 10$ years, and (c) forever. The capitalized cost is given by**

$$C = C_0 + \int_0^n c(t)e^{-rt}\,dt$$

where C_0 is the original investment, t is the time in years, r is the annual interest rate compounded continuously, and $c(t)$ is the annual cost of maintenance.

77. $C_0 = \$700{,}000$
$c(t) = \$25{,}000$
$r = 0.06$

78. $C_0 = \$700{,}000$
$c(t) = \$25{,}000(1 + 0.08t)$
$r = 0.06$

79. Electromagnetic Theory The magnetic potential P at a point on the axis of a circular coil is given by

$$P = \frac{2\pi NIr}{k} \int_c^{\infty} \frac{1}{(r^2 + x^2)^{3/2}}\,dx$$

where N, I, r, k, and c are constants. Find P.

80. Gravitational Force A "semi-infinite" uniform rod occupies the nonnegative x-axis. The rod has a linear density δ, which means that a segment of length dx has a mass of $\delta\,dx$. A particle of mass M is located at the point $(-a, 0)$. The gravitational force F that the rod exerts on the mass is given by

$$F = \int_0^{\infty} \frac{GM\delta}{(a + x)^2}\,dx$$

where G is the gravitational constant. Find F.

True or False? **In Exercises 81–86, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

81. If f is continuous on $[0, \infty)$ and $\lim_{x\to\infty} f(x) = 0$, then $\int_0^{\infty} f(x)\,dx$ converges.

82. If f is continuous on $[0, \infty)$ and $\int_0^{\infty} f(x)\,dx$ diverges, then $\lim_{x\to\infty} f(x) \ne 0$.

83. If f' is continuous on $[0, \infty)$ and $\lim_{x\to\infty} f(x) = 0$, then

$$\int_0^{\infty} f'(x)\,dx = -f(0).$$

84. If the graph of f is symmetric with respect to the origin or the y-axis, then $\int_0^{\infty} f(x)\,dx$ converges if and only if $\int_{-\infty}^{\infty} f(x)\,dx$ converges.

85. $\int_0^{\infty} e^{ax}\,dx$ converges for $a < 0$.

86. If $\lim_{x\to\infty} f(x) = L$, then $\int_0^{\infty} f(x)\,dx$ converges.

87. Comparing Integrals

(a) Show that $\int_{-\infty}^{\infty} \sin x\,dx$ diverges.

(b) Show that $\lim_{a\to\infty} \int_{-a}^{a} \sin x\,dx = 0$.

(c) What do parts (a) and (b) show about the definition of improper integrals?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

88. Exploration Consider the integral

$$\int_0^{\pi/2} \frac{4}{1 + (\tan x)^n}\,dx$$

where n is a positive integer.

(a) Is the integral improper? Explain.

(b) Use a graphing utility to graph the integrand for $n = 2$, 4, 8, and 12.

(c) Use the graphs to approximate the integral as $n \to \infty$.

(d) Use a graphing utility to evaluate the integral for the values of n in part (b). Make a conjecture about the value of the integral for any positive integer n. Compare your results with your answer in part (c).

89. Comparing Integrals Let f be continuous on the interval $[a, \infty)$. Show that if the improper integral $\int_a^\infty |f(x)|\,dx$ converges, then the improper integral $\int_a^\infty f(x)\,dx$ also converges.

90. Writing

(a) The improper integrals

$$\int_1^\infty \frac{1}{x}\,dx \quad \text{and} \quad \int_1^\infty \frac{1}{x^2}\,dx$$

diverge and converge, respectively. Describe the essential difference between the integrands that cause one integral to converge and the other to diverge.

(b) Use a graphing utility to graph the function $y = (\sin x)/x$ over the interval $(1, \infty)$. Use your knowledge of the definite integral to make an inference as to whether the integral

$$\int_1^\infty \frac{\sin x}{x}\,dx$$

converges. Give reasons for your answer.

(c) Use one application of integration by parts and the result of Exercise 89 to determine the divergence or convergence of the integral in part (b).

Laplace Transforms **Let $f(t)$ be a function defined for all positive values of t. The Laplace Transform of $f(t)$ is defined by**

$$F(s) = \int_0^\infty e^{-st} f(t)\,dt$$

when the improper integral exists. Laplace Transforms are used to solve differential equations. In Exercises 91–98, find the Laplace Transform of the function.

91. $f(t) = 1$

92. $f(t) = t$

93. $f(t) = t^2$

94. $f(t) = e^{at}$

95. $f(t) = \cos at$

96. $f(t) = \sin at$

97. $f(t) = \cosh at$

98. $f(t) = \sinh at$

99. The Gamma Function The gamma function $\Gamma(n)$ is defined by

$$\Gamma(n) = \int_0^\infty x^{n-1} e^{-x}\,dx, \quad n > 0.$$

(a) Find $\Gamma(1)$, $\Gamma(2)$, and $\Gamma(3)$.

(b) Use integration by parts to show that $\Gamma(n + 1) = n\Gamma(n)$.

(c) Write $\Gamma(n)$ using factorial notation where n is a positive integer.

100. Proof Prove that $I_n = \left(\frac{n-1}{n+2}\right) I_{n-1}$, where

$$I_n = \int_0^\infty \frac{x^{2n-1}}{(x^2 + 1)^{n+3}}\,dx, \quad n \geq 1.$$

Then evaluate each integral.

(a) $\displaystyle\int_0^\infty \frac{x}{(x^2 + 1)^4}\,dx$

(b) $\displaystyle\int_0^\infty \frac{x^3}{(x^2 + 1)^5}\,dx$

(c) $\displaystyle\int_0^\infty \frac{x^5}{(x^2 + 1)^6}\,dx$

101. Finding a Value For what value of c does the integral

$$\int_0^\infty \left(\frac{1}{\sqrt{x^2 + 1}} - \frac{c}{x + 1}\right) dx$$

converge? Evaluate the integral for this value of c.

102. Finding a Value For what value of c does the integral

$$\int_1^\infty \left(\frac{cx}{x^2 + 2} - \frac{1}{3x}\right) dx$$

converge? Evaluate the integral for this value of c.

103. Volume Find the volume of the solid generated by revolving the region bounded by the graph of f about the x-axis.

$$f(x) = \begin{cases} x \ln x, & 0 < x \leq 2 \\ 0, & x = 0 \end{cases}$$

104. Volume Find the volume of the solid generated by revolving the unbounded region lying between $y = -\ln x$ and the y-axis ($y \geq 0$) about the x-axis.

***u*-Substitution** **In Exercises 105 and 106, rewrite the improper integral as a proper integral using the given u-substitution. Then use the Trapezoidal Rule with $n = 5$ to approximate the integral.**

105. $\displaystyle\int_0^1 \frac{\sin x}{\sqrt{x}}\,dx, \quad u = \sqrt{x}$

106. $\displaystyle\int_0^1 \frac{\cos x}{\sqrt{1 - x}}\,dx, \quad u = \sqrt{1 - x}$

107. Rewriting an Integral Let $\int_{-\infty}^\infty f(x)\,dx$ be convergent, and let a and b be real numbers where $a \neq b$. Show that

$$\int_{-\infty}^a f(x)\,dx + \int_a^\infty f(x)\,dx = \int_{-\infty}^b f(x)\,dx + \int_b^\infty f(x)\,dx.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Review Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Exploring Concepts

You can apply the integration techniques that you learned in this chapter to a wide variety of functions. For instance, integration by parts is particularly useful for integrands involving products of algebraic and transcendental functions. It can even be useful for integrands consisting of single terms! This technique was developed from the product rule for derivatives.

Product Rule (derivatives)	**Integration by parts**
$\frac{d}{dx}[uv] = uv' + vu'$	$\int u\,dv = uv - \int v\,du$

It is important that you learn how to recognize when to use advanced integration techniques.

Technique	**Comment**
Trigonometric substitution	Use with the Power Rule to find trigonometric integrals.
Partial fractions	Decompose a rational function into simpler rational functions to which you can apply basic integration techniques.
Numerical integration	Use the Trapezoidal Rule or Simpson's Rule for integrals of elementary functions that do not have antiderivatives that are elementary functions.
Improper integrals	Use a limit to determine whether an improper integral converges or diverges.

1. Describe how you would find each integral using (i) integration by parts and (ii) substitution. Perform each integration. Are the results equivalent?

(a) $\int 2x\sqrt{2x-3}\,dx$

(b) $\int x\sqrt{9+x}\,dx$

2. Is letting $u = \cos x$ and $dv = x\,dx$ a good choice for finding

$$\int x\cos x\,dx?$$

Explain your reasoning.

3. Describe how you would integrate $\int \sin^m x\cos^n x\,dx$ for each condition.

(a) m is positive and odd.

(b) n is positive and odd.

(c) m and n are both positive and even.

4. Describe how you would integrate $\int \sec^m x\tan^n x\,dx$ for each condition.

(a) m is positive and even.

(b) n is positive and odd.

(c) n is positive and even, and there is no secant function.

(d) m is positive and odd, and there is no tangent function.

5. Describe geometrically how the Trapezoidal Rule is used to approximate a definite integral.

6. Explain why the evaluation of each integral shown below is incorrect. Use the integration capabilities of a graphing utility to attempt to evaluate the integral. Determine whether the utility gives the correct answer.

(a) $\int_{-1}^{1}\frac{1}{x^2}dx = -2$ ✗

(b) $\int_{0}^{\infty}\sec x\,dx = 0$ ✗

Using Basic Integration Rules

In Exercises 7–14, use the basic integration rules to find or evaluate the integral.

7. $\int x^2\sqrt{x^3-27}\,dx$

8. $\int xe^{5-x^2}\,dx$

9. $\int \csc^2\left(\frac{x+8}{4}\right)dx$

10. $\int \frac{x}{\sqrt[3]{4-x^2}}\,dx$

11. $\int_{1}^{e}\frac{\ln 2x}{x}\,dx$

12. $\int_{3/2}^{2} 2x\sqrt{2x-3}\,dx$

13. $\int \frac{100}{\sqrt{100-x^2}}\,dx$

14. $\int \frac{2x}{x-3}\,dx$

Using Integration by Parts

In Exercises 15–22, use integration by parts to find the indefinite integral.

15. $\int x\,e^{1-x}\,dx$

16. $\int x^2e^{x/2}\,dx$

17. $\int e^{2x}\sin 3x\,dx$

18. $\int x\sqrt{x-1}\,dx$

19. $\int x\sec^2 x\,dx$

20. $\int \ln\sqrt{x^2-4}\,dx$

21. $\int x\arcsin 2x\,dx$

22. $\int \arctan 2x\,dx$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding a Trigonometric Integral **In Exercises 23–32, find the trigonometric integral.**

23. $\int \sin x \cos^4 x \, dx$

24. $\int \sin^2 x \cos^3 x \, dx$

25. $\int \cos^3(\pi x - 1) \, dx$

26. $\int \sin^2 \frac{\pi x}{2} \, dx$

27. $\int \sec^4 \frac{x}{2} \, dx$

28. $\int \tan \theta \sec^4 \theta \, d\theta$

29. $\int x \tan^4 x^2 \, dx$

30. $\int \frac{\tan^2 x}{\sec^3 x} \, dx$

31. $\int \frac{1}{1 - \sin \theta} \, d\theta$

32. $\int (\cos 2\theta)(\sin \theta + \cos \theta)^2 \, d\theta$

Area **In Exercises 33 and 34, find the area of the given region.**

33. $y = \sin^4 x$



34. $y = \sin 3x \cos 2x$



Using Trigonometric Substitution **In Exercises 35–40, use trigonometric substitution to find or evaluate the integral.**

35. $\int \frac{-12}{x^2\sqrt{4 - x^2}} \, dx$

36. $\int \frac{\sqrt{x^2 - 9}}{x} \, dx$

37. $\int \frac{x^3}{\sqrt{4 + x^2}} \, dx$

38. $\int \sqrt{25 - 9x^2} \, dx$

39. $\int_0^1 \frac{6x^3}{\sqrt{16 + x^2}} \, dx$

40. $\int_3^4 x^3 \sqrt{x^2 - 9} \, dx$

Using Different Methods **In Exercises 41 and 42, find the indefinite integral using each method.**

41. $\int \frac{x^3}{\sqrt{4 + x^2}} \, dx$

(a) Trigonometric substitution

(b) Substitution: $u^2 = 4 + x^2$

(c) Integration by parts: $dv = \frac{x}{\sqrt{4 + x^2}} \, dx$

42. $\int x\sqrt{4 + x} \, dx$

(a) Trigonometric substitution

(b) Substitution: $u^2 = 4 + x$

(c) Substitution: $u = 4 + x$

(d) Integration by parts: $dv = \sqrt{4 + x} \, dx$

Using Partial Fractions **In Exercises 43–50, use partial fractions to find the indefinite integral.**

43. $\int \frac{x - 8}{x^2 - x - 6} \, dx$

44. $\int \frac{5x - 2}{x^2 - x} \, dx$

45. $\int \frac{x^2 + 2x}{x^3 - x^2 + x - 1} \, dx$

46. $\int \frac{4x - 2}{3(x - 1)^2} \, dx$

47. $\int \frac{x^2}{x^2 - 2x + 1} \, dx$

48. $\int \frac{x^3 + 4}{x^2 - 4x} \, dx$

49. $\int \frac{4e^x}{(e^{2x} - 1)(e^x + 3)} \, dx$

50. $\int \frac{\sec^2 \theta}{(\tan \theta)(\tan \theta - 1)} \, d\theta$

Using the Trapezoidal Rule and Simpson's Rule **In Exercises 51–54, approximate the definite integral using the Trapezoidal Rule and Simpson's Rule with $n = 4$. Compare these results with the approximation of the integral using a graphing utility.**

51. $\int_2^3 \frac{2}{1 + x^2} \, dx$

52. $\int_0^1 \frac{x^{3/2}}{3 - x^2} \, dx$

53. $\int_0^{\pi/2} \sqrt{x} \cos x \, dx$

54. $\int_0^{\pi} \sqrt{1 + \sin^2 x} \, dx$

Integration by Tables **In Exercises 55–62, use integration tables to find or evaluate the integral.**

55. $\int \frac{x}{(4 + 5x)^2} \, dx$

56. $\int \frac{x}{\sqrt{4 + 5x}} \, dx$

57. $\int_0^{\sqrt{\pi}/2} \frac{x}{1 + \sin x^2} \, dx$

58. $\int_0^1 \frac{x}{1 + e^{x^2}} \, dx$

59. $\int \frac{x}{x^2 + 4x + 8} \, dx$

60. $\int \frac{3}{2x\sqrt{9x^2 - 1}} \, dx, \quad x > \frac{1}{3}$

61. $\int \frac{1}{\sin \pi x \cos \pi x} \, dx$

62. $\int \frac{1}{1 + \tan \pi x} \, dx$

Finding an Indefinite Integral **In Exercises 63–70, find the indefinite integral using any method.**

63. $\int \theta \sin \theta \cos \theta \, d\theta$

64. $\int \frac{\csc \sqrt{2x}}{\sqrt{x}} \, dx$

65. $\int \frac{x^{1/4}}{1 + x^{1/2}} \, dx$

66. $\int \sqrt{1 + \sqrt{x}} \, dx$

67. $\int \sqrt{1 + \cos x} \, dx$

68. $\int \frac{3x^3 + 4x}{(x^2 + 1)^2} \, dx$

69. $\int \cos x \ln(\sin x) \, dx$

70. $\int (\sin \theta + \cos \theta)^2 \, d\theta$

Differential Equation **In Exercises 71–74, find the general solution of the differential equation using any method.**

71. $\frac{dy}{dx} = \frac{25}{x^2 - 25}$

72. $\frac{dy}{dx} = \frac{\sqrt{4 - x^2}}{2x}$

73. $y' = \ln(x^2 + x)$

74. $y' = \sqrt{1 - \cos \theta}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Evaluating a Definite Integral **In Exercises 75–80, evaluate the definite integral using any method. Use a graphing utility to verify your result.**

75. $\int_2^{\sqrt{5}} x(x^2 - 4)^{3/2}\,dx$

76. $\int_0^1 \frac{x}{(x-2)(x-4)}\,dx$

77. $\int_1^4 \frac{\ln x}{x}\,dx$

78. $\int_0^2 xe^{3x}\,dx$

79. $\int_2^{\pi} (x^2 - 4)\sin x\,dx$

80. $\int_0^5 \frac{x}{\sqrt{4+x}}\,dx$

Area **In Exercises 81 and 82, find the area of the given region using any method.**

81. $y = x\sqrt{3 - 2x}$

82. $y = \frac{1}{25 - x^2}$





Centroid **In Exercises 83 and 84, find the centroid of the region bounded by the graphs of the equations using any method.**

83. $y = \sqrt{1 - x^2}, \quad y = 0$

84. $(x - 1)^2 + y^2 = 1, \quad (x - 4)^2 + y^2 = 4$

Evaluating an Improper Integral **In Exercises 85–92, determine whether the improper integral diverges or converges. Evaluate the integral if it converges.**

85. $\int_0^{16} \frac{1}{\sqrt[4]{x}}\,dx$

86. $\int_0^2 \frac{7}{x - 2}\,dx$

87. $\int_1^{\infty} x^2 \ln x\,dx$

88. $\int_0^{\infty} \frac{e^{-1/x}}{x^2}\,dx$

89. $\int_1^{\infty} \frac{\ln x}{x^2}\,dx$

90. $\int_1^{\infty} \frac{1}{\sqrt[4]{x}}\,dx$

91. $\int_2^{\infty} \frac{1}{x\sqrt{x^2 - 4}}\,dx$

92. $\int_0^{\infty} \frac{2}{\sqrt{x}(x + 4)}\,dx$

93. **Present Value** The board of directors of a corporation is calculating the price to pay for a business that is forecast to yield a continuous flow of profit of \$500,000 per year. The money will earn a nominal rate of 5% per year compounded continuously. The present value of the business for t_0 years is

$$\text{Present value} = \int_0^{t_0} 500{,}000e^{-0.05t}\,dt.$$

(a) Find the present value of the business for 20 years.

(b) Find the present value of the business in perpetuity (forever).

94. **Volume** Find the volume of the solid generated by revolving the region bounded by the graphs of $y \le xe^{-x}$, $y \ge 0$, and $x \ge 0$ about the x-axis.

95. **Probability** The average lengths (from beak to tail) of different species of warblers in the eastern United States are approximately normally distributed with a mean of 12.9 centimeters and a standard deviation of 0.95 centimeter. The probability that a randomly selected warbler has a length between a and b centimeters is

$$P(a \le x \le b) = \frac{1}{0.95\sqrt{2\pi}} \int_a^b e^{-(x-12.9)^2/1.805}\,dx.$$

Use a graphing utility to approximate the probability that a randomly selected warbler has a length of (a) 13 centimeters or greater and (b) 15 centimeters or greater. (*Source: Peterson's Field Guide: Eastern Birds*)

Building on Concepts

96. (a) Sketch the semicircle given by $y = \sqrt{4 - x^2}$.

(b) Explain why

$$\int_{-2}^{2} \frac{2}{\sqrt{4 - x^2}}\,dx = \int_{-2}^{2} \sqrt{4 - x^2}\,dx$$

without evaluating either integral.

97. The **inner product** of two functions f and g on $[a, b]$ is given by

$$\langle f, g \rangle = \int_a^b f(x)g(x)\,dx.$$

Two distinct functions f and g are said to be **orthogonal** if $\langle f, g \rangle = 0$. Show that the set of functions below is orthogonal on $[-\pi, \pi]$.

$\{\sin x, \sin 2x, \sin 3x, \ldots, \cos x, \cos 2x, \cos 3x, \ldots\}$

98. The sum below is a *finite Fourier series*.

$$f(x) = \sum_{i=1}^{N} a_i \sin ix$$
$$= a_1 \sin x + a_2 \sin 2x + a_3 \sin 3x + \cdots + a_N \sin Nx$$

(a) Use Exercise 97 to show that the nth coefficient a_n is

$$a_n = \frac{1}{\pi}\int_{-\pi}^{\pi} f(x)\sin nx\,dx.$$

(b) Let $f(x) = x$. Find a_1, a_2, and a_3.

99. Consider the two integrals

$$\int \frac{e^x}{x}\,dx \quad \text{and} \quad \int \frac{1}{\ln x}\,dx.$$

Joseph Liouville proved that the first integral does not have an elementary antiderivative. Use this fact to prove that the second integral does not have an elementary antiderivative.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.S. Problem Solving

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

1. Wallis's Formulas

(a) Evaluate the integrals

$$\int_{-1}^{1} (1 - x^2)\,dx \quad \text{and} \quad \int_{-1}^{1} (1 - x^2)^2\,dx.$$

(b) Use Wallis's Formulas to prove that

$$\int_{-1}^{1} (1 - x^2)^n\,dx = \frac{2^{2n+1}(n!)^2}{(2n + 1)!}$$

for all positive integers n.

2. Proof

(a) Evaluate the integrals

$$\int_{0}^{1} \ln x\,dx \quad \text{and} \quad \int_{0}^{1} (\ln x)^2\,dx.$$

(b) Prove that

$$\int_{0}^{1} (\ln x)^n\,dx = (-1)^n\,n!$$

for all positive integers n.

3. Comparing Methods Let $I = \int_0^4 f(x)\,dx$, where f is shown in the figure. Let $L(n)$ and $R(n)$ represent the Riemann sums using the left-hand endpoints and right-hand endpoints of n subintervals of equal width. (Assume n is even.) Let $T(n)$ and $S(n)$ be the corresponding values of the Trapezoidal Rule and Simpson's Rule.



(a) For any n, list $L(n)$, $R(n)$, $T(n)$, and I in increasing order.

(b) Approximate $S(4)$.

4. Area Consider the problem of finding the area of the region bounded by the x-axis, the line $x = 4$, and the curve

$$y = \frac{x^2}{(x^2 + 9)^{3/2}}.$$

(a) Use a graphing utility to graph the region and approximate its area.

(b) Use an appropriate trigonometric substitution to find the exact area.

(c) Use the substitution $x = 3 \sinh u$ to find the exact area and verify that you obtain the same answer as in part (b).

5. Centroid Find the centroid of the region bounded by the x-axis and the curve $y = e^{-c^2x^2}$, where c is a positive constant (see figure).

$$\left(\textit{Hint: Show that } \int_0^\infty e^{-c^2x^2}\,dx = \frac{1}{c}\int_0^\infty e^{-x^2}\,dx.\right)$$



6. Proof Prove the following generalization of the Mean Value Theorem. If f is twice differentiable on the closed interval $[a, b]$, then

$$f(b) - f(a) = f'(a)(b - a) - \int_a^b f''(t)(t - b)\,dt.$$

7. Partial Fraction Decomposition Suppose the denominator of a rational function can be factored into distinct linear factors

$$D(x) = (x - c_1)(x - c_2) \cdot \cdot \cdot (x - c_n)$$

for a positive integer n and distinct real numbers c_1, $c_2, \ldots, c_n$. If N is a polynomial of degree less than n, show that

$$\frac{N(x)}{D(x)} = \frac{P_1}{x - c_1} + \frac{P_2}{x - c_2} + \cdots + \frac{P_n}{x - c_n}$$

where $P_k = N(c_k)/D'(c_k)$ for $k = 1, 2, \ldots, n$. Note that this is the partial fraction decomposition of $N(x)/D(x)$.

8. Partial Fraction Decomposition Use the result of Exercise 7 to find the partial fraction decomposition of

$$\frac{x^3 - 3x^2 + 1}{x^4 - 13x^2 + 12x}.$$

9. Rocket The velocity v (in feet per second) of a rocket whose initial mass (including fuel) is m is given by

$$v = -gt + u \ln \frac{m}{m - rt}, \quad t < \frac{m}{r}$$

where u is the expulsion speed of the fuel, r is the rate at which the fuel is consumed, and $g = 32$ feet per second per second is the acceleration due to gravity. Find the position equation for a rocket for which $m = 50{,}000$ pounds, $u = 12{,}000$ feet per second, and $r = 400$ pounds per second. What is the height of the rocket when $t = 100$ seconds? (Assume that the rocket was fired from ground level and is moving straight upward.)

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

9 Infinite Series

GO DIGITAL

9.1 Sequences
9.2 Series and Convergence
9.3 The Integral Test and *p*-Series
9.4 Comparisons of Series
9.5 Alternating Series
9.6 The Ratio and Root Tests
9.7 Taylor Polynomials and Approximations
9.8 Power Series
9.9 Representation of Functions by Power Series
9.10 Taylor and Maclaurin Series

CalcView®



CalcChat®


Chapter 9
Section 3
Exercise 43
GO
The area under the rectangle is greater than the area under the curve.
Because ∫ 1/√x dx = [2√x] = ∞, diverges, Σ 1/√n diverges.
PREV. 33 35 37 39 41 43 45 47 49 51 53 NEXT

9.1 Population *(Exercise 80, p. 598)*

9.2 Multiplier Effect *(Exercise 75, p. 606)*

left, Dmytro Balkhovitin/Shutterstock.com; right, SVongpra/Shutterstock.com
Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322
Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

9.1 Sequences

GO DIGITAL

- Write the terms of a sequence.
- Use a limit to determine whether a sequence converges or diverges.
- Find a pattern and write a formula for the *n*th term of a sequence.
- Use properties of monotonic sequences and bounded sequences.

Exploration

Finding Patterns Describe a pattern for each of the sequences listed below. Then use your description to write a formula for the nth term of each sequence. As n increases, do the terms appear to be approaching a limit? Explain your reasoning.

a. $1, \frac{1}{2}, \frac{1}{4}, \frac{1}{8}, \frac{1}{16}, \ldots$

b. $1, \frac{1}{2}, \frac{1}{6}, \frac{1}{24}, \frac{1}{120}, \ldots$

c. $10, \frac{10}{3}, \frac{10}{6}, \frac{10}{10}, \frac{10}{15}, \ldots$

d. $\frac{1}{4}, \frac{4}{9}, \frac{9}{16}, \frac{16}{25}, \frac{25}{36}, \ldots$

e. $\frac{3}{7}, \frac{5}{10}, \frac{7}{13}, \frac{9}{16}, \frac{11}{19}, \ldots$

Sequences

In mathematics, the word "sequence" is used in much the same way as it is in ordinary English. Saying that a collection of objects or events is *in sequence* usually means that the collection is ordered in such a way that it has an identified first member, second member, third member, and so on.

Mathematically, a **sequence** is defined as a function whose domain is the set of positive integers. Although a sequence is a function, it is common to represent sequences by subscript notation rather than by the standard function notation. For instance, in the sequence

$$\begin{array}{ccccccccc} 1, & 2, & 3, & 4, & \ldots, & n, & \ldots & & \text{Sequence} \\ \downarrow & \downarrow & \downarrow & \downarrow & \downarrow & \downarrow & \downarrow & & \\ a_1, & a_2, & a_3, & a_4, & \ldots, & a_n, & \ldots & & \end{array}$$

1 is mapped onto a_1, 2 is mapped onto a_2, and so on. The numbers

$$a_1, a_2, a_3, \ldots, a_n, \ldots$$

are the **terms** of the sequence. The number a_n is the ***n*th term** of the sequence, and the entire sequence is denoted by $\{a_n\}$. Occasionally, it is convenient to begin a sequence with a_0 so that the terms of the sequence become $a_0, a_1, a_2, a_3, \ldots, a_n, \ldots$ and the domain is the set of nonnegative integers.

EXAMPLE 1 Writing the Terms of a Sequence

a. The terms of the sequence $\{a_n\} = \{3 + (-1)^n\}$ are

$$\begin{array}{cccccc} 3 + (-1)^1, & 3 + (-1)^2, & 3 + (-1)^3, & 3 + (-1)^4, & \ldots \\ 2, & 4, & 2, & 4, & \ldots \end{array}$$

b. The terms of the sequence $\{b_n\} = \left\{\frac{n}{1 - 2n}\right\}$ are

$$\begin{array}{cccccc} \frac{1}{1 - 2 \cdot 1}, & \frac{2}{1 - 2 \cdot 2}, & \frac{3}{1 - 2 \cdot 3}, & \frac{4}{1 - 2 \cdot 4}, & \ldots \\ -1, & -\frac{2}{3}, & -\frac{3}{5}, & -\frac{4}{7}, & \ldots \end{array}$$

c. The terms of the sequence $\{c_n\} = \left\{\frac{n^2}{2^n - 1}\right\}$ are

$$\begin{array}{cccccc} \frac{1^2}{2^1 - 1}, & \frac{2^2}{2^2 - 1}, & \frac{3^2}{2^3 - 1}, & \frac{4^2}{2^4 - 1}, & \ldots \\ \frac{1}{1}, & \frac{4}{3}, & \frac{9}{7}, & \frac{16}{15}, & \ldots \end{array}$$

d. The terms of the **recursively defined** sequence $\{d_n\}$, where $d_1 = 25$ and $d_{n+1} = d_n - 5$, are

$$25, \quad 25 - 5 = 20, \quad 20 - 5 = 15, \quad 15 - 5 = 10, \ldots$$

REMARK Some sequences are defined recursively. To define a sequence recursively, you need to be given one or more of the first few terms. All other terms of the sequence are then defined using previous terms, as shown in Example 1(d).

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Limit of a Sequence

The primary focus of this chapter concerns sequences whose terms approach limiting values. Such sequences are said to **converge**. For instance, the sequence $\{1/2^n\}$

$$\frac{1}{2}, \frac{1}{4}, \frac{1}{8}, \frac{1}{16}, \frac{1}{32}, \ldots$$

converges to 0, as indicated in the next definition.



For $n > M$, the terms of the sequence all lie within ε units of L.
Figure 9.1

Definition of the Limit of a Sequence

Let L be a real number. The **limit** of a sequence $\{a_n\}$ is L, written as

$$\lim_{n\to\infty} a_n = L$$

if for each $\varepsilon > 0$, there exists $M > 0$ such that $|a_n - L| < \varepsilon$ whenever $n > M$. If the limit L of a sequence exists, then the sequence **converges** to L. If the limit of a sequence does not exist, then the sequence **diverges.**

Graphically, this definition says that eventually (for $n > M$ and $\varepsilon > 0$), the terms of a sequence that converges to L will lie within the band between the lines $y = L + \varepsilon$ and $y = L - \varepsilon$, as shown in Figure 9.1.

If a sequence $\{a_n\}$ agrees with a function f at every positive integer, and if $f(x)$ approaches a limit L as $x \to \infty$, then the sequence must converge to the same limit L.

REMARK The converse of Theorem 9.1 is not true (see Exercise 82).

THEOREM 9.1 Limit of a Sequence

Let L be a real number. Let f be a function of a real variable such that

$$\lim_{x\to\infty} f(x) = L.$$

If $\{a_n\}$ is a sequence such that $f(n) = a_n$ for every positive integer n, then

$$\lim_{n\to\infty} a_n = L.$$

EXAMPLE 2 Finding the Limit of a Sequence

Find the limit of the sequence whose nth term is $a_n = \left(1 + \frac{1}{n}\right)^n$.

Solution In Example 5, Section 5.6, you learned that

$$\lim_{x\to\infty} \left(1 + \frac{1}{x}\right)^x = e.$$

So, you can apply Theorem 9.1 to conclude that

$$\lim_{n\to\infty} a_n = \lim_{n\to\infty} \left(1 + \frac{1}{n}\right)^n = e.$$

There are different ways in which a sequence can fail to have a limit. One way is that the terms of the sequence increase without bound or decrease without bound. These cases are written symbolically, as shown below.

Terms increase without bound: $\lim_{n\to\infty} a_n = \infty$

Terms decrease without bound: $\lim_{n\to\infty} a_n = -\infty$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The properties of limits of sequences listed in the next theorem parallel those given for limits of functions of a real variable in Section 1.3.

THEOREM 9.2 Properties of Limits of Sequences

Let $\lim_{n\to\infty} a_n = L$ and $\lim_{n\to\infty} b_n = K$.

1. Scalar multiple: $\lim_{n\to\infty} (ca_n) = cL$, c is any real number.
2. Sum or difference: $\lim_{n\to\infty} (a_n \pm b_n) = L \pm K$
3. Product: $\lim_{n\to\infty} (a_n b_n) = LK$
4. Quotient: $\lim_{n\to\infty} \frac{a_n}{b_n} = \frac{L}{K}$, $b_n \neq 0$ and $K \neq 0$

Big Ideas of Calculus

To a great extent, mathematics is the study of patterns. In no other branch of mathematics is this more evident than in the study of sequences and series. The study of infinite sequences and series has been a part of calculus from its inception. The representation of a function by an infinite series was part of Newton's early development of calculus. For example, a series representation of $\ln x$ is

$$\sum_{n=0}^{\infty} (-1)^n \frac{(x-1)^{n+1}}{n+1}.$$

Today, sequences and series continue to be a vital part of mathematics. In fact, with computers, sequences and series have become even more useful. For example, in computing, a string is a finite sequence of characters from a finite set (such as an alphabet).

EXAMPLE 3 Determining Convergence or Divergence

See LarsonCalculus.com for an interactive version of this type of example.

a. Because the sequence $\{a_n\} = \{3 + (-1)^n\}$ has terms

$$2, 4, 2, 4, \ldots$$ See Example 1(a).

that alternate between 2 and 4, the limit

$$\lim_{n\to\infty} a_n$$

does not exist. So, the sequence diverges.

b. For $\{b_n\} = \left\{\frac{n}{1-2n}\right\}$, divide the numerator and denominator by n to obtain

$$\lim_{n\to\infty} \frac{n}{1-2n} = \lim_{n\to\infty} \frac{1}{(1/n)-2} = -\frac{1}{2}$$ See Example 1(b).

which implies that the sequence converges to $-\frac{1}{2}$.

EXAMPLE 4 Using L'Hôpital's Rule to Determine Convergence

Show that the sequence whose nth term is $a_n = \frac{n^2}{2^n - 1}$ converges.

Solution Consider the function of a real variable

$$f(x) = \frac{x^2}{2^x - 1}.$$

Applying L'Hôpital's Rule twice produces

$$\lim_{x\to\infty} \frac{x^2}{2^x - 1} = \lim_{x\to\infty} \frac{2x}{(\ln 2)2^x} = \lim_{x\to\infty} \frac{2}{(\ln 2)^2 2^x} = 0.$$

Because $f(n) = a_n$ for every positive integer n, you can apply Theorem 9.1 to conclude that

$$\lim_{n\to\infty} \frac{n^2}{2^n - 1} = 0.$$ See Example 1(c).

So, the sequence converges to 0. ■

TECHNOLOGY

Use a graphing utility to graph the function in Example 4. Notice that as x approaches infinity, the value of the function gets closer and closer to 0. If you have access to a graphing utility that can generate terms of a sequence, use it to calculate the first 20 terms of the sequence in Example 4. Then view the terms to observe numerically that the sequence converges to 0.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The symbol $n!$ (read "n factorial") is used to simplify some of the formulas developed in this chapter. Let n be a positive integer; then ***n* factorial** is defined as

$$n! = 1 \cdot 2 \cdot 3 \cdot 4 \cdot \cdots \cdot (n-1) \cdot n.$$

As a special case, **zero factorial** is defined as $0! = 1$. From this definition, you can conclude that $1! = 1$, $2! = 1 \cdot 2 = 2$, $3! = 1 \cdot 2 \cdot 3 = 6$, and so on. Factorials follow the same conventions for order of operations as exponents. That is, just as $2x^3$ and $(2x)^3$ imply different orders of operations, $2n!$ and $(2n)!$ imply the orders

$$2n! = 2(n!) = 2(1 \cdot 2 \cdot 3 \cdot 4 \cdot \cdots \cdot n)$$

and

$$(2n)! = 1 \cdot 2 \cdot 3 \cdot 4 \cdot \cdots \cdot n \cdot (n+1) \cdot \cdots \cdot 2n$$

respectively.

Another useful limit theorem that can be rewritten for sequences is the Squeeze Theorem from Section 1.3.

THEOREM 9.3 Squeeze Theorem for Sequences

If $\lim_{n\to\infty} a_n = L = \lim_{n\to\infty} b_n$ and there exists an integer N such that $a_n \le c_n \le b_n$ for all $n > N$, then $\lim_{n\to\infty} c_n = L$.

EXAMPLE 5 Using the Squeeze Theorem

Show that the sequence $\{c_n\} = \left\{(-1)^n \frac{1}{n!}\right\}$ converges, and find its limit.

Solution To apply the Squeeze Theorem, you must find two convergent sequences that can be related to $\{c_n\}$. Two possibilities are $a_n = -1/2^n$ and $b_n = 1/2^n$, both of which converge to 0. By comparing the term $n!$ with 2^n, you can see that

$$n! = 1 \cdot 2 \cdot 3 \cdot 4 \cdot 5 \cdot 6 \cdot \cdots \cdot n = 24 \cdot \underbrace{5 \cdot 6 \cdot \cdots \cdot n}_{n-4 \text{ factors}} \qquad (n \ge 4)$$

and

$$2^n = 2 \cdot 2 \cdot 2 \cdot 2 \cdot 2 \cdot 2 \cdot \cdots \cdot 2 = 16 \cdot \underbrace{2 \cdot 2 \cdot \cdots \cdot 2}_{n-4 \text{ factors}}. \qquad (n \ge 4)$$

For $n \ge 4$, this implies that $2^n < n!$, and you have

$$\frac{-1}{2^n} \le (-1)^n \frac{1}{n!} \le \frac{1}{2^n}, \quad n \ge 4$$

as shown in Figure 9.2. So, by the Squeeze Theorem, it follows that

$$\lim_{n\to\infty} (-1)^n \frac{1}{n!} = 0.$$



For $n \ge 4$, $(-1)^n/n!$ is squeezed between $-1/2^n$ and $1/2^n$.

Figure 9.2

Example 5 suggests something about the rate at which $n!$ increases as $n \to \infty$. As Figure 9.2 suggests, both $1/2^n$ and $1/n!$ approach 0 as $n \to \infty$. Yet $1/n!$ approaches 0 so much faster than $1/2^n$ does that

$$\lim_{n\to\infty} \frac{1/n!}{1/2^n} = \lim_{n\to\infty} \frac{2^n}{n!} = 0.$$

In fact, it can be shown that for any fixed number k, $\lim_{n\to\infty} (k^n/n!) = 0$. This means that *the factorial function grows faster than any exponential function.*

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

In Example 5, the sequence $\{c_n\}$ has both positive and negative terms. For this sequence, it happens that the sequence of absolute values, $\{|c_n|\}$, also converges to 0. You can show this by the Squeeze Theorem using the inequality

$$0 \le \frac{1}{n!} \le \frac{1}{2^n}, \quad n \ge 4.$$

In such cases, it is often convenient to consider the sequence of absolute values and then apply Theorem 9.4, which states that if the absolute value sequence converges to 0, then the original signed sequence also converges to 0.

THEOREM 9.4 Absolute Value Theorem

For the sequence $\{a_n\}$, if

$$\lim_{n\to\infty} |a_n| = 0 \quad \text{then} \quad \lim_{n\to\infty} a_n = 0.$$

Proof Consider the two sequences $\{|a_n|\}$ and $\{-|a_n|\}$. Because both of these sequences converge to 0 and

$$-|a_n| \le a_n \le |a_n|$$

you can use the Squeeze Theorem to conclude that $\{a_n\}$ converges to 0. ∎

Pattern Recognition for Sequences

Sometimes the terms of a sequence are generated by some rule that does not explicitly identify the nth term of the sequence. In such cases, you may be required to discover a *pattern* in the sequence and to describe the nth term. Once the nth term has been specified, you can investigate the convergence or divergence of the sequence.

EXAMPLE 6 Finding the *n*th Term of a Sequence

Find a sequence $\{a_n\}$ whose first five terms are

$$\frac{1}{2}, \frac{3}{4}, \frac{5}{8}, \frac{7}{16}, \frac{9}{32}, \ldots$$

and then determine whether the sequence converges or diverges.

Solution First, note that the numerators form the sequence of positive odd integers, and the denominators are successive powers of 2. Comparing a_n with n produces the pattern below.

$$\frac{1}{2^1}, \frac{3}{2^2}, \frac{5}{2^3}, \frac{7}{2^4}, \frac{9}{2^5}, \ldots, \frac{2n-1}{2^n}, \ldots$$

Consider the function of a real variable $f(x) = (2x - 1)/2^x$. Applying L'Hôpital's Rule produces

$$\lim_{x\to\infty} \frac{2x-1}{2^x} = \lim_{x\to\infty} \frac{2}{2^x(\ln x)} = 0.$$

Next, apply Theorem 9.1 to conclude that

$$\lim_{n\to\infty} \frac{2n-1}{2^n} = 0.$$

So, the sequence $a_n = (2n - 1)/2^n$ converges to 0. ∎

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Without a specific rule for generating the terms of a sequence or some knowledge of the context in which the terms of the sequence are obtained, it is not possible to determine the convergence or divergence of the sequence merely from its first several terms. For instance, although the first three terms of the four sequences shown below are identical, the first two sequences converge to 0, the third sequence converges to $\frac{1}{9}$, and the fourth sequence diverges.

$$\{a_n\}: \frac{1}{2}, \frac{1}{4}, \frac{1}{8}, \frac{1}{16}, \ldots, \frac{1}{2n}, \ldots$$

$$\{b_n\}: \frac{1}{2}, \frac{1}{4}, \frac{1}{8}, \frac{1}{15}, \ldots, \frac{6}{(n+1)(n^2-n+6)}, \ldots$$

$$\{c_n\}: \frac{1}{2}, \frac{1}{4}, \frac{1}{8}, \frac{7}{62}, \ldots, \frac{n^2-3n+3}{9n^2-25n+18}, \ldots$$

$$\{d_n\}: \frac{1}{2}, \frac{1}{4}, \frac{1}{8}, 0, \ldots, \frac{-n(n+1)(n-4)}{6(n^2+3n-2)}, \ldots$$

The process of determining an nth term from the pattern observed in the first several terms of a sequence is an example of *inductive reasoning*.

EXAMPLE 7 Finding the nth Term of a Sequence

Determine the nth term for a sequence whose first five terms are

$$-\frac{2}{1}, \frac{8}{2}, -\frac{26}{6}, \frac{80}{24}, -\frac{242}{120}, \ldots$$

and then decide whether the sequence converges or diverges.

Solution Note that the numerators are 1 less than 3^n.

$$3^1 - 1 = 2 \quad 3^2 - 1 = 8 \quad 3^3 - 1 = 26 \quad 3^4 - 1 = 80 \quad 3^5 - 1 = 242$$

So, you can reason that the numerators are given by the rule

$$3^n - 1.$$

Factoring the denominators produces

$$1 = 1 \qquad \text{Factor denominator of 1st term.}$$
$$2 = 1 \cdot 2 \qquad \text{Factor denominator of 2nd term.}$$
$$6 = 1 \cdot 2 \cdot 3 \qquad \text{Factor denominator of 3rd term.}$$
$$24 = 1 \cdot 2 \cdot 3 \cdot 4 \qquad \text{Factor denominator of 4th term.}$$

and

$$120 = 1 \cdot 2 \cdot 3 \cdot 4 \cdot 5. \qquad \text{Factor denominator of 5th term.}$$

This suggests that the denominators are represented by $n!$. Finally, because the signs alternate, you can write the nth term as

$$a_n = (-1)^n \left(\frac{3^n - 1}{n!} \right). \qquad n\text{th term}$$

From the discussion about the growth of $n!$ after Example 5 on page 591, it follows that

$$\lim_{n \to \infty} |a_n| = \lim_{n \to \infty} \frac{3^n - 1}{n!} = 0.$$

Applying Theorem 9.4, you can conclude that

$$\lim_{n \to \infty} a_n = 0.$$

So, the sequence $\{a_n\}$ converges to 0. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Monotonic Sequences and Bounded Sequences

So far, you have determined the convergence of a sequence by finding its limit. Even when you cannot determine the limit of a particular sequence, it still may be useful to know whether the sequence converges. Theorem 9.5 (on the next page) provides a test for convergence of sequences without determining the limit. First, some preliminary definitions are given.

Definition of Monotonic Sequence

A sequence $\{a_n\}$ is **monotonic** when its terms are nondecreasing

$$a_1 \leq a_2 \leq a_3 \leq \cdots \leq a_n \leq \cdots$$

or when its terms are nonincreasing

$$a_1 \geq a_2 \geq a_3 \geq \cdots \geq a_n \geq \cdots.$$

EXAMPLE 8 Determining Whether a Sequence Is Monotonic

Determine whether each sequence having the given nth term is monotonic.

a. $a_n = 3 + (-1)^n$ **b.** $b_n = \dfrac{2n}{1+n}$ **c.** $c_n = \dfrac{n^2}{2^n - 1}$

Solution

a. This sequence alternates between 2 and 4. So, the sequence is not monotonic. [See Figure 9.3(a).]

b. This sequence is monotonic because each successive term is greater than its predecessor. To see this, compare the terms b_n and b_{n+1}. [Note that, because n is positive, you can multiply each side of the inequality by $(1 + n)$ and $(2 + n)$ without reversing the inequality sign.]

$$b_n = \frac{2n}{1+n} \overset{?}{<} \frac{2(n+1)}{1+(n+1)} = b_{n+1} \qquad \text{Write inequality relating } b_n \text{ and } b_{n+1}.$$

$$2n(2+n) \overset{?}{<} (1+n)(2n+2) \qquad \text{Multiply each side by } (1+n)(2+n).$$

$$4n + 2n^2 \overset{?}{<} 2 + 4n + 2n^2 \qquad \text{Expand each side.}$$

$$0 < 2 \qquad \text{Subtract } (4n + 2n^2) \text{ from each side.}$$

Starting with the final inequality, which is valid, you can reverse the steps to conclude that the original inequality is also valid. [See Figure 9.3(b).]

c. This sequence is not monotonic because the second term is greater than the first and third terms. [See Figure 9.3(c).]

$$c_2 = \frac{4}{3} > 1 = c_1 \quad \text{and} \quad c_2 = \frac{4}{3} > \frac{9}{7} = c_3 \qquad c_2 > c_1 \text{ and } c_2 > c_3$$

(Note that when you drop the first term, the remaining sequence $c_2, c_3, c_4, \ldots$ is monotonic.)

In Example 8(b), another way to show that the sequence is monotonic is to note that the derivative of the corresponding differentiable function

$$f(x) = \frac{2x}{1+x}$$

is positive for all x. This implies that f is increasing, which in turn implies that $\{b_n\}$ is increasing.



(a) Not monotonic



(b) Monotonic



(c) Not monotonic

Figure 9.3

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Definition of Bounded Sequence

1. A sequence $\{a_n\}$ is **bounded above** when there is a real number M such that $a_n \leq M$ for all n. The number M is called an **upper bound** of the sequence.
2. A sequence $\{a_n\}$ is **bounded below** when there is a real number N such that $N \leq a_n$ for all n. The number N is called a **lower bound** of the sequence.
3. A sequence $\{a_n\}$ is **bounded** when it is bounded above and bounded below.

Note that all three sequences in Example 8 (and shown in Figure 9.3) are bounded. To see this, note that

$$2 \leq a_n \leq 4, \quad 1 \leq b_n \leq 2, \quad \text{and} \quad 0 \leq c_n \leq \frac{4}{3}.$$

One important property of the real numbers is that they are **complete.** Informally, this means that there are no holes or gaps on the real number line. (The set of rational numbers does not have the completeness property.) The completeness axiom for real numbers can be used to conclude that if a sequence has an upper bound, then it must have a **least upper bound** (an upper bound that is less than all other upper bounds for the sequence). For example, the least upper bound of the sequence $\{a_n\} = \{n/(n+1)\}$,

$$\frac{1}{2}, \frac{2}{3}, \frac{3}{4}, \frac{4}{5}, \ldots, \frac{n}{n+1}, \ldots$$

is 1. The completeness axiom is used in the proof of Theorem 9.5.

THEOREM 9.5 Bounded Monotonic Sequences

If a sequence $\{a_n\}$ is bounded and monotonic, then it converges.



Every bounded, nondecreasing sequence converges.
Figure 9.4

Proof Assume that the sequence is nondecreasing, as shown in Figure 9.4. For simplicity, also assume that each term in the sequence is positive. Because the sequence is bounded, there must exist an upper bound M such that

$$a_1 \leq a_2 \leq a_3 \leq \cdots \leq a_n \leq \cdots \leq M.$$

From the completeness axiom, it follows that there is a least upper bound L such that

$$a_1 \leq a_2 \leq a_3 \leq \cdots \leq a_n \leq \cdots \leq L.$$

For $\varepsilon > 0$, it follows that $L - \varepsilon < L$, and so $L - \varepsilon$ cannot be an upper bound for the sequence. Consequently, at least one term of $\{a_n\}$ is greater than $L - \varepsilon$. That is, $L - \varepsilon < a_N$ for some positive integer N. Because the terms of $\{a_n\}$ are nondecreasing, it follows that $a_N \leq a_n$ for $n > N$. You now know that $L - \varepsilon < a_N \leq a_n \leq L < L + \varepsilon$, for every $n > N$. It follows that $|a_n - L| < \varepsilon$ for $n > N$, which by definition means that $\{a_n\}$ converges to L. The proof for a nonincreasing sequence is similar (see Exercise 89). ■

EXAMPLE 9 Bounded and Monotonic Sequences

a. The sequence $\{a_n\} = \{1/n\}$ is both bounded and monotonic. So, by Theorem 9.5, it must converge.

b. The divergent sequence $\{b_n\} = \{n^2/(n+1)\}$ is monotonic but not bounded. (It is bounded below.)

c. The divergent sequence $\{c_n\} = \{(-1)^n\}$ is bounded but not monotonic. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

9.1 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain what it means for a sequence to be defined recursively.
2. Find the value of L.
$\lim_{n\to\infty} a_n = L, \quad \lim_{n\to\infty} b_n = 8, \quad \text{and} \quad \lim_{n\to\infty} (a_n b_n) = 24$
3. Determine which function grows faster as n approaches infinity. Explain.
$f(n) = 7^n \qquad g(n) = (n-1)!$
4. A sequence $\{a_n\}$ is bounded below and nonincreasing. Does $\{a_n\}$ converge or diverge? Use a graph to support your conclusion.

Writing the Terms of a Sequence In Exercises 5–10, write the first five terms of the sequence with the given nth term.

5. $a_n = 3^n$
6. $a_n = \left(-\frac{2}{5}\right)^n$
7. $a_n = \sin\frac{n\pi}{2}$
8. $a_n = \frac{3n}{n+4}$
9. $a_n = (-1)^{n+1}\left(\frac{2}{n}\right)$
10. $a_n = 2 + \frac{2}{n} - \frac{1}{n^2}$

Writing the Terms of a Sequence In Exercises 11 and 12, write the first five terms of the recursively defined sequence.

11. $a_1 = 3, a_{k+1} = 2(a_k - 1)$
12. $a_1 = 6, a_{k+1} = \frac{1}{3}a_k^2$

Matching In Exercises 13–16, match the sequence with the given nth term with its graph. [The graphs are labeled (a), (b), (c), and (d).]

(a)



(b)



(c)



(d)



13. $a_n = \frac{10}{n+1}$
14. $a_n = \frac{10n}{n+1}$
15. $a_n = (-1)^n$
16. $a_n = \frac{(-1)^n}{n}$

Simplifying Factorials In Exercises 17–20, simplify the ratio of factorials.

17. $\frac{(n+1)!}{(n-1)!}$
18. $\frac{(3n+1)!}{(3n)!}$
19. $\frac{n!}{(n-3)!}$
20. $\frac{(4n+1)!}{(4n+3)!}$

Finding the Limit of a Sequence In Exercises 21–24, find the limit of the sequence with the given nth term.

21. $a_n = \frac{n+1}{n}$
22. $a_n = 6 + \frac{2}{n^2}$
23. $a_n = \frac{2n}{\sqrt{n^2+1}}$
24. $a_n = \cos\frac{2}{n}$

Finding the Limit of a Sequence In Exercises 25–28, use a graphing utility to graph the first 10 terms of the sequence with the given nth term. Use the graph to make an inference about the convergence or divergence of the sequence. Verify your inference analytically and, if the sequence converges, find its limit.

25. $a_n = \frac{4n+1}{n}$
26. $a_n = \frac{1}{n^{3/2}}$
27. $a_n = \sin\frac{n\pi}{2}$
28. $a_n = 2 - \frac{1}{4^n}$

Determining Convergence or Divergence In Exercises 29–44, determine the convergence or divergence of the sequence with the given nth term. If the sequence converges, find its limit.

29. $a_n = \frac{5}{n+2}$
30. $a_n = n - \frac{1}{n!}$
31. $a_n = (-1)^n\left(\frac{n}{n+1}\right)$
32. $a_n = \frac{1+(-1)^n}{n^2}$
33. $a_n = \frac{3n+\sqrt{n}}{4n}$
34. $a_n = \frac{\sqrt[3]{n}}{\sqrt[3]{n}+1}$
35. $a_n = \frac{\ln(n^3)}{2n}$
36. $a_n = \frac{e^n}{4^n}$
37. $a_n = \frac{(n+1)!}{n!}$
38. $a_n = \frac{(n-2)!}{n!}$
39. $a_n = \frac{n^p}{e^n}, \; p > 0$
40. $a_n = n\sin\frac{1}{n}$
41. $a_n = 2^{1/n}$
42. $a_n = -3^{-n}$
43. $a_n = \frac{\sin n}{n}$
44. $a_n = \frac{\cos 2n}{3^n}$

Finding the nth Term of a Sequence In Exercises 45–52, find the nth term, a_n, of the sequence and then determine whether the sequence you have chosen converges or diverges. (There is more than one correct answer.)

45. $2, 8, 14, 20, \ldots$
46. $1, \frac{1}{2}, \frac{1}{6}, \frac{1}{24}, \frac{1}{120}, \ldots$
47. $-2, 1, 6, 13, 22, \ldots$
48. $1, -\frac{1}{4}, \frac{1}{9}, -\frac{1}{16}, \ldots$
49. $\frac{2}{3}, \frac{3}{4}, \frac{4}{5}, \frac{5}{6}, \ldots$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

50. 2, 24, 720, 40,320, 3,628,800, . . .

51. $2, 1 + \frac{1}{2}, 1 + \frac{1}{3}, 1 + \frac{1}{4}, 1 + \frac{1}{5}, \ldots$

52. $\frac{1}{2 \cdot 3}, \frac{2}{3 \cdot 4}, \frac{3}{4 \cdot 5}, \frac{4}{5 \cdot 6}, \ldots$

Monotonic and Bounded Sequences **In Exercises 53–60, determine whether the sequence with the given *n*th term is monotonic and whether it is bounded. Use a graphing utility to confirm your results.**

53. $a_n = 4 - \frac{1}{n}$

54. $a_n = \frac{3n}{n + 2}$

55. $a_n = ne^{-n/2}$

56. $a_n = \left(-\frac{2}{3}\right)^n$

57. $a_n = \left(\frac{2}{3}\right)^n$

58. $a_n = \left(\frac{3}{2}\right)^n$

59. $a_n = \sin\frac{n\pi}{6}$

60. $a_n = \frac{\cos n}{n}$

Using a Theorem **In Exercises 61–64, (a) use Theorem 9.5 to show that the sequence with the given *n*th term converges and (b) use a graphing utility to graph the first 10 terms of the sequence and find its limit.**

61. $a_n = 7 + \frac{1}{n}$

62. $a_n = 5 - \frac{2}{n}$

63. $a_n = \frac{1}{3}\left(1 - \frac{1}{3^n}\right)$

64. $a_n = 2 + \frac{1}{5^n}$

Exploring Concepts

65. Give an example of a sequence satisfying the condition.

(a) A monotonically increasing sequence that converges to 10

(b) A sequence that converges to $\frac{3}{4}$

66. Give an example of a bounded sequence that has a limit and an example of a bounded sequence that does not have a limit.

67. Let $\{a_n\}$ be a monotonic sequence such that $a_n \leq 1$. Discuss the convergence of $\{a_n\}$. When $\{a_n\}$ converges, what can you conclude about its limit?

68. **HOW DO YOU SEE IT?** The graphs of two sequences are shown in the figures. Which graph represents the sequence with alternating signs? Explain.

(a)



(b)



Lucky-photographer/Shutterstock.com

69. Compound Interest Consider the sequence $\{A_n\}$ whose *n*th term is given by

$$A_n = P\left(1 + \frac{r}{12}\right)^n$$

where P is the principal, A_n is the account balance after n months, and r is the interest rate compounded annually.

(a) Is $\{A_n\}$ a convergent sequence? Explain.

(b) Find the first 10 terms of the sequence when $P = \$10{,}000$ and $r = 0.055$.

70. Compound Interest A deposit of \$100 is made in an account at the beginning of each month at an annual interest rate of 3% compounded monthly. The balance in the account after n months is $A_n = 100(401)[(1.0025)^n - 1]$.

(a) Compute the first six terms of the sequence $\{A_n\}$.

(b) Find the balance in the account after 5 years by computing the 60th term of the sequence.

(c) Find the balance in the account after 20 years by computing the 240th term of the sequence.

71. Inflation When the rate of inflation is $4\frac{1}{2}\%$ per year and the average price of a car is currently \$25,000, the average price after n years is $P_n = \$25{,}000(1.045)^n$. Compute the average prices for the next 5 years.

72. Government Expenditures

A government program that currently costs taxpayers \$4.5 billion per year is cut back by 6% per year.

(a) Write an expression for the amount budgeted for this program after n years.

(b) Compute the budgets for the first 4 years.

(c) Determine the convergence or divergence of the sequence of reduced budgets. If the sequence converges, find its limit.

True or False? **In Exercises 73–76, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

73. Sequences that diverge approach either ∞ or $-\infty$.

74. If $\{a_n\}$ converges, then $\lim_{n\to\infty}(a_n - a_{n+1}) = 0$.

75. If $\{a_n\}$ converges, then $\{a_n/n\}$ converges to 0.

76. If $\{a_n\}$ diverges and $\{b_n\}$ diverges, then $\{a_n + b_n\}$ diverges.

77. Using a Sequence Compute the first six terms of the sequence $\{a_n\} = \{\sqrt[n]{n}\}$. If the sequence converges, find its limit.

78. Using a Sequence Compute the first six terms of the sequence

$$\{a_n\} = \left\{\sqrt{n}\ln\left(1 + \frac{1}{n}\right)\right\}.$$

If the sequence converges, find its limit.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

79. Proof Prove that if $\{s_n\}$ converges to L and $L > 0$, then there exists a number N such that $s_n > 0$ for $n > N$.

80. Population

The populations a_n (in millions) of Zimbabwe from 2005 through 2020 are given below as ordered pairs of the form (n, a_n), where n represents the year, with $n = 5$ corresponding to 2005. *(Source: U.S. Census Bureau)*

(5, 12.3), (6, 12.3), (7, 12.4), (8, 12.5), (9, 12.6), (10, 12.7), (11, 12.8), (12, 13.0), (13, 13.1), (14, 13.3), (15, 13.4), (16, 13.6), (17, 13.8), (18, 14.0), (19, 14.3), (20, 14.5)

(a) Use the regression capabilities of a graphing utility to find a model of the form

$$a_n = bn^4 + cn^3 + dn^2 + en + f, \quad n = 5, 6, \ldots, 20$$

for the data. Use the graphing utility to plot the points and graph the model.

(b) Use the model to predict the population of Zimbabwe in 2025.

81. Fibonacci Sequence In a study of the progeny of rabbits, Fibonacci (ca. 1170–ca. 1240) encountered the sequence now bearing his name. The sequence is defined recursively as

$$a_{n+2} = a_n + a_{n+1}$$

where $a_1 = 1$ and $a_2 = 1$.

(a) Write the first 12 terms of the sequence.

(b) Write the first 10 terms of the sequence defined by

$$b_n = \frac{a_{n+1}}{a_n}, \quad n \geq 1.$$

(c) Using the definition in part (b), show that $b_n = 1 + \dfrac{1}{b_{n-1}}$.

(d) The **golden ratio** ρ can be defined by $\lim_{n\to\infty} b_n = \rho$. Show that $\rho = 1 + (1/\rho)$ and solve this equation for ρ.

82. Using a Theorem Show that the converse of Theorem 9.1 is not true. [*Hint:* Find a function $f(x)$ such that $f(n) = a_n$ converges, but $\lim_{x\to\infty} f(x)$ does not exist.]

83. Using a Sequence Consider the sequence

$$\sqrt{2}, \sqrt{2 + \sqrt{2}}, \sqrt{2 + \sqrt{2 + \sqrt{2}}}, \ldots$$

(a) Compute the first five terms of this sequence.

(b) Write a recursion formula for a_n, for $n \geq 2$.

(c) Find $\lim_{n\to\infty} a_n$.

84. Using a Sequence Consider the sequence $\{a_n\}$, where $a_1 = \sqrt{k}$, $a_{n+1} = \sqrt{k + a_n}$, and $k > 0$.

(a) Show that $\{a_n\}$ is increasing and bounded.

(b) Prove that $\lim_{n\to\infty} a_n$ exists.

(c) Find $\lim_{n\to\infty} a_n$.

85. Squeeze Theorem

(a) Show that $\int_1^n \ln x\, dx < \ln(n!)$ for $n \geq 2$.



(b) Draw a graph similar to the one above that shows

$$\ln(n!) < \int_1^{n+1} \ln x\, dx.$$

(c) Use the results of parts (a) and (b) to show that

$$\frac{n^n}{e^{n-1}} < n! < \frac{(n+1)^{n+1}}{e^n} \quad \text{for} \quad n > 1.$$

(d) Use the Squeeze Theorem for Sequences and the result of part (c) to show that

$$\lim_{n\to\infty} \left(\sqrt[n]{n!}/n\right) = 1/e.$$

(e) Test the result of part (d) for $n = 20$, 50, and 100.

86. Proof Prove, using the definition of the limit of a sequence, that

$$\lim_{n\to\infty} \frac{1}{n^3} = 0.$$

87. Proof Prove, using the definition of the limit of a sequence, that $\lim_{n\to\infty} r^n = 0$ for $-1 < r < 1$.

88. Zipper Theorem Prove the **Zipper Theorem.** That is, if

$$\lim_{n\to\infty} a_n = \lim_{n\to\infty} b_n = L$$

then the sequence

$$\{a_1, b_1, a_2, b_2, \ldots, a_n, b_n, \ldots\}$$

converges to L.

89. Proof Prove Theorem 9.5 for a nonincreasing sequence.

PUTNAM EXAM CHALLENGE

90. Let $\{x_n\}$, $n \geq 0$, be a sequence of nonzero real numbers such that $x_n^2 - x_{n-1}x_{n+1} = 1$ for $n = 1, 2, 3, \ldots$. Prove there exists a real number a such that $x_{n+1} = ax_n - x_{n-1}$ for all $n \geq 1$.

91. Let $T_0 = 2$, $T_1 = 3$, $T_2 = 6$, and for $n \geq 3$,

$$T_n = (n + 4)T_{n-1} - 4nT_{n-2} + (4n - 8)T_{n-3}.$$

The first few terms are

2, 3, 6, 14, 40, 152, 784, 5168, 40576.

Find, with proof, a formula for T_n of the form $T_n = A_n + B_n$, where $\{A_n\}$ and $\{B_n\}$ are well-known sequences.

These problems were composed by the Committee on the Putnam Prize Competition. © The Mathematical Association of America. All rights reserved.

Dmytro Balkhovitin/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

9.2 Series and Convergence

GO DIGITAL

- **Determine the convergence or divergence of an infinite series.**
- **Determine the convergence or divergence of a geometric series.**
- **Use the *n*th-Term Test for Divergence of an infinite series.**

Infinite Series

One important application of infinite sequences is in representing "infinite summations." Informally, if $\{a_n\}$ is an infinite sequence, then

$$\sum_{n=1}^{\infty} a_n = a_1 + a_2 + a_3 + \cdots + a_n + \cdots$$ Infinite series

is an **infinite series** (or simply a **series**). The numbers a_1, a_2, a_3, and so on are the **terms** of the series. For some series, it is convenient to begin the index at $n = 0$ (or some other integer). Note that it is common to represent an infinite series as $\Sigma\, a_n$. In such cases, the starting value for the index must be taken from the context of the statement.

To find the sum of an infinite series, consider the **sequence of partial sums** listed below.

$S_1 = a_1$ 1st partial sum
$S_2 = a_1 + a_2$ 2nd partial sum
$S_3 = a_1 + a_2 + a_3$ 3rd partial sum
$S_4 = a_1 + a_2 + a_3 + a_4$ 4th partial sum
$S_5 = a_1 + a_2 + a_3 + a_4 + a_5$ 5th partial sum
$\vdots$
$S_n = a_1 + a_2 + a_3 + a_4 + a_5 + \cdots + a_n$ nth partial sum

If this sequence of partial sums converges, then the series is said to converge and has the sum indicated in the next definition.

REMARK As you study this chapter, it is important to distinguish between an infinite series and a sequence. A sequence is an ordered collection of numbers

$a_1, a_2, a_3, \ldots, a_n, \ldots$

whereas a series is an infinite sum of terms from a sequence

$a_1 + a_2 + a_3 + \cdots + a_n + \cdots$.

INFINITE SERIES

The study of infinite series was considered a novelty in the fourteenth century. Logician Richard Suiseth, whose nickname was Calculator, solved this problem.

If throughout the first half of a given time interval a variation continues at a certain intensity, throughout the next quarter of the interval at double the intensity, throughout the following eighth at triple the intensity and so ad infinitum, then the average intensity for the whole interval will be the intensity of the variation during the second subinterval (or double the intensity).

This is the same as saying that the sum of the infinite series

$$\frac{1}{2} + \frac{2}{4} + \frac{3}{8} + \cdots + \frac{n}{2^n} + \cdots$$

is 2.

Definitions of Convergent and Divergent Series

For the infinite series $\sum_{n=1}^{\infty} a_n$, the ***n*th partial sum** is

$$S_n = a_1 + a_2 + \cdots + a_n.$$

If the sequence of partial sums $\{S_n\}$ converges to S, then the series $\sum_{n=1}^{\infty} a_n$ **converges.** The limit S is called the **sum of the series.**

$$S = a_1 + a_2 + \cdots + a_n + \cdots \qquad S = \sum_{n=1}^{\infty} a_n$$

If $\{S_n\}$ diverges, then the series **diverges.**

As you study this chapter, you will learn that there are two basic questions involving infinite series.

- Does a series converge or does it diverge?
- When a series converges, what is its sum?

These questions are not always easy to answer, especially the second one.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



You can determine the partial sums of the series in Example 1(a) geometrically using this figure.
Figure 9.5

EXAMPLE 1 Convergent and Divergent Series

a. The series

$$\sum_{n=1}^{\infty} \frac{1}{2^n} = \frac{1}{2} + \frac{1}{4} + \frac{1}{8} + \frac{1}{16} + \cdots$$

has the partial sums listed below.

$$S_1 = \frac{1}{2}$$ 1st partial sum

$$S_2 = \frac{1}{2} + \frac{1}{4} = \frac{3}{4}$$ 2nd partial sum

$$S_3 = \frac{1}{2} + \frac{1}{4} + \frac{1}{8} = \frac{7}{8}$$ 3rd partial sum

$$\vdots$$

$$S_n = \frac{1}{2} + \frac{1}{4} + \frac{1}{8} + \cdots + \frac{1}{2^n} = \frac{2^n - 1}{2^n}$$ nth partial sum

Because

$$\lim_{n\to\infty} \frac{2^n - 1}{2^n} = 1$$

it follows that the series converges and its sum is 1. (You can also determine the partial sums of the series geometrically, as shown in Figure 9.5.)

b. The nth partial sum of the series

$$\sum_{n=1}^{\infty} \left(\frac{1}{n} - \frac{1}{n+1}\right) = \left(1 - \frac{1}{2}\right) + \left(\frac{1}{2} - \frac{1}{3}\right) + \left(\frac{1}{3} - \frac{1}{4}\right) + \cdots$$

is

$$S_n = 1 - \frac{1}{n+1}.$$ nth partial sum

Because the limit of S_n is 1, the series converges and its sum is 1.

c. The series

$$\sum_{n=1}^{\infty} 1 = 1 + 1 + 1 + 1 + \cdots$$

diverges because $S_n = n$ and the sequence of partial sums diverges. ■

The series in Example 1(b) is a **telescoping series** of the form

$$(b_1 - b_2) + (b_2 - b_3) + (b_3 - b_4) + (b_4 - b_5) + \cdots.$$ Telescoping series

Note that b_2 is canceled by the second term, b_3 is canceled by the third term, and so on. Because the nth partial sum of this series is

$$S_n = b_1 - b_{n+1}$$

it follows that a telescoping series will converge if and only if b_n approaches a finite number as $n \to \infty$. Moreover, if the series converges, then its sum is

$$S = b_1 - \lim_{n\to\infty} b_{n+1}.$$

FOR FURTHER INFORMATION
To learn more about the partial sums of infinite series, see the article "Six Ways to Sum a Series" by Dan Kalman in *The College Mathematics Journal*. To view this article, go to *MathArticles.com*.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 2 **Writing a Series in Telescoping Form**

Find the sum of the series $\sum_{n=1}^{\infty} \frac{2}{4n^2 - 1}$.

Solution

Using partial fractions, you can write

$$a_n = \frac{2}{4n^2 - 1} = \frac{2}{(2n - 1)(2n + 1)} = \frac{1}{2n - 1} - \frac{1}{2n + 1}.$$

From this telescoping form, you can determine that the nth partial sum is

$$S_n = \left(\frac{1}{1} - \frac{1}{3}\right) + \left(\frac{1}{3} - \frac{1}{5}\right) + \cdots + \left(\frac{1}{2n - 1} - \frac{1}{2n + 1}\right) = 1 - \frac{1}{2n + 1}.$$

So, the series converges and its sum is 1. That is,

$$\sum_{n=1}^{\infty} \frac{2}{4n^2 - 1} = \lim_{n\to\infty} S_n = \lim_{n\to\infty} \left(1 - \frac{1}{2n + 1}\right) = 1.$$

Exploration

In "Proof Without Words," by Benjamin G. Klein and Irl C. Bivens, the authors present the diagram below. Explain why the second statement after the diagram is valid. How is this result related to Theorem 9.6?



$\Delta PQR \sim \Delta TSP$

$$1 + r + r^2 + r^3 + \cdots = \frac{1}{1 - r}$$

Exercise taken from "Proof Without Words" by Benjamin G. Klein and Irl C. Bivens, *Mathematics Magazine*, 61, No. 4, October 1988, p. 219, by permission of the authors.

Geometric Series

The series in Example 1(a) is a **geometric series.** In general, the series

$$\sum_{n=0}^{\infty} ar^n = a + ar + ar^2 + \cdots + ar^n + \cdots, \quad a \neq 0$$ Geometric series

is a **geometric series** with ratio r, $r \neq 0$.

THEOREM 9.6 Convergence of a Geometric Series

A geometric series with ratio r diverges when $|r| \geq 1$. If $|r| < 1$, then the series converges to the sum

$$\sum_{n=0}^{\infty} ar^n = \frac{a}{1 - r}, \quad |r| < 1.$$

Proof It is easy to see that the series diverges when $r = \pm 1$. If $r \neq \pm 1$, then

$$S_n = a + ar + ar^2 + \cdots + ar^{n-1}.$$

Multiplication by r yields

$$rS_n = ar + ar^2 + ar^3 + \cdots + ar^n.$$

Subtracting the second equation from the first produces $S_n - rS_n = a - ar^n$. So, $S_n(1 - r) = a(1 - r^n)$, and the nth partial sum is

$$S_n = \frac{a}{1 - r}(1 - r^n).$$

When $|r| < 1$, it follows that $r^n \to 0$ as $n \to \infty$, and you obtain

$$\lim_{n\to\infty} S_n = \lim_{n\to\infty} \left[\frac{a}{1 - r}(1 - r^n)\right] = \frac{a}{1 - r}\left[\lim_{n\to\infty} (1 - r^n)\right] = \frac{a}{1 - r}$$

which means that the series *converges* and its sum is $a/(1 - r)$. It is left to you to show that the series diverges when $|r| > 1$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

TECHNOLOGY

Figure 9.6 shows the first 20 partial sums of the infinite series in Example 3(a). Notice how the values appear to approach the line $y = 6$. Using a graphing utility to sum the first 20 terms, you should obtain a sum of about 5.999994.



Figure 9.6

GO DIGITAL

EXAMPLE 3 Convergent and Divergent Geometric Series

a. The geometric series

$$\sum_{n=0}^{\infty} \frac{3}{2^n} = \sum_{n=0}^{\infty} 3\left(\frac{1}{2}\right)^n = 3(1) + 3\left(\frac{1}{2}\right) + 3\left(\frac{1}{2}\right)^2 + \cdots$$

has a ratio of $r = \frac{1}{2}$ with $a = 3$. Because $|r| < 1$, the series converges and its sum is

$$S = \frac{a}{1-r} = \frac{3}{1-(1/2)} = 6.$$ See Figure 9.6.

b. The geometric series

$$\sum_{n=0}^{\infty} \left(\frac{3}{2}\right)^n = 1 + \frac{3}{2} + \frac{9}{4} + \frac{27}{8} + \cdots$$

has a ratio of $r = \frac{3}{2}$. Because $|r| \geq 1$, the series diverges. ■

The formula for the sum of a geometric series can be used to write a repeating decimal as the ratio of two integers, as demonstrated in the next example.

EXAMPLE 4 A Geometric Series for a Repeating Decimal

See LarsonCalculus.com for an interactive version of this type of example.

Use a geometric series to write $0.\overline{08}$ as the ratio of two integers.

Solution For the repeating decimal $0.\overline{08}$, you can write

$$0.080808\ldots = \frac{8}{10^2} + \frac{8}{10^4} + \frac{8}{10^6} + \frac{8}{10^8} + \cdots$$
$$= \sum_{n=0}^{\infty} \left(\frac{8}{10^2}\right)\left(\frac{1}{10^2}\right)^n.$$

For this series, you have $a = 8/10^2$ and $r = 1/10^2$. So,

$$0.080808\ldots = \frac{a}{1-r} = \frac{8/10^2}{1-(1/10^2)} = \frac{8}{99}.$$

Try dividing 8 by 99 on a calculator to see that it produces $0.\overline{08}$. ■

REMARK In words, Theorem 9.6 states that "the sum of a convergent geometric series is the first term of the series divided by the difference of 1 and the ratio r." For the series

$$\sum_{n=4}^{\infty} \left(\frac{1}{2}\right)^n$$

note that the first term is $(1/2)^4$ and $r = 1/2$. So, the sum is

$$S = \frac{(1/2)^4}{1-(1/2)} = \frac{1}{8}.$$

The convergence of a series is not affected by the removal of a finite number of terms from the beginning of the series. For instance, the geometric series

$$\sum_{n=4}^{\infty} \left(\frac{1}{2}\right)^n \quad \text{and} \quad \sum_{n=0}^{\infty} \left(\frac{1}{2}\right)^n$$

both converge. Furthermore, because the sum of the second series is

$$\frac{a}{1-r} = \frac{1}{1-(1/2)} = 2$$

you can conclude that the sum of the first series is

$$S = 2 - \left[\left(\frac{1}{2}\right)^0 + \left(\frac{1}{2}\right)^1 + \left(\frac{1}{2}\right)^2 + \left(\frac{1}{2}\right)^3\right]$$
$$= 2 - \frac{15}{8}$$
$$= \frac{1}{8}.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

The properties in the next theorem are direct consequences of the corresponding properties of limits of sequences.

THEOREM 9.7 Properties of Infinite Series

Let Σa_n and Σb_n be convergent series, and let A, B, and c be real numbers. If $\Sigma a_n = A$ and $\Sigma b_n = B$, then the following series converge to the indicated sums.

1. $\sum_{n=1}^{\infty} ca_n = cA$
2. $\sum_{n=1}^{\infty} (a_n + b_n) = A + B$
3. $\sum_{n=1}^{\infty} (a_n - b_n) = A - B$

*n*th-Term Test for Divergence

The next theorem states that when a series converges, the limit of its nth term must be 0.

THEOREM 9.8 Limit of the *n*th Term of a Convergent Series

If $\sum_{n=1}^{\infty} a_n$ converges, then $\lim_{n\to\infty} a_n = 0$.

REMARK The converse of Theorem 9.8 is generally not true. That is, if the sequence $\{a_n\}$ converges to 0, then the series Σa_n may either converge or diverge.

Proof Assume that

$$\sum_{n=1}^{\infty} a_n = \lim_{n\to\infty} S_n = L.$$

Then, because $S_n = S_{n-1} + a_n$ and

$$\lim_{n\to\infty} S_n = \lim_{n\to\infty} S_{n-1} = L$$

it follows that

$$\begin{aligned} L &= \lim_{n\to\infty} S_n \\ &= \lim_{n\to\infty} (S_{n-1} + a_n) \\ &= \lim_{n\to\infty} S_{n-1} + \lim_{n\to\infty} a_n \\ &= L + \lim_{n\to\infty} a_n \end{aligned}$$

which implies that $\{a_n\}$ converges to 0. ∎

The contrapositive of Theorem 9.8 provides a useful test for *divergence*. This ***n*th-Term Test for Divergence** (also known as the **Divergence Test**) states that if the limit of the nth term of a series does *not* converge to 0, then the series must diverge.

THEOREM 9.9 *n*th-Term Test for Divergence

If $\lim_{n\to\infty} a_n \neq 0$ then $\sum_{n=1}^{\infty} a_n$ diverges.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 5 Using the *n*th-Term Test for Divergence

a. For the series $\sum_{n=0}^{\infty} 2^n$, you have

$$\lim_{n\to\infty} 2^n = \infty.$$

So, the limit of the nth term is not 0, and the series diverges.

b. For the series $\sum_{n=1}^{\infty} \frac{n!}{2n! + 1}$, you have

$$\lim_{n\to\infty} \frac{n!}{2n! + 1} = \lim_{n\to\infty} \frac{1}{2 + (1/n!)} = \frac{1}{2}.$$

So, the limit of the nth term is not 0, and the series diverges.

c. For the series $\sum_{n=1}^{\infty} \frac{1}{n}$, you have

$$\lim_{n\to\infty} \frac{1}{n} = 0.$$

Because the limit of the nth term is 0, the nth-Term Test for Divergence does *not* apply and you can draw no conclusions about convergence or divergence. (In the next section, you will learn that this particular series diverges.)

REMARK The series in Example 5(c) will play an important role in this chapter.

$$\sum_{n=1}^{\infty} \frac{1}{n} = 1 + \frac{1}{2} + \frac{1}{3} + \cdots$$

In the next section, you will learn that this series diverges even though the nth term approaches 0 as n approaches ∞.

EXAMPLE 6 Bouncing Ball Problem

A ball is dropped from a height of 6 feet and begins bouncing, as shown in Figure 9.7. The height of each bounce is three-fourths the height of the previous bounce. Find the total vertical distance traveled by the ball.

Solution When the ball hits the ground for the first time, it has traveled a distance of $D_1 = 6$ feet. For subsequent bounces, let D_i be the distance traveled up and down. For example, D_2 and D_3 are

$$D_2 = \underbrace{6\left(\frac{3}{4}\right)}_{\text{Up}} + \underbrace{6\left(\frac{3}{4}\right)}_{\text{Down}} = 12\left(\frac{3}{4}\right)$$

and

$$D_3 = \underbrace{6\left(\frac{3}{4}\right)\left(\frac{3}{4}\right)}_{\text{Up}} + \underbrace{6\left(\frac{3}{4}\right)\left(\frac{3}{4}\right)}_{\text{Down}} = 12\left(\frac{3}{4}\right)^2.$$

By continuing this process, it can be determined that the total vertical distance is

$$\begin{aligned} D &= 6 + 12\left(\frac{3}{4}\right) + 12\left(\frac{3}{4}\right)^2 + 12\left(\frac{3}{4}\right)^3 + \cdots \\ &= 6 + 12\sum_{n=0}^{\infty}\left(\frac{3}{4}\right)^{n+1} \\ &= 6 + 12\left(\frac{3}{4}\right)\sum_{n=0}^{\infty}\left(\frac{3}{4}\right)^n \\ &= 6 + 9\left[\frac{1}{1 - (3/4)}\right] \\ &= 6 + 9(4) \\ &= 42 \text{ feet.} \end{aligned}$$



The height of each bounce is three-fourths the height of the preceding bounce.

Figure 9.7

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

9.2 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe the difference between $\lim_{n\to\infty} a_n = 5$ and $\sum_{n=1}^{\infty} a_n = 5$.
2. Define a geometric series, state when it converges, and give the formula for the sum of a convergent geometric series.
3. The limit of the nth term of a series converges to 0. What can you conclude about the convergence or divergence of the series?
4. The limit of the nth term of a series does not converge to 0. What can you conclude about the convergence or divergence of the series?

Finding Partial Sums In Exercises 5–10, find the sequence of partial sums S_1, S_2, S_3, S_4, and S_5.

5. $1 + \frac{1}{4} + \frac{1}{9} + \frac{1}{16} + \frac{1}{25} + \cdots$
6. $\frac{1}{2 \cdot 3} + \frac{2}{3 \cdot 4} + \frac{3}{4 \cdot 5} + \frac{4}{5 \cdot 6} + \frac{5}{6 \cdot 7} + \cdots$
7. $3 - \frac{9}{2} + \frac{27}{4} - \frac{81}{8} + \frac{243}{16} - \cdots$
8. $1 + \frac{1}{2} + \frac{1}{4} + \frac{1}{6} + \frac{1}{8} + \frac{1}{10} + \cdots$
9. $\sum_{n=1}^{\infty} \frac{3}{2^{n-1}}$
10. $\sum_{n=1}^{\infty} \frac{(-1)^{n+1}}{n!}$

Verifying Divergence In Exercises 11–18, verify that the infinite series diverges.

11. $\sum_{n=0}^{\infty} 5\left(\frac{5}{2}\right)^n$
12. $\sum_{n=0}^{\infty} 4(-1.05)^n$
13. $\sum_{n=1}^{\infty} \frac{n}{n+1}$
14. $\sum_{n=1}^{\infty} \frac{n}{2n+3}$
15. $\sum_{n=1}^{\infty} \frac{n^3+1}{n^3+n^2}$
16. $\sum_{n=1}^{\infty} \frac{2n}{\sqrt{n^2+1}}$
17. $\sum_{n=1}^{\infty} \frac{4^n+3}{4^{n+1}}$
18. $\sum_{n=1}^{\infty} \frac{(n+1)!}{5n!}$

Verifying Convergence In Exercises 19–24, verify that the infinite series converges.

19. $\sum_{n=0}^{\infty} \left(\frac{5}{6}\right)^n$
20. $\sum_{n=1}^{\infty} 2\left(-\frac{1}{2}\right)^n$
21. $\sum_{n=0}^{\infty} (0.9)^n = 1 + 0.9 + 0.81 + 0.729 + \cdots$
22. $\sum_{n=0}^{\infty} (-0.2)^n = 1 - 0.2 + 0.04 - 0.008 + \cdots$
23. $\sum_{n=1}^{\infty} \frac{1}{n(n+1)}$ (*Hint:* Use partial fractions.)
24. $\sum_{n=1}^{\infty} \frac{1}{n(n+2)}$ (*Hint:* Use partial fractions.)

Numerical, Graphical, and Analytic Analysis In Exercises 25–28, (a) find the sum of the series, (b) use a graphing utility to find the indicated partial sum S_n and complete the table, (c) use a graphing utility to graph the first 10 terms of the sequence of partial sums and a horizontal line representing the sum, and (d) explain the relationship between the magnitudes of the terms of the series and the rate at which the sequence of partial sums approaches the sum of the series.

n	5	10	20	50	100
S_n					

25. $\sum_{n=1}^{\infty} \frac{6}{n(n+3)}$
26. $\sum_{n=1}^{\infty} \frac{4}{n(n+4)}$
27. $\sum_{n=1}^{\infty} 2(0.9)^{n-1}$
28. $\sum_{n=1}^{\infty} 10\left(-\frac{1}{4}\right)^{n-1}$

Finding the Sum of a Convergent Series In Exercises 29–38, find the sum of the convergent series.

29. $\sum_{n=0}^{\infty} 5\left(\frac{2}{3}\right)^n$
30. $\sum_{n=0}^{\infty} \left(-\frac{1}{5}\right)^n$
31. $\sum_{n=1}^{\infty} \frac{4}{n(n+2)}$
32. $\sum_{n=1}^{\infty} \frac{1}{(2n+1)(2n+3)}$
33. $8 + 6 + \frac{9}{2} + \frac{27}{8} + \cdots$
34. $9 - 3 + 1 - \frac{1}{3} + \cdots$
35. $\sum_{n=0}^{\infty} \left(\frac{1}{2^n} - \frac{1}{3^n}\right)$
36. $\sum_{n=0}^{\infty} [(0.3)^n + (0.8)^n]$
37. $\sum_{n=1}^{\infty} (\sin 1)^n$
38. $\sum_{n=1}^{\infty} \frac{1}{9n^2+3n-2}$

Using a Geometric Series In Exercises 39–44, (a) write the repeating decimal as a geometric series and (b) write the sum of the series as the ratio of two integers.

39. $0.\overline{4}$
40. $0.\overline{63}$
41. $0.1\overline{2}$
42. $0.0\overline{1}$
43. $0.0\overline{75}$
44. $0.2\overline{15}$

Determining Convergence or Divergence In Exercises 45–58, determine the convergence or divergence of the series.

45. $\sum_{n=0}^{\infty} (1.075)^n$
46. $\sum_{n=0}^{\infty} \frac{6^n}{n+1}$
47. $\sum_{n=1}^{\infty} \frac{n+1}{2n-1}$
48. $\sum_{n=1}^{\infty} \frac{4n+1}{3n-1}$
49. $\sum_{n=1}^{\infty} \left(\frac{1}{n} - \frac{1}{n+2}\right)$
50. $\sum_{n=1}^{\infty} \left(\frac{1}{n+1} - \frac{1}{n+2}\right)$
51. $\sum_{n=1}^{\infty} \frac{3^n}{n^3}$
52. $\sum_{n=0}^{\infty} \frac{7}{5^n}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

53. $\sum_{n=2}^{\infty} \frac{n}{\ln n}$

54. $\sum_{n=1}^{\infty} \ln \frac{1}{n}$

55. $\sum_{n=1}^{\infty} \left(1 + \frac{k}{n}\right)^n$

56. $\sum_{n=1}^{\infty} e^{-n}$

57. $\sum_{n=1}^{\infty} \arctan n$

58. $\sum_{n=1}^{\infty} \ln\left(\frac{n+1}{n}\right)$

Exploring Concepts

59. A finite number of terms are deleted from a divergent series. Determine whether the new series will still diverge. Explain your reasoning.

60. A finite number of terms are added to a convergent series. Determine whether the new series will still converge. Explain your reasoning.

Making a Series Converge **In Exercises 61–66, find all values of x for which the series converges. For these values of x, write the sum of the series as a function of x.**

61. $\sum_{n=1}^{\infty} (3x)^n$

62. $\sum_{n=0}^{\infty} \left(\frac{2}{x}\right)^n$

63. $\sum_{n=1}^{\infty} (x-1)^n$

64. $\sum_{n=0}^{\infty} 5\left(\frac{x-2}{3}\right)^n$

65. $\sum_{n=0}^{\infty} (-1)^n x^n$

66. $\sum_{n=0}^{\infty} (-1)^n x^{2n}$

Using a Geometric Series **In Exercises 67 and 68, (a) find the common ratio of the geometric series, (b) write the function that gives the sum of the series, and (c) use a graphing utility to graph the function and the partial sums S_3 and S_5. What do you notice?**

67. $1 + x + x^2 + x^3 + \cdots$

68. $1 - \frac{x}{2} + \frac{x^2}{4} - \frac{x^3}{8} + \cdots$

Writing **In Exercises 69 and 70, use a graphing utility to determine the first term that is less than 0.0001 in each of the convergent series. Note that the answers are very different. Explain how this will affect the rate at which the series converges.**

69. $\sum_{n=1}^{\infty} \frac{1}{n(n+1)}, \quad \sum_{n=1}^{\infty} \left(\frac{1}{8}\right)^n$

70. $\sum_{n=1}^{\infty} \frac{1}{2^n}, \quad \sum_{n=1}^{\infty} (0.01)^n$

71. Marketing An electronic games manufacturer producing a new product estimates the annual sales to be 8000 units. Each year, 5% of the units that have been sold will become inoperative. So, 8000 units will be in use after 1 year, $[8000 + 0.95(8000)]$ units will be in use after 2 years, and so on. How many units will be in use after n years?

72. Depreciation A company buys a machine for $475,000 that depreciates at a rate of 30% per year. Find a formula for the value of the machine after n years. What is its value after 5 years?

73. Distance A ball is dropped from a height of 16 feet. Each time it drops h feet, it rebounds $0.81h$ feet. Find the total distance traveled by the ball.

74. Time The ball in Exercise 73 takes the following times for each fall.

$s_1 = -16t^2 + 16$, $s_1 = 0$ when $t = 1$

$s_2 = -16t^2 + 16(0.81)$, $s_2 = 0$ when $t = 0.9$

$s_3 = -16t^2 + 16(0.81)^2$, $s_3 = 0$ when $t = (0.9)^2$

$s_4 = -16t^2 + 16(0.81)^3$, $s_4 = 0$ when $t = (0.9)^3$

$\vdots$ $\vdots$

$s_n = -16t^2 + 16(0.81)^{n-1}$, $s_n = 0$ when $t = (0.9)^{n-1}$

Beginning with s_2, the ball takes the same amount of time to bounce up as it does to fall, so the total time elapsed before it comes to rest is given by $t = 1 + 2\sum_{n=1}^{\infty} (0.9)^n$. Find this total time.

75. Multiplier Effect

The total annual spending by tourists in a resort city is $200 million. Approximately 75% of that revenue is again spent in the resort city, and of that amount approximately 75% is again spent in the same city, and so on. Write the geometric series that gives the total amount of spending generated by the $200 million and find the sum of the series.

76. Multiplier Effect Repeat Exercise 75 when the percent of the revenue that is spent again in the city decreases to 60%.

Probability **In Exercises 77 and 78, the random variable n represents the number of units of a product sold per day in a store. The probability distribution of n is given by $P(n)$. Find the probability that two units are sold in a given day $[P(2)]$ and show that $P(0) + P(1) + P(2) + P(3) + \cdots = 1$.**

77. $P(n) = \frac{1}{2}\left(\frac{1}{2}\right)^n$

78. $P(n) = \frac{1}{3}\left(\frac{2}{3}\right)^n$

79. Probability A fair coin is tossed repeatedly. The probability that the first head occurs on the nth toss is given by $P(n) = \left(\frac{1}{2}\right)^n$, where $n \geq 1$.

(a) Show that $\sum_{n=1}^{\infty} \left(\frac{1}{2}\right)^n = 1$.

(b) The expected number of tosses required until the first head occurs in the experiment is given by

$$\sum_{n=1}^{\infty} n\left(\frac{1}{2}\right)^n.$$

Is this series geometric?

(c) Use a graphing utility to find the sum in part (b).

80. Probability In an experiment, three people toss a fair coin one at a time until one of them tosses a head. Determine, for each person, the probability that he or she tosses the first head. Verify that the sum of the three probabilities is 1.

SVongpra/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

81. Area The sides of a square are 16 inches in length. A new square is formed by connecting the midpoints of the sides of the original square, and two of the triangles outside the second square are shaded (see figure). Determine the area of the shaded regions (a) when this process is continued five more times and (b) when this pattern of shading is continued infinitely.



Figure for 81



Figure for 82

82. Length A right triangle XYZ is shown above where $|XY| = z$ and $\angle X = \theta$. Line segments are continually drawn to be perpendicular to the triangle, as shown in the figure.

(a) Find the total length of the perpendicular line segments $|Yy_1| + |x_1y_1| + |x_1y_2| + \cdots$ in terms of z and θ.

(b) Find the total length of the perpendicular line segments when $z = 1$ and $\theta = \pi/6$.

Using a Geometric Series **In Exercises 83–86, use the formula for the *n*th partial sum of a geometric series**

$$\sum_{i=0}^{n-1} ar^i = \frac{a(1 - r^n)}{1 - r}.$$

83. Present Value The winner of a $2,000,000 sweepstakes will be paid $100,000 per year for 20 years. The money earns 6% interest per year. The present value of the winnings is $\sum_{n=1}^{20} 100{,}000\left(\frac{1}{1.06}\right)^n$. Compute the present value and interpret its meaning.

84. Annuities When an employee receives a paycheck at the end of each month, P dollars is invested in a retirement account. These deposits are made each month for t years and the account earns interest at the annual percentage rate r. When the interest is compounded monthly, the amount A in the account at the end of t years is

$$A = P + P\left(1 + \frac{r}{12}\right) + \cdots + P\left(1 + \frac{r}{12}\right)^{12t-1}$$
$$= P\left(\frac{12}{r}\right)\left[\left(1 + \frac{r}{12}\right)^{12t} - 1\right].$$

When the interest is compounded continuously, the amount A in the account after t years is

$$A = P + Pe^{r/12} + Pe^{2r/12} + \cdots + Pe^{(12t-1)r/12}$$
$$= \frac{P(e^{rt} - 1)}{e^{r/12} - 1}.$$

Verify the formulas for the sums given above.

85. Salary You go to work at a company that pays $0.01 for the first day, $0.02 for the second day, $0.04 for the third day, and so on. If the daily wage keeps doubling, what would your total income be for working (a) 29 days, (b) 30 days, and (c) 31 days?

86. Sphereflake

The sphereflake shown below is a computer-generated fractal that was created by Eric Haines. The radius of the large sphere is 1. To the large sphere, nine spheres of radius $\frac{1}{3}$ are attached. To each of these, nine spheres of radius $\frac{1}{9}$ are attached. This process is continued infinitely. Prove that the sphereflake has an infinite surface area.



LoByteSo/Deviant Art

Annuities **In Exercises 87–90, consider making monthly deposits of P dollars in a savings account at an annual interest rate r. Use the results of Exercise 84 to find the balance A in the account after t years when the interest is compounded (a) monthly and (b) continuously.**

87. $P = \$50$, $r = 2\%$, $t = 20$ years

88. $P = \$200$, $r = 5.5\%$, $t = 25$ years

89. $P = \$1050$, $r = 0.9\%$, $t = 35$ years

90. $P = \$175$, $r = 4\%$, $t = 50$ years

True or False? **In Exercises 91–94, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

91. If $|r| < 1$, then $\sum_{n=1}^{\infty} ar^n = \frac{a}{1 - r}$.

92. If $\sum_{n=1}^{\infty} a_n = L$, then $\sum_{n=0}^{\infty} a_n = L + a_0$.

93. $0.75 = 0.749999\ldots$

94. The series $\sum_{n=1}^{\infty} \frac{n}{1000(n + 1)}$ diverges.

95. Using Divergent Series Find two divergent series Σa_n and Σb_n such that $\Sigma(a_n + b_n)$ converges.

96. Remainder Let Σa_n be a convergent series, and let

$$R_N = a_{N+1} + a_{N+2} + \cdots$$

be the remainder of the series after the first N terms. Prove that $\lim_{N\to\infty} R_N = 0$.

97. Proof Prove that $\frac{1}{r} + \frac{1}{r^2} + \frac{1}{r^3} + \cdots = \frac{1}{r - 1}$ for $|r| > 1$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

98. Proof Given two infinite series Σa_n and Σb_n such that Σa_n converges and Σb_n diverges, prove that $\Sigma(a_n + b_n)$ diverges.

99. Fibonacci Sequence The Fibonacci sequence is defined recursively by $a_{n+2} = a_n + a_{n+1}$, where $a_1 = 1$ and $a_2 = 1$.

(a) Show that $\dfrac{1}{a_{n+1}a_{n+3}} = \dfrac{1}{a_{n+1}a_{n+2}} - \dfrac{1}{a_{n+2}a_{n+3}}$.

(b) Show that $\displaystyle\sum_{n=0}^{\infty} \frac{1}{a_{n+1}a_{n+3}} = 1$.

100. HOW DO YOU SEE IT? The figure below represents an informal way of showing that $\displaystyle\sum_{n=1}^{\infty} \frac{1}{n^2} < 2$. Explain how the figure implies this conclusion.



FOR FURTHER INFORMATION For more on this exercise, see the article "Convergence with Pictures" by P. J. Rippon in *American Mathematical Monthly.*

PUTNAM EXAM CHALLENGE

101. Express $\displaystyle\sum_{k=1}^{\infty} \frac{6^k}{(3^{k+1} - 2^{k+1})(3^k - 2^k)}$ as a rational number.

102. Let $f(n)$ be the sum of the first n terms of the sequence $0, 1, 1, 2, 2, 3, 3, 4, \ldots$, where the nth term is given by

$$a_n = \begin{cases} n/2, & \text{if } n \text{ is even} \\ (n-1)/2, & \text{if } n \text{ is odd} \end{cases}.$$

Show that if x and y are positive integers and $x > y$ then $xy = f(x + y) - f(x - y)$.

103. Let $x_0, x_1, x_2, \ldots$ be the sequence such that $x_0 = 1$ and for $n \geq 0$,

$$x_{n+1} = \ln(e^{x_n} - x_n)$$

(as usual, the function ln is the natural logarithm). Show that the infinite series

$$x_0 + x_1 + x_2 + \cdots$$

converges and find its sum.

These problems were composed by the Committee on the Putnam Prize Competition. © The Mathematical Association of America. All rights reserved.

SECTION PROJECT

Cantor's Disappearing Table

The following procedure shows how to make a table disappear by removing only half of the table!

(a) Original table has a length of L.



(b) Remove $\frac{1}{4}$ of the table centered at the midpoint. Each remaining piece has a length that is less than $\frac{1}{2}L$.



(c) Remove $\frac{1}{8}$ of the table by taking sections of length $\frac{1}{16}L$ from the centers of each of the two remaining pieces. Now you have removed $\frac{1}{4} + \frac{1}{8}$ of the table. Each remaining piece has a length that is less than $\frac{1}{4}L$.



(d) Remove $\frac{1}{16}$ of the table by taking sections of length $\frac{1}{64}L$ from the centers of each of the four remaining pieces. Now you have removed $\frac{1}{4} + \frac{1}{8} + \frac{1}{16}$ of the table. Each remaining piece has a length that is less than $\frac{1}{8}L$.



Will continuing this process cause the table to disappear, even though you have removed only half of the table? Why?

FOR FURTHER INFORMATION Read the article "Cantor's Disappearing Table" by Larry E. Knop in *The College Mathematics Journal.* To view this article, go to *MathArticles.com.*

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

9.3 The Integral Test and *p*-Series

GO DIGITAL

- **Use the Integral Test to determine whether an infinite series converges or diverges.**
- **Determine the convergence or divergence of *p*-series and harmonic series.**

The Integral Test

In this and the next section, you will study several convergence tests that apply to series with *positive* terms.

THEOREM 9.10 The Integral Test

If f is positive, continuous, and decreasing for $x \geq 1$ and $a_n = f(n)$, then

$$\sum_{n=1}^{\infty} a_n \quad \text{and} \quad \int_1^{\infty} f(x)\,dx$$

either both converge or both diverge.



Figure 9.8

Proof Begin by partitioning the interval $[1, n]$ into $(n - 1)$ unit intervals, as shown in Figure 9.8. The total areas of the inscribed rectangles and the circumscribed rectangles are

$$\sum_{i=2}^{n} f(i) = f(2) + f(3) + \cdots + f(n) \qquad \text{Inscribed area}$$

and

$$\sum_{i=1}^{n-1} f(i) = f(1) + f(2) + \cdots + f(n-1). \qquad \text{Circumscribed area}$$

The exact area under the graph of f from $x = 1$ to $x = n$ lies between the inscribed and circumscribed areas.

$$\sum_{i=2}^{n} f(i) \leq \int_1^n f(x)\,dx \leq \sum_{i=1}^{n-1} f(i)$$

Use the nth partial sum

$$S_n = f(1) + f(2) + \cdots + f(n)$$

to write this inequality as

$$S_n - f(1) \leq \int_1^n f(x)\,dx \leq S_{n-1}.$$

Now, assuming that $\int_1^{\infty} f(x)\,dx$ converges to L, it follows that for $n \geq 1$,

$$S_n - f(1) \leq L \quad \Rightarrow \quad S_n \leq L + f(1).$$

Consequently, $\{S_n\}$ is bounded and monotonic, and by Theorem 9.5 it converges. So, Σa_n converges. For the other direction of the proof, assume that the improper integral diverges. Then $\int_1^n f(x)\,dx$ approaches infinity as $n \to \infty$, and the inequality $S_{n-1} \geq \int_1^n f(x)\,dx$ implies that $\{S_n\}$ diverges. So, Σa_n diverges. ∎

Remember that the convergence or divergence of Σa_n is not affected by deleting the first N terms. Similarly, when the conditions for the Integral Test are satisfied for all $x \geq N > 1$, use the integral $\int_N^{\infty} f(x)\,dx$ to test for convergence or divergence. (This is illustrated in Example 4.)

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

REMARK Before applying the Integral Test, be sure to check that the function is positive, continuous, and decreasing for $x \geq 1$. When the function fails to satisfy one or more of these conditions, you cannot apply the Integral Test.

EXAMPLE 1 Using the Integral Test

Apply the Integral Test to the series $\sum_{n=1}^{\infty} \frac{n}{n^2 + 1}$.

Solution The function $f(x) = x/(x^2 + 1)$ is positive and continuous for $x \geq 1$. To determine whether f is decreasing, find the derivative.

$$f'(x) = \frac{(x^2 + 1)(1) - x(2x)}{(x^2 + 1)^2} = \frac{-x^2 + 1}{(x^2 + 1)^2}$$

So, $f'(x) < 0$ for $x > 1$ and it follows that f satisfies the conditions for the Integral Test. Next, integrate to obtain

$$\begin{aligned}
\int_1^{\infty} \frac{x}{x^2 + 1}\,dx &= \frac{1}{2}\int_1^{\infty} \frac{2x}{x^2 + 1}\,dx && \text{Multiply and divide by 2.} \\
&= \frac{1}{2}\lim_{b\to\infty} \int_1^{b} \frac{2x}{x^2 + 1}\,dx && \text{Definition of improper integral} \\
&= \frac{1}{2}\lim_{b\to\infty} \Big[\ln(x^2 + 1)\Big]_1^{b} && \text{Apply Log Rule.} \\
&= \frac{1}{2}\lim_{b\to\infty} [\ln(b^2 + 1) - \ln 2] && \text{Apply Fundamental Theorem of Calculus.} \\
&= \infty. && \text{Evaluate limit.}
\end{aligned}$$

The integral *diverges*, so by the Integral Test, the series *diverges*.

EXAMPLE 2 Using the Integral Test

See LarsonCalculus.com for an interactive version of this type of example.

Apply the Integral Test to the series $\sum_{n=1}^{\infty} \frac{1}{n^2 + 1}$.

Solution Because $f(x) = 1/(x^2 + 1)$ satisfies the conditions for the Integral Test (check this), integrate to obtain

$$\begin{aligned}
\int_1^{\infty} \frac{1}{x^2 + 1}\,dx &= \lim_{b\to\infty} \int_1^{b} \frac{1}{x^2 + 1}\,dx && \text{Definition of improper integral} \\
&= \lim_{b\to\infty} \Big[\arctan x\Big]_1^{b} && \text{Apply Arctan Rule.} \\
&= \lim_{b\to\infty} (\arctan b - \arctan 1) && \text{Apply Fundamental Theorem of Calculus.} \\
&= \frac{\pi}{2} - \frac{\pi}{4} && \text{Evaluate limit.} \\
&= \frac{\pi}{4}. && \text{Simplify.}
\end{aligned}$$

The integral *converges*, so by the Integral Test, the series *converges* (see Figure 9.9).



Because the improper integral converges, the infinite series also converges.
Figure 9.9

In Example 2, the fact that the improper integral converges to $\pi/4$ does not imply that the infinite series converges to $\pi/4$. To approximate the sum of the series, you can use the inequality

$$\sum_{n=1}^{N} \frac{1}{n^2 + 1} \leq \sum_{n=1}^{\infty} \frac{1}{n^2 + 1} \leq \sum_{n=1}^{N} \frac{1}{n^2 + 1} + \int_N^{\infty} \frac{1}{x^2 + 1}\,dx.$$

(See Exercise 52.) The larger the value of N, the better the approximation. For instance, using $N = 200$ produces $1.072 \leq \Sigma\,[1/(n^2 + 1)] \leq 1.077$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

p-Series and Harmonic Series

In the remainder of this section, you will investigate a second type of series that has a simple arithmetic test for convergence or divergence. A series of the form

$$\sum_{n=1}^{\infty} \frac{1}{n^p} = \frac{1}{1^p} + \frac{1}{2^p} + \frac{1}{3^p} + \cdots \qquad p\text{-series}$$

is a ***p*-series,** where p is a positive constant. For $p = 1$, the series

$$\sum_{n=1}^{\infty} \frac{1}{n} = 1 + \frac{1}{2} + \frac{1}{3} + \cdots \qquad \text{Harmonic series}$$

is the **harmonic series.** A **general harmonic series** is of the form $\Sigma\,[1/(an + b)]$. In music, strings of the same material, diameter, and tension, and whose lengths form a harmonic series, produce harmonic tones.

HARMONIC SERIES

Pythagoras and his students paid close attention to the development of music as an abstract science. This led to the discovery of the relationship between the tone and the length of a vibrating string. It was observed that the most beautiful musical harmonies corresponded to the simplest ratios of whole numbers. Later mathematicians developed this idea into the harmonic series, where the terms in the harmonic series correspond to the nodes on a vibrating string that produce multiples of the fundamental frequency. For example, $\frac{1}{2}$ is twice the fundamental frequency, $\frac{1}{3}$ is three times the fundamental frequency, and so on.

The Integral Test is convenient for establishing the convergence or divergence of p-series. This is shown in the proof of Theorem 9.11.

THEOREM 9.11 Convergence of *p*-Series

The p-series

$$\sum_{n=1}^{\infty} \frac{1}{n^p} = \frac{1}{1^p} + \frac{1}{2^p} + \frac{1}{3^p} + \frac{1}{4^p} + \cdots$$

converges for $p > 1$ and diverges for $0 < p \leq 1$.

Proof The proof follows from the Integral Test and from Theorem 8.7, which states that

$$\int_1^{\infty} \frac{1}{x^p}\,dx$$

converges for $p > 1$ and diverges for $0 < p \leq 1$. ■

EXAMPLE 3 Convergent and Divergent *p*-Series

Discuss the convergence or divergence of (a) the harmonic series and (b) the p-series with $p = 2$.

Solution

a. From Theorem 9.11, it follows that the harmonic series

$$\sum_{n=1}^{\infty} \frac{1}{n} = \frac{1}{1} + \frac{1}{2} + \frac{1}{3} + \cdots \qquad p = 1$$

diverges.

b. From Theorem 9.11, it follows that the p-series

$$\sum_{n=1}^{\infty} \frac{1}{n^2} = \frac{1}{1^2} + \frac{1}{2^2} + \frac{1}{3^2} + \cdots \qquad p = 2$$

converges. ■

FOR FURTHER INFORMATION

To read about a proof of the sum of the series in Example 3(b), see the article "A Short Elementary Proof of $\Sigma 1/k^2 = \pi^2/6$" by Daniel Daners in *Mathematics Magazine*. To view this article, go to *MathArticles.com*.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The sum of the series in Example 3(b) can be shown to be $\pi^2/6$. (This was proved by Leonhard Euler, but the proof is too difficult to present here.) Be sure you understand that the Integral Test does not tell you that the sum of the series is equal to the value of the integral. For instance, the sum of the series in Example 3(b) is

$$\sum_{n=1}^{\infty} \frac{1}{n^2} = \frac{\pi^2}{6} \approx 1.645$$

whereas the value of the corresponding improper integral is

$$\int_1^{\infty} \frac{1}{x^2}\,dx = 1.$$

REMARK You are asked to prove this result in Chapter 14. (See Exercise 5 on page 1041.)

EXAMPLE 4 Testing a Series for Convergence

Determine whether the series $\sum_{n=2}^{\infty} \frac{1}{n \ln n}$ converges or diverges.

Solution This series is similar to the divergent harmonic series. If its terms were greater than those of the harmonic series, you would expect it to diverge. However, because its terms are less than those of the harmonic series, you are not sure what to expect. The function

$$f(x) = \frac{1}{x \ln x}$$

is positive and continuous for $x \geq 2$. To determine whether f is decreasing, first rewrite f as

$$f(x) = (x \ln x)^{-1}$$ Rewrite using negative exponent.

and then find its derivative.

$$f'(x) = (-1)(x \ln x)^{-2}(1 + \ln x) = -\frac{1 + \ln x}{x^2(\ln x)^2}$$

So, $f'(x) < 0$ for $x > 2$ and it follows that f satisfies the conditions for the Integral Test.

$$\begin{aligned}
\int_2^{\infty} \frac{1}{x \ln x}\,dx &= \int_2^{\infty} \frac{1/x}{\ln x}\,dx && \text{Rewrite integrand.} \\
&= \lim_{b\to\infty} \int_2^{b} \frac{1/x}{\ln x}\,dx && \text{Definition of improper integral} \\
&= \lim_{b\to\infty} \Big[\ln(\ln x)\Big]_2^{b} && \text{Apply Log Rule.} \\
&= \lim_{b\to\infty} [\ln(\ln b) - \ln(\ln 2)] && \text{Apply Fundamental Theorem of Calculus.} \\
&= \infty && \text{Evaluate limit.}
\end{aligned}$$

The integral *diverges*, so by the Integral Test, the series diverges. ■

Note that the infinite series in Example 4 diverges very slowly. For instance, as shown in the table, the sum of the first 10 terms is approximately 1.6878196, whereas the sum of the first 100 terms is slightly greater: 2.3250871. In fact, the sum of the first 10,000 terms is approximately 3.0150217. So, although the infinite series "adds up to infinity," it does so very slowly.

n	11	101	1001	10,001	100,001
S_n	1.6878	2.3251	2.7275	3.0150	3.2382

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

9.3 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Give the conditions that must be satisfied to use the Integral Test.
2. Determine whether each series is a p-series.

(a) $\sum_{n=1}^{\infty} \frac{1}{n^{1.4}}$ (b) $\sum_{n=1}^{\infty} \frac{1}{n^{-2}}$ (c) $\sum_{n=1}^{\infty} \frac{1}{n^3}$

Using the Integral Test In Exercises 3–22, confirm that the Integral Test can be applied to the series. Then use the Integral Test to determine the convergence or divergence of the series.

3. $\sum_{n=1}^{\infty} \frac{1}{n+3}$
4. $\sum_{n=1}^{\infty} \frac{2}{3n+5}$
5. $\sum_{n=1}^{\infty} \frac{1}{2^n}$
6. $\sum_{n=1}^{\infty} 3^{-n}$
7. $\sum_{n=1}^{\infty} e^{-n}$
8. $\sum_{n=1}^{\infty} ne^{-n/2}$
9. $\frac{\ln 2}{2} + \frac{\ln 3}{3} + \frac{\ln 4}{4} + \frac{\ln 5}{5} + \frac{\ln 6}{6} + \cdots$
10. $\frac{\ln 2}{\sqrt{2}} + \frac{\ln 3}{\sqrt{3}} + \frac{\ln 4}{\sqrt{4}} + \frac{\ln 5}{\sqrt{5}} + \frac{\ln 6}{\sqrt{6}} + \cdots$
11. $\frac{1}{3} + \frac{1}{5} + \frac{1}{7} + \frac{1}{9} + \frac{1}{11} + \cdots$
12. $\frac{1}{4} + \frac{2}{7} + \frac{3}{12} + \frac{4}{19} + \frac{5}{28} + \cdots$
13. $\sum_{n=1}^{\infty} \frac{\arctan n}{n^2+1}$
14. $\sum_{n=2}^{\infty} \frac{\ln n}{n^3}$
15. $\sum_{n=1}^{\infty} \frac{\ln n}{n^2}$
16. $\sum_{n=2}^{\infty} \frac{1}{n\sqrt{\ln n}}$
17. $\sum_{n=1}^{\infty} \frac{1}{(2n+3)^3}$
18. $\sum_{n=1}^{\infty} \frac{n+2}{n+1}$
19. $\sum_{n=1}^{\infty} \frac{4n}{2n^2+1}$
20. $\sum_{n=1}^{\infty} \frac{1}{\sqrt[3]{n+9}}$
21. $\sum_{n=1}^{\infty} \frac{n}{n^4+1}$
22. $\sum_{n=1}^{\infty} \frac{n}{n^4+2n^2+1}$

Using the Integral Test In Exercises 23 and 24, use the Integral Test to determine the convergence or divergence of the series, where k is a positive integer.

23. $\sum_{n=1}^{\infty} \frac{n^{k-1}}{n^k+c}$
24. $\sum_{n=1}^{\infty} n^k e^{-n}$

Conditions of the Integral Test In Exercises 25–28, explain why the Integral Test does not apply to the series.

25. $\sum_{n=1}^{\infty} \frac{(-1)^n}{n}$
26. $\sum_{n=1}^{\infty} e^{-n}\cos n$
27. $\sum_{n=1}^{\infty} \frac{2+\sin n}{n}$
28. $\sum_{n=1}^{\infty} \left(\frac{\sin n}{n}\right)^2$

Using the Integral Test In Exercises 29–32, use the Integral Test to determine the convergence or divergence of the p-series.

29. $\sum_{n=1}^{\infty} \frac{1}{n^7}$
30. $\sum_{n=1}^{\infty} \frac{1}{n^{1/2}}$
31. $\sum_{n=1}^{\infty} \frac{1}{n^{0.9}}$
32. $\sum_{n=1}^{\infty} \frac{1}{n^{1.001}}$

Using a p-Series In Exercises 33–38, use Theorem 9.11 to determine the convergence or divergence of the p-series.

33. $\sum_{n=1}^{\infty} \frac{1}{\sqrt[5]{n}}$
34. $\sum_{n=1}^{\infty} \frac{3}{n^{5/3}}$
35. $1 + \frac{1}{2\sqrt{2}} + \frac{1}{3\sqrt{3}} + \frac{1}{4\sqrt{4}} + \frac{1}{5\sqrt{5}} + \cdots$
36. $1 + \frac{1}{\sqrt[3]{4}} + \frac{1}{\sqrt[3]{9}} + \frac{1}{\sqrt[3]{16}} + \frac{1}{\sqrt[3]{25}} + \cdots$
37. $\sum_{n=1}^{\infty} \frac{1}{n^{1.03}}$
38. $\sum_{n=1}^{\infty} \frac{1}{n^{\pi}}$

39. **Numerical and Graphical Analysis** Use a graphing utility to find the indicated partial sum S_n and complete the table. Then use a graphing utility to graph the first 10 terms of the sequence of partial sums. For each series, compare the rate at which the sequence of partial sums approaches the sum of the series.

n	5	10	20	50	100
S_n					

(a) $\sum_{n=1}^{\infty} 3\left(\frac{1}{5}\right)^{n-1} = \frac{15}{4}$

(b) $\sum_{n=1}^{\infty} \frac{1}{n^2} = \frac{\pi^2}{6}$

40. **Numerical Reasoning** Because the harmonic series diverges, it follows that for any positive real number M, there exists a positive integer N such that the partial sum

$$\sum_{n=1}^{N} \frac{1}{n} > M.$$

(a) Use a graphing utility to complete the table.

M	2	4	6	8
N				

(b) As the real number M increases in equal increments, does the number N increase in equal increments? Explain.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploring Concepts

41. Without performing any calculations, determine whether the following series converges. Explain.

$$\frac{1}{10{,}000} + \frac{1}{10{,}001} + \frac{1}{10{,}002} + \cdots$$

42. Let f be a positive, continuous, and decreasing function for $x \geq 1$, such that $a_n = f(n)$. Use a graph to rank the following quantities in decreasing order. Explain your reasoning.

(a) $\sum_{n=2}^{7} a_n$ (b) $\int_1^7 f(x)\,dx$ (c) $\sum_{n=1}^{6} a_n$

43. Use a graph to show that the inequality is true. What can you conclude about the convergence or divergence of the series? Explain.

(a) $\sum_{n=1}^{\infty} \frac{1}{\sqrt{n}} > \int_1^{\infty} \frac{1}{\sqrt{x}}\,dx$

(b) $\sum_{n=2}^{\infty} \frac{1}{n^2} < \int_1^{\infty} \frac{1}{x^2}\,dx$

44. HOW DO YOU SEE IT? The graphs show the sequences of partial sums of the p-series

$$\sum_{n=1}^{\infty} \frac{1}{n^{0.4}} \quad \text{and} \quad \sum_{n=1}^{\infty} \frac{1}{n^{1.5}}.$$

Using Theorem 9.11, the first series diverges and the second series converges. Explain how the graphs show this.



Finding Values

In Exercises 45–50, find the positive values of p for which the series converges.

45. $\sum_{n=2}^{\infty} \frac{1}{n(\ln n)^p}$

46. $\sum_{n=2}^{\infty} \frac{\ln n}{n^p}$

47. $\sum_{n=1}^{\infty} \frac{n}{(1+n^2)^p}$

48. $\sum_{n=1}^{\infty} n(1+n^2)^p$

49. $\sum_{n=1}^{\infty} \left(\frac{3}{p}\right)^n$

50. $\sum_{n=3}^{\infty} \frac{1}{n(\ln n)[\ln(\ln n)]^p}$

51. Proof Let f be a positive, continuous, and decreasing function for $x \geq 1$, such that $a_n = f(n)$. Prove that if the series

$$\sum_{n=1}^{\infty} a_n$$

converges to S, then the remainder $R_N = S - S_N$ is bounded by

$$0 \leq R_N \leq \int_N^{\infty} f(x)\,dx.$$

52. Using a Remainder Show that the result of Exercise 51 can be written as

$$\sum_{n=1}^{N} a_n \leq \sum_{n=1}^{\infty} a_n \leq \sum_{n=1}^{N} a_n + \int_N^{\infty} f(x)\,dx.$$

Approximating a Sum

In Exercises 53–58, use the result of Exercise 51 to approximate the sum of the convergent series using the indicated number of terms. Include an estimate of the maximum error for your approximation.

53. $\sum_{n=1}^{\infty} \frac{1}{n^4}$, three terms

54. $\sum_{n=1}^{\infty} \frac{1}{(n+1)^3}$, six terms

55. $\sum_{n=1}^{\infty} \frac{1}{n^2+1}$, eight terms

56. $\sum_{n=1}^{\infty} \frac{1}{(n+1)[\ln(n+1)]^3}$, ten terms

57. $\sum_{n=1}^{\infty} ne^{-n^2}$, four terms

58. $\sum_{n=1}^{\infty} e^{-2n}$, five terms

Finding a Value

In Exercises 59–62, use the result of Exercise 51 to find N such that $R_N \leq 0.001$ for the convergent series.

59. $\sum_{n=1}^{\infty} \frac{1}{n^4}$

60. $\sum_{n=1}^{\infty} \frac{1}{n^{3/2}}$

61. $\sum_{n=1}^{\infty} e^{-n/2}$

62. $\sum_{n=1}^{\infty} \frac{1}{n^2+1}$

63. Comparing Series

(a) Show that $\sum_{n=2}^{\infty} \frac{1}{n^{1.1}}$ converges and $\sum_{n=2}^{\infty} \frac{1}{n \ln n}$ diverges.

(b) Compare the first five terms of each series in part (a).

(c) Find $n > 3$ such that $\frac{1}{n^{1.1}} < \frac{1}{n \ln n}$.

64. Using a p-Series

Ten terms are used to approximate a convergent p-series. So, the remainder is a function of p and is

$$0 \leq R_{10}(p) \leq \int_{10}^{\infty} \frac{1}{x^p}\,dx, \quad p > 1.$$

(a) Perform the integration in the inequality.

(b) Use a graphing utility to represent the inequality graphically.

(c) Identify any asymptotes of the remainder function and interpret their meaning.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

65. Euler's Constant Let

$$S_n = \sum_{k=1}^{n} \frac{1}{k} = 1 + \frac{1}{2} + \cdots + \frac{1}{n}.$$

(a) Show that $\ln(n+1) \le S_n \le 1 + \ln n$.

(b) Show that the sequence $\{a_n\} = \{S_n - \ln n\}$ is bounded.

(c) Show that the sequence $\{a_n\}$ is decreasing.

(d) Show that the sequence $\{a_n\}$ converges to a limit γ (called Euler's constant).

(e) Approximate γ using a_{100}.

66. Finding a Sum Find the sum of the series

$$\sum_{n=2}^{\infty} \ln\left(1 - \frac{1}{n^2}\right).$$

67. Using a Series Consider the series $\sum_{n=2}^{\infty} x^{\ln n}$.

(a) Determine the convergence or divergence of the series for $x = 1$.

(b) Determine the convergence or divergence of the series for $x = 1/e$.

(c) Find the positive values of x for which the series converges.

68. Riemann Zeta Function The **Riemann zeta function** for real numbers is defined for all x for which the series $\zeta(x) = \sum_{n=1}^{\infty} n^{-x}$ converges. Find the domain of the function.

Review **In Exercises 69–80, determine the convergence or divergence of the series.**

69. $\sum_{n=1}^{\infty} \frac{1}{3n-2}$

70. $\sum_{n=2}^{\infty} \frac{1}{n\sqrt{n^2-1}}$

71. $\sum_{n=1}^{\infty} \frac{1}{n\sqrt[4]{n}}$

72. $3\sum_{n=1}^{\infty} \frac{1}{n^{0.95}}$

73. $\sum_{n=0}^{\infty} \left(\frac{2}{3}\right)^n$

74. $\sum_{n=0}^{\infty} \left(\frac{7}{5}\right)^n$

75. $\sum_{n=1}^{\infty} \frac{n}{\sqrt{3n^2+3}}$

76. $\sum_{n=1}^{\infty} \left(\frac{1}{n^2} - \frac{1}{n^3}\right)$

77. $\sum_{n=1}^{\infty} \left(1 + \frac{1}{n}\right)^n$

78. $\sum_{n=4}^{\infty} \ln \frac{n}{2}$

79. $\sum_{n=2}^{\infty} \frac{1}{n(\ln n)^3}$

80. $\sum_{n=3}^{\infty} \frac{1}{n(\ln n)[\ln(\ln n)]^4}$

81. Harmonic Series Verify the equation

$$\frac{1}{n} + \frac{1}{n+1} = \frac{1}{(n+1)/2} + \frac{1}{n(n+1)}.$$

Then use it to show that the harmonic series diverges.

SECTION PROJECT

The Harmonic Series

The harmonic series

$$\sum_{n=1}^{\infty} \frac{1}{n} = 1 + \frac{1}{2} + \frac{1}{3} + \frac{1}{4} + \cdots + \frac{1}{n} + \cdots$$

is one of the most important series in this chapter. Even though its terms tend to zero as n increases,

$$\lim_{n\to\infty} \frac{1}{n} = 0$$

the harmonic series diverges. In other words, even though the terms are getting smaller and smaller, the sum "adds up to infinity."

(a) One way to show that the harmonic series diverges is attributed to James Bernoulli. He grouped the terms of the harmonic series as follows:

$$1 + \frac{1}{2} + \underbrace{\frac{1}{3} + \frac{1}{4}}_{> \frac{1}{2}} + \underbrace{\frac{1}{5} + \cdots + \frac{1}{8}}_{> \frac{1}{2}} + \underbrace{\frac{1}{9} + \cdots + \frac{1}{16}}_{> \frac{1}{2}} +$$

$$\underbrace{\frac{1}{17} + \cdots + \frac{1}{32}}_{> \frac{1}{2}} + \cdots$$

Write a short paragraph explaining how you can use this grouping to show that the harmonic series diverges.

(b) Use the proof of the Integral Test, Theorem 9.10, to show that

$$\ln(n+1) \le 1 + \frac{1}{2} + \frac{1}{3} + \frac{1}{4} + \cdots + \frac{1}{n} \le 1 + \ln n.$$

(c) Use part (b) to determine how many terms M you would need so that

$$\sum_{n=1}^{M} \frac{1}{n} > 50.$$

(d) Show that the sum of the first million terms of the harmonic series is less than 15.

(e) Show that the following inequalities are valid.

$$\ln \frac{21}{10} \le \frac{1}{10} + \frac{1}{11} + \cdots + \frac{1}{20} \le \ln \frac{20}{9}$$

$$\ln \frac{201}{100} \le \frac{1}{100} + \frac{1}{101} + \cdots + \frac{1}{200} \le \ln \frac{200}{99}$$

(f) Use the inequalities in part (e) to find the limit

$$\lim_{m\to\infty} \sum_{n=m}^{2m} \frac{1}{n}.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

9.4 Comparisons of Series

GO DIGITAL

- **Use the Direct Comparison Test to determine whether a series converges or diverges.**
- **Use the Limit Comparison Test to determine whether a series converges or diverges.**

Direct Comparison Test

For the convergence tests developed so far, the terms of the series have to be fairly simple and the series must have special characteristics for the convergence tests to be applied. A slight deviation from these special characteristics can make a test inapplicable. For example, in the pairs listed below, the second series cannot be tested by the same convergence test as the first series, even though it is similar to the first.

1. $\sum_{n=0}^{\infty} \frac{1}{2^n}$ is geometric, but $\sum_{n=0}^{\infty} \frac{n}{2^n}$ is not.
2. $\sum_{n=1}^{\infty} \frac{1}{n^3}$ is a p-series, but $\sum_{n=1}^{\infty} \frac{1}{n^3 + 1}$ is not.
3. $a_n = \frac{n}{(n^2 + 3)^2}$ is easily integrated, but $b_n = \frac{n^2}{(n^2 + 3)^2}$ is not.

In this section, you will study two additional tests for positive-term series. These two tests greatly expand the variety of series you are able to test for convergence or divergence. They allow you to *compare* a series having complicated terms with a simpler series whose convergence or divergence is known.

REMARK As stated, the Direct Comparison Test requires that $0 < a_n \leq b_n$ for all n. Because the convergence of a series is not dependent on its first several terms, you could modify the test to require only that $0 < a_n \leq b_n$ for all n greater than some integer N.

THEOREM 9.12 Direct Comparison Test

Let $0 < a_n \leq b_n$ for all n.

1. If $\sum_{n=1}^{\infty} b_n$ converges, then $\sum_{n=1}^{\infty} a_n$ converges.
2. If $\sum_{n=1}^{\infty} a_n$ diverges, then $\sum_{n=1}^{\infty} b_n$ diverges.

Proof To prove the first property, let $L = \sum_{n=1}^{\infty} b_n$ and let

$$S_n = a_1 + a_2 + \cdots + a_n.$$

Because $0 < a_n \leq b_n$, the sequence $S_1, S_2, S_3, \ldots$ is nondecreasing and bounded above by L. So, it must converge. Because

$$\lim_{n\to\infty} S_n = \sum_{n=1}^{\infty} a_n$$

it follows that $\sum_{n=1}^{\infty} a_n$ converges. The second property is logically equivalent to the first. ∎

FOR FURTHER INFORMATION Is the Direct Comparison Test just for nonnegative series? To read about the generalization of this test to real series, see the article "The Comparison Test—Not Just for Nonnegative Series" by Michele Longo and Vincenzo Valori in *Mathematics Magazine*. To view this article, go to *MathArticles.com*.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



For the given series in Example 1, the sequence of partial sums is less than the sequence of partial sums of the indicated convergent geometric series.
Figure 9.10

EXAMPLE 1 Using the Direct Comparison Test

Determine the convergence or divergence of

$$\sum_{n=1}^{\infty} \frac{1}{2 + 3^n}.$$

Solution This series resembles

$$\sum_{n=1}^{\infty} \frac{1}{3^n}.$$ Convergent geometric series

Term-by-term comparison yields

$$a_n = \frac{1}{2 + 3^n} < \frac{1}{3^n} = b_n, \quad n \geq 1.$$

So, by the Direct Comparison Test, the given series converges. This conclusion is supported by Figure 9.10, which shows that the sequence of partial sums of $\Sigma\, a_n$ is less than the sequence of partial sums of the convergent geometric series $\Sigma\, b_n$.

EXAMPLE 2 Using the Direct Comparison Test

See LarsonCalculus.com for an interactive version of this type of example.

Determine the convergence or divergence of

$$\sum_{n=1}^{\infty} \frac{1}{2 + \sqrt{n}}.$$

Solution This series resembles

$$\sum_{n=1}^{\infty} \frac{1}{n^{1/2}}.$$ Divergent p-series

Term-by-term comparison yields

$$\frac{1}{2 + \sqrt{n}} \leq \frac{1}{\sqrt{n}}, \quad n \geq 1$$

which *does not* meet the requirements for divergence. (Remember that when term-by-term comparison reveals a series that is *less* than a divergent series, the Direct Comparison Test tells you nothing.) Still expecting the series to diverge, you can compare the series with

$$\sum_{n=1}^{\infty} \frac{1}{n}.$$ Divergent harmonic series

In this case, term-by-term comparison yields

$$a_n = \frac{1}{n} \leq \frac{1}{2 + \sqrt{n}} = b_n, \quad n \geq 4$$

and, by the Direct Comparison Test, the given series diverges (see Figure 9.11). To verify the last inequality, show that

$$2 + \sqrt{n} \leq n$$

whenever $n \geq 4$. ■



For the given series in Example 2, the sequence of partial sums is greater than the sequence of partial sums of the divergent harmonic series.
Figure 9.11

Remember that both parts of the Direct Comparison Test require that $0 < a_n \leq b_n$. Informally, the test says the following about the two series with nonnegative terms.

1. If the "larger" series converges, then the "smaller" series must also converge.
2. If the "smaller" series diverges, then the "larger" series must also diverge.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Limit Comparison Test

Sometimes a series closely resembles a p-series or a geometric series, yet you cannot establish the term-by-term comparison necessary to apply the Direct Comparison Test. Under these circumstances, you may be able to apply a second comparison test, called the **Limit Comparison Test.**

REMARK As with the Direct Comparison Test, the Limit Comparison Test could be modified to require only that a_n and b_n be positive for all n greater than some integer N.

THEOREM 9.13 Limit Comparison Test

If $a_n > 0$, $b_n > 0$, and

$$\lim_{n\to\infty} \frac{a_n}{b_n} = L$$

where L is *finite and positive*, then

$$\sum_{n=1}^{\infty} a_n \quad \text{and} \quad \sum_{n=1}^{\infty} b_n$$

either both converge or both diverge.

Proof Because $a_n > 0$, $b_n > 0$, and

$$\lim_{n\to\infty} \frac{a_n}{b_n} = L$$

there exists $N > 0$ such that

$$0 < \frac{a_n}{b_n} < L + 1, \quad \text{for } n \geq N.$$

This implies that

$$0 < a_n < (L + 1)b_n.$$

So, by the Direct Comparison Test, the convergence of $\Sigma\, b_n$ implies the convergence of $\Sigma\, a_n$. Similarly, the fact that

$$\lim_{n\to\infty} \frac{b_n}{a_n} = \frac{1}{L}$$

can be used to show that the convergence of $\Sigma\, a_n$ implies the convergence of $\Sigma\, b_n$. ■

EXAMPLE 3 Using the Limit Comparison Test

Show that the general harmonic series below diverges.

$$\sum_{n=1}^{\infty} \frac{1}{an + b}, \quad a > 0, \quad b > 0$$

Solution By comparison with

$$\sum_{n=1}^{\infty} \frac{1}{n}$$ Divergent harmonic series

you have

$$\lim_{n\to\infty} \frac{1/(an + b)}{1/n} = \lim_{n\to\infty} \frac{n}{an + b} = \frac{1}{a}.$$

Because this limit is greater than 0, you can conclude from the Limit Comparison Test that the series diverges. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

The Limit Comparison Test works well for comparing a "messy" algebraic series with a p-series. In choosing an appropriate p-series, you must choose one with an nth term of the same magnitude as the nth term of the given series.

Given Series	Comparison Series	Conclusion
$\sum_{n=1}^{\infty} \frac{1}{3n^2 - 4n + 5}$	$\sum_{n=1}^{\infty} \frac{1}{n^2}$	Both series converge.
$\sum_{n=1}^{\infty} \frac{1}{\sqrt{3n - 2}}$	$\sum_{n=1}^{\infty} \frac{1}{\sqrt{n}}$	Both series diverge.
$\sum_{n=1}^{\infty} \frac{n^2 - 10}{4n^5 + n^3}$	$\sum_{n=1}^{\infty} \frac{n^2}{n^5} = \sum_{n=1}^{\infty} \frac{1}{n^3}$	Both series converge.

In other words, when choosing a series for comparison, you can disregard all but the *highest powers of n* in both the numerator and the denominator.

EXAMPLE 4 Using the Limit Comparison Test

Determine the convergence or divergence of

$$\sum_{n=1}^{\infty} \frac{\sqrt{n}}{n^2 + 1}.$$

Solution Disregarding all but the highest powers of n in the numerator and the denominator, you can compare the series with

$$\sum_{n=1}^{\infty} \frac{\sqrt{n}}{n^2} = \sum_{n=1}^{\infty} \frac{1}{n^{3/2}}.$$ Convergent p-series

Because

$$\lim_{n\to\infty} \frac{a_n}{b_n} = \lim_{n\to\infty} \left(\frac{\sqrt{n}}{n^2 + 1}\right)\left(\frac{n^{3/2}}{1}\right)$$
$$= \lim_{n\to\infty} \frac{n^2}{n^2 + 1}$$
$$= 1$$

you can conclude by the Limit Comparison Test that the series converges.

REMARK Recall when finding limits at $\pm\infty$ of a rational function that if the degree of the numerator is equal to the degree of the denominator, then the limit of the rational function is the ratio of the leading coefficients.

EXAMPLE 5 Using the Limit Comparison Test

Determine the convergence or divergence of

$$\sum_{n=1}^{\infty} \frac{n2^n}{4n^3 + 1}.$$

Solution A reasonable comparison would be with the series

$$\sum_{n=1}^{\infty} \frac{2^n}{n^2}.$$ Divergent series

Note that this series diverges by the nth-Term Test. From the limit

$$\lim_{n\to\infty} \frac{a_n}{b_n} = \lim_{n\to\infty} \left(\frac{n2^n}{4n^3 + 1}\right)\left(\frac{n^2}{2^n}\right)$$
$$= \lim_{n\to\infty} \frac{n^3}{4n^3 + 1}$$
$$= \frac{1}{4}$$

you can conclude by the Limit Comparison Test that the series diverges.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

9.4 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. You want to compare the series Σa_n and Σb_n, where $a_n > 0$, $b_n > 0$, and Σb_n converges. For $1 \le n \le 5$, $a_n > b_n$, and for $n \ge 6$, $a_n < b_n$. Explain whether the Direct Comparison Test can be used to compare the two series.
2. When using the Limit Comparison Test, describe how to choose a series for comparison.

Graphical Analysis **In Exercises 3 and 4, the figures show the graphs of the first 10 terms, and the graphs of the first 10 terms of the sequence of partial sums, of each series.**

(a) Identify the series in each figure.

(b) Which series is a *p*-series? Does it converge or diverge?

(c) For the series that are not *p*-series, how do the magnitudes of the terms compare with the magnitudes of the terms of the *p*-series? What conclusion can you draw about the convergence or divergence of the series?

(d) Explain the relationship between the magnitudes of the terms of the series and the magnitudes of the terms of the partial sums.

3. $\sum_{n=1}^{\infty} \frac{6}{n^{3/2}}$, $\sum_{n=1}^{\infty} \frac{6}{n^{3/2}+3}$, and $\sum_{n=1}^{\infty} \frac{6}{n\sqrt{n^2+0.5}}$



Graphs of terms



Graphs of partial sums

4. $\sum_{n=1}^{\infty} \frac{2}{\sqrt{n}}$, $\sum_{n=1}^{\infty} \frac{2}{\sqrt{n}-0.5}$, and $\sum_{n=1}^{\infty} \frac{4}{\sqrt{n}+0.5}$



Graphs of terms



Graphs of partial sums

Using the Direct Comparison Test **In Exercises 5–16, use the Direct Comparison Test to determine the convergence or divergence of the series.**

5. $\sum_{n=1}^{\infty} \frac{1}{2n-1}$
6. $\sum_{n=1}^{\infty} \frac{1}{3n^2+2}$
7. $\sum_{n=2}^{\infty} \frac{1}{\sqrt{n}-1}$
8. $\sum_{n=0}^{\infty} \frac{4^n}{5^n+3}$
9. $\sum_{n=2}^{\infty} \frac{\ln n}{n+1}$
10. $\sum_{n=1}^{\infty} \frac{1}{\sqrt{n^3+1}}$
11. $\sum_{n=0}^{\infty} \frac{1}{n!}$
12. $\sum_{n=1}^{\infty} \frac{1}{4\sqrt[3]{n}-1}$
13. $\sum_{n=0}^{\infty} e^{-n^2}$
14. $\sum_{n=1}^{\infty} \frac{6^n+n}{5^n-1}$
15. $\sum_{n=1}^{\infty} \frac{\sin^2 n}{n^3}$
16. $\sum_{n=1}^{\infty} \frac{\cos n + 2}{\sqrt{n}}$

Using the Limit Comparison Test **In Exercises 17–26, use the Limit Comparison Test to determine the convergence or divergence of the series.**

17. $\sum_{n=1}^{\infty} \frac{n}{n^2+1}$
18. $\sum_{n=1}^{\infty} \frac{5}{4^n+1}$
19. $\sum_{n=0}^{\infty} \frac{1}{\sqrt{n^2+1}}$
20. $\sum_{n=1}^{\infty} \frac{2^n+1}{5^n+1}$
21. $\sum_{n=1}^{\infty} \frac{2n^2-1}{3n^5+2n+1}$
22. $\sum_{n=1}^{\infty} \frac{1}{n^2(n^2+4)}$
23. $\sum_{n=1}^{\infty} \frac{1}{n\sqrt{n^2+1}}$
24. $\sum_{n=1}^{\infty} \frac{n}{(n+1)2^{n-1}}$
25. $\sum_{n=1}^{\infty} \frac{n^{k-1}}{n^k+1}$, $k > 2$
26. $\sum_{n=1}^{\infty} \sin\frac{1}{n}$

Determining Convergence or Divergence **In Exercises 27–34, test for convergence or divergence, using each test at least once. Identify which test was used.**

(a) *n*th-Term Test

(b) Geometric Series Test

(c) *p*-Series Test

(d) Telescoping Series Test

(e) Integral Test

(f) Direct Comparison Test

(g) Limit Comparison Test

27. $\sum_{n=1}^{\infty} \frac{\sqrt[3]{n}}{n}$
28. $\sum_{n=0}^{\infty} 5\left(-\frac{4}{3}\right)^n$
29. $\sum_{n=1}^{\infty} \frac{1}{5^n+1}$
30. $\sum_{n=3}^{\infty} \frac{1}{n^3-8}$
31. $\sum_{n=1}^{\infty} \frac{2n}{3n-2}$
32. $\sum_{n=1}^{\infty} \left(\frac{1}{n+1} - \frac{1}{n+2}\right)$
33. $\sum_{n=1}^{\infty} \frac{n}{(n^2+1)^2}$
34. $\sum_{n=1}^{\infty} \frac{3}{n(n+3)}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

35. Using the Limit Comparison Test Use the Limit Comparison Test with the harmonic series to show that the series Σa_n (where $0 < a_n < a_{n-1}$) diverges when $\lim_{n\to\infty} na_n$ is finite and nonzero.

36. Proof Prove that, if $P(n)$ and $Q(n)$ are polynomials of degree j and k, respectively, then the series

$$\sum_{n=1}^{\infty} \frac{P(n)}{Q(n)}$$

converges if $j < k - 1$ and diverges if $j \geq k - 1$.

Determining Convergence or Divergence **In Exercises 37–40, use the polynomial test given in Exercise 36 to determine whether the series converges or diverges.**

37. $\frac{1}{2} + \frac{2}{5} + \frac{3}{10} + \frac{4}{17} + \frac{5}{26} + \cdots$

38. $\frac{1}{3} + \frac{1}{8} + \frac{1}{15} + \frac{1}{24} + \frac{1}{35} + \cdots$

39. $\sum_{n=1}^{\infty} \frac{1}{n^3 + 1}$

40. $\sum_{n=1}^{\infty} \frac{4n^5 + n^2 + 1}{n^4}$

Verifying Divergence **In Exercises 41 and 42, use the divergence test given in Exercise 35 to show that the series diverges.**

41. $\sum_{n=1}^{\infty} \frac{n^3}{5n^4 + 3}$

42. $\sum_{n=1}^{\infty} \frac{3n^2 + 1}{4n^3 + 2}$

Determining Convergence or Divergence **In Exercises 43–46, determine the convergence or divergence of the series.**

43. $\frac{1}{200} + \frac{1}{400} + \frac{1}{600} + \frac{1}{800} + \cdots$

44. $\frac{1}{200} + \frac{1}{208} + \frac{1}{216} + \frac{1}{224} + \cdots$

45. $\frac{1}{201} + \frac{1}{204} + \frac{1}{209} + \frac{1}{216} + \cdots$

46. $\frac{1}{201} + \frac{1}{208} + \frac{1}{227} + \frac{1}{264} + \cdots$

Exploring Concepts

47. Review the results of Exercises 43–46. Explain why careful analysis is required to determine the convergence or divergence of a series and why considering only the magnitudes of the terms of a series could be misleading.

48. It appears that the terms of the series

$$\frac{1}{1000} + \frac{1}{1001} + \frac{1}{1002} + \frac{1}{1003} + \cdots$$

are less than the corresponding terms of the convergent series

$$1 + \frac{1}{4} + \frac{1}{9} + \frac{1}{16} + \cdots.$$

If the statement above is correct, then the first series converges. Is this correct? Why or why not? Make a statement about how the divergence or convergence of a series is affected by the inclusion or exclusion of the first finite number of terms.

49. Using a Series Consider the series $\sum_{n=1}^{\infty} \frac{1}{(2n-1)^2}$.

(a) Verify that the series converges.

(b) Use a graphing utility to complete the table.

n	5	10	20	50	100
S_n					

(c) The sum of the series is $\pi^2/8$. Find the sum of the series

$$\sum_{n=3}^{\infty} \frac{1}{(2n-1)^2}.$$

(d) Use a graphing utility to find the sum of the series

$$\sum_{n=10}^{\infty} \frac{1}{(2n-1)^2}.$$

50. Using a Series Consider the series $\sum_{n=1}^{\infty} \frac{1}{(n+2)^2}$.

(a) Verify that the series converges.

(b) Use a graphing utility to complete the table.

n	5	10	20	50	100
S_n					

(c) The sum of the series is $(\pi^2/6) - (5/4)$. Find the sum of the series

$$\sum_{n=6}^{\infty} \frac{1}{(n+2)^2}.$$

(d) Use a graphing utility to find the sum of the series

$$\sum_{n=15}^{\infty} \frac{1}{(n+2)^2}.$$

51. Decimal Representation of a Number Show that the series

$$\frac{x_1}{10} + \frac{x_2}{10^2} + \frac{x_3}{10^3} + \frac{x_4}{10^4} + \cdots$$

converges, where x_i is one of the numbers 0, 1, 2, . . ., 9.

52. HOW DO YOU SEE IT? The figure shows the first 20 terms of the series Σc_n using squares and the first 20 terms of the series Σd_n using circles. If Σd_n converges, can you determine anything about the convergence or divergence of Σc_n? Explain.



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

True or False? **In Exercises 53–57, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

53. If $0 < a_n \le b_n$ and $\sum_{n=1}^{\infty} a_n$ converges, then $\sum_{n=1}^{\infty} b_n$ diverges.

54. If $0 < a_{n+10} \le b_n$ and $\sum_{n=1}^{\infty} b_n$ converges, then $\sum_{n=1}^{\infty} a_n$ converges.

55. If $a_n + b_n \le c_n$ and $\sum_{n=1}^{\infty} c_n$ converges, then the series $\sum_{n=1}^{\infty} a_n$ and $\sum_{n=1}^{\infty} b_n$ both converge. (Assume that the terms of all three series are positive.)

56. If $a_n \le b_n + c_n$ and $\sum_{n=1}^{\infty} a_n$ diverges, then the series $\sum_{n=1}^{\infty} b_n$ and $\sum_{n=1}^{\infty} c_n$ both diverge. (Assume that the terms of all three series are positive.)

57. If $0 < a_n \le b_n$ and $\sum_{n=1}^{\infty} a_n$ diverges, then $\sum_{n=1}^{\infty} b_n$ diverges.

58. Proof Prove that the series

$$\sum_{n=1}^{\infty} \frac{1}{1 + 2 + 3 + \cdots + n}$$

converges.

59. Proof Prove that if the nonnegative series

$$\sum_{n=1}^{\infty} a_n \quad \text{and} \quad \sum_{n=1}^{\infty} b_n$$

converge, then so does the series $\sum_{n=1}^{\infty} a_n b_n$.

60. Proof Use the result of Exercise 59 to prove that if the nonnegative series

$$\sum_{n=1}^{\infty} a_n$$

converges, then so does the series $\sum_{n=1}^{\infty} {a_n}^2$.

61. Finding Series Find two series that demonstrate the result of Exercise 59.

62. Finding Series Find two series that demonstrate the result of Exercise 60.

63. Proof Let Σa_n and Σb_n be series with positive terms. Prove that if

$$\lim_{n\to\infty} \frac{a_n}{b_n} = 0$$

and Σb_n converges, then Σa_n also converges.

64. Proof Let Σa_n and Σb_n be series with positive terms. Prove that if

$$\lim_{n\to\infty} \frac{a_n}{b_n} = \infty$$

and Σb_n diverges, then Σa_n also diverges.

65. Verifying Convergence Use the result of Exercise 63 to show that each series converges.

(a) $\sum_{n=1}^{\infty} \frac{1}{(n+1)^3}$

(b) $\sum_{n=1}^{\infty} \frac{1}{\sqrt{n}\pi^n}$

(c) $\sum_{n=2}^{\infty} \frac{\ln n}{n^3}$

(d) $\sum_{n=1}^{\infty} \frac{n^2+1}{e^n}$

66. Verifying Divergence Use the result of Exercise 64 to show that each series diverges.

(a) $\sum_{n=1}^{\infty} (n+2)^2$

(b) $\sum_{n=1}^{\infty} \frac{\ln n}{n}$

(c) $\sum_{n=2}^{\infty} \frac{1}{\ln n}$

(d) $\sum_{n=1}^{\infty} \frac{e^n}{\sqrt{n}}$

67. Proof Let Σa_n be a series with positive terms. Prove that if Σa_n converges, then $\Sigma \sin a_n$ also converges.

68. Determining Convergence or Divergence Determine whether the every-other-term harmonic series

$$1 + \frac{1}{3} + \frac{1}{5} + \frac{1}{7} + \cdots$$

converges or diverges.

69. Comparing Series Show that

$$\sum_{n=1}^{\infty} \frac{\ln n}{n\sqrt{n}}$$

converges by comparison with

$$\sum_{n=1}^{\infty} \frac{1}{n^{5/4}}.$$

70. Determining Convergence or Divergence Determine the convergence or divergence of the series

$$\sum_{n=1}^{\infty} \left(\sin \frac{1}{2n} - \sin \frac{1}{2n+1} \right).$$

PUTNAM EXAM CHALLENGE

71. Is the infinite series

$$\sum_{n=1}^{\infty} \frac{1}{n^{(n+1)/n}}$$

convergent? Prove your statement.

72. Prove that if $\sum_{n=1}^{\infty} a_n$ is a convergent series of positive real numbers, then so is

$$\sum_{n=1}^{\infty} (a_n)^{n/(n+1)}.$$

These problems were composed by the Committee on the Putnam Prize Competition. © The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

9.5 Alternating Series

GO DIGITAL

- **Use the Alternating Series Test to determine whether an infinite series converges.**
- **Use the Alternating Series Remainder to approximate the sum of an alternating series.**
- **Classify a convergent series as absolutely or conditionally convergent.**
- **Rearrange an infinite series to obtain a different sum.**

Alternating Series Test

So far, most series you have studied have had positive terms. In this section and the next section, you will study series that contain both positive and negative terms. The simplest such series is an **alternating series,** whose terms alternate in sign. For example, the geometric series

$$\sum_{n=0}^{\infty}\left(-\frac{1}{2}\right)^n = \sum_{n=0}^{\infty}(-1)^n\frac{1}{2^n} = 1 - \frac{1}{2} + \frac{1}{4} - \frac{1}{8} + \frac{1}{16} - \cdots$$

is an *alternating geometric series* with $r = -\frac{1}{2}$. Alternating series occur in two ways: either the odd terms are negative or the even terms are negative.

THEOREM 9.14 Alternating Series Test

Let $a_n > 0$. The alternating series

$$\sum_{n=1}^{\infty}(-1)^n a_n \quad \text{and} \quad \sum_{n=1}^{\infty}(-1)^{n+1} a_n$$

converge when these two conditions are met.

1. $\lim_{n\to\infty} a_n = 0$ **2.** $a_{n+1} \le a_n$, for all n

REMARK The second condition in the Alternating Series Test can be modified to require only that $0 < a_{n+1} \le a_n$ for all n greater than some integer N.

Proof Consider the alternating series

$$\sum_{n=1}^{\infty}(-1)^{n+1}a_n$$

where $a_n > 0$. For this series, the partial sum (where $2n$ is even)

$$S_{2n} = (a_1 - a_2) + (a_3 - a_4) + (a_5 - a_6) + \cdots + (a_{2n-1} - a_{2n})$$

has all nonnegative terms, and therefore $\{S_{2n}\}$ is a nondecreasing sequence. But you can also write this partial sum as

$$S_{2n} = a_1 - (a_2 - a_3) - (a_4 - a_5) - \cdots - (a_{2n-2} - a_{2n-1}) - a_{2n}$$

which implies that $S_{2n} \le a_1$ for every integer n. So, $\{S_{2n}\}$ is a bounded, nondecreasing sequence that converges to some value L. Because $S_{2n-1} - a_{2n} = S_{2n}$ and $a_{2n} \to 0$,

$$\begin{aligned}\lim_{n\to\infty} S_{2n-1} &= \lim_{n\to\infty}(S_{2n} + a_{2n}) && S_{2n-1} = S_{2n} + a_{2n}\\ &= \lim_{n\to\infty} S_{2n} + \lim_{n\to\infty} a_{2n} && \text{Property of limits}\\ &= L + \lim_{n\to\infty} a_{2n}\\ &= L.\end{aligned}$$

Because both S_{2n} and S_{2n-1} converge to the same limit L, it follows that $\{S_n\}$ also converges to L. Consequently, the given alternating series converges. A similar proof can be made for $\sum_{n=1}^{\infty}(-1)^n a_n$. ∎

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

EXAMPLE 1 Using the Alternating Series Test

REMARK The series in Example 1 is called the *alternating harmonic series*. More is said about this series in Example 8.

Determine the convergence or divergence of

$$\sum_{n=1}^{\infty} (-1)^{n+1} \frac{1}{n}.$$

Solution Note that $\lim_{x\to\infty} a_n = \lim_{n\to\infty} (1/n) = 0$. So, the first condition of Theorem 9.14 is satisfied. Also note that the second condition of Theorem 9.14 is satisfied because

$$a_{n+1} = \frac{1}{n+1} \leq \frac{1}{n} = a_n$$

for all n. So, by the Alternating Series Test, the series converges.

EXAMPLE 2 Using the Alternating Series Test

Determine the convergence or divergence of

$$\sum_{n=1}^{\infty} \frac{n}{(-2)^{n-1}}.$$

Solution To apply the Alternating Series Test, note that, for $n \geq 1$,

$$\begin{aligned} \frac{1}{2} &\leq \frac{n}{n+1} \\ \frac{2^{n-1}}{2^n} &\leq \frac{n}{n+1} \\ (n+1)2^{n-1} &\leq n2^n \\ \frac{n+1}{2^n} &\leq \frac{n}{2^{n-1}}. \end{aligned}$$

So, $a_{n+1} = (n+1)/2^n \leq n/2^{n-1} = a_n$ for all n. Furthermore, by L'Hôpital's Rule,

$$\lim_{x\to\infty} \frac{x}{2^{x-1}} = \lim_{x\to\infty} \frac{1}{2^{x-1}(\ln 2)} = 0 \quad \Rightarrow \quad \lim_{n\to\infty} \frac{n}{2^{n-1}} = 0.$$

Therefore, by the Alternating Series Test, the series converges.

EXAMPLE 3 When the Alternating Series Test Does Not Apply

REMARK In Example 3(a), remember that whenever a series does not satisfy the first condition of the Alternating Series Test, you can use the nth-Term Test for Divergence to conclude that the series diverges.

a. The alternating series

$$\sum_{n=1}^{\infty} \frac{(-1)^{n+1}(n+1)}{n} = \frac{2}{1} - \frac{3}{2} + \frac{4}{3} - \frac{5}{4} + \frac{6}{5} - \cdots$$

satisfies the second condition of the Alternating Series Test because $a_{n+1} \leq a_n$ for all n. You cannot apply the Alternating Series Test, however, because the series does not satisfy the first condition. In fact, the series diverges.

b. The alternating series

$$\frac{2}{1} - \frac{1}{1} + \frac{2}{2} - \frac{1}{2} + \frac{2}{3} - \frac{1}{3} + \frac{2}{4} - \frac{1}{4} + \cdots$$

satisfies the first condition because a_n approaches 0 as $n \to \infty$. You cannot apply the Alternating Series Test, however, because the series does not satisfy the second condition. To conclude that the series diverges, you can argue that S_{2N} equals the Nth partial sum of the divergent harmonic series. This implies that the sequence of partial sums diverges. So, the series diverges. ■

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Alternating Series Remainder

For a convergent alternating series, the partial sum S_N can be a useful approximation for the sum S of the series. The error involved in using $S \approx S_N$ is the remainder $R_N = S - S_N$.

THEOREM 9.15 Alternating Series Remainder

If a convergent alternating series satisfies the condition $a_{n+1} \leq a_n$, then the absolute value of the remainder R_N involved in approximating the sum S by S_N is less than (or equal to) the first neglected term. That is,

$$|S - S_N| = |R_N| \leq a_{N+1}.$$

A proof of this theorem is given in Appendix A.

EXAMPLE 4 Approximating the Sum of an Alternating Series

See LarsonCalculus.com for an interactive version of this type of example.

Approximate the sum of the series by its first six terms.

$$\sum_{n=1}^{\infty} (-1)^{n+1}\left(\frac{1}{n!}\right) = \frac{1}{1!} - \frac{1}{2!} + \frac{1}{3!} - \frac{1}{4!} + \frac{1}{5!} - \frac{1}{6!} + \cdots$$

Solution The series converges by the Alternating Series Test because

$$\frac{1}{(n+1)!} \leq \frac{1}{n!} \quad \text{and} \quad \lim_{n\to\infty} \frac{1}{n!} = 0.$$

The sum of the first six terms is

$$S_6 = 1 - \frac{1}{2} + \frac{1}{6} - \frac{1}{24} + \frac{1}{120} - \frac{1}{720} = \frac{91}{144} \approx 0.63194$$

and, by the Alternating Series Remainder, you have

$$|S - S_6| = |R_6| \leq a_7 = \frac{1}{5040} \approx 0.0002.$$

So, the sum S lies between $0.63194 - 0.0002$ and $0.63194 + 0.0002$, and you have $0.63174 \leq S \leq 0.63214$.

TECHNOLOGY

Later, using the techniques in Section 9.10, you will be able to show that the series in Example 4 converges to

$$\frac{e-1}{e} \approx 0.63212.$$

(See Section 9.10, Exercise 58.) For now, try using a graphing utility to obtain an approximation of the sum of the series. How many terms do you need to obtain an approximation that is within 0.00001 of the actual sum?

EXAMPLE 5 Finding the Number of Terms

Determine the number of terms required to approximate the sum of the series with an error of less than 0.001.

$$\sum_{n=1}^{\infty} \frac{(-1)^{n+1}}{n^4}$$

Solution By Theorem 9.15, you know that

$$|R_N| \leq a_{N+1} = \frac{1}{(N+1)^4}.$$

For an error of less than 0.001, N must satisfy the inequality $1/(N+1)^4 < 0.001$.

$$\frac{1}{(N+1)^4} < 0.001 \quad \Rightarrow \quad (N+1)^4 > 1000 \quad \Rightarrow \quad N > \sqrt[4]{1000} - 1 \approx 4.6$$

So, you will need at least five terms. Using five terms, the sum is $S \approx S_5 \approx 0.94754$, which has an error of less than 0.001.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Absolute and Conditional Convergence

Occasionally, a series may have both positive and negative terms and not be an alternating series. For instance, the series

$$\sum_{n=1}^{\infty} \frac{\sin n}{n^2} = \frac{\sin 1}{1} + \frac{\sin 2}{4} + \frac{\sin 3}{9} + \cdots$$

has both positive and negative terms, yet it is not an alternating series. One way to obtain some information about the convergence of this series is to investigate the convergence of the series

$$\sum_{n=1}^{\infty} \left| \frac{\sin n}{n^2} \right|.$$

By direct comparison, you have $|\sin n| \leq 1$ for all n, so

$$\left| \frac{\sin n}{n^2} \right| \leq \frac{1}{n^2}, \quad n \geq 1.$$

Therefore, by the Direct Comparison Test, the series $\Sigma\, |(\sin n)/n^2|$ converges. The next theorem tells you that the original series also converges.

THEOREM 9.16 Absolute Convergence

If the series $\Sigma\, |a_n|$ converges, then the series $\Sigma\, a_n$ also converges.

Proof Because $0 \leq a_n + |a_n| \leq 2|a_n|$ for all n, the series

$$\sum_{n=1}^{\infty} (a_n + |a_n|)$$

converges by comparison with the convergent series

$$\sum_{n=1}^{\infty} 2|a_n|.$$

Furthermore, because $a_n = (a_n + |a_n|) - |a_n|$, you can write

$$\sum_{n=1}^{\infty} a_n = \sum_{n=1}^{\infty} (a_n + |a_n|) - \sum_{n=1}^{\infty} |a_n|$$

where both series on the right converge. So, it follows that $\Sigma\, a_n$ converges. ∎

The converse of Theorem 9.16 is not true. For instance, the **alternating harmonic series**

$$\sum_{n=1}^{\infty} \frac{(-1)^{n+1}}{n} = \frac{1}{1} - \frac{1}{2} + \frac{1}{3} - \frac{1}{4} + \cdots$$

converges by the Alternating Series Test. Yet the harmonic series diverges. This type of convergence is called **conditional.**

Definitions of Absolute and Conditional Convergence

1. The series $\Sigma\, a_n$ is **absolutely convergent** when $\Sigma\, |a_n|$ converges.
2. The series $\Sigma\, a_n$ is **conditionally convergent** when $\Sigma\, a_n$ converges but $\Sigma\, |a_n|$ diverges.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 6 Absolute and Conditional Convergence

Determine whether each of the series is convergent or divergent. Classify any convergent series as absolutely or conditionally convergent.

a. $\displaystyle\sum_{n=0}^{\infty} \frac{(-1)^n n!}{2^n} = \frac{0!}{2^0} - \frac{1!}{2^1} + \frac{2!}{2^2} - \frac{3!}{2^3} + \cdots$

b. $\displaystyle\sum_{n=1}^{\infty} \frac{(-1)^n}{\sqrt{n}} = -\frac{1}{\sqrt{1}} + \frac{1}{\sqrt{2}} - \frac{1}{\sqrt{3}} + \frac{1}{\sqrt{4}} - \cdots$

Solution

a. This is an alternating series, but the Alternating Series Test does not apply because the limit of the nth term is not zero. By the nth-Term Test for Divergence, however, you can conclude that this series diverges.

b. This series can be shown to be convergent by the Alternating Series Test. Moreover, because the p-series

$$\sum_{n=1}^{\infty} \left|\frac{(-1)^n}{\sqrt{n}}\right| = \frac{1}{\sqrt{1}} + \frac{1}{\sqrt{2}} + \frac{1}{\sqrt{3}} + \frac{1}{\sqrt{4}} + \cdots$$

diverges, the given series is *conditionally* convergent.

EXAMPLE 7 Absolute and Conditional Convergence

Determine whether each of the series is convergent or divergent. Classify any convergent series as absolutely or conditionally convergent.

a. $\displaystyle\sum_{n=1}^{\infty} \frac{(-1)^{n(n+1)/2}}{3^n} = -\frac{1}{3} - \frac{1}{9} + \frac{1}{27} + \frac{1}{81} - \cdots$

b. $\displaystyle\sum_{n=1}^{\infty} \frac{(-1)^n}{\ln(n+1)} = -\frac{1}{\ln 2} + \frac{1}{\ln 3} - \frac{1}{\ln 4} + \frac{1}{\ln 5} - \cdots$

Solution

a. This is *not* an alternating series (the signs change in pairs). However, note that

$$\sum_{n=1}^{\infty} \left|\frac{(-1)^{n(n+1)/2}}{3^n}\right| = \sum_{n=1}^{\infty} \frac{1}{3^n}$$

is a convergent geometric series, with

$$r = \frac{1}{3}.$$

Consequently, by Theorem 9.16, you can conclude that the given series is *absolutely* convergent (and therefore convergent).

b. In this case, the Alternating Series Test indicates that the series converges. However, the series

$$\sum_{n=1}^{\infty} \left|\frac{(-1)^n}{\ln(n+1)}\right| = \frac{1}{\ln 2} + \frac{1}{\ln 3} + \frac{1}{\ln 4} + \cdots$$

diverges by direct comparison with the terms of the harmonic series. Therefore, the given series is *conditionally* convergent. ■

■ **FOR FURTHER INFORMATION** To read more about the convergence of alternating harmonic series, see the article "Almost Alternating Harmonic Series" by Curtis Feist and Ramin Naimi in *The College Mathematics Journal*. To view this article, go to *MathArticles.com*.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Rearrangement of Series

A finite sum such as

$$1 + 3 - 2 + 5 - 4$$

can be rearranged without changing the value of the sum. This is not necessarily true of an infinite series—it depends on whether the series is absolutely convergent or conditionally convergent.

1. If a series is *absolutely convergent,* then its terms can be rearranged in any order without changing the sum of the series.
2. If a series is *conditionally convergent,* then its terms can be rearranged to give a different sum.

The second case is illustrated in Example 8.

EXAMPLE 8 **Rearrangement of a Series**

FOR FURTHER INFORMATION Georg Friedrich Bernhard Riemann (1826–1866) proved that if $\Sigma\, a_n$ is conditionally convergent and S is any real number, then the terms of the series can be rearranged to converge to S. For more on this topic, see the article "Riemann's Rearrangement Theorem" by Stewart Galanor in *Mathematics Teacher.* To view this article, go to *MathArticles.com.*

The alternating harmonic series converges to ln 2. That is,

$$\sum_{n=1}^{\infty} (-1)^{n+1}\frac{1}{n} = \frac{1}{1} - \frac{1}{2} + \frac{1}{3} - \frac{1}{4} + \cdots = \ln 2.$$

See Exercise 55, Section 9.10.

Rearrange the terms of the series to produce a different sum.

Solution Consider the rearrangement below.

$$\begin{aligned}
&1 - \frac{1}{2} - \frac{1}{4} + \frac{1}{3} - \frac{1}{6} - \frac{1}{8} + \frac{1}{5} - \frac{1}{10} - \frac{1}{12} + \frac{1}{7} - \frac{1}{14} - \cdots \\
&= \left(1 - \frac{1}{2}\right) - \frac{1}{4} + \left(\frac{1}{3} - \frac{1}{6}\right) - \frac{1}{8} + \left(\frac{1}{5} - \frac{1}{10}\right) - \frac{1}{12} + \left(\frac{1}{7} - \frac{1}{14}\right) - \cdots \\
&= \frac{1}{2} - \frac{1}{4} + \frac{1}{6} - \frac{1}{8} + \frac{1}{10} - \frac{1}{12} + \frac{1}{14} - \cdots \\
&= \frac{1}{2}\left(1 - \frac{1}{2} + \frac{1}{3} - \frac{1}{4} + \frac{1}{5} - \frac{1}{6} + \frac{1}{7} - \cdots\right) \\
&= \frac{1}{2}(\ln 2)
\end{aligned}$$

By rearranging the terms, you obtain a sum that is half the original sum. ■

Exploration

In Example 8, you learned that the alternating harmonic series

$$\sum_{n=1}^{\infty} (-1)^{n+1}\frac{1}{n} = 1 - \frac{1}{2} + \frac{1}{3} - \frac{1}{4} + \frac{1}{5} - \frac{1}{6} + \cdots$$

converges to $\ln 2 \approx 0.693$. Rearrangement of the terms of the series produces a different sum, $\frac{1}{2}\ln 2 \approx 0.347$.

Below, the terms of the alternating harmonic series have been rearranged in such a way that two positive terms follow each negative term.

$$1 - \frac{1}{2} + \frac{1}{3} + \frac{1}{5} - \frac{1}{4} + \frac{1}{7} + \frac{1}{9} - \frac{1}{6} + \frac{1}{11} + \cdots$$

Calculate the partial sums S_4, S_7, S_{10}, S_{13}, S_{16}, and S_{19}. Then estimate the sum of this series to three decimal places.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

9.5 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. An alternating series does not meet the first condition of the Alternating Series Test. What can you conclude about the convergence or divergence of the series? Explain.
2. What is the remainder of a convergent alternating series whose sum is approximated by the first N terms?
3. Describe the difference between absolute and conditional convergence of an alternating series.
4. Explain whether rearranging the terms of a convergent series changes the sum of the series.

Numerical and Graphical Analysis **In Exercises 5–8, explore the Alternating Series Remainder.**

(a) Use a graphing utility to find the indicated partial sum S_n and complete the table.

n	1	2	3	4	5	6	7	8	9	10
S_n										

(b) Use a graphing utility to graph the first 10 terms of the sequence of partial sums and a horizontal line representing the sum.

(c) What pattern exists between the plot of the successive points in part (b) relative to the horizontal line representing the sum of the series? Do the distances between the successive points and the horizontal line increase or decrease?

(d) Discuss the relationship between the answers in part (c) and the Alternating Series Remainder as given in Theorem 9.15.

5. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n-1}}{2n-1}=\frac{\pi}{4}$

6. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n-1}}{(n-1)!}=\frac{1}{e}$

7. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n-1}}{n^2}=\frac{\pi^2}{12}$

8. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n-1}}{(2n-1)!}=\sin 1$

Determining Convergence or Divergence **In Exercises 9–30, determine the convergence or divergence of the series.**

9. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n+1}}{n+1}$

10. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n+1}\,n}{3n+2}$

11. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n}}{3^n}$

12. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n}}{e^n}$

13. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n}(5n-1)}{4n+1}$

14. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n+1}\,n}{n^2+5}$

15. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n}\,n}{\ln(n+1)}$

16. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n}}{\ln(n+1)}$

17. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n}}{\sqrt{n}}$

18. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n+1}\,n^2}{n^2+4}$

19. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n+1}(n+1)}{\ln(n+1)}$

20. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n+1}\ln(n+1)}{n+1}$

21. $\displaystyle\sum_{n=1}^{\infty}\sin\frac{(2n-1)\pi}{2}$

22. $\displaystyle\sum_{n=1}^{\infty}\frac{1}{n}\cos n\pi$

23. $\displaystyle\sum_{n=0}^{\infty}\frac{(-1)^{n}}{n!}$

24. $\displaystyle\sum_{n=0}^{\infty}\frac{(-1)^{n}}{(2n+1)!}$

25. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n+1}\sqrt{n}}{n+2}$

26. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n+1}\sqrt{n}}{\sqrt[3]{n}}$

27. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n+1}\,n!}{1\cdot 3\cdot 5\cdot\cdots\cdot(2n-1)}$

28. $\displaystyle\sum_{n=1}^{\infty}(-1)^{n+1}\frac{1\cdot 3\cdot 5\cdot\cdots\cdot(2n-1)}{1\cdot 4\cdot 7\cdot\cdots\cdot(3n-2)}$

29. $\displaystyle\sum_{n=1}^{\infty}\frac{2(-1)^{n+1}}{e^n-e^{-n}}=\sum_{n=1}^{\infty}(-1)^{n+1}\operatorname{csch} n$

30. $\displaystyle\sum_{n=1}^{\infty}\frac{2(-1)^{n+1}}{e^n+e^{-n}}=\sum_{n=1}^{\infty}(-1)^{n+1}\operatorname{sech} n$

Approximating the Sum of an Alternating Series **In Exercises 31–34, approximate the sum of the series by using the first six terms. (See Example 4.)**

31. $\displaystyle\sum_{n=0}^{\infty}\frac{(-1)^{n}\,5}{n!}$

32. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n+1}\,4}{\ln(n+1)}$

33. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n+1}\,2}{n^3}$

34. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n+1}\,n}{3^n}$

Finding the Number of Terms **In Exercises 35–40, use Theorem 9.15 to determine the number of terms required to approximate the sum of the series with an error of less than 0.001.**

35. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n+1}}{n^3}$

36. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n+1}}{n^2}$

37. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n+1}}{2n^3-1}$

38. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n+1}}{n^5}$

39. $\displaystyle\sum_{n=0}^{\infty}\frac{(-1)^{n}}{n!}$

40. $\displaystyle\sum_{n=0}^{\infty}\frac{(-1)^{n}}{(2n)!}$

Determining Absolute and Conditional Convergence **In Exercises 41–58, determine whether the series converges absolutely or conditionally, or diverges.**

41. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n}}{2^n}$

42. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n+1}}{n^2}$

43. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n}}{n!}$

44. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n+1}}{n+3}$

45. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n+1}}{\sqrt{n}}$

46. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n+1}}{n\sqrt{n}}$

47. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n+1}\,n^2}{(n+1)^2}$

48. $\displaystyle\sum_{n=1}^{\infty}\frac{(-1)^{n+1}n}{5n+1}$

49. $\displaystyle\sum_{n=2}^{\infty}\frac{(-1)^{n}}{n\ln n}$

50. $\displaystyle\sum_{n=0}^{\infty}(-1)^{n}\,e^{-n^2}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

51. $\sum_{n=2}^{\infty} \frac{(-1)^n n}{n^3 - 5}$

52. $\sum_{n=1}^{\infty} \frac{(-1)^{n+1}}{n^{4/3}}$

53. $\sum_{n=0}^{\infty} \frac{(-1)^n}{(2n+1)!}$

54. $\sum_{n=0}^{\infty} \frac{(-1)^n}{\sqrt{n+4}}$

55. $\sum_{n=0}^{\infty} \frac{\cos n\pi}{n+1}$

56. $\sum_{n=1}^{\infty} (-1)^{n+1} \arctan n$

57. $\sum_{n=1}^{\infty} \frac{\cos(n\pi/3)}{n^2}$

58. $\sum_{n=1}^{\infty} \frac{\sin[(2n-1)\pi/2]}{n}$

Exploring Concepts

59. Determine whether S_{50} is an underestimate or an overestimate of the sum of the alternating series below. Explain.

$$\sum_{n=1}^{\infty} \frac{(-1)^n}{n}$$

60. Give an example of convergent alternating series Σa_n and Σb_n such that $\Sigma a_n b_n$ diverges.

61. Do you agree with the following statements? Why or why not?

(a) If both Σa_n and $\Sigma(-a_n)$ converge, then $\Sigma |a_n|$ converges.

(b) If Σa_n diverges, then $\Sigma |a_n|$ diverges.

62. HOW DO YOU SEE IT? The graphs of the sequences of partial sums of two series are shown in the figures. Which graph represents the partial sums of an alternating series? Explain.

(a)



(b)



Finding Values **In Exercises 63 and 64, find the values of p for which the series converges.**

63. $\sum_{n=1}^{\infty} (-1)^n \left(\frac{1}{n^p}\right)$

64. $\sum_{n=1}^{\infty} (-1)^n \left(\frac{1}{n+p}\right)$

65. Proof Prove that if $\Sigma |a_n|$ converges, then Σa_n^2 converges. Is the converse true? If not, give an example that shows it is false.

66. Finding a Series Use the result of Exercise 63 to give an example of an alternating p-series that converges but whose corresponding p-series diverges.

67. Finding Values Find all values of x for which the series

$$\sum_{n=1}^{\infty} \frac{x^n}{n}$$

(a) converges absolutely and (b) converges conditionally.

68. Using a Series Use the series for $\ln 2$ in Example 8 to show that

$$2 = \frac{e^1}{e^{1/2}} \cdot \frac{e^{1/3}}{e^{1/4}} \cdot \frac{e^{1/5}}{e^{1/6}} \cdot \frac{e^{1/7}}{e^{1/8}} \cdot \cdots$$

Using a Series **In Exercises 69 and 70, use the given series.**

(a) Does the series meet the conditions of Theorem 9.14? Explain why or why not.

(b) Does the series converge? If so, what is the sum?

69. $\frac{1}{2} - \frac{1}{3} + \frac{1}{4} - \frac{1}{9} + \frac{1}{8} - \frac{1}{27} + \cdots + \frac{1}{2^n} - \frac{1}{3^n} + \cdots$

70. $\sum_{n=1}^{\infty} (-1)^{n+1} a_n,\ a_n = \begin{cases} \frac{1}{\sqrt{n}}, & \text{if } n \text{ is odd} \\ \frac{1}{n^3}, & \text{if } n \text{ is even} \end{cases}$

Review **In Exercises 71–80, determine the convergence or divergence of the series and identify the test used.**

71. $\sum_{n=1}^{\infty} \frac{8}{\sqrt[3]{n}}$

72. $\sum_{n=1}^{\infty} \frac{3n+5}{n^3 + 2n^2 + 4}$

73. $\sum_{n=1}^{\infty} \frac{3^n}{n^2}$

74. $\sum_{n=1}^{\infty} \frac{1}{6^n - 5}$

75. $\sum_{n=1}^{\infty} \left(\frac{9}{8}\right)^n$

76. $\sum_{n=1}^{\infty} \frac{2n^2}{(n+1)^2}$

77. $\sum_{n=1}^{\infty} 100e^{-n/2}$

78. $\sum_{n=0}^{\infty} \frac{(-1)^n}{n+4}$

79. $\sum_{n=1}^{\infty} \frac{(-1)^{n+1} 4}{3n^2 - 1}$

80. $\sum_{n=2}^{\infty} \frac{\ln n}{n}$

81. Describing an Error The following argument, that $0 = 1$, is *incorrect*. Describe the error.

$$\begin{aligned} 0 &= 0 + 0 + 0 + \cdots \\ &= (1 - 1) + (1 - 1) + (1 - 1) + \cdots \\ &= 1 + (-1 + 1) + (-1 + 1) + \cdots \\ &= 1 + 0 + 0 + \cdots \\ &= 1 \end{aligned}$$

PUTNAM EXAM CHALLENGE

82. Assume as known the (true) fact that the alternating harmonic series

(1) $1 - \frac{1}{2} + \frac{1}{3} - \frac{1}{4} + \frac{1}{5} - \frac{1}{6} + \frac{1}{7} - \frac{1}{8} + \cdots$

is convergent, and denote its sum by s. Rearrange the series (1) as follows:

(2) $1 + \frac{1}{3} - \frac{1}{2} + \frac{1}{5} + \frac{1}{7} - \frac{1}{4} + \frac{1}{9} + \frac{1}{11} - \frac{1}{6} + \cdots$.

Assume as known the (true) fact that the series (2) is also convergent, and denote its sum by S. Denote by s_k, S_k the kth partial sum of the series (1) and (2), respectively. Prove the following statements.

(i) $S_{3n} = s_{4n} + \frac{1}{2}s_{2n}$, (ii) $S \neq s$

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

9.6 The Ratio and Root Tests

GO DIGITAL

- Use the Ratio Test to determine whether a series converges or diverges.
- Use the Root Test to determine whether a series converges or diverges.
- Apply the guidelines for testing a series for convergence or divergence.

The Ratio Test

This section begins with a test for absolute convergence—the **Ratio Test.**

THEOREM 9.17 Ratio Test

Let Σa_n be a series with nonzero terms.

1. The series Σa_n converges absolutely when $\lim_{n\to\infty} \left|\frac{a_{n+1}}{a_n}\right| < 1$.
2. The series Σa_n diverges when $\lim_{n\to\infty} \left|\frac{a_{n+1}}{a_n}\right| > 1$ or $\lim_{n\to\infty} \left|\frac{a_{n+1}}{a_n}\right| = \infty$.
3. The Ratio Test is inconclusive when $\lim_{n\to\infty} \left|\frac{a_{n+1}}{a_n}\right| = 1$.

REMARK The Ratio Test is always inconclusive for any p-series.

Proof To prove Property 1, assume that

$$\lim_{n\to\infty} \left|\frac{a_{n+1}}{a_n}\right| = r < 1$$

and choose R such that $0 \le r < R < 1$. By the definition of the limit of a sequence, there exists some $N > 0$ such that $|a_{n+1}/a_n| < R$ for all $n > N$. Therefore,

$$|a_{N+1}| < |a_N|R$$
$$|a_{N+2}| < |a_{N+1}|R < |a_N|R^2$$
$$|a_{N+3}| < |a_{N+2}|R < |a_{N+1}|R^2 < |a_N|R^3$$

and so on. The geometric series

$$\sum_{n=1}^{\infty} |a_N|R^n = |a_N|R + |a_N|R^2 + |a_N|R^3 + \cdots + |a_N|R^n + \cdots$$

converges, and so, by the Direct Comparison Test, the series

$$\sum_{n=1}^{\infty} |a_{N+n}| = |a_{N+1}| + |a_{N+2}| + |a_{N+3}| + \cdots + |a_{N+n}| + \cdots$$

also converges. This in turn implies that the series $\Sigma |a_n|$ converges, because discarding a finite number of terms $(n = N - 1)$ does not affect convergence. Consequently, by Theorem 9.16, the series Σa_n converges absolutely. The proof of Property 2 is similar and is left as an exercise (see Exercise 97).

When applying the Ratio Test, note that when the limit of $|a_{n+1}/a_n|$ as $n \to \infty$ is 1, the test is inconclusive. For example, consider the two series $\Sigma (1/n)$ and $\Sigma (1/n^2)$. The first series diverges and the second one converges, but in both cases

$$\lim_{n\to\infty} \left|\frac{a_{n+1}}{a_n}\right| = 1.$$ Limit is 1. Ratio Test is inconclusive.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Although the Ratio Test is not a cure for all ills related to testing for convergence, it is particularly useful for series that *converge rapidly*. Series involving factorials or exponentials are frequently of this type.

EXAMPLE 1 Using the Ratio Test

Determine the convergence or divergence of $\sum_{n=0}^{\infty} \frac{2^n}{n!}$.

Solution Recall from Section 9.1 that the factorial function grows faster than any exponential function. So, you expect this series to converge. Note that the series has nonzero terms. So, you can apply the Ratio Test with

$$a_n = \frac{2^n}{n!} \quad \text{and} \quad a_{n+1} = \frac{2^{n+1}}{(n+1)!}$$

to obtain

$$\begin{aligned}
\lim_{n\to\infty} \left|\frac{a_{n+1}}{a_n}\right| &= \lim_{n\to\infty} \left[\frac{2^{n+1}}{(n+1)!} \div \frac{2^n}{n!}\right] \\
&= \lim_{n\to\infty} \left[\frac{2^{n+1}}{(n+1)!} \cdot \frac{n!}{2^n}\right] && \text{Invert and multiply.} \\
&= \lim_{n\to\infty} \frac{2}{n+1} \\
&= 0. && \text{Limit is less than 1. The series converges.}
\end{aligned}$$

The limit is less than 1, so by the Ratio Test, the series converges.

REMARK Although the Ratio Test is listed with an index that begins with $n = 1$, it can be applied to an infinite series that begins with any other nonnegative integer, such as $n = 0$.

REMARK A step frequently used in applications of the Ratio Test involves simplifying quotients of factorials. In Example 1, for instance, notice that

$$\frac{n!}{(n+1)!} = \frac{n!}{(n+1)n!} = \frac{1}{n+1}.$$

EXAMPLE 2 Using the Ratio Test

Determine whether each series converges or diverges.

a. $\sum_{n=0}^{\infty} \frac{n^2\, 2^{n+1}}{3^n}$ **b.** $\sum_{n=1}^{\infty} \frac{n^n}{n!}$

Solution

a. This series converges because the limit of $|a_{n+1}/a_n|$ as $n \to \infty$ is less than 1.

$$\begin{aligned}
\lim_{n\to\infty} \left|\frac{a_{n+1}}{a_n}\right| &= \lim_{n\to\infty} \left[(n+1)^2 \left(\frac{2^{n+2}}{3^{n+1}}\right)\left(\frac{3^n}{n^2\, 2^{n+1}}\right)\right] \\
&= \lim_{n\to\infty} \frac{2(n+1)^2}{3n^2} \\
&= \frac{2}{3} && \text{Limit is less than 1. The series converges.}
\end{aligned}$$

b. This series diverges because the limit of $|a_{n+1}/a_n|$ as $n \to \infty$ is greater than 1.

$$\begin{aligned}
\lim_{n\to\infty} \left|\frac{a_{n+1}}{a_n}\right| &= \lim_{n\to\infty} \left[\frac{(n+1)^{n+1}}{(n+1)!}\left(\frac{n!}{n^n}\right)\right] \\
&= \lim_{n\to\infty} \left[\frac{(n+1)^{n+1}}{(n+1)}\left(\frac{1}{n^n}\right)\right] \\
&= \lim_{n\to\infty} \frac{(n+1)^n}{n^n} \\
&= \lim_{n\to\infty} \left(1 + \frac{1}{n}\right)^n \\
&= e && \text{Limit is greater than 1. The series diverges.}
\end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 3 A Failure of the Ratio Test

See LarsonCalculus.com for an interactive version of this type of example.

Determine the convergence or divergence of

$$\sum_{n=1}^{\infty} (-1)^n \frac{\sqrt{n}}{n+1}.$$

Solution The limit of $|a_{n+1}/a_n|$ as $n \to \infty$ is equal to 1.

$$\begin{aligned}\lim_{n\to\infty} \left|\frac{a_{n+1}}{a_n}\right| &= \lim_{n\to\infty} \left[\left(\frac{\sqrt{n+1}}{n+2}\right)\left(\frac{n+1}{\sqrt{n}}\right)\right] \\ &= \lim_{n\to\infty} \left[\sqrt{\frac{n+1}{n}}\left(\frac{n+1}{n+2}\right)\right] \\ &= \sqrt{1}\,(1) \\ &= 1\end{aligned}$$

The limit is 1, so the Ratio Test is inconclusive. To determine whether the series converges or diverges, you need to try a different test. In this case, you can apply the Alternating Series Test. To show that $a_{n+1} \le a_n$, let

$$f(x) = \frac{\sqrt{x}}{x+1}.$$

Then the derivative is

$$f'(x) = \frac{-x+1}{2\sqrt{x}(x+1)^2}.$$

The derivative is negative for $x > 1$, so f is a decreasing function. Also, by L'Hôpital's Rule,

$$\begin{aligned}\lim_{x\to\infty} \frac{\sqrt{x}}{x+1} &= \lim_{x\to\infty} \frac{1/(2\sqrt{x})}{1} \\ &= \lim_{x\to\infty} \frac{1}{2\sqrt{x}} \\ &= 0.\end{aligned}$$

Therefore, by the Alternating Series Test, the series converges. ■

The series in Example 3 is *conditionally convergent.* This follows from the fact that the series

$$\sum_{n=1}^{\infty} \left|(-1)^n \frac{\sqrt{n}}{n+1}\right| = \frac{1}{2} + \frac{\sqrt{2}}{3} + \frac{\sqrt{3}}{4} + \frac{\sqrt{4}}{5} + \frac{\sqrt{5}}{6} + \cdots \qquad \Sigma|a_n|$$

diverges (by the Limit Comparison Test with $\Sigma\, 1/\sqrt{n}$), but the series

$$\sum_{n=1}^{\infty} (-1)^n \frac{\sqrt{n}}{n+1} = -\frac{1}{2} + \frac{\sqrt{2}}{3} - \frac{\sqrt{3}}{4} + \frac{\sqrt{4}}{5} - \frac{\sqrt{5}}{6} + \cdots \qquad \Sigma\, a_n$$

converges.

TECHNOLOGY A graphing utility can reinforce the conclusion that the series in Example 3 converges *conditionally*. By adding the first 100 terms of the series, you obtain a sum of about -0.2. (The sum of the first 100 terms of the series $\Sigma\, |a_n|$ is about 16.9.)

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The Root Test

The next test for convergence or divergence of series works especially well for series involving nth powers. The proof of this theorem is similar to the proof given for the Ratio Test and is left as an exercise (see Exercise 98).

REMARK The Root Test is always inconclusive for any p-series.

THEOREM 9.18 Root Test

1. The series Σa_n converges absolutely when $\lim_{n\to\infty} \sqrt[n]{|a_n|} < 1$.
2. The series Σa_n diverges when $\lim_{n\to\infty} \sqrt[n]{|a_n|} > 1$ or $\lim_{n\to\infty} \sqrt[n]{|a_n|} = \infty$.
3. The Root Test is inconclusive when $\lim_{n\to\infty} \sqrt[n]{|a_n|} = 1$.

EXAMPLE 4 Using the Root Test

Determine the convergence or divergence of

$$\sum_{n=1}^{\infty} \frac{e^{2n}}{n^n}.$$

Solution Apply the Root Test with $a_n = e^{2n}/n^n$.

$$\begin{aligned}\lim_{n\to\infty} \sqrt[n]{|a_n|} &= \lim_{n\to\infty} \sqrt[n]{\frac{e^{2n}}{n^n}} \\ &= \lim_{n\to\infty} \frac{e^{2n/n}}{n^{n/n}} \\ &= \lim_{n\to\infty} \frac{e^2}{n} \\ &= 0\end{aligned}$$

Because this limit is less than 1, you can conclude that the series converges absolutely (and therefore converges). ■

To appreciate the usefulness of the Root Test for the series in Example 4, consider applying the Ratio Test to that series. When you do this, you obtain

$$\begin{aligned}\lim_{n\to\infty} \left|\frac{a_{n+1}}{a_n}\right| &= \lim_{n\to\infty} \left[\frac{e^{2(n+1)}}{(n+1)^{n+1}} \div \frac{e^{2n}}{n^n}\right] \\ &= \lim_{n\to\infty} \left[\frac{e^{2(n+1)}}{(n+1)^{n+1}} \cdot \frac{n^n}{e^{2n}}\right] \qquad \text{Invert and multiply.} \\ &= \lim_{n\to\infty} e^2 \frac{n^n}{(n+1)^{n+1}} \\ &= \lim_{n\to\infty} e^2 \left(\frac{n}{n+1}\right)^n \left(\frac{1}{n+1}\right) \\ &= 0.\end{aligned}$$

Note that this limit is not as easily evaluated as the limit obtained by the Root Test in Example 4.

■ **FOR FURTHER INFORMATION** For more information on the usefulness of the Root Test, see the article "$N!$ and the Root Test" by Charles C. Mumma II in *The American Mathematical Monthly*. To view this article, go to *MathArticles.com*.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Guidelines for Testing Series

You have studied 10 tests for determining the convergence or divergence of an infinite series. (See the summary in the table on the next page.) Skill in choosing and applying the various tests will come only with practice. Below is a set of guidelines for choosing an appropriate test.

Guidelines for Testing a Series for Convergence or Divergence

1. Does the nth term approach 0? If not, the series diverges.
2. Is the series one of the special types—geometric, p-series, telescoping, or alternating?
3. Can the Integral Test, the Root Test, or the Ratio Test be applied?
4. Can the series be compared favorably to one of the special types?

In some instances, more than one test is applicable. Your objective, however, should be to choose the most efficient test.

EXAMPLE 5 Applying the Guidelines for Testing Series

Determine the convergence or divergence of each series.

a. $\sum_{n=1}^{\infty} \frac{n+1}{3n+1}$ **b.** $\sum_{n=1}^{\infty} \left(\frac{\pi}{6}\right)^n$ **c.** $\sum_{n=1}^{\infty} ne^{-n^2}$

d. $\sum_{n=1}^{\infty} \frac{1}{3n+1}$ **e.** $\sum_{n=1}^{\infty} (-1)^n \frac{3}{4n+1}$ **f.** $\sum_{n=1}^{\infty} \frac{n!}{10^n}$

g. $\sum_{n=1}^{\infty} \left(\frac{n+1}{2n+1}\right)^n$

Solution

a. For this series, the limit of the nth term is not 0 $\left(a_n \to \frac{1}{3} \text{ as } n \to \infty\right)$. So, by the nth-Term Test, the series diverges.

b. This series is geometric. Moreover, because the ratio of the terms

$$r = \frac{\pi}{6}$$

is less than 1 in absolute value, you can conclude that the series converges.

c. Because the function

$$f(x) = xe^{-x^2}$$

is easily integrated, you can use the Integral Test to conclude that the series converges.

d. The nth term of this series can be compared to the nth term of the harmonic series. After using the Limit Comparison Test, you can conclude that the series diverges.

e. This is an alternating series whose nth term approaches 0. Because $a_{n+1} \leq a_n$, you can use the Alternating Series Test to conclude that the series converges.

f. The nth term of this series involves a factorial, which indicates that the Ratio Test may work well. After applying the Ratio Test, you can conclude that the series diverges.

g. The nth term of this series involves a variable that is raised to the nth power, which indicates that the Root Test may work well. After applying the Root Test, you can conclude that the series converges. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Summary of Tests for Series

Test	Series	Condition(s) of Convergence	Condition(s) of Divergence	Comment
nth-Term	$\sum_{n=1}^{\infty} a_n$		$\lim_{n\to\infty} a_n \neq 0$	This test cannot be used to show convergence.
Geometric Series ($r \neq 0$)	$\sum_{n=0}^{\infty} ar^n$	$\lvert r\rvert < 1$	$\lvert r\rvert \geq 1$	Sum: $S = \frac{a}{1-r}$
Telescoping Series	$\sum_{n=1}^{\infty} (b_n - b_{n+1})$	$\lim_{n\to\infty} b_n = L$		Sum: $S = b_1 - L$
p-Series	$\sum_{n=1}^{\infty} \frac{1}{n^p}$	$p > 1$	$0 < p \leq 1$	
Alternating Series ($a_n > 0$)	$\sum_{n=1}^{\infty} (-1)^{n-1} a_n$	$a_{n+1} \leq a_n$ and $\lim_{n\to\infty} a_n = 0$		Remainder: $\lvert R_N\rvert \leq a_{N+1}$
Integral (f is continuous, positive, and decreasing)	$\sum_{n=1}^{\infty} a_n$, $a_n = f(n) \geq 0$	$\int_1^{\infty} f(x)\,dx$ converges	$\int_1^{\infty} f(x)\,dx$ diverges	Remainder: $0 < R_N < \int_N^{\infty} f(x)\,dx$
Root	$\sum_{n=1}^{\infty} a_n$	$\lim_{n\to\infty} \sqrt[n]{\lvert a_n\rvert} < 1$	$\lim_{n\to\infty} \sqrt[n]{\lvert a_n\rvert} > 1$ or $= \infty$	Test is inconclusive when $\lim_{n\to\infty} \sqrt[n]{\lvert a_n\rvert} = 1$.
Ratio	$\sum_{n=1}^{\infty} a_n$	$\lim_{n\to\infty} \left\lvert \frac{a_{n+1}}{a_n} \right\rvert < 1$	$\lim_{n\to\infty} \left\lvert \frac{a_{n+1}}{a_n} \right\rvert > 1$ or $= \infty$	Test is inconclusive when $\lim_{n\to\infty} \left\lvert \frac{a_{n+1}}{a_n} \right\rvert = 1$.
Direct Comparison ($a_n, b_n > 0$)	$\sum_{n=1}^{\infty} a_n$	$0 < a_n \leq b_n$ and $\sum_{n=1}^{\infty} b_n$ converges	$0 < b_n \leq a_n$ and $\sum_{n=1}^{\infty} b_n$ diverges	
Limit Comparison ($a_n, b_n > 0$)	$\sum_{n=1}^{\infty} a_n$	$\lim_{n\to\infty} \frac{a_n}{b_n} = L > 0$ and $\sum_{n=1}^{\infty} b_n$ converges	$\lim_{n\to\infty} \frac{a_n}{b_n} = L > 0$ and $\sum_{n=1}^{\infty} b_n$ diverges	

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

9.6 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

In Exercises 1–6, what can you conclude about the convergence or divergence of $\sum a_n$?

1. $\lim_{n\to\infty} \left|\frac{a_{n+1}}{a_n}\right| = 0$
2. $\lim_{n\to\infty} \left|\frac{a_{n+1}}{a_n}\right| = 1$
3. $\lim_{n\to\infty} \left|\frac{a_{n+1}}{a_n}\right| = \frac{3}{2}$
4. $\lim_{n\to\infty} \sqrt[n]{|a_n|} = 2$
5. $\lim_{n\to\infty} \sqrt[n]{|a_n|} = 1$
6. $\lim_{n\to\infty} \sqrt[n]{|a_n|} = e$

Verifying a Formula **In Exercises 7 and 8, verify the formula.**

7. $\frac{9^{n+1}(n-1)!}{9^n(n-2)!} = 9(n-1)$
8. $\frac{(2k-2)!}{(2k)!} = \frac{1}{(2k)(2k-1)}$

Matching **In Exercises 9–14, match the series with the graph of its sequence of partial sums. [The graphs are labeled (a), (b), (c), (d), (e), and (f).]**

(a)



(b)



(c)



(d)



(e)



(f)



9. $\sum_{n=1}^{\infty} n\left(\frac{3}{4}\right)^n$
10. $\sum_{n=1}^{\infty} \left(\frac{3}{4}\right)^n\left(\frac{1}{n!}\right)$
11. $\sum_{n=1}^{\infty} \frac{(-3)^{n+1}}{n!}$
12. $\sum_{n=1}^{\infty} \frac{(-1)^{n-1}\,4}{(2n)!}$
13. $\sum_{n=1}^{\infty} \left(\frac{4n}{5n-3}\right)^n$
14. $\sum_{n=0}^{\infty} 4e^{-n}$

Numerical, Graphical, and Analytic Analysis **In Exercises 15 and 16, (a) use the Ratio Test to verify that the series converges, (b) use a graphing utility to find the indicated partial sum S_n and complete the table, (c) use a graphing utility to graph the first 10 terms of the sequence of partial sums, (d) use the table to estimate the sum of the series, and (e) explain the relationship between the magnitudes of the terms of the series and the rate at which the sequence of partial sums approaches the sum of the series.**

n	5	10	15	20	25
S_n					

15. $\sum_{n=1}^{\infty} n^3\left(\frac{1}{2}\right)^n$
16. $\sum_{n=1}^{\infty} \frac{n^2+1}{n!}$

Using the Ratio Test **In Exercises 17–38, use the Ratio Test to determine the convergence or divergence of the series. If the Ratio Test is inconclusive, determine the convergence or divergence of the series using other methods.**

17. $\sum_{n=1}^{\infty} \frac{1}{8^n}$
18. $\sum_{n=1}^{\infty} \frac{5}{n!}$
19. $\sum_{n=1}^{\infty} \frac{(n-1)!}{4^n}$
20. $\sum_{n=0}^{\infty} \frac{2^n}{(n+2)!}$
21. $\sum_{n=0}^{\infty} (n+2)\left(\frac{9}{7}\right)^{n+1}$
22. $\sum_{n=1}^{\infty} n^2\left(\frac{5}{6}\right)^n$
23. $\sum_{n=1}^{\infty} \frac{9^n}{n^5}$
24. $\sum_{n=0}^{\infty} \frac{6^n}{(n+1)^3}$
25. $\sum_{n=1}^{\infty} \frac{n^3}{3^n}$
26. $\sum_{n=1}^{\infty} \frac{(-1)^{n+1}(n+2)}{n(n+1)}$
27. $\sum_{n=0}^{\infty} \frac{(-1)^n\,2^n}{n!}$
28. $\sum_{n=1}^{\infty} \frac{(-1)^{n-1}(3/2)^n}{n^2}$
29. $\sum_{n=1}^{\infty} \frac{n^2}{(n+1)(n^2+2)}$
30. $\sum_{n=1}^{\infty} \frac{(2n)!}{n^5}$
31. $\sum_{n=0}^{\infty} \frac{e^n}{n!}$
32. $\sum_{n=1}^{\infty} \frac{n!}{n^n}$
33. $\sum_{n=0}^{\infty} \frac{6^n}{(n+1)^n}$
34. $\sum_{n=0}^{\infty} \frac{(n!)^2}{(3n)!}$
35. $\sum_{n=0}^{\infty} \frac{5^n}{2^n+1}$
36. $\sum_{n=0}^{\infty} \frac{(-1)^n 2^{4n}}{(2n+1)!}$
37. $\sum_{n=0}^{\infty} \frac{(-1)^{n+1}n!}{1\cdot 3\cdot 5\cdot\cdots\cdot(2n+1)}$
38. $\sum_{n=1}^{\infty} \frac{(-1)^n[2\cdot 4\cdot 6\cdot\cdots\cdot(2n)]}{2\cdot 5\cdot 8\cdot\cdots\cdot(3n-1)}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Using the Root Test **In Exercises 39–52, use the Root Test to determine the convergence or divergence of the series.**

39. $\sum_{n=1}^{\infty} \left(\frac{n}{2n+1}\right)^n$
40. $\sum_{n=1}^{\infty} \frac{1}{n^n}$
41. $\sum_{n=1}^{\infty} \left(\frac{3n+2}{n+3}\right)^n$
42. $\sum_{n=1}^{\infty} \left(\frac{n-2}{5n+1}\right)^n$
43. $\sum_{n=2}^{\infty} \frac{(-1)^n}{(\ln n)^n}$
44. $\sum_{n=1}^{\infty} \left(\frac{-3n}{2n+1}\right)^{3n}$
45. $\sum_{n=1}^{\infty} \left(2\sqrt[n]{n}+1\right)^n$
46. $\sum_{n=0}^{\infty} e^{-3n}$
47. $\sum_{n=1}^{\infty} \frac{n}{3^n}$
48. $\sum_{n=1}^{\infty} \left(\frac{n}{500}\right)^n$
49. $\sum_{n=1}^{\infty} \left(\frac{1}{n}-\frac{1}{n^2}\right)^n$
50. $\sum_{n=1}^{\infty} \left(\frac{\ln n}{n}\right)^n$
51. $\sum_{n=2}^{\infty} \frac{n}{(\ln n)^n}$
52. $\sum_{n=1}^{\infty} \frac{(n!)^n}{(n^n)^2}$

Determining Convergence or Divergence **In Exercises 53–70, determine the convergence or divergence of the series using any appropriate test from this chapter. Identify the test used.**

53. $\sum_{n=1}^{\infty} \frac{(-1)^{n+1}5}{n}$
54. $\sum_{n=1}^{\infty} \frac{100}{n}$
55. $\sum_{n=1}^{\infty} \frac{3}{n\sqrt{n}}$
56. $\sum_{n=1}^{\infty} \left(\frac{2\pi}{3}\right)^n$
57. $\sum_{n=1}^{\infty} \frac{5n}{2n-1}$
58. $\sum_{n=1}^{\infty} \frac{n}{2n^2+1}$
59. $\sum_{n=1}^{\infty} \frac{(-1)^n 3^{n-2}}{2^n}$
60. $\sum_{n=1}^{\infty} \frac{10}{3\sqrt{n^3}}$
61. $\sum_{n=1}^{\infty} \frac{10n+3}{n2^n}$
62. $\sum_{n=1}^{\infty} \frac{2^n}{4n^2-1}$
63. $\sum_{n=1}^{\infty} \frac{\cos n}{3^n}$
64. $\sum_{n=2}^{\infty} \frac{(-1)^n}{n \ln n}$
65. $\sum_{n=1}^{\infty} \frac{n!}{n7^n}$
66. $\sum_{n=1}^{\infty} \frac{\ln n}{n^2}$
67. $\sum_{n=1}^{\infty} \frac{(-1)^n 3^{n-1}}{n!}$
68. $\sum_{n=1}^{\infty} \frac{(-1)^n 3^n}{n2^n}$
69. $\sum_{n=1}^{\infty} \frac{(-3)^n}{3 \cdot 5 \cdot 7 \cdot \cdots \cdot (2n+1)}$
70. $\sum_{n=1}^{\infty} \frac{3 \cdot 5 \cdot 7 \cdot \cdots \cdot (2n+1)}{18^n(2n-1)n!}$

Identifying Series **In Exercises 71–74, identify the two series that are the same.**

71. (a) $\sum_{n=1}^{\infty} \frac{n5^n}{n!}$
(b) $\sum_{n=0}^{\infty} \frac{n5^n}{(n+1)!}$
(c) $\sum_{n=0}^{\infty} \frac{(n+1)5^{n+1}}{(n+1)!}$

72. (a) $\sum_{n=4}^{\infty} n\left(\frac{3}{4}\right)^n$
(b) $\sum_{n=0}^{\infty} (n+1)\left(\frac{3}{4}\right)^n$
(c) $\sum_{n=1}^{\infty} n\left(\frac{3}{4}\right)^{n-1}$

73. (a) $\sum_{n=0}^{\infty} \frac{(-1)^n}{(2n+1)!}$
(b) $\sum_{n=1}^{\infty} \frac{(-1)^{n-1}}{(2n-1)!}$
(c) $\sum_{n=1}^{\infty} \frac{(-1)^{n-1}}{(2n+1)!}$

74. (a) $\sum_{n=2}^{\infty} \frac{(-1)^n}{(n-1)2^{n-1}}$
(b) $\sum_{n=1}^{\infty} \frac{(-1)^{n+1}}{n2^n}$
(c) $\sum_{n=0}^{\infty} \frac{(-1)^{n+1}}{(n+1)2^n}$

Writing an Equivalent Series **In Exercises 75 and 76, write an equivalent series with the index of summation beginning at $n = 0$.**

75. $\sum_{n=1}^{\infty} \frac{n}{7^n}$
76. $\sum_{n=2}^{\infty} \frac{4^{n+1}}{(n-2)!}$

Using a Recursively Defined Series **In Exercises 77–82, the terms of a series $\sum_{n=1}^{\infty} a_n$ are defined recursively. Determine the convergence or divergence of the series. Explain your reasoning.**

77. $a_1 = \frac{1}{2}, a_{n+1} = \frac{4n-1}{3n+2}a_n$
78. $a_1 = 2, a_{n+1} = \frac{2n+1}{5n-4}a_n$
79. $a_1 = 1, a_{n+1} = \frac{\sin n + 1}{\sqrt{n}}a_n$
80. $a_1 = \frac{1}{5}, a_{n+1} = \frac{\cos n + 1}{n}a_n$
81. $a_1 = \frac{1}{3}, a_{n+1} = \left(1+\frac{1}{n}\right)a_n$
82. $a_1 = \frac{1}{4}, a_{n+1} = \sqrt[n]{a_n}$

Using the Ratio Test or Root Test **In Exercises 83–86, use the Ratio Test or the Root Test to determine the convergence or divergence of the series.**

83. $1 + \frac{1 \cdot 2}{1 \cdot 3} + \frac{1 \cdot 2 \cdot 3}{1 \cdot 3 \cdot 5} + \frac{1 \cdot 2 \cdot 3 \cdot 4}{1 \cdot 3 \cdot 5 \cdot 7} + \cdots$
84. $1 + \frac{2}{3} + \frac{3}{3^2} + \frac{4}{3^3} + \frac{5}{3^4} + \frac{6}{3^5} + \cdots$
85. $\frac{1}{(\ln 3)^3} + \frac{1}{(\ln 4)^4} + \frac{1}{(\ln 5)^5} + \frac{1}{(\ln 6)^6} + \cdots$
86. $1 + \frac{1 \cdot 3}{1 \cdot 2 \cdot 3} + \frac{1 \cdot 3 \cdot 5}{1 \cdot 2 \cdot 3 \cdot 4 \cdot 5} + \frac{1 \cdot 3 \cdot 5 \cdot 7}{1 \cdot 2 \cdot 3 \cdot 4 \cdot 5 \cdot 6 \cdot 7} + \cdots$

Finding Values **In Exercises 87–92, find the values of x for which the series converges.**

87. $\sum_{n=0}^{\infty} 2\left(\frac{x}{3}\right)^n$
88. $\sum_{n=0}^{\infty} \left(\frac{x-3}{5}\right)^n$
89. $\sum_{n=1}^{\infty} \frac{(-1)^n(x+1)^n}{n}$
90. $\sum_{n=0}^{\infty} 3(x-4)^n$
91. $\sum_{n=0}^{\infty} n!\left(\frac{x}{2}\right)^n$
92. $\sum_{n=0}^{\infty} \frac{(x+1)^n}{n!}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploring Concepts

93. What can you conclude about the convergence or divergence of Σa_n using the Ratio Test when a_n is a rational function of n? Explain.

94. Describe two ways to show that the geometric series

$$\sum_{n=0}^{\infty} ar^n, \quad r \neq 0$$

converges when $|r| < 1$. Verify that both methods give the same result.

95. You are told that the terms of a positive series appear to approach zero rapidly as n approaches infinity. In fact, $a_7 \leq 0.0001$. Given no other information, does this imply that the series converges? Support your conclusion with examples.

96. HOW DO YOU SEE IT? The graphs show the sequences of partial sums of the series

$$\sum_{n=1}^{\infty} \frac{2^n}{n} \quad \text{and} \quad \sum_{n=1}^{\infty} \frac{n}{3^n}.$$

Using the Ratio Test, the first series diverges and the second series converges. Explain how the graphs show this.



97. Proof Prove Property 2 of Theorem 9.17.

98. Proof Prove Theorem 9.18. (*Hint for Property 1:* If the limit equals $r < 1$, choose a real number R such that $r < R < 1$. By the definitions of the limit, there exists some $N > 0$ such that $\sqrt[n]{|a_n|} < R$ for $n > N$.)

Verifying an Inconclusive Test **In Exercises 99–102, verify that the Ratio Test is inconclusive for the *p*-series.**

99. $\displaystyle\sum_{n=1}^{\infty} \frac{1}{n^{3/2}}$

100. $\displaystyle\sum_{n=1}^{\infty} \frac{1}{n^{0.05}}$

101. $\displaystyle\sum_{n=1}^{\infty} \frac{1}{n^4}$

102. $\displaystyle\sum_{n=1}^{\infty} \frac{1}{n^p}$

103. Verifying an Inconclusive Test Show that the Root Test is inconclusive for the p-series

$$\sum_{n=1}^{\infty} \frac{1}{n^p}.$$

104. Verifying Inconclusive Tests Show that the Ratio Test and the Root Test are both inconclusive for the logarithmic p-series

$$\sum_{n=2}^{\infty} \frac{1}{n(\ln n)^p}.$$

105. Using Values Determine the convergence or divergence of the series

$$\sum_{n=1}^{\infty} \frac{(n!)^2}{(xn)!}$$

when (a) $x = 1$, (b) $x = 2$, (c) $x = 3$, and (d) x is a positive integer.

106. Using a Series Show that if

$$\sum_{n=1}^{\infty} a_n$$

is absolutely convergent, then

$$\left|\sum_{n=1}^{\infty} a_n\right| \leq \sum_{n=1}^{\infty} |a_n|.$$

107. Proof Let $\{a_n\}$ be a sequence of positive numbers satisfying

$$\lim_{n\to\infty} (a_n)^{1/n} = L < \frac{1}{r}, \quad r > 0.$$

Prove that the series $\displaystyle\sum_{n=1}^{\infty} a_n r^n$ converges.

108. Using a Series Consider the infinite series $\displaystyle\sum_{n=1}^{\infty} \frac{1}{2^{n+(-1)^n}}$.

(a) Find the first five terms of the sequence of partial sums.

(b) Show that the Ratio Test is inconclusive for this series.

(c) Use the Root Test to determine the convergence or divergence of this series.

PUTNAM EXAM CHALLENGE

109. Show that if the series

$$a_1 + a_2 + a_3 + \cdots + a_n + \cdots$$

converges, then the series

$$a_1 + \frac{a_2}{2} + \frac{a_3}{3} + \cdots + \frac{a_n}{n} + \cdots$$

converges also.

110. Is the following series convergent or divergent?

$$1 + \frac{1}{2} \cdot \frac{19}{7} + \frac{2!}{3^2}\left(\frac{19}{7}\right)^2 + \frac{3!}{4^3}\left(\frac{19}{7}\right)^3 + \frac{4!}{5^4}\left(\frac{19}{7}\right)^4 + \cdots$$

These problems were composed by the Committee on the Putnam Prize Competition. © The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

9.7 Taylor Polynomials and Approximations

GO DIGITAL

- **Find polynomial approximations of elementary functions and compare them with the elementary functions.**
- **Find Taylor and Maclaurin polynomial approximations of elementary functions.**
- **Use the remainder of a Taylor polynomial to determine the accuracy of an approximation.**

Polynomial Approximations of Elementary Functions

The goal of this section is to show how polynomial functions can be used as approximations for other elementary functions. To find a polynomial function P that approximates another function f, begin by choosing a number c in the domain of f at which f and P have the same value. That is,

$$P(c) = f(c). \qquad \text{Graphs of } f \text{ and } P \text{ pass through } (c, f(c)).$$

The approximating polynomial is said to be **expanded about c** or **centered at c.** Geometrically, the requirement that $P(c) = f(c)$ means that the graph of P passes through the point $(c, f(c))$. Of course, there are many polynomials whose graphs pass through the point $(c, f(c))$. Your task is to find a polynomial whose graph resembles the graph of f near this point. One way to do this is to impose the additional requirement that the slope of the polynomial function be the same as the slope of the graph of f at the point $(c, f(c))$.

$$P'(c) = f'(c) \qquad \text{Graphs of } f \text{ and } P \text{ have the same slope at } (c, f(c)).$$

With these two requirements, you can obtain a simple linear approximation of f, as shown in Figure 9.12.



Near $(c, f(c))$, the graph of P can be used to approximate the graph of f.
Figure 9.12

REMARK Example 1 is not the first time you have used a linear function to approximate another function. The same procedure was used as the basis for Newton's Method.

EXAMPLE 1 **First-Degree Polynomial Approximation of $f(x) = e^x$**

For the function $f(x) = e^x$, find a first-degree polynomial function $P_1(x) = a_0 + a_1x$ whose value and slope agree with the value and slope of f at $x = 0$.

Solution Because $f(x) = e^x$ and $f'(x) = e^x$, the value and the slope of f at $x = 0$ are

$$f(0) = e^0 = 1 \qquad \text{Value of } f \text{ at } x = 0$$

and

$$f'(0) = e^0 = 1. \qquad \text{Slope of } f \text{ at } x = 0$$

Because $P_1(x) = a_0 + a_1x$, use the condition that $P_1(0) = f(0)$ to conclude that $a_0 = 1$. Moreover, because $P_1'(x) = a_1$, use the condition that $P_1'(0) = f'(0)$ to conclude that $a_1 = 1$. So, $P_1(x) = 1 + x$. The figure shows the graphs of $P_1(x) = 1 + x$ and $f(x) = e^x$.



P_1 is the first-degree polynomial approximation of $f(x) = e^x$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



P_2 is the second-degree polynomial approximation of $f(x) = e^x$.
Figure 9.13

Figure 9.13 shows that, at points near $(0, 1)$, the graph of the first-degree polynomial function

$$P_1(x) = 1 + x \qquad \text{1st-degree approximation}$$

is reasonably close to the graph of $f(x) = e^x$. As you move away from $(0, 1)$, however, the graphs move farther and farther from each other and the accuracy of the approximation decreases. To improve the approximation, you can impose yet another requirement—that the values of the second derivatives of P and f agree when $x = 0$. The polynomial, P_2, of least degree that satisfies all three requirements $P_2(0) = f(0)$, $P_2'(0) = f'(0)$, and $P_2''(0) = f''(0)$ is

$$P_2(x) = 1 + x + \frac{1}{2}x^2. \qquad \text{2nd-degree approximation}$$

Moreover, Figure 9.13 shows that P_2 is a better approximation of f than P_1. By requiring that the values of $P_n(x)$ and its first n derivatives match those of $f(x) = e^x$ at $x = 0$, you obtain the nth-degree approximation shown below.

$$P_n(x) = 1 + x + \frac{1}{2}x^2 + \frac{1}{3!}x^3 + \cdots + \frac{1}{n!}x^n \qquad n\text{th-degree approximation}$$
$$\approx e^x$$

EXAMPLE 2 Third-Degree Polynomial Approximation of $f(x) = e^x$

Construct a table comparing the values of the polynomial

$$P_3(x) = 1 + x + \frac{1}{2}x^2 + \frac{1}{3!}x^3 \qquad \text{3rd-degree approximation}$$

with $f(x) = e^x$ for several values of x near 0.

Solution Use a calculator to obtain the results shown in the table. Note that for $x = 0$, the two functions have the same value, but that as x moves farther away from 0, the accuracy of the approximating polynomial $P_3(x)$ decreases.

x	-1	-0.2	-0.1	0	0.1	0.2	1
e^x	0.3679	0.81873	0.904837	1	1.105171	1.22140	2.7183
$P_3(x)$	0.3333	0.81867	0.904833	1	1.105167	1.22133	2.6667



P_3 is the third-degree polynomial approximation of $f(x) = e^x$.
Figure 9.14

TECHNOLOGY A graphing utility can be used to compare the graph of the approximating polynomial with the graph of the function f. For instance, in Figure 9.14, the graph of

$$P_3(x) = 1 + x + \tfrac{1}{2}x^2 + \tfrac{1}{6}x^3 \qquad \text{3rd-degree approximation}$$

is compared with the graph of $f(x) = e^x$. Use a graphing utility to compare the graphs of

$$P_4(x) = 1 + x + \tfrac{1}{2}x^2 + \tfrac{1}{6}x^3 + \tfrac{1}{24}x^4 \qquad \text{4th-degree approximation}$$
$$P_5(x) = 1 + x + \tfrac{1}{2}x^2 + \tfrac{1}{6}x^3 + \tfrac{1}{24}x^4 + \tfrac{1}{120}x^5 \qquad \text{5th-degree approximation}$$

and

$$P_6(x) = 1 + x + \tfrac{1}{2}x^2 + \tfrac{1}{6}x^3 + \tfrac{1}{24}x^4 + \tfrac{1}{120}x^5 + \tfrac{1}{720}x^6 \qquad \text{6th-degree approximation}$$

with the graph of f. What do you notice?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

BROOK TAYLOR (1685–1731)

Although Taylor was not the first to seek polynomial approximations of transcendental functions, his account published in 1715 was one of the first comprehensive works on the subject.

See LarsonCalculus.com to read more of this biography.

Taylor and Maclaurin Polynomials

The polynomial approximation of

$$f(x) = e^x$$

in Example 2 is expanded about $c = 0$. For expansions about an arbitrary value of c, it is convenient to write the polynomial in the form

$$P_n(x) = a_0 + a_1(x - c) + a_2(x - c)^2 + a_3(x - c)^3 + \cdots + a_n(x - c)^n.$$

In this form, repeated differentiation produces

$$\begin{aligned}
P_n'(x) &= a_1 + 2a_2(x - c) + 3a_3(x - c)^2 + \cdots + na_n(x - c)^{n-1} \\
P_n''(x) &= 2a_2 + 2(3a_3)(x - c) + \cdots + n(n - 1)a_n(x - c)^{n-2} \\
P_n'''(x) &= 2(3a_3) + \cdots + n(n - 1)(n - 2)a_n(x - c)^{n-3} \\
&\vdots \\
P_n^{(n)}(x) &= n(n - 1)(n - 2) \cdots (2)(1)a_n.
\end{aligned}$$

Letting $x = c$, you then obtain

$$P_n(c) = a_0, \quad P_n'(c) = a_1, \quad P_n''(c) = 2a_2, \quad \ldots, \quad P_n^{(n)}(c) = n!a_n$$

and because the values of f and its first n derivatives must agree with the values of P_n and its first n derivatives at $x = c$, it follows that

$$f(c) = a_0, \quad f'(c) = a_1, \quad \frac{f''(c)}{2!} = a_2, \quad \ldots, \quad \frac{f^{(n)}(c)}{n!} = a_n.$$

In the definition below, these coefficients are used to define **Taylor polynomials,** named after the English mathematician Brook Taylor, and **Maclaurin polynomials,** named after the Scottish mathematician Colin Maclaurin (1698–1746).

Definitions of *n*th Taylor Polynomial and *n*th Maclaurin Polynomial

If f has n derivatives at c, then the polynomial

$$P_n(x) = f(c) + f'(c)(x - c) + \frac{f''(c)}{2!}(x - c)^2 + \cdots + \frac{f^{(n)}(c)}{n!}(x - c)^n$$

is called the ***n*th Taylor polynomial for f at c.** If $c = 0$, then

$$P_n(x) = f(0) + f'(0)x + \frac{f''(0)}{2!}x^2 + \frac{f'''(0)}{3!}x^3 + \cdots + \frac{f^{(n)}(0)}{n!}x^n$$

is also called the ***n*th Maclaurin polynomial for f.**

REMARK Maclaurin polynomials are special types of Taylor polynomials for which $c = 0$.

EXAMPLE 3 A Maclaurin Polynomial for $f(x) = e^x$

From the discussion on the preceding page, the nth Maclaurin polynomial for $f(x) = e^x$ is given by

$$P_n(x) = 1 + x + \frac{1}{2!}x^2 + \frac{1}{3!}x^3 + \cdots + \frac{1}{n!}x^n.$$

FOR FURTHER INFORMATION To learn how to use series to obtain other approximations to e, see the article "Novel Series-based Approximations to e" by John Knox and Harlan J. Brothers in *The College Mathematics Journal.* To view this article, go to *MathArticles.com.*

The Picture Art Collection/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 4 Finding Taylor Polynomials for ln *x*

Find the Taylor polynomials P_0, P_1, P_2, P_3, and P_4 for

$$f(x) = \ln x$$

centered at $c = 1$.

Solution Begin by expanding about $c = 1$. To do this, find the first four derivatives of f. Then evaluate f and each derivative at $c = 1$.

$f(x) = \ln x$	$f(1) = \ln 1 = 0$	Original function
$f'(x) = \frac{1}{x}$	$f'(1) = \frac{1}{1} = 1$	First derivative
$f''(x) = -\frac{1}{x^2}$	$f''(1) = -\frac{1}{1^2} = -1$	Second derivative
$f'''(x) = \frac{2!}{x^3}$	$f'''(1) = \frac{2!}{1^3} = 2$	Third derivative
$f^{(4)}(x) = -\frac{3!}{x^4}$	$f^{(4)}(1) = -\frac{3!}{1^4} = -6$	Fourth derivative

So, the Taylor polynomials are as follows.

$$P_0(x) = f(1) = 0$$

$$P_1(x) = f(1) + f'(1)(x - 1) = (x - 1)$$

$$P_2(x) = f(1) + f'(1)(x - 1) + \frac{f''(1)}{2!}(x - 1)^2$$

$$= (x - 1) - \frac{1}{2}(x - 1)^2$$

$$P_3(x) = f(1) + f'(1)(x - 1) + \frac{f''(1)}{2!}(x - 1)^2 + \frac{f'''(1)}{3!}(x - 1)^3$$

$$= (x - 1) - \frac{1}{2}(x - 1)^2 + \frac{1}{3}(x - 1)^3$$

$$P_4(x) = f(1) + f'(1)(x - 1) + \frac{f''(1)}{2!}(x - 1)^2 + \frac{f'''(1)}{3!}(x - 1)^3 + \frac{f^{(4)}(1)}{4!}(x - 1)^4$$

$$= (x - 1) - \frac{1}{2}(x - 1)^2 + \frac{1}{3}(x - 1)^3 - \frac{1}{4}(x - 1)^4$$

Figure 9.15 compares the graphs of P_1, P_2, P_3, and P_4 with the graph of $f(x) = \ln x$. Note that near $x = 1$, the graphs are nearly indistinguishable. For instance,

$$P_4(1.1) \approx 0.0953083 \quad \text{and} \quad \ln(1.1) \approx 0.0953102.$$



As n increases, the graph of P_n becomes a better and better approximation of the graph of $f(x) = \ln x$ near $x = 1$.

Figure 9.15

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



Near (0, 1), the graph of P_6 can be used to approximate the graph of $f(x) = \cos x$.
Figure 9.16

EXAMPLE 5 Finding Maclaurin Polynomials for cos *x*

Find the Maclaurin polynomials P_0, P_2, P_4, and P_6 for $f(x) = \cos x$. Use $P_6(x)$ to approximate the value of $\cos(0.1)$.

Solution Begin by expanding about $c = 0$.

$$\begin{aligned} f(x) &= \cos x & f(0) &= \cos 0 = 1 \\ f'(x) &= -\sin x & f'(0) &= -\sin 0 = 0 \\ f''(x) &= -\cos x & f''(0) &= -\cos 0 = -1 \\ f'''(x) &= \sin x & f'''(0) &= \sin 0 = 0 \end{aligned}$$

Through repeated differentiation, the pattern $1, 0, -1, 0$ continues. So, you can write the Maclaurin polynomials

$$P_0(x) = 1, \quad P_2(x) = 1 - \frac{1}{2!}x^2, \quad P_4(x) = 1 - \frac{1}{2!}x^2 + \frac{1}{4!}x^4,$$

and

$$P_6(x) = 1 - \frac{1}{2!}x^2 + \frac{1}{4!}x^4 - \frac{1}{6!}x^6.$$

To nine decimal places, the approximation

$$P_6(0.1) \approx 0.995004165$$

is the same as $\cos(0.1)$. Figure 9.16 compares the graphs of $f(x) = \cos x$ and P_6. ■

Note in Example 5 that the Maclaurin polynomials for $\cos x$ have only even powers of x. Similarly, the Maclaurin polynomials for $\sin x$ have only odd powers of x (see Exercise 19). This is not generally true of the Taylor polynomials for $\sin x$ and $\cos x$ expanded about $c \neq 0$, as shown in the next example.

EXAMPLE 6 Finding a Taylor Polynomial for sin *x*

See LarsonCalculus.com for an interactive version of this type of example.

Find the third Taylor polynomial for $f(x) = \sin x$, expanded about $c = \pi/6$.

Solution Begin by expanding about $c = \pi/6$.

$$\begin{aligned} f(x) &= \sin x & f\left(\frac{\pi}{6}\right) &= \sin\frac{\pi}{6} = \frac{1}{2} \\ f'(x) &= \cos x & f'\left(\frac{\pi}{6}\right) &= \cos\frac{\pi}{6} = \frac{\sqrt{3}}{2} \\ f''(x) &= -\sin x & f''\left(\frac{\pi}{6}\right) &= -\sin\frac{\pi}{6} = -\frac{1}{2} \\ f'''(x) &= -\cos x & f'''\left(\frac{\pi}{6}\right) &= -\cos\frac{\pi}{6} = -\frac{\sqrt{3}}{2} \end{aligned}$$

So, the third Taylor polynomial for $f(x) = \sin x$, expanded about $c = \pi/6$, is

$$\begin{aligned} P_3(x) &= f\left(\frac{\pi}{6}\right) + f'\left(\frac{\pi}{6}\right)\left(x - \frac{\pi}{6}\right) + \frac{f''\left(\frac{\pi}{6}\right)}{2!}\left(x - \frac{\pi}{6}\right)^2 + \frac{f'''\left(\frac{\pi}{6}\right)}{3!}\left(x - \frac{\pi}{6}\right)^3 \\ &= \frac{1}{2} + \frac{\sqrt{3}}{2}\left(x - \frac{\pi}{6}\right) - \frac{1}{2(2!)}\left(x - \frac{\pi}{6}\right)^2 - \frac{\sqrt{3}}{2(3!)}\left(x - \frac{\pi}{6}\right)^3. \end{aligned}$$

Figure 9.17 compares the graphs of $f(x) = \sin x$ and P_3. ■



Near $(\pi/6, 1/2)$, the graph of P_3 can be used to approximate the graph of $f(x) = \sin x$.
Figure 9.17

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Taylor polynomials and Maclaurin polynomials can be used to approximate the value of a function at a specific point. For instance, to approximate the value of $\ln(1.1)$, you can use Taylor polynomials for $f(x) = \ln x$ expanded about $c = 1$, as shown in Example 4, or you can use Maclaurin polynomials, as shown in Example 7.

EXAMPLE 7 Approximation Using Maclaurin Polynomials

Use a fourth Maclaurin polynomial to approximate the value of $\ln(1.1)$.

Solution Because 1.1 is closer to 1 than to 0, you should consider Maclaurin polynomials for the function $g(x) = \ln(1 + x)$.

$$\begin{aligned} g(x) &= \ln(1 + x) & g(0) &= \ln(1 + 0) = 0 \\ g'(x) &= (1 + x)^{-1} & g'(0) &= (1 + 0)^{-1} = 1 \\ g''(x) &= -(1 + x)^{-2} & g''(0) &= -(1 + 0)^{-2} = -1 \\ g'''(x) &= 2(1 + x)^{-3} & g'''(0) &= 2(1 + 0)^{-3} = 2 \\ g^{(4)}(x) &= -6(1 + x)^{-4} & g^{(4)}(0) &= -6(1 + 0)^{-4} = -6 \end{aligned}$$

Note that you obtain the same coefficients as in Example 4. So, the fourth Maclaurin polynomial for $g(x) = \ln(1 + x)$ is

$$\begin{aligned} P_4(x) &= g(0) + g'(0)x + \frac{g''(0)}{2!}x^2 + \frac{g'''(0)}{3!}x^3 + \frac{g^{(4)}(0)}{4!}x^4 \\ &= x - \frac{1}{2}x^2 + \frac{1}{3}x^3 - \frac{1}{4}x^4. \end{aligned}$$

Consequently,

$$\ln(1.1) = \ln(1 + 0.1) \approx P_4(0.1) \approx 0.0953083.$$

REMARK Check that the fourth Taylor polynomial from Example 4, evaluated at $x = 1.1$, yields the same result as the fourth Maclaurin polynomial in Example 7.

The table below illustrates the accuracy of the Maclaurin polynomial approximation of the calculator value of $\ln(1.1)$. The table shows that as n increases, $P_n(0.1)$ approaches the value of $\ln(1.1) \approx 0.0953102$.

Maclaurin Polynomial Approximations of $\ln(1 + x)$ at $x = 0.1$

n	1	2	3	4
$P_n(0.1)$	0.1000000	0.0950000	0.0953333	0.0953083

On the other hand, the table below illustrates that as you move away from the expansion point $c = 0$, the accuracy of the approximation decreases.

Fourth Maclaurin Polynomial Approximations of $\ln(1 + x)$

x	0	0.1	0.5	0.75	1.0
$\ln(1 + x)$	0	0.0953102	0.4054651	0.5596158	0.6931472
$P_4(x)$	0	0.0953083	0.4010417	0.5302734	0.5833333

These two tables illustrate two very important points about the accuracy of Taylor (or Maclaurin) polynomials for use in approximations.

1. The approximation is usually better for higher-degree Taylor (or Maclaurin) polynomials than for those of lower degree.
2. The approximation is usually better at x-values close to c than at x-values far from c.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Remainder of a Taylor Polynomial

An approximation technique is of little value without some idea of its accuracy. To measure the accuracy of approximating a function value $f(x)$ by the Taylor polynomial $P_n(x)$, you can use the concept of a **remainder** $R_n(x)$, defined as follows.

$$f(x) = P_n(x) + R_n(x)$$

Exact value — Approximate value — Remainder

So, $R_n(x) = f(x) - P_n(x)$. The absolute value of $R_n(x)$ is called the **error** associated with the approximation. That is,

$$\text{Error} = |R_n(x)| = |f(x) - P_n(x)|.$$

The next theorem gives a general procedure for estimating the remainder associated with a Taylor polynomial. This important theorem is called **Taylor's Theorem,** and the remainder given in the theorem is called the **Lagrange form of the remainder.**

THEOREM 9.19 Taylor's Theorem

If a function f is differentiable through order $n + 1$ in an interval I containing c, then, for each x in I, there exists z between x and c such that

$$f(x) = f(c) + f'(c)(x - c) + \frac{f''(c)}{2!}(x - c)^2 + \cdots + \frac{f^{(n)}(c)}{n!}(x - c)^n + R_n(x)$$

where

$$R_n(x) = \frac{f^{(n+1)}(z)}{(n + 1)!}(x - c)^{n+1}.$$

A proof of this theorem is given in Appendix A.

REMARK In Exercise 74, you are asked to show that the *integral form* of the remainder R_n is given by

$$\frac{1}{n!}\int_c^x (x - t)^n f^{(n+1)}(t)\, dt.$$

One useful consequence of Taylor's Theorem is that

$$|R_n(x)| \leq \frac{|x - c|^{n+1}}{(n + 1)!} \max |f^{(n+1)}(z)|$$

where $\max|f^{(n+1)}(z)|$ is the maximum value of $f^{(n+1)}(z)$ between x and c.

For $n = 0$, Taylor's Theorem states that if f is differentiable in an interval I containing c, then, for each x in I, there exists z between x and c such that

$$f(x) = f(c) + f'(z)(x - c) \quad \text{or} \quad f'(z) = \frac{f(x) - f(c)}{x - c}.$$

Do you recognize this special case of Taylor's Theorem? (It is the Mean Value Theorem.)

When applying Taylor's Theorem, you should not expect to be able to find the exact value of z. (If you could do this, an approximation would not be necessary.) Rather, you are trying to find bounds for $f^{(n+1)}(z)$ from which you are able to tell how large the remainder $R_n(x)$ is.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 8 Determining the Accuracy of an Approximation

The third Maclaurin polynomial for $\sin x$ is

$$P_3(x) = x - \frac{x^3}{3!}.$$

Use Taylor's Theorem to approximate $\sin(0.1)$ by $P_3(0.1)$ and determine the accuracy of the approximation.

Solution Using Taylor's Theorem, you have

$$\sin x = x - \frac{x^3}{3!} + R_3(x) = x - \frac{x^3}{3!} + \frac{f^{(4)}(z)}{4!}x^4$$

where $0 < z < 0.1$. So,

$$\sin(0.1) \approx 0.1 - \frac{(0.1)^3}{3!} \approx 0.1 - 0.000167 = 0.099833.$$

Because $f^{(4)}(z) = \sin z$, it follows that the error $|R_3(0.1)|$ can be bounded as follows.

$$0 < R_3(0.1) = \frac{\sin z}{4!}(0.1)^4 < \frac{0.0001}{4!} \approx 0.000004$$

This implies that

$$0.099833 < \sin(0.1) \approx 0.099833 + R_3(0.1) < 0.099833 + 0.000004$$

or

$$0.099833 < \sin(0.1) < 0.099837.$$

REMARK Note that when you use a calculator,

$$\sin(0.1) \approx 0.0998334.$$

EXAMPLE 9 Approximating a Value to a Desired Accuracy

Determine the degree of the Taylor polynomial $P_n(x)$ expanded about $c = 1$ that should be used to approximate $\ln(1.2)$ so that the error is less than 0.001.

Solution Use the pattern of Example 4 to determine that the $(n + 1)$st derivative of $f(x) = \ln x$ is

$$f^{(n+1)}(x) = (-1)^n \frac{n!}{x^{n+1}}.$$

Using Taylor's Theorem, the error $|R_n(1.2)|$ is

$$\begin{aligned} |R_n(1.2)| &= \left| \frac{f^{(n+1)}(z)}{(n+1)!}(1.2 - 1)^{n+1} \right| \\ &= \frac{n!}{z^{n+1}} \left[\frac{1}{(n+1)!} \right] (0.2)^{n+1} \\ &= \frac{(0.2)^{n+1}}{z^{n+1}(n+1)} \end{aligned}$$

REMARK Note that when you use a calculator,

$$P_3(1.2) \approx 0.1827$$

and

$$\ln(1.2) \approx 0.1823.$$

where $1 < z < 1.2$. In this interval, $(0.2)^{n+1}/[z^{n+1}(n + 1)]$ is less than $(0.2)^{n+1}/(n + 1)$. So, you are seeking a value of n such that

$$\frac{(0.2)^{n+1}}{(n+1)} < 0.001 \quad \Rightarrow \quad 1000 < (n + 1)5^{n+1}.$$

By trial and error, you can determine that the least value of n that satisfies this inequality is $n = 3$. So, you would need the third Taylor polynomial to achieve the desired accuracy in approximating $\ln(1.2)$. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

9.7 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. An elementary function is approximated by a polynomial. Describe what is meant by saying that the polynomial is *expanded about c* or *centered at c*.
2. Explain how Taylor polynomials and Maclaurin polynomials are related.
3. Describe the accuracy of the nth-degree Taylor polynomial of f centered at c as the distance between c and x increases.
4. In general, how does the accuracy of a Taylor polynomial change as the degree of the polynomial increases? Explain your reasoning.

Matching **In Exercises 5–8, match the Taylor polynomial approximation of the function $f(x) = e^{-x^2/2}$ with its graph. [The graphs are labeled (a), (b), (c), and (d).]**

(a)



(b)



(c)



(d)



5. $g(x) = -\frac{1}{2}x^2 + 1$
6. $g(x) = \frac{1}{8}x^4 - \frac{1}{2}x^2 + 1$
7. $g(x) = e^{-1/2}[(x + 1) + 1]$
8. $g(x) = e^{-1/2}\left[\frac{1}{3}(x - 1)^3 - (x - 1) + 1\right]$

Finding a First-Degree Polynomial Approximation **In Exercises 9–12, find a first-degree polynomial function P_1 whose value and slope agree with the value and slope of f at $x = c$. Use a graphing utility to graph f and P_1.**

9. $f(x) = \frac{\sqrt{x}}{4}, \quad c = 4$
10. $f(x) = \frac{6}{\sqrt[3]{x}}, \quad c = 8$
11. $f(x) = \sec x, \quad c = \frac{\pi}{6}$
12. $f(x) = \tan x, \quad c = \frac{\pi}{4}$

Graphical and Numerical Analysis **In Exercises 13 and 14, use a graphing utility to graph f and its second-degree polynomial approximation P_2 at $x = c$. Complete the table comparing the values of f and P_2.**

13. $f(x) = \frac{4}{\sqrt{x}}, \quad c = 1$

$P_2(x) = 4 - 2(x - 1) + \frac{3}{2}(x - 1)^2$

x	0	0.8	0.9	1	1.1	1.2	2
$f(x)$							
$P_2(x)$							

14. $f(x) = \sec x, \quad c = \frac{\pi}{4}$

$P_2(x) = \sqrt{2} + \sqrt{2}\left(x - \frac{\pi}{4}\right) + \frac{3}{2}\sqrt{2}\left(x - \frac{\pi}{4}\right)^2$

x	-2.15	0.585	0.685	$\frac{\pi}{4}$	0.885	0.985	1.785
$f(x)$							
$P_2(x)$							

15. **Conjecture** Consider the function $f(x) = \cos x$ and its Maclaurin polynomials P_2, P_4, and P_6 (see Example 5).
   (a) Use a graphing utility to graph f and the indicated polynomial approximations.
   (b) Evaluate and compare the values of $f^{(n)}(0)$ and $P_n^{(n)}(0)$ for $n = 2$, 4, and 6.
   (c) Use the results in part (b) to make a conjecture about $f^{(n)}(0)$ and $P_n^{(n)}(0)$.
16. **Conjecture** Consider the function $f(x) = x^2e^x$.
   (a) Find the Maclaurin polynomials P_2, P_3, and P_4 for f.
   (b) Use a graphing utility to graph f, P_2, P_3, and P_4.
   (c) Evaluate and compare the values of $f^{(n)}(0)$ and $P_n^{(n)}(0)$ for $n = 2$, 3, and 4.
   (d) Use the results in part (c) to make a conjecture about $f^{(n)}(0)$ and $P_n^{(n)}(0)$.

Finding a Maclaurin Polynomial **In Exercises 17–26, find the nth Maclaurin polynomial for the function.**

17. $f(x) = e^{4x}, \quad n = 4$
18. $f(x) = e^{-x}, \quad n = 5$
19. $f(x) = \sin x, \quad n = 5$
20. $f(x) = \cos \pi x, \quad n = 4$
21. $f(x) = xe^x, \quad n = 4$
22. $f(x) = x^2e^{-x}, \quad n = 4$
23. $f(x) = \frac{1}{1 - x}, \quad n = 5$
24. $f(x) = \frac{x}{x + 1}, \quad n = 4$
25. $f(x) = \sec x, \quad n = 2$
26. $f(x) = \tan x, \quad n = 3$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding a Taylor Polynomial **In Exercises 27–32, find the nth Taylor polynomial for the function, centered at c.**

27. $f(x) = \frac{2}{x}, \quad n = 3, \quad c = 1$

28. $f(x) = \frac{1}{x^2}, \quad n = 4, \quad c = -2$

29. $f(x) = \sqrt{x}, \quad n = 2, \quad c = 4$

30. $f(x) = \sqrt[3]{x}, \quad n = 3, \quad c = 8$

31. $f(x) = \ln x, \quad n = 4, \quad c = 2$

32. $f(x) = x^2 \cos x, \quad n = 2, \quad c = \pi$

Finding Taylor Polynomials Using Technology **In Exercises 33 and 34, use a graphing utility to find the indicated Taylor polynomials for the function f. Graph the function and the Taylor polynomials.**

33. $f(x) = \tan \pi x$

(a) $n = 3, \quad c = 0$

(b) $n = 3, \quad c = 1/4$

34. $f(x) = \frac{1}{x^2 + 1}$

(a) $n = 4, \quad c = 0$

(b) $n = 4, \quad c = 1$

35. **Numerical and Graphical Approximations**

(a) Use the Maclaurin polynomials $P_1(x)$, $P_3(x)$, and $P_5(x)$ for $f(x) = \sin x$ to complete the table.

x	0	0.25	0.50	0.75	1
$\sin x$	0	0.2474	0.4794	0.6816	0.8415
$P_1(x)$					
$P_3(x)$					
$P_5(x)$					

(b) Use a graphing utility to graph $f(x) = \sin x$ and the Maclaurin polynomials in part (a).

(c) Describe the change in accuracy of a polynomial approximation as the distance from the point where the polynomial is centered increases.

36. **Numerical and Graphical Approximations**

(a) Use the Taylor polynomials $P_1(x)$, $P_2(x)$, and $P_4(x)$ for $f(x) = e^x$, centered at $c = 1$, to complete the table.

x	1	1.25	1.50	1.75	2
e^x	e	3.4903	4.4817	5.7546	7.3891
$P_1(x)$					
$P_2(x)$					
$P_4(x)$					

(b) Use a graphing utility to graph $f(x) = e^x$ and the Taylor polynomials in part (a).

(c) Describe the change in accuracy of polynomial approximations as the degree increases.

Numerical and Graphical Approximations **In Exercises 37 and 38, (a) find the Maclaurin polynomial $P_3(x)$ for $f(x)$, (b) complete the table for $f(x)$ and $P_3(x)$, and (c) sketch the graphs of $f(x)$ and $P_3(x)$, on the same set of coordinate axes.**

x	-0.75	-0.50	-0.25	0	0.25	0.50	0.75
$f(x)$							
$P_3(x)$							

37. $f(x) = \arcsin x$

38. $f(x) = \arctan x$

Approximating a Function Value **In Exercises 39–44, approximate the function at the given value of x, using the polynomial found in the indicated exercise.**

39. $f(x) = e^{4x}, \quad f\left(\frac{1}{4}\right),$ Exercise 17

40. $f(x) = x^2 e^{-x}, \quad f\left(\frac{1}{5}\right),$ Exercise 22

41. $f(x) = \frac{1}{x^2}, \quad f(-2.1),$ Exercise 28

42. $f(x) = \sqrt[3]{x}, \quad f(8.05),$ Exercise 30

43. $f(x) = \ln x, \quad f(2.1),$ Exercise 31

44. $f(x) = x^2 \cos x, \quad f\left(\frac{7\pi}{8}\right),$ Exercise 32

Using Taylor's Theorem **In Exercises 45–50, use Taylor's Theorem to obtain an upper bound for the error of the approximation. Then calculate the exact value of the error.**

45. $\cos(0.3) \approx 1 - \frac{(0.3)^2}{2!} + \frac{(0.3)^4}{4!}$

46. $\arccos(0.15) \approx \frac{\pi}{2} - 0.15$

47. $\sinh(0.2) \approx 0.2 + \frac{(0.2)^3}{3!} + \frac{(0.2)^5}{5!}$

48. $e \approx 1 + 1 + \frac{1^2}{2!} + \frac{1^3}{3!} + \frac{1^4}{4!} + \frac{1^5}{5!}$

49. $\arcsin(0.4) \approx 0.4 + \frac{(0.4)^3}{2 \cdot 3}$

50. $\arctan(0.4) \approx 0.4 - \frac{(0.4)^3}{3}$

Finding a Degree **In Exercises 51–56, determine the degree of the Maclaurin polynomial required for the error in the approximation of the function at the indicated value of x to be less than 0.001.**

51. $f(x) = \sin x, \quad$ approximate $f(0.3)$

52. $f(x) = \cos x, \quad$ approximate $f(0.4)$

53. $f(x) = e^x, \quad$ approximate $f(0.6)$

54. $f(x) = \ln(x + 1), \quad$ approximate $f(1.25)$

55. $f(x) = \frac{1}{x - 2}, \quad$ approximate $f(0.15)$

56. $f(x) = \frac{1}{x + 1}, \quad$ approximate $f(0.2)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding a Degree Using Technology **In Exercises 57 and 58, determine the degree of the Maclaurin polynomial required for the error in the approximation of the function at the indicated value of x to be less than 0.0001. Use a graphing utility to obtain and evaluate the required derivative.**

57. $f(x) = \ln(x + 1)$, approximate $f(0.5)$.

58. $f(x) = e^{-\pi x}$, approximate $f(1.3)$.

Finding Values **In Exercises 59–62, determine the values of x for which the function can be replaced by the Taylor polynomial if the error cannot exceed 0.001.**

59. $f(x) = e^x \approx 1 + x + \frac{x^2}{2!} + \frac{x^3}{3!}, \quad x < 0$

60. $f(x) = \sin x \approx x - \frac{x^3}{3!}$

61. $f(x) = \cos x \approx 1 - \frac{x^2}{2!} + \frac{x^4}{4!}$

62. $f(x) = e^{-2x} \approx 1 - 2x + 2x^2 - \frac{4}{3}x^3$

Exploring Concepts

63. Explain the relationship between the equation of a tangent line to a differentiable function at a point and the first Taylor polynomial for that function centered at the point.

64. Without performing any calculations, find the second Maclaurin polynomial for $f(x) = a + bx^2$. Explain your reasoning.

65. Find the fourth Maclaurin polynomials for $f(x) = e^x$ and $g(x) = e^{2x}$. Explain how you can use the fourth Maclaurin polynomial for f to find the fourth Maclaurin polynomial for g.

66. **HOW DO YOU SEE IT?** The figure shows the graphs of the first-, second-, and third-degree polynomial approximations P_1, P_2, and P_3 of a function f. Label the graphs of P_1, P_2, and P_3. To print an enlarged copy of the graph, go to *MathGraphs.com*.



67. **Proof** Prove that if f is an even function, then its nth Maclaurin polynomial contains only terms with even powers of x.

68. **Proof** Prove that if f is an odd function, then its nth Maclaurin polynomial contains only terms with odd powers of x.

69. **Comparing Maclaurin Polynomials**

(a) Compare the Maclaurin polynomials of degree 4 and degree 5, respectively, for the functions

$$f(x) = e^x \quad \text{and} \quad g(x) = xe^x.$$

What is the relationship between them?

(b) Use the result in part (a) and the Maclaurin polynomial of degree 5 for $f(x) = \sin x$ to find a Maclaurin polynomial of degree 6 for the function $g(x) = x \sin x$.

(c) Use the result in part (a) and the Maclaurin polynomial of degree 5 for $f(x) = \sin x$ to find a Maclaurin polynomial of degree 4 for the function $g(x) = (\sin x)/x$.

70. **Differentiating Maclaurin Polynomials**

(a) Differentiate the Maclaurin polynomial of degree 5 for $f(x) = \sin x$ and compare the result with the Maclaurin polynomial of degree 4 for $g(x) = \cos x$.

(b) Differentiate the Maclaurin polynomial of degree 6 for $f(x) = \cos x$ and compare the result with the Maclaurin polynomial of degree 5 for $g(x) = \sin x$.

(c) Differentiate the Maclaurin polynomial of degree 4 for $f(x) = e^x$. Describe the relationship between the two series.

71. **Graphical Reasoning** The figure shows the graphs of the function $f(x) = \sin(\pi x/4)$ and the second-degree Taylor polynomial $P_2(x) = 1 - (\pi^2/32)(x - 2)^2$ centered at $x = 2$.



(a) Use the symmetry of the graph of f to write the second-degree Taylor polynomial $Q_2(x)$ for f centered at $x = -2$.

(b) Use a horizontal translation of the result in part (a) to find the second-degree Taylor polynomial $R_2(x)$ for f centered at $x = 6$.

(c) Is it possible to use a horizontal translation of the result in part (a) to write a second-degree Taylor polynomial for f centered at $x = 4$? Explain.

72. **Proof** Let $P_n(x)$ be the nth Taylor polynomial for f at c. Prove that $P_n(c) = f(c)$ and $P^{(k)}(c) = f^{(k)}(c)$ for $1 \leq k \leq n$.

73. **Proof** Consider a function f with continuous first and second derivatives at $x = c$. Prove that if f has a relative maximum at $x = c$, then the second Taylor polynomial centered at $x = c$ also has a relative maximum at $x = c$.

74. **Integral Form of the Remainder** Show that the integral form of the remainder R_n is given by

$$\frac{1}{n!}\int_c^x (x - t)^n f^{(n+1)}(t)\, dt.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

9.8 Power Series

GO DIGITAL

- Define a power series.
- Find the radius and interval of convergence of a power series.
- Determine the endpoint convergence of a power series.
- Differentiate and integrate a power series.

Power Series

In Section 9.7, you were introduced to the concept of approximating functions by Taylor polynomials. For instance, the function $f(x) = e^x$ can be *approximated* by its third-degree Maclaurin polynomial

$$e^x \approx 1 + x + \frac{x^2}{2!} + \frac{x^3}{3!}.$$

In that section, you learned that the higher the degree of the approximating polynomial, the better the approximation becomes.

In this section and the next two sections, you will learn that several important types of functions, including $f(x) = e^x$, can be represented *exactly* by an infinite series called a **power series.** For example, the power series representation for e^x is

$$e^x = 1 + x + \frac{x^2}{2!} + \frac{x^3}{3!} + \cdots + \frac{x^n}{n!} + \cdots.$$

For each real number x, it can be shown that the infinite series on the right converges to the number e^x. Before doing this, however, some preliminary results dealing with power series will be discussed—beginning with the next definition.

Exploration

Graphical Reasoning

Use a graphing utility to approximate the graph of each power series near $x = 0$. (Use the first several terms of each series.) Each series represents a well-known function. What is the function?

a. $\displaystyle\sum_{n=0}^{\infty} \frac{(-1)^n x^n}{n!}$

b. $\displaystyle\sum_{n=0}^{\infty} \frac{(-1)^n x^{2n}}{(2n)!}$

c. $\displaystyle\sum_{n=0}^{\infty} \frac{(-1)^n x^{2n+1}}{(2n+1)!}$

d. $\displaystyle\sum_{n=0}^{\infty} \frac{(-1)^n x^{2n+1}}{2n+1}$

e. $\displaystyle\sum_{n=0}^{\infty} \frac{2^n x^n}{n!}$

REMARK To simplify the notation for power series, assume that $(x - c)^0 = 1$, even when $x = c$.

Definition of Power Series

If x is a variable, then an infinite series of the form

$$\sum_{n=0}^{\infty} a_n x^n = a_0 + a_1 x + a_2 x^2 + a_3 x^3 + \cdots + a_n x^n + \cdots$$

is called a **power series.** More generally, an infinite series of the form

$$\sum_{n=0}^{\infty} a_n (x - c)^n = a_0 + a_1 (x - c) + a_2 (x - c)^2 + \cdots + a_n (x - c)^n + \cdots$$

is called a **power series centered at c,** where c is a constant.

EXAMPLE 1 Power Series

a. The power series below is centered at 0.

$$\sum_{n=0}^{\infty} \frac{x^n}{n!} = 1 + x + \frac{x^2}{2} + \frac{x^3}{3!} + \cdots$$

b. The power series below is centered at -1.

$$\sum_{n=0}^{\infty} (-1)^n (x + 1)^n = 1 - (x + 1) + (x + 1)^2 - (x + 1)^3 + \cdots$$

c. The power series below is centered at 1.

$$\sum_{n=1}^{\infty} \frac{1}{n} (x - 1)^n = (x - 1) + \frac{1}{2}(x - 1)^2 + \frac{1}{3}(x - 1)^3 + \cdots$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Radius and Interval of Convergence

A power series in x can be viewed as a function of x

$$f(x) = \sum_{n=0}^{\infty} a_n(x - c)^n$$

where the *domain of* f is the set of all x for which the power series converges. Determination of the domain of a power series is the primary concern in this section. Of course, every power series converges at its center c because

$$\begin{aligned} f(c) &= \sum_{n=0}^{\infty} a_n(c - c)^n \\ &= a_0(1) + 0 + 0 + \cdots + 0 + \cdots \\ &= a_0. \end{aligned}$$

So, c always lies in the domain of f. Theorem 9.20 (see below) states that the domain of a power series can take three basic forms: a single point, an interval centered at c, or the entire real number line, as shown in Figure 9.18.



The domain of a power series has only three basic forms: a single point, an interval centered at c, or the entire real number line.
Figure 9.18

THEOREM 9.20 Convergence of a Power Series

For a power series centered at c, precisely one of three cases is true.

1. The series converges only at c.
2. There exists a real number $R > 0$ such that the series converges absolutely for
$$|x - c| < R$$
and diverges for
$$|x - c| > R.$$
3. The series converges absolutely for all x.

The number R is the **radius of convergence** of the power series. If the series converges only at c, then the radius of convergence is $R = 0$. If the series converges for all x, then the radius of convergence is $R = \infty$. The set of all values of x for which the power series converges is the **interval of convergence** of the power series.

A proof of this theorem is given in Appendix A.

REMARK In Case 2 of Theorem 9.20, the series converges in the interval $(c - R, c + R)$ and diverges in the intervals $(-\infty, c - R)$ and $(c + R, \infty)$. Determining the convergence or divergence at the endpoints $c - R$ and $c + R$ will be discussed later in this section.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

To determine the radius of convergence of a power series, use the Ratio Test, as demonstrated in Examples 2, 3, and 4.

EXAMPLE 2 Finding the Radius of Convergence

Find the radius of convergence of $\sum_{n=0}^{\infty} n!x^n$.

Solution For $x = 0$, you obtain

$$f(0) = \sum_{n=0}^{\infty} n!0^n = 1 + 0 + 0 + \cdots = 1.$$

For any fixed value of x such that $|x| > 0$, let $u_n = n!x^n$. Then

$$\begin{aligned}\lim_{n\to\infty}\left|\frac{u_{n+1}}{u_n}\right| &= \lim_{n\to\infty}\left|\frac{(n+1)!x^{n+1}}{n!x^n}\right| && \text{Apply Ratio Test.}\\ &= |x|\lim_{n\to\infty}(n+1)\\ &= \infty.\end{aligned}$$

By the Ratio Test, the series diverges for $|x| > 0$ and converges only at its center, 0. So, the radius of convergence is $R = 0$.

EXAMPLE 3 Finding the Radius of Convergence

Find the radius of convergence of

$$\sum_{n=0}^{\infty} 3(x-2)^n.$$

Solution For $x \neq 2$, let $u_n = 3(x-2)^n$. Then

$$\begin{aligned}\lim_{n\to\infty}\left|\frac{u_{n+1}}{u_n}\right| &= \lim_{n\to\infty}\left|\frac{3(x-2)^{n+1}}{3(x-2)^n}\right| && \text{Apply Ratio Test.}\\ &= \lim_{n\to\infty}|x-2|\\ &= |x-2|.\end{aligned}$$

By the Ratio Test, the series converges for $|x-2| < 1$ and diverges for $|x-2| > 1$. So, the radius of convergence of the series is $R = 1$.

EXAMPLE 4 Finding the Radius of Convergence

Find the radius of convergence of

$$\sum_{n=0}^{\infty}\frac{(-1)^n x^{2n+1}}{(2n+1)!}.$$

Solution Let $u_n = (-1)^n x^{2n+1}/(2n+1)!$. Then

$$\begin{aligned}\lim_{n\to\infty}\left|\frac{u_{n+1}}{u_n}\right| &= \lim_{n\to\infty}\left|\frac{(-1)^{n+1}x^{2n+3}/(2n+3)!}{(-1)^n x^{2n+1}/(2n+1)!}\right| && \text{Apply Ratio Test.}\\ &= \lim_{n\to\infty}\left|\frac{(-1)^{n+1}x^{2n+3}}{(2n+3)!}\cdot\frac{(2n+1)!}{(-1)^n x^{2n+1}}\right| && \text{Invert and multiply.}\\ &= \lim_{n\to\infty}\frac{x^2}{(2n+3)(2n+2)}.\end{aligned}$$

For any *fixed* value of x, this limit is 0. So, by the Ratio Test, the series converges for all x. The radius of convergence is $R = \infty$. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Endpoint Convergence

Note that for a power series whose radius of convergence is a finite number R, Theorem 9.20 says nothing about the convergence at the *endpoints* of the interval of convergence. Each endpoint must be tested separately for convergence or divergence. As a result, the interval of convergence of a power series can take any one of the six forms shown in Figure 9.19.



Intervals of convergence

Figure 9.19

EXAMPLE 5 Finding the Interval of Convergence

See LarsonCalculus.com for an interactive version of this type of example.

Find the interval of convergence of

$$\sum_{n=1}^{\infty} \frac{x^n}{n}.$$

Solution Letting $u_n = x^n/n$ produces

$$\lim_{n\to\infty} \left|\frac{u_{n+1}}{u_n}\right| = \lim_{n\to\infty} \left|\frac{x^{n+1}/(n+1)}{x^n/n}\right| \qquad \text{Apply Ratio Test.}$$

$$= \lim_{n\to\infty} \left|\frac{x^{n+1}}{n+1} \cdot \frac{n}{x^n}\right| \qquad \text{Invert and multiply.}$$

$$= \lim_{n\to\infty} \left|\frac{nx}{n+1}\right|$$

$$= |x|.$$

So, by the Ratio Test, the radius of convergence is $R = 1$. Moreover, because the series is centered at 0, it converges in the interval $(-1, 1)$. This interval, however, is not necessarily the *interval of convergence*. To determine this, you must test for convergence at each endpoint. When $x = 1$, you obtain the *divergent* harmonic series

$$\sum_{n=1}^{\infty} \frac{1}{n} = \frac{1}{1} + \frac{1}{2} + \frac{1}{3} + \cdots. \qquad \text{Diverges when } x = 1.$$

When $x = -1$, you obtain the *convergent* alternating harmonic series

$$\sum_{n=1}^{\infty} \frac{(-1)^n}{n} = -1 + \frac{1}{2} - \frac{1}{3} + \frac{1}{4} - \cdots. \qquad \text{Converges when } x = -1.$$

So, the interval of convergence for the series is $[-1, 1)$, as shown in Figure 9.20.



Figure 9.20

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 6 Finding the Interval of Convergence

Find the interval of convergence of $\sum_{n=0}^{\infty} \frac{(-1)^n(x+1)^n}{2^n}$.

Solution Letting $u_n = (-1)^n(x+1)^n/2^n$ produces

$$\lim_{n\to\infty}\left|\frac{u_{n+1}}{u_n}\right| = \lim_{n\to\infty}\left|\frac{(-1)^{n+1}(x+1)^{n+1}/2^{n+1}}{(-1)^n(x+1)^n/2^n}\right| \quad \text{Apply Ratio Test.}$$

$$= \lim_{n\to\infty}\left|\frac{(-1)^{n+1}(x+1)^{n+1}}{2^{n+1}} \cdot \frac{2^n}{(-1)^n(x+1)^n}\right| \quad \text{Invert and multiply.}$$

$$= \lim_{n\to\infty}\left|\frac{x+1}{2}\right|$$

$$= \left|\frac{x+1}{2}\right|.$$

By the Ratio Test, the series converges for

$$\left|\frac{x+1}{2}\right| < 1$$

or $|x+1| < 2$. So, the radius of convergence is $R = 2$. Because the series is centered at $x = -1$, it will converge in the interval $(-3, 1)$. Furthermore, at the endpoints,

$$\sum_{n=0}^{\infty} \frac{(-1)^n(-2)^n}{2^n} = \sum_{n=0}^{\infty} \frac{2^n}{2^n} = \sum_{n=0}^{\infty} 1 \quad \text{Diverges when } x = -3.$$

and

$$\sum_{n=0}^{\infty} \frac{(-1)^n(2)^n}{2^n} = \sum_{n=0}^{\infty} (-1)^n \quad \text{Diverges when } x = 1.$$

both of which diverge. So, the interval of convergence is $(-3, 1)$, as shown in Figure 9.21.



Figure 9.21

EXAMPLE 7 Finding the Interval of Convergence

Find the interval of convergence of $\sum_{n=1}^{\infty} \frac{x^n}{n^2}$.

Solution Letting $u_n = x^n/n^2$ produces

$$\lim_{n\to\infty}\left|\frac{u_{n+1}}{u_n}\right| = \lim_{n\to\infty}\left|\frac{x^{n+1}/(n+1)^2}{x^n/n^2}\right| \quad \text{Apply Ratio Test.}$$

$$= \lim_{n\to\infty}\left|\frac{n^2x}{(n+1)^2}\right|$$

$$= |x|.$$

So, the radius of convergence is $R = 1$. Because the series is centered at $x = 0$, it converges in the interval $(-1, 1)$. When $x = 1$, you obtain the convergent p-series

$$\sum_{n=1}^{\infty} \frac{1}{n^2} = \frac{1}{1^2} + \frac{1}{2^2} + \frac{1}{3^2} + \frac{1}{4^2} + \cdots. \quad \text{Converges when } x = 1.$$

When $x = -1$, you obtain the convergent alternating series

$$\sum_{n=1}^{\infty} \frac{(-1)^n}{n^2} = -\frac{1}{1^2} + \frac{1}{2^2} - \frac{1}{3^2} + \frac{1}{4^2} - \cdots. \quad \text{Converges when } x = -1.$$

Therefore, the interval of convergence is $[-1, 1]$, as shown in Figure 9.22.



Figure 9.22

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Differentiation and Integration of Power Series

Power series representation of functions has played an important role in the development of calculus. In fact, much of Newton's work with differentiation and integration was done in the context of power series—especially his work with complicated algebraic functions and transcendental functions. Euler, Lagrange, Leibniz, and the Bernoullis all used power series extensively in calculus.

Once you have defined a function with a power series, it is natural to wonder how you can determine the characteristics of the function. Is it continuous? Differentiable? Theorem 9.21, which is stated without proof, answers these questions.

JAMES GREGORY (1638–1675)

One of the earliest mathematicians to work with power series was a Scotsman, James Gregory. He developed a power series method for interpolating table values—a method that was later used by Brook Taylor in the development of Taylor polynomials and Taylor series.

THEOREM 9.21 Properties of Functions Defined by Power Series

If the function

$$f(x) = \sum_{n=0}^{\infty} a_n(x-c)^n = a_0 + a_1(x-c) + a_2(x-c)^2 + a_3(x-c)^3 + \cdots$$

has a radius of convergence of $R > 0$, then, on the interval

$$(c-R, c+R)$$

f is differentiable (and therefore continuous). Moreover, the derivative and antiderivative of f are as follows.

1. $$f'(x) = \sum_{n=1}^{\infty} na_n(x-c)^{n-1} = a_1 + 2a_2(x-c) + 3a_3(x-c)^2 + \cdots$$

2. $$\int f(x)\,dx = C + \sum_{n=0}^{\infty} a_n \frac{(x-c)^{n+1}}{n+1} = C + a_0(x-c) + a_1\frac{(x-c)^2}{2} + a_2\frac{(x-c)^3}{3} + \cdots$$

The *radius of convergence* of the series obtained by differentiating or integrating a power series is the same as that of the original power series. The *interval of convergence,* however, may differ as a result of the behavior at the endpoints.

Theorem 9.21 states that, in many ways, a function defined by a power series behaves like a polynomial. It is continuous in its interval of convergence, and both its derivative and its antiderivative can be determined by differentiating and integrating each term of the power series. For instance, the derivative of the power series

$$f(x) = \sum_{n=0}^{\infty} \frac{x^n}{n!} = 1 + x + \frac{x^2}{2} + \frac{x^3}{3!} + \frac{x^4}{4!} + \cdots$$

is

$$f'(x) = 1 + (2)\frac{x}{2} + (3)\frac{x^2}{3!} + (4)\frac{x^3}{4!} + \cdots = 1 + x + \frac{x^2}{2} + \frac{x^3}{3!} + \frac{x^4}{4!} + \cdots = f(x).$$

Notice that $f'(x) = f(x)$. Do you recognize this function?

World History Archive/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 8 Intervals of Convergence for $f(x)$, $f'(x)$, and $\int f(x)\,dx$

Consider the function

$$f(x) = \sum_{n=1}^{\infty} \frac{x^n}{n} = x + \frac{x^2}{2} + \frac{x^3}{3} + \cdots.$$

Find the interval of convergence for each expression.

a. $\int f(x)\,dx$ **b.** $f(x)$ **c.** $f'(x)$

Solution By Theorem 9.21, you have

$$f'(x) = \sum_{n=1}^{\infty} x^{n-1}$$
$$= 1 + x + x^2 + x^3 + \cdots$$

and

$$\int f(x)\,dx = C + \sum_{n=1}^{\infty} \frac{x^{n+1}}{n(n+1)}$$
$$= C + \frac{x^2}{1 \cdot 2} + \frac{x^3}{2 \cdot 3} + \frac{x^4}{3 \cdot 4} + \cdots.$$

REMARK Notice in Example 8 that when differentiating the power series, differentiation is done on a *term-by-term* basis. Likewise, when integrating a series, integration is done on a *term-by-term* basis.

By the Ratio Test, you can show that each series has a radius of convergence of $R = 1$. Considering the interval $(-1, 1)$, find the interval of convergence for each given expression.

a. For $\int f(x)\,dx$, the series

$$\sum_{n=1}^{\infty} \frac{x^{n+1}}{n(n+1)}$$ Interval of convergence: $[-1, 1]$

converges for $x = \pm 1$, and its interval of convergence is $[-1, 1]$. See Figure 9.23(a).

b. For $f(x)$, the series

$$\sum_{n=1}^{\infty} \frac{x^n}{n}$$ Interval of convergence: $[-1, 1)$

converges for $x = -1$ and diverges for $x = 1$. So, its interval of convergence is $[-1, 1)$. See Figure 9.23(b).

c. For $f'(x)$, the series

$$\sum_{n=1}^{\infty} x^{n-1}$$ Interval of convergence: $(-1, 1)$

diverges for $x = \pm 1$, and its interval of convergence is $(-1, 1)$. See Figure 9.23(c).



(a) **(b)** **(c)**

Figure 9.23

From Example 8, it appears that of the three series, the one for the derivative, $f'(x)$, is the least likely to converge at the endpoints. In fact, it can be shown that if the series for $f'(x)$ converges at the endpoints

$$x = c \pm R$$

then the series for $f(x)$ will also converge there.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

9.8 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain how a Maclaurin polynomial and a power series centered at 0 for a function are different.
2. Explain what the domain of
$$f(x) = \sum_{n=0}^{\infty} a_n(x - c)^n$$
represents.
3. Determine the radius of convergence for the power series $\sum_{n=0}^{\infty} a_n(x - 2)^n$ given the following result of the Ratio Test, where $u_n = a_n(x - 2)^n$.
$$\lim_{n\to\infty} \left|\frac{u_{n+1}}{u_n}\right| = \left|\frac{x - 2}{5}\right|$$
4. Describe how a function defined by a power series behaves like a polynomial.

Finding the Center of a Power Series

In Exercises 5–8, state where the power series is centered.

5. $\sum_{n=0}^{\infty} nx^n$
6. $\sum_{n=1}^{\infty} \frac{(-1)^n(2n - 1)}{2^n n!}x^n$
7. $\sum_{n=1}^{\infty} \frac{(x - 2)^n}{n^3}$
8. $\sum_{n=0}^{\infty} \frac{(-1)^n(x - \pi)^{2n}}{(2n)!}$

Finding the Radius of Convergence

In Exercises 9–14, find the radius of convergence of the power series.

9. $\sum_{n=0}^{\infty} (-1)^n \frac{x^n}{n + 1}$
10. $\sum_{n=0}^{\infty} (3x)^n$
11. $\sum_{n=1}^{\infty} \frac{(4x)^n}{n^2}$
12. $\sum_{n=0}^{\infty} \frac{(-1)^n x^n}{5^n}$
13. $\sum_{n=0}^{\infty} \frac{x^{2n}}{(2n)!}$
14. $\sum_{n=0}^{\infty} \frac{(2n)!x^{3n}}{n!}$

Finding the Interval of Convergence

In Exercises 15–38, find the interval of convergence of the power series. (Be sure to include a check for convergence at the endpoints of the interval.)

15. $\sum_{n=0}^{\infty} \left(\frac{x}{4}\right)^n$
16. $\sum_{n=0}^{\infty} (2x)^n$
17. $\sum_{n=1}^{\infty} \frac{(-1)^n x^n}{n}$
18. $\sum_{n=0}^{\infty} (-1)^{n+1}(n + 1)x^n$
19. $\sum_{n=0}^{\infty} \frac{x^{5n}}{n!}$
20. $\sum_{n=0}^{\infty} \frac{(3x)^n}{(2n)!}$
21. $\sum_{n=0}^{\infty} (2n)! \left(\frac{x}{3}\right)^n$
22. $\sum_{n=0}^{\infty} \frac{(-1)^n x^n}{(n + 1)(n + 2)}$
23. $\sum_{n=1}^{\infty} \frac{(-1)^{n+1}x^n}{6^n}$
24. $\sum_{n=0}^{\infty} \frac{(-1)^n n!(x - 5)^n}{3^n}$
25. $\sum_{n=1}^{\infty} \frac{(-1)^{n+1}(x - 4)^n}{n9^n}$
26. $\sum_{n=0}^{\infty} \frac{(x - 3)^{n+1}}{(n + 1)4^{n+1}}$
27. $\sum_{n=0}^{\infty} \frac{(-1)^{n+1}(x - 1)^{n+1}}{n + 1}$
28. $\sum_{n=1}^{\infty} \frac{(-1)^{n+1}(x - 2)^n}{n2^n}$
29. $\sum_{n=1}^{\infty} \frac{(x - 3)^{n-1}}{3^{n-1}}$
30. $\sum_{n=0}^{\infty} \frac{(-1)^n x^{2n+1}}{2n + 1}$
31. $\sum_{n=1}^{\infty} \frac{n}{n + 1}(-2x)^{n-1}$
32. $\sum_{n=0}^{\infty} \frac{(-1)^n x^{2n}}{n!}$
33. $\sum_{n=0}^{\infty} \frac{x^{3n+1}}{(3n + 1)!}$
34. $\sum_{n=1}^{\infty} \frac{n!x^n}{(2n)!}$
35. $\sum_{n=1}^{\infty} \frac{2 \cdot 3 \cdot 4 \cdot \cdots (n + 1)x^n}{n!}$
36. $\sum_{n=1}^{\infty} \left[\frac{2 \cdot 4 \cdot 6 \cdot \cdots 2n}{3 \cdot 5 \cdot 7 \cdot \cdots (2n + 1)}\right] x^{2n+1}$
37. $\sum_{n=1}^{\infty} \frac{(-1)^{n+1} 3 \cdot 7 \cdot 11 \cdot \cdots (4n - 1)(x - 3)^n}{4^n}$
38. $\sum_{n=1}^{\infty} \frac{n!(x + 1)^n}{1 \cdot 3 \cdot 5 \cdot \cdots (2n - 1)}$

Finding the Radius of Convergence

In Exercises 39 and 40, find the radius of convergence of the power series, where $c > 0$ and k is a positive integer.

39. $\sum_{n=1}^{\infty} \frac{(x - c)^{n-1}}{c^{n-1}}$
40. $\sum_{n=0}^{\infty} \frac{(n!)^k x^n}{(kn)!}$

Finding the Interval of Convergence

In Exercises 41–44, find the interval of convergence of the power series, where $c > 0$ and k is a positive integer. (Be sure to include a check for convergence at the endpoints of the interval.)

41. $\sum_{n=0}^{\infty} \left(\frac{x}{k}\right)^n$
42. $\sum_{n=1}^{\infty} \frac{(-1)^{n+1}(x - c)^n}{nc^n}$
43. $\sum_{n=1}^{\infty} \frac{k(k + 1)(k + 2) \cdot \cdots (k + n - 1)x^n}{n!}$
44. $\sum_{n=1}^{\infty} \frac{n!(x - c)^n}{1 \cdot 3 \cdot 5 \cdot \cdots (2n - 1)}$

Writing an Equivalent Series

In Exercises 45–48, write an equivalent series with the index of summation beginning at $n = 1$.

45. $\sum_{n=0}^{\infty} \frac{x^n}{n!}$
46. $\sum_{n=0}^{\infty} (-1)^{n+1}(n + 1)x^n$
47. $\sum_{n=2}^{\infty} \frac{x^{n-1}}{(7n - 1)!}$
48. $\sum_{n=2}^{\infty} \frac{x^{3n-1}}{(2n - 1)!}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding Intervals of Convergence **In Exercises 49–52, find the intervals of convergence of (a) $f(x)$, (b) $f'(x)$, (c) $f''(x)$, and (d) $\int f(x)\,dx$. (Be sure to include a check for convergence at the endpoints of the intervals.)**

49. $f(x) = \sum_{n=0}^{\infty} \left(\frac{x}{3}\right)^n$

50. $f(x) = \sum_{n=1}^{\infty} \frac{(-1)^{n+1}(x-5)^n}{n5^n}$

51. $f(x) = \sum_{n=0}^{\infty} \frac{(-1)^{n+1}(x-1)^{n+1}}{n+1}$

52. $f(x) = \sum_{n=1}^{\infty} \frac{(-1)^{n+1}(x-2)^n}{n}$

Exploring Concepts

In Exercises 53 and 54, write a power series that has the indicated interval of convergence. Explain your reasoning.

53. $(-3, 3)$

54. $[-3, 7]$

55. Give examples that show that the convergence of a power series at an endpoint of its interval of convergence may be either conditional or absolute. Explain your reasoning.

56. HOW DO YOU SEE IT? Match the graph of the first 10 terms of the sequence of partial sums of the series

$$g(x) = \sum_{n=0}^{\infty} \left(\frac{x}{3}\right)^n$$

with the indicated value of the function. [The graphs are labeled (i), (ii), (iii), and (iv).] Explain how you made your choice.



(a) $g(1)$ (b) $g(2)$

(c) $g(3)$ (d) $g(-2)$

57. Using Power Series Let $f(x) = \sum_{n=0}^{\infty} \frac{(-1)^n x^{2n+1}}{(2n+1)!}$ and $g(x) = \sum_{n=0}^{\infty} \frac{(-1)^n x^{2n}}{(2n)!}$.

(a) Find the intervals of convergence of f and g.

(b) Show that $f'(x) = g(x)$ and $g'(x) = -f(x)$.

(c) Identify the functions f and g.

58. Using a Power Series Let $f(x) = \sum_{n=0}^{\infty} \frac{x^{2n+1}}{(2n+1)!}$ and $g(x) = \sum_{n=0}^{\infty} \frac{x^{2n}}{(2n)!}$.

(a) Find the intervals of convergence of f and g.

(b) Show that $f'(x) = g(x)$ and $g'(x) = f(x)$.

(c) Identify the functions f and g.

Differential Equation **In Exercises 59–64, show that the function represented by the power series is a solution of the differential equation.**

59. $y = \sum_{n=0}^{\infty} \frac{(-1)^n x^{2n+1}}{(2n+1)!}$, $y'' + y = 0$

60. $y = \sum_{n=0}^{\infty} \frac{(-1)^n x^{2n}}{(2n)!}$, $y'' + y = 0$

61. $y = \sum_{n=0}^{\infty} \frac{x^{2n+1}}{(2n+1)!}$, $y'' - y = 0$

62. $y = \sum_{n=0}^{\infty} \frac{x^{2n}}{(2n)!}$, $y'' - y = 0$

63. $y = \sum_{n=0}^{\infty} \frac{x^{2n}}{2^n n!}$, $y'' - xy' - y = 0$

64. $y = 1 + \sum_{n=1}^{\infty} \frac{(-1)^n x^{4n}}{2^{2n} n! \cdot 3 \cdot 7 \cdot 11 \cdot \cdots \cdot (4n-1)}$, $y'' + x^2 y = 0$

65. Bessel Function The Bessel function of order 0 is

$$J_0(x) = \sum_{k=0}^{\infty} \frac{(-1)^k x^{2k}}{2^{2k}(k!)^2}.$$

(a) Show that the series converges for all x.

(b) Show that the series is a solution of the differential equation $x^2 J_0'' + x J_0' + x^2 J_0 = 0$.

(c) Use a graphing utility to graph the polynomial composed of the first four terms of J_0.

(d) Approximate $\int_0^1 J_0\,dx$ accurate to two decimal places.

66. Bessel Function The Bessel function of order 1 is

$$J_1(x) = x \sum_{k=0}^{\infty} \frac{(-1)^k x^{2k}}{2^{2k+1} k!(k+1)!}$$

(a) Show that the series converges for all x.

(b) Show that the series is a solution of the differential equation $x^2 J_1'' + x J_1' + (x^2 - 1) J_1 = 0$.

(c) Use a graphing utility to graph the polynomial composed of the first four terms of J_1.

(d) Use J_0 from Exercise 65 to show that $J_0'(x) = -J_1(x)$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

67. Investigation The interval of convergence of the geometric series $\sum_{n=0}^{\infty}\left(\frac{x}{4}\right)^n$ is $(-4, 4)$.

(a) Find the sum of the series when $x = \frac{5}{2}$. Use a graphing utility to graph the first six terms of the sequence of partial sums and the horizontal line representing the sum of the series.

(b) Repeat part (a) for $x = -\frac{5}{2}$.

(c) Write a short paragraph comparing the rates of convergence of the partial sums with the sums of the series in parts (a) and (b). How do the plots of the partial sums differ as they converge toward the sum of the series?

(d) Given any positive real number M, there exists a positive integer N such that the partial sum

$$\sum_{n=0}^{N}\left(\frac{5}{4}\right)^n > M.$$

Use a graphing utility to complete the table.

M	10	100	1000	10,000
N				

68. Investigation The interval of convergence of the series $\sum_{n=0}^{\infty}(3x)^n$ is $\left(-\frac{1}{3}, \frac{1}{3}\right)$.

(a) Find the sum of the series when $x = \frac{1}{6}$. Use a graphing utility to graph the first six terms of the sequence of partial sums and the horizontal line representing the sum of the series.

(b) Repeat part (a) for $x = -\frac{1}{6}$.

(c) Write a short paragraph comparing the rates of convergence of the partial sums with the sums of the series in parts (a) and (b). How do the plots of the partial sums differ as they converge toward the sum of the series?

(d) Given any positive real number M, there exists a positive integer N such that the partial sum

$$\sum_{n=0}^{N}\left(3 \cdot \frac{2}{3}\right)^n > M.$$

Use a graphing utility to complete the table.

M	10	100	1000	10,000
N				

Identifying a Function **In Exercises 69–72, the series represents a well-known function. Use a graphing utility to graph the partial sum S_{10} and identify the function from the graph.**

69. $f(x) = \sum_{n=0}^{\infty}(-1)^n \frac{\pi^{2n}x^{2n}}{(2n)!}$

70. $f(x) = \sum_{n=0}^{\infty}(-1)^{n+1} \frac{x^{2n+1}}{(2n+1)!}$

71. $f(x) = \sum_{n=0}^{\infty}(-1)^n x^n, \quad -1 < x < 1$

72. $f(x) = \sum_{n=0}^{\infty}(3x)^n$

True or False? **In Exercises 73–75, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

73. If the interval of convergence for

$$\sum_{n=0}^{\infty} a_n x^n$$

is $(-1, 1)$, then the interval of convergence for $\sum_{n=0}^{\infty} a_n(x-1)^n$ is $(0, 2)$.

74. It is possible to find a power series whose interval of convergence is $[0, \infty)$.

75. If $f(x) = \sum_{n=0}^{\infty} a_n x^n$ converges for $|x| < 2$, then

$$\int_0^1 f(x)\,dx = \sum_{n=0}^{\infty}\frac{a_n}{n+1}.$$

76. Using a Power Series Let

$$g(x) = 1 + 2x + x^2 + 2x^3 + x^4 + \cdots$$

where the coefficients are $c_{2n} = 1$ and $c_{2n+1} = 2$ for $n \geq 0$.

(a) Find the interval of convergence of the series.

(b) Find an explicit formula for $g(x)$.

77. Using a Power Series Let

$$f(x) = \sum_{n=0}^{\infty} c_n x^n$$

where $c_{n+3} = c_n$ for $n \geq 0$.

(a) Find the interval of convergence of the series.

(b) Find an explicit formula for $f(x)$.

78. Proof Prove that the power series

$$\sum_{n=0}^{\infty}\frac{(n+p)!}{n!(n+q)!}x^n$$

has a radius of convergence of $R = \infty$ when p and q are positive integers.

79. Proof For $n > 0$, let $R > 0$ and $c_n > 0$. Prove that if the interval of convergence of the series

$$\sum_{n=0}^{\infty} c_n(x - x_0)^n$$

is $[x_0 - R, x_0 + R)$, then the series converges conditionally at $x = x_0 - R$.

80. Proof Prove that if the power series $\sum_{n=0}^{\infty} c_n x^n$ has a radius of convergence of R, then $\sum_{n=0}^{\infty} c_n x^{2n}$ has a radius of convergence of $\sqrt{R}$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

9.9 Representation of Functions by Power Series

GO DIGITAL

- **Find a geometric power series that represents a function.**
- **Construct a power series using series operations.**

JOSEPH FOURIER (1768–1830)

Some of the early work in representing functions by power series was done by the French mathematician Joseph Fourier. Fourier's work is important in the history of calculus, partly because it forced eighteenth-century mathematicians to question the then-prevailing narrow concept of a function. Both Cauchy and Dirichlet were motivated by Fourier's work with series, and in 1837, Dirichlet published the general definition of a function that is used today.

See LarsonCalculus.com to read more of this biography.

Geometric Power Series

In this section and the next section, you will study several techniques for finding a power series that represents a function. Consider the function

$$f(x) = \frac{1}{1 - x}.$$

The form of f closely resembles the sum of a geometric series

$$\sum_{n=0}^{\infty} ar^n = \frac{a}{1 - r}, \quad |r| < 1.$$

In other words, when $a = 1$ and $r = x$, a power series representation for $1/(1 - x)$, centered at 0, is

$$\begin{aligned} \frac{1}{1 - x} &= \sum_{n=0}^{\infty} ar^n \\ &= \sum_{n=0}^{\infty} x^n \\ &= 1 + x + x^2 + x^3 + \cdots, \quad |x| < 1. \end{aligned}$$

Of course, this series represents $f(x) = 1/(1 - x)$ only on the interval $(-1, 1)$, whereas f is defined for all $x \neq 1$, as shown in Figure 9.24. To represent f in another interval, you must develop a different series. For instance, to obtain the power series centered at -1, you could write

$$\frac{1}{1 - x} = \frac{1}{2 - (x + 1)} = \frac{1/2}{1 - [(x + 1)/2]} = \frac{a}{1 - r}$$

which implies that $a = \frac{1}{2}$ and $r = (x + 1)/2$. So, for $|x + 1| < 2$, you have

$$\begin{aligned} \frac{1}{1 - x} &= \sum_{n=0}^{\infty} \left(\frac{1}{2}\right)\left(\frac{x + 1}{2}\right)^n \\ &= \frac{1}{2}\left[1 + \frac{(x + 1)}{2} + \frac{(x + 1)^2}{4} + \frac{(x + 1)^3}{8} + \cdots\right], \quad |x + 1| < 2 \end{aligned}$$

which converges on the interval $(-3, 1)$.



Figure 9.24

Science History Images/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 1 Finding a Geometric Power Series Centered at 0

Find a power series for $f(x) = \dfrac{4}{x+2}$, centered at 0.

Solution Writing $f(x)$ in the form $a/(1-r)$ produces

$$\frac{4}{2+x} = \frac{2}{1-(-x/2)} = \frac{a}{1-r}$$

which implies that $a = 2$ and

$$r = -\frac{x}{2}.$$

So, the power series for $f(x)$ is

$$\begin{aligned}\frac{4}{x+2} &= \sum_{n=0}^{\infty} ar^n \\ &= \sum_{n=0}^{\infty} 2\left(-\frac{x}{2}\right)^n \\ &= 2\left(1 - \frac{x}{2} + \frac{x^2}{4} - \frac{x^3}{8} + \cdots\right).\end{aligned}$$

This power series converges when

$$\left|-\frac{x}{2}\right| < 1$$

which implies that the interval of convergence is $(-2, 2)$. ■

Long Division

$$\begin{array}{r} 2 - x + \frac{1}{2}x^2 - \frac{1}{4}x^3 + \cdots \\ 2 + x \overline{)\,4} \\ \underline{4 + 2x} \\ -2x \\ \underline{-2x - x^2} \\ x^2 \\ \underline{x^2 + \frac{1}{2}x^3} \\ -\frac{1}{2}x^3 \\ \underline{-\frac{1}{2}x^3 - \frac{1}{4}x^4} \end{array}$$

Another way to determine a power series for a rational function such as the one in Example 1 is to use long division. For instance, by dividing $2 + x$ into 4, you obtain the result shown at the left.

EXAMPLE 2 Finding a Geometric Power Series Centered at 1

Find a power series for $f(x) = \dfrac{1}{x}$, centered at 1.

Solution Writing $f(x)$ in the form $a/(1-r)$ produces

$$\frac{1}{x} = \frac{1}{1-(-x+1)} = \frac{a}{1-r}$$

which implies that $a = 1$ and $r = 1 - x = -(x-1)$. So, the power series for $f(x)$ is

$$\begin{aligned}\frac{1}{x} &= \sum_{n=0}^{\infty} ar^n \\ &= \sum_{n=0}^{\infty} [-(x-1)]^n \\ &= \sum_{n=0}^{\infty} (-1)^n (x-1)^n \\ &= 1 - (x-1) + (x-1)^2 - (x-1)^3 + \cdots.\end{aligned}$$

This power series converges when

$$|x-1| < 1$$

which implies that the interval of convergence is $(0, 2)$. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Operations with Power Series

The versatility of geometric power series will be shown later in this section, following a discussion of power series operations. These operations, used with differentiation and integration, provide a means of developing power series for a variety of elementary functions. (For simplicity, the operations are stated for a series centered at 0.)

Operations with Power Series

Let $f(x) = \sum_{n=0}^{\infty} a_n x^n$ and $g(x) = \sum_{n=0}^{\infty} b_n x^n$.

1. $f(kx) = \sum_{n=0}^{\infty} a_n k^n x^n$
2. $f(x^N) = \sum_{n=0}^{\infty} a_n x^{nN}$
3. $f(x) \pm g(x) = \sum_{n=0}^{\infty} (a_n \pm b_n) x^n$

The operations described above can change the interval of convergence for the resulting series. For example, in the addition shown below, the interval of convergence for the sum is the *intersection* of the intervals of convergence of the two original series.

$$\underbrace{\sum_{n=0}^{\infty} x^n}_{(-1,\,1)} + \underbrace{\sum_{n=0}^{\infty} \left(\frac{x}{2}\right)^n}_{(-2,\,2)} = \underbrace{\sum_{n=0}^{\infty} \left(1 + \frac{1}{2^n}\right) x^n}_{(-1,\,1)}$$

$(-1, 1) \cap (-2, 2) = (-1, 1)$

EXAMPLE 3 Adding Two Power Series

Find a power series for

$$f(x) = \frac{3x - 1}{x^2 - 1}$$

centered at 0.

Solution Using partial fractions, you can write $f(x)$ as

$$\frac{3x - 1}{x^2 - 1} = \frac{2}{x + 1} + \frac{1}{x - 1}.$$

By adding the two geometric power series

$$\frac{2}{x + 1} = \frac{2}{1 - (-x)} = \sum_{n=0}^{\infty} 2(-1)^n x^n, \quad |x| < 1$$

and

$$\frac{1}{x - 1} = \frac{-1}{1 - x} = -\sum_{n=0}^{\infty} x^n, \quad |x| < 1$$

you obtain the power series shown below.

$$\begin{aligned} \frac{3x - 1}{x^2 - 1} &= \sum_{n=0}^{\infty} \left[2(-1)^n - 1\right] x^n \\ &= 1 - 3x + x^2 - 3x^3 + x^4 - \cdots \end{aligned}$$

The interval of convergence for this power series is $(-1, 1)$. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 4 Finding a Power Series by Integration

Find a power series for

$$f(x) = \ln x$$

centered at 1.

Solution Recall from Example 2 that

$$\frac{1}{x} = \sum_{n=0}^{\infty} (-1)^n (x-1)^n.$$ Interval of convergence: (0, 2)

Integrating this series produces

$$\begin{aligned}\ln x &= \int \frac{1}{x}\,dx + C \\ &= C + \sum_{n=0}^{\infty} (-1)^n \frac{(x-1)^{n+1}}{n+1}.\end{aligned}$$

By letting $x = 1$, you can conclude that $C = 0$. So,

$$\begin{aligned}\ln x &= \sum_{n=0}^{\infty} (-1)^n \frac{(x-1)^{n+1}}{n+1} \\ &= \frac{(x-1)}{1} - \frac{(x-1)^2}{2} + \frac{(x-1)^3}{3} - \frac{(x-1)^4}{4} + \cdots.\end{aligned}$$ Interval of convergence: (0, 2]

Note that the series converges at $x = 2$. This is consistent with the observation in Section 9.8 that integration of a power series may alter the convergence at the endpoints of the interval of convergence. ■

■ **FOR FURTHER INFORMATION** To read about finding a power series using integration by parts, see the article "Integration by Parts and Infinite Series" by Shelby J. Kilmer in *Mathematics Magazine.* To view this article, go to *MathArticles.com.*

In Section 9.7, Example 4, the fourth-degree Taylor polynomial (centered at $c = 1$) for the natural logarithmic function

$$\ln x \approx (x-1) - \frac{(x-1)^2}{2} + \frac{(x-1)^3}{3} - \frac{(x-1)^4}{4}$$

was used to approximate $\ln(1.1)$.

$$\begin{aligned}\ln(1.1) &\approx (0.1) - \frac{1}{2}(0.1)^2 + \frac{1}{3}(0.1)^3 - \frac{1}{4}(0.1)^4 \\ &\approx 0.0953083\end{aligned}$$

You now know from Example 4 in this section that this polynomial represents the first four terms of the power series for $\ln x$. Moreover, using the Alternating Series Remainder, you can determine that the error in this approximation is less than

$$\begin{aligned}|R_4| &\le |a_5| \\ &= \frac{1}{5}(0.1)^5 \\ &= 0.000002.\end{aligned}$$

During the seventeenth and eighteenth centuries, mathematical tables for logarithms and values of other transcendental functions were computed in this manner. Such numerical techniques are far from outdated, because it is precisely by such means that many modern calculating devices are programmed to evaluate transcendental functions.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 5 Finding a Power Series by Integration

See LarsonCalculus.com for an interactive version of this type of example.

Find a power series for

$$g(x) = \arctan x$$

centered at 0.

Solution Because $D_x[\arctan x] = 1/(1 + x^2)$, you can use the series

$$f(x) = \frac{1}{1+x} = \sum_{n=0}^{\infty} (-1)^n x^n. \qquad \text{Interval of convergence: } (-1, 1)$$

Substituting x^2 for x produces

$$f(x^2) = \frac{1}{1+x^2} = \sum_{n=0}^{\infty} (-1)^n x^{2n}.$$

Finally, by integrating, you obtain

$$\begin{aligned} \arctan x &= \int \frac{1}{1+x^2}\,dx + C \\ &= C + \sum_{n=0}^{\infty} (-1)^n \frac{x^{2n+1}}{2n+1} \\ &= \sum_{n=0}^{\infty} (-1)^n \frac{x^{2n+1}}{2n+1} && \text{Let } x = 0, \text{ then } C = 0. \\ &= x - \frac{x^3}{3} + \frac{x^5}{5} - \frac{x^7}{7} + \cdots. && \text{Interval of convergence: } (-1, 1) \end{aligned}$$

SRINIVASA RAMANUJAN (1887–1920)

Series that can be used to approximate π have interested mathematicians for the past 300 years. An amazing series for approximating $1/\pi$ was discovered by the Indian mathematician Srinivasa Ramanujan in 1914 (see Exercise 57). Each successive term of Ramanujan's series adds roughly eight more correct digits to the value of $1/\pi$. For more information about Ramanujan's work, see the article "Ramanujan and Pi" by Jonathan M. Borwein and Peter B. Borwein in *Scientific American*.

See LarsonCalculus.com to read more of this biography.

It can be shown that the power series developed for $\arctan x$ in Example 5 also converges (to $\arctan x$) for $x = \pm 1$. For instance, when $x = 1$, you can write

$$\begin{aligned} \arctan 1 &= 1 - \frac{1}{3} + \frac{1}{5} - \frac{1}{7} + \cdots \\ &= \frac{\pi}{4}. \end{aligned}$$

This series (developed by James Gregory in 1671) is, however, not a practical way of approximating π because it converges so slowly that hundreds of terms have to be used to obtain reasonable accuracy. Example 6 shows how to use *two* different arctangent series to obtain a very good approximation of π using only a few terms. This approximation was developed by John Machin in 1706.

EXAMPLE 6 Approximating π with a Series

Use the trigonometric identity

$$4 \arctan \frac{1}{5} - \arctan \frac{1}{239} = \frac{\pi}{4}$$

to approximate the number π. [See Exercise 44(b).]

Solution By using only five terms from each of the series for $\arctan(1/5)$ and $\arctan(1/239)$, you obtain

$$4\left(4 \arctan \frac{1}{5} - \arctan \frac{1}{239}\right) \approx 3.1415927$$

which agrees with the exact value of π with an error of less than 0.0000001.

FOR FURTHER INFORMATION

To read about other methods for approximating π, see the article "Two Methods for Approximating π" by Chien-Lih Hwang in *Mathematics Magazine*. To view this article, go to *MathArticles.com*.

Saran Images/GRANGER

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

9.9 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain how to use a geometric power series to represent a function of the form $f(x) = \dfrac{b}{c - x}$.

2. Consider $f(x) = \sum_{n=0}^{\infty} 5x^{2n}$. What are the values of a and b in terms of n?

$f\left(\dfrac{x^3}{5}\right) = \sum_{n=0}^{\infty} \dfrac{x^a}{5^b}$

Finding a Geometric Power Series **In Exercises 3–6, find a geometric power series for the function, centered at 0, (a) by the technique shown in Examples 1 and 2 and (b) by long division.**

3. $f(x) = \dfrac{1}{4 - x}$

4. $f(x) = \dfrac{1}{2 + x}$

5. $f(x) = \dfrac{4}{3 + x}$

6. $f(x) = \dfrac{2}{5 - x}$

Finding a Power Series **In Exercises 7–18, find a power series for the function, centered at c, and determine the interval of convergence.**

7. $f(x) = \dfrac{1}{6 - x}, \quad c = 1$

8. $f(x) = \dfrac{2}{6 - x}, \quad c = -2$

9. $f(x) = \dfrac{1}{1 - 3x}, \quad c = 0$

10. $h(x) = \dfrac{1}{1 - 4x}, \quad c = 0$

11. $g(x) = \dfrac{5}{2x - 3}, \quad c = -3$

12. $f(x) = \dfrac{3}{2x - 1}, \quad c = 2$

13. $f(x) = \dfrac{2}{5x + 4}, \quad c = -1$

14. $f(x) = \dfrac{4}{3x + 2}, \quad c = 3$

15. $g(x) = \dfrac{4x}{x^2 + 2x - 3}, \quad c = 0$

16. $g(x) = \dfrac{3x - 8}{3x^2 + 5x - 2}, \quad c = 0$

17. $f(x) = \dfrac{2}{1 - x^2}, \quad c = 0$

18. $f(x) = \dfrac{5}{4 - x^2}, \quad c = 0$

Using a Power Series **In Exercises 19–28, use the power series**

$$\frac{1}{1 + x} = \sum_{n=0}^{\infty} (-1)^n x^n, \quad |x| < 1$$

to find a power series for the function, centered at 0, and determine the interval of convergence.

19. $h(x) = \dfrac{-2}{x^2 - 1} = \dfrac{1}{1 + x} + \dfrac{1}{1 - x}$

20. $h(x) = \dfrac{x}{x^2 - 1} = \dfrac{1}{2(1 + x)} - \dfrac{1}{2(1 - x)}$

21. $f(x) = -\dfrac{1}{(x + 1)^2} = \dfrac{d}{dx}\left[\dfrac{1}{x + 1}\right]$

22. $f(x) = \dfrac{2}{(x + 1)^3} = \dfrac{d^2}{dx^2}\left[\dfrac{1}{x + 1}\right]$

23. $f(x) = \ln(x + 1) = \displaystyle\int \frac{1}{x + 1}\,dx$

24. $f(x) = \ln(1 - x^2) = \displaystyle\int \frac{1}{1 + x}\,dx - \int \frac{1}{1 - x}\,dx$

25. $g(x) = \dfrac{1}{x^2 + 1}$

26. $f(x) = \ln(x^2 + 1)$

27. $h(x) = \dfrac{1}{4x^2 + 1}$

28. $f(x) = \arctan 2x$

Graphical and Numerical Analysis **In Exercises 29 and 30, let**

$$S_n = x - \frac{x^2}{2} + \frac{x^3}{3} - \frac{x^4}{4} + \cdots \pm \frac{x^n}{n}.$$

Use a graphing utility to confirm the inequality graphically. Then complete the table to confirm the inequality numerically.

x	0.0	0.2	0.4	0.6	0.8	1.0
S_n						
$\ln(x + 1)$						
S_{n+1}						

29. $S_2 \le \ln(x + 1) \le S_3$

30. $S_4 \le \ln(x + 1) \le S_5$

Approximating a Sum **In Exercises 31 and 32, (a) use a graphing utility to graph several partial sums of the series, (b) find the sum of the series and its radius of convergence, (c) use a graphing utility and 50 terms of the series to approximate the sum when $x = 0.5$, and (d) determine what the approximation represents and how good the approximation is.**

31. $\displaystyle\sum_{n=1}^{\infty} \frac{(-1)^{n+1}(x - 1)^n}{n}$

32. $\displaystyle\sum_{n=0}^{\infty} \frac{(-1)^n x^{2n+1}}{(2n + 1)!}$

Approximating a Value **In Exercises 33–36, use the power series for $f(x) = \arctan x$ to approximate the value, using $R_N \le 0.001$.**

33. $\arctan \dfrac{1}{4}$

34. $\displaystyle\int_0^{3/4} \arctan x^2\,dx$

35. $\displaystyle\int_0^{1/2} \frac{\arctan x^2}{x}\,dx$

36. $\displaystyle\int_0^{1/2} x^2 \arctan x\,dx$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Using a Power Series **In Exercises 37–40, use the power series**

$$\frac{1}{1-x} = \sum_{n=0}^{\infty} x^n, \quad |x| < 1$$

to find a power series for the function, centered at 0, and determine the interval of convergence.

37. $f(x) = \dfrac{1}{(1-x)^2}$

38. $f(x) = \dfrac{x}{(1-x)^2}$

39. $f(x) = \dfrac{1+x}{(1-x)^2}$

40. $f(x) = \dfrac{x(1+x)}{(1-x)^2}$

41. Probability A fair coin is tossed repeatedly. The probability that the first head occurs on the nth toss is $P(n) = \left(\frac{1}{2}\right)^n$. When this game is repeated many times, the average number of tosses required until the first head occurs is

$$E(n) = \sum_{n=1}^{\infty} nP(n).$$

(This value is called the *expected value* of n.) Use the results of Exercises 37–40 to find $E(n)$. Is the answer what you expected? Why or why not?

42. Finding the Sum of a Series Use the results of Exercises 37–40 to find the sum of each series.

(a) $\dfrac{1}{3}\displaystyle\sum_{n=1}^{\infty} n\left(\frac{2}{3}\right)^n$ (b) $\dfrac{1}{10}\displaystyle\sum_{n=1}^{\infty} n\left(\frac{9}{10}\right)^n$

43. Proof Prove that

$$\arctan x + \arctan y = \arctan\frac{x+y}{1-xy}$$

for $xy \neq 1$, provided the value of the left side of the equation is between $-\pi/2$ and $\pi/2$.

44. Verifying an Identity Use the result of Exercise 43 to verify each identity.

(a) $\arctan\dfrac{120}{119} - \arctan\dfrac{1}{239} = \dfrac{\pi}{4}$

(b) $4\arctan\dfrac{1}{5} - \arctan\dfrac{1}{239} = \dfrac{\pi}{4}$

[*Hint:* Use Exercise 43 twice to find $4\arctan\frac{1}{5}$. Then use part (a).]

Approximating Pi **In Exercises 45 and 46, (a) use the result of Exercise 43 to verify the given identity and (b) use the identity and the series for the arctangent to approximate π by using four terms of each series.**

45. $2\arctan\dfrac{1}{2} - \arctan\dfrac{1}{7} = \dfrac{\pi}{4}$

46. $\arctan\dfrac{1}{2} + \arctan\dfrac{1}{3} = \dfrac{\pi}{4}$

Finding the Sum of a Series **In Exercises 47–52, find the sum of the convergent series by using a well-known function. Identify the function and explain how you obtained the sum.**

47. $\displaystyle\sum_{n=1}^{\infty} (-1)^{n+1}\frac{1}{2^n n}$

48. $\displaystyle\sum_{n=1}^{\infty} (-1)^{n+1}\frac{1}{3^n n}$

49. $\displaystyle\sum_{n=1}^{\infty} (-1)^{n+1}\frac{2^n}{5^n n}$

50. $\displaystyle\sum_{n=0}^{\infty} (-1)^{n}\frac{1}{2n+1}$

51. $\displaystyle\sum_{n=0}^{\infty} (-1)^{n}\frac{1}{2^{2n+1}(2n+1)}$

52. $\displaystyle\sum_{n=1}^{\infty} (-1)^{n+1}\frac{1}{3^{2n-1}(2n-1)}$

Exploring Concepts

53. Determine which of the series in Exercises 47–52 converges to its sum at a much slower rate than the other five series. Explain why this series converges so slowly. Use a graphing utility to illustrate the rate of convergence.

54. The radius of convergence of the power series $\displaystyle\sum_{n=0}^{\infty} a_n x^n$ is 3. What is the radius of convergence of the series

$$\sum_{n=1}^{\infty} n a_n x^{n-1}?$$

Explain.

55. The power series $\displaystyle\sum_{n=0}^{\infty} a_n x^n$ converges for $|x+1| < 4$. What can you conclude about the convergence of the series

$$\sum_{n=0}^{\infty} a_n \frac{x^{n+1}}{n+1}?$$

Explain.

56. HOW DO YOU SEE IT? The figure on the left shows the graph of a function. The figure on the right shows the graph of a power series representation of the function.



(a) Identify the function.

(b) What are the center and interval of convergence of the power series?

57. Ramanujan and Pi Use a graphing utility to show that

$$\frac{\sqrt{8}}{9801}\sum_{n=0}^{\infty}\frac{(4n)!(1103+26{,}390n)}{(n!)^4 396^{4n}} = \frac{1}{\pi}.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

9.10 Taylor and Maclaurin Series

GO DIGITAL

- Find a Taylor or Maclaurin series for a function.
- Find a binomial series.
- Use a basic list of Taylor series to find other Taylor series.

Taylor Series and Maclaurin Series

In Section 9.9, you derived power series for several functions using geometric series with term-by-term differentiation or integration. In this section, you will study a *general* procedure for deriving the power series for a function that has derivatives of all orders. The next theorem gives the form that *every* convergent power series must take.

REMARK Be sure you understand Theorem 9.22. The theorem says that *if a power series converges to* $f(x)$, then the series must be a Taylor series. The theorem does *not* say that every series formed with the Taylor coefficients $a_n = f^{(n)}(c)/n!$ will converge to $f(x)$.

THEOREM 9.22 The Form of a Convergent Power Series

If f is represented by a power series $f(x) = \Sigma\, a_n(x - c)^n$ for all x in an open interval I containing c, then

$$a_n = \frac{f^{(n)}(c)}{n!}$$

and

$$f(x) = f(c) + f'(c)(x - c) + \frac{f''(c)}{2!}(x - c)^2 + \cdots + \frac{f^{(n)}(c)}{n!}(x - c)^n + \cdots.$$

Proof Consider a power series $\Sigma\, a_n(x - c)^n$ that has a radius of convergence R. Then, by Theorem 9.21, the nth derivative of f exists for $|x - c| < R$, and by successive differentiation you obtain the following.

$$\begin{aligned}
f^{(0)}(x) &= a_0 + a_1(x - c) + a_2(x - c)^2 + a_3(x - c)^3 + a_4(x - c)^4 + \cdots \\
f^{(1)}(x) &= a_1 + 2a_2(x - c) + 3a_3(x - c)^2 + 4a_4(x - c)^3 + \cdots \\
f^{(2)}(x) &= 2a_2 + 3!a_3(x - c) + 4 \cdot 3a_4(x - c)^2 + \cdots \\
f^{(3)}(x) &= 3!a_3 + 4!a_4(x - c) + \cdots \\
&\vdots \\
f^{(n)}(x) &= n!a_n + (n + 1)!a_{n+1}(x - c) + \cdots
\end{aligned}$$

Evaluating each of these derivatives at $x = c$ yields

$$\begin{aligned}
f^{(0)}(c) &= 0!a_0 \\
f^{(1)}(c) &= 1!a_1 \\
f^{(2)}(c) &= 2!a_2 \\
f^{(3)}(c) &= 3!a_3
\end{aligned}$$

and, in general, $f^{(n)}(c) = n!a_n$. Solving for a_n, the coefficients of the power series representation of $f(x)$ are

$$a_n = \frac{f^{(n)}(c)}{n!}.$$

Notice that the coefficients of the power series in Theorem 9.22 are precisely the coefficients of the Taylor polynomials for f at c as defined in Section 9.7. For this reason, the series is called the **Taylor series** for f at c.

MADHAVA (1350–1425)

Madhava, a mathematician and astronomer, was born in 1350 in Sangamagramma in Kerala, India. Although some of his astronomy texts have been preserved, none of his works in mathematics have survived. It was only through research into other Keralese mathematicians that Madhava's relevance in mathematics was again uncovered. Around 1400, Madhava identified infinite series equivalent to what is now known as the Maclaurin expansions of the sine, cosine, and arctangent functions. This puts his discovery of the series over 200 years before their rediscovery in Europe.
See LarsonCalculus.com to read more of this biography.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

COLIN MACLAURIN (1698–1746)

The development of power series to represent functions is credited to the combined work of many seventeenth- and eighteenth-century mathematicians. Gregory, Newton, John and James Bernoulli, Leibniz, Euler, Lagrange, Wallis, and Fourier all contributed to this work. However, the two names that are most commonly associated with power series are Brook Taylor and Colin Maclaurin.

See LarsonCalculus.com to read more of this biography.

Definition of Taylor and Maclaurin Series

If a function f has derivatives of all orders at $x = c$, then the series

$$\sum_{n=0}^{\infty} \frac{f^{(n)}(c)}{n!}(x-c)^n = f(c) + f'(c)(x-c) + \cdots + \frac{f^{(n)}(c)}{n!}(x-c)^n + \cdots$$

is called the **Taylor series for f at c.** Moreover, if $c = 0$, then the series is the **Maclaurin series for f.**

When you know the pattern for the coefficients of the Taylor polynomials for a function, you can extend the pattern to form the corresponding Taylor series. For instance, in Example 4 in Section 9.7, you found the fourth Taylor polynomial for $\ln x$, centered at 1, to be

$$P_4(x) = (x-1) - \frac{1}{2}(x-1)^2 + \frac{1}{3}(x-1)^3 - \frac{1}{4}(x-1)^4.$$

From this pattern, you can obtain the Taylor series for $\ln x$ centered at $c = 1$,

$$(x-1) - \frac{1}{2}(x-1)^2 + \cdots + \frac{(-1)^{n+1}}{n}(x-1)^n + \cdots.$$

EXAMPLE 1 Forming a Power Series

Use the function

$$f(x) = \sin x$$

to form the Maclaurin series

$$\sum_{n=0}^{\infty} \frac{f^{(n)}(0)}{n!}x^n = f(0) + f'(0)x + \frac{f''(0)}{2!}x^2 + \frac{f'''(0)}{3!}x^3 + \frac{f^{(4)}(0)}{4!}x^4 + \cdots$$

and determine the interval of convergence.

Solution Taking successive derivatives of f yields

$f(x) = \sin x$	$f(0) = \sin 0 = 0$	Original function
$f'(x) = \cos x$	$f'(0) = \cos 0 = 1$	First derivative
$f''(x) = -\sin x$	$f''(0) = -\sin 0 = 0$	Second derivative
$f'''(x) = -\cos x$	$f'''(0) = -\cos 0 = -1$	Third derivative
$f^{(4)}(x) = \sin x$	$f^{(4)}(0) = \sin 0 = 0$	Fourth derivative
$f^{(5)}(x) = \cos x$	$f^{(5)}(0) = \cos 0 = 1$	Fifth derivative

and so on. The pattern repeats after the third derivative. So, the power series is as follows.

$$\begin{aligned}\sum_{n=0}^{\infty} \frac{f^{(n)}(0)}{n!}x^n &= f(0) + f'(0)x + \frac{f''(0)}{2!}x^2 + \frac{f'''(0)}{3!}x^3 + \frac{f^{(4)}(0)}{4!}x^4 + \cdots \\ &= 0 + (1)x + \frac{0}{2!}x^2 + \frac{(-1)}{3!}x^3 + \frac{0}{4!}x^4 + \frac{1}{5!}x^5 + \frac{0}{6!}x^6 + \frac{(-1)}{7!}x^7 + \cdots \\ &= x - \frac{x^3}{3!} + \frac{x^5}{5!} - \frac{x^7}{7!} + \cdots \\ &= \sum_{n=0}^{\infty} \frac{(-1)^n x^{2n+1}}{(2n+1)!}\end{aligned}$$

By the Ratio Test, you can conclude that this series converges for all x. ■

GO DIGITAL

Science History Images/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 9.25

Notice that in Example 1, you cannot conclude that the power series converges to $\sin x$ for all x. You can simply conclude that the power series converges to some function, but you are not sure what function it is. This is a subtle, but important, point in dealing with Taylor or Maclaurin series. To persuade yourself that the series

$$f(c) + f'(c)(x - c) + \frac{f''(c)}{2!}(x - c)^2 + \cdots + \frac{f^{(n)}(c)}{n!}(x - c)^n + \cdots$$

might converge to a function other than f, remember that the derivatives are being evaluated at a single point. It can easily happen that another function will agree with the values of $f^{(n)}(x)$ when $x = c$ and disagree at other x-values. For instance, the power series (centered at 0) for the function f shown in Figure 9.25 is the same series as in Example 1. The series converges for all x, and yet it obviously cannot converge to both $f(x)$ and $\sin x$ for all x.

Let f have derivatives of all orders in an open interval I centered at c. The Taylor series for f may fail to converge for some x in I. Even when the series is convergent, it may fail to have $f(x)$ as its sum. Nevertheless, Theorem 9.19 tells us that for each n,

$$f(x) = f(c) + f'(c)(x - c) + \frac{f''(c)}{2!}(x - c)^2 + \cdots + \frac{f^{(n)}(c)}{n!}(x - c)^n + R_n(x)$$

where

$$R_n(x) = \frac{f^{(n+1)}(z)}{(n + 1)!}(x - c)^{n+1}.$$

Note that in this remainder formula, the particular value of z that makes the remainder formula true depends on the values of x and n. If $R_n \to 0$ as $n \to \infty$, then the next theorem tells us that the Taylor series for f actually converges to $f(x)$ for all x in I.

THEOREM 9.23 Convergence of Taylor Series

If $\lim_{n\to\infty} R_n = 0$ for all x in the interval I, then the Taylor series for f converges and equals $f(x)$,

$$f(x) = \sum_{n=0}^{\infty} \frac{f^{(n)}(c)}{n!}(x - c)^n.$$

Proof For a Taylor series, the nth partial sum coincides with the nth Taylor polynomial. That is, $S_n(x) = P_n(x)$. Moreover, because

$$P_n(x) = f(x) - R_n(x)$$

it follows that

$$\begin{aligned} \lim_{n\to\infty} S_n(x) &= \lim_{n\to\infty} P_n(x) \\ &= \lim_{n\to\infty} [f(x) - R_n(x)] \\ &= f(x) - \lim_{n\to\infty} R_n(x). \end{aligned}$$

So, for a given x, the Taylor series (the sequence of partial sums) converges to $f(x)$ if and only if $R_n(x) \to 0$ as $n \to \infty$. ■

Stated another way, Theorem 9.23 says that a power series formed with Taylor coefficients

$$a_n = \frac{f^{(n)}(c)}{n!}$$

converges to the function from which it was derived at precisely those values for which the remainder approaches 0 as $n \to \infty$.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

In Example 1, you derived the power series from the sine function and you also concluded that the series converges to some function on the entire real number line. In Example 2, you will see that the series actually converges to sin x. The key observation is that although the value of z is not known, it is possible to obtain an upper bound for

$$|f^{(n+1)}(z)|.$$

EXAMPLE 2 A Convergent Maclaurin Series

Show that the Maclaurin series for

$$f(x) = \sin x$$

converges to sin x for all x.

Solution Using the result in Example 1, you need to show that

$$\sin x = x - \frac{x^3}{3!} + \frac{x^5}{5!} - \frac{x^7}{7!} + \cdots + \frac{(-1)^n x^{2n+1}}{(2n+1)!} + \cdots$$

is true for all x. Because

$$f^{(n+1)}(x) = \pm\sin x$$

or

$$f^{(n+1)}(x) = \pm\cos x$$

you can conclude that

$$|f^{(n+1)}(z)| \leq 1$$

for every real number z. So, for any fixed x, you can apply Taylor's Theorem (Theorem 9.19) to conclude that

$$0 \leq |R_n(x)| = \left|\frac{f^{(n+1)}(z)}{(n+1)!}x^{n+1}\right| \leq \frac{|x|^{n+1}}{(n+1)!}.$$

From the discussion in Section 9.1 regarding the relative rates of convergence of exponential and factorial sequences, it follows that for a fixed x,

$$\lim_{n\to\infty} \frac{|x|^{n+1}}{(n+1)!} = 0.$$

Finally, by the Squeeze Theorem, it follows that for all x, $R_n(x) \to 0$ as $n \to \infty$. So, by Theorem 9.23, the Maclaurin series for sin x converges to sin x for all x. ■

Figure 9.26 shows the convergence of the Maclaurin series for sin x by comparing the graphs of the Maclaurin polynomials P_1, P_3, P_5, and P_7 with the graph of the sine function. Notice that as the degree of the polynomial increases, its graph more closely resembles that of the sine function.



As n increases, the graph of P_n more closely resembles the sine function.

Figure 9.26

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

The guidelines for finding a Taylor series for f at c are summarized below.

Guidelines for Finding a Taylor Series

1. Differentiate f with respect to x several times and evaluate each derivative at c.

   $$f(c), f'(c), f''(c), f'''(c), \cdots, f^{(n)}(c), \cdots$$

   Try to recognize a pattern in these numbers.
2. Use the sequence developed in the first step to form the Taylor coefficients $a_n = f^{(n)}(c)/n!$ and determine the interval of convergence for the resulting power series

   $$f(c) + f'(c)(x - c) + \frac{f''(c)}{2!}(x - c)^2 + \cdots + \frac{f^{(n)}(c)}{n!}(x - c)^n + \cdots.$$

3. Within this interval of convergence, determine whether the series converges to $f(x)$.

REMARK When you have difficulty recognizing a pattern, remember that you can use Theorem 9.22 to find the Taylor series. Also, you can try using the coefficients of a known Taylor or Maclaurin series, as shown in Example 3.

The direct determination of Taylor or Maclaurin coefficients using successive differentiation can be difficult, and the next example illustrates a shortcut for finding the coefficients indirectly—using the coefficients of a known Taylor or Maclaurin series.

EXAMPLE 3 **Maclaurin Series for a Composite Function**

Find the Maclaurin series for

$$f(x) = \sin x^2.$$

Solution To find the coefficients for this Maclaurin series directly, you must calculate successive derivatives of $f(x) = \sin x^2$. Calculating the first two derivatives

$$f'(x) = 2x \cos x^2$$

and

$$f''(x) = -4x^2 \sin x^2 + 2 \cos x^2$$

shows you that this task would be quite cumbersome. Fortunately, there is an alternative. First, consider the Maclaurin series for $\sin x$ found in Example 1.

$$g(x) = \sin x = x - \frac{x^3}{3!} + \frac{x^5}{5!} - \frac{x^7}{7!} + \cdots$$

Now, because $\sin x^2 = g(x^2)$, you can substitute x^2 for x in the series for $\sin x$ to obtain

$$\sin x^2 = g(x^2) = x^2 - \frac{x^6}{3!} + \frac{x^{10}}{5!} - \frac{x^{14}}{7!} + \cdots.$$

Be sure to understand the point illustrated in Example 3. Because direct computation of Taylor or Maclaurin coefficients can be tedious, the most practical way to find a Taylor or Maclaurin series is to develop power series for a *basic list* of elementary functions. From this list, you can determine power series for other functions by the operations of addition, subtraction, multiplication, division, differentiation, integration, and composition with known power series.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Binomial Series

Before presenting the basic list for elementary functions, you will develop one more series—for a function of the form $f(x) = (1 + x)^k$. This produces the **binomial series.**

EXAMPLE 4 Binomial Series

Find the Maclaurin series for

$$f(x) = (1 + x)^k$$

and determine its radius of convergence. Assume that k is not a positive integer and $k \neq 0$.

Solution By successive differentiation, you have

$$\begin{aligned} f(x) &= (1 + x)^k & f(0) &= 1 \\ f'(x) &= k(1 + x)^{k-1} & f'(0) &= k \\ f''(x) &= k(k - 1)(1 + x)^{k-2} & f''(0) &= k(k - 1) \\ f'''(x) &= k(k - 1)(k - 2)(1 + x)^{k-3} & f'''(0) &= k(k - 1)(k - 2) \\ &\vdots & &\vdots \\ f^{(n)}(x) &= k \cdot \cdot \cdot (k - n + 1)(1 + x)^{k-n} & f^{(n)}(0) &= k(k - 1) \cdot \cdot \cdot (k - n + 1) \end{aligned}$$

which produces the series

$$1 + kx + \frac{k(k - 1)x^2}{2} + \cdot \cdot \cdot + \frac{k(k - 1) \cdot \cdot \cdot (k - n + 1)x^n}{n!} + \cdot \cdot \cdot .$$

By the Ratio Test, you can conclude that the radius of convergence is $R = 1$. So, the series converges to some function in the interval $(-1, 1)$. ■

Note that Example 4 shows that the Taylor series for $(1 + x)^k$ converges to some function in the interval $(-1, 1)$. However, the example does not show that the series actually converges to $(1 + x)^k$. To do this, you could show that the remainder $R_n(x)$ converges to 0, as illustrated in Example 2. You now have enough information to find a binomial series for a function, as shown in the next example.

EXAMPLE 5 Finding a Binomial Series

Find the power series for $f(x) = \sqrt[3]{1 + x}$.

Solution Using the binomial series

$$(1 + x)^k = 1 + kx + \frac{k(k - 1)x^2}{2!} + \frac{k(k - 1)(k - 2)x^3}{3!} + \cdot \cdot \cdot$$

let $k = \frac{1}{3}$ and write

$$(1 + x)^{1/3} = 1 + \frac{x}{3} - \frac{2x^2}{3^2 2!} + \frac{2 \cdot 5x^3}{3^3 3!} - \frac{2 \cdot 5 \cdot 8x^4}{3^4 4!} + \cdot \cdot \cdot .$$ ■



Figure 9.27

TECHNOLOGY Use a graphing utility to support the result in Example 5. When you graph the functions

$$f(x) = (1 + x)^{1/3}$$

and

$$P_4(x) = 1 + \frac{x}{3} - \frac{x^2}{9} + \frac{5x^3}{81} - \frac{10x^4}{243}$$

in the same viewing window, you should obtain the result shown in Figure 9.27.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Deriving Taylor Series from a Basic List

The list below provides the power series for several elementary functions with the corresponding intervals of convergence.

Power Series for Elementary Functions

Function	Interval of Convergence
$\frac{1}{x} = 1 - (x-1) + (x-1)^2 - (x-1)^3 + (x-1)^4 - \cdots + (-1)^n(x-1)^n + \cdots$	$0 < x < 2$
$\frac{1}{1-x} = 1 + x + x^2 + x^3 + x^4 + x^5 + \cdots + x^n + \cdots$	$-1 < x < 1$
$\frac{1}{1+x} = 1 - x + x^2 - x^3 + x^4 - x^5 + \cdots + (-1)^n x^n + \cdots$	$-1 < x < 1$
$\ln x = (x-1) - \frac{(x-1)^2}{2} + \frac{(x-1)^3}{3} - \frac{(x-1)^4}{4} + \cdots + \frac{(-1)^{n-1}(x-1)^n}{n} + \cdots$	$0 < x \le 2$
$e^x = 1 + x + \frac{x^2}{2!} + \frac{x^3}{3!} + \frac{x^4}{4!} + \frac{x^5}{5!} + \cdots + \frac{x^n}{n!} + \cdots$	$-\infty < x < \infty$
$\sin x = x - \frac{x^3}{3!} + \frac{x^5}{5!} - \frac{x^7}{7!} + \frac{x^9}{9!} - \cdots + \frac{(-1)^n x^{2n+1}}{(2n+1)!} + \cdots$	$-\infty < x < \infty$
$\cos x = 1 - \frac{x^2}{2!} + \frac{x^4}{4!} - \frac{x^6}{6!} + \frac{x^8}{8!} - \cdots + \frac{(-1)^n x^{2n}}{(2n)!} + \cdots$	$-\infty < x < \infty$
$\arctan x = x - \frac{x^3}{3} + \frac{x^5}{5} - \frac{x^7}{7} + \frac{x^9}{9} - \cdots + \frac{(-1)^n x^{2n+1}}{2n+1} + \cdots$	$-1 \le x \le 1$
$\arcsin x = x + \frac{x^3}{2 \cdot 3} + \frac{1 \cdot 3x^5}{2 \cdot 4 \cdot 5} + \frac{1 \cdot 3 \cdot 5x^7}{2 \cdot 4 \cdot 6 \cdot 7} + \cdots + \frac{(2n)!x^{2n+1}}{(2^n n!)^2(2n+1)} + \cdots$	$-1 \le x \le 1$
$(1+x)^k = 1 + kx + \frac{k(k-1)x^2}{2!} + \frac{k(k-1)(k-2)x^3}{3!} + \cdots + \frac{k(k-1)\cdots(k-n+1)x^n}{n!} + \cdots$	$-1 < x < 1^*$

* The convergence at $x = \pm 1$ depends on the value of k.

Note that the binomial series is valid for noninteger values of k. Also, when k is a positive integer, the binomial series reduces to a simple binomial expansion.

EXAMPLE 6 Deriving a Power Series from a Basic List

Find the power series for

$$f(x) = \cos \sqrt{x}.$$

Solution Using the power series

$$\cos x = 1 - \frac{x^2}{2!} + \frac{x^4}{4!} - \frac{x^6}{6!} + \frac{x^8}{8!} - \cdots$$

you can replace x by $\sqrt{x}$ to obtain the series

$$\cos \sqrt{x} = 1 - \frac{x}{2!} + \frac{x^2}{4!} - \frac{x^3}{6!} + \frac{x^4}{8!} - \cdots.$$

This series converges for all x in the domain of $\cos \sqrt{x}$—that is, for $x \ge 0$. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Power series can be multiplied and divided like polynomials. After finding the first few terms of the product (or quotient), you may be able to recognize a pattern.

EXAMPLE 7 Multiplication of Power Series

Find the first three nonzero terms in the Maclaurin series $e^x \arctan x$.

Solution Using the Maclaurin series for e^x and $\arctan x$ in the table, you have

$$e^x \arctan x = \left(1 + x + \frac{x^2}{2!} + \frac{x^3}{3!} + \frac{x^4}{4!} + \cdots\right)\left(x - \frac{x^3}{3} + \frac{x^5}{5} - \cdots\right).$$

Multiply these expressions and collect like terms as you would in multiplying polynomials.

$$\begin{array}{r}
1 + x + \frac{1}{2}x^2 + \frac{1}{6}x^3 + \frac{1}{24}x^4 + \cdots \\
x \qquad - \frac{1}{3}x^3 \qquad + \frac{1}{5}x^5 - \cdots \\
\hline
x + \quad x^2 + \frac{1}{2}x^3 + \quad \frac{1}{6}x^4 + \frac{1}{24}x^5 + \cdots \\
\quad - \frac{1}{3}x^3 - \quad \frac{1}{3}x^4 - \quad \frac{1}{6}x^5 - \cdots \\
\qquad\qquad + \quad \frac{1}{5}x^5 + \cdots \\
\hline
x + \quad x^2 + \frac{1}{6}x^3 - \quad \frac{1}{6}x^4 + \frac{3}{40}x^5 + \cdots
\end{array}$$

So, $e^x \arctan x = x + x^2 + \frac{1}{6}x^3 + \cdots$.

EXAMPLE 8 Division of Power Series

Find the first three nonzero terms in the Maclaurin series $\tan x$.

Solution Using the Maclaurin series for $\sin x$ and $\cos x$ in the table, you have

$$\tan x = \frac{\sin x}{\cos x} = \frac{x - \frac{x^3}{3!} + \frac{x^5}{5!} - \cdots}{1 - \frac{x^2}{2!} + \frac{x^4}{4!} - \cdots}.$$

Divide using long division.

$$\begin{array}{r}
x + \frac{1}{3}x^3 + \quad \frac{2}{15}x^5 + \cdots \\
\hline
1 - \frac{1}{2}x^2 + \frac{1}{24}x^4 - \cdots \;\Big)\; x - \frac{1}{6}x^3 + \frac{1}{120}x^5 - \cdots \\
\qquad\quad x - \frac{1}{2}x^3 + \quad \frac{1}{24}x^5 - \cdots \\
\hline
\qquad\quad \frac{1}{3}x^3 - \quad \frac{1}{30}x^5 + \cdots \\
\qquad\quad \frac{1}{3}x^3 - \quad \frac{1}{6}x^5 + \cdots \\
\hline
\qquad\qquad\quad \frac{2}{15}x^5 + \cdots
\end{array}$$

So, $\tan x = x + \frac{1}{3}x^3 + \frac{2}{15}x^5 + \cdots$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 9 A Power Series for $\sin^2 x$

Find the power series for

$$f(x) = \sin^2 x.$$

Solution Consider rewriting $\sin^2 x$ as

$$\sin^2 x = \frac{1 - \cos 2x}{2} = \frac{1}{2} - \frac{1}{2}\cos 2x.$$

Now, use the series for $\cos x$.

$$\cos x = 1 - \frac{x^2}{2!} + \frac{x^4}{4!} - \frac{x^6}{6!} + \frac{x^8}{8!} - \cdots$$

$$\cos 2x = 1 - \frac{2^2}{2!}x^2 + \frac{2^4}{4!}x^4 - \frac{2^6}{6!}x^6 + \frac{2^8}{8!}x^8 - \cdots$$

$$-\frac{1}{2}\cos 2x = -\frac{1}{2} + \frac{2}{2!}x^2 - \frac{2^3}{4!}x^4 + \frac{2^5}{6!}x^6 - \frac{2^7}{8!}x^8 + \cdots$$

$$\frac{1}{2} - \frac{1}{2}\cos 2x = \frac{1}{2} - \frac{1}{2} + \frac{2}{2!}x^2 - \frac{2^3}{4!}x^4 + \frac{2^5}{6!}x^6 - \frac{2^7}{8!}x^8 + \cdots$$

So, the series for $f(x) = \sin^2 x$ is

$$\sin^2 x = \frac{2}{2!}x^2 - \frac{2^3}{4!}x^4 + \frac{2^5}{6!}x^6 - \frac{2^7}{8!}x^8 + \cdots.$$

This series converges for $-\infty < x < \infty$. ■

As mentioned in Section 9.9, power series can be used to obtain tables of values of transcendental functions. They are also useful for estimating the values of definite integrals for which antiderivatives cannot be found. The next example demonstrates this use.

EXAMPLE 10 Power Series Approximation of a Definite Integral

See LarsonCalculus.com for an interactive version of this type of example.

Use a power series to approximate

$$\int_0^1 e^{-x^2}\,dx$$

with an error of less than 0.01.

Solution Replacing x with $-x^2$ in the series for e^x produces the following.

$$e^{-x^2} = 1 - x^2 + \frac{x^4}{2!} - \frac{x^6}{3!} + \frac{x^8}{4!} - \cdots$$

$$\int_0^1 e^{-x^2}\,dx = \left[x - \frac{x^3}{3} + \frac{x^5}{5 \cdot 2!} - \frac{x^7}{7 \cdot 3!} + \frac{x^9}{9 \cdot 4!} - \cdots\right]_0^1$$

$$= 1 - \frac{1}{3} + \frac{1}{10} - \frac{1}{42} + \frac{1}{216} - \cdots$$

Summing the first four terms, you have

$$\int_0^1 e^{-x^2}\,dx \approx 0.74$$

which, by the Alternating Series Test, has an error of less than $\frac{1}{216} \approx 0.005$. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

9.10 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain how to determine whether a Taylor series for a function f converges to f.
2. The binomial series is used to represent a function of what form? What is the radius of convergence for the binomial series?
3. Explain how to multiply and divide power series.
4. Explain how to use the series

$$g(x) = e^x = \sum_{n=0}^{\infty} \frac{x^n}{n!}$$

to find the series for $f(x) = x^2e^{-3x}$. Do not find the series.

Finding a Taylor Series **In Exercises 5–16, use the definition of Taylor series to find the Taylor series, centered at c, for the function.**

5. $f(x) = e^{2x}, \quad c = 0$
6. $f(x) = e^{-4x}, \quad c = 0$
7. $f(x) = \cos x, \quad c = \frac{\pi}{4}$
8. $f(x) = \sin x, \quad c = \frac{\pi}{4}$
9. $f(x) = \frac{1}{x}, \quad c = 1$
10. $f(x) = \frac{1}{1-x}, \quad c = 2$
11. $f(x) = \ln x, \quad c = 1$
12. $f(x) = e^x, \quad c = 1$
13. $f(x) = \sin 3x, \quad c = 0$
14. $f(x) = \ln(x^2 + 1), \quad c = 0$
15. $f(x) = \sec x, \quad c = 0$ (first three nonzero terms)
16. $f(x) = \tan x, \quad c = 0$ (first three nonzero terms)

Proof **In Exercises 17–20, prove that the Maclaurin series for the function converges to the function for all x.**

17. $f(x) = \cos x$
18. $f(x) = e^{-2x}$
19. $f(x) = \sinh x$
20. $f(x) = \cosh x$

Using a Binomial Series **In Exercises 21–26, use the binomial series to find the Maclaurin series for the function.**

21. $f(x) = \frac{1}{\sqrt{1-x}}$
22. $f(x) = \frac{1}{(1+x)^4}$
23. $f(x) = \frac{1}{\sqrt{1-x^2}}$
24. $f(x) = \frac{1}{(2+x)^3}$
25. $f(x) = \sqrt[4]{1+x}$
26. $f(x) = \sqrt{1+x^3}$

Finding a Maclaurin Series **In Exercises 27–40, find the Maclaurin series for the function. Use the table of power series for elementary functions on page 674.**

27. $f(x) = e^{x^2/2}$
28. $g(x) = e^{-x/3}$
29. $f(x) = \ln(1 + x)$
30. $f(x) = \ln(1 + x^3)$
31. $f(x) = \cos 4x$
32. $f(x) = \sin \pi x$
33. $g(x) = \arctan 5x$
34. $f(x) = \arcsin \pi x$
35. $f(x) = \cos x^{3/2}$
36. $g(x) = 2 \sin x^3$
37. $f(x) = \frac{1}{2}(e^x - e^{-x}) = \sinh x$
38. $f(x) = e^x + e^{-x} = 2 \cosh x$
39. $f(x) = \cos^2 x$
40. $f(x) = \sinh^{-1} x = \ln\left(x + \sqrt{x^2 + 1}\right)$

$\left(\textit{Hint:}\ \text{Integrate the series for } \frac{1}{\sqrt{x^2+1}}.\right)$

Verifying a Formula **In Exercises 41 and 42, use a power series and the fact that $i^2 = -1$ to verify the formula.**

41. $g(x) = \frac{1}{2i}(e^{ix} - e^{-ix}) = \sin x$
42. $g(x) = \frac{1}{2}(e^{ix} + e^{-ix}) = \cos x$

Finding a Maclaurin Series **In Exercises 43–46, find the Maclaurin series for the function.**

43. $f(x) = x \sin x$
44. $h(x) = x \cos x$
45. $g(x) = \begin{cases} \frac{\sin x}{x}, & x \neq 0 \\ 1, & x = 0 \end{cases}$
46. $f(x) = \begin{cases} \frac{\arcsin x}{x}, & x \neq 0 \\ 1, & x = 0 \end{cases}$

Finding Terms of a Maclaurin Series **In Exercises 47–52, find the first four nonzero terms of the Maclaurin series for the function by multiplying or dividing the appropriate power series. Use the table of power series for elementary functions on page 674.**

47. $f(x) = e^x \sin x$
48. $g(x) = e^x \cos x$
49. $h(x) = (\cos x) \ln(1 + x)$
50. $f(x) = e^x \ln(1 + x)$
51. $g(x) = \frac{\sin x}{1 + x}$
52. $f(x) = \frac{e^x}{1 + x}$

Finding a Maclaurin Series **In Exercises 53 and 54, find a Maclaurin series for $f(x)$.**

53. $f(x) = \int_0^x (e^{-t^2} - 1)\, dt$
54. $f(x) = \int_0^x \sqrt{1 + t^3}\, dt$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Verifying a Sum **In Exercises 55–58, verify the sum. Then use a graphing utility to approximate the sum with an error of less than 0.0001.**

55. $\sum_{n=1}^{\infty} (-1)^{n+1} \frac{1}{n} = \ln 2$

56. $\sum_{n=0}^{\infty} (-1)^n \left[\frac{1}{(2n+1)!}\right] = \sin 1$

57. $\sum_{n=0}^{\infty} \frac{2^n}{n!} = e^2$

58. $\sum_{n=1}^{\infty} (-1)^{n-1} \left(\frac{1}{n!}\right) = \frac{e-1}{e}$

Finding a Limit **In Exercises 59–62, use the series representation of the function f to find $\lim_{x\to 0} f(x)$, if it exists.**

59. $f(x) = \frac{1-\cos x}{x}$

60. $f(x) = \frac{\sin x}{x}$

61. $f(x) = \frac{e^x - 1}{x}$

62. $f(x) = \frac{\ln(x+1)}{x}$

Approximating an Integral **In Exercises 63–70, use a power series to approximate the value of the definite integral with an error of less than 0.0001. (In Exercises 65 and 67, assume that the integrand is defined as 1 when $x = 0$.)**

63. $\int_0^1 e^{-x^3}\,dx$

64. $\int_0^{1/4} x \ln(x+1)\,dx$

65. $\int_0^1 \frac{\sin x}{x}\,dx$

66. $\int_0^1 \cos x^2\,dx$

67. $\int_0^{1/2} \frac{\arctan x}{x}\,dx$

68. $\int_0^{1/2} \arctan x^2\,dx$

69. $\int_{0.1}^{0.3} \sqrt{1+x^3}\,dx$

70. $\int_0^{0.2} \sqrt{1+x^2}\,dx$

Area **In Exercises 71 and 72, use a power series to approximate the area of the region with an error of less than 0.0001. Use a graphing utility to verify the result.**

71. $\int_0^{\pi/2} \sqrt{x}\cos x\,dx$



72. $\int_{0.5}^{1} \cos\sqrt{x}\,dx$



Probability **In Exercises 73 and 74, approximate the probability with an error of less than 0.0001, where the probability is given by**

$$P(a < x < b) = \frac{1}{\sqrt{2\pi}} \int_a^b e^{-x^2/2}\,dx.$$



73. $P(0 < x < 1)$

74. $P(1 < x < 2)$

Exploring Concepts

75. Describe three ways to find the Maclaurin series for $\cos^2 x$. Show that each method produces the same first three terms.

76. Explain how to use the power series for $f(x) = \arctan x$ to find the Maclaurin series for

$$g(x) = \frac{1}{1+x^2}.$$

What is another way to find the Maclaurin series for g using a power series for an elementary function?

77. Which function has the Maclaurin series

$$\sum_{n=0}^{\infty} \frac{(-1)^n (x+3)^{2n+1}}{2^2\,(2n+1)!}\,?$$

Explain your reasoning.

78. **HOW DO YOU SEE IT?** Identify the function represented by each power series and match the function with its graph. [The graphs are labeled (i) and (ii).]

(i)



(ii)



(a) $\sum_{n=0}^{\infty} \frac{(-1)^n x^{4n+2}}{(2n+1)!}$

(b) $\sum_{n=0}^{\infty} \frac{(-1)^n x^n}{n!}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

79. Projectile Motion A projectile fired from the ground follows the trajectory given by

$$y = \left(\tan\theta + \frac{g}{kv_0\cos\theta}\right)x + \frac{g}{k^2}\ln\left(1 - \frac{kx}{v_0\cos\theta}\right)$$

where v_0 is the initial speed, θ is the angle of projection, g is the acceleration due to gravity, and k is the drag factor caused by air resistance. Using the power series representation

$$\ln(1+x) = x - \frac{x^2}{2} + \frac{x^3}{3} - \frac{x^4}{4} + \cdots, \quad -1 < x < 1$$

verify that the trajectory can be rewritten as

$$y = (\tan\theta)x - \frac{gx^2}{2v_0^2\cos^2\theta} - \frac{kgx^3}{3v_0^3\cos^3\theta} - \frac{k^2gx^4}{4v_0^4\cos^4\theta} - \cdots.$$

80. Projectile Motion

Use the result of Exercise 79 to determine the series for the path of a projectile launched from ground level at an angle of $\theta = 60°$, with an initial speed of $v_0 = 64$ feet per second and a drag factor of $k = \frac{1}{16}$.

81. Investigation Consider the function f defined by

$$f(x) = \begin{cases} e^{-1/x^2}, & x \neq 0 \\ 0, & x = 0. \end{cases}$$

(a) Sketch a graph of the function.

(b) Use the alternative form of the definition of the derivative (Section 2.1) and L'Hôpital's Rule to show that $f'(0) = 0$. [By continuing this process, it can be shown that $f^{(n)}(0) = 0$ for $n > 1$.]

(c) Using the result in part (b), find the Maclaurin series for f. Does the series converge to f?

82. Investigation

(a) Find the power series centered at 0 for the function

$$f(x) = \frac{\ln(x^2+1)}{x^2}.$$

(b) Use a graphing utility to graph f and the eighth-degree Taylor polynomial $P_8(x)$ for f.

(c) Use a graphing utility to complete the table, where

$$F(x) = \int_0^x \frac{\ln(t^2+1)}{t^2}\,dt \quad \text{and} \quad G(x) = \int_0^x P_8(t)\,dt.$$

x	0.25	0.50	0.75	1.00	1.50	2.00
$F(x)$						
$G(x)$						

(d) Describe the relationship between the graphs of f and P_8 and the results given in the table in part (c).

83. Proof Prove that

$$\lim_{n\to\infty}\frac{x^n}{n!} = 0$$

for any real x.

84. Finding a Maclaurin Series Find the Maclaurin series for

$$f(x) = \ln\frac{1+x}{1-x}$$

and determine its radius of convergence. Use the first four terms of the series to approximate ln 3.

85. Writing a Power Series Write the power series for $(1+x)^k$ in terms of binomial coefficients.

86. Proof Prove that the Taylor series for e^x, centered at $x = a$, is given by

$$e^a\left[1 + (x-a) + \frac{(x-a)^2}{2!} + \cdots\right].$$

87. Proof Prove that e is irrational. [*Hint:* Assume that $e = p/q$ is rational (p and q are integers) and consider

$$e = 1 + 1 + \frac{1}{2!} + \cdots + \frac{1}{n!} + \cdots.\Big]$$

88. Using Fibonacci Numbers Show that the Maclaurin series for the function

$$g(x) = \frac{x}{1-x-x^2}$$

is

$$\sum_{n=1}^{\infty} F_n x^n$$

where F_n is the nth Fibonacci number with $F_1 = F_2 = 1$ and $F_n = F_{n-2} + F_{n-1}$, for $n \geq 3$. (*Hint:* Write

$$\frac{x}{1-x-x^2} = a_0 + a_1x + a_2x^2 + \cdots$$

and multiply each side of this equation by $1 - x - x^2$.)

89. Limits Consider the function

$$f(x) = \frac{\sin x - x}{x^3}.$$

(a) Calculate $\lim_{x\to 0} f(x)$ using L'Hôpital's Rule.

(b) Calculate $\lim_{x\to 0} f(x)$ using an appropriate infinite series.

PUTNAM EXAM CHALLENGE

90. Assume that $|f(x)| \leq 1$ and $|f''(x)| \leq 1$ for all x on an interval of length at least 2. Show that $|f'(x)| \leq 2$ on the interval.

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Ujjal Boro/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Review Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Exploring Concepts

The theory of sequences and series is one of the most beautiful and useful areas of calculus. After studying sequences and limits of sequences, you learned that an infinite series (or simply a series) is an "infinite summation."

$$\sum_{n=1}^{\infty} a_n = a_1 + a_2 + a_3 + \cdots + a_n + \cdots$$

You studied several types of series, including geometric, telescoping, p-series, and alternating series. The convergence or divergence of a series is determined by the behavior of its sequence of partial sums. To determine this behavior, you can use a convergence test, such as the Integral Test, the comparison tests, the Ratio Test, and the Root Test. While the first six sections covered sequences and series of *constant* terms, the last four sections considered series with *variable* terms. This led to the development of Taylor polynomials, Taylor series, and power series. Many elementary functions, such as $\ln x$, e^x, $\sin x$, and $\arctan x$, can be represented by power series.

1. Is it possible for a sequence to converge to two different numbers? If so, give an example. If not, explain why not.

2. In your own words, explain the difference between a sequence and a series.

3. Determine whether each statement is true or false. If it is false, explain why or give an example that shows it is false.

(a) If $\lim_{n\to\infty} a_n = 0$, then $\sum_{n=1}^{\infty} a_n$ converges.

(b) If $\sum_{n=1}^{\infty} |a_n|$ diverges, then $\sum_{n=1}^{\infty} a_n$ diverges.

(c) $\sum_{n=0}^{\infty} r^n = \dfrac{1}{1-r}$

(d) If $0 < a_n \le b_n$ and $\sum_{n=1}^{\infty} b_n$ diverges, then $\sum_{n=1}^{\infty} a_n$ diverges.

(e) If the power series

$$\sum_{n=1}^{\infty} a_n x^n$$

converges for $x = 2$, then it also converges for $x = -2$.

4. Explain why the statement is incorrect.

$$\sum_{n=0}^{\infty} x^n + \sum_{n=0}^{\infty} \left(\frac{x}{5}\right)^n = \sum_{n=0}^{\infty} \left(1 + \frac{1}{5}\right) x^n$$ ✗

5. The graph of $y = \cos x$ is shown with four of its Maclaurin polynomials. Identify the Maclaurin polynomials and use a graphing utility to confirm your results.



6. Let $f(x) = \sum_{n=0}^{\infty} \dfrac{x^n}{n!}$.

(a) Find the interval of convergence of f.

(b) Show that $f'(x) = f(x)$ and $f(0) = 1$.

(c) Identify the function f.

Writing the Terms of a Sequence **In Exercises 7–10, write the first five terms of the sequence with the given nth term.**

7. $a_n = 6^n - 2$

8. $a_n = \dfrac{5^{n-1}}{n!}$

9. $a_n = \left(-\dfrac{1}{4}\right)^n$

10. $a_n = \dfrac{2n}{n+5}$

Finding the Limit of a Sequence **In Exercises 11 and 12, use a graphing utility to graph the first 10 terms of the sequence with the given nth term. Use the graph to make an inference about the convergence or divergence of the sequence. Verify your inference analytically and, if the sequence converges, find its limit.**

11. $a_n = \dfrac{5n+2}{n}$

12. $a_n = \cos\dfrac{n\pi}{3}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Determining Convergence or Divergence **In Exercises 13–20, determine the convergence or divergence of the sequence with the given *n*th term. If the sequence converges, find its limit.**

13. $a_n = \dfrac{1}{\sqrt{n}}$

14. $a_n = \dfrac{n}{n^2 + 1}$

15. $a_n = \left(\dfrac{2}{5}\right)^n + 5$

16. $a_n = \dfrac{2n^3 - 1}{3n + 4}$

17. $a_n = \dfrac{(4n)!}{(4n - 1)!}$

18. $a_n = \dfrac{n}{\ln n}$

19. $a_n = \dfrac{e^{2n}}{\ln n}$

20. $a_n = \dfrac{\sin\sqrt{n}}{\sqrt{n}}$

Finding the *n*th Term of a Sequence **In Exercises 21–24, find the *n*th term, a_n, of the sequence and then determine whether the sequence you have chosen converges or diverges. (There is more than one correct answer.)**

21. 3, 8, 13, 18, 23, . . .

22. $-5, -2, 3, 10, 19, \ldots$

23. $\dfrac{1}{2}, \dfrac{1}{3}, \dfrac{1}{7}, \dfrac{1}{25}, \dfrac{1}{121}, \ldots$

24. $\dfrac{1}{2}, \dfrac{2}{5}, \dfrac{3}{10}, \dfrac{4}{17}, \ldots$

Monotonic and Bounded Sequences **In Exercises 25 and 26, determine whether the sequence with the given *n*th term is monotonic and whether it is bounded. Use a graphing utility to confirm your results.**

25. $a_n = 3 - \dfrac{1}{2n}$

26. $a_n = \left(\dfrac{4}{3}\right)^n$

27. Compound Interest A deposit of \$8000 is made in an account that earns 5% interest compounded quarterly. The balance in the account after n quarters is

$$A_n = 8000(1.0125)^n, \quad n = 1, 2, 3, \ldots$$

(a) Compute the first eight terms of the sequence $\{A_n\}$.

(b) Find the balance in the account after 10 years by computing the 40th term of the sequence.

28. Depreciation A company buys a machine for \$175,000. During the next 5 years, the machine will depreciate at a rate of 30% per year. (That is, at the end of each year, the depreciated value will be 70% of what it was at the beginning of the year.)

(a) Write an expression for the value of the machine after n years.

(b) Compute the depreciated values of the machine for the first 5 years.

Finding Partial Sums **In Exercises 29 and 30, find the sequence of partial sums $S_1, S_2, S_3, S_4,$ and S_5.**

29. $3 + \dfrac{3}{2} + 1 + \dfrac{3}{4} + \dfrac{3}{5} + \cdots$

30. $-7 + 1 - \dfrac{1}{7} + \dfrac{1}{49} - \dfrac{1}{343} + \cdots$

Numerical, Graphical, and Analytic Analysis **In Exercises 31 and 32, (a) use a graphing utility to find the indicated partial sum S_n and complete the table, and (b) use a graphing utility to graph the first 10 terms of the sequence of partial sums.**

n	5	10	15	20	25
S_n					

31. $\displaystyle\sum_{n=1}^{\infty} \left(\frac{3}{2}\right)^{n-1}$

32. $\displaystyle\sum_{n=1}^{\infty} \frac{1}{n(n + 1)}$

Finding the Sum of a Convergent Series **In Exercises 33–36, find the sum of the convergent series.**

33. $\displaystyle\sum_{n=0}^{\infty} \left(\frac{2}{5}\right)^n$

34. $\displaystyle\sum_{n=0}^{\infty} \frac{3^{n+2}}{7^n}$

35. $\displaystyle\sum_{n=0}^{\infty} [(0.4)^n + (0.9)^n]$

36. $\displaystyle\sum_{n=0}^{\infty} \left[\left(\frac{3}{4}\right)^n - \frac{1}{(n + 1)(n + 2)}\right]$

Using a Geometric Series **In Exercises 37 and 38, (a) write the repeating decimal as a geometric series and (b) write the sum of the series as the ratio of two integers.**

37. $0.\overline{09}$

38. $0.\overline{64}$

Using a Geometric Series or the *n*th-Term Test **In Exercises 39–42, use a geometric series or the *n*th-Term Test to determine the convergence or divergence of the series.**

39. $\displaystyle\sum_{n=0}^{\infty} (1.67)^n$

40. $\displaystyle\sum_{n=0}^{\infty} 9^{-n}$

41. $\displaystyle\sum_{n=0}^{\infty} \frac{2n + 1}{3n + 2}$

42. $\displaystyle\sum_{n=1}^{\infty} \frac{5n! + 6}{n! + 1}$

43. Marketing A manufacturer producing a new product estimates the annual sales to be 9600 units. Each year, 8% of the units that have been sold will become inoperative. So, 9600 units will be in use after 1 year, $[9600 + 0.92(9600)]$ units will be in use after 2 years, and so on. How many units will be in use after n years?

44. Distance A ball is dropped from a height of 8 meters. Each time it drops h meters, it rebounds $0.7h$ meters. Find the total distance traveled by the ball.

Using the Integral Test or a *p*-Series **In Exercises 45–50, use the Integral Test or a *p*-series to determine the convergence or divergence of the series.**

45. $\displaystyle\sum_{n=1}^{\infty} \frac{2}{6n + 1}$

46. $\displaystyle\sum_{n=1}^{\infty} \frac{1}{\sqrt[4]{n^3}}$

47. $\displaystyle\sum_{n=1}^{\infty} \frac{1}{n^{5/2}}$

48. $\displaystyle\sum_{n=1}^{\infty} \frac{1}{5^n}$

49. $\displaystyle\sum_{n=1}^{\infty} \left(\frac{1}{n^2} - \frac{1}{n}\right)$

50. $\displaystyle\sum_{n=1}^{\infty} \frac{\ln n}{n^4}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Using the Direct Comparison Test or the Limit Comparison Test In Exercises 51–56, use the Direct Comparison Test or the Limit Comparison Test to determine the convergence or divergence of the series.

51. $\sum_{n=2}^{\infty} \frac{1}{\sqrt[3]{n} - 1}$

52. $\sum_{n=0}^{\infty} \frac{7^n}{8^n + 5}$

53. $\sum_{n=1}^{\infty} \frac{1}{\sqrt{n^3 + 2n}}$

54. $\sum_{n=1}^{\infty} \frac{n + 1}{n(n + 2)}$

55. $\sum_{n=1}^{\infty} \frac{1 \cdot 3 \cdot 5 \cdot \cdots \cdot (2n - 1)}{2 \cdot 4 \cdot 6 \cdot \cdots \cdot (2n)}$

56. $\sum_{n=1}^{\infty} \frac{1}{3^n - 5}$

Using the Alternating Series Test In Exercises 57–62, use the Alternating Series Test, if applicable, to determine the convergence or divergence of the series.

57. $\sum_{n=1}^{\infty} \frac{(-1)^n}{n^5}$

58. $\sum_{n=1}^{\infty} \frac{(-1)^n(n + 1)}{n^2 + 1}$

59. $\sum_{n=2}^{\infty} \frac{(-1)^n n}{n^2 - 3}$

60. $\sum_{n=4}^{\infty} \frac{(-1)^n n}{n - 3}$

61. $\sum_{n=1}^{\infty} \frac{(-1)^{n+1}\sqrt{n}}{\sqrt[4]{n} + 2}$

62. $\sum_{n=2}^{\infty} \frac{(-1)^n \ln n^3}{n}$

Finding the Number of Terms In Exercises 63 and 64, use Theorem 9.15 to determine the number of terms required to approximate the sum of the series with an error of less than 0.0001.

63. $\sum_{n=1}^{\infty} \frac{(-1)^n}{n^4}$

64. $\sum_{n=1}^{\infty} \frac{(-1)^{n+1}}{3n^3 - 2}$

Using the Ratio Test or the Root Test In Exercises 65–70, use the Ratio Test or the Root Test to determine the convergence or divergence of the series.

65. $\sum_{n=1}^{\infty} \left(\frac{3n - 1}{2n + 5}\right)^n$

66. $\sum_{n=1}^{\infty} \left(\frac{4n}{7n - 1}\right)^n$

67. $\sum_{n=1}^{\infty} \frac{2^n}{n^3}$

68. $\sum_{n=0}^{\infty} \frac{7^n}{(2n + 3)^n}$

69. $\sum_{n=1}^{\infty} \frac{n}{e^{n^2}}$

70. $\sum_{n=1}^{\infty} \frac{n!}{e^{2n}}$

Finding a Maclaurin Polynomial In Exercises 71 and 72, find the nth Maclaurin polynomial for the function.

71. $f(x) = e^{-2x}, \quad n = 3$

72. $f(x) = \cos 3x, \quad n = 4$

Finding a Taylor Polynomial In Exercises 73 and 74, find the third Taylor polynomial for the function, centered at c.

73. $f(x) = \frac{1}{x^3}, \quad c = 1$

74. $f(x) = \tan x, \quad c = -\frac{\pi}{4}$

Finding a Degree In Exercises 75 and 76, determine the degree of the Maclaurin polynomial required for the error in the approximation of the function at the indicated value of x to be less than 0.001.

75. $f(x) = \cos x$, approximate $f(0.75)$

76. $f(x) = e^x$, approximate $f(-0.25)$

Numerical, Graphical, and Analytic Analysis In Exercises 77 and 78, (a) verify that the series converges, (b) use a graphing utility to find the indicated partial sum S_n and complete the table, (c) use a graphing utility to graph the first 10 terms of the sequence of partial sums, and (d) use the table to estimate the sum of the series.

n	5	10	15	20	25
S_n					

77. $\sum_{n=1}^{\infty} n\left(\frac{3}{5}\right)^n$

78. $\sum_{n=1}^{\infty} \frac{(-1)^{n-1}n}{n^3 + 5}$

Determining Convergence or Divergence In Exercises 79–84, determine the convergence or divergence of the series using any appropriate test from this chapter. Identify the test used.

79. $\sum_{n=1}^{\infty} \frac{4}{n^{2\pi}}$

80. $\sum_{n=0}^{\infty} \frac{7^{n+1}}{8^n}$

81. $\sum_{n=1}^{\infty} \frac{5n^3 + 6}{7n^3 + 2n}$

82. $\sum_{n=1}^{\infty} e^{-n/3}$

83. $\sum_{n=1}^{\infty} \frac{10^n}{4 + 9^n}$

84. $\sum_{n=1}^{\infty} \frac{(n!)^n}{3^n}$

Finding the Interval of Convergence In Exercises 85–90, find the interval of convergence of the power series. (Be sure to include a check for convergence at the endpoints of the interval.)

85. $\sum_{n=0}^{\infty} \left(\frac{x}{10}\right)^n$

86. $\sum_{n=0}^{\infty} (5x)^n$

87. $\sum_{n=0}^{\infty} \frac{(-1)^n(x - 2)^n}{(n + 1)^2}$

88. $\sum_{n=1}^{\infty} \frac{4^n(x - 1)^n}{n}$

89. $\sum_{n=0}^{\infty} n!(x - 2)^n$

90. $\sum_{n=0}^{\infty} \frac{(x - 3)^n}{3^n}$

Finding Intervals of Convergence In Exercises 91 and 92, find the intervals of convergence of (a) $f(x)$, (b) $f'(x)$, (c) $f''(x)$, and (d) $\int f(x)\,dx$. (Be sure to include a check for convergence at the endpoints of the intervals.)

91. $f(x) = \sum_{n=0}^{\infty} \left(\frac{x}{5}\right)^n$

92. $f(x) = \sum_{n=1}^{\infty} \frac{(-1)^{n+1}(x - 4)^n}{n}$

Differential Equation In Exercises 93 and 94, show that the function represented by the power series is a solution of the differential equation.

93. $y = \sum_{n=0}^{\infty} (-1)^n \frac{x^{2n}}{4^n(n!)^2}, \quad x^2y'' + xy' + x^2y = 0$

94. $y = \sum_{n=0}^{\infty} \frac{(-3)^n x^{2n}}{2^n n!}, \quad y'' + 3xy' + 3y = 0$

Finding a Geometric Power Series In Exercises 95 and 96, find a geometric power series for the function, centered at 0.

95. $g(x) = \frac{2}{3 - x}$

96. $h(x) = \frac{3}{2 + x}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding a Power Series **In Exercises 97 and 98, find a power series for the function, centered at c, and determine the interval of convergence.**

97. $f(x) = \dfrac{6}{4 - x}, \quad c = 1$

98. $f(x) = \dfrac{6x}{x^2 + 4x - 5}, \quad c = 0$

Finding the Sum of a Series **In Exercises 99–104, find the sum of the convergent series by using a well-known function. Identify the function and explain how you obtained the sum.**

99. $\displaystyle\sum_{n=1}^{\infty} (-1)^{n+1} \frac{1}{4^n n}$

100. $\displaystyle\sum_{n=1}^{\infty} (-1)^{n+1} \frac{1}{5^n n}$

101. $\displaystyle\sum_{n=0}^{\infty} \frac{1}{2^n\, n!}$

102. $\displaystyle\sum_{n=0}^{\infty} \frac{2^n}{3^n\, n!}$

103. $\displaystyle\sum_{n=0}^{\infty} (-1)^n \frac{2^{2n}}{3^{2n}\,(2n)!}$

104. $\displaystyle\sum_{n=0}^{\infty} (-1)^n \frac{1}{3^{2n+1}(2n+1)!}$

Finding a Taylor Series **In Exercises 105–112, use the definition of Taylor series to find the Taylor series, centered at c, for the function.**

105. $f(x) = \sin x, \quad c = \dfrac{3\pi}{4}$

106. $f(x) = \cos x, \quad c = -\dfrac{\pi}{4}$

107. $f(x) = 3^x, \quad c = 0$

108. $f(x) = \csc x, \quad c = \dfrac{\pi}{2}$ (first three nonzero terms)

109. $f(x) = \dfrac{1}{x}, \quad c = -1$

110. $f(x) = \sqrt{x}, \quad c = 4$

111. $g(x) = \sqrt[5]{1 + x}, \quad c = 0$

112. $h(x) = \dfrac{1}{(1 + x)^3}, \quad c = 0$

113. Forming Maclaurin Series Determine the first four terms of the Maclaurin series for e^{2x}

(a) by using the definition of Maclaurin series.

(b) by replacing x by $2x$ in the series for e^x.

(c) by multiplying the series for e^x by itself, because $e^{2x} = e^x \cdot e^x$.

114. Forming Maclaurin Series Determine the first four terms of the Maclaurin series for $\sin 2x$

(a) by using the definition of Maclaurin series.

(b) by replacing x by $2x$ in the series for $\sin 2x$.

(c) by multiplying 2 by the series for $\sin x$ by the series for $\cos x$, because $\sin 2x = 2 \sin x \cos x$.

Finding a Maclaurin Series **In Exercises 115–118, find the Maclaurin series for the function. Use the table of power series for elementary functions on page 674.**

115. $f(x) = e^{6x}$

116. $f(x) = \ln(x - 1)$

117. $f(x) = \sin 5x$

118. $f(x) = \cos 3x$

Approximating an Integral **In Exercises 119 and 120, use a power series to approximate the value of the definite integral with an error of less than 0.01.**

119. $\displaystyle\int_0^{0.5} \cos x^3\, dx$

120. $\displaystyle\int_0^1 e^{-x^4}\, dx$

Building on Concepts

121. It can be shown that

$$\sum_{n=1}^{\infty} \frac{1}{n^2} = \frac{\pi^2}{6}.$$

(See Section 9.3, page 612.) Use this fact to show that

$$\sum_{n=1}^{\infty} \frac{1}{(2n - 1)^2} = \frac{\pi^2}{8}.$$

122. (a) Find a power series for the function $f(x) = xe^x$ centered at 0. Use this representation to find the sum of the infinite series

$$\sum_{n=1}^{\infty} \frac{1}{n!(n + 2)}.$$

(b) Differentiate the power series for $f(x) = xe^x$. Use the result to find the sum of the infinite series

$$\sum_{n=0}^{\infty} \frac{n + 1}{n!}.$$

123. The **Cantor set** (Georg Cantor, 1845–1918) is a subset of the unit interval $[0, 1]$. To construct the Cantor set, first remove the middle third of the interval, $\left(\frac{1}{3}, \frac{2}{3}\right)$, leaving two line segments. For the second step, remove the middle third of each of the two remaining segments, leaving four line segments. Continue this procedure indefinitely, as shown in the figure. The Cantor set consists of all numbers in the unit interval $[0, 1]$ that still remain.



(a) Find the total length of the removed line segments.

(b) Identify three numbers that are in the Cantor set.

(c) Let C_n denote the total length of the remaining line segments after n steps. Find $\lim_{n\to\infty} C_n$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.S. Problem Solving

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

1. Finding a Limit Let T be an equilateral triangle with sides of length 1. Let a_n be the number of circles that can be packed tightly in n rows inside the triangle. For example, $a_1 = 1$, $a_2 = 3$, and $a_3 = 6$, as shown in the figure. Let A_n be the combined area of the a_n circles. Find $\lim_{n\to\infty} A_n$.



2. Deriving Identities Derive each identity using the appropriate geometric series.

(a) $\dfrac{1}{0.99} = 1.01010101\ldots$

(b) $\dfrac{1}{0.98} = 1.0204081632\ldots$

3. Proof

(a) Consider the following sequence of numbers defined recursively.

$$a_1 = 3$$
$$a_2 = \sqrt{3}$$
$$a_3 = \sqrt{3 + \sqrt{3}}$$
$$\vdots$$
$$a_{n+1} = \sqrt{3 + a_n}$$

Write the decimal approximations for the first six terms of this sequence. Prove that the sequence converges and find its limit.

(b) Consider the following sequence defined recursively by $a_1 = \sqrt{a}$ and $a_{n+1} = \sqrt{a + a_n}$, where $a > 2$.

$$\sqrt{a},\quad \sqrt{a + \sqrt{a}},\quad \sqrt{a + \sqrt{a + \sqrt{a}}},\ldots$$

Prove that this sequence converges and find its limit.

4. Using the Alternating Series Test The graph of the function

$$f(x) = \begin{cases} 1, & x = 0 \\ \dfrac{\sin x}{x}, & x > 0 \end{cases}$$

is shown below. Use the Alternating Series Test to show that the improper integral $\int_1^\infty f(x)\,dx$ converges.



5. Using Sequences

(a) Given that $\lim_{n\to\infty} a_{2n} = L$ and $\lim_{n\to\infty} a_{2n+1} = L$, show that $\{a_n\}$ is convergent and $\lim_{n\to\infty} a_n = L$.

(b) Let $a_1 = 1$ and $a_{n+1} = 1 + \dfrac{1}{1 + a_n}$. Write out the first eight terms of $\{a_n\}$. Use part (a) to show that $\lim_{n\to\infty} a_n = \sqrt{2}$. This gives the **continued fraction expansion**

$$\sqrt{2} = 1 + \cfrac{1}{2 + \cfrac{1}{2 + \cdots}}.$$

6. Using Center of Gravity Identical blocks of unit length are stacked on top of each other at the edge of a table. The center of gravity of the top block must lie over the block below it, the center of gravity of the top two blocks must lie over the block below them, and so on (see figure).



(a) When there are three blocks, show that it is possible to stack them so that the left edge of the top block extends $\frac{11}{12}$ unit beyond the edge of the table.

(b) Is it possible to stack the blocks so that the right edge of the top block extends beyond the edge of the table?

(c) How far beyond the table can the blocks be stacked?

7. Using Power Series

(a) Consider the power series

$$\sum_{n=0}^{\infty} a_n x^n = 1 + 2x + 3x^2 + x^3 + 2x^4 + 3x^5 + x^6 + \cdots$$

in which the coefficients $a_n = 1, 2, 3, 1, 2, 3, 1, \ldots$ are periodic of period $p = 3$. Find the radius of convergence and the sum of this power series.

(b) Consider a power series

$$\sum_{n=0}^{\infty} a_n x^n$$

in which the coefficients are periodic, $(a_{n+p} = a_p)$, and $a_n > 0$. Find the radius of convergence and the sum of this power series.

8. Conditional and Absolute Convergence For what values of the positive constants a and b does the following series converge absolutely? For what values does it converge conditionally?

$$a - \frac{b}{2} + \frac{a}{3} - \frac{b}{4} + \frac{a}{5} - \frac{b}{6} + \frac{a}{7} - \frac{b}{8} + \cdots$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

10 Conics, Parametric Equations, and Polar Coordinates

GO DIGITAL

10.1 Conics and Calculus
10.2 Plane Curves and Parametric Equations
10.3 Parametric Equations and Calculus
10.4 Polar Coordinates and Polar Graphs
10.5 Area and Arc Length in Polar Coordinates
10.6 Polar Equations of Conics and Kepler's Laws

CalcView®



CalcChat®


Chapter 10
Section 4
Exercise 73
GO
$r = 5\sin\theta$
$r^2 = 5r\sin\theta$
$x^2 + y^2 = 5y$
$x^2 + \left(y^2 - 5y + \frac{25}{4}\right) = \frac{25}{4}$
$x^2 + \left(y - \frac{5}{2}\right)^2 = \frac{25}{4}$
Circle: center: $\left(0, \frac{5}{2}\right)$, radius: $\frac{5}{2}$
Tangent at pole: $\theta = 0$
Note: $f(\theta) = r = 5\sin\theta$
$f(0) = 0, f'(0) \neq 0$
PREV. 63 65 67 69 71 73 75 77 79 81 83 NEXT

10.5 Antenna Radiation *(Exercise 49, p. 736)*

10.6 Planetary Motion *(Exercise 65, p. 745)*

left, This Lama/Shutterstock.com; right, NASA images/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

10.1 Conics and Calculus

GO DIGITAL

- **Describe a conic section.**
- **Analyze and write equations of parabolas using properties of parabolas.**
- **Analyze and write equations of ellipses using properties of ellipses.**
- **Analyze and write equations of hyperbolas using properties of hyperbolas.**

HYPATIA (370–415 A.D.)

The Greeks discovered conic sections sometime between 600 and 300 B.C. By the beginning of the Alexandrian period, enough was known about conics for Apollonius (262–190 B.C.) to produce an eight-volume work on the subject. Later, toward the end of the Alexandrian period, Hypatia wrote a textbook entitled *On the Conics of Apollonius*. Her death marked the end of major mathematical discoveries in Europe for several hundred years. The early Greeks were largely concerned with the geometric properties of conics. It was not until 1900 years later, in the early seventeenth century, that the broader applicability of conics became apparent. Conics then played a prominent role in the development of calculus.

See LarsonCalculus.com to read more of this biography.

Conic Sections

Each **conic section** (or simply **conic**) can be described as the intersection of a plane and a double-napped cone. Notice in Figure 10.1 that for the four basic conics, the intersecting plane does not pass through the vertex of the cone. When the plane passes through the vertex, the resulting figure is a **degenerate conic,** as shown in Figure 10.2.



Circle | Parabola | Ellipse | Hyperbola

Conic sections

Figure 10.1

Point | Line | Two intersecting lines

Degenerate conics

Figure 10.2

There are several ways to study conics. You could begin as the Greeks did, by defining the conics in terms of the intersections of planes and cones, or you could define them algebraically in terms of the general second-degree equation

$$Ax^2 + Bxy + Cy^2 + Dx + Ey + F = 0.$$ General second-degree equation

However, a third approach, in which each of the conics is defined as a **locus** (collection) of points satisfying a certain geometric property, works best. For example, a circle can be defined as the collection of all points (x, y) that are equidistant from a fixed point (h, k). This locus definition easily produces the standard equation of a circle

$$(x - h)^2 + (y - k)^2 = r^2.$$ Standard equation of a circle

For information about rotating second-degree equations in two variables, see Appendix D.

FOR FURTHER INFORMATION

To learn more about the mathematical activities of Hypatia, see the article "Hypatia and Her Mathematics" by Michael A. B. Deakin in *The American Mathematical Monthly*. To view this article, go to *MathArticles.com*.

Bettmann/Contributor/Getty Images

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Parabolas



Figure 10.3

A **parabola** is the set of all points (x, y) that are equidistant from a fixed line, the **directrix,** and a fixed point, the **focus,** not on the line. The midpoint between the focus and the directrix is the **vertex,** and the line passing through the focus and the vertex is the **axis** of the parabola. Note in Figure 10.3 that a parabola is symmetric with respect to its axis.

THEOREM 10.1 Standard Equation of a Parabola

The **standard form** of the equation of a parabola with vertex (h, k) and directrix $y = k - p$ is

$$(x - h)^2 = 4p(y - k). \qquad \text{Vertical axis}$$

For directrix $x = h - p$, the equation is

$$(y - k)^2 = 4p(x - h). \qquad \text{Horizontal axis}$$

The focus lies on the axis p units (*directed distance*) from the vertex. The coordinates of the focus are as follows.

$$(h, k + p) \qquad \text{Vertical axis}$$
$$(h + p, k) \qquad \text{Horizontal axis}$$

EXAMPLE 1 Finding the Focus of a Parabola

Find the focus of the parabola

$$y = \frac{1}{2} - x - \frac{1}{2}x^2.$$

Solution To find the focus, convert to standard form by completing the square.

$$y = \frac{1}{2} - x - \frac{1}{2}x^2 \qquad \text{Write original equation.}$$
$$2y = 1 - 2x - x^2 \qquad \text{Multiply each side by 2.}$$
$$2y = 1 - (x^2 + 2x) \qquad \text{Group terms.}$$
$$2y = 2 - (x^2 + 2x + 1) \qquad \text{Add and subtract 1 on right side.}$$
$$x^2 + 2x + 1 = -2y + 2$$
$$(x + 1)^2 = -2(y - 1) \qquad \text{Write in standard form.}$$

Comparing this equation with

$$(x - h)^2 = 4p(y - k)$$

you can conclude that

$$h = -1, \quad k = 1, \quad \text{and} \quad p = -\frac{1}{2}.$$



Parabola with a vertical axis, $p < 0$

Figure 10.4

Because p is negative, the parabola opens downward, as shown in Figure 10.4. So, the focus of the parabola is p units from the vertex, or

$$(h, k + p) = \left(-1, \frac{1}{2}\right). \qquad \text{Focus}$$

GO DIGITAL

A line segment that passes through the focus of a parabola and has endpoints on the parabola is called a **focal chord.** The specific focal chord perpendicular to the axis of the parabola is the **latus rectum.** The next example shows how to determine the length of the latus rectum and the length of the corresponding intercepted arc.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 2 Focal Chord Length and Arc Length

See LarsonCalculus.com for an interactive version of this type of example.

Find the length of the latus rectum of the parabola

$$x^2 = 4py.$$

Then find the length of the parabolic arc intercepted by the latus rectum.



Length of latus rectum: $4p$
Figure 10.5

Solution Because the latus rectum passes through the focus $(0, p)$ and is perpendicular to the y-axis, the coordinates of its endpoints are

$$(-x, p) \quad \text{and} \quad (x, p).$$

Substituting p for y in the equation of the parabola produces

$$x^2 = 4p(p) \quad \Rightarrow \quad x = \pm 2p.$$

So, the endpoints of the latus rectum are $(-2p, p)$ and $(2p, p)$, and you can conclude that its length is $4p$, as shown in Figure 10.5. In contrast, the length of the intercepted arc is

$$s = \int_{-2p}^{2p} \sqrt{1 + (y')^2}\, dx \qquad \text{Use arc length formula.}$$

$$= 2\int_{0}^{2p} \sqrt{1 + \left(\frac{x}{2p}\right)^2}\, dx \qquad y = \frac{x^2}{4p} \Rightarrow y' = \frac{x}{2p}$$

$$= \frac{1}{p}\int_{0}^{2p} \sqrt{4p^2 + x^2}\, dx \qquad \text{Simplify.}$$

$$= \frac{1}{2p}\left[x\sqrt{4p^2 + x^2} + 4p^2 \ln\left|x + \sqrt{4p^2 + x^2}\right|\right]_0^{2p} \qquad \text{Theorem 8.2}$$

$$= \frac{1}{2p}\left[2p\sqrt{8p^2} + 4p^2 \ln\left(2p + \sqrt{8p^2}\right) - 4p^2 \ln(2p)\right]$$

$$= 2p\left[\sqrt{2} + \ln\left(1 + \sqrt{2}\right)\right]$$

$$\approx 4.59p.$$



Parabolic reflector: light is reflected in parallel rays.
Figure 10.6

One widely used property of a parabola is its reflective property. In physics, a surface is called **reflective** when the tangent line at any point on the surface makes equal angles with an incoming ray and the resulting outgoing ray. The angle corresponding to the incoming ray is the **angle of incidence,** and the angle corresponding to the outgoing ray is the **angle of reflection.** One example of a reflective surface is a flat mirror.

Another type of reflective surface is that formed by revolving a parabola about its axis. The resulting surface has the property that all incoming rays parallel to the axis are directed through the focus of the parabola. This is the principle behind the design of the parabolic mirrors used in reflecting telescopes. Conversely, all light rays emanating from the focus of a parabolic reflector used in a flashlight are parallel, as shown in Figure 10.6.

THEOREM 10.2 Reflective Property of a Parabola

Let P be a point on a parabola. The tangent line to the parabola at point P makes equal angles with the following two lines.

1. The line passing through P and the focus
2. The line passing through P parallel to the axis of the parabola

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

NICOLAUS COPERNICUS (1473–1543)

Copernicus began to study planetary motion when he was asked to revise the calendar. At that time, the exact length of the year could not be accurately predicted using the theory that Earth was the center of the universe.

See LarsonCalculus.com to read more of this biography.

Ellipses

More than a thousand years after the close of the Alexandrian period of Greek mathematics, Western civilization finally began a Renaissance of mathematical and scientific discovery. One of the principal figures in this rebirth was the Polish astronomer Nicolaus Copernicus (1473–1543). In his work *On the Revolutions of the Heavenly Spheres,* Copernicus claimed that all of the planets, including Earth, revolved about the sun in circular orbits. Although some of Copernicus's claims were invalid, the controversy set off by his heliocentric theory motivated astronomers to search for a mathematical model to explain the observed movements of the sun and planets. The first to find an accurate model was the German astronomer Johannes Kepler (1571–1630). Kepler discovered that the planets move about the sun in elliptical orbits, with the sun not as the center but as a focal point of the orbit.

The use of ellipses to explain the movements of the planets is only one of many practical and aesthetic uses. As with parabolas, you will begin your study of this second type of conic by defining it as a locus of points. Now, however, *two* focal points are used rather than one.

An **ellipse** is the set of all points (x, y) the sum of whose distances from two distinct fixed points called **foci** is constant. (See Figure 10.7.) The line through the foci intersects the ellipse at two points called **vertices.** The chord joining the vertices is the **major axis,** and its midpoint is the **center** of the ellipse. The chord perpendicular to the major axis at the center is the **minor axis** of the ellipse. (See Figure 10.8.)

GO DIGITAL



$d_1 + d_2$ is constant.

Figure 10.7



Figure 10.8



If the ends of a fixed length of string are fastened to the thumbtacks and the string is drawn taut with a pencil, then the path traced by the pencil will be an ellipse.

Figure 10.9

THEOREM 10.3 Standard Equation of an Ellipse

The **standard form** of the equation of an ellipse with center (h, k) and major and minor axes of lengths $2a$ and $2b$, respectively, where $a > b$, is

$$\frac{(x-h)^2}{a^2} + \frac{(y-k)^2}{b^2} = 1$$ Major axis is horizontal.

or

$$\frac{(x-h)^2}{b^2} + \frac{(y-k)^2}{a^2} = 1.$$ Major axis is vertical.

The foci lie on the major axis, c units from the center, with

$$c^2 = a^2 - b^2.$$

You can visualize the definition of an ellipse by imagining two thumbtacks placed at the foci, as shown in Figure 10.9.

FOR FURTHER INFORMATION To learn about how an ellipse may be "exploded" into a parabola, see the article "Exploding the Ellipse" by Arnold Good in *Mathematics Teacher.* To view this article, go to *MathArticles.com.*

Bettmann/Contributor/Getty Images

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 3 Analyzing an Ellipse

Find the center, vertices, and foci of the ellipse

$$4x^2 + y^2 - 8x + 4y - 8 = 0.$$ General second-degree equation

Solution Complete the square to write the original equation in standard form.

$$\begin{aligned} 4x^2 + y^2 - 8x + 4y - 8 &= 0 && \text{Write original equation.} \\ 4x^2 - 8x + y^2 + 4y &= 8 \\ 4(x^2 - 2x + 1) + (y^2 + 4y + 4) &= 8 + 4 + 4 \\ 4(x - 1)^2 + (y + 2)^2 &= 16 \\ \frac{(x - 1)^2}{4} + \frac{(y + 2)^2}{16} &= 1 && \text{Write in standard form.} \end{aligned}$$

So, the major axis is vertical, where $h = 1$, $k = -2$, $a = 4$, $b = 2$, and

$$c = \sqrt{16 - 4} = 2\sqrt{3}.$$

So, you obtain the following.

Center: $(1, -2)$ (h, k)

Vertices: $(1, -6)$ and $(1, 2)$ $(h, k \pm a)$

Foci: $\left(1, -2 - 2\sqrt{3}\right)$ and $\left(1, -2 + 2\sqrt{3}\right)$ $(h, k \pm c)$

The graph of the ellipse is shown in Figure 10.10.



Ellipse with a vertical major axis
Figure 10.10

In Example 3, the constant term in the general second-degree equation is $F = -8$. For a constant term greater than or equal to 8, you would obtain one of the degenerate cases listed below.

1. $F = 8$, single point, $(1, -2)$: $\dfrac{(x - 1)^2}{4} + \dfrac{(y + 2)^2}{16} = 0$

2. $F > 8$, no solution points: $\dfrac{(x - 1)^2}{4} + \dfrac{(y + 2)^2}{16} < 0$

EXAMPLE 4 The Orbit of the Moon

The moon orbits Earth in an elliptical path with the center of Earth at one focus, as shown in Figure 10.11. The major and minor axes of the orbit have lengths of 768,800 kilometers and 767,641 kilometers, respectively. Find the greatest and least distances (the apogee and perigee) from Earth's center to the moon's center.

Solution Begin by solving for a and b.

$2a = 768{,}800$ Length of major axis

$a = 384{,}400$ Solve for a.

$2b = 767{,}641$ Length of minor axis

$b = 383{,}820.5$ Solve for b.

Now, using these values, you can solve for c as follows.

$$c = \sqrt{a^2 - b^2} \approx 21{,}099$$

The greatest distance between the center of Earth and the center of the moon is

$$a + c \approx 405{,}499 \text{ kilometers}$$

and the least distance is

$$a - c \approx 363{,}301 \text{ kilometers.}$$



Figure 10.11

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

FOR FURTHER INFORMATION
For more information on some uses of the reflective properties of conics, see the article "Parabolic Mirrors, Elliptic and Hyperbolic Lenses" by Mohsen Maesumi in *The American Mathematical Monthly.* Also see the article "The Geometry of Microwave Antennas" by William R. Parzynski in *Mathematics Teacher.*

Theorem 10.2 presented a reflective property of parabolas. Ellipses have a similar reflective property. You are asked to prove the next theorem in Exercise 80.

THEOREM 10.4 Reflective Property of an Ellipse

Let P be a point on an ellipse. The tangent line to the ellipse at point P makes equal angles with the lines through P and the foci.

One of the reasons that astronomers had difficulty detecting that the orbits of the planets are ellipses is that the foci of the planetary orbits are relatively close to the center of the sun, making the orbits nearly circular. To measure the ovalness of an ellipse, you can use the concept of **eccentricity.**

Definition of Eccentricity of an Ellipse

The **eccentricity** e of an ellipse is given by the ratio $e = \frac{c}{a}$.

To see how this ratio is used to describe the shape of an ellipse, note that because the foci of an ellipse are located along the major axis between the vertices and the center, it follows that $0 < c < a$. For an ellipse that is nearly circular, the foci are close to the center and the ratio c/a is close to 0, and for an elongated ellipse, the foci are close to the vertices and the ratio c/a is close to 1, as shown in Figure 10.12. Note that

$0 < e < 1$ The eccentricity e of an ellipse is between 0 and 1.

for every ellipse.



(a) $\frac{c}{a}$ is small. **(b)** $\frac{c}{a}$ is close to 1.

Eccentricity is the ratio $\frac{c}{a}$.

Figure 10.12

The orbit of the moon has an eccentricity of $e \approx 0.0549$, and the eccentricities of the eight planetary orbits are listed below.

Mercury:	$e \approx 0.2056$	Jupiter:	$e \approx 0.0489$
Venus:	$e \approx 0.0067$	Saturn:	$e \approx 0.0565$
Earth:	$e \approx 0.0167$	Uranus:	$e \approx 0.0457$
Mars:	$e \approx 0.0935$	Neptune:	$e \approx 0.0113$

Recall from Section 8.4, Example 5, that you used integration to show that the area of an ellipse is $A = \pi ab$. It is not so simple, however, to find the *circumference* of an ellipse. The next example shows how to use eccentricity to set up an "elliptic integral" for the circumference of an ellipse.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 5 Finding the Circumference of an Ellipse

See LarsonCalculus.com for an interactive version of this type of example.

Show that the circumference of the ellipse $(x^2/a^2) + (y^2/b^2) = 1$ is

$$4a\int_0^{\pi/2} \sqrt{1 - e^2 \sin^2\theta}\, d\theta. \qquad e = \frac{c}{a}$$

Solution Because the ellipse is symmetric with respect to both the x-axis and the y-axis, you know that its circumference C is four times the arc length of

$$y = \frac{b}{a}\sqrt{a^2 - x^2}$$

in the first quadrant. The function y is differentiable for all x in the interval $[0, a]$ except at $x = a$. So, the circumference is given by the improper integral

$$C = \lim_{d\to a^-} 4\int_0^d \sqrt{1 + (y')^2}\, dx = 4\int_0^a \sqrt{1 + (y')^2}\, dx = 4\int_0^a \sqrt{1 + \frac{b^2x^2}{a^2(a^2 - x^2)}}\, dx.$$

Using the trigonometric substitution $x = a \sin\theta$, you obtain

$$\begin{aligned} C &= 4\int_0^{\pi/2} \sqrt{1 + \frac{b^2\sin^2\theta}{a^2\cos^2\theta}}(a\cos\theta)\, d\theta \\ &= 4\int_0^{\pi/2} \sqrt{a^2\cos^2\theta + b^2\sin^2\theta}\, d\theta \\ &= 4\int_0^{\pi/2} \sqrt{a^2(1 - \sin^2\theta) + b^2\sin^2\theta}\, d\theta \\ &= 4\int_0^{\pi/2} \sqrt{a^2 - (a^2 - b^2)\sin^2\theta}\, d\theta. \end{aligned}$$

Because $e^2 = c^2/a^2 = (a^2 - b^2)/a^2$, you can rewrite this integral as

$$C = 4a\int_0^{\pi/2} \sqrt{1 - e^2\sin^2\theta}\, d\theta.$$

AREA AND CIRCUMFERENCE OF AN ELLIPSE

In his work with elliptic orbits in the early 1600s, Johannes Kepler successfully developed a formula for the area of an ellipse, $A = \pi ab$. He was less successful, however, in developing a formula for the circumference of an ellipse; the best he could do was to give the approximate formula $C = \pi(a + b)$.

A great deal of time has been devoted to the study of elliptic integrals. Such integrals generally do not have elementary antiderivatives. To find the circumference of an ellipse, you must usually resort to an approximation technique.

EXAMPLE 6 Approximating the Value of an Elliptic Integral

Use the elliptic integral in Example 5 to approximate the circumference of the ellipse

$$\frac{x^2}{25} + \frac{y^2}{16} = 1.$$

Solution Because $e^2 = c^2/a^2 = (a^2 - b^2)/a^2 = 9/25$, you have

$$C = (4)(5)\int_0^{\pi/2} \sqrt{1 - \frac{9\sin^2\theta}{25}}\, d\theta.$$

Applying Simpson's Rule with $n = 4$ produces

$$\begin{aligned} C &\approx 20\left[\frac{\pi/2}{3(4)}\right][1 + 4(0.9733) + 2(0.9055) + 4(0.8323) + 0.8] \\ &\approx 28.36. \end{aligned}$$

So, the ellipse has a circumference of about 28.36 units, as shown in Figure 10.13.



Figure 10.13

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.





Figure 10.14

Hyperbolas

The definition of a hyperbola is similar to that of an ellipse. For an ellipse, the *sum* of the distances between the foci and a point on the ellipse is fixed, whereas for a hyperbola, the absolute value of the *difference* between these distances is fixed.

A **hyperbola** is the set of all points (x, y) for which the absolute value of the difference between the distances from two distinct fixed points called **foci** is constant. (See Figure 10.14.) The line through the two foci intersects a hyperbola at two points called **vertices.** The line segment connecting the vertices is the **transverse axis,** and the midpoint of the transverse axis is the **center** of the hyperbola. One distinguishing feature of a hyperbola is that its graph has two separate *branches.*

THEOREM 10.5 Standard Equation of a Hyperbola

The **standard form** of the equation of a hyperbola with center at (h, k) is

$$\frac{(x-h)^2}{a^2} - \frac{(y-k)^2}{b^2} = 1 \qquad \text{Transverse axis is horizontal.}$$

or

$$\frac{(y-k)^2}{a^2} - \frac{(x-h)^2}{b^2} = 1. \qquad \text{Transverse axis is vertical.}$$

The vertices are a units from the center, and the foci are c units from the center, where $c^2 = a^2 + b^2$.



Figure 10.15

Note that the constants a, b, and c do not have the same relationship for hyperbolas as they do for ellipses. For hyperbolas, $c^2 = a^2 + b^2$, but for ellipses, $c^2 = a^2 - b^2$.

An important aid in sketching the graph of a hyperbola is the determination of its **asymptotes,** as shown in Figure 10.15. Each hyperbola has two asymptotes that intersect at the center of the hyperbola. The asymptotes pass through the vertices of a rectangle of dimensions $2a$ by $2b$, with its center at (h, k). The line segment of length $2b$ joining

$$(h, k + b)$$

and

$$(h, k - b)$$

is referred to as the **conjugate axis** of the hyperbola.

THEOREM 10.6 Asymptotes of a Hyperbola

For a *horizontal* transverse axis, the equations of the asymptotes are

$$y = k + \frac{b}{a}(x - h) \quad \text{and} \quad y = k - \frac{b}{a}(x - h).$$

For a *vertical* transverse axis, the equations of the asymptotes are

$$y = k + \frac{a}{b}(x - h) \quad \text{and} \quad y = k - \frac{a}{b}(x - h).$$

Notice in Figure 10.15 that the asymptotes coincide with the diagonals of the rectangle with dimensions $2a$ and $2b$, centered at (h, k). This provides you with a quick means of sketching the asymptotes, which in turn aids in sketching the hyperbola.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 7 Using Asymptotes to Sketch a Hyperbola

See LarsonCalculus.com for an interactive version of this type of example.

Sketch the graph of the hyperbola

$$4x^2 - y^2 = 16.$$

Solution Begin by rewriting the equation in standard form.

$$\frac{x^2}{4} - \frac{y^2}{16} = 1$$

The transverse axis is horizontal and the vertices occur at $(-2, 0)$ and $(2, 0)$. The ends of the conjugate axis occur at $(0, -4)$ and $(0, 4)$. Using these four points, you can sketch the rectangle shown in Figure 10.16(a). By drawing the asymptotes through the corners of this rectangle, you can complete the sketch as shown in Figure 10.16(b).



(a) **(b)**

Figure 10.16

Definition of Eccentricity of a Hyperbola

The **eccentricity** e of a hyperbola is given by the ratio

$$e = \frac{c}{a}.$$

FOR FURTHER INFORMATION To read about using a string that traces both elliptic and hyperbolic arcs having the same foci, see the article "Ellipse to Hyperbola: 'With This String I Thee Wed'" by Tom M. Apostol and Mamikon A. Mnatsakanian in *Mathematics Magazine*. To view this article, go to *MathArticles.com*.

As with an ellipse, the **eccentricity** of a hyperbola is $e = c/a$. Because $c > a$ for hyperbolas, it follows that $e > 1$ for hyperbolas. If the eccentricity is large, then the branches of the hyperbola are nearly flat. If the eccentricity is close to 1, then the branches of the hyperbola are more pointed, as shown in Figure 10.17.



Figure 10.17

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The application in Example 8 was developed during World War II. It shows how the properties of hyperbolas can be used in radar and other detection systems.

EXAMPLE 8 A Hyperbolic Detection System

Two microphones, 1 mile apart, record an explosion. Microphone A receives the sound 2 seconds before microphone B. Where was the explosion? (Assume sound travels at 1100 feet per second.)



Figure 10.18

Solution Note that 1 mile = 5280 feet. So, place A at $(2640, 0)$ and B at $(-2640, 0)$, as shown in Figure 10.18. Because A received the sound 2 seconds before B, you can conclude that the explosion took place 2200 feet farther from B than from A. The locus of all points that are 2200 feet closer to A than to B is one branch of the hyperbola with the form

$$\frac{x^2}{a^2} - \frac{y^2}{b^2} = 1.$$

From the figure, it follows that $d_2 - d_1 = 2a = 2200$. Solving for a yields

$$a = \frac{2200}{2} = 1100.$$

The distance from the center of the hyperbola to the focus at A is 2640 feet, so $c = 2640$. Because $c^2 = a^2 + b^2$, it follows that the value of b^2 is

$$\begin{aligned} b^2 &= c^2 - a^2 && \text{Solve for } b^2. \\ &= (2640)^2 - (1100)^2 && \text{Substitute for } c \text{ and } a. \\ &= 5{,}759{,}600. && \text{Simplify.} \end{aligned}$$

So, you can conclude that the explosion occurred somewhere on the right branch of the hyperbola

$$\frac{x^2}{1{,}210{,}000} - \frac{y^2}{5{,}759{,}600} = 1.$$

CAROLINE HERSCHEL (1750–1848)

The first woman to be credited with detecting a new comet was the English astronomer Caroline Herschel. During her life, Caroline Herschel discovered a total of eight new comets.

See LarsonCalculus.com to read more of this biography.

GL Archive/Alamy Stock Photo

In Example 8, you were able to determine only the hyperbola on which the explosion occurred, but not the exact location of the explosion. If, however, you had received the sound at a third position C, then two other hyperbolas would be determined. The exact location of the explosion would be the point at which these three hyperbolas intersect.

Another interesting application of conics involves the orbits of comets in our solar system. Comets can have elliptical, parabolic, or hyperbolic orbits. The center of the sun is a focus of each orbit, and each orbit has a vertex at the point at which the comet is closest to the sun. Undoubtedly, many comets with parabolic or hyperbolic orbits have not been identified—such comets pass through our solar system only once. Only comets with elliptical orbits, such as Halley's comet, remain in our solar system.

The type of orbit for a comet can be determined as follows.

1. Ellipse: $v < \sqrt{2GM/p}$
2. Parabola: $v = \sqrt{2GM/p}$
3. Hyperbola: $v > \sqrt{2GM/p}$

In each of the above, p is the distance between one vertex and one focus of the comet's orbit (in meters), v is the velocity of the comet at the vertex (in meters per second), $M \approx 1.989 \times 10^{30}$ kilograms is the mass of the sun, and $G \approx 6.67 \times 10^{-11}$ cubic meter per kilogram-second squared is the gravitational constant.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

10.1 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. State the definitions of parabola, ellipse, and hyperbola.
2. State the definitions of major axis, minor axis, and transverse axis.
3. Consider an ellipse with eccentricity e.
   (a) What are the possible values of e?
   (b) What happens to the graph of the ellipse as e increases?
4. Explain how to sketch a hyperbola with a vertical transverse axis.

Matching **In Exercises 5–10, match the equation with its graph. [The graphs are labeled (a), (b), (c), (d), (e), and (f).]**

(a)



(b)



(c)



(d)



(e)



(f)



5. $y^2 = 4x$
6. $(x + 4)^2 = -2(y - 2)$
7. $\frac{y^2}{16} - \frac{x^2}{1} = 1$
8. $\frac{(x - 2)^2}{16} + \frac{(y + 1)^2}{4} = 1$
9. $\frac{x^2}{4} + \frac{y^2}{9} = 1$
10. $\frac{(x - 2)^2}{9} - \frac{y^2}{4} = 1$

Sketching a Parabola **In Exercises 11–16, find the vertex, focus, and directrix of the parabola, and sketch its graph.**

11. $(x + 5) + (y - 3)^2 = 0$
12. $(x - 6)^2 - 2(y + 7) = 0$
13. $y^2 - 4y - 4x = 0$
14. $y^2 + 6y + 8x + 25 = 0$
15. $x^2 + 4x + 4y - 4 = 0$
16. $x^2 - 2x - 4y - 7 = 0$

Finding the Standard Equation of a Parabola **In Exercises 17–24, find the standard form of the equation of the parabola with the given characteristics.**

17. Vertex: $(5, 4)$
    Focus: $(3, 4)$
18. Vertex: $(-3, -1)$
    Focus: $(-3, 1)$
19. Vertex: $(0, 5)$
    Directrix: $y = -3$
20. Focus: $(2, 2)$
    Directrix: $x = -2$
21. Vertex: $(1, -1)$
    Points on the parabola: $(-1, -4), (3, -4)$
22. Vertex: $(2, 4)$
    Points on the parabola: $(0, 0), (4, 0)$
23. Axis is parallel to y-axis; graph passes through $(0, 3)$, $(3, 4)$, and $(4, 11)$.
24. Directrix: $y = -2$; endpoints of latus rectum are $(0, 2)$ and $(8, 2)$.

Sketching an Ellipse **In Exercises 25–30, find the center, foci, vertices, and eccentricity of the ellipse, and sketch its graph.**

25. $16x^2 + y^2 = 16$
26. $3x^2 + 7y^2 = 63$
27. $\frac{(x - 3)^2}{16} + \frac{(y - 1)^2}{25} = 1$
28. $(x + 4)^2 + \frac{(y + 6)^2}{1/4} = 1$
29. $9x^2 + 4y^2 + 36x - 24y - 36 = 0$
30. $x^2 + 10y^2 - 6x + 20y + 18 = 0$

Finding the Standard Equation of an Ellipse **In Exercises 31–36, find the standard form of the equation of the ellipse with the given characteristics.**

31. Center: $(0, 0)$
    Focus: $(5, 0)$
    Vertex: $(6, 0)$
32. Vertices: $(0, 3), (8, 3)$
    Eccentricity: $\frac{3}{4}$
33. Vertices: $(3, 1), (3, 9)$
    Minor axis length: 6
34. Foci: $(0, \pm 9)$
    Major axis length: 22
35. Center: $(0, 0)$
    Major axis: horizontal
    Points on the ellipse: $(3, 1), (4, 0)$
36. Center: $(1, 2)$
    Major axis: vertical
    Points on the ellipse: $(1, 6), (3, 2)$

Sketching a Hyperbola **In Exercises 37–40, find the center, foci, vertices, and eccentricity of the hyperbola, and sketch its graph using asymptotes as an aid.**

37. $\frac{x^2}{25} - \frac{y^2}{16} = 1$
38. $\frac{(y + 3)^2}{225} - \frac{(x - 5)^2}{64} = 1$
39. $9x^2 - y^2 - 36x - 6y + 18 = 0$
40. $y^2 - 16x^2 + 64x - 208 = 0$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding the Standard Equation of a Hyperbola **In Exercises 41–48, find the standard form of the equation of the hyperbola with the given characteristics.**

41. Vertices: $(\pm 1, 0)$
Asymptotes: $y = \pm 5x$

42. Vertices: $(0, \pm 4)$
Asymptotes: $y = \pm 2x$

43. Vertices: $(2, \pm 3)$
Point on graph: $(0, 5)$

44. Vertices: $(2, \pm 3)$
Foci: $(2, \pm 5)$

45. Center: $(0, 0)$
Vertex: $(0, 2)$
Focus: $(0, 4)$

46. Center: $(0, 0)$
Vertex: $(6, 0)$
Focus: $(10, 0)$

47. Vertices: $(0, 2), (6, 2)$
Asymptotes: $y = \frac{2}{3}x$
$y = 4 - \frac{2}{3}x$

48. Focus: $(20, 0)$
Asymptotes: $y = \pm\frac{3}{4}x$

Finding Equations of Tangent Lines and Normal Lines **In Exercises 49 and 50, find equations for (a) the tangent lines and (b) the normal lines to the hyperbola for the given value of x. (The *normal line* at a point is perpendicular to the tangent line at the point.)**

49. $\frac{x^2}{9} - y^2 = 1, \quad x = 6$

50. $\frac{y^2}{4} - \frac{x^2}{2} = 1, \quad x = 4$

Classifying the Graph of an Equation **In Exercises 51–56, classify the graph of the equation as a circle, a parabola, an ellipse, or a hyperbola.**

51. $25x^2 - 10x - 200y - 119 = 0$

52. $4x^2 - y^2 - 4x - 3 = 0$

53. $3(x - 1)^2 = 6 + 2(y + 1)^2$

54. $9(x + 3)^2 = 36 - 4(y - 2)^2$

55. $9x^2 + 9y^2 - 36x + 6y + 34 = 0$

56. $y^2 - 4y = x + 5$

Exploring Concepts

57. Consider the equation $9x^2 + 4y^2 - 36x - 24y - 36 = 0$.

(a) Classify the graph of the equation as a circle, a parabola, an ellipse, or a hyperbola.

(b) Change the $4y^2$-term in the equation to $-4y^2$. Classify the graph of the new equation.

(c) Change the $9x^2$-term in the original equation to $4x^2$. Classify the graph of the new equation.

(d) Describe one way you could change the original equation so that its graph is a parabola.

58. Sketch the graphs of $x^2 = 4py$ for $p = \frac{1}{4}, \frac{1}{2}, 1, \frac{3}{2}$, and 2 on the same coordinate axes. Discuss the change in the graphs as p increases.

59. Let C be the circumference of the ellipse

$(x^2/a^2) + (y^2/b^2) = 1, \quad b < a.$

Explain why $2\pi b < C < 2\pi a$. Use a graph to support your explanation.

60. HOW DO YOU SEE IT? Describe in words how a plane could intersect with the double-napped cone to form each conic section (see figure).

(a) Circle (b) Ellipse
(c) Parabola (d) Hyperbola

61. Solar Collector A solar collector for heating water is constructed with a sheet of stainless steel that is formed into the shape of a parabola (see figure). The water will flow through a pipe that is located at the focus of the parabola. At what distance from the vertex is the pipe?



Figure for 61



Figure for 62

62. Beam Deflection A simply supported beam that is 16 meters long has a load concentrated at the center (see figure). The deflection of the beam at its center is 3 centimeters. Assume that the shape of the deflected beam is parabolic.

(a) Find an equation of the parabola. (Assume that the origin is at the center of the beam.)

(b) How far from the center of the beam is the deflection 1 centimeter?

63. Proof

(a) Prove that any two distinct tangent lines to a parabola intersect.

(b) Demonstrate the result of part (a) by finding the point of intersection of the tangent lines to the parabola $x^2 - 4x - 4y = 0$ at the points $(0, 0)$ and $(6, 3)$.

64. Proof

(a) Prove that if any two tangent lines to a parabola intersect at right angles, then their point of intersection must lie on the directrix.

(b) Demonstrate the result of part (a) by showing that the tangent lines to the parabola $x^2 - 4x - 4y + 8 = 0$ at the points $(-2, 5)$ and $\left(3, \frac{5}{4}\right)$ intersect at right angles and that their point of intersection lies on the directrix.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

65. Bridge Design A cable of a suspension bridge is suspended (in the shape of a parabola) between two towers that are 120 meters apart and 20 meters above the roadway (see figure). The cable touches the roadway midway between the towers. Find an equation for the parabolic shape of the cable.



66. Arc Length Find the length of the parabolic cable in Exercise 65.

67. Architecture

A church window is bounded above by a parabola and below by the arc of a circle (see figure). Find the area of the window.



68. Surface Area A satellite signal receiving dish is formed by revolving the parabola given by

$$x^2 = 20y$$

about the y-axis. The radius of the dish is r feet. Verify that the surface area of the dish is given by

$$2\pi\int_0^r x\sqrt{1+\left(\frac{x}{10}\right)^2}\,dx = \frac{\pi}{15}[(100+r^2)^{3/2} - 1000].$$

69. Orbit of Earth Earth moves in an elliptical orbit with the sun at one of the foci. The length of half of the major axis is 149,598,000 kilometers, and the eccentricity is 0.0167. Find the minimum distance (*perihelion*) and the maximum distance (*aphelion*) of Earth from the sun.

70. Satellite Orbit The *apogee* (the point in orbit farthest from Earth) and the *perigee* (the point in orbit closest to Earth) of an elliptical orbit of an Earth satellite are given by A and P, respectively. Show that the eccentricity of the orbit is

$$e = \frac{A-P}{A+P}.$$

71. Explorer 1 On January 31, 1958, the United States launched the research satellite Explorer 1. Its low and high points above the surface of Earth were 220 miles and 1563 miles. Find the eccentricity of its elliptical orbit. (Use 4000 miles as the radius of Earth.)

72. Explorer 55 On November 20, 1975, the United States launched the research satellite Explorer 55. Its low and high points above the surface of Earth were 96 miles and 1865 miles. Find the eccentricity of its elliptical orbit. (Use 4000 miles as the radius of Earth.)

73. Halley's Comet

Probably the most famous of all comets, Halley's comet, has an elliptical orbit with the sun at one focus. Its maximum distance from the sun is approximately 35.29 AU (1 astronomical unit is approximately 92.956×10^6 miles), and its minimum distance is approximately 0.59 AU. Find the eccentricity of the orbit.

74. Particle Motion Consider a particle traveling clockwise on the elliptical path

$$\frac{x^2}{100} + \frac{y^2}{25} = 1.$$

The particle leaves the orbit at the point $(-8, 3)$ and travels in a straight line tangent to the ellipse. At what point will the particle cross the y-axis?

Area, Volume, and Surface Area **In Exercises 75 and 76, find (a) the area of the region bounded by the ellipse, (b) the volume and surface area of the solid generated by revolving the region about its major axis (prolate spheroid), and (c) the volume and surface area of the solid generated by revolving the region about its minor axis (oblate spheroid).**

75. $\frac{x^2}{4} + \frac{y^2}{1} = 1$

76. $\frac{x^2}{16} + \frac{y^2}{9} = 1$

77. Arc Length Use the integration capabilities of a graphing utility to approximate to two-decimal-place accuracy the elliptical integral representing the circumference of the ellipse

$$\frac{x^2}{25} + \frac{y^2}{49} = 1.$$

78. Conjecture

(a) Show that the equation of an ellipse can be written as

$$\frac{(x-h)^2}{a^2} + \frac{(y-k)^2}{a^2(1-e^2)} = 1.$$

(b) Use a graphing utility to graph the ellipse

$$\frac{(x-2)^2}{4} + \frac{(y-3)^2}{4(1-e^2)} = 1$$

for $e = 0.95$, $e = 0.75$, $e = 0.5$, $e = 0.25$, and $e = 0$.

(c) Use the results of part (b) to make a conjecture about the change in the shape of the ellipse as e approaches 0.

chirajuti/Shutterstock.com

NASA

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

79. Geometry The area of the ellipse in the figure is twice the area of the circle. What is the length of the major axis?



Figure for 79



Figure for 80

80. Proof Prove Theorem 10.4 by showing that the tangent line to an ellipse at a point P makes equal angles with lines through P and the foci (see figure). [*Hint:* (1) Find the slope of the tangent line at P, (2) find the slopes of the lines through P and each focus, and (3) use the formula for the tangent of the angle θ between two lines with slopes m_1 and m_2,

$$\tan\theta = \left|\frac{m_1 - m_2}{1 + m_1 m_2}\right|.]$$

81. Finding an Equation of a Hyperbola Find an equation of the hyperbola such that for any point on the hyperbola, the difference between its distances from the points $(2, 2)$ and $(10, 2)$ is 6.

82. Hyperbola Consider a hyperbola centered at the origin with a horizontal transverse axis. Use the definition of a hyperbola to derive its standard form

$$\frac{x^2}{a^2} - \frac{y^2}{b^2} = 1.$$

83. Navigation LORAN (long distance radio navigation) for aircraft and ships uses synchronized pulses transmitted by widely separated transmitting stations. These pulses travel at the speed of light (186,000 miles per second). The difference in the times of arrival of these pulses at an aircraft or ship is constant on a hyperbola having the transmitting stations as foci. Assume that two stations, 300 miles apart, are positioned on a rectangular coordinate system at $(-150, 0)$ and $(150, 0)$ and that a ship is traveling on a path with coordinates $(x, 75)$ (see figure). Find the x-coordinate of the position of the ship when the time difference between the pulses from the transmitting stations is 1000 microseconds (0.001 second).



Figure for 83



Figure for 84

84. Hyperbolic Mirror A hyperbolic mirror (used in some telescopes) has the property that a light ray directed at the focus will be reflected to the other focus. The mirror in the figure has the equation

$$\frac{x^2}{36} - \frac{y^2}{64} = 1.$$

At which point on the mirror will light from the point $(0, 10)$ be reflected to the other focus?

85. Tangent Line Show that the equation of the tangent line to $\frac{x^2}{a^2} - \frac{y^2}{b^2} = 1$ at the point (x_0, y_0) is $\left(\frac{x_0}{a^2}\right)x - \left(\frac{y_0}{b^2}\right)y = 1$.

86. Proof Prove that the graph of the equation

$$Ax^2 + Cy^2 + Dx + Ey + F = 0$$

is one of the following (except in degenerate cases).

Conic	Condition
(a) Circle	$A = C$
(b) Parabola	$A = 0$ or $C = 0$ (but not both)
(c) Ellipse	$AC > 0$
(d) Hyperbola	$AC < 0$

True or False? **In Exercises 87–92, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

87. It is possible for a parabola to intersect its directrix.

88. The point on a parabola closest to its focus is its vertex.

89. The eccentricity of a hyperbola with a horizontal transverse axis is $e = \sqrt{1 + m^2}$, where m and $-m$ the slopes of the asymptotes.

90. If $D \neq 0$ or $E \neq 0$, then the graph of

$$y^2 - x^2 + Dx + Ey = 0$$

is a hyperbola.

91. If the asymptotes of the hyperbola $(x^2/a^2) - (y^2/b^2) = 1$ intersect at right angles, then $a = b$.

92. Every tangent line to a hyperbola intersects the hyperbola only at the point of tangency.

PUTNAM EXAM CHALLENGE

93. For a point P on an ellipse, let d be the distance from the center of the ellipse to the line tangent to the ellipse at P. Prove that $(PF_1)(PF_2)d^2$ is constant as P varies on the ellipse, where PF_1 and PF_2 are the distances from P to the foci F_1 and F_2 of the ellipse.

94. Find the minimum value of

$$(u - v)^2 + \left(\sqrt{2 - u^2} - \frac{9}{v}\right)^2$$

for $0 < u < \sqrt{2}$ and $v > 0$.

These problems were composed by the Committee on the Putnam Prize Competition. © The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

10.2 Plane Curves and Parametric Equations

GO DIGITAL

- **Sketch the graph of a curve given by a set of parametric equations.**
- **Eliminate the parameter in a set of parametric equations.**
- **Find a set of parametric equations to represent a curve.**
- **Describe two classic calculus problems, the tautochrone and brachistochrone problems.**

Big Ideas of Calculus

So far, your study of calculus has centered around plane curves given by $y = f(x)$. Now, you will extend the concepts of calculus to curves given by a set of parametric equations and to those represented by polar coordinates. These representations are very useful in studying the motions of objects. In some applications, such as in finding the area of a region, these alternative forms may be more convenient to use than the corresponding rectangular form.

Plane Curves and Parametric Equations

Until now, you have been representing a graph by a single equation involving *two* variables. In this section, you will study situations in which *three* variables are used to represent a curve in the plane.

Consider the path followed by an object that is propelled into the air at an angle of 45°. For an initial velocity of 48 feet per second, the object travels the parabolic path given by the rectangular equation

$$y = -\frac{x^2}{72} + x$$

as shown in Figure 10.19. This equation, however, does not tell the whole story. Although it does tell you *where* the object has been, it does not tell you *when* the object was at a given point (x, y). To determine this time, you can introduce a third variable t, called a **parameter.** By writing both x and y as functions of t, you obtain the **parametric equations**



Curvilinear motion: two variables for position, one variable for time
Figure 10.19

$$x = 24\sqrt{2}t \qquad \text{Parametric equation for } x$$

and

$$y = -16t^2 + 24\sqrt{2}t. \qquad \text{Parametric equation for } y$$

From this set of equations, you can determine that at time $t = 0$, the object is at the point $(0, 0)$. Similarly, at time $t = 1$, the object is at the point

$$\left(24\sqrt{2}, 24\sqrt{2} - 16\right)$$

and so on. (You will learn a method for determining this particular set of parametric equations—the equations of motion—later, in Section 12.3.)

For this particular motion problem, x and y are continuous functions of t, and the resulting path is called a **plane curve.**

REMARK At times, it is important to distinguish between a graph (the set of points) and a curve (the points together with their defining parametric equations). When it is important, the distinction will be explicit. When it is not important, C will be used to represent either the graph or the curve.

Definition of a Plane Curve

If f and g are continuous functions of t on an interval I, then the equations

$$x = f(t) \quad \text{and} \quad y = g(t)$$

are **parametric equations** and t is the **parameter.** The set of points (x, y) obtained as t varies over the interval I is the **graph** of the parametric equations. Taken together, the parametric equations and the graph are a **plane curve,** denoted by C.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

When sketching a curve represented by a set of parametric equations, you can plot points in the xy-plane. Each set of coordinates (x, y) is determined from a value chosen for the parameter t. By plotting the resulting points in order of increasing values of t, the curve is traced out in a specific direction. This is called the **orientation** of the curve.

EXAMPLE 1 Sketching a Curve

Sketch the curve described by the parametric equations

$$x = f(t) = t^2 - 4$$

and

$$y = g(t) = \frac{t}{2}$$

where $-2 \le t \le 3$.

Solution For values of t on the given interval, the parametric equations yield the points (x, y) shown in the table.

t	-2	-1	0	1	2	3
x	0	-3	-4	-3	0	5
y	-1	$-\frac{1}{2}$	0	$\frac{1}{2}$	1	$\frac{3}{2}$

By plotting these points in order of increasing values of t and using the continuity of f and g, you obtain the curve C shown in Figure 10.20. Note that the arrows on the curve indicate its orientation as t increases from -2 to 3.



Figure 10.20



Figure 10.21

According to the Vertical Line Test, the graph shown in Figure 10.20 does not define y as a function of x. This points out one benefit of parametric equations—they can be used to represent graphs that are more general than graphs of functions.

It often happens that two different sets of parametric equations have the same graph. For instance, the set of parametric equations

$$x = 4t^2 - 4 \quad \text{and} \quad y = t, \quad -1 \le t \le \frac{3}{2}$$

has the same graph as the set given in Example 1. (See Figure 10.21.) By comparing the values of t in Figures 10.20 and 10.21, however, notice that the second graph is traced out more *rapidly* (considering t as time) than the first graph. So, in applications, different parametric representations can be used to represent various *speeds* at which objects travel along a given path.

TECHNOLOGY Most graphing utilities have a *parametric* graphing mode. If you have access to such a utility, use it to confirm the graphs shown in Figures 10.20 and 10.21. Does the curve given by the parametric equations

$$x = 4t^2 - 8t \quad \text{and} \quad y = 1 - t, \quad -\frac{1}{2} \le t \le 2$$

represent the same graph as that shown in Figures 10.20 and 10.21? What do you notice about the *orientation* of this curve?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Eliminating the Parameter

Finding a rectangular equation that represents the graph of a set of parametric equations is called **eliminating the parameter.** For instance, one way to eliminate the parameter from the set of parametric equations in Example 1 is shown below.

Parametric equations	⇨	Solve for t in one equation.	⇨	Substitute into other equation.	⇨	Rectangular equation
$x = t^2 - 4$				$x = (2y)^2 - 4$		$x = 4y^2 - 4$
$y = \frac{t}{2}$		$t = 2y$				

After eliminating the parameter, you can recognize that the equation $x = 4y^2 - 4$ represents a parabola with a horizontal axis and vertex at $(-4, 0)$, as shown in Figure 10.20.

The range of x and y implied by the parametric equations may be altered by the change to rectangular form. In such instances, the domain of the rectangular equation must be adjusted so that its graph matches the graph of the parametric equations. Such a situation is demonstrated in the next example.

EXAMPLE 2 Eliminating the Parameter

Sketch the curve represented by the equations

$$x = \frac{1}{\sqrt{t+1}} \quad \text{and} \quad y = \frac{t}{t+1}, \quad t > -1$$

by eliminating the parameter and adjusting the domain of the resulting rectangular equation.

Solution Begin by solving one of the parametric equations for t. For instance, you can solve the first equation for t as shown below.

$$x = \frac{1}{\sqrt{t+1}} \qquad \text{Parametric equation for } x$$

$$x^2 = \frac{1}{t+1} \qquad \text{Square each side.}$$

$$t + 1 = \frac{1}{x^2}$$

$$t = \frac{1}{x^2} - 1$$

$$t = \frac{1 - x^2}{x^2} \qquad \text{Solve for } t.$$

Now, substituting into the parametric equation for y produces

$$y = \frac{t}{t+1} \qquad \text{Parametric equation for } y$$

$$y = \frac{(1 - x^2)/x^2}{[(1 - x^2)/x^2] + 1} \qquad \text{Substitute } (1 - x^2)/x^2 \text{ for } t.$$

$$y = 1 - x^2. \qquad \text{Simplify.}$$

The rectangular equation $y = 1 - x^2$ is defined for all values of x, but the parametric equation for x is defined only when $t > -1$. This implies that you should restrict the domain of x to positive values, as shown in Figure 10.22. ■



Figure 10.22

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

It is not necessary for the parameter in a set of parametric equations to represent time. The next example uses an *angle* as the parameter.

EXAMPLE 3 Using Trigonometry to Eliminate a Parameter

See LarsonCalculus.com for an interactive version of this type of example.

Sketch the curve represented by

$$x = 3\cos\theta \quad \text{and} \quad y = 4\sin\theta, \quad 0 \le \theta \le 2\pi$$

by eliminating the parameter and finding the corresponding rectangular equation.

Solution Begin by solving for $\cos\theta$ and $\sin\theta$ in the given equations.

$$\cos\theta = \frac{x}{3} \qquad \text{Solve for } \cos\theta.$$

and

$$\sin\theta = \frac{y}{4} \qquad \text{Solve for } \sin\theta.$$

Next, make use of the identity

$$\sin^2\theta + \cos^2\theta = 1$$

to form an equation involving only x and y.

$$\cos^2\theta + \sin^2\theta = 1 \qquad \text{Trigonometric identity}$$

$$\left(\frac{x}{3}\right)^2 + \left(\frac{y}{4}\right)^2 = 1 \qquad \text{Substitute.}$$

$$\frac{x^2}{9} + \frac{y^2}{16} = 1 \qquad \text{Rectangular equation}$$

From this rectangular equation, you can determine that the graph is an ellipse centered at $(0, 0)$, with vertices at $(0, 4)$ and $(0, -4)$ and minor axis of length $2b = 6$, as shown in Figure 10.23. Note that the ellipse is traced out *counterclockwise* as θ varies from 0 to 2π. ■



Figure 10.23

Using the technique shown in Example 3, you can conclude that the graph of the parametric equations

$$x = h + a\cos\theta \quad \text{and} \quad y = k + b\sin\theta, \quad 0 \le \theta \le 2\pi$$

is the ellipse (traced counterclockwise) given by

$$\frac{(x-h)^2}{a^2} + \frac{(y-k)^2}{b^2} = 1.$$

The graph of the parametric equations

$$x = h + a\sin\theta \quad \text{and} \quad y = k + b\cos\theta, \quad 0 \le \theta \le 2\pi$$

is also the ellipse (traced clockwise) given by

$$\frac{(x-h)^2}{a^2} + \frac{(y-k)^2}{b^2} = 1.$$

In Examples 2 and 3, it is important to realize that eliminating the parameter is primarily an *aid to curve sketching*. When the parametric equations represent the path of a moving object, the graph alone is not sufficient to describe the motion of the object. You still need the parametric equations to tell you the *position, direction,* and *speed* at a given time.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Finding Parametric Equations

The first three examples in this section illustrate techniques for sketching the graph represented by a set of parametric equations. You will now investigate the reverse problem. How can you determine a set of parametric equations for a given graph or a given physical description? As indicated by the discussion following Example 1, such a representation is not unique. This is demonstrated further in the next example, which finds two different parametric representations for a given graph.

EXAMPLE 4 Finding Parametric Equations for a Given Graph

For each parameter, find a set of parametric equations that represents the graph of $y = 1 - x^2$.

a. $t = x$ **b.** The slope $m = dy/dx$ at the point (x, y)

Solution

a. Letting $x = t$ produces the parametric equations

$$x = t \quad \text{and} \quad y = 1 - x^2 = 1 - t^2.$$

b. To write x and y in terms of the parameter m, you can proceed as follows.

$$m = \frac{dy}{dx}$$

$$m = -2x \qquad \text{Differentiate } y = 1 - x^2.$$

$$x = -\frac{m}{2} \qquad \text{Solve for } x.$$

This produces a parametric equation for x. To obtain a parametric equation for y, substitute $-m/2$ for x in the original equation.

$$y = 1 - x^2 \qquad \text{Write original rectangular equation.}$$

$$y = 1 - \left(-\frac{m}{2}\right)^2 \qquad \text{Substitute } -m/2 \text{ for } x.$$

$$y = 1 - \frac{m^2}{4} \qquad \text{Simplify.}$$

So, the parametric equations are

$$x = -\frac{m}{2} \quad \text{and} \quad y = 1 - \frac{m^2}{4}.$$

In Figure 10.24, note that the resulting curve has a right-to-left orientation as determined by the increasing values of slope m. For part (a), the curve would have the opposite orientation. ■



Rectangular equation: $y = 1 - x^2$
Parametric equations:
$x = -\frac{m}{2}, y = 1 - \frac{m^2}{4}$

Figure 10.24

FOR FURTHER INFORMATION
To read about other methods for finding parametric equations, see the article "Finding Rational Parametric Curves of Relative Degree One or Two" by Dave Boyles in *The College Mathematics Journal.* To view this article, go to *MathArticles.com.*

TECHNOLOGY To be efficient at using a graphing utility, it is important that you develop skill in representing a graph by a set of parametric equations. The reason for this is that some graphing utilities have only three graphing modes—(1) functions, (2) parametric equations, and (3) polar equations. Some graphing utilities are not programmed to graph a general equation. For instance, to graph the hyperbola $x^2 - y^2 = 1$ in *function* mode, you need two equations

$$y = \sqrt{x^2 - 1} \quad \text{and} \quad y = -\sqrt{x^2 - 1}.$$

In *parametric* mode, you need *one* set of parametric equations, $x = \sec t$ and $y = \tan t$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

CYCLOIDS

Galileo first called attention to the cycloid, once recommending that it be used for the arches of bridges. Pascal once spent 8 days attempting to solve many of the problems of cycloids, such as finding the area under one arch and finding the volume of the solid of revolution formed by revolving the curve about a line. The cycloid has so many interesting properties and has caused so many quarrels among mathematicians that it has been called "the Helen of geometry" and "the apple of discord."

FOR FURTHER INFORMATION

For more information on cycloids, see the article "The Geometry of Rolling Curves" by John Bloom and Lee Whitt in *The American Mathematical Monthly*. To view this article, go to *MathArticles.com*.

EXAMPLE 5 Parametric Equations for a Cycloid

Determine the curve traced by a point P on the circumference of a circle of radius a rolling along a straight line in a plane. Such a curve is called a **cycloid.**

Solution Let the parameter θ be the measure of the circle's rotation, and let the point $P = (x, y)$ begin at the origin. When $\theta = 0$, P is at the origin. When $\theta = \pi$, P is at a maximum point $(\pi a, 2a)$. When $\theta = 2\pi$, P is back on the x-axis at $(2\pi a, 0)$. From Figure 10.25, you can determine that $\angle APC = 180° - \theta$. So,

$$\sin\theta = \sin(180° - \theta) = \sin(\angle APC) = \frac{AC}{a} = \frac{BD}{a}$$

and

$$\cos\theta = -\cos(180° - \theta) = -\cos(\angle APC) = \frac{AP}{-a}$$

which implies that $AP = -a\cos\theta$ and $BD = a\sin\theta$. Because the circle rolls along the x-axis, you can determine that $OD = \overset{\frown}{PD} = a\theta$. Furthermore, because $BA = DC = a$, you have

$$x = OD - BD = a\theta - a\sin\theta \quad \text{and} \quad y = BA + AP = a - a\cos\theta.$$

So, the parametric equations are

$$x = a(\theta - \sin\theta) \quad \text{and} \quad y = a(1 - \cos\theta).$$



Figure 10.25

TECHNOLOGY Some graphing utilities can simulate the motion of an object that is moving in the plane. If you have access to such a utility, use it to trace out the path of the cycloid shown in Figure 10.25.

The cycloid in Figure 10.25 has sharp corners called **cusps** at the values $x = 2n\pi a$. Notice that the derivatives $x'(\theta)$ and $y'(\theta)$ are both zero at the points for which $\theta = 2n\pi$.

$$x(\theta) = a(\theta - \sin\theta) \qquad y(\theta) = a(1 - \cos\theta)$$
$$x'(\theta) = a - a\cos\theta \qquad y'(\theta) = a\sin\theta$$
$$x'(2n\pi) = 0 \qquad y'(2n\pi) = 0$$

Between these points, the cycloid is called **smooth.**

Definition of a Smooth Curve

A curve C represented by $x = f(t)$ and $y = g(t)$ on an interval I is called **smooth** when f' and g' are continuous on I and not simultaneously 0, except possibly at the endpoints of I. The curve C is called **piecewise smooth** when it is smooth on each subinterval of some partition of I.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The time required to complete a full swing of the pendulum when starting from point C is approximately the same as the time required when starting from point A.
Figure 10.26

JAMES BERNOULLI (1654–1705)

James Bernoulli, also called Jacques, was the older brother of John. He was one of several accomplished mathematicians of the Swiss Bernoulli family. James's mathematical accomplishments have given him a prominent place in the early development of calculus. *See LarsonCalculus.com to read more of this biography.*

The Tautochrone and Brachistochrone Problems

The curve described in Example 5 is related to one of the most famous pairs of problems in the history of calculus. The first problem (called the **tautochrone problem**) began with Galileo's discovery that the time required to complete a full swing of a pendulum is *approximately* the same whether it makes a large movement at high speed or a small movement at lower speed (see Figure 10.26). Late in his life, Galileo realized that he could use this principle to construct a clock. However, he was not able to conquer the mechanics of actual construction. Christian Huygens (1629–1695) was the first to design and construct a working model. In his work with pendulums, Huygens realized that a pendulum does not take exactly the same time to complete swings of varying lengths. (This does not affect a pendulum clock, because the length of the circular arc is kept constant by giving the pendulum a slight boost each time it passes its lowest point.) But, in studying the problem, Huygens discovered that a ball rolling back and forth on an inverted cycloid does complete each cycle in exactly the same time.

The second problem, which was posed by John Bernoulli in 1696, is called the **brachistochrone problem**—in Greek, *brachys* means short and *chronos* means time. The problem was to determine the path down which a particle (such as a ball) will slide from point A to point B in the *shortest time*. Several mathematicians took up the challenge, and the following year the problem was solved by Newton, Leibniz, L'Hôpital, John Bernoulli, and James Bernoulli. As it turns out, the solution is not a straight line from A to B, but an inverted cycloid passing through the points A and B, as shown in Figure 10.27.



An inverted cycloid is the path down which a ball will roll in the shortest time.
Figure 10.27

The amazing part of the solution to the brachistochrone problem is that a particle starting at rest at *any* point C of the cycloid between A and B will take exactly the same time to reach B, as shown in Figure 10.28.



A ball starting at point C takes the same time to reach point B as one that starts at point A.
Figure 10.28

FOR FURTHER INFORMATION To see a proof of the famous brachistochrone problem, see the article "A New Minimization Proof for the Brachistochrone" by Gary Lawlor in *The American Mathematical Monthly*. To view this article, go to *MathArticles.com*.

GO DIGITAL

INTERFOTO/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

10.2 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. When describing the motion of an object, what information is given in a set of parametric equations that is not given in a rectangular equation?
2. Explain the process of sketching a plane curve given by parametric equations. What is meant by the orientation of the curve?
3. Explain how two sets of parametric equations can represent the same graph but different curves.
4. Consider the parametric equations

   $x = \sqrt{t-2}$ and $y = \frac{1}{2}t + 1, \quad t \geq 2.$

   What is implied about the domain of the resulting rectangular equation?

Using Parametric Equations **In Exercises 5–22, sketch the curve represented by the parametric equations (indicate the orientation of the curve), and write the corresponding rectangular equation by eliminating the parameter.**

5. $x = 2t - 3, \quad y = 3t + 1$
6. $x = 5 - 4t, \quad y = 2 + 5t$
7. $x = t + 1, \quad y = t^2$
8. $x = 2t^2, \quad y = t^4 + 1$
9. $x = t^3, \quad y = \dfrac{t^2}{2}$
10. $x = t^2 + t, \quad y = t^2 - t$
11. $x = \sqrt{t}, \quad y = t - 5$
12. $x = \sqrt[4]{t}, \quad y = 8 - t$
13. $x = t - 3, \quad y = \dfrac{t}{t-3}$
14. $x = 1 + \dfrac{1}{t}, \quad y = t - 1$
15. $x = 2t, \quad y = |t - 2|$
16. $x = |t - 1|, \quad y = t + 2$
17. $x = e^t, \quad y = e^{3t} + 1$
18. $x = e^{-t}, \quad y = e^{2t} - 1$
19. $x = 8\cos\theta, \quad y = 8\sin\theta$
20. $x = 3\cos\theta, \quad y = 7\sin\theta$
21. $x = \sec\theta, \quad y = \cos\theta, \quad 0 \leq \theta < \pi/2, \quad \pi/2 < \theta \leq \pi$
22. $x = \tan^2\theta, \quad y = \sec^2\theta$

Using Parametric Equations **In Exercises 23–34, use a graphing utility to graph the curve represented by the parametric equations (indicate the orientation of the curve). Eliminate the parameter and write the corresponding rectangular equation.**

23. $x = 6\sin 2\theta$, $y = 4\cos 2\theta$
24. $x = \cos\theta$, $y = 2\sin 2\theta$
25. $x = 4 + 2\cos\theta$, $y = -1 + \sin\theta$
26. $x = -2 + 3\cos\theta$, $y = -5 + 3\sin\theta$
27. $x = -3 + 4\cos\theta$, $y = 2 + 5\sin\theta$
28. $x = \sec\theta$, $y = \tan\theta$
29. $x = 4\sec\theta$, $y = 3\tan\theta$
30. $x = \cos^3\theta$, $y = \sin^3\theta$
31. $x = t^3, \quad y = 3\ln t$
32. $x = \ln 2t, \quad y = t^2$
33. $x = e^{-t}, \quad y = e^{3t}$
34. $x = e^{2t}, \quad y = e^t$

Comparing Plane Curves **In Exercises 35–38, determine any differences between the curves of the parametric equations. Are the graphs the same? Are the orientations the same? Are the curves smooth? Explain.**

35. (a) $x = t, y = t^2$ (b) $x = -t, y = t^2$
36. (a) $x = t + 1, y = t^3$ (b) $x = -t + 1, y = (-t)^3$
37. (a) $x = t$, $y = 2t + 1$ (b) $x = \cos\theta$, $y = 2\cos\theta + 1$
    (c) $x = e^{-t}$, $y = 2e^{-t} + 1$ (d) $x = e^t$, $y = 2e^t + 1$
38. (a) $x = 2\cos\theta$, $y = 2\sin\theta$ (b) $x = \sqrt{4t^2 - 1}/|t|$, $y = 1/t$
    (c) $x = \sqrt{t}$, $y = \sqrt{4 - t}$ (d) $x = -\sqrt{4 - e^{2t}}$, $y = e^t$

Eliminating a Parameter **In Exercises 39–42, eliminate the parameter and obtain the standard form of the rectangular equation.**

39. Line through (x_1, y_1) and (x_2, y_2):
    $x = x_1 + t(x_2 - x_1), \quad y = y_1 + t(y_2 - y_1)$
40. Circle: $x = h + r\cos\theta, \quad y = k + r\sin\theta$
41. Ellipse: $x = h + a\cos\theta, \quad y = k + b\sin\theta$
42. Hyperbola: $x = h + a\sec\theta, \quad y = k + b\tan\theta$

Writing a Set of Parametric Equations **In Exercises 43–50, use the results of Exercises 39–42 to find a set of parametric equations for the line or conic.**

43. Line: passes through $(0, 0)$ and $(4, -7)$
44. Line: passes through $(-3, 1)$ and $(1, 9)$
45. Circle: center: $(1, 1)$; radius: 2
46. Circle: center: $\left(-\frac{1}{2}, -4\right)$; radius: $\frac{1}{2}$
47. Ellipse: vertices: $(-3, 0), (7, 0)$; foci: $(-1, 0), (5, 0)$
48. Ellipse: vertices: $(-1, 8), (-1, -12)$; foci: $(-1, 4), (-1, -8)$
49. Hyperbola: vertices: $(0, \pm 1)$; foci: $\left(0, \pm\sqrt{5}\right)$
50. Hyperbola: vertices: $(-2, 1), (0, 1)$; foci: $(-3, 1), (1, 1)$

Finding Parametric Equations **In Exercises 51–54, find two different sets of parametric equations for the rectangular equation.**

51. $y = 6x - 5$
52. $y = 4/(x - 1)$
53. $y = x^3$
54. $y = x^2$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding Parametric Equations **In Exercises 55–58, find a set of parametric equations for the rectangular equation that satisfies the given condition.**

55. $y = 2x - 5$, $t = 0$ at the point $(3, 1)$

56. $y = 4x + 1$, $t = -1$ at the point $(-2, -7)$

57. $y = x^2$, $t = 4$ at the point $(4, 16)$

58. $y = 4 - x^2$, $t = 1$ at the point $(1, 3)$

Graphing a Plane Curve **In Exercises 59–66, use a graphing utility to graph the curve represented by the parametric equations. Indicate the orientation of the curve. Identify any points at which the curve is not smooth.**

59. Cycloid: $x = 2(\theta - \sin\theta)$, $y = 2(1 - \cos\theta)$

60. Cycloid: $x = \theta + \sin\theta$, $y = 1 - \cos\theta$

61. Prolate cycloid: $x = \theta - \frac{3}{2}\sin\theta$, $y = 1 - \frac{3}{2}\cos\theta$

62. Prolate cycloid: $x = 2\theta - 4\sin\theta$, $y = 2 - 4\cos\theta$

63. Hypocycloid: $x = 3\cos^3\theta$, $y = 3\sin^3\theta$

64. Curtate cycloid: $x = 2\theta - \sin\theta$, $y = 2 - \cos\theta$

65. Witch of Agnesi: $x = 2\cot\theta$, $y = 2\sin^2\theta$

66. Folium of Descartes: $x = 3t/(1 + t^3)$, $y = 3t^2/(1 + t^3)$

Exploring Concepts

67. Describe the orientation of the parametric equations $x = t^2$ and $y = t^4$ for $-1 \le t \le 1$.

68. Make a conjecture about the change in the graph of parametric equations when the sign of the parameter is changed. Explain your reasoning using examples to support your conjecture.

69. The following sets of parametric equations have the same graph. Does this contradict your conjecture from Exercise 68? Explain.

$x = \cos\theta$, $y = \sin^2\theta$, $0 < \theta < \pi$

$x = \cos(-\theta)$, $y = \sin^2(-\theta)$, $0 < \theta < \pi$

70. **HOW DO YOU SEE IT?** Which set of parametric equations is shown in the graph below? Explain your reasoning.

(a) $x = t$, $y = t^2$ (b) $x = t^2$, $y = t$



Matching **In Exercises 71–74, match the set of parametric equations with its graph. [The graphs are labeled (a), (b), (c), and (d).] Explain your reasoning.**

(a)



(b)



(c)



(d)



71. Lissajous curve: $x = 4\cos\theta$, $y = 2\sin 2\theta$

72. Evolute of ellipse: $x = \cos^3\theta$, $y = 2\sin^3\theta$

73. Involute of circle: $x = \cos\theta + \theta\sin\theta$, $y = \sin\theta - \theta\cos\theta$

74. Serpentine curve: $x = \cot\theta$, $y = 4\sin\theta\cos\theta$

75. **Curtate Cycloid** A wheel of radius a rolls along a line without slipping. The curve traced by a point P that is b units from the center ($b < a$) is called a **curtate cycloid** (see figure). Use the angle θ to find a set of parametric equations for this curve.



Figure for 75



Figure for 76

76. **Epicycloid** A circle of radius 1 rolls around the outside of a circle of radius 2 without slipping. The curve traced by a point on the circumference of the smaller circle is called an **epicycloid** (see figure). Use the angle θ to find a set of parametric equations for this curve.

True or False? **In Exercises 77–79, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

77. The graph of the parametric equations $x = t^2$ and $y = t^2$ is the line $y = x$.

78. If y is a function of t and x is a function of t, then y is a function of x.

79. The curve represented by the parametric equations $x = t$ and $y = \cos t$ can be written as an equation of the form $y = f(x)$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

80. Translation of a Plane Curve Consider the parametric equations $x = 8\cos t$ and $y = 8\sin t$.

(a) Describe the curve represented by the parametric equations.

(b) How does the curve represented by the parametric equations

$x = 8\cos t + 3$ and $y = 8\sin t + 6$

compare to the curve described in part (a)?

(c) How does the original curve change when cosine and sine are interchanged?

Projectile Motion **In Exercises 81 and 82, consider a projectile launched at a height h feet above the ground and at an angle θ with the horizontal. When the initial velocity is v_0 feet per second, the path of the projectile is modeled by the parametric equations**

$$x = (v_0 \cos\theta)t$$

and

$$y = h + (v_0 \sin\theta)t - 16t^2.$$

81. Baseball

The center field fence in a ballpark is 10 feet high and 400 feet from home plate. The ball is hit 3 feet above the ground. It leaves the bat at an angle of θ degrees with the horizontal at a speed of 100 miles per hour.

Randy Faris/Getty Images

(a) Write a set of parametric equations for the path of the ball.

(b) Use a graphing utility to graph the path of the ball when $\theta = 15°$. Is the hit a home run?

(c) Use a graphing utility to graph the path of the ball when $\theta = 23°$. Is the hit a home run?

(d) Find the minimum angle at which the ball must leave the bat for the hit to be a home run.

82. A rectangular equation for the path of a projectile is $y = 5 + x - 0.005x^2$.

(a) Eliminate the parameter t from the position function for the motion of a projectile to show that the rectangular equation is

$$y = -\frac{16\sec^2\theta}{v_0^2}x^2 + (\tan\theta)x + h.$$

(b) Use the result of part (a) to find h, v_0, and θ. Find the parametric equations of the path.

(c) Use a graphing utility to graph the rectangular equation for the path of the projectile. Confirm your answer in part (b) by sketching the curve represented by the parametric equations.

(d) Use a graphing utility to approximate the maximum height of the projectile and its range.

SECTION PROJECT

Cycloids

In Greek, the word *cycloid* means *wheel*, the word *hypocycloid* means *under the wheel,* and the word *epicycloid* means *upon the wheel.* Match the hypocycloid or epicycloid with its graph. [The graphs are labeled (a), (b), (c), (d), (e), and (f).]

Hypocycloid, H(A, B)

The path traced by a fixed point on a circle of radius B as it rolls around the *inside* of a circle of radius A

$$x = (A - B)\cos t + B\cos\left(\frac{A - B}{B}\right)t$$

$$y = (A - B)\sin t - B\sin\left(\frac{A - B}{B}\right)t$$

Epicycloid, E(A, B)

The path traced by a fixed point on a circle of radius B as it rolls around the *outside* of a circle of radius A

$$x = (A + B)\cos t - B\cos\left(\frac{A + B}{B}\right)t$$

$$y = (A + B)\sin t - B\sin\left(\frac{A + B}{B}\right)t$$

I. $H(8, 3)$ II. $E(8, 3)$ III. $H(8, 7)$

IV. $E(24, 3)$ V. $H(24, 7)$ VI. $E(24, 7)$

(a)



(b)



(c)



(d)



(e)



(f)



Exercises based on "Mathematical Discovery via Computer Graphics: Hypocycloids and Epicycloids" by Florence S. Gordon and Sheldon P. Gordon, *College Mathematics Journal,* November 1984, p. 441. Used by permission of the authors.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

10.3 Parametric Equations and Calculus

GO DIGITAL

- **Find the slope of a tangent line to a curve given by a set of parametric equations.**
- **Find the arc length of a curve given by a set of parametric equations.**
- **Find the area of a surface of revolution (parametric form).**



At time t, the angle of elevation of the projectile is θ.
Figure 10.29

Slope and Tangent Lines

Now that you can represent a graph in the plane by a set of parametric equations, it is natural to ask how to use calculus to study plane curves. Consider the projectile represented by the parametric equations

$$x = 24\sqrt{2}t \quad \text{and} \quad y = -16t^2 + 24\sqrt{2}t$$

as shown in Figure 10.29. From the discussion at the beginning of Section 10.2, you know that these equations enable you to locate the position of the projectile at a given time. You also know that the object is initially projected at an angle of 45°, or a slope of $m = \tan 45° = 1$. But how can you find the slope at some other time t? The next theorem answers this question by giving a formula for the slope of the tangent line as a function of t.

THEOREM 10.7 Parametric Form of the Derivative

If a smooth curve C is given by the equations

$$x = f(t) \quad \text{and} \quad y = g(t)$$

then the slope of C at (x, y) is

$$\frac{dy}{dx} = \frac{dy/dt}{dx/dt}, \quad \frac{dx}{dt} \neq 0.$$



The slope of the secant line through the points $(f(t), g(t))$ and $(f(t + \Delta t), g(t + \Delta t))$ is $\Delta y/\Delta x$.
Figure 10.30

Proof In Figure 10.30, consider $\Delta t > 0$ and let

$$\Delta y = g(t + \Delta t) - g(t) \quad \text{and} \quad \Delta x = f(t + \Delta t) - f(t).$$

Because $\Delta x \to 0$ as $\Delta t \to 0$, you can write

$$\frac{dy}{dx} = \lim_{\Delta x \to 0} \frac{\Delta y}{\Delta x}$$ Definition of derivative

$$= \lim_{\Delta t \to 0} \frac{g(t + \Delta t) - g(t)}{f(t + \Delta t) - f(t)}.$$ Substitute for Δy and Δx.

Dividing both the numerator and denominator by Δt, you can use the differentiability of f and g to conclude that

$$\frac{dy}{dx} = \lim_{\Delta t \to 0} \frac{[g(t + \Delta t) - g(t)]/\Delta t}{[f(t + \Delta t) - f(t)]/\Delta t}$$ Divide numerator and denominator by Δt.

$$= \frac{\lim_{\Delta t \to 0} \dfrac{g(t + \Delta t) - g(t)}{\Delta t}}{\lim_{\Delta t \to 0} \dfrac{f(t + \Delta t) - f(t)}{\Delta t}}$$ The limit of a quotient is equal to the quotient of the limits.

$$= \frac{g'(t)}{f'(t)}$$ Definition of derivative

$$= \frac{dy/dt}{dx/dt}.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploration

The curve traced out in Example 1 is a circle. Use the formula

$$\frac{dy}{dx} = -\tan t$$

to find the slopes at the points $(1, 0)$ and $(0, 1)$.

GO DIGITAL

EXAMPLE 1 Differentiation and Parametric Form

Find dy/dx for the curve given by $x = \sin t$ and $y = \cos t$.

Solution Note that $dx/dt = \cos t$ and $dy/dt = -\sin t$.

$$\frac{dy}{dx} = \frac{dy/dt}{dx/dt} \qquad \text{Apply Theorem 10.7.}$$

$$= \frac{-\sin t}{\cos t}$$

$$= -\tan t$$

Because dy/dx is a function of t, you can use Theorem 10.7 repeatedly to find *higher-order* derivatives. For example, the second and third derivatives are shown below.

$$\frac{d^2y}{dx^2} = \frac{d}{dx}\left[\frac{dy}{dx}\right] = \frac{\frac{d}{dt}\left[\frac{dy}{dx}\right]}{dx/dt} \qquad \text{Second derivative}$$

$$\frac{d^3y}{dx^3} = \frac{d}{dx}\left[\frac{d^2y}{dx^2}\right] = \frac{\frac{d}{dt}\left[\frac{d^2y}{dx^2}\right]}{dx/dt} \qquad \text{Third derivative}$$

EXAMPLE 2 Finding Slope and Concavity

For the curve given by

$$x = \sqrt{t} \quad \text{and} \quad y = \frac{1}{4}(t^2 - 4), \quad t \geq 0$$

find the slope and concavity at the point $(2, 3)$.

Solution The first derivative is

$$\frac{dy}{dx} = \frac{dy/dt}{dx/dt} = \frac{(1/2)t}{(1/2)t^{-1/2}} = t^{3/2}. \qquad \text{Parametric form of first derivative}$$

So, the second derivative is

$$\frac{d^2y}{dx^2} = \frac{\frac{d}{dt}\left[\frac{dy}{dx}\right]}{dx/dt} = \frac{\frac{d}{dt}[t^{3/2}]}{dx/dt} = \frac{(3/2)t^{1/2}}{(1/2)t^{-1/2}} = 3t. \qquad \text{Parametric form of second derivative}$$

At $(x, y) = (2, 3)$, it follows that $t = 4$, and the slope is

$$\frac{dy}{dx} = (4)^{3/2} = 8.$$

Moreover, when $t = 4$, the second derivative is

$$\frac{d^2y}{dx^2} = 3(4) = 12 > 0$$

and you can conclude that the graph is concave upward at $(2, 3)$, as shown in Figure 10.31.



The graph is concave upward at $(2, 3)$ when $t = 4$.

Figure 10.31

Because the parametric equations $x = f(t)$ and $y = g(t)$ need not define y as a function of x, it is possible for a plane curve to loop around and cross itself. At such points, the curve may have more than one tangent line, as shown in the next example.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



This prolate cycloid has two tangent lines at the point $(0, 2)$.
Figure 10.32

EXAMPLE 3 A Curve with Two Tangent Lines at a Point

See LarsonCalculus.com for an interactive version of this type of example.

The **prolate cycloid** given by

$$x = 2t - \pi \sin t \quad \text{and} \quad y = 2 - \pi \cos t$$

crosses itself at the point $(0, 2)$, as shown in Figure 10.32. Find the equations of both tangent lines at this point.

Solution Because $x = 0$ and $y = 2$ when $t = \pm\pi/2$, and

$$\frac{dy}{dx} = \frac{dy/dt}{dx/dt} = \frac{\pi \sin t}{2 - \pi \cos t}$$

you have $dy/dx = -\pi/2$ when $t = -\pi/2$ and $dy/dx = \pi/2$ when $t = \pi/2$. So, the two tangent lines at $(0, 2)$ are

$$y - 2 = -\frac{\pi}{2}x \qquad \text{Tangent line when } t = -\frac{\pi}{2}$$

and

$$y - 2 = \frac{\pi}{2}x. \qquad \text{Tangent line when } t = \frac{\pi}{2}$$

If $dy/dt = 0$ and $dx/dt \neq 0$ when $t = t_0$, then the curve represented by $x = f(t)$ and $y = g(t)$ has a horizontal tangent at $(f(t_0), g(t_0))$. For instance, in Example 3, the given curve has a horizontal tangent at the point $(0, 2 - \pi)$ (when $t = 0$). Similarly, if $dx/dt = 0$ and $dy/dt \neq 0$ when $t = t_0$, then the curve represented by $x = f(t)$ and $y = g(t)$ has a vertical tangent at $(f(t_0), g(t_0))$. If dy/dt and dx/dt are *simultaneously* 0, then no conclusion can be drawn about tangent lines.

Arc Length

You have seen how parametric equations can be used to describe the path of a particle moving in the plane. You will now develop a formula for determining the *distance* traveled by the particle along its path.

Recall from Section 7.4 that the formula for the arc length of a curve C given by $y = h(x)$ over the interval $[x_0, x_1]$ is

$$s = \int_{x_0}^{x_1} \sqrt{1 + [h'(x)]^2}\, dx \qquad \text{Formula for arc length}$$
$$= \int_{x_0}^{x_1} \sqrt{1 + \left(\frac{dy}{dx}\right)^2}\, dx.$$

If C is represented by the parametric equations $x = f(t)$ and $y = g(t)$, $a \le t \le b$, and if $dx/dt = f'(t) > 0$, then

$$s = \int_{x_0}^{x_1} \sqrt{1 + \left(\frac{dy}{dx}\right)^2}\, dx$$
$$= \int_{x_0}^{x_1} \sqrt{1 + \left(\frac{dy/dt}{dx/dt}\right)^2}\, dx$$
$$= \int_{a}^{b} \sqrt{\frac{(dx/dt)^2 + (dy/dt)^2}{(dx/dt)^2}}\, \frac{dx}{dt}\, dt$$
$$= \int_{a}^{b} \sqrt{\left(\frac{dx}{dt}\right)^2 + \left(\frac{dy}{dt}\right)^2}\, dt$$
$$= \int_{a}^{b} \sqrt{[f'(t)]^2 + [g'(t)]^2}\, dt.$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

THEOREM 10.8 Arc Length in Parametric Form

If a smooth curve C is given by $x = f(t)$ and $y = g(t)$ such that C does not intersect itself on the interval $a \le t \le b$ (except possibly at the endpoints), then the arc length of C over the interval is given by

$$s = \int_a^b \sqrt{\left(\frac{dx}{dt}\right)^2 + \left(\frac{dy}{dt}\right)^2}\, dt = \int_a^b \sqrt{[f'(t)]^2 + [g'(t)]^2}\, dt.$$

REMARK When applying the arc length formula to a curve, be sure that the curve is traced out only once on the interval of integration. For instance, the circle given by $x = \cos t$ and $y = \sin t$ is traced out once on the interval $0 \le t \le 2\pi$ but is traced out twice on the interval $0 \le t \le 4\pi$.

In the preceding section, you learned that if a circle rolls along a line, then a point on its circumference will trace a path called a cycloid. If the circle rolls around the circumference of another circle, then the path of the point is an **epicycloid.** The next example shows how to find the arc length of an epicycloid.

ARCH OF A CYCLOID

The arc length of an arch of a cycloid was first calculated in 1658 by British architect and mathematician Christopher Wren, famous for rebuilding many buildings and churches in London, including St. Paul's Cathedral.

EXAMPLE 4 Finding Arc Length

A circle of radius 1 inch rolls around the circumference of a larger circle of radius 4 inches, as shown in Figure 10.33. The epicycloid traced by a point on the circumference of the smaller circle is given by

$$x = 5\cos t - \cos 5t \quad \text{and} \quad y = 5\sin t - \sin 5t.$$

Find the distance traveled by the point in one complete trip about the larger circle.

Solution Before applying Theorem 10.8, note in Figure 10.33 that the curve has sharp points when $t = 0$ and $t = \pi/2$. Between these two points, dx/dt and dy/dt are not simultaneously 0. So, the portion of the curve generated from $t = 0$ to $t = \pi/2$ is smooth. To find the total distance traveled by the point, you can find the arc length of that portion lying in the first quadrant and multiply by 4.

$$\begin{aligned}
s &= 4\int_0^{\pi/2} \sqrt{\left(\frac{dx}{dt}\right)^2 + \left(\frac{dy}{dt}\right)^2}\, dt && \text{Parametric form for arc length}\\
&= 4\int_0^{\pi/2} \sqrt{(-5\sin t + 5\sin 5t)^2 + (5\cos t - 5\cos 5t)^2}\, dt\\
&= 20\int_0^{\pi/2} \sqrt{2 - 2\sin t \sin 5t - 2\cos t \cos 5t}\, dt\\
&= 20\int_0^{\pi/2} \sqrt{2 - 2\cos 4t}\, dt && \text{Difference formula for cosine}\\
&= 20\int_0^{\pi/2} \sqrt{4\sin^2 2t}\, dt && \text{Double-angle formula}\\
&= 40\int_0^{\pi/2} \sin 2t\, dt\\
&= -20\Big[\cos 2t\Big]_0^{\pi/2}\\
&= 40 \text{ inches}
\end{aligned}$$

For the epicycloid shown in Figure 10.33, an arc length of 40 inches seems about right because the circumference of a circle of radius 6 inches is

$$2\pi r = 12\pi \approx 37.7 \text{ inches.}$$



An epicycloid is traced by a point on the smaller circle as it rolls around the larger circle.

Figure 10.33

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Area of a Surface of Revolution

You can use the formula for the area of a surface of revolution in rectangular form to develop a formula for surface area in parametric form.

THEOREM 10.9 Area of a Surface of Revolution

If a smooth curve C given by $x = f(t)$ and $y = g(t)$ does not cross itself on an interval $a \le t \le b$, then the area S of the surface of revolution formed by revolving C about the coordinate axes is given by the following.

1. $S = 2\pi \int_a^b g(t) \sqrt{\left(\frac{dx}{dt}\right)^2 + \left(\frac{dy}{dt}\right)^2}\, dt$ Revolution about the x-axis: $g(t) \ge 0$

2. $S = 2\pi \int_a^b f(t) \sqrt{\left(\frac{dx}{dt}\right)^2 + \left(\frac{dy}{dt}\right)^2}\, dt$ Revolution about the y-axis: $f(t) \ge 0$

These formulas may be easier to remember if you think of the differential of arc length as

$$ds = \sqrt{\left(\frac{dx}{dt}\right)^2 + \left(\frac{dy}{dt}\right)^2}\, dt.$$ Differential of arc length

Then the formulas in Theorem 10.9 can be written as follows.

1. $S = 2\pi \int_a^b g(t)\, ds$ **2.** $S = 2\pi \int_a^b f(t)\, ds$

EXAMPLE 5 Finding the Area of a Surface of Revolution

Let C be the arc of the circle $x^2 + y^2 = 9$ from $(3, 0)$ to

$$\left(\frac{3}{2}, \frac{3\sqrt{3}}{2}\right)$$

as shown in Figure 10.34. Find the area of the surface formed by revolving C about the x-axis.



The surface of revolution has a surface area of 9π.
Figure 10.34

Solution You can represent C parametrically by the equations

$$x = 3\cos t \quad \text{and} \quad y = 3\sin t, \quad 0 \le t \le \pi/3.$$

(Note that you can determine the interval for t by observing that $t = 0$ when $x = 3$ and $t = \pi/3$ when $x = 3/2$.) On this interval, C is smooth and y is nonnegative, and you can apply Theorem 10.9 to obtain a surface area of

$$\begin{aligned}
S &= 2\pi \int_0^{\pi/3} (3\sin t)\sqrt{(-3\sin t)^2 + (3\cos t)^2}\, dt && \text{Apply formula for area of a surface of revolution.}\\
&= 6\pi \int_0^{\pi/3} \sin t \sqrt{9(\sin^2 t + \cos^2 t)}\, dt \\
&= 6\pi \int_0^{\pi/3} 3\sin t\, dt && \text{Trigonometric identity}\\
&= -18\pi \Big[\cos t\Big]_0^{\pi/3} \\
&= -18\pi\left(\frac{1}{2} - 1\right) \\
&= 9\pi.
\end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

10.3 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain what the parametric form of the derivative represents.
2. Under what circumstances can a graph that represents a set of parametric equations have more than one tangent line at a given point?
3. Consider a curve represented by the parametric equations $x = f(t)$ and $y = g(t)$. When does the graph have horizontal tangent lines? Vertical tangent lines?
4. Why does the arc length formula require that the curve not intersect itself on an interval, except possibly at the endpoints?

Finding a Derivative

In Exercises 5–8, find dy/dx.

5. $x = t^2, \quad y = 7 - 6t$
6. $x = \sqrt[3]{t}, \quad y = 4 - t$
7. $x = \sin^2\theta, \quad y = \cos^2\theta$
8. $x = 2e^{\theta}, \quad y = e^{-\theta/2}$

Finding Slope and Concavity

In Exercises 9–18, find dy/dx and d^2y/dx^2, and find the slope and concavity (if possible) at the given value of the parameter.

Parametric Equations	Parameter
9. $x = 4t, \quad y = 3t - 2$	$t = 3$
10. $x = \sqrt{t}, \quad y = 3t - 1$	$t = 1$
11. $x = t + 1, \quad y = t^2 + 3t$	$t = -2$
12. $x = t^2 + 5t + 4, \quad y = 4t$	$t = 0$
13. $x = 4\cos\theta, \quad y = 4\sin\theta$	$\theta = \frac{\pi}{4}$
14. $x = \cos\theta, \quad y = 3\sin\theta$	$\theta = 0$
15. $x = 2 + \sec\theta, \quad y = 1 + 2\tan\theta$	$\theta = -\frac{\pi}{3}$
16. $x = \sqrt{t}, \quad y = \sqrt{t-1}$	$t = 5$
17. $x = \cos^3\theta, \quad y = \sin^3\theta$	$\theta = \frac{\pi}{4}$
18. $x = \theta - \sin\theta, \quad y = 1 - \cos\theta$	$\theta = \pi$

Finding Equations of Tangent Lines

In Exercises 19–22, find an equation of the tangent line to the curve at each given point.

19. $x = 2\cot\theta, \quad y = 2\sin^2\theta, \quad \left(-\frac{2}{\sqrt{3}}, \frac{3}{2}\right), (0, 2), \left(2\sqrt{3}, \frac{1}{2}\right)$
20. $x = 2 - 3\cos\theta, \quad y = 3 + 2\sin\theta,$
$(-1, 3), (2, 5), \left(\frac{4 + 3\sqrt{3}}{2}, 2\right)$
21. $x = t^2 - 4, \quad y = t^2 - 2t, \quad (0, 0), (-3, -1), (-3, 3)$
22. $x = t^4 + 2, \quad y = t^3 + t, \quad (2, 0), (3, -2), (18, 10)$

Finding an Equation of a Tangent Line

In Exercises 23–26, (a) use a graphing utility to graph the curve represented by the parametric equations, (b) use a graphing utility to find dx/dt, dy/dt, and dy/dx at the given value of the parameter, (c) find an equation of the tangent line to the curve at the given value of the parameter, and (d) use a graphing utility to graph the curve and the tangent line from part (c).

Parametric Equations	Parameter
23. $x = 6t, \quad y = 1 - 4t^2$	$t = -\frac{1}{2}$
24. $x = t - 2, \quad y = \frac{1}{t} + 3$	$t = 1$
25. $x = t^2 - t + 2, \quad y = t^3 - 3t$	$t = -1$
26. $x = 3t - t^2, \quad y = 2t^{3/2}$	$t = \frac{1}{4}$

Finding Equations of Tangent Lines

In Exercises 27–30, find the equations of the tangent lines at the point where the curve crosses itself.

27. $x = 2\sin 2t, \quad y = 3\sin t$
28. $x = 2 - \pi\cos t, \quad y = 2t - \pi\sin t$
29. $x = t^2 - t, \quad y = t^3 - 3t - 1$
30. $x = t^3 - 6t, \quad y = t^2$

Horizontal and Vertical Tangency

In Exercises 31 and 32, find all points (if any) of horizontal and vertical tangency to the curve on the given interval.

31. $x = \cos\theta + \theta\sin\theta$
$y = \sin\theta - \theta\cos\theta$
$-2\pi \le \theta \le 2\pi$



32. $x = 2\theta$
$y = 2(1 - \cos\theta)$
$0 \le \theta \le 2\pi$



Horizontal and Vertical Tangency

In Exercises 33–42, find all points (if any) of horizontal and vertical tangency to the curve. Use a graphing utility to confirm your results.

33. $x = 9 - t, \quad y = -t^2$
34. $x = t + 1, \quad y = t^2 + 3t$
35. $x = t + 4, \quad y = t^3 - 12t + 6$
36. $x = t^2 - t + 2, \quad y = t^3 - 3t$
37. $x = 7\cos\theta, \quad y = 7\sin\theta$
38. $x = \cos\theta, \quad y = 2\sin 2\theta$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

39. $x = 5 + 3\cos\theta, \quad y = -2 + \sin\theta$

40. $x = \sec\theta, \quad y = \tan\theta$

41. $x = 4\cos^2\theta, \quad y = 2\sin\theta$ **42.** $x = \cos^2\theta, \quad y = \cos\theta$

Determining Concavity **In Exercises 43–48, determine the open t-intervals on which the curve is concave downward or concave upward.**

43. $x = 3t^2, \quad y = t^3 - t$ **44.** $x = 2 + t^2, \quad y = t^2 + t^3$

45. $x = 2t + \ln t, \quad y = 2t - \ln t$

46. $x = t^2, \quad y = \ln t$

47. $x = \sin t, \quad y = \cos t, \quad 0 < t < \pi$

48. $x = 4\cos t, \quad y = 2\sin t, \quad 0 < t < 2\pi$

Arc Length **In Exercises 49–54, find the arc length of the curve on the given interval.**

Parametric Equations	Interval
49. $x = 3t + 5, \quad y = 7 - 2t$	$-1 \le t \le 3$
50. $x = 6t^2, \quad y = 2t^3$	$1 \le t \le 4$
51. $x = e^{-t}\cos t, \quad y = e^{-t}\sin t$	$0 \le t \le \frac{\pi}{2}$
52. $x = \arcsin t, \quad y = \ln\sqrt{1 - t^2}$	$0 \le t \le \frac{1}{2}$
53. $x = \sqrt{t}, \quad y = 3t - 1$	$0 \le t \le 1$
54. $x = t, \quad y = \frac{t^5}{10} + \frac{1}{6t^3}$	$1 \le t \le 2$

Arc Length **In Exercises 55–58, find the arc length of the curve on the interval $[0, 2\pi]$.**

55. Hypocycloid perimeter: $x = a\cos^3\theta, y = a\sin^3\theta$

56. Involute of a circle: $x = \cos\theta + \theta\sin\theta$
$y = \sin\theta - \theta\cos\theta$

57. Cycloid arch: $x = a(\theta - \sin\theta), y = a(1 - \cos\theta)$

58. Nephroid perimeter: $x = a(3\cos t - \cos 3t)$
$y = a(3\sin t - \sin 3t)$

59. Path of a Projectile The path of a projectile is modeled by the parametric equations

$$x = (90\cos 30°)t \quad \text{and} \quad y = (90\sin 30°)t - 16t^2$$

where x and y are measured in feet.

(a) Use a graphing utility to graph the path of the projectile.

(b) Use a graphing utility to approximate the range of the projectile.

(c) Use the integration capabilities of a graphing utility to approximate the arc length of the path. Compare this result with the range of the projectile.

60. Path of a Projectile When the projectile in Exercise 59 is launched at an angle θ with the horizontal, its parametric equations are $x = (90\cos\theta)t$ and $y = (90\sin\theta)t - 16t^2$. Find the angle that maximizes the range of the projectile. Use a graphing utility to find the angle that maximizes the arc length of the trajectory.

61. Folium of Descartes Consider the parametric equations

$$x = \frac{4t}{1 + t^3} \quad \text{and} \quad y = \frac{4t^2}{1 + t^3}.$$

(a) Use a graphing utility to graph the curve represented by the parametric equations.

(b) Use a graphing utility to find the points of horizontal tangency to the curve.

(c) Use the integration capabilities of a graphing utility to approximate the arc length of the closed loop. (*Hint:* Use symmetry and integrate over the interval $0 \le t \le 1$.)

62. Witch of Agnesi Consider the parametric equations

$$x = 4\cot\theta \quad \text{and} \quad y = 4\sin^2\theta, \quad -\frac{\pi}{2} \le \theta \le \frac{\pi}{2}.$$

(a) Use a graphing utility to graph the curve represented by the parametric equations.

(b) Use a graphing utility to find the points of horizontal tangency to the curve.

(c) Use the integration capabilities of a graphing utility to approximate the arc length over the interval $\pi/4 \le \theta \le \pi/2$.

Surface Area **In Exercises 63–68, find the area of the surface generated by revolving the curve about each given axis.**

63. $x = 2t, \quad y = 3t, \quad 0 \le t \le 3$

(a) x-axis

(b) y-axis

64. $x = t, \quad y = 4 - 2t, \quad 0 \le t \le 2$

(a) x-axis

(b) y-axis

65. $x = 5\cos\theta, \quad y = 5\sin\theta, \quad 0 \le \theta \le \frac{\pi}{2}$, y-axis

66. $x = \frac{1}{3}t^3, \quad y = t + 1, \quad 1 \le t \le 2$, y-axis

67. $x = a\cos^3\theta, \quad y = a\sin^3\theta, \quad 0 \le \theta \le \pi$, x-axis

68. $x = a\cos\theta, \quad y = b\sin\theta, \quad 0 \le \theta \le 2\pi$

(a) x-axis

(b) y-axis

Surface Area **In Exercises 69–72, write an integral that represents the area of the surface generated by revolving the curve about the x-axis. Use a graphing utility to approximate the integral.**

Parametric Equations	Interval
69. $x = t^3, \quad y = t + 2$	$0 \le t \le 2$
70. $x = t^2, \quad y = \sqrt{t}$	$1 \le t \le 3$
71. $x = \cos^2\theta, \quad y = \cos\theta$	$0 \le \theta \le \frac{\pi}{2}$
72. $x = \theta + \sin\theta, \quad y = \theta + \cos\theta$	$0 \le \theta \le \frac{\pi}{2}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploring Concepts

73. (a) Use a graphing utility to graph each set of parametric equations.

$x = t - \sin t, \quad y = 1 - \cos t, \quad 0 \le t \le 2\pi$

$x = 2t - \sin(2t), \quad y = 1 - \cos(2t), \quad 0 \le t \le \pi$

(b) Compare the graphs of the two sets of parametric equations in part (a). When the curve represents the motion of a particle and t is time, what can you infer about the average speeds of the particle on the paths represented by the two sets of parametric equations?

(c) Without graphing the curve, determine the time required for a particle to traverse the same path as in parts (a) and (b) when the path is modeled by

$x = \frac{1}{2}t - \sin\left(\frac{1}{2}t\right)$ and $y = 1 - \cos\left(\frac{1}{2}t\right)$.

74. (a) Each set of parametric equations represents the motion of a particle. Use a graphing utility to graph each set.

First Particle: $x = 3\cos t, \ y = 4\sin t, \ 0 \le t \le 2\pi$

Second Particle: $x = 4\sin t, \ y = 3\cos t, \ 0 \le t \le 2\pi$

(b) Determine the number of points of intersection.

(c) Will the particles ever be at the same place at the same time? If so, identify the point(s).

75. Find a set of parametric equations $x = f(t)$ and $y = g(t)$ such that $dx/dt < 0$ and $dy/dt < 0$ for all real numbers t. Then sketch a graph of the curve.

76. HOW DO YOU SEE IT? Using the graph of f, (a) determine whether dy/dt is positive or negative given that dx/dt is negative and (b) determine whether dx/dt is positive or negative given that dy/dt is positive. Explain your reasoning.

(i)



(ii)



77. Integration by Substitution Use integration by substitution to show that if y is a continuous function of x on the interval $a \le x \le b$, where $x = f(t)$ and $y = g(t)$, then

$$\int_a^b y\,dx = \int_{t_1}^{t_2} g(t)f'(t)\,dt$$

where $f(t_1) = a$, $f(t_2) = b$, and both g and f' are continuous on $[t_1, t_2]$.

78. Surface Area A portion of a sphere of radius r is removed by cutting out a circular cone with its vertex at the center of the sphere. The vertex of the cone forms an angle of 2θ. Find the surface area removed from the sphere.

Area **In Exercises 79 and 80, find the area of the region. (Use the result of Exercise 77.)**

79. $x = 2\sin^2\theta$

$y = 2\sin^2\theta\tan\theta$

$0 \le \theta < \frac{\pi}{2}$



80. $x = 2\cot\theta$

$y = 2\sin^2\theta$

$0 < \theta < \pi$



Areas of Simple Closed Curves **In Exercises 81–86, use a computer algebra system and the result of Exercise 77 to match the closed curve with its area. (These exercises were based on "The Surveyor's Area Formula" by Bart Braden, *College Mathematics Journal*, September 1986, pp. 335–337, by permission of the author.)**

(a) $\frac{8}{3}ab$ **(b)** $\frac{3}{8}\pi a^2$

(c) $2\pi a^2$ **(d)** πab

(e) $2\pi ab$ **(f)** $6\pi a^2$

81. Ellipse: $(0 \le t \le 2\pi)$

$x = b\cos t$

$y = a\sin t$



82. Astroid: $(0 \le t \le 2\pi)$

$x = a\cos^3 t$

$y = a\sin^3 t$



83. Cardioid: $(0 \le t \le 2\pi)$

$x = 2a\cos t - a\cos 2t$

$y = 2a\sin t - a\sin 2t$



84. Deltoid: $(0 \le t \le 2\pi)$

$x = 2a\cos t + a\cos 2t$

$y = 2a\sin t - a\sin 2t$



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

85. Hourglass: $(0 \le t \le 2\pi)$

$x = a \sin 2t$

$y = b \sin t$



86. Teardrop: $(0 \le t \le 2\pi)$

$x = 2a \cos t - a \sin 2t$

$y = b \sin t$



Centroid **In Exercises 87 and 88, find the centroid of the region bounded by the graph of the parametric equations and the coordinate axes. (Use the result of Exercise 77.)**

87. $x = \sqrt{t}, \quad y = 4 - t$

88. $x = \sqrt{4 - t}, \quad y = \sqrt{t}$

Volume **In Exercises 89 and 90, find the volume of the solid formed by revolving the region bounded by the graph of the parametric equations about the x-axis. (Use the result of Exercise 77.)**

89. $x = 6 \cos \theta, \quad y = 6 \sin \theta$

90. $x = \cos \theta, \quad y = 3 \sin \theta, \quad a > 0$

91. Cycloid Use the parametric equations

$x = a(\theta - \sin \theta)$ and $y = a(1 - \cos \theta), a > 0$

to answer the following.

(a) Find dy/dx and d^2y/dx^2.

(b) Find the equation of the tangent line at the point where $\theta = \pi/6$.

(c) Find all points of horizontal tangency.

(d) Determine where the curve is concave upward or concave downward.

(e) Find the length of one arc of the curve.

92. Using Parametric Equations Use the parametric equations

$$x = t^2\sqrt{3} \quad \text{and} \quad y = 3t - \frac{1}{3}t^3$$

to answer the following.

(a) Use a graphing utility to graph the curve on the interval $-3 \le t \le 3$.

(b) Find dy/dx and d^2y/dx^2.

(c) Find the equation of the tangent line at the point $\left(\sqrt{3}, \frac{8}{3}\right)$.

(d) Find the length of the curve on the interval $-3 \le t \le 3$.

(e) Find the area of the surface generated by revolving the curve about the x-axis.

93. Involute of a Circle The involute of a circle is described by the endpoint P of a string that is held taut as it is unwound from a spool that does not turn (see figure). Show that a parametric representation of the involute is

$x = r(\cos \theta + \theta \sin \theta)$ and $y = r(\sin \theta - \theta \cos \theta)$.



Figure for 93



Figure for 94

94. Involute of a Circle The figure shows a piece of string tied to a circle with a radius of one unit. The string is just long enough to reach the opposite side of the circle. Find the area that is covered when the string is unwound counterclockwise.

95. Using Parametric Equations

(a) Use a graphing utility to graph the curve given by

$$x = \frac{1 - t^2}{1 + t^2} \quad \text{and} \quad y = \frac{2t}{1 + t^2}, \quad -20 \le t \le 20.$$

(b) Describe the graph and confirm your result analytically.

(c) Discuss the speed at which the curve is traced as t increases from -20 to 20.

96. Tractrix A person moves from the origin along the positive y-axis pulling a weight at the end of a 12-meter rope. Initially, the weight is located at the point $(12, 0)$.

(a) In Exercise 61 of Section 8.4, it was shown that the path of the weight is modeled by the rectangular equation

$$y = -12 \ln \frac{12 - \sqrt{144 - x^2}}{x} - \sqrt{144 - x^2}$$

where $0 < x \le 12$. Use a graphing utility to graph the rectangular equation.

(b) Use a graphing utility to graph the parametric equations

$$y = 12 \operatorname{sech} \frac{t}{12} \quad \text{and} \quad y = t - 12 \tanh \frac{t}{12}$$

where $t \ge 0$. How does this graph compare with the graph in part (a)? Which graph (if either) do you think is a better representation of the path?

(c) Use the parametric equations for the tractrix to verify that the distance from the y-intercept of the tangent line to the point of tangency is independent of the location of the point of tangency.

True or False? **In Exercises 97–100, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

97. If $x = f(t)$ and $y = g(t)$, then $\dfrac{d^2y}{dx^2} = \dfrac{g''(t)}{f''(t)}$.

98. The curve given by $x = t^3$ and $y = t^2$ has a horizontal tangent at the origin because $dy/dt = 0$ when $t = 0$.

99. The curve given by $x = x_1 + t(x_2 - x_1)$ and $y = y_1 + t(y_2 - y_1)$, $y_1 \ne y_2$, has at least one horizontal asymptote.

100. The curve given by $x = h + a \cos \theta$ and $y = k + b \sin \theta$ has two horizontal asymptotes and two vertical asymptotes.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

10.4 Polar Coordinates and Polar Graphs

GO DIGITAL

- **Describe the polar coordinate system.**
- **Rewrite rectangular coordinates and equations in polar form and vice versa.**
- **Sketch the graph of an equation given in polar form.**
- **Find the slope of a tangent line to a polar graph.**
- **Identify several types of special polar graphs.**

Polar Coordinates

So far, you have been representing graphs as collections of points (x, y) on the rectangular coordinate system. The corresponding equations for these graphs have been in either rectangular or parametric form. In this section, you will study a coordinate system called the **polar coordinate system.**

To form the polar coordinate system in the plane, fix a point O, called the **pole** (or **origin**), and construct from O an initial ray called the **polar axis,** as shown in Figure 10.35. Then each point P in the plane can be assigned **polar coordinates** (r, θ), as follows.



Polar coordinates
Figure 10.35

r = *directed distance* from O to P

θ = *directed angle*, counterclockwise from polar axis to segment $\overline{OP}$

Figure 10.36 shows three points on the polar coordinate system. Notice that in this system, it is convenient to locate points with respect to a grid of concentric circles intersected by **radial lines** through the pole.



(a) **(b)** **(c)**

Figure 10.36

With rectangular coordinates, each point (x, y) has a unique representation. This is not true with polar coordinates. For instance, the coordinates

$$(r, \theta) \quad \text{and} \quad (r, 2\pi + \theta)$$

represent the same point [see parts (b) and (c) in Figure 10.36]. Also, because r is a *directed distance,* the coordinates

$$(r, \theta) \quad \text{and} \quad (-r, \theta + \pi)$$

represent the same point. In general, the point (r, θ) can be written as

$$(r, \theta) = (r, \theta + 2n\pi)$$

or

$$(r, \theta) = (-r, \theta + (2n + 1)\pi)$$

where n is any integer. Moreover, the pole is represented by $(0, \theta)$, where θ is any angle.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Coordinate Conversion



Relating polar and rectangular coordinates

Figure 10.37

To establish the relationship between polar and rectangular coordinates, let the polar axis coincide with the positive x-axis and the pole with the origin, as shown in Figure 10.37. Because (x, y) lies on a circle of radius r, it follows that

$$r^2 = x^2 + y^2.$$

Moreover, for $r > 0$, the definitions of the trigonometric functions imply that

$$\tan\theta = \frac{y}{x}, \quad \cos\theta = \frac{x}{r}, \quad \text{and} \quad \sin\theta = \frac{y}{r}.$$

You can show that the same relationships hold for $r < 0$.

THEOREM 10.10 Coordinate Conversion

The polar coordinates (r, θ) of a point are related to the rectangular coordinates (x, y) of the point as follows.

Polar-to-Rectangular	Rectangular-to-Polar
$x = r\cos\theta$	$\tan\theta = \frac{y}{x}$
$y = r\sin\theta$	$r^2 = x^2 + y^2$

GO DIGITAL



To convert from polar to rectangular coordinates, let $x = r\cos\theta$ and $y = r\sin\theta$.

Figure 10.38

EXAMPLE 1 Polar-to-Rectangular Conversion

a. For the point $(r, \theta) = (2, \pi)$,

$$x = r\cos\theta = 2\cos\pi = -2 \quad \text{and} \quad y = r\sin\theta = 2\sin\pi = 0.$$

So, the rectangular coordinates are $(x, y) = (-2, 0)$.

b. For the point $(r, \theta) = \left(\sqrt{3}, \pi/6\right)$,

$$x = \sqrt{3}\cos\frac{\pi}{6} = \frac{3}{2} \quad \text{and} \quad y = \sqrt{3}\sin\frac{\pi}{6} = \frac{\sqrt{3}}{2}.$$

So, the rectangular coordinates are $(x, y) = \left(3/2, \sqrt{3}/2\right)$.

See Figure 10.38.



To convert from rectangular to polar coordinates, let $\tan\theta = y/x$ and $r = \sqrt{x^2 + y^2}$.

Figure 10.39

EXAMPLE 2 Rectangular-to-Polar Conversion

a. For the second-quadrant point $(x, y) = (-1, 1)$,

$$\tan\theta = \frac{y}{x} = -1 \quad \Rightarrow \quad \theta = \frac{3\pi}{4}.$$

Because θ was chosen to be in the same quadrant as (x, y), use a positive value of r.

$$r = \sqrt{x^2 + y^2} = \sqrt{(-1)^2 + (1)^2} = \sqrt{2}$$

This implies that *one* set of polar coordinates is $(r, \theta) = \left(\sqrt{2}, 3\pi/4\right)$.

b. Because the point $(x, y) = (0, 2)$ lies on the positive y-axis, choose $\theta = \pi/2$ and $r = 2$, and one set of polar coordinates is $(r, \theta) = (2, \pi/2)$.

See Figure 10.39. ■

Note that you can also use Theorem 10.10 to convert a polar equation to a rectangular equation (and vice versa), as shown in Example 3.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Polar Graphs

One way to sketch the graph of a polar equation is to convert to rectangular coordinates and then sketch the graph of the rectangular equation.

EXAMPLE 3 Graphing Polar Equations

Describe the graph of each polar equation. Confirm each description by converting to a rectangular equation.

a. $r = 2$ **b.** $\theta = \frac{\pi}{3}$ **c.** $r = \sec\theta$

Solution

a. The graph of the polar equation $r = 2$ consists of all points that are two units from the pole. So, this graph is a circle centered at the origin with a radius of 2. [See Figure 10.40(a).] You can confirm this by using the relationship $r^2 = x^2 + y^2$ to obtain the rectangular equation

$$x^2 + y^2 = 2^2. \qquad \text{Rectangular equation}$$

b. The graph of the polar equation $\theta = \pi/3$ consists of all points on the line that makes an angle of $\pi/3$ with the positive x-axis. [See Figure 10.40(b).] You can confirm this by using the relationship $\tan\theta = y/x$ to obtain the rectangular equation

$$y = \sqrt{3}x. \qquad \text{Rectangular equation}$$

c. The graph of the polar equation $r = \sec\theta$ is not evident by simple inspection, so you can begin by converting to rectangular form using the relationship $r\cos\theta = x$.

$$r = \sec\theta \qquad \text{Polar equation}$$
$$r\cos\theta = 1$$
$$x = 1 \qquad \text{Rectangular equation}$$

From the rectangular equation, you can determine that the graph is a vertical line. [See Figure 10.40(c).]



(a) Circle: $r = 2$



(b) Radial line: $\theta = \frac{\pi}{3}$



(c) Vertical line: $r = \sec\theta$

Figure 10.40

TECHNOLOGY Sketching the graphs of complicated polar equations without technology can be tedious. With technology, however, the task is not difficult. Use a graphing utility in *polar* mode to graph the equations in the exercise set. If your graphing utility does not have a *polar* mode but does have a *parametric* mode, you can graph $r = f(\theta)$ by writing the equation as

$$x = f(\theta)\cos\theta$$
$$y = f(\theta)\sin\theta.$$

For instance, the graph of $r = \frac{1}{4}\theta$ shown in Figure 10.41 was produced with a graphing utility in parametric mode. This equation was graphed using the parametric equations

$$x = \frac{1}{4}\theta\cos\theta$$

$$y = \frac{1}{4}\theta\sin\theta$$

with the values of θ varying from 0 to 8π. This curve is of the form $r = a\theta$ and is called a **spiral of Archimedes.**



Spiral of Archimedes

Figure 10.41

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 4 Sketching a Polar Graph

See LarsonCalculus.com for an interactive version of this type of example.

Sketch the graph of $r = 2\cos 3\theta$.

Solution Begin by writing the polar equation in parametric form.

$$x = 2\cos 3\theta \cos\theta \quad \text{and} \quad y = 2\cos 3\theta \sin\theta$$

After some experimentation, you will find that the entire curve, which is called a **rose curve,** can be sketched by letting θ vary from 0 to π, as shown in Figure 10.42. If you try duplicating this graph with a graphing utility, you will find that by letting θ vary from 0 to 2π, you will actually trace the entire curve *twice.*

REMARK One way to sketch the graph of $r = 2\cos 3\theta$ is to make a table of values.

θ	0	$\frac{\pi}{6}$	$\frac{\pi}{3}$	$\frac{\pi}{2}$	$\frac{2\pi}{3}$
r	2	0	-2	0	2

By extending the table and plotting the points, you will obtain the curve shown in Example 4.



Figure 10.42

Use a graphing utility to experiment with other rose curves. Note that rose curves are of the form

$$r = a\cos n\theta \quad \text{or} \quad r = a\sin n\theta.$$

For instance, Figure 10.43 shows the graphs of two other rose curves.



Rose curves

Figure 10.43

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Slope and Tangent Lines

To find the slope of a tangent line to a polar graph, consider a differentiable function given by $r = f(\theta)$. To find the slope in polar form, use the parametric equations

$$x = r\cos\theta = f(\theta)\cos\theta \quad \text{and} \quad y = r\sin\theta = f(\theta)\sin\theta.$$

Using the parametric form of dy/dx given in Theorem 10.7, you have

$$\frac{dy}{dx} = \frac{dy/d\theta}{dx/d\theta} = \frac{f(\theta)\cos\theta + f'(\theta)\sin\theta}{-f(\theta)\sin\theta + f'(\theta)\cos\theta}$$

which establishes the next theorem.



Tangent line to polar curve
Figure 10.44

THEOREM 10.11 Slope in Polar Form

If f is a differentiable function of θ, then the *slope* of the tangent line to the graph of $r = f(\theta)$ at the point (r, θ) is

$$\frac{dy}{dx} = \frac{dy/d\theta}{dx/d\theta} = \frac{f(\theta)\cos\theta + f'(\theta)\sin\theta}{-f(\theta)\sin\theta + f'(\theta)\cos\theta}$$

provided that $dx/d\theta \neq 0$ at (r, θ). (See Figure 10.44.)

From Theorem 10.11, you can make the following observations.

1. Solutions of $\frac{dy}{d\theta} = 0$ yield horizontal tangents, provided that $\frac{dx}{d\theta} \neq 0$.
2. Solutions of $\frac{dx}{d\theta} = 0$ yield vertical tangents, provided that $\frac{dy}{d\theta} \neq 0$.

If $dy/d\theta$ and $dx/d\theta$ are *simultaneously* 0, then no conclusion can be drawn about tangent lines.

EXAMPLE 5 Finding Horizontal and Vertical Tangent Lines

Find the horizontal and vertical tangent lines of $r = \sin\theta$, where $0 \leq \theta < \pi$.

Solution Begin by writing the equation in parametric form.

$$x = r\cos\theta = \sin\theta\cos\theta$$

and

$$y = r\sin\theta = \sin\theta\sin\theta = \sin^2\theta$$

Next, differentiate x and y with respect to θ and set each derivative equal to 0.

$$\frac{dx}{d\theta} = \cos^2\theta - \sin^2\theta = \cos 2\theta = 0 \quad \Rightarrow \quad \theta = \frac{\pi}{4}, \frac{3\pi}{4}$$

$$\frac{dy}{d\theta} = 2\sin\theta\cos\theta = \sin 2\theta = 0 \quad \Rightarrow \quad \theta = 0, \frac{\pi}{2}$$

So, the graph has vertical tangent lines at

$$\left(\frac{\sqrt{2}}{2}, \frac{\pi}{4}\right) \quad \text{and} \quad \left(\frac{\sqrt{2}}{2}, \frac{3\pi}{4}\right)$$

and it has horizontal tangent lines at

$$(0, 0) \quad \text{and} \quad \left(1, \frac{\pi}{2}\right)$$

as shown in Figure 10.45.



Horizontal and vertical tangent lines of $r = \sin\theta$
Figure 10.45

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 6 Finding Horizontal and Vertical Tangent Lines

Find the horizontal and vertical tangent lines to the graph of $r = 2(1 - \cos\theta)$, where $0 \le \theta < 2\pi$.

Solution Let $y = r\sin\theta$ and then differentiate with respect to θ.

$$\begin{aligned} y &= r\sin\theta && \text{Parametric equation for } y \\ &= 2(1 - \cos\theta)\sin\theta && \text{Substitute for } r. \\ \frac{dy}{d\theta} &= 2[(1 - \cos\theta)(\cos\theta) + (\sin\theta)(\sin\theta)] && \text{Derivative of } y \text{ with respect to } \theta \\ &= 2(\cos\theta - \cos^2\theta + \sin^2\theta) && \text{Multiply.} \\ &= 2(\cos\theta - \cos^2\theta + 1 - \cos^2\theta) && \text{Pythagorean identity} \\ &= -2(2\cos^2\theta - \cos\theta - 1) && \text{Combine like terms; factor out } -1. \\ &= -2(2\cos\theta + 1)(\cos\theta - 1) && \text{Factor.} \end{aligned}$$

Setting $dy/d\theta$ equal to 0, you can see that $\cos\theta = -\frac{1}{2}$ and $\cos\theta = 1$. So, $dy/d\theta = 0$ when $\theta = 2\pi/3$, $4\pi/3$, and 0. Similarly, using $x = r\cos\theta$, you have

$$\begin{aligned} x &= r\cos\theta && \text{Parametric equation for } x \\ &= 2(1 - \cos\theta)\cos\theta && \text{Substitute for } r. \\ &= 2\cos\theta - 2\cos^2\theta && \text{Multiply.} \\ \frac{dx}{d\theta} &= -2\sin\theta + 4\cos\theta\sin\theta && \text{Derivative of } x \text{ with respect to } \theta \\ &= (2\sin\theta)(2\cos\theta - 1). && \text{Factor.} \end{aligned}$$

Setting $dx/d\theta$ equal to 0, you can see that $\sin\theta = 0$ and $\cos\theta = \frac{1}{2}$. So, you can conclude that $dx/d\theta = 0$ when $\theta = 0$, π, $\pi/3$, and $5\pi/3$. From these results and from the graph shown in Figure 10.46, you can conclude that the graph has horizontal tangents at $(3, 2\pi/3)$ and $(3, 4\pi/3)$ and has vertical tangents at $(1, \pi/3)$, $(1, 5\pi/3)$, and $(4, \pi)$. This graph is called a **cardioid.** Note that both derivatives ($dy/d\theta$ and $dx/d\theta$) are 0 when $\theta = 0$. Using this information alone, you do not know whether the graph has a horizontal or vertical tangent line at the pole. From Figure 10.46, however, you can see that the graph has a cusp at the pole. ■



Horizontal and vertical tangent lines of $r = 2(1 - \cos\theta)$

Figure 10.46

Theorem 10.11 has an important consequence. If the graph of $r = f(\theta)$ passes through the pole when $\theta = \alpha$ and $f'(\alpha) \ne 0$, then the formula for dy/dx simplifies as follows.

$$\frac{dy}{dx} = \frac{f'(\alpha)\sin\alpha + f(\alpha)\cos\alpha}{f'(\alpha)\cos\alpha - f(\alpha)\sin\alpha} = \frac{f'(\alpha)\sin\alpha + 0}{f'(\alpha)\cos\alpha - 0} = \frac{\sin\alpha}{\cos\alpha} = \tan\alpha$$

So, the line $\theta = \alpha$ is tangent to the graph at the pole, $(0, \alpha)$.



This rose curve has three tangent lines ($\theta = \pi/6$, $\theta = \pi/2$, and $\theta = 5\pi/6$) at the pole.

Figure 10.47

THEOREM 10.12 Tangent Lines at the Pole

If $f(\alpha) = 0$ and $f'(\alpha) \ne 0$, then the line $\theta = \alpha$ is tangent at the pole to the graph of $r = f(\theta)$.

Theorem 10.12 is useful because it states that the zeros of $r = f(\theta)$ can be used to find the tangent lines at the pole. Note that because a polar curve can cross the pole more than once, it can have more than one tangent line at the pole. For example, the rose curve $f(\theta) = 2\cos 3\theta$ has three tangent lines at the pole, as shown in Figure 10.47. For this curve, $f(\theta) = 2\cos 3\theta$ is 0 when θ is $\pi/6$, $\pi/2$, and $5\pi/6$. Moreover, the derivative $f'(\theta) = -6\sin 3\theta$ is not 0 for these values of θ.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Special Polar Graphs

Several important types of graphs have equations that are simpler in polar form than in rectangular form. For example, the polar equation of a circle having a radius of a and centered at the origin is simply $r = a$. Later in the text, you will come to appreciate this benefit. For now, several other types of graphs that have simpler equations in polar form are shown below. (Conics are considered in Section 10.6.)

Limaçons

$r = a \pm b \cos\theta$

$r = a \pm b \sin\theta$

$(a > 0, b > 0)$



$\frac{a}{b} < 1$

Limaçon with inner loop



$\frac{a}{b} = 1$

Cardioid (heart-shaped)



$1 < \frac{a}{b} < 2$

Dimpled limaçon



$\frac{a}{b} \geq 2$

Convex limaçon

Rose Curves

n petals when n is odd

$2n$ petals when n is even

$(n \geq 2)$



$r = a \cos n\theta$

Rose curve



$r = a \cos n\theta$

Rose curve



$r = a \sin n\theta$

Rose curve



$r = a \sin n\theta$

Rose curve

Circles and Lemniscates



$r = a \cos\theta$

Circle



$r = a \sin\theta$

Circle



$r^2 = a^2 \sin 2\theta$

Lemniscate



$r^2 = a^2 \cos 2\theta$

Lemniscate

TECHNOLOGY The rose curves described above are of the form $r = a \cos n\theta$ or $r = a \sin n\theta$, where n is a positive integer that is greater than or equal to 2. Use a graphing utility to graph

$$r = a \cos n\theta \quad \text{or} \quad r = a \sin n\theta$$

for some noninteger values of n. Are these graphs also rose curves? For example, try sketching the graph of

$$r = \cos\frac{2}{3}\theta, \quad 0 \leq \theta \leq 6\pi.$$



Generated by Maple

FOR FURTHER INFORMATION For more information on rose curves and related curves, see the article "A Rose is a Rose . . ." by Peter M. Maurer in *The American Mathematical Monthly*. The computer-generated graph at the left is the result of an algorithm that Maurer calls "The Rose." To view this article, go to *MathArticles.com*.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

10.4 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Consider the polar coordinates (r, θ). What does r represent? What does θ represent?
2. Plot the points below on the same set of coordinate axes.

$$(r, \theta) = \left(2, \frac{\pi}{2}\right) \quad \text{and} \quad (x, y) = \left(2, \frac{\pi}{2}\right)$$

3. Describe the differences between the rectangular coordinate system and the polar coordinate system.
4. Explain how to write a polar equation in parametric form.

Polar-to-Rectangular Conversion **In Exercises 5–14, the polar coordinates of a point are given. Plot the point and find the corresponding rectangular coordinates for the point.**

5. $\left(8, \frac{\pi}{2}\right)$
6. $\left(-2, \frac{5\pi}{3}\right)$
7. $\left(-4, -\frac{3\pi}{4}\right)$
8. $\left(0, -\frac{7\pi}{6}\right)$
9. $\left(7, \frac{5\pi}{4}\right)$
10. $\left(-2, \frac{11\pi}{6}\right)$
11. $\left(\sqrt{2}, 2.36\right)$
12. $(-3, -1.57)$
13. $(-8, 0.75)$
14. $(1.25, -5)$

Rectangular-to-Polar Conversion **In Exercises 15–24, the rectangular coordinates of a point are given. Plot the point and find *two* sets of polar coordinates for the point for $0 \le \theta < 2\pi$.**

15. $(1, 0)$
16. $(0, -9)$
17. $(-3, 4)$
18. $(6, -2)$
19. $\left(-5, -5\sqrt{3}\right)$
20. $\left(3, -\sqrt{3}\right)$
21. $\left(\sqrt{7}, -\sqrt{7}\right)$
22. $\left(-2\sqrt{2}, -2\sqrt{2}\right)$
23. $(4, 5)$
24. $(1, 8)$

Rectangular-to-Polar Conversion **In Exercises 25–34, convert the rectangular equation to polar form and sketch its graph.**

25. $x^2 + y^2 = 9$
26. $x^2 - y^2 = 9$
27. $x^2 + y^2 = a^2$
28. $x^2 + y^2 - 2ax = 0$
29. $y = 8$
30. $x = 12$
31. $3x - y + 2 = 0$
32. $xy = 4$
33. $y^2 = 9x$
34. $(x^2 + y^2)^2 - 9(x^2 - y^2) = 0$

Polar-to-Rectangular Conversion **In Exercises 35–44, convert the polar equation to rectangular form and sketch its graph.**

35. $r = 4$
36. $r = -1$
37. $r = 3 \sin \theta$
38. $r = 5 \cos \theta$
39. $r = \theta$
40. $\theta = \frac{5\pi}{6}$
41. $r = 3 \sec \theta$
42. $r = -6 \csc \theta$
43. $r = \sec \theta \tan \theta$
44. $r = \cot \theta \csc \theta$

Graphing a Polar Equation **In Exercises 45–54, use a graphing utility to graph the polar equation. Find an interval for θ over which the graph is traced *only once*.**

45. $r = 2 - 5 \cos \theta$
46. $r = 3(1 - 4 \cos \theta)$
47. $r = -1 + \sin \theta$
48. $r = 4 + 3 \cos \theta$
49. $r = \frac{2}{1 + \cos \theta}$
50. $r = \frac{1}{4 - 3 \sin \theta}$
51. $r = 5 \cos \frac{3\theta}{2}$
52. $r = 3 \sin \frac{5\theta}{2}$
53. $r^2 = 4 \sin 2\theta$
54. $r^2 = \frac{1}{\theta}$

55. **Verifying a Polar Equation** Convert the equation

$$r = 2(h \cos \theta + k \sin \theta)$$

to rectangular form and verify that it is the equation of a circle. Find the radius and the rectangular coordinates of the center of the circle.

56. **HOW DO YOU SEE IT?** Identify each special polar graph and write its equation.

(a)



(b)



(c)



(d)



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

57. Sketching a Graph Sketch the graph of $r = 4 \sin \theta$ over each interval.

(a) $0 \le \theta \le \frac{\pi}{2}$ (b) $\frac{\pi}{2} \le \theta \le \pi$ (c) $-\frac{\pi}{2} \le \theta \le \frac{\pi}{2}$

58. Distance Formula

(a) Verify that the Distance Formula for the distance between the two points (r_1, θ_1) and (r_2, θ_2) in polar coordinates is

$$d = \sqrt{r_1^2 + r_2^2 - 2r_1 r_2 \cos(\theta_1 - \theta_2)}.$$

(b) Describe the positions of the points relative to each other for $\theta_1 = \theta_2$. Simplify the Distance Formula for this case. Is the simplification what you expected? Explain.

(c) Simplify the Distance Formula for $\theta_1 - \theta_2 = 90°$. Is the simplification what you expected? Explain.

(d) Choose two points on the polar coordinate system and find the distance between them. Then choose different polar representations of the same two points and apply the Distance Formula again. Discuss the result.

Distance Formula **In Exercises 59–62, use the result of Exercise 58 to find the distance between the two points in polar coordinates.**

59. $\left(1, \frac{5\pi}{6}\right)$, $\left(4, \frac{\pi}{3}\right)$ **60.** $\left(8, \frac{7\pi}{4}\right)$, $(5, \pi)$

61. $(2, 0.5)$, $(7, 1.2)$ **62.** $(4, 2.5)$, $(12, 1)$

Finding Slopes of Tangent Lines **In Exercises 63 and 64, find dy/dx and the slopes of the tangent lines shown on the graph of the polar equation.**

63. $r = 2(1 - \sin \theta)$ **64.** $r = 2 + 3 \sin \theta$



Finding Slopes of Tangent Lines Using Technology **In Exercises 65–68, use a graphing utility to (a) graph the polar equation, (b) draw the tangent line at the given value of θ, and (c) find dy/dx at the given value of θ. (*Hint:* Let the increment between the values of θ equal $\pi/24$.)**

65. $r = 3(1 - \cos \theta)$, $\theta = \frac{\pi}{2}$ **66.** $r = 3 - 2 \cos \theta$, $\theta = 0$

67. $r = 3 \sin \theta$, $\theta = \frac{\pi}{3}$ **68.** $r = 4$, $\theta = \frac{\pi}{4}$

Horizontal and Vertical Tangency **In Exercises 69 and 70, find the points of horizontal and vertical tangency to the polar curve.**

69. $r = 1 - \sin \theta$

70. $r = a \sin \theta$

Horizontal Tangency **In Exercises 71 and 72, find the points of horizontal tangency to the polar curve.**

71. $r = 2 \csc \theta + 3$ **72.** $r = a \sin \theta \cos^2 \theta$

Tangent Lines at the Pole **In Exercises 73–80, sketch a graph of the polar equation and find the tangent lines at the pole (if any).**

73. $r = 5 \sin \theta$ **74.** $r = 5 \cos \theta$

75. $r = 4(1 - \sin \theta)$ **76.** $r = 2(1 - \cos \theta)$

77. $r = 4 \cos 3\theta$ **78.** $r = -\sin 5\theta$

79. $r = 3 \sin 2\theta$ **80.** $r = 3 \cos 2\theta$

Sketching a Polar Graph **In Exercises 81–92, sketch a graph of the polar equation.**

81. $r = 8$ **82.** $r = 1$

83. $r = 4(1 + \cos \theta)$ **84.** $r = 1 + \sin \theta$

85. $r = 3 - 2 \cos \theta$ **86.** $r = 5 - 4 \sin \theta$

87. $r = -7 \csc \theta$ **88.** $r = \frac{6}{2 \sin \theta - 3 \cos \theta}$

89. $r = 3\theta$

90. $r = \frac{1}{\theta}$

91. $r^2 = 4 \cos 2\theta$

92. $r^2 = 4 \sin \theta$

Asymptote **In Exercises 93–96, use a graphing utility to graph the equation and show that the given line is an asymptote of the graph.**

Name of Graph	Polar Equation	Asymptote
93. Conchoid	$r = 2 - \sec \theta$	$x = -1$
94. Conchoid	$r = 2 + \csc \theta$	$y = 1$
95. Hyperbolic spiral	$r = 2/\theta$	$y = 2$
96. Strophoid	$r = 2 \cos 2\theta \sec \theta$	$x = -2$

Exploring Concepts

In Exercises 97 and 98, use the graph of $r = f(\theta)$ to sketch a graph of the transformation.

97. $r = f(-\theta)$ **98.** $r = -f(\theta)$





99. Describe how to test whether a polar graph is symmetric about (a) the x-axis and (b) the y-axis.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

100. Think About It Use a graphing utility to graph the polar equation $r = 6[1 + \cos(\theta - \phi)]$ for (a) $\phi = 0$, (b) $\phi = \pi/4$, and (c) $\phi = \pi/2$. Use the graphs to describe the effect of the angle ϕ. Write the equation as a function of $\sin\theta$ for part (c).

101. Rotated Curve Verify that if the curve whose polar equation is $r = f(\theta)$ is rotated about the pole through an angle ϕ, then an equation for the rotated curve is $r = f(\theta - \phi)$.

102. Rotated Curve The polar form of an equation of a curve is $r = f(\sin\theta)$. Show that the form becomes

(a) $r = f(-\cos\theta)$ if the curve is rotated counterclockwise $\pi/2$ radians about the pole.

(b) $r = f(-\sin\theta)$ if the curve is rotated counterclockwise π radians about the pole.

(c) $r = f(\cos\theta)$ if the curve is rotated counterclockwise $3\pi/2$ radians about the pole.

Rotated Curve **In Exercises 103–105, use the results of Exercises 101 and 102.**

103. Write an equation for the limaçon $r = 2 - \sin\theta$ after it has been rotated counterclockwise by an angle of (a) $\theta = \pi/4$, (b) $\theta = \pi/2$, (c) $\theta = \pi$, and (d) $\theta = 3\pi/2$. Use a graphing utility to graph each rotated limaçon.

104. Write an equation for the rose curve $r = 2\sin 2\theta$ after it has been rotated counterclockwise by an angle of (a) $\theta = \pi/6$, (b) $\theta = \pi/2$, (c) $\theta = 2\pi/3$, and (d) $\theta = \pi$. Use a graphing utility to graph each rotated rose curve.

105. Sketch the graph of each equation.

(a) $r = 1 - \sin\theta$ (b) $r = 1 - \sin\left(\theta - \frac{\pi}{4}\right)$

106. Proof Prove that the tangent of the angle $\psi\,(0 \le \psi \le \pi/2)$ between the radial line and the tangent line at the point (r, θ) on the graph of $r = f(\theta)$ (see figure) is given by

$$\tan\psi = \left|\frac{r}{dr/d\theta}\right|.$$



Finding an Angle **In Exercises 107–112, use the result of Exercise 106 to find the angle ψ between the radial and tangent lines to the graph for the indicated value of θ. Use a graphing utility to graph the polar equation, the radial line, and the tangent line for the indicated value of θ. Identify the angle ψ.**

	Polar Equation	Value of θ
107.	$r = 2(1 - \cos\theta)$	$\theta = \pi$
108.	$r = 3(1 - \cos\theta)$	$\theta = \frac{3\pi}{4}$
109.	$r = 2\cos 3\theta$	$\theta = \frac{\pi}{4}$
110.	$r = 4\sin 2\theta$	$\theta = \frac{\pi}{6}$
111.	$r = \frac{6}{1 - \cos\theta}$	$\theta = \frac{2\pi}{3}$
112.	$r = 5$	$\theta = \frac{\pi}{6}$

True or False? **In Exercises 113–116, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

113. If (r_1, θ_1) and (r_2, θ_2) represent the same point on the polar coordinate system, then $|r_1| = |r_2|$.

114. If (r, θ_1) and (r, θ_2) represent the same point on the polar coordinate system, then $\theta_1 = \theta_2 + 2n\pi$ for some integer n.

115. If $x > 0$, then the point (x, y) on the rectangular coordinate system can be represented by (r, θ) on the polar coordinate system, where $r = \sqrt{x^2 + y^2}$ and $\theta = \arctan(y/x)$.

116. The polar equations $r = \sin 2\theta$, $r = -\sin 2\theta$, and $r = \sin(-2\theta)$ all have the same graph.

SECTION PROJECT

Cassini Oval

A Cassini oval is defined as the set of all points the product of whose distances from two fixed points is constant. These curves are named after the astronomer Giovanni Domenico Cassini (1625–1712). He suspected that these curves could model planetary motion. However, as you saw in Section 10.1, Kepler used ellipses to describe planetary motion. You will learn more about Kepler's Laws of planetary motion in Section 10.6.

Let $(-c, 0)$ and $(c, 0)$ be two fixed points in the plane. A point (x, y) lies on a Cassini oval when the distance between (x, y) and $(-c, 0)$ times the distance between (x, y) and $(c, 0)$ is b^2, where b is a constant.



Four different types of Cassini ovals

(a) Show that $(x^2 + y^2)^2 - 2c^2(x^2 - y^2) + c^4 = b^4$

(b) Convert the equation in part (a) to polar coordinates.

(c) Show that if $b = c$, then the Cassini oval is a lemniscate.

(d) Use a graphing utility to graph the Cassini oval for $c = 1$ and $b = 2$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

10.5 Area and Arc Length in Polar Coordinates

GO DIGITAL

- Find the area of a region bounded by a polar graph.
- Find the points of intersection of two polar graphs.
- Find the arc length of a polar graph.
- Find the area of a surface of revolution (polar form).

Area of a Polar Region

The development of a formula for the area of a polar region parallels that for the area of a region on the rectangular coordinate system but uses sectors of a circle instead of rectangles as the basic elements of area. In Figure 10.48, note that the area of a circular sector of radius r is $\frac{1}{2}\theta r^2$, provided θ is measured in radians.



The area of a sector of a circle is $A = \frac{1}{2}\theta r^2$.
Figure 10.48

Consider the function $r = f(\theta)$, where f is continuous and nonnegative on the interval $\alpha \le \theta \le \beta$. The region bounded by the graph of f and the radial lines $\theta = \alpha$ and $\theta = \beta$ is shown in Figure 10.49(a). To find the area of this region, partition the interval $[\alpha, \beta]$ into n equal subintervals

$$\alpha = \theta_0 < \theta_1 < \theta_2 < \cdots < \theta_{n-1} < \theta_n = \beta.$$

Then approximate the area of the region by the sum of the areas of the n sectors, as shown in Figure 10.49(b).



(a)



(b)
Figure 10.49

$$\text{Radius of } i\text{th sector} = f(\theta_i)$$

$$\text{Central angle of } i\text{th sector} = \frac{\beta - \alpha}{n} = \Delta\theta$$

$$A \approx \sum_{i=1}^{n} \left(\frac{1}{2}\right)\Delta\theta[f(\theta_i)]^2$$

Taking the limit as $n \to \infty$ produces

$$A = \lim_{n\to\infty} \frac{1}{2} \sum_{i=1}^{n} [f(\theta_i)]^2 \Delta\theta$$
$$= \frac{1}{2}\int_{\alpha}^{\beta} [f(\theta)]^2 \, d\theta$$

which leads to the next theorem.

THEOREM 10.13 Area in Polar Coordinates

If a function f is continuous and nonnegative on the interval $[\alpha, \beta]$, where $0 < \beta - \alpha \le 2\pi$, then the area of the region bounded by the graph of $r = f(\theta)$ between the radial lines $\theta = \alpha$ and $\theta = \beta$ is

$$A = \frac{1}{2}\int_{\alpha}^{\beta} [f(\theta)]^2 \, d\theta$$
$$= \frac{1}{2}\int_{\alpha}^{\beta} r^2 \, d\theta. \qquad 0 < \beta - \alpha \le 2\pi$$

You can use the formula in Theorem 10.13 to find the area of a region bounded by the graph of a continuous *nonpositive* function. The formula is not necessarily valid, however, when f takes on both positive *and* negative values in the interval $[\alpha, \beta]$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



The area of one petal of the rose curve that lies between the radial lines $\theta = -\pi/6$ and $\theta = \pi/6$ is $3\pi/4$.
Figure 10.50

EXAMPLE 1 Finding the Area of a Polar Region

See LarsonCalculus.com for an interactive version of this type of example.

Find the area of one petal of the rose curve $r = 3\cos 3\theta$.

Solution Figure 10.50 shows that the petal on the right is traced as θ increases from $-\pi/6$ to $\pi/6$. So, the area is

$$A = \frac{1}{2}\int_{\alpha}^{\beta} r^2\,d\theta = \frac{1}{2}\int_{-\pi/6}^{\pi/6} (3\cos 3\theta)^2\,d\theta$$ Use formula for area in polar coordinates.

$$= \frac{9}{2}\int_{-\pi/6}^{\pi/6} \frac{1+\cos 6\theta}{2}\,d\theta$$ Power-reducing formula

$$= \frac{9}{4}\left[\theta + \frac{\sin 6\theta}{6}\right]_{-\pi/6}^{\pi/6}$$

$$= \frac{9}{4}\left(\frac{\pi}{6} + \frac{\pi}{6}\right)$$

$$= \frac{3\pi}{4}.$$

To find the area of the region lying inside all three petals of the rose curve in Example 1, you could *not* simply integrate between 0 and 2π. By doing this, you would obtain $9\pi/2$, which is twice the area of the three petals. The duplication occurs because the rose curve is traced twice as θ increases from 0 to 2π.

EXAMPLE 2 Finding the Area Bounded by a Single Curve

Find the area of the region lying between the inner and outer loops of the limaçon $r = 1 - 2\sin\theta$.

Solution In Figure 10.51, note that the inner loop is traced as θ increases from $\pi/6$ to $5\pi/6$. So, the area inside the *inner loop* is

$$A_1 = \frac{1}{2}\int_{\pi/6}^{5\pi/6} (1 - 2\sin\theta)^2\,d\theta$$ Use formula for area in polar coordinates.

$$= \frac{1}{2}\int_{\pi/6}^{5\pi/6} (1 - 4\sin\theta + 4\sin^2\theta)\,d\theta$$

$$= \frac{1}{2}\int_{\pi/6}^{5\pi/6} \left[1 - 4\sin\theta + 4\left(\frac{1-\cos 2\theta}{2}\right)\right]d\theta$$ Power-reducing formula

$$= \frac{1}{2}\int_{\pi/6}^{5\pi/6} (3 - 4\sin\theta - 2\cos 2\theta)\,d\theta$$ Simplify.

$$= \frac{1}{2}\left[3\theta + 4\cos\theta - \sin 2\theta\right]_{\pi/6}^{5\pi/6}$$

$$= \frac{1}{2}\left(2\pi - 3\sqrt{3}\right)$$

$$= \pi - \frac{3\sqrt{3}}{2}.$$



The area between the inner and outer loops is approximately 8.34.
Figure 10.51

In a similar way, you can integrate from $5\pi/6$ to $13\pi/6$ to find that the area of the region lying inside the *outer loop* is $A_2 = 2\pi + \left(3\sqrt{3}/2\right)$. The area of the region lying between the two loops is the difference of A_2 and A_1.

$$A = A_2 - A_1 = \left(2\pi + \frac{3\sqrt{3}}{2}\right) - \left(\pi - \frac{3\sqrt{3}}{2}\right) = \pi + 3\sqrt{3} \approx 8.34$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Points of Intersection of Polar Graphs

Because a point may be represented in different ways in polar coordinates, care must be taken in determining the points of intersection of two polar graphs. For example, consider the points of intersection of the graphs of

$$r = 1 - 2\cos\theta \quad \text{and} \quad r = 1$$

as shown in Figure 10.52. As with rectangular equations, you can attempt to find the points of intersection by solving the two equations simultaneously, as shown.

$$r = 1 - 2\cos\theta \qquad \text{First equation}$$
$$1 = 1 - 2\cos\theta \qquad \text{Substitute } r = 1 \text{ from second equation into first equation.}$$
$$\cos\theta = 0 \qquad \text{Simplify.}$$
$$\theta = \frac{\pi}{2}, \frac{3\pi}{2} \qquad \text{Solve for } \theta.$$



Three points of intersection: $(1, \pi/2)$, $(-1, 0)$, and $(1, 3\pi/2)$

Figure 10.52

The corresponding points of intersection are $(1, \pi/2)$ and $(1, 3\pi/2)$. Figure 10.52 shows, however, that there is a *third* point of intersection that did not show up when the two polar equations were solved simultaneously. (This is one reason why you should sketch a graph when finding the area of a polar region.) The third point was not found because it does not occur with the same coordinates in the two graphs. On the graph of $r = 1$, the point occurs with coordinates $(1, \pi)$, but on the graph of

$$r = 1 - 2\cos\theta$$

the point occurs with coordinates $(-1, 0)$.

In addition to solving equations simultaneously and sketching a graph, note that because the pole can be represented by $(0, \theta)$, where θ is *any* angle, you should check separately for the pole when finding points of intersection.

You can compare the problem of finding points of intersection of two polar graphs with that of finding collision points of two satellites in intersecting orbits about Earth, as shown in Figure 10.53. The satellites will not collide as long as they reach the points of intersection at different times (θ-values). Collisions will occur only at the points of intersection that are "simultaneous points"—those that are reached at the same time (θ-value).



The paths of satellites can cross without causing a collision.

Figure 10.53

FOR FURTHER INFORMATION For more information on using technology to find points of intersection, see the article "Finding Points of Intersection of Polar-Coordinate Graphs" by Warren W. Esty in *Mathematics Teacher*. To view this article, go to *MathArticles.com*.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 3 Finding the Area of a Region Between Two Curves

Find the area of the region common to the two regions bounded by the curves

$$r = -6\cos\theta \qquad \text{Circle}$$

and

$$r = 2 - 2\cos\theta. \qquad \text{Cardioid}$$



Figure 10.54

Solution Because both curves are symmetric with respect to the x-axis, you can work with the upper half-plane, as shown in Figure 10.54. The blue shaded region lies between the circle and the radial line

$$\theta = \frac{2\pi}{3}.$$

Because the circle has coordinates $(0, \pi/2)$ at the pole, you can integrate between $\pi/2$ and $2\pi/3$ to obtain the area of this region. The region that is shaded orange is bounded by the cardioid and the radial lines $\theta = 2\pi/3$ and $\theta = \pi$. So, you can find the area of this second region by integrating between $2\pi/3$ and π. The sum of these two integrals gives the area of the common region lying *above* the radial line $\theta = \pi$.

$$\frac{A}{2} = \underbrace{\frac{1}{2}\int_{\pi/2}^{2\pi/3} (-6\cos\theta)^2\,d\theta}_{\text{Region between circle and radial line } \theta = 2\pi/3} + \underbrace{\frac{1}{2}\int_{2\pi/3}^{\pi} (2 - 2\cos\theta)^2\,d\theta}_{\text{Region between cardioid and radial lines } \theta = 2\pi/3 \text{ and } \theta = \pi}$$

$$= 18\int_{\pi/2}^{2\pi/3} \cos^2\theta\,d\theta + \frac{1}{2}\int_{2\pi/3}^{\pi} (4 - 8\cos\theta + 4\cos^2\theta)\,d\theta$$

$$= 9\int_{\pi/2}^{2\pi/3} (1 + \cos 2\theta)\,d\theta + \int_{2\pi/3}^{\pi} (3 - 4\cos\theta + \cos 2\theta)\,d\theta$$

$$= 9\left[\theta + \frac{\sin 2\theta}{2}\right]_{\pi/2}^{2\pi/3} + \left[3\theta - 4\sin\theta + \frac{\sin 2\theta}{2}\right]_{2\pi/3}^{\pi}$$

$$= 9\left(\frac{2\pi}{3} - \frac{\sqrt{3}}{4} - \frac{\pi}{2}\right) + \left(3\pi - 2\pi + 2\sqrt{3} + \frac{\sqrt{3}}{4}\right)$$

$$= \frac{5\pi}{2}$$

Finally, multiplying by 2, you can conclude that the total area is

$$5\pi \approx 15.7. \qquad \text{Area of region inside circle and cardioid}$$

To check the reasonableness of this result, note that the area of the circular region is

$$\pi r^2 = 9\pi. \qquad \text{Area of circle}$$

So, it seems reasonable that the area of the region lying inside the circle and the cardioid is 5π. ■

To see the benefit of polar coordinates for finding the area in Example 3, consider the integral below, which gives the comparable area in rectangular coordinates.

$$\frac{A}{2} = \int_{-4}^{-3/2} \sqrt{2\sqrt{1 - 2x} - x^2 - 2x + 2}\,dx + \int_{-3/2}^{0} \sqrt{-x^2 - 6x}\,dx$$

Use the integration capabilities of a graphing utility to show that you obtain the same area as that found in Example 3.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Arc Length in Polar Form

The formula for the length of a polar arc can be obtained from the arc length formula for a curve described by parametric equations. (See Exercise 84.)

REMARK When applying the arc length formula to a polar curve, be sure that the curve is traced out only once on the interval of integration. For instance, the rose curve $r = \cos 3\theta$ is traced out once on the interval $0 \le \theta \le \pi$ but is traced out twice on the interval $0 \le \theta \le 2\pi$.

THEOREM 10.14 Arc Length of a Polar Curve

Let f be a function whose derivative is continuous on an interval $\alpha \le \theta \le \beta$. The length of the graph of $r = f(\theta)$ from $\theta = \alpha$ to $\theta = \beta$ is

$$s = \int_{\alpha}^{\beta} \sqrt{[f(\theta)]^2 + [f'(\theta)]^2}\, d\theta = \int_{\alpha}^{\beta} \sqrt{r^2 + \left(\frac{dr}{d\theta}\right)^2}\, d\theta.$$

EXAMPLE 4 Finding the Length of a Polar Curve

Find the length of the arc from $\theta = 0$ to $\theta = 2\pi$ for the cardioid

$$r = f(\theta) = 2 - 2\cos\theta$$

as shown in Figure 10.55.



Figure 10.55

Solution Because $f'(\theta) = 2\sin\theta$, you can find the arc length as follows.

$$\begin{aligned}
s &= \int_{\alpha}^{\beta} \sqrt{[f(\theta)]^2 + [f'(\theta)]^2}\, d\theta && \text{Formula for arc length of a polar curve} \\
&= \int_{0}^{2\pi} \sqrt{(2 - 2\cos\theta)^2 + (2\sin\theta)^2}\, d\theta \\
&= 2\sqrt{2}\int_{0}^{2\pi} \sqrt{1 - \cos\theta}\, d\theta && \text{Simplify.} \\
&= 2\sqrt{2}\int_{0}^{2\pi} \sqrt{2\sin^2\frac{\theta}{2}}\, d\theta && \text{Trigonometric identity} \\
&= 4\int_{0}^{2\pi} \sin\frac{\theta}{2}\, d\theta && \sin\tfrac{\theta}{2} \ge 0 \text{ for } 0 \le \theta \le 2\pi \\
&= 8\left[-\cos\frac{\theta}{2}\right]_{0}^{2\pi} \\
&= 8(1 + 1) \\
&= 16
\end{aligned}$$

Using Figure 10.55, you can determine the reasonableness of this answer by comparing it with the circumference of a circle. For example, a circle of radius $\frac{5}{2}$ has a circumference of

$$5\pi \approx 15.7.$$

Note that in the fifth step of the solution, it is legitimate to write

$$\sqrt{2\sin^2\frac{\theta}{2}} = \sqrt{2}\sin\frac{\theta}{2}$$

rather than

$$\sqrt{2\sin^2\frac{\theta}{2}} = \sqrt{2}\left|\sin\frac{\theta}{2}\right|$$

because $\sin(\theta/2) \ge 0$ for $0 \le \theta \le 2\pi$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Area of a Surface of Revolution

The polar coordinate versions of the formulas for the area of a surface of revolution can be obtained from the parametric versions given in Theorem 10.9, using the equations $x = r\cos\theta$ and $y = r\sin\theta$.

REMARK When using Theorem 10.15, check to see that the graph of $r = f(\theta)$ is traced only once on the interval $\alpha \le \theta \le \beta$. For example, the circle $r = \cos\theta$ is traced only once on the interval $0 \le \theta \le \pi$.

THEOREM 10.15 Area of a Surface of Revolution

Let f be a function whose derivative is continuous on an interval $\alpha \le \theta \le \beta$. The area of the surface formed by revolving the graph of $r = f(\theta)$ from $\theta = \alpha$ to $\theta = \beta$ about the indicated line is as follows.

1. $S = 2\pi\int_{\alpha}^{\beta} f(\theta)\sin\theta\sqrt{[f(\theta)]^2 + [f'(\theta)]^2}\,d\theta$ About the polar axis

2. $S = 2\pi\int_{\alpha}^{\beta} f(\theta)\cos\theta\sqrt{[f(\theta)]^2 + [f'(\theta)]^2}\,d\theta$ About the line $\theta = \frac{\pi}{2}$

EXAMPLE 5 Finding the Area of a Surface of Revolution

Find the area of the surface formed by revolving the circle $r = f(\theta) = \cos\theta$ about the line $\theta = \pi/2$, as shown in Figure 10.56.



(a) (b)

Figure 10.56

Solution Use the second formula in Theorem 10.15 with $f'(\theta) = -\sin\theta$. Because the circle is traced once as θ increases from 0 to π, you have

$$S = 2\pi\int_{\alpha}^{\beta} f(\theta)\cos\theta\sqrt{[f(\theta)]^2 + [f'(\theta)]^2}\,d\theta$$ Formula for area of a surface of revolution

$$= 2\pi\int_{0}^{\pi} (\cos\theta)(\cos\theta)\sqrt{\cos^2\theta + \sin^2\theta}\,d\theta$$

$$= 2\pi\int_{0}^{\pi} \cos^2\theta\,d\theta$$ Trigonometric identity

$$= \pi\int_{0}^{\pi} (1 + \cos 2\theta)\,d\theta$$ Trigonometric identity

$$= \pi\left[\theta + \frac{\sin 2\theta}{2}\right]_0^{\pi}$$

$$= \pi^2.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

10.5 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Give the conditions that must be true to apply Theorem 10.13 to find the area of the region bounded by the graph of $r = f(\theta)$.
2. Explain why finding points of intersection of polar graphs may require further analysis beyond solving two equations simultaneously.

Area of a Polar Region **In Exercises 3–6, write an integral that represents the area of the shaded region of the figure. Do not evaluate the integral.**

3. $r = 4 \sin \theta$



4. $r = \cos 2\theta$



5. $r = 3 - 2 \sin \theta$



6. $r = 1 - \cos 2\theta$



Finding the Area of a Polar Region **In Exercises 7–18, find the area of the region.**

7. Interior of $r = 6 \sin \theta$

8. Interior of $r = 3 \cos \theta$

9. One petal of $r = 2 \cos 3\theta$

10. Two petals of $r = 4 \sin 3\theta$

11. Two petals of $r = \sin 8\theta$

12. Three petals of $r = \cos 5\theta$

13. Interior of $r = 6 + 5 \sin \theta$ (below the polar axis)

14. Interior of $r = 9 - \sin \theta$ (above the polar axis)

15. Interior of $r = 4 + \sin \theta$

16. Interior of $r = 1 - \cos \theta$

17. Interior of $r^2 = 4 \cos 2\theta$

18. Interior of $r^2 = 6 \sin 2\theta$

Finding the Area of a Polar Region **In Exercises 19–26, use a graphing utility to graph the polar equation. Find the area of the given region analytically.**

19. Inner loop of $r = 1 + 2 \cos \theta$

20. Inner loop of $r = 2 - 4 \cos \theta$

21. Inner loop of $r = 1 + 2 \sin \theta$

22. Inner loop of $r = 4 - 6 \sin \theta$

23. Between the loops of $r = 1 + 2 \cos \theta$

24. Between the loops of $r = 2(1 + 2 \sin \theta)$

25. Between the loops of $r = 3 - 6 \sin \theta$

26. Between the loops of $r = \frac{1}{2} + \cos \theta$

Finding Points of Intersection **In Exercises 27–34, find the points of intersection of the graphs of the equations.**

27. $r = 1 + \cos \theta$
$r = 1 - \cos \theta$



28. $r = 3(1 + \sin \theta)$
$r = 3(1 - \sin \theta)$



29. $r = 1 + \cos \theta$
$r = 1 - \sin \theta$



30. $r = 2 - 3 \cos \theta$
$r = \cos \theta$



31. $r = 4 - 5 \sin \theta$
$r = 3 \sin \theta$

32. $r = 3 + \sin \theta$
$r = 2 \csc \theta$

33. $r = \dfrac{\theta}{2}$
$r = 2$

34. $\theta = \dfrac{\pi}{4}$
$r = 2$

Writing **In Exercises 35 and 36, use a graphing utility to graph the polar equations and approximate the points of intersection of the graphs. Explain why the pole is not a point of intersection obtained by solving the equations simultaneously.**

35. $r = \cos \theta$
$r = 2 - 3 \sin \theta$

36. $r = 4 \sin \theta$
$r = 2(1 + \sin \theta)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding the Area of a Polar Region Between Two Curves **In Exercises 37–44, use a graphing utility to graph the polar equations. Find the area of the given region analytically.**

37. Common interior of $r = 4 \sin 2\theta$ and $r = 2$

38. Common interior of $r = 2(1 + \cos\theta)$ and $r = 2(1 - \cos\theta)$

39. Common interior of $r = 3 - 2\sin\theta$ and $r = -3 + 2\sin\theta$

40. Common interior of $r = 5 - 3\sin\theta$ and $r = 5 - 3\cos\theta$

41. Common interior of $r = 4\sin\theta$ and $r = 2$

42. Common interior of $r = 2\cos\theta$ and $r = 2\sin\theta$

43. Inside $r = 2\cos\theta$ and outside $r = 1$

44. Inside $r = 3\sin\theta$ and outside $r = 1 + \sin\theta$

Finding the Area of a Polar Region Between Two Curves **In Exercises 45–48, find the area of the region.**

45. Inside $r = a(1 + \cos\theta)$ and outside $r = a\cos\theta$

46. Inside $r = 2a\cos\theta$ and outside $r = a$

47. Common interior of $r = a(1 + \cos\theta)$ and $r = a\sin\theta$

48. Common interior of $r = a\cos\theta$ and $r = a\sin\theta$, where $a > 0$

49. Antenna Radiation

The radiation from a transmitting antenna is not uniform in all directions. The intensity from a particular antenna is modeled by $r = a\cos^2\theta$.

(a) Convert the polar equation to rectangular form.

(b) Use a graphing utility to graph the model for $a = 4$ and $a = 6$.

(c) Find the area of the geographical region between the two curves in part (b).

50. Area The area inside one or more of the three interlocking circles $r = 2a\cos\theta$, $r = 2a\sin\theta$, and $r = a$ is divided into seven regions. Find the area of each region.

51. Conjecture Find the area of the region enclosed by

$$r = a\cos(n\theta)$$

for $n = 1, 2, 3, \ldots$. Use the results to make a conjecture about the area enclosed by the function when n is even and when n is odd.

52. Area Sketch the strophoid

$$r = \sec\theta - 2\cos\theta, \quad -\frac{\pi}{2} < \theta < \frac{\pi}{2}.$$

Convert this equation to rectangular coordinates. Find the area enclosed by the loop.

Finding the Arc Length of a Polar Curve **In Exercises 53–58, find the length of the curve over the given interval.**

53. $r = 8, \quad \left[0, \frac{\pi}{6}\right]$

54. $r = a, \quad [0, 2\pi]$

55. $r = 4\sin\theta, \quad [0, \pi]$

56. $r = 2a\cos\theta, \quad \left[-\frac{\pi}{4}, \frac{\pi}{4}\right]$

57. $r = 1 + \sin\theta, \quad [0, 2\pi]$

58. $r = 8(1 + \cos\theta), \quad \left[0, \frac{\pi}{3}\right]$

Finding the Arc Length of a Polar Curve **In Exercises 59–64, use a graphing utility to graph the polar equation over the given interval. Use the integration capabilities of the graphing utility to approximate the length of the curve.**

59. $r = 2\theta, \quad \left[0, \frac{\pi}{2}\right]$

60. $r = \sec\theta, \quad \left[0, \frac{\pi}{3}\right]$

61. $r = \frac{1}{\theta}, \quad [\pi, 2\pi]$

62. $r = e^{\theta}, \quad [0, \pi]$

63. $r = \sin(3\cos\theta), \quad [0, \pi]$

64. $r = 2\sin(2\cos\theta), \quad [0, \pi]$

Finding the Area of a Surface of Revolution **In Exercises 65–68, find the area of the surface formed by revolving the polar equation over the given interval about the given line.**

	Polar Equation	Interval	Axis of Revolution
65.	$r = 6\cos\theta$	$0 \le \theta \le \frac{\pi}{2}$	Polar axis
66.	$r = a\cos\theta$	$0 \le \theta \le \frac{\pi}{2}$	$\theta = \frac{\pi}{2}$
67.	$r = e^{a\theta}$	$0 \le \theta \le \frac{\pi}{2}$	$\theta = \frac{\pi}{2}$
68.	$r = a(1 + \cos\theta)$	$0 \le \theta \le \pi$	Polar axis

Finding the Area of a Surface of Revolution **In Exercises 69 and 70, use the integration capabilities of a graphing utility to approximate the area of the surface formed by revolving the polar equation over the given interval about the polar axis.**

69. $r = 4\cos 2\theta, \quad \left[0, \frac{\pi}{4}\right]$

70. $r = \theta, \quad [0, \pi]$

Exploring Concepts

In Exercises 71 and 72, (a) sketch the graph of the polar equation, (b) determine the interval that traces the graph only once, (c) find the area of the region bounded by the graph using a geometric formula, and (d) find the area of the region bounded by the graph using integration.

71. $r = 10\cos\theta$

72. $r = 5\sin\theta$

73. Let $f(\theta) > 0$ for all θ and let $g(\theta) < 0$ for all θ. Find polar equations $r = f(\theta)$ and $r = g(\theta)$ such that their graphs intersect.

This Lama/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

74. HOW DO YOU SEE IT? Which graph, traced out only once, has a larger arc length? Explain your reasoning.

(a)



(b)



75. Surface Area of a Torus Find the surface area of the torus generated by revolving the circle given by $r = 2$ about the line $r = 5 \sec \theta$.

76. Surface Area of a Torus Find the surface area of the torus generated by revolving the circle given by $r = a$ about the line $r = b \sec \theta$, where $0 < a < b$.

77. Approximating Area Consider the circle

$r = 8 \cos \theta$.

(a) Find the area of the circle.

(b) Complete the table for the areas A of the sectors of the circle between $\theta = 0$ and the values of θ in the table.

θ	0.2	0.4	0.6	0.8	1.0	1.2	1.4
A							

(c) Use the table in part (b) to approximate the values of θ for which the sector of the circle composes $\frac{1}{4}$, $\frac{1}{2}$, and $\frac{3}{4}$ of the total area of the circle.

(d) Use a graphing utility to approximate, to two decimal places, the angles θ for which the sector of the circle composes $\frac{1}{4}$, $\frac{1}{2}$, and $\frac{3}{4}$ of the total area of the circle.

(e) Do the results of part (d) depend on the radius of the circle? Explain.

78. Approximating Area Consider the circle

$r = 3 \sin \theta$.

(a) Find the area of the circle.

(b) Complete the table for the areas A of the sectors of the circle between $\theta = 0$ and the values of θ in the table.

θ	0.2	0.4	0.6	0.8	1.0	1.2	1.4
A							

(c) Use the table in part (b) to approximate the values of θ for which the sector of the circle composes $\frac{1}{8}$, $\frac{1}{4}$, and $\frac{1}{2}$ of the total area of the circle.

(d) Use a graphing utility to approximate, to two decimal places, the angles θ for which the sector of the circle composes $\frac{1}{8}$, $\frac{1}{4}$, and $\frac{1}{2}$ of the total area of the circle.

79. Spiral of Archimedes The curve represented by the equation $r = a\theta$, where a is a constant, is called the **spiral of Archimedes.**

(a) Use a graphing utility to graph $r = \theta$, where $\theta \geq 0$. What happens to the graph of $r = a\theta$ as a increases? What happens if $\theta \leq 0$?

(b) Determine the points on the spiral $r = a\theta$ $(a > 0, \theta \geq 0)$, where the curve crosses the polar axis.

(c) Find the length of $r = \theta$ over the interval $0 \leq \theta \leq 2\pi$.

(d) Find the area under the curve $r = \theta$ for $0 \leq \theta \leq 2\pi$.

80. Logarithmic Spiral The curve represented by the equation $r = ae^{b\theta}$, where a and b are constants, is called a **logarithmic spiral.** The figure shows the graph of $r = e^{\theta/6}$, $-2\pi \leq \theta \leq 2\pi$. Find the area of the shaded region.



81. Area The larger circle in the figure is the graph of $r = 1$. Find the polar equation of the smaller circle such that the shaded regions are equal.



82. Area Find the area of the circle given by

$r = \sin \theta + \cos \theta$.

Check your result by converting the polar equation to rectangular form, then using the formula for the area of a circle.

83. Folium of Descartes A curve called the **folium of Descartes** can be represented by the parametric equations

$$x = \frac{3t}{1 + t^3} \quad \text{and} \quad y = \frac{3t^2}{1 + t^3}.$$

(a) Convert the parametric equations to polar form.

(b) Sketch the graph of the polar equation from part (a).

(c) Use a graphing utility to approximate the area enclosed by the loop of the curve.

84. Arc Length in Polar Form Use the formula for the arc length of a curve in parametric form to derive the formula for the arc length of a polar curve.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

10.6 Polar Equations of Conics and Kepler's Laws

GO DIGITAL

- **Analyze and write polar equations of conics.**
- **Describe Kepler's Laws of planetary motion.**

Exploration

Graphing Conics Set a graphing utility to *polar* mode and enter polar equations of the form

$$r = \frac{a}{1 \pm b \cos \theta}$$

or

$$r = \frac{a}{1 \pm b \sin \theta}.$$

As long as $a \neq 0$, the graph should be a conic. What values of a and b produce parabolas? What values produce ellipses? What values produce hyperbolas?

Polar Equations of Conics

In this chapter, you have learned that the rectangular equations of ellipses and hyperbolas take simple forms when the origin lies at their *centers*. As it happens, there are many important applications of conics in which it is more convenient to use one of the foci as the reference point (the origin) for the coordinate system. Here are two examples.

1. The sun lies at a focus of Earth's orbit.
2. The light source of a parabolic reflector lies at its focus.

In this section, you will learn that the polar equations of conics take simpler forms when one of the foci lies at the pole.

The next theorem uses the concept of *eccentricity*, as defined in Section 10.1, to classify the three basic types of conics.

THEOREM 10.16 Classification of Conics by Eccentricity

Let F be a fixed point (*focus*) and let D be a fixed line (*directrix*) in the plane. Let P be another point in the plane and let e (*eccentricity*) be the ratio of the distance between P and F to the distance between P and D. The collection of all points P with a given eccentricity is a conic.

1. The conic is an ellipse for $0 < e < 1$.
2. The conic is a parabola for $e = 1$.
3. The conic is a hyperbola for $e > 1$.

A proof of this theorem is given in Appendix A.

In Figure 10.57, note that for each type of conic, the pole corresponds to the fixed point (focus) given in the definition.



Ellipse: $0 < e < 1$

$\frac{PF}{PQ} < 1$

Parabola: $e = 1$

$PF = PQ$

Hyperbola: $e > 1$

$\frac{PF}{PQ} = \frac{P'F}{P'Q'} > 1$

Figure 10.57

The benefit of locating a focus of a conic at the pole is that the equation of the conic becomes simpler, as shown in the proof of the next theorem.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

THEOREM 10.17 Polar Equations of Conics

The graph of a polar equation of the form

$$r = \frac{ed}{1 \pm e\cos\theta} \quad \text{or} \quad r = \frac{ed}{1 \pm e\sin\theta}$$

is a conic, where $e > 0$ is the eccentricity and $|d|$ is the distance between the focus at the pole and its corresponding directrix.



Figure 10.58

Proof This is a proof for $r = ed/(1 + e\cos\theta)$ with $d > 0$. In Figure 10.58, consider a vertical directrix d units to the right of the focus $F = (0, 0)$. If $P = (r, \theta)$ is a point on the graph of $r = ed/(1 + e\cos\theta)$, then the distance between P and the directrix can be shown to be

$$PQ = |d - x| = |d - r\cos\theta| = \left|\frac{r(1 + e\cos\theta)}{e} - r\cos\theta\right| = \left|\frac{r}{e}\right|.$$

Because the distance between P and the pole is simply $PF = |r|$, the ratio of PF to PQ is

$$\frac{PF}{PQ} = \frac{|r|}{|r/e|} = |e| = e$$

and, by Theorem 10.16, the graph of the equation must be a conic. The proofs of the other cases are similar. ∎

The four types of equations indicated in Theorem 10.17 can be classified as shown below, where $d > 0$.

a. Horizontal directrix above the pole: $r = \dfrac{ed}{1 + e\sin\theta}$

b. Horizontal directrix below the pole: $r = \dfrac{ed}{1 - e\sin\theta}$

c. Vertical directrix to the right of the pole: $r = \dfrac{ed}{1 + e\cos\theta}$

d. Vertical directrix to the left of the pole: $r = \dfrac{ed}{1 - e\cos\theta}$

Figure 10.59 illustrates these four possibilities for a parabola. Note that for convenience, the equation for the directrix is shown in rectangular form.



(a) **(b)** **(c)** **(d)**

The four types of polar equations for a parabola

Figure 10.59

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

EXAMPLE 1 Determining a Conic from Its Equation

Sketch the graph of the conic $r = \dfrac{15}{3 - 2\cos\theta}$.

Solution To determine the type of conic, rewrite the equation as

$$r = \frac{15}{3 - 2\cos\theta} \qquad \text{Write original equation.}$$

$$= \frac{5}{1 - (2/3)\cos\theta}. \qquad \text{Divide numerator and denominator by 3.}$$

So, the graph is an ellipse with $e = \frac{2}{3}$. You can sketch the upper half of the ellipse by plotting points from $\theta = 0$ to $\theta = \pi$, as shown in Figure 10.60. Then, using symmetry with respect to the polar axis, you can sketch the lower half. ■



The graph of the conic is an ellipse with $e = \frac{2}{3}$.
Figure 10.60

For the ellipse in Figure 10.60, the major axis is horizontal and the vertices lie at $(15, 0)$ and $(3, \pi)$. So, the length of the *major* axis is $2a = 18$. To find the length of the minor axis, use the equations $e = c/a$ and $b^2 = a^2 - c^2$ to conclude that

$$b^2 = a^2 - c^2 = a^2 - (ea)^2 = a^2(1 - e^2). \qquad \text{Ellipse}$$

Because $e = \frac{2}{3}$, you have

$$b^2 = 9^2\left[1 - \left(\frac{2}{3}\right)^2\right] = 45$$

which implies that $b = \sqrt{45} = 3\sqrt{5}$. So, the length of the minor axis is $2b = 6\sqrt{5}$. A similar analysis for hyperbolas yields

$$b^2 = c^2 - a^2 = (ea)^2 - a^2 = a^2(e^2 - 1). \qquad \text{Hyperbola}$$

EXAMPLE 2 Sketching a Conic from Its Polar Equation

See LarsonCalculus.com for an interactive version of this type of example.

Sketch the graph of the polar equation $r = \dfrac{32}{3 + 5\sin\theta}$.

Solution Dividing the numerator and denominator by 3 produces

$$r = \frac{32/3}{1 + (5/3)\sin\theta}.$$

Because $e = \frac{5}{3} > 1$, the graph is a hyperbola. Because $d = \frac{32}{5}$, the directrix is the line $y = \frac{32}{5}$. The transverse axis of the hyperbola lies on the line $\theta = \pi/2$, and the vertices occur at

$$(r, \theta) = \left(4, \frac{\pi}{2}\right) \quad \text{and} \quad (r, \theta) = \left(-16, \frac{3\pi}{2}\right).$$

The length of the transverse axis is 12, so $a = 6$. To find b, write

$$b^2 = a^2(e^2 - 1) = 6^2\left[\left(\frac{5}{3}\right)^2 - 1\right] = 64.$$

So, $b = 8$. Finally, you can use a and b to determine the asymptotes of the hyperbola and obtain the sketch shown in Figure 10.61. ■



The graph of the conic is a hyperbola with $e = \frac{5}{3}$.
Figure 10.61

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

JOHANNES KEPLER (1571–1630)

Kepler formulated his three laws from the extensive data recorded by Danish astronomer Tycho Brahe and from direct observation of the orbit of Mars.

See LarsonCalculus.com to read more of this biography.

Kepler's Laws

Kepler's Laws, named after the German astronomer Johannes Kepler, can be used to describe the orbits of the planets about the sun.

1. Each planet moves in an elliptical orbit with the sun as a focus.
2. A ray from the sun to the planet sweeps out equal areas of the ellipse in equal times.
3. The square of the period is proportional to the cube of the mean distance between the planet and the sun.*

Although Kepler derived these laws empirically, they were later validated by Newton. In fact, Newton was able to show that each law can be deduced from a set of universal laws of motion and gravitation that govern the movement of all heavenly bodies, including comets and satellites. This is shown in the next example, involving the comet named after the English mathematician and physicist Edmund Halley (1656–1742).

EXAMPLE 3 Halley's Comet

Halley's comet has an elliptical orbit with the sun at one focus and has an eccentricity of $e \approx 0.967$. The length of the major axis of the orbit is approximately 35.88 astronomical units (AU). (An astronomical unit is defined as the mean distance between Earth and the sun, which is 93 million miles.) Find a polar equation for the orbit. How close does Halley's comet come to the sun?

Solution Using a vertical axis, you can choose an equation of the form

$$r = \frac{ed}{1 + e \sin\theta}.$$

Because the vertices of the ellipse occur when $\theta = \pi/2$ and $\theta = 3\pi/2$, you can determine the length of the major axis to be the sum of the r-values of the vertices, as shown in Figure 10.62. That is,

$$2a = \frac{0.967d}{1 + 0.967} + \frac{0.967d}{1 - 0.967}$$

$$35.88 \approx 29.79d. \qquad 2a \approx 35.88$$

So, $d \approx 1.204$ and

$$ed \approx (0.967)(1.204) \approx 1.164.$$

Using this value in the equation produces

$$r = \frac{1.164}{1 + 0.967 \sin\theta}$$

where r is measured in astronomical units. To find the closest point to the sun (the focus), you can write

$$c = ea \approx (0.967)(17.94) \approx 17.35.$$

Because c is the distance between the focus and the center, the closest point is

$$\begin{aligned} a - c &\approx 17.94 - 17.35 \\ &= 0.59 \text{ AU} \\ &\approx 55{,}000{,}000 \text{ miles}. \end{aligned}$$



Figure 10.62

* If Earth is used as a reference with a period of 1 year and a distance of 1 astronomical unit, then the proportionality constant is 1. For example, because Mars has a mean distance to the sun of $D \approx 1.524$ AU, its period P is $D^3 = P^2$. So, the period for Mars is $P \approx 1.88$ years.

GO DIGITAL

Hilary Morgan/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Kepler's Second Law states that as a planet moves about the sun, a ray from the sun to the planet sweeps out equal areas in equal times. This law can also be applied to comets or asteroids with elliptical orbits. For example, Figure 10.63 shows the orbit of the asteroid Apollo about the sun. Applying Kepler's Second Law to this asteroid, you know that the closer it is to the sun, the greater its velocity, because a short ray must be moving quickly to sweep out as much area as a long ray.



A ray from the sun to the asteroid Apollo sweeps out equal areas in equal times.
Figure 10.63

EXAMPLE 4 The Asteroid Apollo



Figure 10.64

The asteroid Apollo has a period of about 661 Earth days, and its orbit is approximated by the ellipse

$$r = \frac{1}{1 + (5/9)\cos\theta} = \frac{9}{9 + 5\cos\theta}$$

where r is measured in astronomical units. How long does it take Apollo to move from the position $\theta = -\pi/2$ to $\theta = \pi/2$, as shown in Figure 10.64?

Solution Begin by finding the area swept out as θ increases from $-\pi/2$ to $\pi/2$.

$$A = \frac{1}{2}\int_{\alpha}^{\beta} r^2\, d\theta \qquad \text{Formula for area of a polar graph}$$

$$= \frac{1}{2}\int_{-\pi/2}^{\pi/2} \left(\frac{9}{9 + 5\cos\theta}\right)^2 d\theta$$

Using the substitution $u = \tan(\theta/2)$, as discussed in Section 8.7, you obtain

$$A = \frac{81}{112}\left[\frac{-5\sin\theta}{9 + 5\cos\theta} + \frac{18}{\sqrt{56}}\arctan\frac{\sqrt{56}\tan(\theta/2)}{14}\right]_{-\pi/2}^{\pi/2} \approx 0.90429.$$

Because the major axis of the ellipse has length $2a = 81/28$ and the eccentricity is $e = 5/9$, you can determine that

$$b = a\sqrt{1 - e^2} = \frac{9}{\sqrt{56}}.$$

So, the area of the ellipse is

$$\text{Area of ellipse} = \pi ab = \pi\left(\frac{81}{56}\right)\left(\frac{9}{\sqrt{56}}\right) \approx 5.46507.$$

Because the time required to complete the orbit is 661 days, you can apply Kepler's Second Law to conclude that the time t required to move from the position $\theta = -\pi/2$ to $\theta = \pi/2$ is

$$\frac{t}{661} = \frac{\text{area of elliptical segment}}{\text{area of ellipse}} \approx \frac{0.90429}{5.46507}$$

which implies that $t \approx 109$ days.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

10.6 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Identify each conic using eccentricity.

(a) $r = \dfrac{4}{1 + 3\sin\theta}$ (b) $r = \dfrac{7}{1 - \cos\theta}$

(c) $r = \dfrac{8}{6 + 5\cos\theta}$ (d) $r = \dfrac{3}{2 - 3\sin\theta}$

2. Without graphing, how are the graphs of the following conics different? Explain.

$r = \dfrac{1}{1 + \sin\theta}$ and $r = \dfrac{1}{1 - \sin\theta}$

Graphing a Conic **In Exercises 3 and 4, use a graphing utility to graph the polar equation when (a) $e = 1$, (b) $e = 0.5$, and (c) $e = 1.5$. Identify the conic.**

3. $r = \dfrac{2e}{1 + e\cos\theta}$

4. $r = \dfrac{2e}{1 - e\sin\theta}$

Writing **In Exercises 5 and 6, consider the polar equation**

$$r = \frac{4}{1 + e\sin\theta}.$$

5. Use a graphing utility to graph the equation for $e = 0.1$, $e = 0.25$, $e = 0.5$, $e = 0.75$, and $e = 0.9$. Identify the conic and discuss the change in its shape as $e \to 1^-$ and $e \to 0^+$.

6. Use a graphing utility to graph the equation for $e = 1.1$, $e = 1.5$, and $e = 2$. Identify the conic and discuss the change in its shape as $e \to 1^+$ and $e \to \infty$.

Matching **In Exercises 7–12, match the polar equation with its correct graph. [The graphs are labeled (a), (b), (c), (d), (e), and (f).]**

(a)



(b)



(c)



(d)



(e)



(f)



7. $r = \dfrac{6}{1 - \cos\theta}$

8. $r = \dfrac{2}{2 - \cos\theta}$

9. $r = \dfrac{3}{1 - 2\sin\theta}$

10. $r = \dfrac{2}{1 + \sin\theta}$

11. $r = \dfrac{6}{2 - \sin\theta}$

12. $r = \dfrac{2}{2 + 3\cos\theta}$

Identifying and Sketching a Conic **In Exercises 13–22, find the eccentricity and the distance from the pole to the directrix of the conic. Then identify the conic and sketch its graph. Use a graphing utility to confirm your results.**

13. $r = \dfrac{1}{1 - \cos\theta}$

14. $r = \dfrac{5}{5 - 3\cos\theta}$

15. $r = \dfrac{7}{4 + 8\sin\theta}$

16. $r = \dfrac{4}{1 + \cos\theta}$

17. $r = \dfrac{6}{-2 + 3\cos\theta}$

18. $r = \dfrac{10}{5 + 4\sin\theta}$

19. $r = \dfrac{6}{2 + \cos\theta}$

20. $r = \dfrac{-6}{3 + 7\sin\theta}$

21. $r = \dfrac{300}{-12 + 6\sin\theta}$

22. $r = \dfrac{24}{25 + 25\cos\theta}$

Identifying a Conic **In Exercises 23–26, use a graphing utility to graph the polar equation. Identify the graph and find its eccentricity.**

23. $r = \dfrac{3}{-4 + 2\sin\theta}$

24. $r = \dfrac{-15}{2 + 8\sin\theta}$

25. $r = \dfrac{-10}{1 - \cos\theta}$

26. $r = \dfrac{6}{6 + 7\cos\theta}$

Comparing Graphs **In Exercises 27–30, use a graphing utility to graph the conic. Describe how the graph differs from the graph in the indicated exercise.**

27. $r = \dfrac{4}{1 + \cos(\theta - \pi/3)}$ (See Exercise 16.)

28. $r = \dfrac{10}{5 + 4\sin(\theta - \pi/4)}$ (See Exercise 18.)

29. $r = \dfrac{6}{2 + \cos(\theta + \pi/6)}$ (See Exercise 19.)

30. $r = \dfrac{-6}{3 + 7\sin(\theta + 2\pi/3)}$ (See Exercise 20.)

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

31. Rotated Ellipse Write the equation for the ellipse rotated $\pi/6$ radian clockwise from the ellipse

$$r = \frac{8}{8 + 5\cos\theta}.$$

32. Rotated Parabola Write the equation for the parabola rotated $\pi/4$ radian counterclockwise from the parabola

$$r = \frac{9}{1 + \sin\theta}.$$

Finding a Polar Equation **In Exercises 33–38, find a polar equation for the conic with its focus at the pole and the given eccentricity and directrix. (For convenience, the equation for the directrix is given in rectangular form.)**

Conic	Eccentricity	Directrix
33. Parabola	$e = 1$	$x = -3$
34. Parabola	$e = 1$	$y = 4$
35. Ellipse	$e = \frac{1}{4}$	$y = 1$
36. Ellipse	$e = \frac{5}{6}$	$y = -2$
37. Hyperbola	$e = \frac{4}{3}$	$x = 2$
38. Hyperbola	$e = \frac{3}{2}$	$x = -1$

Finding a Polar Equation **In Exercises 39–44, find a polar equation for the conic with its focus at the pole and the given vertex or vertices.**

Conic	Vertex or Vertices
39. Parabola	$\left(1, -\frac{\pi}{2}\right)$
40. Parabola	$(5, \pi)$
41. Ellipse	$(2, 0), \quad (8, \pi)$
42. Ellipse	$\left(2, \frac{\pi}{2}\right), \quad \left(4, \frac{3\pi}{2}\right)$
43. Hyperbola	$\left(1, \frac{3\pi}{2}\right), \quad \left(9, \frac{3\pi}{2}\right)$
44. Hyperbola	$(2, 0), \quad (10, 0)$

Exploring Concepts

45. Consider two ellipses, where the foci of the first ellipse are farther apart than the foci of the second ellipse. Is the eccentricity of the first ellipse always greater than the eccentricity of the second ellipse? Explain.

46. Describe what happens to the distance between the directrix and the center of an ellipse when the foci remain fixed and e approaches 0.

47. Finding a Polar Equation Find a polar equation for the ellipse with the following characteristics.

Focus: $(0, 0)$

Eccentricity: $e = \frac{1}{2}$

Directrix: $r = 4 \sec\theta$

48. HOW DO YOU SEE IT? Identify the conic in the graph and give the possible values for the eccentricity.



49. Ellipse Show that the polar equation for $\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$ is

$$r^2 = \frac{b^2}{1 - e^2\cos^2\theta}.$$ Ellipse

50. Hyperbola Show that the polar equation for $\frac{x^2}{a^2} - \frac{y^2}{b^2} = 1$ is

$$r^2 = \frac{-b^2}{1 - e^2\cos^2\theta}.$$ Hyperbola

Finding a Polar Equation **In Exercises 51–54, use the results of Exercises 49 and 50 to write the polar form of the equation of the conic.**

51. Ellipse: focus at $(4, 0)$; vertices at $(5, 0)$, $(5, \pi)$

52. Hyperbola: focus at $(5, 0)$; vertices at $(4, 0)$, $(4, \pi)$

53. $\frac{x^2}{9} - \frac{y^2}{16} = 1$

54. $\frac{x^2}{4} + y^2 = 1$

Area of a Region **In Exercises 55–58, use the integration capabilities of a graphing utility to approximate the area of the region bounded by the graph of the polar equation.**

55. $r = \frac{3}{2 - \cos\theta}$

56. $r = \frac{9}{4 + \cos\theta}$

57. $r = \frac{2}{7 - 6\sin\theta}$

58. $r = \frac{3}{6 + 5\sin\theta}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

59. Explorer 18 On November 27, 1963, the United States launched Explorer 18. Its low and high points above the surface of Earth were approximately 119 miles and 123,000 miles (see figure). The center of Earth is a focus of the orbit. Find the polar equation for the orbit and find the distance between the surface of Earth and the satellite when $\theta = 60°$. (Assume that the radius of Earth is 4000 miles.)



60. Planetary Motion The planets travel in elliptical orbits with the sun as a focus, as shown in the figure.



(a) Show that the polar equation of the orbit is given by

$$r = \frac{(1 - e^2)a}{1 - e\cos\theta}$$

where e is the eccentricity.

(b) Show that the minimum distance (*perihelion*) from the sun to the planet is $r = a(1 - e)$ and the maximum distance (*aphelion*) is $r = a(1 + e)$.

Planetary Motion **In Exercises 61–64, use Exercise 60 to find the polar equation of the elliptical orbit of the planet and the perihelion and aphelion distances.**

61. Earth

$a = 1.496 \times 10^8$ kilometers

$e = 0.0167$

62. Saturn

$a = 1.434 \times 10^9$ kilometers

$e = 0.0565$

63. Neptune

$a = 4.495 \times 10^9$ kilometers

$e = 0.0113$

64. Mercury

$a = 5.791 \times 10^7$ kilometers

$e = 0.2056$

NASA images/Shutterstock.com

65. Planetary Motion

In Exercise 63, the polar equation for the elliptical orbit of Neptune was found. Use the equation and a graphing utility to perform each of the following.

(a) Approximate the area swept out by a ray from the sun to the planet as θ increases from 0 to $\pi/9$. Use this result to determine the number of years required for the planet to move through this arc when the period of one revolution around the sun is 165 years.

(b) By trial and error, approximate the angle α such that the area swept out by a ray from the sun to the planet as θ increases from π to α equals the area found in part (a) (see figure). Does the ray sweep through a larger or smaller angle than in part (a) to generate the same area? Why is this the case?



(c) Approximate the distances the planet traveled in parts (a) and (b). Use these distances to approximate the average number of kilometers per year the planet traveled in the two cases.

66. Comet Hale-Bopp The comet Hale-Bopp has an elliptical orbit with the sun at one focus and has an eccentricity of $e \approx 0.995$. The length of the major axis of the orbit is approximately 500 astronomical units. (a) Find the length of its minor axis. (b) Find a polar equation for the orbit. (c) Find the perihelion and aphelion distances.

Eccentricity **In Exercises 67 and 68, let r_0 represent the distance from a focus to the nearest vertex, and let r_1 represent the distance from the focus to the farthest vertex.**

67. Show that the eccentricity of an ellipse can be written as

$$e = \frac{r_1 - r_0}{r_1 + r_0}.$$

Then show that $\dfrac{r_1}{r_0} = \dfrac{1 + e}{1 - e}$.

68. Show that the eccentricity of a hyperbola can be written as

$$e = \frac{r_1 + r_0}{r_1 - r_0}.$$

Then show that $\dfrac{r_1}{r_0} = \dfrac{e + 1}{e - 1}$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Review Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Exploring Concepts

Some of the topics in this chapter, conics, parametric equations, and polar coordinates, are ones you may have studied in precalculus. Using calculus concepts with these topics gives you flexibility in solving many problems. For instance, here are two ways to find the area of the region common to the two regions bounded by the curves

$$r = -6\cos\theta \quad \text{and} \quad r = 2 - 2\cos\theta$$

shown in the figure. The first integral gives the area in polar coordinates and the second integral gives the area in rectangular coordinates. Clearly, the first integral is easier to evaluate than the second one.

$$\frac{1}{2}\int_{\pi/2}^{2\pi/3} (-6\cos\theta)^2\,d\theta + \frac{1}{2}\int_{2\pi/3}^{\pi} (2 - 2\cos\theta)^2\,d\theta \qquad \text{Polar}$$

$$\int_{-4}^{-3/2} \sqrt{2\sqrt{1-2x} - x^2 - 2x + 2}\,dx + \int_{-3/2}^{0} \sqrt{-x^2 - 6x}\,dx \qquad \text{Rectangular}$$



In addition to area, there are many other applications where conics, parametric equations, and polar coordinates are useful, such as projectile motion, arc length, and planetary motion.

1. Use a sketch to illustrate the reflective property of an ellipse.

2. (a) Describe the curve given by the parametric equations $x = 4\sin t$ and $y = 4\cos t$.

(b) How does the curve given by the parametric equations

$$x = 7 + 4\sin t \quad \text{and} \quad y = -2 + 4\cos t$$

differ from the curve in part (a)?

(c) How does the curve given by the parametric equations

$$x = 4\cos t \quad \text{and} \quad y = 4\sin t$$

differ from the curve in part (a)?

3. Find a set of parametric equations $x = f(t)$ and $y = g(t)$ such that

$$\frac{dx}{dt} > 0 \quad \text{and} \quad \frac{dy}{dt} < 0$$

for all real numbers t. Then sketch a graph of the curve.

4. (a) Explain how to find the polar coordinates of a point (x, y) given in rectangular coordinates. Are the polar coordinates unique?

(b) Explain how to find the rectangular coordinates of a point (r, θ) given in polar coordinates. Are the rectangular coordinates unique?

5. The figure shows the graph of $r = 3/(1 + \sin\theta)$.



Explain how the graph of each conic in parts (a)–(d) differs from the one shown above.

(a) $r = \dfrac{3}{1 - \cos\theta}$ (b) $r = \dfrac{3}{1 - \sin\theta}$

(c) $r = \dfrac{3}{1 + \cos\theta}$ (d) $r = \dfrac{3}{1 - \sin(\theta - \pi/4)}$

6. Describe the graph of each polar equation.

(a) $r = 7$ (b) $r^2 = 7$

(c) $r = \dfrac{7}{\cos\theta}$ (d) $r = \dfrac{7}{\sin\theta}$

(e) $r = 7\cos\theta$ (f) $r = 7\sin\theta$

Identifying a Conic **In Exercises 7–14, identify the conic, analyze the equation (center, radius, vertices, foci, eccentricity, directrix, and asymptotes, if possible), and sketch its graph. Use a graphing utility to confirm your results.**

7. $x^2 + y^2 - 2x - 8y - 8 = 0$

8. $y^2 - 12y - 8x + 20 = 0$

9. $3x^2 - 2y^2 + 24x + 12y + 24 = 0$

10. $5x^2 + y^2 - 20x + 19 = 0$

11. $16x^2 + 16y^2 - 16x + 24y - 3 = 0$

12. $-4x^2 + 3y^2 - 16x - 18y + 10 = 0$

13. $x^2 + 10x - 12y + 13 = 0$

14. $9x^2 + 25y^2 + 18x - 100y - 116 = 0$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding the Standard Equation of a Parabola **In Exercises 15 and 16, find the standard form of the equation of the parabola with the given characteristics.**

15. Vertex: $(7, 0)$
Directrix: $x = 5$

16. Vertex: $(2, 6)$
Focus: $(2, 4)$

Finding the Standard Equation of an Ellipse **In Exercises 17–20, find the standard form of the equation of the ellipse with the given characteristics.**

17. Center: $(0, 1)$
Focus: $(4, 1)$
Vertex: $(6, 1)$

18. Center: $(0, 0)$
Major axis: vertical
Points on the ellipse: $(1, 2)$, $(2, 0)$

19. Vertices: $(3, 1)$, $(3, 7)$
Eccentricity: $\frac{2}{3}$

20. Foci: $(0, \pm 7)$
Major axis length: 20

Finding the Standard Equation of a Hyperbola **In Exercises 21–24, find the standard form of the equation of the hyperbola with the given characteristics.**

21. Vertices: $(0, \pm 8)$
Asymptotes: $y = \pm 2x$

22. Vertices: $(\pm 2, 0)$
Asymptotes: $y = \pm 32x$

23. Vertices: $(\pm 7, -1)$
Foci: $(\pm 9, -1)$

24. Center: $(0, 0)$
Vertex: $(0, 3)$
Focus: $(0, 6)$

Finding a Standard Equation **In Exercises 25–28, find the standard form of the equation of the parabola, ellipse, or hyperbola shown in the graph.**

25.



26.



27.



28.



29. Satellite Antenna A cross section of a large parabolic antenna is modeled by the graph of $y = x^2/200$, $-100 \le x \le 100$. The receiving and transmitting equipment is positioned at the focus.

(a) Find the coordinates of the focus.

(b) Find the surface area of the antenna.

30. Using an Ellipse Consider the ellipse $\frac{x^2}{25} + \frac{y^2}{9} = 1$.

(a) Find the area of the region bounded by the ellipse.

(b) Find the volume of the solid generated by revolving the region about its major axis.

Using Parametric Equations **In Exercises 31–38, sketch the curve represented by the parametric equations (indicate the orientation of the curve), and write the corresponding rectangular equation by eliminating the parameter.**

31. $x = 1 + 8t, \quad y = 3 - 4t$

32. $x = t - 2, \quad y = t^2 - 1$

33. $x = \sqrt{t} + 1, \quad y = t - 3$

34. $x = e^t - 1, \quad y = e^{3t}$

35. $x = 6 \cos \theta, \quad y = 6 \sin \theta$

36. $x = 2 + 5 \cos t, \quad y = 3 + 2 \sin t$

37. $x = 2 + \sec \theta, \quad y = 3 + \tan \theta$

38. $x = 5 \sin^3 \theta, \quad y = 5 \cos^3 \theta$

Finding Parametric Equations **In Exercises 39 and 40, find two different sets of parametric equations for the rectangular equation.**

39. $y = 4x + 3$

40. $y = x^2 - 2$

41. Rotary Engine The rotary engine was developed by Felix Wankel in the 1950s. It features a rotor that is a modified equilateral triangle. The rotor moves in a chamber that, in two dimensions, is an epitrochoid. Use a graphing utility to graph the chamber modeled by the parametric equations

$$x = \cos 3\theta + 5 \cos \theta \quad \text{and} \quad y = \sin 3\theta + 5 \sin \theta.$$

42. Serpentine Curve Consider the parametric equations $x = 2 \cot \theta$ and $y = 4 \sin \theta \cos \theta$, $0 < \theta < \pi$.

(a) Use a graphing utility to graph the curve.

(b) Eliminate the parameter to show that the rectangular equation of the serpentine curve is $(4 + x^2)y = 8x$.

Finding Slope and Concavity **In Exercises 43–50, find dy/dx and d^2y/dx^2, and find the slope and concavity (if possible) at the given value of the parameter.**

Parametric Equations	Parameter
43. $x = 1 + 6t, \quad y = 4 - 5t$	$t = 3$
44. $x = t - 6, \quad y = t^2$	$t = 5$
45. $x = \frac{1}{t}, \quad y = t^2$	$t = -2$
46. $x = \frac{1}{\sqrt{t}} + 1, \quad y = 3 - 2t$	$t = 4$
47. $x = e^t, \quad y = e^{-t}$	$t = 1$
48. $x = 5 + \cos \theta, \quad y = 3 + 4 \sin \theta$	$\theta = \frac{\pi}{6}$
49. $x = 10 \cos \theta, \quad y = 10 \sin \theta$	$\theta = \frac{\pi}{4}$
50. $x = \cos^4 \theta, \quad y = \sin^4 \theta$	$\theta = -\frac{\pi}{3}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding an Equation of a Tangent Line **In Exercises 51 and 52, (a) use a graphing utility to graph the curve represented by the parametric equations, (b) use a graphing utility to find $dx/d\theta$, $dy/d\theta$, and dy/dx at the given value of the parameter, (c) find an equation of the tangent line to the curve at the given value of the parameter, and (d) use a graphing utility to graph the curve and the tangent line from part (c).**

Parametric Equations	Parameter
51. $x = \cot\theta, \quad y = \sin 2\theta$	$\theta = \frac{\pi}{6}$
52. $x = \frac{1}{4}\tan\theta, \quad y = 6\sin\theta$	$\theta = \frac{\pi}{3}$

Horizontal and Vertical Tangency **In Exercises 53–56, find all points (if any) of horizontal and vertical tangency to the curve. Use a graphing utility to confirm your results.**

53. $x = 5 - t, \quad y = 2t^2$

54. $x = t + 2, \quad y = t^3 - 2t$

55. $x = 2 + 2\sin\theta, \quad y = 1 + \cos\theta$

56. $x = 2 - 2\cos\theta, \quad y = 2\sin 2\theta$

Arc Length **In Exercises 57 and 58, find the arc length of the curve on the given interval.**

Parametric Equations	Interval
57. $x = t^2 + 1, \quad y = 4t^3 + 3$	$0 \le t \le 2$
58. $x = 7\cos\theta, \quad y = 7\sin\theta$	$0 \le \theta \le \pi$

Surface Area **In Exercises 59 and 60, find the area of the surface generated by revolving the curve about (a) the x-axis and (b) the y-axis.**

59. $x = 4t, \quad y = 3t + 1, \quad 0 \le t \le 1$

60. $x = 2\cos\theta, \quad y = 2\sin\theta, \quad 0 \le \theta \le \frac{\pi}{2}$

Area **In Exercises 61 and 62, find the area of the region.**

61. $x = 3\sin\theta, \quad y = 2\cos\theta, \quad -\frac{\pi}{2} \le \theta \le \frac{\pi}{2}$



62. $x = 2\cos\theta, \quad y = \sin\theta, \quad 0 \le \theta \le \pi$



Polar-to-Rectangular Conversion **In Exercises 63–66, the polar coordinates of a point are given. Plot the point and find the corresponding rectangular coordinates for the point.**

63. $\left(5, \frac{3\pi}{2}\right)$

64. $\left(-6, \frac{5\pi}{6}\right)$

65. $\left(\sqrt{7}, 3.25\right)$

66. $(-2, -2.45)$

Rectangular-to-Polar Conversion **In Exercises 67–70, the rectangular coordinates of a point are given. Plot the point and find *two* sets of polar coordinates for the point for $0 \le \theta < 2\pi$.**

67. $(4, -4)$

68. $(0, -7)$

69. $(-1, 3)$

70. $\left(-\sqrt{3}, -\sqrt{3}\right)$

Rectangular-to-Polar Conversion **In Exercises 71–76, convert the rectangular equation to polar form and sketch its graph.**

71. $x^2 + y^2 = 25$

72. $x^2 - y^2 = 4$

73. $y = 9$

74. $x = 6$

75. $-x + 4y - 3 = 0$

76. $x^2 = 4y$

Polar-to-Rectangular Conversion **In Exercises 77–82, convert the polar equation to rectangular form and sketch its graph.**

77. $r = 6\cos\theta$

78. $r = 10$

79. $r = -4\sec\theta$

80. $r = 3\csc\theta$

81. $\theta = \frac{3\pi}{4}$

82. $r = -2\sec\theta\tan\theta$

Graphing a Polar Equation **In Exercises 83–86, use a graphing utility to graph the polar equation. Find an interval for θ over which the graph is traced *only once*.**

83. $r = \frac{3\pi}{2}\sin 3\theta$

84. $r = 2\sin\theta\cos^2\theta$

85. $r = 4\cos 2\theta\sec\theta$

86. $r = 4(\sec\theta - \cos\theta)$

Horizontal and Vertical Tangency **In Exercises 87 and 88, find the points of horizontal and vertical tangency (if any) to the polar curve.**

87. $r = 1 - \cos\theta$

88. $r = 3\tan\theta$

Tangent Lines at the Pole **In Exercises 89 and 90, sketch a graph of the polar equation and find the tangent lines at the pole.**

89. $r = 4\sin 3\theta$

90. $r = 3\cos 4\theta$

Sketching a Polar Graph **In Exercises 91–100, sketch a graph of the polar equation.**

91. $r = 6$

92. $\theta = \frac{\pi}{10}$

93. $r = -\sec\theta$

94. $r = 5\csc\theta$

95. $r = 4 - 3\cos\theta$

96. $r = 3 + 2\sin\theta$

97. $r = 4\theta$

98. $r = -3\cos 2\theta$

99. $r^2 = 4\sin 2\theta$

100. $r^2 = 9\cos 2\theta$

Finding the Area of a Polar Region **In Exercises 101–104, find the area of the region.**

101. One petal of $r = 3\cos 5\theta$

102. One petal of $r = 2\sin 6\theta$

103. Interior of $r = 2 + \cos\theta$

104. Interior of $r = 5(1 - \sin\theta)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding Points of Intersection **In Exercises 105 and 106, find the points of intersection of the graphs of the equations.**

105. $r = 1 - \cos\theta$, $r = 1 + \sin\theta$

106. $r = 1 + \sin\theta$, $r = 3\sin\theta$

Finding the Area of a Polar Region **In Exercises 107–112, use a graphing utility to graph the polar equation. Find the area of the given region analytically.**

107. Inner loop of $r = 3 - 6\cos\theta$

108. Inner loop of $r = 4 + 8\sin\theta$

109. Between the loops of $r = 3 - 6\cos\theta$

110. Between the loops of $r = 4 + 8\sin\theta$

111. Common interior of $r = 5 - 2\sin\theta$ and $r = -5 + 2\sin\theta$

112. Common interior of $r = 4\cos\theta$ and $r = 2$

Finding the Arc Length of a Polar Curve **In Exercises 113 and 114, find the length of the curve over the given interval.**

	Polar Equation	Interval
113.	$r = 5\cos\theta$	$\left[\frac{\pi}{2}, \pi\right]$
114.	$r = 3(1 - \cos\theta)$	$[0, \pi]$

Finding the Area of a Surface of Revolution **In Exercises 115 and 116, find the area of the surface formed by revolving the polar equation over the given interval about the given line.**

	Polar Equation	Interval	Axis of Revolution
115.	$r = 2\sin\theta$	$0 \le \theta \le \pi$	Polar axis
116.	$r = 2\sin\theta$	$0 \le \theta \le \frac{\pi}{2}$	$\theta = \frac{\pi}{2}$

Identifying and Sketching a Conic **In Exercises 117–122, find the eccentricity and the distance from the pole to the directrix of the conic. Then identify the conic and sketch its graph. Use a graphing utility to confirm your results.**

117. $r = \dfrac{6}{1 - \sin\theta}$

118. $r = \dfrac{2}{1 + \cos\theta}$

119. $r = \dfrac{6}{3 + 2\cos\theta}$

120. $r = \dfrac{4}{5 - 3\sin\theta}$

121. $r = \dfrac{4}{2 - 3\sin\theta}$

122. $r = \dfrac{8}{2 - 5\cos\theta}$

Finding a Polar Equation **In Exercises 123–126, find a polar equation for the conic with its focus at the pole and the given eccentricity and directrix. (For convenience, the equation for the directrix is given in rectangular form.)**

	Conic	Eccentricity	Directrix
123.	Parabola	$e = 1$	$x = 5$
124.	Ellipse	$e = \frac{3}{4}$	$y = -2$
125.	Hyperbola	$e = 3$	$y = 3$
126.	Hyperbola	$e = \frac{5}{2}$	$x = -1$

Finding a Polar Equation **In Exercises 127–130, find a polar equation for the conic with its focus at the pole and the given vertex or vertices.**

	Conic	Vertex or Vertices
127.	Parabola	$\left(2, \frac{\pi}{2}\right)$
128.	Parabola	$(3, \pi)$
129.	Ellipse	$(5, 0), (1, \pi)$
130.	Hyperbola	$(1, 0), (7, 0)$

Building on Concepts

131. Consider the hyperbola

$$\frac{x^2}{a^2} - \frac{y^2}{b^2} = 1$$

with foci F_1 and F_2, as shown in the figure. Let T be the tangent line at a point M on the hyperbola. Show that incoming rays of light aimed at one focus are reflected by a hyperbolic mirror toward the other focus.



132. Four dogs are located at the corners of a square with side length d. The dogs all move counterclockwise at the same speed directly toward the next dog, as shown in the figure. Find the polar equation of a dog's path as it spirals toward the center of the square. (Assume the pole is at the center of the square.)



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.S. Problem Solving

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

1. Using a Parabola Consider the parabola

$x^2 = 4y$

and the focal chord

$y = \frac{3}{4}x + 1$.

(a) Sketch the graph of the parabola and the focal chord.

(b) Show that the tangent lines to the parabola at the endpoints of the focal chord intersect at right angles.

(c) Show that the tangent lines to the parabola at the endpoints of the focal chord intersect on the directrix of the parabola.

2. Area Let a and b be positive constants. Find the area of the region in the first quadrant bounded by the graph of the polar equation

$$r = \frac{ab}{(a \sin\theta + b \cos\theta)}, \quad 0 \le \theta \le \frac{\pi}{2}.$$

3. Proof Prove Theorem 10.2, Reflective Property of a Parabola, as shown in the figure.



4. Flight Paths An air traffic controller spots two planes at the same altitude flying toward each other (see figure). Their flight paths are 20° and 315°. One plane is 150 miles from point P with a speed of 375 miles per hour. The other is 190 miles from point P with a speed of 450 miles per hour.



(a) Find parametric equations for the path of each plane where t is the time in hours, with $t = 0$ corresponding to the time at which the air traffic controller spots the planes.

(b) Use the result of part (a) to write the distance between the planes as a function of t.

(c) Use a graphing utility to graph the function in part (b). When will the distance between the planes be minimum? If the planes must keep a separation of at least 3 miles, is the requirement met?

5. Strophoid The curve given by the parametric equations

$$x(t) = \frac{1 - t^2}{1 + t^2} \quad \text{and} \quad y(t) = \frac{t(1 - t^2)}{1 + t^2}$$

is called a **strophoid.**

(a) Find a rectangular equation of the strophoid.

(b) Find a polar equation of the strophoid.

(c) Sketch a graph of the strophoid.

(d) Find the equations of the two tangent lines at the origin.

(e) Find the points on the graph at which the tangent lines are horizontal.

6. Butterfly Curve Use a graphing utility to graph the curve shown in the figure below. The curve is given by

$$r = e^{\cos\theta} - 2\cos 4\theta + \sin^5\frac{\theta}{12}.$$

Over what interval must θ vary to produce the curve?



FOR FURTHER INFORMATION For more information on this curve, see the article "A Study in Step Size" by Temple H. Fay in *Mathematics Magazine*. To view this article, go to *MathArticles.com.*

7. Area Consider a circular pasture of radius 1 kilometer and a goat tied to a rope on the inside of the fence surrounding the pasture. How long should the rope be in order for the goat to have access to exactly half the pasture? (Ingo Ullisch found the first exact solution to this centuries old problem, as published in *Quanta Magazine*.)

8. Cornu Spiral Consider the **cornu spiral** given by

$$x(t) = \int_0^t \cos\frac{\pi u^2}{2}\,du \quad \text{and} \quad y(t) = \int_0^t \sin\frac{\pi u^2}{2}\,du.$$

(a) Use a graphing utility to graph the spiral over the interval $-\pi \le t \le \pi$.

(b) Show that the cornu spiral is symmetric with respect to the origin.

(c) Find the length of the cornu spiral from $t = 0$ to $t = a$. What is the length of the spiral from $t = -\pi$ to $t = \pi$?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

11 Vectors and the Geometry of Space

GO DIGITAL

11.1 Vectors in the Plane
11.2 Space Coordinates and Vectors in Space
11.3 The Dot Product of Two Vectors
11.4 The Cross Product of Two Vectors in Space
11.5 Lines and Planes in Space
11.6 Surfaces in Space
11.7 Cylindrical and Spherical Coordinates

CalcView®



CalcChat®



Geography *(Exercise 47, p. 807)*

Navigation *(Exercise 84, p. 761)*

left, Denis Tabler/Shutterstock.com; right, Jag_cz/Shutterstock.com
© Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322
Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

11.1 Vectors in the Plane

GO DIGITAL

- **Write the component form of a vector.**
- **Perform vector operations and interpret the results geometrically.**
- **Write a vector as a linear combination of standard unit vectors.**

Component Form of a Vector



A directed line segment
Figure 11.1



Equivalent directed line segments
Figure 11.2

Many quantities in geometry and physics, such as area, volume, temperature, mass, and time, can be characterized by a single real number that is scaled to appropriate units of measure. These are called **scalar quantities,** and the real number associated with each is called a **scalar.**

Other quantities, such as force, velocity, and acceleration, involve both magnitude and direction and cannot be characterized completely by a single real number. A **directed line segment** is used to represent such a quantity, as shown in Figure 11.1. The directed line segment $\overrightarrow{PQ}$ has **initial point** P and **terminal point** Q, and its **length** (or **magnitude**) is denoted by $\|\overrightarrow{PQ}\|$. Directed line segments that have the same length and direction are **equivalent,** as shown in Figure 11.2. The set of all directed line segments that are equivalent to a given directed line segment $\overrightarrow{PQ}$ is a **vector in the plane** and is denoted by

$$\mathbf{v} = \overrightarrow{PQ}.$$

A common notation for vectors is to use lowercase, boldface letters such as **u**, **v**, and **w**. Another common notation for vectors is to use letters with arrows above them, such as $\vec{u}$, $\vec{v}$, and $\vec{w}$.

Be sure you understand that a vector represents a *set* of directed line segments (each having the same length and direction). In practice, however, it is common not to distinguish between a vector and one of its representatives.

Big Ideas of Calculus

Vectors are important in many areas of mathematics and its applications. Force, torque, velocity, and work are common vector quantities. Some concepts, such as electricity and magnetism, are impossible to understand without vectors. Also, vectors are used to describe lines and planes in space (the three-dimensional coordinate system).

In addition to vectors, you will study surfaces in space and alternative coordinate systems for space. These concepts will be used in Chapter 12 to study vector calculus and the calculus of space.

EXAMPLE 1 Vector Representation: Directed Line Segments

Let **v** be represented by the directed line segment from $(0, 0)$ to $(3, 2)$, and let **u** be represented by the directed line segment from $(1, 2)$ to $(4, 4)$. Show that **v** and **u** are equivalent.

Solution Let $P(0, 0)$ and $Q(3, 2)$ be the initial and terminal points of **v**, and let $R(1, 2)$ and $S(4, 4)$ be the initial and terminal points of **u**, as shown in Figure 11.3. You can use the Distance Formula to show that $\overrightarrow{PQ}$ and $\overrightarrow{RS}$ have the *same length.*

$$\|\overrightarrow{PQ}\| = \sqrt{(3-0)^2 + (2-0)^2} = \sqrt{13}$$
$$\|\overrightarrow{RS}\| = \sqrt{(4-1)^2 + (4-2)^2} = \sqrt{13}$$

Both line segments have the *same direction,* because they both are directed toward the upper right on lines having the same slope.

$$\text{Slope of } \overrightarrow{PQ} = \frac{2-0}{3-0} = \frac{2}{3}$$

and

$$\text{Slope of } \overrightarrow{RS} = \frac{4-2}{4-1} = \frac{2}{3}$$

Because $\overrightarrow{PQ}$ and $\overrightarrow{RS}$ have the same length and direction, you can conclude that the two vectors are equivalent. That is, **v** and **u** are equivalent.



The vectors **u** and **v** are equivalent.
Figure 11.3

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



A vector in standard position
Figure 11.4

The directed line segment whose initial point is the origin is often the most convenient representative of a set of equivalent directed line segments such as those shown in Figure 11.3. This representation of **v** is said to be in **standard position.** A directed line segment whose initial point is the origin can be uniquely represented by the coordinates of its terminal point $Q(v_1, v_2)$, as shown in Figure 11.4. In the next definition, note the difference in the notation between the *component form* of a vector $\mathbf{v} = \langle v_1, v_2 \rangle$ and the point (v_1, v_2).

Definition of Component Form of a Vector in the Plane

If **v** is a vector in the plane whose initial point is the origin and whose terminal point is (v_1, v_2), then the **component form of v** is $\mathbf{v} = \langle v_1, v_2 \rangle$. The coordinates v_1 and v_2 are called the **components of v.** If both the initial point and the terminal point lie at the origin, then **v** is called the **zero vector** and is denoted by $\mathbf{0} = \langle 0, 0 \rangle$.

GO DIGITAL

This definition implies that two vectors $\mathbf{u} = \langle u_1, u_2 \rangle$ and $\mathbf{v} = \langle v_1, v_2 \rangle$ are **equal** if and only if $u_1 = v_1$ and $u_2 = v_2$.

The procedures listed below can be used to convert directed line segments to component form or vice versa.

1. If $P(p_1, p_2)$ and $Q(q_1, q_2)$ are the initial and terminal points of a directed line segment, then the component form of the vector **v** represented by $\overrightarrow{PQ}$ is

$$\langle v_1, v_2 \rangle = \langle q_1 - p_1, q_2 - p_2 \rangle.$$

Moreover, from the Distance Formula, you can determine that the **length** (or **magnitude**) **of v** is

$$\begin{aligned} \|\mathbf{v}\| &= \sqrt{(q_1 - p_1)^2 + (q_2 - p_2)^2} \\ &= \sqrt{v_1^2 + v_2^2}. \end{aligned}$$

Length of a vector

2. If $\mathbf{v} = \langle v_1, v_2 \rangle$, then **v** can be represented by the directed line segment, in standard position, from $P(0, 0)$ to $Q(v_1, v_2)$.

The length of **v** is also called the **norm of v.** If $\|\mathbf{v}\| = 1$, then **v** is a **unit vector.** Moreover, $\|\mathbf{v}\| = 0$ if and only if **v** is the zero vector **0**.



Component form of **v**: $\mathbf{v} = \langle -5, 12 \rangle$
Figure 11.5

EXAMPLE 2 Component Form and Length of a Vector

Find the component form and length of the vector **v** that has initial point $(3, -7)$ and terminal point $(-2, 5)$.

Solution Let $P(3, -7) = (p_1, p_2)$ and $Q(-2, 5) = (q_1, q_2)$. Then the components of $\mathbf{v} = \langle v_1, v_2 \rangle$ are

$$v_1 = q_1 - p_1 = -2 - 3 = -5$$

and

$$v_2 = q_2 - p_2 = 5 - (-7) = 12.$$

So, as shown in Figure 11.5, $\mathbf{v} = \langle -5, 12 \rangle$, and the length of **v** is

$$\begin{aligned} \|\mathbf{v}\| &= \sqrt{(-5)^2 + 12^2} \\ &= \sqrt{169} \\ &= 13. \end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Vector Operations

Definitions of Vector Addition and Scalar Multiplication

Let $\mathbf{u} = \langle u_1, u_2 \rangle$ and $\mathbf{v} = \langle v_1, v_2 \rangle$ be vectors and let c be a scalar.

1. The **vector sum** of $\mathbf{u}$ and $\mathbf{v}$ is the vector $\mathbf{u} + \mathbf{v} = \langle u_1 + v_1, u_2 + v_2 \rangle$.
2. The **scalar multiple** of c and $\mathbf{u}$ is the vector
$$c\mathbf{u} = \langle cu_1, cu_2 \rangle.$$
3. The **negative** of $\mathbf{v}$ is the vector
$$-\mathbf{v} = (-1)\mathbf{v} = \langle -v_1, -v_2 \rangle.$$
4. The **difference** of $\mathbf{u}$ and $\mathbf{v}$ is
$$\mathbf{u} - \mathbf{v} = \mathbf{u} + (-\mathbf{v}) = \langle u_1 - v_1, u_2 - v_2 \rangle.$$



The scalar multiplication of $\mathbf{v}$

Figure 11.6

Geometrically, the scalar multiple of a vector $\mathbf{v}$ and a scalar c is the vector that is $|c|$ times as long as $\mathbf{v}$, as shown in Figure 11.6. If c is positive, then $c\mathbf{v}$ has the same direction as $\mathbf{v}$. If c is negative, then $c\mathbf{v}$ has the opposite direction.

The sum of two vectors can be represented geometrically by positioning the vectors (without changing their magnitudes or directions) so that the initial point of one coincides with the terminal point of the other, as shown in Figure 11.7. The vector $\mathbf{u} + \mathbf{v}$, called the **resultant vector,** is the diagonal of a parallelogram having $\mathbf{u}$ and $\mathbf{v}$ as its adjacent sides.



To find $\mathbf{u} + \mathbf{v}$, (1) move the initial point of $\mathbf{v}$ to the terminal point of $\mathbf{u}$, or (2) move the initial point of $\mathbf{u}$ to the terminal point of $\mathbf{v}$.

Figure 11.7

Figure 11.8 shows the equivalence of the geometric and algebraic definitions of vector addition and scalar multiplication and presents (at far right) a geometric interpretation of $\mathbf{u} - \mathbf{v}$.



Vector addition — Scalar multiplication — Vector subtraction

Figure 11.8

WILLIAM ROWAN HAMILTON (1805–1865)

Some of the earliest work with vectors was done by the Irish mathematician William Rowan Hamilton. Hamilton spent many years developing a system of vector-like quantities called *quaternions*. It was not until the latter half of the nineteenth century that the Scottish physicist James Maxwell (1831–1879) restructured Hamilton's quaternions in a form useful for representing physical quantities such as force, velocity, and acceleration.

See LarsonCalculus.com to read more of this biography.

GRANGER

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 3 Vector Operations

For $\mathbf{v} = \langle -2, 5 \rangle$ and $\mathbf{w} = \langle 3, 4 \rangle$, find each of the vectors.

a. $\frac{1}{2}\mathbf{v}$ **b.** $\mathbf{w} - \mathbf{v}$ **c.** $\mathbf{v} + 2\mathbf{w}$

Solution

a. $\frac{1}{2}\mathbf{v} = \left\langle \frac{1}{2}(-2), \frac{1}{2}(5) \right\rangle = \left\langle -1, \frac{5}{2} \right\rangle$

b. $\mathbf{w} - \mathbf{v} = \langle w_1 - v_1, w_2 - v_2 \rangle$
$= \langle 3 - (-2), 4 - 5 \rangle$
$= \langle 5, -1 \rangle$

c. Using $2\mathbf{w} = \langle 6, 8 \rangle$, you have

$$\begin{aligned} \mathbf{v} + 2\mathbf{w} &= \langle -2, 5 \rangle + \langle 6, 8 \rangle \\ &= \langle -2 + 6, 5 + 8 \rangle \\ &= \langle 4, 13 \rangle. \end{aligned}$$

Vector addition and scalar multiplication share many properties of ordinary arithmetic, as shown in the next theorem.

EMMY NOETHER (1882–1935)

One person who contributed to our knowledge of axiomatic systems was the German mathematician Emmy Noether. Noether is generally recognized as the leading woman mathematician in recent history.

FOR FURTHER INFORMATION

For more information on Emmy Noether, see the article "Emmy Noether, Greatest Woman Mathematician" by Clark Kimberling in *Mathematics Teacher.* To view this article, go to *MathArticles.com.*

THEOREM 11.1 Properties of Vector Operations

Let $\mathbf{u}$, $\mathbf{v}$, and $\mathbf{w}$ be vectors in the plane, and let c and d be scalars.

1. $\mathbf{u} + \mathbf{v} = \mathbf{v} + \mathbf{u}$	Commutative Property
2. $(\mathbf{u} + \mathbf{v}) + \mathbf{w} = \mathbf{u} + (\mathbf{v} + \mathbf{w})$	Associative Property
3. $\mathbf{u} + \mathbf{0} = \mathbf{u}$	Additive Identity Property
4. $\mathbf{u} + (-\mathbf{u}) = \mathbf{0}$	Additive Inverse Property
5. $c(d\mathbf{u}) = (cd)\mathbf{u}$	
6. $(c + d)\mathbf{u} = c\mathbf{u} + d\mathbf{u}$	Distributive Property
7. $c(\mathbf{u} + \mathbf{v}) = c\mathbf{u} + c\mathbf{v}$	Distributive Property
8. $1(\mathbf{u}) = \mathbf{u}$, $0(\mathbf{u}) = \mathbf{0}$	

Proof The proof of the *Associative Property* of vector addition uses the Associative Property of addition of real numbers.

$$\begin{aligned} (\mathbf{u} + \mathbf{v}) + \mathbf{w} &= [\langle u_1, u_2 \rangle + \langle v_1, v_2 \rangle] + \langle w_1, w_2 \rangle \\ &= \langle u_1 + v_1, u_2 + v_2 \rangle + \langle w_1, w_2 \rangle \\ &= \langle (u_1 + v_1) + w_1, (u_2 + v_2) + w_2 \rangle \\ &= \langle u_1 + (v_1 + w_1), u_2 + (v_2 + w_2) \rangle \\ &= \langle u_1, u_2 \rangle + \langle v_1 + w_1, v_2 + w_2 \rangle \\ &= \mathbf{u} + (\mathbf{v} + \mathbf{w}) \end{aligned}$$

The other properties can be proved in a similar manner. (See Exercise 81.)

Any set of vectors (with an accompanying set of scalars) that satisfies the eight properties listed in Theorem 11.1 is a **vector space.*** The eight properties are the *vector space axioms.* So, this theorem states that the set of vectors in the plane (with the set of real numbers) forms a vector space.

* For more information about vector spaces, see *Elementary Linear Algebra,* Eighth Edition, by Ron Larson (Boston, Massachusetts: Cengage Learning, 2017).

Sarin Images/GRANGER

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

THEOREM 11.2 Length of a Scalar Multiple

Let $\mathbf{v}$ be a vector and let c be a scalar. Then

$$\|c\mathbf{v}\| = |c|\|\mathbf{v}\|.$$

$|c|$ is the absolute value of c.

Proof Because $c\mathbf{v} = \langle cv_1, cv_2 \rangle$, it follows that

$$\begin{aligned}
\|c\mathbf{v}\| &= \|\langle cv_1, cv_2 \rangle\| \\
&= \sqrt{(cv_1)^2 + (cv_2)^2} \\
&= \sqrt{c^2v_1^2 + c^2v_2^2} \\
&= \sqrt{c^2(v_1^2 + v_2^2)} \\
&= |c|\sqrt{v_1^2 + v_2^2} \\
&= |c|\|\mathbf{v}\|.
\end{aligned}$$

In many applications of vectors, it is useful to find a unit vector that has the same direction as a given vector. The next theorem gives a procedure for doing this.

THEOREM 11.3 Unit Vector in the Direction of v

If $\mathbf{v}$ is a nonzero vector in the plane, then the vector

$$\mathbf{u} = \frac{\mathbf{v}}{\|\mathbf{v}\|} = \frac{1}{\|\mathbf{v}\|}\mathbf{v}$$

has length 1 and the same direction as $\mathbf{v}$.

Proof Because $1/\|\mathbf{v}\|$ is positive and $\mathbf{u} = (1/\|\mathbf{v}\|)\mathbf{v}$, you can conclude that $\mathbf{u}$ has the same direction as $\mathbf{v}$. To see that $\|\mathbf{u}\| = 1$, note that

$$\|\mathbf{u}\| = \left\| \left(\frac{1}{\|\mathbf{v}\|}\right)\mathbf{v} \right\| = \left|\frac{1}{\|\mathbf{v}\|}\right| \|\mathbf{v}\| = \frac{1}{\|\mathbf{v}\|}\|\mathbf{v}\| = 1.$$

So, $\mathbf{u}$ has length 1 and the same direction as $\mathbf{v}$.

In Theorem 11.3, $\mathbf{u}$ is called a **unit vector in the direction of v.** The process of multiplying $\mathbf{v}$ by $1/\|\mathbf{v}\|$ to get a unit vector is called **normalization of v.**

EXAMPLE 4 Finding a Unit Vector

Find a unit vector in the direction of $\mathbf{v} = \langle -2, 5 \rangle$ and verify that it has length 1.

Solution From Theorem 11.3, the unit vector in the direction of $\mathbf{v}$ is

$$\begin{aligned}
\frac{\mathbf{v}}{\|\mathbf{v}\|} &= \frac{\langle -2, 5 \rangle}{\sqrt{(-2)^2 + (5)^2}} \\
&= \frac{1}{\sqrt{29}}\langle -2, 5 \rangle \\
&= \left\langle \frac{-2}{\sqrt{29}}, \frac{5}{\sqrt{29}} \right\rangle.
\end{aligned}$$

This vector has length 1, because

$$\sqrt{\left(\frac{-2}{\sqrt{29}}\right)^2 + \left(\frac{5}{\sqrt{29}}\right)^2} = \sqrt{\frac{4}{29} + \frac{25}{29}} = \sqrt{\frac{29}{29}} = 1.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Triangle inequality
Figure 11.9

Generally, the length of the sum of two vectors is not equal to the sum of their lengths. To see this, consider the vectors $\mathbf{u}$ and $\mathbf{v}$ as shown in Figure 11.9. With $\mathbf{u}$ and $\mathbf{v}$ as two sides of a triangle, the length of the third side is $\|\mathbf{u} + \mathbf{v}\|$, and

$$\|\mathbf{u} + \mathbf{v}\| \leq \|\mathbf{u}\| + \|\mathbf{v}\|.$$

Equality occurs only when the vectors $\mathbf{u}$ and $\mathbf{v}$ have the *same direction.* This result is called the **triangle inequality** for vectors. (You are asked to prove this in Exercise 73, Section 11.3.)

Standard Unit Vectors

The unit vectors $\langle 1, 0\rangle$ and $\langle 0, 1\rangle$ are called the **standard unit vectors** in the plane and are denoted by

$$\mathbf{i} = \langle 1, 0\rangle \quad \text{and} \quad \mathbf{j} = \langle 0, 1\rangle \qquad \text{Standard unit vectors}$$



Standard unit vectors **i** and **j**
Figure 11.10

as shown in Figure 11.10. These vectors can be used to represent any vector uniquely, as follows.

$$\mathbf{v} = \langle v_1, v_2\rangle = \langle v_1, 0\rangle + \langle 0, v_2\rangle = v_1\langle 1, 0\rangle + v_2\langle 0, 1\rangle = v_1\mathbf{i} + v_2\mathbf{j}$$

The vector $\mathbf{v} = v_1\mathbf{i} + v_2\mathbf{j}$ is called a **linear combination** of $\mathbf{i}$ and $\mathbf{j}$. The scalars v_1 and v_2 are called the **horizontal** and **vertical components of v.**

EXAMPLE 5 Writing a Linear Combination of Unit Vectors

Let $\mathbf{u}$ be the vector with initial point $(2, -5)$ and terminal point $(-1, 3)$, and let $\mathbf{v} = 2\mathbf{i} - \mathbf{j}$. Write each vector as a linear combination of $\mathbf{i}$ and $\mathbf{j}$.

a. $\mathbf{u}$

b. $\mathbf{w} = 2\mathbf{u} - 3\mathbf{v}$

Solution

a. $\mathbf{u} = \langle q_1 - p_1, q_2 - p_2\rangle = \langle -1 - 2, 3 - (-5)\rangle = \langle -3, 8\rangle = -3\mathbf{i} + 8\mathbf{j}$

b. $\mathbf{w} = 2\mathbf{u} - 3\mathbf{v} = 2(-3\mathbf{i} + 8\mathbf{j}) - 3(2\mathbf{i} - \mathbf{j}) = -6\mathbf{i} + 16\mathbf{j} - 6\mathbf{i} + 3\mathbf{j} = -12\mathbf{i} + 19\mathbf{j}$

GO DIGITAL

If $\mathbf{u}$ is a unit vector and θ is the angle (measured counterclockwise) from the positive x-axis to $\mathbf{u}$, then the terminal point of $\mathbf{u}$ lies on the unit circle, and you have

$$\mathbf{u} = \langle \cos\theta, \sin\theta\rangle = \cos\theta\mathbf{i} + \sin\theta\mathbf{j} \qquad \text{Unit vector}$$

as shown in Figure 11.11. Moreover, it follows that any other nonzero vector $\mathbf{v}$ making an angle θ with the positive x-axis has the same direction as $\mathbf{u}$, and you can write

$$\mathbf{v} = \|\mathbf{v}\|\langle \cos\theta, \sin\theta\rangle = \|\mathbf{v}\|\cos\theta\mathbf{i} + \|\mathbf{v}\|\sin\theta\mathbf{j}.$$



The angle θ from the positive x-axis to the vector $\mathbf{u}$
Figure 11.11

EXAMPLE 6 Writing a Vector of Given Magnitude and Direction

The vector $\mathbf{v}$ has a magnitude of 3 and makes an angle of $30° = \pi/6$ with the positive x-axis. Write $\mathbf{v}$ as a linear combination of the unit vectors $\mathbf{i}$ and $\mathbf{j}$.

Solution Because the angle between $\mathbf{v}$ and the positive x-axis is $\theta = \pi/6$, you can write

$$\mathbf{v} = \|\mathbf{v}\|\cos\theta\mathbf{i} + \|\mathbf{v}\|\sin\theta\mathbf{j} = 3\cos\frac{\pi}{6}\mathbf{i} + 3\sin\frac{\pi}{6}\mathbf{j} = \frac{3\sqrt{3}}{2}\mathbf{i} + \frac{3}{2}\mathbf{j}.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Vectors have many applications in physics and engineering. One example is force. A vector can be used to represent force, because force has both magnitude and direction. If two or more forces are acting on an object, then the **resultant force** on the object is the vector sum of the vector forces.

EXAMPLE 7 Finding the Resultant Force

Two tugboats are pushing an ocean liner, as shown in Figure 11.12. Each boat is exerting a force of 400 pounds. What is the resultant force on the ocean liner?



The resultant force on the ocean liner that is exerted by the two tugboats
Figure 11.12

Solution Using Figure 11.12, you can represent the forces exerted by the first and second tugboats as

$$\mathbf{F}_1 = 400\langle \cos 20°, \sin 20° \rangle = 400\cos(20°)\mathbf{i} + 400\sin(20°)\mathbf{j}$$
$$\mathbf{F}_2 = 400\langle \cos(-20°), \sin(-20°) \rangle = 400\cos(20°)\mathbf{i} - 400\sin(20°)\mathbf{j}.$$

The resultant force on the ocean liner is

$$\begin{aligned}\mathbf{F} &= \mathbf{F}_1 + \mathbf{F}_2 \\ &= [400\cos(20°)\mathbf{i} + 400\sin(20°)\mathbf{j}] + [400\cos(20°)\mathbf{i} - 400\sin(20°)\mathbf{j}] \\ &= 800\cos(20°)\mathbf{i} \\ &\approx 752\mathbf{i}.\end{aligned}$$

So, the resultant force on the ocean liner is approximately 752 pounds in the direction of the positive x-axis. ■

In surveying and navigation, a **bearing** is a direction that measures the acute angle that a path or line of sight makes with a fixed north-south line. In air navigation, bearings are measured in degrees clockwise from north.

EXAMPLE 8 Finding a Velocity

See LarsonCalculus.com for an interactive version of this type of example.

An airplane is traveling at a fixed altitude with a negligible wind factor. The airplane is traveling at a speed of 500 miles per hour with a bearing of 330°, as shown in Figure 11.13(a). As the airplane reaches a certain point, it encounters wind with a velocity of 70 miles per hour in the direction N 45° E (45° east of north), as shown in Figure 11.13(b). What are the resultant speed and direction of the airplane?



(a) Direction without wind



(b) Direction with wind
Figure 11.13

Solution Using Figure 11.13(a), represent the velocity of the airplane (alone) as

$$\mathbf{v}_1 = 500\cos(120°)\mathbf{i} + 500\sin(120°)\mathbf{j}.$$

The velocity of the wind is represented by the vector

$$\mathbf{v}_2 = 70\cos(45°)\mathbf{i} + 70\sin(45°)\mathbf{j}.$$

The resultant velocity of the airplane (in the wind) is

$$\begin{aligned}\mathbf{v} &= \mathbf{v}_1 + \mathbf{v}_2 \\ &= 500\cos(120°)\mathbf{i} + 500\sin(120°)\mathbf{j} + 70\cos(45°)\mathbf{i} + 70\sin(45°)\mathbf{j} \\ &\approx -200.5\mathbf{i} + 482.5\mathbf{j}.\end{aligned}$$

To find the resultant speed and direction, write $\mathbf{v} = \|\mathbf{v}\|(\cos\theta\mathbf{i} + \sin\theta\mathbf{j})$. Because $\|\mathbf{v}\| \approx \sqrt{(-200.5)^2 + (482.5)^2} \approx 522.5$, you can write

$$\mathbf{v} \approx 522.5\left(\frac{-200.5}{522.5}\mathbf{i} + \frac{482.5}{522.5}\mathbf{j}\right) \approx 522.5[\cos(112.6°)\mathbf{i} + \sin(112.6°)\mathbf{j}].$$

The new speed of the airplane, as altered by the wind, is approximately 522.5 miles per hour in a path that makes an angle of 112.6° with the positive x-axis. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

11.1 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe the difference between a scalar and a vector. Give examples of each.
2. Two points and a vector are given. Determine which point is the initial point and which point is the terminal point. Explain.

   $P(2, -1)$, $Q(-4, 6)$, and $\mathbf{v} = \langle 6, -7 \rangle$

Sketching a Vector In Exercises 3 and 4, (a) find the component form of the vector v and (b) sketch the vector with its initial point at the origin.

3.



4.



Equivalent Vectors In Exercises 5–8, find the vectors u and v whose initial and terminal points are given. Show that u and v are equivalent.

	Initial Point	Terminal Point		Initial Point	Terminal Point
5.	u: (3, 2)	(5, 6)	6.	u: (−4, 0)	(1, 8)
	v: (1, 4)	(3, 8)		v: (2, −1)	(7, 7)
7.	u: (0, 3)	(6, −2)	8.	u: (−4, −1)	(11, −4)
	v: (3, 10)	(9, 5)		v: (10, 13)	(25, 10)

Writing a Vector in Different Forms In Exercises 9–16, the initial and terminal points of a vector v are given. (a) Sketch the given directed line segment. (b) Write the vector in component form. (c) Write the vector as the linear combination of the standard unit vectors i and j. (d) Sketch the vector with its initial point at the origin.

	Initial Point	Terminal Point		Initial Point	Terminal Point
9.	(2, 0)	(5, 5)	10.	(4, −6)	(3, 6)
11.	(8, 3)	(6, −1)	12.	(0, −4)	(−5, −1)
13.	(6, 2)	(6, 6)	14.	(7, −1)	(−3, −1)
15.	$\left(\frac{3}{2}, \frac{4}{3}\right)$	$\left(\frac{1}{2}, 3\right)$	16.	(0.12, 0.60)	(0.84, 1.25)

Finding a Terminal Point In Exercises 17 and 18, the vector v and its initial point are given. Find the terminal point.

17. $\mathbf{v} = \langle -1, 3 \rangle$; Initial point: (4, 2)
18. $\mathbf{v} = \langle 4, -9 \rangle$; Initial point: (5, 3)

Finding a Magnitude of a Vector In Exercises 19–24, find the magnitude of v.

19. $\mathbf{v} = 4\mathbf{i}$
20. $\mathbf{v} = -9\mathbf{j}$
21. $\mathbf{v} = \langle 8, 15 \rangle$
22. $\mathbf{v} = \langle -24, 7 \rangle$
23. $\mathbf{v} = -\mathbf{i} - 5\mathbf{j}$
24. $\mathbf{v} = 3\mathbf{i} + 3\mathbf{j}$

Sketching Scalar Multiples In Exercises 25 and 26, sketch each scalar multiple of v.

25. $\mathbf{v} = \langle 3, 5 \rangle$ (a) $2\mathbf{v}$ (b) $-3\mathbf{v}$ (c) $\frac{7}{2}\mathbf{v}$ (d) $\frac{2}{3}\mathbf{v}$
26. $\mathbf{v} = \langle -2, 3 \rangle$ (a) $4\mathbf{v}$ (b) $-\frac{1}{2}\mathbf{v}$ (c) $0\mathbf{v}$ (d) $-6\mathbf{v}$

Using Vector Operations In Exercises 27 and 28, find (a) $\frac{2}{3}\mathbf{u}$, (b) $3\mathbf{v}$, (c) $\mathbf{v} - \mathbf{u}$, and (d) $2\mathbf{u} + 5\mathbf{v}$.

27. $\mathbf{u} = \langle 4, 9 \rangle$, $\mathbf{v} = \langle 2, -5 \rangle$
28. $\mathbf{u} = \langle -3, -8 \rangle$, $\mathbf{v} = \langle 8, 7 \rangle$

Sketching a Vector In Exercises 29–34, use the figure to sketch a graph of the vector. To print an enlarged copy of the graph, go to *MathGraphs.com*.

29. $-\mathbf{u}$
30. $2\mathbf{u}$
31. $-\mathbf{v}$
32. $\frac{1}{2}\mathbf{v}$
33. $\mathbf{u} - \mathbf{v}$
34. $\mathbf{u} + 2\mathbf{v}$



Finding a Unit Vector In Exercises 35–38, find the unit vector in the direction of v and verify that it has length 1.

35. $\mathbf{v} = \langle 3, 12 \rangle$
36. $\mathbf{v} = \langle -5, 15 \rangle$
37. $\mathbf{v} = \left\langle \frac{3}{2}, \frac{5}{2} \right\rangle$
38. $\mathbf{v} = \langle -6.2, 3.4 \rangle$

Finding Magnitudes In Exercises 39–42, find the following.

(a) $\|\mathbf{u}\|$ (b) $\|\mathbf{v}\|$ (c) $\|\mathbf{u} + \mathbf{v}\|$

(d) $\left\| \frac{\mathbf{u}}{\|\mathbf{u}\|} \right\|$ (e) $\left\| \frac{\mathbf{v}}{\|\mathbf{v}\|} \right\|$ (f) $\left\| \frac{\mathbf{u} + \mathbf{v}}{\|\mathbf{u} + \mathbf{v}\|} \right\|$

39. $\mathbf{u} = \langle 1, -1 \rangle$, $\mathbf{v} = \langle -1, 2 \rangle$
40. $\mathbf{u} = \langle 0, 1 \rangle$, $\mathbf{v} = \langle 3, -3 \rangle$
41. $\mathbf{u} = \left\langle 1, \frac{1}{2} \right\rangle$, $\mathbf{v} = \langle 2, 3 \rangle$
42. $\mathbf{u} = \langle 2, -4 \rangle$, $\mathbf{v} = \langle 5, 5 \rangle$

Using the Triangle Inequality In Exercises 43 and 44, sketch a graph of u, v, and $\mathbf{u} + \mathbf{v}$. Then demonstrate the triangle inequality using the vectors u and v.

43. $\mathbf{u} = \langle 2, 1 \rangle$, $\mathbf{v} = \langle 5, 4 \rangle$
44. $\mathbf{u} = \langle -3, 2 \rangle$, $\mathbf{v} = \langle 1, -2 \rangle$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding a Vector In Exercises 45–48, find the vector v with the given magnitude and the same direction as u.

	Magnitude	Direction
45.	$\|\mathbf{v}\| = 6$	$\mathbf{u} = \langle 0, 3 \rangle$
46.	$\|\mathbf{v}\| = 4$	$\mathbf{u} = \langle 1, 1 \rangle$
47.	$\|\mathbf{v}\| = 5$	$\mathbf{u} = \langle -1, 2 \rangle$
48.	$\|\mathbf{v}\| = 2$	$\mathbf{u} = \langle \sqrt{3}, 3 \rangle$

Finding a Vector In Exercises 49–52, find the component form of v given its magnitude and the angle it makes with the positive x-axis.

49. $\|\mathbf{v}\| = 3, \quad \theta = 0°$
50. $\|\mathbf{v}\| = 5, \quad \theta = 120°$
51. $\|\mathbf{v}\| = 2, \quad \theta = 150°$
52. $\|\mathbf{v}\| = 4, \quad \theta = 3.5°$

Finding a Vector In Exercises 53–56, find the component form of u + v given the lengths of u and v and the angles that u and v make with the positive x-axis.

53. $\|\mathbf{u}\| = 1, \quad \theta_{\mathbf{u}} = 0°$
$\|\mathbf{v}\| = 3, \quad \theta_{\mathbf{v}} = 45°$

54. $\|\mathbf{u}\| = 4, \quad \theta_{\mathbf{u}} = 0°$
$\|\mathbf{v}\| = 2, \quad \theta_{\mathbf{v}} = 60°$

55. $\|\mathbf{u}\| = 2, \quad \theta_{\mathbf{u}} = 4$
$\|\mathbf{v}\| = 1, \quad \theta_{\mathbf{v}} = 2$

56. $\|\mathbf{u}\| = 5, \quad \theta_{\mathbf{u}} = -0.5$
$\|\mathbf{v}\| = 5, \quad \theta_{\mathbf{v}} = 0.5$

Exploring Concepts

In Exercises 57 and 58, consider two forces of equal magnitude acting on a point.

57. Make a conjecture about the angle between the forces when the magnitude of the resultant is the sum of the magnitudes of the two forces.

58. Make a conjecture about the angle between the forces when the resultant of the forces is 0.

59. Consider a triangle with vertices X, Y, and Z. What is $\overrightarrow{XY} + \overrightarrow{YZ} + \overrightarrow{ZX}$? Explain.

60. **HOW DO YOU SEE IT?** Use the figure to determine whether each statement is true or false. Justify your answer.



(a) $\mathbf{a} = -\mathbf{d}$
(b) $\mathbf{c} = \mathbf{s}$
(c) $\mathbf{a} + \mathbf{u} = \mathbf{c}$
(d) $\mathbf{v} + \mathbf{w} = -\mathbf{s}$
(e) $\mathbf{a} + \mathbf{d} = \mathbf{0}$
(f) $\mathbf{u} - \mathbf{v} = -2(\mathbf{b} + \mathbf{t})$

Finding Values In Exercises 61–66, find a and b such that $\mathbf{v} = a\mathbf{u} + b\mathbf{w}$, where $\mathbf{u} = \langle 1, 2 \rangle$ and $\mathbf{w} = \langle 1, -1 \rangle$.

61. $\mathbf{v} = \langle 4, 5 \rangle$
62. $\mathbf{v} = \langle -7, -2 \rangle$
63. $\mathbf{v} = \langle -6, 0 \rangle$
64. $\mathbf{v} = \langle 0, 6 \rangle$
65. $\mathbf{v} = \langle 1, -3 \rangle$
66. $\mathbf{v} = \langle -1, 8 \rangle$

Finding Unit Vectors In Exercises 67–72, find a unit vector (a) parallel to and (b) perpendicular to the graph of f at the given point. Then sketch the graph of f and sketch the vectors at the given point.

67. $f(x) = x^2, \quad (3, 9)$
68. $f(x) = -x^2 + 5, \quad (1, 4)$
69. $f(x) = x^3, \quad (1, 1)$
70. $f(x) = x^3, \quad (-2, -8)$
71. $f(x) = \sqrt{25 - x^2}, \quad (3, 4)$
72. $f(x) = \tan x, \quad \left(\frac{\pi}{4}, 1\right)$

Finding a Vector In Exercises 73 and 74, find the component form of v given the magnitudes of u and u + v and the angles that u and u + v make with the positive x-axis.

73. $\|\mathbf{u}\| = 1, \quad \theta = 45°$
$\|\mathbf{u} + \mathbf{v}\| = \sqrt{2}, \quad \theta = 90°$

74. $\|\mathbf{u}\| = 4, \quad \theta = 30°$
$\|\mathbf{u} + \mathbf{v}\| = 6, \quad \theta = 120°$

75. **Resultant Force** Forces with magnitudes of 500 pounds and 200 pounds act on a machine part at angles of 30° and −45°, respectively, with the x-axis (see figure). Find the direction and magnitude of the resultant force.



Figure for 75



Figure for 76

76. **Numerical and Graphical Analysis** Forces with magnitudes of 180 newtons and 275 newtons act on a hook (see figure). The angle between the two forces is θ degrees.

(a) When $\theta = 30°$, find the direction and magnitude of the resultant force.

(b) Write the magnitude M and direction α of the resultant force as functions of θ, where $0° \le \theta \le 180°$.

(c) Use a graphing utility to complete the table.

θ	0°	30°	60°	90°	120°	150°	180°
M							
α							

(d) Use a graphing utility to graph the two functions M and α.

(e) Explain why one of the functions decreases for increasing values of θ, whereas the other does not.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

77. Resultant Force Three forces with magnitudes of 75 pounds, 100 pounds, and 125 pounds act on an object at angles of 30°, 45°, and 120°, respectively, with the positive x-axis. Find the direction and magnitude of the resultant force.

78. Resultant Force Three forces with magnitudes of 400 newtons, 280 newtons, and 350 newtons act on an object at angles of $-30°$, 45°, and 135°, respectively, with the positive x-axis. Find the direction and magnitude of the resultant force.

Cable Tension **In Exercises 79 and 80, determine the tension supporting the given load in cable *CB* and cable *CA*.**

79.



80.



81. Proof The Associative Property of Vector Operations in Theorem 11.1 was proved on page 755. Prove the remaining properties listed in Theorem 11.1.

82. Shared Load To carry a 100-pound cylindrical weight, two workers lift on the ends of short ropes tied to an eyelet on the top center of the cylinder. One rope makes a 20° angle away from the vertical and the other makes a 30° angle (see figure).

(a) Find each rope's tension when the resultant force is vertical.

(b) Find the vertical component of each worker's force.



83. Navigation A plane is flying with a bearing of 302°. Its speed with respect to the air is 900 kilometers per hour. The wind at the plane's altitude is from the southwest at 100 kilometers per hour (see figure). What is the true direction of the plane, and what is its speed with respect to the ground?



84. Navigation

A plane flies at a constant ground speed of 400 miles per hour due east and encounters a 50-mile-per-hour wind from the northwest. Find the airspeed and compass direction that will allow the plane to maintain its ground speed and eastward direction.

True or False? **In Exercises 85–94, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

85. The weight of a car is a scalar.

86. The mass of a book is a scalar.

87. The temperature of your blood is a scalar.

88. The velocity of a bicycle is a vector.

89. If $\mathbf{u}$ and $\mathbf{v}$ have the same magnitude and direction, then $\mathbf{u}$ and $\mathbf{v}$ are equivalent.

90. If $\mathbf{u}$ is a unit vector in the direction of $\mathbf{v}$, then $\mathbf{v} = \|\mathbf{v}\|\mathbf{u}$.

91. If $\mathbf{u} = a\mathbf{i} + b\mathbf{j}$ is a unit vector, then $a^2 + b^2 = 1$.

92. If $\mathbf{v} = a\mathbf{i} + b\mathbf{j} = \mathbf{0}$, then $a = -b$.

93. If $a = b$, then $\|a\mathbf{i} + b\mathbf{j}\| = \sqrt{2}a$.

94. If $\mathbf{u}$ and $\mathbf{v}$ have the same magnitude but opposite directions, then $\mathbf{u} + \mathbf{v} = \mathbf{0}$.

95. Proof Prove that

$$\mathbf{u} = (\cos\theta)\mathbf{i} - (\sin\theta)\mathbf{j} \quad \text{and} \quad \mathbf{v} = (\sin\theta)\mathbf{i} + (\cos\theta)\mathbf{j}$$

are unit vectors for any angle θ.

96. Geometry Using vectors, prove that the line segment joining the midpoints of two sides of a triangle is parallel to, and one-half the length of, the third side.

97. Geometry Using vectors, prove that the diagonals of a parallelogram bisect each other.

98. Proof Prove that the vector

$$\mathbf{w} = \|\mathbf{u}\|\mathbf{v} + \|\mathbf{v}\|\mathbf{u}$$

bisects the angle between $\mathbf{u}$ and $\mathbf{v}$.

99. Using a Vector Consider the vector $\mathbf{u} = \langle x, y \rangle$. Describe the set of all points (x, y) such that $\|\mathbf{u}\| = 5$.

PUTNAM EXAM CHALLENGE

100. A coast artillery gun can fire at any angle of elevation between 0° and 90° in a fixed vertical plane. If air resistance is neglected and the muzzle velocity is constant $(= v_0)$, determine the set H of points in the plane and above the horizontal which can be hit.

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Jag_cz/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

11.2 Space Coordinates and Vectors in Space

GO DIGITAL

- **Describe the three-dimensional rectangular coordinate system.**
- **Analyze vectors in space.**

Coordinates in Space

Up to this point in the text, you have been primarily concerned with the two-dimensional coordinate system. Much of the remaining part of your study of calculus will involve the three-dimensional coordinate system.

Before extending the concept of a vector to three dimensions, you must be able to identify points in the **three-dimensional coordinate system.** You can construct this system by passing a z-axis perpendicular to both the x- and y-axes at the origin, as shown in Figure 11.14. Taken as pairs, the axes determine three **coordinate planes:** the ***xy*-plane,** the ***xz*-plane,** and the ***yz*-plane.** These three coordinate planes separate three-space into eight **octants.** The first octant is the one for which all three coordinates are positive. In this three-dimensional system, a point P in space is determined by an ordered triple (x, y, z), where x, y, and z are as follows.

x = directed distance from yz-plane to P

y = directed distance from xz-plane to P

z = directed distance from xy-plane to P

Several points are shown in Figure 11.15.



The three-dimensional coordinate system

Figure 11.14

REMARK The three-dimensional rotatable graphs that are available at *LarsonCalculus.com* can help you visualize points or objects in a three-dimensional coordinate system.



Points in the three-dimensional coordinate system are represented by ordered triples.

Figure 11.15

A three-dimensional coordinate system can have either a **right-handed** or a **left-handed** orientation. To determine the orientation of a system, imagine that you are standing at the origin, with your arms pointing in the direction of the positive x- and y-axes and with the positive z-axis pointing up, as shown in Figure 11.16. The system is right-handed or left-handed depending on which hand points along the x-axis. In this text, you will work exclusively with the right-handed system.



Right-handed system

Left-handed system

Figure 11.16

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The distance between two points in space

Figure 11.17

Many of the formulas established for the two-dimensional coordinate system can be extended to three dimensions. For example, to find the distance between two points in space, you can use the Pythagorean Theorem twice, as shown in Figure 11.17. By doing this, you will obtain the formula for the distance between the points (x_1, y_1, z_1) and (x_2, y_2, z_2).

$$d = \sqrt{(x_2 - x_1)^2 + (y_2 - y_1)^2 + (z_2 - z_1)^2}$$ Distance Formula

EXAMPLE 1 Finding the Distance Between Two Points in Space

Find the distance between the points $(2, -1, 3)$ and $(1, 0, -2)$.

Solution

$$\begin{aligned} d &= \sqrt{(1 - 2)^2 + (0 + 1)^2 + (-2 - 3)^2} \quad \text{Distance Formula} \\ &= \sqrt{1 + 1 + 25} \\ &= \sqrt{27} \\ &= 3\sqrt{3} \end{aligned}$$



Figure 11.18

A **sphere** with center at (x_0, y_0, z_0) and radius r is defined to be the set of all points (x, y, z) such that the distance between (x, y, z) and (x_0, y_0, z_0) is r. You can use the Distance Formula to find the **standard equation of a sphere** of radius r, centered at (x_0, y_0, z_0). If (x, y, z) is an arbitrary point on the sphere, then the equation of the sphere is

$$(x - x_0)^2 + (y - y_0)^2 + (z - z_0)^2 = r^2$$ Equation of sphere

as shown in Figure 11.18. Moreover, the midpoint of the line segment joining the points (x_1, y_1, z_1) and (x_2, y_2, z_2) has coordinates

$$\left(\frac{x_1 + x_2}{2}, \frac{y_1 + y_2}{2}, \frac{z_1 + z_2}{2}\right).$$ Midpoint Formula

EXAMPLE 2 Finding the Equation of a Sphere

Find the standard equation of the sphere that has the points

$$(5, -2, 3) \quad \text{and} \quad (0, 4, -3)$$

as endpoints of a diameter.

Solution Using the Midpoint Formula, the center of the sphere is

$$\left(\frac{5 + 0}{2}, \frac{-2 + 4}{2}, \frac{3 - 3}{2}\right) = \left(\frac{5}{2}, 1, 0\right).$$ Midpoint Formula

By the Distance Formula, the radius is

$$r = \sqrt{\left(0 - \frac{5}{2}\right)^2 + (4 - 1)^2 + (-3 - 0)^2} = \sqrt{\frac{97}{4}} = \frac{\sqrt{97}}{2}.$$

So, the standard equation of the sphere is

$$\left(x - \frac{5}{2}\right)^2 + (y - 1)^2 + z^2 = \frac{97}{4}.$$ Equation of sphere

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The standard unit vectors in space
Figure 11.19



Figure 11.20

Vectors in Space

In space, vectors are denoted by ordered triples $\mathbf{v} = \langle v_1, v_2, v_3 \rangle$. The **zero vector** is denoted by $\mathbf{0} = \langle 0, 0, 0 \rangle$. Using the unit vectors

$$\mathbf{i} = \langle 1, 0, 0 \rangle, \quad \mathbf{j} = \langle 0, 1, 0 \rangle, \quad \text{and} \quad \mathbf{k} = \langle 0, 0, 1 \rangle$$

the **standard unit vector notation** for $\mathbf{v}$ is

$$\mathbf{v} = v_1\mathbf{i} + v_2\mathbf{j} + v_3\mathbf{k}$$

as shown in Figure 11.19. If $\mathbf{v}$ is represented by the directed line segment from $P(p_1, p_2, p_3)$ to $Q(q_1, q_2, q_3)$, as shown in Figure 11.20, then the component form of $\mathbf{v}$ is written by subtracting the coordinates of the initial point from the coordinates of the terminal point, as follows.

$$\mathbf{v} = \langle v_1, v_2, v_3 \rangle = \langle q_1 - p_1, q_2 - p_2, q_3 - p_3 \rangle$$

Vectors in Space

Let $\mathbf{u} = \langle u_1, u_2, u_3 \rangle$ and $\mathbf{v} = \langle v_1, v_2, v_3 \rangle$ be vectors in space and let c be a scalar.

1. *Equality of Vectors:* $\mathbf{u} = \mathbf{v}$ if and only if $u_1 = v_1$, $u_2 = v_2$, and $u_3 = v_3$.
2. *Component Form:* If $\mathbf{v}$ is represented by the directed line segment from $P(p_1, p_2, p_3)$ to $Q(q_1, q_2, q_3)$, then
$$\mathbf{v} = \langle v_1, v_2, v_3 \rangle = \langle q_1 - p_1, q_2 - p_2, q_3 - p_3 \rangle.$$
3. *Length:* $\|\mathbf{v}\| = \sqrt{v_1^2 + v_2^2 + v_3^2}$
4. *Unit Vector in the Direction of* $\mathbf{v}$: $\dfrac{\mathbf{v}}{\|\mathbf{v}\|} = \left(\dfrac{1}{\|\mathbf{v}\|}\right)\langle v_1, v_2, v_3 \rangle, \quad \mathbf{v} \neq \mathbf{0}$
5. *Vector Addition:* $\mathbf{v} + \mathbf{u} = \langle v_1 + u_1, v_2 + u_2, v_3 + u_3 \rangle$
6. *Scalar Multiplication:* $c\mathbf{v} = \langle cv_1, cv_2, cv_3 \rangle$

Note that the properties of vector operations listed in Theorem 11.1 (see Section 11.1) are also valid for vectors in space.

EXAMPLE 3 Finding the Component Form of a Vector in Space

See LarsonCalculus.com for an interactive version of this type of example.

Find the component form and magnitude of the vector $\mathbf{v}$ having initial point $(-2, 3, 1)$ and terminal point $(0, -4, 4)$. Then find a unit vector in the direction of $\mathbf{v}$.

Solution The component form of $\mathbf{v}$ is

$$\mathbf{v} = \langle q_1 - p_1, q_2 - p_2, q_3 - p_3 \rangle = \langle 0 - (-2), -4 - 3, 4 - 1 \rangle = \langle 2, -7, 3 \rangle$$

which implies that its magnitude is

$$\|\mathbf{v}\| = \sqrt{2^2 + (-7)^2 + 3^2} = \sqrt{62}.$$

A unit vector in the direction of $\mathbf{v}$ is

$$\begin{aligned} \mathbf{u} &= \frac{\mathbf{v}}{\|\mathbf{v}\|} \\ &= \frac{1}{\sqrt{62}}\langle 2, -7, 3 \rangle \\ &= \left\langle \frac{2}{\sqrt{62}}, \frac{-7}{\sqrt{62}}, \frac{3}{\sqrt{62}} \right\rangle. \end{aligned}$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Parallel vectors
Figure 11.21

Recall from the definition of scalar multiplication that positive scalar multiples of a nonzero vector **v** have the same direction as **v**, whereas negative multiples have the direction opposite of **v**. In general, two nonzero vectors **u** and **v** are **parallel** when there is some scalar c such that $\mathbf{u} = c\mathbf{v}$. For example, in Figure 11.21, the vectors **u**, **v**, and **w** are parallel because

$$\mathbf{u} = 2\mathbf{v} \quad \text{and} \quad \mathbf{w} = -\mathbf{v}.$$

Definition of Parallel Vectors

Two nonzero vectors **u** and **v** are **parallel** when there is some scalar c such that $\mathbf{u} = c\mathbf{v}$.

EXAMPLE 4 Parallel Vectors

Vector **w** has initial point $(2, -1, 3)$ and terminal point $(-4, 7, 5)$. Which of the following vectors is parallel to **w**?

a. $\mathbf{u} = \langle 3, -4, -1 \rangle$

b. $\mathbf{v} = \langle 12, -16, 4 \rangle$

Solution Begin by writing **w** in component form.

$$\mathbf{w} = \langle -4 - 2, 7 - (-1), 5 - 3 \rangle = \langle -6, 8, 2 \rangle$$

a. Because $\mathbf{u} = \langle 3, -4, -1 \rangle = -\frac{1}{2}\langle -6, 8, 2 \rangle = -\frac{1}{2}\mathbf{w}$, you can conclude that **u** is parallel to **w**.

b. In this case, you want to find a scalar c such that

$$\langle 12, -16, 4 \rangle = c\langle -6, 8, 2 \rangle.$$

To find c, equate the corresponding components and solve as shown.

$$\begin{aligned} 12 &= -6c \quad \Rightarrow \quad c = -2 \\ -16 &= 8c \quad \Rightarrow \quad c = -2 \\ 4 &= 2c \quad \Rightarrow \quad c = 2 \end{aligned}$$

Note that $c = -2$ for the first two components and $c = 2$ for the third component. This means that the equation $\langle 12, -16, 4 \rangle = c\langle -6, 8, 2 \rangle$ has no solution, and the vectors are not parallel.

EXAMPLE 5 Using Vectors to Determine Collinear Points

Determine whether the points

$$P(1, -2, 3), \quad Q(2, 1, 0), \quad \text{and} \quad R(4, 7, -6)$$

are collinear.

Solution The component forms of $\overrightarrow{PQ}$ and $\overrightarrow{PR}$ are

$$\overrightarrow{PQ} = \langle 2 - 1, 1 - (-2), 0 - 3 \rangle = \langle 1, 3, -3 \rangle$$

and

$$\overrightarrow{PR} = \langle 4 - 1, 7 - (-2), -6 - 3 \rangle = \langle 3, 9, -9 \rangle.$$

These two vectors have a common initial point. So, P, Q, and R lie on the same line if and only if $\overrightarrow{PQ}$ and $\overrightarrow{PR}$ are parallel—which they are because $\overrightarrow{PR} = 3\overrightarrow{PQ}$, as shown in Figure 11.22.



The points P, Q, and R lie on the same line.
Figure 11.22

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 6 Standard Unit Vector Notation

a. Write the vector $\mathbf{v} = 4\mathbf{i} - 5\mathbf{k}$ in component form.

b. Find the terminal point of the vector $\mathbf{v} = 7\mathbf{i} - \mathbf{j} + 3\mathbf{k}$, given that the initial point is $P(-2, 3, 5)$.

c. Find the magnitude of the vector $\mathbf{v} = -6\mathbf{i} + 2\mathbf{j} - 3\mathbf{k}$. Then find a unit vector in the direction of $\mathbf{v}$.

Solution

a. Because $\mathbf{j}$ is missing, its component is 0 and

$$\mathbf{v} = 4\mathbf{i} - 5\mathbf{k} = \langle 4, 0, -5 \rangle.$$

b. You need to find $Q(q_1, q_2, q_3)$ such that

$$\mathbf{v} = \overrightarrow{PQ} = 7\mathbf{i} - \mathbf{j} + 3\mathbf{k}.$$

This implies that $q_1 - (-2) = 7$, $q_2 - 3 = -1$, and $q_3 - 5 = 3$. The solution of these three equations is $q_1 = 5$, $q_2 = 2$, and $q_3 = 8$. So, Q is $(5, 2, 8)$.

c. Note that $v_1 = -6$, $v_2 = 2$, and $v_3 = -3$. So, the magnitude of $\mathbf{v}$ is

$$\|\mathbf{v}\| = \sqrt{(-6)^2 + 2^2 + (-3)^2} = \sqrt{49} = 7.$$

The unit vector in the direction of $\mathbf{v}$ is

$$\frac{1}{7}(-6\mathbf{i} + 2\mathbf{j} - 3\mathbf{k}) = -\frac{6}{7}\mathbf{i} + \frac{2}{7}\mathbf{j} - \frac{3}{7}\mathbf{k}.$$

EXAMPLE 7 Measuring Force

A professional video camera weighing 9 pounds is supported by a tripod, as shown in Figure 11.23. Represent the force exerted on each leg of the tripod as a vector.



Figure 11.23

Solution

Let the vectors $\mathbf{F}_1$, $\mathbf{F}_2$, and $\mathbf{F}_3$ represent the forces exerted on the three legs. From Figure 11.23, you can determine the directions of $\mathbf{F}_1$, $\mathbf{F}_2$, and $\mathbf{F}_3$ to be as follows.

$$\mathbf{F}_1 = \overrightarrow{PQ}_1 = \langle 0 - 0, -1 - 0, 0 - 4 \rangle = \langle 0, -1, -4 \rangle$$

$$\mathbf{F}_2 = \overrightarrow{PQ}_2 = \left\langle \frac{\sqrt{3}}{2} - 0, \frac{1}{2} - 0, 0 - 4 \right\rangle = \left\langle \frac{\sqrt{3}}{2}, \frac{1}{2}, -4 \right\rangle$$

$$\mathbf{F}_3 = \overrightarrow{PQ}_3 = \left\langle -\frac{\sqrt{3}}{2} - 0, \frac{1}{2} - 0, 0 - 4 \right\rangle = \left\langle -\frac{\sqrt{3}}{2}, \frac{1}{2}, -4 \right\rangle.$$

Because all three legs have the same length and the total force is distributed equally among the three legs, you know that $\|\mathbf{F}_1\| = \|\mathbf{F}_2\| = \|\mathbf{F}_3\|$. So, there exists a constant c such that

$$\mathbf{F}_1 = c\langle 0, -1, -4 \rangle, \quad \mathbf{F}_2 = c\left\langle \frac{\sqrt{3}}{2}, \frac{1}{2}, -4 \right\rangle, \quad \text{and} \quad \mathbf{F}_3 = c\left\langle -\frac{\sqrt{3}}{2}, \frac{1}{2}, -4 \right\rangle.$$

Let the total force exerted by the object be given by $\mathbf{F} = \langle 0, 0, -9 \rangle$. Then, using the fact that

$$\mathbf{F} = \mathbf{F}_1 + \mathbf{F}_2 + \mathbf{F}_3$$

you can conclude that $\mathbf{F}_1$, $\mathbf{F}_2$, and $\mathbf{F}_3$ all have a vertical component of -3. This implies that $c(-4) = -3$ and $c = 3/4$. So, the forces exerted on the legs can be represented by

$$\mathbf{F}_1 = \left\langle 0, -\frac{3}{4}, -3 \right\rangle, \quad \mathbf{F}_2 = \left\langle \frac{3\sqrt{3}}{8}, \frac{3}{8}, -3 \right\rangle, \quad \text{and} \quad \mathbf{F}_3 = \left\langle -\frac{3\sqrt{3}}{8}, \frac{3}{8}, -3 \right\rangle.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

11.2 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. A point in the three-dimensional coordinate system has coordinates (x_0, y_0, z_0). Describe what each coordinate measures.
2. Explain why the y-coordinate of any point in the xz-plane is 0.
3. Describe the graph of $x = 4$ on (a) the number line, (b) the two-dimensional coordinate system, and (c) the three-dimensional coordinate system.
4. Explain how to determine whether two nonzero vectors $\mathbf{u}$ and $\mathbf{v}$ are parallel.

Plotting Points **In Exercises 5–8, plot the points in the same three-dimensional coordinate system.**

5. (a) $(2, 1, 3)$ (b) $(-1, 2, 1)$
6. (a) $(3, -2, 5)$ (b) $\left(\frac{3}{2}, 4, -2\right)$
7. (a) $(5, -2, 2)$ (b) $(5, -2, -2)$
8. (a) $(0, 4, -5)$ (b) $(4, 0, 5)$

Finding Coordinates of a Point **In Exercises 9–12, find the coordinates of the point.**

9. The point is located three units behind the yz-plane, four units to the right of the xz-plane, and five units above the xy-plane.
10. The point is located seven units in front of the yz-plane, two units to the left of the xz-plane, and one unit below the xy-plane.
11. The point is located on the x-axis, 12 units in front of the yz-plane.
12. The point is located in the yz-plane, three units to the right of the xz-plane, and two units above the xy-plane.

Using the Three-Dimensional Coordinate System **In Exercises 13–24, determine the location of a point (x, y, z) that satisfies the condition(s).**

13. $z = 1$
14. $y = 6$
15. $x = -3$
16. $z = -5$
17. $y < 0$
18. $x > 0$
19. $|y| \leq 3$
20. $|x| > 4$
21. $xy > 0, \quad z = -3$
22. $xy < 0, \quad z = 4$
23. $xyz < 0$
24. $xyz > 0$

Finding the Distance Between Two Points in Space **In Exercises 25–28, find the distance between the points.**

25. $(4, 1, 5), (8, 2, 6)$
26. $(-1, 1, 1), (-3, 5, -3)$
27. $(0, 2, 4), (3, 2, 8)$
28. $(-3, 7, 1), (-5, 8, -4)$

Classifying a Triangle **In Exercises 29–32, find the lengths of the sides of the triangle with the indicated vertices, and determine whether the triangle is a right triangle, an isosceles triangle, or neither.**

29. $(0, 0, 4), (2, 6, 7), (6, 4, -8)$
30. $(3, 4, 1), (0, 6, 2), (3, 5, 6)$
31. $(-1, 0, -2), (-1, 5, 2), (-3, -1, 1)$
32. $(4, -1, -1), (2, 0, -4), (3, 5, -1)$

Finding the Midpoint **In Exercises 33–36, find the coordinates of the midpoint of the line segment joining the points.**

33. $(4, 0, -6), (8, 8, 20)$
34. $(7, 2, 2), (-5, -2, -3)$
35. $(3, 4, 6), (1, 8, 0)$
36. $(5, -9, 7), (-2, 3, 3)$

Finding the Equation of a Sphere **In Exercises 37–42, find the standard equation of the sphere with the given characteristics.**

37. Center: $(7, 1, -2)$; Radius: 1
38. Center: $(-1, -5, 8)$; Radius: 5
39. Endpoints of a diameter: $(2, 1, 3), (1, 3, -1)$
40. Endpoints of a diameter: $(-2, 4, -5), (-4, 0, 3)$
41. Center: $(-7, 7, 6)$, tangent to the xy-plane
42. Center: $(-4, 0, 0)$, tangent to the yz-plane

Finding the Equation of a Sphere **In Exercises 43–46, complete the square to write the equation of the sphere in standard form. Find the center and radius.**

43. $x^2 + y^2 + z^2 - 2x + 6y + 8z + 1 = 0$
44. $x^2 + y^2 + z^2 + 9x - 2y + 10z + 19 = 0$
45. $9x^2 + 9y^2 + 9z^2 - 6x + 18y + 1 = 0$
46. $4x^2 + 4y^2 + 4z^2 - 24x - 4y + 8z - 23 = 0$

Finding the Component Form of a Vector in Space **In Exercises 47 and 48, (a) find the component form of the vector $\mathbf{v}$, (b) write the vector using standard unit vector notation, and (c) sketch the vector with its initial point at the origin.**

47.



48.



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Writing a Vector in Different Forms **In Exercises 49 and 50, the initial and terminal points of a vector v are given. (a) Sketch the directed line segment. (b) Find the component form of the vector. (c) Write the vector using standard unit vector notation. (d) Sketch the vector with its initial point at the origin.**

49. Initial point: $(-1, 2, 3)$
Terminal point: $(3, 3, 4)$

50. Initial point: $(2, -1, -2)$
Terminal point: $(-4, 3, 7)$

Finding the Component Form of a Vector in Space **In Exercises 51–54, find the component form and magnitude of the vector v with the given initial and terminal points. Then find a unit vector in the direction of v.**

51. Initial point: $(3, 2, 0)$
Terminal point: $(4, 1, 6)$

52. Initial point: $(1, -2, 4)$
Terminal point: $(2, 4, -2)$

53. Initial point: $(4, 2, 0)$
Terminal point: $(0, 5, 2)$

54. Initial point: $(1, -2, 0)$
Terminal point: $(1, -2, -3)$

Finding a Terminal Point **In Exercises 55 and 56, the vector v and its initial point are given. Find the terminal point.**

55. $\mathbf{v} = \langle 3, -5, 6 \rangle$
Initial point: $(0, 6, 2)$

56. $\mathbf{v} = \left\langle 1, -\frac{2}{3}, \frac{1}{2} \right\rangle$
Initial point: $\left(0, 2, \frac{5}{2}\right)$

Finding Scalar Multiples **In Exercises 57 and 58, find each scalar multiple of v and sketch its graph.**

57. $\mathbf{v} = \langle 1, 2, 2 \rangle$
(a) $2\mathbf{v}$ (b) $-\mathbf{v}$
(c) $\frac{3}{2}\mathbf{v}$ (d) $0\mathbf{v}$

58. $\mathbf{v} = \langle 2, -2, 1 \rangle$
(a) $-\mathbf{v}$ (b) $2\mathbf{v}$
(c) $\frac{1}{2}\mathbf{v}$ (d) $\frac{5}{2}\mathbf{v}$

Finding a Vector **In Exercises 59–62, find the vector z, given that $\mathbf{u} = \langle 1, 2, 3 \rangle$, $\mathbf{v} = \langle 2, 2, -1 \rangle$, and $\mathbf{w} = \langle 4, 0, -4 \rangle$.**

59. $\mathbf{z} = \mathbf{u} - \mathbf{v} + \mathbf{w}$

60. $\mathbf{z} = 5\mathbf{u} - 3\mathbf{v} - \frac{1}{2}\mathbf{w}$

61. $\frac{1}{3}\mathbf{z} - 3\mathbf{u} = \mathbf{w}$

62. $2\mathbf{u} + \mathbf{v} - \mathbf{w} + 3\mathbf{z} = \mathbf{0}$

Parallel Vectors **In Exercises 63–66, determine which of the vectors are parallel to z. Use a graphing utility to confirm your results.**

63. $\mathbf{z} = \langle 3, 2, -5 \rangle$
(a) $\langle -6, -4, 10 \rangle$
(b) $\left\langle 2, \frac{4}{3}, -\frac{10}{3} \right\rangle$
(c) $\langle 6, 4, 10 \rangle$
(d) $\langle 1, -4, 2 \rangle$

64. $\mathbf{z} = \frac{1}{2}\mathbf{i} - \frac{2}{3}\mathbf{j} + \frac{3}{4}\mathbf{k}$
(a) $6\mathbf{i} - 4\mathbf{j} + 9\mathbf{k}$
(b) $-\mathbf{i} + \frac{4}{3}\mathbf{j} - \frac{3}{2}\mathbf{k}$
(c) $12\mathbf{i} + 9\mathbf{k}$
(d) $\frac{3}{4}\mathbf{i} - \mathbf{j} + \frac{9}{8}\mathbf{k}$

65. z has initial point $(1, -1, 3)$ and terminal point $(-2, 3, 5)$.
(a) $-6\mathbf{i} + 8\mathbf{j} + 4\mathbf{k}$ (b) $4\mathbf{j} + 2\mathbf{k}$

66. z has initial point $(5, 4, 1)$ and terminal point $(-2, -4, 4)$.
(a) $\langle 7, 6, 2 \rangle$ (b) $\langle 14, 16, -6 \rangle$

Using Vectors to Determine Collinear Points **In Exercises 67–70, use vectors to determine whether the points are collinear.**

67. $(0, -2, -5)$, $(3, 4, 4)$, $(2, 2, 1)$

68. $(4, -2, 7)$, $(-2, 0, 3)$, $(7, -3, 9)$

69. $(1, 2, 4)$, $(2, 5, 0)$, $(0, 1, 5)$

70. $(0, 0, 0)$, $(1, 3, -2)$, $(2, -6, 4)$

Verifying a Parallelogram **In Exercises 71 and 72, use vectors to show that the points form the vertices of a parallelogram.**

71. $(2, 9, 1)$, $(3, 11, 4)$, $(0, 10, 2)$, $(1, 12, 5)$

72. $(1, 1, 3)$, $(9, -1, -2)$, $(11, 2, -9)$, $(3, 4, -4)$

Finding the Magnitude **In Exercises 73–78, find the magnitude of v.**

73. $\mathbf{v} = \langle -1, 0, 1 \rangle$

74. $\mathbf{v} = \langle -5, -3, -4 \rangle$

75. $\mathbf{v} = 3\mathbf{j} - 5\mathbf{k}$

76. $\mathbf{v} = 2\mathbf{i} + 5\mathbf{j} - \mathbf{k}$

77. $\mathbf{v} = \mathbf{i} - 2\mathbf{j} - 3\mathbf{k}$

78. $\mathbf{v} = -4\mathbf{i} + 3\mathbf{j} + 7\mathbf{k}$

Finding Unit Vectors **In Exercises 79–82, find a unit vector (a) in the direction of v and (b) in the direction opposite of v.**

79. $\mathbf{v} = \langle 2, -1, 2 \rangle$

80. $\mathbf{v} = \langle 6, 0, 8 \rangle$

81. $\mathbf{v} = 4\mathbf{i} - 5\mathbf{j} + 3\mathbf{k}$

82. $\mathbf{v} = 5\mathbf{i} + 3\mathbf{j} - \mathbf{k}$

Finding a Vector **In Exercises 83–86, find the vector v with the given magnitude and the same direction as u.**

	Magnitude	Direction
83.	$\|\mathbf{v}\| = 10$	$\mathbf{u} = \langle 0, 3, 3 \rangle$
84.	$\|\mathbf{v}\| = 3$	$\mathbf{u} = \langle 1, 1, 1 \rangle$
85.	$\|\mathbf{v}\| = \frac{3}{2}$	$\mathbf{u} = \langle 2, -2, 1 \rangle$
86.	$\|\mathbf{v}\| = 7$	$\mathbf{u} = \langle -4, 6, 2 \rangle$

Sketching a Vector **In Exercises 87 and 88, sketch the vector v and write its component form.**

87. **v** lies in the yz-plane, has magnitude 2, and makes an angle of $30°$ with the positive y-axis.

88. **v** lies in the xz-plane, has magnitude 5, and makes an angle of $45°$ with the positive z-axis.

Finding a Point Using Vectors **In Exercises 89 and 90, use vectors to find the point that lies two-thirds of the way from P to Q.**

89. $P(4, 3, 0)$, $Q(1, -3, 3)$

90. $P(1, 2, 5)$, $Q(6, 8, 2)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploring Concepts

91. The initial and terminal points of the vector $\mathbf{v}$ are (x_1, y_1, z_1) and (x, y, z). Describe the set of all points (x, y, z) such that $\|\mathbf{v}\| = 4$.

92. Let $\mathbf{r} = \langle x, y, z \rangle$ and $\mathbf{r}_0 = \langle 1, 1, 1 \rangle$. Describe the set of all points (x, y, z) such that $\|\mathbf{r} - \mathbf{r}_0\| = 2$.

93. Let $\mathbf{r} = \langle x, y, z \rangle$. Describe the set of all points (x, y, z) such that $\|\mathbf{r}\| > 1$.

94. HOW DO YOU SEE IT? Determine (x, y, z) for each figure. Then find the component form of the vector from the point on the x-axis to the point (x, y, z).

(a)



(b)



95. Using Vectors Consider two nonzero vectors $\mathbf{u}$ and $\mathbf{v}$, and let s and t be real numbers. Describe the geometric figure generated by connecting the terminal points of the three vectors $t\mathbf{v}$, $\mathbf{u} + t\mathbf{v}$, and $s\mathbf{u} + t\mathbf{v}$.

96. Using Vectors Let $\mathbf{u} = \mathbf{i} + \mathbf{j}$, $\mathbf{v} = \mathbf{j} + \mathbf{k}$, and $\mathbf{w} = a\mathbf{u} + b\mathbf{v}$.

(a) Sketch $\mathbf{u}$ and $\mathbf{v}$.

(b) If $\mathbf{w} = \mathbf{0}$, show that a and b must both be zero.

(c) Find a and b such that $\mathbf{w} = \mathbf{i} + 2\mathbf{j} + \mathbf{k}$.

(d) Show that no choice of a and b yields $\mathbf{w} = \mathbf{i} + 2\mathbf{j} + 3\mathbf{k}$.

97. Diagonal of a Cube Find the component form of the unit vector $\mathbf{v}$ in the direction of the diagonal of the cube shown in the figure.



Figure for 97



Figure for 98

98. Tower Guy Wire The guy wire supporting a 100-foot tower has a tension of 550 pounds. Using the distance shown in the figure, write the component form of the vector $\mathbf{F}$ representing the tension in the wire.

99. Auditorium Lights

The lights in an auditorium are 24-pound discs of radius 18 inches. Each disc is supported by three equally spaced cables that are L inches long (see figure).





(a) Write the tension T in each cable as a function of L. Determine the domain of the function.

(b) Use a graphing utility and the function in part (a) to complete the table.

L	20	25	30	35	40	45	50
T							

(c) Use a graphing utility to graph the function in part (a). Determine the asymptotes of the graph.

(d) Confirm the asymptotes of the graph in part (c) analytically.

(e) Determine the minimum length of each cable when a cable is designed to carry a maximum load of 10 pounds.

100. Think About It Suppose the length of each cable in Exercise 99 has a fixed length $L = a$ and the radius of each disc is r_0 inches. Make a conjecture about the limit $\lim_{r_0 \to a^-} T$ and give a reason for your answer.

101. Load Supports Find the tension in each of the supporting cables in the figure when the weight of the crate is 500 newtons.



Figure for 101



Figure for 102

102. Construction A precast concrete wall is temporarily kept in its vertical position by ropes (see figure). Find the total force exerted on the pin at position A. The tensions in AB and AC are 420 pounds and 650 pounds, respectively.

103. Geometry Write an equation whose graph consists of the set of points $P(x, y, z)$ that are twice as far from $A(0, -1, 1)$ as from $B(1, 2, 0)$. Describe the geometric figure represented by the equation.

Pavel L Photo and Video/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

11.3 The Dot Product of Two Vectors

GO DIGITAL

- Use properties of the dot product of two vectors.
- Find the angle between two vectors using the dot product.
- Find the direction cosines of a vector in space.
- Find the projection of a vector onto another vector.
- Use vectors to find the work done by a constant force.

The Dot Product

So far, you have studied two operations with vectors—vector addition and multiplication by a scalar—each of which yields another vector. In this section, you will study a third vector operation, the **dot product.** This product yields a scalar, rather than a vector.

REMARK Because the dot product of two vectors yields a scalar, it is also called the *scalar product* (or *inner product*) of the two vectors.

Definition of Dot Product

The **dot product** of $\mathbf{u} = \langle u_1, u_2 \rangle$ and $\mathbf{v} = \langle v_1, v_2 \rangle$ is

$$\mathbf{u} \cdot \mathbf{v} = u_1v_1 + u_2v_2.$$

The **dot product** of $\mathbf{u} = \langle u_1, u_2, u_3 \rangle$ and $\mathbf{v} = \langle v_1, v_2, v_3 \rangle$ is

$$\mathbf{u} \cdot \mathbf{v} = u_1v_1 + u_2v_2 + u_3v_3.$$

Exploration

Interpreting a Dot Product

Several vectors are shown below on the unit circle. Find the dot products of several pairs of vectors. Then find the angle between each pair that you used. Make a conjecture about the relationship between the dot product of two vectors and the angle between the vectors.



THEOREM 11.4 Properties of the Dot Product

Let $\mathbf{u}$, $\mathbf{v}$, and $\mathbf{w}$ be vectors in the plane or in space and let c be a scalar.

1. $\mathbf{u} \cdot \mathbf{v} = \mathbf{v} \cdot \mathbf{u}$ — Commutative Property
2. $\mathbf{u} \cdot (\mathbf{v} + \mathbf{w}) = \mathbf{u} \cdot \mathbf{v} + \mathbf{u} \cdot \mathbf{w}$ — Distributive Property
3. $c(\mathbf{u} \cdot \mathbf{v}) = c\mathbf{u} \cdot \mathbf{v} = \mathbf{u} \cdot c\mathbf{v}$ — Associative Property
4. $\mathbf{0} \cdot \mathbf{v} = 0$
5. $\mathbf{v} \cdot \mathbf{v} = \|\mathbf{v}\|^2$

Proof To prove the first property, let $\mathbf{u} = \langle u_1, u_2, u_3 \rangle$ and $\mathbf{v} = \langle v_1, v_2, v_3 \rangle$. Then

$$\mathbf{u} \cdot \mathbf{v} = u_1v_1 + u_2v_2 + u_3v_3 = v_1u_1 + v_2u_2 + v_3u_3 = \mathbf{v} \cdot \mathbf{u}.$$

For the fifth property, let $\mathbf{v} = \langle v_1, v_2, v_3 \rangle$. Then

$$\mathbf{v} \cdot \mathbf{v} = v_1^2 + v_2^2 + v_3^2 = \left(\sqrt{v_1^2 + v_2^2 + v_3^2}\right)^2 = \|\mathbf{v}\|^2.$$

Proofs of the other properties are left to you. ■

EXAMPLE 1 Finding Dot Products

Let $\mathbf{u} = \langle 2, -2 \rangle$, $\mathbf{v} = \langle 5, 8 \rangle$, and $\mathbf{w} = \langle -4, 3 \rangle$.

a. $\mathbf{u} \cdot \mathbf{v} = \langle 2, -2 \rangle \cdot \langle 5, 8 \rangle = 2(5) + (-2)(8) = -6$

b. $(\mathbf{u} \cdot \mathbf{v})\mathbf{w} = -6\langle -4, 3 \rangle = \langle 24, -18 \rangle$

c. $\mathbf{u} \cdot (2\mathbf{v}) = 2(\mathbf{u} \cdot \mathbf{v}) = 2(-6) = -12$

d. $\|\mathbf{w}\|^2 = \mathbf{w} \cdot \mathbf{w} = \langle -4, 3 \rangle \cdot \langle -4, 3 \rangle = (-4)(-4) + (3)(3) = 25$

Notice that the result of part (b) is a *vector* quantity, whereas the results of the other three parts are *scalar* quantities. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Angle Between Two Vectors

The **angle between two nonzero vectors** is the angle θ, $0 \le \theta \le \pi$, between their respective standard position vectors, as shown in Figure 11.24. The next theorem shows how to find this angle using the dot product. (Note that the angle between the zero vector and another vector is not defined here.)



The angle between two vectors
Figure 11.24

THEOREM 11.5 Angle Between Two Vectors

If θ is the angle between two nonzero vectors $\mathbf{u}$ and $\mathbf{v}$, where $0 \le \theta \le \pi$, then

$$\cos\theta = \frac{\mathbf{u} \cdot \mathbf{v}}{\|\mathbf{u}\|\,\|\mathbf{v}\|}.$$



Law of Cosines:
$b^2 = a^2 + c^2 - 2ac\cos\theta$
Figure 11.25

Proof Consider the triangle determined by vectors $\mathbf{u}$, $\mathbf{v}$, and $\mathbf{v} - \mathbf{u}$, as shown in Figure 11.24. By the Law of Cosines (see Figure 11.25),

$$\|\mathbf{v} - \mathbf{u}\|^2 = \|\mathbf{u}\|^2 + \|\mathbf{v}\|^2 - 2\|\mathbf{u}\|\,\|\mathbf{v}\|\cos\theta.$$

Using the properties of the dot product, the left side can be rewritten as

$$\begin{aligned}\|\mathbf{v} - \mathbf{u}\|^2 &= (\mathbf{v} - \mathbf{u}) \cdot (\mathbf{v} - \mathbf{u}) \\ &= (\mathbf{v} - \mathbf{u}) \cdot \mathbf{v} - (\mathbf{v} - \mathbf{u}) \cdot \mathbf{u} \\ &= \mathbf{v} \cdot \mathbf{v} - \mathbf{u} \cdot \mathbf{v} - \mathbf{v} \cdot \mathbf{u} + \mathbf{u} \cdot \mathbf{u} \\ &= \|\mathbf{v}\|^2 - 2\mathbf{u} \cdot \mathbf{v} + \|\mathbf{u}\|^2\end{aligned}$$

and substitution back into the Law of Cosines yields

$$\begin{aligned}\|\mathbf{v}\|^2 - 2\mathbf{u} \cdot \mathbf{v} + \|\mathbf{u}\|^2 &= \|\mathbf{u}\|^2 + \|\mathbf{v}\|^2 - 2\|\mathbf{u}\|\,\|\mathbf{v}\|\cos\theta \\ -2\mathbf{u} \cdot \mathbf{v} &= -2\|\mathbf{u}\|\,\|\mathbf{v}\|\cos\theta \\ \cos\theta &= \frac{\mathbf{u} \cdot \mathbf{v}}{\|\mathbf{u}\|\,\|\mathbf{v}\|}.\end{aligned}$$

Note in Theorem 11.5 that because $\|\mathbf{u}\|$ and $\|\mathbf{v}\|$ are always positive, $\mathbf{u} \cdot \mathbf{v}$ and $\cos\theta$ will always have the same sign. Figure 11.26 shows the possible orientations of two vectors.



$\theta = \pi$	$\pi/2 < \theta < \pi$	$\theta = \pi/2$	$0 < \theta < \pi/2$	$\theta = 0$
$\cos\theta = -1$	$-1 < \cos\theta < 0$	$\cos\theta = 0$	$0 < \cos\theta < 1$	$\cos\theta = 1$

Figure 11.26

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

From Theorem 11.5, you can determine that two nonzero vectors meet at a right angle if and only if their dot product is zero. Two such vectors are said to be **orthogonal.**

Definition of Orthogonal Vectors

The vectors $\mathbf{u}$ and $\mathbf{v}$ are orthogonal when $\mathbf{u} \cdot \mathbf{v} = 0$.

REMARK The terms "perpendicular," "orthogonal," and "normal" all mean essentially the same thing—meeting at right angles. It is common, however, to say that two vectors are *orthogonal*, two lines or planes are *perpendicular*, and a vector is *normal* to a line or plane.

From this definition, it follows that the zero vector is orthogonal to every vector $\mathbf{u}$, because $\mathbf{0} \cdot \mathbf{u} = 0$. Moreover, for $0 \leq \theta \leq \pi$, you know that $\cos\theta = 0$ if and only if $\theta = \pi/2$. So, you can use Theorem 11.5 to conclude that two *nonzero* vectors are orthogonal if and only if the angle between them is $\pi/2$.

EXAMPLE 2 Finding the Angle Between Two Vectors

See LarsonCalculus.com for an interactive version of this type of example.

For $\mathbf{u} = \langle 3, -1, 2\rangle$, $\mathbf{v} = \langle -4, 0, 2\rangle$, $\mathbf{w} = \langle 1, -1, -2\rangle$, and $\mathbf{z} = \langle 2, 0, -1\rangle$, find the angle between each pair of vectors.

a. $\mathbf{u}$ and $\mathbf{v}$ **b.** $\mathbf{u}$ and $\mathbf{w}$ **c.** $\mathbf{v}$ and $\mathbf{z}$

Solution

a. $\cos\theta = \dfrac{\mathbf{u} \cdot \mathbf{v}}{\|\mathbf{u}\|\|\mathbf{v}\|} = \dfrac{-12 + 0 + 4}{\sqrt{14}\sqrt{20}} = \dfrac{-8}{2\sqrt{14}\sqrt{5}} = \dfrac{-4}{\sqrt{70}}$

Because $\mathbf{u} \cdot \mathbf{v} < 0$, $\theta = \arccos\dfrac{-4}{\sqrt{70}} \approx 2.069$ radians.

REMARK The angle between $\mathbf{u}$ and $\mathbf{v}$ in Example 2(a) can also be written as approximately 118.561°.

b. $\cos\theta = \dfrac{\mathbf{u} \cdot \mathbf{w}}{\|\mathbf{u}\|\|\mathbf{w}\|} = \dfrac{3 + 1 - 4}{\sqrt{14}\sqrt{6}} = \dfrac{0}{\sqrt{84}} = 0$

Because $\mathbf{u} \cdot \mathbf{w} = 0$, $\mathbf{u}$ and $\mathbf{w}$ are *orthogonal*. So, $\theta = \pi/2$.

c. $\cos\theta = \dfrac{\mathbf{v} \cdot \mathbf{z}}{\|\mathbf{v}\|\|\mathbf{z}\|} = \dfrac{-8 + 0 - 2}{\sqrt{20}\sqrt{5}} = \dfrac{-10}{\sqrt{100}} = -1$

Consequently, $\theta = \pi$. Note that $\mathbf{v}$ and $\mathbf{z}$ are parallel, with $\mathbf{v} = -2\mathbf{z}$. ■

When the angle between two vectors is known, rewriting Theorem 11.5 in the form

$$\mathbf{u} \cdot \mathbf{v} = \|\mathbf{u}\|\|\mathbf{v}\|\cos\theta \qquad \text{Alternative form of dot product}$$

produces an alternative way to calculate the dot product.

EXAMPLE 3 Alternative Form of the Dot Product

Given that $\|\mathbf{u}\| = 10$, $\|\mathbf{v}\| = 7$, and the angle between $\mathbf{u}$ and $\mathbf{v}$ is $\pi/4$, find $\mathbf{u} \cdot \mathbf{v}$.

Solution Use the alternative form of the dot product as shown.

$$\mathbf{u} \cdot \mathbf{v} = \|\mathbf{u}\|\|\mathbf{v}\|\cos\theta = (10)(7)\cos\frac{\pi}{4} = 35\sqrt{2}$$

■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Direction Cosines



Direction angles

For a vector in the plane, you have seen that it is convenient to measure direction in terms of the angle, measured counterclockwise, *from* the positive x-axis *to* the vector. In space, it is more convenient to measure direction in terms of the angles *between* the nonzero vector $\mathbf{v}$ and the three unit vectors $\mathbf{i}$, $\mathbf{j}$, and $\mathbf{k}$, as shown in the figure at the right. The angles α, β, and γ are the **direction angles of v,** and $\cos\alpha$, $\cos\beta$, and $\cos\gamma$ are the **direction cosines of v.** Because

$$\mathbf{v} \cdot \mathbf{i} = \|\mathbf{v}\|\|\mathbf{i}\| \cos\alpha = \|\mathbf{v}\| \cos\alpha$$

and

$$\mathbf{v} \cdot \mathbf{i} = \langle v_1, v_2, v_3 \rangle \cdot \langle 1, 0, 0 \rangle = v_1$$

it follows that $\cos\alpha = v_1/\|\mathbf{v}\|$. By similar reasoning with the unit vectors $\mathbf{j}$ and $\mathbf{k}$, you have

$$\cos\alpha = \frac{v_1}{\|\mathbf{v}\|} \qquad \alpha \text{ is the angle between } \mathbf{v} \text{ and } \mathbf{i}.$$

$$\cos\beta = \frac{v_2}{\|\mathbf{v}\|} \qquad \beta \text{ is the angle between } \mathbf{v} \text{ and } \mathbf{j}.$$

$$\cos\gamma = \frac{v_3}{\|\mathbf{v}\|}. \qquad \gamma \text{ is the angle between } \mathbf{v} \text{ and } \mathbf{k}.$$

Consequently, any nonzero vector $\mathbf{v}$ in space has the normalized form

$$\frac{\mathbf{v}}{\|\mathbf{v}\|} = \frac{v_1}{\|\mathbf{v}\|}\mathbf{i} + \frac{v_2}{\|\mathbf{v}\|}\mathbf{j} + \frac{v_3}{\|\mathbf{v}\|}\mathbf{k} = \cos\alpha\mathbf{i} + \cos\beta\mathbf{j} + \cos\gamma\mathbf{k}$$

and because $\mathbf{v}/\|\mathbf{v}\|$ is a unit vector, it follows that

$$\cos^2\alpha + \cos^2\beta + \cos^2\gamma = 1.$$

REMARK Recall that α, β, and γ are the Greek letters alpha, beta, and gamma, respectively.

EXAMPLE 4 Finding Direction Angles

Find the direction cosines and angles for the vector $\mathbf{v} = 2\mathbf{i} + 3\mathbf{j} + 4\mathbf{k}$, and show that $\cos^2\alpha + \cos^2\beta + \cos^2\gamma = 1$.

Solution Because $\|\mathbf{v}\| = \sqrt{2^2 + 3^2 + 4^2} = \sqrt{29}$, you can write the following.

$$\cos\alpha = \frac{v_1}{\|\mathbf{v}\|} = \frac{2}{\sqrt{29}} \Rightarrow \alpha \approx 68.2° \qquad \text{Angle between } \mathbf{v} \text{ and } \mathbf{i}$$

$$\cos\beta = \frac{v_2}{\|\mathbf{v}\|} = \frac{3}{\sqrt{29}} \Rightarrow \beta \approx 56.1° \qquad \text{Angle between } \mathbf{v} \text{ and } \mathbf{j}$$

$$\cos\gamma = \frac{v_3}{\|\mathbf{v}\|} = \frac{4}{\sqrt{29}} \Rightarrow \gamma \approx 42.0° \qquad \text{Angle between } \mathbf{v} \text{ and } \mathbf{k}$$

Furthermore, the sum of the squares of the direction cosines is

$$\cos^2\alpha + \cos^2\beta + \cos^2\gamma = \frac{4}{29} + \frac{9}{29} + \frac{16}{29} = \frac{29}{29} = 1.$$

See Figure 11.27.

α = angle between $\mathbf{v}$ and $\mathbf{i}$
β = angle between $\mathbf{v}$ and $\mathbf{j}$
γ = angle between $\mathbf{v}$ and $\mathbf{k}$



The direction angles of $\mathbf{v}$
Figure 11.27

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The force due to gravity pulls the boat against the ramp and down the ramp.
Figure 11.28

GO DIGITAL

Projections and Vector Components

You have already seen applications in which two vectors are added to produce a resultant vector. Many applications in physics and engineering pose the reverse problem—decomposing a vector into the sum of two **vector components.** The following physical example enables you to see the usefulness of this procedure.

Consider a boat on an inclined ramp, as shown in Figure 11.28. The force $\mathbf{F}$ due to gravity pulls the boat *down* the ramp and *against* the ramp. These two forces, $\mathbf{w}_1$ and $\mathbf{w}_2$, are orthogonal—they are called the vector components of $\mathbf{F}$.

$$\mathbf{F} = \mathbf{w}_1 + \mathbf{w}_2 \qquad \text{Vector components of } \mathbf{F}$$

The forces $\mathbf{w}_1$ and $\mathbf{w}_2$ help you analyze the effect of gravity on the boat. For example, $\mathbf{w}_1$ indicates the force necessary to keep the boat from rolling down the ramp, whereas $\mathbf{w}_2$ indicates the force that the tires must withstand.

Definitions of Projection and Vector Components

Let $\mathbf{u}$ and $\mathbf{v}$ be nonzero vectors. Moreover, let

$$\mathbf{u} = \mathbf{w}_1 + \mathbf{w}_2$$

where $\mathbf{w}_1$ is parallel to $\mathbf{v}$ and $\mathbf{w}_2$ is orthogonal to $\mathbf{v}$, as shown in Figure 11.29.

1. $\mathbf{w}_1$ is called the **projection of u onto v** or the **vector component of u along v,** and is denoted by $\mathbf{w}_1 = \text{proj}_{\mathbf{v}}\mathbf{u}$.
2. $\mathbf{w}_2 = \mathbf{u} - \mathbf{w}_1$ is called the **vector component of u orthogonal to v.**



$\mathbf{w}_1 = \text{proj}_{\mathbf{v}}\mathbf{u}$ = projection of $\mathbf{u}$ onto $\mathbf{v}$ = vector component of $\mathbf{u}$ along $\mathbf{v}$
$\mathbf{w}_2$ = vector component of $\mathbf{u}$ orthogonal to $\mathbf{v}$
Figure 11.29

EXAMPLE 5 Finding a Vector Component of u Orthogonal to v

Find the vector component of $\mathbf{u} = \langle 5, 10\rangle$ that is orthogonal to $\mathbf{v} = \langle 4, 3\rangle$, given that

$$\mathbf{w}_1 = \text{proj}_{\mathbf{v}}\mathbf{u} = \langle 8, 6\rangle$$

and

$$\mathbf{u} = \langle 5, 10\rangle = \mathbf{w}_1 + \mathbf{w}_2.$$

Solution Because $\mathbf{u} = \mathbf{w}_1 + \mathbf{w}_2$, where $\mathbf{w}_1$ is parallel to $\mathbf{v}$, it follows that $\mathbf{w}_2$ is the vector component of $\mathbf{u}$ orthogonal to $\mathbf{v}$. So, you have

$$\begin{aligned}\mathbf{w}_2 &= \mathbf{u} - \mathbf{w}_1\\ &= \langle 5, 10\rangle - \langle 8, 6\rangle\\ &= \langle -3, 4\rangle.\end{aligned}$$

Check to see that $\mathbf{w}_2$ is orthogonal to $\mathbf{v}$, as shown in Figure 11.30. ■



$\mathbf{u} = \mathbf{w}_1 + \mathbf{w}_2$
Figure 11.30

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

In Example 5, you were given the projection of $\mathbf{u}$ onto $\mathbf{v}$. In general, to find a projection, use the next theorem. The proof of this theorem is left as an exercise (see Exercise 74).

THEOREM 11.6 Projection Using the Dot Product

If $\mathbf{u}$ and $\mathbf{v}$ are nonzero vectors, then the projection of $\mathbf{u}$ onto $\mathbf{v}$ is

$$\text{proj}_{\mathbf{v}}\mathbf{u} = \left(\frac{\mathbf{u} \cdot \mathbf{v}}{\|\mathbf{v}\|^2}\right)\mathbf{v}.$$

REMARK Note the distinction between the terms "component" and "vector component." For example, using the standard unit vectors with $\mathbf{u} = u_1\mathbf{i} + u_2\mathbf{j}$, u_1 is the *component* of $\mathbf{u}$ in the direction of $\mathbf{i}$, and $u_1\mathbf{i}$ is the *vector component* in the direction of $\mathbf{i}$.

The projection of $\mathbf{u}$ onto $\mathbf{v}$ can be written as a scalar multiple of a unit vector in the direction of $\mathbf{v}$. That is,

$$\left(\frac{\mathbf{u} \cdot \mathbf{v}}{\|\mathbf{v}\|^2}\right)\mathbf{v} = \left(\frac{\mathbf{u} \cdot \mathbf{v}}{\|\mathbf{v}\|}\right)\frac{\mathbf{v}}{\|\mathbf{v}\|} = (k)\frac{\mathbf{v}}{\|\mathbf{v}\|}.$$

The scalar k is called the **component of u in the direction of v.** So,

$$k = \frac{\mathbf{u} \cdot \mathbf{v}}{\|\mathbf{v}\|} = \|\mathbf{u}\| \cos\theta.$$

EXAMPLE 6 Decomposing a Vector into Vector Components

Find the projection of $\mathbf{u}$ onto $\mathbf{v}$ and the vector component of $\mathbf{u}$ orthogonal to $\mathbf{v}$ for

$$\mathbf{u} = 3\mathbf{i} - 5\mathbf{j} + 2\mathbf{k} \quad \text{and} \quad \mathbf{v} = 7\mathbf{i} + \mathbf{j} - 2\mathbf{k}.$$

Solution The projection of $\mathbf{u}$ onto $\mathbf{v}$ is

$$\mathbf{w}_1 = \text{proj}_{\mathbf{v}}\mathbf{u} = \left(\frac{\mathbf{u} \cdot \mathbf{v}}{\|\mathbf{v}\|^2}\right)\mathbf{v} = \left(\frac{12}{54}\right)(7\mathbf{i} + \mathbf{j} - 2\mathbf{k}) = \frac{14}{9}\mathbf{i} + \frac{2}{9}\mathbf{j} - \frac{4}{9}\mathbf{k}.$$

The vector component of $\mathbf{u}$ orthogonal to $\mathbf{v}$ is the vector

$$\mathbf{w}_2 = \mathbf{u} - \mathbf{w}_1 = (3\mathbf{i} - 5\mathbf{j} + 2\mathbf{k}) - \left(\frac{14}{9}\mathbf{i} + \frac{2}{9}\mathbf{j} - \frac{4}{9}\mathbf{k}\right) = \frac{13}{9}\mathbf{i} - \frac{47}{9}\mathbf{j} + \frac{22}{9}\mathbf{k}.$$

See Figure 11.31.



$\mathbf{u} = \mathbf{w}_1 + \mathbf{w}_2$

Figure 11.31

EXAMPLE 7 Finding a Force

A 600-pound boat sits on a ramp inclined at 30°, as shown in Figure 11.32. What force is required to keep the boat from rolling down the ramp?

Solution Because the force due to gravity is vertical and downward, you can represent the gravitational force by the vector $\mathbf{F} = -600\mathbf{j}$. To find the force required to keep the boat from rolling down the ramp, project $\mathbf{F}$ onto a unit vector $\mathbf{v}$ in the direction of the ramp, as follows.

$$\mathbf{v} = \cos 30°\mathbf{i} + \sin 30°\mathbf{j} = \frac{\sqrt{3}}{2}\mathbf{i} + \frac{1}{2}\mathbf{j} \qquad \text{Unit vector along ramp}$$

Therefore, the projection of $\mathbf{F}$ onto $\mathbf{v}$ is

$$\mathbf{w}_1 = \text{proj}_{\mathbf{v}}\mathbf{F} = \left(\frac{\mathbf{F} \cdot \mathbf{v}}{\|\mathbf{v}\|^2}\right)\mathbf{v} = (\mathbf{F} \cdot \mathbf{v})\mathbf{v} = (-600)\left(\frac{1}{2}\right)\mathbf{v} = -300\left(\frac{\sqrt{3}}{2}\mathbf{i} + \frac{1}{2}\mathbf{j}\right).$$

The magnitude of this force is 300, so a force of 300 pounds is required to keep the boat from rolling down the ramp. ■



Figure 11.32

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Work

The work W done by the constant force $\mathbf{F}$ acting along the line of motion of an object is given by

$$W = (\text{magnitude of force})(\text{distance}) = \|\mathbf{F}\|\|\overrightarrow{PQ}\|$$

as shown in Figure 11.33(a). When the constant force $\mathbf{F}$ is not directed along the line of motion, Figure 11.33(b) shows that the work W done by the force is

$$W = \|\text{proj}_{\overrightarrow{PQ}}\mathbf{F}\|\|\overrightarrow{PQ}\| = (\cos\theta)\|\mathbf{F}\|\|\overrightarrow{PQ}\| = \mathbf{F} \cdot \overrightarrow{PQ}.$$



(a) Force acts along the line of motion. **(b)** Force acts at angle θ with the line of motion.

Figure 11.33

This notion of work is summarized in the next definition.

Definition of Work

The work W done by a constant force $\mathbf{F}$ as its point of application moves along the vector $\overrightarrow{PQ}$ is one of the following.

1. $W = \|\text{proj}_{\overrightarrow{PQ}}\mathbf{F}\|\|\overrightarrow{PQ}\|$ Projection form
2. $W = \mathbf{F} \cdot \overrightarrow{PQ}$ Dot product form

EXAMPLE 8 Finding Work

To close a sliding door, a person pulls on a rope with a constant force of 50 pounds at a constant angle of 60°, as shown in Figure 11.34. Find the work done in moving the door 12 feet to its closed position.



Figure 11.34

Solution Using a projection, you can calculate the work as follows.

$$W = \|\text{proj}_{\overrightarrow{PQ}}\mathbf{F}\|\|\overrightarrow{PQ}\| = \cos(60°)\|\mathbf{F}\|\|\overrightarrow{PQ}\| = \frac{1}{2}(50)(12) = 300 \text{ foot-pounds}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

11.3 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Two nonzero vectors have a dot product of zero. What is true about the relative position of the vectors?
2. Consider the vector

$\mathbf{v} = \langle v_1, v_2, v_3 \rangle$.

What is the meaning of $\arccos \dfrac{v_2}{\|\mathbf{v}\|} = 30°$?

Finding Dot Products In Exercises 3–10, find (a) $\mathbf{u} \cdot \mathbf{v}$, (b) $\mathbf{u} \cdot \mathbf{u}$, (c) $\|\mathbf{v}\|^2$, (d) $(\mathbf{u} \cdot \mathbf{v})\mathbf{v}$, and (e) $\mathbf{u} \cdot (3\mathbf{v})$.

3. $\mathbf{u} = \langle 3, 4 \rangle$, $\mathbf{v} = \langle -1, 5 \rangle$
4. $\mathbf{u} = \langle 4, 10 \rangle$, $\mathbf{v} = \langle -2, 3 \rangle$
5. $\mathbf{u} = \langle 6, -4 \rangle$, $\mathbf{v} = \langle -3, 2 \rangle$
6. $\mathbf{u} = \langle -7, -1 \rangle$, $\mathbf{v} = \langle -4, -1 \rangle$
7. $\mathbf{u} = \langle 2, -3, 4 \rangle$, $\mathbf{v} = \langle 0, 6, 5 \rangle$
8. $\mathbf{u} = \langle -5, 0, 5 \rangle$, $\mathbf{v} = \langle -1, 2, 1 \rangle$
9. $\mathbf{u} = 2\mathbf{i} - \mathbf{j} + \mathbf{k}$, $\mathbf{v} = \mathbf{i} - \mathbf{k}$
10. $\mathbf{u} = 2\mathbf{i} + \mathbf{j} - 2\mathbf{k}$, $\mathbf{v} = \mathbf{i} - 3\mathbf{j} + 2\mathbf{k}$

Finding the Angle Between Two Vectors In Exercises 11–18, find the angle θ between the vectors (a) in radians and (b) in degrees.

11. $\mathbf{u} = \langle 1, 1 \rangle$, $\mathbf{v} = \langle 2, -2 \rangle$
12. $\mathbf{u} = \langle 3, 1 \rangle$, $\mathbf{v} = \langle 2, -1 \rangle$
13. $\mathbf{u} = 3\mathbf{i} + \mathbf{j}$, $\mathbf{v} = -2\mathbf{i} + 4\mathbf{j}$
14. $\mathbf{u} = \cos\left(\dfrac{\pi}{6}\right)\mathbf{i} + \sin\left(\dfrac{\pi}{6}\right)\mathbf{j}$, $\mathbf{v} = \cos\left(\dfrac{3\pi}{4}\right)\mathbf{i} + \sin\left(\dfrac{3\pi}{4}\right)\mathbf{j}$
15. $\mathbf{u} = \langle 1, 1, 1 \rangle$, $\mathbf{v} = \langle 2, 1, -1 \rangle$
16. $\mathbf{u} = 3\mathbf{i} + 2\mathbf{j} + \mathbf{k}$, $\mathbf{v} = 2\mathbf{i} - 3\mathbf{j}$
17. $\mathbf{u} = 3\mathbf{i} + 4\mathbf{j}$, $\mathbf{v} = -2\mathbf{j} + 3\mathbf{k}$
18. $\mathbf{u} = 2\mathbf{i} - 3\mathbf{j} + \mathbf{k}$, $\mathbf{v} = \mathbf{i} - 2\mathbf{j} + \mathbf{k}$

Alternative Form of Dot Product In Exercises 19 and 20, use the alternative form of the dot product to find $\mathbf{u} \cdot \mathbf{v}$.

19. $\|\mathbf{u}\| = 8$, $\|\mathbf{v}\| = 5$, and the angle between $\mathbf{u}$ and $\mathbf{v}$ is $\pi/3$.
20. $\|\mathbf{u}\| = 40$, $\|\mathbf{v}\| = 25$, and the angle between $\mathbf{u}$ and $\mathbf{v}$ is $5\pi/6$.

Comparing Vectors In Exercises 21–26, determine whether $\mathbf{u}$ and $\mathbf{v}$ are orthogonal, parallel, or neither.

21. $\mathbf{u} = \langle 4, 3 \rangle$, $\mathbf{v} = \left\langle \frac{1}{2}, -\frac{2}{3} \right\rangle$
22. $\mathbf{u} = -\frac{1}{3}(\mathbf{i} - 2\mathbf{j})$, $\mathbf{v} = 2\mathbf{i} - 4\mathbf{j}$
23. $\mathbf{u} = \mathbf{j} + 6\mathbf{k}$, $\mathbf{v} = \mathbf{i} - 2\mathbf{j} - \mathbf{k}$
24. $\mathbf{u} = -2\mathbf{i} + 3\mathbf{j} - \mathbf{k}$, $\mathbf{v} = 2\mathbf{i} + \mathbf{j} - \mathbf{k}$
25. $\mathbf{u} = \langle 2, -3, 1 \rangle$, $\mathbf{v} = \langle -1, -1, -1 \rangle$
26. $\mathbf{u} = \langle \cos\theta, \sin\theta, -1 \rangle$, $\mathbf{v} = \langle \sin\theta, -\cos\theta, 0 \rangle$

Classifying a Triangle In Exercises 27–30, the vertices of a triangle are given. Determine whether the triangle is an acute triangle, an obtuse triangle, or a right triangle. Explain your reasoning.

27. $(1, 2, 0)$, $(0, 0, 0)$, $(-2, 1, 0)$
28. $(-3, 0, 0)$, $(0, 0, 0)$, $(1, 2, 3)$
29. $(2, 0, 1)$, $(0, 1, 2)$, $(-0.5, 1.5, 0)$
30. $(2, -7, 3)$, $(-1, 5, 8)$, $(4, 6, -1)$

Finding Direction Angles In Exercises 31–36, find the direction cosines and angles of $\mathbf{u}$ and show that $\cos^2\alpha + \cos^2\beta + \cos^2\gamma = 1$.

31. $\mathbf{u} = \mathbf{i} + 2\mathbf{j} + 2\mathbf{k}$
32. $\mathbf{u} = 5\mathbf{i} + 3\mathbf{j} - \mathbf{k}$
33. $\mathbf{u} = 7\mathbf{i} + \mathbf{j} - \mathbf{k}$
34. $\mathbf{u} = -4\mathbf{i} + 3\mathbf{j} + 5\mathbf{k}$
35. $\mathbf{u} = \langle 0, 6, -4 \rangle$
36. $\mathbf{u} = \langle -1, 5, 2 \rangle$

Finding the Projection of u onto v In Exercises 37–44, (a) find the projection of $\mathbf{u}$ onto $\mathbf{v}$ and (b) find the vector component of $\mathbf{u}$ orthogonal to $\mathbf{v}$.

37. $\mathbf{u} = \langle 6, 7 \rangle$, $\mathbf{v} = \langle 1, 4 \rangle$
38. $\mathbf{u} = \langle 9, 7 \rangle$, $\mathbf{v} = \langle 1, 3 \rangle$
39. $\mathbf{u} = 2\mathbf{i} + 3\mathbf{j}$, $\mathbf{v} = 5\mathbf{i} + \mathbf{j}$
40. $\mathbf{u} = 2\mathbf{i} - 3\mathbf{j}$, $\mathbf{v} = 3\mathbf{i} + 2\mathbf{j}$
41. $\mathbf{u} = \langle 0, 3, 3 \rangle$, $\mathbf{v} = \langle -1, 1, 1 \rangle$
42. $\mathbf{u} = \langle 8, 2, 0 \rangle$, $\mathbf{v} = \langle 2, 1, -1 \rangle$
43. $\mathbf{u} = -9\mathbf{i} - 2\mathbf{j} - 4\mathbf{k}$, $\mathbf{v} = 4\mathbf{j} + 4\mathbf{k}$
44. $\mathbf{u} = 5\mathbf{i} - \mathbf{j} - \mathbf{k}$, $\mathbf{v} = -\mathbf{i} + 5\mathbf{j} + 8\mathbf{k}$

Exploring Concepts

45. Explain why $\mathbf{u} + \mathbf{v} \cdot \mathbf{w}$ is not defined, where $\mathbf{u}$, $\mathbf{v}$, and $\mathbf{w}$ are nonzero vectors.
46. What can be said about the vectors $\mathbf{u}$ and $\mathbf{v}$ when the projection of $\mathbf{u}$ onto $\mathbf{v}$ equals $\mathbf{u}$?
47. When the projection of $\mathbf{u}$ onto $\mathbf{v}$ has the same magnitude as the projection of $\mathbf{v}$ onto $\mathbf{u}$, can you conclude that $\|\mathbf{u}\| = \|\mathbf{v}\|$? Explain.

48. **HOW DO YOU SEE IT?** What is known about θ, the angle between two nonzero vectors $\mathbf{u}$ and $\mathbf{v}$, when

(a) $\mathbf{u} \cdot \mathbf{v} = 0$? (b) $\mathbf{u} \cdot \mathbf{v} > 0$? (c) $\mathbf{u} \cdot \mathbf{v} < 0$?



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

49. Revenue The vector $\mathbf{u} = \langle 3240, 1450, 2235 \rangle$ gives the numbers of hamburgers, chicken sandwiches, and cheeseburgers, respectively, sold at a fast-food restaurant in one week. The vector $\mathbf{v} = \langle 2.25, 2.95, 2.65 \rangle$ gives the prices (in dollars) per unit for the three food items. Find the dot product $\mathbf{u} \cdot \mathbf{v}$ and explain what information it gives.

50. Revenue Repeat Exercise 49 after decreasing the prices by 2%. Identify the vector operation used to decrease the prices by 2%.

Orthogonal Vectors **In Exercises 51–54, find two vectors in opposite directions that are orthogonal to the vector u. (The answers are not unique.)**

51. $\mathbf{u} = -\frac{1}{4}\mathbf{i} + \frac{3}{2}\mathbf{j}$

52. $\mathbf{u} = 9\mathbf{i} - 4\mathbf{j}$

53. $\mathbf{u} = \langle 3, 1, -2 \rangle$

54. $\mathbf{u} = \langle 4, -3, 6 \rangle$

55. Finding an Angle Find the angle between a cube's diagonal and one of its edges.

56. Finding an Angle Find the angle between the diagonal of a cube and the diagonal of one of its sides.

57. Braking Load A 48,000-pound truck is parked on a 10° slope (see figure). Assume the only force to overcome is that due to gravity. Find (a) the force required to keep the truck from rolling down the hill and (b) the force perpendicular to the hill.



58. Braking Load A 5400-pound sport utility vehicle is parked on an 18° slope. Assume the only force to overcome is that due to gravity. Find (a) the force required to keep the vehicle from rolling down the hill and (b) the force perpendicular to the hill.

59. Work An object is pulled 10 feet across a floor using a force of 85 pounds. The direction of the force is 60° above the horizontal (see figure). Find the work done.



Figure for 59



Figure for 60

60. Work A wagon is pulled by exerting a force of 65 pounds on a handle that makes a 20° angle with the horizontal (see figure). Find the work done in pulling the wagon 50 feet.

61. Work A car is towed using a force of 1600 newtons. The chain used to pull the car makes a 25° angle with the horizontal. Find the work done in towing the car 2 kilometers.

62. Work

A pallet truck is pulled by exerting a force of 400 newtons on a handle that makes a 60° angle with the horizontal. Find the work done in pulling the truck 40 meters.

True or False? **In Exercises 63 and 64, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

63. If $\mathbf{u} \cdot \mathbf{v} = \mathbf{u} \cdot \mathbf{w}$ and $\mathbf{u} \neq \mathbf{0}$, then $\mathbf{v} = \mathbf{w}$.

64. If $\mathbf{u}$ and $\mathbf{v}$ are orthogonal to $\mathbf{w}$, then $\mathbf{u} + \mathbf{v}$ is orthogonal to $\mathbf{w}$.

Using Points of Intersection **In Exercises 65–68, (a) find all points of intersection of the graphs of the two equations, (b) find the unit tangent vectors to each curve at their points of intersection, and (c) find the angles ($0° \leq \theta \leq 90°$) between the curves at their points of intersection.**

65. $y = x^2, \quad y = x^{1/3}$

66. $y = x^3, \quad y = x^{1/3}$

67. $y = 1 - x^2, \quad y = x^2 - 1$

68. $(y + 1)^2 = x, \quad y = x^3 - 1$

69. Proof Use vectors to prove that the diagonals of a rhombus are perpendicular.

70. Proof Use vectors to prove that a parallelogram is a rectangle if and only if its diagonals are equal in length.

71. Bond Angle Consider a regular tetrahedron with vertices $(0, 0, 0)$, $(k, k, 0)$, $(k, 0, k)$, and $(0, k, k)$, where k is a positive real number.

(a) Sketch the graph of the tetrahedron.

(b) Find the length of each edge.

(c) Find the angle between any two edges.

(d) Find the angle between the line segments from the centroid $(k/2, k/2, k/2)$ to two vertices. This is the bond angle for a molecule, such as CH_4 (methane) or $PbCl_4$ (lead tetrachloride), where the structure of the molecule is a tetrahedron.

72. Proof Consider the vectors $\mathbf{u} = \langle \cos\alpha, \sin\alpha, 0 \rangle$ and $\mathbf{v} = \langle \cos\beta, \sin\beta, 0 \rangle$, where $\alpha > \beta$. Find the dot product of the vectors and use the result to prove the identity

$$\cos(\alpha - \beta) = \cos\alpha \cos\beta + \sin\alpha \sin\beta.$$

73. Proof Prove the triangle inequality $\|\mathbf{u} + \mathbf{v}\| \leq \|\mathbf{u}\| + \|\mathbf{v}\|$.

74. Proof Prove Theorem 11.6.

75. Proof Prove the **Cauchy-Schwarz Inequality,**

$$|\mathbf{u} \cdot \mathbf{v}| \leq \|\mathbf{u}\| \|\mathbf{v}\|.$$

Siwakorn1933/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

11.4 The Cross Product of Two Vectors in Space

GO DIGITAL

- **Find the cross product of two vectors in space.**
- **Use the triple scalar product of three vectors in space.**

Exploration

Geometric Property of the Cross Product Three pairs of vectors are shown below. Use the definition to find the cross product of each pair. Sketch all three vectors in a three-dimensional system. Describe any relationships among the three vectors. Use your description to write a conjecture about $\mathbf{u}$, $\mathbf{v}$, and $\mathbf{u} \times \mathbf{v}$.

a. $\mathbf{u} = \langle 3, 0, 3 \rangle$
$\mathbf{v} = \langle 3, 0, -3 \rangle$



b. $\mathbf{u} = \langle 0, 3, 3 \rangle$
$\mathbf{v} = \langle 0, -3, 3 \rangle$



c. $\mathbf{u} = \langle 3, 3, 0 \rangle$
$\mathbf{v} = \langle 3, -3, 0 \rangle$



The Cross Product

Many applications in physics, engineering, and geometry involve finding a vector in space that is orthogonal to two given vectors. In this section, you will study a product that will yield such a vector. It is called the **cross product,** and it is most conveniently defined and calculated using the standard unit vector form. Because the cross product yields a vector, it is also called the **vector product.**

Definition of Cross Product of Two Vectors in Space

Let $\mathbf{u}$ and $\mathbf{v}$ be vectors in space, where

$$\mathbf{u} = u_1\mathbf{i} + u_2\mathbf{j} + u_3\mathbf{k} \quad \text{and} \quad \mathbf{v} = v_1\mathbf{i} + v_2\mathbf{j} + v_3\mathbf{k}.$$

The **cross product** of $\mathbf{u}$ and $\mathbf{v}$ is the vector

$$\mathbf{u} \times \mathbf{v} = (u_2v_3 - u_3v_2)\mathbf{i} - (u_1v_3 - u_3v_1)\mathbf{j} + (u_1v_2 - u_2v_1)\mathbf{k}.$$

It is important to note that this definition applies only to three-dimensional vectors. The cross product is not defined for two-dimensional vectors.

A convenient way to calculate $\mathbf{u} \times \mathbf{v}$ is to use the *determinant form* with cofactor expansion shown below. (This 3×3 determinant form is used simply to help remember the formula for the cross product. The corresponding array is technically not a matrix because its entries are not all numbers.)

$$\mathbf{u} \times \mathbf{v} = \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ u_1 & u_2 & u_3 \\ v_1 & v_2 & v_3 \end{vmatrix} \begin{array}{l} \\ \leftarrow \text{Put "}\mathbf{u}\text{" in Row 2.} \\ \leftarrow \text{Put "}\mathbf{v}\text{" in Row 3.} \end{array}$$

$$= \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ u_1 & u_2 & u_3 \\ v_1 & v_2 & v_3 \end{vmatrix} \mathbf{i} - \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ u_1 & u_2 & u_3 \\ v_1 & v_2 & v_3 \end{vmatrix} \mathbf{j} + \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ u_1 & u_2 & u_3 \\ v_1 & v_2 & v_3 \end{vmatrix} \mathbf{k}$$

$$= \begin{vmatrix} u_2 & u_3 \\ v_2 & v_3 \end{vmatrix} \mathbf{i} - \begin{vmatrix} u_1 & u_3 \\ v_1 & v_3 \end{vmatrix} \mathbf{j} + \begin{vmatrix} u_1 & u_2 \\ v_1 & v_2 \end{vmatrix} \mathbf{k}$$

$$= (u_2v_3 - u_3v_2)\mathbf{i} - (u_1v_3 - u_3v_1)\mathbf{j} + (u_1v_2 - u_2v_1)\mathbf{k}$$

Note the minus sign in front of the $\mathbf{j}$-component. Each of the three 2×2 determinants can be evaluated by using the diagonal pattern

$$\begin{vmatrix} a & b \\ c & d \end{vmatrix} = ad - bc.$$

Here are a couple of examples.

$$\begin{vmatrix} 2 & 4 \\ 3 & -1 \end{vmatrix} = (2)(-1) - (4)(3) = -2 - 12 = -14$$

and

$$\begin{vmatrix} 4 & 0 \\ -6 & 3 \end{vmatrix} = (4)(3) - (0)(-6) = 12$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 1 Finding the Cross Product

For $\mathbf{u} = \mathbf{i} - 2\mathbf{j} + \mathbf{k}$ and $\mathbf{v} = 3\mathbf{i} + \mathbf{j} - 2\mathbf{k}$, find each of the following.

a. $\mathbf{u} \times \mathbf{v}$ **b.** $\mathbf{v} \times \mathbf{u}$ **c.** $\mathbf{v} \times \mathbf{v}$

Solution

$$\mathbf{a.}\ \mathbf{u} \times \mathbf{v} = \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ 1 & -2 & 1 \\ 3 & 1 & -2 \end{vmatrix}$$

$$= \begin{vmatrix} -2 & 1 \\ 1 & -2 \end{vmatrix}\mathbf{i} - \begin{vmatrix} 1 & 1 \\ 3 & -2 \end{vmatrix}\mathbf{j} + \begin{vmatrix} 1 & -2 \\ 3 & 1 \end{vmatrix}\mathbf{k}$$

$$= (4 - 1)\mathbf{i} - (-2 - 3)\mathbf{j} + (1 + 6)\mathbf{k}$$

$$= 3\mathbf{i} + 5\mathbf{j} + 7\mathbf{k}$$

$$\mathbf{b.}\ \mathbf{v} \times \mathbf{u} = \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ 3 & 1 & -2 \\ 1 & -2 & 1 \end{vmatrix}$$

$$= \begin{vmatrix} 1 & -2 \\ -2 & 1 \end{vmatrix}\mathbf{i} - \begin{vmatrix} 3 & -2 \\ 1 & 1 \end{vmatrix}\mathbf{j} + \begin{vmatrix} 3 & 1 \\ 1 & -2 \end{vmatrix}\mathbf{k}$$

$$= (1 - 4)\mathbf{i} - (3 + 2)\mathbf{j} + (-6 - 1)\mathbf{k}$$

$$= -3\mathbf{i} - 5\mathbf{j} - 7\mathbf{k}$$

REMARK Note that this result is the negative of that in part (a).

$$\mathbf{c.}\ \mathbf{v} \times \mathbf{v} = \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ 3 & 1 & -2 \\ 3 & 1 & -2 \end{vmatrix} = \mathbf{0}$$

The results obtained in Example 1 suggest some interesting *algebraic* properties of the cross product. For instance, $\mathbf{u} \times \mathbf{v} = -(\mathbf{v} \times \mathbf{u})$, and $\mathbf{v} \times \mathbf{v} = \mathbf{0}$. These properties, and several others, are summarized in the next theorem.

NOTATION FOR DOT AND CROSS PRODUCTS

The notation for the dot product and cross product of vectors was first introduced by the American physicist Josiah Willard Gibbs (1839–1903). In the early 1880s, Gibbs built a system to represent physical quantities called "vector analysis." The system was a departure from Hamilton's theory of quaternions.

THEOREM 11.7 Algebraic Properties of the Cross Product

Let $\mathbf{u}$, $\mathbf{v}$, and $\mathbf{w}$ be vectors in space, and let c be a scalar.

1. $\mathbf{u} \times \mathbf{v} = -(\mathbf{v} \times \mathbf{u})$
2. $\mathbf{u} \times (\mathbf{v} + \mathbf{w}) = (\mathbf{u} \times \mathbf{v}) + (\mathbf{u} \times \mathbf{w})$
3. $c(\mathbf{u} \times \mathbf{v}) = (c\mathbf{u}) \times \mathbf{v} = \mathbf{u} \times (c\mathbf{v})$
4. $\mathbf{u} \times \mathbf{0} = \mathbf{0} \times \mathbf{u} = \mathbf{0}$
5. $\mathbf{u} \times \mathbf{u} = \mathbf{0}$
6. $\mathbf{u} \cdot (\mathbf{v} \times \mathbf{w}) = (\mathbf{u} \times \mathbf{v}) \cdot \mathbf{w}$

Proof To prove Property 1, let $\mathbf{u} = u_1\mathbf{i} + u_2\mathbf{j} + u_3\mathbf{k}$ and $\mathbf{v} = v_1\mathbf{i} + v_2\mathbf{j} + v_3\mathbf{k}$. Then

$$\mathbf{u} \times \mathbf{v} = (u_2v_3 - u_3v_2)\mathbf{i} - (u_1v_3 - u_3v_1)\mathbf{j} + (u_1v_2 - u_2v_1)\mathbf{k}$$

and

$$\mathbf{v} \times \mathbf{u} = (v_2u_3 - v_3u_2)\mathbf{i} - (v_1u_3 - v_3u_1)\mathbf{j} + (v_1u_2 - v_2u_1)\mathbf{k}$$

which implies that $\mathbf{u} \times \mathbf{v} = -(\mathbf{v} \times \mathbf{u})$. Proofs of Properties 2, 3, 5, and 6 are left as exercises (see Exercises 49–52).

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Note that Property 1 of Theorem 11.7 indicates that the cross product is *not commutative*. In particular, this property indicates that the vectors $\mathbf{u} \times \mathbf{v}$ and $\mathbf{v} \times \mathbf{u}$ have equal lengths but opposite directions. The next theorem lists some other *geometric* properties of the cross product of two vectors.

THEOREM 11.8 Geometric Properties of the Cross Product

Let $\mathbf{u}$ and $\mathbf{v}$ be nonzero vectors in space, and let θ be the angle between $\mathbf{u}$ and $\mathbf{v}$.

1. $\mathbf{u} \times \mathbf{v}$ is orthogonal to both $\mathbf{u}$ and $\mathbf{v}$.
2. $\|\mathbf{u} \times \mathbf{v}\| = \|\mathbf{u}\| \|\mathbf{v}\| \sin \theta$
3. $\mathbf{u} \times \mathbf{v} = \mathbf{0}$ if and only if $\mathbf{u}$ and $\mathbf{v}$ are scalar multiples of each other.
4. $\|\mathbf{u} \times \mathbf{v}\|$ = area of parallelogram having $\mathbf{u}$ and $\mathbf{v}$ as adjacent sides.

REMARK It follows from Properties 1 and 2 in Theorem 11.8 that if $\mathbf{n}$ is a unit vector orthogonal to both $\mathbf{u}$ and $\mathbf{v}$, then

$$\mathbf{u} \times \mathbf{v} = \pm(\|\mathbf{u}\| \|\mathbf{v}\| \sin \theta)\mathbf{n}.$$

Proof To prove Property 2, note because $\cos \theta = (\mathbf{u} \cdot \mathbf{v})/(\|\mathbf{u}\| \|\mathbf{v}\|)$, it follows that

$$\begin{aligned}
\|\mathbf{u}\| \|\mathbf{v}\| \sin \theta &= \|\mathbf{u}\| \|\mathbf{v}\| \sqrt{1 - \cos^2 \theta} \\
&= \|\mathbf{u}\| \|\mathbf{v}\| \sqrt{1 - \frac{(\mathbf{u} \cdot \mathbf{v})^2}{\|\mathbf{u}\|^2 \|\mathbf{v}\|^2}} \\
&= \sqrt{\|\mathbf{u}\|^2 \|\mathbf{v}\|^2 - (\mathbf{u} \cdot \mathbf{v})^2} \\
&= \sqrt{(u_1^2 + u_2^2 + u_3^2)(v_1^2 + v_2^2 + v_3^2) - (u_1v_1 + u_2v_2 + u_3v_3)^2} \\
&= \sqrt{(u_2v_3 - u_3v_2)^2 + (u_1v_3 - u_3v_1)^2 + (u_1v_2 - u_2v_1)^2} \\
&= \|\mathbf{u} \times \mathbf{v}\|.
\end{aligned}$$

To prove Property 4, refer to Figure 11.35, which is a parallelogram having $\mathbf{v}$ and $\mathbf{u}$ as adjacent sides. Because the height of the parallelogram is $\|\mathbf{v}\| \sin \theta$, the area is

$$\begin{aligned}
\text{Area} &= (\text{base})(\text{height}) \\
&= \|\mathbf{u}\| \|\mathbf{v}\| \sin \theta \\
&= \|\mathbf{u} \times \mathbf{v}\|.
\end{aligned}$$

Proofs of Properties 1 and 3 are left as exercises (see Exercises 53 and 54).



The vectors $\mathbf{u}$ and $\mathbf{v}$ form adjacent sides of a parallelogram.
Figure 11.35

Both $\mathbf{u} \times \mathbf{v}$ and $\mathbf{v} \times \mathbf{u}$ are perpendicular to the plane determined by $\mathbf{u}$ and $\mathbf{v}$. One way to remember the orientations of the vectors $\mathbf{u}$, $\mathbf{v}$, and $\mathbf{u} \times \mathbf{v}$ is to compare them with the unit vectors $\mathbf{i}$, $\mathbf{j}$, and $\mathbf{k} = \mathbf{i} \times \mathbf{j}$, as shown in Figure 11.36. The three vectors $\mathbf{u}$, $\mathbf{v}$, and $\mathbf{u} \times \mathbf{v}$ form a *right-handed system,* whereas the three vectors $\mathbf{u}$, $\mathbf{v}$, and $\mathbf{v} \times \mathbf{u}$ form a *left-handed system.*



Right-handed systems
Figure 11.36

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The vector $\mathbf{u} \times \mathbf{v}$ is orthogonal to both $\mathbf{u}$ and $\mathbf{v}$.
Figure 11.37

EXAMPLE 2 Using the Cross Product

See LarsonCalculus.com for an interactive version of this type of example.

Find a unit vector that is orthogonal to both

$$\mathbf{u} = \mathbf{i} - 4\mathbf{j} + \mathbf{k}$$

and

$$\mathbf{v} = 2\mathbf{i} + 3\mathbf{j}.$$

Solution The cross product $\mathbf{u} \times \mathbf{v}$, as shown in Figure 11.37, is orthogonal to both $\mathbf{u}$ and $\mathbf{v}$.

$$\mathbf{u} \times \mathbf{v} = \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ 1 & -4 & 1 \\ 2 & 3 & 0 \end{vmatrix} \qquad \text{Cross product}$$

$$= -3\mathbf{i} + 2\mathbf{j} + 11\mathbf{k}$$

Because

$$\|\mathbf{u} \times \mathbf{v}\| = \sqrt{(-3)^2 + 2^2 + 11^2} = \sqrt{134}$$

a unit vector orthogonal to both $\mathbf{u}$ and $\mathbf{v}$ is

$$\frac{\mathbf{u} \times \mathbf{v}}{\|\mathbf{u} \times \mathbf{v}\|} = -\frac{3}{\sqrt{134}}\mathbf{i} + \frac{2}{\sqrt{134}}\mathbf{j} + \frac{11}{\sqrt{134}}\mathbf{k}.$$

GO DIGITAL

In Example 2, note that you could have used the cross product $\mathbf{v} \times \mathbf{u}$ to form a unit vector that is orthogonal to both $\mathbf{u}$ and $\mathbf{v}$. With that choice, you would have obtained the negative of the unit vector found in the example.

EXAMPLE 3 Geometric Application of the Cross Product

The vertices of a quadrilateral are listed below. Show that the quadrilateral is a parallelogram and find its area.

$A = (5, 2, 0)$ $\quad B = (2, 6, 1)$
$C = (2, 4, 7)$ $\quad D = (5, 0, 6)$

Solution From Figure 11.38, you can determine that the sides of the quadrilateral correspond to the four vectors below.

$\overrightarrow{AB} = -3\mathbf{i} + 4\mathbf{j} + \mathbf{k}$ $\quad \overrightarrow{CD} = 3\mathbf{i} - 4\mathbf{j} - \mathbf{k} = -\overrightarrow{AB}$
$\overrightarrow{AD} = 0\mathbf{i} - 2\mathbf{j} + 6\mathbf{k}$ $\quad \overrightarrow{CB} = 0\mathbf{i} + 2\mathbf{j} - 6\mathbf{k} = -\overrightarrow{AD}$

So, $\overrightarrow{AB}$ is parallel to $\overrightarrow{CD}$ and $\overrightarrow{AD}$ is parallel to $\overrightarrow{CB}$, and you can conclude that the quadrilateral is a parallelogram with $\overrightarrow{AB}$ and $\overrightarrow{AD}$ as adjacent sides. Moreover, because

$$\overrightarrow{AB} \times \overrightarrow{AD} = \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ -3 & 4 & 1 \\ 0 & -2 & 6 \end{vmatrix} \qquad \text{Cross product}$$

$$= 26\mathbf{i} + 18\mathbf{j} + 6\mathbf{k}$$

the area of the parallelogram is

$$\|\overrightarrow{AB} \times \overrightarrow{AD}\| = \sqrt{1036} \approx 32.19.$$

Is the parallelogram a rectangle? You can determine whether it is by finding the angle between the vectors $\overrightarrow{AB}$ and $\overrightarrow{AD}$.



The area of the parallelogram is approximately 32.19.
Figure 11.38

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The moment of **F** about P
Figure 11.39

In physics, the cross product can be used to measure **torque**—the **moment M of a force F about a point *P*,** as shown in Figure 11.39. If the point of application of the force is Q, then the moment of **F** about P is

$$\mathbf{M} = \overrightarrow{PQ} \times \mathbf{F}.$$ Moment of **F** about P

The magnitude of the moment **M** measures the tendency of the vector $\overrightarrow{PQ}$ to rotate counterclockwise (using the right-hand rule) about an axis directed along the vector **M**.

EXAMPLE 4 An Application of the Cross Product

A vertical force of 50 pounds is applied to the end of a one-foot lever that is attached to an axle at point P, as shown in Figure 11.40. Find the moment of this force about the point P when $\theta = 60°$.



A vertical force of 50 pounds is applied at point Q.
Figure 11.40

Solution Represent the 50-pound force as

$$\mathbf{F} = -50\mathbf{k}$$

and the lever as

$$\overrightarrow{PQ} = \cos(60°)\mathbf{j} + \sin(60°)\mathbf{k} = \frac{1}{2}\mathbf{j} + \frac{\sqrt{3}}{2}\mathbf{k}.$$

The moment of **F** about P is

$$\mathbf{M} = \overrightarrow{PQ} \times \mathbf{F} = \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ 0 & \frac{1}{2} & \frac{\sqrt{3}}{2} \\ 0 & 0 & -50 \end{vmatrix} = -25\mathbf{i}.$$ Moment of **F** about P

The magnitude of this moment is 25 foot-pounds. ■

In Example 4, note that the moment (the tendency of the lever to rotate about its axle) is dependent on the angle θ. When $\theta = \pi/2$, the moment is **0**. The moment is greatest when $\theta = 0$.

The Triple Scalar Product

For vectors **u**, **v**, and **w** in space, the dot product of **u** and **v** × **w**

$$\mathbf{u} \cdot (\mathbf{v} \times \mathbf{w})$$

is called the **triple scalar product,** as defined in Theorem 11.9. The proof of this theorem is left as an exercise (see Exercise 57).

THEOREM 11.9 The Triple Scalar Product

For $\mathbf{u} = u_1\mathbf{i} + u_2\mathbf{j} + u_3\mathbf{k}$, $\mathbf{v} = v_1\mathbf{i} + v_2\mathbf{j} + v_3\mathbf{k}$, and $\mathbf{w} = w_1\mathbf{i} + w_2\mathbf{j} + w_3\mathbf{k}$, the triple scalar product is

$$\mathbf{u} \cdot (\mathbf{v} \times \mathbf{w}) = \begin{vmatrix} u_1 & u_2 & u_3 \\ v_1 & v_2 & v_3 \\ w_1 & w_2 & w_3 \end{vmatrix}.$$

Note that the value of a determinant is multiplied by -1 when two rows are interchanged. After two such interchanges, the value of the determinant will be unchanged. So, the following triple scalar products are equivalent.

$$\mathbf{u} \cdot (\mathbf{v} \times \mathbf{w}) = \mathbf{v} \cdot (\mathbf{w} \times \mathbf{u}) = \mathbf{w} \cdot (\mathbf{u} \times \mathbf{v})$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Area of base $= \|\mathbf{v} \times \mathbf{w}\|$
Volume of parallelepiped $= |\mathbf{u} \cdot (\mathbf{v} \times \mathbf{w})|$
Figure 11.41

If the vectors $\mathbf{u}$, $\mathbf{v}$, and $\mathbf{w}$ do not lie in the same plane, then the triple scalar product $\mathbf{u} \cdot (\mathbf{v} \times \mathbf{w})$ can be used to determine the volume of the parallelepiped (a polyhedron, all of whose faces are parallelograms) with $\mathbf{u}$, $\mathbf{v}$, and $\mathbf{w}$ as adjacent edges, as shown in Figure 11.41. This is established in the next theorem.

THEOREM 11.10 Geometric Property of the Triple Scalar Product

The volume V of a parallelepiped with vectors $\mathbf{u}$, $\mathbf{v}$, and $\mathbf{w}$ as adjacent edges is

$$V = |\mathbf{u} \cdot (\mathbf{v} \times \mathbf{w})|.$$

Proof In Figure 11.41, note that the area of the base is $\|\mathbf{v} \times \mathbf{w}\|$ and the height of the parallelepiped is $\|\text{proj}_{\mathbf{v}\times\mathbf{w}}\mathbf{u}\|$. Therefore, the volume is

$$\begin{aligned} V &= (\text{height})(\text{area of base}) \\ &= \|\text{proj}_{\mathbf{v}\times\mathbf{w}}\mathbf{u}\|\,\|\mathbf{v} \times \mathbf{w}\| \\ &= \left|\frac{\mathbf{u} \cdot (\mathbf{v} \times \mathbf{w})}{\|\mathbf{v} \times \mathbf{w}\|}\right| \|\mathbf{v} \times \mathbf{w}\| \\ &= |\mathbf{u} \cdot (\mathbf{v} \times \mathbf{w})|. \end{aligned}$$

EXAMPLE 5 Volume by the Triple Scalar Product

Find the volume of the parallelepiped shown in Figure 11.42 having

$$\mathbf{u} = 3\mathbf{i} - 5\mathbf{j} + \mathbf{k}$$
$$\mathbf{v} = 2\mathbf{j} - 2\mathbf{k}$$

and

$$\mathbf{w} = 3\mathbf{i} + \mathbf{j} + \mathbf{k}$$

as adjacent edges.



The parallelepiped has a volume of 36.
Figure 11.42

Solution By Theorem 11.10, you have

$$\begin{aligned} V &= |\mathbf{u} \cdot (\mathbf{v} \times \mathbf{w})| \qquad \text{Triple scalar product} \\ &= \begin{vmatrix} 3 & -5 & 1 \\ 0 & 2 & -2 \\ 3 & 1 & 1 \end{vmatrix} \\ &= 3\begin{vmatrix} 2 & -2 \\ 1 & 1 \end{vmatrix} - (-5)\begin{vmatrix} 0 & -2 \\ 3 & 1 \end{vmatrix} + (1)\begin{vmatrix} 0 & 2 \\ 3 & 1 \end{vmatrix} \\ &= 3(4) + 5(6) + 1(-6) \\ &= 36. \end{aligned}$$

A natural consequence of Theorem 11.10 is that the volume of the parallelepiped is 0 if and only if the three vectors are coplanar. That is, when the vectors $\mathbf{u} = \langle u_1, u_2, u_3 \rangle$, $\mathbf{v} = \langle v_1, v_2, v_3 \rangle$, and $\mathbf{w} = \langle w_1, w_2, w_3 \rangle$ have the same initial point, they lie in the same plane if and only if

$$\mathbf{u} \cdot (\mathbf{v} \times \mathbf{w}) = \begin{vmatrix} u_1 & u_2 & u_3 \\ v_1 & v_2 & v_3 \\ w_1 & w_2 & w_3 \end{vmatrix} = 0.$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

11.4 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain what $\mathbf{u} \times \mathbf{v}$ represents geometrically.
2. Explain how to find the area of a parallelogram using vectors.
3. Determine what must be true about two nonzero vectors whose cross product is 0.
4. Explain how torque and moments are related.

Cross Product of Unit Vectors **In Exercises 5–8, find the cross product of the unit vectors and sketch your result.**

5. $\mathbf{j} \times \mathbf{i}$
6. $\mathbf{j} \times \mathbf{k}$
7. $\mathbf{i} \times \mathbf{k}$
8. $\mathbf{k} \times \mathbf{i}$

Finding Cross Products **In Exercises 9–12, find (a) $\mathbf{u} \times \mathbf{v}$, (b) $\mathbf{v} \times \mathbf{u}$, and (c) $\mathbf{v} \times \mathbf{v}$.**

9. $\mathbf{u} = -2\mathbf{i} + 4\mathbf{j}$, $\mathbf{v} = 3\mathbf{i} + 2\mathbf{j} + 5\mathbf{k}$
10. $\mathbf{u} = 3\mathbf{i} + 5\mathbf{k}$, $\mathbf{v} = 2\mathbf{i} + 3\mathbf{j} - 2\mathbf{k}$
11. $\mathbf{u} = \langle 7, 3, 2 \rangle$, $\mathbf{v} = \langle 1, -1, 5 \rangle$
12. $\mathbf{u} = \langle 2, 1, -9 \rangle$, $\mathbf{v} = \langle -6, -2, -1 \rangle$

Finding a Cross Product **In Exercises 13–16, find $\mathbf{u} \times \mathbf{v}$ and show that it is orthogonal to both u and v.**

13. $\mathbf{u} = \langle 4, -1, 0 \rangle$, $\mathbf{v} = \langle -6, 3, 0 \rangle$
14. $\mathbf{u} = \langle -5, 2, 2 \rangle$, $\mathbf{v} = \langle 0, 1, 8 \rangle$
15. $\mathbf{u} = \mathbf{i} + \mathbf{j} + \mathbf{k}$, $\mathbf{v} = 2\mathbf{i} + \mathbf{j} - \mathbf{k}$
16. $\mathbf{u} = \mathbf{i} + 6\mathbf{j}$, $\mathbf{v} = -2\mathbf{i} + \mathbf{j} + \mathbf{k}$

Finding a Unit Vector **In Exercises 17–20, find a unit vector that is orthogonal to both u and v.**

17. $\mathbf{u} = \langle 4, -3, 1 \rangle$, $\mathbf{v} = \langle 2, 5, 3 \rangle$
18. $\mathbf{u} = \langle -8, -6, 4 \rangle$, $\mathbf{v} = \langle 10, -12, -2 \rangle$
19. $\mathbf{u} = -3\mathbf{i} + 2\mathbf{j} - 5\mathbf{k}$, $\mathbf{v} = \mathbf{i} - \mathbf{j} + 4\mathbf{k}$
20. $\mathbf{u} = 2\mathbf{k}$, $\mathbf{v} = 4\mathbf{i} + 6\mathbf{k}$

Area **In Exercises 21–24, find the area of the parallelogram that has the given vectors as adjacent sides. Use a graphing utility to verify your result.**

21. $\mathbf{u} = \mathbf{j}$, $\mathbf{v} = \mathbf{j} + \mathbf{k}$
22. $\mathbf{u} = \mathbf{i} + \mathbf{j} + \mathbf{k}$, $\mathbf{v} = \mathbf{j} + \mathbf{k}$
23. $\mathbf{u} = \langle 3, 2, -1 \rangle$, $\mathbf{v} = \langle 1, 2, 3 \rangle$
24. $\mathbf{u} = \langle 2, -1, 0 \rangle$, $\mathbf{v} = \langle -1, 2, 0 \rangle$

Area **In Exercises 25 and 26, verify that the points are the vertices of a parallelogram, and find its area.**

25. $A(0, 3, 2)$, $B(1, 5, 5)$, $C(6, 9, 5)$, $D(5, 7, 2)$
26. $A(2, -3, 1)$, $B(6, 5, -1)$, $C(7, 2, 2)$, $D(3, -6, 4)$

Area **In Exercises 27 and 28, find the area of the triangle with the given vertices. (*Hint:* $\frac{1}{2}\|\mathbf{u} \times \mathbf{v}\|$ is the area of the triangle having u and v as adjacent sides.)**

27. $A(0, 0, 0)$, $B(1, 0, 3)$, $C(-3, 2, 0)$
28. $A(2, -3, 4)$, $B(0, 1, 2)$, $C(-1, 2, 0)$

29. **Torque** The brakes on a bicycle are applied using a downward force of 20 pounds on the pedal when the crank makes a 40° angle with the horizontal (see figure). The crank is 6 inches in length. Find the torque at P.



Figure for 29



Figure for 30

30. **Torque** Both the magnitude and the direction of the force on a crankshaft change as the crankshaft rotates. Find the torque on the crankshaft using the position and data shown in the figure.

31. **Optimization** A force of 180 pounds acts on the bracket shown in the figure.



(a) Determine the vector $\overrightarrow{AB}$ and the vector $\mathbf{F}$ representing the force. ($\mathbf{F}$ will be in terms of θ.)

(b) Find the magnitude of the moment about A by evaluating $\|\overrightarrow{AB} \times \mathbf{F}\|$.

(c) Use the result of part (b) to determine the magnitude of the moment when $\theta = 30°$.

(d) Use the result of part (b) to determine the angle θ when the magnitude of the moment is maximum. At that angle, what is the relationship between the vectors $\mathbf{F}$ and $\overrightarrow{AB}$? Is it what you expected? Why or why not?

(e) Use a graphing utility to graph the function for the magnitude of the moment about A for $0° \le \theta \le 180°$. Find the zero of the function in the given domain. Interpret the meaning of the zero in the context of the problem.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

32. Optimization A force of 56 pounds acts on the pipe wrench shown in the figure.



(a) Find the magnitude of the moment about O by evaluating $\|\overrightarrow{OA} \times \mathbf{F}\|$. Use a graphing utility to graph the resulting function of θ.

(b) Use the result of part (a) to determine the magnitude of the moment when $\theta = 45°$.

(c) Use the result of part (a) to determine the angle θ when the magnitude of the moment is maximum. Is the answer what you expected? Why or why not?

Finding a Triple Scalar Product **In Exercises 33–36, find $\mathbf{u} \cdot (\mathbf{v} \times \mathbf{w})$.**

33. $\mathbf{u} = \mathbf{i}$, $\mathbf{v} = \mathbf{j}$, $\mathbf{w} = \mathbf{k}$

34. $\mathbf{u} = \langle 1, 1, 1 \rangle$, $\mathbf{v} = \langle 2, 1, 0 \rangle$, $\mathbf{w} = \langle 0, 0, 1 \rangle$

35. $\mathbf{u} = \langle 2, 0, 1 \rangle$, $\mathbf{v} = \langle 0, 3, 0 \rangle$, $\mathbf{w} = \langle 0, 0, 1 \rangle$

36. $\mathbf{u} = \langle 2, 0, 0 \rangle$, $\mathbf{v} = \langle 1, 1, 1 \rangle$, $\mathbf{w} = \langle 0, 2, 2 \rangle$

Volume **In Exercises 37 and 38, use the triple scalar product to find the volume of the parallelepiped having adjacent edges u, v, and w.**

37. $\mathbf{u} = \mathbf{i} + \mathbf{j}$, $\mathbf{v} = \mathbf{j} + \mathbf{k}$, $\mathbf{w} = \mathbf{i} + \mathbf{k}$



38. $\mathbf{u} = \langle 1, 3, 1 \rangle$, $\mathbf{v} = \langle 0, 6, 6 \rangle$, $\mathbf{w} = \langle -4, 0, -4 \rangle$



Volume **In Exercises 39 and 40, find the volume of the parallelepiped with the given vertices.**

39. (0, 0, 0), (3, 0, 0), (0, 5, 1), (2, 0, 5), (3, 5, 1), (5, 0, 5), (2, 5, 6), (5, 5, 6)

40. (0, 0, 0), (0, 4, 0), (−3, 0, 0), (−1, 1, 5), (−3, 4, 0), (−1, 5, 5), (−4, 1, 5), (−4, 5, 5)

Exploring Concepts

41. Identify the dot products that are equal. Explain your reasoning. (Assume $\mathbf{u}$, $\mathbf{v}$, and $\mathbf{w}$ are nonzero vectors.)

(a) $\mathbf{u} \cdot (\mathbf{v} \times \mathbf{w})$ (b) $(\mathbf{v} \times \mathbf{w}) \cdot \mathbf{u}$
(c) $(\mathbf{u} \times \mathbf{v}) \cdot \mathbf{w}$ (d) $(\mathbf{u} \times -\mathbf{w}) \cdot \mathbf{v}$
(e) $\mathbf{u} \cdot (\mathbf{w} \times \mathbf{v})$ (f) $\mathbf{w} \cdot (\mathbf{v} \times \mathbf{u})$
(g) $(-\mathbf{u} \times \mathbf{v}) \cdot \mathbf{w}$ (h) $(\mathbf{w} \times \mathbf{u}) \cdot \mathbf{v}$

42. When $\mathbf{u} \times \mathbf{v} = \mathbf{0}$ and $\mathbf{u} \cdot \mathbf{v} = \mathbf{0}$, what can you conclude about $\mathbf{u}$ and $\mathbf{v}$?

43. Two nonzero vectors lie in the yz-plane. Where does the cross product of the vectors lie? Explain.

44. HOW DO YOU SEE IT? The vertices of a triangle in space are (x_1, y_1, z_1), (x_2, y_2, z_2), and (x_3, y_3, z_3). Explain how to find a vector perpendicular to the triangle.



True or False? **In Exercises 45–48, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

45. It is possible to find the cross product of two vectors in a two-dimensional coordinate system.

46. The cross product of two nonzero vectors is a nonzero vector.

47. If $\mathbf{u} \neq \mathbf{0}$ and $\mathbf{u} \times \mathbf{v} = \mathbf{u} \times \mathbf{w}$, then $\mathbf{v} = \mathbf{w}$.

48. If $\mathbf{u} \neq \mathbf{0}$, $\mathbf{u} \cdot \mathbf{v} = \mathbf{u} \cdot \mathbf{w}$, and $\mathbf{u} \times \mathbf{v} = \mathbf{u} \times \mathbf{w}$, then $\mathbf{v} = \mathbf{w}$.

Proof **In Exercises 49–54, prove the property of the cross product.**

49. $\mathbf{u} \times (\mathbf{v} + \mathbf{w}) = (\mathbf{u} \times \mathbf{v}) + (\mathbf{u} \times \mathbf{w})$

50. $c(\mathbf{u} \times \mathbf{v}) = (c\mathbf{u}) \times \mathbf{v} = \mathbf{u} \times (c\mathbf{v})$

51. $\mathbf{u} \times \mathbf{u} = \mathbf{0}$

52. $\mathbf{u} \cdot (\mathbf{v} \times \mathbf{w}) = (\mathbf{u} \times \mathbf{v}) \cdot \mathbf{w}$

53. $\mathbf{u} \times \mathbf{v}$ is orthogonal to both $\mathbf{u}$ and $\mathbf{v}$.

54. $\mathbf{u} \times \mathbf{v} = \mathbf{0}$ if and only if $\mathbf{u}$ and $\mathbf{v}$ are scalar multiples of each other.

55. Proof Prove that $\|\mathbf{u} \times \mathbf{v}\| = \|\mathbf{u}\| \|\mathbf{v}\|$ if $\mathbf{u}$ and $\mathbf{v}$ are orthogonal.

56. Proof Prove that $\mathbf{u} \times (\mathbf{v} \times \mathbf{w}) = (\mathbf{u} \cdot \mathbf{w})\mathbf{v} - (\mathbf{u} \cdot \mathbf{v})\mathbf{w}$.

57. Proof Prove Theorem 11.9.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

11.5 Lines and Planes in Space

GO DIGITAL

- **Write a set of parametric equations for a line in space.**
- **Write a linear equation to represent a plane in space.**
- **Sketch the plane given by a linear equation.**
- **Find the distances between points, planes, and lines in space.**

Lines in Space

In the plane, *slope* is used to determine the equation of a line. In space, it is more convenient to use *vectors* to determine the equation of a line.

In Figure 11.43, consider the line L through the point $P(x_1, y_1, z_1)$ and parallel to the vector $\mathbf{v} = \langle a, b, c \rangle$. The vector $\mathbf{v}$ is a **direction vector** for the line L, and a, b, and c are **direction numbers.** One way of describing the line L is to say that it consists of all points $Q(x, y, z)$ for which the vector $\overrightarrow{PQ}$ is parallel to $\mathbf{v}$. This means that $\overrightarrow{PQ}$ is a scalar multiple of $\mathbf{v}$ and you can write $\overrightarrow{PQ} = t\mathbf{v}$, where t is a scalar (a real number).

$$\overrightarrow{PQ} = \langle x - x_1, y - y_1, z - z_1 \rangle = \langle at, bt, ct \rangle = t\mathbf{v}$$

By equating corresponding components, you can obtain **parametric equations** of a line in space.



Line L and its direction vector $\mathbf{v}$
Figure 11.43

THEOREM 11.11 Parametric Equations of a Line in Space

A line L parallel to the vector $\mathbf{v} = \langle a, b, c \rangle$ and passing through the point $P(x_1, y_1, z_1)$ is represented by the **parametric equations**

$$x = x_1 + at, \quad y = y_1 + bt, \quad \text{and} \quad z = z_1 + ct.$$

If the direction numbers a, b, and c are all nonzero, then you can eliminate the parameter t in the parametric equations to obtain **symmetric equations** of the line.

$$\frac{x - x_1}{a} = \frac{y - y_1}{b} = \frac{z - z_1}{c} \qquad \text{Symmetric equations}$$



The vector $\mathbf{v}$ is parallel to the line L.
Figure 11.44

EXAMPLE 1 Finding Parametric and Symmetric Equations

Find parametric and symmetric equations of the line L that passes through the point $(1, -2, 4)$ and is parallel to $\mathbf{v} = \langle 2, 4, -4 \rangle$, as shown in Figure 11.44.

Solution To find a set of parametric equations of the line, use the coordinates $x_1 = 1$, $y_1 = -2$, and $z_1 = 4$ and direction numbers $a = 2$, $b = 4$, and $c = -4$.

$$x = 1 + 2t, \quad y = -2 + 4t, \quad z = 4 - 4t \qquad \text{Parametric equations}$$

Because a, b, and c are all nonzero, a set of symmetric equations is

$$\frac{x - 1}{2} = \frac{y + 2}{4} = \frac{z - 4}{-4}. \qquad \text{Symmetric equations}$$

Neither parametric equations nor symmetric equations of a given line are unique. For instance, in Example 1, by letting $t = 1$ in the parametric equations, you would obtain the point $(3, 2, 0)$. Using this point with the direction numbers $a = 2$, $b = 4$, and $c = -4$ would produce a different set of parametric equations

$$x = 3 + 2t, \quad y = 2 + 4t, \quad \text{and} \quad z = -4t.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 2 **Parametric Equations of a Line Through Two Points**

See LarsonCalculus.com for an interactive version of this type of example.

Find a set of parametric equations of the line that passes through the points

$$(-2, 1, 0) \quad \text{and} \quad (1, 3, 5).$$

Solution Begin by using the points $P(-2, 1, 0)$ and $Q(1, 3, 5)$ to find a direction vector for the line passing through P and Q.

$$\mathbf{v} = \overrightarrow{PQ} = \langle 1 - (-2), 3 - 1, 5 - 0 \rangle = \langle 3, 2, 5 \rangle = \langle a, b, c \rangle$$

Using the direction numbers $a = 3$, $b = 2$, and $c = 5$ with the point $P(-2, 1, 0)$, you obtain the parametric equations

$$x = -2 + 3t, \quad y = 1 + 2t, \quad \text{and} \quad z = 5t.$$

REMARK As t varies over all real numbers, the parametric equations in Example 2 determine the points (x, y, z) on the line. In particular, note that $t = 0$ and $t = 1$ give the original points $(-2, 1, 0)$ and $(1, 3, 5)$.

Planes in Space

You have seen how an equation of a line in space can be obtained from a point on the line and a vector *parallel* to it. You will now see that an equation of a plane in space can be obtained from a point in the plane and a vector *normal* (perpendicular) to the plane.

Consider the plane containing the point $P(x_1, y_1, z_1)$ having a nonzero normal vector

$$\mathbf{n} = \langle a, b, c \rangle$$

as shown in Figure 11.45. This plane consists of all points $Q(x, y, z)$ for which vector $\overrightarrow{PQ}$ is orthogonal to $\mathbf{n}$. Using the dot product, you can write the following.

$$\mathbf{n} \cdot \overrightarrow{PQ} = 0$$
$$\langle a, b, c \rangle \cdot \langle x - x_1, y - y_1, z - z_1 \rangle = 0$$
$$a(x - x_1) + b(y - y_1) + c(z - z_1) = 0$$



The normal vector $\mathbf{n}$ is orthogonal to each vector $\overrightarrow{PQ}$ in the plane.
Figure 11.45

The third equation of the plane is said to be in **standard form.**

THEOREM 11.12 Standard Equation of a Plane in Space

The plane containing the point (x_1, y_1, z_1) and having normal vector

$$\mathbf{n} = \langle a, b, c \rangle$$

can be represented by the **standard form** of the equation of a plane

$$a(x - x_1) + b(y - y_1) + c(z - z_1) = 0.$$

By regrouping terms in the standard form of the equation of a plane, you obtain the **general form.**

$$ax + by + cz + d = 0$$ General form of equation of plane

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Given the general form of the equation of a plane, it is easy to find a normal vector to the plane. Simply use the coefficients of x, y, and z and write $\mathbf{n} = \langle a, b, c \rangle$.

EXAMPLE 3 Finding an Equation of a Plane in Three-Space

Find an equation (in standard form and in general form) of the plane containing the points

$$(2, 1, 1), \quad (1, 4, 1), \quad \text{and} \quad (-2, 0, 4).$$



A plane determined by $\mathbf{u}$ and $\mathbf{v}$
Figure 11.46

Solution To apply Theorem 11.12, you need a point in the plane and a vector that is normal to the plane. There are three choices for the point, but no normal vector is given. To obtain a normal vector, use the cross product of vectors $\mathbf{u}$ and $\mathbf{v}$ extending from the point $(2, 1, 1)$ to the points $(1, 4, 1)$ and $(-2, 0, 4)$, as shown in Figure 11.46. The component forms of $\mathbf{u}$ and $\mathbf{v}$ are

$$\mathbf{u} = \langle 1 - 2, 4 - 1, 1 - 1 \rangle = \langle -1, 3, 0 \rangle$$

and

$$\mathbf{v} = \langle -2 - 2, 0 - 1, 4 - 1 \rangle = \langle -4, -1, 3 \rangle.$$

So, it follows that a vector normal to the given plane is

$$\begin{aligned} \mathbf{n} &= \mathbf{u} \times \mathbf{v} \\ &= \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ -1 & 3 & 0 \\ -4 & -1 & 3 \end{vmatrix} \\ &= 9\mathbf{i} + 3\mathbf{j} + 13\mathbf{k}. \qquad \langle a, b, c \rangle \end{aligned}$$

The direction numbers for $\mathbf{n}$ are $a = 9$, $b = 3$, and $c = 13$. Using these numbers and the point $(x_1, y_1, z_1) = (2, 1, 1)$, you can determine an equation of the plane in standard form.

$$\begin{aligned} a(x - x_1) + b(y - y_1) + c(z - z_1) &= 0 \\ 9(x - 2) + 3(y - 1) + 13(z - 1) &= 0 \qquad \text{Standard form} \end{aligned}$$

By regrouping terms, the general form is

$$\begin{aligned} 9x - 18 + 3y - 3 + 13z - 13 &= 0 \\ 9x + 3y + 13z - 34 &= 0. \qquad \text{General form} \end{aligned}$$

REMARK In Example 3, check to see that each of the three original points satisfies the equation $9x + 3y + 13z - 34 = 0$.

Two distinct planes in three-space either are parallel or intersect in a line. For two planes that intersect, you can determine the angle $(0 \le \theta \le \pi/2)$ between them from the angle between their normal vectors, as shown in Figure 11.47. Specifically, if vectors $\mathbf{n}_1$ and $\mathbf{n}_2$ are normal to two intersecting planes, then the angle θ between the normal vectors is equal to the angle between the two planes and is

$$\cos\theta = \frac{|\mathbf{n}_1 \cdot \mathbf{n}_2|}{\|\mathbf{n}_1\| \, \|\mathbf{n}_2\|}. \qquad \text{Angle between two planes}$$



The angle θ between two planes
Figure 11.47

Consequently, two planes with normal vectors $\mathbf{n}_1$ and $\mathbf{n}_2$ are

1. *perpendicular* when $\mathbf{n}_1 \cdot \mathbf{n}_2 = 0$.
2. *parallel* when $\mathbf{n}_1$ is a scalar multiple of $\mathbf{n}_2$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

REMARK The three-dimensional rotatable graphs that are available at *LarsonCalculus.com* can help you visualize surfaces such as those shown in Figure 11.48. If you have access to these graphs, use them to help your spatial intuition when studying this section and other sections in the text that deal with vectors, curves, or surfaces in space.

EXAMPLE 4 Finding the Line of Intersection of Two Planes

In Figure 11.48, the equation for Plane 1 is $x - 2y + z = 0$ and the equation for Plane 2 is $2x + 3y - 2z = 0$. Find the angle between the two planes. Then find a set of parametric equations for the line of intersection of the planes.



Figure 11.48

Solution Normal vectors for the planes are $\mathbf{n}_1 = \langle 1, -2, 1 \rangle$ and $\mathbf{n}_2 = \langle 2, 3, -2 \rangle$. Consequently, the angle between the two planes is determined as follows.

$$\cos\theta = \frac{|\mathbf{n}_1 \cdot \mathbf{n}_2|}{\|\mathbf{n}_1\|\,\|\mathbf{n}_2\|} = \frac{|-6|}{\sqrt{6}\sqrt{17}} = \frac{6}{\sqrt{102}} \quad \Rightarrow \quad \theta = \arccos\frac{6}{\sqrt{102}}$$

This implies that the angle between the two planes is $\theta \approx 53.55°$. You can find the line of intersection of the two planes by simultaneously solving the two linear equations representing the planes. One way to do this is to multiply the first equation by -2 and add the result to the second equation.

$$\begin{aligned} x - 2y + z = 0 \quad &\Rightarrow \quad -2x + 4y - 2z = 0 && \text{Multiply Equation 1 by } -2. \\ 2x + 3y - 2z = 0 \quad &\Rightarrow \quad \underline{2x + 3y - 2z = 0} && \text{Write Equation 2.} \\ & \qquad\qquad 7y - 4z = 0 && \text{Add equations.} \\ & \qquad\qquad y = \frac{4z}{7} && \text{Solve for } y. \end{aligned}$$

Substituting $y = 4z/7$ back into one of the original equations, you can determine that $x = z/7$. Finally, by letting $t = z/7$, you obtain the parametric equations

$$x = t, \quad y = 4t, \quad \text{and} \quad z = 7t \qquad \text{Line of intersection}$$

which indicate that 1, 4, and 7 are direction numbers for the line of intersection. ■

Note that the direction numbers in Example 4 can be obtained from the cross product of the two normal vectors as follows.

$$\begin{aligned} \mathbf{n}_1 \times \mathbf{n}_2 &= \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ 1 & -2 & 1 \\ 2 & 3 & -2 \end{vmatrix} \\ &= \begin{vmatrix} -2 & 1 \\ 3 & -2 \end{vmatrix}\mathbf{i} - \begin{vmatrix} 1 & 1 \\ 2 & -2 \end{vmatrix}\mathbf{j} + \begin{vmatrix} 1 & -2 \\ 2 & 3 \end{vmatrix}\mathbf{k} \\ &= \mathbf{i} + 4\mathbf{j} + 7\mathbf{k} \end{aligned}$$

This means that the line of intersection of the two planes is parallel to the cross product of their normal vectors.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Sketching Planes in Space

If a plane in space intersects one of the coordinate planes, then the line of intersection is called the **trace** of the given plane in the coordinate plane. To sketch a plane in space, it is helpful to find its points of intersection with the coordinate axes and its traces in the coordinate planes. For example, consider the plane

$$3x + 2y + 4z = 12.$$ Equation of plane

You can find the xy-trace by letting $z = 0$ and sketching the line

$$3x + 2y = 12$$ xy-trace

in the xy-plane. This line intersects the x-axis at $(4, 0, 0)$ and the y-axis at $(0, 6, 0)$. In Figure 11.49, this process is continued by finding the yz-trace and the xz-trace and then shading the triangular region lying in the first octant.



xy-trace ($z = 0$): $3x + 2y = 12$ | yz-trace ($x = 0$): $2y + 4z = 12$ | xz-trace ($y = 0$): $3x + 4z = 12$

Traces of the plane $3x + 2y + 4z = 12$

Figure 11.49

If an equation of a plane has a missing variable, such as

$$2x + z = 1$$

then the plane must be *parallel to the axis* represented by the missing variable, as shown in Figure 11.50. If two variables are missing from an equation of a plane, such as

$$ax + d = 0$$

then it is *parallel to the coordinate plane* represented by the missing variables, as shown in Figure 11.51.



Plane $2x + z = 1$ is parallel to the y-axis.

Figure 11.50



Plane $ax + d = 0$ is parallel to the yz-plane. | Plane $by + d = 0$ is parallel to the xz-plane. | Plane $cz + d = 0$ is parallel to the xy-plane.

Figure 11.51

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Distances Between Points, Planes, and Lines

Consider two types of problems involving distance in space: (1) finding the distance between a point and a plane and (2) finding the distance between a point and a line. The solutions of these problems illustrate the versatility and usefulness of vectors in coordinate geometry: the first problem uses the *dot product* of two vectors, and the second problem uses the *cross product.*

The distance D between a point Q and a plane is the length of the shortest line segment connecting Q to the plane, as shown in Figure 11.52. For *any* point P in the plane, you can find this distance by projecting the vector $\overrightarrow{PQ}$ onto the normal vector $\mathbf{n}$. The length of this projection is the desired distance.



$D = \|\text{proj}_{\mathbf{n}}\overrightarrow{PQ}\|$

The distance between a point and a plane

Figure 11.52

THEOREM 11.13 Distance Between a Point and a Plane

The distance between a plane and a point Q (not in the plane) is

$$D = \|\text{proj}_{\mathbf{n}}\overrightarrow{PQ}\| = \frac{|\overrightarrow{PQ} \cdot \mathbf{n}|}{\|\mathbf{n}\|}$$

where P is a point in the plane and $\mathbf{n}$ is normal to the plane.

To find a point in the plane $ax + by + cz + d = 0$, where $a \neq 0$, let $y = 0$ and $z = 0$. Then, from the equation $ax + d = 0$, you can conclude that the point

$$\left(-\frac{d}{a}, 0, 0\right)$$

lies in the plane.

EXAMPLE 5 Finding the Distance Between a Point and a Plane

Find the distance between the point $Q(1, 5, -4)$ and the plane $3x - y + 2z = 6$.

Solution You know that $\mathbf{n} = \langle 3, -1, 2\rangle$ is normal to the plane. To find a point in the plane, let $y = 0$ and $z = 0$, and obtain the point $P(2, 0, 0)$. The vector from P to Q is

$$\begin{aligned}\overrightarrow{PQ} &= \langle 1 - 2, 5 - 0, -4 - 0\rangle \\ &= \langle -1, 5, -4\rangle.\end{aligned}$$

Using the Distance Formula given in Theorem 11.13 produces

$$D = \frac{|\overrightarrow{PQ} \cdot \mathbf{n}|}{\|\mathbf{n}\|} = \frac{|\langle -1, 5, -4\rangle \cdot \langle 3, -1, 2\rangle|}{\sqrt{9 + 1 + 4}} = \frac{|-3 - 5 - 8|}{\sqrt{14}} = \frac{16}{\sqrt{14}} \approx 4.28.$$

REMARK In the solution to Example 5, note that the choice of the point P is arbitrary. Try choosing a different point in the plane to verify that you obtain the same distance.

From Theorem 11.13, you can determine that the distance between the point $Q(x_0, y_0, z_0)$ and the plane $ax + by + cz + d = 0$ is

$$D = \frac{|a(x_0 - x_1) + b(y_0 - y_1) + c(z_0 - z_1)|}{\sqrt{a^2 + b^2 + c^2}}$$

or

$$D = \frac{|ax_0 + by_0 + cz_0 + d|}{\sqrt{a^2 + b^2 + c^2}}$$ Distance between a point and a plane

where $P(x_1, y_1, z_1)$ is a point in the plane and $d = -(ax_1 + by_1 + cz_1)$.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The distance between the parallel planes is approximately 2.14.
Figure 11.53

GO DIGITAL



The distance between a point and a line
Figure 11.54



The distance between the point Q and the line is $\sqrt{6} \approx 2.45$.
Figure 11.55

EXAMPLE 6 Finding the Distance Between Two Parallel Planes

Two parallel planes, $3x - y + 2z - 6 = 0$ and $6x - 2y + 4z + 4 = 0$, are shown in Figure 11.53. To find the distance between the planes, choose a point in the first plane, such as $(x_0, y_0, z_0) = (2, 0, 0)$. Then, from the second plane, you can determine that $a = 6$, $b = -2$, $c = 4$, and $d = 4$ and conclude that the distance is

$$D = \frac{|ax_0 + by_0 + cz_0 + d|}{\sqrt{a^2 + b^2 + c^2}}$$
$$= \frac{|6(2) + (-2)(0) + (4)(0) + 4|}{\sqrt{6^2 + (-2)^2 + 4^2}}$$
$$= \frac{16}{\sqrt{56}} = \frac{8}{\sqrt{14}} \approx 2.14.$$

The formula for the distance between a point and a line in space resembles that for the distance between a point and a plane—except that you replace the dot product with the length of the cross product and the normal vector $\mathbf{n}$ with a direction vector for the line.

THEOREM 11.14 Distance Between a Point and a Line in Space

The distance between a point Q and a line in space is

$$D = \frac{\|\overrightarrow{PQ} \times \mathbf{u}\|}{\|\mathbf{u}\|}$$

where $\mathbf{u}$ is a direction vector for the line and P is a point on the line.

Proof In Figure 11.54, let D be the distance between the point Q and the line. Then $D = \|\overrightarrow{PQ}\| \sin\theta$, where θ is the angle between $\mathbf{u}$ and $\overrightarrow{PQ}$. By Property 2 of Theorem 11.8, you have $\|\mathbf{u}\|\|\overrightarrow{PQ}\| \sin\theta = \|\mathbf{u} \times \overrightarrow{PQ}\| = \|\overrightarrow{PQ} \times \mathbf{u}\|$. Consequently,

$$D = \|\overrightarrow{PQ}\| \sin\theta = \frac{\|\overrightarrow{PQ} \times \mathbf{u}\|}{\|\mathbf{u}\|}.$$

EXAMPLE 7 Finding the Distance Between a Point and a Line

Find the distance between the point $Q(3, -1, 4)$ and the line

$$x = -2 + 3t, \quad y = -2t, \quad \text{and} \quad z = 1 + 4t.$$

Solution Using the direction numbers 3, −2, and 4, a direction vector for the line is $\mathbf{u} = \langle 3, -2, 4\rangle$. To find a point on the line, let $t = 0$ and obtain $P = (-2, 0, 1)$. So,

$$\overrightarrow{PQ} = \langle 3 - (-2), -1 - 0, 4 - 1\rangle = \langle 5, -1, 3\rangle$$

and you can form the cross product

$$\overrightarrow{PQ} \times \mathbf{u} = \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ 5 & -1 & 3 \\ 3 & -2 & 4 \end{vmatrix} = 2\mathbf{i} - 11\mathbf{j} - 7\mathbf{k} = \langle 2, -11, -7\rangle.$$

Finally, using Theorem 11.14, you can find the distance to be

$$D = \frac{\|\overrightarrow{PQ} \times \mathbf{u}\|}{\|\mathbf{u}\|} = \frac{\sqrt{174}}{\sqrt{29}} = \sqrt{6} \approx 2.45.$$

See Figure 11.55.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

11.5 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Give the parametric equations and the symmetric equations of a line in space. Describe what is required to find these equations.
2. Explain how to obtain the general form of the equation of a plane given the standard form.
3. Let $2(x-1)+4(y-3)-(z+5)=0$ represent a plane in space. What is the normal vector to this plane?
4. Write an equation of a plane in space that is parallel to the x-axis.

Checking Points on a Line

In Exercises 5 and 6, determine whether each point lies on the line.

5. $x=-2+t,\ y=3t,\ z=4+t$

(a) $(0,6,6)$ (b) $(2,3,5)$ (c) $(-4,-6,2)$

6. $\dfrac{x-3}{2}=\dfrac{y-7}{8}=z+2$

(a) $(7,23,0)$ (b) $(1,-1,-3)$ (c) $(-7,47,-7)$

Finding Parametric and Symmetric Equations

In Exercises 7–12, find sets of (a) parametric equations and (b) symmetric equations of the line that passes through the given point and is parallel to the given vector or line. (For each line, write the direction numbers as integers.)

	Point	Parallel to
7.	$(0,0,0)$	$\mathbf{v}=\langle 3,1,5\rangle$
8.	$(0,0,0)$	$\mathbf{v}=\langle -2,\frac{5}{2},1\rangle$
9.	$(-2,0,3)$	$\mathbf{v}=2\mathbf{i}+4\mathbf{j}-2\mathbf{k}$
10.	$(-3,0,2)$	$\mathbf{v}=6\mathbf{j}+3\mathbf{k}$
11.	$(1,0,1)$	$x=3+3t,\ y=5-2t,\ z=-7+t$
12.	$(-3,5,4)$	$\dfrac{x-1}{3}=\dfrac{y+1}{-2}=z-3$

Finding Parametric and Symmetric Equations

In Exercises 13–16, find sets of (a) parametric equations and (b) symmetric equations of the line that passes through the two points (if possible). (For each line, write the direction numbers as integers.)

13. $(5,-3,-2),\ \left(-\frac{2}{3},\frac{2}{3},1\right)$

14. $(0,4,3),\ (-1,2,5)$

15. $(7,-2,6),\ (-3,0,6)$

16. $(0,0,25),\ (10,10,0)$

Finding Parametric Equations

In Exercises 17–24, find a set of parametric equations of the line with the given characteristics.

17. The line passes through the point $(2,3,4)$ and is parallel to the xz-plane and the yz-plane.

18. The line passes through the point $(-4,5,2)$ and is parallel to the xy-plane and the yz-plane.

19. The line passes through the point $(2,3,4)$ and is perpendicular to the plane given by $3x+2y-z=6$.

20. The line passes through the point $(-4,5,2)$ and is perpendicular to the plane given by $-x+2y+z=5$.

21. The line passes through the point $(5,-3,-4)$ and is parallel to $\mathbf{v}=\langle 2,-1,3\rangle$.

22. The line passes through the point $(-1,4,-3)$ and is parallel to $\mathbf{v}=5\mathbf{i}-\mathbf{j}$.

23. The line passes through the point $(2,1,2)$ and is parallel to the line $x=-t,\ y=1+t,\ z=-2+t$.

24. The line passes through the point $(-6,0,8)$ and is parallel to the line $x=5-2t,\ y=-4+2t,\ z=0$.

Using Parametric and Symmetric Equations

In Exercises 25–28, find the coordinates of a point P on the line and a vector $\mathbf{v}$ parallel to the line.

25. $x=3-t,\quad y=-1+2t,\quad z=-2$

26. $x=4t,\quad y=5-t,\quad z=4+3t$

27. $\dfrac{x-7}{4}=\dfrac{y+6}{2}=z+2$

28. $\dfrac{x+3}{5}=\dfrac{y}{8}=\dfrac{z-3}{6}$

Determining Parallel Lines

In Exercises 29–32, determine whether the lines are parallel or identical.

29. $x=6-3t,\quad y=-2+2t,\quad z=5+4t$

$x=6t,\quad y=2-4t,\quad z=13-8t$

30. $x=1+2t,\quad y=-1-t,\quad z=3t$

$x=5+2t,\quad y=1-t,\quad z=8+3t$

31. $\dfrac{x-8}{4}=\dfrac{y+5}{-2}=\dfrac{z+9}{3}$

$\dfrac{x+4}{-8}=\dfrac{y-1}{4}=\dfrac{z+18}{-6}$

32. $\dfrac{x-1}{4}=\dfrac{y-1}{2}=\dfrac{z+3}{4}$

$\dfrac{x+2}{1}=\dfrac{y-1}{0.5}=\dfrac{z-3}{1}$

Finding a Point of Intersection

In Exercises 33–36, determine whether the lines intersect, and if so, find the point of intersection and the angle between the lines.

33. $x=4t+2,\quad y=3,\quad z=-t+1$

$x=2s+2,\quad y=2s+3,\quad z=s+1$

34. $x=-3t+1,\quad y=4t+1,\quad z=2t+4$

$x=3s+1,\quad y=2s+4,\quad z=-s+1$

35. $\dfrac{x}{3}=\dfrac{y-2}{-1}=z+1,\quad \dfrac{x-1}{4}=y+2=\dfrac{z+3}{-3}$

36. $\dfrac{x-2}{-3}=\dfrac{y-2}{6}=z-3,\quad \dfrac{x-3}{2}=y+5=\dfrac{z+2}{4}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Checking Points in a Plane **In Exercises 37 and 38, determine whether each point lies in the plane.**

37. $x + 2y - 4z - 1 = 0$

(a) $(-7, 2, -1)$ (b) $(5, 2, 2)$ (c) $(-6, 1, -1)$

38. $2x + y + 3z - 6 = 0$

(a) $(3, 6, -2)$ (b) $(-1, 5, -1)$ (c) $(2, 1, 0)$

Finding an Equation of a Plane **In Exercises 39–44, find an equation of the plane that passes through the given point and is perpendicular to the given vector or line.**

	Point	Perpendicular to
39.	$(1, 3, -7)$	$\mathbf{n} = \mathbf{j}$
40.	$(0, -1, 4)$	$\mathbf{n} = \mathbf{k}$
41.	$(3, 2, 2)$	$\mathbf{n} = 2\mathbf{i} + 3\mathbf{j} - \mathbf{k}$
42.	$(0, 0, 0)$	$\mathbf{n} = -3\mathbf{i} + 2\mathbf{k}$
43.	$(-1, 4, 0)$	$x = -1 + 2t, y = 5 - t, z = 3 - 2t$
44.	$(3, 2, 2)$	$\frac{x-1}{4} = y + 2 = \frac{z+3}{-3}$

Finding an Equation of a Plane **In Exercises 45–56, find an equation of the plane with the given characteristics.**

45. The plane passes through $(0, 0, 0)$, $(2, 0, 3)$, and $(-3, -1, 5)$.

46. The plane passes through $(3, -1, 2)$, $(2, 1, 5)$, and $(1, -2, -2)$.

47. The plane passes through $(1, 2, 3)$, $(3, 2, 1)$, and $(-1, -2, 2)$.

48. The plane passes through the point $(1, 2, 3)$ and is parallel to the yz-plane.

49. The plane passes through the point $(1, 2, 3)$ and is parallel to the xy-plane.

50. The plane contains the y-axis and makes an angle of $\pi/6$ with the positive x-axis.

51. The plane contains the lines given by

$$\frac{x-1}{-2} = y - 4 = z \quad \text{and} \quad \frac{x-2}{-3} = \frac{y-1}{4} = \frac{z-2}{-1}.$$

52. The plane passes through the point $(2, 2, 1)$ and contains the line given by

$$\frac{x}{2} = \frac{y-4}{-1} = z.$$

53. The plane passes through the points $(2, 2, 1)$ and $(-1, 1, -1)$ and is perpendicular to the plane

$$2x - 3y + z = 3.$$

54. The plane passes through the points $(3, 2, 1)$ and $(3, 1, -5)$ and is perpendicular to the plane

$$6x + 7y + 2z = 10.$$

55. The plane passes through the points $(1, -2, -1)$ and $(2, 5, 6)$ and is parallel to the x-axis.

56. The plane passes through the points $(4, 2, 1)$ and $(-3, 5, 7)$ and is parallel to the z-axis.

Finding an Equation of a Plane **In Exercises 57–60, find an equation of the plane that contains all the points that are equidistant from the given points.**

57. $(2, 2, 0)$, $(0, 2, 2)$

58. $(1, 0, 2)$, $(2, 0, 1)$

59. $(-3, 1, 2)$, $(6, -2, 4)$

60. $(-5, 1, -3)$, $(2, -1, 6)$

Parallel Planes **In Exercises 61–64, determine whether the planes are parallel or identical.**

61. $-5x + 2y - 8z = 6$
$15x - 6y + 24z = 17$

62. $2x - y + 3z = 8$
$8x - 4y + 12z = 5$

63. $3x - 2y + 5z = 10$
$75x - 50y + 125z = 250$

64. $-x + 4y - z = 6$
$-\frac{5}{2}x + 10y - \frac{5}{2}z = 15$

Intersection of Planes **In Exercises 65–68, (a) find the angle between the two planes and (b) find a set of parametric equations for the line of intersection of the planes.**

65. $3x + 2y - z = 7$
$x - 4y + 2z = 0$

66. $-2x + y + z = 2$
$6x - 3y + 2z = 4$

67. $3x - y + z = 7$
$4x + 6y + 3z = 2$

68. $6x - 3y + z = 5$
$-x + y + 5z = 5$

Comparing Planes **In Exercises 69–74, determine whether the planes are parallel, orthogonal, or neither. If they are neither parallel nor orthogonal, find the angle between the planes.**

69. $5x - 3y + z = 4$
$x + 4y + 7z = 1$

70. $3x + y - 4z = 3$
$-9x - 3y + 12z = 4$

71. $x - 3y + 6z = 4$
$5x + y - z = 4$

72. $3x + 2y - z = 7$
$x - 4y + 2z = 0$

73. $x - 5y - z = 1$
$5x - 25y - 5z = -3$

74. $2x - z = 1$
$4x + y + 8z = 10$

Sketching a Graph of a Plane **In Exercises 75–82, sketch a graph of the plane and label any intercepts.**

75. $y = -2$

76. $z = 1$

77. $x + z = 6$

78. $2x + y = 8$

79. $4x + 2y + 6z = 12$

80. $3x + 6y + 2z = 6$

81. $2x - y + 3z = 4$

82. $2x - y + z = 4$

Intersection of a Plane and a Line **In Exercises 83–86, find the point(s) of intersection (if any) of the plane and the line. Also, determine whether the line lies in the plane.**

83. $x + 3y - z = 6$, $\frac{x+7}{2} = y - 4 = \frac{z+1}{5}$

84. $2x + 3y = -5$, $\frac{x-1}{4} = \frac{y}{2} = \frac{z-3}{6}$

85. $2x + 3y = 10$, $\frac{x-1}{3} = \frac{y+1}{-2} = z - 3$

86. $5x + 3y = 17$, $\frac{x-4}{2} = \frac{y+1}{-3} = \frac{z+2}{5}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding the Distance Between a Point and a Plane

In Exercises 87–90, find the distance between the point and the plane.

87. $(0, 0, 0)$
$2x + 3y + z = 12$

88. $(0, 0, 0)$
$5x + y - z = 9$

89. $(2, 8, 4)$
$2x + y + z = 5$

90. $(1, 3, -1)$
$3x - 4y + 5z = 6$

Finding the Distance Between Two Parallel Planes

In Exercises 91–94, verify that the two planes are parallel and find the distance between the planes.

91. $x - 3y + 4z = 10$
$x - 3y + 4z = 6$

92. $2x + 7y + z = 13$
$2x + 7y + z = 9$

93. $-3x + 6y + 7z = 1$
$6x - 12y - 14z = 25$

94. $-x + 6y + 2z = 3$
$-\frac{1}{2}x + 3y + z = 4$

Finding the Distance Between a Point and a Line

In Exercises 95–98, find the distance between the point and the line given by the set of parametric equations.

95. $(1, 5, -2)$; $x = 4t - 2$, $y = 3$, $z = -t + 1$

96. $(1, -2, 4)$; $x = 2t$, $y = t - 3$, $z = 2t + 2$

97. $(-2, 1, 3)$; $x = 1 - t$, $y = 2 + t$, $z = -2t$

98. $(4, -1, 5)$; $x = 3$, $y = 1 + 3t$, $z = 1 + t$

Finding the Distance Between Two Parallel Lines

In Exercises 99 and 100, verify that the two lines are parallel and find the distance between the lines.

99. L_1: $x = 2 - t$, $y = 3 + 2t$, $z = 4 + t$
L_2: $x = 3t$, $y = 1 - 6t$, $z = 4 - 3t$

100. L_1: $x = 3 + 6t$, $y = -2 + 9t$, $z = 1 - 12t$
L_2: $x = -1 + 4t$, $y = 3 + 6t$, $z = -8t$

Exploring Concepts

101. Consider a line and a point not on the line. How many planes contain the line and the point? Explain.

102. How many planes are orthogonal to a given plane in space? Explain.

103. Do two distinct lines in space determine a unique plane? Explain.

104. HOW DO YOU SEE IT? Match the general equation with its graph. Then state what axis or plane the equation is parallel to.

(a) $ax + by + d = 0$

(b) $ax + d = 0$

(c) $cz + d = 0$

(d) $ax + cz + d = 0$

(i)



(ii)



(iii)



(iv)



105. Modeling Data

Personal consumption expenditures (in billions of dollars) for several types of recreation from 2012 through 2017 are shown in the table, where x is the expenditures on amusement parks and campgrounds, y is the expenditures on live entertainment (excluding sports), and z is the expenditures on spectator sports. *(Source: U.S. Bureau of Economic Analysis)*

Year	2012	2013	2014	2015	2016	2017
x	44.3	46.8	49.8	54.2	57.9	61.9
y	24.9	24.8	26.5	28.9	30.7	32.6
z	20.9	22.1	23.2	23.1	24.2	26.1

A model for the data is given by

$0.53x - 0.6y - z = -11.98.$

(a) Complete a fourth row in the table using the model to approximate z for the given values of x and y. Compare the approximations with the actual values of z.

(b) According to this model, an increase in expenditures on recreation type x and a decrease in expenditures on recreation type y would correspond to what kind of change in expenditures on recreation type z?

Jaroslav Moravcik/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

106. Mechanical Design The figure shows a chute at the top of a grain elevator of a combine that funnels the grain into a bin. Find the angle between two adjacent sides.



107. Distance Two insects are crawling along different lines in three-space. At time t (in minutes), the first insect is at the point (x, y, z) on the line $x = 6 + t$, $y = 8 - t$, $z = 3 + t$. Also, at time t, the second insect is at the point (x, y, z) on the line $x = 1 + t$, $y = 2 + t$, $z = 2t$. Assume that distances are given in inches.

(a) Find the distance between the two insects at time $t = 0$.

(b) Use a graphing utility to graph the distance between the insects from $t = 0$ to $t = 10$.

(c) Using the graph from part (b), what can you conclude about the distance between the insects?

(d) How close to each other do the insects get?

108. Finding an Equation of a Sphere Find the standard equation of the sphere with center $(-3, 2, 4)$ that is tangent to the plane given by $2x + 4y - 3z = 8$.

109. Finding a Point of Intersection Find the point of intersection of the plane $3x - y + 4z = 7$ and the line through $(5, 4, -3)$ that is perpendicular to this plane.

110. Finding the Distance Between a Plane and a Line Show that the plane $2x - y - 3z = 4$ is parallel to the line $x = -2 + 2t$, $y = -1 + 4t$, $z = 4$, and find the distance between them.

111. Finding Parametric Equations Find a set of parametric equations for the line passing through the point $(0, 1, 4)$ that is perpendicular to $\mathbf{u} = \langle 2, -5, 1 \rangle$ and $\mathbf{v} = \langle -3, 1, 4 \rangle$.

112. Finding Parametric Equations Find a set of parametric equations for the line passing through the point $(1, 0, 2)$ that is parallel to the plane given by $x + y + z = 5$ and perpendicular to the line $x = t$, $y = 1 + t$, $z = 1 + t$.

True or False? In Exercises 113–118, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.

113. If $\mathbf{v} = a_1\mathbf{i} + b_1\mathbf{j} + c_1\mathbf{k}$ is any vector in the plane given by $a_2x + b_2y + c_2z + d_2 = 0$, then $a_1a_2 + b_1b_2 + c_1c_2 = 0$.

114. Two lines in space are either intersecting or parallel.

115. Two planes in space are either intersecting or parallel.

116. If two lines L_1 and L_2 are each parallel to a plane, then L_1 and L_2 are parallel.

117. If two planes P_1 and P_2 are each perpendicular to a third plane in space, then P_1 and P_2 are parallel.

118. A plane and a line in space are either intersecting or parallel.

SECTION PROJECT

Distances in Space

You have learned two distance formulas in this section—one for the distance between a point and a plane, and one for the distance between a point and a line. In this project, you will study a third distance problem—the distance between two skew lines. Two lines in space are *skew* if they are neither parallel nor intersecting (see figure).

(a) Consider the following two lines in space.

L_1: $x = 4 + 5t$, $y = 5 + 5t$, $z = 1 - 4t$

L_2: $x = 4 + s$, $y = -6 + 8s$, $z = 7 - 3s$

(i) Show that these lines are not parallel.

(ii) Show that these lines do not intersect and therefore are skew lines.

(iii) Show that the two lines lie in parallel planes.

(iv) Find the distance between the parallel planes from part (iii). This is the distance between the original skew lines.

(b) Use the procedure in part (a) to find the distance between the lines.

L_1: $x = 2t$, $y = 4t$, $z = 6t$

L_2: $x = 1 - s$, $y = 4 + s$, $z = -1 + s$

(c) Use the procedure in part (a) to find the distance between the lines.

L_1: $x = 3t$, $y = 2 - t$, $z = -1 + t$

L_2: $x = 1 + 4s$, $y = -2 + s$, $z = -3 - 3s$

(d) Develop a formula for finding the distance between the skew lines.

L_1: $x = x_1 + a_1t$, $y = y_1 + b_1t$, $z = z_1 + c_1t$

L_2: $x = x_2 + a_2s$, $y = y_2 + b_2s$, $z = z_2 + c_2s$



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

11.6 Surfaces in Space

GO DIGITAL

- **Recognize and write equations of cylindrical surfaces.**
- **Recognize and write equations of quadric surfaces.**
- **Recognize and write equations of surfaces of revolution.**

Cylindrical Surfaces

The first five sections of this chapter contained the vector portion of the preliminary work necessary to study vector calculus and the calculus of space. In this and the next section, you will study surfaces in space and alternative coordinate systems for space. You have already studied two special types of surfaces.

1. Spheres: $(x - x_0)^2 + (y - y_0)^2 + (z - z_0)^2 = r^2$ Section 11.2

2. Planes: $ax + by + cz + d = 0$ Section 11.5

A third type of surface in space is a **cylindrical surface,** or simply a **cylinder.** To define a cylinder, consider the familiar right circular cylinder shown in Figure 11.56. The cylinder was generated by a vertical line moving around the circle $x^2 + y^2 = a^2$ in the xy-plane. This circle is a **generating curve** for the cylinder, as indicated in the next definition.



Rulings are parallel to z-axis
Figure 11.56

Definition of a Cylinder

Let C be a curve in a plane and let L be a line not in a parallel plane. The set of all lines parallel to L and intersecting C is a **cylinder.** The curve C is the **generating curve** (or **directrix**) of the cylinder, and the parallel lines are **rulings.**

Without loss of generality, you can assume that C lies in one of the three coordinate planes. Moreover, this text restricts the discussion to *right* cylinders—cylinders whose rulings are perpendicular to the coordinate plane containing C, as shown in Figure 11.57. Note that the rulings intersect C and are parallel to the line L.

For the right circular cylinder shown in Figure 11.56, the equation of the generating curve in the xy-plane is

$$x^2 + y^2 = a^2.$$



Right cylinder: A cylinder whose rulings are perpendicular to the coordinate plane containing C
Figure 11.57

To find an equation of the cylinder, note that you can generate any one of the rulings by fixing the values of x and y and then allowing z to take on all real values. In this sense, the value of z is arbitrary and so it is not included in the equation. In other words, the equation of this cylinder is simply the equation of its generating curve.

$$x^2 + y^2 = a^2$$ Equation of cylinder in space

Equations of Cylinders

The equation of a cylinder whose rulings are parallel to one of the coordinate axes contains only the variables corresponding to the other two axes.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 1 **Sketching a Cylinder**

Sketch the surface represented by each equation.

a. $z = y^2$ **b.** $z = \sin x, \quad 0 \le x \le 2\pi$

Solution

a. The graph is a cylinder whose generating curve, $z = y^2$, is a parabola in the yz-plane. The rulings of the cylinder are parallel to the x-axis, as shown in Figure 11.58(a).

b. The graph is a cylinder generated by the sine curve in the xz-plane. The rulings are parallel to the y-axis, as shown in Figure 11.58(b).



(a) Rulings are parallel to x-axis. **(b)** Rulings are parallel to y-axis.

Figure 11.58

Quadric Surfaces

The fourth basic type of surface in space is a **quadric surface.** Quadric surfaces are the three-dimensional analogs of conic sections.

Quadric Surface

The equation of a **quadric surface** in space is a second-degree equation in three variables. The **general form** of the equation is

$$Ax^2 + By^2 + Cz^2 + Dxy + Exz + Fyz + Gx + Hy + Iz + J = 0.$$

There are six basic types of quadric surfaces: **ellipsoid, hyperboloid of one sheet, hyperboloid of two sheets, elliptic cone, elliptic paraboloid,** and **hyperbolic paraboloid.**

The intersection of a surface with a plane is called the **trace of the surface** in the plane. To visualize a surface in space, it is helpful to determine its traces in some well-chosen planes. The traces of quadric surfaces are conics. These traces, together with the **standard form** of the equation of each quadric surface, are shown in the table on the next two pages.

In the table on the next two pages, only one of several orientations of each quadric surface is shown. When the surface is oriented along a different axis, its standard equation will change accordingly, as illustrated in Examples 2 and 3. The fact that the two types of paraboloids have one variable raised to the first power can be helpful in classifying quadric surfaces. The other four types of basic quadric surfaces have equations that are of *second degree* in all three variables.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Ellipsoid

$$\frac{x^2}{a^2}+\frac{y^2}{b^2}+\frac{z^2}{c^2}=1$$

Trace	Plane
Ellipse	Parallel to xy-plane
Ellipse	Parallel to xz-plane
Ellipse	Parallel to yz-plane

The surface is a sphere when $a = b = c \neq 0$.





Hyperboloid of One Sheet

$$\frac{x^2}{a^2}+\frac{y^2}{b^2}-\frac{z^2}{c^2}=1$$

Trace	Plane
Ellipse	Parallel to xy-plane
Hyperbola	Parallel to xz-plane
Hyperbola	Parallel to yz-plane

The axis of the hyperboloid corresponds to the variable whose coefficient is negative.





Hyperboloid of Two Sheets

$$\frac{z^2}{c^2}-\frac{x^2}{a^2}-\frac{y^2}{b^2}=1$$

Trace	Plane
Ellipse	Parallel to xy-plane
Hyperbola	Parallel to xz-plane
Hyperbola	Parallel to yz-plane

The axis of the hyperboloid corresponds to the variable whose coefficient is positive. There is no trace in the coordinate plane perpendicular to this axis.



GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Elliptic Cone

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} - \frac{z^2}{c^2} = 0$$

Trace	Plane
Ellipse	Parallel to xy-plane
Hyperbola	Parallel to xz-plane
Hyperbola	Parallel to yz-plane

The axis of the cone corresponds to the variable whose coefficient is negative. The traces in the coordinate planes parallel to this axis are intersecting lines.





Elliptic Paraboloid

$$z = \frac{x^2}{a^2} + \frac{y^2}{b^2}$$

Trace	Plane
Ellipse	Parallel to xy-plane
Parabola	Parallel to xz-plane
Parabola	Parallel to yz-plane

The axis of the paraboloid corresponds to the variable raised to the first power.





Hyperbolic Paraboloid

$$z = \frac{y^2}{b^2} - \frac{x^2}{a^2}$$

Trace	Plane
Hyperbola	Parallel to xy-plane
Parabola	Parallel to xz-plane
Parabola	Parallel to yz-plane

The axis of the paraboloid corresponds to the variable raised to the first power.



GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

To classify a quadric surface, begin by writing the equation of the surface in standard form. Then, determine several traces taken in the coordinate planes *or* taken in planes that are parallel to the coordinate planes.

EXAMPLE 2 Sketching a Quadric Surface

Classify and sketch the surface

$$4x^2 - 3y^2 + 12z^2 + 12 = 0.$$

Solution Begin by writing the equation in standard form.

$$4x^2 - 3y^2 + 12z^2 + 12 = 0 \qquad \text{Write original equation.}$$

$$\frac{x^2}{-3} + \frac{y^2}{4} - z^2 - 1 = 0 \qquad \text{Divide by } -12.$$

$$\frac{y^2}{4} - \frac{x^2}{3} - z^2 = 1 \qquad \text{Standard form}$$

From the table on pages 800 and 801, you can conclude that the surface is a hyperboloid of two sheets with the y-axis as its axis. To sketch the graph of this surface, it helps to find the traces in the coordinate planes.

$$xy\text{-trace } (z = 0): \quad \frac{y^2}{4} - \frac{x^2}{3} = 1 \qquad \text{Hyperbola}$$

$$xz\text{-trace } (y = 0): \quad \frac{x^2}{3} + \frac{z^2}{1} = -1 \qquad \text{No trace}$$

$$yz\text{-trace } (x = 0): \quad \frac{y^2}{4} - \frac{z^2}{1} = 1 \qquad \text{Hyperbola}$$

The graph is shown in Figure 11.59.



Figure 11.59

EXAMPLE 3 Sketching a Quadric Surface

Classify and sketch the surface

$$x - y^2 - 4z^2 = 0.$$

Solution Because x is raised only to the first power, the surface is a paraboloid. The axis of the paraboloid is the x-axis. In standard form, the equation is

$$x = y^2 + 4z^2. \qquad \text{Standard form}$$

Some convenient traces are listed below.

$$xy\text{-trace } (z = 0): \quad x = y^2 \qquad \text{Parabola}$$

$$xz\text{-trace } (y = 0): \quad x = 4z^2 \qquad \text{Parabola}$$

$$\text{parallel to } yz\text{-plane } (x = 4): \quad \frac{y^2}{4} + \frac{z^2}{1} = 1 \qquad \text{Ellipse}$$

The surface is an *elliptic* paraboloid, as shown in Figure 11.60.



Figure 11.60

Some second-degree equations in x, y, and z do not represent any of the basic types of quadric surfaces. For example, the graph of

$$x^2 + y^2 + z^2 = 0 \qquad \text{Single point}$$

is a single point, and the graph of

$$x^2 + y^2 = 1 \qquad \text{Right circular cylinder}$$

is a right circular cylinder.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



An ellipsoid centered at $(2, -1, 1)$
Figure 11.61

For a quadric surface not centered at the origin, you can form the standard equation by completing the square, as demonstrated in Example 4.

EXAMPLE 4 A Quadric Surface Not Centered at the Origin

See LarsonCalculus.com for an interactive version of this type of example.

Classify and sketch the surface

$$x^2 + 2y^2 + z^2 - 4x + 4y - 2z + 3 = 0.$$

Solution Begin by grouping terms and factoring where possible.

$$x^2 - 4x + 2(y^2 + 2y) + z^2 - 2z = -3$$

Next, complete the square for each variable and write the equation in standard form.

$$(x^2 - 4x + \ \ ) + 2(y^2 + 2y + \ \ ) + (z^2 - 2z + \ \ ) = -3$$
$$(x^2 - 4x + 4) + 2(y^2 + 2y + 1) + (z^2 - 2z + 1) = -3 + 4 + 2 + 1$$
$$(x - 2)^2 + 2(y + 1)^2 + (z - 1)^2 = 4$$
$$\frac{(x-2)^2}{4} + \frac{(y+1)^2}{2} + \frac{(z-1)^2}{4} = 1$$

From this equation, you can conclude that the quadric surface is an ellipsoid that is centered at $(2, -1, 1)$. Its graph is shown in Figure 11.61. ■

TECHNOLOGY A three-dimensional graphing utility can help you visualize a surface in space.* Such a graphing utility may create a three-dimensional graph by sketching several traces of the surface and then applying a "hidden-line" routine that blocks out portions of the surface that lie behind other portions of the surface. Two examples of figures that were generated by *Mathematica* are shown below.



Generated by Mathematica

Elliptic paraboloid

$$x = \frac{y^2}{2} + \frac{z^2}{2}$$



Generated by Mathematica

Hyperbolic paraboloid

$$z = \frac{y^2}{16} - \frac{x^2}{16}$$

Using a graphing utility to graph a surface in space requires practice. For one thing, you must know enough about the surface to be able to specify a *viewing window* that gives a representative view of the surface. Also, you can often improve the view of a surface by rotating the axes. For instance, note that the elliptic paraboloid in the figure is seen from a line of sight that is "higher" than the line of sight used to view the hyperbolic paraboloid.

* Some three-dimensional graphing utilities require surfaces to be entered with parametric equations. For a discussion of this technique, see Section 15.5.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 11.62

Surfaces of Revolution

The fifth special type of surface you will study is a **surface of revolution.** In Section 7.4, you studied a method for finding the *area* of such a surface. You will now look at a procedure for finding its *equation.* Consider the graph of the **radius function**

$$y = r(z) \qquad \text{Generating curve}$$

in the yz-plane. When this graph is revolved about the z-axis, it forms a surface of revolution, as shown in Figure 11.62. The trace of the surface in the plane $z = z_0$ is a circle whose radius is $r(z_0)$ and whose equation is

$$x^2 + y^2 = [r(z_0)]^2. \qquad \text{Circular trace in plane: } z = z_0$$

Replacing z_0 with z produces an equation that is valid for all values of z. In a similar manner, you can obtain equations for surfaces of revolution for the other two axes, and the results are summarized as follows.

GO DIGITAL

Surface of Revolution

If the graph of a radius function r is revolved about one of the coordinate axes, then the equation of the resulting surface of revolution has one of the forms listed below.

1. Revolved about the x-axis: $y^2 + z^2 = [r(x)]^2$
2. Revolved about the y-axis: $x^2 + z^2 = [r(y)]^2$
3. Revolved about the z-axis: $x^2 + y^2 = [r(z)]^2$

EXAMPLE 5 Finding an Equation for a Surface of Revolution

Find an equation for the surface of revolution formed by revolving (a) the graph of $y = 1/z$ about the z-axis and (b) the graph of $9x^2 = y^3$ about the y-axis.

Solution

a. An equation for the surface of revolution formed by revolving the graph of

$$y = \frac{1}{z} \qquad \text{Radius function}$$

about the z-axis is

$$x^2 + y^2 = [r(z)]^2 \qquad \text{Revolved about the } z\text{-axis}$$

$$x^2 + y^2 = \left(\frac{1}{z}\right)^2. \qquad \text{Substitute } 1/z \text{ for } r(z).$$



Figure 11.63

b. To find an equation for the surface formed by revolving the graph of $9x^2 = y^3$ about the y-axis, solve for x in terms of y to obtain

$$x = \frac{1}{3}y^{3/2} = r(y). \qquad \text{Radius function}$$

So, the equation for this surface is

$$x^2 + z^2 = [r(y)]^2 \qquad \text{Revolved about the } y\text{-axis}$$

$$x^2 + z^2 = \left(\frac{1}{3}y^{3/2}\right)^2 \qquad \text{Substitute } \tfrac{1}{3}y^{3/2} \text{ for } r(y).$$

$$x^2 + z^2 = \frac{1}{9}y^3. \qquad \text{Equation of surface}$$

The graph is shown in Figure 11.63. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The generating curve for a surface of revolution is not unique. For instance, the surface

$$x^2 + z^2 = e^{-2y}$$

can be formed by revolving either the graph of

$$x = e^{-y}$$

about the y-axis or the graph of

$$z = e^{-y}$$

about the y-axis, as shown in Figure 11.64.



Figure 11.64

EXAMPLE 6 Finding a Generating Curve

Find a generating curve and the axis of revolution for the surface

$$x^2 + 3y^2 + z^2 = 9.$$

Solution The equation has one of the forms listed below.

$$x^2 + y^2 = [r(z)]^2 \quad \text{Revolved about } z\text{-axis}$$
$$y^2 + z^2 = [r(x)]^2 \quad \text{Revolved about } x\text{-axis}$$
$$x^2 + z^2 = [r(y)]^2 \quad \text{Revolved about } y\text{-axis}$$

Because the coefficients of x^2 and z^2 are equal, you should choose the third form and write

$$x^2 + z^2 = 9 - 3y^2.$$

The y-axis is the axis of revolution. You can choose a generating curve from either of the traces

$$x^2 = 9 - 3y^2 \quad \text{Trace in } xy\text{-plane}$$

or

$$z^2 = 9 - 3y^2. \quad \text{Trace in } yz\text{-plane}$$

For instance, using the first trace, the generating curve is the semiellipse

$$x = \sqrt{9 - 3y^2}. \quad \text{Generating curve}$$

The graph of this surface is shown in Figure 11.65.



Figure 11.65

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

11.6 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain how quadric surfaces and conic sections are related.
2. Explain what the equation $z = x^2$ represents in the xz-plane. What does it represent in three-space?
3. Explain what is meant by the trace of a surface. How do you find a trace?
4. Determine whether every second-degree equation in x, y, and z represents a quadric surface. Explain.

Matching In Exercises 5–10, match the equation with its graph. [The graphs are labeled (a), (b), (c), (d), (e), and (f).]

(a)



(b)



(c)



(d)



(e)



(f)



5. $\frac{x^2}{9} + \frac{y^2}{16} + \frac{z^2}{9} = 1$
6. $15x^2 - 4y^2 + 15z^2 = -4$
7. $4x^2 - y^2 + 4z^2 = 4$
8. $y^2 = 4x^2 + 9z^2$
9. $4x^2 - 4y + z^2 = 0$
10. $4x^2 - y^2 + 4z = 0$

Sketching a Surface in Space In Exercises 11–14, describe and sketch the surface.

11. $y^2 + z^2 = 9$
12. $y^2 + z = 6$
13. $4x^2 + y^2 = 4$
14. $y^2 - z^2 = 25$

Sketching a Quadric Surface In Exercises 15–26, classify and sketch the quadric surface. Use a graphing utility to confirm your sketch.

15. $4x^2 - y^2 - z^2 = 1$
16. $\frac{x^2}{16} + \frac{y^2}{25} + \frac{z^2}{25} = 1$
17. $16x^2 - y^2 + 16z^2 = 4$
18. $z = x^2 + 4y^2$
19. $x^2 + \frac{y^2}{4} + z^2 = 1$
20. $z^2 - x^2 - \frac{y^2}{4} = 1$
21. $z^2 = x^2 + \frac{y^2}{9}$
22. $3z = -y^2 + x^2$
23. $x^2 - y^2 + z = 0$
24. $x^2 = 2y^2 + 2z^2$
25. $x^2 - y + z^2 = 0$
26. $-8x^2 + 18y^2 + 18z^2 = 2$

Exploring Concepts

27. Explain how to determine whether a quadric surface is a hyperboloid of one sheet or a hyperboloid of two sheets.
28. Is every trace of an ellipsoid an ellipse? Explain.
29. Determine whether there exists a quadric surface whose traces are all parabolas. Explain.

30. **HOW DO YOU SEE IT?** The four figures below are graphs of the quadric surface $z = x^2 + y^2$. Match each of the four graphs with the point in space from which the paraboloid is viewed.

(a)



(b)



(c)



(d)



(i) (0, 0, 20)
(ii) (0, 20, 0)
(iii) (20, 0, 0)
(iv) (10, 10, 20)

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding an Equation for a Surface of Revolution **In Exercises 31–36, find an equation for the surface of revolution formed by revolving the curve in the indicated coordinate plane about the given axis.**

	Equation of Curve	Coordinate Plane	Axis of Revolution
31.	$z = 5y$	yz-plane	y-axis
32.	$z^2 = 9y$	yz-plane	y-axis
33.	$y^3 = 8z$	yz-plane	z-axis
34.	$z = \ln x$	xz-plane	z-axis
35.	$xy = 2$	xy-plane	x-axis
36.	$2z = \sqrt{4 - x^2}$	xz-plane	x-axis

Finding a Generating Curve **In Exercises 37–40, find an equation of a generating curve given the equation of its surface of revolution.**

37. $x^2 + y^2 - 2z = 0$
38. $x^2 + z^2 = \cos^2 y$
39. $8x^2 + y^2 + z^2 = 5$
40. $6x^2 + 2y^2 + 2z^2 = 1$

Finding the Volume of a Solid **In Exercises 41 and 42, use the shell method to find the volume of the solid below the surface of revolution and above the xy-plane.**

41. The curve $z = 4x - x^2$ in the xz-plane is revolved about the z-axis.
42. The curve

$$z = \sin y, \quad 0 \le y \le \pi$$

in the yz-plane is revolved about the z-axis.

Analyzing a Trace **In Exercises 43 and 44, analyze the trace when the surface**

$$z = \tfrac{1}{2}x^2 + \tfrac{1}{4}y^2$$

is intersected by the indicated planes.

43. Find the lengths of the major and minor axes and the coordinates of the foci of the ellipse generated when the surface is intersected by the planes given by

(a) $z = 2$ and (b) $z = 8$.

44. Find the coordinates of the focus of the parabola formed when the surface is intersected by the planes given by

(a) $y = 4$ and (b) $x = 2$.

Finding an Equation of a Surface **In Exercises 45 and 46, find an equation of the surface satisfying the conditions, and identify the surface.**

45. The set of all points equidistant from the point $(0, 2, 0)$ and the plane $y = -2$
46. The set of all points equidistant from the point $(0, 0, 4)$ and the xy-plane

47. Geography

Because of the forces caused by its rotation, Earth is an oblate ellipsoid rather than a sphere. The equatorial radius is 3963 miles and the polar radius is 3950 miles. Find an equation of the ellipsoid. (Assume that the center of Earth is at the origin and that the trace formed by the plane $z = 0$ corresponds to the equator.)

Denis Tabler/Shutterstock.com

48. **Machine Design** The top of a rubber bushing designed to absorb vibrations in an automobile is the surface of revolution generated by revolving the curve

$$z = \frac{1}{2}y^2 + 1$$

for $0 \le y \le 2$ in the yz-plane about the z-axis.

(a) Find an equation for the surface of revolution.

(b) All measurements are in centimeters and the bushing is set on the xy-plane. Use the shell method to find its volume.

(c) The bushing has a hole of diameter 1 centimeter through its center and parallel to the axis of revolution. Find the volume of the rubber bushing.

49. **Using a Hyperbolic Paraboloid** Determine the intersection of the hyperbolic paraboloid

$$z = \frac{y^2}{b^2} - \frac{x^2}{a^2}$$

with the plane $bx + ay - z = 0$. (Assume $a, b > 0$.)

50. **Intersection of Surfaces** Explain why the curve of intersection of the surfaces $x^2 + 3y^2 - 2z^2 + 2y = 4$ and $2x^2 + 6y^2 - 4z^2 - 3x = 2$ lies in a plane.

51. **Think About It** Three types of classic *topological surfaces* are shown below. The sphere and torus have both an "inside" and an "outside." Does the Klein bottle have both an "inside" and an "outside?" Explain.

Sphere

Torus

Klein bottle

Klein bottle

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

11.7 Cylindrical and Spherical Coordinates

GO DIGITAL

- **Use cylindrical coordinates to represent surfaces in space.**
- **Use spherical coordinates to represent surfaces in space.**

Cylindrical Coordinates

You have already seen that some two-dimensional graphs are easier to represent in polar coordinates than in rectangular coordinates. A similar situation exists for surfaces in space. In this section, you will study two alternative space-coordinate systems. The first, the **cylindrical coordinate system,** is an extension of polar coordinates in the plane to three-dimensional space.



Figure 11.66

The Cylindrical Coordinate System

In a **cylindrical coordinate system,** a point P in space is represented by an ordered triple (r, θ, z).

1. (r, θ) is a polar representation of the projection of P in the xy-plane.
2. z is the directed distance from (r, θ) to P.

To convert from rectangular to cylindrical coordinates (or vice versa), use the conversion guidelines for polar coordinates listed below and illustrated in Figure 11.66.

Cylindrical to rectangular:

$$x = r\cos\theta, \quad y = r\sin\theta, \quad z = z$$

Rectangular to cylindrical:

$$r^2 = x^2 + y^2, \quad \tan\theta = \frac{y}{x}, \quad z = z$$

The point $(0, 0, 0)$ is called the **pole.** Moreover, because the representation of a point in the polar coordinate system is not unique, it follows that the representation in the cylindrical coordinate system is also not unique.



Figure 11.67

EXAMPLE 1 Cylindrical-to-Rectangular Conversion

Convert the point $(r, \theta, z) = (4, 5\pi/6, 3)$ to rectangular coordinates.

Solution Using the cylindrical-to-rectangular conversion equations produces

$$x = 4\cos\frac{5\pi}{6} = 4\left(-\frac{\sqrt{3}}{2}\right) = -2\sqrt{3} \qquad x\text{-coordinate}$$

$$y = 4\sin\frac{5\pi}{6} = 4\left(\frac{1}{2}\right) = 2 \qquad y\text{-coordinate}$$

and

$$z = 3. \qquad z\text{-coordinate}$$

So, in rectangular coordinates, the point is

$$(x, y, z) = \left(-2\sqrt{3}, 2, 3\right).$$ See Figure 11.67. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



Figure 11.68

EXAMPLE 2 Rectangular-to-Cylindrical Conversion

Convert the point

$$(x, y, z) = \left(1, \sqrt{3}, 2\right)$$

to cylindrical coordinates.

Solution Use the rectangular-to-cylindrical conversion equations.

$$r = \pm\sqrt{1 + 3} = \pm 2$$

$$\tan\theta = \sqrt{3} \quad \Rightarrow \quad \theta = \arctan\sqrt{3} + n\pi = \frac{\pi}{3} + n\pi$$

$$z = 2$$

You have two choices for r and infinitely many choices for θ. As shown in Figure 11.68, two convenient representations of the point are

$$\left(2, \frac{\pi}{3}, 2\right) \qquad r > 0 \text{ and } \theta \text{ in Quadrant I}$$

and

$$\left(-2, \frac{4\pi}{3}, 2\right). \qquad r < 0 \text{ and } \theta \text{ in Quadrant III}$$

Cylindrical coordinates are especially convenient for representing cylindrical surfaces and surfaces of revolution with the z-axis as the axis of symmetry, as shown in Figure 11.69.



Cylinder | Paraboloid | Cone | Hyperboloid

Figure 11.69

Vertical planes containing the z-axis and horizontal planes also have simple cylindrical coordinate equations, as shown in Figure 11.70.



Figure 11.70

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



Figure 11.71

EXAMPLE 3 Rectangular-to-Cylindrical Conversion

Find an equation in cylindrical coordinates for the surface represented by each rectangular equation.

a. $x^2 + y^2 = 4z^2$

b. $y^2 = x$

Solution

a. From Section 11.6, you know that the graph of

$$x^2 + y^2 = 4z^2$$

is an elliptic cone with its axis along the z-axis, as shown in Figure 11.71. When you replace $x^2 + y^2$ with r^2, the equation in cylindrical coordinates is

$$x^2 + y^2 = 4z^2 \qquad \text{Rectangular equation}$$
$$r^2 = 4z^2. \qquad \text{Cylindrical equation}$$

b. The graph of the surface

$$y^2 = x$$

is a parabolic cylinder with rulings parallel to the z-axis, as shown in Figure 11.72. To obtain the equation in cylindrical coordinates, replace y^2 with $r^2 \sin^2 \theta$ and x with $r \cos \theta$, as shown.

$$y^2 = x \qquad \text{Rectangular equation}$$
$$r^2 \sin^2 \theta = r \cos \theta \qquad \text{Substitute } r \sin \theta \text{ for } y \text{ and } r \cos \theta \text{ for } x.$$
$$r(r \sin^2 \theta - \cos \theta) = 0 \qquad \text{Collect terms and factor.}$$
$$r \sin^2 \theta - \cos \theta = 0 \qquad \text{Divide each side by } r.$$
$$r = \frac{\cos \theta}{\sin^2 \theta} \qquad \text{Solve for } r.$$
$$r = \csc \theta \cot \theta \qquad \text{Cylindrical equation}$$

Note that this equation includes a point for which $r = 0$, so nothing was lost by dividing each side by the factor r. ■



Figure 11.72

Converting from cylindrical coordinates to rectangular coordinates is less straightforward than converting from rectangular coordinates to cylindrical coordinates, as demonstrated in Example 4.

EXAMPLE 4 Cylindrical-to-Rectangular Conversion

Find an equation in rectangular coordinates for the surface represented by the cylindrical equation

$$r^2 \cos 2\theta + z^2 + 1 = 0.$$

Solution

$$r^2 \cos 2\theta + z^2 + 1 = 0 \qquad \text{Cylindrical equation}$$
$$r^2(\cos^2 \theta - \sin^2 \theta) + z^2 + 1 = 0 \qquad \text{Trigonometric identity}$$
$$r^2 \cos^2 \theta - r^2 \sin^2 \theta + z^2 = -1$$
$$x^2 - y^2 + z^2 = -1 \qquad \text{Replace } r \cos \theta \text{ with } x \text{ and } r \sin \theta \text{ with } y.$$
$$y^2 - x^2 - z^2 = 1 \qquad \text{Rectangular equation}$$

This is a hyperboloid of two sheets whose axis lies along the y-axis, as shown in Figure 11.73. ■



Figure 11.73

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Spherical Coordinates



Figure 11.74

In the **spherical coordinate system,** each point is represented by an ordered triple: the first coordinate is a distance, and the second and third coordinates are angles. This system is similar to the latitude-longitude system used to identify points on the surface of Earth. For example, the point on the surface of Earth whose latitude is 40° North (of the equator) and whose longitude is 80° West (of the prime meridian) is shown in Figure 11.74. Assuming that Earth is spherical and has a radius of 4000 miles, you would label this point as

$$(4000, -80°, 50°).$$

Radius; 80° clockwise from prime meridian; 50° down from North Pole

The Spherical Coordinate System

In a **spherical coordinate system,** a point P in space is represented by an ordered triple (ρ, θ, ϕ), where ρ is the lowercase Greek letter rho and ϕ is the lowercase Greek letter phi.

1. ρ is the distance between P and the origin, $\rho \geq 0$.
2. θ is the same angle used in cylindrical coordinates for $r \geq 0$.
3. ϕ is the angle *between* the positive z-axis and the line segment $\overrightarrow{OP}$, $0 \leq \phi \leq \pi$.

Note that the first and third coordinates, ρ and ϕ, are nonnegative.



Spherical coordinates

Figure 11.75

The relationship between rectangular and spherical coordinates is illustrated in Figure 11.75. To convert from one system to the other, use the conversion guidelines listed below.

Spherical to rectangular:

$$x = \rho \sin\phi \cos\theta, \quad y = \rho \sin\phi \sin\theta, \quad z = \rho \cos\phi$$

Rectangular to spherical:

$$\rho^2 = x^2 + y^2 + z^2, \quad \tan\theta = \frac{y}{x}, \quad \phi = \arccos \frac{z}{\sqrt{x^2 + y^2 + z^2}}$$

To change coordinates between the cylindrical and spherical systems, use the conversion guidelines listed below.

Spherical to cylindrical **($r \geq 0$):**

$$r^2 = \rho^2 \sin^2\phi, \quad \theta = \theta, \quad z = \rho \cos\phi$$

Cylindrical to spherical **($r \geq 0$):**

$$\rho = \sqrt{r^2 + z^2}, \quad \theta = \theta, \quad \phi = \arccos \frac{z}{\sqrt{r^2 + z^2}}$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The spherical coordinate system is useful primarily for surfaces in space that have a *point* or *center* of symmetry. For example, Figure 11.76 shows three surfaces with simple spherical equations.



Figure 11.76

EXAMPLE 5 Rectangular-to-Spherical Conversion

See LarsonCalculus.com for an interactive version of this type of example.

Find an equation in spherical coordinates for the surface represented by each rectangular equation.

a. Cone: $x^2 + y^2 = z^2$ **b.** Sphere: $x^2 + y^2 + z^2 - 4z = 0$

Solution

a. Use the spherical-to-rectangular equations

$$x = \rho \sin\phi \cos\theta, \quad y = \rho \sin\phi \sin\theta, \quad \text{and} \quad z = \rho \cos\phi$$

and substitute in the rectangular equation as shown.

$$\begin{aligned} x^2 + y^2 &= z^2 \\ \rho^2 \sin^2\phi \cos^2\theta + \rho^2 \sin^2\phi \sin^2\theta &= \rho^2 \cos^2\phi \\ \rho^2 \sin^2\phi(\cos^2\theta + \sin^2\theta) &= \rho^2 \cos^2\phi \\ \rho^2 \sin^2\phi &= \rho^2 \cos^2\phi \\ \frac{\sin^2\phi}{\cos^2\phi} &= 1 \qquad \rho \geq 0 \\ \tan^2\phi &= 1 \\ \tan\phi &= \pm 1 \end{aligned}$$

So, you can conclude that

$$\phi = \frac{\pi}{4} \quad \text{or} \quad \phi = \frac{3\pi}{4}.$$

The equation $\phi = \pi/4$ represents the *upper* half-cone, and the equation $\phi = 3\pi/4$ represents the *lower* half-cone.

b. Because $\rho^2 = x^2 + y^2 + z^2$ and $z = \rho\cos\phi$, the rectangular equation has the following spherical form.

$$\rho^2 - 4\rho\cos\phi = 0 \quad \Rightarrow \quad \rho(\rho - 4\cos\phi) = 0$$

Temporarily discarding the possibility that $\rho = 0$, you have the spherical equation

$$\rho - 4\cos\phi = 0 \quad \text{or} \quad \rho = 4\cos\phi.$$

Note that the solution set for this equation includes a point for which $\rho = 0$, so nothing is lost by discarding the factor ρ. The sphere represented by the equation $\rho = 4\cos\phi$ is shown in Figure 11.77.

Rectangular: $x^2 + y^2 + z^2 - 4z = 0$

Spherical: $\rho = 4\cos\phi$



Figure 11.77

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

11.7 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe the cylindrical coordinate system in your own words.
2. Describe the position of the point $(2, 0°, 30°)$ given in spherical coordinates.

Cylindrical-to-Rectangular Conversion **In Exercises 3–8, convert the point from cylindrical coordinates to rectangular coordinates.**

3. $(-7, 0, 5)$
4. $(2, -\pi, -4)$
5. $\left(3, \frac{\pi}{4}, 1\right)$
6. $\left(6, -\frac{3\pi}{2}, 2\right)$
7. $\left(4, \frac{7\pi}{6}, -3\right)$
8. $\left(-\frac{2}{3}, \frac{4\pi}{3}, 8\right)$

Rectangular-to-Cylindrical Conversion **In Exercises 9–14, convert the point from rectangular coordinates to cylindrical coordinates.**

9. $(0, 5, 1)$
10. $\left(6, 2\sqrt{3}, -1\right)$
11. $(2, -2, -4)$
12. $(3, -3, 7)$
13. $\left(1, \sqrt{3}, 4\right)$
14. $\left(2\sqrt{3}, -2, 6\right)$

Rectangular-to-Cylindrical Conversion **In Exercises 15–22, find an equation in cylindrical coordinates for the surface represented by the rectangular equation.**

15. $z = 4$
16. $x = 9$
17. $x^2 + y^2 - 2z^2 = 5$
18. $z = x^2 + y^2 - 11$
19. $y = x^2$
20. $x^2 + y^2 = 8x$
21. $y^2 = 10 - z^2$
22. $x^2 + y^2 + z^2 - 3z = 0$

Cylindrical-to-Rectangular Conversion **In Exercises 23–30, find an equation in rectangular coordinates for the surface represented by the cylindrical equation, and sketch its graph.**

23. $r = 3$
24. $z = -2$
25. $\theta = \frac{\pi}{6}$
26. $r = \frac{1}{2}z$
27. $r^2 + z^2 = 5$
28. $z = r^2 \cos^2 \theta$
29. $r = 4 \sin \theta$
30. $r = 2 \cos \theta$

Rectangular-to-Spherical Conversion **In Exercises 31–36, convert the point from rectangular coordinates to spherical coordinates.**

31. $(4, 0, 0)$
32. $(-4, 0, 0)$
33. $\left(-2, 2\sqrt{3}, 4\right)$
34. $\left(-5, -5, \sqrt{2}\right)$
35. $\left(\sqrt{3}, 1, 2\sqrt{3}\right)$
36. $(-1, 2, 1)$

Spherical-to-Rectangular Conversion **In Exercises 37–42, convert the point from spherical coordinates to rectangular coordinates.**

37. $\left(4, \frac{\pi}{6}, \frac{\pi}{4}\right)$
38. $\left(6, \pi, \frac{\pi}{2}\right)$
39. $\left(12, -\frac{\pi}{4}, 0\right)$
40. $\left(9, \frac{\pi}{4}, \pi\right)$
41. $\left(5, \frac{\pi}{4}, \frac{\pi}{12}\right)$
42. $\left(7, \frac{3\pi}{4}, \frac{\pi}{9}\right)$

Rectangular-to-Spherical Conversion **In Exercises 43–50, find an equation in spherical coordinates for the surface represented by the rectangular equation.**

43. $y = 2$
44. $z = 6$
45. $x^2 + y^2 + z^2 = 49$
46. $x^2 + y^2 - 3z^2 = 0$
47. $x^2 + y^2 = 16$
48. $x = 13$
49. $x^2 + y^2 = 2z^2$
50. $x^2 + y^2 + z^2 - 9z = 0$

Spherical-to-Rectangular Conversion **In Exercises 51–58, find an equation in rectangular coordinates for the surface represented by the spherical equation, and sketch its graph.**

51. $\rho = 1$
52. $\theta = \frac{3\pi}{4}$
53. $\phi = \frac{\pi}{6}$
54. $\phi = \frac{\pi}{2}$
55. $\rho = 4 \cos \phi$
56. $\rho = 2 \sec \phi$
57. $\rho = \csc \phi$
58. $\rho = 4 \csc \phi \sec \theta$

Cylindrical-to-Spherical Conversion **In Exercises 59–64, convert the point from cylindrical coordinates to spherical coordinates.**

59. $\left(4, \frac{\pi}{4}, 0\right)$
60. $\left(3, -\frac{\pi}{4}, 0\right)$
61. $\left(6, \frac{\pi}{2}, -6\right)$
62. $\left(-4, \frac{\pi}{3}, 4\right)$
63. $(12, \pi, 5)$
64. $\left(4, \frac{\pi}{2}, 3\right)$

Spherical-to-Cylindrical Conversion **In Exercises 65–70, convert the point from spherical coordinates to cylindrical coordinates.**

65. $\left(10, \frac{\pi}{6}, \frac{\pi}{2}\right)$
66. $\left(4, \frac{\pi}{18}, \frac{\pi}{2}\right)$
67. $\left(6, -\frac{\pi}{6}, \frac{\pi}{3}\right)$
68. $\left(5, -\frac{5\pi}{6}, \pi\right)$
69. $\left(8, \frac{7\pi}{6}, \frac{\pi}{6}\right)$
70. $\left(7, \frac{\pi}{4}, \frac{3\pi}{4}\right)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Matching **In Exercises 71–76, match the equation (written in terms of cylindrical or spherical coordinates) with its graph. [The graphs are labeled (a), (b), (c), (d), (e), and (f).]**

(a)



(b)



(c)



(d)



(e)



(f)



71. $r = 5$

72. $\theta = \dfrac{\pi}{4}$

73. $\rho = 5$

74. $\phi = \dfrac{\pi}{4}$

75. $r^2 = z$

76. $\rho = 4 \sec \phi$

77. Spherical Coordinates Explain why in spherical coordinates the graph of $\theta = c$ is a half-plane and not an entire plane.

78. HOW DO YOU SEE IT? Identify the surface graphed and match the graph with its rectangular equation. Then find an equation in cylindrical coordinates for the equation given in rectangular coordinates.

(a)



(b)



(i) $x^2 + y^2 = \frac{4}{9}z^2$

(ii) $x^2 + y^2 - z^2 = 2$

Converting a Rectangular Equation **In Exercises 79–86, convert the rectangular equation to an equation in (a) cylindrical coordinates and (b) spherical coordinates.**

79. $x^2 + y^2 + z^2 = 27$

80. $4(x^2 + y^2) = z^2$

81. $x^2 + y^2 + z^2 - 2z = 0$

82. $x^2 + y^2 = z$

83. $x^2 + y^2 = 4y$

84. $x^2 + y^2 = 45$

85. $x^2 - y^2 = 9$

86. $y = 4$

Sketching a Solid **In Exercises 87–90, sketch the solid that has the given description in cylindrical coordinates.**

87. $0 \le \theta \le \pi/2, 0 \le r \le 2, 0 \le z \le 4$

88. $-\pi/2 \le \theta \le \pi/2, 0 \le r \le 3, 0 \le z \le r \cos\theta$

89. $0 \le \theta \le 2\pi, 0 \le r \le a, r \le z \le a$

90. $0 \le \theta \le 2\pi, 2 \le r \le 4, z^2 \le -r^2 + 6r - 8$

Sketching a Solid **In Exercises 91–94, sketch the solid that has the given description in spherical coordinates.**

91. $0 \le \theta \le 2\pi, 0 \le \phi \le \pi/6, 0 \le \rho \le a \sec\phi$

92. $0 \le \theta \le 2\pi, \pi/4 \le \phi \le \pi/2, 0 \le \rho \le 1$

93. $0 \le \theta \le \pi/2, 0 \le \phi \le \pi/2, 0 \le \rho \le 2$

94. $0 \le \theta \le \pi, 0 \le \phi \le \pi/2, 1 \le \rho \le 3$

Exploring Concepts

In Exercises 95–100, find inequalities that describe the solid and state the coordinate system used. Position the solid on the coordinate system such that the inequalities are as simple as possible.

95. A cube with each edge 10 centimeters long

96. A cylindrical shell 8 meters long with an inside diameter of 0.75 meter and an outside diameter of 1.25 meters

97. A spherical shell with inside and outside radii of 4 inches and 6 inches, respectively

98. The solid that remains after a hole 1 inch in diameter is drilled through the center of a sphere 6 inches in diameter

99. The solid inside both $x^2 + y^2 + z^2 = 9$ and $\left(x - \frac{3}{2}\right)^2 + y^2 = \frac{9}{4}$

100. The solid between the spheres $x^2 + y^2 + z^2 = 4$ and $x^2 + y^2 + z^2 = 9$, and inside the cone $z^2 = x^2 + y^2$

True or False? **In Exercises 101 and 102, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

101. The cylindrical coordinates of a point (x, y, z) are unique.

102. The spherical coordinates of a point (x, y, z) are unique.

103. Intersection of Surfaces Identify the curve of intersection of the surfaces (in cylindrical coordinates) $z = \sin\theta$ and $r = 1$.

104. Intersection of Surfaces Identify the curve of intersection of the surfaces (in spherical coordinates) $\rho = 2 \sec\phi$ and $\rho = 4$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Review Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Exploring Concepts

This chapter showed you the importance of vectors in mathematics. You first learned that vector operations, such as the dot product and the cross product, are used to find many different quantities. For instance, you can find

- the angle between two vectors,
- the resultant force required to move an ocean liner,
- and the torque on a crankshaft.

You then used vectors to define lines and planes in space. The parametric equations for a line require a direction vector and a point on the line. The standard equation of a plane requires a point on the plane and a normal (perpendicular) vector to the plane. You also studied some of the basic surfaces that you will use in upcoming chapters, and two new coordinate systems: cylindrical coordinates and spherical coordinates.

1. Describe the difference between the point (x, y, z) and the vector $\langle x, y, z \rangle$.

2. The initial and terminal points of vector $\mathbf{v}$ are $(3, -4)$ and $(9, 1)$, respectively.

(a) Write $\mathbf{v}$ in component form.

(b) Write $\mathbf{v}$ as the linear combination of the standard unit vectors $\mathbf{i}$ and $\mathbf{j}$.

(c) Sketch $\mathbf{v}$ with its initial point at the origin.

(d) Find the magnitude of $\mathbf{v}$.

3. Describe how to do each of the following.

(a) Find the angle between two vectors.

(b) Find a vector perpendicular to a plane.

(c) Determine whether three points lie in the same plane.

(d) Find the distance between two parallel planes.

4. Determine whether each expression is defined for nonzero vectors $\mathbf{u}$, $\mathbf{v}$, and $\mathbf{w}$. Explain your reasoning.

(a) $\mathbf{u} \cdot (\mathbf{v} + \mathbf{w})$ (b) $(\mathbf{u} \cdot \mathbf{v})\mathbf{w}$

(c) $\mathbf{u} \cdot \mathbf{v} + \mathbf{w}$ (d) $\|\mathbf{u}\| \cdot (\mathbf{v} + \mathbf{w})$

5. For each figure, determine mentally the projection of $\mathbf{u}$ onto $\mathbf{v}$. (The coordinates of the terminal points of the vectors in standard position are given.) Verify your results analytically.

(a)



(b)



6. Consider the points

$A(1, 1, 1)$, $B(-2, 3, 1)$, and $C(-1, 0, 2)$.

(a) Which point lies closest to the xz-plane?

(b) What is the distance between A and B?

(c) What is the midpoint between B and C?

(d) Find an equation of all points that are equidistant from A and B. Describe this set of points.

Writing Vectors in Different Forms

In Exercises 7 and 8, let $\mathbf{u} = \overrightarrow{PQ}$ and $\mathbf{v} = \overrightarrow{PR}$ and (a) write $\mathbf{u}$ and $\mathbf{v}$ in component form, (b) write $\mathbf{u}$ and $\mathbf{v}$ as the linear combination of the standard unit vectors $\mathbf{i}$ and $\mathbf{j}$, (c) find the magnitudes of $\mathbf{u}$ and $\mathbf{v}$, and (d) find $-3\mathbf{u} + \mathbf{v}$.

7. $P = (1, 2)$, $Q = (4, 1)$, $R = (5, 4)$

8. $P = (-2, -1)$, $Q = (5, -1)$, $R = (2, 4)$

Finding a Vector

In Exercises 9 and 10, find the component form of $\mathbf{v}$ given its magnitude and the angle it makes with the positive x-axis.

9. $\|\mathbf{v}\| = 8$, $\theta = 60°$ **10.** $\|\mathbf{v}\| = \frac{1}{2}$, $\theta = 225°$

11. Finding Coordinates of a Point Find the coordinates of the point located in the xy-plane, four units to the right of the xz-plane, and five units behind the yz-plane.

12. Using the Three-Dimensional Coordinate System Determine the location of a point (x, y, z) that satisfies the condition $y = 3$.

Finding the Distance Between Two Points in Space

In Exercises 13 and 14, find the distance between the points.

13. $(1, 6, 3)$, $(-2, 3, 5)$

14. $(-2, 1, -5)$, $(4, -1, -1)$

Finding the Equation of a Sphere

In Exercises 15 and 16, find the standard equation of the sphere with the given characteristics.

15. Center: $(3, -2, 6)$; Radius: 4

16. Endpoints of a diameter: $(0, 0, 4)$, $(4, 6, 0)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding the Equation of a Sphere **In Exercises 17 and 18, complete the square to write the equation of the sphere in standard form. Find the center and radius.**

17. $x^2 + y^2 + z^2 - 4x - 6y + 4 = 0$

18. $x^2 + y^2 + z^2 - 10x + 6y - 4z + 34 = 0$

Writing a Vector in Different Forms **In Exercises 19 and 20, the initial and terminal points of a vector v are given. (a) Sketch the directed line segment. (b) Find the component form of the vector. (c) Write the vector using standard unit vector notation. (d) Sketch the vector with its initial point at the origin.**

19. Initial point: $(2, -1, 3)$
Terminal point: $(4, 4, -7)$

20. Initial point: $(6, 2, 0)$
Terminal point: $(3, -3, 8)$

Finding a Vector **In Exercises 21 and 22, find the vector z, given that $\mathbf{u} = \langle 5, -2, 3\rangle$, $\mathbf{v} = \langle 0, 2, 1\rangle$, and $\mathbf{w} = \langle -6, -6, 2\rangle$.**

21. $\mathbf{z} = -\mathbf{u} + 3\mathbf{v} + \frac{1}{2}\mathbf{w}$

22. $\mathbf{u} - \mathbf{v} + \mathbf{w} - 2\mathbf{z} = \mathbf{0}$

Using Vectors to Determine Collinear Points **In Exercises 23 and 24, use vectors to determine whether the points are collinear.**

23. $(3, 4, -1)$, $(-1, 6, 9)$, $(5, 3, -6)$

24. $(5, -4, 7)$, $(8, -5, 5)$, $(11, 6, 3)$

25. Finding a Unit Vector Find a unit vector in the direction of $\mathbf{u} = \langle 2, 3, 5\rangle$.

26. Finding a Vector Find the vector $\mathbf{v}$ of magnitude 8 in the direction $\langle 6, -3, 2\rangle$.

Finding Dot Products **In Exercises 27 and 28, let $\mathbf{u} = \overrightarrow{PQ}$ and $\mathbf{v} = \overrightarrow{PR}$, and find (a) the component forms of u and v, (b) $\mathbf{u} \cdot \mathbf{v}$, and (c) $\mathbf{v} \cdot \mathbf{v}$.**

27. $P = (5, 0, 0)$, $Q = (4, 4, 0)$, $R = (2, 0, 6)$

28. $P = (2, -1, 3)$, $Q = (0, 5, 1)$, $R = (5, 5, 0)$

Finding the Angle Between Two Vectors **In Exercises 29 and 30, find the angle θ between the vectors (a) in radians and (b) in degrees.**

29. $\mathbf{u} = 5[\cos(3\pi/4)\mathbf{i} + \sin(3\pi/4)\mathbf{j}]$
$\mathbf{v} = 2[\cos(2\pi/3)\mathbf{i} + \sin(2\pi/3)\mathbf{j}]$

30. $\mathbf{u} = \langle 1, 0, -3\rangle$, $\mathbf{v} = \langle 2, -2, 1\rangle$

Comparing Vectors **In Exercises 31 and 32, determine whether u and v are orthogonal, parallel, or neither.**

31. $\mathbf{u} = \langle 7, -2, 3\rangle$
$\mathbf{v} = \langle -1, 4, 5\rangle$

32. $\mathbf{u} = \langle -3, 0, 9\rangle$
$\mathbf{v} = \langle 1, 0, -3\rangle$

Finding the Projection of u onto v **In Exercises 33 and 34, (a) find the projection of u onto v, and (b) find the vector component of u orthogonal to v.**

33. $\mathbf{u} = 4\mathbf{i} + 2\mathbf{j}$, $\mathbf{v} = 3\mathbf{i} + 4\mathbf{j}$

34. $\mathbf{u} = \langle 1, -1, 1\rangle$, $\mathbf{v} = \langle 2, 0, 2\rangle$

35. Orthogonal Vectors Find two vectors in opposite directions that are orthogonal to the vector $\mathbf{u} = \langle 5, 6, -3\rangle$.

36. Work An object is pulled 8 feet across a floor using a force of 75 pounds. The direction of the force is 30° above the horizontal. Find the work done.

Finding Cross Products **In Exercises 37 and 38, find (a) $\mathbf{u} \times \mathbf{v}$, (b) $\mathbf{v} \times \mathbf{u}$, and (c) $\mathbf{v} \times \mathbf{v}$.**

37. $\mathbf{u} = 4\mathbf{i} + 3\mathbf{j} + 6\mathbf{k}$
$\mathbf{v} = 5\mathbf{i} + 2\mathbf{j} + \mathbf{k}$

38. $\mathbf{u} = \langle 0, 2, 1\rangle$
$\mathbf{v} = \langle 1, -3, 4\rangle$

39. Finding a Unit Vector Find a unit vector that is orthogonal to both $\mathbf{u} = \langle 2, -10, 8\rangle$ and $\mathbf{v} = \langle 4, 6, -8\rangle$.

40. Area Find the area of the parallelogram that has the vectors $\mathbf{u} = \langle 3, -1, 5\rangle$ and $\mathbf{v} = \langle 2, -4, 1\rangle$ as adjacent sides.

41. Torque A vertical force of 40 pounds acts on a wrench, as shown in the figure. Find the torque at P.



42. Volume Use the triple scalar product to find the volume of the parallelepiped having adjacent edges $\mathbf{u} = 2\mathbf{i} + \mathbf{j}$, $\mathbf{v} = 2\mathbf{j} + \mathbf{k}$, and $\mathbf{w} = -\mathbf{j} + 2\mathbf{k}$.

Finding Parametric and Symmetric Equations **In Exercises 43 and 44, find sets of (a) parametric equations and (b) symmetric equations of the line that passes through the two points. (For each line, write the direction numbers as integers.)**

43. $(3, 0, 2)$, $(9, 11, 6)$

44. $(-1, 4, 3)$, $(8, 10, 5)$

Finding Parametric Equations **In Exercises 45 and 46, find a set of parametric equations of the line with the given characteristics.**

45. The line passes through the point $(-6, -8, 2)$ and is perpendicular to the xz-plane.

46. The line passes through the point $(1, 2, 3)$ and is parallel to the line given by $x = y = z$.

Finding an Equation of a Plane **In Exercises 47–50, find an equation of the plane with the given characteristics.**

47. The plane passes through $(-3, -4, 2)$, $(-3, 4, 1)$, and $(1, 1, -2)$.

48. The plane passes through the point $(-2, 3, 1)$ and is perpendicular to $\mathbf{n} = 3\mathbf{i} - \mathbf{j} + \mathbf{k}$.

49. The plane contains the lines given by

$$\frac{x-1}{-2} = y = z + 1 \quad \text{and} \quad \frac{x+1}{-2} = y - 1 = z - 2.$$

50. The plane passes through the points $(5, 1, 3)$ and $(2, -2, 1)$ and is perpendicular to the plane $2x + y - z = 4$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

51. Distance Find the distance between the point $(1, 0, 2)$ and the plane $2x - 3y + 6z = 6$.

52. Distance Find the distance between the point $(3, -2, 4)$ and the plane $2x - 5y + z = 10$.

53. Distance Find the distance between the planes $5x - 3y + z = 2$ and $5x - 3y + z = -3$.

54. Distance Find the distance between the point $(-5, 1, 3)$ and the line given by $x = 1 + t$, $y = 3 - 2t$, and $z = 5 - t$.

Sketching a Surface in Space **In Exercises 55–64, describe and sketch the surface.**

55. $x + 2y + 3z = 6$

56. $y = z^2$

57. $y = \frac{1}{2}z$

58. $y = \cos z$

59. $\frac{x^2}{16} + \frac{y^2}{9} + z^2 = 1$

60. $16x^2 + 16y^2 - 9z^2 = 0$

61. $\frac{x^2}{16} - \frac{y^2}{9} + z^2 = -1$

62. $\frac{x^2}{25} + \frac{y^2}{4} - \frac{z^2}{100} = 1$

63. $x^2 + z^2 = 4$

64. $y^2 + z^2 = 16$

65. Surface of Revolution Find an equation for the surface of revolution formed by revolving the curve $z^2 = 2y$ in the yz-plane about the y-axis.

66. Surface of Revolution Find an equation for the surface of revolution formed by revolving the curve $2x + 3z = 1$ in the xz-plane about the x-axis.

Cylindrical-to-Rectangular Conversion **In Exercises 67 and 68, convert the point from cylindrical coordinates to rectangular coordinates.**

67. $(5, \pi, 1)$

68. $\left(-2, \frac{\pi}{3}, 3\right)$

Cylindrical-to-Rectangular Conversion **In Exercises 69 and 70, find an equation in rectangular coordinates for the surface represented by the cylindrical equation, and sketch its graph.**

69. $z = r^2 \sin^2\theta + 3r\cos\theta$

70. $r = -5z$

Converting Rectangular Coordinates **In Exercises 71 and 72, convert the point from rectangular coordinates to (a) cylindrical coordinates and (b) spherical coordinates.**

71. $\left(-\sqrt{3}, 3, -5\right)$

72. $(8, 8, 1)$

Spherical-to-Rectangular Conversion **In Exercises 73 and 74, convert the point from spherical coordinates to rectangular coordinates.**

73. $\left(4, \pi, \frac{\pi}{4}\right)$

74. $\left(8, -\frac{\pi}{6}, \frac{\pi}{3}\right)$

Spherical-to-Rectangular Conversion **In Exercises 75 and 76, find an equation in rectangular coordinates for the surface represented by the spherical equation, and sketch its graph.**

75. $\phi = \frac{\pi}{4}$

76. $\rho = 9\sec\theta$

Converting a Rectangular Equation **In Exercises 77 and 78, convert the rectangular equation to an equation in (a) cylindrical coordinates and (b) spherical coordinates.**

77. $x^2 - y^2 = 2z$

78. $x^2 + y^2 + z^2 = 16$

Building on Concepts

In Exercises 79–82, use the following information. Los Angeles is located at 34.05° North latitude and 118.24° West longitude, and Rio de Janeiro, Brazil, is located at 22.90° South latitude and 43.23° West longitude (see figure). Assume that Earth is spherical and has a radius of 4000 miles.



79. Find the spherical coordinates for the location of each city.

80. Find the rectangular coordinates for the location of each city.

81. Find the angle (in radians) between the vectors from the center of Earth to the two cities.

82. Find the great-circle distance s between the cities. (*Hint:* $s = r\theta$)

83. Consider the points

$$Q(2, 0, 0), \quad P_1(0, 0, 1), \quad \text{and} \quad P_2(0, 1, 2).$$

(a) Find the shortest distance between Q and the line determined by the points P_1 and P_2.

(b) Find the shortest distance between Q and the line segment joining the points P_1 and P_2.

84. Consider the vectors

$$\mathbf{u} = \langle \cos\alpha, \sin\alpha, 0\rangle \quad \text{and} \quad \mathbf{v} = \langle \cos\beta, \sin\beta, 0\rangle$$

where $\alpha > \beta$. Find the cross product of the vectors and use the result to prove the identity

$$\sin(\alpha - \beta) = \sin\alpha\cos\beta - \cos\alpha\sin\beta.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.S. Problem Solving

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

1. Proof Using vectors, prove the Law of Sines: If **a**, **b**, and **c** are the three sides of the triangle shown in the figure, then

$$\frac{\sin A}{\|\mathbf{a}\|} = \frac{\sin B}{\|\mathbf{b}\|} = \frac{\sin C}{\|\mathbf{c}\|}.$$



2. Using an Equation Consider the function

$$f(x) = \int_0^x \sqrt{t^4 + 1}\, dt.$$

(a) Use a graphing utility to graph the function on the interval $-2 \le x \le 2$.

(b) Find a unit vector parallel to the graph of f at the point $(0, 0)$.

(c) Find a unit vector perpendicular to the graph of f at the point $(0, 0)$.

(d) Find the parametric equations of the tangent line to the graph of f at the point $(0, 0)$.

3. Proof Using vectors, prove that the line segments joining the midpoints of the sides of a parallelogram form a parallelogram (see figure).



4. Proof Using vectors, prove that the diagonals of a rhombus are perpendicular (see figure).



5. Sketching Graphs Sketch the graph of each equation given in spherical coordinates.

(a) $\rho = 2 \sin \phi$ (b) $\rho = 2 \cos \phi$

6. Orthogonal Vectors Let P_0 be a point in the plane with normal vector **n**. Describe the set of points P in the plane for which $\left(\mathbf{n} + \overrightarrow{PP_0}\right)$ is orthogonal to $\left(\mathbf{n} - \overrightarrow{PP_0}\right)$.

7. Volume

(a) Find the volume of the solid bounded below by the paraboloid

$$z = x^2 + y^2$$

and above by the plane $z = 1$.

(b) Find the volume of the solid bounded below by the elliptic paraboloid

$$z = \frac{x^2}{a^2} + \frac{y^2}{b^2}$$

and above by the plane $z = k$, where $k > 0$.

(c) Show that the volume of the solid in part (b) is equal to one-half the product of the area of the base times the altitude, as shown in the figure.



8. Distance Between a Point and a Plane Consider the plane that passes through the points P, R, and S. Show that the distance from a point Q to this plane is

$$\text{Distance} = \frac{|\mathbf{u} \cdot (\mathbf{v} \times \mathbf{w})|}{\|\mathbf{u} \times \mathbf{v}\|}$$

where $\mathbf{u} = \overrightarrow{PR}$, $\mathbf{v} = \overrightarrow{PS}$, and $\mathbf{w} = \overrightarrow{PQ}$.

9. Proof Prove the following property of the cross product.

$$(\mathbf{u} \times \mathbf{v}) \times (\mathbf{w} \times \mathbf{z}) = [(\mathbf{u} \times \mathbf{v}) \cdot \mathbf{z}]\mathbf{w} - [(\mathbf{u} \times \mathbf{v}) \cdot \mathbf{w}]\mathbf{z}$$

10. Using Parametric Equations Consider the line given by the parametric equations

$$x = -t + 3, \quad y = \tfrac{1}{2}t + 1, \quad z = 2t - 1$$

and the point $(4, 3, s)$ for any real number s.

(a) Write the distance between the point and the line as a function of s.

(b) Use a graphing utility to graph the function in part (a). Use the graph to find the value of s such that the distance between the point and the line is minimum.

(c) Use the *zoom* feature of a graphing utility to zoom out several times on the graph in part (b). Does it appear that the graph has slant asymptotes? Explain. If it appears to have slant asymptotes, find them.

11. Intersection of Planes Show that the curve of intersection of the plane $z = 2y$ and the cylinder $x^2 + y^2 = 1$ is an ellipse.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

12 Vector-Valued Functions

GO DIGITAL

12.1 Vector-Valued Functions
12.2 Differentiation and Integration of Vector-Valued Functions
12.3 Velocity and Acceleration
12.4 Tangent Vectors and Normal Vectors
12.5 Arc Length and Curvature

CalcView®

CalcChat®



Air Traffic Control *(Exercise 61, p. 854)*

Speed *(Exercise 66, p. 865)*

left, mr. teerapon buekhom/Shutterstock.com; right, Bannafarsai_Stock/Shutterstock.com
This material is protected by Copyright and written permission should be obtained from the publisher prior to any prohibited reproduction, storage in a retrieval system, or transmission in any form or by any means, electronic, mechanical, photocopying, recording, or likewise. For product information and technology assistance, contact us at Cengage Customer & Sales Support, 1-800-354-9706 or support.cengage.com. For permission to use material from this text or product, submit all requests online at www.cengage.com/permissions. Further permissions questions can be emailed to permissionrequest@cengage.com. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322
Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

12.1 Vector-Valued Functions

GO DIGITAL

- **Analyze and sketch a space curve given by a vector-valued function.**
- **Extend the concepts of limits and continuity to vector-valued functions.**

Big Ideas of Calculus

This chapter combines the ideas of vectors and functions to introduce vector-valued functions. Interestingly, the domains of vector-valued functions are real numbers, but the ranges are vectors! When vector-valued functions change, the change can occur in both magnitude and direction. A key application of these functions is representing the motions of objects in the plane or in space. Using the first and second derivatives of an object's position vector, you can find the object's velocity and acceleration.

Space Curves and Vector-Valued Functions

In Section 10.2, a *plane curve* was defined as the set of ordered pairs $(f(t), g(t))$ together with their defining parametric equations $x = f(t)$ and $y = g(t)$, where f and g are continuous functions of t on an interval I. This definition can be extended naturally to three-dimensional space. A **space curve** C is the set of all ordered triples $(f(t), g(t), h(t))$ together with their defining parametric equations

$$x = f(t), \quad y = g(t), \quad \text{and} \quad z = h(t)$$

where f, g, and h are continuous functions of t on an interval I.

Before looking at examples of space curves, a new type of function, called a **vector-valued function,** is introduced. This type of function maps real numbers to vectors.

Definition of Vector-Valued Function

A function of the form

$$\mathbf{r}(t) = f(t)\mathbf{i} + g(t)\mathbf{j} \qquad \text{Plane}$$

or

$$\mathbf{r}(t) = f(t)\mathbf{i} + g(t)\mathbf{j} + h(t)\mathbf{k} \qquad \text{Space}$$

is a **vector-valued function,** where the **component functions** f, g, and h are real-valued functions of the parameter t. Vector-valued functions are sometimes denoted as

$$\mathbf{r}(t) = \langle f(t), g(t) \rangle \qquad \text{Plane}$$

or

$$\mathbf{r}(t) = \langle f(t), g(t), h(t) \rangle. \qquad \text{Space}$$





Curve C is traced out by the terminal point of position vector $\mathbf{r}(t)$.
Figure 12.1

Technically, a curve in a plane or in space consists of a collection of points and the defining parametric equations. Two different curves can have the same graph. For instance, each of the curves

$$\mathbf{r}(t) = \sin t\,\mathbf{i} + \cos t\,\mathbf{j} \quad \text{and} \quad \mathbf{r}(t) = \sin t^2\mathbf{i} + \cos t^2\mathbf{j}$$

has the unit circle as its graph, but these equations do not represent the same curve—because the circle is traced out in different ways on the graphs.

Be sure you understand the distinction between the vector-valued function $\mathbf{r}$ and the real-valued functions f, g, and h. All are functions of the real variable t, but $\mathbf{r}(t)$ is a vector, whereas $f(t)$, $g(t)$, and $h(t)$ are real numbers (for each specific value of t). Real-valued functions are sometimes called **scalar functions** to distinguish them from vector-valued functions.

Vector-valued functions serve dual roles in the representation of curves. By letting the parameter t represent time, you can use a vector-valued function to represent *motion* along a curve. Or, in the more general case, you can use a vector-valued function to *trace the graph* of a curve. In either case, the terminal point of the position vector $\mathbf{r}(t)$ coincides with the point (x, y) or (x, y, z) on the curve given by the parametric equations, as shown in Figure 12.1. The arrowhead on the curve indicates the curve's *orientation* by pointing in the direction of increasing values of t.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Unless stated otherwise, the **domain** of a vector-valued function $\mathbf{r}$ is considered to be the intersection of the domains of the component functions f, g, and h. For instance, the domain of $\mathbf{r}(t) = \ln t\,\mathbf{i} + \sqrt{1-t}\,\mathbf{j} + t\,\mathbf{k}$ is the interval $(0, 1]$.



The ellipse is traced clockwise as t increases from 0 to 2π.
Figure 12.2

EXAMPLE 1 Sketching a Plane Curve

Sketch the plane curve represented by the vector-valued function

$$\mathbf{r}(t) = 2\cos t\,\mathbf{i} - 3\sin t\,\mathbf{j}, \quad 0 \le t \le 2\pi.$$ Vector-valued function

Solution From the position vector $\mathbf{r}(t)$, you can write the parametric equations

$$x = 2\cos t \quad \text{and} \quad y = -3\sin t.$$ Parametric equations

Solving for $\cos t$ and $\sin t$ and using the identity $\cos^2 t + \sin^2 t = 1$, you get the rectangular equation

$$\frac{x^2}{2^2} + \frac{y^2}{3^2} = 1.$$ Rectangular equation

The graph of this rectangular equation is the ellipse shown in Figure 12.2. The curve has a *clockwise* orientation. That is, as t increases from 0 to 2π, the position vector $\mathbf{r}(t)$ moves clockwise, and its terminal point traces the ellipse.

EXAMPLE 2 Sketching a Space Curve

See LarsonCalculus.com for an interactive version of this type of example.

Sketch the space curve represented by the vector-valued function

$$\mathbf{r}(t) = 4\cos t\,\mathbf{i} + 4\sin t\,\mathbf{j} + t\,\mathbf{k}, \quad 0 \le t \le 4\pi.$$ Vector-valued function

Solution From the first two parametric equations

$$x = 4\cos t \quad \text{and} \quad y = 4\sin t$$

you can obtain

$$x^2 + y^2 = 16.$$ Rectangular equation

This means that the curve lies on a right circular cylinder of radius 4, centered about the z-axis. To locate the curve on this cylinder, you can use the third parametric equation

$$z = t.$$

In Figure 12.3, note that as t increases from 0 to 4π, the point (x, y, z) spirals up the cylinder to produce a **helix.** A real-life example of a helix is shown in the drawing at the left.

In 1953, Francis Crick and James D. Watson discovered the double helix structure of DNA.



As t increases from 0 to 4π, two spirals on the helix are traced out.
Figure 12.3

In Examples 1 and 2, you were given a vector-valued function and were asked to sketch the corresponding curve. The next two examples address the reverse problem—finding a vector-valued function to represent a given graph. Of course, when the graph is described parametrically, representation by a vector-valued function is straightforward. For instance, to represent the line in space given by $x = 2 + t$, $y = 3t$, and $z = 4 - t$, you can simply use the vector-valued function

$$\mathbf{r}(t) = (2 + t)\mathbf{i} + 3t\,\mathbf{j} + (4 - t)\mathbf{k}.$$

When a set of parametric equations for the graph is not given, the problem of representing the graph by a vector-valued function boils down to finding a set of parametric equations.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



There are many ways to parametrize this graph. One way is to let $x = t$.
Figure 12.4

GO DIGITAL

EXAMPLE 3 Representing a Graph: Vector-Valued Function

Represent the parabola

$$y = x^2 + 1$$ Rectangular equation

by a vector-valued function.

Solution Although there are many ways to choose the parameter t, a natural choice is to let $x = t$. Then $y = t^2 + 1$ and you have

$$\mathbf{r}(t) = t\mathbf{i} + (t^2 + 1)\mathbf{j}.$$ Vector-valued function

Note in Figure 12.4 the orientation produced by this particular choice of parameter. Had you chosen $x = -t$ as the parameter, the curve would have been oriented in the opposite direction.

EXAMPLE 4 Representing a Graph: Vector-Valued Function

Sketch the space curve C represented by the intersection of the semiellipsoid

$$\frac{x^2}{12} + \frac{y^2}{24} + \frac{z^2}{4} = 1, \quad z \geq 0$$ Rectangular equation

and the parabolic cylinder $y = x^2$. Then find a vector-valued function to represent the graph.

Solution The intersection of the two surfaces is shown in Figure 12.5. As in Example 3, a natural choice of parameter is $x = t$. For this choice, you can use the given equation $y = x^2$ to obtain $y = t^2$. Then it follows that

$$\frac{z^2}{4} = 1 - \frac{x^2}{12} - \frac{y^2}{24} = 1 - \frac{t^2}{12} - \frac{t^4}{24} = \frac{24 - 2t^2 - t^4}{24} = \frac{(6 + t^2)(4 - t^2)}{24}.$$

Because the curve lies above the xy-plane, you should choose the positive square root for z and obtain the parametric equations

$$x = t, \quad y = t^2, \quad \text{and} \quad z = \sqrt{\frac{(6 + t^2)(4 - t^2)}{6}}.$$ Parametric equations

The resulting vector-valued function is

$$\mathbf{r}(t) = t\mathbf{i} + t^2\mathbf{j} + \sqrt{\frac{(6 + t^2)(4 - t^2)}{6}}\mathbf{k}, \quad -2 \leq t \leq 2.$$ Vector-valued function

(Note that the $\mathbf{k}$-component of $\mathbf{r}(t)$ implies $-2 \leq t \leq 2$.) From the points $(-2, 4, 0)$ and $(2, 4, 0)$ shown in Figure 12.5, notice that the curve is traced as t increases from -2 to 2.



The curve C is the intersection of the semiellipsoid and the parabolic cylinder.
Figure 12.5

REMARK Curves in space can be specified in various ways. For instance, the curve in Example 4 is described as the intersection of two surfaces in space.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Limits and Continuity

Many techniques and definitions used in the calculus of real-valued functions can be applied to vector-valued functions. For instance, you can add and subtract vector-valued functions, multiply a vector-valued function by a scalar, take the limit of a vector-valued function, differentiate a vector-valued function, and so on. The basic approach is to capitalize on the linearity of vector operations by extending the definitions on a component-by-component basis. For example, to add two vector-valued functions (in the plane), you can write

$$\begin{aligned}\mathbf{r}_1(t) + \mathbf{r}_2(t) &= [f_1(t)\mathbf{i} + g_1(t)\mathbf{j}] + [f_2(t)\mathbf{i} + g_2(t)\mathbf{j}] \\ &= [f_1(t) + f_2(t)]\mathbf{i} + [g_1(t) + g_2(t)]\mathbf{j}.\end{aligned}$$ Sum

To subtract two vector-valued functions, you can write

$$\begin{aligned}\mathbf{r}_1(t) - \mathbf{r}_2(t) &= [f_1(t)\mathbf{i} + g_1(t)\mathbf{j}] - [f_2(t)\mathbf{i} + g_2(t)\mathbf{j}] \\ &= [f_1(t) - f_2(t)]\mathbf{i} + [g_1(t) - g_2(t)]\mathbf{j}.\end{aligned}$$ Difference

Similarly, to multiply a vector-valued function by a scalar, you can write

$$\begin{aligned}c\mathbf{r}(t) &= c[f_1(t)\mathbf{i} + g_1(t)\mathbf{j}] \\ &= cf_1(t)\mathbf{i} + cg_1(t)\mathbf{j}.\end{aligned}$$ Scalar multiplication

To divide a vector-valued function by a scalar, you can write

$$\begin{aligned}\frac{\mathbf{r}(t)}{c} &= \frac{[f_1(t)\mathbf{i} + g_1(t)\mathbf{j}]}{c}, \quad c \neq 0 \\ &= \frac{f_1(t)}{c}\mathbf{i} + \frac{g_1(t)}{c}\mathbf{j}.\end{aligned}$$ Scalar division

This component-by-component extension of operations with real-valued functions to vector-valued functions is further illustrated in the definition of the limit of a vector-valued function.

Definition of the Limit of a Vector-Valued Function

1. If $\mathbf{r}$ is a vector-valued function such that $\mathbf{r}(t) = f(t)\mathbf{i} + g(t)\mathbf{j}$, then

$$\lim_{t\to a} \mathbf{r}(t) = \left[\lim_{t\to a} f(t)\right]\mathbf{i} + \left[\lim_{t\to a} g(t)\right]\mathbf{j}$$ Plane

provided f and g have limits as $t \to a$.

2. If $\mathbf{r}$ is a vector-valued function such that $\mathbf{r}(t) = f(t)\mathbf{i} + g(t)\mathbf{j} + h(t)\mathbf{k}$, then

$$\lim_{t\to a} \mathbf{r}(t) = \left[\lim_{t\to a} f(t)\right]\mathbf{i} + \left[\lim_{t\to a} g(t)\right]\mathbf{j} + \left[\lim_{t\to a} h(t)\right]\mathbf{k}$$ Space

provided f, g, and h have limits as $t \to a$.



As t approaches a, $\mathbf{r}(t)$ approaches the limit $\mathbf{L}$. For the limit $\mathbf{L}$ to exist, it is not necessary that $\mathbf{r}(a)$ be defined or that $\mathbf{r}(a)$ be equal to $\mathbf{L}$.

Figure 12.6

If $\mathbf{r}(t)$ approaches the vector $\mathbf{L}$ as $t \to a$, then the length of the vector $\mathbf{r}(t) - \mathbf{L}$ approaches 0. That is,

$$\|\mathbf{r}(t) - \mathbf{L}\| \to 0 \quad \text{as} \quad t \to a.$$

This is illustrated graphically in Figure 12.6. With this definition of the limit of a vector-valued function, you can develop vector versions of most of the limit theorems given in Chapter 1. For example, the limit of the sum of two vector-valued functions is the sum of their individual limits. Also, you can use the orientation of the curve $\mathbf{r}(t)$ to define one-sided limits of vector-valued functions. The next definition extends the notion of continuity to vector-valued functions.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Definition of Continuity of a Vector-Valued Function

A vector-valued function $\mathbf{r}$ is **continuous at the point** given by $t = a$ when the limit of $\mathbf{r}(t)$ exists as $t \to a$ and

$$\lim_{t \to a} \mathbf{r}(t) = \mathbf{r}(a).$$

A vector-valued function $\mathbf{r}$ is **continuous on an interval** I when it is continuous at every point in the interval.

From this definition, it follows that a vector-valued function is continuous at $t = a$ if and only if each of its component functions is continuous at $t = a$.



For each value of a, the curve represented by the vector-valued function $\mathbf{r}(t) = t\mathbf{i} + a\mathbf{j} + (a^2 - t^2)\mathbf{k}$ is a parabola.

Figure 12.7

EXAMPLE 5 Continuity of a Vector-Valued Function

Discuss the continuity of the vector-valued function

$$\mathbf{r}(t) = t\mathbf{i} + a\mathbf{j} + (a^2 - t^2)\mathbf{k} \qquad a \text{ is a constant.}$$

at $t = 0$.

Solution As t approaches 0, the limit is

$$\begin{aligned}\lim_{t \to 0} \mathbf{r}(t) &= \left[\lim_{t \to 0} t\right]\mathbf{i} + \left[\lim_{t \to 0} a\right]\mathbf{j} + \left[\lim_{t \to 0} (a^2 - t^2)\right]\mathbf{k} \\ &= 0\mathbf{i} + a\mathbf{j} + a^2\mathbf{k} \\ &= a\mathbf{j} + a^2\mathbf{k}.\end{aligned}$$

Because

$$\begin{aligned}\mathbf{r}(0) &= (0)\mathbf{i} + (a)\mathbf{j} + (a^2)\mathbf{k} \\ &= a\mathbf{j} + a^2\mathbf{k}\end{aligned}$$

you can conclude that $\mathbf{r}$ is continuous at $t = 0$. By similar reasoning, you can conclude that the vector-valued function $\mathbf{r}$ is continuous at all real-number values of t. ■

For each value of a, the curve represented by the vector-valued function in Example 5

$$\mathbf{r}(t) = t\mathbf{i} + a\mathbf{j} + (a^2 - t^2)\mathbf{k} \qquad a \text{ is a constant.}$$

is a parabola. You can think of each parabola as the intersection of the vertical plane $y = a$ and the hyperbolic paraboloid

$$y^2 - x^2 = z$$

as shown in Figure 12.7.

EXAMPLE 6 Continuity of a Vector-Valued Function

Determine the interval(s) on which the vector-valued function

$$\mathbf{r}(t) = t\mathbf{i} + \sqrt{t + 1}\,\mathbf{j} + (t^2 + 1)\mathbf{k}$$

is continuous.

Solution The component functions are

$$f(t) = t, \quad g(t) = \sqrt{t + 1}, \quad \text{and} \quad h(t) = (t^2 + 1).$$

Both f and h are continuous for all real-number values of t. The function g, however, is continuous only for $t \geq -1$. So, $\mathbf{r}$ is continuous on the interval $[-1, \infty)$. ■

TECHNOLOGY

Almost any type of three-dimensional sketch is difficult to do without a graphing utility, but sketching curves in space is especially difficult. The problem is trying to create the illusion of three dimensions. Graphing utilities use a variety of techniques to add "three-dimensionality" to graphs of space curves. One way is to show the curve on a surface, as in Figure 12.7.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

12.1 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe how you can use a vector-valued function to represent a curve.
2. Describe what it means for a vector-valued function $\mathbf{r}(t)$ to be continuous at a point.

Finding the Domain In Exercises 3–10, find the domain of the vector-valued function.

3. $\mathbf{r}(t) = \frac{1}{t+1}\mathbf{i} + \frac{t}{2}\mathbf{j} - 3t\mathbf{k}$
4. $\mathbf{r}(t) = \sqrt{4-t^2}\mathbf{i} + t^2\mathbf{j} - 6t\mathbf{k}$
5. $\mathbf{r}(t) = \ln t\,\mathbf{i} - e^t\mathbf{j} - t\mathbf{k}$
6. $\mathbf{r}(t) = \sin t\,\mathbf{i} + 4\cos t\,\mathbf{j} + t\mathbf{k}$
7. $\mathbf{r}(t) = \mathbf{F}(t) + \mathbf{G}(t)$, where
   $\mathbf{F}(t) = \cos t\,\mathbf{i} - \sin t\,\mathbf{j} + \sqrt{t}\,\mathbf{k}, \quad \mathbf{G}(t) = \cos t\,\mathbf{i} + \sin t\,\mathbf{j}$
8. $\mathbf{r}(t) = \mathbf{F}(t) - \mathbf{G}(t)$, where
   $\mathbf{F}(t) = \ln t\,\mathbf{i} + 5t\mathbf{j} - 3t^2\mathbf{k}, \quad \mathbf{G}(t) = \mathbf{i} + 4t\mathbf{j} - 3t^2\mathbf{k}$
9. $\mathbf{r}(t) = \mathbf{F}(t) \times \mathbf{G}(t)$, where
   $\mathbf{F}(t) = \sin t\,\mathbf{i} + \cos t\,\mathbf{j}, \quad \mathbf{G}(t) = \sin t\,\mathbf{j} + \cos t\,\mathbf{k}$
10. $\mathbf{r}(t) = \mathbf{F}(t) \times \mathbf{G}(t)$, where
    $\mathbf{F}(t) = t^3\mathbf{i} - t\mathbf{j} + t\mathbf{k},$
    $\mathbf{G}(t) = \sqrt[3]{t}\,\mathbf{i} + \frac{1}{t+1}\mathbf{j} + (t+2)\mathbf{k}$

Evaluating a Function In Exercises 11 and 12, evaluate the vector-valued function at each given value of t.

11. $\mathbf{r}(t) = \frac{1}{2}t^2\mathbf{i} - (t-1)\mathbf{j}$
    (a) $\mathbf{r}(1)$ (b) $\mathbf{r}(0)$ (c) $\mathbf{r}(s+1)$
    (d) $\mathbf{r}(2+\Delta t) - \mathbf{r}(2)$
12. $\mathbf{r}(t) = \cos t\,\mathbf{i} + 2\sin t\,\mathbf{j}$
    (a) $\mathbf{r}(0)$ (b) $\mathbf{r}(\pi/4)$ (c) $\mathbf{r}(\theta - \pi)$
    (d) $\mathbf{r}(\pi/6 + \Delta t) - \mathbf{r}(\pi/6)$

Writing a Vector-Valued Function In Exercises 13–16, represent the line segment from P to Q by a vector-valued function and by a set of parametric equations.

13. $P(0, 0, 0)$, $Q(5, 2, 2)$
14. $P(0, 2, -1)$, $Q(4, 7, 2)$
15. $P(-3, -6, -1)$, $Q(-1, -9, -8)$
16. $P(1, -6, 8)$, $Q(-3, -2, 5)$

Think About It In Exercises 17 and 18, find $\mathbf{r}(t) \cdot \mathbf{u}(t)$. Determine whether the result is a vector-valued function. Explain.

17. $\mathbf{r}(t) = (3t-1)\mathbf{i} + \frac{1}{4}t^3\mathbf{j} + 4\mathbf{k}, \quad \mathbf{u}(t) = t^2\mathbf{i} - 8\mathbf{j} + t^3\mathbf{k}$
18. $\mathbf{r}(t) = \langle 3\cos t, 2\sin t, t-2\rangle, \quad \mathbf{u}(t) = \langle 4\sin t, -6\cos t, t^2\rangle$

Matching In Exercises 19–22, match the equation with its graph. [The graphs are labeled (a), (b), (c), and (d).]

(a)



(b)



(c)



(d)



19. $\mathbf{r}(t) = t\mathbf{i} + 2t\mathbf{j} + t^2\mathbf{k}, \quad -2 \le t \le 2$
20. $\mathbf{r}(t) = \cos(\pi t)\mathbf{i} + \sin(\pi t)\mathbf{j} + t^2\mathbf{k}, \quad -1 \le t \le 1$
21. $\mathbf{r}(t) = t\mathbf{i} + t^2\mathbf{j} + e^{0.75t}\mathbf{k}, \quad -2 \le t \le 2$
22. $\mathbf{r}(t) = t\mathbf{i} + \ln t\,\mathbf{j} + \frac{2t}{3}\mathbf{k}, \quad 0.1 \le t \le 5$

Sketching a Plane Curve In Exercises 23–30, sketch the plane curve represented by the vector-valued function and give the orientation of the curve.

23. $\mathbf{r}(t) = \frac{t}{4}\mathbf{i} + (t-1)\mathbf{j}$
24. $\mathbf{r}(t) = (5-t)\mathbf{i} + \sqrt{t}\,\mathbf{j}$
25. $\mathbf{r}(t) = t^3\mathbf{i} + t^2\mathbf{j}$
26. $\mathbf{r}(t) = (t^2+t)\mathbf{i} + (t^2-t)\mathbf{j}$
27. $\mathbf{r}(\theta) = \cos\theta\,\mathbf{i} + 3\sin\theta\,\mathbf{j}$
28. $\mathbf{r}(t) = 2\cos t\,\mathbf{i} + 2\sin t\,\mathbf{j}$
29. $\mathbf{r}(\theta) = 3\sec\theta\,\mathbf{i} + 2\tan\theta\,\mathbf{j}$
30. $\mathbf{r}(t) = 2\cos^3 t\,\mathbf{i} + 2\sin^3 t\,\mathbf{j}$

Sketching a Space Curve In Exercises 31–38, sketch the space curve represented by the vector-valued function and give the orientation of the curve.

31. $\mathbf{r}(t) = (-t+1)\mathbf{i} + (4t+2)\mathbf{j} + (2t+3)\mathbf{k}$
32. $\mathbf{r}(t) = t\mathbf{i} + (2t-5)\mathbf{j} + 3t\mathbf{k}$
33. $\mathbf{r}(t) = 2\cos t\,\mathbf{i} + 2\sin t\,\mathbf{j} + t\mathbf{k}$
34. $\mathbf{r}(t) = t\mathbf{i} + 3\cos t\,\mathbf{j} + 3\sin t\,\mathbf{k}$
35. $\mathbf{r}(t) = 2\sin t\,\mathbf{i} + 2\cos t\,\mathbf{j} + e^{-t}\mathbf{k}$
36. $\mathbf{r}(t) = t^2\mathbf{i} + 2t\mathbf{j} + \frac{3}{2}t\mathbf{k}$
37. $\mathbf{r}(t) = \langle t, t^2, \frac{2}{3}t^3\rangle$
38. $\mathbf{r}(t) = \langle \cos t + t\sin t, \sin t - t\cos t, t\rangle$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Identifying a Common Curve **In Exercises 39 and 40, use a graphing utility to graph the vector-valued function and identify the common curve.**

39. $\mathbf{r}(t) = -\frac{1}{2}t^2\mathbf{i} + t\mathbf{j} - \frac{\sqrt{3}}{2}t^2\mathbf{k}$

40. $\mathbf{r}(t) = -\sqrt{2}\sin t\mathbf{i} + 2\cos t\mathbf{j} + \sqrt{2}\sin t\mathbf{k}$

Transformations of Vector-Valued Functions **In Exercises 41 and 42, use a graphing utility to graph the vector-valued function $\mathbf{r}(t)$. For each $\mathbf{u}(t)$, make a conjecture about the transformation (if any) of the graph of $\mathbf{r}(t)$. Use a graphing utility to verify your conjecture.**

41. $\mathbf{r}(t) = 2\cos t\mathbf{i} + 2\sin t\mathbf{j} + \frac{1}{2}t\mathbf{k}$

(a) $\mathbf{u}(t) = 2(\cos t - 1)\mathbf{i} + 2\sin t\mathbf{j} + \frac{1}{2}t\mathbf{k}$

(b) $\mathbf{u}(t) = 2\cos t\mathbf{i} + 2\sin t\mathbf{j} + 2t\mathbf{k}$

(c) $\mathbf{u}(t) = 2\cos(-t)\mathbf{i} + 2\sin(-t)\mathbf{j} + \frac{1}{2}(-t)\mathbf{k}$

(d) $\mathbf{u}(t) = 6\cos t\mathbf{i} + 6\sin t\mathbf{j} + \frac{1}{2}t\mathbf{k}$

42. $\mathbf{r}(t) = t\mathbf{i} + t^2\mathbf{j} + \frac{1}{2}t^3\mathbf{k}$

(a) $\mathbf{u}(t) = (-t)\mathbf{i} + (-t)^2\mathbf{j} + \frac{1}{2}(-t)^3\mathbf{k}$

(b) $\mathbf{u}(t) = t^2\mathbf{i} + t\mathbf{j} + \frac{1}{2}t^3\mathbf{k}$

(c) $\mathbf{u}(t) = t\mathbf{i} + t^2\mathbf{j} + \left(\frac{1}{2}t^3 + 4\right)\mathbf{k}$

(d) $\mathbf{u}(t) = t\mathbf{i} + t^2\mathbf{j} + \frac{1}{8}t^3\mathbf{k}$

Writing a Transformation **In Exercises 43–46, consider the vector-valued function $\mathbf{r}(t) = 3t^2\mathbf{i} + (t-1)\mathbf{j} + t\mathbf{k}$. Write a vector-valued function $\mathbf{u}(t)$ that is the specified transformation of $\mathbf{r}$.**

43. A vertical translation two units upward

44. A horizontal translation one unit in the direction of the positive x-axis

45. The y-value increases by a factor of two

46. The z-value increases by a factor of three

Representing a Graph by a Vector-Valued Function **In Exercises 47–54, represent the plane curve by a vector-valued function. (There are many correct answers.)**

47. $y = x + 5$

48. $2x - 3y + 5 = 0$

49. $y = (x-2)^2$

50. $y = 4 - x^2$

51. $x^2 + y^2 = 25$

52. $(x-2)^2 + y^2 = 4$

53. $\frac{x^2}{16} - \frac{y^2}{4} = 1$

54. $\frac{x^2}{9} + \frac{y^2}{16} = 1$

Representing a Graph by a Vector-Valued Function **In Exercises 55–62, sketch the space curve represented by the intersection of the surfaces. Then represent the curve by a vector-valued function using the given parameter.**

Surfaces	Parameter
55. $z = x^2 + y^2, \quad x + y = 0$	$x = t$
56. $z = x^2 + y^2, \quad z = 4$	$x = 2\cos t$
57. $x^2 + y^2 = 4, \quad z = x^2$	$x = 2\sin t$
58. $4x^2 + 4y^2 + z^2 = 16, \quad x = z^2$	$z = t$
59. $x^2 + y^2 + z^2 = 4, \quad x + z = 2$	$x = 1 + \sin t$
60. $x^2 + y^2 + z^2 = 10, \quad x + y = 4$	$x = 2 + \sin t$
61. $x^2 + z^2 = 4, \quad y^2 + z^2 = 4$	$x = t$ (first octant)
62. $x^2 + y^2 + z^2 = 16, \quad xy = 4$	$x = t$ (first octant)

63. Sketching a Curve Show that the vector-valued function

$\mathbf{r}(t) = t\mathbf{i} + 2t\cos t\mathbf{j} + 2t\sin t\mathbf{k}$

lies on the cone $4x^2 = y^2 + z^2$. Sketch the curve.

64. Sketching a Curve Show that the vector-valued function

$\mathbf{r}(t) = e^{-t}\cos t\mathbf{i} + e^{-t}\sin t\mathbf{j} + e^{-t}\mathbf{k}$

lies on the cone $z^2 = x^2 + y^2$. Sketch the curve.

Finding a Limit **In Exercises 65–70, find the limit (if it exists).**

65. $\lim_{t\to\pi}(t\mathbf{i} + \cos t\mathbf{j} + \sin t\mathbf{k})$

66. $\lim_{t\to 2}\left(3t\mathbf{i} + \frac{2}{t^2-1}\mathbf{j} + \frac{1}{t}\mathbf{k}\right)$

67. $\lim_{t\to 0}\left(t^2\mathbf{i} + 3t\mathbf{j} + \frac{1-\cos t}{t}\mathbf{k}\right)$

68. $\lim_{t\to 1}\left(\sqrt{t}\mathbf{i} + \frac{\ln t}{t^2-1}\mathbf{j} + \frac{1}{t-1}\mathbf{k}\right)$

69. $\lim_{t\to 0}\left(e^t\mathbf{i} + \frac{\sin t}{t}\mathbf{j} + e^{-t}\mathbf{k}\right)$

70. $\lim_{t\to\infty}\left(e^{-t}\mathbf{i} + \frac{1}{t}\mathbf{j} + t^{1/t}\mathbf{k}\right)$

Continuity of a Vector-Valued Function **In Exercises 71–76, determine the interval(s) on which the vector-valued function is continuous.**

71. $\mathbf{r}(t) = \frac{1}{2t+1}\mathbf{i} + \frac{1}{t}\mathbf{j}$

72. $\mathbf{r}(t) = \sqrt{t}\mathbf{i} + \sqrt{t-1}\mathbf{j}$

73. $\mathbf{r}(t) = t\mathbf{i} + \arcsin t\mathbf{j} + (t-1)\mathbf{k}$

74. $\mathbf{r}(t) = 2e^{-t}\mathbf{i} + e^{-t}\mathbf{j} + \ln(t-1)\mathbf{k}$

75. $\mathbf{r}(t) = \langle e^{-t}, t^2, \tan t\rangle$

76. $\mathbf{r}(t) = \langle 8, \sqrt{t}, \sqrt[3]{t}\rangle$

Exploring Concepts

77. Consider first-degree polynomial functions $f(t)$, $g(t)$, and $h(t)$. Determine whether the curve represented by $\mathbf{r}(t) = f(t)\mathbf{i} + g(t)\mathbf{j} + h(t)\mathbf{k}$ is a line. Explain.

78. The curve represented by $\mathbf{r}(t) = f(t)\mathbf{i} + g(t)\mathbf{j} + h(t)\mathbf{k}$ is a line. Are f, g, and h first-degree polynomial functions of t? Explain.

79. Give an example of a vector-valued function that is defined but not continuous at $t = 3$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

80. Comparing Functions Which of the following vector-valued functions represent the same graph?

(a) $\mathbf{r}(t) = (-3\cos t + 1)\mathbf{i} + (5\sin t + 2)\mathbf{j} + 4\mathbf{k}$

(b) $\mathbf{r}(t) = 4\mathbf{i} + (-3\cos t + 1)\mathbf{j} + (5\sin t + 2)\mathbf{k}$

(c) $\mathbf{r}(t) = (3\cos t - 1)\mathbf{i} + (-5\sin t - 2)\mathbf{j} + 4\mathbf{k}$

(d) $\mathbf{r}(t) = (-3\cos 2t + 1)\mathbf{i} + (5\sin 2t + 2)\mathbf{j} + 4\mathbf{k}$

81. Staircase

The outer bottom edge of a staircase is in the shape of a helix of radius 1 meter. The staircase has a height of 4 meters and makes two complete revolutions from top to bottom. Find a vector-valued function for the staircase. Use a graphing utility to graph your function. (There are many correct answers.)

82. HOW DO YOU SEE IT? The four figures below are graphs of the vector-valued function

$$\mathbf{r}(t) = 4\cos t\,\mathbf{i} + 4\sin t\,\mathbf{j} + \frac{t}{4}\mathbf{k}.$$

Match each of the four graphs with the point in space from which the helix is viewed.

(a)



Generated by Mathematica

(b)



Generated by Mathematica

(c)



Generated by Mathematica

(d)



Generated by Mathematica

(i) (0, 0, 20)

(ii) (20, 0, 0)

(iii) (−20, 0, 0)

(iv) (10, 20, 10)

83. Proof Let $\mathbf{r}(t)$ and $\mathbf{u}(t)$ be vector-valued functions whose limits exist as $t \to c$. Prove that

$$\lim_{t\to c}[\mathbf{r}(t) \times \mathbf{u}(t)] = \lim_{t\to c}\mathbf{r}(t) \times \lim_{t\to c}\mathbf{u}(t).$$

84. Proof Let $\mathbf{r}(t)$ and $\mathbf{u}(t)$ be vector-valued functions whose limits exist as $t \to c$. Prove that

$$\lim_{t\to c}[\mathbf{r}(t) \cdot \mathbf{u}(t)] = \lim_{t\to c}\mathbf{r}(t) \cdot \lim_{t\to c}\mathbf{u}(t).$$

85. Proof Prove that if $\mathbf{r}$ is a vector-valued function that is continuous at c, then $\|\mathbf{r}\|$ is continuous at c.

86. Verifying a Converse Verify that the converse of Exercise 85 is not true by finding a vector-valued function $\mathbf{r}$ such that $\|\mathbf{r}\|$ is continuous at c but $\mathbf{r}$ is not continuous at c.

Particle Motion **In Exercises 87 and 88, two particles travel along the space curves $\mathbf{r}(t)$ and $\mathbf{u}(t)$. Do the particles collide? Do their paths intersect?**

87. $\mathbf{r}(t) = t^2\mathbf{i} + (9t - 20)\mathbf{j} + t^2\mathbf{k}$

$\mathbf{u}(t) = (3t + 4)\mathbf{i} + t^2\mathbf{j} + (5t - 4)\mathbf{k}$

88. $\mathbf{r}(t) = t\mathbf{i} + t^2\mathbf{j} + t^3\mathbf{k}$

$\mathbf{u}(t) = (-2t + 3)\mathbf{i} + 8t\mathbf{j} + (12t + 2)\mathbf{k}$

Think About It **In Exercises 89 and 90, two particles travel along the space curves $\mathbf{r}(t)$ and $\mathbf{u}(t)$.**

89. If $\mathbf{r}(t)$ and $\mathbf{u}(t)$ intersect, will the particles collide?

90. If the particles collide, do their paths $\mathbf{r}(t)$ and $\mathbf{u}(t)$ intersect?

SECTION PROJECT

Witch of Agnesi

In Section 3.5, you studied a famous curve called the **Witch of Agnesi.** In this project, you will take a closer look at this function.

Consider a circle of radius a centered on the y-axis at $(0, a)$. Let A be a point on the horizontal line $y = 2a$, let O be the origin, and let B be the point where the segment OA intersects the circle. A point P is on the Witch of Agnesi when P lies on the horizontal line through B and on the vertical line through A.

(a) Show that the point A is traced out by the vector-valued function

$$\mathbf{r}_A(\theta) = 2a\cot\theta\,\mathbf{i} + 2a\mathbf{j}, \quad 0 < \theta < \pi$$

where θ is the angle that OA makes with the positive x-axis.

(b) Show that the point B is traced out by the vector-valued function $\mathbf{r}_B(\theta) = a\sin 2\theta\,\mathbf{i} + a(1 - \cos 2\theta)\mathbf{j}$, $0 < \theta < \pi$.

(c) Combine the results of parts (a) and (b) to find the vector-valued function $\mathbf{r}(\theta)$ for the Witch of Agnesi. Use a graphing utility to graph this curve for $a = 1$.

(d) Describe the limits $\lim_{\theta\to 0^+}\mathbf{r}(\theta)$ and $\lim_{\theta\to\pi^-}\mathbf{r}(\theta)$.

(e) Eliminate the parameter θ and determine the rectangular equation of the Witch of Agnesi. Use a graphing utility to graph this function for $a = 1$ and compare your graph with that obtained in part (c).

Felix Lipov/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

12.2 Differentiation and Integration of Vector-Valued Functions

GO DIGITAL

- **Differentiate a vector-valued function.**
- **Integrate a vector-valued function.**

Differentiation of Vector-Valued Functions

In Sections 12.3–12.5, you will study several important applications involving the calculus of vector-valued functions. In preparation for that study, this section is devoted to the mechanics of differentiation and integration of vector-valued functions.

The definition of the derivative of a vector-valued function parallels the definition for real-valued functions.

Definition of the Derivative of a Vector-Valued Function

The **derivative of a vector-valued function r** is

$$\mathbf{r}'(t) = \lim_{\Delta t \to 0} \frac{\mathbf{r}(t + \Delta t) - \mathbf{r}(t)}{\Delta t}$$

for all t for which the limit exists. If $\mathbf{r}'(t)$ exists, then $\mathbf{r}$ is **differentiable at *t*.** If $\mathbf{r}'(t)$ exists for all t in an open interval I, then $\mathbf{r}$ is **differentiable on the interval *I*.** Differentiability of vector-valued functions can be extended to closed intervals by considering one-sided limits.

REMARK In addition to $\mathbf{r}'(t)$, other notations for the derivative of a vector-valued function are

$$\frac{d}{dt}[\mathbf{r}(t)], \quad \frac{d\mathbf{r}}{dt}, \quad \text{and} \quad D_t[\mathbf{r}(t)].$$

Differentiation of vector-valued functions can be done on a *component-by-component basis*. To understand why this is true, let $\mathbf{r}(t) = f(t)\mathbf{i} + g(t)\mathbf{j}$. Applying the definition of the derivative produces the following.

$$\begin{aligned}
\mathbf{r}'(t) &= \lim_{\Delta t \to 0} \frac{\mathbf{r}(t + \Delta t) - \mathbf{r}(t)}{\Delta t} \\
&= \lim_{\Delta t \to 0} \frac{f(t + \Delta t)\mathbf{i} + g(t + \Delta t)\mathbf{j} - f(t)\mathbf{i} - g(t)\mathbf{j}}{\Delta t} \\
&= \lim_{\Delta t \to 0} \left\{ \left[\frac{f(t + \Delta t) - f(t)}{\Delta t} \right]\mathbf{i} + \left[\frac{g(t + \Delta t) - g(t)}{\Delta t} \right]\mathbf{j} \right\} \\
&= \left\{ \lim_{\Delta t \to 0} \left[\frac{f(t + \Delta t) - f(t)}{\Delta t} \right] \right\}\mathbf{i} + \left\{ \lim_{\Delta t \to 0} \left[\frac{g(t + \Delta t) - g(t)}{\Delta t} \right] \right\}\mathbf{j} \\
&= f'(t)\mathbf{i} + g'(t)\mathbf{j}
\end{aligned}$$



Figure 12.8

This important result is listed in Theorem 12.1. Note that the derivative of the vector-valued function $\mathbf{r}$ is itself a vector-valued function. Figure 12.8 shows that $\mathbf{r}'(t)$ is a vector tangent to the curve given by $\mathbf{r}(t)$ and pointing in the direction of increasing t-values.

THEOREM 12.1 Differentiation of Vector-Valued Functions

1. If $\mathbf{r}(t) = f(t)\mathbf{i} + g(t)\mathbf{j}$, where f and g are differentiable functions of t, then
$$\mathbf{r}'(t) = f'(t)\mathbf{i} + g'(t)\mathbf{j}.$$ Plane
2. If $\mathbf{r}(t) = f(t)\mathbf{i} + g(t)\mathbf{j} + h(t)\mathbf{k}$, where f, g, and h are differentiable functions of t, then
$$\mathbf{r}'(t) = f'(t)\mathbf{i} + g'(t)\mathbf{j} + h'(t)\mathbf{k}.$$ Space

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



Figure 12.9

EXAMPLE 1 Differentiation of a Vector-Valued Function

See LarsonCalculus.com for an interactive version of this type of example.

For the vector-valued function

$$\mathbf{r}(t) = t\mathbf{i} + (t^2 + 2)\mathbf{j}$$

find $\mathbf{r}'(t)$. Then sketch the plane curve represented by $\mathbf{r}(t)$ and the graphs of $\mathbf{r}(1)$ and $\mathbf{r}'(1)$.

Solution Differentiate on a component-by-component basis to obtain

$$\mathbf{r}'(t) = \mathbf{i} + 2t\mathbf{j}. \qquad \text{Derivative}$$

From the position vector $\mathbf{r}(t)$, you can write the parametric equations $x = t$ and $y = t^2 + 2$. The corresponding rectangular equation is $y = x^2 + 2$. When $t = 1$,

$$\mathbf{r}(1) = \mathbf{i} + 3\mathbf{j} \quad \text{and} \quad \mathbf{r}'(1) = \mathbf{i} + 2\mathbf{j}.$$

In Figure 12.9, $\mathbf{r}(1)$ is drawn starting at the origin, and $\mathbf{r}'(1)$ is drawn starting at the terminal point of $\mathbf{r}(1)$. Note that at $(1, 3)$, the vector $\mathbf{r}'(1)$ is tangent to the curve given by $\mathbf{r}(t)$ and is pointing in the direction of increasing t-values. ■

Higher-order derivatives of vector-valued functions are obtained by successive differentiation of each component function.

EXAMPLE 2 Higher-Order Differentiation

For the vector-valued function

$$\mathbf{r}(t) = \cos t\mathbf{i} + \sin t\mathbf{j} + 2t\mathbf{k}$$

find each of the following.

a. $\mathbf{r}'(t)$ **b.** $\mathbf{r}''(t)$

c. $\mathbf{r}'(t) \cdot \mathbf{r}''(t)$ **d.** $\mathbf{r}'(t) \times \mathbf{r}''(t)$

Solution

a. $\mathbf{r}'(t) = -\sin t\mathbf{i} + \cos t\mathbf{j} + 2\mathbf{k}$ First derivative

b. $\mathbf{r}''(t) = -\cos t\mathbf{i} - \sin t\mathbf{j} + 0\mathbf{k}$

$= -\cos t\mathbf{i} - \sin t\mathbf{j}$ Second derivative

c. $\mathbf{r}'(t) \cdot \mathbf{r}''(t) = \sin t \cos t - \sin t \cos t = 0$ Dot product

d. $\mathbf{r}'(t) \times \mathbf{r}''(t) = \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ -\sin t & \cos t & 2 \\ -\cos t & -\sin t & 0 \end{vmatrix}$ Cross product

$$= \begin{vmatrix} \cos t & 2 \\ -\sin t & 0 \end{vmatrix}\mathbf{i} - \begin{vmatrix} -\sin t & 2 \\ -\cos t & 0 \end{vmatrix}\mathbf{j} + \begin{vmatrix} -\sin t & \cos t \\ -\cos t & -\sin t \end{vmatrix}\mathbf{k}$$

$$= 2\sin t\mathbf{i} - 2\cos t\mathbf{j} + \mathbf{k}$$ ■

REMARK In Example 2(c), the dot product of $\mathbf{r}'$ and $\mathbf{r}''$ is 0. What does this result tell you about the angle between $\mathbf{r}'$ and $\mathbf{r}''$ for any value of t?

In Example 2(c), note that the dot product is a real-valued function, not a vector-valued function.

The parametrization of the curve represented by the vector-valued function

$$\mathbf{r}(t) = f(t)\mathbf{i} + g(t)\mathbf{j} + h(t)\mathbf{k}$$

is **smooth on an open interval I** when f', g', and h' are continuous on I and $\mathbf{r}'(t) \neq \mathbf{0}$ for any value of t in the interval I.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



The epicycloid is not smooth at the points where it intersects the axes.
Figure 12.10

EXAMPLE 3 Finding Intervals on Which a Curve Is Smooth

Consider the epicycloid C given by $\mathbf{r}(t) = (5 \cos t - \cos 5t)\mathbf{i} + (5 \sin t - \sin 5t)\mathbf{j}$, where $0 \le t \le 2\pi$. Find the intervals on which the epicycloid is smooth.

Solution The derivative of $\mathbf{r}$ is

$$\mathbf{r}'(t) = (-5 \sin t + 5 \sin 5t)\mathbf{i} + (5 \cos t - 5 \cos 5t)\mathbf{j}.$$

In the interval $[0, 2\pi]$, the only values of t for which $\mathbf{r}'(t) = 0\mathbf{i} + 0\mathbf{j}$ are $t = 0, \pi/2, \pi, 3\pi/2$, and 2π. So, C is smooth on the intervals

$$\left(0, \frac{\pi}{2}\right), \quad \left(\frac{\pi}{2}, \pi\right), \quad \left(\pi, \frac{3\pi}{2}\right), \quad \text{and} \quad \left(\frac{3\pi}{2}, 2\pi\right).$$

See Figure 12.10. ■

In Figure 12.10, note that the curve is not smooth at points at which the curve makes abrupt changes in direction. Such points are called cusps or **nodes.**

Most of the differentiation rules in Chapter 2 have counterparts for vector-valued functions, and several of these are listed in the next theorem. Note that the theorem contains three versions of "product rules." Property 3 gives the derivative of the product of a real-valued function w and a vector-valued function $\mathbf{r}$, Property 4 gives the derivative of the dot product of two vector-valued functions, and Property 5 gives the derivative of the cross product of two vector-valued functions (in space).

REMARK Note that Property 5 applies only to three-dimensional vector-valued functions because the cross product is not defined for two-dimensional vectors.

THEOREM 12.2 Properties of the Derivative

Let $\mathbf{r}$ and $\mathbf{u}$ be differentiable vector-valued functions of t, let w be a differentiable real-valued function of t, and let c be a scalar.

1. $\dfrac{d}{dt}[c\mathbf{r}(t)] = c\mathbf{r}'(t)$
2. $\dfrac{d}{dt}[\mathbf{r}(t) \pm \mathbf{u}(t)] = \mathbf{r}'(t) \pm \mathbf{u}'(t)$
3. $\dfrac{d}{dt}[w(t)\mathbf{r}(t)] = w(t)\mathbf{r}'(t) + w'(t)\mathbf{r}(t)$
4. $\dfrac{d}{dt}[\mathbf{r}(t) \cdot \mathbf{u}(t)] = \mathbf{r}(t) \cdot \mathbf{u}'(t) + \mathbf{r}'(t) \cdot \mathbf{u}(t)$
5. $\dfrac{d}{dt}[\mathbf{r}(t) \times \mathbf{u}(t)] = \mathbf{r}(t) \times \mathbf{u}'(t) + \mathbf{r}'(t) \times \mathbf{u}(t)$
6. $\dfrac{d}{dt}[\mathbf{r}(w(t))] = \mathbf{r}'(w(t))w'(t)$
7. If $\mathbf{r}(t) \cdot \mathbf{r}(t) = c$, then $\mathbf{r}(t) \cdot \mathbf{r}'(t) = 0$.

Proof To prove Property 4, let $\mathbf{r}(t) = f_1(t)\mathbf{i} + g_1(t)\mathbf{j}$ and $\mathbf{u}(t) = f_2(t)\mathbf{i} + g_2(t)\mathbf{j}$, where f_1, f_2, g_1, and g_2 are differentiable functions of t. Then

$$\mathbf{r}(t) \cdot \mathbf{u}(t) = f_1(t)f_2(t) + g_1(t)g_2(t)$$

and it follows that

$$\begin{aligned}\frac{d}{dt}[\mathbf{r}(t) \cdot \mathbf{u}(t)] &= f_1(t)f_2'(t) + f_1'(t)f_2(t) + g_1(t)g_2'(t) + g_1'(t)g_2(t) \\ &= [f_1(t)f_2'(t) + g_1(t)g_2'(t)] + [f_1'(t)f_2(t) + g_1'(t)g_2(t)] \\ &= \mathbf{r}(t) \cdot \mathbf{u}'(t) + \mathbf{r}'(t) \cdot \mathbf{u}(t).\end{aligned}$$

Proofs of the other properties are left as exercises (see Exercises 61–66). ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Exploration

Let $\mathbf{r}(t) = \cos t\mathbf{i} + \sin t\mathbf{j}$. Sketch the graph of $\mathbf{r}(t)$. Explain why the graph is a circle of radius 1 centered at the origin. Calculate $\mathbf{r}(\pi/4)$ and $\mathbf{r}'(\pi/4)$. Position the vector $\mathbf{r}'(\pi/4)$ so that its initial point is at the terminal point of $\mathbf{r}(\pi/4)$. What do you observe? Show that $\mathbf{r}(t) \cdot \mathbf{r}(t)$ is constant and that $\mathbf{r}(t) \cdot \mathbf{r}'(t) = 0$ for all t. How does this example relate to Property 7 of Theorem 12.2?

EXAMPLE 4 Using Properties of the Derivative

For the vector-valued functions

$$\mathbf{r}(t) = \frac{1}{t}\mathbf{i} - \mathbf{j} + \ln t\mathbf{k} \quad \text{and} \quad \mathbf{u}(t) = t^2\mathbf{i} - 2t\mathbf{j} + \mathbf{k}$$

find each derivative.

a. $\dfrac{d}{dt}[\mathbf{r}(t) \cdot \mathbf{u}(t)]$ **b.** $\dfrac{d}{dt}[\mathbf{u}(t) \times \mathbf{u}'(t)]$

Solution

a. Note that the derivatives of $\mathbf{r}$ and $\mathbf{u}$ are

$$\mathbf{r}'(t) = -\frac{1}{t^2}\mathbf{i} + \frac{1}{t}\mathbf{k} \quad \text{and} \quad \mathbf{u}'(t) = 2t\mathbf{i} - 2\mathbf{j}.$$

Using Property 4 of Theorem 12.2, you have

$$\begin{aligned}
&\frac{d}{dt}[\mathbf{r}(t) \cdot \mathbf{u}(t)] \\
&\quad = \mathbf{r}(t) \cdot \mathbf{u}'(t) + \mathbf{r}'(t) \cdot \mathbf{u}(t) \\
&\quad = \left(\frac{1}{t}\mathbf{i} - \mathbf{j} + \ln t\mathbf{k}\right) \cdot (2t\mathbf{i} - 2\mathbf{j}) + \left(-\frac{1}{t^2}\mathbf{i} + \frac{1}{t}\mathbf{k}\right) \cdot (t^2\mathbf{i} - 2t\mathbf{j} + \mathbf{k}) \\
&\quad = 2 + 2 + (-1) + \frac{1}{t} \\
&\quad = 3 + \frac{1}{t}.
\end{aligned}$$

b. Note that the first and second derivatives of $\mathbf{u}$ are

$$\mathbf{u}'(t) = 2t\mathbf{i} - 2\mathbf{j} \quad \text{and} \quad \mathbf{u}''(t) = 2\mathbf{i}.$$

Using Property 5 of Theorem 12.2, you have

$$\begin{aligned}
\frac{d}{dt}[\mathbf{u}(t) \times \mathbf{u}'(t)] &= [\mathbf{u}(t) \times \mathbf{u}''(t)] + [\mathbf{u}'(t) \times \mathbf{u}'(t)] \\
&= \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ t^2 & -2t & 1 \\ 2 & 0 & 0 \end{vmatrix} + \mathbf{0} \\
&= \begin{vmatrix} -2t & 1 \\ 0 & 0 \end{vmatrix}\mathbf{i} - \begin{vmatrix} t^2 & 1 \\ 2 & 0 \end{vmatrix}\mathbf{j} + \begin{vmatrix} t^2 & -2t \\ 2 & 0 \end{vmatrix}\mathbf{k} \\
&= 0\mathbf{i} - (-2)\mathbf{j} + 4t\mathbf{k} \\
&= 2\mathbf{j} + 4t\mathbf{k}.
\end{aligned}$$

Try reworking parts (a) and (b) in Example 4 by first forming the dot and cross products and then differentiating to show that you obtain the same results.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Integration of Vector-Valued Functions

The next definition is a consequence of the definition of the derivative of a vector-valued function.

Definition of Integration of Vector-Valued Functions

1. If $\mathbf{r}(t) = f(t)\mathbf{i} + g(t)\mathbf{j}$, where f and g are continuous on $[a, b]$, then the **indefinite integral (antiderivative)** of $\mathbf{r}$ is

$$\int \mathbf{r}(t)\,dt = \left[\int f(t)\,dt\right]\mathbf{i} + \left[\int g(t)\,dt\right]\mathbf{j}$$ Plane

and its **definite integral** over the interval $a \le t \le b$ is

$$\int_a^b \mathbf{r}(t)\,dt = \left[\int_a^b f(t)\,dt\right]\mathbf{i} + \left[\int_a^b g(t)\,dt\right]\mathbf{j}.$$

2. If $\mathbf{r}(t) = f(t)\mathbf{i} + g(t)\mathbf{j} + h(t)\mathbf{k}$, where f, g, and h are continuous on $[a, b]$, then the **indefinite integral (antiderivative)** of $\mathbf{r}$ is

$$\int \mathbf{r}(t)\,dt = \left[\int f(t)\,dt\right]\mathbf{i} + \left[\int g(t)\,dt\right]\mathbf{j} + \left[\int h(t)\,dt\right]\mathbf{k}$$ Space

and its **definite integral** over the interval $a \le t \le b$ is

$$\int_a^b \mathbf{r}(t)\,dt = \left[\int_a^b f(t)\,dt\right]\mathbf{i} + \left[\int_a^b g(t)\,dt\right]\mathbf{j} + \left[\int_a^b h(t)\,dt\right]\mathbf{k}.$$

The antiderivative of a vector-valued function is a family of vector-valued functions all differing by a constant vector $\mathbf{C}$. For instance, if $\mathbf{r}(t)$ is a three-dimensional vector-valued function, then for the indefinite integral $\int \mathbf{r}(t)\,dt$, you obtain three constants of integration

$$\int f(t)\,dt = F(t) + C_1, \quad \int g(t)\,dt = G(t) + C_2, \quad \int h(t)\,dt = H(t) + C_3$$

where $F'(t) = f(t)$, $G'(t) = g(t)$, and $H'(t) = h(t)$. These three *scalar* constants produce one *vector* constant of integration

$$\begin{aligned}\int \mathbf{r}(t)\,dt &= [F(t) + C_1]\mathbf{i} + [G(t) + C_2]\mathbf{j} + [H(t) + C_3]\mathbf{k} \\ &= [F(t)\mathbf{i} + G(t)\mathbf{j} + H(t)\mathbf{k}] + [C_1\mathbf{i} + C_2\mathbf{j} + C_3\mathbf{k}] \\ &= \mathbf{R}(t) + \mathbf{C}\end{aligned}$$

where $\mathbf{R}'(t) = \mathbf{r}(t)$.

EXAMPLE 5 Integrating a Vector-Valued Function

Find the indefinite integral

$$\int (t\mathbf{i} + 3\mathbf{j})\,dt.$$

Solution Integrating on a component-by-component basis produces

$$\int (t\mathbf{i} + 3\mathbf{j})\,dt = \frac{t^2}{2}\mathbf{i} + 3t\mathbf{j} + \mathbf{C}.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Example 6 shows how to evaluate the definite integral of a vector-valued function.

EXAMPLE 6 Definite Integral of a Vector-Valued Function

Evaluate the integral

$$\int_0^1 \mathbf{r}(t)\,dt = \int_0^1 \left(\sqrt[3]{t}\,\mathbf{i} + \frac{1}{t+1}\mathbf{j} + e^{-t}\mathbf{k}\right) dt.$$

Solution

$$\begin{aligned}\int_0^1 \mathbf{r}(t)\,dt &= \left(\int_0^1 t^{1/3}\,dt\right)\mathbf{i} + \left(\int_0^1 \frac{1}{t+1}\,dt\right)\mathbf{j} + \left(\int_0^1 e^{-t}\,dt\right)\mathbf{k} \\ &= \left[\left(\frac{3}{4}\right)t^{4/3}\right]_0^1\mathbf{i} + \left[\ln|t+1|\right]_0^1\mathbf{j} + \left[-e^{-t}\right]_0^1\mathbf{k} \\ &= \frac{3}{4}\mathbf{i} + (\ln 2)\mathbf{j} + \left(1 - \frac{1}{e}\right)\mathbf{k}\end{aligned}$$

As with real-valued functions, you can narrow the family of antiderivatives of a vector-valued function $\mathbf{r}'$ down to a single antiderivative by imposing an initial condition on the vector-valued function $\mathbf{r}$. This is demonstrated in the next example.

EXAMPLE 7 The Antiderivative of a Vector-Valued Function

Find the antiderivative of

$$\mathbf{r}'(t) = \cos 2t\,\mathbf{i} - 2\sin t\,\mathbf{j} + \frac{1}{1+t^2}\mathbf{k}$$

that satisfies the initial condition

$$\mathbf{r}(0) = 3\mathbf{i} - 2\mathbf{j} + \mathbf{k}.$$

Solution

$$\begin{aligned}\mathbf{r}(t) &= \int \mathbf{r}'(t)\,dt \\ &= \left(\int \cos 2t\,dt\right)\mathbf{i} + \left(\int -2\sin t\,dt\right)\mathbf{j} + \left(\int \frac{1}{1+t^2}\,dt\right)\mathbf{k} \\ &= \left(\frac{1}{2}\sin 2t + C_1\right)\mathbf{i} + (2\cos t + C_2)\mathbf{j} + (\arctan t + C_3)\mathbf{k}\end{aligned}$$

Letting $t = 0$, you can write

$$\mathbf{r}(0) = (0 + C_1)\mathbf{i} + (2 + C_2)\mathbf{j} + (0 + C_3)\mathbf{k}.$$

Using the fact that $\mathbf{r}(0) = 3\mathbf{i} - 2\mathbf{j} + \mathbf{k}$, you have

$$(0 + C_1)\mathbf{i} + (2 + C_2)\mathbf{j} + (0 + C_3)\mathbf{k} = 3\mathbf{i} - 2\mathbf{j} + \mathbf{k}.$$

Equating corresponding components produces

$$C_1 = 3, \quad 2 + C_2 = -2, \quad \text{and} \quad C_3 = 1.$$

So, the antiderivative that satisfies the initial condition is

$$\mathbf{r}(t) = \left(\frac{1}{2}\sin 2t + 3\right)\mathbf{i} + (2\cos t - 4)\mathbf{j} + (\arctan t + 1)\mathbf{k}.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

12.2 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe the relationship between the graph of $\mathbf{r}'(t_0)$ and the curve represented by $\mathbf{r}(t)$.
2. Explain why the family of vector-valued functions that are the antiderivatives of a vector-valued function differ by a constant vector.

Differentiation of Vector-Valued Functions

In Exercises 3–10, find $\mathbf{r}'(t)$, $\mathbf{r}(t_0)$, and $\mathbf{r}'(t_0)$ for the given value of t_0. Then sketch the curve represented by the vector-valued function and sketch the vectors $\mathbf{r}(t_0)$ and $\mathbf{r}'(t_0)$.

3. $\mathbf{r}(t) = (1 - t^2)\mathbf{i} + t\mathbf{j}, \quad t_0 = 3$
4. $\mathbf{r}(t) = (1 + t)\mathbf{i} + t^3\mathbf{j}, \quad t_0 = 1$
5. $\mathbf{r}(t) = \cos t\,\mathbf{i} + \sin t\,\mathbf{j}, \quad t_0 = \dfrac{\pi}{2}$
6. $\mathbf{r}(t) = 3 \sin t\,\mathbf{i} + 4 \cos t\,\mathbf{j}, \quad t_0 = \dfrac{\pi}{2}$
7. $\mathbf{r}(t) = \langle e^t, e^{2t} \rangle, \quad t_0 = 0$
8. $\mathbf{r}(t) = \langle e^{-t}, e^t \rangle, \quad t_0 = 0$
9. $\mathbf{r}(t) = 2 \cos t\,\mathbf{i} + 2 \sin t\,\mathbf{j} + t\mathbf{k}, \quad t_0 = \dfrac{3\pi}{2}$
10. $\mathbf{r}(t) = t\mathbf{i} + t^2\mathbf{j} + \frac{3}{2}\mathbf{k}, \quad t_0 = 2$

Finding a Derivative

In Exercises 11–18, find $\mathbf{r}'(t)$.

11. $\mathbf{r}(t) = t^4\mathbf{i} - 5t\mathbf{j}$
12. $\mathbf{r}(t) = \sqrt{t}\,\mathbf{i} + (1 - t^3)\mathbf{j}$
13. $\mathbf{r}(t) = 3 \cos^3 t\,\mathbf{i} + 2 \sin^3 t\,\mathbf{j} + \mathbf{k}$
14. $\mathbf{r}(t) = 4\sqrt{t}\,\mathbf{i} + t^2\sqrt{t}\,\mathbf{j} + \ln t^2\mathbf{k}$
15. $\mathbf{r}(t) = e^{-t}\mathbf{i} + 4\mathbf{j} + 5te^t\mathbf{k}$
16. $\mathbf{r}(t) = \langle t^3, \cos 3t, \sin 3t \rangle$
17. $\mathbf{r}(t) = \langle t \sin t, t \cos t, t \rangle$
18. $\mathbf{r}(t) = \langle \arcsin t, \arccos t, 0 \rangle$

Higher-Order Differentiation

In Exercises 19–22, find (a) $\mathbf{r}'(t)$, (b) $\mathbf{r}''(t)$, and (c) $\mathbf{r}'(t) \cdot \mathbf{r}''(t)$.

19. $\mathbf{r}(t) = t^3\mathbf{i} + \frac{1}{2}t^2\mathbf{j}$
20. $\mathbf{r}(t) = (t^2 + t)\mathbf{i} + (t^2 - t)\mathbf{j}$
21. $\mathbf{r}(t) = 4 \cos t\,\mathbf{i} + 4 \sin t\,\mathbf{j}$
22. $\mathbf{r}(t) = 8 \cos t\,\mathbf{i} + 3 \sin t\,\mathbf{j}$

Higher-Order Differentiation

In Exercises 23–26, find (a) $\mathbf{r}'(t)$, (b) $\mathbf{r}''(t)$, (c) $\mathbf{r}'(t) \cdot \mathbf{r}''(t)$, and (d) $\mathbf{r}'(t) \times \mathbf{r}''(t)$.

23. $\mathbf{r}(t) = \frac{1}{2}t^2\mathbf{i} - t\mathbf{j} + \frac{1}{6}t^3\mathbf{k}$
24. $\mathbf{r}(t) = t^3\mathbf{i} + (2t^2 + 3)\mathbf{j} + (3t - 5)\mathbf{k}$
25. $\mathbf{r}(t) = \langle \cos t + t \sin t, \sin t - t \cos t, t \rangle$
26. $\mathbf{r}(t) = \langle e^{-t}, t^2, \tan t \rangle$

Finding Intervals on Which a Curve Is Smooth

In Exercises 27–34, find all the open intervals on which the curve given by the vector-valued function is smooth.

27. $\mathbf{r}(t) = t^2\mathbf{i} + t^3\mathbf{j}$
28. $\mathbf{r}(t) = 5t^5\mathbf{i} - t^4\mathbf{j}$
29. $\mathbf{r}(\theta) = 2 \cos^3 \theta\,\mathbf{i} + 3 \sin^3 \theta\,\mathbf{j}, \quad 0 \le \theta \le 2\pi$
30. $\mathbf{r}(\theta) = (\theta + \sin \theta)\mathbf{i} + (1 - \cos \theta)\mathbf{j}, \quad 0 \le \theta \le 2\pi$
31. $\mathbf{r}(t) = \dfrac{2t}{8 + t^3}\mathbf{i} + \dfrac{2t^2}{8 + t^3}\mathbf{j}$
32. $\mathbf{r}(t) = e^t\mathbf{i} - e^{-t}\mathbf{j} + 3t\mathbf{k}$
33. $\mathbf{r}(t) = t\mathbf{i} - 3t\mathbf{j} + \tan t\,\mathbf{k}$
34. $\mathbf{r}(t) = \sqrt{t}\,\mathbf{i} + (t^2 - 1)\mathbf{j} + \frac{1}{4}t\mathbf{k}$

Using Properties of the Derivative

In Exercises 35 and 36, use the properties of the derivative to find the following.

(a) $\mathbf{r}'(t)$ (b) $\dfrac{d}{dt}[3\mathbf{r}(t) - \mathbf{u}(t)]$ (c) $\dfrac{d}{dt}[(5t)\mathbf{u}(t)]$

(d) $\dfrac{d}{dt}[\mathbf{r}(t) \cdot \mathbf{u}(t)]$ (e) $\dfrac{d}{dt}[\mathbf{r}(t) \times \mathbf{u}(t)]$ (f) $\dfrac{d}{dt}[\mathbf{r}(2t)]$

35. $\mathbf{r}(t) = t\mathbf{i} + 3t\mathbf{j} + t^2\mathbf{k}, \quad \mathbf{u}(t) = 4t\mathbf{i} + t^2\mathbf{j} + t^3\mathbf{k}$
36. $\mathbf{r}(t) = \langle t, 2 \sin t, 2 \cos t \rangle, \quad \mathbf{u}(t) = \left\langle \dfrac{1}{t}, 2 \sin t, 2 \cos t \right\rangle$

Using Two Methods

In Exercises 37 and 38, find (a) $\dfrac{d}{dt}[\mathbf{r}(t) \cdot \mathbf{u}(t)]$ and (b) $\dfrac{d}{dt}[\mathbf{r}(t) \times \mathbf{u}(t)]$ in two different ways.

(i) Find the product first, then differentiate.
(ii) Apply the properties of Theorem 12.2.

37. $\mathbf{r}(t) = t\mathbf{i} + 2t^2\mathbf{j} + t^3\mathbf{k}, \quad \mathbf{u}(t) = t^4\mathbf{k}$
38. $\mathbf{r}(t) = \cos t\,\mathbf{i} + \sin t\,\mathbf{j} + t\mathbf{k}, \quad \mathbf{u}(t) = \mathbf{j} + t\mathbf{k}$

Finding an Indefinite Integral

In Exercises 39–46, find the indefinite integral.

39. $\displaystyle\int (2t\mathbf{i} + \mathbf{j} + 9\mathbf{k})\,dt$
40. $\displaystyle\int (4t^3\mathbf{i} + 6t\mathbf{j} - 4\sqrt{t}\,\mathbf{k})\,dt$
41. $\displaystyle\int \left(\frac{1}{t}\mathbf{i} + \mathbf{j} - t^{3/2}\mathbf{k}\right)dt$
42. $\displaystyle\int \left(\ln t\,\mathbf{i} + \frac{1}{t}\mathbf{j} + \mathbf{k}\right)dt$
43. $\displaystyle\int (\mathbf{i} + 4t^3\mathbf{j} + 5^t\mathbf{k})\,dt$
44. $\displaystyle\int \left(\sec^2 t\,\mathbf{i} + \frac{1}{1 + t^2}\mathbf{j}\right)dt$
45. $\displaystyle\int (e^t\mathbf{i} + \mathbf{j} + t \cos t\,\mathbf{k})\,dt$
46. $\displaystyle\int (e^{-t} \sin t\,\mathbf{i} + \cot t\,\mathbf{j})\,dt$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Evaluating a Definite Integral **In Exercises 47–52, evaluate the definite integral.**

47. $\int_0^1 (8t\mathbf{i} + t\mathbf{j} - \mathbf{k})\,dt$

48. $\int_{-1}^1 \left(t\mathbf{i} + t^3\mathbf{j} + \sqrt[3]{t}\,\mathbf{k}\right)dt$

49. $\int_0^{\pi/2} [(5\cos t)\mathbf{i} + (6\sin t)\mathbf{j} + \mathbf{k}]\,dt$

50. $\int_0^{\pi/4} [(\sec t \tan t)\mathbf{i} + (\tan t)\mathbf{j} + (2\sin t\cos t)\mathbf{k}]\,dt$

51. $\int_0^2 (t\mathbf{i} + e^t\mathbf{j} - te^t\mathbf{k})\,dt$

52. $\int_0^3 \|t\mathbf{i} + t^2\mathbf{j}\|\,dt$

Finding an Antiderivative **In Exercises 53–58, find $\mathbf{r}(t)$ that satisfies the initial conditions.**

53. $\mathbf{r}'(t) = 4e^{2t}\mathbf{i} + 3e^t\mathbf{j}, \quad \mathbf{r}(0) = 2\mathbf{i}$

54. $\mathbf{r}'(t) = 3t^2\mathbf{j} + 6\sqrt{t}\,\mathbf{k}, \quad \mathbf{r}(0) = \mathbf{i} + 2\mathbf{j}$

55. $\mathbf{r}''(t) = -32\mathbf{j}, \quad \mathbf{r}'(0) = 600\sqrt{3}\,\mathbf{i} + 600\mathbf{j}, \quad \mathbf{r}(0) = \mathbf{0}$

56. $\mathbf{r}''(t) = -4\cos t\,\mathbf{j} - 3\sin t\,\mathbf{k}, \quad \mathbf{r}'(0) = 3\mathbf{k}, \quad \mathbf{r}(0) = 4\mathbf{j}$

57. $\mathbf{r}'(t) = te^{-t^2}\mathbf{i} - e^{-t}\mathbf{j} + \mathbf{k}, \quad \mathbf{r}(0) = \frac{1}{2}\mathbf{i} - \mathbf{j} + \mathbf{k}$

58. $\mathbf{r}'(t) = \dfrac{1}{1+t^2}\mathbf{i} + \dfrac{1}{t^2}\mathbf{j} + \dfrac{1}{t}\mathbf{k}, \quad \mathbf{r}(1) = 2\mathbf{i}$

Exploring Concepts

59. The three components of the derivative of the vector-valued function $\mathbf{u}$ are positive at $t = t_0$. Describe the behavior of $\mathbf{u}$ at $t = t_0$.

60. Find two vector-valued functions $\mathbf{f}(t)$ and $\mathbf{g}(t)$ such that

$$\int_a^b [\mathbf{f}(t) \cdot \mathbf{g}(t)]\,dt \neq \left[\int_a^b \mathbf{f}(t)\,dt\right] \cdot \left[\int_a^b \mathbf{g}(t)\,dt\right].$$

Proof **In Exercises 61–68, prove the property. In each case, assume r, u, and v are differentiable vector-valued functions of t in space, w is a differentiable real-valued function of t, and c is a scalar.**

61. $\dfrac{d}{dt}[c\mathbf{r}(t)] = c\mathbf{r}'(t)$

62. $\dfrac{d}{dt}[\mathbf{r}(t) \pm \mathbf{u}(t)] = \mathbf{r}'(t) \pm \mathbf{u}'(t)$

63. $\dfrac{d}{dt}[w(t)\mathbf{r}(t)] = w(t)\mathbf{r}'(t) + w'(t)\mathbf{r}(t)$

64. $\dfrac{d}{dt}[\mathbf{r}(t) \times \mathbf{u}(t)] = \mathbf{r}(t) \times \mathbf{u}'(t) + \mathbf{r}'(t) \times \mathbf{u}(t)$

65. $\dfrac{d}{dt}[\mathbf{r}(w(t))] = \mathbf{r}'(w(t))w'(t)$

66. If $\mathbf{r}(t) \cdot \mathbf{r}(t)$ is a constant, then $\mathbf{r}(t) \cdot \mathbf{r}'(t) = 0$.

67. $\dfrac{d}{dt}\{\mathbf{r}(t) \cdot [\mathbf{u}(t) \times \mathbf{v}(t)]\} = \mathbf{r}'(t) \cdot [\mathbf{u}(t) \times \mathbf{v}(t)] + \mathbf{r}(t) \cdot [\mathbf{u}'(t) \times \mathbf{v}(t)] + \mathbf{r}(t) \cdot [\mathbf{u}(t) \times \mathbf{v}'(t)]$

68. $\dfrac{d}{dt}[\mathbf{r}(t) \times \mathbf{r}'(t)] = \mathbf{r}(t) \times \mathbf{r}''(t)$

69. **Particle Motion** A particle moves in the xy-plane along the curve represented by the vector-valued function $\mathbf{r}(t) = (t - \sin t)\mathbf{i} + (1 - \cos t)\mathbf{j}$.

(a) Use a graphing utility to graph $\mathbf{r}$. Describe the curve.

(b) Find the minimum and maximum values of $\|\mathbf{r}'\|$ and $\|\mathbf{r}''\|$.

70. **Particle Motion** A particle moves in the yz-plane along the curve represented by the vector-valued function $\mathbf{r}(t) = (2\cos t)\mathbf{j} + (3\sin t)\mathbf{k}$.

(a) Describe the curve.

(b) Find the minimum and maximum values of $\|\mathbf{r}'\|$ and $\|\mathbf{r}''\|$.

71. **Perpendicular Vectors** Consider the vector-valued function $\mathbf{r}(t) = (e^t \sin t)\mathbf{i} + (e^t \cos t)\mathbf{j}$. Show that $\mathbf{r}(t)$ and $\mathbf{r}''(t)$ are always perpendicular to each other.

72. **HOW DO YOU SEE IT?** The graph shows a vector-valued function $\mathbf{r}(t)$ for $0 \le t \le 2\pi$ and its derivative $\mathbf{r}'(t)$ for several values of t.



(a) For each derivative shown in the graph, determine whether each component is positive or negative.

(b) Is the curve smooth on the interval $(0, 2\pi)$? Explain.

True or False? **In Exercises 73–76, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

73. If a particle moves along a sphere centered at the origin, then its derivative vector is always tangent to the sphere.

74. The definite integral of a vector-valued function is a real number.

75. $\dfrac{d}{dt}[\|\mathbf{r}(t)\|] = \|\mathbf{r}'(t)\|$

76. If $\mathbf{r}$ and $\mathbf{u}$ are differentiable vector-valued functions of t, then

$$\frac{d}{dt}[\mathbf{r}(t) \cdot \mathbf{u}(t)] = \mathbf{r}'(t) \cdot \mathbf{u}'(t).$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

12.3 Velocity and Acceleration

GO DIGITAL

- **Describe the velocity and acceleration associated with a vector-valued function.**
- **Use a vector-valued function to analyze projectile motion.**

Exploration

Exploring Velocity

Consider the circle given by

$\mathbf{r}(t) = (\cos \omega t)\mathbf{i} + (\sin \omega t)\mathbf{j}$.

(The symbol ω is the Greek letter omega.) Use a graphing utility in *parametric* mode to graph this circle for several values of ω. How does ω affect the velocity of the terminal point as it traces out the curve? For a given value of ω, does the speed appear constant? Does the acceleration appear constant? Explain your reasoning.



Velocity and Acceleration

You are now ready to combine your study of parametric equations, curves, vectors, and vector-valued functions to form a model for motion along a curve. You will begin by looking at the motion of an object in the plane. (The motion of an object in space can be developed similarly.)

As an object moves along a curve in the plane, the coordinates x and y of its center of mass are each functions of time t. Rather than using the letters f and g to represent these two functions, it is convenient to write $x = x(t)$ and $y = y(t)$. So, the position vector $\mathbf{r}(t)$ takes the form

$$\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j}. \qquad \text{Position vector}$$

The beauty of this vector model for representing motion is that you can use the first and second derivatives of the vector-valued function $\mathbf{r}$ to find the object's velocity and acceleration. (Recall from Chapter 11 that velocity and acceleration are both vector quantities having magnitude and direction.) To find the velocity and acceleration vectors at a given time t, consider a point $Q(x(t + \Delta t), y(t + \Delta t))$ that is approaching the point $P(x(t), y(t))$ along the curve C given by $\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j}$, as shown in Figure 12.11. As $\Delta t \to 0$, the direction of the vector $\overrightarrow{PQ}$ (denoted by $\Delta\mathbf{r}$) approaches the *direction of motion* at time t.

$$\Delta\mathbf{r} = \mathbf{r}(t + \Delta t) - \mathbf{r}(t)$$

$$\frac{\Delta\mathbf{r}}{\Delta t} = \frac{\mathbf{r}(t + \Delta t) - \mathbf{r}(t)}{\Delta t}$$

$$\lim_{\Delta t \to 0} \frac{\Delta\mathbf{r}}{\Delta t} = \lim_{\Delta t \to 0} \frac{\mathbf{r}(t + \Delta t) - \mathbf{r}(t)}{\Delta t}$$

When this limit exists, it is defined as the **velocity vector** or **tangent vector** to the curve at point P. Note that this is the same limit used to define $\mathbf{r}'(t)$. So, the direction of $\mathbf{r}'(t)$ gives the direction of motion at time t. Moreover, the magnitude of the vector $\mathbf{r}'(t)$

$$\|\mathbf{r}'(t)\| = \|x'(t)\mathbf{i} + y'(t)\mathbf{j}\| = \sqrt{[x'(t)]^2 + [y'(t)]^2}$$

gives the **speed** of the object at time t.



As $\Delta t \to 0$, $\dfrac{\Delta\mathbf{r}}{\Delta t}$ approaches the velocity vector.

Figure 12.11

Similar to how $\mathbf{r}'(t)$ is used to find velocity, you can use $\mathbf{r}''(t)$ to find acceleration, as indicated in the definitions at the top of the next page.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Definitions of Velocity and Acceleration

If x and y are twice-differentiable functions of t, and $\mathbf{r}$ is a vector-valued function given by $\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j}$, then the velocity vector, acceleration vector, and speed at time t are as follows.

$$\begin{aligned}\textbf{Velocity} &= \mathbf{v}(t) = \mathbf{r}'(t) = x'(t)\mathbf{i} + y'(t)\mathbf{j}\\ \textbf{Acceleration} &= \mathbf{a}(t) = \mathbf{r}''(t) = x''(t)\mathbf{i} + y''(t)\mathbf{j}\\ \textbf{Speed} &= \|\mathbf{v}(t)\| = \|\mathbf{r}'(t)\| = \sqrt{[x'(t)]^2 + [y'(t)]^2}\end{aligned}$$

For motion along a space curve, the definitions are similar. That is, for

$$\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j} + z(t)\mathbf{k}$$

you have the following.

$$\begin{aligned}\textbf{Velocity} &= \mathbf{v}(t) = \mathbf{r}'(t) = x'(t)\mathbf{i} + y'(t)\mathbf{j} + z'(t)\mathbf{k}\\ \textbf{Acceleration} &= \mathbf{a}(t) = \mathbf{r}''(t) = x''(t)\mathbf{i} + y''(t)\mathbf{j} + z''(t)\mathbf{k}\\ \textbf{Speed} &= \|\mathbf{v}(t)\| = \|\mathbf{r}'(t)\| = \sqrt{[x'(t)]^2 + [y'(t)]^2 + [z'(t)]^2}\end{aligned}$$

EXAMPLE 1 Velocity and Acceleration Along a Plane Curve

Find the (a) velocity vector, (b) speed, and (c) acceleration vector for the particle that moves along the plane curve C described by

$$\mathbf{r}(t) = 2\sin\frac{t}{2}\mathbf{i} + 2\cos\frac{t}{2}\mathbf{j}.$$ Position vector

Solution

a. $\mathbf{v}(t) = \mathbf{r}'(t) = \cos\frac{t}{2}\mathbf{i} - \sin\frac{t}{2}\mathbf{j}$ Velocity vector

b. $\|\mathbf{r}'(t)\| = \sqrt{\cos^2\frac{t}{2} + \sin^2\frac{t}{2}} = 1$ Speed (at any time)

c. $\mathbf{a}(t) = \mathbf{r}''(t) = -\frac{1}{2}\sin\frac{t}{2}\mathbf{i} - \frac{1}{2}\cos\frac{t}{2}\mathbf{j}$ Acceleration vector ■

REMARK In Example 1, note that the velocity and acceleration vectors are orthogonal at any point in time (see Figure 12.12). This is characteristic of motion at a constant speed. (See Exercise 61.)

The parametric equations for the curve in Example 1 are

$$x = 2\sin\frac{t}{2} \quad \text{and} \quad y = 2\cos\frac{t}{2}.$$

By eliminating the parameter t, you obtain the rectangular equation

$$x^2 + y^2 = 4.$$ Rectangular equation

So, the curve is a circle of radius 2 centered at the origin, as shown in Figure 12.12. Because the velocity vector

$$\mathbf{v}(t) = \cos\frac{t}{2}\mathbf{i} - \sin\frac{t}{2}\mathbf{j}$$

has a constant magnitude but a changing direction as t increases, the particle moves around the circle at a constant speed.



The particle moves around the circle at a constant speed.
Figure 12.12

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



At each point on the curve, the acceleration vector points to the right.
Figure 12.13



At each point in the comet's orbit, the acceleration vector points toward the sun.
Figure 12.14

GO DIGITAL



Figure 12.15

EXAMPLE 2 Velocity and Acceleration Vectors in the Plane

Sketch the path of an object moving along the plane curve given by

$$\mathbf{r}(t) = (t^2 - 4)\mathbf{i} + t\mathbf{j}$$ Position vector

and find the velocity and acceleration vectors when $t = 0$ and $t = 2$.

Solution Using the parametric equations $x = t^2 - 4$ and $y = t$, you can determine that the curve is a parabola given by

$$x = y^2 - 4$$ Rectangular equation

as shown in Figure 12.13. The velocity vector (at any time) is

$$\mathbf{v}(t) = \mathbf{r}'(t) = 2t\mathbf{i} + \mathbf{j}$$ Velocity vector

and the acceleration vector (at any time) is

$$\mathbf{a}(t) = \mathbf{r}''(t) = 2\mathbf{i}.$$ Acceleration vector

When $t = 0$, the velocity and acceleration vectors are

$$\mathbf{v}(0) = 2(0)\mathbf{i} + \mathbf{j} = \mathbf{j} \quad \text{and} \quad \mathbf{a}(0) = 2\mathbf{i}.$$

When $t = 2$, the velocity and acceleration vectors are

$$\mathbf{v}(2) = 2(2)\mathbf{i} + \mathbf{j} = 4\mathbf{i} + \mathbf{j} \quad \text{and} \quad \mathbf{a}(2) = 2\mathbf{i}.$$

For the object moving along the path shown in Figure 12.13, note that the acceleration vector is constant (it has a magnitude of 2 and points to the right). This implies that the speed of the object is decreasing as the object moves toward the vertex of the parabola, and the speed is increasing as the object moves away from the vertex of the parabola.

This type of motion is *not* characteristic of comets that travel on parabolic paths through our solar system. For such comets, the acceleration vector always points to the origin (the sun), which implies that the comet's speed increases as it approaches the vertex of the path and decreases as it moves away from the vertex. (See Figure 12.14.)

EXAMPLE 3 Velocity and Acceleration Vectors in Space

See LarsonCalculus.com for an interactive version of this type of example.

Sketch the path of an object moving along the space curve C given by

$$\mathbf{r}(t) = t\mathbf{i} + t^3\mathbf{j} + 3t\mathbf{k}, \quad t \geq 0$$ Position vector

and find the velocity and acceleration vectors when $t = 1$.

Solution Using the parametric equations $x = t$ and $y = t^3$, you can determine that the path of the object lies on the cubic cylinder given by

$$y = x^3.$$ Rectangular equation

Moreover, because $z = 3t$, the object starts at $(0, 0, 0)$ and moves upward as t increases, as shown in Figure 12.15. Because $\mathbf{r}(t) = t\mathbf{i} + t^3\mathbf{j} + 3t\mathbf{k}$, you have

$$\mathbf{v}(t) = \mathbf{r}'(t) = \mathbf{i} + 3t^2\mathbf{j} + 3\mathbf{k}$$ Velocity vector

and

$$\mathbf{a}(t) = \mathbf{r}''(t) = 6t\mathbf{j}.$$ Acceleration vector

When $t = 1$, the velocity and acceleration vectors are

$$\mathbf{v}(1) = \mathbf{r}'(1) = \mathbf{i} + 3\mathbf{j} + 3\mathbf{k} \quad \text{and} \quad \mathbf{a}(1) = \mathbf{r}''(1) = 6\mathbf{j}.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

So far in this section, you have concentrated on finding the velocity and acceleration by differentiating the position vector. Many practical applications involve the reverse problem—finding the position vector for a given velocity or acceleration. This is demonstrated in the next example.

EXAMPLE 4 Finding a Position Vector by Integration

An object starts from rest at the point $(1, 2, 0)$ and moves with an acceleration of

$$\mathbf{a}(t) = \mathbf{j} + 2\mathbf{k}$$ Acceleration vector

where $\|\mathbf{a}(t)\|$ is measured in feet per second per second. Find the location of the object after $t = 2$ seconds.

Solution From the description of the object's motion, you can deduce the following *initial conditions*. Because the object starts from rest, you have

$$\mathbf{v}(0) = \mathbf{0}.$$

Moreover, because the object starts at the point $(x, y, z) = (1, 2, 0)$, you have

$$\mathbf{r}(0) = x(0)\mathbf{i} + y(0)\mathbf{j} + z(0)\mathbf{k} = 1\mathbf{i} + 2\mathbf{j} + 0\mathbf{k} = \mathbf{i} + 2\mathbf{j}.$$

To find the position vector, you should integrate twice, each time using one of the initial conditions to solve for the constant of integration. The velocity vector is

$$\begin{aligned}\mathbf{v}(t) &= \int \mathbf{a}(t)\,dt \\ &= \int (\mathbf{j} + 2\mathbf{k})\,dt \\ &= t\mathbf{j} + 2t\mathbf{k} + \mathbf{C}\end{aligned}$$

where $\mathbf{C} = C_1\mathbf{i} + C_2\mathbf{j} + C_3\mathbf{k}$. Letting $t = 0$ and applying the initial condition $\mathbf{v}(0) = \mathbf{0}$, you obtain

$$\mathbf{v}(0) = C_1\mathbf{i} + C_2\mathbf{j} + C_3\mathbf{k} = \mathbf{0} \quad \Rightarrow \quad C_1 = C_2 = C_3 = 0.$$

So, the *velocity* at any time t is

$$\mathbf{v}(t) = t\mathbf{j} + 2t\mathbf{k}.$$ Velocity vector

Integrating once more produces

$$\begin{aligned}\mathbf{r}(t) &= \int \mathbf{v}(t)\,dt \\ &= \int (t\mathbf{j} + 2t\mathbf{k})\,dt \\ &= \frac{t^2}{2}\mathbf{j} + t^2\mathbf{k} + \mathbf{C}\end{aligned}$$

where $\mathbf{C} = C_4\mathbf{i} + C_5\mathbf{j} + C_6\mathbf{k}$. Letting $t = 0$ and applying the initial condition $\mathbf{r}(0) = \mathbf{i} + 2\mathbf{j}$, you have

$$\mathbf{r}(0) = C_4\mathbf{i} + C_5\mathbf{j} + C_6\mathbf{k} = \mathbf{i} + 2\mathbf{j} \quad \Rightarrow \quad C_4 = 1, C_5 = 2, C_6 = 0.$$

So, the *position* vector is

$$\mathbf{r}(t) = \mathbf{i} + \left(\frac{t^2}{2} + 2\right)\mathbf{j} + t^2\mathbf{k}.$$ Position vector

The location of the object after $t = 2$ seconds is given by

$$\mathbf{r}(2) = \mathbf{i} + 4\mathbf{j} + 4\mathbf{k}$$

as shown in Figure 12.16.



The object takes 2 seconds to move from point $(1, 2, 0)$ to point $(1, 4, 4)$ along the curve.
Figure 12.16

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 12.17

Projectile Motion

To derive the parametric equations for the path of a projectile, assume that gravity is the only force acting on the projectile after it is launched. So, the motion occurs in a vertical plane, which can be represented by the xy-coordinate system with the origin as a point on Earth's surface, as shown in Figure 12.17. For a projectile of mass m, the force due to gravity is

$$\mathbf{F} = -mg\mathbf{j}$$ Force due to gravity

where the acceleration due to gravity is $g = 32$ feet per second per second, or 9.8 meters per second per second. By **Newton's Second Law of Motion,** this same force produces an acceleration $\mathbf{a} = \mathbf{a}(t)$ and satisfies the equation $\mathbf{F} = m\mathbf{a}$. Consequently, the acceleration of the projectile is given by $m\mathbf{a} = -mg\mathbf{j}$, which implies that

$$\mathbf{a} = -g\mathbf{j}.$$ Acceleration of projectile

EXAMPLE 5 **Derivation of the Position Vector for a Projectile**

A projectile of mass m is launched from an initial position $\mathbf{r}_0$ with an initial velocity $\mathbf{v}_0$. Find its position vector as a function of time.

Solution Begin with the acceleration $\mathbf{a}(t) = -g\mathbf{j}$ and integrate twice.

$$\mathbf{v}(t) = \int \mathbf{a}(t)\,dt = \int -g\mathbf{j}\,dt = -gt\mathbf{j} + \mathbf{C}_1$$

$$\mathbf{r}(t) = \int \mathbf{v}(t)\,dt = \int (-gt\mathbf{j} + \mathbf{C}_1)\,dt = -\frac{1}{2}gt^2\mathbf{j} + \mathbf{C}_1 t + \mathbf{C}_2$$

You can use the initial conditions $\mathbf{v}(0) = \mathbf{v}_0$ and $\mathbf{r}(0) = \mathbf{r}_0$ to solve for the constant vectors $\mathbf{C}_1$ and $\mathbf{C}_2$. Doing this produces

$$\mathbf{C}_1 = \mathbf{v}_0 \quad \text{and} \quad \mathbf{C}_2 = \mathbf{r}_0.$$

So, the position vector is

$$\mathbf{r}(t) = -\frac{1}{2}gt^2\mathbf{j} + t\mathbf{v}_0 + \mathbf{r}_0.$$ Position vector



Figure 12.18

In many projectile problems, the constant vectors $\mathbf{r}_0$ and $\mathbf{v}_0$ are not given explicitly. Often you are given the initial height h, the initial speed v_0, and the angle θ at which the projectile is launched, as shown in Figure 12.18. From the given height, you can deduce that $\mathbf{r}_0 = h\mathbf{j}$. Because the speed gives the magnitude of the initial velocity, it follows that $v_0 = \|\mathbf{v}_0\|$ and you can write

$$\begin{aligned}\mathbf{v}_0 &= x\mathbf{i} + y\mathbf{j} \\ &= (\|\mathbf{v}_0\| \cos\theta)\mathbf{i} + (\|\mathbf{v}_0\| \sin\theta)\mathbf{j} \\ &= v_0 \cos\theta\mathbf{i} + v_0 \sin\theta\mathbf{j}.\end{aligned}$$

So, the position vector can be written in the form

$$\mathbf{r}(t) = -\frac{1}{2}gt^2\mathbf{j} + t\mathbf{v}_0 + \mathbf{r}_0$$ Position vector

$$= -\frac{1}{2}gt^2\mathbf{j} + tv_0 \cos\theta\mathbf{i} + tv_0 \sin\theta\mathbf{j} + h\mathbf{j}$$

$$= (v_0 \cos\theta)t\mathbf{i} + \left[h + (v_0 \sin\theta)t - \frac{1}{2}gt^2\right]\mathbf{j}.$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

THEOREM 12.3 Position Vector for a Projectile

Neglecting air resistance, the path of a projectile launched from an initial height h with initial speed v_0 and angle of elevation θ is described by the vector function

$$\mathbf{r}(t) = (v_0 \cos\theta)t\mathbf{i} + \left[h + (v_0 \sin\theta)t - \tfrac{1}{2}gt^2\right]\mathbf{j}$$

where g is the acceleration due to gravity.

EXAMPLE 6 Describing the Path of a Baseball

A baseball is hit 3 feet above ground level at 100 feet per second and at an angle of 45° with respect to the ground, as shown in Figure 12.19. Find the maximum height reached by the baseball. Will it clear a 10-foot-high fence located 300 feet from home plate?



Figure 12.19

Solution You are given

$$h = 3, \quad v_0 = 100, \quad \text{and} \quad \theta = 45°.$$

So, using Theorem 12.3 with $g = 32$ feet per second per second produces

$$\mathbf{r}(t) = \left(100\cos\frac{\pi}{4}\right)t\mathbf{i} + \left[3 + \left(100\sin\frac{\pi}{4}\right)t - 16t^2\right]\mathbf{j}$$
$$= \left(50\sqrt{2}t\right)\mathbf{i} + \left(3 + 50\sqrt{2}t - 16t^2\right)\mathbf{j}.$$

The velocity vector is

$$\mathbf{v}(t) = \mathbf{r}'(t) = 50\sqrt{2}\mathbf{i} + \left(50\sqrt{2} - 32t\right)\mathbf{j}.$$

The maximum height occurs when

$$y'(t) = 50\sqrt{2} - 32t$$

is equal to 0, which implies that

$$t = \frac{25\sqrt{2}}{16} \approx 2.21 \text{ seconds}.$$

So, the maximum height reached by the ball is

$$y = 3 + 50\sqrt{2}\left(\frac{25\sqrt{2}}{16}\right) - 16\left(\frac{25\sqrt{2}}{16}\right)^2$$
$$= \frac{649}{8}$$
$$\approx 81 \text{ feet.} \qquad \text{Maximum height when } t \approx 2.21 \text{ seconds}$$

The ball is 300 feet from where it was hit when

$$x(t) = 300 \quad \Rightarrow \quad 50\sqrt{2}t = 300.$$

Solving this equation for t produces $t = 3\sqrt{2} \approx 4.24$ seconds. At this time, the height of the ball is

$$y = 3 + 50\sqrt{2}\left(3\sqrt{2}\right) - 16\left(3\sqrt{2}\right)^2$$
$$= 303 - 288$$
$$= 15 \text{ feet.} \qquad \text{Height when } t \approx 4.24 \text{ seconds}$$

Therefore, the ball clears the 10-foot fence for a home run. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

12.3 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. An object moves along a curve in the plane. What information do you gain about the motion of the object from the velocity vector to the curve at time t?
2. For each scenario, describe the direction of the acceleration vectors. Explain your reasoning.
   (a) A comet traveling through our solar system in a parabolic path
   (b) An object thrown on Earth's surface

Finding Velocity and Acceleration Along a Plane Curve

In Exercises 3–12, the position vector r describes the path of an object moving in the xy-plane.

(a) Find the velocity vector, speed, and acceleration vector of the object.

(b) Evaluate the velocity vector and acceleration vector of the object at the given point.

(c) Sketch a graph of the path and sketch the velocity and acceleration vectors at the given point.

	Position Vector	Point
3.	$\mathbf{r}(t) = 3t\mathbf{i} + (t-1)\mathbf{j}$	$(3, 0)$
4.	$\mathbf{r}(t) = (6-t)\mathbf{i} + t\mathbf{j}$	$(3, 3)$
5.	$\mathbf{r}(t) = t^2\mathbf{i} + t^3\mathbf{j}$	$(1, 1)$
6.	$\mathbf{r}(t) = t\mathbf{i} + (-t^2+4)\mathbf{j}$	$(1, 3)$
7.	$\mathbf{r}(t) = t^2\mathbf{i} + t\mathbf{j}$	$(4, 2)$
8.	$\mathbf{r}(t) = (\frac{1}{4}t^3 + 1)\mathbf{i} + t\mathbf{j}$	$(3, 2)$
9.	$\mathbf{r}(t) = 2\cos t\mathbf{i} + 2\sin t\mathbf{j}$	$(\sqrt{2}, \sqrt{2})$
10.	$\mathbf{r}(t) = 3\cos t\mathbf{i} + 2\sin t\mathbf{j}$	$(3, 0)$
11.	$\mathbf{r}(t) = \langle t - \sin t, 1 - \cos t\rangle$	$(\pi, 2)$
12.	$\mathbf{r}(t) = \langle e^{-t}, e^t\rangle$	$(1, 1)$

Finding Velocity and Acceleration Vectors in Space

In Exercises 13–22, the position vector r describes the path of an object moving in space.

(a) Find the velocity vector, speed, and acceleration vector of the object.

(b) Evaluate the velocity vector and acceleration vector of the object at the given value of t.

	Position Vector	Time
13.	$\mathbf{r}(t) = t\mathbf{i} + 5t\mathbf{j} + 3t\mathbf{k}$	$t = 1$
14.	$\mathbf{r}(t) = 4t\mathbf{i} + 4t\mathbf{j} - 2t\mathbf{k}$	$t = 3$
15.	$\mathbf{r}(t) = t\mathbf{i} + t^2\mathbf{j} + \frac{1}{2}t^2\mathbf{k}$	$t = 4$
16.	$\mathbf{r}(t) = 3t\mathbf{i} + t\mathbf{j} + \frac{1}{4}t^2\mathbf{k}$	$t = 2$
17.	$\mathbf{r}(t) = t\mathbf{i} - t\mathbf{j} + \sqrt{9-t^2}\,\mathbf{k}$	$t = 0$
18.	$\mathbf{r}(t) = t^2\mathbf{i} + t\mathbf{j} + 2t^{3/2}\mathbf{k}$	$t = 4$
19.	$\mathbf{r}(t) = \langle 4t, 3\cos t, 3\sin t\rangle$	$t = \pi$
20.	$\mathbf{r}(t) = \langle 2\cos t, \sin 3t, t^2\rangle$	$t = \frac{\pi}{4}$
21.	$\mathbf{r}(t) = \langle e^t\cos t, e^t\sin t, e^t\rangle$	$t = 0$
22.	$\mathbf{r}(t) = \left\langle \ln t, \frac{1}{t^2}, t^4\right\rangle$	$t = \sqrt{3}$

Finding a Position Vector by Integration

In Exercises 23–28, use the given acceleration vector and initial conditions to find the velocity and position vectors. Then find the position at time $t = 2$.

23. $\mathbf{a}(t) = \mathbf{i} + \mathbf{j} + \mathbf{k}, \quad \mathbf{v}(0) = \mathbf{0}, \quad \mathbf{r}(0) = \mathbf{0}$
24. $\mathbf{a}(t) = 2\mathbf{i} + 3\mathbf{k}, \quad \mathbf{v}(0) = 4\mathbf{j}, \quad \mathbf{r}(0) = \mathbf{0}$
25. $\mathbf{a}(t) = t\mathbf{j} + t\mathbf{k}, \quad \mathbf{v}(1) = 5\mathbf{j}, \quad \mathbf{r}(1) = \mathbf{0}$
26. $\mathbf{a}(t) = -32\mathbf{k}, \quad \mathbf{v}(0) = 3\mathbf{i} - 2\mathbf{j} + \mathbf{k}, \quad \mathbf{r}(0) = 5\mathbf{j} + 2\mathbf{k}$
27. $\mathbf{a}(t) = -\cos t\mathbf{i} - \sin t\mathbf{j}, \quad \mathbf{v}(0) = \mathbf{j} + \mathbf{k}, \quad \mathbf{r}(0) = \mathbf{i}$
28. $\mathbf{a}(t) = e^t\mathbf{i} - 8\mathbf{k}, \quad \mathbf{v}(0) = 2\mathbf{i} + 3\mathbf{j} + \mathbf{k}, \quad \mathbf{r}(0) = \mathbf{0}$

Projectile Motion

In Exercises 29–42, use the model for projectile motion, assuming there is no air resistance and $g = 32$ feet per second per second.

29. A baseball is hit from a height of 2.5 feet above the ground with an initial speed of 140 feet per second and at an angle of 22° above the horizontal. Find the maximum height reached by the baseball. Determine whether it will clear a 10-foot-high fence located 375 feet from home plate.
30. Determine the maximum height and range of a projectile fired at a height of 3 feet above the ground with an initial speed of 900 feet per second and at an angle of 45° above the horizontal.
31. A baseball, hit 3 feet above the ground, leaves the bat at an angle of 45° and is caught by an outfielder 3 feet above the ground and 300 feet from home plate. What is the initial speed of the ball, and how high does it rise?
32. A baseball player at second base throws a ball 90 feet to the player at first base. The ball is released at a point 5 feet above the ground with an initial speed of 50 miles per hour and at an angle of 15° above the horizontal. At what height does the player at first base catch the ball?
33. Eliminate the parameter t from the position vector for the motion of a projectile to show that the rectangular equation is

$$y = -\frac{g\sec^2\theta}{2v_0^2}x^2 + (\tan\theta)x + h.$$

34. The path of a ball is given by the rectangular equation

$$y = x - 0.005x^2.$$

Use the result of Exercise 33 to find the position vector. Then find the speed and direction of the ball at the point at which it has traveled 60 feet horizontally.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

35. The Rogers Centre in Toronto, Ontario, has a center field fence that is 10 feet high and 400 feet from home plate. A ball is hit 3 feet above the ground and leaves the bat at a speed of 100 miles per hour.

(a) The ball leaves the bat at an angle of $\theta = \theta_0$ with the horizontal. Write the vector-valued function for the path of the ball.

(b) Use a graphing utility to graph the vector-valued function for $\theta_0 = 10°$, $\theta_0 = 15°$, $\theta_0 = 20°$, and $\theta_0 = 25°$. Use the graphs to approximate the minimum angle required for the hit to be a home run.

(c) Determine analytically the minimum angle required for the hit to be a home run.

36. Football

The quarterback of a football team releases a pass at a height of 7 feet above the playing field, and the football is caught by a receiver 30 yards directly downfield at a height of 4 feet. The pass is released at an angle of 35° with the horizontal.

(a) Find the speed of the football when it is released.

(b) Find the maximum height of the football.

(c) Find the time the receiver has to reach the proper position after the quarterback releases the football.

37. A bale ejector consists of two variable-speed belts at the end of a baler. Its purpose is to toss bales into a trailing wagon. In loading the back of a wagon, a bale must be thrown to a position 8 feet above and 16 feet behind the ejector.

(a) Find the minimum initial speed of the bale and the corresponding angle at which it must be ejected from the baler.

(b) The ejector has a fixed angle of 45°. Find the initial speed required.

38. To test the impact speeds of different air supply drops, a pilot is flying horizontally at an altitude of 400 feet with a speed of 60 miles per hour (see figure). When should the package be released for it to hit the target? (Give your answer in terms of the angle of depression from the plane to the target.) What is the speed of the package at the time of impact?



39. A ball fired from a cannon with an exit speed of 1200 feet per second is to hit a target 3000 feet away. Determine the minimum angle of elevation of the cannon.

40. A projectile is fired from ground level at an angle of 12° with the horizontal. The projectile is to have a range of 200 feet. Find the minimum initial speed necessary.

41. Use a graphing utility to graph the paths of a projectile for the given values of θ and v_0. For each case, use the graph to approximate the maximum height and range of the projectile. (Assume that the projectile is launched from ground level.)

(a) $\theta = 10°$, $v_0 = 66$ ft/sec

(b) $\theta = 10°$, $v_0 = 146$ ft/sec

(c) $\theta = 45°$, $v_0 = 66$ ft/sec

(d) $\theta = 45°$, $v_0 = 146$ ft/sec

(e) $\theta = 60°$, $v_0 = 66$ ft/sec

(f) $\theta = 60°$, $v_0 = 146$ ft/sec

42. Find the angles at which an object must be thrown to obtain (a) the maximum range and (b) the maximum height.

Projectile Motion **In Exercises 43 and 44, use the model for projectile motion, assuming there is no air resistance and $g = 9.8$ meters per second per second.**

43. Determine the maximum height and range of a projectile fired at a height of 1.5 meters above the ground with an initial speed of 100 meters per second and at an angle of 30° above the horizontal.

44. A projectile is fired from ground level at an angle of 8° with the horizontal. The projectile is to have a range of 50 meters. Find the minimum initial speed necessary.

45. Shot-Put Throw The path of a shot thrown at an angle θ is

$$\mathbf{r}(t) = (v_0 \cos\theta)t\mathbf{i} + \left[h + (v_0 \sin\theta)t - \frac{1}{2}gt^2\right]\mathbf{j}$$

where v_0 is the initial speed, h is the initial height, t is the time in seconds, and g is the acceleration due to gravity. Verify that the shot will remain in the air for a total of

$$t = \frac{v_0 \sin\theta + \sqrt{v_0^2 \sin^2\theta + 2gh}}{g} \text{ seconds}$$

and will travel a horizontal distance of

$$\frac{v_0^2 \cos\theta}{g}\left(\sin\theta + \sqrt{\sin^2\theta + \frac{2gh}{v_0^2}}\right) \text{ feet.}$$

46. Shot-Put Throw

A shot is thrown from a height of $h = 5.75$ feet with an initial speed of $v_0 = 41$ feet per second and at an angle of $\theta = 42.5°$ with the horizontal. Use the result of Exercise 45 to find the total time of travel and the total horizontal distance traveled.

JoeSAPhotos/Shutterstock.com

PCN Photography/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Cycloidal Motion **In Exercises 47 and 48, consider the motion of a point (or particle) on the circumference of a rolling circle. As the circle rolls, it generates the cycloid**

$$\mathbf{r}(t) = b(\omega t - \sin \omega t)\mathbf{i} + b(1 - \cos \omega t)\mathbf{j}$$

where ω is the constant angular speed of the circle and b is the radius of the circle.

47. Find the velocity and acceleration vectors of the particle. Use the results to determine the times at which the speed of the particle will be (a) zero and (b) maximized.

48. Find the maximum speed of a point on the circumference of an automobile tire of radius 1 foot when the automobile is traveling at 60 miles per hour. Compare this speed with the speed of the automobile.

Circular Motion **In Exercises 49–52, consider a particle moving on a circular path of radius b described by**

$$\mathbf{r}(t) = b \cos \omega t\mathbf{i} + b \sin \omega t\mathbf{j}$$

where $\omega = du/dt$ is the constant angular speed.

49. Find the velocity vector and show that it is orthogonal to $\mathbf{r}(t)$.

50. (a) Show that the speed of the particle is $b\omega$.

(b) Use a graphing utility in *parametric* mode to graph the circle for $b = 6$. Try different values of ω. Does the graphing utility draw the circle faster for greater values of ω?

51. Find the acceleration vector and show that its direction is always toward the center of the circle.

52. Show that the magnitude of the acceleration vector is $b\omega^2$.

Circular Motion **In Exercises 53 and 54, use the results of Exercises 49–52.**

53. A psychrometer (an instrument used to measure humidity) weighing 4 ounces is whirled horizontally using a six-inch string (see figure). The string will break under a force of 2 pounds. Find the maximum speed the instrument can attain without breaking the string. (Use $\mathbf{F} = m\mathbf{a}$, where $m = 1/128$.)



Figure for 53



Figure for 54

54. A 3400-pound automobile is negotiating a circular interchange of radius 300 feet at 30 miles per hour (see figure). Assuming the roadway is level, find the force between the tires and the road such that the car stays on the circular path and does not skid. (Use $\mathbf{F} = m\mathbf{a}$, where $m = 3400/32$.) Find the angle at which the roadway should be banked so that no lateral frictional force is exerted on the tires of the automobile.

Exploring Concepts

55. Explain the difference between the velocity of an object and its speed.

56. Consider a particle that is moving along the space curve given by $\mathbf{r}_1(t) = t^3\mathbf{i} + (3 - t)\mathbf{j} + 2t^2\mathbf{k}$. Write a vector-valued function $\mathbf{r}_2$ for a particle that moves four times as fast as the particle represented by $\mathbf{r}_1$. Explain how you found the function.

57. Consider a particle that moves around a circle. Is the velocity vector of the particle always orthogonal to the acceleration vector of the particle? Explain.

58. **Particle Motion** Consider a particle moving on an elliptical path described by $\mathbf{r}(t) = a \cos \omega t\mathbf{i} + b \sin \omega t\mathbf{j}$, where $\omega = d\theta/dt$ is the constant angular speed.

(a) Find the velocity vector. What is the speed of the particle?

(b) Find the acceleration vector and show that its direction is always toward the center of the ellipse.

59. **Path of an Object** When $t = 0$, an object is at the point $(0, 1)$ and has a velocity vector $\mathbf{v}(0) = -\mathbf{i}$. It moves with an acceleration of $\mathbf{a}(t) = \sin t\mathbf{i} - \cos t\mathbf{j}$. Show that the path of the object is a circle.

60. **HOW DO YOU SEE IT?** The graph shows the path of a projectile and the velocity and acceleration vectors at times t_1 and t_2. Classify the angle between the velocity vector and the acceleration vector at times t_1 and t_2. Using the vectors, is the speed increasing or decreasing at times t_1 and t_2? Explain your reasoning.



61. **Proof** Prove that when an object is traveling at a constant speed, its velocity and acceleration vectors are orthogonal.

62. **Proof** Prove that an object moving in a straight line at a constant speed has an acceleration of 0.

True or False? **In Exercises 63–65, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

63. The velocity vector points in the direction of motion.

64. If a particle moves along a straight line, then the velocity and acceleration vectors are orthogonal.

65. A velocity vector of variable magnitude cannot have a constant direction.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

12.4 Tangent Vectors and Normal Vectors

GO DIGITAL

- **Find a unit tangent vector and a principal unit normal vector at a point on a space curve.**
- **Find the tangential and normal components of acceleration.**

Tangent Vectors and Normal Vectors

In the preceding section, you learned that the velocity vector points in the direction of motion. This observation leads to the next definition, which applies to any smooth curve—not just to those for which the parameter represents time.

Definition of Unit Tangent Vector

Let C be a smooth curve represented by $\mathbf{r}$ on an open interval I. The **unit tangent vector** $\mathbf{T}(t)$ at t is defined as

$$\mathbf{T}(t) = \frac{\mathbf{r}'(t)}{\|\mathbf{r}'(t)\|}, \quad \mathbf{r}'(t) \neq \mathbf{0}.$$

Recall that a curve is *smooth* on an interval when $\mathbf{r}'$ is continuous and nonzero on the interval. So, "smoothness" is sufficient to guarantee that a curve has a unit tangent vector.

EXAMPLE 1 Finding the Unit Tangent Vector

Find the unit tangent vector to the curve given by

$$\mathbf{r}(t) = t\mathbf{i} + t^2\mathbf{j}$$

when $t = 1$.

Solution The derivative of $\mathbf{r}$ is

$$\mathbf{r}'(t) = \mathbf{i} + 2t\mathbf{j}.$$ Derivative of $\mathbf{r}$

So, the unit tangent vector is

$$\mathbf{T}(t) = \frac{\mathbf{r}'(t)}{\|\mathbf{r}'(t)\|}$$ Definition of unit tangent vector

$$= \frac{1}{\sqrt{1 + 4t^2}}(\mathbf{i} + 2t\mathbf{j}).$$ Substitute for $\mathbf{r}'(t)$.

When $t = 1$, the unit tangent vector is

$$\mathbf{T}(1) = \frac{1}{\sqrt{5}}(\mathbf{i} + 2\mathbf{j})$$

as shown in Figure 12.20. ■



The direction of the unit tangent vector depends on the orientation of the curve.
Figure 12.20

In Example 1, note that the direction of the unit tangent vector depends on the orientation of the curve. For the parabola described by

$$\mathbf{r}(t) = -(t - 2)\mathbf{i} + (t - 2)^2\mathbf{j}$$

$\mathbf{T}(1)$ would still represent the unit tangent vector at the point $(1, 1)$, but it would point in the opposite direction. Try verifying this.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The **tangent line to a curve** at a point is the line that passes through the point and is parallel to the unit tangent vector. In Example 2, the unit tangent vector is used to find the tangent line at a point on a helix.

EXAMPLE 2 Finding the Tangent Line at a Point on a Curve

Find $\mathbf{T}(t)$ and then find a set of parametric equations for the tangent line to the helix given by

$$\mathbf{r}(t) = 2\cos t\mathbf{i} + 2\sin t\mathbf{j} + t\mathbf{k}$$

at the point $\left(\sqrt{2}, \sqrt{2}, \frac{\pi}{4}\right)$.

Solution The derivative of $\mathbf{r}$ is

$$\mathbf{r}'(t) = -2\sin t\mathbf{i} + 2\cos t\mathbf{j} + \mathbf{k}$$

which implies that $\|\mathbf{r}'(t)\| = \sqrt{4\sin^2 t + 4\cos^2 t + 1} = \sqrt{5}$. So, the unit tangent vector is

$$\mathbf{T}(t) = \frac{\mathbf{r}'(t)}{\|\mathbf{r}'(t)\|} = \frac{1}{\sqrt{5}}(-2\sin t\mathbf{i} + 2\cos t\mathbf{j} + \mathbf{k}).$$ Unit tangent vector

At the point $\left(\sqrt{2}, \sqrt{2}, \pi/4\right)$, $t = \pi/4$ and the unit tangent vector is

$$\mathbf{T}\left(\frac{\pi}{4}\right) = \frac{1}{\sqrt{5}}\left(-2\frac{\sqrt{2}}{2}\mathbf{i} + 2\frac{\sqrt{2}}{2}\mathbf{j} + \mathbf{k}\right) = \frac{1}{\sqrt{5}}\left(-\sqrt{2}\mathbf{i} + \sqrt{2}\mathbf{j} + \mathbf{k}\right).$$

Using the direction numbers $a = -\sqrt{2}$, $b = \sqrt{2}$, and $c = 1$, and the point $(x_1, y_1, z_1) = \left(\sqrt{2}, \sqrt{2}, \pi/4\right)$, you can obtain the parametric equations (given with parameter s) listed below.

$$x = x_1 + as = \sqrt{2} - \sqrt{2}s$$
$$y = y_1 + bs = \sqrt{2} + \sqrt{2}s$$
$$z = z_1 + cs = \frac{\pi}{4} + s$$

This tangent line is shown in Figure 12.21.



The tangent line to a curve at a point is determined by the unit tangent vector at the point.
Figure 12.21

In Example 2, there are infinitely many vectors that are orthogonal to the tangent vector $\mathbf{T}(t)$. One of these is the vector $\mathbf{T}'(t)$. This follows from Property 7 of Theorem 12.2. That is,

$$\mathbf{T}(t) \cdot \mathbf{T}(t) = \|\mathbf{T}(t)\|^2 = 1 \quad \Rightarrow \quad \mathbf{T}(t) \cdot \mathbf{T}'(t) = 0.$$

By normalizing the vector $\mathbf{T}'(t)$, you obtain a special vector called the **principal unit normal vector,** as indicated in the next definition.

Definition of Principal Unit Normal Vector

Let C be a smooth curve represented by $\mathbf{r}$ on an open interval I. If $\mathbf{T}'(t) \neq \mathbf{0}$, then the **principal unit normal vector** at t is defined as

$$\mathbf{N}(t) = \frac{\mathbf{T}'(t)}{\|\mathbf{T}'(t)\|}.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 3 **Finding the Principal Unit Normal Vector**

Find $\mathbf{N}(t)$ and $\mathbf{N}(1)$ for the curve represented by $\mathbf{r}(t) = 3t\mathbf{i} + 2t^2\mathbf{j}$.

Solution By differentiating, you obtain

$$\mathbf{r}'(t) = 3\mathbf{i} + 4t\mathbf{j}$$

which implies that

$$\|\mathbf{r}'(t)\| = \sqrt{9 + 16t^2}.$$

So, the unit tangent vector is

$$\mathbf{T}(t) = \frac{\mathbf{r}'(t)}{\|\mathbf{r}'(t)\|} = \frac{1}{\sqrt{9 + 16t^2}}(3\mathbf{i} + 4t\mathbf{j}).$$ Unit tangent vector

Using Theorem 12.2, differentiate $\mathbf{T}(t)$ with respect to t to obtain

$$\mathbf{T}'(t) = \frac{1}{\sqrt{9 + 16t^2}}(4\mathbf{j}) - \frac{16t}{(9 + 16t^2)^{3/2}}(3\mathbf{i} + 4t\mathbf{j}) = \frac{12}{(9 + 16t^2)^{3/2}}(-4t\mathbf{i} + 3\mathbf{j})$$

which implies that

$$\|\mathbf{T}'(t)\| = 12\sqrt{\frac{9 + 16t^2}{(9 + 16t^2)^3}} = \frac{12}{9 + 16t^2}.$$

Therefore, the principal unit normal vector is

$$\mathbf{N}(t) = \frac{\mathbf{T}'(t)}{\|\mathbf{T}'(t)\|} = \frac{1}{\sqrt{9 + 16t^2}}(-4t\mathbf{i} + 3\mathbf{j}).$$ Principal unit normal vector

When $t = 1$, the principal unit normal vector is

$$\mathbf{N}(1) = \frac{1}{5}(-4\mathbf{i} + 3\mathbf{j})$$

as shown in Figure 12.22.



The principal unit normal vector points toward the concave side of the curve.

Figure 12.22

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The principal unit normal vector can be difficult to evaluate algebraically. For plane curves, you can simplify the algebra by finding

$$\mathbf{T}(t) = x(t)\mathbf{i} + y(t)\mathbf{j}$$ Unit tangent vector

and observing that $\mathbf{N}(t)$ must be either

$$\mathbf{N}_1(t) = y(t)\mathbf{i} - x(t)\mathbf{j} \quad \text{or} \quad \mathbf{N}_2(t) = -y(t)\mathbf{i} + x(t)\mathbf{j}.$$

Because $\sqrt{[x(t)]^2 + [y(t)]^2} = 1$, it follows that both $\mathbf{N}_1(t)$ and $\mathbf{N}_2(t)$ are unit normal vectors. The *principal* unit normal vector $\mathbf{N}$ is the one that points toward the concave side of the curve, as shown in Figure 12.22 (see Exercise 72). This also holds for curves in space. That is, for an object moving along a curve C in space, the vector $\mathbf{T}(t)$ points in the direction the object is moving, whereas the vector $\mathbf{N}(t)$ is orthogonal to $\mathbf{T}(t)$ and points in the direction in which the object is turning, as shown in Figure 12.23.



At any point on a curve, a unit normal vector is orthogonal to the unit tangent vector. The *principal* unit normal vector points in the direction in which the curve is turning.
Figure 12.23

Helix:
$\mathbf{r}(t) = 2\cos t\mathbf{i} + 2\sin t\mathbf{j} + t\mathbf{k}$



$\mathbf{N}(t)$ is horizontal and points toward the z-axis.
Figure 12.24

EXAMPLE 4 Finding the Principal Unit Normal Vector

Find the principal unit normal vector for the helix $\mathbf{r}(t) = 2\cos t\mathbf{i} + 2\sin t\mathbf{j} + t\mathbf{k}$.

Solution From Example 2, you know that the unit tangent vector is

$$\mathbf{T}(t) = \frac{1}{\sqrt{5}}(-2\sin t\mathbf{i} + 2\cos t\mathbf{j} + \mathbf{k}).$$ Unit tangent vector

So, $\mathbf{T}'(t)$ is given by

$$\mathbf{T}'(t) = \frac{1}{\sqrt{5}}(-2\cos t\mathbf{i} - 2\sin t\mathbf{j}).$$

Because $\|\mathbf{T}'(t)\| = 2/\sqrt{5}$, it follows that the principal unit normal vector is

$$\begin{aligned}\mathbf{N}(t) &= \frac{\mathbf{T}'(t)}{\|\mathbf{T}'(t)\|} \\ &= \frac{1}{2}(-2\cos t\mathbf{i} - 2\sin t\mathbf{j}) \\ &= -\cos t\mathbf{i} - \sin t\mathbf{j}.\end{aligned}$$ Principal unit normal vector

Note that this vector is horizontal and points toward the z-axis, as shown in Figure 12.24. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Tangential and Normal Components of Acceleration

In the preceding section, you considered the problem of describing the motion of an object along a curve. You learned that for an object traveling at a *constant speed,* the velocity and acceleration vectors are perpendicular. This seems reasonable, because the speed would not be constant if any acceleration were acting in the direction of motion. You can verify this observation by noting that

$$\mathbf{r}''(t) \cdot \mathbf{r}'(t) = 0$$

when $\|\mathbf{r}'(t)\|$ is a constant. (See Property 7 of Theorem 12.2.)

For an object traveling at a *variable speed,* however, the velocity and acceleration vectors are not necessarily perpendicular. For instance, you learned that the acceleration vector for a projectile always points down, regardless of the direction of motion.

In general, part of the acceleration (the tangential component) acts in the line of motion, and part of it (the normal component) acts perpendicular to the line of motion. To determine these two components, you can use the unit vectors $\mathbf{T}(t)$ and $\mathbf{N}(t)$, which serve in much the same way as do $\mathbf{i}$ and $\mathbf{j}$ in representing vectors in the plane. The next theorem states that the acceleration vector lies in the plane determined by $\mathbf{T}(t)$ and $\mathbf{N}(t)$.

THEOREM 12.4 Acceleration Vector

If $\mathbf{r}(t)$ is the position vector for a smooth curve C and $\mathbf{N}(t)$ exists, then the acceleration vector $\mathbf{a}(t)$ lies in the plane determined by $\mathbf{T}(t)$ and $\mathbf{N}(t)$.

Proof To simplify the notation, write $\mathbf{T}$ for $\mathbf{T}(t)$, $\mathbf{T}'$ for $\mathbf{T}'(t)$, and so on. Because $\mathbf{T} = \mathbf{r}'/\|\mathbf{r}'\| = \mathbf{v}/\|\mathbf{v}\|$, it follows that

$$\mathbf{v} = \|\mathbf{v}\|\mathbf{T}.$$

By differentiating, you obtain

$$\begin{aligned}
\mathbf{a} &= \mathbf{v}' \\
&= \frac{d}{dt}\left[\|\mathbf{v}\|\right]\mathbf{T} + \|\mathbf{v}\|\mathbf{T}' && \text{Product Rule} \\
&= \frac{d}{dt}\left[\|\mathbf{v}\|\right]\mathbf{T} + \|\mathbf{v}\|\mathbf{T}'\left(\frac{\|\mathbf{T}'\|}{\|\mathbf{T}'\|}\right) \\
&= \frac{d}{dt}\left[\|\mathbf{v}\|\right]\mathbf{T} + \|\mathbf{v}\|\,\|\mathbf{T}'\|\mathbf{N}. && \mathbf{N} = \mathbf{T}'/\|\mathbf{T}'\|
\end{aligned}$$

Because $\mathbf{a}$ is written as a linear combination of $\mathbf{T}$ and $\mathbf{N}$, it follows that $\mathbf{a}$ lies in the plane determined by $\mathbf{T}$ and $\mathbf{N}$. ∎

The coefficients of $\mathbf{T}$ and $\mathbf{N}$ in the proof of Theorem 12.4 are called the **tangential and normal components of acceleration** and are denoted by

$$a_{\mathbf{T}} = \frac{d}{dt}\left[\|\mathbf{v}\|\right] \quad \text{and} \quad a_{\mathbf{N}} = \|\mathbf{v}\|\,\|\mathbf{T}'\|.$$

So, you can write

$$\mathbf{a}(t) = a_{\mathbf{T}}\mathbf{T}(t) + a_{\mathbf{N}}\mathbf{N}(t).$$

The next theorem lists some convenient formulas for $a_{\mathbf{T}}$ and $a_{\mathbf{N}}$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The tangential and normal components of acceleration are obtained by projecting **a** onto **T** and **N**.
Figure 12.25

THEOREM 12.5 Tangential and Normal Components of Acceleration

If $\mathbf{r}(t)$ is the position vector for a smooth curve C [for which $\mathbf{N}(t)$ exists], then the tangential and normal components of acceleration are as follows.

$$a_{\mathbf{T}} = \frac{d}{dt}\left[\|\mathbf{v}\|\right] = \mathbf{a} \cdot \mathbf{T} = \frac{\mathbf{v} \cdot \mathbf{a}}{\|\mathbf{v}\|}$$

$$a_{\mathbf{N}} = \|\mathbf{v}\|\|\mathbf{T}'\| = \mathbf{a} \cdot \mathbf{N} = \frac{\|\mathbf{v} \times \mathbf{a}\|}{\|\mathbf{v}\|} = \sqrt{\|\mathbf{a}\|^2 - a_{\mathbf{T}}^2}$$

Note that $a_{\mathbf{N}} \geq 0$. The normal component of acceleration is also called the **centripetal component of acceleration.**

Proof Note that **a** lies in the plane of **T** and **N**. So, you can use Figure 12.25 to conclude that, for any time t, the components of the projection of the acceleration vector onto **T** and onto **N** are given by $a_{\mathbf{T}} = \mathbf{a} \cdot \mathbf{T}$ and $a_{\mathbf{N}} = \mathbf{a} \cdot \mathbf{N}$, respectively. Moreover, because $\mathbf{a} = \mathbf{v}'$ and $\mathbf{T} = \mathbf{v}/\|\mathbf{v}\|$, you have

$$a_{\mathbf{T}} = \mathbf{a} \cdot \mathbf{T} = \mathbf{T} \cdot \mathbf{a} = \frac{\mathbf{v}}{\|\mathbf{v}\|} \cdot \mathbf{a} = \frac{\mathbf{v} \cdot \mathbf{a}}{\|\mathbf{v}\|}.$$

In Exercises 74 and 75, you are asked to prove the other parts of the theorem. ■

EXAMPLE 5 Tangential and Normal Components of Acceleration

See LarsonCalculus.com for an interactive version of this type of example.

Find the tangential and normal components of acceleration for the position vector given by $\mathbf{r}(t) = 3t\mathbf{i} - t\mathbf{j} + t^2\mathbf{k}$.

Solution Begin by finding the velocity, speed, and acceleration.

$$\mathbf{v}(t) = \mathbf{r}'(t) = 3\mathbf{i} - \mathbf{j} + 2t\mathbf{k} \qquad \text{Velocity vector}$$

$$\|\mathbf{v}(t)\| = \sqrt{9 + 1 + 4t^2} = \sqrt{10 + 4t^2} \qquad \text{Speed}$$

$$\mathbf{a}(t) = \mathbf{r}''(t) = 2\mathbf{k} \qquad \text{Acceleration vector}$$

By Theorem 12.5, the tangential component of acceleration is

$$a_{\mathbf{T}} = \frac{\mathbf{v} \cdot \mathbf{a}}{\|\mathbf{v}\|} = \frac{4t}{\sqrt{10 + 4t^2}} \qquad \text{Tangential component of acceleration}$$

and because

$$\mathbf{v} \times \mathbf{a} = \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ 3 & -1 & 2t \\ 0 & 0 & 2 \end{vmatrix} = -2\mathbf{i} - 6\mathbf{j}$$

the normal component of acceleration is

$$a_{\mathbf{N}} = \frac{\|\mathbf{v} \times \mathbf{a}\|}{\|\mathbf{v}\|} = \frac{\sqrt{4 + 36}}{\sqrt{10 + 4t^2}} = \frac{2\sqrt{10}}{\sqrt{10 + 4t^2}}. \qquad \text{Normal component of acceleration}$$

■

In Example 5, you could have used the alternative formula for $a_{\mathbf{N}}$ as follows.

$$a_{\mathbf{N}} = \sqrt{\|\mathbf{a}\|^2 - a_{\mathbf{T}}^2} = \sqrt{(2)^2 - \frac{16t^2}{10 + 4t^2}} = \frac{2\sqrt{10}}{\sqrt{10 + 4t^2}}$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 6 Finding a_T and a_N for a Circular Helix

Find the tangential and normal components of acceleration for the helix given by

$$\mathbf{r}(t) = b\cos t\mathbf{i} + b\sin t\mathbf{j} + ct\mathbf{k}, \quad b > 0.$$

Solution

$$\mathbf{v}(t) = \mathbf{r}'(t) = -b\sin t\mathbf{i} + b\cos t\mathbf{j} + c\mathbf{k}$$ Velocity vector

$$\|\mathbf{v}(t)\| = \sqrt{b^2\sin^2 t + b^2\cos^2 t + c^2} = \sqrt{b^2 + c^2}$$ Speed

$$\mathbf{a}(t) = \mathbf{r}''(t) = -b\cos t\mathbf{i} - b\sin t\mathbf{j}$$ Acceleration vector

By Theorem 12.5, the tangential component of acceleration is

$$a_T = \frac{\mathbf{v}\cdot\mathbf{a}}{\|\mathbf{v}\|} = \frac{b^2\sin t\cos t - b^2\sin t\cos t + 0}{\sqrt{b^2 + c^2}} = 0.$$ Tangential component of acceleration

Moreover, because

$$\|\mathbf{a}\| = \sqrt{b^2\cos^2 t + b^2\sin^2 t} = b$$

you can use the alternative formula for the normal component of acceleration to obtain

$$a_N = \sqrt{\|\mathbf{a}\|^2 - a_T^2} = \sqrt{b^2 - 0^2} = b.$$ Normal component of acceleration

Note that the normal component of acceleration is equal to the magnitude of the acceleration. In other words, because the speed is constant, the acceleration is perpendicular to the velocity. See Figure 12.26.



The normal component of acceleration is equal to the radius of the cylinder around which the helix is spiraling.
Figure 12.26

EXAMPLE 7 Projectile Motion

The position vector for the projectile shown in Figure 12.27 is

$$\mathbf{r}(t) = \left(50\sqrt{2}t\right)\mathbf{i} + \left(50\sqrt{2}t - 16t^2\right)\mathbf{j}.$$ Position vector

Find the tangential components of acceleration when $t = 0$, 1, and $25\sqrt{2}/16$.

Solution

$$\mathbf{v}(t) = 50\sqrt{2}\mathbf{i} + \left(50\sqrt{2} - 32t\right)\mathbf{j}$$ Velocity vector

$$\|\mathbf{v}(t)\| = 2\sqrt{50^2 - 16(50)\sqrt{2}t + 16^2t^2}$$ Speed

$$\mathbf{a}(t) = -32\mathbf{j}$$ Acceleration vector

The tangential component of acceleration is

$$a_T(t) = \frac{\mathbf{v}(t)\cdot\mathbf{a}(t)}{\|\mathbf{v}(t)\|} = \frac{-32\left(50\sqrt{2} - 32t\right)}{2\sqrt{50^2 - 16(50)\sqrt{2}t + 16^2t^2}}.$$ Tangential component of acceleration

At the specified times, you have

$$a_T(0) = \frac{-32\left(50\sqrt{2}\right)}{100} = -16\sqrt{2} \approx -22.6$$

$$a_T(1) = \frac{-32\left(50\sqrt{2} - 32\right)}{2\sqrt{50^2 - 16(50)\sqrt{2} + 16^2}} \approx -15.4$$

$$a_T\left(\frac{25\sqrt{2}}{16}\right) = \frac{-32\left(50\sqrt{2} - 50\sqrt{2}\right)}{50\sqrt{2}} = 0.$$

Figure 12.27 shows that at the projectile's maximum height, when $t = 25\sqrt{2}/16$, the tangential component is 0. This is reasonable because the direction of motion is horizontal at the point, and the tangential component of the acceleration is equal to the horizontal component of the acceleration. ■



The path of a projectile
Figure 12.27

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

12.4 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain how the unit tangent vector is related to the orientation of a curve.
2. In what direction does the principal unit normal vector point?

Finding the Unit Tangent Vector **In Exercises 3–8, find the unit tangent vector to the curve at the specified value of the parameter.**

3. $\mathbf{r}(t) = t^2\mathbf{i} + 2t\mathbf{j}, \quad t = 1$
4. $\mathbf{r}(t) = t^3\mathbf{i} + 2t^2\mathbf{j}, \quad t = 1$
5. $\mathbf{r}(t) = 5\cos t\,\mathbf{i} + 5\sin t\,\mathbf{j}, \quad t = \frac{\pi}{3}$
6. $\mathbf{r}(t) = 6\sin t\,\mathbf{i} - 2\cos t\,\mathbf{j}, \quad t = \frac{\pi}{6}$
7. $\mathbf{r}(t) = 3t\mathbf{i} - \ln t\,\mathbf{j}, \quad t = e$
8. $\mathbf{r}(t) = e^t\cos t\,\mathbf{i} + e^t\mathbf{j}, \quad t = 0$

Finding a Tangent Line **In Exercises 9–14, find the unit tangent vector $\mathbf{T}(t)$ and a set of parametric equations for the tangent line to the space curve at point P.**

9. $\mathbf{r}(t) = t\mathbf{i} + t^2\mathbf{j} + t\mathbf{k}, \quad P(0, 0, 0)$
10. $\mathbf{r}(t) = t^2\mathbf{i} + t\mathbf{j} + \frac{4}{3}\mathbf{k}, \quad P\left(1, 1, \frac{4}{3}\right)$
11. $\mathbf{r}(t) = \cos t\,\mathbf{i} + 3\sin t\,\mathbf{j} + (3t - 4)\mathbf{k}, \quad P(1, 0, -4)$
12. $\mathbf{r}(t) = \left\langle t, t, \sqrt{4 - t^2}\right\rangle, \quad P\left(1, 1, \sqrt{3}\right)$
13. $\mathbf{r}(t) = \langle 2\cos t, 2\sin t, 4\rangle, \quad P\left(\sqrt{2}, \sqrt{2}, 4\right)$
14. $\mathbf{r}(t) = \langle 2\sin t, 2\cos t, 4\sin^2 t\rangle, \quad P\left(1, \sqrt{3}, 1\right)$

Finding the Principal Unit Normal Vector **In Exercises 15–20, find the principal unit normal vector to the curve at the specified value of the parameter.**

15. $\mathbf{r}(t) = t\mathbf{i} + \frac{1}{2}t^2\mathbf{j}, \quad t = 2$
16. $\mathbf{r}(t) = t\mathbf{i} + \frac{6}{t}\mathbf{j}, \quad t = 3$
17. $\mathbf{r}(t) = t\mathbf{i} + t^2\mathbf{j} + \ln t\,\mathbf{k}, \quad t = 1$
18. $\mathbf{r}(t) = \sqrt{2}t\mathbf{i} + e^t\mathbf{j} + e^{-t}\mathbf{k}, \quad t = 0$
19. $\mathbf{r}(t) = 6\cos t\,\mathbf{i} + 6\sin t\,\mathbf{j} + \mathbf{k}, \quad t = \frac{3\pi}{4}$
20. $\mathbf{r}(t) = \cos 3t\,\mathbf{i} + 2\sin 3t\,\mathbf{j} + \mathbf{k}, \quad t = \pi$

Sketching a Graph and Vectors **In Exercises 21–24, sketch the graph of the plane curve $\mathbf{r}(t)$ and sketch the vectors $\mathbf{T}(t)$ and $\mathbf{N}(t)$ at the given value of t.**

21. $\mathbf{r}(t) = t\mathbf{i} + \frac{1}{t}\mathbf{j}, \quad t = 2$
22. $\mathbf{r}(t) = t\mathbf{i} - t^3\mathbf{j}, \quad t = 1$
23. $\mathbf{r}(t) = (2t + 1)\mathbf{i} - t^2\mathbf{j}, \quad t = 2$
24. $\mathbf{r}(t) = 2\cos t\,\mathbf{i} + 2\sin t\,\mathbf{j}, \quad t = \frac{7\pi}{6}$

Finding Tangential and Normal Components of Acceleration **In Exercises 25–30, find the tangential and normal components of acceleration at the given time t for the plane curve $\mathbf{r}(t)$.**

25. $\mathbf{r}(t) = t\mathbf{i} + \frac{1}{t}\mathbf{j}, \quad t = 1$
26. $\mathbf{r}(t) = t^2\mathbf{i} + 2t\mathbf{j}, \quad t = 1$
27. $\mathbf{r}(t) = e^t\mathbf{i} + e^{-2t}\mathbf{j}, \quad t = 0$
28. $\mathbf{r}(t) = e^t\mathbf{i} + e^{-t}\mathbf{j}, \quad t = 0$
29. $\mathbf{r}(t) = e^t\cos t\,\mathbf{i} + e^t\sin t\,\mathbf{j}, \quad t = \frac{\pi}{2}$
30. $\mathbf{r}(t) = 4\cos 3t\mathbf{i} + 4\sin 3t\mathbf{j}, \quad t = \pi$

Circular Motion **In Exercises 31–34, consider an object moving according to the position vector**

$$\mathbf{r}(t) = a\cos\omega t\,\mathbf{i} + a\sin\omega t\,\mathbf{j}.$$

31. Find $\mathbf{T}(t)$, $\mathbf{N}(t)$, $a_{\mathbf{T}}$, and $a_{\mathbf{N}}$.
32. Determine the directions of $\mathbf{T}$ and $\mathbf{N}$ relative to the position vector $\mathbf{r}$.
33. Determine the speed of the object at any time t and explain its value relative to the value of $a_{\mathbf{T}}$.
34. When the angular speed ω is halved, by what factor is $a_{\mathbf{N}}$ changed?

Finding Tangential and Normal Components of Acceleration **In Exercises 35–40, find the tangential and normal components of acceleration at the given time t for the space curve $\mathbf{r}(t)$.**

35. $\mathbf{r}(t) = t\mathbf{i} + 2t\mathbf{j} - 3t\mathbf{k}, \quad t = 1$
36. $\mathbf{r}(t) = \cos t\,\mathbf{i} + \sin t\,\mathbf{j} + 2t\mathbf{k}, \quad t = \frac{\pi}{3}$
37. $\mathbf{r}(t) = t\mathbf{i} + t^2\mathbf{j} + \frac{t^2}{2}\mathbf{k}, \quad t = 1$
38. $\mathbf{r}(t) = (2t - 1)\mathbf{i} + t^2\mathbf{j} - 4t\mathbf{k}, \quad t = 2$
39. $\mathbf{r}(t) = e^t\sin t\,\mathbf{i} + e^t\cos t\,\mathbf{j} + e^t\mathbf{k}, \quad t = 0$
40. $\mathbf{r}(t) = e^t\mathbf{i} + 2t\mathbf{j} + e^{-t}\mathbf{k}, \quad t = 0$

Exploring Concepts

41. Describe the motion of a particle when the normal component of acceleration is 0.
42. Describe the motion of a particle when the tangential component of acceleration is 0.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

43. Finding Vectors An object moves along the path given by

$\mathbf{r}(t) = 3t\mathbf{i} + 4t\mathbf{j}$.

Find $\mathbf{v}(t)$, $\mathbf{a}(t)$, $\mathbf{T}(t)$, and $\mathbf{N}(t)$ (if it exists). What is the form of the path? Is the speed of the object constant or changing?

44. HOW DO YOU SEE IT? The figures show the paths of two particles.



(a) Which vector, $\mathbf{s}$ or $\mathbf{t}$, represents the unit tangent vector? Explain.

(b) Which vector, $\mathbf{y}$ or $\mathbf{z}$, represents the principal unit normal vector? Explain.

45. Cycloidal Motion The figure shows the path of a particle modeled by the vector-valued function

$\mathbf{r}(t) = \langle \pi t - \sin \pi t, 1 - \cos \pi t \rangle$.

The figure also shows the vectors $\mathbf{v}(t)/\|\mathbf{v}(t)\|$ and $\mathbf{a}(t)/\|\mathbf{a}(t)\|$ at the indicated values of t.

(a) Find $a_{\mathbf{T}}$ and $a_{\mathbf{N}}$ at $t = \frac{1}{2}$, $t = 1$, and $t = \frac{3}{2}$.

(b) Determine whether the speed of the particle is increasing or decreasing at each of the indicated values of t. Give reasons for your answers.



Figure for 45



Figure for 46

46. Motion Along an Involute of a Circle The figure shows a particle moving along a path modeled by

$\mathbf{r}(t) = \langle \cos \pi t + \pi t \sin \pi t, \sin \pi t - \pi t \cos \pi t \rangle$.

The figure also shows the vectors $\mathbf{v}(t)$ and $\mathbf{a}(t)$ for $t = 1$ and $t = 2$.

(a) Find $a_{\mathbf{T}}$ and $a_{\mathbf{N}}$ at $t = 1$ and $t = 2$.

(b) Determine whether the speed of the particle is increasing or decreasing at each of the indicated values of t. Give reasons for your answers.

Finding a Binormal Vector **In Exercises 47–52, find the vectors T and N and the binormal vector $\mathbf{B} = \mathbf{T} \times \mathbf{N}$ for the vector-valued function $\mathbf{r}(t)$ at the given value of t.**

47. $\mathbf{r}(t) = 2\cos t\mathbf{i} + 2\sin t\mathbf{j} + \frac{t}{2}\mathbf{k}, \quad t = \frac{\pi}{2}$

48. $\mathbf{r}(t) = t\mathbf{i} + t^2\mathbf{j} + \frac{t^3}{3}\mathbf{k}, \quad t = 1$

49. $\mathbf{r}(t) = \mathbf{i} + \sin t\mathbf{j} + \cos t\mathbf{k}, \quad t = \frac{\pi}{4}$

50. $\mathbf{r}(t) = 2e^t\mathbf{i} + e^t\cos t\mathbf{j} + e^t\sin t\mathbf{k}, \quad t = 0$

51. $\mathbf{r}(t) = 4\sin t\mathbf{i} + 4\cos t\mathbf{j} + 2t\mathbf{k}, \quad t = \frac{\pi}{3}$

52. $\mathbf{r}(t) = 3\cos 2t\mathbf{i} + 3\sin 2t\mathbf{j} + t\mathbf{k}, \quad t = \frac{\pi}{4}$

Alternative Formula for the Principal Unit Normal Vector **In Exercises 53–56, use the vector-valued function $\mathbf{r}(t)$ to find the principal unit normal vector $\mathbf{N}(t)$ using the alternative formula**

$$\mathbf{N} = \frac{(\mathbf{v}\cdot\mathbf{v})\mathbf{a} - (\mathbf{v}\cdot\mathbf{a})\mathbf{v}}{\|(\mathbf{v}\cdot\mathbf{v})\mathbf{a} - (\mathbf{v}\cdot\mathbf{a})\mathbf{v}\|}.$$

53. $\mathbf{r}(t) = 3t\mathbf{i} + 2t^2\mathbf{j}$

54. $\mathbf{r}(t) = 3\cos 2t\mathbf{i} + 3\sin 2t\mathbf{j}$

55. $\mathbf{r}(t) = 2t\mathbf{i} + 4t\mathbf{j} + t^2\mathbf{k}$

56. $\mathbf{r}(t) = 5\cos t\mathbf{i} + 5\sin t\mathbf{j} + 3t\mathbf{k}$

57. Projectile Motion Find the tangential and normal components of acceleration for a projectile fired at an angle θ with the horizontal at an initial speed of v_0. What are the components when the projectile is at its maximum height?

58. Projectile Motion Use your results from Exercise 57 to find the tangential and normal components of acceleration for a projectile fired at an angle of 45° with the horizontal at an initial speed of 150 feet per second. What are the components when the projectile is at its maximum height?

59. Projectile Motion A projectile is launched with an initial speed of 120 feet per second at a height of 5 feet and at an angle of 30° with the horizontal.

(a) Determine the vector-valued function for the path of the projectile.

(b) Use a graphing utility to graph the path and approximate the maximum height and range of the projectile.

(c) Find $\mathbf{v}(t)$, $\|\mathbf{v}(t)\|$, and $\mathbf{a}(t)$.

(d) Use a graphing utility to complete the table.

t	0.5	1.0	1.5	2.0	2.5	3.0
Speed						

(e) Use a graphing utility to graph the scalar functions $a_{\mathbf{T}}$ and $a_{\mathbf{N}}$. How is the speed of the projectile changing when $a_{\mathbf{T}}$ and $a_{\mathbf{N}}$ have opposite signs?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

60. Projectile Motion A projectile is launched with an initial speed of 220 feet per second at a height of 4 feet and at an angle of 45° with the horizontal.

(a) Determine the vector-valued function for the path of the projectile.

(b) Use a graphing utility to graph the path and approximate the maximum height and range of the projectile.

(c) Find $\mathbf{v}(t)$, $\|\mathbf{v}(t)\|$, and $\mathbf{a}(t)$.

(d) Use a graphing utility to complete the table.

t	0.5	1.0	1.5	2.0	2.5	3.0
Speed						

61. Air Traffic Control

Because of a storm, ground controllers instruct the pilot of a plane flying at an altitude of 4 miles to make a 90° turn and climb to an altitude of 4.2 miles. The model for the path of the plane during this maneuver is

$$\mathbf{r}(t) = \langle 10 \cos 10\pi t, 10 \sin 10\pi t, 4 + 4t \rangle, \quad 0 \le t \le \tfrac{1}{20}$$

where t is the time in hours and $\mathbf{r}$ is the distance in miles.

(a) Determine the speed of the plane.

(b) Calculate $a_{\mathbf{T}}$ and $a_{\mathbf{N}}$. Why is one of these equal to 0?

62. Projectile Motion A plane flying at an altitude of 36,000 feet at a speed of 600 miles per hour releases a supply package. Find the tangential and normal components of acceleration acting on the supply package.

63. Centripetal Acceleration An object is spinning at a constant speed on the end of a string, according to the position vector $\mathbf{r}(t) = a \cos \omega t\mathbf{i} + a \sin \omega t\mathbf{j}$.

(a) When the angular speed ω is doubled, how is the centripetal component of acceleration changed?

(b) When the angular speed is unchanged but the length of the string is halved, how is the centripetal component of acceleration changed?

64. Centripetal Force An object of mass m moves at a constant speed v in a circular path of radius r, according to the position vector $\mathbf{r}(t) = r \cos \omega t\mathbf{i} + r \sin \omega t\mathbf{j}$.

(a) The force required to produce the centripetal component of acceleration is called the *centripetal force* and is given by $F = mv^2/r$. Use $\mathbf{F} = m\mathbf{a}$ to verify the centripetal force.

(b) Newton's Law of Universal Gravitation is given by $F = GMm/d^2$, where d is the distance between the centers of the two bodies of masses M and m, and G is the gravitational constant. Use this law to show that the speed required for circular motion is $v = \sqrt{GM/r}$.

Orbital Speed **In Exercises 65–68, use the result of Exercise 64 to find the speed necessary for the given circular orbit around Earth. Let $GM = 9.56 \times 10^4$ cubic miles per second per second, and assume the radius of Earth is 4000 miles.**

65. The orbit of the International Space Station 255 miles above the surface of Earth

66. The orbit of the Hubble telescope 340 miles above the surface of Earth

67. The orbit of a heat capacity mapping satellite 385 miles above the surface of Earth

68. The orbit of a communications satellite r miles above the surface of Earth that is in geosynchronous orbit. [The satellite completes one orbit per sidereal day (approximately 23 hours, 56 minutes) and therefore appears to remain stationary above a point on Earth.]

True or False? **In Exercises 69 and 70, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

69. The velocity and acceleration vectors of a moving object are always perpendicular.

70. If $a_{\mathbf{N}} = 0$ for a moving object, then the object is moving in a straight line.

71. Motion of a Particle A particle moves along a path modeled by

$$\mathbf{r}(t) = \cosh(bt)\mathbf{i} + \sinh(bt)\mathbf{j}$$

where b is a positive constant.

(a) Show that the path of the particle is a hyperbola.

(b) Show that $\mathbf{a}(t) = b^2\mathbf{r}(t)$.

72. Proof Prove that the principal unit normal vector $\mathbf{N}$ points toward the concave side of a plane curve.

73. Proof Prove that the vector $\mathbf{T}'(t)$ is 0 for an object moving in a straight line.

74. Proof Prove that $a_{\mathbf{N}} = \dfrac{\|\mathbf{v} \times \mathbf{a}\|}{\|\mathbf{v}\|}$.

75. Proof Prove that $a_{\mathbf{N}} = \sqrt{\|\mathbf{a}\|^2 - a_{\mathbf{T}}^2}$.

PUTNAM EXAM CHALLENGE

76. A particle of unit mass moves on a straight line under the action of a force which is a function $f(v)$ of the velocity v of the particle, but the form of this function is not known. A motion is observed, and the distance x covered in time t is found to be connected with t by the formula

$$x = at + bt^2 + ct^3$$

where a, b, and c have numerical values determined by observation of the motion. Find the function $f(v)$ for the range of v covered by the experiment.

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

mr. teerapon tiuekhom/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

12.5 Arc Length and Curvature

GO DIGITAL

- Find the arc length of a space curve.
- Use the arc length parameter to describe a plane curve or space curve.
- Find the curvature of a curve at a point on the curve.
- Use a vector-valued function to find frictional force.

Arc Length

In Section 10.3, you learned that the arc length of a smooth *plane* curve C given by the parametric equations $x = x(t)$ and $y = y(t)$, $a \le t \le b$, is

$$s = \int_a^b \sqrt{[x'(t)]^2 + [y'(t)]^2}\, dt.$$

In vector form, where C is given by $\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j}$, you can rewrite this equation for arc length as

$$s = \int_a^b \|\mathbf{r}'(t)\|\, dt.$$

The formula for the arc length of a plane curve has a natural extension to a smooth curve in *space,* as stated in the next theorem.

THEOREM 12.6 Arc Length of a Space Curve

If C is a smooth curve given by $\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j} + z(t)\mathbf{k}$ on an interval $[a, b]$, then the arc length of C on the interval is

$$s = \int_a^b \sqrt{[x'(t)]^2 + [y'(t)]^2 + [z'(t)]^2}\, dt = \int_a^b \|\mathbf{r}'(t)\|\, dt.$$

Exploration

Arc Length Formula The formula for the arc length of a space curve is given in terms of the parametric equations used to represent the curve. Does this mean that the arc length of the curve depends on the parameter being used? Would you want this to be true? Explain your reasoning.

Here is a different parametric representation of the curve in Example 1.

$$\mathbf{r}(t) = t^2\mathbf{i} + \frac{4}{3}t^3\mathbf{j} + \frac{1}{2}t^4\mathbf{k}$$

Find the arc length from $t = 0$ to $t = \sqrt{2}$ and compare the result with that found in Example 1.



As t increases from 0 to 2, the vector $\mathbf{r}(t)$ traces out a curve.
Figure 12.28

EXAMPLE 1 Finding the Arc Length of a Curve in Space

See LarsonCalculus.com for an interactive version of this type of example.

Find the arc length of the curve given by

$$\mathbf{r}(t) = t\mathbf{i} + \frac{4}{3}t^{3/2}\mathbf{j} + \frac{1}{2}t^2\mathbf{k}$$

from $t = 0$ to $t = 2$, as shown in Figure 12.28.

Solution Using $x(t) = t$, $y(t) = \frac{4}{3}t^{3/2}$, and $z(t) = \frac{1}{2}t^2$, you obtain $x'(t) = 1$, $y'(t) = 2t^{1/2}$, and $z'(t) = t$. So, the arc length from $t = 0$ to $t = 2$ is given by

$$\begin{aligned}
s &= \int_0^2 \sqrt{[x'(t)]^2 + [y'(t)]^2 + [z'(t)]^2}\, dt && \text{Formula for arc length} \\
&= \int_0^2 \sqrt{1 + 4t + t^2}\, dt \\
&= \int_0^2 \sqrt{(t+2)^2 - 3}\, dt && \text{Integration tables (Appendix B), Formula 26} \\
&= \left[\frac{t+2}{2}\sqrt{(t+2)^2 - 3} - \frac{3}{2}\ln\left|(t+2) + \sqrt{(t+2)^2 - 3}\right|\right]_0^2 \\
&= 2\sqrt{13} - \frac{3}{2}\ln\left(4 + \sqrt{13}\right) - 1 + \frac{3}{2}\ln 3 \\
&\approx 4.816.
\end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Curve:
$\mathbf{r}(t) = b\cos t\mathbf{i} + b\sin t\mathbf{j} + \sqrt{1-b^2}\,t\mathbf{k}$



One turn of a helix
Figure 12.29

EXAMPLE 2 Finding the Arc Length of a Helix

Find the length of one turn of the helix given by

$$\mathbf{r}(t) = b\cos t\mathbf{i} + b\sin t\mathbf{j} + \sqrt{1-b^2}\,t\mathbf{k}$$

as shown in Figure 12.29.

Solution Begin by finding the derivative.

$$\mathbf{r}'(t) = -b\sin t\mathbf{i} + b\cos t\mathbf{j} + \sqrt{1-b^2}\mathbf{k}$$ Derivative

Now, using the formula for arc length, you can find the length of one turn of the helix by integrating $\|\mathbf{r}'(t)\|$ from 0 to 2π.

$$\begin{aligned} s &= \int_0^{2\pi} \|\mathbf{r}'(t)\|\,dt && \text{Formula for arc length} \\ &= \int_0^{2\pi} \sqrt{b^2(\sin^2 t + \cos^2 t) + (1-b^2)}\,dt \\ &= \int_0^{2\pi} dt \\ &= t\Big]_0^{2\pi} \\ &= 2\pi \end{aligned}$$

So, the length is 2π units. ■

Arc Length Parameter

You have learned that curves can be represented by vector-valued functions in different ways, depending on the choice of parameter. For *motion* along a curve, the convenient parameter is time t. For studying the *geometric properties* of a curve, however, the convenient parameter is often arc length s.

$s(t) = \int_a^t \sqrt{[x'(u)]^2 + [y'(u)]^2 + [z'(u)]^2}\,du$



Figure 12.30

Definition of Arc Length Function

Let C be a smooth curve given by $\mathbf{r}(t)$ defined on the closed interval $[a, b]$. For $a \le t \le b$, the **arc length function** is

$$s(t) = \int_a^t \|\mathbf{r}'(u)\|\,du = \int_a^t \sqrt{[x'(u)]^2 + [y'(u)]^2 + [z'(u)]^2}\,du.$$

The arc length s is called the **arc length parameter.** (See Figure 12.30.)

Note that the arc length function s is *nonnegative*. It measures the distance along C from the initial point $(x(a), y(a), z(a))$ to the point $(x(t), y(t), z(t))$.

Using the definition of the arc length function and the Second Fundamental Theorem of Calculus, you can conclude that

$$\frac{ds}{dt} = \|\mathbf{r}'(t)\|.$$ Derivative of arc length function

In differential form, you can write

$$ds = \|\mathbf{r}'(t)\|\,dt.$$ Differential form of arc length function

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The line segment from (3, 0) to (0, 4) can be parametrized using the arc length parameter s.
Figure 12.31

EXAMPLE 3 Finding the Arc Length Function for a Line

Find the arc length function $s(t)$ for the line segment given by

$$\mathbf{r}(t) = (3 - 3t)\mathbf{i} + 4t\mathbf{j}, \quad 0 \le t \le 1$$

and write $\mathbf{r}$ as a function of the parameter s. (See Figure 12.31.)

Solution Because $\mathbf{r}'(t) = -3\mathbf{i} + 4\mathbf{j}$ and

$$\|\mathbf{r}'(t)\| = \sqrt{(-3)^2 + 4^2} = 5$$

you have

$$\begin{aligned} s(t) &= \int_0^t \|\mathbf{r}'(u)\|\, du \\ &= \int_0^t 5\, du \\ &= 5t. \end{aligned}$$

Using $s = 5t$ (or $t = s/5$), you can rewrite $\mathbf{r}$ using the arc length parameter as follows.

$$\mathbf{r}(s) = \left(3 - \frac{3}{5}s\right)\mathbf{i} + \frac{4}{5}s\mathbf{j}, \quad 0 \le s \le 5$$

One of the advantages of writing a vector-valued function in terms of the arc length parameter is that $\|\mathbf{r}'(s)\| = 1$. For instance, in Example 3, you have

$$\|\mathbf{r}'(s)\| = \sqrt{\left(-\frac{3}{5}\right)^2 + \left(\frac{4}{5}\right)^2} = 1.$$

So, for a smooth curve C represented by $\mathbf{r}(s)$, where s is the arc length parameter, the arc length between a and b is

$$\begin{aligned} \text{Length of arc} &= \int_a^b \|\mathbf{r}'(s)\|\, ds \\ &= \int_a^b ds \\ &= b - a \\ &= \text{length of interval.} \end{aligned}$$

Furthermore, if t is *any* parameter such that $\|\mathbf{r}'(t)\| = 1$, then t must be the arc length parameter. These results are summarized in the next theorem, which is stated without proof.

THEOREM 12.7 Arc Length Parameter

If C is a smooth curve given by

$$\mathbf{r}(s) = x(s)\mathbf{i} + y(s)\mathbf{j} \qquad \text{Plane curve}$$

or

$$\mathbf{r}(s) = x(s)\mathbf{i} + y(s)\mathbf{j} + z(s)\mathbf{k} \qquad \text{Space curve}$$

where s is the arc length parameter, then

$$\|\mathbf{r}'(s)\| = 1.$$

Moreover, if t is *any* parameter for the vector-valued function $\mathbf{r}$ such that $\|\mathbf{r}'(t)\| = 1$, then t must be the arc length parameter.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Curvature at P is greater than at Q.
Figure 12.32



The magnitude of the rate of change of **T** with respect to the arc length is the curvature of a curve.
Figure 12.33

Curvature

An important use of the arc length parameter is to find **curvature**—the measure of how sharply a curve bends. For instance, in Figure 12.32, the curve bends more sharply at P than at Q, and you can say that the curvature is greater at P than at Q. You can calculate curvature by calculating the magnitude of the rate of change of the unit tangent vector $\mathbf{T}$ with respect to the arc length s, as shown in Figure 12.33.

Definition of Curvature

Let C be a smooth curve (in the plane *or* in space) given by $\mathbf{r}(s)$, where s is the arc length parameter. The **curvature** K at s is

$$K = \left\| \frac{d\mathbf{T}}{ds} \right\| = \|\mathbf{T}'(s)\|.$$

A circle has the same curvature at any point. Moreover, the curvature and the radius of the circle are inversely related. That is, a circle with a large radius has a small curvature, and a circle with a small radius has a large curvature. This inverse relationship is made explicit in the next example.

EXAMPLE 4 Finding the Curvature of a Circle

Show that the curvature of a circle of radius r is

$$K = \frac{1}{r}.$$



The curvature of a circle is constant.
Figure 12.34

Solution Without loss of generality, you can consider the circle to be centered at the origin. Let (x, y) be any point on the circle and let s be the length of the arc from $(r, 0)$ to (x, y), as shown in Figure 12.34. By letting θ be the central angle of the circle, you can represent the circle by

$$\mathbf{r}(\theta) = r\cos\theta\mathbf{i} + r\sin\theta\mathbf{j}. \qquad \theta \text{ is the parameter.}$$

Using the formula for the length of a circular arc $s = r\theta$, you can rewrite $\mathbf{r}(\theta)$ in terms of the arc length parameter as follows.

$$\mathbf{r}(s) = r\cos\frac{s}{r}\mathbf{i} + r\sin\frac{s}{r}\mathbf{j} \qquad \text{Arc length } s \text{ is the parameter.}$$

So, $\mathbf{r}'(s) = -\sin\frac{s}{r}\mathbf{i} + \cos\frac{s}{r}\mathbf{j}$, and it follows that $\|\mathbf{r}'(s)\| = 1$, which implies that the unit tangent vector is

$$\mathbf{T}(s) = \frac{\mathbf{r}'(s)}{\|\mathbf{r}'(s)\|} = -\sin\frac{s}{r}\mathbf{i} + \cos\frac{s}{r}\mathbf{j}$$

and the curvature is

$$K = \|\mathbf{T}'(s)\| = \left\| -\frac{1}{r}\cos\frac{s}{r}\mathbf{i} - \frac{1}{r}\sin\frac{s}{r}\mathbf{j} \right\| = \frac{1}{r}$$

at every point on the circle. ■

Because a straight line does not curve, you would expect its curvature to be 0. Try checking this by finding the curvature of the line given by

$$\mathbf{r}(s) = \left(3 - \frac{3}{5}s\right)\mathbf{i} + \frac{4}{5}s\mathbf{j}.$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 12.35

In Example 4, the curvature was found by applying the definition directly. This requires that the curve be written in terms of the arc length parameter s. The next theorem gives two other formulas for finding the curvature of a curve written in terms of an arbitrary parameter t. The proof of this theorem is left as an exercise [see Exercise 82, parts (a) and (b)].

THEOREM 12.8 Formulas for Curvature

If C is a smooth curve given by $\mathbf{r}(t)$, then the curvature K of C at t is

$$K = \frac{\|\mathbf{T}'(t)\|}{\|\mathbf{r}'(t)\|} = \frac{\|\mathbf{r}'(t) \times \mathbf{r}''(t)\|}{\|\mathbf{r}'(t)\|^3}.$$

Because $\|\mathbf{r}'(t)\| = ds/dt$, the first formula implies that curvature is the ratio of the rate of change of the unit tangent vector $\mathbf{T}$ to the rate of change of the arc length. To show that this is reasonable, let Δt be a "small number." Then,

$$\frac{\mathbf{T}'(t)}{ds/dt} \approx \frac{[\mathbf{T}(t + \Delta t) - \mathbf{T}(t)]/\Delta t}{[s(t + \Delta t) - s(t)]/\Delta t} = \frac{\mathbf{T}(t + \Delta t) - \mathbf{T}(t)}{s(t + \Delta t) - s(t)} = \frac{\Delta \mathbf{T}}{\Delta s}.$$

In other words, for a given Δs, the greater the length of $\Delta \mathbf{T}$, the more the curve bends at t, as shown in Figure 12.35.

EXAMPLE 5 Finding the Curvature of a Space Curve

Find the curvature of the curve given by

$$\mathbf{r}(t) = 2t\mathbf{i} + t^2\mathbf{j} - \frac{1}{3}t^3\mathbf{k}.$$

Solution It is not apparent whether this parameter represents arc length, so you should use the formula $K = \|\mathbf{T}'(t)\|/\|\mathbf{r}'(t)\|$.

$$\begin{aligned}
\mathbf{r}'(t) &= 2\mathbf{i} + 2t\mathbf{j} - t^2\mathbf{k} \\
\|\mathbf{r}'(t)\| &= \sqrt{4 + 4t^2 + t^4} && \text{Length of } \mathbf{r}'(t) \\
&= t^2 + 2 \\
\mathbf{T}(t) &= \frac{\mathbf{r}'(t)}{\|\mathbf{r}'(t)\|} \\
&= \frac{2\mathbf{i} + 2t\mathbf{j} - t^2\mathbf{k}}{t^2 + 2} \\
\mathbf{T}'(t) &= \frac{(t^2 + 2)(2\mathbf{j} - 2t\mathbf{k}) - (2t)(2\mathbf{i} + 2t\mathbf{j} - t^2\mathbf{k})}{(t^2 + 2)^2} \\
&= \frac{-4t\mathbf{i} + (4 - 2t^2)\mathbf{j} - 4t\mathbf{k}}{(t^2 + 2)^2} \\
\|\mathbf{T}'(t)\| &= \frac{\sqrt{16t^2 + 16 - 16t^2 + 4t^4 + 16t^2}}{(t^2 + 2)^2} \\
&= \frac{2(t^2 + 2)}{(t^2 + 2)^2} \\
&= \frac{2}{t^2 + 2} && \text{Length of } \mathbf{T}'(t)
\end{aligned}$$

So, the curvature is

$$K = \frac{\|\mathbf{T}'(t)\|}{\|\mathbf{r}'(t)\|} = \frac{2}{(t^2 + 2)^2}.$$ Curvature ■

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The next theorem presents a formula for calculating the curvature of a plane curve given by $y = f(x)$.

THEOREM 12.9 Curvature in Rectangular Coordinates

If C is the graph of a twice-differentiable function given by $y = f(x)$, then the curvature K at the point (x, y) is

$$K = \frac{|y''|}{[1 + (y')^2]^{3/2}}.$$

Proof By representing the curve C by $\mathbf{r}(x) = x\mathbf{i} + f(x)\mathbf{j} + 0\mathbf{k}$, where x is the parameter, you obtain $\mathbf{r}'(x) = \mathbf{i} + f'(x)\mathbf{j}$,

$$\|\mathbf{r}'(x)\| = \sqrt{1 + [f'(x)]^2}$$

and $\mathbf{r}''(x) = f''(x)\mathbf{j}$. Because $\mathbf{r}'(x) \times \mathbf{r}''(x) = f''(x)\mathbf{k}$, it follows that the curvature is

$$K = \frac{\|\mathbf{r}'(x) \times \mathbf{r}''(x)\|}{\|\mathbf{r}'(x)\|^3} \qquad \text{Theorem 12.8}$$

$$= \frac{|f''(x)|}{\{1 + [f'(x)]^2\}^{3/2}}$$

$$= \frac{|y''|}{[1 + (y')^2]^{3/2}}.$$



The circle of curvature

Figure 12.36

Let C be a curve with curvature K at point P. The circle passing through point P with radius $r = 1/K$ is called the **circle of curvature** when the circle lies on the concave side of the curve and shares a common tangent line with the curve at point P. The radius is called the **radius of curvature** at P, and the center of the circle is called the **center of curvature.**

The circle of curvature gives you a nice way to estimate the curvature K at a point P on a curve graphically. Using a compass, you can sketch a circle that lies against the concave side of the curve at point P, as shown in Figure 12.36. If the circle has a radius of r, then you can estimate the curvature to be $K = 1/r$.

EXAMPLE 6 Finding Curvature in Rectangular Coordinates

Find the curvature of the parabola given by

$$y = x - \frac{1}{4}x^2$$

at $x = 2$. Sketch the circle of curvature at $(2, 1)$.

Solution The curvature at $x = 2$ is as follows.

$$y' = 1 - \frac{x}{2} \qquad y' = 0 \qquad \text{First derivative}$$

$$y'' = -\frac{1}{2} \qquad y'' = -\frac{1}{2} \qquad \text{Second derivative}$$

$$K = \frac{|y''|}{[1 + (y')^2]^{3/2}} \qquad K = \frac{1}{2} \qquad \text{Curvature}$$



The circle of curvature

Figure 12.37

Because the curvature at $P(2, 1)$ is $\frac{1}{2}$, it follows that the radius of the circle of curvature at that point is 2. So, the center of curvature is $(2, -1)$, as shown in Figure 12.37. [In the figure, note that the curve has the greatest curvature at P. Try showing that the curvature at $Q(4, 0)$ is $1/2^{5/2} \approx 0.177$.]

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The amount of thrust felt by passengers in a car that is turning depends on two things—the speed of the car and the sharpness of the turn.
Figure 12.38

Arc length and curvature are closely related to the tangential and normal components of acceleration. The tangential component of acceleration is the rate of change of the speed, which in turn is the rate of change of the arc length. This component is negative as a moving object slows down and positive as it speeds up—regardless of whether the object is turning or traveling in a straight line. So, the tangential component is solely a function of the arc length and is independent of the curvature.

On the other hand, the normal component of acceleration is a function of *both* speed and curvature. This component measures the acceleration acting perpendicular to the direction of motion. To understand why the normal component is affected by both speed and curvature, imagine that you are driving a car around a turn, as shown in Figure 12.38. When your speed is high and the turn is sharp, you feel yourself thrown against the car door. By lowering your speed *or* taking a more gentle turn, you are able to lessen this sideways thrust.

The next theorem explicitly states the relationships among speed, curvature, and the components of acceleration.

REMARK Note that Theorem 12.10 gives additional formulas for $a_{\mathbf{T}}$ and $a_{\mathbf{N}}$.

THEOREM 12.10 Acceleration, Speed, and Curvature

If $\mathbf{r}(t)$ is the position vector for a smooth curve C, then the acceleration vector is given by

$$\mathbf{a}(t) = \frac{d^2s}{dt^2}\mathbf{T} + K\left(\frac{ds}{dt}\right)^2\mathbf{N}$$

where K is the curvature of C and ds/dt is the speed.

Proof For the position vector $\mathbf{r}(t)$, you have

$$\begin{aligned}\mathbf{a}(t) &= a_{\mathbf{T}}\mathbf{T} + a_{\mathbf{N}}\mathbf{N} \\ &= \frac{d}{dt}\left[\|\mathbf{v}\|\right]\mathbf{T} + \|\mathbf{v}\|\,\|\mathbf{T}'\|\mathbf{N} \\ &= \frac{d^2s}{dt^2}\mathbf{T} + \frac{ds}{dt}\left(\|\mathbf{v}\|K\right)\mathbf{N} \\ &= \frac{d^2s}{dt^2}\mathbf{T} + K\left(\frac{ds}{dt}\right)^2\mathbf{N}.\end{aligned}$$

EXAMPLE 7 Tangential and Normal Components of Acceleration

Find $a_{\mathbf{T}}$ and $a_{\mathbf{N}}$ for the curve given by

$$\mathbf{r}(t) = 2t\mathbf{i} + t^2\mathbf{j} - \tfrac{1}{3}t^3\mathbf{k}.$$

Solution From Example 5, you know that

$$\frac{ds}{dt} = \|\mathbf{r}'(t)\| = t^2 + 2 \quad \text{and} \quad K = \frac{2}{(t^2+2)^2}.$$

Therefore, the tangential component of acceleration is

$$a_{\mathbf{T}} = \frac{d^2s}{dt^2} = 2t \qquad \text{Tangential component}$$

and the normal component of acceleration is

$$a_{\mathbf{N}} = K\left(\frac{ds}{dt}\right)^2 = \frac{2}{(t^2+2)^2}(t^2+2)^2 = 2. \qquad \text{Normal component}$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Application

There are many applications in physics and engineering dynamics that involve the relationships among speed, arc length, curvature, and acceleration. One such application concerns frictional force.

A moving object with mass m is in contact with a stationary object. The total force required to produce an acceleration $\mathbf{a}$ along a given path is

$$\begin{aligned}\mathbf{F} &= m\mathbf{a} \\ &= m\left(\frac{d^2s}{dt^2}\right)\mathbf{T} + mK\left(\frac{ds}{dt}\right)^2\mathbf{N} \\ &= ma_{\mathbf{T}}\mathbf{T} + ma_{\mathbf{N}}\mathbf{N}.\end{aligned}$$

The portion of this total force that is supplied by the stationary object is called the **force of friction.** For example, when a car moving with constant speed is rounding a turn, the roadway exerts a frictional force that keeps the car from sliding off the road. If the car is not sliding, the frictional force is perpendicular to the direction of motion and has magnitude equal to the normal component of acceleration, as shown in Figure 12.39. The potential frictional force of a road around a turn can be increased by banking the roadway.



The force of friction is perpendicular to the direction of motion.
Figure 12.39

EXAMPLE 8 Frictional Force

A 360-kilogram go-cart is driven at a speed of 60 kilometers per hour around a circular racetrack of radius 12 meters, as shown in Figure 12.40. To keep the cart from skidding off course, what frictional force must the track surface exert on the tires?



Figure 12.40

Solution The frictional force must equal the mass times the normal component of acceleration. For this circular path, you know that the curvature is

$$K = \frac{1}{12}.$$ Curvature of circular racetrack

So, the frictional force is

$$\begin{aligned}ma_{\mathbf{N}} &= mK\left(\frac{ds}{dt}\right)^2 \\ &= (360\text{ kg})\left(\frac{1}{12\text{ m}}\right)\left(\frac{60{,}000\text{ m}}{3600\text{ sec}}\right)^2 \\ &\approx 8333\ (\text{kg})(\text{m})/\text{sec}^2.\end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Summary of Velocity, Acceleration, and Curvature

Unless noted otherwise, let C be a curve (in the plane or in space) given by the position vector

$$\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j} \qquad \text{Curve in the plane}$$

or

$$\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j} + z(t)\mathbf{k} \qquad \text{Curve in space}$$

where x, y, and z are twice-differentiable functions of t.

Velocity vector, speed, and acceleration vector

$$\mathbf{v}(t) = \mathbf{r}'(t) \qquad \text{Velocity vector}$$

$$\|\mathbf{v}(t)\| = \|\mathbf{r}'(t)\| = \frac{ds}{dt} \qquad \text{Speed}$$

$$\begin{aligned}\mathbf{a}(t) &= \mathbf{r}''(t) \qquad \text{Acceleration vector}\\ &= a_{\mathbf{T}}\mathbf{T}(t) + a_{\mathbf{N}}\mathbf{N}(t)\\ &= \frac{d^2s}{dt^2}\mathbf{T}(t) + K\left(\frac{ds}{dt}\right)^2\mathbf{N}(t) \qquad K \text{ is curvature and } \frac{ds}{dt} \text{ is speed.}\end{aligned}$$

Unit tangent vector and principal unit normal vector

$$\mathbf{T}(t) = \frac{\mathbf{r}'(t)}{\|\mathbf{r}'(t)\|} \qquad \text{Unit tangent vector}$$

$$\mathbf{N}(t) = \frac{\mathbf{T}'(t)}{\|\mathbf{T}'(t)\|} \qquad \text{Principal unit normal vector}$$

Components of acceleration

$$a_{\mathbf{T}} = \mathbf{a} \cdot \mathbf{T} = \frac{\mathbf{v} \cdot \mathbf{a}}{\|\mathbf{v}\|} = \frac{d^2s}{dt^2} \qquad \text{Tangential component of acceleration}$$

$$\begin{aligned}a_{\mathbf{N}} &= \mathbf{a} \cdot \mathbf{N} \qquad \text{Normal component of acceleration}\\ &= \frac{\|\mathbf{v} \times \mathbf{a}\|}{\|\mathbf{v}\|}\\ &= \sqrt{\|\mathbf{a}\|^2 - a_{\mathbf{T}}^2}\\ &= K\left(\frac{ds}{dt}\right)^2 \qquad K \text{ is curvature and } \frac{ds}{dt} \text{ is speed.}\end{aligned}$$

Formulas for curvature in the plane

$$K = \frac{|y''|}{[1 + (y')^2]^{3/2}} \qquad C \text{ given by } y = f(x)$$

$$K = \frac{|x'y'' - y'x''|}{[(x')^2 + (y')^2]^{3/2}} \qquad C \text{ given by } x = x(t),\ y = y(t)$$

Formulas for curvature in the plane or in space

$$K = \|\mathbf{T}'(s)\| = \|\mathbf{r}''(s)\| \qquad s \text{ is arc length parameter.}$$

$$K = \frac{\|\mathbf{T}'(t)\|}{\|\mathbf{r}'(t)\|} = \frac{\|\mathbf{r}'(t) \times \mathbf{r}''(t)\|}{\|\mathbf{r}'(t)\|^3} \qquad t \text{ is general parameter.}$$

$$K = \frac{\mathbf{a}(t) \cdot \mathbf{N}(t)}{\|\mathbf{v}(t)\|^2}$$

Cross product formulas apply only to curves in space.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

12.5 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Consider points P and Q on a curve. Explain what it means for the curvature at P to be less than the curvature at Q.
2. Let $\mathbf{r}(t)$ be a space curve. Explain how to determine whether t is the arc length parameter.

Finding the Arc Length of a Plane Curve **In Exercises 3–8, sketch the plane curve and find its length over the given interval.**

3. $\mathbf{r}(t) = 3t\mathbf{i} - t\mathbf{j}, \quad [0, 3]$
4. $\mathbf{r}(t) = t\mathbf{i} + t^2\mathbf{j}, \quad [0, 4]$
5. $\mathbf{r}(t) = t^3\mathbf{i} + t^2\mathbf{j}, \quad [0, 1]$
6. $\mathbf{r}(t) = t^2\mathbf{i} - 4t\mathbf{j}, \quad [0, 5]$
7. $\mathbf{r}(t) = a\cos^3 t\mathbf{i} + a\sin^3 t\mathbf{j}, \quad [0, 2\pi]$
8. $\mathbf{r}(t) = a\cos t\mathbf{i} + a\sin t\mathbf{j}, \quad [0, 2\pi]$
9. **Projectile Motion** The position of a baseball is represented by $\mathbf{r}(t) = 50\sqrt{2}t\mathbf{i} + (3 + 50\sqrt{2}t - 16t^2)\mathbf{j}$. Find the arc length of the trajectory of the baseball.
10. **Projectile Motion** The position of a baseball is represented by $\mathbf{r}(t) = 40\sqrt{3}t\mathbf{i} + (4 + 40t - 16t^2)\mathbf{j}$. Find the arc length of the trajectory of the baseball.

Finding the Arc Length of a Curve in Space **In Exercises 11–16, sketch the space curve and find its length over the given interval.**

11. $\mathbf{r}(t) = -t\mathbf{i} + 4t\mathbf{j} + 3t\mathbf{k}, \quad [0, 1]$
12. $\mathbf{r}(t) = \mathbf{i} + t^2\mathbf{j} + t^3\mathbf{k}, \quad [0, 2]$
13. $\mathbf{r}(t) = \langle 4t, -\cos t, \sin t\rangle, \quad \left[0, \frac{3\pi}{2}\right]$
14. $\mathbf{r}(t) = \langle 2\sin t, 5t, 2\cos t\rangle, \quad [0, \pi]$
15. $\mathbf{r}(t) = a\cos t\mathbf{i} + a\sin t\mathbf{j} + bt\mathbf{k}, \quad [0, 2\pi]$
16. $\mathbf{r}(t) = \langle \cos t + t\sin t, \sin t - t\cos t, t^2\rangle, \quad \left[0, \frac{\pi}{2}\right]$
17. **Investigation** Consider the graph of the vector-valued function $\mathbf{r}(t) = t\mathbf{i} + (4 - t^2)\mathbf{j} + t^3\mathbf{k}$ on the interval $[0, 2]$.
    (a) Approximate the length of the curve by finding the length of the line segment connecting its endpoints.
    (b) Approximate the length of the curve by summing the lengths of the line segments connecting the terminal points of the vectors $\mathbf{r}(0)$, $\mathbf{r}(0.5)$, $\mathbf{r}(1)$, $\mathbf{r}(1.5)$, and $\mathbf{r}(2)$.
    (c) Describe how you could obtain a more accurate approximation by continuing the processes in parts (a) and (b).
    (d) Use the integration capabilities of a graphing utility to approximate the length of the curve. Compare this result with the answers in parts (a) and (b).
18. **Investigation** Consider the helix represented by the vector-valued function $\mathbf{r}(t) = \langle 2\cos t, 2\sin t, t\rangle$.
    (a) Write the length of the arc s on the helix as a function of t by evaluating the integral
    $$s = \int_0^t \sqrt{[x'(u)]^2 + [y'(u)]^2 + [z'(u)]^2}\, du.$$
    (b) Solve for t in the relationship derived in part (a), and substitute the result into the original vector-valued function. This yields a parametrization of the curve in terms of the arc length parameter s.
    (c) Find the coordinates of the point on the helix for arc lengths $s = \sqrt{5}$ and $s = 4$.
    (d) Verify that $\|\mathbf{r}'(s)\| = 1$.

Finding Curvature **In Exercises 19–22, find the curvature of the curve, where s is the arc length parameter.**

19. $\mathbf{r}(s) = \left(1 + \frac{\sqrt{2}}{2}s\right)\mathbf{i} + \left(1 - \frac{\sqrt{2}}{2}s\right)\mathbf{j}$
20. $\mathbf{r}(s) = (3 + s)\mathbf{i} + \mathbf{j}$
21. $\mathbf{r}(s) = \cos\frac{1}{2}s\mathbf{i} + \frac{\sqrt{3}}{2}s\mathbf{j} + \sin\frac{1}{2}s\mathbf{k}$
22. $\mathbf{r}(s) = \cos s\mathbf{i} + \sin s\mathbf{j} + 5\mathbf{k}$

Finding Curvature **In Exercises 23–28, find the curvature of the plane curve at the given value of the parameter.**

23. $\mathbf{r}(t) = 4t\mathbf{i} - 2t\mathbf{j}, \quad t = 1$
24. $\mathbf{r}(t) = t^2\mathbf{i} + \mathbf{j}, \quad t = 2$
25. $\mathbf{r}(t) = t\mathbf{i} + \frac{1}{t}\mathbf{j}, \quad t = 1$
26. $\mathbf{r}(t) = t\mathbf{i} + \frac{1}{9}t^3\mathbf{j}, \quad t = 2$
27. $\mathbf{r}(t) = \langle t, \sin t\rangle, \quad t = \frac{\pi}{2}$
28. $\mathbf{r}(t) = \langle 5\cos t, 4\sin t\rangle, \quad t = \frac{\pi}{3}$

Finding Curvature **In Exercises 29–36, find the curvature of the curve.**

29. $\mathbf{r}(t) = 4\cos 2\pi t\mathbf{i} + 4\sin 2\pi t\mathbf{j}$
30. $\mathbf{r}(t) = 2\cos \pi t\mathbf{i} + \sin \pi t\mathbf{j}$
31. $\mathbf{r}(t) = a\cos \omega t\mathbf{i} + a\sin \omega t\mathbf{j}$
32. $\mathbf{r}(t) = a\cos \omega t\mathbf{i} + b\sin \omega t\mathbf{j}$
33. $\mathbf{r}(t) = t\mathbf{i} + t^2\mathbf{j} + \frac{t^2}{2}\mathbf{k}$
34. $\mathbf{r}(t) = 2t^2\mathbf{i} + t\mathbf{j} + \frac{1}{2}t^2\mathbf{k}$
35. $\mathbf{r}(t) = 4t\mathbf{i} + 3\cos t\mathbf{j} + 3\sin t\mathbf{k}$
36. $\mathbf{r}(t) = e^{2t}\mathbf{i} + e^{2t}\cos t\mathbf{j} + e^{2t}\sin t\mathbf{k}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding Curvature **In Exercises 37–40, find the curvature of the curve at the point P.**

37. $\mathbf{r}(t) = 3t\mathbf{i} + 2t^2\mathbf{j}, \quad P(-3, 2)$

38. $\mathbf{r}(t) = e^t\mathbf{i} + 4t\mathbf{j}, \quad P(1, 0)$

39. $\mathbf{r}(t) = t\mathbf{i} + t^2\mathbf{j} + \frac{t^3}{4}\mathbf{k}, \quad P(2, 4, 2)$

40. $\mathbf{r}(t) = e^t \cos t\mathbf{i} + e^t \sin t\mathbf{j} + e^t\mathbf{k}, \quad P(1, 0, 1)$

Finding Curvature in Rectangular Coordinates **In Exercises 41–48, find the curvature and radius of curvature of the plane curve at the given value of x.**

41. $y = 6x, \quad x = 3$

42. $y = x - \frac{4}{x}, \quad x = 2$

43. $y = 5x^2 + 7, \quad x = -1$

44. $y = 2\sqrt{9 - x^2}, \quad x = 0$

45. $y = \sin 2x, \quad x = \frac{\pi}{4}$

46. $y = e^{-x/4}, \quad x = 8$

47. $y = x^3, \quad x = 2$

48. $y = x^n, \quad x = 1, \quad n \geq 2$

Maximum Curvature **In Exercises 49–54, (a) find the point on the curve at which the curvature is a maximum and (b) find the limit of the curvature as $x \to \infty$.**

49. $y = (x - 1)^2 + 3$

50. $y = x^3$

51. $y = x^{2/3}$

52. $y = \frac{1}{x}$

53. $y = \ln x$

54. $y = e^x$

Curvature **In Exercises 55–58, find all points on the graph of the function such that the curvature is zero.**

55. $y = 1 - x^4$

56. $y = (x - 2)^6 + 3x$

57. $y = \cos\frac{x}{2}$

58. $y = \sin x$

Exploring Concepts

59. Consider the function $f(x) = e^{cx}$. What value(s) of c produce a maximum curvature at $x = 0$?

60. Given a twice-differentiable function $y = f(x)$, determine its curvature at a relative extremum. Can the curvature ever be greater than it is at a relative extremum? Explain.

61. Investigation Consider the function $f(x) = x^4 - x^2$.

(a) Use a graphing utility to find the curvature K of the curve as a function of x.

(b) Use the result of part (a) to find the circles of curvature to the graph of f when $x = 0$ and $x = 1$. Use a graphing utility to graph the function and the two circles of curvature.

(c) Graph the function $K(x)$ and compare it with the graph of $f(x)$. For example, do the extrema of f and K occur at the same critical numbers? Explain your reasoning.

62. Motion of a Particle A particle moves along the plane curve C described by $\mathbf{r}(t) = t\mathbf{i} + t^2\mathbf{j}$.

(a) Find the length of C on the interval $0 \leq t \leq 2$.

(b) Find the curvature of C at $t = 0$, $t = 1$, and $t = 2$.

(c) Describe the curvature of C as t changes from $t = 0$ to $t = 2$.

63. Investigation Find all a and b such that the two curves given by

$$y_1 = ax(b - x) \quad \text{and} \quad y_2 = \frac{x}{x + 2}$$

intersect at only one point and have a common tangent line and equal curvature at that point. Sketch a graph for each set of values of a and b.

64. HOW DO YOU SEE IT? Using the graph of the ellipse, at what point(s) is the curvature the least and the greatest?



65. Sphere and Paraboloid A sphere of radius 4 is dropped into the paraboloid given by $z = x^2 + y^2$.

(a) How close will the sphere come to the vertex of the paraboloid?

(b) What is the radius of the largest sphere that will touch the vertex?

66. Speed

The smaller the curvature of a bend in a road, the faster a car can travel. Assume that the maximum speed around a turn is inversely proportional to the square root of the curvature. A car moving on the path $y = \frac{1}{3}x^3$, where x and y are measured in miles, can safely go 30 miles per hour at $\left(1, \frac{1}{3}\right)$. How fast can it go at $\left(\frac{3}{2}, \frac{9}{8}\right)$?

67. Center of Curvature Let C be a curve given by $y = f(x)$. Let K be the curvature $(K \neq 0)$ at the point $P(x_0, y_0)$ and let

$$z = \frac{1 + f'(x_0)^2}{f''(x_0)}.$$

Show that the coordinates (α, β) of the center of curvature at P are $(\alpha, \beta) = (x_0 - f'(x_0)z, y_0 + z)$.

Bannafarsai_Stock/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

68. Center of Curvature Use the result of Exercise 67 to find the center of curvature for the curve at the given point.

(a) $y = e^x$, $(0, 1)$ (b) $y = \frac{x^2}{2}$, $\left(1, \frac{1}{2}\right)$ (c) $y = x^2$, $(0, 0)$

69. Curvature A curve C is given by the polar equation $r = f(\theta)$. Show that the curvature K at the point (r, θ) is

$$K = \frac{|2(r')^2 - rr'' + r^2|}{[(r')^2 + r^2]^{3/2}}.$$

[*Hint:* Represent the curve by $\mathbf{r}(\theta) = r\cos\theta\mathbf{i} + r\sin\theta\mathbf{j}$.]

70. Curvature Use the result of Exercise 69 to find the curvature of each polar curve.

(a) $r = 1 + \sin\theta$ (b) $r = \theta$

(c) $r = a\sin\theta$ (d) $r = e^{\theta}$

71. Curvature Given the polar curve $r = e^{a\theta}$, $a > 0$, use the result of Exercise 69 to find the curvature K and determine the limit of K as (a) $\theta \to \infty$ and (b) $a \to \infty$.

72. Curvature at the Pole Show that the formula for the curvature of a polar curve $r = f(\theta)$ given in Exercise 69 reduces to $K = 2/|r'|$ for the curvature at the pole.

Curvature at the Pole **In Exercises 73 and 74, use the result of Exercise 72 to find the curvature of the rose curve at the pole.**

73. $r = 4\sin 2\theta$ **74.** $r = \cos 3\theta$

75. Proof For a smooth curve given by the parametric equations $x = f(t)$ and $y = g(t)$, prove that the curvature is given by

$$K = \frac{|f'(t)g''(t) - g'(t)f''(t)|}{\{[f'(t)]^2 + [g'(t)]^2\}^{3/2}}.$$

76. Horizontal Asymptotes Use the result of Exercise 75 to find the curvature K of the curve represented by the parametric equations $x(t) = t^3$ and $y(t) = \frac{1}{2}t^2$. Use a graphing utility to graph K and determine any horizontal asymptotes. Interpret the asymptotes in the context of the problem.

77. Curvature of a Cycloid Use the result of Exercise 75 to find the curvature K of the cycloid represented by the parametric equations

$$x(\theta) = a(\theta - \sin\theta) \quad \text{and} \quad y(\theta) = a(1 - \cos\theta).$$

What are the minimum and maximum values of K?

78. Tangential and Normal Components of Acceleration Use Theorem 12.10 to find $a_{\mathbf{T}}$ and $a_{\mathbf{N}}$ for each curve given by the vector-valued function.

(a) $\mathbf{r}(t) = 3t^2\mathbf{i} + (3t - t^3)\mathbf{j}$

(b) $\mathbf{r}(t) = t\mathbf{i} + t^2\mathbf{j} + \frac{1}{2}t^2\mathbf{k}$

79. Frictional Force A 5500-pound vehicle is driven at a speed of 30 miles per hour on a circular interchange of radius 100 feet. To keep the vehicle from skidding off course, what frictional force must the road surface exert on the tires?

80. Frictional Force A 6400-pound vehicle is driven at a speed of 35 miles per hour on a circular interchange of radius 250 feet. To keep the vehicle from skidding off course, what frictional force must the road surface exert on the tires?

81. Curvature Verify that the curvature at any point (x, y) on the graph of $y = \cosh x$ is $1/y^2$.

82. Formulas for Curvature Use the definition of curvature in space, $K = \|\mathbf{T}'(s)\| = \|\mathbf{r}''(s)\|$, to verify each formula.

(a) $K = \dfrac{\|\mathbf{T}'(t)\|}{\|\mathbf{r}'(t)\|}$

(b) $K = \dfrac{\|\mathbf{r}'(t) \times \mathbf{r}''(t)\|}{\|\mathbf{r}'(t)\|^3}$

(c) $K = \dfrac{\mathbf{a}(t) \cdot \mathbf{N}(t)}{\|\mathbf{v}(t)\|^2}$

True or False? **In Exercises 83–86, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

83. The arc length of a space curve depends on the parametrization.

84. The curvature of a plane curve at an inflection point is zero.

85. The curvature of a parabola is a maximum at its vertex.

86. The normal component of acceleration is a function of both speed and curvature.

Kepler's Laws **In Exercises 87–94, you are asked to verify Kepler's Laws of Planetary Motion. For these exercises, assume that each planet moves in an orbit given by the vector-valued function r. Let $r = \|\mathbf{r}\|$, let G represent the universal gravitational constant, let M represent the mass of the sun, and let m represent the mass of the planet.**

87. Prove that $\mathbf{r} \cdot \mathbf{r}' = r\dfrac{dr}{dt}$.

88. Using Newton's Second Law of Motion, $\mathbf{F} = m\mathbf{a}$, and Newton's Second Law of Gravitation

$$\mathbf{F} = -\frac{GmM}{r^3}\mathbf{r}$$

show that $\mathbf{a}$ and $\mathbf{r}$ are parallel, and that $\mathbf{r}(t) \times \mathbf{r}'(t) = \mathbf{L}$ is a constant vector. So, $\mathbf{r}(t)$ moves *in a fixed plane,* orthogonal to $\mathbf{L}$.

89. Prove that $\dfrac{d}{dt}\left[\dfrac{\mathbf{r}}{r}\right] = \dfrac{1}{r^3}[(\mathbf{r} \times \mathbf{r}') \times \mathbf{r}]$.

90. Show that $\dfrac{\mathbf{r}'}{GM} \times \mathbf{L} - \dfrac{\mathbf{r}}{r} = \mathbf{e}$ is a constant vector.

91. Prove Kepler's First Law: Each planet moves in an elliptical orbit with the sun as a focus.

92. Assume that the elliptical orbit

$$r = \frac{ed}{1 + e\cos\theta}$$

is in the xy-plane, with $\mathbf{L}$ along the z-axis. Prove that

$$\|\mathbf{L}\| = r^2\frac{d\theta}{dt}.$$

93. Prove Kepler's Second Law: Each ray from the sun to a planet sweeps out equal areas of the ellipse in equal times.

94. Prove Kepler's Third Law: The square of the period of a planet's orbit is proportional to the cube of the mean distance between the planet and the sun.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Review Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Exploring Concepts

This chapter combined your knowledge of vectors with that of functions. For a real-valued function f, the derivative $f'(x)$ is a scalar that indicates the rate of change of f at x. Contrast this with a vector-valued function $\mathbf{r}(t)$, where the derivative $\mathbf{r}'(t)$ is a vector that indicates the magnitude *and* the rate of change of $\mathbf{r}$ at t. The calculus of real-valued functions, limits, derivatives, and integrals also applies to vector-valued functions. One of the most important applications of vector-valued functions is modeling velocity and acceleration, whether in a plane or in space.

Vector	In the Plane	In Space
Position	$\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j}$	$\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j} + z(t)\mathbf{k}$
Velocity	$\mathbf{v}(t) = x'(t)\mathbf{i} + y'(t)\mathbf{j}$	$\mathbf{v}(t) = x'(t)\mathbf{i} + y'(t)\mathbf{j} + z'(t)\mathbf{k}$
Acceleration	$\mathbf{a}(t) = x''(t)\mathbf{i} + y''(t)\mathbf{j}$	$\mathbf{a}(t) = x''(t)\mathbf{i} + y''(t)\mathbf{j} + z''(t)\mathbf{k}$

Vector-valued functions are also useful when investigating the features of space curves, such as arc length, curvature, and tangent and normal vectors.

1. In your own words, describe the domain and range of a vector-valued function.

2. Define the derivative of a vector-valued function.

3. Explain how a particle can be accelerating even though its speed is constant.

4. Consider the vector-valued function

$\mathbf{r}(t) = t\mathbf{i} + (4 - t^2)\mathbf{j}$.

(a) Sketch the graph of $\mathbf{r}(t)$. Use a graphing utility to verify your sketch.

(b) Sketch the vectors $\mathbf{r}(1)$, $\mathbf{r}(1.25)$, and $\mathbf{r}(1.25) - \mathbf{r}(1)$ on the graph in part (a).

(c) Compare the vector $\mathbf{r}'(1)$ with the vector

$$\frac{\mathbf{r}(1.25) - \mathbf{r}(1)}{1.25 - 1}.$$

5. Two circles of curvature to the graph of $f(x) = \sin x$ are shown in the figure. (a) Find the equation of the smaller circle, and (b) write a short paragraph explaining why the circles have different radii.



Figure for 5



Figure for 6

6. A civil engineer designs a highway as shown in the figure. BC is an arc of the circle. AB and CD are straight lines tangent to the circular arc. Criticize the design.

Domain and Continuity

In Exercises 7–10, (a) find the domain of r, and (b) determine the interval(s) on which the function is continuous.

7. $\mathbf{r}(t) = \tan t\mathbf{i} + \mathbf{j} + t\mathbf{k}$

8. $\mathbf{r}(t) = \sqrt{t}\mathbf{i} + \dfrac{1}{t-4}\mathbf{j} + \mathbf{k}$

9. $\mathbf{r}(t) = \sqrt{t^2 - 9}\mathbf{i} - \mathbf{j} + \ln(t-1)\mathbf{k}$

10. $\mathbf{r}(t) = (2t+1)\mathbf{i} + t^2\mathbf{j} + t\mathbf{k}$

Evaluating a Function

In Exercises 11 and 12, evaluate the vector-valued function at each given value of t.

11. $\mathbf{r}(t) = (2t+1)\mathbf{i} + t^2\mathbf{j} - \sqrt{t+2}\mathbf{k}$

(a) $\mathbf{r}(0)$ (b) $\mathbf{r}(-2)$ (c) $\mathbf{r}(c-1)$

(d) $\mathbf{r}(1 + \Delta t) - \mathbf{r}(1)$

12. $\mathbf{r}(t) = 3\cos t\mathbf{i} + (1 - \sin t)\mathbf{j} - t\mathbf{k}$

(a) $\mathbf{r}(0)$ (b) $\mathbf{r}\left(\dfrac{\pi}{2}\right)$ (c) $\mathbf{r}(s - \pi)$

(d) $\mathbf{r}(\pi + \Delta t) - \mathbf{r}(\pi)$

Writing a Vector-Valued Function

In Exercises 13 and 14, represent the line segment from P to Q by a vector-valued function and by a set of parametric equations.

13. $P(3, 0, 5)$, $Q(2, -2, 3)$ **14.** $P(-2, -3, 8)$, $Q(5, 1, -2)$

Sketching a Curve

In Exercises 15–18, sketch the curve represented by the vector-valued function and give the orientation of the curve.

15. $\mathbf{r}(t) = \langle \pi\cos t, \pi\sin t \rangle$ **16.** $\mathbf{r}(t) = \langle t + 2, t^2 - 1 \rangle$

17. $\mathbf{r}(t) = (t+1)\mathbf{i} + (3t-1)\mathbf{j} + 2t\mathbf{k}$

18. $\mathbf{r}(t) = 2\cos t\mathbf{i} + t\mathbf{j} + 2\sin t\mathbf{k}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Representing a Graph by a Vector-Valued Function

In Exercises 19 and 20, represent the plane curve by a vector-valued function. (There are many correct answers.)

19. $3x + 4y - 12 = 0$ **20.** $y = 9 - x^2$

Representing a Graph by a Vector-Valued Function

In Exercises 21 and 22, sketch the space curve represented by the intersection of the surfaces. Then use the parameter $x = t$ to find a vector-valued function for the space curve.

21. $z = x^2 + y^2, \quad y = 2$ **22.** $x^2 + z^2 = 4, \quad x - y = 0$

Finding a Limit

In Exercises 23 and 24, find the limit.

23. $\lim_{t\to 3}\left(\sqrt{3-t}\,\mathbf{i} + \ln t\,\mathbf{j} - \frac{1}{t}\mathbf{k}\right)$

24. $\lim_{t\to 0}\left(\frac{\sin 2t}{t}\mathbf{i} + e^{-t}\mathbf{j} + 4\mathbf{k}\right)$

Higher-Order Differentiation

In Exercises 25 and 26, find (a) $\mathbf{r}'(t)$, (b) $\mathbf{r}''(t)$, and (c) $\mathbf{r}'(t) \cdot \mathbf{r}''(t)$.

25. $\mathbf{r}(t) = (t^2 + 4t)\mathbf{i} - 3t^2\mathbf{j}$ **26.** $\mathbf{r}(t) = 5\cos t\,\mathbf{i} + 2\sin t\,\mathbf{j}$

Higher-Order Differentiation

In Exercises 27 and 28, find (a) $\mathbf{r}'(t)$, (b) $\mathbf{r}''(t)$, (c) $\mathbf{r}'(t) \cdot \mathbf{r}''(t)$, and (d) $\mathbf{r}'(t) \times \mathbf{r}''(t)$.

27. $\mathbf{r}(t) = 2t^3\mathbf{i} + 4t\mathbf{j} - t^2\mathbf{k}$

28. $\mathbf{r}(t) = (4t + 3)\mathbf{i} + t^2\mathbf{j} + (2t^2 + 4)\mathbf{k}$

Finding Intervals on Which a Curve Is Smooth

In Exercises 29 and 30, find all open intervals on which the curve given by the vector-valued function is smooth.

29. $\mathbf{r}(t) = (t - 1)^3\mathbf{i} + (t - 1)^4\mathbf{j}$

30. $\mathbf{r}(t) = \frac{t}{t-2}\mathbf{i} + t\mathbf{j} + \sqrt{1+t}\,\mathbf{k}$

Using Properties of the Derivative

In Exercises 31 and 32, use the properties of the derivative to find the following.

(a) $\mathbf{r}'(t)$ **(b)** $\frac{d}{dt}[\mathbf{u}(t) - 2\mathbf{r}(t)]$ **(c)** $\frac{d}{dt}[(3t)\mathbf{r}(t)]$

(d) $\frac{d}{dt}[\mathbf{r}(t) \cdot \mathbf{u}(t)]$ **(e)** $\frac{d}{dt}[\mathbf{r}(t) \times \mathbf{u}(t)]$ **(f)** $\frac{d}{dt}[\mathbf{u}(2t)]$

31. $\mathbf{r}(t) = 3t\mathbf{i} + (t - 1)\mathbf{j}, \quad \mathbf{u}(t) = t\mathbf{i} + t^2\mathbf{j} + \frac{2}{3}t^3\mathbf{k}$

32. $\mathbf{r}(t) = \sin t\,\mathbf{i} + \cos t\,\mathbf{j} + t\mathbf{k}, \quad \mathbf{u}(t) = \sin t\,\mathbf{i} + \cos t\,\mathbf{j} + \frac{1}{t}\mathbf{k}$

Finding an Indefinite Integral

In Exercises 33–36, find the indefinite integral.

33. $\int (t^2\mathbf{i} + 5t\mathbf{j} + 8t^3\mathbf{k})\,dt$

34. $\int (6\mathbf{i} - 2t\mathbf{j} + \ln t\,\mathbf{k})\,dt$

35. $\int \left(3\sqrt{t}\,\mathbf{i} + \frac{2}{t}\mathbf{j} + \mathbf{k}\right)dt$

36. $\int (\sin t\,\mathbf{i} + \mathbf{j} + e^{2t}\,\mathbf{k})\,dt$

Evaluating a Definite Integral

In Exercises 37–40, evaluate the definite integral.

37. $\int_{-2}^{2} (3t\mathbf{i} + 2t^2\mathbf{j} - t^3\mathbf{k})\,dt$ **38.** $\int_{0}^{3} \left(t\mathbf{i} + \sqrt{t}\,\mathbf{j} + 4t\mathbf{k}\right)dt$

39. $\int_{0}^{2} (e^{t/2}\mathbf{i} - 3t^2\mathbf{j} - \mathbf{k})\,dt$

40. $\int_{0}^{\pi/3} (2\cos t\,\mathbf{i} + \sin t\,\mathbf{j} + 3\mathbf{k})\,dt$

Finding an Antiderivative

In Exercises 41 and 42, find $\mathbf{r}(t)$ that satisfies the initial condition.

41. $\mathbf{r}'(t) = 2t\mathbf{i} + e^t\mathbf{j} + e^{-t}\mathbf{k}, \quad \mathbf{r}(0) = \mathbf{i} + 3\mathbf{j} - 5\mathbf{k}$

42. $\mathbf{r}'(t) = \sec t\,\mathbf{i} + \tan t\,\mathbf{j} + t^2\mathbf{k}, \quad r(0) = 3\mathbf{k}$

Finding Velocity and Acceleration Vectors in Space

In Exercises 43–46, the position vector $\mathbf{r}$ describes the path of an object moving in space. (a) Find the velocity vector, speed, and acceleration vector of the object. (b) Evaluate the velocity vector and acceleration vector of the object at the given value of t.

	Position Vector	Time
43.	$\mathbf{r}(t) = 4t\mathbf{i} + t^3\mathbf{j} - t\mathbf{k}$	$t = 1$
44.	$\mathbf{r}(t) = \sqrt{t}\,\mathbf{i} + 5t\mathbf{j} + 2t^2\mathbf{k}$	$t = 4$
45.	$\mathbf{r}(t) = \langle \cos^3 t, \sin^3 t, 3t\rangle$	$t = \pi$
46.	$\mathbf{r}(t) = \langle t, -\tan t, e^t\rangle$	$t = 0$

Projectile Motion

In Exercises 47 and 48, use the model for projectile motion, assuming there is no air resistance and $g = 32$ feet per second per second.

47. A baseball is hit from a height of 3.5 feet above the ground with an initial speed of 120 feet per second and at an angle of 30° above the horizontal. Find the maximum height reached by the baseball. Determine whether it will clear an eight-foot-high fence located 375 feet from home plate.

48. Determine the maximum height and range of a projectile fired at a height of 6 feet above the ground with an initial speed of 400 feet per second and an angle of 60° above the horizontal.

Finding the Unit Tangent Vector

In Exercises 49 and 50, find the unit tangent vector to the curve at the specified value of the parameter.

49. $\mathbf{r}(t) = 6t\mathbf{i} - t^2\mathbf{j}, \quad t = 2$

50. $\mathbf{r}(t) = 2\sin t\,\mathbf{i} + 4\cos t\,\mathbf{j}, \quad t = \pi/6$

Finding a Tangent Line

In Exercises 51 and 52, find the unit tangent vector $\mathbf{T}(t)$ and a set of parametric equations for the tangent line to the space curve at point P.

51. $\mathbf{r}(t) = e^{2t}\mathbf{i} + \cos t\,\mathbf{j} - \sin 3t\,\mathbf{k}, \quad P(1, 1, 0)$

52. $\mathbf{r}(t) = t\mathbf{i} + t^2\mathbf{j} + \frac{2}{3}t^3\mathbf{k}, \quad P\left(2, 4, \frac{16}{3}\right)$

Finding the Principal Unit Normal Vector

In Exercises 53–56, find the principal unit normal vector to the curve at the specified value of the parameter.

53. $\mathbf{r}(t) = 2t\mathbf{i} + 3t^2\mathbf{j}, \quad t = 1$ **54.** $\mathbf{r}(t) = t\mathbf{i} + \ln t\,\mathbf{j}, \quad t = 2$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

55. $\mathbf{r}(t) = 3\cos 2t\mathbf{i} + 3\sin 2t\mathbf{j} + 3\mathbf{k}, \quad t = \dfrac{\pi}{4}$

56. $\mathbf{r}(t) = 4\cos t\mathbf{i} + 4\sin t\mathbf{j} + \mathbf{k}, \quad t = \dfrac{2\pi}{3}$

Finding Tangential and Normal Components of Acceleration **In Exercises 57 and 58, find the tangential and normal components of acceleration at the given time t for the plane curve $\mathbf{r}(t)$.**

57. $\mathbf{r}(t) = \dfrac{3}{t}\mathbf{i} - 6t\mathbf{j}, \quad t = 3$

58. $\mathbf{r}(t) = 3\cos 2t\mathbf{i} + 3\sin 2t\mathbf{j}, \quad t = \dfrac{\pi}{6}$

Finding Tangential and Normal Components of Acceleration **In Exercises 59 and 60, find the tangential and normal components of acceleration at the given time t for the space curve $\mathbf{r}(t)$.**

59. $\mathbf{r}(t) = \sin t\mathbf{i} - 3t\mathbf{j} + \cos t\mathbf{k}, \quad t = \dfrac{\pi}{6}$

60. $\mathbf{r}(t) = \dfrac{t^3}{3}\mathbf{i} - 6t\mathbf{j} + t^2\mathbf{k}, \quad t = 2$

Finding the Arc Length of a Plane Curve **In Exercises 61–64, sketch the plane curve and find its length over the given interval.**

61. $\mathbf{r}(t) = 2t\mathbf{i} - 3t\mathbf{j}, \quad [0, 5]$

62. $\mathbf{r}(t) = t^2\mathbf{i} + 2t\mathbf{k}, \quad [0, 3]$

63. $\mathbf{r}(t) = 2\sin t\mathbf{i} + \mathbf{j}, \quad \left[\dfrac{\pi}{2}, \pi\right]$

64. $\mathbf{r}(t) = 10\cos t\mathbf{i} + 10\sin t\mathbf{j}, \quad [0, 2\pi]$

Finding the Arc Length of a Curve in Space **In Exercises 65–68, sketch the space curve and find its length over the given interval.**

65. $\mathbf{r}(t) = -3t\mathbf{i} + 2t\mathbf{j} + 4t\mathbf{k}, \quad [0, 3]$

66. $\mathbf{r}(t) = t\mathbf{i} + t^2\mathbf{j} + 2t\mathbf{k}, \quad [0, 2]$

67. $\mathbf{r}(t) = \langle 8\cos t, 8\sin t, t\rangle, \quad \left[0, \dfrac{\pi}{2}\right]$

68. $\mathbf{r}(t) = \langle 2(\sin t - t\cos t), 2(\cos t + t\sin t), t\rangle, \quad \left[0, \dfrac{\pi}{2}\right]$

Finding Curvature **In Exercises 69–72, find the curvature of the curve.**

69. $\mathbf{r}(t) = 3t\mathbf{i} + 2t\mathbf{j}$

70. $\mathbf{r}(t) = 2\sqrt{t}\mathbf{i} + 3t\mathbf{j}$

71. $\mathbf{r}(t) = 2t\mathbf{i} + \frac{1}{2}t^2\mathbf{j} + t^2\mathbf{k}$

72. $\mathbf{r}(t) = 2t\mathbf{i} + 5\cos t\mathbf{j} + 5\sin t\mathbf{k}$

Finding Curvature **In Exercises 73 and 74, find the curvature of the curve at the point P.**

73. $\mathbf{r}(t) = \frac{1}{2}t^2\mathbf{i} + t\mathbf{j} + \frac{1}{3}t^3\mathbf{k}, \quad P\left(\frac{1}{2}, 1, \frac{1}{3}\right)$

74. $\mathbf{r}(t) = 4\cos t\mathbf{i} + 3\sin t\mathbf{j} + t\mathbf{k}, \quad P(-4, 0, \pi)$

Finding Curvature in Rectangular Coordinates **In Exercises 75–78, find the curvature and radius of curvature of the plane curve at the given value of x.**

75. $y = \frac{1}{2}x^2 + x, \quad x = 4$

76. $y = e^{-x/2}, \quad x = 0$

77. $y = \ln x, \quad x = 1$

78. $y = \tan x, \quad x = \dfrac{\pi}{4}$

Building on Concepts

In Exercises 79–81, use the *binormal vector* defined by the equation $\mathbf{B} = \mathbf{T} \times \mathbf{N}$.

79. Find the unit tangent, principal unit normal, and binormal vectors for the helix

$\mathbf{r}(t) = 4\cos t\mathbf{i} + 4\sin t\mathbf{j} + 3t\mathbf{k}$

at $t = \pi/2$. Sketch the helix together with these three mutually orthogonal unit vectors.

80. Find the unit tangent, principal unit normal, and binormal vectors for the curve

$\mathbf{r}(t) = \cos t\mathbf{i} + \sin t\mathbf{j} - \mathbf{k}$

at $t = \pi/4$. Sketch the curve together with these three mutually orthogonal unit vectors.

81. (a) Prove that there exists a scalar τ, called the **torsion,** such that $d\mathbf{B}/ds = -\tau\mathbf{N}$.

(b) Prove that $d\mathbf{N}/ds = -K\mathbf{T} + \tau\mathbf{B}$.

(The three equations $d\mathbf{T}/ds = K\mathbf{N}$, $d\mathbf{N}/ds = -K\mathbf{T} + \tau\mathbf{B}$, and $d\mathbf{B}/ds = -\tau\mathbf{N}$ are called the *Frenet-Serret formulas*.)

82. The **cornu spiral** is given by

$$x(t) = \int_0^t \cos\left(\frac{\pi u^2}{2}\right) du \quad \text{and} \quad y(t) = \int_0^t \sin\left(\frac{\pi u^2}{2}\right) du.$$

The spiral shown in the figure was graphed over the interval $-\pi \le t \le \pi$.



Generated by Mathematica

(a) Find the arc length of this curve from $t = 0$ to $t = a$.

(b) Find the curvature of the graph when $t = a$.

(c) The cornu spiral was discovered by James Bernoulli. He found that the spiral has an amazing relationship between curvature and arc length. What is this relationship?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.S. Problem Solving

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

1. Projectile Motion During an air show, a plane is flying horizontally at an altitude of 3200 feet with a speed of 400 feet per second when it releases a heavy target. A projectile is launched 5 seconds later from a cannon at a site facing the plane and 5000 feet from the point that was directly beneath the plane when the target was released, as shown in the figure. The projectile is to intercept the target at an altitude of 1600 feet. Determine the required initial speed and angle of inclination of the projectile. (Ignore air resistance.)



2. Radius of Curvature Let T be the tangent line at the point $P(x, y)$ on the graph of the curve $x^{2/3} + y^{2/3} = a^{2/3}$, $a > 0$, as shown in the figure. Show that the radius of curvature at P is three times the distance from the origin to the tangent line T.



3. Proof If $\mathbf{r}(t)$ is a nonzero differentiable function of t, prove that

$$\frac{d}{dt}\left[\|\mathbf{r}(t)\|\right] = \frac{\mathbf{r}(t) \cdot \mathbf{r}'(t)}{\|\mathbf{r}(t)\|}.$$

4. Satellite A communications satellite moves in a circular orbit around Earth at a distance of 42,000 kilometers from the center of Earth. The angular speed

$$\frac{d\theta}{dt} = \omega = \frac{\pi}{12} \text{ radian per hour}$$

is constant.

(a) Use polar coordinates to show that the acceleration vector is given by

$$\mathbf{a} = \frac{d^2\mathbf{r}}{dt^2} = \left[\frac{d^2r}{dt^2} - r\left(\frac{d\theta}{dt}\right)^2\right]\mathbf{u}_r + \left[r\frac{d^2\theta}{dt^2} + 2\frac{dr}{dt}\frac{d\theta}{dt}\right]\mathbf{u}_\theta$$

where $\mathbf{u}_r = \cos\theta\mathbf{i} + \sin\theta\mathbf{j}$ is the unit vector in the radial direction and $\mathbf{u}_\theta = -\sin\theta\mathbf{i} + \cos\theta\mathbf{j}$.

(b) Find the radial and angular components of acceleration for the satellite.

5. Cycloid Consider one arch of the cycloid

$$\mathbf{r}(\theta) = (\theta - \sin\theta)\mathbf{i} + (1 - \cos\theta)\mathbf{j}, \quad 0 \le \theta \le 2\pi$$

as shown in the figure. Let $s(\theta)$ be the arc length from the highest point on the arch to the point $(x(\theta), y(\theta))$, and let $\rho(\theta) = 1/K$ be the radius of curvature at the point $(x(\theta), y(\theta))$. Show that s and ρ are related by the equation $s^2 + \rho^2 = 16$. (This equation is called a *natural equation* for the curve.)



6. Cardioid Consider the cardioid

$$r = 1 - \cos\theta, \quad 0 \le \theta \le 2\pi$$

as shown in the figure. Let $s(\theta)$ be the arc length from the point $(2, \pi)$ on the cardioid to the point (r, θ), and let $p(\theta) = 1/K$ be the radius of curvature at the point (r, θ). Show that s and ρ are related by the equation $s^2 + 9\rho^2 = 16$. (This equation is called a *natural equation* for the curve.)



7. Exit Ramp A highway has an exit ramp that begins at the origin of a coordinate system and follows the curve

$$y = \frac{1}{32}x^{5/2}$$

to the point (4, 1) (see figure). Then it follows a circular path whose curvature is that given by the curve at (4, 1). What is the radius of the circular arc? Explain why the curve and the circular arc should have the same curvature at (4, 1).



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

13 Functions of Several Variables

GO DIGITAL

13.1 Introduction to Functions of Several Variables
13.2 Limits and Continuity
13.3 Partial Derivatives
13.4 Differentials
13.5 Chain Rules for Functions of Several Variables
13.6 Directional Derivatives and Gradients
13.7 Tangent Planes and Normal Lines
13.8 Extrema of Functions of Two Variables
13.9 Applications of Extrema
13.10 Lagrange Multipliers

CalcView®

CalcChat®


Chapter 13
Section 1
Exercise 57
GO
The level curves are of the form
So, the level curves are circles passing through the origin and centered at (±1/2c, 0).
PREV. 47 49 51 53 55 57 59 61 63 65 67 NEXT

Ocean Floor *(Exercise 66, p. 930)*

Wind Chill *(Exercise 27, p. 910)*

left, NaturePicsFilms/Shutterstock.com; right, Ipedan/Shutterstock.com
Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

13.1 Introduction to Functions of Several Variables

GO DIGITAL

- Describe the notation for a function of several variables.
- Sketch the graph of a function of two variables.
- Sketch level curves for a function of two variables.
- Sketch level surfaces for a function of three variables.
- Use a graphing utility to graph a function of two variables.

Big Ideas of Calculus

Calculus was originally developed to study functions of a single variable. It was later discovered that the two basic operations of calculus—differentiation and integration—can be meaningfully extended to functions of two or more variables.

Graphically, functions of *one* variable are represented by curves in the plane. Graphs of functions of *two* variables are represented by surfaces in space.

Functions of Several Variables

So far in this text, you have dealt only with functions of a single (independent) variable. Many familiar quantities, however, are functions of two or more variables. Here are three examples.

1. The work done by a force, $W = FD$, is a function of two variables.
2. The volume of a right circular cylinder, $V = \pi r^2 h$, is a function of two variables.
3. The volume of a rectangular solid, $V = lwh$, is a function of three variables.

The notation for a function of two or more variables is similar to that for a function of a single variable. Here are two examples.

$$z = \underbrace{f(x, y)}_{\text{2 variables}} = x^2 + xy \qquad \text{Function of two variables}$$

and

$$w = \underbrace{f(x, y, z)}_{\text{3 variables}} = x + 2y - 3z \qquad \text{Function of three variables}$$

Definition of a Function of Two Variables

Let D be a set of ordered pairs of real numbers. If to each ordered pair (x, y) in D there corresponds a unique real number $f(x, y)$, then f is a **function of x and y.** The set D is the **domain** of f, and the corresponding set of values for $f(x, y)$ is the **range** of f. For the function

$$z = f(x, y)$$

x and y are called the **independent variables** and z is called the **dependent variable.**

Exploration

Without using a graphing utility, describe the graph of each function of two variables.

a. $z = x^2 + y^2$
b. $z = x + y$
c. $z = x^2 + y$
d. $z = \sqrt{x^2 + y^2}$
e. $z = \sqrt{1 - x^2 + y^2}$

Similar definitions can be given for functions of three, four, or n variables, where the domains consist of ordered triples (x_1, x_2, x_3), quadruples (x_1, x_2, x_3, x_4), and n-tuples $(x_1, x_2, \ldots, x_n)$. In all cases, the range is a set of real numbers. In this chapter, you will study only functions of two or three variables.

As with functions of one variable, the most common way to describe a function of several variables is with an *equation*, and unless it is otherwise restricted, you can assume that the domain is the set of all points for which the equation is defined. For instance, the domain of the function

$$f(x, y) = x^2 + y^2$$

is the entire xy-plane. Similarly, the domain of

$$f(x, y) = \ln xy$$

is the set of all points (x, y) in the plane for which $xy > 0$. This consists of all points in the first and third quadrants.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 13.1

EXAMPLE 1 Domains of Functions of Several Variables

Find the domain of each function.

a. $f(x, y) = \dfrac{\sqrt{x^2 + y^2 - 9}}{x}$ **b.** $g(x, y, z) = \dfrac{x}{\sqrt{9 - x^2 - y^2 - z^2}}$

Solution

a. The function f is defined for all points (x, y) such that $x \neq 0$ and

$$x^2 + y^2 \geq 9.$$

So, the domain is the set of all points lying on or outside the circle $x^2 + y^2 = 9$ *except* those points on the y-axis, as shown in Figure 13.1.

b. The function g is defined for all points (x, y, z) such that

$$x^2 + y^2 + z^2 < 9.$$

Consequently, the domain is the set of all points (x, y, z) lying inside a sphere of radius 3 that is centered at the origin. ■

Functions of several variables can be combined in the same ways as functions of single variables. For instance, you can form the sum, difference, product, and quotient of two functions of two variables as follows.

$$(f \pm g)(x, y) = f(x, y) \pm g(x, y) \quad \text{Sum or difference}$$
$$(fg)(x, y) = f(x, y)g(x, y) \quad \text{Product}$$
$$\frac{f}{g}(x, y) = \frac{f(x, y)}{g(x, y)}, \quad g(x, y) \neq 0 \quad \text{Quotient}$$

MARY FAIRFAX SOMERVILLE (1780–1872)

Somerville was interested in the problem of creating geometric models for functions of several variables. Her most well-known book, *The Mechanics of the Heavens*, was published in 1831.

See LarsonCalculus.com to read more of this biography.

You cannot form the composite of two functions of several variables. You can, however, form the **composite** function $(g \circ h)(x, y)$, where g is a function of a single variable and h is a function of two variables.

$$(g \circ h)(x, y) = g(h(x, y)) \quad \text{Composition}$$

The domain of this composite function consists of all (x, y) in the domain of h such that $h(x, y)$ is in the domain of g. For example, the function

$$f(x, y) = \sqrt{16 - 4x^2 - y^2}$$

can be viewed as the composite of the function of two variables given by

$$h(x, y) = 16 - 4x^2 - y^2$$

and the function of a single variable given by

$$g(u) = \sqrt{u}.$$

The domain of this function is the set of all points lying on or inside the ellipse $4x^2 + y^2 = 16$.

A function that can be written as a sum of functions of the form $cx^m y^n$ (where c is a real number and m and n are nonnegative integers) is called a **polynomial function** of two variables. For instance, the functions

$$f(x, y) = x^2 + y^2 - 2xy + x + 2 \quad \text{and} \quad g(x, y) = 3xy^2 + x - 2$$

are polynomial functions of two variables. A **rational function** is the quotient of two polynomial functions. Similar terminology is used for functions of more than two variables.

GO DIGITAL

Chronicle/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

The Graph of a Function of Two Variables



Figure 13.2

As with functions of a single variable, you can learn a lot about the behavior of a function of two variables by sketching its graph. The **graph** of a function f of two variables is the set of all points (x, y, z) for which $z = f(x, y)$ and (x, y) is in the domain of f. This graph can be interpreted geometrically as a *surface in space,* as discussed in Sections 11.5 and 11.6. In Figure 13.2, note that the graph of $z = f(x, y)$ is a surface whose projection onto the xy-plane is D, the domain of f. To each point (x, y) in D there corresponds a point (x, y, z) on the surface, and, conversely, to each point (x, y, z) on the surface there corresponds a point (x, y) in D.

EXAMPLE 2 Describing the Graph of a Function of Two Variables

Consider the function given by

$$f(x, y) = \sqrt{16 - 4x^2 - y^2}.$$

a. Find the domain and range of the function.

b. Describe the graph of f.

Solution

a. The domain D implied by the equation of f is the set of all points (x, y) such that

$$16 - 4x^2 - y^2 \geq 0. \qquad \text{Quantity inside radical must be nonnegative.}$$

So, D is the set of all points lying on or inside the ellipse

$$\frac{x^2}{4} + \frac{y^2}{16} = 1. \qquad \text{Ellipse in the } xy\text{-plane}$$

The range of f is all values $z = f(x, y)$ such that $0 \leq z \leq \sqrt{16}$, or

$$0 \leq z \leq 4. \qquad \text{Range of } f$$



The graph of $f(x, y) = \sqrt{16 - 4x^2 - y^2}$ is the upper half of an ellipsoid.

Figure 13.3

b. A point (x, y, z) is on the graph of f if and only if

$$z = \sqrt{16 - 4x^2 - y^2}$$
$$z^2 = 16 - 4x^2 - y^2$$
$$4x^2 + y^2 + z^2 = 16$$
$$\frac{x^2}{4} + \frac{y^2}{16} + \frac{z^2}{16} = 1, \quad 0 \leq z \leq 4.$$

From Section 11.6, you know that the graph of f is the upper half of an ellipsoid, as shown in Figure 13.3. ■



Figure 13.4

To sketch a surface in space without a graphing utility, it helps to use traces in planes parallel to the coordinate planes, as shown in Figure 13.3. For example, to find the trace of the surface in the plane $z = 2$, substitute $z = 2$ in the equation $z = \sqrt{16 - 4x^2 - y^2}$ and obtain

$$2 = \sqrt{16 - 4x^2 - y^2} \quad \Rightarrow \quad \frac{x^2}{3} + \frac{y^2}{12} = 1.$$

So, the trace is an ellipse centered at the point $(0, 0, 2)$ with major and minor axes of lengths $4\sqrt{3}$ and $2\sqrt{3}$.

Traces are also used with most three-dimensional graphing utilities. For instance, Figure 13.4 shows a computer-generated version of the surface given in Example 2. For this graph, the computer took 25 traces parallel to the xy-plane and 12 traces in vertical planes.

If you have access to a three-dimensional graphing utility, use it to graph several surfaces.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Level Curves

A second way to visualize a function of two variables is to use a **scalar field** in which the scalar

$$z = f(x, y)$$

is assigned to the point (x, y). A scalar field can be characterized by **level curves** (or **contour lines**) along which the value of $f(x, y)$ is constant. For instance, the weather map in Figure 13.5 shows level curves of equal pressure called **isobars.** In weather maps for which the level curves represent points of equal temperature, the level curves are called **isotherms,** as shown in Figure 13.6. Another common use of level curves is in representing electric potential fields. In this type of map, the level curves are called **equipotential lines.**



Level curves show the lines of equal pressure (isobars), measured in millibars.

Figure 13.5



Level curves show the lines of equal temperature (isotherms), measured in degrees Fahrenheit.

Figure 13.6

Contour maps are commonly used to show regions on Earth's surface, with the level curves representing the height above sea level. This type of map is called a **topographic map.** For example, the mountain shown in Figure 13.7 is represented by the topographic map in Figure 13.8.

Figure 13.7

Figure 13.8

A contour map depicts the variation of z with respect to x and y by the spacing between level curves. Much space between level curves indicates that z is changing slowly, whereas little space indicates a rapid change in z. Furthermore, to produce a good three-dimensional illusion in a contour map, it is important to choose c-values that are *evenly spaced.*

Drewthehobbit/Shutterstock.com

USGS

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 3 Sketching a Contour Map

The hemisphere

$$f(x, y) = \sqrt{64 - x^2 - y^2}$$

is shown in Figure 13.9. Sketch a contour map of this surface using level curves corresponding to $c = 0, 1, 2, \ldots, 8$.

Solution For each value of c, the equation $f(x, y) = c$ is a circle (or point) in the xy-plane. For example, when $c_1 = 0$, the level curve is

$$x^2 + y^2 = 64 \qquad \text{Circle of radius 8}$$

which is a circle of radius 8. Figure 13.10 shows the nine level curves for the hemisphere.



Hemisphere
Figure 13.9



Contour map
Figure 13.10



Hyperbolic paraboloid
Figure 13.11

EXAMPLE 4 Sketching a Contour Map

See LarsonCalculus.com for an interactive version of this type of example.

The hyperbolic paraboloid

$$z = y^2 - x^2$$

is shown in Figure 13.11. Sketch a contour map of this surface.

Solution For each value of c, let $f(x, y) = c$ and sketch the resulting level curve in the xy-plane. For this function, each of the level curves ($c \neq 0$) is a hyperbola whose asymptotes are the lines $y = \pm x$. When $c < 0$, the transverse axis is horizontal. For instance, the level curve for $c = -4$ is

$$\frac{x^2}{2^2} - \frac{y^2}{2^2} = 1.$$

When $c > 0$, the transverse axis is vertical. For instance, the level curve for $c = 4$ is

$$\frac{y^2}{2^2} - \frac{x^2}{2^2} = 1.$$

When $c = 0$, the level curve is the degenerate conic representing the intersecting asymptotes, as shown in Figure 13.12.



Hyperbolic level curves (at increments of 2)
Figure 13.12

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

One example of a function of two variables used in economics is the **Cobb-Douglas production function.** This function is used as a model to represent the numbers of units produced by varying amounts of labor and capital. If x measures the units of labor and y measures the units of capital, then the number of units produced is

$$f(x, y) = Cx^a y^{1-a}$$

where C and a are constants with $0 < a < 1$.

EXAMPLE 5 The Cobb-Douglas Production Function

A manufacturer estimates a production function to be

$$f(x, y) = 100x^{0.6}y^{0.4}$$

where x is the number of units of labor and y is the number of units of capital. Compare the production level when $x = 1000$ and $y = 500$ with the production level when $x = 2000$ and $y = 1000$.

Solution When $x = 1000$ and $y = 500$, the production level is

$$f(1000, 500) = 100(1000^{0.6})(500^{0.4}) \approx 75{,}786.$$

When $x = 2000$ and $y = 1000$, the production level is

$$f(2000, 1000) = 100(2000^{0.6})(1000^{0.4}) \approx 151{,}572.$$

The level curves of $z = f(x, y)$ are shown in Figure 13.13. Note that by doubling both x and y, you double the production level (see Exercise 83).



Level curves (at increments of 10,000)
Figure 13.13

Level Surfaces

The concept of a level curve can be extended by one dimension to define a **level surface.** If f is a function of three variables and c is a constant, then the graph of the equation

$$f(x, y, z) = c$$

is a **level surface** of f, as shown in Figure 13.14.



Level surfaces of f
Figure 13.14

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



Figure 13.15

EXAMPLE 6 **Level Surfaces**

Describe the level surfaces of

$$f(x, y, z) = 4x^2 + y^2 + z^2.$$

Solution Each level surface has an equation of the form

$$4x^2 + y^2 + z^2 = c. \qquad \text{Equation of level surface}$$

So, the level surfaces are ellipsoids (whose cross sections parallel to the yz-plane are circles). As c increases, the radii of the circular cross sections increase according to the square root of c. For example, the level surfaces corresponding to the values $c = 0$, $c = 4$, and $c = 16$ are as follows.

$$4x^2 + y^2 + z^2 = 0 \qquad \text{Level surface for } c = 0 \text{ (single point)}$$

$$\frac{x^2}{1} + \frac{y^2}{4} + \frac{z^2}{4} = 1 \qquad \text{Level surface for } c = 4 \text{ (ellipsoid)}$$

$$\frac{x^2}{4} + \frac{y^2}{16} + \frac{z^2}{16} = 1 \qquad \text{Level surface for } c = 16 \text{ (ellipsoid)}$$

These level surfaces are shown in Figure 13.15. ■

If the function in Example 6 represented the *temperature* at the point (x, y, z), then the level surfaces shown in Figure 13.15 would be called **isothermal surfaces.**

Graphing Utilities and Surfaces

The problem of sketching the graph of a surface in space can be simplified by using a graphing utility. Although there are several types of three-dimensional graphing utilities, most use some form of trace analysis to give the illusion of three dimensions. To use such a graphing utility, you usually need to enter the equation of the surface and the region in the xy-plane over which the surface is to be plotted. (You might also need to enter the number of traces to be taken.) For instance, to graph the surface

$$f(x, y) = (x^2 + y^2)e^{1-x^2-y^2}$$

you might choose the following bounds for x, y, and z.

$$-3 \le x \le 3 \qquad \text{Bounds for } x$$

$$-3 \le y \le 3 \qquad \text{Bounds for } y$$

$$0 \le z \le 3 \qquad \text{Bounds for } z$$

Figure 13.16 shows a computer-generated graph of this surface using 26 traces taken parallel to the yz-plane. To heighten the three-dimensional effect, the graphing utility uses a "hidden line" routine. That is, it begins by plotting the traces in the foreground (those corresponding to the largest x-values), and then, as each new trace is plotted, the graphing utility determines whether all or only part of the next trace should be shown.

The graphs on the next page show a variety of surfaces. Use a graphing utility to reproduce these surfaces. Remember also that the three-dimensional graphics in this text can be viewed and rotated. These rotatable graphs are available at *LarsonCalculus.com.*



Figure 13.16

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Three different views of the graph of $f(x, y) = (2 - y^2 + x^2)e^{1-x^2-(y^2/4)}$



Single traces | Double traces | Level curves

Traces and level curves of the graph of $f(x, y) = \dfrac{-4x}{x^2 + y^2 + 1}$



$f(x, y) = \sin x \sin y$ | $f(x, y) = -\dfrac{1}{\sqrt{x^2 + y^2}}$ | $f(x, y) = \dfrac{1 - x^2 - y^2}{\sqrt{|1 - x^2 - y^2|}}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

13.1 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain why $z^2 = x + 3y$ is not a function of x and y.
2. What is a graph of a function of two variables? How is it interpreted geometrically?
3. Use the graph to determine whether z is a function of x and y. Explain.



4. Explain how to sketch a contour map of a function of x and y.

Determining Whether an Equation Is a Function

In Exercises 5–8, determine whether z is a function of x and y.

5. $x^2z + 3y^2 - xy = 10$
6. $xz^2 + 2xy - y^2 = 4$
7. $\frac{x^2}{4} + \frac{y^2}{9} + z^2 = 1$
8. $z + x \ln y - 8yz = 0$

Evaluating a Function

In Exercises 9–20, evaluate the function at the given values of the independent variables. Simplify the results.

9. $f(x, y) = 2x - y + 3$
   (a) $f(0, 2)$ (b) $f(-1, 0)$
   (c) $f(5, 30)$ (d) $f(3, y)$
   (e) $f(x, 4)$ (f) $f(5, t)$
10. $f(x, y) = 4 - x^2 - 4y^2$
   (a) $f(0, 0)$ (b) $f(0, 1)$
   (c) $f(2, 3)$ (d) $f(1, y)$
   (e) $f(x, 0)$ (f) $f(t, 1)$
11. $f(x, y) = xe^y$
   (a) $f(-1, 0)$ (b) $f(0, 2)$
   (c) $f(x, 3)$ (d) $f(t, -y)$
12. $g(x, y) = \ln|x + y|$
   (a) $g(1, 0)$ (b) $g(0, -t^2)$
   (c) $g(e, 0)$ (d) $g(e, e)$
13. $h(x, y, z) = \frac{xy}{z}$
   (a) $h(-1, 3, -1)$
   (b) $h(2, 2, 2)$
   (c) $h(4, 4t, t^2)$
   (d) $h(-3, 2, 5)$
14. $f(x, y, z) = \sqrt{x + y + z}$
   (a) $f(2, 2, 5)$
   (b) $f(0, 6, -2)$
   (c) $f(8, -7, 2)$
   (d) $f(0, 1, -1)$
15. $f(x, y) = x \sin y$
   (a) $f(2, \pi/4)$
   (b) $f(3, 1)$
   (c) $f(-3, 0)$
   (d) $f(4, \pi/2)$
16. $V(r, h) = \pi r^2 h$
   (a) $V(3, 10)$
   (b) $V(5, 2)$
   (c) $V(4, 8)$
   (d) $V(6, \pi)$
17. $g(x, y) = \int_x^y (2t - 3)\, dt$
   (a) $g(4, 0)$ (b) $g(4, 1)$ (c) $g\left(4, \frac{3}{2}\right)$ (d) $g\left(\frac{3}{2}, 0\right)$
18. $g(x, y) = \int_x^y \frac{1}{t}\, dt$
   (a) $g(4, 1)$ (b) $g(6, 3)$ (c) $g(2, 5)$ (d) $g\left(\frac{1}{2}, 7\right)$
19. $f(x, y) = 2x + y^2$
   (a) $\frac{f(x + \Delta x, y) - f(x, y)}{\Delta x}$ (b) $\frac{f(x, y + \Delta y) - f(x, y)}{\Delta y}$
20. $f(x, y) = 3x^2 - 2y$
   (a) $\frac{f(x + \Delta x, y) - f(x, y)}{\Delta x}$ (b) $\frac{f(x, y + \Delta y) - f(x, y)}{\Delta y}$

Finding the Domain and Range of a Function

In Exercises 21–32, find the domain and range of the function.

21. $f(x, y) = 3x^2 - y$
22. $f(x, y) = e^{xy}$
23. $g(x, y) = x\sqrt{y}$
24. $g(x, y) = \frac{y}{\sqrt{x}}$
25. $z = \frac{x + y}{xy}$
26. $z = \frac{xy}{x + y}$
27. $f(x, y) = \sqrt{4 - x^2 - y^2}$
28. $f(x, y) = \sqrt{9 - 6x^2 + y^2}$
29. $f(x, y) = \arccos(x + y)$
30. $f(x, y) = \arcsin(y/x)$
31. $f(x, y) = \ln(5 - x - y)$
32. $f(x, y) = \ln(xy - 6)$

33. **Think About It** The graphs labeled (a), (b), (c), and (d) are graphs of the function

$$f(x, y) = \frac{-4x}{x^2 + y^2 + 1}.$$

Match each of the four graphs with the point in space from which the surface is viewed. The four points are $(20, 15, 25)$, $(-15, 10, 20)$, $(20, 20, 0)$, and $(20, 0, 0)$.

(a)



Generated by Maple

(b)



Generated by Maple

(c)



Generated by Maple

(d)



Generated by Maple

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

34. Think About It Use the function given in Exercise 33.

(a) Find the domain and range of the function.

(b) Identify the points in the xy-plane at which the function value is 0.

(c) Does the surface pass through all the octants of the rectangular coordinate system? Give reasons for your answer.

Sketching a Surface **In Exercises 35–42, describe and sketch the surface given by the function.**

35. $f(x, y) = 4$

36. $f(x, y) = 6 - 2x - 3y$

37. $f(x, y) = y^2$

38. $g(x, y) = \frac{1}{2}y$

39. $z = -x^2 - y^2$

40. $z = \frac{1}{2}\sqrt{x^2 + y^2}$

41. $f(x, y) = e^{-x}$

42. $f(x, y) = \begin{cases} xy, & x \geq 0, y \geq 0 \\ 0, & x < 0 \text{ or } y < 0 \end{cases}$

Graphing a Function Using Technology **In Exercises 43–46, use a graphing utility to graph the function.**

43. $z = y^2 - x^2 + 1$

44. $z = \frac{1}{12}\sqrt{144 - 16x^2 - 9y^2}$

45. $f(x, y) = x^2e^{(-xy/2)}$

46. $f(x, y) = x \sin y$

Matching **In Exercises 47–50, match the graph of the surface with one of the contour maps. [The contour maps are labeled (a), (b), (c), and (d).]**

(a)



(b)



(c)



(d)



47. $f(x, y) = e^{1-x^2-y^2}$



48. $f(x, y) = e^{1-x^2+y^2}$



49. $f(x, y) = \ln|y - x^2|$



50. $f(x, y) = \cos\left(\frac{x^2 + 2y^2}{4}\right)$



Sketching a Contour Map **In Exercises 51–58, describe the level curves of the function. Sketch a contour map of the surface using level curves for the given c-values.**

51. $z = x + y$, $c = -1, 0, 2, 4$

52. $z = 6 - 2x - 3y$, $c = 0, 2, 4, 6, 8, 10$

53. $z = x^2 + 4y^2$, $c = 0, 1, 2, 3, 4$

54. $f(x, y) = \sqrt{9 - x^2 - y^2}$, $c = 0, 1, 2, 3$

55. $f(x, y) = xy$, $c = \pm 1, \pm 2, \ldots, \pm 6$

56. $f(x, y) = e^{xy/2}$, $c = 2, 3, 4, \frac{1}{2}, \frac{1}{3}, \frac{1}{4}$

57. $f(x, y) = x/(x^2 + y^2)$, $c = \pm\frac{1}{2}, \pm 1, \pm\frac{3}{2}, \pm 2$

58. $f(x, y) = \ln(x - y)$, $c = 0, \pm\frac{1}{2}, \pm 1, \pm\frac{3}{2}, \pm 2$

Graphing Level Curves Using Technology **In Exercises 59–62, use a graphing utility to graph six level curves of the function.**

59. $f(x, y) = x^2 - y^2 + 2$

60. $f(x, y) = |xy|$

61. $g(x, y) = \dfrac{8}{1 + x^2 + y^2}$

62. $h(x, y) = 3 \sin(|x| + |y|)$

Exploring Concepts

63. Does the Vertical Line Test apply to functions of two variables? Explain your reasoning.

64. All of the level curves of the surface given by $z = f(x, y)$ are concentric circles. Does this imply that the graph of f is a hemisphere? Give an example that supports your answer.

65. Construct a function whose level curves are lines passing through the origin.

66. Consider the function $f(x, y) = xy$ for $x \geq 0$ and $y \geq 0$.

(a) Sketch the graph of the surface given by f.

(b) Make a conjecture about the relationship between the graphs of f and $g(x, y) = f(x, y) - 3$. Explain your reasoning.

(c) Repeat part (b) for $g(x, y) = -f(x, y)$.

(d) Repeat part (b) for $g(x, y) = \frac{1}{2}f(x, y)$.

(e) On the surface in part (a), sketch the graph of $z = f(x, x)$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Writing **In Exercises 67 and 68, use the graphs of the level curves (c-values evenly spaced) of the function f to write a description of a possible graph of f. Is the graph of f unique? Explain.**

67.



68.



69. Investment In 2020, an investment of \$1000 was made in a bond earning 6% compounded annually. Assume that the buyer pays tax at rate R and the annual rate of inflation is I. In the year 2030, the value V of the investment in constant 2020 dollars is

$$V(I, R) = 1000\left[\frac{1 + 0.06(1 - R)}{1 + I}\right]^{10}.$$

Use this function of two variables to complete the table.

	Inflation Rate		
Tax Rate	0	0.03	0.05
0			
0.28			
0.35			

70. Investment A principal of \$5000 is deposited in a savings account that earns interest at a rate of r (written as a decimal), compounded continuously. The amount $A(r, t)$ after t years is

$$A(r, t) = 5000e^{rt}.$$

Use this function of two variables to complete the table.

	Number of Years			
Rate	5	10	15	20
0.02				
0.03				
0.04				
0.05				

Sketching a Level Surface **In Exercises 71–76, describe and sketch the graph of the level surface $f(x, y, z) = c$ at the given value of c.**

71. $f(x, y, z) = x - y + z,\ c = 1$

72. $f(x, y, z) = 4x + y + 2z,\ c = 4$

73. $f(x, y, z) = x^2 + y^2 + z^2,\ c = 9$

74. $f(x, y, z) = x^2 + \frac{1}{4}y^2 - z,\ c = 1$

75. $f(x, y, z) = 4x^2 + 4y^2 - z^2,\ c = 0$

76. $f(x, y, z) = \sin x - z,\ c = 0$

77. Forestry

The *Doyle Log Rule* is one of several methods used to determine the lumber yield of a log (in board-feet) in terms of its diameter d (in inches) and its length L (in feet). The number of board-feet is

$$N(d, L) = \left(\frac{d - 4}{4}\right)^2 L.$$

(a) Find the number of board-feet of lumber in a log 22 inches in diameter and 12 feet in length.

(b) Find $N(30, 12)$.

78. Queuing Model The average length of time that a customer waits in line for service is

$$W(x, y) = \frac{1}{x - y}, \quad x > y$$

where y is the average arrival rate, written as the number of customers per unit of time, and x is the average service rate, written in the same units. Evaluate each of the following.

(a) $W(15, 9)$ (b) $W(15, 13)$

(c) $W(12, 7)$ (d) $W(5, 2)$

79. Temperature Distribution The temperature T (in degrees Celsius) at any point (x, y) on a circular steel plate of radius 10 meters is

$$T = 600 - 0.75x^2 - 0.75y^2$$

where x and y are measured in meters. Sketch the isothermal curves for $T = 0, 100, 200, \ldots, 600$.

80. Electric Potential The electric potential V at any point (x, y) is

$$V(x, y) = \frac{5}{\sqrt{25 + x^2 + y^2}}.$$

Sketch the equipotential curves for $V = \frac{1}{2}$, $V = \frac{1}{3}$, and $V = \frac{1}{4}$.

Cobb-Douglas Production Function **In Exercises 81 and 82, use the Cobb-Douglas production function to find the production level when $x = 600$ units of labor and $y = 350$ units of capital.**

81. $f(x, y) = 80x^{0.5}y^{0.5}$

82. $f(x, y) = 100x^{0.65}y^{0.35}$

83. Cobb-Douglas Production Function Use the Cobb-Douglas production function, $f(x, y) = Cx^a y^{1-a}$, to show that when the number of units of labor and the number of units of capital are doubled, the production level is also doubled.

Kletr/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

84. Cobb-Douglas Production Function Show that the Cobb-Douglas production function $z = Cx^a y^{1-a}$ can be rewritten as

$$\ln \frac{z}{y} = \ln C + a \ln \frac{x}{y}.$$

85. Ideal Gas Law According to the Ideal Gas Law, $PV = kT$, where P is pressure, V is volume, T is temperature (in kelvins), and k is a constant of proportionality. A tank contains 2000 cubic inches of nitrogen at a pressure of 26 pounds per square inch and a temperature of 300 K.

(a) Determine k.

(b) Write P as a function of V and T and describe the level curves.

86. Modeling Data The table shows the net sales x (in billions of dollars), the total assets y (in billions of dollars), and the shareholder's equity z (in billions of dollars) for Walmart for the years 2015 through 2020. *(Source: Wal-Mart Stores, Inc.)*

Year	2015	2016	2017	2018	2019	2020
x	482.2	478.6	481.3	495.8	510.3	519.9
y	203.7	199.6	198.8	204.5	219.3	236.5
z	81.4	80.5	77.8	77.9	72.5	74.7

A model for the data is $z = f(x, y) = -0.328x + 0.195y + 198.7$.

(a) Complete a fourth row in the table using the model to approximate z for the given values of x and y. Compare the approximations with the actual values of z.

(b) Which of the two variables in this model has more influence on shareholder's equity? Explain.

(c) Simplify the expression for $f(x, 150)$ and interpret its meaning in the context of the problem.

87. Meteorology Meteorologists measure the atmospheric pressure in millibars. From these observations, they create weather maps on which the curves of equal atmospheric pressure (isobars) are drawn (see figure). On the map, the closer the isobars, the higher the wind speed. Match points A, B, and C with (a) highest pressure, (b) lowest pressure, and (c) highest wind velocity.



Figure for 87



Figure for 88

88. Acid Rain The acidity of rainwater is measured in units called pH. A pH of 7 is neutral, smaller values are increasingly acidic, and larger values are increasingly alkaline. The map shows curves of equal pH and gives evidence that downwind of heavily industrialized areas, the acidity has been increasing. Using the level curves on the map, determine the direction of the prevailing winds in the northeastern United States.

NASA

89. Construction Cost A rectangular storage box with an open top has a length of x feet, a width of y feet, and a height of z feet. It costs \$4.50 per square foot to build the base and \$2.50 per square foot to build the sides. Write the cost C of constructing the box as a function of x, y, and z.

90. HOW DO YOU SEE IT? The contour map of the Southern Hemisphere shown in the figure was computer generated using data collected by satellite instrumentation. Color and contour lines are used to show the "ozone hole" in Earth's atmosphere. The purple and blue areas with larger spaced contour lines represent the lowest levels of ozone, and the green areas with smaller spaced contour lines represent the highest levels. *(Source: NASA)*



(a) Do the level curves correspond to equally spaced ozone levels? Explain.

(b) Describe how to obtain a more detailed contour map.

True or False? In Exercises 91–94, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.

91. If $f(x_0, y_0) = f(x_1, y_1)$, then $x_0 = x_1$ and $y_0 = y_1$.

92. If f is a function, then $f(ax, ay) = a^2 f(x, y)$.

93. The equation for a sphere is a function of three variables.

94. Two different level curves of the graph of $z = f(x, y)$ can intersect.

PUTNAM EXAM CHALLENGE

95. Let $f\colon \mathbb{R}^2 \to \mathbb{R}$ be a function such that

$$f(x, y) + f(y, z) + f(z, x) = 0$$

for all real numbers x, y, and z. Prove that there exists a function $g\colon \mathbb{R} \to \mathbb{R}$ such that

$$f(x, y) = g(x) - g(y)$$

for all real numbers x and y.

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

13.2 Limits and Continuity

GO DIGITAL

- Define a neighborhood in the plane.
- Use the definition of the limit of a function of two variables.
- Extend the concept of continuity to a function of two variables.
- Extend the concept of continuity to a function of three variables.

SONYA KOVALEVSKY (1850–1891)

Much of the terminology used to define limits and continuity of a function of two or three variables was introduced by the German mathematician Karl Weierstrass (1815–1897). Weierstrass's rigorous approach to limits and other topics in calculus gained him the reputation as the "father of modern analysis." Weierstrass was a gifted teacher. One of his best-known students was the Russian mathematician Sonya Kovalevsky, who applied many of Weierstrass's techniques to problems in mathematical physics and became one of the first women to gain acceptance as a research mathematician. *See LarsonCalculus.com to read more of this biography.*

Neighborhoods in the Plane

In this section, you will study limits and continuity involving functions of two or three variables. The section begins with functions of two variables. At the end of the section, the concepts are extended to functions of three variables.

Your study of the limit of a function of two variables begins by defining a two-dimensional analog to an interval on the real number line. Using the formula for the distance between two points

$$(x, y) \quad \text{and} \quad (x_0, y_0)$$

in the plane, you can define the **δ-neighborhood** about (x_0, y_0) to be the **disk** centered at (x_0, y_0) with radius $\delta > 0$

$$\{(x, y): \sqrt{(x - x_0)^2 + (y - y_0)^2} < \delta\} \qquad \text{Open disk}$$

as shown in Figure 13.17. When this formula contains the *less than* inequality sign, $<$, the disk is called **open,** and when it contains the *less than or equal to* inequality sign, $\leq$, the disk is called **closed.** This corresponds to the use of $<$ and $\leq$ to define open and closed intervals.



An open disk

Figure 13.17



The boundary and interior points of a region R

Figure 13.18

Let the region R be a set of points in the plane. A point (x_0, y_0) in R is an **interior point** of R if there exists a δ-neighborhood about (x_0, y_0) that lies entirely in R, as shown in Figure 13.18. If every point in R is an interior point, then R is an **open region.** A point (x_0, y_0) is a **boundary point** of R if every open disk centered at (x_0, y_0) contains points inside R *and* points outside R. If R contains all its boundary points, then R is a **closed region.**

FOR FURTHER INFORMATION For more information on Sonya Kovalevsky, see the article "S. Kovalevsky: A Mathematical Lesson" by Karen D. Rappaport in *The American Mathematical Monthly.* To view this article, go to *MathArticles.com.*

Album/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Limit of a Function of Two Variables

Definition of the Limit of a Function of Two Variables

Let f be a function of two variables defined, except possibly at (x_0, y_0), on an open disk centered at (x_0, y_0), and let L be a real number. Then

$$\lim_{(x, y)\to(x_0, y_0)} f(x, y) = L$$

if for each $\varepsilon > 0$ there corresponds a $\delta > 0$ such that

$$|f(x, y) - L| < \varepsilon \quad \text{whenever} \quad 0 < \sqrt{(x - x_0)^2 + (y - y_0)^2} < \delta.$$

Graphically, the definition of the limit of a function of two variables implies that for any point $(x, y) \neq (x_0, y_0)$ in the disk of radius δ, the value $f(x, y)$ lies between $L + \varepsilon$ and $L - \varepsilon$, as shown in Figure 13.19.

The definition of the limit of a function of two variables is similar to the definition of the limit of a function of a single variable, yet there is a critical difference. To determine whether a function of a single variable has a limit, you need only test the approach from two directions—from the right and from the left. When the function approaches the same limit from the right and from the left, you can conclude that the limit exists. For a function of two variables, however, the statement

$$(x, y) \to (x_0, y_0)$$

means that the point (x, y) is allowed to approach (x_0, y_0) from any direction. If the value of

$$\lim_{(x, y)\to(x_0, y_0)} f(x, y)$$

is not the same for all possible approaches, or **paths,** to (x_0, y_0), then the limit does not exist.



For any (x, y) in the disk of radius δ, the value $f(x, y)$ lies between $L + \varepsilon$ and $L - \varepsilon$.

Figure 13.19

EXAMPLE 1 Verifying a Limit by the Definition

Show that $\lim_{(x, y)\to(a, b)} x = a$.

Solution Let $f(x, y) = x$ and $L = a$. You need to show that for each $\varepsilon > 0$, there exists a δ-neighborhood about (a, b) such that

$$|f(x, y) - L| = |x - a| < \varepsilon$$

whenever $(x, y) \neq (a, b)$ lies in the neighborhood. You can first observe that from

$$0 < \sqrt{(x - a)^2 + (y - b)^2} < \delta$$

it follows that

$$\begin{aligned} |f(x, y) - L| &= |x - a| \\ &= \sqrt{(x - a)^2} \\ &\leq \sqrt{(x - a)^2 + (y - b)^2} \\ &< \delta. \end{aligned}$$

So, you can choose $\delta = \varepsilon$, and the limit is verified.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Limits of functions of several variables have the same properties regarding sums, differences, products, and quotients as do limits of functions of single variables. (See Theorem 1.2 in Section 1.3.) Some of these properties are used in the next example.

EXAMPLE 2 Finding a Limit

Find the limit.

$$\lim_{(x, y)\to(1, 2)} \frac{5x^2y}{x^2 + y^2}$$

Solution By using the properties of limits of products and sums, you obtain

$$\lim_{(x, y)\to(1, 2)} 5x^2y = 5(1^2)(2) = 10$$

and

$$\lim_{(x, y)\to(1, 2)} (x^2 + y^2) = (1^2 + 2^2) = 5.$$

Because the limit of a quotient is equal to the quotient of the limits (and the denominator is not 0), you have

$$\lim_{(x, y)\to(1, 2)} \frac{5x^2y}{x^2 + y^2} = \frac{10}{5} = 2.$$

EXAMPLE 3 Finding a Limit

Find the limit: $\lim_{(x, y)\to(0, 0)} \frac{5x^2y}{x^2 + y^2}$.



Figure 13.20

Solution In this case, the limits of the numerator and of the denominator are both 0, so you cannot determine the existence (or nonexistence) of a limit by taking the limits of the numerator and denominator separately and then dividing. From the graph of f in Figure 13.20, however, it seems reasonable that the limit might be 0. So, you can try applying the definition to $L = 0$. First, note that

$$|y| \le \sqrt{x^2 + y^2}$$

and

$$\frac{x^2}{x^2 + y^2} \le 1.$$

Then, in a δ-neighborhood about $(0, 0)$, you have

$$0 < \sqrt{x^2 + y^2} < \delta$$

and it follows that, for $(x, y) \neq (0, 0)$,

$$\begin{aligned} |f(x, y) - 0| &= \left|\frac{5x^2y}{x^2 + y^2}\right| \\ &= 5|y|\left(\frac{x^2}{x^2 + y^2}\right) \\ &\le 5|y| \\ &\le 5\sqrt{x^2 + y^2} \\ &< 5\delta. \end{aligned}$$

So, you can choose $\delta = \varepsilon/5$ and conclude that

$$\lim_{(x, y)\to(0, 0)} \frac{5x^2y}{x^2 + y^2} = 0.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



$\lim_{(x, y)\to(0, 0)} \frac{1}{x^2 + y^2}$ does not exist.

Figure 13.21

For some functions, it is easy to recognize that a limit does not exist. For instance, it is clear that the limit

$$\lim_{(x, y)\to(0, 0)} \frac{1}{x^2 + y^2}$$

does not exist because the values of $f(x, y)$ increase without bound as (x, y) approaches $(0, 0)$ along *any* path (see Figure 13.21).

For other functions, it is not so easy to recognize that a limit does not exist. For instance, the next example describes a limit that does not exist because the function approaches different values along different paths.

EXAMPLE 4 A Limit That Does Not Exist

See LarsonCalculus.com for an interactive version of this type of example.

Show that the limit does not exist.

$$\lim_{(x, y)\to(0, 0)} \left(\frac{x^2 - y^2}{x^2 + y^2}\right)^2$$

Solution The domain of the function

$$f(x, y) = \left(\frac{x^2 - y^2}{x^2 + y^2}\right)^2$$

consists of all points in the xy-plane except for the point $(0, 0)$. To show that the limit as (x, y) approaches $(0, 0)$ does not exist, consider approaching $(0, 0)$ along two different "paths," as shown in Figure 13.22. Along the x-axis, every point is of the form

$$(x, 0)$$

and the limit along this approach is

$$\lim_{(x, 0)\to(0, 0)} \left(\frac{x^2 - 0^2}{x^2 + 0^2}\right)^2 = \lim_{(x, 0)\to(0, 0)} 1^2 = 1. \qquad \text{Limit along } x\text{-axis}$$

However, when (x, y) approaches $(0, 0)$ along the line $y = x$, you obtain

$$\lim_{(x, x)\to(0, 0)} \left(\frac{x^2 - x^2}{x^2 + x^2}\right)^2 = \lim_{(x, x)\to(0, 0)} \left(\frac{0}{2x^2}\right)^2 = 0. \qquad \text{Limit along line } y = x$$

This means that in any open disk centered at $(0, 0)$, there are points (x, y) at which f takes on the value 1 and other points at which f takes on the value 0. For instance,

$$f(x, y) = 1$$

at $(1, 0)$, $(0.1, 0)$, $(0.01, 0)$, and $(0.001, 0)$, and

$$f(x, y) = 0$$

at $(1, 1)$, $(0.1, 0.1)$, $(0.01, 0.01)$, and $(0.001, 0.001)$. So, f does not have a limit as (x, y) approaches $(0, 0)$.



$\lim_{(x, y)\to(0, 0)} \left(\frac{x^2 - y^2}{x^2 + y^2}\right)^2$ does not exist.

Figure 13.22

In Example 4, you could conclude that the limit does not exist because you found two approaches that produced different limits. Be sure you understand that when two approaches produce the same limit, you *cannot* conclude that the limit exists. To form such a conclusion, you must show that the limit is the same along *all* possible approaches.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Continuity of a Function of Two Variables

Notice in Example 2 that the limit of $f(x, y) = 5x^2y/(x^2 + y^2)$ as $(x, y) \to (1, 2)$ can be evaluated by direct substitution. That is, the limit is $f(1, 2) = 2$. In such cases, the function f is said to be **continuous** at the point $(1, 2)$.

REMARK This definition of continuity can be extended to *boundary points* of the open region R by considering a special type of limit in which (x, y) is allowed to approach (x_0, y_0) along paths lying in the region R. This notion is similar to that of one-sided limits, as discussed in Chapter 1.

Definition of Continuity of a Function of Two Variables

A function f of two variables is **continuous at a point (x_0, y_0)** in an open region R if $f(x_0, y_0)$ is defined and is equal to the limit of $f(x, y)$ as (x, y) approaches (x_0, y_0). That is,

$$\lim_{(x, y) \to (x_0, y_0)} f(x, y) = f(x_0, y_0).$$

The function f is **continuous in the open region R** if it is continuous at every point in R.

In Example 3, it was shown that the function

$$f(x, y) = \frac{5x^2y}{x^2 + y^2}$$

is not continuous at $(0, 0)$. Because the limit at this point exists, however, you can remove the discontinuity by defining f at $(0, 0)$ as being equal to its limit there. Such a discontinuity is called **removable.** In Example 4, the function

$$f(x, y) = \left(\frac{x^2 - y^2}{x^2 + y^2}\right)^2$$

was also shown not to be continuous at $(0, 0)$, but this discontinuity is **nonremovable.**

THEOREM 13.1 Continuous Functions of Two Variables

If k is a real number and $f(x, y)$ and $g(x, y)$ are continuous at (x_0, y_0), then the following functions are also continuous at (x_0, y_0).

1. Scalar multiple: kf
2. Sum or difference: $f \pm g$
3. Product: fg
4. Quotient: $f/g, g(x_0, y_0) \neq 0$

Theorem 13.1 establishes the continuity of *polynomial* and *rational* functions at every point in their domains. Furthermore, the continuity of other types of functions can be extended naturally from one to two variables. For instance, the functions whose graphs are shown in Figures 13.23 and 13.24 are continuous at every point in the plane.



The function f is continuous at every point in the plane.
Figure 13.23



The function f is continuous at every point in the plane.
Figure 13.24

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The next theorem states conditions under which a composite function is continuous.

THEOREM 13.2 Continuity of a Composite Function

If h is continuous at (x_0, y_0) and g is continuous at $h(x_0, y_0)$, then the composite function given by $(g \circ h)(x, y) = g(h(x, y))$ is continuous at (x_0, y_0). That is,

$$\lim_{(x, y)\to(x_0, y_0)} g(h(x, y)) = g(h(x_0, y_0)).$$

Note in Theorem 13.2 that h is a function of two variables and g is a function of one variable.

EXAMPLE 5 Testing for Continuity

Discuss the continuity of each function.

a. $f(x, y) = \dfrac{x - 2y}{x^2 + y^2}$ **b.** $g(x, y) = \dfrac{2}{y - x^2}$

Solution

a. Because a rational function is continuous at every point in its domain, you can conclude that f is continuous at each point in the xy-plane except at $(0, 0)$, as shown in Figure 13.25.

b. The function

$$g(x, y) = \frac{2}{y - x^2}$$

is continuous except at the points at which the denominator is 0. These points are given by the equation

$$y - x^2 = 0.$$

So, you can conclude that the function is continuous at all points except those lying on the parabola $y = x^2$. Inside this parabola, $y > x^2$ and the surface represented by the function lies above the xy-plane, as shown in Figure 13.26. Outside the parabola, $y < x^2$ and the surface lies below the xy-plane.



The function f is not continuous at $(0, 0)$.

Figure 13.25



The function g is not continuous on the parabola $y = x^2$.

Figure 13.26

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Continuity of a Function of Three Variables

The preceding definitions of limits and continuity can be extended to functions of three variables by considering points (x, y, z) within the *open sphere*

$$(x - x_0)^2 + (y - y_0)^2 + (z - z_0)^2 < \delta^2. \qquad \text{Open sphere}$$

The radius of this sphere is δ, and the sphere is centered at (x_0, y_0, z_0), as shown in Figure 13.27.



Open sphere in space

Figure 13.27

A point (x_0, y_0, z_0) in a region R in space is an **interior point** of R if there exists a δ-sphere about (x_0, y_0, z_0) that lies entirely in R. If every point in R is an interior point, then R is called **open.**

Definition of Continuity of a Function of Three Variables

A function f of three variables is **continuous at a point (x_0, y_0, z_0)** in an open region R if $f(x_0, y_0, z_0)$ is defined and is equal to the limit of $f(x, y, z)$ as (x, y, z) approaches (x_0, y_0, z_0). That is,

$$\lim_{(x, y, z) \to (x_0, y_0, z_0)} f(x, y, z) = f(x_0, y_0, z_0).$$

The function f is **continuous in the open region R** if it is continuous at every point in R.

EXAMPLE 6 Testing Continuity of a Function of Three Variables

Discuss the continuity of

$$f(x, y, z) = \frac{1}{x^2 + y^2 - z}.$$

Solution The function f is continuous except at the points at which the denominator is 0, which are given by the equation

$$x^2 + y^2 - z = 0.$$

So, f is continuous at each point in space except at the points on the paraboloid

$$z = x^2 + y^2.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

13.2 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Write a brief description of the meaning of the notation $\lim_{(x, y)\to(-1, 3)} f(x, y) = 1$.

2. Explain how examining limits along different paths might show that a limit does not exist. Does this type of examination show that a limit does exist? Explain.

Verifying a Limit by the Definition **In Exercises 3–6, use the definition of the limit of a function of two variables to verify the limit.**

3. $\lim_{(x, y)\to(1, 0)} x = 1$
4. $\lim_{(x, y)\to(4, -1)} x = 4$
5. $\lim_{(x, y)\to(1, -3)} y = -3$
6. $\lim_{(x, y)\to(a, b)} y = b$

Using Properties of Limits **In Exercises 7–10, find the indicated limit by using the limits**

$$\lim_{(x,y)\to(a,b)} f(x, y) = 4 \quad \text{and} \quad \lim_{(x,y)\to(a,b)} g(x, y) = -5.$$

7. $\lim_{(x, y)\to(a, b)} [f(x, y) - g(x, y)]$
8. $\lim_{(x, y)\to(a, b)} \left[\frac{3f(x, y)}{g(x, y)}\right]$
9. $\lim_{(x, y)\to(a, b)} [f(x, y)g(x, y)]$
10. $\lim_{(x, y)\to(a, b)} \left[\frac{f(x, y) + g(x, y)}{f(x, y)}\right]$

Limit and Continuity **In Exercises 11–24, find the limit and discuss the continuity of the function.**

11. $\lim_{(x, y)\to(3, 1)} (x^2 - 2y)$
12. $\lim_{(x, y)\to(-1, 1)} (x + 4y^2 + 5)$
13. $\lim_{(x, y)\to(1, 2)} e^{xy}$
14. $\lim_{(x, y)\to(2, 4)} \frac{x + y}{x^2 + 1}$
15. $\lim_{(x, y)\to(0, 2)} \frac{x}{y}$
16. $\lim_{(x, y)\to(-1, 2)} \frac{x + y}{x - y}$
17. $\lim_{(x, y)\to(1, 1)} \frac{xy}{x^2 + y^2}$
18. $\lim_{(x, y)\to(1, 1)} \frac{x}{\sqrt{x + y}}$
19. $\lim_{(x, y)\to(\pi/3, 2)} y \cos xy$
20. $\lim_{(x, y)\to(\pi, -4)} \sin \frac{x}{y}$
21. $\lim_{(x, y)\to(0, 1)} \frac{\arcsin xy}{1 - xy}$
22. $\lim_{(x, y)\to(0, 1)} \frac{\arccos(x/y)}{1 + xy}$
23. $\lim_{(x, y, z)\to(1, 3, 4)} \sqrt{x + y + z}$
24. $\lim_{(x, y, z)\to(-2, 1, 0)} xe^{yz}$

Finding a Limit **In Exercises 25–36, find the limit (if it exists). If the limit does not exist, explain why.**

25. $\lim_{(x, y)\to(1, 1)} \frac{xy - 1}{1 + xy}$
26. $\lim_{(x, y)\to(1, -1)} \frac{x^2y}{1 + xy^2}$
27. $\lim_{(x, y)\to(0, 0)} \frac{1}{x + y}$
28. $\lim_{(x, y)\to(0, 0)} \frac{1}{x^2y^2}$
29. $\lim_{(x, y)\to(0, 0)} \frac{x - y}{\sqrt{x} - \sqrt{y}}$
30. $\lim_{(x, y)\to(2, 1)} \frac{x - y - 1}{\sqrt{x - y} - 1}$
31. $\lim_{(x, y)\to(0, 0)} \frac{x + y}{x^2 + y}$
32. $\lim_{(x, y)\to(0, 0)} \frac{x}{x^2 - y^2}$
33. $\lim_{(x, y)\to(0, 0)} \frac{x^2}{(x^2 + 1)(y^2 + 1)}$
34. $\lim_{(x, y)\to(0, 0)} \ln(x^2 + y^2)$
35. $\lim_{(x, y, z)\to(0, 0, 0)} \frac{xy + yz + xz}{x^2 + y^2 + z^2}$
36. $\lim_{(x, y, z)\to(0, 0, 0)} \frac{xy + yz^2 + xz^2}{x^2 + y^2 + z^2}$

Exploring Concepts

37. Can you conclude anything about $\lim_{(x, y)\to(2, 3)} f(x, y)$ when $f(2, 3) = 4$? Explain.

38. Can you conclude anything about $f(2, 3)$ when $\lim_{(x, y)\to(2, 3)} f(x, y) = 4$? Explain.

39. Let $\lim_{(x, y)\to(0, 0)} f(x, y) = 0$. Does $\lim_{(x, 0)\to(0, 0)} f(x, 0) = 0$? Explain your reasoning.

40. **HOW DO YOU SEE IT?** The figure shows the graph of $f(x, y) = \ln(x^2 + y^2)$. From the graph, does it appear that the limit at each point exists?



(a) $(-1, -1)$ (b) $(0, 3)$ (c) $(0, 0)$ (d) $(2, 0)$

Continuity **In Exercises 41 and 42, discuss the continuity of the function and evaluate the limit of $f(x, y)$ (if it exists) as $(x, y) \to (0, 0)$.**

41. $f(x, y) = e^{xy}$



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

42. $f(x, y) = 1 - \dfrac{\cos(x^2 + y^2)}{x^2 + y^2}$



Limit and Continuity **In Exercises 43–46, use a graphing utility to make a table showing the values of $f(x, y)$ at the given points for each path. Use the result to make a conjecture about the limit of $f(x, y)$ as $(x, y) \to (0, 0)$. Determine analytically whether the limit exists and discuss the continuity of the function.**

43. $f(x, y) = \dfrac{xy}{x^2 + y^2}$

Path: $y = 0$

Points: $(1, 0), (0.5, 0), (0.1, 0), (0.01, 0), (0.001, 0)$

Path: $y = x$

Points: $(1, 1), (0.5, 0.5), (0.1, 0.1), (0.01, 0.01), (0.001, 0.001)$



44. $f(x, y) = -\dfrac{xy^2}{x^2 + y^4}$

Path: $x = y^2$

Points: $(1, 1), (0.25, 0.5), (0.01, 0.1), (0.0001, 0.01), (0.000001, 0.001)$

Path: $x = -y^2$

Points: $(-1, 1), (-0.25, 0.5), (-0.01, 0.1), (-0.0001, 0.01), (-0.000001, 0.001)$



45. $f(x, y) = \dfrac{y}{x^2 + y^2}$

Path: $y = 0$

Points: $(1, 0), (0.5, 0), (0.1, 0), (0.01, 0), (0.001, 0)$

Path: $y = x$

Points: $(1, 1), (0.5, 0.5), (0.1, 0.1), (0.01, 0.01), (0.001, 0.001)$



46. $f(x, y) = \dfrac{2x - y^2}{2x^2 + y}$

Path: $y = 0$

Points: $(1, 0), (0.25, 0), (0.01, 0), (0.001, 0), (0.000001, 0)$

Path: $y = x$

Points: $(1, 1), (0.25, 0.25), (0.01, 0.01), (0.001, 0.001), (0.0001, 0.0001)$



47. Limit Consider $\lim\limits_{(x, y) \to (0, 0)} \dfrac{x^2 + y^2}{xy}$ (see figure).



(a) Determine (if possible) the limit along any line of the form $y = ax$.

(b) Determine (if possible) the limit along the parabola $y = x^2$.

(c) Does the limit exist? Explain.

48. Limit Consider $\lim\limits_{(x, y) \to (0, 0)} \dfrac{x^2y}{x^4 + y^2}$ (see figure).



(a) Determine (if possible) the limit along any line of the form $y = ax$.

(b) Determine (if possible) the limit along the parabola $y = x^2$.

(c) Does the limit exist? Explain.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Comparing Continuity **In Exercises 49 and 50, discuss the continuity of the functions f and g. Explain any differences.**

49.
$$f(x,y)=\begin{cases}\dfrac{x^4-y^4}{x^2+y^2}, & (x,y)\neq(0,0)\\ 0, & (x,y)=(0,0)\end{cases}$$
$$g(x,y)=\begin{cases}\dfrac{x^4-y^4}{x^2+y^2}, & (x,y)\neq(0,0)\\ 1, & (x,y)=(0,0)\end{cases}$$

50.
$$f(x,y)=\begin{cases}\dfrac{x^2+2xy^2+y^2}{x^2+y^2}, & (x,y)\neq(0,0)\\ 0, & (x,y)=(0,0)\end{cases}$$
$$g(x,y)=\begin{cases}\dfrac{x^2+2xy^2+y^2}{x^2+y^2}, & (x,y)\neq(0,0)\\ 1, & (x,y)=(0,0)\end{cases}$$

Finding a Limit Using Polar Coordinates **In Exercises 51–56, use polar coordinates to find the limit. [*Hint:* Let $x=r\cos\theta$ and $y=r\sin\theta$, and note that $(x,y)\to(0,0)$ implies $r\to 0$.]**

51. $\lim\limits_{(x,y)\to(0,0)}\dfrac{xy^2}{x^2+y^2}$

52. $\lim\limits_{(x,y)\to(0,0)}\dfrac{x^3+y^3}{x^2+y^2}$

53. $\lim\limits_{(x,y)\to(0,0)}\dfrac{x^2y^2}{x^2+y^2}$

54. $\lim\limits_{(x,y)\to(0,0)}\dfrac{x^2-y^2}{\sqrt{x^2+y^2}}$

55. $\lim\limits_{(x,y)\to(0,0)}\cos(x^2+y^2)$

56. $\lim\limits_{(x,y)\to(0,0)}\sin\sqrt{x^2+y^2}$

Finding a Limit Using Polar Coordinates **In Exercises 57–60, use polar coordinates and L'Hôpital's Rule to find the limit.**

57. $\lim\limits_{(x,y)\to(0,0)}\dfrac{\sin\sqrt{x^2+y^2}}{\sqrt{x^2+y^2}}$

58. $\lim\limits_{(x,y)\to(0,0)}\dfrac{\sin(x^2+y^2)}{x^2+y^2}$

59. $\lim\limits_{(x,y)\to(0,0)}\dfrac{1-\cos(x^2+y^2)}{x^2+y^2}$

60. $\lim\limits_{(x,y)\to(0,0)}(x^2+y^2)\ln(x^2+y^2)$

Continuity **In Exercises 61–66, discuss the continuity of the function.**

61. $f(x,y,z)=\dfrac{1}{\sqrt{x^2+y^2+z^2}}$

62. $f(x,y,z)=\dfrac{z}{x^2+y^2-4}$

63. $f(x,y,z)=\dfrac{\sin z}{e^x+e^y}$

64. $f(x,y,z)=xy\sin z$

65.
$$f(x,y)=\begin{cases}\dfrac{\sin xy}{xy}, & xy\neq 0\\ 1, & xy=0\end{cases}$$

66.
$$f(x,y)=\begin{cases}\dfrac{\sin(x^2-y^2)}{x^2-y^2}, & x^2\neq y^2\\ 1, & x^2=y^2\end{cases}$$

Continuity of a Composite Function **In Exercises 67–70, discuss the continuity of the composite function $f\circ g$.**

67. $f(t)=t^2$, $g(x,y)=2x-3y$

68. $f(t)=\dfrac{1}{t}$, $g(x,y)=x^2+y^2$

69. $f(t)=\dfrac{1}{t}$, $g(x,y)=2x-3y$

70. $f(t)=\dfrac{1}{1-t}$, $g(x,y)=x^2+y^2$

Finding a Limit **In Exercises 71–76, find each limit.**

(a) $\lim\limits_{\Delta x\to 0}\dfrac{f(x+\Delta x,y)-f(x,y)}{\Delta x}$

(b) $\lim\limits_{\Delta y\to 0}\dfrac{f(x,y+\Delta y)-f(x,y)}{\Delta y}$

71. $f(x,y)=x^2-4y$

72. $f(x,y)=3x^2+y^2$

73. $f(x,y)=\dfrac{x}{y}$

74. $f(x,y)=\dfrac{1}{x+y}$

75. $f(x,y)=3x+xy-2y$

76. $f(x,y)=\sqrt{y}(y+1)$

Finding a Limit Using Spherical Coordinates **In Exercises 77 and 78, use spherical coordinates to find the limit. [*Hint:* Let $x=\rho\sin\phi\cos\theta$, $y=\rho\sin\phi\sin\theta$, and $z=\rho\cos\phi$, and note that $(x,y,z)\to(0,0,0)$ implies $\rho\to 0^+$.]**

77. $\lim\limits_{(x,y)\to(0,0,0)}\dfrac{xyz}{x^2+y^2+z^2}$

78. $\lim\limits_{(x,y)\to(0,0,0)}\tan^{-1}\left(\dfrac{1}{x^2+y^2+z^2}\right)$

True or False? **In Exercises 79–82, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

79. A closed region contains all of its boundary points.

80. Every point in an open region is an interior point.

81. If f is continuous for all nonzero x and y, and $f(0,0)=0$, then $\lim\limits_{(x,y)\to(0,0)}f(x,y)=0$.

82. If g is a continuous function of x, h is a continuous function of y, and $f(x,y)=g(x)+h(y)$, then f is continuous.

83. Finding a Limit Find the following limit.

$$\lim_{(x,y)\to(0,1)}\tan^{-1}\left[\frac{x^2+1}{x^2+(y-1)^2}\right]$$

84. Continuity For the function

$$f(x,y)=xy\left(\frac{x^2-y^2}{x^2+y^2}\right)$$

define $f(0,0)$ such that f is continuous at the origin.

85. Proof Prove that $\lim\limits_{(x,y)\to(a,b)}[f(x,y)+g(x,y)]=L_1+L_2$ where $f(x,y)$ approaches L_1 and $g(x,y)$ approaches L_2 as $(x,y)\to(a,b)$.

86. Proof Prove that if f is continuous and $f(a,b)<0$, then there exists a δ-neighborhood about (a,b) such that $f(x,y)<0$ for every point (x,y) in the neighborhood.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

13.3 Partial Derivatives

GO DIGITAL

- Find and use partial derivatives of a function of two variables.
- Find and use partial derivatives of a function of three or more variables.
- Find higher-order partial derivatives of a function of two or three variables.

JEAN LE ROND D'ALEMBERT (1717–1783)

The introduction of partial derivatives followed Newton's and Leibniz's work in calculus by several years. Between 1730 and 1760, Leonhard Euler and Jean Le Rond d'Alembert separately published several papers on dynamics, in which they established much of the theory of partial derivatives. These papers used functions of two or more variables to study problems involving equilibrium, fluid motion, and vibrating strings.

See LarsonCalculus.com to read more of this biography.

Partial Derivatives of a Function of Two Variables

In applications of functions of several variables, the question often arises, "How will the value of a function be affected by a change in one of its independent variables?" You can answer this by considering the independent variables one at a time. For example, to determine the effect of a catalyst in an experiment, a chemist could conduct the experiment several times using varying amounts of the catalyst while keeping constant other variables such as temperature and pressure. You can use a similar procedure to determine the rate of change of a function f with respect to one of its several independent variables. This process is called **partial differentiation,** and the result is referred to as the **partial derivative** of f with respect to the chosen independent variable.

Definition of Partial Derivatives of a Function of Two Variables

If $z = f(x, y)$, then the **first partial derivatives** of f with respect to x and y are the functions f_x and f_y defined by

$$f_x(x, y) = \lim_{\Delta x \to 0} \frac{f(x + \Delta x, y) - f(x, y)}{\Delta x}$$ Partial derivative with respect to x

and

$$f_y(x, y) = \lim_{\Delta y \to 0} \frac{f(x, y + \Delta y) - f(x, y)}{\Delta y}$$ Partial derivative with respect to y

provided the limits exist.

This definition indicates that if $z = f(x, y)$, then to find f_x, *consider y to be constant* and differentiate with respect to x. Similarly, to find f_y, *consider x to be constant* and differentiate with respect to y.

EXAMPLE 1 Finding Partial Derivatives

a. To find f_x for $f(x, y) = 3x - x^2y^2 + 2x^3y$, consider y to be constant and differentiate with respect to x.

$$f_x(x, y) = 3 - 2xy^2 + 6x^2y$$ Partial derivative with respect to x

To find f_y, consider x to be constant and differentiate with respect to y.

$$f_y(x, y) = -2x^2y + 2x^3$$ Partial derivative with respect to y

b. To find f_x for $f(x, y) = (\ln x)(\sin x^2y)$, consider y to be constant and differentiate with respect to x.

$$f_x(x, y) = (\ln x)(\cos x^2y)(2xy) + \frac{\sin x^2y}{x}$$ Partial derivative with respect to x

To find f_y, consider x to be constant and differentiate with respect to y.

$$f_y(x, y) = (\ln x)(\cos x^2y)(x^2)$$ Partial derivative with respect to y

Heritage Image Partnership Ltd/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

REMARK The notation $\partial z/\partial x$ is read as "the partial derivative of z with respect to x," and $\partial z/\partial y$ is read as "the partial derivative of z with respect to y."

GO DIGITAL

Notation for First Partial Derivatives

For $z = f(x, y)$, the partial derivatives f_x and f_y are denoted by

$$\frac{\partial}{\partial x}f(x, y) = f_x(x, y) = z_x = \frac{\partial z}{\partial x}$$ Partial derivative with respect to x

and

$$\frac{\partial}{\partial y}f(x, y) = f_y(x, y) = z_y = \frac{\partial z}{\partial y}.$$ Partial derivative with respect to y

The first partials evaluated at the point (a, b) are denoted by

$$\left.\frac{\partial z}{\partial x}\right|_{(a, b)} = f_x(a, b) \quad \text{and} \quad \left.\frac{\partial z}{\partial y}\right|_{(a, b)} = f_y(a, b).$$

EXAMPLE 2 Finding and Evaluating Partial Derivatives

For $f(x, y) = xe^{x^2y}$, find f_x and f_y, and evaluate each at the point $(1, \ln 2)$.

Solution To find the first partial derivative with respect to x, hold y constant and differentiate using the Product Rule.

$$\begin{aligned} f_x(x, y) &= (x)\frac{\partial}{\partial x}[e^{x^2y}] + (e^{x^2y})\frac{\partial}{\partial x}[x] && \text{Apply Product Rule.} \\ &= xe^{x^2y}(2xy) + e^{x^2y} && y \text{ is held constant.} \end{aligned}$$

The value of f_x at the point $(1, \ln 2)$ is

$$f_x(1, \ln 2) = e^{\ln 2}(2 \ln 2) + e^{\ln 2} = 4 \ln 2 + 2.$$

To find the first partial derivative with respect to y, hold x constant and differentiate using the Constant Multiple Rule.

$$\begin{aligned} f_y(x, y) &= (x)\frac{\partial}{\partial y}[e^{x^2y}] && \text{Apply Constant Multiple Rule.} \\ &= xe^{x^2y}(x^2) && x \text{ is held constant.} \\ &= x^3e^{x^2y} && \text{Simplify.} \end{aligned}$$

The value of f_y at the point $(1, \ln 2)$ is

$$f_y(1, \ln 2) = e^{\ln 2} = 2.$$ ■



$f_x(x_0, y_0)$ = slope in x-direction

Figure 13.28



$f_y(x_0, y_0)$ = slope in y-direction

Figure 13.29

The partial derivatives of a function of two variables, $z = f(x, y)$, have a useful geometric interpretation. If $y = y_0$, then $z = f(x, y_0)$ represents the curve formed by intersecting the surface $z = f(x, y)$ with the plane $y = y_0$, as shown in Figure 13.28. So,

$$f_x(x_0, y_0) = \lim_{\Delta x \to 0}\frac{f(x_0 + \Delta x, y_0) - f(x_0, y_0)}{\Delta x}$$

represents the slope of this curve at the point $(x_0, y_0, f(x_0, y_0))$. Note that both the curve and the tangent line lie in the plane $y = y_0$. Similarly,

$$f_y(x_0, y_0) = \lim_{\Delta y \to 0}\frac{f(x_0, y_0 + \Delta y) - f(x_0, y_0)}{\Delta y}$$

represents the slope of the curve given by the intersection of $z = f(x, y)$ and the plane $x = x_0$ at $(x_0, y_0, f(x_0, y_0))$, as shown in Figure 13.29.

Informally, the values of $\partial f/\partial x$ and $\partial f/\partial y$ at the point (x_0, y_0, z_0) denote the **slopes of the surface in the x- and y-directions,** respectively.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 3 Finding the Slopes of a Surface

See LarsonCalculus.com for an interactive version of this type of example.

Find the slopes in the x-direction and in the y-direction of the surface

$$f(x, y) = -\frac{x^2}{2} - y^2 + \frac{25}{8}$$

at the point $\left(\frac{1}{2}, 1, 2\right)$.

Solution The partial derivatives of f with respect to x and y are

$$f_x(x, y) = -x \quad \text{and} \quad f_y(x, y) = -2y.$$ Partial derivatives

At the point $\left(\frac{1}{2}, 1, 2\right)$, the slope in the x-direction is

$$f_x\left(\frac{1}{2}, 1\right) = -\frac{1}{2}$$ Figure 13.30

and the slope in the y-direction is

$$f_y\left(\frac{1}{2}, 1\right) = -2.$$ Figure 13.31

REMARK The guidelines below may help you find the slopes of a surface in the x- and y-directions. Let (x_0, y_0, z_0) be a point on the surface of $z = f(x, y)$.

1. Find the partial derivatives of f with respect to x and y.
2. The slope in the x-direction at (x_0, y_0, z_0) is $f_x(x_0, y_0)$.
3. The slope in the y-direction at (x_0, y_0, z_0) is $f_y(x_0, y_0)$.



Figure 13.30



Figure 13.31

EXAMPLE 4 Finding the Slopes of a Surface

Find the slopes of the surface

$$f(x, y) = 1 - (x - 1)^2 - (y - 2)^2$$

at the point $(1, 2, 1)$ in the x-direction and in the y-direction.

Solution The partial derivatives of f with respect to x and y are

$$f_x(x, y) = -2(x - 1) \quad \text{and} \quad f_y(x, y) = -2(y - 2).$$ Partial derivatives

At the point $(1, 2, 1)$, the slope in the x-direction is

$$f_x(1, 2) = -2(1 - 1) = 0$$

and the slope in the y-direction is

$$f_y(1, 2) = -2(2 - 2) = 0$$

as shown in Figure 13.32.



Figure 13.32

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The area of the parallelogram is $ab \sin \theta$.
Figure 13.33

No matter how many variables are involved, partial derivatives can be interpreted as *rates of change.*

EXAMPLE 5 **Using Partial Derivatives to Find Rates of Change**

The area of a parallelogram with adjacent sides a and b and included angle θ is given by $A = ab \sin \theta$, as shown in Figure 13.33.

a. Find the rate of change of A with respect to a for $a = 10$, $b = 20$, and $\theta = \pi/6$.

b. Find the rate of change of A with respect to θ for $a = 10$, $b = 20$, and $\theta = \pi/6$.

Solution

a. To find the rate of change of the area with respect to a, hold b and θ constant and differentiate with respect to a to obtain

$$\frac{\partial A}{\partial a} = b \sin \theta.$$ Find partial derivative with respect to a.

For $a = 10$, $b = 20$, and $\theta = \pi/6$, the rate of change of the area with respect to a is

$$\frac{\partial A}{\partial a} = 20 \sin \frac{\pi}{6} = 10.$$ Substitute for b and θ.

b. To find the rate of change of the area with respect to θ, hold a and b constant and differentiate with respect to θ to obtain

$$\frac{\partial A}{\partial \theta} = ab \cos \theta.$$ Find partial derivative with respect to θ.

For $a = 10$, $b = 20$, and $\theta = \pi/6$, the rate of change of the area with respect to θ is

$$\frac{\partial A}{\partial \theta} = (10)(20) \cos \frac{\pi}{6} = 100\sqrt{3}.$$ Substitute for a, b, and θ. ■

Partial Derivatives of a Function of Three or More Variables

The concept of a partial derivative can be extended naturally to functions of three or more variables. For instance, the function

$$w = f(x, y, z)$$ Function of three variables

has three partial derivatives, each of which is formed by holding two of the variables constant. That is, to define the partial derivative of w with respect to x, consider y and z to be constant and differentiate with respect to x. A similar process is used to find the derivatives of w with respect to y and with respect to z.

$$\frac{\partial w}{\partial x} = f_x(x, y, z) = \lim_{\Delta x \to 0} \frac{f(x + \Delta x, y, z) - f(x, y, z)}{\Delta x}$$

$$\frac{\partial w}{\partial y} = f_y(x, y, z) = \lim_{\Delta y \to 0} \frac{f(x, y + \Delta y, z) - f(x, y, z)}{\Delta y}$$

$$\frac{\partial w}{\partial z} = f_z(x, y, z) = \lim_{\Delta z \to 0} \frac{f(x, y, z + \Delta z) - f(x, y, z)}{\Delta z}$$

In general, if $w = f(x_1, x_2, \ldots, x_n)$, then there are n partial derivatives denoted by

$$\frac{\partial w}{\partial x_k} = f_{x_k}(x_1, x_2, \ldots, x_n), \quad k = 1, 2, \ldots, n.$$

To find the partial derivative with respect to one of the variables, hold the other variables constant and differentiate with respect to the given variable.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 6 Finding Partial Derivatives

a. To find the partial derivative of $f(x, y, z) = xy + yz^2 + xz$ with respect to z, consider x and y to be constant and obtain

$$\frac{\partial}{\partial z}[xy + yz^2 + xz] = 2yz + x.$$

b. To find the partial derivative of $f(x, y, z) = z \sin(xy^2 + 2z)$ with respect to z, consider x and y to be constant. Then, using the Product Rule, you obtain

$$\begin{aligned}\frac{\partial}{\partial z}[z \sin(xy^2 + 2z)] &= (z)\frac{\partial}{\partial z}[\sin(xy^2 + 2z)] + \sin(xy^2 + 2z)\frac{\partial}{\partial z}[z] \\ &= (z)[\cos(xy^2 + 2z)](2) + \sin(xy^2 + 2z) \\ &= 2z \cos(xy^2 + 2z) + \sin(xy^2 + 2z).\end{aligned}$$

c. To find the partial derivative of

$$f(x, y, z, w) = \frac{x + y + z}{w}$$

with respect to w, consider x, y, and z to be constant and obtain

$$\frac{\partial}{\partial w}\left[\frac{x + y + z}{w}\right] = -\frac{x + y + z}{w^2}.$$

Higher-Order Partial Derivatives

As is true for ordinary derivatives, it is possible to take second, third, and higher-order partial derivatives of a function of several variables, provided such derivatives exist. Higher-order derivatives are denoted by the order in which the differentiation occurs. For instance, the function $z = f(x, y)$ has the following second partial derivatives.

1. Differentiate twice with respect to x:

$$\frac{\partial}{\partial x}\left(\frac{\partial f}{\partial x}\right) = \frac{\partial^2 f}{\partial x^2} = f_{xx}.$$

2. Differentiate twice with respect to y:

$$\frac{\partial}{\partial y}\left(\frac{\partial f}{\partial y}\right) = \frac{\partial^2 f}{\partial y^2} = f_{yy}.$$

3. Differentiate first with respect to x and then with respect to y:

$$\frac{\partial}{\partial y}\left(\frac{\partial f}{\partial x}\right) = \frac{\partial^2 f}{\partial y \partial x} = f_{xy}.$$

4. Differentiate first with respect to y and then with respect to x:

$$\frac{\partial}{\partial x}\left(\frac{\partial f}{\partial y}\right) = \frac{\partial^2 f}{\partial x \partial y} = f_{yx}.$$

The third and fourth cases are called **mixed partial derivatives.**

REMARK Note that the two types of notation for mixed partials have different conventions for indicating the order of differentiation.

$$\frac{\partial}{\partial y}\left(\frac{\partial f}{\partial x}\right) = \frac{\partial^2 f}{\partial y \partial x} \quad \text{Right-to-left order}$$

$$(f_x)_y = f_{xy} \quad \text{Left-to-right order}$$

You can remember the order by observing that in both notations you differentiate first with respect to the variable "nearest" f.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 7 Finding Second Partial Derivatives

Find the second partial derivatives of

$$f(x, y) = 3xy^2 - 2y + 5x^2y^2$$

and determine the value of $f_{xy}(-1, 2)$.

Solution Begin by finding the first partial derivatives with respect to x and y.

$$f_x(x, y) = 3y^2 + 10xy^2 \quad \text{and} \quad f_y(x, y) = 6xy - 2 + 10x^2y$$

Then, differentiate each of these with respect to x and y.

$$f_{xx}(x, y) = 10y^2 \quad \text{and} \quad f_{yy}(x, y) = 6x + 10x^2$$
$$f_{xy}(x, y) = 6y + 20xy \quad \text{and} \quad f_{yx}(x, y) = 6y + 20xy$$

At $(-1, 2)$, the value of f_{xy} is

$$f_{xy}(-1, 2) = 6(2) + 20(-1)(2) = 12 - 40 = -28.$$

Notice in Example 7 that the two mixed partials are equal. Sufficient conditions for this occurrence are given in Theorem 13.3.

THEOREM 13.3 Equality of Mixed Partial Derivatives

If f is a function of x and y such that f_{xy} and f_{yx} are continuous on an open disk R, then, for every (x, y) in R,

$$f_{xy}(x, y) = f_{yx}(x, y).$$

Theorem 13.3 also applies to a function f of *three or more variables* as long as all second partial derivatives are continuous. For example, if

$$w = f(x, y, z) \qquad \text{Function of three variables}$$

and all the second partial derivatives are continuous in an open region R, then at each point in R, the order of differentiation in the mixed second partial derivatives is irrelevant. If the third partial derivatives of f are also continuous, then the order of differentiation of the mixed third partial derivatives is irrelevant.

EXAMPLE 8 Finding Higher-Order Partial Derivatives

Show that $f_{xz} = f_{zx}$ and $f_{xzz} = f_{zxz} = f_{zzx}$ for the function

$$f(x, y, z) = ye^x + x \ln z.$$

Solution Begin by finding the first partial derivatives with respect to x and z.

$$f_x(x, y, z) = ye^x + \ln z, \quad f_z(x, y, z) = \frac{x}{z}$$

Next, find the second partial derivatives with respect to x and z. Note that $f_{xz} = f_{zx}$.

$$f_{xz}(x, y, z) = \frac{1}{z}, \quad f_{zx}(x, y, z) = \frac{1}{z}, \quad f_{zz}(x, y, z) = -\frac{x}{z^2}$$

Finally, find the third partial derivatives with respect to x and z. Note that all three are equal.

$$f_{xzz}(x, y, z) = -\frac{1}{z^2}, \quad f_{zxz}(x, y, z) = -\frac{1}{z^2}, \quad f_{zzx}(x, y, z) = -\frac{1}{z^2}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

13.3 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. List three ways of writing the first partial derivative with respect to x of $z = f(x, y)$.
2. Sketch a surface representing a function f of two variables x and y. Use the sketch to give geometric interpretations of $\partial f/\partial x$ and $\partial f/\partial y$.
3. Describe the order in which the differentiation of $f(x, y, z)$ occurs for (a) f_{yxz} and (b) $\partial^2 f/\partial x \partial z$.
4. If f is a function of x and y such that f_{xy} and f_{yx} are continuous, what is the relationship between the mixed partial derivatives?

Examining a Partial Derivative **In Exercises 5–10, explain whether the Quotient Rule should be used to find the partial derivative. Do not differentiate.**

5. $\dfrac{\partial}{\partial x}\left(\dfrac{x^2y}{y^2 - 3}\right)$
6. $\dfrac{\partial}{\partial y}\left(\dfrac{x^2y}{y^2 - 3}\right)$
7. $\dfrac{\partial}{\partial y}\left(\dfrac{x - y}{x^2 + 1}\right)$
8. $\dfrac{\partial}{\partial x}\left(\dfrac{x - y}{x^2 + 1}\right)$
9. $\dfrac{\partial}{\partial x}\left(\dfrac{xy}{x^2 + 1}\right)$
10. $\dfrac{\partial}{\partial y}\left(\dfrac{xy}{x^2 + 1}\right)$

Finding Partial Derivatives **In Exercises 11–40, find both first partial derivatives.**

11. $f(x, y) = 2x - 5y + 3$
12. $f(x, y) = x^2 - 2y^2 + 4$
13. $z = 6x - x^2y + 8y^2$
14. $f(x, y) = 4x^3y^{-2}$
15. $z = x\sqrt{y}$
16. $z = 2y^2\sqrt{x}$
17. $z = e^{xy}$
18. $z = e^{x/y}$
19. $z = x^2e^{2y}$
20. $z = 7ye^{y/x}$
21. $z = \ln\dfrac{x}{y}$
22. $z = \ln\sqrt{xy}$
23. $z = \ln(x^2 + y^2)$
24. $z = \ln\dfrac{x + y}{x - y}$
25. $z = \dfrac{x^2}{2y} + \dfrac{3y^2}{x}$
26. $z = \dfrac{xy}{x^2 + y^2}$
27. $h(x, y) = e^{-(x^2+y^2)}$
28. $g(x, y) = \ln\sqrt{x^2 + y^2}$
29. $f(x, y) = \sqrt{x^2 + y^2}$
30. $f(x, y) = \sqrt{2x + y^3}$
31. $z = \cos xy$
32. $z = \sin(x + 2y)$
33. $z = \tan(2x - y)$
34. $z = \sin 5x \cos 5y$
35. $z = e^y \sin 8xy$
36. $z = \cos(x^2 + y^2)$
37. $z = \sinh(2x + 3y)$
38. $z = \cosh xy^2$
39. $f(x, y) = \displaystyle\int_x^y (t^2 - 1)\,dt$
40. $f(x, y) = \displaystyle\int_x^y (2t + 1)\,dt + \int_y^x (2t - 1)\,dt$

Finding Partial Derivatives **In Exercises 41–44, use the limit definition of partial derivatives to find $f_x(x, y)$ and $f_y(x, y)$.**

41. $f(x, y) = 3x + 2y$
42. $f(x, y) = x^2 - 2xy + y^2$
43. $f(x, y) = \sqrt{x + y}$
44. $f(x, y) = \dfrac{1}{x + y}$

Finding and Evaluating Partial Derivatives **In Exercises 45–52, find f_x and f_y, and evaluate each at the given point.**

45. $f(x, y) = e^x y^2$, $(\ln 3, 2)$
46. $f(x, y) = x^3 \ln 5y$, $(1, 1)$
47. $f(x, y) = \cos(2x - y)$, $\left(\dfrac{\pi}{4}, \dfrac{\pi}{3}\right)$
48. $f(x, y) = \sin xy$, $\left(2, \dfrac{\pi}{4}\right)$
49. $f(x, y) = \arctan\dfrac{y}{x}$, $(2, -2)$
50. $f(x, y) = \arccos xy$, $(1, 1)$
51. $f(x, y) = \dfrac{xy}{x - y}$, $(2, -2)$
52. $f(x, y) = \dfrac{2xy}{\sqrt{4x^2 + 5y^2}}$, $(1, 1)$

Finding the Slopes of a Surface **In Exercises 53–56, find the slopes of the surface in the x- and y-directions at the given point.**

53. $z = xy$
$(1, 2, 2)$



54. $z = \sqrt{25 - x^2 - y^2}$
$(3, 0, 4)$



55. $g(x, y) = 4 - x^2 - y^2$
$(1, 1, 2)$



56. $h(x, y) = x^2 - y^2$
$(-2, 1, 3)$



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding Partial Derivatives **In Exercises 57–62, find the first partial derivatives with respect to x, y, and z.**

57. $H(x, y, z) = \sin(x + 2y + 3z)$

58. $f(x, y, z) = 3x^2y - 5xyz + 10yz^2$

59. $w = \sqrt{x^2 + y^2 + z^2}$

60. $w = \dfrac{7xz}{x + y}$

61. $F(x, y, z) = \ln\sqrt{x^2 + y^2 + z^2}$

62. $G(x, y, z) = \dfrac{1}{\sqrt{1 - x^2 - y^2 - z^2}}$

Finding and Evaluating Partial Derivatives **In Exercises 63–68, find f_x, f_y, and f_z, and evaluate each at the given point.**

63. $f(x, y, z) = x^3yz^2,\ (1, 1, 1)$

64. $f(x, y, z) = x^2y^3 + 2xyz - 3yz,\ (-2, 1, 2)$

65. $f(x, y, z) = \dfrac{\ln x}{yz},\ (1, -1, -1)$

66. $f(x, y, z) = \dfrac{xy}{x + y + z},\ (3, 1, -1)$

67. $f(x, y, z) = z\sin(x + 6y),\ \left(0, \dfrac{\pi}{2}, -4\right)$

68. $f(x, y, z) = \sqrt{3x^2 + y^2 - 2z^2},\ (1, -2, 1)$

Using First Partial Derivatives **In Exercises 69–76, find all values of x and y such that $f_x(x, y) = 0$ and $f_y(x, y) = 0$ simultaneously.**

69. $f(x, y) = x^2 + xy + y^2 - 2x + 2y$

70. $f(x, y) = x^2 - xy + y^2 - 5x + y$

71. $f(x, y) = x^2 + 4xy + y^2 - 4x + 16y + 3$

72. $f(x, y) = x^2 - xy + y^2$

73. $f(x, y) = \dfrac{1}{x} + \dfrac{1}{y} + xy$

74. $f(x, y) = 3x^3 - 12xy + y^3$

75. $f(x, y) = e^{x^2 + xy + y^2}$

76. $f(x, y) = \ln(x^2 + y^2 + 1)$

Finding Second Partial Derivatives **In Exercises 77–86, find the four second partial derivatives. Observe that the second mixed partials are equal.**

77. $z = 3xy^2$

78. $z = x^2 + 3y^2$

79. $z = x^4 - 2xy + 3y^3$

80. $z = x^4 - 3x^2y^2 + y^4$

81. $z = \sqrt{x^2 + y^2}$

82. $z = \ln(x - y)$

83. $z = e^x \tan y$

84. $z = 2xe^y - 3ye^{-x}$

85. $z = \cos xy$

86. $z = \arctan\dfrac{y}{x}$

Finding Partial Derivatives Using Technology **In Exercises 87–90, use a graphing utility to find the first and second partial derivatives of the function. Determine whether there exist values of x and y such that $f_x(x, y) = 0$ and $f_y(x, y) = 0$ simultaneously.**

87. $f(x, y) = x\sec y$

88. $f(x, y) = \sqrt{25 - x^2 - y^2}$

89. $f(x, y) = \ln\dfrac{x}{x^2 + y^2}$

90. $f(x, y) = \dfrac{xy}{x - y}$

Finding Higher-Order Partial Derivatives **In Exercises 91–94, show that the mixed partial derivatives f_{xyy}, f_{yxy}, and f_{yyx} are equal.**

91. $f(x, y, z) = xyz$

92. $f(x, y, z) = x^2 - 3xy + 4yz + z^3$

93. $f(x, y, z) = e^{-x}\sin yz$

94. $f(x, y, z) = \dfrac{2z}{x + y}$

Laplace's Equation **In Exercises 95–98, show that the function satisfies Laplace's equation $\partial^2z/\partial x^2 + \partial^2z/\partial y^2 = 0$.**

95. $z = 5xy$

96. $z = \frac{1}{2}(e^y - e^{-y})\sin x$

97. $z = e^x\sin y$

98. $z = \arctan\dfrac{y}{x}$

Wave Equation **In Exercises 99–102, show that the function satisfies the wave equation $\partial^2z/\partial t^2 = c^2(\partial^2z/\partial x^2)$.**

99. $z = \sin(x - ct)$

100. $z = \cos(4x + 4ct)$

101. $z = \ln(x + ct)$

102. $z = \sin\omega ct\sin\omega x$

Heat Equation **In Exercises 103 and 104, show that the function satisfies the heat equation $\partial z/\partial t = c^2(\partial^2z/\partial x^2)$.**

103. $z = e^{-t}\cos\dfrac{x}{c}$

104. $z = e^{-t}\sin\dfrac{x}{c}$

Cauchy-Riemann Equations **In Exercises 105 and 106, show that the functions u and v satisfy the Cauchy-Riemann equations**

$$\frac{\partial u}{\partial x} = \frac{\partial v}{\partial y} \quad \text{and} \quad \frac{\partial u}{\partial y} = -\frac{\partial v}{\partial x}.$$

105. $u = x^2 - y^2,\ v = 2xy$

106. $u = e^x\cos y,\ v = e^x\sin y$

Using First Partial Derivatives **In Exercises 107 and 108, determine whether there exists a function $f(x, y)$ with the given partial derivatives. Explain your reasoning. If such a function exists, give an example.**

107. $f_x(x, y) = -3\sin(3x - 2y),\ f_y(x, y) = 2\sin(3x - 2y)$

108. $f_x(x, y) = 2x + y,\ f_y(x, y) = x - 4y$

Exploring Concepts

109. Consider $z = f(x, y)$ such that $z_x = z_y$. Does $z = c(x + y)$? Explain.

110. Given $z = f(x)g(y)$, find $z_x + z_y$.

111. Sketch the graph of a function $z = f(x, y)$ whose derivative f_x is always negative and whose derivative f_y is always positive.

112. The price P (in dollars) of a used car is a function of its initial cost C (in dollars) and its age A (in years). What are the units of $\partial P/\partial A$? Is $\partial P/\partial A$ positive or negative? Explain.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

113. Area A rectangle is 8 meters long and 6 meters wide (see figure). A horizontal line and a vertical line are drawn, creating four smaller rectangles.



Let S be the sum of the squares of the areas of the four smaller rectangles. Find the maximum and minimum values of S.

114. HOW DO YOU SEE IT? Use the graph of the surface to determine the sign of each partial derivative. Explain your reasoning.



(a) $f_x(4, 1)$ (b) $f_y(4, 1)$
(c) $f_x(-1, -2)$ (d) $f_y(-1, -2)$

115. Area The area of a triangle is represented by $A = \frac{1}{2}ab \sin\theta$, where a and b are two of the side lengths and θ is the angle between a and b.

(a) Find the rate of change of A with respect to b for $a = 4$, $b = 1$, and $\theta = \pi/4$.

(b) Find the rate of change of A with respect to θ for $a = 2$, $b = 5$, and $\theta = \pi/3$.

116. Volume The volume of a right circular cone of radius r and height h is represented by $V = \frac{1}{3}\pi r^2 h$.

(a) Find the rate of change of V with respect to r for $r = 2$ and $h = 2$.

(b) Find the rate of change of V with respect to h for $r = 2$ and $h = 2$.

117. Marginal Revenue A pharmaceutical corporation has two plants that produce the same over-the-counter medicine. If x_1 and x_2 are the numbers of units produced at plant 1 and plant 2, respectively, then the total revenue for the product is given by

$$R = 200x_1 + 200x_2 - 4x_1^2 - 8x_1x_2 - 4x_2^2.$$

When $x_1 = 4$ and $x_2 = 12$, find (a) the marginal revenue for plant 1, $\partial R/\partial x_1$, and (b) the marginal revenue for plant 2, $\partial R/\partial x_2$.

118. Marginal Costs

A company manufactures two types of wood-burning stoves: a freestanding model and a fireplace-insert model. The cost function for producing x freestanding and y fireplace-insert stoves is

$$C = 32\sqrt{xy} + 175x + 205y + 1050.$$

(a) Find the marginal costs ($\partial C/\partial x$ and $\partial C/\partial y$) when $x = 80$ and $y = 20$.

(b) When additional production is required, which model of stove results in the cost increasing at a higher rate? How can this be determined from the cost model?

119. Psychology Early in the twentieth century, an intelligence test called the *Stanford-Binet Test* (more commonly known as the IQ test) was developed. In this test, an individual's mental age M is divided by the individual's chronological age C and then the quotient is multiplied by 100. The result is the individual's IQ.

$$IQ(M, C) = \frac{M}{C} \times 100$$

Find the partial derivatives of IQ with respect to M and with respect to C. Evaluate the partial derivatives at the point $(12, 10)$ and interpret the result. *(Source: Adapted from Bernstein/Clark-Stewart/Roy/Wickens, Psychology, Fourth Edition)*

120. Marginal Productivity Consider the Cobb-Douglas production function $f(x, y) = 200x^{0.7}y^{0.3}$. When $x = 1000$ and $y = 500$, find (a) the marginal productivity of labor, $\partial f/\partial x$, and (b) the marginal productivity of capital, $\partial f/\partial y$.

121. Think About It Let N be the number of applicants to a university, p the charge for food and housing at the university, and t the tuition. Suppose that N is a function of p and t such that $\partial N/\partial p < 0$ and $\partial N/\partial t < 0$. What information is gained by noticing that both partials are negative?

122. Investment The value of an investment of \$1000 earning 6% compounded annually is

$$V(I, R) = 1000\left[\frac{1 + 0.06(1 - R)}{1 + I}\right]^{10}$$

where I is the annual rate of inflation and R is the tax rate for the person making the investment. Calculate $V_I(0.03, 0.28)$ and $V_R(0.03, 0.28)$. Determine whether the tax rate or the rate of inflation is the greater "negative" factor in the growth of the investment.

123. Temperature Distribution The temperature at any point (x, y) on a steel plate is $T = 500 - 0.6x^2 - 1.5y^2$, where x and y are measured in meters. At the point $(2, 3)$, find the rates of change of the temperature with respect to the distances moved along the plate in the directions of the x- and y-axes.

BRODOV/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

124. Apparent Temperature A measure of how hot weather feels to an average person is the Apparent Temperature Index. A model for this index is

$$A = 0.885t - 22.4h + 1.20th - 0.544$$

where A is the apparent temperature in degrees Celsius, t is the air temperature, and h is the relative humidity in decimal form. *(Source: The UMAP Journal)*

(a) Find $\frac{\partial A}{\partial t}$ and $\frac{\partial A}{\partial h}$ when $t = 30°$ and $h = 0.80$.

(b) Which has a greater effect on A, air temperature or humidity? Explain.

125. Ideal Gas Law The Ideal Gas Law states that

$$PV = nRT$$

where P is pressure, V is volume, n is the number of moles of gas, R is a fixed constant (the gas constant), and T is absolute temperature. Show that

$$\frac{\partial T}{\partial P} \cdot \frac{\partial P}{\partial V} \cdot \frac{\partial V}{\partial T} = -1.$$

126. Marginal Utility The utility function $U = f(x, y)$ is a measure of the utility (or satisfaction) derived by a person from the consumption of two products x and y. The utility function for two products is

$$U = -5x^2 + xy - 3y^2.$$

(a) Determine the marginal utility of product x.

(b) Determine the marginal utility of product y.

(c) When $x = 2$ and $y = 3$, should a person consume one more unit of product x or one more unit of product y? Explain your reasoning.

(d) Use a graphing utility to graph the function. Interpret the marginal utilities of products x and y graphically.

127. Modeling Data Personal consumption expenditures (in billions of dollars) for several types of recreation from 2012 through 2017 are shown in the table, where x is the expenditures on amusement parks and campgrounds, y is the expenditures on live entertainment (excluding sports), and z is the expenditures on spectator sports. *(Source: U.S. Bureau of Economic Analysis)*

Year	2012	2013	2014	2015	2016	2017
x	44.3	46.8	49.8	54.2	57.9	61.9
y	24.9	24.8	26.5	28.9	30.7	32.6
z	20.9	22.1	23.2	23.1	24.2	26.1

A model for the data is given by

$$z = 0.54x - 0.6y + 11.98.$$

(a) Find $\frac{\partial z}{\partial x}$ and $\frac{\partial z}{\partial y}$.

(b) Interpret the partial derivatives in the context of the problem.

128. Modeling Data The table shows the national health expenditures (in billions of dollars) for the Department of Veterans Affairs x, workers' compensation y, and Medicaid z from 2014 through 2019. *(Source: Centers for Medicare and Medicaid Services)*

Year	2014	2015	2016	2017	2018	2019
x	57.9	64.7	67.4	72.1	76.2	82.3
y	47.5	48.4	48.8	47.9	48.5	48.5
z	498.2	542.7	564.8	578.2	596.0	613.5

A model for the data is given by

$$z = -0.111x^2 + 20.256x + 14.003y^2 - 1343.977y + 31{,}942.$$

(a) Find $\frac{\partial^2 z}{\partial x^2}$ and $\frac{\partial^2 z}{\partial y^2}$.

(b) Determine the concavity of traces parallel to the xz-plane. Interpret the result in the context of the problem.

(c) Determine the concavity of traces parallel to the yz-plane. Interpret the result in the context of the problem.

129. Using a Function Consider the function defined by

$$f(x, y) = \begin{cases} \dfrac{xy(x^2 - y^2)}{x^2 + y^2}, & (x, y) \neq (0, 0) \\ 0, & (x, y) = (0, 0) \end{cases}.$$

(a) Find $f_x(x, y)$ and $f_y(x, y)$ for $(x, y) \neq (0, 0)$.

(b) Use the definition of partial derivatives to find $f_x(0, 0)$ and $f_y(0, 0)$.

$$\left[\textit{Hint: } f_x(0, 0) = \lim_{\Delta x \to 0} \frac{f(\Delta x, 0) - f(0, 0)}{\Delta x} \right]$$

(c) Use the definition of partial derivatives to find $f_{xy}(0, 0)$ and $f_{yx}(0, 0)$.

(d) Using Theorem 13.3 and the result of part (c), what can be said about f_{xy} or f_{yx}?

130. Using a Function Consider the function

$$f(x, y) = (x^3 + y^3)^{1/3}.$$

(a) Find $f_x(0, 0)$ and $f_y(0, 0)$.

(b) Determine the points (if any) at which $f_x(x, y)$ or $f_y(x, y)$ fails to exist.

131. Using a Function Consider the function

$$f(x, y) = (x^2 + y^2)^{2/3}.$$

Show that

$$f_x(x, y) = \begin{cases} \dfrac{4x}{3(x^2 + y^2)^{1/3}}, & (x, y) \neq (0, 0) \\ 0, & (x, y) = (0, 0) \end{cases}.$$

FOR FURTHER INFORMATION For more information about this problem, see the article "A Classroom Note on a Naturally Occurring Piecewise Defined Function" by Don Cohen in *Mathematics and Computer Education.*

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

13.4 Differentials

GO DIGITAL

- Apply the concepts of increments and differentials.
- Extend the concept of differentiability to a function of two variables.
- Use a differential as an approximation.

Increments and Differentials

In this section, the concepts of increments and differentials are generalized to functions of two or more variables. Recall from Section 3.9 that for $y = f(x)$, the differential of y was defined as

$$dy = f'(x)\,dx.$$

Similar terminology is used for a function of two variables, $z = f(x, y)$. That is, Δx and Δy are the **increments of x and y,** and the **increment of z** is

$$\Delta z = f(x + \Delta x, y + \Delta y) - f(x, y).$$ Increment of z

Definition of Total Differential

If $z = f(x, y)$ and Δx and Δy are increments of x and y, then the **differentials** of the independent variables x and y are

$$dx = \Delta x \quad \text{and} \quad dy = \Delta y$$

and the **total differential** of the dependent variable z is

$$dz = \frac{\partial z}{\partial x}\,dx + \frac{\partial z}{\partial y}\,dy = f_x(x, y)\,dx + f_y(x, y)\,dy.$$

This definition can be extended to a function of three or more variables. For instance, if $w = f(x, y, z, u)$, then $dx = \Delta x$, $dy = \Delta y$, $dz = \Delta z$, $du = \Delta u$, and the total differential of w is

$$dw = \frac{\partial w}{\partial x}\,dx + \frac{\partial w}{\partial y}\,dy + \frac{\partial w}{\partial z}\,dz + \frac{\partial w}{\partial u}\,du.$$

EXAMPLE 1 Finding the Total Differential

Find the total differential for each function.

a. $z = 2x \sin y - 3x^2y^2$ **b.** $w = x^2 + y^2 + z^2$

Solution

a. The total differential dz for $z = 2x \sin y - 3x^2y^2$ is

$$dz = \frac{\partial z}{\partial x}\,dx + \frac{\partial z}{\partial y}\,dy$$ Total differential dz

$$= (2 \sin y - 6xy^2)\,dx + (2x \cos y - 6x^2y)\,dy.$$

b. The total differential dw for $w = x^2 + y^2 + z^2$ is

$$dw = \frac{\partial w}{\partial x}\,dx + \frac{\partial w}{\partial y}\,dy + \frac{\partial w}{\partial z}\,dz$$ Total differential dw

$$= 2x\,dx + 2y\,dy + 2z\,dz.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Differentiability

In Section 3.9, you learned that for a *differentiable* function given by $y = f(x)$, you can use the differential $dy = f'(x)\,dx$ as an approximation (for small Δx) of the value $\Delta y = f(x + \Delta x) - f(x)$. When a similar approximation is possible for a function of two variables, the function is said to be **differentiable.** This is stated explicitly in the next definition.

Definition of Differentiability

A function f given by $z = f(x, y)$ is **differentiable** at (x_0, y_0) if Δz can be written in the form

$$\Delta z = f_x(x_0, y_0)\,\Delta x + f_y(x_0, y_0)\,\Delta y + \varepsilon_1 \Delta x + \varepsilon_2 \Delta y$$

where both ε_1 and $\varepsilon_2 \to 0$ as

$$(\Delta x, \Delta y) \to (0, 0).$$

The function f is **differentiable in a region R** if it is differentiable at each point in R.

EXAMPLE 2 Showing That a Function Is Differentiable

Show that the function

$$f(x, y) = x^2 + 3y$$

is differentiable at every point in the plane.

Solution Letting $z = f(x, y)$, the increment of z at an arbitrary point (x, y) in the plane is

$$\begin{aligned}
\Delta z &= f(x + \Delta x, y + \Delta y) - f(x, y) && \text{Increment of } z \\
&= (x + \Delta x)^2 + 3(y + \Delta y) - (x^2 + 3y) \\
&= x^2 + 2x\Delta x + (\Delta x)^2 + 3y + 3\Delta y - x^2 - 3y \\
&= 2x\Delta x + (\Delta x)^2 + 3\Delta y \\
&= 2x(\Delta x) + 3(\Delta y) + \Delta x(\Delta x) + 0(\Delta y) \\
&= f_x(x, y)\Delta x + f_y(x, y)\Delta y + \varepsilon_1 \Delta x + \varepsilon_2 \Delta y
\end{aligned}$$

where $\varepsilon_1 = \Delta x$ and $\varepsilon_2 = 0$. Because $\varepsilon_1 \to 0$ and $\varepsilon_2 \to 0$ as $(\Delta x, \Delta y) \to (0, 0)$, it follows that f is differentiable at every point in the plane. The graph of f is shown in Figure 13.34. ■



Figure 13.34

Be sure you understand that the term "differentiable" is used differently for functions of two variables than for functions of one variable. A function of one variable is differentiable at a point when its derivative exists at the point. For a function of two variables, however, the existence of the partial derivatives f_x and f_y does not guarantee that the function is differentiable (see Example 5). The next theorem gives a *sufficient* condition for differentiability of a function of two variables.

THEOREM 13.4 Sufficient Condition for Differentiability

If f is a function of x and y, where f_x and f_y are continuous in an open region R, then f is differentiable on R. A proof of this theorem is given in Appendix A.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The exact change in z is Δz. This change can be approximated by the differential dz.

Figure 13.35

Approximation by Differentials

Theorem 13.4 tells you that you can choose $(x + \Delta x, y + \Delta y)$ close enough to (x, y) to make $\varepsilon_1\Delta x$ and $\varepsilon_2\Delta y$ insignificant. In other words, for small Δx and Δy, you can use the approximation

$$\Delta z \approx dz.$$ Approximate change in z

This approximation is illustrated graphically in Figure 13.35. Recall that the partial derivatives $\partial z/\partial x$ and $\partial z/\partial y$ can be interpreted as the slopes of the surface in the x- and y-directions. This means that

$$dz = \frac{\partial z}{\partial x}\Delta x + \frac{\partial z}{\partial y}\Delta y$$

represents the change in height of a plane that is tangent to the surface at the point $(x, y, f(x, y))$. Because a plane in space is represented by a linear equation in the variables x, y, and z, the approximation of Δz by dz is called a **linear approximation.** You will learn more about this geometric interpretation in Section 13.7.

EXAMPLE 3 Using a Differential as an Approximation

See LarsonCalculus.com for an interactive version of this type of example.

Use the differential dz to approximate the change in

$$z = \sqrt{4 - x^2 - y^2}$$

as (x, y) moves from the point $(1, 1)$ to the point $(1.01, 0.97)$. Compare this approximation with the exact change in z.



As (x, y) moves from the point $(1, 1)$ to the point $(1.01, 0.97)$, the value of $f(x, y)$ changes by about 0.0137.

Figure 13.36

Solution Letting $(x, y) = (1, 1)$ and $(x + \Delta x, y + \Delta y) = (1.01, 0.97)$ produces

$$dx = \Delta x = 0.01 \quad \text{and} \quad dy = \Delta y = -0.03.$$

So, the change in z can be approximated by

$$\Delta z \approx dz = \frac{\partial z}{\partial x}dx + \frac{\partial z}{\partial y}dy = \frac{-x}{\sqrt{4 - x^2 - y^2}}\Delta x + \frac{-y}{\sqrt{4 - x^2 - y^2}}\Delta y.$$

When $x = 1$ and $y = 1$, you have

$$\Delta z \approx -\frac{1}{\sqrt{2}}(0.01) - \frac{1}{\sqrt{2}}(-0.03) = \frac{0.02}{\sqrt{2}} = \sqrt{2}(0.01) \approx 0.0141.$$

In Figure 13.36, notice that the exact change corresponds to the difference in the heights of two points on the surface of a hemisphere. This difference is given by

$$\begin{aligned}\Delta z &= f(1.01, 0.97) - f(1, 1)\\ &= \sqrt{4 - (1.01)^2 - (0.97)^2} - \sqrt{4 - 1^2 - 1^2}\\ &\approx 0.0137.\end{aligned}$$

■

A function of three variables $w = f(x, y, z)$ is **differentiable** at (x, y, z) provided that $\Delta w = f(x + \Delta x, y + \Delta y, z + \Delta z) - f(x, y, z)$ can be written in the form

$$\Delta w = f_x\Delta x + f_y\Delta y + f_z\Delta z + \varepsilon_1\Delta x + \varepsilon_2\Delta y + \varepsilon_3\Delta z$$

where ε_1, ε_2, and $\varepsilon_3 \to 0$ as $(\Delta x, \Delta y, \Delta z) \to (0, 0, 0)$. With this definition of differentiability, Theorem 13.4 has the following extension for functions of three variables: If f is a function of x, y, and z, where f_x, f_y, and f_z are continuous in an open region R, then f is differentiable on R.

In Section 3.9, you used differentials to approximate the propagated error introduced by an error in measurement. This application of differentials is further illustrated in Example 4.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Volume = xyz

Figure 13.37

EXAMPLE 4 Error Analysis

The possible error involved in measuring each dimension of a rectangular box is ± 0.1 millimeter. The dimensions of the box are $x = 50$ centimeters, $y = 20$ centimeters, and $z = 15$ centimeters, as shown in Figure 13.37. Use dV to estimate the propagated error and the relative error in the calculated volume of the box.

Solution The volume of the box is $V = xyz$, so

$$\begin{aligned} dV &= \frac{\partial V}{\partial x}\,dx + \frac{\partial V}{\partial y}\,dy + \frac{\partial V}{\partial z}\,dz \\ &= yz\,dx + xz\,dy + xy\,dz. \end{aligned}$$

Using 0.1 millimeter = 0.01 centimeter, you have

$$dx = dy = dz = \pm 0.01$$

and the propagated error is approximately

$$\begin{aligned} dV &= (20)(15)(\pm 0.01) + (50)(15)(\pm 0.01) + (50)(20)(\pm 0.01) \\ &= 300(\pm 0.01) + 750(\pm 0.01) + 1000(\pm 0.01) \\ &= 2050(\pm 0.01) \\ &= \pm 20.5 \text{ cubic centimeters.} \end{aligned}$$

Because the measured volume is

$$V = (50)(20)(15) = 15{,}000 \text{ cubic centimeters}$$

the relative error, $\Delta V/V$, is approximately

$$\frac{\Delta V}{V} \approx \frac{dV}{V} = \frac{\pm 20.5}{15{,}000} \approx \pm 0.0014$$

which is a percent error of about 0.14%. ■

As is true for a function of a single variable, when a function in two or more variables is differentiable at a point, it is also continuous there.

THEOREM 13.5 Differentiability Implies Continuity

If a function of x and y is differentiable at (x_0, y_0), then it is continuous at (x_0, y_0).

Proof Let f be differentiable at (x_0, y_0), where $z = f(x, y)$. Then

$$\Delta z = [f_x(x_0, y_0) + \varepsilon_1]\,\Delta x + [f_y(x_0, y_0) + \varepsilon_2]\,\Delta y$$

where both ε_1 and $\varepsilon_2 \to 0$ as $(\Delta x, \Delta y) \to (0, 0)$. However, by definition, you know that Δz is

$$\Delta z = f(x_0 + \Delta x, y_0 + \Delta y) - f(x_0, y_0).$$

Letting $x = x_0 + \Delta x$ and $y = y_0 + \Delta y$ produces

$$\begin{aligned} f(x, y) - f(x_0, y_0) &= [f_x(x_0, y_0) + \varepsilon_1]\,\Delta x + [f_y(x_0, y_0) + \varepsilon_2]\,\Delta y \\ &= [f_x(x_0, y_0) + \varepsilon_1](x - x_0) + [f_y(x_0, y_0) + \varepsilon_2](y - y_0). \end{aligned}$$

Taking the limit as $(x, y) \to (x_0, y_0)$, you have

$$\lim_{(x, y) \to (x_0, y_0)} f(x, y) = f(x_0, y_0)$$

which means that f is continuous at (x_0, y_0). ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Remember that the existence of f_x and f_y is not sufficient to guarantee differentiability, as illustrated in the next example.

EXAMPLE 5 A Function That Is Not Differentiable

For the function

$$f(x, y) = \begin{cases} \dfrac{-3xy}{x^2 + y^2}, & (x, y) \neq (0, 0) \\ 0, & (x, y) = (0, 0) \end{cases}$$

show that $f_x(0, 0)$ and $f_y(0, 0)$ both exist but that f is not differentiable at $(0, 0)$.

Solution You can show that f is not differentiable at $(0, 0)$ by showing that it is not continuous at this point. To show that f is not continuous at $(0, 0)$, check the values of $f(x, y)$ along two different approaches to $(0, 0)$, as shown in Figure 13.38. Along the line $y = x$, the limit is

$$\lim_{(x, x) \to (0, 0)} f(x, y) = \lim_{(x, x) \to (0, 0)} \frac{-3x^2}{2x^2} = -\frac{3}{2}$$

whereas along $y = -x$, you have

$$\lim_{(x, -x) \to (0, 0)} f(x, y) = \lim_{(x, -x) \to (0, 0)} \frac{3x^2}{2x^2} = \frac{3}{2}.$$

So, the limit of $f(x, y)$ as $(x, y) \to (0, 0)$ does not exist, and you can conclude that f is not continuous at $(0, 0)$. Therefore, by Theorem 13.5, you know that f is not differentiable at $(0, 0)$. On the other hand, by the definition of the partial derivatives f_x and f_y, you have

$$f_x(0, 0) = \lim_{\Delta x \to 0} \frac{f(\Delta x, 0) - f(0, 0)}{\Delta x} = \lim_{\Delta x \to 0} \frac{0 - 0}{\Delta x} = 0$$

and

$$f_y(0, 0) = \lim_{\Delta y \to 0} \frac{f(0, \Delta y) - f(0, 0)}{\Delta y} = \lim_{\Delta y \to 0} \frac{0 - 0}{\Delta y} = 0.$$

So, the partial derivatives at $(0, 0)$ exist.


$f(x, y) = \begin{cases} \frac{-3xy}{x^2 + y^2}, & (x, y) \neq (0, 0) \\ 0, & (x, y) = (0, 0) \end{cases}$
Along the line $y = -x$, $f(x, y)$ approaches 3/2.
z
(0, 0, 0)
y
x
Along the line $y = x$, $f(x, y)$ approaches $-3/2$.

Figure 13.38

TECHNOLOGY A graphing utility can be used to graph piecewise-defined functions like the one given in Example 5.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

13.4 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe the change in accuracy of dz as an approximation of Δz as Δx and Δy increase.
2. Explain what is meant by a linear approximation of $z = f(x, y)$ at the point $P(x_0, y_0)$.

Finding a Total Differential **In Exercises 3–8, find the total differential.**

3. $z = 5x^3y^2$
4. $z = 2x^3y - 8xy^4$
5. $z = \frac{1}{2}\left(e^{x^2+y^2} - e^{-x^2-y^2}\right)$
6. $z = e^{-x}\tan y$
7. $w = x^2yz^2 + \sin yz$
8. $w = (x + y)/(z - 3y)$

Using a Differential as an Approximation **In Exercises 9–14, (a) find $f(2, 1)$ and $f(2.1, 1.05)$ and calculate Δz, and (b) use the total differential dz to approximate Δz.**

9. $f(x, y) = 2x - 3y$
10. $f(x, y) = x^2 + y^2$
11. $f(x, y) = 16 - x^2 - y^2$
12. $f(x, y) = y/x$
13. $f(x, y) = ye^x$
14. $f(x, y) = x\cos y$

Approximating an Expression **In Exercises 15–18, find $z = f(x, y)$ and use the total differential to approximate the quantity.**

15. $(2.01)^2(9.02) - 2^2 \cdot 9$
16. $\dfrac{1 - (3.05)^2}{(5.95)^2} - \dfrac{1 - 3^2}{6^2}$
17. $\sin[(1.05)^2 + (0.95)^2] - \sin(1^2 + 1^2)$
18. $\sqrt{(4.03)^2 + (3.1)^2} - \sqrt{4^2 + 3^2}$

Exploring Concepts

19. Determine whether $f(x, y)$ is continuous in an open region R when f_x and f_y are each continuous in R. Explain your reasoning.

20. **HOW DO YOU SEE IT?** Which point has a greater differential, (2, 2) or $\left(\frac{1}{2}, \frac{1}{2}\right)$? Explain. (Assume that dx and dy are the same for both points.)



21. **Area** The area of the shaded rectangle in the figure is $A = lh$. The possible errors in the length and height are Δl and Δh, respectively. Find dA and identify the regions in the figure whose areas are given by the terms of dA. What region represents the difference between ΔA and dA?



Figure for 21



Figure for 22

22. **Volume** The volume of the red right circular cylinder in the figure is $V = \pi r^2 h$. The possible errors in the radius and the height are Δr and Δh, respectively. Find dV and identify the solids in the figure whose volumes are given by the terms of dV. What solid represents the difference between ΔV and dV?
23. **Volume** The possible error involved in measuring each dimension of a rectangular box is ± 0.02 inch. The dimensions of the box are 8 inches by 5 inches by 12 inches. Approximate the propagated error and the relative error in the calculated volume of the box.
24. **Volume** The possible error involved in measuring each dimension of a right circular cylinder is ± 0.05 centimeter. The radius is 3 centimeters and the height is 10 centimeters. Approximate the propagated error and the relative error in the calculated volume of the cylinder.
25. **Numerical Analysis** A right circular cone of height $h = 8$ meters and radius $r = 4$ meters is constructed, and in the process, errors Δr and Δh are made in the radius and height, respectively. Let V be the volume of the cone. Complete the table to show the relationship between ΔV and dV for the indicated errors.

Δr	Δh	dV or dS	ΔV or ΔS	$\Delta V - dV$ or $\Delta S - dS$
0.1	0.1			
0.1	−0.1			
0.001	0.002			
−0.0001	0.0002			

Table for Exercises 25 and 26

26. **Numerical Analysis** A right circular cone of height $h = 16$ meters and radius $r = 6$ meters is constructed, and in the process, errors of Δr and Δh are made in the radius and height, respectively. Let S be the lateral surface area of the cone. Complete the table above to show the relationship between ΔS and dS for the indicated errors.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

27. Wind Chill

The formula for wind chill C (in degrees Fahrenheit) is given by

$$C = 35.74 + 0.6215T - 35.75v^{0.16} + 0.4275Tv^{0.16}$$

where v is the wind speed in miles per hour and T is the temperature in degrees Fahrenheit. The wind speed is 23 ± 3 miles per hour and the temperature is $8° \pm 1°$. Use dC to estimate the maximum possible propagated error and relative error in calculating the wind chill. *(Source: National Oceanic and Atmospheric Administration)*

28. Resistance The total resistance R (in ohms) of two resistors connected in parallel is given by

$$\frac{1}{R} = \frac{1}{R_1} + \frac{1}{R_2}.$$

Approximate the change in R as R_1 is increased from 10 ohms to 10.5 ohms and R_2 is decreased from 15 ohms to 13 ohms.

29. Power Electrical power P is given by

$$P = \frac{E^2}{R}$$

where E is voltage and R is resistance. Approximate the maximum percent error in calculating power when 120 volts is applied to a 2000-ohm resistor and the possible percent errors in measuring E and R are 3% and 4%, respectively.

30. Acceleration The centripetal acceleration of a particle moving in a circle is $a = v^2/r$, where v is the velocity and r is the radius of the circle. Approximate the maximum percent error in measuring the acceleration due to errors of 3% in v and 2% in r.

31. Volume A trough is 16 feet long (see figure). Its cross sections are isosceles triangles with each of the two equal sides measuring 18 inches. The angle between the two equal sides is θ.



Not drawn to scale

(a) Write the volume of the trough as a function of θ and determine the value of θ such that the volume is a maximum.

(b) The maximum error in the linear measurements is one-half inch, and the maximum error in the angle measure is 2°. Approximate the change in the maximum volume.

32. Sports A baseball player in center field is playing approximately 330 feet from a television camera that is behind home plate. A batter hits a fly ball that goes to the wall 420 feet from the camera (see figure).



(a) The camera turns 9° to follow the play. Approximate the number of feet that the center fielder has to run to make the catch.

(b) The position of the center fielder could be in error by as much as 6 feet, and the maximum error in measuring the rotation of the camera is 1°. Approximate the maximum possible error in the result of part (a).

33. Inductance The inductance L (in microhenrys) of a straight nonmagnetic wire in free space is

$$L = 0.00021\left(\ln\frac{2h}{r} - 0.75\right)$$

where h is the length of the wire in millimeters and r is the radius of a circular cross section. Approximate L when $r = 2 \pm \frac{1}{16}$ millimeters and $h = 100 \pm \frac{1}{100}$ millimeters.

34. Pendulum The period T of a pendulum of length L is $T = \left(2\pi\sqrt{L}\right)/\sqrt{g}$, where g is the acceleration due to gravity. A pendulum is moved from the Canal Zone, where $g = 32.09$ feet per second per second, to Greenland, where $g = 32.23$ feet per second per second. Because of the change in temperature, the length of the pendulum changes from 2.5 feet to 2.48 feet. Approximate the change in the period of the pendulum.

Differentiability **In Exercises 35–38, show that the function is differentiable by finding values of ε_1 and ε_2 as designated in the definition of differentiability, and verify that both ε_1 and ε_2 approach 0 as $(\Delta x, \Delta y) \to (0, 0)$.**

35. $f(x, y) = x^2 - 2x + y$

36. $f(x, y) = x^2 + y^2$

37. $f(x, y) = x^2y$

38. $f(x, y) = 5x - 10y + y^3$

Differentiability **In Exercises 39–41, use the function to show that $f_x(0, 0)$ and $f_y(0, 0)$ both exist but that f is not differentiable at $(0, 0)$.**

39. $$f(x, y) = \begin{cases} \dfrac{3x^2y}{x^4 + y^2}, & (x, y) \neq (0, 0) \\ 0, & (x, y) = (0, 0) \end{cases}$$

40. $$f(x, y) = \begin{cases} \dfrac{5x^2y}{x^3 + y^3}, & (x, y) \neq (0, 0) \\ 0, & (x, y) = (0, 0) \end{cases}$$

41. $$f(x, y) = \begin{cases} 1, & x = 0 \text{ or } y = 0 \\ 0, & \text{elsewhere} \end{cases}$$

lpedan/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

13.5 Chain Rules for Functions of Several Variables

GO DIGITAL

- **Use the Chain Rules for functions of several variables.**
- **Find partial derivatives implicitly.**



Chain Rule: one independent variable w is a function of x and y, which are each functions of t. This diagram represents the derivative of w with respect to t.

Figure 13.39

Chain Rules for Functions of Several Variables

Your work with differentials in the preceding section provides the basis for the extension of the Chain Rule to functions of two variables. There are two cases. The first case involves w as a function of x and y, where x and y are functions of a single independent variable t, as shown in Theorem 13.6.

THEOREM 13.6 Chain Rule: One Independent Variable

Let $w = f(x, y)$, where f is a differentiable function of x and y. If $x = g(t)$ and $y = h(t)$, where g and h are differentiable functions of t, then w is a differentiable function of t, and

$$\frac{dw}{dt} = \frac{\partial w}{\partial x}\frac{dx}{dt} + \frac{\partial w}{\partial y}\frac{dy}{dt}.$$

The Chain Rule is shown schematically in Figure 13.39.
A proof of this theorem is given in Appendix A.

EXAMPLE 1 Chain Rule: One Independent Variable

Let $w = x^2y - y^2$, where $x = \sin t$ and $y = e^t$. Find dw/dt when $t = 0$.

Solution By the Chain Rule for one independent variable, you have

$$\begin{aligned}
\frac{dw}{dt} &= \frac{\partial w}{\partial x}\frac{dx}{dt} + \frac{\partial w}{\partial y}\frac{dy}{dt} && \text{Apply Theorem 13.6.}\\
&= 2xy(\cos t) + (x^2 - 2y)e^t && \text{Find derivatives.}\\
&= 2(\sin t)(e^t)(\cos t) + (\sin^2 t - 2e^t)e^t && \text{Substitute } x = \sin t \text{ and } y = e^t.\\
&= 2e^t \sin t \cos t + e^t \sin^2 t - 2e^{2t}. && \text{Simplify.}
\end{aligned}$$

When $t = 0$, it follows that

$$\frac{dw}{dt} = -2. \qquad \text{Evaluate } \frac{dw}{dt} \text{ when } t = 0.$$

The Chain Rules presented in this section provide alternative techniques for solving many problems in single-variable calculus. For instance, in Example 1, you could have used single-variable techniques to find dw/dt by first writing w as a function of t,

$$\begin{aligned}
w &= x^2y - y^2 && w \text{ as a function of } x \text{ and } y\\
&= (\sin t)^2(e^t) - (e^t)^2 && \text{Substitute } x = \sin t \text{ and } y = e^t.\\
&= e^t \sin^2 t - e^{2t} && w \text{ as a function of } t
\end{aligned}$$

and then differentiating as usual. As shown below, the result is the same as the one in Example 1.

$$\begin{aligned}
\frac{dw}{dt} &= e^t(2)(\sin t)(\cos t) + (\sin^2 t)(e^t) - e^{2t}(2)\\
&= 2e^t \sin t \cos t + e^t \sin^2 t - 2e^{2t}
\end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The Chain Rule in Theorem 13.6 can be extended to any number of variables. For example, if each x_i is a differentiable function of a single variable t, then for

$$w = f(x_1, x_2, \ldots, x_n)$$

you have

$$\frac{dw}{dt} = \frac{\partial w}{\partial x_1}\frac{dx_1}{dt} + \frac{\partial w}{\partial x_2}\frac{dx_2}{dt} + \cdots + \frac{\partial w}{\partial x_n}\frac{dx_n}{dt}.$$

EXAMPLE 2 An Application of a Chain Rule to Related Rates

Two objects are traveling in elliptical paths given by the following parametric equations.

$x_1 = 4\cos t$ and $y_1 = 2\sin t$ First object

$x_2 = 2\sin 2t$ and $y_2 = 3\cos 2t$ Second object

At what rate is the distance between the two objects changing when $t = \pi$?

Solution From Figure 13.40, you can determine that the distance s between the two objects is given by

$$s = \sqrt{(x_2 - x_1)^2 + (y_2 - y_1)^2}$$

and that when $t = \pi$, you have $x_1 = -4$, $y_1 = 0$, $x_2 = 0$, $y_2 = 3$, and

$$s = \sqrt{(0 + 4)^2 + (3 + 0)^2} = 5.$$

When $t = \pi$, the partial derivatives of s are as follows.

$$\frac{\partial s}{\partial x_1} = \frac{-(x_2 - x_1)}{\sqrt{(x_2 - x_1)^2 + (y_2 - y_1)^2}} = -\frac{1}{5}(0 + 4) = -\frac{4}{5}$$

$$\frac{\partial s}{\partial y_1} = \frac{-(y_2 - y_1)}{\sqrt{(x_2 - x_1)^2 + (y_2 - y_1)^2}} = -\frac{1}{5}(3 - 0) = -\frac{3}{5}$$

$$\frac{\partial s}{\partial x_2} = \frac{(x_2 - x_1)}{\sqrt{(x_2 - x_1)^2 + (y_2 - y_1)^2}} = \frac{1}{5}(0 + 4) = \frac{4}{5}$$

$$\frac{\partial s}{\partial y_2} = \frac{(y_2 - y_1)}{\sqrt{(x_2 - x_1)^2 + (y_2 - y_1)^2}} = \frac{1}{5}(3 - 0) = \frac{3}{5}$$

When $t = \pi$, the derivatives of x_1, y_1, x_2, and y_2 are

$$\frac{dx_1}{dt} = -4\sin t = 0$$

$$\frac{dy_1}{dt} = 2\cos t = -2$$

$$\frac{dx_2}{dt} = 4\cos 2t = 4$$

$$\frac{dy_2}{dt} = -6\sin 2t = 0.$$

So, using the appropriate Chain Rule, you know that the distance is changing at a rate of

$$\frac{ds}{dt} = \frac{\partial s}{\partial x_1}\frac{dx_1}{dt} + \frac{\partial s}{\partial y_1}\frac{dy_1}{dt} + \frac{\partial s}{\partial x_2}\frac{dx_2}{dt} + \frac{\partial s}{\partial y_2}\frac{dy_2}{dt}$$

$$= \left(-\frac{4}{5}\right)(0) + \left(-\frac{3}{5}\right)(-2) + \left(\frac{4}{5}\right)(4) + \left(\frac{3}{5}\right)(0)$$

$$= \frac{22}{5}.$$



Paths of two objects traveling in elliptical orbits

Figure 13.40

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

In Example 2, note that s is the function of four *intermediate* variables, x_1, y_1, x_2, and y_2, each of which is a function of a single variable t. Another type of composite function is one in which the intermediate variables are themselves functions of more than one variable. For instance, for $w = f(x, y)$, where $x = g(s, t)$ and $y = h(s, t)$, it follows that w is a function of s and t, and you can consider the partial derivatives of w with respect to s and t. One way to find these partial derivatives is to write w as a function of s and t explicitly by substituting the equations $x = g(s, t)$ and $y = h(s, t)$ into the equation $w = f(x, y)$. Then you can find the partial derivatives in the usual way, as demonstrated in the next example.

EXAMPLE 3 Finding Partial Derivatives by Substitution

Find $\partial w/\partial s$ and $\partial w/\partial t$ for $w = 2xy$, where $x = s^2 + t^2$ and $y = s/t$.

Solution Begin by substituting $x = s^2 + t^2$ and $y = s/t$ into the equation $w = 2xy$ to obtain

$$w = 2xy = 2(s^2 + t^2)\left(\frac{s}{t}\right) = 2\left(\frac{s^3}{t} + st\right).$$

Then, to find $\partial w/\partial s$, hold t constant and differentiate with respect to s.

$$\frac{\partial w}{\partial s} = 2\left(\frac{3s^2}{t} + t\right) \qquad t \text{ is held constant.}$$
$$= \frac{6s^2 + 2t^2}{t}$$

Similarly, to find $\partial w/\partial t$, hold s constant and differentiate with respect to t to obtain

$$\frac{\partial w}{\partial t} = 2\left(-\frac{s^3}{t^2} + s\right) \qquad s \text{ is held constant.}$$
$$= 2\left(\frac{-s^3 + st^2}{t^2}\right)$$
$$= \frac{2st^2 - 2s^3}{t^2}.$$

Theorem 13.7 gives an alternative method for finding the partial derivatives in Example 3 without explicitly writing w as a function of s and t.



Chain Rule: two independent variables
Figure 13.41

THEOREM 13.7 Chain Rule: Two Independent Variables

Let $w = f(x, y)$, where f is a differentiable function of x and y. If $x = g(s, t)$ and $y = h(s, t)$ such that the first partials $\partial x/\partial s$, $\partial x/\partial t$, $\partial y/\partial s$, and $\partial y/\partial t$ all exist, then $\partial w/\partial s$ and $\partial w/\partial t$ exist and are given by

$$\frac{\partial w}{\partial s} = \frac{\partial w}{\partial x}\frac{\partial x}{\partial s} + \frac{\partial w}{\partial y}\frac{\partial y}{\partial s}$$

and

$$\frac{\partial w}{\partial t} = \frac{\partial w}{\partial x}\frac{\partial x}{\partial t} + \frac{\partial w}{\partial y}\frac{\partial y}{\partial t}.$$

The Chain Rule is shown schematically in Figure 13.41.

Proof To obtain $\partial w/\partial s$, hold t constant and apply Theorem 13.6 to obtain the desired result. Similarly, for $\partial w/\partial t$, hold s constant and apply Theorem 13.6.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 4 The Chain Rule with Two Independent Variables

See LarsonCalculus.com for an interactive version of this type of example.

Use the Chain Rule to find $\partial w/\partial s$ and $\partial w/\partial t$ for

$$w = 2xy$$

where $x = s^2 + t^2$ and $y = s/t$.

Solution Note that these same partials were found in Example 3. This time, using Theorem 13.7, you can hold t constant and differentiate with respect to s to obtain

$$\begin{aligned}
\frac{\partial w}{\partial s} &= \frac{\partial w}{\partial x}\frac{\partial x}{\partial s} + \frac{\partial w}{\partial y}\frac{\partial y}{\partial s} \\
&= 2y(2s) + 2x\left(\frac{1}{t}\right) && t \text{ is held constant.} \\
&= 2\left(\frac{s}{t}\right)(2s) + 2(s^2 + t^2)\left(\frac{1}{t}\right) && \text{Substitute } \frac{s}{t} \text{ for } y \text{ and } s^2 + t^2 \text{ for } x. \\
&= \frac{4s^2}{t} + \frac{2s^2 + 2t^2}{t} \\
&= \frac{6s^2 + 2t^2}{t}.
\end{aligned}$$

Similarly, holding s constant gives

$$\begin{aligned}
\frac{\partial w}{\partial t} &= \frac{\partial w}{\partial x}\frac{\partial x}{\partial t} + \frac{\partial w}{\partial y}\frac{\partial y}{\partial t} \\
&= 2y(2t) + 2x\left(\frac{-s}{t^2}\right) && s \text{ is held constant.} \\
&= 2\left(\frac{s}{t}\right)(2t) + 2(s^2 + t^2)\left(\frac{-s}{t^2}\right) && \text{Substitute } \frac{s}{t} \text{ for } y \text{ and } s^2 + t^2 \text{ for } x. \\
&= 4s - \frac{2s^3 + 2st^2}{t^2} \\
&= \frac{4st^2 - 2s^3 - 2st^2}{t^2} \\
&= \frac{2st^2 - 2s^3}{t^2}.
\end{aligned}$$

■

The Chain Rule in Theorem 13.7 can also be extended to any number of variables. For example, if w is a differentiable function of the n variables

$$x_1, x_2, \ldots, x_n$$

where each x_i is a differentiable function of the m variables $t_1, t_2, \ldots, t_m$, then for

$$w = f(x_1, x_2, \ldots, x_n)$$

you obtain the following.

$$\begin{aligned}
\frac{\partial w}{\partial t_1} &= \frac{\partial w}{\partial x_1}\frac{\partial x_1}{\partial t_1} + \frac{\partial w}{\partial x_2}\frac{\partial x_2}{\partial t_1} + \cdots + \frac{\partial w}{\partial x_n}\frac{\partial x_n}{\partial t_1} \\
\frac{\partial w}{\partial t_2} &= \frac{\partial w}{\partial x_1}\frac{\partial x_1}{\partial t_2} + \frac{\partial w}{\partial x_2}\frac{\partial x_2}{\partial t_2} + \cdots + \frac{\partial w}{\partial x_n}\frac{\partial x_n}{\partial t_2} \\
&\vdots \\
\frac{\partial w}{\partial t_m} &= \frac{\partial w}{\partial x_1}\frac{\partial x_1}{\partial t_m} + \frac{\partial w}{\partial x_2}\frac{\partial x_2}{\partial t_m} + \cdots + \frac{\partial w}{\partial x_n}\frac{\partial x_n}{\partial t_m}
\end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 5 **The Chain Rule for a Function of Three Variables**

Find $\partial w/\partial s$ and $\partial w/\partial t$ when $s = 1$ and $t = 2\pi$ for

$$w = xy + yz + xz$$

where $x = s\cos t$, $y = s\sin t$, and $z = t$.

Solution By extending the result of Theorem 13.7, you have

$$\begin{aligned}\frac{\partial w}{\partial s} &= \frac{\partial w}{\partial x}\frac{\partial x}{\partial s} + \frac{\partial w}{\partial y}\frac{\partial y}{\partial s} + \frac{\partial w}{\partial z}\frac{\partial z}{\partial s} \\ &= (y + z)(\cos t) + (x + z)(\sin t) + (y + x)(0) \\ &= (y + z)(\cos t) + (x + z)(\sin t).\end{aligned}$$

When $s = 1$ and $t = 2\pi$, you have $x = 1$, $y = 0$, and $z = 2\pi$. So,

$$\frac{\partial w}{\partial s} = (0 + 2\pi)(1) + (1 + 2\pi)(0) = 2\pi.$$

Furthermore,

$$\begin{aligned}\frac{\partial w}{\partial t} &= \frac{\partial w}{\partial x}\frac{\partial x}{\partial t} + \frac{\partial w}{\partial y}\frac{\partial y}{\partial t} + \frac{\partial w}{\partial z}\frac{\partial z}{\partial t} \\ &= (y + z)(-s\sin t) + (x + z)(s\cos t) + (y + x)(1)\end{aligned}$$

and for $s = 1$ and $t = 2\pi$, it follows that

$$\begin{aligned}\frac{\partial w}{\partial t} &= (0 + 2\pi)(0) + (1 + 2\pi)(1) + (0 + 1)(1) \\ &= 2 + 2\pi.\end{aligned}$$

Implicit Partial Differentiation

This section concludes with an application of the Chain Rule to determine the derivative of a function defined *implicitly*. Let x and y be related by the equation $F(x, y) = 0$, where $y = f(x)$ is a differentiable function of x. To find dy/dx, you could use the techniques discussed in Section 2.5. The Chain Rule, however, provides a convenient alternative. Consider the function

$$w = F(x, y) = F(x, f(x)).$$

You can apply Theorem 13.6 to obtain

$$\frac{dw}{dx} = F_x(x, y)\frac{dx}{dx} + F_y(x, y)\frac{dy}{dx}.$$

Because $w = F(x, y) = 0$ for all x in the domain of f, you know that

$$\frac{dw}{dx} = 0$$

and you have

$$F_x(x, y)\frac{dx}{dx} + F_y(x, y)\frac{dy}{dx} = 0.$$

Now, if $F_y(x, y) \neq 0$, you can use the fact that $dx/dx = 1$ to conclude that

$$\frac{dy}{dx} = -\frac{F_x(x, y)}{F_y(x, y)}.$$

A similar procedure can be used to find the partial derivatives of functions of several variables that are defined implicitly.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

THEOREM 13.8 Chain Rule: Implicit Differentiation

If the equation $F(x, y) = 0$ defines y implicitly as a differentiable function of x, then

$$\frac{dy}{dx} = -\frac{F_x(x, y)}{F_y(x, y)}, \quad F_y(x, y) \neq 0.$$

If the equation $F(x, y, z) = 0$ defines z implicitly as a differentiable function of x and y, then

$$\frac{\partial z}{\partial x} = -\frac{F_x(x, y, z)}{F_z(x, y, z)} \quad \text{and} \quad \frac{\partial z}{\partial y} = -\frac{F_y(x, y, z)}{F_z(x, y, z)}, \quad F_z(x, y, z) \neq 0.$$

This theorem can be extended to differentiable functions defined implicitly with any number of variables.

EXAMPLE 6 Finding a Derivative Implicitly

Find dy/dx for

$$y^3 + y^2 - 5y - x^2 + 4 = 0.$$

Solution Begin by letting

$$F(x, y) = y^3 + y^2 - 5y - x^2 + 4.$$

Then

$$F_x(x, y) = -2x \quad \text{and} \quad F_y(x, y) = 3y^2 + 2y - 5.$$

Using Theorem 13.8, you have

$$\frac{dy}{dx} = -\frac{F_x(x, y)}{F_y(x, y)} = \frac{-(-2x)}{3y^2 + 2y - 5} = \frac{2x}{3y^2 + 2y - 5}.$$

REMARK Compare the solution to Example 6 with the solution to Example 2 in Section 2.5.

EXAMPLE 7 Finding Partial Derivatives Implicitly

Find $\partial z/\partial x$ and $\partial z/\partial y$ for

$$3x^2z - x^2y^2 + 2z^3 + 3yz - 5 = 0.$$

Solution Begin by letting

$$F(x, y, z) = 3x^2z - x^2y^2 + 2z^3 + 3yz - 5.$$

Then

$$F_x(x, y, z) = 6xz - 2xy^2$$
$$F_y(x, y, z) = -2x^2y + 3z$$

and

$$F_z(x, y, z) = 3x^2 + 6z^2 + 3y.$$

Using Theorem 13.8, you have

$$\frac{\partial z}{\partial x} = -\frac{F_x(x, y, z)}{F_z(x, y, z)} = \frac{2xy^2 - 6xz}{3x^2 + 6z^2 + 3y}$$

and

$$\frac{\partial z}{\partial y} = -\frac{F_y(x, y, z)}{F_z(x, y, z)} = \frac{2x^2y - 3z}{3x^2 + 6z^2 + 3y}.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

13.5 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Consider $w = f(x, y)$, where $x = g(s, t)$ and $y = h(s, t)$. Describe two ways of finding the partial derivatives $\partial w/\partial s$ and $\partial w/\partial t$.
2. Explain why using the Chain Rule to determine the derivative of the equation

   $F(x, y) = 0$

   is implicitly easier than using the method you learned in Section 2.5.

Using the Chain Rule **In Exercises 3–6, find dw/dt using the appropriate Chain Rule. Evaluate dw/dt at the given value of t.**

	Function	Value
3.	$w = x^2 + 5y$ $x = 2t,\ y = t$	$t = 2$
4.	$w = \sqrt{x^2 + y^2}$ $x = \cos t,\ y = e^t$	$t = 0$
5.	$w = x \sin y$ $x = e^t,\ y = \pi - t$	$t = 0$
6.	$w = \ln \frac{y}{x}$ $x = \cos t,\ y = \sin t$	$t = \frac{\pi}{4}$

Using Different Methods **In Exercises 7–12, find dw/dt (a) by using the appropriate Chain Rule and (b) by converting w to a function of t before differentiating.**

7. $w = x - \frac{1}{y}, \quad x = e^{2t}, \quad y = t^3$
8. $w = \cos(x - y), \quad x = t^2, \quad y = 1$
9. $w = x^2 + y^2 + z^2, \quad x = \cos t, \quad y = \sin t, \quad z = e^t$
10. $w = xy \cos z, \quad x = t, \quad y = t^2, \quad z = \arccos t$
11. $w = xy + xz + yz, \quad x = t - 1, \quad y = t^2 - 1, \quad z = t$
12. $w = xy^2 + x^2z + yz^2, \quad x = t^2, \quad y = 2t, \quad z = 2$

Projectile Motion **In Exercises 13 and 14, the parametric equations for the paths of two objects are given. At what rate is the distance between the two objects changing at the given value of t?**

13. $x_1 = 10 \cos 2t, \quad y_1 = 6 \sin 2t$ First object
    $x_2 = 7 \cos t, \quad y_2 = 4 \sin t$ Second object
    $t = \pi/2$
14. $x_1 = 48\sqrt{2}t, \quad y_1 = 48\sqrt{2}t - 16t^2$ First object
    $x_2 = 48\sqrt{3}t, \quad y_2 = 48t - 16t^2$ Second object
    $t = 1$

Finding Partial Derivatives **In Exercises 15–18, find $\partial w/\partial s$ and $\partial w/\partial t$ using the appropriate Chain Rule. Evaluate each partial derivative at the given values of s and t.**

	Function	Values
15.	$w = x^2 + y^2$ $x = s + t, \quad y = s - t$	$s = 1, \quad t = 3$
16.	$w = y^3 - 3x^2y$ $x = e^s, \quad y = e^t$	$s = -1, \quad t = 2$
17.	$w = \sin(2x + 3y)$ $x = s + t, \quad y = s - t$	$s = 0, \quad t = \frac{\pi}{2}$
18.	$w = x^2 - y^2$ $x = s \cos t, \quad y = s \sin t$	$s = 3, \quad t = \frac{\pi}{4}$

Using Different Methods **In Exercises 19–22, find $\partial w/\partial s$ and $\partial w/\partial t$ (a) by using the appropriate Chain Rule and (b) by converting w to a function of s and t before differentiating.**

19. $w = xyz, \quad x = s + t, \quad y = s - t, \quad z = st^2$
20. $w = x^2 + y^2 + z^2, \quad x = t \sin s, \quad y = t \cos s, \quad z = st^2$
21. $w = ze^{xy}, \quad x = s - t, \quad y = s + t, \quad z = st$
22. $w = x \cos yz, \quad x = s^2, \quad y = t^2, \quad z = s - 2t$

Finding a Derivative Implicitly **In Exercises 23–26, differentiate implicitly to find dy/dx.**

23. $x^2 - xy + y^2 - x + y = 0$
24. $\sec xy + \tan xy + 5 = 0$
25. $\ln\sqrt{x^2 + y^2} + x + y = 4$
26. $\frac{x}{x^2 + y^2} - y^2 = 6$

Finding Partial Derivatives Implicitly **In Exercises 27–34, differentiate implicitly to find the first partial derivatives of z.**

27. $x^2 + y^2 + z^2 = 1$
28. $xz + yz + xy = 0$
29. $x^2 + 2yz + z^2 = 1$
30. $x + \sin(y + z) = 0$
31. $\tan(x + y) + \cos z = 2$
32. $z = e^x \sin(y + z)$
33. $e^{xz} + xy = 0$
34. $x \ln y + y^2z + z^2 = 8$

Finding Partial Derivatives Implicitly **In Exercises 35–38, differentiate implicitly to find the first partial derivatives of w.**

35. $7xy + yz^2 - 4wz + w^2z + w^2x - 6 = 0$
36. $x^2 + y^2 + z^2 - 5yw + 10w^2 = 2$
37. $\cos xy + \sin yz + wz = 20$
38. $w - \sqrt{x - y} - \sqrt{y - z} = 0$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Homogeneous Functions **A function f is *homogeneous of degree n* when $f(tx, ty) = t^n f(x, y)$. In Exercises 39–42, (a) show that the function is homogeneous and determine n, and (b) show that $xf_x(x, y) + yf_y(x, y) = nf(x, y)$.**

39. $f(x, y) = 2x^2 - 5xy$

40. $f(x, y) = x^3 - 3xy^2 + y^3$

41. $f(x, y) = e^{x/y}$

42. $f(x, y) = x \cos \dfrac{x + y}{y}$

43. Using a Table of Values Let $w = f(x, y)$, $x = g(t)$, and $y = h(t)$, where f, g, and h are differentiable. Use the appropriate Chain Rule and the table of values to find dw/dt when $t = 2$.

$g(2)$	$h(2)$	$g'(2)$	$h'(2)$	$f_x(4, 3)$	$f_y(4, 3)$
4	3	-1	6	-5	7

44. Using a Table of Values Let $w = f(x, y)$, $x = g(s, t)$, and $y = h(s, t)$, where f, g, and h are differentiable. Use the appropriate Chain Rule and the table of values to find $w_s(1, 2)$.

$g(1, 2)$	$h(1, 2)$	$g_s(1, 2)$	$h_s(1, 2)$	$f_x(4, 3)$	$f_y(4, 3)$
4	3	-3	5	-5	7

Exploring Concepts

45. Show that $\dfrac{\partial w}{\partial u} + \dfrac{\partial w}{\partial v} = 0$ for $w = f(x, y)$, $x = u - v$, and $y = v - u$.

46. Demonstrate the result of Exercise 45 for

$w = (x - y) \sin(y - x)$.

47. Let $F(u, v)$ be a function of two variables. Find a formula for $f'(x)$ when (a) $f(x) = F(4x, 4)$ and (b) $f(x) = F(-2x, x^2)$.

48. HOW DO YOU SEE IT? The path of an object represented by $w = f(x, y)$ is shown, where x and y are functions of t. The point on the graph represents the position of the object.



Determine whether each of the following is positive, negative, or zero.

(a) $\dfrac{dx}{dt}$ (b) $\dfrac{dy}{dt}$

49. Volume and Surface Area The radius of a right circular cylinder is increasing at a rate of 6 inches per minute, and the height is decreasing at a rate of 4 inches per minute. What are the rates of change of the volume and surface area when the radius is 12 inches and the height is 36 inches?

50. Ideal Gas Law The Ideal Gas Law is

$PV = mRT$

where P is the pressure, V is the volume, m is the constant mass, R is a constant, T is the temperature, and P and V are functions of time. Find dT/dt, the rate at which the temperature changes with respect to time.

51. Moment of Inertia An annular cylinder has an inside radius of r_1 and an outside radius of r_2 (see figure). Its moment of inertia is

$I = \frac{1}{2}m(r_1^2 + r_2^2)$

where m is the mass. The two radii are increasing at a rate of 2 centimeters per second. Find the rate at which I is changing at the instant the radii are 6 centimeters and 8 centimeters. (Assume mass is a constant.)



Figure for 51



Figure for 52

52. Volume and Surface Area The two radii of the frustum of a right circular cone are increasing at a rate of 4 centimeters per minute, and the height is increasing at a rate of 12 centimeters per minute (see figure). Find the rates at which the volume and surface area are changing when the two radii are 15 centimeters and 25 centimeters and the height is 10 centimeters.

53. Cauchy-Riemann Equations Given the functions $u(x, y)$ and $v(x, y)$, verify that the **Cauchy-Riemann equations**

$$\frac{\partial u}{\partial x} = \frac{\partial v}{\partial y} \quad \text{and} \quad \frac{\partial u}{\partial y} = -\frac{\partial v}{\partial x}$$

can be written in polar coordinate form as

$$\frac{\partial u}{\partial r} = \frac{1}{r} \cdot \frac{\partial v}{\partial \theta} \quad \text{and} \quad \frac{\partial v}{\partial r} = -\frac{1}{r} \cdot \frac{\partial u}{\partial \theta}.$$

54. Cauchy-Riemann Equations Demonstrate the result of Exercise 53 for the functions

$u = \ln \sqrt{x^2 + y^2}$ and $v = \arctan \dfrac{y}{x}$.

55. Homogeneous Function Show that if $f(x, y)$ is homogeneous of degree n, then

$xf_x(x, y) + yf_y(x, y) = nf(x, y)$.

[*Hint:* Let $g(t) = f(tx, ty) = t^n f(x, y)$. Find $g'(t)$ and then let $t = 1$.]

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

13.6 Directional Derivatives and Gradients

GO DIGITAL

- Find and use directional derivatives of a function of two variables.
- Find the gradient of a function of two variables.
- Use the gradient of a function of two variables in applications.
- Find directional derivatives and gradients of functions of three variables.

Directional Derivative

You are on the hillside represented by $z = f(x, y)$ in Figure 13.42 and want to determine the hill's incline toward the z-axis. You already know how to determine the slopes in two different directions—the slope in the y-direction is given by the partial derivative $f_y(x, y)$, and the slope in the x-direction is given by the partial derivative $f_x(x, y)$. In this section, you will see that these two partial derivatives can be used to find the slope in *any* direction.



Figure 13.42

To determine the slope at a point on a surface, you will define a new type of derivative called a **directional derivative.** Begin by letting $z = f(x, y)$ be a *surface* and $P(x_0, y_0)$ be a *point* in the domain of f, as shown in Figure 13.43. The "direction" of the directional derivative is given by a unit vector

$$\mathbf{u} = \cos\theta\mathbf{i} + \sin\theta\mathbf{j}$$



Figure 13.43

where θ is the angle the vector makes with the positive x-axis. To find the desired slope, reduce the problem to two dimensions by intersecting the surface with a vertical plane passing through the point P and parallel to $\mathbf{u}$, as shown in Figure 13.44. This vertical plane intersects the surface to form a curve C. The slope of the surface at $(x_0, y_0, f(x_0, y_0))$ in the direction of $\mathbf{u}$ is defined as the slope of the curve C at that point.

Informally, you can write the slope of the curve C as a limit that looks much like those used in single-variable calculus. The vertical plane used to form C intersects the xy-plane in a line L, represented by the parametric equations

$$x = x_0 + t\cos\theta$$

and

$$y = y_0 + t\sin\theta$$

so that for any value of t, the point $Q(x, y)$ lies on the line L. For each of the points P and Q, there is a corresponding point on the surface.

$(x_0, y_0, f(x_0, y_0))$ Point above P

$(x, y, f(x, y))$ Point above Q

Moreover, because the distance between P and Q is

$$\sqrt{(x - x_0)^2 + (y - y_0)^2} = \sqrt{(t\cos\theta)^2 + (t\sin\theta)^2} = |t|$$

you can write the slope of the secant line through $(x_0, y_0, f(x_0, y_0))$ and $(x, y, f(x, y))$ as

$$\frac{f(x, y) - f(x_0, y_0)}{t} = \frac{f(x_0 + t\cos\theta, y_0 + t\sin\theta) - f(x_0, y_0)}{t}.$$

Finally, by letting t approach 0, you arrive at the definition on the next page.



Figure 13.44

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

REMARK Be sure you understand that the directional derivative represents the *rate of change of a function* in the direction of the unit vector $\mathbf{u} = \cos\theta\mathbf{i} + \sin\theta\mathbf{j}$. Geometrically, you can interpret the directional derivative as giving the *slope of a surface* in the direction of $\mathbf{u}$ at a point on the surface. (See Figure 13.46.)

Definition of Directional Derivative

Let f be a function of two variables x and y and let $\mathbf{u} = \cos\theta\mathbf{i} + \sin\theta\mathbf{j}$ be a unit vector. Then the **directional derivative of f in the direction of $\mathbf{u}$,** denoted by $D_{\mathbf{u}}f$, is

$$D_{\mathbf{u}}f(x, y) = \lim_{t\to 0}\frac{f(x + t\cos\theta, y + t\sin\theta) - f(x, y)}{t}$$

provided this limit exists.

Calculating directional derivatives by this definition is similar to finding the derivative of a function of one variable by the limit process (see Section 2.1). A simpler formula for finding directional derivatives involves the partial derivatives f_x and f_y.

GO DIGITAL

THEOREM 13.9 Directional Derivative

If f is a differentiable function of x and y, then the directional derivative of f in the direction of the unit vector $\mathbf{u} = \cos\theta\mathbf{i} + \sin\theta\mathbf{j}$ is

$$D_{\mathbf{u}}f(x, y) = f_x(x, y)\cos\theta + f_y(x, y)\sin\theta.$$

Proof For a fixed point (x_0, y_0), let

$$x = x_0 + t\cos\theta \quad \text{and} \quad y = y_0 + t\sin\theta.$$

Then, let $g(t) = f(x, y)$. Because f is differentiable, you can apply the Chain Rule given in Theorem 13.6 to obtain

$$\begin{aligned} g'(t) &= f_x(x, y)x'(t) + f_y(x, y)y'(t) \qquad \text{Apply Chain Rule (Theorem 13.6).} \\ &= f_x(x, y)\cos\theta + f_y(x, y)\sin\theta. \end{aligned}$$

If $t = 0$, then $x = x_0$ and $y = y_0$, so

$$g'(0) = f_x(x_0, y_0)\cos\theta + f_y(x_0, y_0)\sin\theta.$$

By the definition of $g'(t)$, it is also true that

$$\begin{aligned} g'(0) &= \lim_{t\to 0}\frac{g(t) - g(0)}{t} \\ &= \lim_{t\to 0}\frac{f(x_0 + t\cos\theta, y_0 + t\sin\theta) - f(x_0, y_0)}{t}. \end{aligned}$$

Consequently, $D_{\mathbf{u}}f(x_0, y_0) = f_x(x_0, y_0)\cos\theta + f_y(x_0, y_0)\sin\theta$. ∎

There are infinitely many directional derivatives of a surface at a given point—one for each direction specified by $\mathbf{u}$, as shown in Figure 13.45. Two of these are the partial derivatives f_x and f_y.



Figure 13.45

1. Direction of positive x-axis $(\theta = 0)$: $\mathbf{u} = \cos 0\mathbf{i} + \sin 0\mathbf{j} = \mathbf{i}$

$$D_{\mathbf{i}}f(x, y) = f_x(x, y)\cos 0 + f_y(x, y)\sin 0 = f_x(x, y)$$

2. Direction of positive y-axis $\left(\theta = \frac{\pi}{2}\right)$: $\mathbf{u} = \cos\frac{\pi}{2}\mathbf{i} + \sin\frac{\pi}{2}\mathbf{j} = \mathbf{j}$

$$D_{\mathbf{j}}f(x, y) = f_x(x, y)\cos\frac{\pi}{2} + f_y(x, y)\sin\frac{\pi}{2} = f_y(x, y)$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 1 Finding a Directional Derivative

Find the directional derivative of

$$f(x, y) = 4 - x^2 - \frac{1}{4}y^2 \qquad \text{Surface}$$

at $(1, 2)$ in the direction of

$$\mathbf{u} = \left(\cos\frac{\pi}{3}\right)\mathbf{i} + \left(\sin\frac{\pi}{3}\right)\mathbf{j}. \qquad \text{Direction}$$

Solution Because $f_x(x, y) = -2x$ and $f_y(x, y) = -y/2$ are continuous, f is differentiable, and you can apply Theorem 13.9.

$$D_{\mathbf{u}}f(x, y) = f_x(x, y)\cos\theta + f_y(x, y)\sin\theta = (-2x)\cos\theta + \left(-\frac{y}{2}\right)\sin\theta$$

Evaluating at $\theta = \pi/3$, $x = 1$, and $y = 2$ produces

$$\begin{aligned} D_{\mathbf{u}}f(1, 2) &= (-2)\left(\frac{1}{2}\right) + (-1)\left(\frac{\sqrt{3}}{2}\right) \\ &= -1 - \frac{\sqrt{3}}{2} \\ &\approx -1.866. \end{aligned}$$ See Figure 13.46.

Note in Figure 13.46 that you can interpret the directional derivative as giving the slope of the surface at the point $(1, 2, 2)$ in the direction of the unit vector $\mathbf{u}$.



Figure 13.46

You have been specifying direction by a unit vector $\mathbf{u}$. When the direction is given by a vector whose length is not 1, you must normalize the vector before applying the formula in Theorem 13.9.

EXAMPLE 2 Finding a Directional Derivative

See LarsonCalculus.com for an interactive version of this type of example.

Find the directional derivative of

$$f(x, y) = x^2 \sin 2y \qquad \text{Surface}$$

at $(1, \pi/2)$ in the direction of

$$\mathbf{v} = 3\mathbf{i} - 4\mathbf{j}. \qquad \text{Direction}$$

Solution Because $f_x(x, y) = 2x \sin 2y$ and $f_y(x, y) = 2x^2 \cos 2y$ are continuous, f is differentiable, and you can apply Theorem 13.9. Begin by finding a unit vector in the direction of $\mathbf{v}$.

$$\mathbf{u} = \frac{\mathbf{v}}{\|\mathbf{v}\|} = \frac{3}{5}\mathbf{i} - \frac{4}{5}\mathbf{j} = \cos\theta\mathbf{i} + \sin\theta\mathbf{j}$$

Using this unit vector, you have

$$D_{\mathbf{u}}f(x, y) = (2x \sin 2y)(\cos\theta) = (2x^2 \cos 2y)(\sin\theta)$$

$$\begin{aligned} D_{\mathbf{u}}f\left(1, \frac{\pi}{2}\right) &= (2\sin\pi)\left(\frac{3}{5}\right) + (2\cos\pi)\left(-\frac{4}{5}\right) \\ &= (0)\left(\frac{3}{5}\right) + (-2)\left(-\frac{4}{5}\right) \\ &= \frac{8}{5}. \end{aligned}$$ See Figure 13.47.



Figure 13.47

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The gradient of f is a vector in the xy-plane.

Figure 13.48

The Gradient of a Function of Two Variables

The **gradient** of a function of two variables is a vector-valued function of two variables. This function has many important uses, some of which are described later in this section.

Definition of Gradient of a Function of Two Variables

Let $z = f(x, y)$ be a function of x and y such that f_x and f_y exist. Then the **gradient of f,** denoted by $\nabla f(x, y)$, is the vector

$$\nabla f(x, y) = f_x(x, y)\mathbf{i} + f_y(x, y)\mathbf{j}.$$

(The symbol ∇f is read as "del f.") Another notation for the gradient is given by **grad** $f(x, y)$. In Figure 13.48, note that for each (x, y), the gradient $\nabla f(x, y)$ is a vector in the plane (not a vector in space).

Notice that no value is assigned to the symbol ∇ by itself. It is an operator in the same sense that d/dx is an operator. When ∇ operates on $f(x, y)$, it produces the vector $\nabla f(x, y)$.

EXAMPLE 3 Finding the Gradient of a Function

Find the gradient of

$$f(x, y) = y \ln x + xy^2$$

at the point $(1, 2)$.

Solution Using

$$f_x(x, y) = \frac{y}{x} + y^2 \quad \text{and} \quad f_y(x, y) = \ln x + 2xy$$

you have

$$\begin{aligned}\nabla f(x, y) &= f_x(x, y)\mathbf{i} + f_y(x, y)\mathbf{j} \\ &= \left(\frac{y}{x} + y^2\right)\mathbf{i} + (\ln x + 2xy)\mathbf{j}.\end{aligned}$$

At the point $(1, 2)$, the gradient is

$$\begin{aligned}\nabla f(1, 2) &= \left(\frac{2}{1} + 2^2\right)\mathbf{i} + [\ln 1 + 2(1)(2)]\mathbf{j} \\ &= 6\mathbf{i} + 4\mathbf{j}.\end{aligned}$$

■

Because the gradient of f is a vector, you can write the directional derivative of f in the direction of $\mathbf{u}$ as

$$D_{\mathbf{u}}f(x, y) = [f_x(x, y)\mathbf{i} + f_y(x, y)\mathbf{j}] \cdot (\cos\theta\mathbf{i} + \sin\theta\mathbf{j}).$$

In other words, the directional derivative is the dot product of the gradient and the direction vector. This useful result is summarized in the next theorem.

THEOREM 13.10 Alternative Form of the Directional Derivative

If f is a differentiable function of x and y, then the directional derivative of f in the direction of the unit vector $\mathbf{u}$ is

$$D_{\mathbf{u}}f(x, y) = \nabla f(x, y) \cdot \mathbf{u}.$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 4 Using $\nabla f(x, y)$ to Find a Directional Derivative

Find the directional derivative of $f(x, y) = 3x^2 - 2y^2$ at $\left(-\frac{3}{4}, 0\right)$ in the direction from $P\left(-\frac{3}{4}, 0\right)$ to $Q(0, 1)$.

Solution Because the partials of f are continuous, f is differentiable and you can apply Theorem 13.10. A vector in the specified direction is

$$\overrightarrow{PQ} = \left(0 + \frac{3}{4}\right)\mathbf{i} + (1 - 0)\mathbf{j} = \frac{3}{4}\mathbf{i} + \mathbf{j}$$

and a unit vector in this direction is

$$\mathbf{u} = \frac{\overrightarrow{PQ}}{\|\overrightarrow{PQ}\|} = \frac{3}{5}\mathbf{i} + \frac{4}{5}\mathbf{j}.$$ Unit vector in direction of $\overrightarrow{PQ}$

Because $\nabla f(x, y) = f_x(x, y)\mathbf{i} + f_y(x, y)\mathbf{j} = 6x\mathbf{i} - 4y\mathbf{j}$, the gradient at $\left(-\frac{3}{4}, 0\right)$ is

$$\nabla f\left(-\frac{3}{4}, 0\right) = -\frac{9}{2}\mathbf{i} + 0\mathbf{j}.$$ Gradient at $\left(-\frac{3}{4}, 0\right)$

Consequently, at $\left(-\frac{3}{4}, 0\right)$, the directional derivative is

$$\begin{aligned} D_{\mathbf{u}} f\left(-\frac{3}{4}, 0\right) &= \nabla f\left(-\frac{3}{4}, 0\right) \cdot \mathbf{u} \\ &= \left(-\frac{9}{2}\mathbf{i} + 0\mathbf{j}\right) \cdot \left(\frac{3}{5}\mathbf{i} + \frac{4}{5}\mathbf{j}\right) \\ &= -\frac{27}{10}. \end{aligned}$$ Directional derivative at $\left(-\frac{3}{4}, 0\right)$

See Figure 13.49.



Figure 13.49

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Applications of the Gradient

You have already seen that there are many directional derivatives at the point (x, y) on a surface. In many applications, you may want to know in which direction to move so that $f(x, y)$ increases most rapidly. This direction is called the direction of steepest ascent, and it is given by the gradient, as stated in the next theorem.

THEOREM 13.11 Properties of the Gradient

Let f be differentiable at the point (x, y).

1. If $\nabla f(x, y) = \mathbf{0}$, then $D_{\mathbf{u}} f(x, y) = 0$ for all $\mathbf{u}$.
2. The direction of *maximum* increase of f is given by $\nabla f(x, y)$. The maximum value of $D_{\mathbf{u}} f(x, y)$ is
$$\|\nabla f(x, y)\|. \qquad \text{Maximum value of } D_{\mathbf{u}} f(x, y)$$
3. The direction of *minimum* increase of f is given by $-\nabla f(x, y)$. The minimum value of $D_{\mathbf{u}} f(x, y)$ is
$$-\|\nabla f(x, y)\|. \qquad \text{Minimum value of } D_{\mathbf{u}} f(x, y)$$

REMARK Property 2 of Theorem 13.11 says that at the point (x, y), f increases most rapidly in the direction of the gradient, $\nabla f(x, y)$.

Proof If $\nabla f(x, y) = \mathbf{0}$, then for any direction (any $\mathbf{u}$), you have

$$\begin{aligned} D_{\mathbf{u}} f(x, y) &= \nabla f(x, y) \cdot \mathbf{u} \\ &= (0\mathbf{i} + 0\mathbf{j}) \cdot (\cos\theta\mathbf{i} + \sin\theta\mathbf{j}) \\ &= 0. \end{aligned}$$

If $\nabla f(x, y) \neq \mathbf{0}$, then let ϕ be the angle between $\nabla f(x, y)$ and a unit vector $\mathbf{u}$. Using the dot product, you can apply Theorem 11.5 to conclude that

$$\begin{aligned} D_{\mathbf{u}} f(x, y) &= \nabla f(x, y) \cdot \mathbf{u} \\ &= \|\nabla f(x, y)\| \, \|\mathbf{u}\| \cos\phi \\ &= \|\nabla f(x, y)\| \cos\phi \end{aligned}$$

and it follows that the maximum value of $D_{\mathbf{u}} f(x, y)$ will occur when

$$\cos\phi = 1.$$

So, $\phi = 0$, and the maximum value of the directional derivative occurs when $\mathbf{u}$ has the same direction as $\nabla f(x, y)$. Moreover, this largest value of $D_{\mathbf{u}} f(x, y)$ is precisely

$$\|\nabla f(x, y)\| \cos\phi = \|\nabla f(x, y)\|.$$

Similarly, the minimum value of $D_{\mathbf{u}} f(x, y)$ can be obtained by letting

$$\phi = \pi$$

so that $\mathbf{u}$ points in the direction opposite that of $\nabla f(x, y)$, as shown in Figure 13.50.



The gradient of f is a vector in the xy-plane that points in the direction of maximum increase on the surface given by $z = f(x, y)$.
Figure 13.50

To visualize one of the properties of the gradient, imagine a skier coming down a mountainside. If $f(x, y)$ denotes the altitude of the skier, then $-\nabla f(x, y)$ indicates the *compass direction* the skier should take to ski the path of steepest descent. (Remember that the gradient indicates direction in the xy-plane and does not itself point up or down the mountainside.)

As another illustration of the gradient, consider the temperature $T(x, y)$ at any point (x, y) on a flat metal plate. In this case, $\nabla T(x, y)$ gives the direction of greatest temperature increase at the point (x, y), as illustrated in the next example.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



The direction of most rapid increase in temperature at $(2, -3)$ is given by $-16\mathbf{i} + 6\mathbf{j}$.

Figure 13.51

EXAMPLE 5 Finding the Direction of Maximum Increase

The temperature in degrees Celsius on the surface of a metal plate is

$$T(x, y) = 20 - 4x^2 - y^2$$

where x and y are measured in centimeters. In what direction from $(2, -3)$ does the temperature increase most rapidly? What is this rate of increase?

Solution The gradient is

$$\nabla T(x, y) = T_x(x, y)\mathbf{i} + T_y(x, y)\mathbf{j} = -8x\mathbf{i} - 2y\mathbf{j}.$$

It follows that the direction of maximum increase is given by

$$\nabla T(2, -3) = -16\mathbf{i} + 6\mathbf{j}$$

as shown in Figure 13.51, and the rate of increase is

$$\|\nabla T(2, -3)\| = \sqrt{256 + 36} = \sqrt{292} \approx 17.09° \text{ per centimeter.}$$

The solution presented in Example 5 can be misleading. Although the gradient points in the direction of maximum temperature increase, it does not necessarily point toward the hottest spot on the plate. In other words, the gradient provides a local solution to finding an increase relative to the temperature at the point $(2, -3)$. *Once you leave that position, the direction of maximum increase may change.*

EXAMPLE 6 Finding the Path of a Heat-Seeking Particle

A heat-seeking particle is located at the point $(2, -3)$ on a metal plate whose temperature at (x, y) is

$$T(x, y) = 20 - 4x^2 - y^2.$$

Find the path of the particle as it continuously moves in the direction of maximum temperature increase.

Solution Let the path be represented by the position vector

$$\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j}.$$

A tangent vector at each point $(x(t), y(t))$ is given by

$$\mathbf{r}'(t) = \frac{dx}{dt}\mathbf{i} + \frac{dy}{dt}\mathbf{j}.$$

Because the particle seeks maximum temperature increase, the directions of $\mathbf{r}'(t)$ and $\nabla T(x, y) = -8x\mathbf{i} - 2y\mathbf{j}$ are the same at each point on the path. So,

$$-8x = k\frac{dx}{dt} \quad \text{and} \quad -2y = k\frac{dy}{dt}$$

where k depends on t. By solving each equation for dt/k and equating the results, you obtain

$$\frac{dx}{-8x} = \frac{dy}{-2y}.$$

The solution of this differential equation is $x = Cy^4$. Because the particle starts at the point $(2, -3)$, you can determine that $C = 2/81$. So, the path of the heat-seeking particle is

$$x = \frac{2}{81}y^4.$$

The path is shown in Figure 13.52.



Path followed by a heat-seeking particle

Figure 13.52

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

In Figure 13.52, the path of the particle (determined by the gradient at each point) appears to be orthogonal to each of the level curves. This becomes clear when you consider that the temperature $T(x, y)$ is constant along a given level curve. So, at any point (x, y) on the curve, the rate of change of T in the direction of a unit tangent vector $\mathbf{u}$ is 0, and you can write

$$\nabla f(x, y) \cdot \mathbf{u} = D_{\mathbf{u}}T(x, y) = 0.$$ $\mathbf{u}$ is a unit tangent vector.

Because the dot product of $\nabla f(x, y)$ and $\mathbf{u}$ is 0, you can conclude that they must be orthogonal. This result is stated in the next theorem.

THEOREM 13.12 Gradient Is Normal to Level Curves

If f is differentiable at (x_0, y_0) and $\nabla f(x_0, y_0) \neq \mathbf{0}$, then $\nabla f(x_0, y_0)$ is normal to the level curve through (x_0, y_0).

EXAMPLE 7 Finding a Normal Vector to a Level Curve

Sketch the level curve corresponding to $c = 0$ for the function given by

$$f(x, y) = y - \sin x$$

and find a normal vector at several points on the curve.

Solution The level curve for $c = 0$ is given by

$$0 = y - \sin x \quad \Rightarrow \quad y = \sin x$$

as shown in Figure 13.53(a). Because the gradient of f at (x, y) is

$$\begin{aligned}\nabla f(x, y) &= f_x(x, y)\mathbf{i} + f_y(x, y)\mathbf{j} \\ &= -\cos x\mathbf{i} + \mathbf{j}\end{aligned}$$

you can use Theorem 13.12 to conclude that $\nabla f(x, y)$ is normal to the level curve at the point (x, y). Some gradients are

$$\nabla f(-\pi, 0) = \mathbf{i} + \mathbf{j}$$

$$\nabla f\left(-\frac{2\pi}{3}, -\frac{\sqrt{3}}{2}\right) = \frac{1}{2}\mathbf{i} + \mathbf{j}$$

$$\nabla f\left(-\frac{\pi}{2}, -1\right) = \mathbf{j}$$

$$\nabla f\left(-\frac{\pi}{3}, -\frac{\sqrt{3}}{2}\right) = -\frac{1}{2}\mathbf{i} + \mathbf{j}$$

$$\nabla f(0, 0) = -\mathbf{i} + \mathbf{j}$$

$$\nabla f\left(\frac{\pi}{3}, \frac{\sqrt{3}}{2}\right) = -\frac{1}{2}\mathbf{i} + \mathbf{j}$$

$$\nabla f\left(\frac{\pi}{2}, 1\right) = \mathbf{j}$$

$$\nabla f\left(\frac{2\pi}{3}, \frac{\sqrt{3}}{2}\right) = \frac{1}{2}\mathbf{i} + \mathbf{j}$$

and

$$\nabla f(\pi, 0) = \mathbf{i} + \mathbf{j}.$$

These gradients and the level curve $y = \sin x$ are shown in Figure 13.53(b). ■



(a) The surface is given by $f(x, y) = y - \sin x$.



(b) The level curve is given by $f(x, y) = 0$.

Figure 13.53

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Functions of Three Variables

The definitions of the directional derivative and the gradient can be extended naturally to functions of three or more variables. As often happens, some of the geometric interpretation is lost in the generalization from functions of two variables to those of three variables. For example, you cannot interpret the directional derivative of a function of three variables as representing slope.

The definitions and properties of the directional derivative and the gradient of a function of three variables are listed below.

Directional Derivative and Gradient for Three Variables

Let f be a function of x, y, and z with continuous first partial derivatives. The **directional derivative of f** in the direction of a unit vector

$$\mathbf{u} = a\mathbf{i} + b\mathbf{j} + c\mathbf{k}$$

is given by

$$D_{\mathbf{u}}f(x, y, z) = af_x(x, y, z) + bf_y(x, y, z) + cf_z(x, y, z).$$

The **gradient of f** is defined as

$$\nabla f(x, y, z) = f_x(x, y, z)\mathbf{i} + f_y(x, y, z)\mathbf{j} + f_z(x, y, z)\mathbf{k}.$$

Properties of the gradient are as follows.

1. $D_{\mathbf{u}}f(x, y, z) = \nabla f(x, y, z) \cdot \mathbf{u}$
2. If $\nabla f(x, y, z) = \mathbf{0}$, then $D_{\mathbf{u}}f(x, y, z) = 0$ for all $\mathbf{u}$.
3. The direction of *maximum* increase of f is given by $\nabla f(x, y, z)$. The maximum value of $D_{\mathbf{u}}f(x, y, z)$ is
$$\|\nabla f(x, y, z)\|. \qquad \text{Maximum value of } D_{\mathbf{u}}f(x, y, z)$$
4. The direction of *minimum* increase of f is given by $-\nabla f(x, y, z)$. The minimum value of $D_{\mathbf{u}}f(x, y, z)$ is
$$-\|\nabla f(x, y, z)\|. \qquad \text{Minimum value of } D_{\mathbf{u}}f(x, y, z)$$

You can generalize Theorem 13.12 to functions of three variables. Under suitable hypotheses,

$$\nabla f(x_0, y_0, z_0)$$

is normal to the level surface through (x_0, y_0, z_0).



Level surface and gradient at $(2, -1, 1)$ for $f(x, y, z) = x^2 + y^2 - 4z$

Figure 13.54

EXAMPLE 8 Finding the Gradient of a Function

Find $\nabla f(x, y, z)$ for the function

$$f(x, y, z) = x^2 + y^2 - 4z$$

and find the direction of maximum increase of f at the point $(2, -1, 1)$.

Solution The gradient is

$$\begin{aligned}\nabla f(x, y, z) &= f_x(x, y, z)\mathbf{i} + f_y(x, y, z)\mathbf{j} + f_z(x, y, z)\mathbf{k} \\ &= 2x\mathbf{i} + 2y\mathbf{j} - 4\mathbf{k}.\end{aligned}$$

So, it follows that the direction of maximum increase at $(2, -1, 1)$ is

$$\nabla f(2, -1, 1) = 4\mathbf{i} - 2\mathbf{j} - 4\mathbf{k}. \qquad \text{See Figure 13.54.}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

13.6 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. For a function $f(x, y)$, when does the directional derivative at the point (x_0, y_0) equal the partial derivative with respect to x at the point (x_0, y_0)? Explain what this means graphically.
2. What is the meaning of the gradient of a function f at a point (x, y)?

Finding a Directional Derivative **In Exercises 3–6, use Theorem 13.9 to find the directional derivative of the function at P in the direction of the unit vector $\mathbf{u} = \cos\theta\mathbf{i} + \sin\theta\mathbf{j}$.**

3. $f(x, y) = x^2 + y^2, \quad P(1, -2), \quad \theta = \frac{\pi}{4}$
4. $f(x, y) = \frac{y}{x + y}, \quad P(3, 0), \quad \theta = -\frac{\pi}{6}$
5. $f(x, y) = \sin(2x + y), \quad P(0, \pi), \quad \theta = -\frac{5\pi}{6}$
6. $g(x, y) = xe^y, \quad P(0, 2), \quad \theta = \frac{2\pi}{3}$

Finding a Directional Derivative **In Exercises 7–10, use Theorem 13.9 to find the directional derivative of the function at P in the direction of $\mathbf{v}$.**

7. $f(x, y) = 3x - 4xy + 9y, \quad P(1, 2), \quad \mathbf{v} = \frac{3}{5}\mathbf{i} + \frac{4}{5}\mathbf{j}$
8. $f(x, y) = x^3 - y^3, \quad P(4, 3), \quad \mathbf{v} = \frac{\sqrt{2}}{2}(\mathbf{i} + \mathbf{j})$
9. $g(x, y) = \sqrt{x^2 + y^2}, \quad P(3, 4), \quad \mathbf{v} = 3\mathbf{i} - 4\mathbf{j}$
10. $h(x, y) = e^{-(x^2+y^2)}, \quad P(0, 0), \quad \mathbf{v} = \mathbf{i} + \mathbf{j}$

Finding a Directional Derivative **In Exercises 11–14, use Theorem 13.9 to find the directional derivative of the function at P in the direction of $\overrightarrow{PQ}$.**

11. $f(x, y) = x^2 + 3y^2, \quad P(1, 1), \quad Q(4, 5)$
12. $f(x, y) = \cos(x + y), \quad P(0, \pi), \quad Q\left(\frac{\pi}{2}, 0\right)$
13. $f(x, y) = e^y \sin x, \quad P(0, 0), \quad Q(2, 1)$
14. $f(x, y) = \sin 2x \cos y, \quad P(\pi, 0), \quad Q\left(\frac{\pi}{2}, \pi\right)$

Finding the Gradient of a Function **In Exercises 15–20, find the gradient of the function at the given point.**

15. $f(x, y) = 3x + 5y^2 + 1, \quad (2, 1)$
16. $g(x, y) = 2xe^{y/x}, \quad (2, 0)$
17. $z = \frac{\ln(x^2 - y)}{x} - 4, \quad (2, 3)$
18. $z = \cos(x^2 + y^2), \quad (3, -4)$
19. $w = 6xy - y^2 + 2xyz^3, \quad (-1, 5, -1)$
20. $w = x\tan(y + z), \quad (4, 3, -1)$

Finding a Directional Derivative **In Exercises 21–24, use the gradient to find the directional derivative of the function at P in the direction of $\mathbf{v}$.**

21. $f(x, y) = xy, \quad P(0, -2), \quad \mathbf{v} = \frac{1}{2}(\mathbf{i} + \sqrt{3}\mathbf{j})$
22. $h(x, y) = e^{-3x}\sin y, \quad P\left(1, \frac{\pi}{2}\right), \quad \mathbf{v} = -\mathbf{i}$
23. $f(x, y, z) = x^2 + y^2 + z^2, \quad P(1, 1, 1), \quad \mathbf{v} = \frac{\sqrt{3}}{3}(\mathbf{i} - \mathbf{j} + \mathbf{k})$
24. $f(x, y, z) = xy + yz + xz, \quad P(1, 2, -1), \quad \mathbf{v} = 2\mathbf{i} + \mathbf{j} - \mathbf{k}$

Finding a Directional Derivative **In Exercises 25–28, use the gradient to find the directional derivative of the function at P in the direction of $\overrightarrow{PQ}$.**

25. $g(x, y) = x^2 + y^2 + 1, \quad P(1, 2), \quad Q(2, 3)$
26. $f(x, y) = 3x^2 - y^2 + 4, \quad P(-1, 4), \quad Q(3, 6)$
27. $g(x, y, z) = xye^z, \quad P(2, 4, 0), \quad Q(0, 0, 0)$
28. $h(x, y, z) = \ln(x + y + z), \quad P(1, 0, 0), \quad Q(4, 3, 1)$

Using Properties of the Gradient **In Exercises 29–38, find the gradient of the function and the maximum value of the directional derivative at the given point.**

29. $f(x, y) = y^2 - x\sqrt{y}, \quad (0, 3)$
30. $f(x, y) = \frac{x + y}{y + 1}, \quad (0, 1)$
31. $h(x, y) = x\tan y, \quad \left(2, \frac{\pi}{4}\right)$
32. $h(x, y) = y\cos(x - y), \quad \left(0, \frac{\pi}{3}\right)$
33. $f(x, y) = \sin x^2y^3, \quad \left(\frac{1}{\pi}, \pi\right)$
34. $g(x, y) = \ln\sqrt[3]{x^2 + y^2}, \quad (1, 2)$
35. $f(x, y, z) = \sqrt{x^2 + y^2 + z^2}, \quad (1, 4, 2)$
36. $w = \frac{1}{\sqrt{1 - x^2 - y^2 - z^2}}, \quad (0, 0, 0)$
37. $w = xy^2z^2, \quad (2, 1, 1)$
38. $f(x, y, z) = xe^{yz}, \quad (2, 0, -4)$

Finding a Normal Vector to a Level Curve **In Exercises 39–42, find a normal vector to the level curve $f(x, y) = c$ at P.**

39. $f(x, y) = 6 - 2x - 3y$
$c = 6, \quad P(0, 0)$

40. $f(x, y) = x^2 + y^2$
$c = 25, \quad P(3, 4)$

41. $f(x, y) = xy$
$c = -3, \quad P(-1, 3)$

42. $f(x, y) = \frac{x}{x^2 + y^2}$
$c = \frac{1}{2}, \quad P(1, 1)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Using a Function **In Exercises 43–46, (a) find the gradient of the function at P, (b) find a unit normal vector to the level curve $f(x, y) = c$ at P, (c) find the tangent line to the level curve $f(x, y) = c$ at P, and (d) sketch the level curve, the unit normal vector, and the tangent line in the xy-plane.**

43. $f(x, y) = 4x^2 - y$, $c = 6$, $P(2, 10)$

44. $f(x, y) = x - y^2$, $c = 3$, $P(4, -1)$

45. $f(x, y) = 3x^2 - 2y^2$, $c = 1$, $P(1, 1)$

46. $f(x, y) = 9x^2 + 4y^2$, $c = 40$, $P(2, -1)$

47. Using a Function Consider the function

$$f(x, y) = 3 - \frac{x}{3} - \frac{y}{2}.$$

(a) Sketch the graph of f in the first octant and plot the point $(3, 2, 1)$ on the surface.

(b) Find $D_{\mathbf{u}}f(3, 2)$, where $\mathbf{u} = \cos\theta\mathbf{i} + \sin\theta\mathbf{j}$, using each given value of θ.

(i) $\theta = \frac{\pi}{4}$ (ii) $\theta = \frac{2\pi}{3}$ (iii) $\theta = \frac{4\pi}{3}$ (iv) $\theta = -\frac{\pi}{6}$

(c) Find $D_{\mathbf{u}}f(3, 2)$, where $\mathbf{u} = \frac{\mathbf{v}}{\|\mathbf{v}\|}$, using each given vector $\mathbf{v}$.

(i) $\mathbf{v} = \mathbf{i} + \mathbf{j}$

(ii) $\mathbf{v} = -3\mathbf{i} - 4\mathbf{j}$

(iii) $\mathbf{v}$ is the vector from $(1, 2)$ to $(-2, 6)$.

(iv) $\mathbf{v}$ is the vector from $(3, 2)$ to $(4, 5)$.

(d) Find $\nabla f(x, y)$.

(e) Find the maximum value of the directional derivative at $(3, 2)$.

(f) Find a unit vector $\mathbf{u}$ orthogonal to $\nabla f(3, 2)$ and calculate $D_{\mathbf{u}}f(3, 2)$. Discuss the geometric meaning of the result.

48. Using a Function Consider the function

$$f(x, y) = 9 - x^2 - y^2.$$

(a) Sketch the graph of f in the first octant and plot the point $(1, 2, 4)$ on the surface.

(b) Find $D_{\mathbf{u}}f(1, 2)$, where $\mathbf{u} = \cos\theta\mathbf{i} + \sin\theta\mathbf{j}$, using each given value of θ.

(i) $\theta = -\frac{\pi}{4}$ (ii) $\theta = \frac{\pi}{3}$ (iii) $\theta = \frac{3\pi}{4}$ (iv) $\theta = -\frac{\pi}{2}$

(c) Find $D_{\mathbf{u}}f(1, 2)$, where $\mathbf{u} = \frac{\mathbf{v}}{\|\mathbf{v}\|}$, using each given vector $\mathbf{v}$.

(i) $\mathbf{v} = 3\mathbf{i} + \mathbf{j}$

(ii) $\mathbf{v} = -8\mathbf{i} - 6\mathbf{j}$

(iii) $\mathbf{v}$ is the vector from $(-1, -1)$ to $(3, 5)$.

(iv) $\mathbf{v}$ is the vector from $(-2, 0)$ to $(1, 3)$.

(d) Find $\nabla f(1, 2)$.

(e) Find the maximum value of the directional derivative at $(1, 2)$.

(f) Find a unit vector $\mathbf{u}$ orthogonal to $\nabla f(1, 2)$ and calculate $D_{\mathbf{u}}f(1, 2)$. Discuss the geometric meaning of the result.

49. Investigation Consider the function

$$f(x, y) = x^2 - y^2$$

at the point $(4, -3, 7)$.

(a) Use a graphing utility to graph the surface represented by the function.

(b) Determine the directional derivative $D_{\mathbf{u}}f(4, -3)$ as a function of θ, where

$$\mathbf{u} = \cos\theta\mathbf{i} + \sin\theta\mathbf{j}.$$

Use a graphing utility to graph the function on the interval $[0, 2\pi)$.

(c) Approximate the zeros of the function in part (b) and interpret each in the context of the problem.

(d) Approximate the critical numbers of the function in part (b) and interpret each in the context of the problem.

(e) Find $\|\nabla f(4, -3)\|$ and explain its relationship to your answers in part (d).

(f) Use a graphing utility to graph the level curve of the function f at the level $c = 7$. On this curve, graph the vector in the direction of $\nabla f(4, -3)$ and state its relationship to the level curve.

50. Investigation Consider the function

$$f(x, y) = \frac{8y}{1 + x^2 + y^2}.$$

(a) Analytically verify that the level curve of $f(x, y)$ at the level $c = 2$ is a circle.

(b) At the point $(\sqrt{3}, 2)$ on the level curve for which $c = 2$, sketch the vector showing the direction of the greatest rate of increase of the function. To print a graph of the level curve, go to *MathGraphs.com.*

(c) At the point $(\sqrt{3}, 2)$ on the level curve for which $c = 2$, sketch a vector such that the directional derivative is 0.

(d) Use a graphing utility to graph the surface to verify your answers in parts (a)–(c).

Exploring Concepts

51. Consider $\mathbf{v} = 3\mathbf{u}$. Determine whether the directional derivative of a differentiable function $f(x, y)$ in the direction of $\mathbf{v}$ at the point (x_0, y_0) is three times the directional derivative of f in the direction of $\mathbf{u}$ at the point (x_0, y_0). Explain.

52. Sketch the graph of a surface and select a point P on the surface. Sketch a vector in the xy-plane giving the direction of steepest ascent on the surface at P.

53. Topography The surface of a mountain is modeled by the equation

$$h(x, y) = 5000 - 0.001x^2 - 0.004y^2.$$

A mountain climber is at the point $(500, 300, 4390)$. In what direction should the climber move to ascend at the greatest rate?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

54. HOW DO YOU SEE IT? The figure shows a topographic map carried by a group of hikers. Sketch the paths of steepest descent when the hikers start at point A and when they start at point B. (To print an enlarged copy of the graph, go to *MathGraphs.com*.)



55. Temperature The temperature at the point (x, y) on a metal plate is

$$T(x, y) = \frac{x}{x^2 + y^2}.$$

Find the direction of greatest increase in heat from the point $(3, 4)$.

56. Temperature The temperature at the point (x, y) on a metal plate is $T(x, y) = 400e^{-(x^2+y)/2}$, $x \geq 0$, $y \geq 0$.

(a) Use a graphing utility to graph the temperature distribution function.

(b) Find the directions of no change in heat on the plate from the point $(3, 5)$.

(c) Find the direction of greatest increase in heat from the point $(3, 5)$.

Finding the Direction of Maximum Increase **In Exercises 57 and 58, the temperature in degrees Celsius on the surface of a metal plate is given by $T(x, y)$, where x and y are measured in centimeters. Find the direction from point P where the temperature increases most rapidly and this rate of increase.**

57. $T(x, y) = 80 - 3x^2 - y^2$, $P(-1, 5)$

58. $T(x, y) = 50 - x^2 - 4y^2$, $P(2, -1)$

Finding the Path of a Heat-Seeking Particle **In Exercises 59 and 60, find the path of a heat-seeking particle placed at point P on a metal plate whose temperature at (x, y) is $T(x, y)$.**

59. $T(x, y) = 400 - 2x^2 - y^2$, $P(10, 10)$

60. $T(x, y) = 100 - x^2 - 2y^2$, $P(4, 3)$

True or False? **In Exercises 61–64, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

61. If $f(x, y) = \sqrt{1 - x^2 - y^2}$, then $D_{\mathbf{u}} f(0, 0) = 0$ for any unit vector $\mathbf{u}$.

62. If $f(x, y) = x + y$, then $-1 \leq D_{\mathbf{u}} f(x, y) \leq 1$.

63. If $D_{\mathbf{u}} f(x, y)$ exists, then $D_{\mathbf{u}} f(x, y) = -D_{\mathbf{u}} f(x, y)$.

64. If $D_{\mathbf{u}} f(x_0, y_0) = c$ for any unit vector $\mathbf{u}$, then $c = 0$.

65. Finding a Function Find a function f such that

$$\nabla f = e^x \cos y\mathbf{i} - e^x \sin y\mathbf{j} + z\mathbf{k}.$$

66. Ocean Floor

A team of oceanographers is mapping the ocean floor to assist in the recovery of a sunken ship. Using sonar, they develop the model

$$D = 250 + 30x^2 + 50 \sin \frac{\pi y}{2}, \quad 0 \leq x \leq 2, \quad 0 \leq y \leq 2$$

where D is the depth in meters, and x and y are the distances in kilometers.

(a) Use a graphing utility to graph D.

(b) Because the graph in part (a) is showing depth, it is not a map of the ocean floor. How could the model be changed so that the graph of the ocean floor could be obtained?

(c) What is the depth of the ship if it is located at the coordinates $x = 1$ and $y = 0.5$?

(d) Determine the steepness of the ocean floor in the positive x-direction from the position of the ship.

(e) Determine the steepness of the ocean floor in the positive y-direction from the position of the ship.

(f) Determine the direction of the greatest rate of change of depth from the position of the ship.

67. Using a Function Consider the function

$$f(x, y) = \sqrt[3]{xy}.$$

(a) Show that f is continuous at the origin.

(b) Show that f_x and f_y exist at the origin but that the directional derivatives at the origin in all other directions do not exist.

(c) Use a graphing utility to graph f near the origin to verify your answers in parts (a) and (b). Explain.

68. Directional Derivative Consider the function

$$f(x, y) = \begin{cases} \dfrac{4xy}{x^2 + y^2}, & (x, y) \neq (0, 0) \\ 0, & (x, y) \neq (0, 0) \end{cases}$$

and the unit vector

$$\mathbf{u} = \frac{1}{\sqrt{2}}(\mathbf{i} + \mathbf{j}).$$

Does the directional derivative of f at $P(0, 0)$ in the direction of $\mathbf{u}$ exist? If $f(0, 0)$ were defined as 2 instead of 0, would the directional derivative exist? Explain.

NaturePicsFilms/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

13.7 Tangent Planes and Normal Lines

GO DIGITAL

- **Find equations of tangent planes and normal lines to surfaces.**
- **Find the angle of inclination of a plane in space.**
- **Compare the gradients $\nabla f(x, y)$ and $\nabla F(x, y, z)$.**

Exploration

Billiard Balls and Normal Lines In each of the three figures below, the cue ball is about to strike a stationary ball at point P. Explain how you can use the normal line to the stationary ball at point P to describe the resulting motion of each of the two balls. Assuming that each cue ball has the same speed, which stationary ball will acquire the greatest speed? Which will acquire the least? Explain your reasoning.



Tangent Plane and Normal Line to a Surface

So far, you have represented surfaces in space primarily by equations of the form

$$z = f(x, y).$$ Equation of a surface S

In the development to follow, however, it is convenient to use the more general representation $F(x, y, z) = 0$. For a surface S given by $z = f(x, y)$, you can convert to the general form by defining F as

$$F(x, y, z) = f(x, y) - z.$$

Because $f(x, y) - z = 0$, you can consider S to be the level surface of F given by

$$F(x, y, z) = 0.$$ Alternative equation of surface S

EXAMPLE 1 Writing an Equation of a Surface

For the function

$$F(x, y\, z) = x^2 + y^2 + z^2 - 4$$

describe the level surface given by

$$F(x, y, z) = 0.$$

Solution The level surface given by $F(x, y, z) = 0$ can be written as

$$x^2 + y^2 + z^2 = 4$$

which is a sphere of radius 2 whose center is at the origin. ■

You have seen many examples of the usefulness of normal lines in applications involving curves. Normal lines are equally important in analyzing surfaces and solids. For example, consider the collision of two billiard balls. When a stationary ball is struck at a point P on its surface, it moves along the **line of impact** determined by P and the center of the ball. The impact can occur in *two* ways. When the cue ball is moving along the line of impact, it stops dead and imparts all of its momentum to the stationary ball, as shown in Figure 13.55.



Figure 13.55



Figure 13.56

When the cue ball is not moving along the line of impact, it is deflected to one side or the other and retains part of its momentum. The part of the momentum that is transferred to the stationary ball occurs along the line of impact, *regardless* of the direction of the cue ball, as shown in Figure 13.56. This line of impact is called the **normal line** to the surface of the ball at the point P.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

In the process of finding a normal line to a surface, you are also able to solve the problem of finding a **tangent plane** to the surface. Let S be a surface given by

$$F(x, y, z) = 0$$

and let $P(x_0, y_0, z_0)$ be a point on S. Let C be a curve on S through P that is defined by the vector-valued function

$$\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j} + z(t)\mathbf{k}.$$

Then, for all t,

$$F(x(t), y(t), z(t)) = 0.$$

If F is differentiable and $x'(t)$, $y'(t)$, and $z'(t)$ all exist, then it follows from the Chain Rule that

$$\begin{aligned} 0 &= F'(t) \\ &= F_x(x, y, z)x'(t) + F_y(x, y, z)y'(t) + F_z(x, y, z)z'(t). \end{aligned}$$

At (x_0, y_0, z_0), the equivalent vector form is

$$0 = \underbrace{\nabla F(x_0, y_0, z_0)}_{\text{Gradient}} \cdot \underbrace{\mathbf{r}'(t_0)}_{\text{Tangent vector}}.$$



Tangent plane to surface S at P
Figure 13.57

This result means that the gradient at P is orthogonal to the tangent vector of every curve on S through P. So, all tangent lines on S lie in a plane that is normal to $\nabla F(x_0, y_0, z_0)$ and contains P, as shown in Figure 13.57.

REMARK In the remainder of this section, assume $\nabla F(x_0, y_0, z_0)$ to be nonzero unless stated otherwise.

Definitions of Tangent Plane and Normal Line

Let F be differentiable at the point $P(x_0, y_0, z_0)$ on the surface S given by $F(x, y, z) = 0$ such that

$$\nabla F(x_0, y_0, z_0) \neq \mathbf{0}.$$

1. The plane through P that is normal to $\nabla F(x_0, y_0, z_0)$ is called the **tangent plane to S at P.**
2. The line through P having the direction of $\nabla F(x_0, y_0, z_0)$ is called the **normal line to S at P.**

To find an equation for the tangent plane to S at (x_0, y_0, z_0), let (x, y, z) be an arbitrary point in the tangent plane. Then the vector

$$\mathbf{v} = (x - x_0)\mathbf{i} + (y - y_0)\mathbf{j} + (z - z_0)\mathbf{k}$$

lies in the tangent plane. Because $\nabla F(x_0, y_0, z_0)$ is normal to the tangent plane at (x_0, y_0, z_0), it must be orthogonal to every vector in the tangent plane, and you have

$$\nabla F(x_0, y_0, z_0) \cdot \mathbf{v} = 0$$

which leads to the next theorem.

THEOREM 13.13 Equation of Tangent Plane

If F is differentiable at (x_0, y_0, z_0), then an equation of the tangent plane to the surface given by $F(x, y, z) = 0$ at (x_0, y_0, z_0) is

$$F_x(x_0, y_0, z_0)(x - x_0) + F_y(x_0, y_0, z_0)(y - y_0) + F_z(x_0, y_0, z_0)(z - z_0) = 0.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 2 **Finding an Equation of a Tangent Plane**

Find an equation of the tangent plane to the hyperboloid

$$z^2 - 2x^2 - 2y^2 = 12$$

at the point $(1, -1, 4)$.

Solution Begin by writing the equation of the surface as

$$z^2 - 2x^2 - 2y^2 - 12 = 0.$$

Then, considering

$$F(x, y, z) = z^2 - 2x^2 - 2y^2 - 12$$

you have

$$F_x(x, y, z) = -4x, \quad F_y(x, y, z) = -4y, \quad \text{and} \quad F_z(x, y, z) = 2z.$$

At the point $(1, -1, 4)$, the partial derivatives are

$$F_x(1, -1, 4) = -4, \quad F_y(1, -1, 4) = 4, \quad \text{and} \quad F_z(1, -1, 4) = 8.$$

So, an equation of the tangent plane at $(1, -1, 4)$ is

$$\begin{aligned} -4(x - 1) + 4(y + 1) + 8(z - 4) &= 0 \\ -4x + 4 + 4y + 4 + 8z - 32 &= 0 \\ -4x + 4y + 8z - 24 &= 0 \\ x - y - 2z + 6 &= 0. \end{aligned}$$

Figure 13.58 shows a portion of the hyperboloid and the tangent plane.



Tangent plane to surface

Figure 13.58

To find an equation of the tangent plane at a point on a surface given by $z = f(x, y)$, you can define the function F by

$$F(x, y, z) = f(x, y) - z.$$

Then S is given by the level surface $F(x, y, z) = 0$, and by Theorem 13.13, an equation of the tangent plane to S at the point (x_0, y_0, z_0) is

$$f_x(x_0, y_0)(x - x_0) + f_y(x_0, y_0)(y - y_0) - (z - z_0) = 0.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 3 Finding an Equation of the Tangent Plane

Find an equation of the tangent plane to the paraboloid

$$z = 1 - \frac{1}{10}(x^2 + 4y^2)$$

at the point $\left(1, 1, \frac{1}{2}\right)$.

Solution From $z = f(x, y) = 1 - \frac{1}{10}(x^2 + 4y^2)$, you obtain

$$f_x(x, y) = -\frac{x}{5} \quad \Rightarrow \quad f_x(1, 1) = -\frac{1}{5}$$

and

$$f_y(x, y) = -\frac{4y}{5} \quad \Rightarrow \quad f_y(1, 1) = -\frac{4}{5}.$$

So, an equation of the tangent plane at $\left(1, 1, \frac{1}{2}\right)$ is

$$f_x(1, 1)(x - 1) + f_y(1, 1)(y - 1) - \left(z - \frac{1}{2}\right) = 0$$

$$-\frac{1}{5}(x - 1) - \frac{4}{5}(y - 1) - \left(z - \frac{1}{2}\right) = 0$$

$$-\frac{1}{5}x - \frac{4}{5}y - z + \frac{3}{2} = 0.$$

This tangent plane is shown in Figure 13.59.



Figure 13.59

The gradient $\nabla F(x, y, z)$ provides a convenient way to find equations of normal lines, as shown in Example 4.

EXAMPLE 4 Finding an Equation of a Normal Line to a Surface

See LarsonCalculus.com for an interactive version of this type of example.

Find a set of symmetric equations for the normal line to the surface

$$xyz = 12$$

at the point $(2, -2, -3)$.

Solution Begin by letting

$$F(x, y, z) = xyz - 12.$$

Then, the gradient is given by

$$\nabla F(x, y, z) = F_x(x, y, z)\mathbf{i} + F_y(x, y, z)\mathbf{j} + F_z(x, y, z)\mathbf{k}$$
$$= yz\mathbf{i} + xz\mathbf{j} + xy\mathbf{k}$$

and at the point $(2, -2, -3)$, you have

$$\nabla F(2, -2, -3) = (-2)(-3)\mathbf{i} + (2)(-3)\mathbf{j} + (2)(-2)\mathbf{k}$$
$$= 6\mathbf{i} - 6\mathbf{j} - 4\mathbf{k}.$$

The normal line at $(2, -2, -3)$ has direction numbers 6, -6, and -4, and the corresponding set of symmetric equations is

$$\frac{x - 2}{6} = \frac{y + 2}{-6} = \frac{z + 3}{-4}.$$

See Figure 13.60.



Figure 13.60

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Knowing that the gradient $\nabla F(x, y, z)$ is normal to the surface given by $F(x, y, z) = 0$ allows you to solve a variety of problems dealing with surfaces and curves in space.

EXAMPLE 5 Finding the Equation of a Tangent Line to a Curve

Find a set of parametric equations for the tangent line to the curve of intersection of the ellipsoid

$$x^2 + 2y^2 + 2z^2 = 20 \qquad \text{Ellipsoid}$$

and the paraboloid

$$x^2 + y^2 + z = 4 \qquad \text{Paraboloid}$$

at the point $(0, 1, 3)$, as shown in Figure 13.61.



Figure 13.61

Solution Begin by finding the gradients to both surfaces at the point $(0, 1, 3)$.

Ellipsoid	**Paraboloid**
$F(x, y, z) = x^2 + 2y^2 + 2z^2 - 20$	$G(x, y, z) = x^2 + y^2 + z - 4$
$\nabla F(x, y, z) = 2x\mathbf{i} + 4y\mathbf{j} + 4z\mathbf{k}$	$\nabla G(x, y, z) = 2x\mathbf{i} + 2y\mathbf{j} + \mathbf{k}$
$\nabla F(0, 1, 3) = 4\mathbf{j} + 12\mathbf{k}$	$\nabla G(0, 1, 3) = 2\mathbf{j} + \mathbf{k}$

The cross product of these two gradients is a vector that is tangent to both surfaces at the point $(0, 1, 3)$.

$$\nabla F(0, 1, 3) \times \nabla G(0, 1, 3) = \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ 0 & 4 & 12 \\ 0 & 2 & 1 \end{vmatrix} = -20\mathbf{i}$$

So, the tangent line to the curve of intersection of the two surfaces at the point $(0, 1, 3)$ is a line that is parallel to the x-axis and passes through the point $(0, 1, 3)$. Because $-20\mathbf{i} = -20(\mathbf{i} + 0\mathbf{j} + 0\mathbf{k})$, the direction numbers are 1, 0, and 0. So a set of parametric equations for the tangent line passing through the point $(0, 1, 3)$ is $x = t$, $y = 1$, and $z = 3$. ■

The Angle of Inclination of a Plane

Another use of the gradient $\nabla F(x, y, z)$ is to determine the angle of inclination of the tangent plane to a surface. The **angle of inclination** of a plane is defined as the angle θ $(0 \le \theta \le \pi/2)$ between the given plane and the xy-plane, as shown in Figure 13.62. (The angle of inclination of a horizontal plane is defined as zero.) Because the vector $\mathbf{k}$ is normal to the xy-plane, you can use the formula for the cosine of the angle between two planes (given in Section 11.5) to conclude that the angle of inclination of a plane with normal vector $\mathbf{n}$ is

$$\cos\theta = \frac{|\mathbf{n} \cdot \mathbf{k}|}{\|\mathbf{n}\|\,\|\mathbf{k}\|} = \frac{|\mathbf{n} \cdot \mathbf{k}|}{\|\mathbf{n}\|}. \qquad \text{Angle of inclination of a plane}$$



The angle of inclination

Figure 13.62

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 6 Finding the Angle of Inclination of a Tangent Plane

Find the angle of inclination of the tangent plane to the ellipsoid

$$\frac{x^2}{12} + \frac{y^2}{12} + \frac{z^2}{3} = 1$$

at the point $(2, 2, 1)$.

Solution Begin by letting

$$F(x, y, z) = \frac{x^2}{12} + \frac{y^2}{12} + \frac{z^2}{3} - 1.$$

Then, the gradient of F at the point $(2, 2, 1)$ is

$$\nabla F(x, y, z) = \frac{x}{6}\mathbf{i} + \frac{y}{6}\mathbf{j} + \frac{2z}{3}\mathbf{k}$$

$$\nabla F(2, 2, 1) = \frac{1}{3}\mathbf{i} + \frac{1}{3}\mathbf{j} + \frac{2}{3}\mathbf{k}.$$



Figure 13.63

Because $\nabla F(2, 2, 1)$ is normal to the tangent plane and $\mathbf{k}$ is normal to the xy-plane, it follows that the angle of inclination of the tangent plane is

$$\cos\theta = \frac{|\nabla F(2, 2, 1) \cdot \mathbf{k}|}{\|\nabla F(2, 2, 1)\|} = \frac{2/3}{\sqrt{(1/3)^2 + (1/3)^2 + (2/3)^2}} = \sqrt{\frac{2}{3}}$$

which implies that

$$\theta = \arccos\sqrt{\frac{2}{3}} \approx 35.3°$$

as shown in Figure 13.63. ■

A special case of the procedure shown in Example 6 is worth noting. The angle of inclination θ of the tangent plane to the surface $z = f(x, y)$ at (x_0, y_0, z_0) is

$$\cos\theta = \frac{1}{\sqrt{[f_x(x_0, y_0)]^2 + [f_y(x_0, y_0)]^2 + 1}}.$$

Alternative formula for angle of inclination (See Exercise 65.)

A Comparison of the Gradients $\nabla f(x, y)$ and $\nabla F(x, y, z)$

This section concludes with a comparison of the gradients $\nabla f(x, y)$ and $\nabla F(x, y, z)$. In the preceding section, you learned that the gradient of a function f of two variables is normal to the level curves of f. Specifically, Theorem 13.12 states that if f is differentiable at (x_0, y_0) and $\nabla f(x_0, y_0) \neq \mathbf{0}$, then $\nabla f(x_0, y_0)$ is normal to the level curve through (x_0, y_0). Having developed normal lines to surfaces, you can now extend this result to a function of three variables. The proof of Theorem 13.14 is left as an exercise (see Exercise 66).

THEOREM 13.14 Gradient Is Normal to Level Surfaces

If F is differentiable at (x_0, y_0, z_0) and

$$\nabla F(x_0, y_0, z_0) \neq \mathbf{0}$$

then $\nabla F(x_0, y_0, z_0)$ is normal to the level surface through (x_0, y_0, z_0).

When working with the gradients $\nabla f(x, y)$ and $\nabla F(x, y, z)$, be sure you remember that $\nabla f(x, y)$ is a vector in the xy-plane and $\nabla F(x, y, z)$ is a vector in space.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

13.7 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Consider a point (x_0, y_0, z_0) on a surface given by $F(x, y, z) = 0$. What is the relationship between $\nabla F(x_0, y_0, z_0)$ and any tangent vector $\mathbf{v}$ at (x_0, y_0, z_0)? How do you represent this relationship mathematically?
2. Consider a point (x_0, y_0, z_0) on a surface given by $F(x, y, z) = 0$. What is the relationship between $\nabla F(x_0, y_0, z_0)$ and the normal line through (x_0, y_0, z_0)?

Describing a Surface **In Exercises 3–6, describe the level surface $F(x, y, z) = 0$.**

3. $F(x, y, z) = 3x - 5y + 3z - 15$
4. $F(x, y, z) = 36 - x^2 - y^2 - z^2$
5. $F(x, y, z) = 4x^2 + 9y^2 - 4z^2$
6. $F(x, y, z) = 16x^2 - 9y^2 + 36z$

Finding a Unit Normal Vector **In Exercises 7 and 8, find a unit normal vector to the surface at the given point. [*Hint:* Normalize the gradient vector $\nabla F(x, y, z)$.]**

Surface	Point
7. $3x + 4y + 12z = 0$	$(0, 0, 0)$
8. $x^2y^3 - y^2z + 2xz^3 = 4$	$(-1, 1, -1)$

Finding an Equation of a Tangent Plane **In Exercises 9–18, find an equation of the tangent plane to the surface at the given point.**

9. $z = x^2 + y^2 + 3$, $(2, 1, 8)$



10. $f(x, y) = \frac{y}{x}$, $(1, 2, 2)$



11. $z = \sqrt{x^2 + y^2}$, $(3, 4, 5)$
12. $g(x, y) = \arctan\frac{y}{x}$, $(1, 0, 0)$
13. $g(x, y) = x^2 + y^2$, $(1, -1, 2)$
14. $f(x, y) = x^2 - 2xy + y^2$, $(1, 2, 1)$
15. $h(x, y) = \ln\sqrt{x^2 + y^2}$, $(3, 4, \ln 5)$
16. $f(x, y) = \sin x \cos y$, $\left(\frac{\pi}{3}, \frac{\pi}{6}, \frac{3}{4}\right)$
17. $x^2 + y^2 - 5z^2 = 15$, $(-4, -2, 1)$
18. $x^2 + 2z^2 = y^2$, $(1, 3, -2)$

Finding an Equation of a Tangent Plane and a Normal Line **In Exercises 19–28, (a) find an equation of the tangent plane to the surface at the given point and (b) find a set of symmetric equations for the normal line to the surface at the given point.**

19. $x + y + z = 9$, $(3, 3, 3)$
20. $x^2 + y^2 + z^2 = 9$, $(1, 2, 2)$
21. $x^2 + 2y^2 + z^2 = 7$, $(1, -1, 2)$
22. $z = 16 - x^2 - y^2$, $(2, 2, 8)$
23. $z = x^2 - y^2$, $(3, 2, 5)$
24. $xy - z = 0$, $(-2, -3, 6)$
25. $xyz = 10$, $(1, 2, 5)$
26. $6xy = z$, $(-1, 1, -6)$
27. $z = ye^{2xy}$, $(0, 2, 2)$
28. $y \ln xz^2 = 2$, $(e, 2, 1)$

Finding the Equation of a Tangent Line to a Curve **In Exercises 29–34, find a set of parametric equations for the tangent line to the curve of intersection of the surfaces at the given point.**

29. $x^2 + y^2 = 2$, $z = x$, $(1, 1, 1)$
30. $z = x^2 + y^2$, $z = 4 - y$, $(2, -1, 5)$
31. $x^2 + z^2 = 25$, $y^2 + z^2 = 25$, $(3, 3, 4)$
32. $z = \sqrt{x^2 + y^2}$, $5x - 2y + 3z = 22$, $(3, 4, 5)$
33. $x^2 + y^2 + z^2 = 14$, $x - y - z = 0$, $(3, 1, 2)$
34. $z = x^2 + y^2$, $x + y + 6z = 33$, $(1, 2, 5)$

Finding the Angle of Inclination of a Tangent Plane **In Exercises 35–38, find the angle of inclination of the tangent plane to the surface at the given point.**

35. $3x^2 + 2y^2 - z = 15$, $(2, 2, 5)$
36. $2xy - z^3 = 0$, $(2, 2, 2)$
37. $x^2 - y^2 + z = 0$, $(1, 2, 3)$
38. $x^2 + y^2 = 5$, $(2, 1, 3)$

Horizontal Tangent Plane **In Exercises 39–44, find the point(s) on the surface at which the tangent plane is horizontal.**

39. $z = 3 - x^2 - y^2 + 6y$
40. $z = 3x^2 + 2y^2 - 3x + 4y - 5$
41. $z = x^2 - xy + y^2 - 2x - 2y$
42. $z = 4x^2 + 4xy - 2y^2 + 8x - 5y - 4$
43. $z = 5xy$
44. $z = xy + \frac{1}{x} + \frac{1}{y}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Tangent Surfaces **In Exercises 45 and 46, show that the surfaces are tangent to each other at the given point by showing that the surfaces have the same tangent plane at this point.**

45. $x^2 + 2y^2 + 3z^2 = 3$, $x^2 + y^2 + z^2 + 6x - 10y + 14 = 0$, $(-1, 1, 0)$

46. $x^2 + y^2 + z^2 - 8x - 12y + 4z + 42 = 0$, $x^2 + y^2 + 2z = 7$, $(2, 3, -3)$

Perpendicular Tangent Planes **In Exercises 47 and 48, (a) show that the surfaces intersect at the given point and (b) show that the surfaces have perpendicular tangent planes at this point.**

47. $z = 2xy^2$, $8x^2 - 5y^2 - 8z = -13$, $(1, 1, 2)$

48. $x^2 + y^2 + z^2 + 2x - 4y - 4z - 12 = 0$, $4x^2 + y^2 + 16z^2 = 24$, $(1, -2, 1)$

Exploring Concepts

49. The tangent plane to the surface represented by $F(x, y, z) = 0$ at a point P is also tangent to the surface represented by $G(x, y, z) = 0$ at P. Is $\nabla F(x, y, z) = \nabla G(x, y, z)$ at P? Explain.

50. For some surfaces, the normal lines at any point pass through the same geometric object. What is the common geometric object for a sphere? What is the common geometric object for a right circular cylinder? Explain.

51. Using an Ellipsoid Find a point on the ellipsoid $3x^2 + y^2 + 3z^2 = 1$ where the tangent line is parallel to the plane $-12x + 2y + 6z = 0$.

52. Using a Hyperboloid Find a point on the hyperboloid $x^2 + 4y^2 - z^2 = 1$ where the tangent plane is parallel to the plane $x + 4y - z = 0$.

53. Using an Ellipsoid Find a point on the ellipsoid $x^2 + 4y^2 + z^2 = 9$ where the tangent plane is perpendicular to the line with parametric equations

$x = 2 - 4t$, $y = 1 + 8t$, and $z = 3 - 2t$.

54. HOW DO YOU SEE IT? The graph shows the ellipsoid $x^2 + 4y^2 + z^2 = 16$. Use the graph to determine the equation of the tangent plane at each of the given points.



(a) $(4, 0, 0)$ (b) $(0, -2, 0)$ (c) $(0, 0, -4)$

55. Investigation Consider the function

$$f(x, y) = \frac{4xy}{(x^2 + 1)(y^2 + 1)}$$

on the intervals $-2 \le x \le 2$ and $0 \le y \le 3$.

(a) Find a set of parametric equations of the normal line and an equation of the tangent plane to the surface at the point $(1, 1, 1)$.

(b) Repeat part (a) for the point $\left(-1, 2, -\frac{4}{5}\right)$.

(c) Use a graphing utility to graph the surface, the normal lines, and the tangent planes found in parts (a) and (b).

56. Investigation Consider the function

$$f(x, y) = \frac{\sin y}{x}$$

on the intervals $-3 \le x \le 3$ and $0 \le y \le 2\pi$.

(a) Find a set of parametric equations of the normal line and an equation of the tangent plane to the surface at the point

$$\left(2, \frac{\pi}{2}, \frac{1}{2}\right).$$

(b) Repeat part (a) for the point $\left(-\frac{2}{3}, \frac{3\pi}{2}, \frac{3}{2}\right)$.

(c) Use a graphing utility to graph the surface, the normal lines, and the tangent planes found in parts (a) and (b).

57. Using Functions Consider the functions

$$f(x, y) = 6 - x^2 - \frac{y^2}{4} \quad \text{and} \quad g(x, y) = 2x + y.$$

(a) Find a set of parametric equations of the tangent line to the curve of intersection of the surfaces at the point $(1, 2, 4)$ and find the angle between the gradients of f and g.

(b) Use a graphing utility to graph the surfaces and the tangent line found in part (a).

58. Using Functions Consider the functions

$$f(x, y) = \sqrt{16 - x^2 - y^2 + 2x - 4y}$$

and

$$g(x, y) = \frac{\sqrt{2}}{2}\sqrt{1 - 3x^2 + y^2 + 6x + 4y}.$$

(a) Use a graphing utility to graph the first-octant portion of the surfaces represented by f and g.

(b) Find one first-octant point on the curve of intersection and show that the surfaces are orthogonal at this point.

(c) These surfaces are orthogonal along the curve of intersection. Does part (b) prove this fact? Explain.

Writing a Tangent Plane **In Exercises 59 and 60, show that the tangent plane to the quadric surface at the point (x_0, y_0, z_0) can be written in the given form.**

59. Ellipsoid: $\frac{x^2}{a^2} + \frac{y^2}{b^2} + \frac{z^2}{c^2} = 1$

Tangent plane: $\frac{x_0 x}{a^2} + \frac{y_0 y}{b^2} + \frac{z_0 z}{c^2} = 1$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

60. Hyperboloid: $\frac{x^2}{a^2} + \frac{y^2}{b^2} - \frac{z^2}{c^2} = 1$

Tangent plane: $\frac{x_0 x}{a^2} + \frac{y_0 y}{b^2} - \frac{z_0 z}{c^2} = 1$

61. Tangent Planes of a Cone Show that any tangent plane to the cone

$$z^2 = a^2x^2 + b^2y^2$$

passes through the origin.

62. Tangent Planes Let f be a differentiable function and consider the surface

$$z = xf\left(\frac{y}{x}\right).$$

Show that the tangent plane at any point $P(x_0, y_0, z_0)$ on the surface passes through the origin.

63. Approximation Consider the following approximations for a function $f(x, y)$ centered at $(0, 0)$.

Linear Approximation:

$$P_1(x, y) = f(0, 0) + f_x(0, 0)x + f_y(0, 0)y$$

Quadratic Approximation:

$$P_2(x, y) = f(0, 0) + f_x(0, 0)x + f_y(0, 0)y + \tfrac{1}{2}f_{xx}(0, 0)x^2 + f_{xy}(0, 0)xy + \tfrac{1}{2}f_{yy}(0, 0)y^2$$

[Note that the linear approximation is the tangent plane to the surface at $(0, 0, f(0, 0))$.]

(a) Find the linear approximation of $f(x, y) = e^{x-y}$ centered at $(0, 0)$.

(b) Find the quadratic approximation of $f(x, y) = e^{x-y}$ centered at $(0, 0)$.

(c) When $x = 0$ in the quadratic approximation, you obtain the second-degree Taylor polynomial for what function? Answer the same question for $y = 0$.

(d) Complete the table.

x	y	$f(x, y)$	$P_1(x, y)$	$P_2(x, y)$
0	0			
0	0.1			
0.2	0.1			
0.2	0.5			
1	0.5			

(e) Use a graphing utility to graph the surfaces $z = f(x, y)$, $z = P_1(x, y)$, and $z = P_2(x, y)$.

64. Approximation Repeat Exercise 63 for the function $f(x, y) = \cos(x + y)$.

65. Proof Prove that the angle of inclination θ of the tangent plane to the surface $z = f(x, y)$ at the point (x_0, y_0, z_0) is given by

$$\cos\theta = \frac{1}{\sqrt{[f_x(x_0, y_0)]^2 + [f_y(x_0, y_0)]^2 + 1}}.$$

66. Proof Prove Theorem 13.14.

SECTION PROJECT

Wildflowers

The diversity of wildflowers in a meadow can be measured by counting the numbers of daisies, buttercups, shooting stars, and so on. When there are n types of wildflowers, each with a proportion p_i of the total population, it follows that

$$p_1 + p_2 + \cdots + p_n = 1.$$

The measure of diversity of the population is defined as

$$H = -\sum_{i=1}^{n} p_i \log_2 p_i.$$

In this definition, it is understood that $p_i \log_2 p_i = 0$ when $p_i = 0$. The tables show proportions of wildflowers in a meadow in May, June, August, and September.

May

Flower type	1	2	3	4
Proportion	$\frac{5}{16}$	$\frac{5}{16}$	$\frac{5}{16}$	$\frac{1}{16}$

June

Flower type	1	2	3	4
Proportion	$\frac{1}{4}$	$\frac{1}{4}$	$\frac{1}{4}$	$\frac{1}{4}$

August

Flower type	1	2	3	4
Proportion	$\frac{1}{4}$	0	$\frac{1}{4}$	$\frac{1}{2}$

September

Flower type	1	2	3	4
Proportion	0	0	0	1

(a) Determine the wildflower diversity for each month. How would you interpret September's diversity? Which month had the greatest diversity?

(b) When the meadow contains 10 types of wildflowers in roughly equal proportions, is the diversity of the population greater than or less than the diversity of a similar distribution of 4 types of flowers? What type of distribution (of 10 types of wildflowers) would produce maximum diversity?

(c) Let H_n represent the maximum diversity of n types of wildflowers. Does H_n approach a limit as n approaches ∞?

FOR FURTHER INFORMATION Biologists use the concept of diversity to measure the proportions of different types of organisms within an environment. For more information on this technique, see the article "Information Theory and Biological Diversity" by Steven Kolmes and Kevin Mitchell in the *UMAP Modules.*

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

13.8 Extrema of Functions of Two Variables

GO DIGITAL

- **Find absolute extrema and relative extrema of a function of two variables.**
- **Use the Second Partials Test to find relative extrema of a function of two variables.**

Absolute Extrema and Relative Extrema

In Chapter 3, you studied techniques for finding the extreme values of a function of a single variable. In this section, you will extend these techniques to functions of two variables. For example, in Theorem 13.15 below, the Extreme Value Theorem for a function of a single variable is extended to a function of two variables.

Consider the continuous function f of two variables, defined on a closed bounded region R in the xy-plane. The values $f(a, b)$ and $f(c, d)$ such that

$$f(a, b) \leq f(x, y) \leq f(c, d) \qquad (a, b) \text{ and } (c, d) \text{ are in } R.$$

for all (x, y) in R are called the **minimum** and **maximum** of f in the region R, as shown in Figure 13.64. Recall from Section 13.2 that a region in the plane is *closed* when it contains all of its boundary points. The Extreme Value Theorem deals with a region in the plane that is both closed and *bounded.* A region in the plane is **bounded** when it is a subregion of a closed disk in the plane.



R contains point(s) at which $f(x, y)$ is a minimum and point(s) at which $f(x, y)$ is a maximum.

Figure 13.64

THEOREM 13.15 Extreme Value Theorem

Let f be a continuous function of two variables x and y defined on a closed bounded region R in the xy-plane.

1. There is at least one point in R at which f takes on a minimum value.
2. There is at least one point in R at which f takes on a maximum value.

A minimum is also called an **absolute minimum** and a maximum is also called an **absolute maximum.** As in single-variable calculus, there is a distinction made between absolute extrema and **relative extrema.**

Definition of Relative Extrema

Let f be a function defined on a region R containing (x_0, y_0).

1. The function f has a **relative minimum** at (x_0, y_0) if
$$f(x, y) \geq f(x_0, y_0)$$
for all (x, y) in an *open* disk containing (x_0, y_0).
2. The function f has a **relative maximum** at (x_0, y_0) if
$$f(x, y) \leq f(x_0, y_0)$$
for all (x, y) in an *open* disk containing (x_0, y_0).



Relative extrema

Figure 13.65

To say that f has a relative maximum at (x_0, y_0) means that the point (x_0, y_0, z_0) is at least as high as all nearby points on the graph of

$$z = f(x, y).$$

Similarly, f has a relative minimum at (x_0, y_0) when (x_0, y_0, z_0) is at least as low as all nearby points on the graph. (See Figure 13.65.)

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

KARL WEIERSTRASS (1815–1897)

Although the Extreme Value Theorem had been used by earlier mathematicians, the first to provide a rigorous proof was the German mathematician Karl Weierstrass. Weierstrass also provided rigorous justifications for many other mathematical results already in common use. We are indebted to him for much of the logical foundation on which modern calculus is built. *See LarsonCalculus.com to read more of this biography.*

To locate relative extrema of f, you can investigate the points at which the gradient of f is $\mathbf{0}$ or the points at which one of the partial derivatives does not exist. Such points are called **critical points** of f.

Definition of Critical Point

Let f be defined on an open region R containing (x_0, y_0). The point (x_0, y_0) is a **critical point** of f if one of the following is true.

1. $f_x(x_0, y_0) = 0$ and $f_y(x_0, y_0) = 0$
2. $f_x(x_0, y_0)$ or $f_y(x_0, y_0)$ does not exist.

Recall from Theorem 13.11 that if f is differentiable and

$$\nabla f(x_0, y_0) = f_x(x_0, y_0)\mathbf{i} + f_y(x_0, y_0)\mathbf{j} = 0\mathbf{i} + 0\mathbf{j}$$

then every directional derivative at (x_0, y_0) must be 0. This implies that the function has a horizontal tangent plane at the point (x_0, y_0), as shown in Figure 13.66. It appears that such a point is a likely location of a relative extremum. This is confirmed by Theorem 13.16.



Relative maximum



Relative minimum

Figure 13.66

THEOREM 13.16 Relative Extrema Occur Only at Critical Points

If f has a relative extremum at (x_0, y_0) on an open region R, then (x_0, y_0) is a critical point of f.

Exploration

Use a graphing utility to graph $z = x^3 - 3xy + y^3$ using the bounds $0 \le x \le 3$, $0 \le y \le 3$, and $-3 \le z \le 3$. This view makes it appear as though the surface has an absolute minimum. Does the surface have an absolute minimum? Why or why not?



Science History Images/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



The function $z = f(x, y)$ has a relative minimum at $(-2, 3)$.

Figure 13.67

EXAMPLE 1 Finding a Relative Extremum

See LarsonCalculus.com for an interactive version of this type of example.

Determine the relative extrema of

$$f(x, y) = 2x^2 + y^2 + 8x - 6y + 20.$$

Solution Begin by finding the critical points of f. Because

$$f_x(x, y) = 4x + 8 \qquad \text{Partial with respect to } x$$

and

$$f_y(x, y) = 2y - 6 \qquad \text{Partial with respect to } y$$

are defined for all x and y, the only critical points are those for which both first partial derivatives are 0. To locate these points, set $f_x(x, y)$ and $f_y(x, y)$ equal to 0, and solve the equations

$$4x + 8 = 0 \quad \text{and} \quad 2y - 6 = 0$$

to obtain the critical point $(-2, 3)$. By completing the square for f, you can see that for all $(x, y) \neq (-2, 3)$

$$f(x, y) = 2(x + 2)^2 + (y - 3)^2 + 3 > 3.$$

So, a relative *minimum* of f occurs at $(-2, 3)$. The value of the relative minimum is $f(-2, 3) = 3$, as shown in Figure 13.67. ■

Example 1 shows a relative minimum occurring at one type of critical point—the type for which both $f_x(x, y)$ and $f_y(x, y)$ are 0. The next example concerns a relative maximum that occurs at the other type of critical point—the type for which either $f_x(x, y)$ or $f_y(x, y)$ does not exist.



$f_x(x, y)$ and $f_y(x, y)$ are undefined at $(0, 0)$.

Figure 13.68

EXAMPLE 2 Finding a Relative Extremum

Determine the relative extrema of

$$f(x, y) = 1 - (x^2 + y^2)^{1/3}.$$

Solution Because

$$f_x(x, y) = -\frac{2x}{3(x^2 + y^2)^{2/3}} \qquad \text{Partial with respect to } x$$

and

$$f_y(x, y) = -\frac{2y}{3(x^2 + y^2)^{2/3}} \qquad \text{Partial with respect to } y$$

it follows that both partial derivatives exist for all points in the xy-plane except for $(0, 0)$. Moreover, because the partial derivatives cannot both be 0 unless both x and y are 0, you can conclude that $(0, 0)$ is the only critical point. In Figure 13.68, note that $f(0, 0)$ is 1. For all other (x, y), it is clear that

$$f(x, y) = 1 - (x^2 + y^2)^{1/3} < 1.$$

So, f has a relative *maximum* at $(0, 0)$. ■

In Example 2, $f_x(x, y) = 0$ for every point on the y-axis other than $(0, 0)$. However, because $f_y(x, y)$ is nonzero, these are not critical points. Remember that *one* of the partials must not exist or *both* must be 0 to yield a critical point.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The Second Partials Test

Theorem 13.16 tells you that to find relative extrema, you need only examine values of $f(x, y)$ at critical points. However, as is true for a function of one variable, the critical points of a function of two variables do not always yield relative maxima or minima. Some critical points yield **saddle points,** which are neither relative maxima nor relative minima.

As an example of a critical point that does not yield a relative extremum, consider the hyperbolic paraboloid

$$f(x, y) = y^2 - x^2$$

as shown in Figure 13.69. At the point $(0, 0)$, both partial derivatives

$$f_x(x, y) = -2x \quad \text{and} \quad f_y(x, y) = 2y$$

are 0. The function f does not, however, have a relative extremum at this point because in any open disk centered at $(0, 0)$, the function takes on both negative values (along the x-axis) *and* positive values (along the y-axis), So, the point $(0, 0, 0)$ is a saddle point of the surface. (The term "saddle point" comes from the fact that surfaces such as the one shown in Figure 13.69 resemble saddles.)



Saddle point at $(0, 0, 0)$:
$f_x(0, 0) = f_y(0, 0) = 0$
Figure 13.69

For the functions in Examples 1 and 2, it was relatively easy to determine the relative extrema, because each function was either given, or could be written, in completed square form. For more complicated functions, algebraic arguments are less convenient and it is better to rely on the analytic means presented in the following Second Partials Test. This is the two-variable counterpart of the Second Derivative Test for functions of one variable. The proof of this theorem is best left to a course in advanced calculus.

THEOREM 13.17 Second Partials Test

Let f have continuous second partial derivatives on an open region containing a point (a, b) for which

$$f_x(a, b) = 0 \quad \text{and} \quad f_y(a, b) = 0.$$

To test for relative extrema of f, consider the quantity

$$d = f_{xx}(a, b)f_{yy}(a, b) - [f_{xy}(a, b)]^2.$$

1. If $d > 0$ and $f_{xx}(a, b) > 0$, then f has a **relative minimum** at (a, b).
2. If $d > 0$ and $f_{xx}(a, b) < 0$, then f has a **relative maximum** at (a, b).
3. If $d < 0$, then $(a, b, f(a, b))$ is a **saddle point.**
4. The test is inconclusive if $d = 0$.

REMARK If $d > 0$, then $f_{xx}(a, b)$ and $f_{yy}(a, b)$ must have the same sign. This means that $f_{xx}(a, b)$ can be replaced by $f_{yy}(a, b)$ in the first two parts of the test.

A convenient device for remembering the formula for d in the Second Partials Test is given by the 2×2 determinant

$$d = \begin{vmatrix} f_{xx}(a, b) & f_{xy}(a, b) \\ f_{yx}(a, b) & f_{yy}(a, b) \end{vmatrix}$$

where $f_{xy}(a, b) = f_{yx}(a, b)$ by Theorem 13.3.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



Figure 13.70

EXAMPLE 3 Using the Second Partials Test

Find the relative extrema of $f(x, y) = -x^3 + 4xy - 2y^2 + 1$.

Solution Begin by finding the critical points of f. Because

$$f_x(x, y) = -3x^2 + 4y \quad \text{and} \quad f_y(x, y) = 4x - 4y$$

exist for all x and y, the only critical points are those for which both first partial derivatives are 0. To locate these points, set $f_x(x, y)$ and $f_y(x, y)$ equal to 0 to obtain

$$-3x^2 + 4y = 0 \quad \text{and} \quad 4x - 4y = 0.$$

From the second equation, you know that $x = y$. Substituting for x in the first equation and solving for y yields two solutions.

$$-3y^2 + 4y = 0 \quad \Rightarrow \quad y(-3y + 4) = 0 \quad \Rightarrow \quad y = 0 \quad \text{and} \quad y = \frac{4}{3}$$

So, with $x = y$, the critical points are $(0, 0)$ and $\left(\frac{4}{3}, \frac{4}{3}\right)$. The second partials are

$$f_{xx}(x, y) = -6x, \quad f_{yy}(x, y) = -4, \quad \text{and} \quad f_{xy}(x, y) = 4.$$

For the critical point $(0, 0)$, it follows that

$$d = f_{xx}(0, 0)f_{yy}(0, 0) - [f_{xy}(0, 0)]^2 = 0 - 16 < 0$$

and, by the Second Partials Test, you can conclude that $(0, 0, 1)$ is a saddle point of f. Furthermore, for the critical point $\left(\frac{4}{3}, \frac{4}{3}\right)$,

$$d = f_{xx}\left(\frac{4}{3}, \frac{4}{3}\right)f_{yy}\left(\frac{4}{3}, \frac{4}{3}\right) - \left[f_{xy}\left(\frac{4}{3}, \frac{4}{3}\right)\right]^2 = -8(-4) - 16 = 16 > 0$$

and because $f_{xx}\left(\frac{4}{3}, \frac{4}{3}\right) = -8 < 0$, you can conclude that f has a relative maximum at $\left(\frac{4}{3}, \frac{4}{3}\right)$, as shown in Figure 13.70. ■

The Second Partials Test can fail to find relative extrema in two ways. If either of the first partial derivatives does not exist, you cannot use the test. Also, if

$$d = f_{xx}(a, b)f_{yy}(a, b) - [f_{xy}(a, b)]^2 = 0$$

the test fails. In such cases, you can try a sketch or some other approach, as demonstrated in the next example.

EXAMPLE 4 Failure of the Second Partials Test

Find the relative extrema of $f(x, y) = x^2y^2$.

Solution Because $f_x(x, y) = 2xy^2$ and $f_y(x, y) = 2x^2y$, you know that both partial derivatives are 0 when $x = 0$ or $y = 0$. That is, every point along the x- or y-axis is a critical point. Moreover, because

$$f_{xx}(x, y) = 2y^2, \quad f_{yy}(x, y) = 2x^2, \quad \text{and} \quad f_{xy}(x, y) = 4xy$$

you know that

$$\begin{aligned} d &= f_{xx}(x, y)f_{yy}(x, y) - [f_{xy}(x, y)]^2 \\ &= 4x^2y^2 - 16x^2y^2 \\ &= -12x^2y^2 \end{aligned}$$

which is 0 when either $x = 0$ or $y = 0$. So, the Second Partials Test fails. However, because $f(x, y) = 0$ for every point along the x- or y-axis and $f(x, y) = x^2y^2 > 0$ for all other points, you can conclude that each of these critical points yields an absolute minimum, as shown in Figure 13.71. ■



Figure 13.71

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Absolute extrema of a function can occur in two ways. First, some relative extrema also happen to be absolute extrema. For instance, in Example 1, $f(-2, 3)$ is an absolute minimum of the function. (On the other hand, the relative maximum found in Example 3 is not an absolute maximum of the function.) Second, absolute extrema can occur at a boundary point of the domain. This is illustrated in Example 5.

EXAMPLE 5 Finding Absolute Extrema

Find the absolute extrema of the function

$$f(x, y) = \sin xy$$

on the closed region given by

$$0 \le x \le \pi \quad \text{and} \quad 0 \le y \le 1.$$

Solution From the partial derivatives

$$f_x(x, y) = y \cos xy \quad \text{and} \quad f_y(x, y) = x \cos xy$$

you can determine that each point lying on the hyperbola $xy = \pi/2$ is a critical point. These points each yield the value

$$f(x, y) = \sin \frac{\pi}{2} = 1$$

which you know is the absolute maximum, as shown in Figure 13.72. The only other critical point of f *lying in the given region* is $(0, 0)$. It yields an absolute minimum of 0, because

$$0 \le xy \le \pi$$

implies that

$$0 \le \sin xy \le 1.$$

To locate other absolute extrema, you should consider the four boundaries of the region formed by taking traces with the vertical planes $x = 0$, $x = \pi$, $y = 0$, and $y = 1$. In doing this, you will find that $\sin xy = 0$ at all points on the x-axis, at all points on the y-axis, and at the point $(\pi, 1)$. Each of these points yields an absolute minimum for the surface, as shown in Figure 13.72.



Figure 13.72

The concepts of relative extrema and critical points can be extended to functions of three or more variables. When all first partial derivatives of

$$w = f(x_1, x_2, x_3, \ldots, x_n)$$

exist, it can be shown that a relative maximum or minimum can occur at $(x_1, x_2, x_3, \ldots, x_n)$ only when every first partial derivative is 0 at that point. This means that the critical points are obtained by solving the following system of equations.

$$\begin{aligned} f_{x_1}(x_1, x_2, x_3, \ldots, x_n) &= 0 \\ f_{x_2}(x_1, x_2, x_3, \ldots, x_n) &= 0 \\ &\vdots \\ f_{x_n}(x_1, x_2, x_3, \ldots, x_n) &= 0 \end{aligned}$$

The extension of Theorem 13.17 to three or more variables is also possible, although you will not study such an extension in this text.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

13.8 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. For a function of two variables, describe (a) relative minimum, (b) relative maximum, (c) critical point, and (d) saddle point.
2. Under what condition does the Second Partials Test fail? Explain why the test fails under this condition.

Finding Relative Extrema **In Exercises 3–8, identify any extrema of the function by recognizing its given form or its form after completing the square. Verify your results by using the partial derivatives to locate any critical points and test for relative extrema.**

3. $g(x, y) = (x - 1)^2 + (y - 3)^2$
4. $g(x, y) = 5 - (x - 6)^2 - (y + 2)^2$
5. $f(x, y) = \sqrt{x^2 + y^2 + 1}$
6. $f(x, y) = \sqrt{49 - (x - 2)^2 - y^2}$
7. $f(x, y) = x^2 + y^2 + 2x - 6y + 6$
8. $f(x, y) = -x^2 - y^2 + 10x + 12y - 64$

Using the Second Partials Test **In Exercises 9–24, find all relative extrema and saddle points of the function. Use the Second Partials Test where applicable.**

9. $f(x, y) = x^2 + y^2 + 8x - 12y - 3$
10. $g(x, y) = x^2 - y^2 - x - y$
11. $f(x, y) = -2x^4y^4$
12. $f(x, y) = \frac{1}{2}xy$
13. $f(x, y) = -3x^2 - 2y^2 + 3x - 4y + 5$
14. $h(x, y) = x^2 - 3xy - y^2$
15. $f(x, y) = 7x^2 + 2y^2 - 7x + 16y - 13$
16. $f(x, y) = x^5 + y^5$
17. $z = x^2 + xy + \frac{1}{2}y^2 - 2x + y$
18. $z = -5x^2 + 4xy - y^2 + 16x + 10$
19. $f(x, y) = -4(x^2 + y^2 + 81)^{1/4}$
20. $h(x, y) = (x^2 + y^2)^{1/3} + 2$
21. $f(x, y) = x^2 - xy - y^2 - 3x - y$



22. $f(x, y) = 2xy - \frac{1}{2}(x^4 + y^4) + 1$



23. $z = e^{-x} \sin y$



24. $z = \left(\frac{1}{2} - x^2 + y^2\right)e^{1-x^2-y^2}$



Finding Relative Extrema and Saddle Points Using Technology **In Exercises 25–28, use a graphing utility to graph the surface and locate any relative extrema and saddle points.**

25. $z = \dfrac{-4x}{x^2 + y^2 + 1}$
26. $z = \cos x + \sin y, \quad -\pi/2 < x < \pi/2, \quad -\pi < y < \pi$
27. $z = (x^2 + 4y^2)e^{1-x^2-y^2}$
28. $z = e^{xy}$

Finding Relative Extrema **In Exercises 29 and 30, examine the function for extrema without using the derivative tests, and use a graphing utility to graph the surface and verify your answers. (*Hint:* By observation, determine whether it is possible for z to be negative. When is z equal to 0?)**

29. $z = \dfrac{(x - y)^4}{x^2 + y^2}$
30. $z = \dfrac{(x^2 - y^2)^2}{x^2 + y^2}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Think About It **In Exercises 31–34, determine whether there is a relative maximum, a relative minimum, a saddle point, or insufficient information to determine the nature of the function $f(x, y)$ at the critical point (x_0, y_0).**

31. $f_{xx}(x_0, y_0) = 9, \quad f_{yy}(x_0, y_0) = 4, \quad f_{xy}(x_0, y_0) = 6$

32. $f_{xx}(x_0, y_0) = -3, \quad f_{yy}(x_0, y_0) = -8, \quad f_{xy}(x_0, y_0) = 2$

33. $f_{xx}(x_0, y_0) = -9, \quad f_{yy}(x_0, y_0) = 6, \quad f_{xy}(x_0, y_0) = 10$

34. $f_{xx}(x_0, y_0) = 25, \quad f_{yy}(x_0, y_0) = 8, \quad f_{xy}(x_0, y_0) = 10$

Finding Relative Extrema and Saddle Points **In Exercises 35–38, (a) find the critical points, (b) test for relative extrema, (c) list the critical points for which the Second Partials Test fails, and (d) use a graphing utility to graph the function, labeling any extrema and saddle points.**

35. $f(x, y) = x^3 + y^3$

36. $f(x, y) = x^3 + y^3 - 6x^2 + 9x^2 + 12x + 27y + 19$

37. $f(x, y) = (x - 1)^2(y + 4)^2$

38. $f(x, y) = x^{2/3} + y^{2/3}$

Finding Absolute Extrema **In Exercises 39–46, find the absolute extrema of the function over the region R. (In each case, R contains the boundaries.) Use a graphing utility to confirm your results.**

39. $f(x, y) = x^2 - 4xy + 5$

$R = \{(x, y): 1 \le x \le 4, 0 \le y \le 2\}$

40. $f(x, y) = x^2 + xy$

$R = \{(x, y): |x| \le 2, |y| \le 1\}$

41. $f(x, y) = 12 - 3x - 2y$

R: The triangular region in the xy-plane with vertices $(2, 0)$, $(0, 1)$, and $(1, 2)$

42. $f(x, y) = (2x - y)^2$

R: The triangular region in the xy-plane with vertices $(2, 0)$, $(0, 1)$, and $(1, 2)$

43. $f(x, y) = 3x^2 + 2y^2 - 4y$

R: The region in the xy-plane bounded by the graphs of $y = x^2$ and $y = 4$

44. $f(x, y) = 2x - 2xy + y^2$

R: The region in the xy-plane bounded by the graphs of $y = x^2$ and $y = 1$

45. $f(x, y) = x^2 + 2xy + y^2$

$R = \{(x, y): |x| \le 2, |y| \le 1\}$

46. $f(x, y) = \dfrac{4xy}{(x^2 + 1)(y^2 + 1)}$

$R = \{(x, y): 0 \le x \le 1, 0 \le y \le 1\}$

Examining a Function **In Exercises 47 and 48, find the critical points of the function and, from the form of the function, determine whether a relative maximum or a relative minimum occurs at each point.**

47. $f(x, y, z) = x^2 + (y - 3)^2 + (z + 1)^2$

48. $f(x, y, z) = 9 - [x(y - 1)(z + 2)]^2$

Exploring Concepts

49. A function f has continuous second partial derivatives on an open region containing the critical point $(3, 7)$. The function has a minimum at $(3, 7)$, and $d > 0$ for the Second Partials Test. Determine the interval for $f_{xy}(3, 7)$ when $f_{xx}(3, 7) = 2$ and $f_{yy}(3, 7) = 8$.

50. A function f has continuous second partial derivatives on an open region containing the critical point (a, b). What is implied when $f_{xx}(a, b)$ and $f_{yy}(a, b)$ have opposite signs? Explain.

In Exercises 51 and 52, sketch the graph of an arbitrary function f satisfying the given conditions. State whether the function has any extrema or saddle points. (There are many correct answers.)

51. All of the first and second partial derivatives of f are 0.

52. $f_x(x, y) > 0$ and $f_y(x, y) < 0$ for all (x, y).

53. Comparing Functions Consider the functions

$f(x, y) = x^2 - y^2$ and $g(x, y) = x^2 + y^2$.

(a) Show that both functions have a critical point at $(0, 0)$.

(b) Explain how f and g behave differently at this critical point.

54. HOW DO YOU SEE IT? Determine whether each labeled point is an absolute maximum, an absolute minimum, or neither.



True or False? **In Exercises 55–58, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

55. If f has a relative maximum at (x_0, y_0, z_0), then

$f_x(x_0, y_0) = f_y(x_0, y_0) = 0.$

56. If

$f_x(x_0, y_0) = f_y(x_0, y_0) = 0$

then f has a relative extremum at (x_0, y_0, z_0).

57. Between any two relative minima of f, there must be at least one relative maximum of f.

58. If f is continuous for all x and y and has two relative minima, then f must have at least one relative maximum.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

13.9 Applications of Extrema

GO DIGITAL

- Solve optimization problems involving functions of several variables.
- Use the method of least squares.

Applied Optimization Problems

In this section, you will study a few of the many applications of extrema of functions of two (or more) variables.

EXAMPLE 1 Finding Maximum Volume

See LarsonCalculus.com for an interactive version of this type of example.

A rectangular box is resting on the xy-plane with one vertex at the origin. The opposite vertex lies in the plane $6x + 4y + 3z = 24$, as shown in Figure 13.73. Find the maximum volume of the box.



Figure 13.73

Solution Let x, y, and z represent the length, width, and height of the box. Because one vertex of the box lies in the plane $6x + 4y + 3z = 24$, you know that $z = \frac{1}{3}(24 - 6x - 4y)$. So, you can write the volume xyz of the box as a function of two variables.

$$V(x, y) = (x)(y)\left[\frac{1}{3}(24 - 6x - 4y)\right] = \frac{1}{3}(24xy - 6x^2y - 4xy^2)$$

Next, find the first partial derivatives of V.

$$V_x(x, y) = \frac{1}{3}(24y - 12xy - 4y^2) = \frac{y}{3}(24 - 12x - 4y)$$

and

$$V_y(x, y) = \frac{1}{3}(24x - 6x^2 - 8xy) = \frac{x}{3}(24 - 6x - 8y)$$

Note that the first partial derivatives are defined for all x and y. So, by setting $V_x(x, y)$ and $V_y(x, y)$ equal to 0 and solving the equations $\frac{1}{3}y(24 - 12x - 4y) = 0$ and $\frac{1}{3}x(24 - 6x - 8y) = 0$, you obtain the critical points $(0, 0)$, $(4, 0)$, $(0, 6)$, and $\left(\frac{4}{3}, 2\right)$. At $(0, 0)$, $(4, 0)$, and $(0, 6)$, the volume is 0, so these points do not yield a maximum volume. At the point $\left(\frac{4}{3}, 2\right)$, you can apply the Second Partials Test.

$$V_{xx}(x, y) = -4y, \quad V_{yy}(x, y) = \frac{-8x}{3}, \quad V_{xy}(x, y) = \frac{1}{3}(24 - 12x - 8y)$$

Because

$$V_{xx}\left(\frac{4}{3}, 2\right)V_{yy}\left(\frac{4}{3}, 2\right) - \left[V_{xy}\left(\frac{4}{3}, 2\right)\right]^2 = (-8)\left(-\frac{32}{9}\right) - \left(-\frac{8}{3}\right)^2 = \frac{64}{3} > 0$$

and

$$V_{xx}\left(\frac{4}{3}, 2\right) = -8 < 0$$

you can conclude from the Second Partials Test that the maximum volume is

$$V\left(\frac{4}{3}, 2\right) = \frac{1}{3}\left[24\left(\frac{4}{3}\right)(2) - 6\left(\frac{4}{3}\right)^2(2) - 4\left(\frac{4}{3}\right)(2^2)\right] = \frac{64}{9} \text{ cubic units.}$$

Note that the volume is 0 at the boundary points of the triangular domain of V. ■

REMARK In many applied problems, the domain of the function to be optimized is a closed bounded region. To find minimum or maximum points, you must not only test critical points, but also consider the values of the function at points on the boundary.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Applications of extrema in economics and business often involve more than one independent variable. For instance, a company may produce several models of one type of product. The price per unit and profit per unit are usually different for each model. Moreover, the demand for each model is often a function of the prices of the other models (as well as its own price). The next example illustrates an application involving two products.

EXAMPLE 2 Finding the Maximum Profit

A manufacturer determines that the profit P (in dollars) obtained by producing and selling x units of Product 1 and y units of Product 2 is approximated by the model

$$P(x, y) = 8x + 10y - (0.001)(x^2 + xy + y^2) - 10{,}000.$$

Find the production level that produces a maximum profit. What is the maximum profit?

Solution The first partial derivatives of the profit function are

$$P_x(x, y) = 8 - (0.001)(2x + y)$$

and

$$P_y(x, y) = 10 - (0.001)(x + 2y).$$

By setting these partial derivatives equal to 0, you obtain the following system of equations.

$$\begin{aligned} 8 - (0.001)(2x + y) &= 0 \\ 10 - (0.001)(x + 2y) &= 0 \end{aligned}$$

After simplifying, this system of linear equations can be written as

$$\begin{aligned} 2x + y &= 8000 \\ x + 2y &= 10{,}000. \end{aligned}$$

Solving this system produces $x = 2000$ and $y = 4000$. The second partial derivatives of P are

$$\begin{aligned} P_{xx}(2000, 4000) &= -0.002 \\ P_{yy}(2000, 4000) &= -0.002 \end{aligned}$$

and

$$P_{xy}(2000, 4000) = -0.001.$$

Because $P_{xx} < 0$ and

$$P_{xx}(2000, 4000)P_{yy}(2000, 4000) - [P_{xy}(2000, 4000)]^2 = (-0.002)^2 - (-0.001)^2$$

is greater than 0, you can conclude that the production level of $x = 2000$ units and $y = 4000$ units yields a *maximum* profit. The maximum profit is

$$\begin{aligned} &P(2000, 4000) \\ &\quad = 8(2000) + 10(4000) - (0.001)[2000^2 + 2000(4000) + 4000^2] - 10{,}000 \\ &\quad = \$18{,}000. \end{aligned}$$

In Example 2, it was assumed that the manufacturing plant is able to produce the required number of units to yield a maximum profit. In actual practice, the production would be bounded by physical constraints. You will study such constrained optimization problems in the next section.

FOR FURTHER INFORMATION For more information on the use of mathematics in economics, see the article "Mathematical Methods of Economics" by Joel Franklin in *The American Mathematical Monthly*. To view this article, go to *MathArticles.com*.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The Method of Least Squares

Many of the examples in this text have involved **mathematical models.** For instance, Example 2 involves a quadratic model for profit. There are several ways to develop such models; one is called the **method of least squares.**

In constructing a model to represent a particular phenomenon, the goals are simplicity and accuracy. Of course, these goals often conflict. For instance, a simple linear model for the points in Figure 13.74 is

$$y = 1.9x - 5.$$ Linear model

Figure 13.75, however, shows that by choosing the slightly more complicated quadratic model

$$y = 0.20x^2 - 0.7x + 1$$ Quadratic model

you can achieve greater accuracy.



Figure 13.74



Figure 13.75

As a measure of how well the model $y = f(x)$ fits the collection of points

$$\{(x_1, y_1), (x_2, y_2), (x_3, y_3), \ldots, (x_n, y_n)\}$$

add the squares of the differences between the actual y-values and the values given by the model to obtain the **sum of the squared errors**

$$S = \sum_{i=1}^{n} [f(x_i) - y_i]^2.$$ Sum of the squared errors

Graphically, S can be interpreted as the sum of the squares of the vertical distances between the graph of f and the given points in the plane, as shown in Figure 13.76. If the model is a perfect fit, then $S = 0$. However, when a perfect fit is not feasible, you can use a model that minimizes S. For instance, the sum of the squared errors for the linear model in Figure 13.74 is

$$S = 17.6.$$

Statisticians call the *linear model* that minimizes S the **least squares regression line.** The proof that this line actually minimizes S involves the minimizing of a function of two variables.



Sum of the squared errors:
$S = d_1^2 + d_2^2 + d_3^2$

Figure 13.76

REMARK A method for finding the least squares regression quadratic for a collection of data is described in Exercise 31.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

ADRIEN-MARIE LEGENDRE (1752–1833)

The method of least squares was introduced by the French mathematician Adrien-Marie Legendre. Legendre is best known for his work in geometry. In fact, his text *Elements of Geometry* was so popular in the United States that it continued to be used for 33 editions, spanning a period of more than 100 years. *See LarsonCalculus.com to read more of this biography.*

THEOREM 13.18 Least Squares Regression Line

The **least squares regression line** for the points

$$\{(x_1, y_1), (x_2, y_2), \ldots, (x_n, y_n)\}$$

is given by $f(x) = ax + b$, where

$$a = \frac{n\sum_{i=1}^{n} x_i y_i - \sum_{i=1}^{n} x_i \sum_{i=1}^{n} y_i}{n\sum_{i=1}^{n} x_i^2 - \left(\sum_{i=1}^{n} x_i\right)^2} \quad \text{and} \quad b = \frac{1}{n}\left(\sum_{i=1}^{n} y_i - a\sum_{i=1}^{n} x_i\right).$$

Proof Let $S(a, b)$ represent the sum of the squared errors for the model

$$f(x) = ax + b$$

and the given set of points. That is,

$$\begin{aligned} S(a, b) &= \sum_{i=1}^{n} [f(x_i) - y_i]^2 \\ &= \sum_{i=1}^{n} (ax_i + b - y_i)^2 \end{aligned}$$

where the points (x_i, y_i) represent constants. Because S is a function of a and b, you can use the methods discussed in the preceding section to find the minimum value of S. Specifically, the first partial derivatives of S are

$$\begin{aligned} S_a(a, b) &= \sum_{i=1}^{n} 2x_i(ax_i + b - y_i) \\ &= 2a\sum_{i=1}^{n} x_i^2 + 2b\sum_{i=1}^{n} x_i - 2\sum_{i=1}^{n} x_i y_i \end{aligned}$$

and

$$\begin{aligned} S_b(a, b) &= \sum_{i=1}^{n} 2(ax_i + b - y_i) \\ &= 2a\sum_{i=1}^{n} x_i + 2nb - 2\sum_{i=1}^{n} y_i. \end{aligned}$$

By setting these two partial derivatives equal to 0, you obtain the values of a and b that are listed in the theorem. It is left to you to apply the Second Partials Test (see Exercise 41) to verify that these values of a and b yield a minimum. ■

If the x-values are symmetrically spaced about the y-axis, then $\Sigma x_i = 0$ and the formulas for a and b simplify to

$$a = \frac{\sum_{i=1}^{n} x_i y_i}{\sum_{i=1}^{n} x_i^2}$$

and

$$b = \frac{1}{n}\sum_{i=1}^{n} y_i.$$

This simplification is often possible with a translation of the x-values. For instance, given that the x-values in a data set are 9, 10, 11, 12, and 13, you could let 0 represent 11. So, after the translation, the values are -2, -1, 0, 1, and 2.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 3 Finding the Least Squares Regression Line

Find the least squares regression line for the points

$$(-3, 0), \quad (-1, 1), \quad (0, 2), \quad \text{and} \quad (2, 3).$$

Solution The table shows the calculations involved in finding the least squares regression line using $n = 4$.

x	y	xy	x^2
-3	0	0	9
-1	1	-1	1
0	2	0	0
2	3	6	4
$\sum_{i=1}^{n} x_i = -2$	$\sum_{i=1}^{n} y_i = 6$	$\sum_{i=1}^{n} x_i y_i = 5$	$\sum_{i=1}^{n} x_i^2 = 14$

Applying Theorem 13.18 produces

$$\begin{aligned} a &= \frac{n\sum_{i=1}^{n} x_i y_i - \sum_{i=1}^{n} x_i \sum_{i=1}^{n} y_i}{n\sum_{i=1}^{n} x_i^2 - \left(\sum_{i=1}^{n} x_i\right)^2} \\ &= \frac{4(5) - (-2)(6)}{4(14) - (-2)^2} \\ &= \frac{8}{13} \end{aligned}$$

and

$$\begin{aligned} b &= \frac{1}{n}\left(\sum_{i=1}^{n} y_i - a\sum_{i=1}^{n} x_i\right) \\ &= \frac{1}{4}\left[6 - \frac{8}{13}(-2)\right] \\ &= \frac{47}{26}. \end{aligned}$$

TECHNOLOGY

Many calculators have "built-in" least squares regression programs. If your calculator has such a program, use it to duplicate the results of Example 3.

The least squares regression line is

$$f(x) = \frac{8}{13}x + \frac{47}{26}$$

as shown in Figure 13.77.



Least squares regression line

Figure 13.77

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

13.9 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. State the problem-solving strategy for applied minimum and maximum problems.
2. Describe the method of least squares for finding mathematical models.

Finding Minimum Distance **In Exercises 3 and 4, find the minimum distance from the point to the plane $x - y + z = 3$. (*Hint:* To simplify the computations, minimize the square of the distance.)**

3. $(1, -3, 2)$
4. $(4, 0, 6)$

Finding Minimum Distance **In Exercises 5 and 6, find the minimum distance from the point to the surface $z = \sqrt{1 - 2x - 2y}$. (*Hint:* To simplify the computations, minimize the square of the distance.)**

5. $(-2, -2, 0)$
6. $(-4, 1, 0)$

Finding Positive Numbers **In Exercises 7–10, find three positive integers x, y, and z that satisfy the given conditions.**

7. The product is 27, and the sum is a minimum.
8. The sum is 32, and $P = xy^2z$ is a maximum.
9. The sum is 30, and the sum of the squares is a minimum.
10. The product is 1, and the sum of the squares is a minimum.

11. **Cost** A home improvement contractor is painting the walls and ceiling of a rectangular room. The volume of the room is 668.25 cubic feet. The cost of wall paint is \$0.06 per square foot and the cost of ceiling paint is \$0.11 per square foot. Find the room dimensions that result in a minimum cost for the paint. What is the minimum cost for the paint?
12. **Maximum Volume** The material for constructing the base of an open box costs 1.5 times as much per unit area as the material for constructing the sides. For a fixed amount of money C, find the dimensions of the box of largest volume that can be made.
13. **Volume and Surface Area** Show that a rectangular box of given volume and minimum surface area is a cube.
14. **Maximum Volume** Show that the rectangular box of maximum volume inscribed in a sphere of radius r is a cube.
15. **Maximum Revenue** A company manufactures running shoes and basketball shoes. The total revenue (in thousands of dollars) from x_1 units of running shoes and x_2 units of basketball shoes is

$$R = -5x_1^2 - 8x_2^2 - 2x_1x_2 + 42x_1 + 102x_2$$

where x_1 and x_2 are in thousands of units. Find x_1 and x_2 so as to maximize the revenue.

16. **Maximum Profit** A corporation manufactures candles at two locations. The cost of producing x_1 units at location 1 is $C_1 = 0.02x_1^2 + 4x_1 + 500$ and the cost of producing x_2 units at location 2 is $C_2 = 0.05x_2^2 + 4x_2 + 275$. The candles sell for \$15 per unit. Find the quantity that should be produced at each location to maximize the profit $P = 15(x_1 + x_2) - C_1 - C_2$.
17. **Hardy-Weinberg Law** Common blood types are determined genetically by three alleles A, B, and O. (An allele is any of a group of possible mutational forms of a gene.) A person whose blood type is AA, BB, or OO is homozygous. A person whose blood type is AB, AO, or BO is heterozygous. The Hardy-Weinberg Law states that the proportion P of heterozygous individuals in any given population is

$$P(p, q, r) = 2pq + 2pr + 2qr$$

where p represents the percent of allele A in the population, q represents the percent of allele B in the population, and r represents the percent of allele O in the population. Use the fact that

$$p + q + r = 1$$

to show that the maximum proportion of heterozygous individuals in any population is $\frac{2}{3}$.

18. **Shannon Diversity Index** One way to measure species diversity is to use the Shannon diversity index H. If a habitat consists of three species, A, B, and C, then its Shannon diversity index is

$$H = -x \ln x - y \ln y - z \ln z$$

where x is the percent of species A in the habitat, y is the percent of species B in the habitat, and z is the percent of species C in the habitat. Use the fact that

$$x + y + z = 1$$

to show that the maximum value of H occurs when $x = y = z = \frac{1}{3}$. What is the maximum value of H?

19. **Minimum Cost** A water line is to be built from point P to point S and must pass through regions where construction costs differ (see figure). The cost per kilometer (in dollars) is $3k$ from P to Q, $2k$ from Q to R, and k from R to S. Find x and y such that the total cost C will be minimized.



Figure for 19



Figure for 20

20. **Area** A trough with trapezoidal cross sections is formed by turning up the edges of a 30-inch-wide sheet of aluminum (see figure). Find the cross section of maximum area.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding the Least Squares Regression Line **In Exercises 21–24, (a) find the least squares regression line and (b) calculate S, the sum of the squared errors. Use the regression capabilities of a graphing utility to verify your results.**

21.



22.



23.



24.



Finding the Least Squares Regression Line **In Exercises 25–28, find the least squares regression line for the points. Use the regression capabilities of a graphing utility to verify your results. Use the graphing utility to plot the points and graph the regression line.**

25. $(0, 0),\ (1, 1),\ (3, 6),\ (4, 8),\ (5, 9)$

26. $(0, 4),\ (4, 1),\ (7, -3)$

27. $(0, 6),\ (4, 3),\ (5, 0),\ (8, -4),\ (10, -5)$

28. $(6, 4),\ (1, 2),\ (3, 3),\ (8, 6),\ (11, 8),\ (13, 8)$

29. Modeling Data The table shows the gross tax collections (in billions of dollars) by the Internal Revenue Service for internal revenue x and income taxes y for selected years. *(Source: U.S. Internal Revenue Service)*

Year	1985	1990	1995	2000
Internal Revenue, x	743	1056	1376	2097
Income Taxes, y	474	650	850	1373

Year	2005	2010	2015	2020
Internal Revenue, x	2269	2345	3303	3493
Income Taxes, y	1415	1454	2183	2135

(a) Use the regression capabilities of a graphing utility to find the least squares regression line for the data.

(b) Use the model to estimate the income taxes collected when the internal revenue collected is \$1300 billion.

(c) In 1980, the internal revenue collected was \$519 billion and the income taxes collected was \$360 billion. Describe how including this information would affect the model.

30. Modeling Data The ages x (in years) and systolic blood pressures y (in mmHg) of seven men are shown in the table.

Age, x	16	25	39	45	49	64	70
Systolic Blood Pressure, y	109	122	150	165	159	183	199

(a) Use the regression capabilities of a graphing utility to find the least squares regression line for the data.

(b) Use a graphing utility to plot the data and graph the model.

(c) Use the model to approximate the change in systolic blood pressure for each one-year increase in age.

(d) A 30-year-old man has a systolic blood pressure of 180 mmHg. Describe how including this information would affect the model.

Exploring Concepts

31. Find a system of equations whose solution yields the coefficients a, b, and c for the least squares regression quadratic

$$y = ax^2 + bx + c$$

for the points $(x_1, y_1), (x_2, y_2), \ldots, (x_n, y_n)$ by minimizing the sum

$$S(a, b, c) = \sum_{i=1}^{n} (y_i - ax_i^2 - bx_i - c)^2.$$

32. HOW DO YOU SEE IT? Match the regression equation with the appropriate graph. Explain your reasoning. (Note that the x- and y-axes are broken.)

(a) $y = 0.22x - 7.5$

(b) $y = -0.35x + 11.5$

(c) $y = 0.09x + 19.8$

(d) $y = -1.29x + 89.8$

(i)



(ii)



(iii)



(iv)



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding the Least Squares Regression Quadratic **In Exercises 33–36, use the result of Exercise 31 to find the least squares regression quadratic for the points. Use the regression capabilities of a graphing utility to verify your results. Use the graphing utility to plot the points and graph the least squares regression quadratic.**

33. $(-2, 0),\ (-1, 0),\ (0, 1),\ (1, 2),\ (2, 5)$

34. $(-4, 5),\ (-2, 6),\ (2, 6),\ (4, 2)$

35. $(0, 0),\ (2, 2),\ (3, 6),\ (4, 12)$

36. $(0, 10),\ (1, 9),\ (2, 6),\ (3, 0)$

37. Modeling Data After a new turbocharger for an automobile engine was developed, the following experimental data were obtained for speed y in miles per hour at two-second time intervals x.

Time, x	0	2	4	6	8	10
Speed, y	0	15	30	50	65	70

(a) Use the result of Exercise 31 to find the least squares regression quadratic for the data.

(b) Use a graphing utility to plot the points and graph the model.

38. Modeling Data The table shows the total numbers of veterans y (in millions) with a service-connected disability for 2015 through 2019. Let $x = 5$ represent the year 2015. *(Source: U.S. Department of Veterans Affairs)*

Year, x	2015	2016	2017	2018	2019
Veterans, y	4.2	4.4	4.6	4.7	4.9

(a) Use the regression capabilities of a graphing utility to find the least squares regression line for the data.

(b) Use the regression capabilities of a graphing utility to find the least squares regression quadratic for the data.

(c) Use a graphing utility to plot the data and graph the models.

(d) Use both models to forecast the total number of veterans with a service-connected disability for the year 2030. How do the two models differ as you extrapolate into the future?

39. Modeling Data A meteorologist measures the atmospheric pressure P (in kilograms per square meter) at altitude h (in kilometers). The data are shown below.

Altitude, h	0	5	10	15	20
Pressure, P	10,332	5583	2376	1240	517

(a) Use the regression capabilities of a graphing utility to find the least squares regression line for the points $(h, \ln P)$.

(b) The result in part (a) is an equation of the form $\ln P = ah + b$. Write this logarithmic form in exponential form.

(c) Use a graphing utility to plot the original data, and graph the exponential model in part (b).

40. Modeling Data The endpoints of the interval over which distinct vision is possible are called the *near point* and *far point* of the eye. With increasing age, these points normally change. The table shows the approximate near points y (in inches) for various ages x (in years). *(Source: Ophthalmology & Physiological Optics)*

Age, x	16	32	44	50	60
Near Point, y	3.0	4.7	9.8	19.7	39.4

(a) Find a rational model for the data by taking the reciprocals of the near points to generate the points $(x, 1/y)$. Use the regression capabilities of a graphing utility to find the least squares regression line for the revised data. The resulting line has the form $1/y = ax + b$. Solve for y.

(b) Use a graphing utility to plot the data and graph the model.

(c) Do you think the model can be used to predict the near point for a person who is 70 years old? Explain.

41. Using the Second Partials Test Use the Second Partials Test to verify that the formulas for a and b given in Theorem 13.18 yield a minimum.

$$\left[\textit{Hint: } \text{Use the fact that } n\sum_{i=1}^{n} x_i^2 \geq \left(\sum_{i=1}^{n} x_i\right)^2.\right]$$

SECTION PROJECT

Building a Pipeline

An oil company wishes to construct a pipeline from its offshore facility A to its refinery B. The offshore facility is 2 miles from shore, and the refinery is 1 mile inland. Furthermore, A and B are 5 miles apart, as shown in the figure.



The cost of building the pipeline is \$3 million per mile in the water and \$4 million per mile on land. So, the cost of the pipeline depends on the location of point P, where it meets the shore. What would be the most economical route of the pipeline?

Imagine that you are to write a report to the oil company about this problem. Let x be the distance shown in the figure. Determine the cost of building the pipeline from A to P and the cost of building it from P to B. Analyze some sample pipeline routes and their corresponding costs. For instance, what is the cost of the most direct route? Then use calculus to determine the route of the pipeline that minimizes the cost. Explain all steps of your development and include any relevant graphs.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

13.10 Lagrange Multipliers

GO DIGITAL

- **Describe the Method of Lagrange Multipliers.**
- **Use Lagrange multipliers to solve constrained optimization problems.**
- **Use the Method of Lagrange Multipliers with two constraints.**

LAGRANGE MULTIPLIERS

The Method of Lagrange Multipliers is named after the French mathematician Joseph-Louis Lagrange. Lagrange first introduced the method in his famous paper on mechanics, written when he was just 19 years old.

Lagrange Multipliers

Many optimization problems have restrictions, or **constraints,** on the values that can be used to produce the optimal solution. Such constraints tend to complicate optimization problems because the optimal solution can occur at a boundary point of the domain. In this section, you will study an ingenious technique for solving such problems. It is called the **Method of Lagrange Multipliers.**

To see how this technique works, consider the problem of finding the rectangle of maximum area that can be inscribed in the ellipse

$$\frac{x^2}{3^2} + \frac{y^2}{4^2} = 1.$$

Let (x, y) be the vertex of the rectangle in the first quadrant, as shown in Figure 13.78. Because the rectangle has sides of lengths $2x$ and $2y$, its area is given by

$$f(x, y) = 4xy. \qquad \text{Objective function}$$

You want to find x and y such that $f(x, y)$ is a maximum. Your choice of (x, y) is restricted to first-quadrant points that lie on the ellipse

$$\frac{x^2}{3^2} + \frac{y^2}{4^2} = 1. \qquad \text{Constraint}$$

Now, consider the constraint equation to be a fixed level curve of

$$g(x, y) = \frac{x^2}{3^2} + \frac{y^2}{4^2}.$$

The level curves of f represent a family of hyperbolas

$$f(x, y) = 4xy = k.$$

In this family, the level curves that meet the constraint correspond to the hyperbolas that intersect the ellipse. Moreover, to maximize $f(x, y)$, you want to find the hyperbola that just barely satisfies the constraint. The level curve that does this is the one that is *tangent* to the ellipse, as shown in Figure 13.79.



Objective function: $f(x, y) = 4xy$

Figure 13.78



Constraint: $g(x, y) = \frac{x^2}{3^2} + \frac{y^2}{4^2} = 1$

Figure 13.79

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

To find the appropriate hyperbola, use the fact that two curves are tangent at a point if and only if their gradients are parallel. This means that $\nabla f(x, y)$ must be a scalar multiple of $\nabla g(x, y)$ at the point of tangency. In the context of constrained optimization problems, this scalar is denoted by λ (the lowercase Greek letter lambda).

$$\nabla f(x, y) = \lambda \nabla g(x, y)$$

The scalar λ is called a **Lagrange multiplier.** Theorem 13.19 gives the necessary conditions for the existence of such multipliers.

THEOREM 13.19 Lagrange's Theorem

Let f and g have continuous first partial derivatives such that f has an extremum at a point (x_0, y_0) on the smooth constraint curve $g(x, y) = c$. If $\nabla g(x_0, y_0) \neq \mathbf{0}$, then there is a real number λ such that

$$\nabla f(x_0, y_0) = \lambda \nabla g(x_0, y_0).$$

REMARK Using a similar argument with level surfaces and Theorem 13.14, it can be shown that Lagrange's Theorem is also true for functions of three variables.

Proof To begin, represent the smooth curve given by $g(x, y) = c$ by the vector-valued function

$$\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j}, \quad \mathbf{r}'(t) \neq \mathbf{0}$$

where x' and y' are continuous on an open interval I. Define the function h as $h(t) = f(x(t), y(t))$. Then, because $f(x_0, y_0)$ is an extreme value of f, you know that

$$h(t_0) = f(x(t_0), y(t_0)) = f(x_0, y_0)$$

is an extreme value of h. This implies that $h'(t_0) = 0$, and, by the Chain Rule,

$$\begin{aligned} h'(t_0) &= f_x(x_0, y_0)x'(t_0) + f_y(x_0, y_0)y'(t_0) \\ &= \nabla f(x_0, y_0) \cdot \mathbf{r}'(t_0) \\ &= 0. \end{aligned}$$

So, $\nabla f(x_0, y_0)$ is orthogonal to $\mathbf{r}'(t_0)$. Moreover, by Theorem 13.12, $\nabla g(x_0, y_0)$ is also orthogonal to $\mathbf{r}'(t_0)$. Consequently, the gradients $\nabla f(x_0, y_0)$ and $\nabla g(x_0, y_0)$ are parallel, and there must exist a scalar λ such that

$$\nabla f(x_0, y_0) = \lambda \nabla g(x_0, y_0).$$

The Method of Lagrange Multipliers uses Theorem 13.19 to find the extreme values of a function f subject to a constraint.

REMARK As you will see in Examples 1 and 2, the Method of Lagrange Multipliers requires solving systems of nonlinear equations. This often can require some tricky algebraic manipulation.

Method of Lagrange Multipliers

Let f and g satisfy the hypothesis of Lagrange's Theorem, and let f have a minimum or maximum subject to the constraint $g(x, y) = c$. To find the minimum or maximum of f, use these steps.

1. Simultaneously solve the equations $\nabla f(x, y) = \lambda \nabla g(x, y)$ and $g(x, y) = c$ by solving the following system of equations.

$$\begin{aligned} f_x(x, y) &= \lambda g_x(x, y) \\ f_y(x, y) &= \lambda g_y(x, y) \\ g(x, y) &= c \end{aligned}$$

2. Evaluate f at each solution point obtained in the first step. The greatest value yields the maximum of f subject to the constraint $g(x, y) = c$, and the least value yields the minimum of f subject to the constraint $g(x, y) = c$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Constrained Optimization Problems

In the problem at the beginning of this section, you wanted to maximize the area of a rectangle that is inscribed in an ellipse. Example 1 shows how to use Lagrange multipliers to solve this problem.

EXAMPLE 1 **Using a Lagrange Multiplier with One Constraint**

Find the maximum value of $f(x, y) = 4xy$, where $x > 0$ and $y > 0$, subject to the constraint $(x^2/3^2) + (y^2/4^2) = 1$.

Solution To begin, let

$$g(x, y) = \frac{x^2}{3^2} + \frac{y^2}{4^2} = 1.$$

By equating $\nabla f(x, y) = 4y\mathbf{i} + 4x\mathbf{j}$ and $\lambda \nabla g(x, y) = (2\lambda x/9)\mathbf{i} + (\lambda y/8)\mathbf{j}$, you obtain the following system of equations.

$$4y = \frac{2}{9}\lambda x \qquad f_x(x, y) = \lambda g_x(x, y)$$

$$4x = \frac{1}{8}\lambda y \qquad f_y(x, y) = \lambda g_y(x, y)$$

$$\frac{x^2}{3^2} + \frac{y^2}{4^2} = 1 \qquad \text{Constraint}$$

From the first equation, you obtain $\lambda = 18y/x$, and substitution into the second equation produces

$$4x = \frac{1}{8}\left(\frac{18y}{x}\right)y \quad \Rightarrow \quad x^2 = \frac{9}{16}y^2.$$

Substituting this value for x^2 into the third equation produces

$$\frac{1}{9}\left(\frac{9}{16}y^2\right) + \frac{1}{16}y^2 = 1 \quad \Rightarrow \quad y^2 = 8 \quad \Rightarrow \quad y = \pm 2\sqrt{2}.$$

Because $y > 0$, choose the positive value and find that

$$x^2 = \frac{9}{16}y^2$$

$$= \frac{9}{16}(8)$$

$$= \frac{9}{2}$$

$$x = \pm\frac{3}{\sqrt{2}}.$$

Because $x > 0$, choose the positive value. So, the maximum value of f is

$$f\left(\frac{3}{\sqrt{2}}, 2\sqrt{2}\right) = 4\left(\frac{3}{\sqrt{2}}\right)\left(2\sqrt{2}\right) = 24.$$

REMARK Note in Example 1 that writing the constraint as

$$\frac{x^2}{3^2} + \frac{y^2}{4^2} = 1$$

or

$$\frac{x^2}{3^2} + \frac{y^2}{4^2} - 1 = 0$$

does not affect the solution—the constant is eliminated when you form ∇g.

Example 1 can also be solved using the techniques you learned in Chapter 3. To see how, try to find the maximum value of $A = 4xy$ given that $(x^2/3^2) + (y^2/4^2) = 1$. To begin, solve the second equation for y to obtain $y = \frac{4}{3}\sqrt{9 - x^2}$. Then substitute into the first equation to obtain $A = 4x\left(\frac{4}{3}\sqrt{9 - x^2}\right)$. Finally, use the techniques of Chapter 3 to maximize A.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



For some industrial applications, a robot can cost more than the annual wages and benefits for one employee. So, manufacturers must carefully balance the amount of money spent on labor and capital.

GO DIGITAL

FOR FURTHER INFORMATION
For more information on the use of Lagrange multipliers in economics, see the article "Lagrange Multiplier Problems in Economics" by John V. Baxley and John C. Moorhouse in *The American Mathematical Monthly*. To view this article, go to *MathArticles.com*.

EXAMPLE 2 A Business Application

The Cobb-Douglas production function (see Section 13.1) for a manufacturer is given by

$$f(x, y) = 100x^{3/4}y^{1/4}$$ Objective function

where x represents the units of labor (at \$150 per unit) and y represents the units of capital (at \$250 per unit). The total cost of labor and capital is limited to \$50,000. Find the maximum production level for this manufacturer.

Solution The gradient of f is

$$\nabla f(x, y) = 75x^{-1/4}y^{1/4}\mathbf{i} + 25x^{3/4}y^{-3/4}\mathbf{j}.$$

The limit on the cost of labor and capital produces the constraint

$$g(x, y) = 150x + 250y = 50{,}000.$$ Constraint

So, $\lambda\nabla g(x, y) = 150\lambda\mathbf{i} + 250\lambda\mathbf{j}$. This gives rise to the following system of equations.

$$\begin{aligned} 75x^{-1/4}y^{1/4} &= 150\lambda && f_x(x, y) = \lambda g_x(x, y) \\ 25x^{3/4}y^{-3/4} &= 250\lambda && f_y(x, y) = \lambda g_y(x, y) \\ 150x + 250y &= 50{,}000 && \text{Constraint} \end{aligned}$$

By solving for λ in the first equation

$$\lambda = \frac{75x^{-1/4}y^{1/4}}{150} = \frac{x^{-1/4}y^{1/4}}{2}$$

and substituting into the second equation, you obtain

$$\begin{aligned} 25x^{3/4}y^{-3/4} &= 250\left(\frac{x^{-1/4}y^{1/4}}{2}\right) \\ 25x &= 125y && \text{Multiply by } x^{1/4}y^{3/4}. \\ x &= 5y. \end{aligned}$$

By substituting this value for x in the third equation, you have

$$\begin{aligned} 150(5y) + 250y &= 50{,}000 \\ 1000y &= 50{,}000 \\ y &= 50 \text{ units of capital.} \end{aligned}$$

This means that the value of x is

$$\begin{aligned} x &= 5(50) \\ &= 250 \text{ units of labor.} \end{aligned}$$

So, the maximum production level is

$$\begin{aligned} f(250, 50) &= 100(250)^{3/4}(50)^{1/4} \\ &\approx 16{,}719 \text{ units of product.} \end{aligned}$$

Economists call the Lagrange multiplier obtained in a production function the **marginal productivity of money.** For instance, in Example 2, the marginal productivity of money at $x = 250$ and $y = 50$ is

$$\lambda = \frac{x^{-1/4}y^{1/4}}{2} = \frac{(250)^{-1/4}(50)^{1/4}}{2} \approx 0.334.$$

This means that for each additional dollar spent on production, approximately 0.334 additional unit of the product can be produced.

iStock.com/RicAguiar

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 3 Lagrange Multipliers and Three Variables

See LarsonCalculus.com for an interactive version of this type of example.

Find the minimum value of

$$f(x, y, z) = 2x^2 + y^2 + 3z^2$$ Objective function

subject to the constraint $2x - 3y - 4z = 49$.

Solution Let $g(x, y, z) = 2x - 3y - 4z = 49$. Then, because

$$\nabla f(x, y, z) = 4x\mathbf{i} + 2y\mathbf{j} + 6z\mathbf{k}$$

and

$$\lambda \nabla g(x, y, z) = 2\lambda\mathbf{i} - 3\lambda\mathbf{j} - 4\lambda\mathbf{k}$$

you obtain the following system of equations.

$$\begin{aligned} 4x &= 2\lambda && f_x(x, y, z) = \lambda g_x(x, y, z) \\ 2y &= -3\lambda && f_y(x, y, z) = \lambda g_y(x, y, z) \\ 6z &= -4\lambda && f_z(x, y, z) = \lambda g_z(x, y, z) \\ 2x - 3y - 4z &= 49 && \text{Constraint} \end{aligned}$$

The solution of this system is $x = 3$, $y = -9$, and $z = -4$. So, the optimum value of f is

$$\begin{aligned} f(3, -9, -4) &= 2(3)^2 + (-9)^2 + 3(-4)^2 \\ &= 147. \end{aligned}$$

From the original function and constraint, it is clear that $f(x, y, z)$ has no maximum. So, the optimum value of f determined above is a minimum. ■



Figure 13.80

A graphical interpretation of constrained optimization problems in two variables was given at the beginning of this section. In three variables, the interpretation is similar, except that level surfaces are used instead of level curves. For instance, in Example 3, the level surfaces of f are ellipsoids centered at the origin, and the constraint

$$2x - 3y - 4z = 49$$

is a plane. The minimum value of f is represented by the ellipsoid that is tangent to the constraint plane, as shown in Figure 13.80.

EXAMPLE 4 Optimization Inside a Region

Find the extreme values of

$$f(x, y) = x^2 + 2y^2 - 2x + 3$$ Objective function

subject to the constraint $x^2 + y^2 \leq 10$.

Solution To solve this problem, you can break the constraint into two cases.

a. For points *on the circle* $x^2 + y^2 = 10$, you can use Lagrange multipliers to find that the maximum value of $f(x, y)$ is 24—this value occurs at $(-1, 3)$ and at $(-1, -3)$. In a similar way, you can determine that the minimum value of $f(x, y)$ is approximately 6.675—this value occurs at $\left(\sqrt{10}, 0\right)$.

b. For points *inside the circle,* you can use the techniques discussed in Section 13.8 to conclude that the function has a relative minimum of 2 at the point $(1, 0)$.

By combining these two results, you can conclude that f has a maximum of 24 at $(-1, \pm 3)$ and a minimum of 2 at $(1, 0)$, as shown in Figure 13.81. ■



Figure 13.81

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The Method of Lagrange Multipliers with Two Constraints

For optimization problems involving *two* constraint functions g and h, you can introduce a second Lagrange multiplier, μ (the lowercase Greek letter mu), and then solve the equation

$$\nabla f = \lambda \nabla g + \mu \nabla h$$

where the gradients are not parallel, as illustrated in Example 5.

EXAMPLE 5 Optimization with Two Constraints

Let $T(x, y, z) = 20 + 2x + 2y + z^2$ represent the temperature at each point on the sphere

$$x^2 + y^2 + z^2 = 11.$$

Find the extreme temperatures on the curve formed by the intersection of the plane $x + y + z = 3$ and the sphere.

Solution The two constraints are

$$g(x, y, z) = x^2 + y^2 + z^2 = 11 \quad \text{and} \quad h(x, y, z) = x + y + z = 3.$$

Using

$$\nabla T(x, y, z) = 2\mathbf{i} + 2\mathbf{j} + 2z\mathbf{k}$$
$$\lambda \nabla g(x, y, z) = 2\lambda x\mathbf{i} + 2\lambda y\mathbf{j} + 2\lambda z\mathbf{k}$$

and

$$\mu \nabla h(x, y, z) = \mu\mathbf{i} + \mu\mathbf{j} + \mu\mathbf{k}$$

you can write the following system of equations.

$$\begin{aligned} 2 &= 2\lambda x + \mu && T_x(x, y, z) = \lambda g_x(x, y, z) + \mu h_x(x, y, z) \\ 2 &= 2\lambda y + \mu && T_y(x, y, z) = \lambda g_y(x, y, z) + \mu h_y(x, y, z) \\ 2z &= 2\lambda z + \mu && T_z(x, y, z) = \lambda g_z(x, y, z) + \mu h_z(x, y, z) \\ x^2 + y^2 + z^2 &= 11 && \text{Constraint 1} \\ x + y + z &= 3 && \text{Constraint 2} \end{aligned}$$

By subtracting the second equation from the first, you obtain the following system.

$$\begin{aligned} \lambda(x - y) &= 0 \\ 2z(1 - \lambda) - \mu &= 0 \\ x^2 + y^2 + z^2 &= 11 \\ x + y + z &= 3 \end{aligned}$$

From the first equation, you can conclude that $\lambda = 0$ or $x = y$. For $\lambda = 0$, you can show that the critical points are $(3, -1, 1)$ and $(-1, 3, 1)$. (Try doing this—it takes a little work.) For $\lambda \neq 0$, then $x = y$ and you can show that the critical points occur when $x = y = \left(3 \pm 2\sqrt{3}\right)/3$ and $z = \left(3 \mp 4\sqrt{3}\right)/3$. Finally, to find the optimal solutions, compare the temperatures at the four critical points.

$$T(3, -1, 1) = T(-1, 3, 1) = 25$$
$$T\left(\frac{3 - 2\sqrt{3}}{3}, \frac{3 - 2\sqrt{3}}{3}, \frac{3 + 4\sqrt{3}}{3}\right) = \frac{91}{3} \approx 30.33$$
$$T\left(\frac{3 + 2\sqrt{3}}{3}, \frac{3 + 2\sqrt{3}}{3}, \frac{3 - 4\sqrt{3}}{3}\right) = \frac{91}{3} \approx 30.33$$

So, $T = 25$ is the minimum temperature and $T = \frac{91}{3}$ is the maximum temperature on the curve. ■

REMARK The systems of equations that arise when the Method of Lagrange Multipliers is used are not, in general, linear systems, and finding the solutions often requires ingenuity.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

13.10 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain what is meant by constrained optimization problems.
2. Describe the Method of Lagrange Multipliers for solving constrained optimization problems.

Using Lagrange Multipliers **In Exercises 3–10, use Lagrange multipliers to find the indicated extrema, assuming that x and y are positive.**

3. Maximize $f(x, y) = xy$
   Constraint: $x + y = 10$
4. Minimize $f(x, y) = 2x + y$
   Constraint: $xy = 32$
5. Minimize $f(x, y) = x^2 + y^2$
   Constraint: $x + 2y - 5 = 0$
6. Maximize $f(x, y) = x^2 - y^2$
   Constraint: $2y - x^2 = 0$
7. Maximize $f(x, y) = 2x + 2xy + y$
   Constraint: $2x + y = 100$
8. Minimize $f(x, y) = 3x + y + 10$
   Constraint: $x^2y = 6$
9. Maximize $f(x, y) = \sqrt{6 - x^2 - y^2}$
   Constraint: $x + y - 2 = 0$
10. Minimize $f(x, y) = \sqrt{x^2 + y^2}$
    Constraint: $2x + 4y - 15 = 0$

Using Lagrange Multipliers **In Exercises 11–14, use Lagrange multipliers to find the indicated extrema, assuming that x, y, and z are positive.**

11. Minimize $f(x, y, z) = x^2 + y^2 + z^2$
    Constraint: $x + y + z - 9 = 0$
12. Maximize $f(x, y, z) = xyz$
    Constraint: $x + y + z - 3 = 0$
13. Minimize $f(x, y, z) = x^2 + y^2 + z^2$
    Constraint: $x + y + z = 1$
14. Maximize $f(x, y, z) = x + y + z$
    Constraint: $x^2 + y^2 + z^2 = 1$

Using Lagrange Multipliers **In Exercises 15 and 16, use Lagrange multipliers to find any extrema of the function subject to the constraint $x^2 + y^2 \leq 1$.**

15. $f(x, y) = x^2 + 3xy + y^2$
16. $f(x, y) = e^{-xy/4}$

Using Lagrange Multipliers **In Exercises 17 and 18, use Lagrange multipliers to find the indicated extrema of f subject to two constraints, assuming that x, y, and z are nonnegative.**

17. Maximize $f(x, y, z) = xyz$
    Constraints: $x + y + z = 32, \quad x - y + z = 0$
18. Minimize $f(x, y, z) = x^2 + y^2 + z^2$
    Constraints: $x + 2z = 6, \quad x + y = 12$

Finding Minimum Distance **In Exercises 19–28, use Lagrange multipliers to find the minimum distance from the curve or surface to the indicated point. (*Hint:* To simplify the computations, minimize the square of the distance.)**

Curve	Point
19. Line: $x + y = 1$	$(0, 0)$
20. Line: $2x + 3y = -1$	$(0, 0)$
21. Line: $x - y = 4$	$(0, 2)$
22. Line: $x + 4y = 3$	$(1, 0)$
23. Parabola: $y = x^2$	$(0, 3)$
24. Parabola: $y = x^2$	$(-3, 0)$
25. Circle: $x^2 + (y - 1)^2 = 9$	$(4, 4)$
26. Circle: $(x - 4)^2 + y^2 = 4$	$(0, 10)$
Surface	**Point**
27. Plane: $x + y + z = 1$	$(2, 1, 1)$
28. Cone: $z = \sqrt{x^2 + y^2}$	$(4, 0, 0)$

Intersection of Surfaces **In Exercises 29 and 30, use Lagrange multipliers to find the highest point on the curve of intersection of the surfaces.**

29. Cone: $x^2 + y^2 - z^2 = 0$
    Plane: $x + 2z = 4$
30. Sphere: $x^2 + y^2 + z^2 = 36$
    Plane: $2x + y - z = 2$

Using Lagrange Multipliers **In Exercises 31–38, use Lagrange multipliers to solve the indicated exercise in Section 13.9.**

31. Exercise 3
32. Exercise 4
33. Exercise 7
34. Exercise 8
35. Exercise 11
36. Exercise 12
37. Exercise 17
38. Exercise 18

39. **Maximum Volume** Use Lagrange multipliers to find the dimensions of a rectangular box of maximum volume that can be inscribed (with edges parallel to the coordinate axes) in the ellipsoid

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} + \frac{z^2}{c^2} = 1.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

40. HOW DO YOU SEE IT? The graphs show the constraint and several level curves of the objective function. Use the graph to approximate the indicated extrema.

(a) Maximize $z = xy$ Constraint: $2x + y = 4$

(b) Minimize $z = x^2 + y^2$ Constraint: $x + y - 4 = 0$



Exploring Concepts

41. Explain why you cannot use Lagrange multipliers to find the minimum of the function $f(x, y) = x$ subject to the constraint $y^2 + x^4 - x^3 = 0$.

42. Draw the level curves for $f(x, y) = x^2 + y^2 = c$ for $c = 1, 2, 3$, and 4, and sketch the constraint $x + y = 2$. Explain analytically how you know that the extremum of $f(x, y) = x^2 + y^2$ at $(1, 1)$ is a minimum instead of a maximum.

43. Minimum Cost A cargo container (in the shape of a rectangular solid) must have a volume of 480 cubic feet. The bottom will cost \$5 per square foot to construct, and the sides and the top will cost \$3 per square foot to construct. Use Lagrange multipliers to find the dimensions of the container of this size that has minimum cost.

44. Geometric and Arithmetic Means

(a) Use Lagrange multipliers to prove that the product of three positive numbers x, y, and z, whose sum has the constant value S, is a maximum when the three numbers are equal. Use this result to prove that

$$\sqrt[3]{xyz} \le \frac{x + y + z}{3}.$$

(b) Generalize the result of part (a) to prove that the product $x_1x_2x_3 \cdots x_n$ is a maximum when

$$x_1 = x_2 = x_3 = \cdots = x_n, \sum_{i=1}^{n} x_i = S, \text{ and all } x_i \ge 0.$$

Then prove that

$$\sqrt[n]{x_1x_2x_3 \cdots x_n} \le \frac{x_1 + x_2 + x_3 + \cdots + x_n}{n}.$$

This shows that the geometric mean is never greater than the arithmetic mean.

45. Minimum Surface Area Use Lagrange multipliers to find the dimensions of a right circular cylinder with volume V_0 and minimum surface area.

46. Temperature Let $T(x, y, z) = 100 + x^2 + y^2$ represent the temperature at each point on the sphere

$$x^2 + y^2 + z^2 = 50.$$

Use Lagrange multipliers to find the maximum temperature on the curve formed by the intersection of the sphere and the plane $x - z = 0$.

47. Refraction of Light When light waves traveling in a transparent medium strike the surface of a second transparent medium, they tend to "bend" to follow the path of minimum time. This tendency is called *refraction* and is described by **Snell's Law of Refraction,**

$$\frac{\sin\theta_1}{v_1} = \frac{\sin\theta_2}{v_2}$$

where θ_1 and θ_2 are the magnitudes of the angles shown in the figure, and v_1 and v_2 are the velocities of light in the two media. Use Lagrange multipliers to derive this law using $x + y = a$.



Figure for 47



Figure for 48

48. Area and Perimeter A semicircle is on top of a rectangle (see figure). When the area is fixed and the perimeter is a minimum, or when the perimeter is fixed and the area is a maximum, use Lagrange multipliers to verify that the length of the rectangle is twice its height.

Production Level **In Exercises 49 and 50, use Lagrange multipliers to find the maximum production level when the total cost of labor (at \$112 per unit) and capital (at \$60 per unit) is limited to \$250,000, where P is the production function, x is the number of units of labor, and y is the number of units of capital.**

49. $P(x, y) = 100x^{0.25}y^{0.75}$

50. $P(x, y) = 100x^{0.4}y^{0.6}$

Cost **In Exercises 51 and 52, use Lagrange multipliers to find the minimum cost of producing 50,000 units of a product, where P is the production function, x is the number of units of labor (at \$72 per unit), and y is the number of units of capital (at \$80 per unit).**

51. $P(x, y) = 100x^{0.25}y^{0.75}$ **52.** $P(x, y) = 100x^{0.6}y^{0.4}$

PUTNAM EXAM CHALLENGE

53. A can buoy is to be made of three pieces, namely, a cylinder and two equal cones, the altitude of each cone being equal to the altitude of the cylinder. For a given area of surface, what shape will have the greatest volume?

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Review Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Exploring Concepts

In this chapter, you expanded your knowledge of calculus from functions of one variable to functions of two or more variables. Many of the formulas and techniques in this chapter are extensions of those used in earlier chapters of the text. Several examples are listed below.

Single variable	**Two variable**
Limit of $y = f(x)$	*Limit of* $z = f(x, y)$
$\lim_{x \to c} f(x) = L$	$\lim_{(x, y) \to (x_0, y_0)} f(x, y) = L$
Derivative of $y = f(x)$	*Partial Derivative of* $z = f(x, y)$
$\frac{dy}{dx} = \lim_{\Delta x \to 0} \frac{f(x + \Delta x) - f(x)}{\Delta x}$	$\frac{\partial z}{\partial x} = \lim_{\Delta x \to 0} \frac{f(x + \Delta x, y) - f(x, y)}{\Delta x}$

1. In your own words, describe how to sketch the graph of a function of two variables.

2. How can you visualize a function of three variables?

3. Use the graph to determine whether z is a function of x and y. Explain.



4. Sketch a graph of a function $z = f(x, y)$ whose derivative f_x is always negative and whose derivative f_y is always negative.

5. The figure shows the level curves for an unknown function $f(x, y)$. What, if any, information can be determined about f at the points A, B, C, and D? Explain your reasoning.



6. Consider the functions $f(x, y) = x^2 - y^2$ and $g(x, y) = x^2 + y^2$.

(a) Show that both functions have a critical point at $(0, 0)$.

(b) Explain how f and g behave differently at this critical point.

Evaluating a Function **In Exercises 7 and 8, evaluate the function at the given values of the independent variables. Simplify the results.**

7. $f(x, y) = x^2y - 3$

(a) $f(0, 4)$ (b) $f(2, -1)$ (c) $f(-3, 2)$ (d) $f(x, 7)$

8. $f(x, y) = 6 - 4x - 2y^2$

(a) $f(0, 2)$ (b) $f(5, 0)$ (c) $f(-1, -2)$ (d) $f(-3, y)$

Finding the Domain and Range of a Function **In Exercises 9 and 10, find the domain and range of the function.**

9. $f(x, y) = \frac{\sqrt{x}}{y}$

10. $f(x, y) = \sqrt{36 - x^2 - y^2}$

Sketching a Surface **In Exercises 11 and 12, describe and sketch the surface given by the function.**

11. $f(x, y) = -2$

12. $g(x, y) = x$

Sketching a Contour Map **In Exercises 13 and 14, describe the level curves of the function. Sketch a contour map of the surface using level curves for the given c-values.**

13. $z = 3 - 2x + y, \quad c = 0, 2, 4, 6, 8$

14. $z = 2x^2 + y^2, \quad c = 1, 2, 3, 4, 5$

15. Conjecture Consider the function $f(x, y) = x^2 + y^2$.

(a) Sketch the graph of the surface given by f.

(b) Make a conjecture about the relationship between the graphs of f and $g(x, y) = f(x, y) + 2$. Explain your reasoning.

(c) Make a conjecture about the relationship between the graphs of f and $g(x, y) = f(x, y - 2)$. Explain your reasoning.

(d) On the surface in part (a), sketch the graphs of $z = f(1, y)$ and $z = f(x, 1)$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

16. Cobb-Douglas Production Function A manufacturer estimates that its production can be modeled by

$$f(x, y) = 100x^{0.8}y^{0.2}$$

where x is the number of units of labor and y is the number of units of capital.

(a) Find the production level when $x = 100$ and $y = 200$.

(b) Find the production level when $x = 500$ and $y = 1500$.

Sketching a Level Surface **In Exercises 17 and 18, describe and sketch the graph of the level surface $f(x, y, z) = c$ at the given value of c.**

17. $f(x, y, z) = x^2 - y + z^2, \quad c = 2$

18. $f(x, y, z) = 4x^2 - y^2 + 4z^2, \quad c = 0$

Limit and Continuity **In Exercises 19–24, find the limit (if it exists) and discuss the continuity of the function.**

19. $\lim_{(x, y)\to(1, 1)} \dfrac{xy}{x^2 + y^2}$

20. $\lim_{(x, y)\to(1, 1)} \dfrac{xy}{x^2 - y^2}$

21. $\lim_{(x, y)\to(0, 0)} \dfrac{y + xe^{-y^2}}{1 + x^2}$

22. $\lim_{(x, y)\to(0, 0)} \dfrac{x^2y}{x^4 + y^2}$

23. $\lim_{(x, y, z)\to(-3, 1, 2)} \dfrac{\ln z}{xy - z}$

24. $\lim_{(x, y, z)\to(1, 3, \pi)} \sin\dfrac{xz}{2y}$

Finding Partial Derivatives **In Exercises 25–32, find all first partial derivatives.**

25. $f(x, y) = 5x^3 + 7y - 3$

26. $f(x, y) = 4x^2 - 2xy + y^2$

27. $f(x, y) = e^x \cos y$

28. $f(x, y) = \dfrac{xy}{x + y}$

29. $f(x, y) = y^3e^{y/x}$

30. $z = \ln(x^2 + y^2 + 1)$

31. $f(x, y, z) = 2xz^2 + 6xyz$

32. $w = \sqrt{x^2 - y^2 - z^2}$

Finding and Evaluating Partial Derivatives **In Exercises 33–36, find all first partial derivatives, and evaluate each at the given point.**

33. $f(x, y) = x^2 - y, \quad (0, 2)$

34. $f(x, y) = xe^{2y}, \quad (-1, 1)$

35. $f(x, y, z) = xy \cos xz, \quad (2, 3, -\pi/3)$

36. $f(x, y, z) = \sqrt{x^2 + y - z^2}, \quad (-3, -3, 1)$

Finding Second Partial Derivatives **In Exercises 37–40, find the four second partial derivatives. Observe that the second mixed partials are equal.**

37. $f(x, y) = 3x^2 - xy + 2y^3$

38. $h(x, y) = \dfrac{x}{x + y}$

39. $h(x, y) = x \sin y + y \cos x$

40. $g(x, y) = \cos(x - 2y)$

41. Finding the Slopes of a Surface Find the slopes of the surface

$$z = x^2 \ln(y + 1)$$

in the x- and y-directions at the point $(2, 0, 0)$.

42. Marginal Revenue A company has two plants that produce the same lawn mower. If x_1 and x_2 are the numbers of units produced at plant 1 and plant 2, respectively, then the total revenue for the product is given by

$$R = 300x_1 + 300x_2 - 5x_1^2 - 10x_1x_2 - 5x_2^2.$$

When $x_1 = 5$ and $x_2 = 8$, find (a) the marginal revenue for plant 1, $\partial R/\partial x_1$, and (b) the marginal revenue for plant 2, $\partial R/\partial x_2$.

Finding a Total Differential **In Exercises 43–46, find the total differential.**

43. $z = x \sin xy$

44. $z = 5x^4y^3$

45. $w = 3xy^2 - 2x^3yz^2$

46. $w = \dfrac{3x + 4y}{y + 3z}$

Using a Differential as an Approximation **In Exercises 47 and 48, (a) find $f(2, 1)$ and $f(2.1, 1.05)$ and calculate Δz, and (b) use the total differential dz to approximate Δz.**

47. $f(x, y) = 4x + 2y$

48. $f(x, y) = 36 - x^2 - y^2$

49. Volume The possible error involved in measuring each dimension of a right circular cone is $\pm\frac{1}{8}$ inch. The radius is 2 inches and the height is 5 inches. Approximate the propagated error and the relative error in the calculated volume of the cone.

50. Lateral Surface Area Approximate the propagated error and the relative error in the calculated lateral surface area of the cone in Exercise 49. (The lateral surface area is given by $A = \pi r\sqrt{r^2 + h^2}$.)

Differentiability **In Exercises 51 and 52, show that the function is differentiable by finding values of ε_1 and ε_2 as designated in the definition of differentiability, and verify that both ε_1 and ε_2 approach 0 as $(\Delta x, \Delta y) \to (0, 0)$.**

51. $f(x, y) = 6x - y^2$

52. $f(x, y) = xy^2$

Using Different Methods **In Exercises 53–56, find dw/dt (a) by using the appropriate Chain Rule and (b) by converting w to a function of t before differentiating.**

53. $w = \ln(x^2 + y), \quad x = 2t, \quad y = 4 - t$

54. $w = y^2 - x, \quad x = \cos t, \quad y = \sin t$

55. $w = x^2z + y + z, \quad x = e^t, \quad y = t, \quad z = t^2$

56. $w = \sin x + y^2z + 2z, \quad x = \arcsin(t - 1), \quad y = t^3, \quad z = 3$

Using Different Methods **In Exercises 57 and 58, find $\partial w/\partial r$ and $\partial w/\partial t$ (a) by using the appropriate Chain Rule and (b) by converting w to a function of r and t before differentiating.**

57. $w = \dfrac{xy}{z}, \quad x = 2r + t, \quad y = rt, \quad z = 2r - t$

58. $w = x^2 + y^2 + z^2, \quad x = r \cos t, \quad y = r \sin t, \quad z = t$

Finding a Derivative Implicitly **In Exercises 59 and 60, differentiate implicitly to find dy/dx.**

59. $x^3 - xy + 5y = 0$

60. $\dfrac{xy^2}{x + y} = 3$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding Partial Derivatives Implicitly **In Exercises 61 and 62, differentiate implicitly to find the first partial derivatives of z.**

61. $x^2 + xy + y^2 + yz + z^2 = 0$

62. $xz^2 - y \sin z = 0$

Finding a Directional Derivative **In Exercises 63 and 64, use Theorem 13.9 to find the directional derivative of the function at P in the direction of $\mathbf{v}$.**

63. $f(x, y) = x^2y, \quad P(-5, 5), \quad \mathbf{v} = 3\mathbf{i} - 4\mathbf{j}$

64. $f(x, y) = \frac{1}{4}y^2 - x^2, \quad P(1, 4), \quad \mathbf{v} = 2\mathbf{i} + \mathbf{j}$

Finding a Directional Derivative **In Exercises 65 and 66, use the gradient to find the directional derivative of the function at P in the direction of $\mathbf{v}$.**

65. $w = y^2 + xz, \quad P(1, 2, 2), \quad \mathbf{v} = 2\mathbf{i} - \mathbf{j} + 2\mathbf{k}$

66. $w = 5x^2 + 2xy - 3y^2z, \quad P(1, 0, 1), \quad \mathbf{v} = \mathbf{i} + \mathbf{j} - \mathbf{k}$

Using Properties of the Gradient **In Exercises 67–72, find the gradient of the function and the maximum value of the directional derivative at the given point.**

67. $z = x^2y, \quad (2, 1)$

68. $z = e^{-x} \cos y, \quad \left(0, \frac{\pi}{4}\right)$

69. $z = \frac{y}{x^2 + y^2}, \quad (1, 1)$

70. $z = \frac{x^2}{x - y}, \quad (2, 1)$

71. $w = x^4y - y^2z^2, \quad \left(-1, \frac{1}{2}, 2\right)$

72. $w = e^{\sqrt{x+y+z^2}}, \quad (5, 0, 2)$

Using a Function **In Exercises 73 and 74, (a) find the gradient of the function at P, (b) find a unit normal vector to the level curve $f(x, y) = c$ at P, (c) find the tangent line to the level curve $f(x, y) = c$ at P, and (d) sketch the level curve, the unit normal vector, and the tangent line in the xy-plane.**

73. $f(x, y) = 9x^2 - 4y^2$

$c = 65, \quad P(3, 2)$

74. $f(x, y) = 4y \sin x - y$

$c = 3, \quad P\left(\frac{\pi}{2}, 1\right)$

Finding an Equation of a Tangent Plane **In Exercises 75–78, find an equation of the tangent plane to the surface at the given point.**

75. $z = x^2 + y^2 + 2, \quad (1, 3, 12)$

76. $9x^2 + y^2 + 4z^2 = 25, \quad (0, -3, 2)$

77. $z = -9 + 4x - 6y - x^2 - y^2, \quad (2, -3, 4)$

78. $f(x, y) = \sqrt{25 - y^2}, \quad (2, 3, 4)$

Finding an Equation of a Tangent Plane and a Normal Line **In Exercises 79 and 80, (a) find an equation of the tangent plane to the surface at the given point and (b) find a set of symmetric equations for the normal line to the surface at the given point.**

79. $f(x, y) = x^2y, \quad (2, 1, 4)$

80. $z = \sqrt{9 - x^2 - y^2}, \quad (1, 2, 2)$

Finding the Angle of Inclination of a Tangent Plane **In Exercises 81 and 82, find the angle of inclination of the tangent plane to the surface at the given point.**

81. $x^2 + y^2 + z^2 = 14, \quad (2, 1, 3)$

82. $xy + yz^2 = 32, \quad (-4, 1, 6)$

Horizontal Tangent Plane **In Exercises 83 and 84, find the point(s) on the surface at which the tangent plane is horizontal.**

83. $z = 9 - 2x^2 + y^3$

84. $z = 2xy + 3x + 5y$

Using the Second Partials Test **In Exercises 85–90, find all relative extrema and saddle points of the function. Use the Second Partials Test where applicable.**

85. $f(x, y) = -x^2 - 4y^2 + 8x - 8y - 11$

86. $f(x, y) = x^2 - y^2 - 16x - 16y$

87. $f(x, y) = 2x^2 + 6xy + 9y^2 + 8x + 14$

88. $f(x, y) = x^6y^6$

89. $f(x, y) = xy + \frac{1}{x} + \frac{1}{y}$

90. $f(x, y) = -8x^2 + 4xy - y^2 + 12x + 7$

91. Finding Minimum Distance Find the minimum distance from the point $(2, 1, 4)$ to the surface $x + y + z = 4$. (*Hint:* To simplify the computations, minimize the square of the distance.)

92. Finding Positive Numbers Find three positive integers, x, y, and z, such that the product is 64 and the sum is a minimum.

93. Maximum Revenue A company manufactures two types of bicycles, a racing bicycle and a mountain bicycle. The total revenue (in thousands of dollars) from x_1 units of racing bicycles and x_2 units of mountain bicycles is

$$R = -6x_1^2 - 10x_2^2 - 2x_1x_2 + 32x_1 + 84x_2$$

where x_1 and x_2 are in thousands of units. Find x_1 and x_2 so as to maximize the revenue.

94. Maximum Profit A corporation manufactures digital cameras at two locations. The cost of producing x_1 units at location 1 is $C_1 = 0.05x_1^2 + 15x_1 + 5400$ and the cost of producing x_2 units at location 2 is $C_2 = 0.03x_2^2 + 15x_2 + 6100$. The digital cameras sell for \$180 per unit. Find the quantity that should be produced at each location to maximize the profit $P = 180(x_1 + x_2) - C_1 - C_2$.

Finding the Least Squares Regression Line **In Exercises 95 and 96, find the least squares regression line for the points. Use the regression capabilities of a graphing utility to verify your results. Use the graphing utility to plot the points and graph the regression line.**

95. $(0, 4), (1, 5), (3, 6), (6, 8), (8, 10)$

96. $(0, 10), (2, 8), (4, 7), (7, 5), (9, 3), (12, 0)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

97. Modeling Data An agronomist used four test plots to determine the relationship between the wheat yield y (in bushels per acre) and the amount of fertilizer x (in pounds per acre). The results are shown in the table. Use a graphing utility to find the least squares regression line for the data. Use the model to approximate the wheat yield for a fertilizer application of 175 pounds per acre.

Fertilizer, x	100	150	200	250
Yield, y	35	44	50	56

98. Modeling Data The table shows the yield y (in milligrams) of a chemical reaction after t minutes.

Minutes, t	1	2	3	4
Yield, y	1.2	7.1	9.9	13.1

Minutes, t	5	6	7	8
Yield, y	15.5	16.0	17.9	18.0

(a) Use a graphing utility to find the least squares regression line for the data. Then use the graphing utility to plot the data and graph the model.

(b) Use a graphing utility to plot the points $(\ln t, y)$. Do these points appear to follow a linear pattern more closely than the plot of the given data in part (a)?

(c) Use a graphing utility to find the least squares regression line for the points $(\ln t, y)$ and obtain the logarithmic model $y = a + b \ln t$. Then, plot the original data and graph the linear and logarithmic models. Which is a better model? Explain.

Using Lagrange Multipliers **In Exercises 99–104, use Lagrange multipliers to find the indicated extrema, assuming that x and y are positive.**

99. Minimize $f(x, y) = x^2 + y^2$

Constraint: $x + y - 8 = 0$

100. Maximize $f(x, y) = xy$

Constraint: $x + 3y - 6 = 0$

101. Maximize $f(x, y) = 2x + 3xy + y$

Constraint: $x + 2y = 29$

102. Minimize $f(x, y) = x^2 - y^2$

Constraint: $x - 2y + 6 = 0$

103. Maximize $f(x, y) = 2xy$

Constraint: $2x + y = 12$

104. Minimize $f(x, y) = 3x^2 - y^2$

Constraint: $2x - 2y + 5 = 0$

105. Minimum Cost A water line is to be built from point P to point S and must pass through regions where construction costs differ (see figure). The cost per kilometer (in dollars) is $3k$ from P to Q, $2k$ from Q to R, and k from R to S. For simplicity, let $k = 1$. Use Lagrange multipliers to find x, y, and z such that the total cost C will be minimized.



Building on Concepts

106. Heron's Formula states that the area of a triangle with sides of lengths a, b, and c is given by

$$A = \sqrt{s(s-a)(s-b)(s-c)}$$

where

$$s = \frac{a+b+c}{2}$$

as shown in the figure.



(a) Use Heron's Formula to find the area of the triangle with vertices $(0, 0)$, $(3, 4)$, and $(6, 0)$.

(b) Show that among all triangles having a fixed perimeter, the triangle with the largest area is an equilateral triangle.

(c) Show that among all triangles having a fixed area, the triangle with the smallest perimeter is an equilateral triangle.

107. The Ideal Gas Law states that $PV = nRT$, where P is pressure, V is volume, n is the number of moles of gas, R is a fixed constant (the gas constant), and T is temperature (in kelvins). The **van der Waals equation**

$$\left(P + \frac{an^2}{V^2}\right)(V - nb) = nRT$$

is a modification of the Ideal Gas Law. Here, b is the volume per mole that is occupied by the gas molecules, and a is a constant that represents the interaction of the gas molecules. Find $\partial P/\partial V$ and $\partial T/\partial P$.

108. Show that

$$u(x, t) = \frac{1}{2}\left[f(x - ct) + f(x + ct)\right]$$

is a solution of the one-dimensional wave equation

$$\frac{\partial^2 u}{\partial t^2} = c^2 \frac{\partial^2 u}{\partial x^2}.$$

(This equation describes the small transverse vibration of an elastic string such as those on certain musical instruments.)

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.S. Problem Solving

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

1. Tangent Plane Let $P(x_0, y_0, z_0)$ be a point in the first octant on the surface $xyz = 1$, as shown in the figure.

(a) Find the equation of the tangent plane to the surface at the point P.

(b) Show that the volume of the tetrahedron formed by the three coordinate planes and the tangent plane is constant, independent of the point of tangency (see figure).



Figure for 1



Figure for 2

2. Minimizing Material An industrial container is in the shape of a cylinder with hemispherical ends, as shown in the figure. The container must hold 1000 liters of fluid. Determine the radius r and length h that minimize the amount of material used in the construction of the tank.

3. Finding Maximum and Minimum Values

(a) Let $f(x, y) = x - y$ and $g(x, y) = x^2 + y^2 = 4$. Graph various level curves of f and the constraint g in the xy-plane. Use the graph to determine the maximum value of f subject to the constraint $g = 4$. Then verify your answer using Lagrange multipliers.

(b) Let $f(x, y) = x - y$ and $g(x, y) = x^2 + y^2 = 0$. Find the maximum and minimum values of f subject to the constraint $g = 0$. Does the Method of Lagrange Multipliers work in this case? Explain.

4. Using Functions Use a graphing utility to graph the functions $f(x) = \sqrt[3]{x^3 - 1}$ and $g(x) = x$ in the same viewing window.

(a) Show that

$$\lim_{x\to\infty}[f(x) - g(x)] = 0 \quad \text{and} \quad \lim_{x\to-\infty}[f(x) - g(x)] = 0.$$

(b) Find the point on the graph of f that is farthest from the graph of g.

5. Cobb-Douglas Production Function Consider the Cobb-Douglas production function

$$f(x, y) = Cx^a y^{1-a}, \quad 0 < a < 1.$$

(a) Show that f satisfies the equation $x\dfrac{\partial f}{\partial x} + y\dfrac{\partial f}{\partial y} = f$.

(b) Show that $f(tx, ty) = tf(x, y)$.

6. Laplace's Equation Rewrite Laplace's equation

$$\frac{\partial^2 u}{\partial x^2} + \frac{\partial^2 u}{\partial y^2} + \frac{\partial^2 u}{\partial z^2} = 0$$

in cylindrical coordinates.

7. Finding Extrema and Saddle Points Consider the function

$$f(x, y) = (\alpha x^2 + \beta y^2)e^{-(x^2+y^2)}, \quad 0 < |\alpha| < \beta.$$

(a) Use a graphing utility to graph the function for $\alpha = 1$ and $\beta = 2$, and identify any extrema or saddle points.

(b) Use a graphing utility to graph the function for $\alpha = -1$ and $\beta = 2$, and identify any extrema or saddle points.

(c) Generalize the results in parts (a) and (b) for the function f.

8. Temperature Consider a circular plate of radius 1 given by $x^2 + y^2 \le 1$, as shown in the figure. The temperature at any point $P(x, y)$ on the plate is $T(x, y) = 2x^2 + y^2 - y + 10$.



(a) Sketch the isotherm $T(x, y) = 10$. To print an enlarged copy of the graph, go to *MathGraphs.com.*

(b) Find the hottest and coldest points on the plate.

9. Wave Equation Show that

$$u(x, t) = \frac{1}{2}[\sin(x - t) + \sin(x + t)]$$

is a solution of the one-dimensional wave equation

$$\frac{\partial^2 u}{\partial t^2} = \frac{\partial^2 u}{\partial x^2}.$$

10. Tangent Planes Let f be a differentiable function of one variable. Show that all tangent planes to the surface $z = yf(x/y)$ intersect in a common point.

11. Verifying Equations Consider the function $w = f(x, y)$, where $x = r\cos\theta$ and $y = r\sin\theta$. Verify each of the following.

(a) $$\frac{\partial w}{\partial x} = \frac{\partial w}{\partial r}\cos\theta - \frac{\partial w}{\partial \theta}\frac{\sin\theta}{r}$$

$$\frac{\partial w}{\partial y} = \frac{\partial w}{\partial r}\sin\theta + \frac{\partial w}{\partial \theta}\frac{\cos\theta}{r}$$

(b) $$\left(\frac{\partial w}{\partial x}\right)^2 + \left(\frac{\partial w}{\partial y}\right)^2 = \left(\frac{\partial w}{\partial r}\right)^2 + \left(\frac{1}{r^2}\right)\left(\frac{\partial w}{\partial \theta}\right)^2$$

12. Using a Function Demonstrate the result of Exercise 11(b) for

$$w = \arctan\frac{y}{x}.$$

13. Proof Prove that if f is a differentiable function such that $\nabla f(x_0, y_0) = \mathbf{0}$, then the tangent plane at (x_0, y_0) is horizontal.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

14 Multiple Integration

GO DIGITAL

14.1 Iterated Integrals and Area in the Plane
14.2 Double Integrals and Volume
14.3 Change of Variables: Polar Coordinates
14.4 Center of Mass and Moments of Inertia
14.5 Surface Area
14.6 Triple Integrals and Applications
14.7 Triple Integrals in Other Coordinates
14.8 Change of Variables: Jacobians

CalcView®



CalcChat®


Chapter 14
Section 2
Exercise 35
GO
$V = 2\int_0^2 \int_0^{\sqrt{1-(x-1)^2}} \left([4 - x^2 - y^2] - [4 - 2x]\right) dy\, dx$
$= 2\int_0^2 \int_0^{\sqrt{1-(x-1)^2}} \left(2x - x^2 - y^2\right) dy\, dx$
$(x-1)^2 + y^2 = 1$
PREV. 25 27 29 31 33 35 37 39 41 43 45 NEXT

Center of Pressure on a Sail *(Section Project, p. 1005)*

Glacier *(Exercise 58, p. 997)*

left, Valentin Valkov/Shutterstock.com; right, Denis Burdin/Shutterstock.com
Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it. WCN 02-200-322

14.1 Iterated Integrals and Area in the Plane

GO DIGITAL

- **Evaluate an iterated integral.**
- **Use an iterated integral to find the area of a plane region.**

Big Ideas of Calculus

Just as you extended the concepts of limits and derivatives to functions of several variables, you can extend *single* integration

$$\int_a^b f(x)\,dx$$

to *multiple* integration. In multiple integration, the integrand is a function of several variables, such as

$$\int_a^b \int_{g_1(x)}^{g_2(x)} f(x, y)\,dy\,dx.$$

With multiple integration, you can analyze more general regions to find their volumes, masses, and centroids. You can also find the center of mass and moments of inertia of a solid with a variable density.

Iterated Integrals

In Chapters 14 and 15, you will study several applications of integration involving functions of several variables. Chapter 14 is like Chapter 7 in that it surveys the use of integration to find plane areas, volumes, surface areas, moments, and centers of mass.

In Chapter 13, you differentiated functions of several variables with respect to one variable while holding the other variables constant. You can *integrate* functions of several variables by a similar procedure. For example, consider the partial derivative $f_x(x, y) = 2xy$. By considering y constant, you can integrate with respect to x to obtain

$$\begin{aligned} f(x, y) &= \int f_x(x, y)\,dx && \text{Integrate with respect to } x. \\ &= \int 2xy\,dx && \text{Hold } y \text{ constant.} \\ &= y \int 2x\,dx && \text{Factor out constant } y. \\ &= y(x^2) + C(y) && \text{Antiderivative of } 2x \text{ is } x^2. \\ &= x^2y + C(y). && C(y) \text{ is a function of } y. \end{aligned}$$

The "constant" of integration, $C(y)$, is a function of y. In other words, by integrating with respect to x, you are able to recover $f(x, y)$ only partially. The total recovery of a function of x and y from its partial derivatives is a topic you will study in Chapter 15. For now, you will focus on extending definite integrals to functions of several variables. For instance, by considering y constant, you can apply the Fundamental Theorem of Calculus to evaluate

$$\int_1^{2y} 2xy\,dx = x^2y\Big]_1^{2y} = (2y)^2y - (1)^2y = 4y^3 - y.$$

x is the variable of integration, and y is fixed. — Replace x by the limits of integration. — The result is a function of y.

Similarly, you can integrate with respect to y by holding x fixed. Both procedures are summarized as follows.

$$\int_{h_1(y)}^{h_2(y)} f_x(x, y)\,dx = f(x, y)\Big]_{h_1(y)}^{h_2(y)} = f(h_2(y), y) - f(h_1(y), y) \qquad \text{With respect to } x$$

$$\int_{g_1(x)}^{g_2(x)} f_y(x, y)\,dy = f(x, y)\Big]_{g_1(x)}^{g_2(x)} = f(x, g_2(x)) - f(x, g_1(x)) \qquad \text{With respect to } y$$

Note that the variable of integration cannot appear in either limit of integration. For instance, it makes no sense to write

$$\int_0^x y\,dx.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 1 Integrating with Respect to *y*

Evaluate $\int_1^x (2xy + 3y^2)\,dy$.

Solution Considering x to be constant and integrating with respect to y, you have

$$\int_1^x (2xy + 3y^2)\,dy = \Big[xy^2 + y^3\Big]_1^x \qquad \text{Integrate with respect to } y.$$
$$= (2x^3) - (x + 1)$$
$$= 2x^3 - x - 1.$$

REMARK Remember that you can check an antiderivative using differentiation. For instance, in Example 1, you can verify that

$$xy^2 + y^3$$

is the correct antiderivative by finding

$$\frac{\partial}{\partial y}[xy^2 + y^3].$$

Notice in Example 1 that the integral defines a function of x and can *itself* be integrated, as shown in the next example.

EXAMPLE 2 The Integral of an Integral

Evaluate $\int_1^2 \left[\int_1^x (2xy + 3y^2)\,dy\right] dx$.

Solution Using the result of Example 1, you have

$$\int_1^2 \left[\int_1^x (2xy + 3y^2)\,dy\right] dx = \int_1^2 (2x^3 - x - 1)\,dx$$
$$= \left[\frac{x^4}{2} - \frac{x^2}{2} - x\right]_1^2 \qquad \text{Integrate with respect to } x.$$
$$= 4 - (-1)$$
$$= 5.$$

The integral in Example 2 is an **iterated integral.** The brackets used in Example 2 are normally not written. Instead, iterated integrals are usually written simply as

$$\int_a^b \int_{g_1(x)}^{g_2(x)} f(x, y)\,dy\,dx \quad \text{and} \quad \int_c^d \int_{h_1(y)}^{h_2(y)} f(x, y)\,dx\,dy.$$

The **inside limits of integration** can be variable with respect to the outer variable of integration. However, the **outside limits of integration** *must be* constant with respect to both variables of integration. After performing the inside integration, you obtain a "standard" definite integral, and the second integration produces a real number. The limits of integration for an iterated integral identify two sets of boundary intervals for the variables. For instance, in Example 2, the outside limits indicate that x lies in the interval $1 \le x \le 2$, and the inside limits indicate that y lies in the interval $1 \le y \le x$. Together, these two intervals determine the **region of integration** R of the iterated integral, as shown in Figure 14.1.



The region of integration for $\int_1^2 \int_1^x f(x, y)\,dy\,dx$

Figure 14.1

Because an iterated integral is just a special type of definite integral—one in which the integrand is also an integral—you can use the properties of definite integrals to evaluate iterated integrals.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Vertically simple region
Figure 14.2

Area of a Plane Region

In the remainder of this section, you will revisit the problem of finding the area of a plane region. Consider the plane region R bounded by $a \le x \le b$ and $g_1(x) \le y \le g_2(x)$, as shown in Figure 14.2. The area of R is

$$\int_a^b [g_2(x) - g_1(x)]\,dx. \qquad \text{Area of } R$$

Using the Fundamental Theorem of Calculus, you can rewrite the integrand $g_2(x) - g_1(x)$ as a definite integral. Specifically, consider x to be fixed and let y vary from $g_1(x)$ to $g_2(x)$, and you can write

$$\int_{g_1(x)}^{g_2(x)} dy = y\Big]_{g_1(x)}^{g_2(x)} = g_2(x) - g_1(x).$$

Combining these two integrals, you can write the area of the region R as an iterated integral

$$\int_a^b \int_{g_1(x)}^{g_2(x)} dy\,dx = \int_a^b y\Big]_{g_1(x)}^{g_2(x)} dx$$

$$= \int_a^b [g_2(x) - g_1(x)]\,dx. \qquad \text{Area of } R$$

GO DIGITAL

Placing a representative rectangle in the region R helps determine both the order and the limits of integration. A vertical rectangle implies the order $dy\,dx$, with the inside limits of integration corresponding to the upper and lower bounds of the rectangle, as shown in Figure 14.2. This type of region is **vertically simple,** because the outside limits of integration represent the vertical lines

$$x = a \quad \text{and} \quad x = b.$$

Similarly, a horizontal rectangle implies the order $dx\,dy$, with the inside limits of integration determined by the left and right bounds of the rectangle, as shown in Figure 14.3. This type of region is **horizontally simple,** because the outside limits of integration represent the horizontal lines

$$y = c \quad \text{and} \quad y = d.$$



Horizontally simple region
Figure 14.3

The iterated integrals used for these two types of simple regions are summarized as follows.

REMARK Be sure you understand that the orders of integration of these two integrals are different—the order $dy\,dx$ corresponds to a vertically simple region (see Figure 14.2), and the order $dx\,dy$ corresponds to a horizontally simple region (see Figure 14.3).

Area of a Region in the Plane

1. If R is defined by $a \le x \le b$ and $g_1(x) \le y \le g_2(x)$, where g_1 and g_2 are continuous on $[a, b]$, then the area of R is

$$A = \int_a^b \int_{g_1(x)}^{g_2(x)} dy\,dx. \qquad \text{Figure 14.2 (vertically simple)}$$

2. If R is defined by $c \le y \le d$ and $h_1(y) \le x \le h_2(y)$, where h_1 and h_2 are continuous on $[c, d]$, then the area of R is

$$A = \int_c^d \int_{h_1(y)}^{h_2(y)} dx\,dy. \qquad \text{Figure 14.3 (horizontally simple)}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

If all four limits of integration happen to be constants, then the region of integration is rectangular, as shown in Example 3.

EXAMPLE 3 The Area of a Rectangular Region

Use an iterated integral to represent the area of the rectangle shown in Figure 14.4.



Figure 14.4

Solution The region shown in Figure 14.4 is both vertically simple and horizontally simple, so you can use either order of integration. By choosing the order $dy\,dx$, you obtain the following.

$$\int_a^b \int_c^d dy\,dx = \int_a^b y\Big]_c^d dx \qquad \text{Integrate with respect to } y.$$

$$= \int_a^b (d - c)\,dx$$

$$= \Big[(d - c)x\Big]_a^b \qquad \text{Integrate with respect to } x.$$

$$= (d - c)(b - a)$$

Notice that this answer is consistent with what you know from geometry.

EXAMPLE 4 Finding Area by an Iterated Integral

Use an iterated integral to find the area of the region bounded by the graphs of

$$f(x) = \sin x \qquad \text{Sine curve forms upper boundary.}$$

and

$$g(x) = \cos x \qquad \text{Cosine curve forms lower boundary.}$$

between $x = \pi/4$ and $x = 5\pi/4$.



Figure 14.5

Solution Because f and g are given as functions of x, a vertical representative rectangle is convenient, and you can choose $dy\,dx$ as the order of integration, as shown in Figure 14.5. The outside limits of integration are

$$\frac{\pi}{4} \le x \le \frac{5\pi}{4}.$$

Moreover, because the rectangle is bounded above by $f(x) = \sin x$ and below by $g(x) = \cos x$, you have

$$\text{Area of } R = \int_{\pi/4}^{5\pi/4} \int_{\cos x}^{\sin x} dy\,dx$$

$$= \int_{\pi/4}^{5\pi/4} y\Big]_{\cos x}^{\sin x} dx \qquad \text{Integrate with respect to } y.$$

$$= \int_{\pi/4}^{5\pi/4} (\sin x - \cos x)\,dx$$

$$= \Big[-\cos x - \sin x\Big]_{\pi/4}^{5\pi/4} \qquad \text{Integrate with respect to } x.$$

$$= 2\sqrt{2}.$$

The region of integration of an iterated integral need not have any straight lines as boundaries. For instance, the region of integration shown in Figure 14.5 is *vertically simple* even though it has no vertical lines as left and right boundaries. The quality that makes the region vertically simple is that it is bounded above and below by the graphs of *functions of x*.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

One order of integration will often produce a simpler integration problem than the other order. For instance, rework Example 4 with the order $dx\,dy$. You may be surprised to find that the task is formidable. However, if you succeed, you will discover that the answer is the same. In other words, the order of integration affects the ease of integration but not the value of the integral.

EXAMPLE 5 Comparing Different Orders of Integration

See LarsonCalculus.com for an interactive version of this type of example.

Sketch the region whose area is represented by the integral

$$\int_0^2 \int_{y^2}^4 dx\,dy.$$

Then find another iterated integral using the order $dy\,dx$ to represent the same area and show that both integrals yield the same value.



(a)



(b)

Figure 14.6

Solution From the given limits of integration, you know that

$$y^2 \le x \le 4 \qquad \text{Inner limits of integration}$$

which means that the region R is bounded on the left by the parabola $x = y^2$ and on the right by the line $x = 4$. Furthermore, because

$$0 \le y \le 2 \qquad \text{Outer limits of integration}$$

you know that R is bounded below by the x-axis, as shown in Figure 14.6(a). The value of this integral is

$$\begin{aligned}\int_0^2 \int_{y^2}^4 dx\,dy &= \int_0^2 x\Big]_{y^2}^4 dy && \text{Integrate with respect to } x.\\ &= \int_0^2 (4 - y^2)\,dy\\ &= \left[4y - \frac{y^3}{3}\right]_0^2 && \text{Integrate with respect to } y.\\ &= \frac{16}{3}.\end{aligned}$$

To change the order of integration to $dy\,dx$, place a vertical rectangle in the region, as shown in Figure 14.6(b). From this, you can determine that the constant bounds $0 \le x \le 4$ serve as the outer limits of integration. By solving for y in the equation $x = y^2$, you can conclude that the inner bounds are $0 \le y \le \sqrt{x}$. So, the area of the region can also be represented by

$$\int_0^4 \int_0^{\sqrt{x}} dy\,dx.$$

As shown below, evaluating this integral yields the same value as the original integral.

$$\begin{aligned}\int_0^4 \int_0^{\sqrt{x}} dy\,dx &= \int_0^4 y\Big]_0^{\sqrt{x}} dx && \text{Integrate with respect to } y.\\ &= \int_0^4 \sqrt{x}\,dx\\ &= \frac{2}{3}x^{3/2}\Big]_0^4 && \text{Integrate with respect to } x.\\ &= \frac{16}{3}\end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Sometimes it is not possible to calculate the area of a region with a single iterated integral. In these cases, divide the region into subregions such that the area of each subregion can be calculated by an iterated integral. The total area is then the sum of the iterated integrals.

EXAMPLE 6 An Area Represented by Two Iterated Integrals

Find the area of the region R that lies below the parabola

$$y = 4x - x^2$$ Parabola forms upper boundary.

above the x-axis, and above the line

$$y = -3x + 6.$$ Line and x-axis form lower boundary.

Solution Begin by dividing R into the two subregions R_1 and R_2 shown in Figure 14.7.



Figure 14.7

REMARK In Examples 3 through 6, be sure you see the benefit of sketching the region of integration. You should develop the habit of making sketches to help you determine the limits of integration for all iterated integrals in this chapter.

In both regions, it is convenient to use vertical rectangles, and you have

$$\begin{aligned}
\text{Area} &= \int_1^2 \int_{-3x+6}^{4x-x^2} dy\, dx + \int_2^4 \int_0^{4x-x^2} dy\, dx \\
&= \int_1^2 (4x - x^2 + 3x - 6)\, dx + \int_2^4 (4x - x^2)\, dx \\
&= \left[\frac{7x^2}{2} - \frac{x^3}{3} - 6x\right]_1^2 + \left[2x^2 - \frac{x^3}{3}\right]_2^4 \\
&= \left(14 - \frac{8}{3} - 12 - \frac{7}{2} + \frac{1}{3} + 6\right) + \left(32 - \frac{64}{3} - 8 + \frac{8}{3}\right) \\
&= \frac{15}{2}.
\end{aligned}$$

The area of the region is $15/2$ square units. Try checking this using the procedure for finding the area between two curves, as presented in Section 7.1. ■

At this point, you may be wondering why you would need iterated integrals. After all, you already know how to use conventional integration to find the area of a region in the plane. (For instance, compare the solution to Example 4 in this section with that given in Example 3 in Section 7.1.) The need for iterated integrals will become clear in the next section. In this section, primary attention is given to procedures for finding the limits of integration of the region of an iterated integral, and the following exercise set is designed to develop skill in this important procedure.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

14.1 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain what is meant by an iterated integral. How is it evaluated?
2. Sketch the region of integration for the iterated integral $\int_1^2 \int_0^{2-x} f(x, y)\, dy\, dx$.

Evaluating an Integral In Exercises 3–10, evaluate the integral.

3. $\int_0^x (2x - y)\, dy$
4. $\int_x^{x^2} \frac{y}{x}\, dy$
5. $\int_0^{\sqrt{4-x^2}} x^2 y\, dy$
6. $\int_{x^3}^{\sqrt{x}} (x^2 + 3y^2)\, dy$
7. $\int_{e^y}^{y} \frac{y \ln x}{x}\, dx, \quad y > 0$
8. $\int_{-\sqrt{1-y^2}}^{\sqrt{1-y^2}} (x^2 + y^2)\, dx$
9. $\int_0^{x^3} ye^{-y/x}\, dy$
10. $\int_y^{\pi/2} \sin^3 x \cos y\, dx$

Evaluating an Iterated Integral In Exercises 11–28, evaluate the iterated integral.

11. $\int_0^1 \int_0^2 (x + y)\, dy\, dx$
12. $\int_{-1}^1 \int_{-2}^2 (x^2 - y^2)\, dy\, dx$
13. $\int_0^{\pi/4} \int_0^1 y \cos x\, dy\, dx$
14. $\int_0^{\ln 4} \int_0^{\ln 3} e^{x+y}\, dy\, dx$
15. $\int_0^2 \int_0^{6x^2} x^3\, dy\, dx$
16. $\int_0^1 \int_0^y (6x + 5y^3)\, dx\, dy$
17. $\int_0^{\pi/2} \int_0^{\cos x} (1 + \sin x)\, dy\, dx$
18. $\int_1^4 \int_1^{\sqrt{x}} 2ye^{-x}\, dy\, dx$
19. $\int_0^1 \int_0^x \sqrt{1 - x^2}\, dy\, dx$
20. $\int_{-4}^4 \int_0^{x^2} \sqrt{64 - x^3}\, dy\, dx$
21. $\int_0^1 \int_0^{\sqrt{1-y^2}} (x + y)\, dx\, dy$
22. $\int_0^2 \int_{3y^2-6y}^{2y-y^2} 3y\, dx\, dy$
23. $\int_0^2 \int_0^{\sqrt{4-y^2}} \frac{2}{\sqrt{4 - y^2}}\, dx\, dy$
24. $\int_1^3 \int_0^y \frac{4}{x^2 + y^2}\, dx\, dy$
25. $\int_0^{\pi/2} \int_0^{2\cos\theta} r\, dr\, d\theta$
26. $\int_0^{\pi/4} \int_{\sqrt{3}}^{\sqrt{3}\cos\theta} r\, dr\, d\theta$
27. $\int_0^{\pi/2} \int_0^{\sin\theta} \theta r\, dr\, d\theta$
28. $\int_0^{\pi/4} \int_0^{\cos\theta} 3r^2 \sin\theta\, dr\, d\theta$

Evaluating an Improper Iterated Integral In Exercises 29–32, evaluate the improper iterated integral.

29. $\int_1^{\infty} \int_0^{1/x} y\, dy\, dx$
30. $\int_0^3 \int_0^{\infty} \frac{x^2}{1 + y^2}\, dy\, dx$
31. $\int_1^{\infty} \int_1^{\infty} \frac{1}{xy}\, dx\, dy$
32. $\int_0^{\infty} \int_0^{\infty} xye^{-(x^2+y^2)} dx\, dy$

Finding the Area of a Region In Exercises 33–36, use an iterated integral to find the area of the region.

33.


34.


35.


36.


Finding the Area of a Region In Exercises 37–42, use an iterated integral to find the area of the region bounded by the graphs of the equations.

37. $y = 9 - x^2, \quad y = 0$
38. $2x - 3y = 0, \quad x + y = 5, \quad y = 0$
39. $\sqrt{x} + \sqrt{y} = 2, \quad x = 0, \quad y = 0$
40. $y = x^{3/2}, \quad y = 2x$
41. $y = 4 - x^2, \quad y = x + 2$
42. $y = x, \quad y = 2x, \quad x = 2$

Changing the Order of Integration In Exercises 43–50, sketch the region R of integration and change the order of integration.

43. $\int_0^4 \int_0^y f(x, y)\, dx\, dy$
44. $\int_0^4 \int_{\sqrt{y}}^2 f(x, y)\, dx\, dy$
45. $\int_{-2}^2 \int_0^{\sqrt{4-x^2}} f(x, y)\, dy\, dx$
46. $\int_0^2 \int_0^{4-x^2} f(x, y)\, dy\, dx$
47. $\int_1^{10} \int_0^{\ln y} f(x, y)\, dx\, dy$
48. $\int_{-1}^2 \int_0^{e^{-x}} f(x, y)\, dy\, dx$
49. $\int_{-1}^1 \int_{x^2}^1 f(x, y)\, dy\, dx$
50. $\int_{-\pi/2}^{\pi/2} \int_0^{\cos x} f(x, y)\, dy\, dx$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Changing the Order of Integration **In Exercises 51–60, sketch the region R whose area is given by the iterated integral. Then change the order of integration and show that both orders yield the same area.**

51. $\int_0^1 \int_0^2 dy\,dx$

52. $\int_1^2 \int_2^4 dx\,dy$

53. $\int_0^1 \int_{2y}^2 dx\,dy$

54. $\int_0^9 \int_{\sqrt{x}}^3 dy\,dx$

55. $\int_0^1 \int_{-\sqrt{1-y^2}}^{\sqrt{1-y^2}} dx\,dy$

56. $\int_{-2}^2 \int_{-\sqrt{4-x^2}}^{\sqrt{4-x^2}} dy\,dx$

57. $\int_0^2 \int_0^x dy\,dx + \int_2^4 \int_0^{4-x} dy\,dx$

58. $\int_0^4 \int_0^{x/2} dy\,dx + \int_4^6 \int_0^{6-x} dy\,dx$

59. $\int_0^1 \int_{y^2}^{\sqrt[3]{y}} dx\,dy$

60. $\int_{-2}^2 \int_0^{4-y^2} dx\,dy$

Changing the Order of Integration **In Exercises 61–66, sketch the region of integration. Then evaluate the iterated integral. (*Hint:* Note that it is necessary to change the order of integration.)**

61. $\int_0^2 \int_x^2 x\sqrt{1+y^3}\,dy\,dx$

62. $\int_0^4 \int_{\sqrt{x}}^2 \frac{3}{2+y^3}\,dy\,dx$

63. $\int_0^1 \int_{2x}^2 4e^{y^2}\,dy\,dx$

64. $\int_0^2 \int_x^2 e^{-y^2}\,dy\,dx$

65. $\int_0^1 \int_y^1 \sin x^2\,dx\,dy$

66. $\int_0^2 \int_{y^2}^4 \sqrt{x}\sin x\,dx\,dy$

Exploring Concepts

67. Write an iterated integral that represents the area of a circle of radius 5 centered at the origin. Verify that your integral produces the correct area.

68. Express the area of the region bounded by $x = \sqrt{4-4y^2}$, $y = 1$, and $x = 2$ in at least two different ways, one of which is an iterated integral. Do not find the area of the region.

69. Determine whether each expression represents the area of the shaded region (see figure).

(a) $\int_0^5 \int_y^{\sqrt{50-y^2}} dy\,dx$ (b) $\int_0^5 \int_x^{\sqrt{50-x^2}} dy\,dx$

(c) $\int_0^5 \int_0^y dx\,dy + \int_5^{5\sqrt{2}} \int_0^{\sqrt{50-y^2}} dx\,dy$



70. HOW DO YOU SEE IT? Use each order of integration to write an iterated integral that represents the area of the region R (see figure).

(a) Area $= \iint dy\,dx$

(b) Area $= \iint dy\,dx$



Evaluating an Iterated Integral **In Exercises 71–78, use a graphing utility to evaluate the iterated integral.**

71. $\int_0^2 \int_{x^2}^{2x} (x^3 + 3y^2)\,dy\,dx$

72. $\int_0^a \int_0^{a-x} (x^2 + y^2)\,dy\,dx$

73. $\int_0^1 \int_y^{2y} \sin(x+y)\,dx\,dy$

74. $\int_0^2 \int_0^{4-x^2} e^{xy}\,dy\,dx$

75. $\int_0^4 \int_0^y \frac{2}{(x+1)(y+1)}\,dx\,dy$

76. $\int_0^2 \int_x^2 \sqrt{16 - x^3 - y^3}\,dy\,dx$

77. $\int_0^{2\pi} \int_0^{1+\cos\theta} 6r^2\cos\theta\,dr\,d\theta$

78. $\int_0^{\pi/2} \int_0^{1+\sin\theta} 15\theta r\,dr\,d\theta$

Comparing Different Orders of Integration **In Exercises 79 and 80, (a) sketch the region of integration, (b) change the order of integration, and (c) use a graphing utility to show that both orders yield the same value.**

79. $\int_0^2 \int_{y^3}^{4\sqrt{2y}} (x^2y - xy^2)\,dx\,dy$

80. $\int_0^2 \int_{\sqrt{4-x^2}}^{4-(x^2/4)} \frac{xy}{x^2+y^2+1}\,dy\,dx$

True or False? **In Exercises 81 and 82, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

81. $\int_a^b \int_c^d f(x,y)\,dy\,dx = \int_c^d \int_a^b f(x,y)\,dx\,dy$

82. $\int_0^1 \int_0^x f(x,y)\,dy\,dx = \int_0^1 \int_0^y f(x,y)\,dx\,dy$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

14.2 Double Integrals and Volume

GO DIGITAL

- **Use a double integral to represent the volume of a solid region and use properties of double integrals.**
- **Evaluate a double integral as an iterated integral.**
- **Find the average value of a function over a region.**

Double Integrals and Volume of a Solid Region



Figure 14.8

You already know that a definite integral over an *interval* uses a limit process to assign measures to quantities such as area, volume, arc length, and mass. In this section, you will use a similar process to define the **double integral** of a function of two variables over a *region in the plane*.

Consider a continuous function f such that $f(x, y) \geq 0$ for all (x, y) in a region R in the xy-plane. The goal is to find the volume of the solid region lying between the surface given by

$z = f(x, y)$ Surface lying above the xy-plane

and the xy-plane, as shown in Figure 14.8. You can begin by superimposing a rectangular grid over the region, as shown in Figure 14.9. The rectangles lying entirely within R form an **inner partition** Δ, whose **norm** $\|\Delta\|$ is defined as the length of the longest diagonal of the n rectangles. Next, choose a point (x_i, y_i) in each rectangle and form the rectangular prism whose height is

$f(x_i, y_i)$ Height of ith prism

as shown in Figure 14.10. Because the area of the ith rectangle is

ΔA_i Area of ith rectangle

it follows that the volume of the ith prism is

$f(x_i, y_i)\,\Delta A_i$ Volume of ith prism

and you can approximate the volume of the solid region by the Riemann sum of the volumes of all n prisms,

$$\sum_{i=1}^{n} f(x_i, y_i)\,\Delta A_i$$ Riemann sum

as shown in Figure 14.11. This approximation can be improved by tightening the mesh of the grid to form smaller and smaller rectangles, as shown in Example 1.



The rectangles lying within R form an inner partition of R.
Figure 14.9



Rectangular prism whose base has an area of ΔA_i and whose height is $f(x_i, y_i)$
Figure 14.10



Volume approximated by rectangular prisms
Figure 14.11

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 1 Approximating the Volume of a Solid

Approximate the volume of the solid lying between the paraboloid

$$f(x, y) = 1 - \frac{1}{2}x^2 - \frac{1}{2}y^2$$

and the square region R given by $0 \le x \le 1, 0 \le y \le 1$. Use a partition made up of squares whose sides have a length of $\frac{1}{4}$.

Solution Begin by forming the specified partition of R. For this partition, it is convenient to choose the centers of the subregions as the points at which to evaluate $f(x, y)$.

$$\begin{array}{cccc} \left(\frac{1}{8}, \frac{1}{8}\right) & \left(\frac{1}{8}, \frac{3}{8}\right) & \left(\frac{1}{8}, \frac{5}{8}\right) & \left(\frac{1}{8}, \frac{7}{8}\right) \\ \left(\frac{3}{8}, \frac{1}{8}\right) & \left(\frac{3}{8}, \frac{3}{8}\right) & \left(\frac{3}{8}, \frac{5}{8}\right) & \left(\frac{3}{8}, \frac{7}{8}\right) \\ \left(\frac{5}{8}, \frac{1}{8}\right) & \left(\frac{5}{8}, \frac{3}{8}\right) & \left(\frac{5}{8}, \frac{5}{8}\right) & \left(\frac{5}{8}, \frac{7}{8}\right) \\ \left(\frac{7}{8}, \frac{1}{8}\right) & \left(\frac{7}{8}, \frac{3}{8}\right) & \left(\frac{7}{8}, \frac{5}{8}\right) & \left(\frac{7}{8}, \frac{7}{8}\right) \end{array}$$

Because the area of each square is $\Delta A_i = \frac{1}{16}$, you can approximate the volume by the sum

$$\sum_{i=1}^{16} f(x_i, y_i)\,\Delta A_i = \sum_{i=1}^{16} \left(1 - \frac{1}{2}x_i^2 - \frac{1}{2}y_i^2\right)\left(\frac{1}{16}\right) \approx 0.672.$$

This approximation is shown graphically in Figure 14.12. The exact volume of the solid is $\frac{2}{3}$ (see Example 2).



Figure 14.12

REMARK In Example 1, to obtain a better approximation, use a finer partition. For instance, using a partition of squares with sides of length $1/10$, the approximation is 0.668.

In Example 1, note that by using finer partitions, you obtain better approximations of the volume. This observation suggests that you could obtain the exact volume by taking a limit. That is,

$$\text{Volume} = \lim_{\|\Delta\| \to 0} \sum_{i=1}^{n} f(x_i, y_i)\,\Delta A_i.$$

The precise meaning of this limit is that the limit is equal to L if for every $\varepsilon > 0$, there exists a $\delta > 0$ such that

$$\left| L - \sum_{i=1}^{n} f(x_i, y_i)\,\Delta A_i \right| < \varepsilon$$

for all partitions Δ of the plane region R (that satisfy $\|\Delta\| < \delta$) and for all possible choices of x_i and y_i in the ith region.

Using the limit of a Riemann sum to define volume is a special case of using the limit to define a **double integral.** The general case, however, does not require that the function be positive or continuous.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Definition of Double Integral

If f is defined on a closed, bounded region R in the xy-plane, then the **double integral of f over R** is

$$\iint_R f(x, y)\, dA = \lim_{\|\Delta\| \to 0} \sum_{i=1}^{n} f(x_i, y_i)\, \Delta A_i$$

provided the limit exists. If the limit exists, then f is **integrable** over R.

Having defined a double integral, you will see that a definite integral is occasionally referred to as a **single integral.**

Sufficient conditions for the double integral of f on the region R to exist are that R can be written as a union of a finite number of nonoverlapping subregions (see Figure 14.13) that are vertically or horizontally simple *and* that f is continuous on the region R. This means that the intersection of two nonoverlapping regions is a set that has an area of 0. In Figure 14.13, the area of the line segment common to R_1 and R_2 is 0.

A double integral can be used to find the volume of a solid region that lies between the xy-plane and the surface given by $z = f(x, y)$.



The two regions R_1 and R_2 are nonoverlapping.
Figure 14.13

Volume of a Solid Region

If f is integrable over a plane region R and $f(x, y) \geq 0$ for all (x, y) in R, then the volume of the solid region that lies above R and below the graph of f is

$$V = \iint_R f(x, y)\, dA.$$

Double integrals share many properties of single integrals.

THEOREM 14.1 Properties of Double Integrals

Let f and g be continuous over a closed, bounded plane region R, and let c be a constant.

1. $\displaystyle\iint_R cf(x, y)\, dA = c\iint_R f(x, y)\, dA$
2. $\displaystyle\iint_R [f(x, y) \pm g(x, y)]\, dA = \iint_R f(x, y)\, dA \pm \iint_R g(x, y)\, dA$
3. $\displaystyle\iint_R f(x, y)\, dA \geq 0, \quad \text{if } f(x, y) \geq 0$
4. $\displaystyle\iint_R f(x, y)\, dA \geq \iint_R g(x, y)\, dA, \quad \text{if } f(x, y) \geq g(x, y)$
5. $\displaystyle\iint_R f(x, y)\, dA = \iint_{R_1} f(x, y)\, dA + \iint_{R_2} f(x, y)\, dA$, where R is the union of two nonoverlapping subregions R_1 and R_2.

Exploration

The entries in the table represent the depths (in yards) of earth at the centers of the squares in the figure below.

x \ y	10	20	30
10	100	90	70
20	70	70	40
30	50	50	40
40	40	50	30



Approximate the number of cubic yards of earth in the first octant. (This exploration was submitted by Robert Vojack.)

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 14.14

GO DIGITAL



Triangular cross section

Figure 14.15

Evaluation of Double Integrals

Normally, the first step in evaluating a double integral is to rewrite it as an iterated integral. To show how this is done, a geometric model of a double integral is used as the volume of a solid.

Consider the solid region bounded by the plane $z = f(x, y) = 2 - x - 2y$ and the three coordinate planes, as shown in Figure 14.14. Each vertical cross section taken parallel to the yz-plane is a triangular region whose base has a length of $y = (2 - x)/2$ and whose height is $z = 2 - x$. This implies that for a fixed value of x, the area of the triangular cross section is

$$A(x) = \frac{1}{2}(\text{base})(\text{height}) = \frac{1}{2}\left(\frac{2 - x}{2}\right)(2 - x) = \frac{(2 - x)^2}{4}.$$

By the formula for the volume of a solid with known cross sections (see Section 7.2), the volume of the solid is

$$\begin{aligned}
\text{Volume} &= \int_a^b A(x)\,dx && \text{Formula for volume} \\
&= \int_0^2 \frac{(2 - x)^2}{4}\,dx && \text{Substitute.} \\
&= -\frac{(2 - x)^3}{12}\Big]_0^2 && \text{Integrate with respect to } x. \\
&= \frac{2}{3}. && \text{Volume of solid region (See Figure 14.14.)}
\end{aligned}$$

This procedure works no matter how $A(x)$ is obtained. In particular, you can find $A(x)$ by integration, as shown in Figure 14.15. That is, you consider x to be constant and integrate $z = 2 - x - 2y$ from 0 to $(2 - x)/2$ to obtain

$$\begin{aligned}
A(x) &= \int_0^{(2-x)/2} (2 - x - 2y)\,dy && \text{Apply formula for area.} \\
&= \left[(2 - x)y - y^2\right]_0^{(2-x)/2} && \text{Integrate with respect to } y. \\
&= \frac{(2 - x)^2}{4}. && \text{Area of triangular cross section (See Figure 14.15.)}
\end{aligned}$$

Combining these results, you have the *iterated integral*

$$\text{Volume} = \int_R\int f(x, y)\,dA = \int_0^2 \int_0^{(2-x)/2} (2 - x - 2y)\,dy\,dx.$$

To understand this procedure better, it helps to imagine the integration as two sweeping motions. For the inner integration, a vertical line sweeps out the area of a cross section. For the outer integration, the triangular cross section sweeps out the volume, as shown in Figure 14.16.



Integrate with respect to y to obtain the area of the cross section.

Integrate with respect to x to obtain the volume of the solid.

Figure 14.16

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The next theorem was proved by the Italian mathematician Guido Fubini (1879–1943). The theorem states that if R is a vertically or horizontally simple region and f is continuous on R, then the double integral of f on R is equal to an iterated integral.

THEOREM 14.2 Fubini's Theorem

Let f be continuous on a plane region R.

1. If R is defined by $a \le x \le b$ and $g_1(x) \le y \le g_2(x)$, where g_1 and g_2 are continuous on $[a, b]$, then
$$\iint_R f(x, y)\, dA = \int_a^b \int_{g_1(x)}^{g_2(x)} f(x, y)\, dy\, dx.$$
2. If R is defined by $c \le y \le d$ and $h_1(y) \le x \le h_2(y)$, where h_1 and h_2 are continuous on $[c, d]$, then
$$\iint_R f(x, y)\, dA = \int_c^d \int_{h_1(y)}^{h_2(y)} f(x, y)\, dx\, dy.$$

EXAMPLE 2 Evaluating a Double Integral as an Iterated Integral

Evaluate
$$\iint_R \left(1 - \frac{1}{2}x^2 - \frac{1}{2}y^2\right) dA$$
where R is the region given by
$$0 \le x \le 1, \quad 0 \le y \le 1.$$



Solution Because the region R is a square, it is both vertically and horizontally simple, and you can use either order of integration. Choose $dy\, dx$ by placing a vertical representative rectangle in the region (see the figure at the right). This produces the following.

$$\begin{aligned}
\iint_R \left(1 - \frac{1}{2}x^2 - \frac{1}{2}y^2\right) dA &= \int_0^1 \int_0^1 \left(1 - \frac{1}{2}x^2 - \frac{1}{2}y^2\right) dy\, dx \\
&= \int_0^1 \left[\left(1 - \frac{1}{2}x^2\right)y - \frac{y^3}{6}\right]_0^1 dx \\
&= \int_0^1 \left(\frac{5}{6} - \frac{1}{2}x^2\right) dx \\
&= \left[\frac{5}{6}x - \frac{x^3}{6}\right]_0^1 \\
&= \frac{2}{3}
\end{aligned}$$

The double integral evaluated in Example 2 represents the volume of the solid region approximated in Example 1. Note that the approximation obtained in Example 1 is quite good $\left(0.672 \text{ vs. } \frac{2}{3}\right)$, even though you used a partition consisting of only 16 squares. The error resulted because the centers of the square subregions were used as the points in the approximation. This is comparable to the Midpoint Rule approximation of a single integral.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploration

Volume of a Paraboloid Sector The solid in Example 3 has an elliptical (not a circular) base. Consider the region bounded by the circular paraboloid

$z = a^2 - x^2 - y^2, \quad a > 0$

and the xy-plane. How many ways of finding the volume of this solid do you now know? For instance, you could use the disk method to find the volume as a solid of revolution. Does each method involve integration?



The difficulty of evaluating a single integral $\int_a^b f(x)\,dx$ usually depends on the function f, not on the interval $[a, b]$. This is a major difference between single and double integrals. In the next example, you will integrate a function similar to the one in Examples 1 and 2. Notice that a change in the region R produces a much more difficult integration problem.

EXAMPLE 3 Finding Volume by a Double Integral

Find the volume of the solid region bounded by the paraboloid $z = 4 - x^2 - 2y^2$ and the xy-plane, as shown in Figure 14.17(a).

Solution By letting $z = 0$, you can see that the base of the region in the xy-plane is the ellipse $x^2 + 2y^2 = 4$, as shown in Figure 14.17(b). This plane region is both vertically and horizontally simple, so the order $dy\,dx$ is appropriate.

Variable bounds for y: $-\sqrt{\dfrac{4 - x^2}{2}} \le y \le \sqrt{\dfrac{4 - x^2}{2}}$

Constant bounds for x: $-2 \le x \le 2$

The volume is

$$V = \int_{-2}^{2}\int_{-\sqrt{(4-x^2)/2}}^{\sqrt{(4-x^2)/2}} (4 - x^2 - 2y^2)\,dy\,dx \qquad \text{See Figure 14.17(b).}$$

$$= \int_{-2}^{2}\left[(4 - x^2)y - \frac{2y^3}{3}\right]_{-\sqrt{(4-x^2)/2}}^{\sqrt{(4-x^2)/2}} dx$$

$$= \frac{4}{3\sqrt{2}}\int_{-2}^{2}(4 - x^2)^{3/2}\,dx$$

$$= \frac{4}{3\sqrt{2}}\int_{-\pi/2}^{\pi/2} 16\cos^4\theta\,d\theta \qquad x = 2\sin\theta$$

$$= \frac{64}{3\sqrt{2}}(2)\int_{0}^{\pi/2}\cos^4\theta\,d\theta$$

$$= \frac{128}{3\sqrt{2}}\left(\frac{3\pi}{16}\right) \qquad \text{Wallis's Formula}$$

$$= 4\sqrt{2}\pi.$$

REMARK In Example 3, note the usefulness of Wallis's Formula to evaluate $\int_0^{\pi/2}\cos^n\theta\,d\theta$. You may want to review this formula in Section 8.3.



(a)



(b)

Figure 14.17

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

In Examples 2 and 3, the problems could be solved with either order of integration because the regions were both vertically and horizontally simple. Moreover, had you used the order $dx\,dy$, you would have obtained integrals of comparable difficulty. There are, however, some occasions when one order of integration is much more convenient than the other. Example 4 shows such a case.

EXAMPLE 4 Comparing Different Orders of Integration

See LarsonCalculus.com for an interactive version of this type of example.

Find the volume of the solid region bounded by the surface

$$f(x, y) = e^{-x^2}$$ Surface

and the planes $z = 0$, $y = 0$, $y = x$, and $x = 1$, as shown in Figure 14.18.



Base is bounded by $y = 0$, $y = x$, and $x = 1$.

Figure 14.18

Solution The base of the solid region in the xy-plane is bounded by the lines $y = 0$, $x = 1$, and $y = x$. The two possible orders of integration are shown in Figure 14.19.



Figure 14.19

By setting up the corresponding iterated integrals, you can determine that the order $dx\,dy$ requires the antiderivative

$$\int e^{-x^2}\,dx$$

which is not an elementary function. On the other hand, the order $dy\,dx$ produces

$$\begin{aligned}
\int_0^1 \int_0^x e^{-x^2}\,dy\,dx &= \int_0^1 e^{-x^2} y \Big]_0^x\,dx && \text{Integrate with respect to } y. \\
&= \int_0^1 x e^{-x^2}\,dx \\
&= -\frac{1}{2} e^{-x^2} \Big]_0^1 && \text{Integrate with respect to } x. \\
&= -\frac{1}{2}\left(\frac{1}{e} - 1\right) \\
&= \frac{e - 1}{2e} && \text{Volume of solid region (See Figure 14.18.)} \\
&\approx 0.316.
\end{aligned}$$

TECHNOLOGY Use a graphing utility to evaluate the iterated integral in Example 4.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 5 Volume of a Region Bounded by Two Surfaces

Find the volume of the solid region bounded above by the paraboloid

$$z = 1 - x^2 - y^2$$ Paraboloid

and below by the plane

$$z = 1 - y$$ Plane

as shown in Figure 14.20.



Figure 14.20



R: $0 \le y \le 1$
$-\sqrt{y - y^2} \le x \le \sqrt{y - y^2}$

Figure 14.21

Solution Equating z-values, you can determine that the intersection of the two surfaces occurs on the right circular cylinder given by

$$1 - y = 1 - x^2 - y^2 \quad \Rightarrow \quad x^2 = y - y^2.$$

So, the region R in the xy-plane is a circle, as shown in Figure 14.21. Because the volume of the solid region is the difference between the volume under the paraboloid and the volume under the plane, you have

$$\begin{aligned}
\text{Volume} &= (\text{volume under paraboloid}) - (\text{volume under plane}) \\
&= \int_0^1 \int_{-\sqrt{y-y^2}}^{\sqrt{y-y^2}} (1 - x^2 - y^2)\, dx\, dy - \int_0^1 \int_{-\sqrt{y-y^2}}^{\sqrt{y-y^2}} (1 - y)\, dx\, dy \\
&= \int_0^1 \int_{-\sqrt{y-y^2}}^{\sqrt{y-y^2}} (y - y^2 - x^2)\, dx\, dy \\
&= \int_0^1 \left[(y - y^2)x - \frac{x^3}{3} \right]_{-\sqrt{y-y^2}}^{\sqrt{y-y^2}} dy \\
&= \frac{4}{3} \int_0^1 (y - y^2)^{3/2}\, dy \\
&= \left(\frac{4}{3}\right)\left(\frac{1}{8}\right) \int_0^1 [1 - (2y - 1)^2]^{3/2}\, dy \\
&= \frac{1}{6} \int_{-\pi/2}^{\pi/2} \frac{\cos^4 \theta}{2}\, d\theta \qquad 2y - 1 = \sin\theta \\
&= \frac{1}{6} \int_0^{\pi/2} \cos^4 \theta\, d\theta \\
&= \left(\frac{1}{6}\right)\left(\frac{3\pi}{16}\right) \qquad \text{Wallis's Formula} \\
&= \frac{\pi}{32}.
\end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Average Value of a Function

Recall from Section 4.4 that for a function f in one variable, the average value of f on the interval $[a, b]$ is

$$\frac{1}{b-a}\int_a^b f(x)\,dx.$$

Given a function f in two variables, you can find the average value of f over the plane region R as shown in the following definition.

Definition of the Average Value of a Function Over a Region

If f is integrable over the plane region R, then the **average value** of f over R is

$$\text{Average value} = \frac{1}{A}\iint_R f(x, y)\,dA$$

where A is the area of R.

EXAMPLE 6 **Finding the Average Value of a Function**

Find the average value of

$$f(x, y) = \frac{1}{2}xy$$

over the plane region R, where R is a rectangle with vertices

$$(0, 0), (4, 0), (4, 3), \quad \text{and} \quad (0, 3).$$

Solution The area of the rectangular region R is

$$A = (4)(3) = 12$$

as shown in Figure 14.22. The bounds for x are

$$0 \le x \le 4$$

and the bounds for y are

$$0 \le y \le 3.$$

So, the average value is

$$\begin{aligned}
\text{Average value} &= \frac{1}{A}\iint_R f(x, y)\,dA \\
&= \frac{1}{12}\int_0^4\int_0^3 \frac{1}{2}xy\,dy\,dx \\
&= \frac{1}{12}\int_0^4 \frac{1}{4}xy^2\Big]_0^3\,dx \\
&= \left(\frac{1}{12}\right)\left(\frac{9}{4}\right)\int_0^4 x\,dx \\
&= \frac{3}{16}\left[\frac{1}{2}x^2\right]_0^4 \\
&= \left(\frac{3}{16}\right)(8) \\
&= \frac{3}{2}.
\end{aligned}$$



Figure 14.22

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

14.2 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe the process of using an inner partition to approximate the volume of a solid region lying above the xy-plane. How can the approximation be improved?
2. Explain the benefit of Fubini's Theorem when evaluating a double integral.

Approximation **In Exercises 3–6, approximate the integral $\int_R\int f(x,y)\,dA$ by dividing the rectangle R with vertices $(0,0)$, $(4,0)$, $(4,2)$, and $(0,2)$ into eight equal squares and finding the sum $\sum_{i=1}^{8} f(x_i,y_i)\,\Delta A_i$, where (x_i,y_i) is the center of the ith square. Evaluate the iterated integral and compare it with the approximation.**

3. $\int_0^4\int_0^2 (x+y)\,dy\,dx$
4. $\frac{1}{2}\int_0^4\int_0^2 x^2y\,dy\,dx$
5. $\int_0^4\int_0^2 (x^2+y^2)\,dy\,dx$
6. $\int_0^4\int_0^2 \frac{1}{(x+1)(y+1)}\,dy\,dx$

Evaluating a Double Integral **In Exercises 7–12, sketch the region R and evaluate the iterated integral $\int_R\int f(x,y)\,dA$.**

7. $\int_0^2\int_0^1 (1-4x+8y)\,dy\,dx$
8. $\int_0^{\pi}\int_0^{\pi/2} \sin^2 x\cos^2 y\,dy\,dx$
9. $\int_0^6\int_{y/2}^3 (x+y)\,dx\,dy$
10. $\int_0^4\int_{y/2}^{\sqrt{y}} x^2y^2\,dx\,dy$
11. $\int_{-3}^3\int_{-\sqrt{9-x^2}}^{\sqrt{9-x^2}} (x+y)\,dy\,dx$
12. $\int_0^1\int_{y-1}^0 e^{x+y}\,dx\,dy + \int_0^1\int_0^{1-y} e^{x+y}\,dx\,dy$

Evaluating a Double Integral **In Exercises 13–20, set up integrals for both orders of integration. Use the more convenient order to evaluate the integral over the plane region R.**

13. $\int_R\int xy\,dA$

R: rectangle with vertices $(0,0)$, $(0,5)$, $(3,5)$, $(3,0)$

14. $\int_R\int \sin x\sin y\,dA$

R: rectangle with vertices $(-\pi,0)$, $(\pi,0)$, $(\pi,\pi/2)$, $(-\pi,\pi/2)$

15. $\int_R\int \frac{y}{x^2+y^2}\,dA$

R: trapezoid bounded by $y=x$, $y=2x$, $x=1$, $x=2$

16. $\int_R\int xe^y\,dA$

R: triangle bounded by $y=4-x$, $y=0$, $x=0$

17. $\int_R\int -2y\,dA$

R: region bounded by $y=4-x^2$, $y=4-x$

18. $\int_R\int \frac{y}{1+x^2}\,dA$

R: region bounded by $y=0$, $y=\sqrt{x}$, $x=4$

19. $\int_R\int x\,dA$

R: sector of a circle in the first quadrant bounded by $y=\sqrt{25-x^2}$, $3x-4y=0$, $y=0$

20. $\int_R\int (x^2+y^2)\,dA$

R: semicircle bounded by $y=\sqrt{4-x^2}$, $y=0$

Finding Volume **In Exercises 21–26, use a double integral to find the volume of the indicated solid.**

21.



$0 \le x \le 4$
$0 \le y \le 2$

22.



$0 \le x \le 4$
$0 \le y \le 2$

23.



24.



25.



26.



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding Volume **In Exercises 27 and 28, use an improper double integral to find the volume of the indicated solid.**

27.



28.



Finding Volume **In Exercises 29–34, set up and evaluate a double integral to find the volume of the solid bounded by the graphs of the equations.**

29. $z = xy,\ z = 0,\ y = x^3,\ x = 1,$ first octant

30. $z = 0,\ z = x^2,\ x = 0,\ x = 2,\ y = 0,\ y = 4$

31. $z = x + y,\ x^2 + y^2 = 4,$ first octant

32. $z = \dfrac{1}{1 + y^2},\ x = 0,\ x = 2,\ y \ge 0$

33. $y = 4 - x^2,\ z = 4 - x^2,$ first octant

34. $x^2 + z^2 = 1,\ y^2 + z^2 = 1,$ first octant

Volume of a Region Bounded by Two Surfaces **In Exercises 35–40, set up a double integral to find the volume of the solid region bounded by the graphs of the equations. Do not evaluate the integral.**

35.



36.



37. $z = x^2 + y^2,\ x^2 + y^2 = 4,\ z = 0$

38. $z = \sin^2 x,\ z = 0,\ 0 \le x \le \pi,\ 0 \le y \le 5$

39. $z = x^2 + 2y^2,\ z = 4y$

40. $z = x^2 + y^2,\ z = 18 - x^2 - y^2$

Finding Volume Using Technology **In Exercises 41–44, use a graphing utility to find the volume of the solid bounded by the graphs of the equations.**

41. $z = 9 - x^2 - y^2,\ z = 0$

42. $x^2 = 9 - y,\ z^2 = 9 - y,$ first octant

43. $z = \dfrac{2}{1 + x^2 + y^2},\ z = 0,\ y = 0,\ x = 0,\ y = -0.5x + 1$

44. $z = \ln(1 + x + y),\ z = 0,\ y = 0,\ x = 0,\ x = 4 - \sqrt{y}$

Evaluating an Iterated Integral **In Exercises 45–50, sketch the region of integration. Then evaluate the iterated integral, changing the order of integration if necessary.**

45. $\displaystyle\int_0^1 \int_{y/2}^{1/2} e^{-x^2}\,dx\,dy$

46. $\displaystyle\int_0^{\ln 10} \int_{e^x}^{10} \frac{1}{\ln y}\,dy\,dx$

47. $\displaystyle\int_{-2}^{2} \int_{-\sqrt{4-x^2}}^{\sqrt{4-x^2}} \sqrt{4 - y^2}\,dy\,dx$

48. $\displaystyle\int_0^3 \int_{y/3}^{1} \frac{1}{1 + x^4}\,dx\,dy$

49. $\displaystyle\int_0^2 \int_{2x}^{4} \sin y^2\,dy\,dx$

50. $\displaystyle\int_0^2 \int_{x^2/2}^{2} \sqrt{y} \cos y\,dy\,dx$

Average Value **In Exercises 51–56, find the average value of $f(x, y)$ over the plane region R.**

51. $f(x, y) = x$, R: rectangle with vertices $(0, 0), (4, 0), (4, 2), (0, 2)$

52. $f(x, y) = 2xy$, R: rectangle with vertices $(0, 1), (1, 1), (1, 6), (0, 6)$

53. $f(x, y) = x^2 + y^2$

R: square with vertices $(0, 0), (2, 0), (2, 2), (0, 2)$

54. $f(x, y) = \dfrac{1}{x + y}$, R: triangle with vertices $(0, 0), (1, 0), (1, 1)$

55. $f(x, y) = e^{x+y}$, R: triangle with vertices $(0, 0), (0, 1), (1, 1)$

56. $f(x, y) = \sin(x + y)$

R: rectangle with vertices $(0, 0), (\pi, 0), (\pi, \pi), (0, \pi)$

57. Average Production

The Cobb-Douglas production function for an automobile manufacturer is $f(x, y) = 100x^{0.6}y^{0.4}$, where x is the number of units of labor and y is the number of units of capital. Estimate the average production level when the number of units of labor x varies between 200 and 250 and the number of units of capital y varies between 300 and 325.

58. Average Temperature The temperature in degrees Celsius on the surface of a metal plate is

$$T(x, y) = 20 - 4x^2 - y^2$$

where x and y are measured in centimeters. Estimate the average temperature when x varies between 0 and 2 centimeters and y varies between 0 and 4 centimeters.

Exploring Concepts

59. Let R be a region in the xy-plane whose area is B. When $f(x, y) = k$ for every point (x, y) in R, what is the value of $\int_R \int f(x, y)\,dA$? Explain.

60. Let the plane region R be a unit circle and let the maximum value of f on R be 6. Is the greatest possible value of $\int_R \int f(x, y)\,dy\,dx$ equal to 6? Why or why not? If not, what is the greatest possible value?

Bert Hoferichter/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Probability A *joint density function* of the continuous random variables x and y is a function $f(x, y)$ satisfying the following properties.

(a) $f(x, y) \geq 0$ for all (x, y)

(b) $\int_{-\infty}^{\infty} \int_{-\infty}^{\infty} f(x, y)\, dA = 1$

(c) $P[(x, y) \in R] = \int_R \int f(x, y)\, dA$

In Exercises 61–64, show that the function is a joint density function and find the required probability.

61. $f(x, y) = \begin{cases} \frac{1}{3}, & 0 \leq x \leq 1, 1 \leq y \leq 4 \\ 0, & \text{elsewhere} \end{cases}$

$P(0 \leq x \leq 1, 1 \leq y \leq 3)$

62. $f(x, y) = \begin{cases} \frac{1}{5}xy, & 0 \leq x \leq 2, 0 \leq y \leq \sqrt{5} \\ 0, & \text{elsewhere} \end{cases}$

$P(0 \leq x \leq 1, 0 \leq y \leq 2)$

63. $f(x, y) = \begin{cases} \frac{1}{27}(9 - x - y), & 0 \leq x \leq 3, 3 \leq y \leq 6 \\ 0, & \text{elsewhere} \end{cases}$

$P(0 \leq x \leq 1, 3 \leq y \leq 6)$

64. $f(x, y) = \begin{cases} e^{-x-y}, & x \geq 0, y \geq 0 \\ 0, & \text{elsewhere} \end{cases}$

$P(0 \leq x \leq 1, x \leq y \leq 1)$

65. Proof Let f be a continuous function such that $0 \leq f(x, y) \leq 1$ over a region R of area 1. Prove that $0 \leq \int_R \int f(x, y)\, dA \leq 1$.

66. Finding Volume Find the volume of the solid in the first octant bounded by the coordinate planes and the plane

$$\frac{x}{a} + \frac{y}{b} + \frac{z}{c} = 1$$

where $a > 0$, $b > 0$, and $c > 0$.

67. Approximation The table shows values of a function f over a square region R. Divide the region into 16 equal squares and select (x_i, y_i) to be the point in the ith square closest to the origin. Approximate the value of the integral below. Compare this approximation with that obtained by using the point in the ith square farthest from the origin.

$$\int_0^4 \int_0^4 f(x, y)\, dy\, dx$$

x \ y	0	1	2	3	4
0	32	31	28	23	16
1	31	30	27	22	15
2	28	27	24	19	12
3	23	22	19	14	7
4	16	15	12	7	0

68. HOW DO YOU SEE IT? The figure below shows Erie County, New York. Let $f(x, y)$ represent the total annual snowfall at the point (x, y) in the county, where R is the county. Interpret each of the following.

(a) $\int_R \int f(x, y)\, dA$

(b) $\dfrac{\int_R \int f(x, y)\, dA}{\int_R \int dA}$

True or False? **In Exercises 69 and 70, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

69. The volume of the sphere $x^2 + y^2 + z^2 = 1$ is given by the integral

$$V = 8 \int_0^1 \int_0^1 \sqrt{1 - x^2 - y^2}\, dx\, dy.$$

70. If $f(x, y) \leq g(x, y)$ for all (x, y) in R, and both f and g are continuous over R, then $\int_R \int f(x, y)\, dA \leq \int_R \int g(x, y)\, dA$.

71. Maximizing a Double Integral Determine the region R in the xy-plane that maximizes the value of

$$\int_R \int (9 - x^2 - y^2)\, dA.$$

72. Minimizing a Double Integral Determine the region R in the xy-plane that minimizes the value of

$$\int_R \int (x^2 + y^2 - 4)\, dA.$$

73. Average Value Let

$$f(x) = \int_1^x e^{t^2}\, dt.$$

Find the average value of f on the interval $[0, 1]$.

74. Using Geometry Use a geometric argument to show that

$$\int_0^3 \int_0^{\sqrt{9-y^2}} \sqrt{9 - x^2 - y^2}\, dx\, dy = \frac{9\pi}{2}.$$

PUTNAM EXAM CHALLENGE

75. Evaluate $\int_0^a \int_0^b e^{\max\{b^2x^2,\, a^2y^2\}}\, dy\, dx$, where a and b are positive.

76. Show that if $\lambda > \frac{1}{2}$ there does not exist a real-valued function u such that for all x in the closed interval $0 \leq x \leq 1$, $u(x) = 1 + \lambda \int_x^1 u(y)u(y - x)\, dy$.

These problems were composed by the Committee on the Putnam Prize Competition. © The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

14.3 Change of Variables: Polar Coordinates

GO DIGITAL

Write and evaluate double integrals in polar coordinates.

Double Integrals in Polar Coordinates

Some double integrals are *much* easier to evaluate in polar form than in rectangular form. This is especially true for regions such as circles, cardioids, and rose curves, and for integrands that involve $x^2 + y^2$.

In Section 10.4, you learned that the polar coordinates (r, θ) of a point are related to the rectangular coordinates (x, y) of the point as follows.

$$x = r\cos\theta \quad \text{and} \quad y = r\sin\theta$$

$$r^2 = x^2 + y^2 \quad \text{and} \quad \tan\theta = \frac{y}{x}$$

EXAMPLE 1 **Using Polar Coordinates to Describe a Region**

Use polar coordinates to describe each region shown in Figure 14.23.



(a)



(b)



(c)

Figure 14.23

Solution

a. The region R is a quarter circle of radius 2. It can be described in polar coordinates as

$$R = \{(r, \theta):\ 0 \le r \le 2, \quad 0 \le \theta \le \pi/2\}.$$

b. The region R consists of all points between concentric circles of radii 1 and 3. It can be described in polar coordinates as

$$R = \{(r, \theta):\ 1 \le r \le 3, \quad 0 \le \theta \le 2\pi\}.$$

c. The region R is a cardioid with $a = b = 3$. It can be described in polar coordinates as

$$R = \{(r, \theta):\ 0 \le r \le 3 + 3\sin\theta, \quad 0 \le \theta \le 2\pi\}.$$

The regions in Example 1 are special cases of **polar sectors**

$$R = \{(r, \theta):\ r_1 \le r \le r_2, \quad \theta_1 \le \theta \le \theta_2\}$$ Polar sector

as shown in Figure 14.24.



Polar sector

Figure 14.24

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Polar grid superimposed over region R
Figure 14.25

To define a double integral of a continuous function $z = f(x, y)$ in polar coordinates, consider a region R bounded by the graphs of

$$r = g_1(\theta) \quad \text{and} \quad r = g_2(\theta)$$

and the lines $\theta = \alpha$ and $\theta = \beta$. Instead of partitioning R into small rectangles, use a partition of small polar sectors. On R, superimpose a polar grid made of rays and circular arcs, as shown in Figure 14.25. The polar sectors R_i lying entirely within R form an **inner polar partition** Δ, whose **norm** $\|\Delta\|$ is the length of the longest diagonal of the n polar sectors.

Consider a specific polar sector R_i, as shown in Figure 14.26. It can be shown (see Exercise 68) that the area of R_i is

$$\Delta A_i = r_i \, \Delta r_i \, \Delta\theta_i \qquad \text{Area of } R_i$$

where $\Delta r_i = r_2 - r_1$ and $\Delta\theta_i = \theta_2 - \theta_1$. This implies that the volume of the solid of height $f(r_i \cos\theta_i, r_i \sin\theta_i)$ above R_i is approximately

$$f(r_i \cos\theta_i, r_i \sin\theta_i) r_i \, \Delta r_i \, \Delta\theta_i$$

and you have

$$\iint_R f(x, y)\, dA \approx \sum_{i=1}^{n} f(r_i \cos\theta_i, r_i \sin\theta_i) r_i \, \Delta r_i \, \Delta\theta_i.$$

The sum on the right can be interpreted as a Riemann sum for

$$f(r \cos\theta, r \sin\theta) r.$$

The region R corresponds to a *horizontally simple* region S in the $r\theta$-plane, as shown in Figure 14.27. The polar sectors R_i correspond to rectangles S_i, and the area ΔA_i of S_i is $\Delta r_i \, \Delta\theta_i$. So, the right side of the equation corresponds to the double integral

$$\iint_S f(r \cos\theta, r \sin\theta) r \, dA.$$

From this, you can apply Theorem 14.2 to write

$$\begin{aligned} \iint_R f(x, y)\, dA &= \iint_S f(r \cos\theta, r \sin\theta) r \, dA \\ &= \int_\alpha^\beta \int_{g_1(\theta)}^{g_2(\theta)} f(r \cos\theta, r \sin\theta) r \, dr \, d\theta. \end{aligned}$$

This suggests the theorem on the next page, the proof of which is discussed in Section 14.8.



The polar sector R_i is the set of all points (r, θ) such that $r_1 \le r \le r_2$ and $\theta_1 \le \theta \le \theta_2$.
Figure 14.26



Horizontally simple region S
Figure 14.27

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

THEOREM 14.3 Change of Variables to Polar Form

Let R be a plane region consisting of all points $(x, y) = (r\cos\theta, r\sin\theta)$ satisfying the conditions $0 \le g_1(\theta) \le r \le g_2(\theta)$, $\alpha \le \theta \le \beta$, where $0 \le (\beta - \alpha) \le 2\pi$. If g_1 and g_2 are continuous on $[\alpha, \beta]$ and f is continuous on R, then

$$\iint_R f(x, y)\,dA = \int_\alpha^\beta \int_{g_1(\theta)}^{g_2(\theta)} f(r\cos\theta, r\sin\theta) r\,dr\,d\theta.$$

Exploration

Volume of a Paraboloid Sector In the Exploration on page 983, you were asked to summarize the different ways you know of finding the volume of the solid bounded by the paraboloid

$z = a^2 - x^2 - y^2, a > 0$

and the xy-plane. You now know another way. Use it to find the volume of the solid.

If $z = f(x, y)$ is nonnegative on R, then the integral in Theorem 14.3 can be interpreted as the volume of the solid region between the graph of f and the region R. When using the integral in Theorem 14.3, be certain not to omit the extra factor of r in the integrand.

The region R is restricted to two basic types, ***r*-simple** regions and ***θ*-simple** regions, as shown in Figure 14.28.



r-Simple region θ-Simple region

Figure 14.28

EXAMPLE 2 Evaluating a Double Polar Integral

Let R be the annular region lying between the two circles $x^2 + y^2 = 1$ and $x^2 + y^2 = 5$. Evaluate the integral

$$\iint_R (x^2 + y)\,dA.$$



Figure 14.29

Solution The polar boundaries are $1 \le r \le \sqrt{5}$ and $0 \le \theta \le 2\pi$, as shown in Figure 14.29. Furthermore, $x^2 = (r\cos\theta)^2$ and $y = r\sin\theta$. So, you have

$$\begin{aligned}
\iint_R (x^2 + y)\,dA &= \int_0^{2\pi}\int_1^{\sqrt{5}} (r^2\cos^2\theta + r\sin\theta) r\,dr\,d\theta \\
&= \int_0^{2\pi}\int_1^{\sqrt{5}} (r^3\cos^2\theta + r^2\sin\theta)\,dr\,d\theta \\
&= \int_0^{2\pi} \left(\frac{r^4}{4}\cos^2\theta + \frac{r^3}{3}\sin\theta\right)\Big]_1^{\sqrt{5}} d\theta \\
&= \int_0^{2\pi} \left(6\cos^2\theta + \frac{5\sqrt{5} - 1}{3}\sin\theta\right) d\theta \\
&= \int_0^{2\pi} \left(3 + 3\cos 2\theta + \frac{5\sqrt{5} - 1}{3}\sin\theta\right) d\theta \\
&= \left(3\theta + \frac{3\sin 2\theta}{2} - \frac{5\sqrt{5} - 1}{3}\cos\theta\right)\Big]_0^{2\pi} \\
&= 6\pi.
\end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

In Example 2, be sure to notice the factor of r with $dr\,d\theta$ in the integrand. This comes from the formula for the area of a polar sector. In differential notation, you can write

$$dA = r\,dr\,d\theta$$

which indicates that the area of a polar sector increases as you move away from the origin.



Figure 14.30

EXAMPLE 3 Change of Variables to Polar Coordinates

Use polar coordinates to find the volume of the solid region bounded above by the hemisphere

$$z = \sqrt{16 - x^2 - y^2}$$ Hemisphere forms upper surface.

and below by the circular region R given by

$$x^2 + y^2 \le 4$$ Circular region forms lower surface.

as shown in Figure 14.30.

Solution In Figure 14.30, R has the bounds

$$-\sqrt{4 - y^2} \le x \le \sqrt{4 - y^2}, \quad -2 \le y \le 2$$

and that $0 \le z \le \sqrt{16 - x^2 - y^2}$. In polar coordinates, the bounds are

$$0 \le r \le 2 \quad \text{and} \quad 0 \le \theta \le 2\pi$$

with height $z = \sqrt{16 - x^2 - y^2} = \sqrt{16 - r^2}$. Consequently, the volume V is

$$\begin{aligned}
V &= \int_R\int f(x, y)\,dA && \text{Formula for volume} \\
&= \int_0^{2\pi}\int_0^2 \sqrt{16 - r^2}\,r\,dr\,d\theta && \text{Polar coordinates} \\
&= -\frac{1}{3}\int_0^{2\pi} (16 - r^2)^{3/2}\Big]_0^2\,d\theta && \text{Integrate with respect to } r. \\
&= -\frac{1}{3}\int_0^{2\pi} \left(24\sqrt{3} - 64\right)d\theta \\
&= -\frac{8}{3}\left(3\sqrt{3} - 8\right)\theta\Big]_0^{2\pi} && \text{Integrate with respect to } \theta. \\
&= \frac{16\pi}{3}\left(8 - 3\sqrt{3}\right) \\
&\approx 46.979.
\end{aligned}$$

REMARK To see the benefit of polar coordinates in Example 3, evaluate the corresponding rectangular iterated integral

$$\int_{-2}^{2}\int_{-\sqrt{4-y^2}}^{\sqrt{4-y^2}} \sqrt{16 - x^2 - y^2}\,dx\,dy.$$

TECHNOLOGY Any graphing utility that can evaluate double integrals in rectangular coordinates can also evaluate double integrals in polar coordinates. The reason this is true is that once you have formed the iterated integral, its value is not changed by using different variables. In other words, when you use a graphing utility to evaluate

$$\int_0^{2\pi}\int_0^2 \sqrt{16 - x^2}\,x\,dx\,dy$$

you will obtain the same value as that obtained in Example 3.

Just as with rectangular coordinates, the double integral

$$\int_R\int dA$$

can be used to find the area of a region in the plane.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 14.31

GO DIGITAL

EXAMPLE 4 Finding Areas of Polar Regions

See LarsonCalculus.com for an interactive version of this type of example.

To use a double integral to find the area enclosed by the graph of $r = 3\cos 3\theta$, let R be one petal of the curve shown in Figure 14.31. This region is r-simple, and the boundaries are $-\pi/6 \le \theta \le \pi/6$ and $0 \le r \le 3\cos 3\theta$. So, the area of one petal is

$$\begin{aligned}
\frac{1}{3}A = \iint_R dA &= \int_{-\pi/6}^{\pi/6}\int_0^{3\cos 3\theta} r\,dr\,d\theta \\
&= \int_{-\pi/6}^{\pi/6} \frac{r^2}{2}\Big]_0^{3\cos 3\theta} d\theta \qquad \text{Integrate with respect to } r. \\
&= \frac{9}{2}\int_{-\pi/6}^{\pi/6} \cos^2 3\theta\,d\theta \\
&= \frac{9}{4}\int_{-\pi/6}^{\pi/6} (1 + \cos 6\theta)\,d\theta \\
&= \frac{9}{4}\left[\theta + \frac{1}{6}\sin 6\theta\right]_{-\pi/6}^{\pi/6} \qquad \text{Integrate with respect to } \theta. \\
&= \frac{3\pi}{4}.
\end{aligned}$$

So, the total area is $A = 9\pi/4$. ■

As illustrated in Example 4, the area of a region in the plane can be represented by

$$A = \int_\alpha^\beta \int_{g_1(\theta)}^{g_2(\theta)} r\,dr\,d\theta.$$

For $g_1(\theta) = 0$, you obtain

$$A = \int_\alpha^\beta \int_0^{g_2(\theta)} r\,dr\,d\theta = \int_\alpha^\beta \frac{r^2}{2}\Big]_0^{g_2(\theta)} d\theta = \frac{1}{2}\int_\alpha^\beta [g_2(\theta)]^2\,d\theta$$

which agrees with Theorem 10.13.

So far in this section, all of the examples of iterated integrals in polar form have been of the form

$$\int_\alpha^\beta \int_{g_1(\theta)}^{g_2(\theta)} f(r\cos\theta, r\sin\theta) r\,dr\,d\theta$$

in which the order of integration is with respect to r first. Sometimes you can obtain a simpler integration problem by integrating with respect to θ first.



θ-Simple region

Figure 14.32

EXAMPLE 5 Integrating with Respect to θ First

Find the area of the region bounded above by the spiral $r = \pi/(3\theta)$ and below by the polar axis, between $r = 1$ and $r = 2$.

Solution The region is shown in Figure 14.32. The polar boundaries for the region are

$$1 \le r \le 2 \quad \text{and} \quad 0 \le \theta \le \frac{\pi}{3r}.$$

So, the area of the region can be evaluated as follows.

$$A = \int_1^2 \int_0^{\pi/(3r)} r\,d\theta\,dr = \int_1^2 r\theta\Big]_0^{\pi/(3r)} dr = \int_1^2 \frac{\pi}{3}\,dr = \frac{\pi r}{3}\Big]_1^2 = \frac{\pi}{3}$$

■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

14.3 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

In Exercises 1 and 2, the region R for the integral $\int_R\int f(x, y)\,dA$ is shown. State whether you would use rectangular or polar coordinates to evaluate the integral.

1.



2.



3. Describe r-simple regions and θ-simple regions.

4. Sketch the region of integration represented by the double integral

$$\int_0^{2\pi}\int_3^6 f(r, \theta)r\,dr\,d\theta.$$

Describing a Region

In Exercises 5–8, use polar coordinates to describe the region shown.

5.



6.



7.



8.



Evaluating a Double Integral

In Exercises 9–16, evaluate the double integral $\int_R\int f(r, \theta)\,dA$ and sketch the region R.

9. $\displaystyle\int_0^{\pi}\int_0^{2\cos\theta} r\,dr\,d\theta$

10. $\displaystyle\int_0^{\pi/2}\int_0^{\sin\theta} r^2\,dr\,d\theta$

11. $\displaystyle\int_0^{2\pi}\int_0^{1} 6r^2\sin\theta\,dr\,d\theta$

12. $\displaystyle\int_0^{\pi/4}\int_0^{4} r^2\sin\theta\cos\theta\,dr\,d\theta$

13. $\displaystyle\int_0^{\pi/2}\int_1^{3} \sqrt{9 - r^2}\,r\,dr\,d\theta$

14. $\displaystyle\int_0^{\pi/2}\int_0^{3} re^{-r^2}\,dr\,d\theta$

15. $\displaystyle\int_0^{\pi/2}\int_0^{1+\sin\theta} \theta r\,dr\,d\theta$

16. $\displaystyle\int_0^{\pi/2}\int_0^{1-\cos\theta} (\sin\theta)r\,dr\,d\theta$

Converting to Polar Coordinates

In Exercises 17–26, evaluate the iterated integral by converting to polar coordinates.

17. $\displaystyle\int_0^{3}\int_0^{\sqrt{9-y^2}} y\,dx\,dy$

18. $\displaystyle\int_0^{2}\int_0^{\sqrt{4-x^2}} x\,dy\,dx$

19. $\displaystyle\int_{-2}^{2}\int_0^{\sqrt{4-x^2}} (x^2 + y^2)\,dy\,dx$

20. $\displaystyle\int_0^{1}\int_{-\sqrt{x-x^2}}^{\sqrt{x-x^2}} (x^2 + y^2)\,dy\,dx$

21. $\displaystyle\int_0^{1}\int_0^{\sqrt{1-x^2}} (x^2 + y^2)^{3/2}\,dy\,dx$

22. $\displaystyle\int_0^{2}\int_y^{\sqrt{8-y^2}} \sqrt{x^2 + y^2}\,dx\,dy$

23. $\displaystyle\int_0^{2}\int_0^{\sqrt{2x-x^2}} xy\,dy\,dx$

24. $\displaystyle\int_0^{4}\int_0^{\sqrt{4y-y^2}} x^2\,dx\,dy$

25. $\displaystyle\int_{-1}^{1}\int_0^{\sqrt{1-x^2}} \cos(x^2 + y^2)\,dy\,dx$

26. $\displaystyle\int_0^{\sqrt{6}}\int_0^{\sqrt{6-x^2}} \sin\sqrt{x^2 + y^2}\,dy\,dx$

Converting to Polar Coordinates

In Exercises 27 and 28, write the sum of the two iterated integrals as a single iterated integral by converting to polar coordinates. Evaluate the resulting iterated integral.

27. $\displaystyle\int_0^{2}\int_0^{x} \sqrt{x^2 + y^2}\,dy\,dx + \int_2^{2\sqrt{2}}\int_0^{\sqrt{8-x^2}} \sqrt{x^2 + y^2}\,dy\,dx$

28. $\displaystyle\int_0^{(5\sqrt{2})/2}\int_0^{x} xy\,dy\,dx + \int_{(5\sqrt{2})/2}^{5}\int_0^{\sqrt{25-x^2}} xy\,dy\,dx$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Converting to Polar Coordinates **In Exercises 29–32, use polar coordinates to set up and evaluate the double integral $\int_R\int f(x, y)\, dA$.**

29. $f(x, y) = x + y$

R: $x^2 + y^2 \le 36,\ x \ge 0,\ y \ge 0$

30. $f(x, y) = e^{-(x^2+y^2)/2}$

R: $x^2 + y^2 \le 25,\ x \ge 0$

31. $f(x, y) = \arctan\dfrac{y}{x}$

R: $x^2 + y^2 \ge 1,\ x^2 + y^2 \le 4,\ 0 \le y \le x$

32. $f(x, y) = 9 - x^2 - y^2$

R: $x^2 + y^2 \le 9,\ x \ge 0,\ y \ge 0$

Volume **In Exercises 33–38, use a double integral in polar coordinates to find the volume of the solid bounded by the graphs of the equations.**

33. $z = xy,\ x^2 + y^2 = 1,$ first octant

34. $z = x^2 + y^2 + 3,\ z = 0,\ x^2 + y^2 = 1$

35. $z = \sqrt{x^2 + y^2},\ z = 0,\ x^2 + y^2 = 25$

36. $z = \ln(x^2 + y^2),\ z = 0,\ x^2 + y^2 \ge 1,\ x^2 + y^2 \le 4$

37. Inside the hemisphere $z = \sqrt{16 - x^2 - y^2}$ and inside the cylinder $x^2 + y^2 - 4x = 0$

38. Inside the hemisphere $z = \sqrt{16 - x^2 - y^2}$ and outside the cylinder $x^2 + y^2 = 1$

39. Volume Use a double integral in polar coordinates to find a such that the volume inside the hemisphere

$z = \sqrt{16 - x^2 - y^2}$

and outside the cylinder $x^2 + y^2 = a^2$ is one-half the volume of the hemisphere.

40. Volume Use a double integral in polar coordinates to find the volume of a sphere of radius a.

Area **In Exercises 41–46, use a double integral to find the area of the shaded region.**

41.



42.



43.



44.



45.



46.



Area **In Exercises 47–52, sketch a graph of the region bounded by the graphs of the equations. Then use a double integral to find the area of the region.**

47. Inside the circle $r = 2\cos\theta$ and outside the circle $r = 1$

48. Inside the cardioid $r = 2 + 2\cos\theta$ and outside the circle $r = 1$

49. Inside the circle $r = 3\cos\theta$ and outside the cardioid $r = 1 + \cos\theta$

50. Inside the cardioid $r = 1 + \cos\theta$ and outside the circle $r = 3\cos\theta$

51. Inside the rose curve $r = 4\sin 3\theta$ and outside the circle $r = 2$

52. Inside the circle $r = 2$ and outside the cardioid $r = 2 - 2\cos\theta$

Exploring Concepts

53. Express the area of the region R in the figure using the sum of two double polar integrals. Then find the area of the region without using integrals.



54. Let R be the region bounded by the circle $x^2 + y^2 = 9$.

(a) Set up the integral $\displaystyle\int_R\int f(x, y)\, dA$.

(b) Convert the integral in part (a) to polar coordinates.

(c) Which integral would you choose to evaluate? Why?

55. Population

The population density of a city is approximated by the model

$f(x, y) = 4000e^{-0.01(x^2+y^2)}$

for the region $x^2 + y^2 \le 49$, where x and y are measured in miles. Integrate the density function over the indicated circular region to approximate the population of the city.

SergeyIT/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

56. HOW DO YOU SEE IT? Each figure shows a region of integration R for the double integral $\int_R\int f(x, y)\, dA$. For each region, state whether horizontal representative elements, vertical representative elements, or polar sectors would yield the easiest method for obtaining the limits of integration. Explain your reasoning.



57. Volume Determine the diameter of a hole that is drilled vertically through the center of the solid bounded by the graphs of the equations $z = 25e^{-(x^2+y^2)/4}$, $z = 0$, and $x^2 + y^2 = 16$ when one-tenth of the volume of the solid is removed.

58. Glacier

Horizontal cross sections of a piece of ice that broke from a glacier are in the shape of a quarter of a circle with a radius of approximately 50 feet. The base is divided into 20 subregions, as shown in the figure. At the center of each subregion, the height of the ice is measured, yielding the following points in cylindrical coordinates.

$\left(5, \frac{\pi}{16}, 7\right)$, $\left(15, \frac{\pi}{16}, 8\right)$, $\left(25, \frac{\pi}{16}, 10\right)$, $\left(35, \frac{\pi}{16}, 12\right)$, $\left(45, \frac{\pi}{16}, 9\right)$,
$\left(5, \frac{3\pi}{16}, 9\right)$, $\left(15, \frac{3\pi}{16}, 10\right)$, $\left(25, \frac{3\pi}{16}, 14\right)$, $\left(35, \frac{3\pi}{16}, 15\right)$, $\left(45, \frac{3\pi}{16}, 10\right)$,
$\left(5, \frac{5\pi}{16}, 9\right)$, $\left(15, \frac{5\pi}{16}, 11\right)$, $\left(25, \frac{5\pi}{16}, 15\right)$, $\left(35, \frac{5\pi}{16}, 18\right)$, $\left(45, \frac{5\pi}{16}, 14\right)$,
$\left(5, \frac{7\pi}{16}, 5\right)$, $\left(15, \frac{7\pi}{16}, 8\right)$, $\left(25, \frac{7\pi}{16}, 11\right)$, $\left(35, \frac{7\pi}{16}, 16\right)$, $\left(45, \frac{7\pi}{16}, 12\right)$

(a) Approximate the volume of the piece of ice.

(b) Ice weighs approximately 57 pounds per cubic foot. Approximate the weight of the piece of ice.

(c) There are 7.48 gallons of water per cubic foot. Approximate the number of gallons of water in the piece of ice.



Denis Burdin/Shutterstock.com

Approximation **In Exercises 59 and 60, use a graphing utility to approximate the iterated integral.**

59. $\int_{\pi/4}^{\pi/2}\int_0^5 r\sqrt{1 + r^3}\sin\sqrt{\theta}\, dr\, d\theta$

60. $\int_0^{\pi/4}\int_0^4 5re^{\sqrt{r\theta}}\, dr\, d\theta$

True or False? **In Exercises 61 and 62, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

61. If $\int_R\int f(r, \theta)\, dA > 0$, then $f(r, \theta) > 0$ for all (r, θ) in R.

62. If $f(r, \theta)$ is a constant function and the area of the region S is twice that of the region R, then

$$2\int_R\int f(r, \theta)\, dA = \int_S\int f(r, \theta)\, dA.$$

63. Probability The value of the integral

$$I = \int_{-\infty}^{\infty} e^{-x^2/2}\, dx$$

is required in the development of the normal probability density function.

(a) Use polar coordinates to evaluate the improper integral.

$$I^2 = \left(\int_{-\infty}^{\infty} e^{-x^2/2}\, dx\right)\left(\int_{-\infty}^{\infty} e^{-y^2/2}\, dy\right)$$
$$= \int_{-\infty}^{\infty}\int_{-\infty}^{\infty} e^{-(x^2+y^2)/2}\, dA$$

(b) Use the result of part (a) to determine I.

FOR FURTHER INFORMATION For more information on this problem, see the article "Integrating e^{-x^2} Without Polar Coordinates" by William Dunham in *Mathematics Teacher*. To view this article, go to *MathArticles.com*.

64. Evaluating Integrals Use the result of Exercise 63 and a change of variables to evaluate each integral. No integration is required.

(a) $\int_{-\infty}^{\infty} e^{-x^2}\, dx$ (b) $\int_{-\infty}^{\infty} e^{-4x^2}\, dx$

65. Think About It Consider the region R bounded by the graphs of $y = 2$, $y = 4$, $y = x$, and $y = \sqrt{3}x$ and the double integral $\int_R\int f(x, y)\, dA$. Determine the limits of integration when the region R is divided into (a) horizontal representative elements, (b) vertical representative elements, and (c) polar sectors.

66. Think About It Repeat Exercise 65 for a region R bounded by the graph of the equation $(x - 2)^2 + y^2 = 4$.

67. Probability Find k such that the function

$$f(x, y) = \begin{cases} ke^{-(x^2+y^2)}, & x \geq 0, y \geq 0 \\ 0, & \text{elsewhere} \end{cases}$$

is a probability density function. (*Hint:* Show that $\int_R\int f(x, y)\, dA = 1$.)

68. Area Show that the area A of the polar sector R (see figure) is $A = r\Delta r\Delta\theta$, where $r = (r_1 + r_2)/2$ is the average radius of R.



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

14.4 Center of Mass and Moments of Inertia

GO DIGITAL

- **Find the mass of a planar lamina using a double integral.**
- **Find the center of mass of a planar lamina using double integrals.**
- **Find moments of inertia using double integrals.**



Lamina of constant density ρ
Figure 14.33

Mass

Section 7.6 discussed several applications of integration involving a lamina of *constant* density ρ. For example, if the lamina corresponding to the region R, as shown in Figure 14.33, has a constant density ρ, then the mass of the lamina is given by

$$\text{Mass} = \rho A = \rho \iint_R dA = \iint_R \rho \, dA. \qquad \text{Constant density}$$

If not otherwise stated, a lamina is assumed to have a constant density. In this section, however, you will extend the definition of the term *lamina* to include thin plates of *variable* density. Double integrals can be used to find the mass of a lamina of variable density, where the density at (x, y) is given by the **density function ρ.**

Definition of Mass of a Planar Lamina of Variable Density

If ρ is a continuous density function on the lamina corresponding to a plane region R, then the mass m of the lamina is given by

$$m = \iint_R \rho(x, y) \, dA. \qquad \text{Variable density}$$

Density is normally expressed as mass per unit volume. For a planar lamina, however, density is mass per unit surface area.

EXAMPLE 1 Finding the Mass of a Planar Lamina

Find the mass of the triangular lamina with vertices $(0, 0)$, $(0, 3)$, and $(2, 3)$, given that the density at (x, y) is $\rho(x, y) = 2x + y$.



Lamina of variable density
$\rho(x, y) = 2x + y$
Figure 14.34

Solution As shown in Figure 14.34, region R has the boundaries $x = 0$, $y = 3$, and $y = 3x/2$ (or $x = 2y/3$). Therefore, the mass of the lamina is

$$\begin{aligned} m &= \iint_R (2x + y) \, dA \\ &= \int_0^3 \int_0^{2y/3} (2x + y) \, dx \, dy \\ &= \int_0^3 \left[x^2 + xy \right]_0^{2y/3} dy \qquad \text{Integrate with respect to } x. \\ &= \frac{10}{9} \int_0^3 y^2 \, dy \\ &= \frac{10}{9} \left[\frac{y^3}{3} \right]_0^3 \qquad \text{Integrate with respect to } y. \\ &= 10. \end{aligned}$$

In Figure 14.34, note that the planar lamina is shaded so that the darkest shading corresponds to the densest part. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Density at (x, y): $\rho(x, y) = k\sqrt{x^2 + y^2}$
Figure 14.35

EXAMPLE 2 Finding Mass by Polar Coordinates

Find the mass of the lamina corresponding to the first-quadrant portion of the circle

$$x^2 + y^2 = 4$$

where the density at the point (x, y) is proportional to the distance between the point and the origin, as shown in Figure 14.35.

Solution At any point (x, y), the density of the lamina is

$$\rho(x, y) = k\sqrt{(x - 0)^2 + (y - 0)^2}$$
$$= k\sqrt{x^2 + y^2}$$

where k is the constant of proportionality. Because $0 \le x \le 2$ and $0 \le y \le \sqrt{4 - x^2}$, the mass is given by

$$m = \int_R\int k\sqrt{x^2 + y^2}\, dA$$
$$= \int_0^2 \int_0^{\sqrt{4-x^2}} k\sqrt{x^2 + y^2}\, dy\, dx.$$

To simplify the integration, you can convert to polar coordinates, using the bounds

$$0 \le \theta \le \pi/2 \quad \text{and} \quad 0 \le r \le 2.$$

So, the mass is

$$m = \int_R\int k\sqrt{x^2 + y^2}\, dA$$
$$= \int_0^{\pi/2} \int_0^2 k\sqrt{r^2}\, r\, dr\, d\theta \qquad \text{Polar coordinates}$$
$$= \int_0^{\pi/2} \int_0^2 kr^2\, dr\, d\theta \qquad \text{Simplify integrand.}$$
$$= \int_0^{\pi/2} \frac{kr^3}{3}\Big]_0^2 d\theta \qquad \text{Integrate with respect to } r.$$
$$= \frac{8k}{3}\int_0^{\pi/2} d\theta$$
$$= \frac{8k}{3}\Big[\theta\Big]_0^{\pi/2} \qquad \text{Integrate with respect } \theta.$$
$$= \frac{4\pi k}{3}.$$

TECHNOLOGY On many occasions, this text has mentioned the benefits of graphing utilities that perform symbolic integration. Remember that getting the best results from a graphing utility requires a knowledgeable user. For instance, notice how much simpler the integral in Example 2 becomes when it is converted to polar form.

Rectangular Form	Polar Form
$\int_0^2 \int_0^{\sqrt{4-x^2}} k\sqrt{x^2 + y^2}\, dy\, dx$	$\int_0^{\pi/2} \int_0^2 kr^2\, dr\, d\theta$

Use a graphing utility to evaluate both integrals. Note that some graphing utilities cannot evaluate the first integral, but any graphing utility that can perform double integration can evaluate the second integral.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Moments and Center of Mass



$M_x = (\text{mass})(y_i)$
$M_y = (\text{mass})(x_i)$
Figure 14.36

For a lamina of variable density, moments of mass are defined in a manner similar to that used for the uniform density case. For a partition Δ of a lamina corresponding to a plane region R, consider the ith rectangle R_i of one area ΔA_i, as shown in Figure 14.36. Assume that the mass of R_i is concentrated at one of its interior points (x_i, y_i). The moment of mass of R_i with respect to the x-axis can be approximated by

$$(\text{Mass})(y_i) \approx [\rho(x_i, y_i)\,\Delta A_i](y_i).$$

Similarly, the moment of mass with respect to the y-axis can be approximated by

$$(\text{Mass})(x_i) \approx [\rho(x_i, y_i)\Delta A_i](x_i).$$

By forming the Riemann sum of all such products and taking the limits as the norm of Δ approaches 0, you obtain the following definitions of moments of mass with respect to the x- and y-axes.

Moments and Center of Mass of a Variable Density Planar Lamina

Let ρ be a continuous density function on the planar lamina R. The **moments of mass** with respect to the x- and y-axes are

$$M_x = \int_R\int (y)\rho(x, y)\,dA$$

and

$$M_y = \int_R\int (x)\rho(x, y)\,dA.$$

If m is the mass of the lamina, then the **center of mass** is

$$(\bar{x}, \bar{y}) = \left(\frac{M_y}{m}, \frac{M_x}{m}\right).$$

If R represents a simple plane region rather than a lamina, then the point $(\bar{x}, \bar{y})$ is called the **centroid** of the region.

For some planar laminas with a constant density ρ, you can determine the center of mass (or one of its coordinates) using symmetry rather than using integration. For instance, consider the laminas of constant density shown in Figure 14.37. Using symmetry, you can see that $\bar{y} = 0$ for the first lamina and $\bar{x} = 0$ for the second lamina.

R: $0 \le x \le 1$
$-\sqrt{1 - x^2} \le y \le \sqrt{1 - x^2}$



Lamina of constant density that is symmetric with respect to the x-axis

R: $-\sqrt{1 - y^2} \le x \le \sqrt{1 - y^2}$
$0 \le y \le 1$



Lamina of constant density that is symmetric with respect to the y-axis

Figure 14.37

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

EXAMPLE 3 Finding the Center of Mass

See LarsonCalculus.com for an interactive version of this type of example.

Find the center of mass of the lamina corresponding to the parabolic region

$$0 \le y \le 4 - x^2$$ Parabolic region

where the density at the point (x, y) is proportional to the distance between (x, y) and the x-axis, as shown in Figure 14.38.



Parabolic region of variable density
Figure 14.38

Solution The lamina is symmetric with respect to the y-axis and $\rho(x, y) = ky$, where k is the constant of proportionality. So, the center of mass lies on the y-axis and $\bar{x} = 0$. To find $\bar{y}$, first find the mass of the lamina.

$$\begin{aligned} m &= \int_{-2}^{2}\int_{0}^{4-x^2} ky\, dy\, dx \\ &= \frac{k}{2}\int_{-2}^{2} y^2\Big]_{0}^{4-x^2} dx && \text{Integrate with respect to } y. \\ &= \frac{k}{2}\int_{-2}^{2} (16 - 8x^2 + x^4)\, dx \\ &= \frac{k}{2}\left[16x - \frac{8x^3}{3} + \frac{x^5}{5}\right]_{-2}^{2} && \text{Integrate with respect to } x. \\ &= k\left(32 - \frac{64}{3} + \frac{32}{5}\right) \\ &= \frac{256k}{15} && \text{Mass of the limina} \end{aligned}$$

Next, find the moment of mass about the x-axis.

$$\begin{aligned} M_x &= \int_{-2}^{2}\int_{0}^{4-x^2} (y)(ky)\, dy\, dx \\ &= \frac{k}{3}\int_{-2}^{2} y^3\Big]_{0}^{4-x^2} dx && \text{Integrate with respect to } y. \\ &= \frac{k}{3}\int_{-2}^{2} (64 - 48x^2 + 12x^4 - x^6)\, dx \\ &= \frac{k}{3}\left[64x - 16x^3 + \frac{12x^5}{5} - \frac{x^7}{7}\right]_{-2}^{2} && \text{Integrate with respect to } x. \\ &= \frac{4096k}{105} && \text{Moment of mass about } x\text{-axis} \end{aligned}$$

So,

$$\bar{y} = \frac{M_x}{m} = \frac{4096k/105}{256k/15} = \frac{16}{7}$$

and the center of mass is $\left(0, \frac{16}{7}\right)$. ■



Figure 14.39

Although you can think of the moments M_x and M_y as measuring the tendency to rotate about the x- or y-axis, the calculation of moments is usually an intermediate step toward a more tangible goal. The use of the moments M_x and M_y is typical—to find the center of mass. Determination of the center of mass is useful in a variety of applications that allow you to treat a lamina as if its mass were concentrated at just one point. Intuitively, you can think of the center of mass as the balancing point of the lamina. For instance, the lamina in Example 3 should balance on the point of a pencil placed at $\left(0, \frac{16}{7}\right)$, as shown in Figure 14.39.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Moments of Inertia

The moments of M_x and M_y used in determining the center of mass of a lamina are sometimes called the **first moments** about the x- and y-axes. In each case, the moment is the product of a mass times a distance.

$$M_x = \int_R\int (y)\underbrace{\rho(x, y)\, dA}_{\text{Mass}} \qquad M_y = \int_R\int (x)\underbrace{\rho(x, y)\, dA}_{\text{Mass}}$$

Distance to x-axis (for M_x); Distance to y-axis (for M_y)

You will now look at another type of moment—the **second moment,** or the **moment of inertia** of a lamina about a line. In the same way that mass is a measure of the tendency of matter to resist a change in straight-line motion, the moment of inertia about a line is a *measure of the tendency of matter to resist a change in rotational motion.* For example, when a particle of mass m is a distance d from a fixed line, its moment of inertia about the line is defined as

$$I = md^2 = (\text{mass})(\text{distance})^2.$$

As with moments of mass, you can generalize this concept to obtain the moments of inertia about the x- and y-axes of a lamina of variable density. These second moments are denoted by I_x and I_y, and in each case the moment is the product of a mass times the square of a distance.

$$I_x = \int_R\int (y^2)\underbrace{\rho(x, y)\, dA}_{\text{Mass}} \qquad I_y = \int_R\int (x^2)\underbrace{\rho(x, y)\, dA}_{\text{Mass}}$$

Square of distance to x-axis (for I_x); Square of distance to y-axis (for I_y)

The sum of the moments I_x and I_y is called the **polar moment of inertia** and is denoted by I_0. For a lamina in the xy-plane, I_0 represents the moment of inertia of the lamina about the z-axis. The term "polar moment of inertia" stems from the fact that the square of the polar distance r is used in the calculation.

$$I_0 = \int_R\int (x^2 + y^2)\rho(x, y)\, dA = \int_R\int (r^2)\rho(x, y)\, dA$$

EXAMPLE 4 Finding the Moment of Inertia

Find the moment of inertia about the x-axis of the lamina in Example 3.

Solution From the definition of moment of inertia, you have

$$\begin{aligned} I_x &= \int_{-2}^{2}\int_{0}^{4-x^2} (y^2)(ky)\, dy\, dx \\ &= \frac{k}{4}\int_{-2}^{2} y^4\Big]_{0}^{4-x^2} dx && \text{Integrate with respect to } y. \\ &= \frac{k}{4}\int_{-2}^{2} (256 - 256x^2 + 96x^4 - 16x^6 + x^8)\, dx \\ &= \frac{k}{4}\left[256x - \frac{256x^3}{3} + \frac{96x^5}{5} - \frac{16x^7}{7} + \frac{x^9}{9}\right]_{-2}^{2} && \text{Integrate with respect to } x. \\ &= \frac{32{,}768k}{315}. && \text{Moment of inertia about } x\text{-axis} \end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Planar lamina revolving at ω radians per second

Figure 14.40

The moment of inertia I of a revolving lamina can be used to measure its kinetic energy. For example, suppose a planar lamina is revolving about a line with an **angular speed** of ω radians per second, as shown in Figure 14.40. The kinetic energy E of the revolving lamina is

$$E = \frac{1}{2} I\omega^2. \qquad \text{Kinetic energy for rotational motion}$$

On the other hand, the kinetic energy E of a mass m moving in a straight line at a velocity v is

$$E = \frac{1}{2} mv^2. \qquad \text{Kinetic energy for linear motion}$$

So, the kinetic energy of a mass moving in a straight line is proportional to its mass, but the kinetic energy of a mass revolving about an axis is proportional to its moment of inertia.

The **radius of gyration** $\bar{\bar{r}}$ of a revolving mass m with moment of inertia I is defined as

$$\bar{\bar{r}} = \sqrt{\frac{I}{m}}. \qquad \text{Radius of gyration}$$

If the entire mass were located at a distance $\bar{\bar{r}}$ from its axis of revolution, it would have the same moment of inertia and, consequently, the same kinetic energy. For instance, the radius of gyration of the lamina in Example 4 about the x-axis is

$$\bar{\bar{y}} = \sqrt{\frac{I_x}{m}} = \sqrt{\frac{32{,}768k/315}{256k/15}} = \sqrt{\frac{128}{21}} \approx 2.469.$$

EXAMPLE 5 Finding the Radius of Gyration

Find the radius of gyration about the y-axis for the lamina corresponding to the region R: $0 \le y \le \sin x$, $0 \le x \le \pi$, where the density at (x, y) is given by $\rho(x, y) = x$.



Figure 14.41

Solution The region R is shown in Figure 14.41. By integrating $\rho(x, y) = x$ over the region R, you can determine that the mass of the region is π. The moment of inertia about the y-axis is

$$\begin{aligned} I_y &= \int_0^{\pi} \int_0^{\sin x} x^3 \, dy \, dx \\ &= \int_0^{\pi} x^3 y \Big]_0^{\sin x} dx \qquad \text{Integrate with respect to } y. \\ &= \int_0^{\pi} x^3 \sin x \, dx \\ &= \Big[(3x^2 - 6)(\sin x) - (x^3 - 6x)(\cos x) \Big]_0^{\pi} \qquad \text{Integrate with respect to } x. \\ &= \pi^3 - 6\pi. \qquad \text{Moment of inertia about } y\text{-axis} \end{aligned}$$

So, the radius of gyration about the y-axis is

$$\begin{aligned} \bar{\bar{x}} &= \sqrt{\frac{I_y}{m}} \\ &= \sqrt{\frac{\pi^3 - 6\pi}{\pi}} \\ &= \sqrt{\pi^2 - 6} \\ &\approx 1.967. \qquad \text{Radius of gyration about } y\text{-axis} \end{aligned}$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

14.4 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain when you should use a double integral to find the mass of a planar lamina.
2. Describe what the moment of inertia measures. Explain how it is used to find the polar moment of inertia.

Finding the Mass of a Lamina **In Exercises 3–6, find the mass of the lamina described by the inequalities, given that its density is $\rho(x, y) = xy$.**

3. $0 \le x \le 2,\ 0 \le y \le 2$
4. $0 \le x \le 2,\ 0 \le y \le 4 - x^2$
5. $0 \le x \le 1,\ 0 \le y \le \sqrt{1 - x^2}$
6. $x \ge 0,\ 3 \le y \le 3 + \sqrt{9 - x^2}$

Finding the Center of Mass **In Exercises 7–10, find the mass and center of mass of the lamina corresponding to the region R for each density.**

7. R: square with vertices $(0, 0), (a, 0), (0, a), (a, a)$
   (a) $\rho = k$ (b) $\rho = ky$ (c) $\rho = kx$
8. R: rectangle with vertices $(0, 0), (a, 0), (0, b), (a, b)$
   (a) $\rho = kxy$ (b) $\rho = k(x^2 + y^2)$
9. R: triangle with vertices $(0, 0), (0, a), (a, a)$
   (a) $\rho = k$ (b) $\rho = ky$ (c) $\rho = kx$
10. R: triangle with vertices $(0, 0), (a/2, a), (a, 0)$
    (a) $\rho = k$ (b) $\rho = kxy$

11. **Translations in the Plane** Translate the lamina in Exercise 7 to the right five units and determine the resulting center of mass.
12. **Conjecture** Use the result of Exercise 11 to make a conjecture about the change in the center of mass when a lamina of constant density is translated c units horizontally or d units vertically. Is the conjecture true when the density is not constant? Explain.

Finding the Center of Mass **In Exercises 13–24, find the mass and center of mass of the lamina bounded by the graphs of the equations for the given density.**

13. $y = \sqrt{x},\ y = 0,\ x = 1,\ \rho = ky$
14. $y = x^2,\ y = 0,\ x = 2,\ \rho = kxy$
15. $y = 4/x,\ y = 0,\ x = 1,\ x = 4,\ \rho = kx^2$
16. $y = \dfrac{1}{1 + x^2},\ y = 0,\ x = -1,\ x = 1,\ \rho = k$
17. $y = e^x,\ y = 0,\ x = 0,\ x = 1,\ \rho = k$
18. $y = e^{-x},\ y = 0,\ x = 0,\ x = 1,\ \rho = ky^2$
19. $y = 4 - x^2,\ y = 0,\ \rho = ky$
20. $x = 9 - y^2,\ x = 0,\ \rho = kx$
21. $y = \sin\dfrac{\pi x}{3},\ y = 0,\ x = 0,\ x = 3,\ \rho = k$
22. $y = \cos\dfrac{\pi x}{8},\ y = 0,\ x = 0,\ x = 4,\ \rho = ky$
23. $y = \sqrt{36 - x^2},\ 0 \le y \le x,\ \rho = k$
24. $x^2 + y^2 = 16,\ x \ge 0,\ y \ge 0,\ \rho = k(x^2 + y^2)$

Finding the Center of Mass Using Technology **In Exercises 25–28, use a graphing utility to find the mass and center of mass of the lamina bounded by the graphs of the equations for the given density.**

25. $y = e^{-x},\ y = 0,\ x = 0,\ x = 2,\ \rho = kxy$
26. $y = \ln x,\ y = 0,\ x = 1,\ x = e,\ \rho = k/x$
27. $r = 2\cos 3\theta,\ -\dfrac{\pi}{6} \le \theta \le \dfrac{\pi}{6},\ \rho = k$
28. $r = 1 + \cos\theta,\ \rho = k$

Finding the Radius of Gyration About Each Axis **In Exercises 29–34, verify the given moment(s) of inertia and find $\bar{\bar{x}}$ and $\bar{\bar{y}}$. Assume that each lamina has a density of $\rho = 1$ gram per square centimeter. (These regions are common shapes used in engineering.)**

29. Rectangle



30. Right triangle



31. Circle



32. Semicircle



33. Quarter circle



34. Ellipse



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding Moments of Inertia and Radii of Gyration **In Exercises 35–38, find I_x, I_y, I_0, $\bar{x}$, and $\bar{y}$ for the lamina bounded by the graphs of the equations.**

35. $y = 4 - x^2,\ y = 0,\ x > 0,\ \rho = kx$

36. $y = x,\ y = x^2,\ \rho = kxy$

37. $y = \sqrt{x},\ y = 0,\ x = 4,\ \rho = kxy$

38. $y = x^2,\ y^2 = x,\ \rho = kx$

Finding a Moment of Inertia Using Technology **In Exercises 39–42, set up the double integral required to find the moment of inertia about the given line of the lamina bounded by the graphs of the equations for the given density. Use a graphing utility to evaluate the double integral.**

39. $x^2 + y^2 = b^2,\ \rho = k,$ line: $x = a\ (a > b)$

40. $y = \sqrt{x},\ y = 0,\ x = 4,\ \rho = kx,$ line: $x = 6$

41. $y = \sqrt{a^2 - x^2},\ y = 0,\ \rho = ky,$ line: $y = a$

42. $y = 4 - x^2,\ y = 0,\ \rho = k,$ line: $y = 2$

Hydraulics **In Exercises 43–46, determine the location of the horizontal axis y_a at which a vertical gate in a dam is to be hinged so that there is no moment causing rotation under the indicated loading (see figure). The model for y_a is**

$$y_a = \bar{y} - \frac{I_{\bar{y}}}{hA}$$

where $\bar{y}$ is the y-coordinate of the centroid of the gate, $I_{\bar{y}}$ is the moment of inertia of the gate about the line $y = \bar{y}$, h is the depth of the centroid below the surface, and A is the area of the gate.



43.



44.



45.



46.



Valentin Valkov/Shutterstock.com

Exploring Concepts

47. What does it mean for an object to have a greater polar moment of inertia than another object?

48. **HOW DO YOU SEE IT?** The center of mass of the lamina of constant density shown in the figure is $\left(2, \frac{8}{5}\right)$. Make a conjecture about how the center of mass $(\bar{x}, \bar{y})$ changes for each given nonconstant density $\rho(x, y)$. Explain. (Make your conjecture *without* performing any calculations.)



(a) $\rho(x, y) = ky$ (b) $\rho(x, y) = k|2 - x|$

(c) $\rho(x, y) = kxy$ (d) $\rho(x, y) = k(4 - x)(4 - y)$

49. **Proof** Prove the following Theorem of Pappus: Let R be a region in a plane and let L be a line in the same plane such that L does not intersect the interior of R. If r is the distance between the centroid of R and the line, then the volume V of the solid of revolution formed by revolving R about the line is $V = 2\pi rA$, where A is the area of R.

SECTION PROJECT

Center of Pressure on a Sail

The center of pressure on a sail is the point (x_p, y_p) at which the total aerodynamic force may be assumed to act. If the sail is represented by a plane region R, then the center of pressure is

$$x_p = \frac{\int_R\int xy\,dA}{\int_R\int y\,dA} \quad \text{and} \quad y_p = \frac{\int_R\int y^2\,dA}{\int_R\int y\,dA}.$$

Consider a triangular sail with vertices at (0, 0), (2, 1), and (0, 5). Verify the value of each integral.

(a) $\displaystyle\int_R\int y\,dA = 10$

(b) $\displaystyle\int_R\int xy\,dA = \frac{35}{6}$

(c) $\displaystyle\int_R\int y^2\,dA = \frac{155}{6}$

Calculate the coordinates (x_p, y_p) of the center of pressure. Sketch a graph of the sail and indicate the location of the center of pressure.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

14.5 Surface Area

GO DIGITAL

Use a double integral to find the area of a surface.

Surface Area

At this point, you know a great deal about the solid region lying between a surface and a closed and bounded region R in the xy-plane, as shown in Figure 14.42. For example, you know how to find the extrema of f on R (Section 13.8), the area of the base R of the solid (Section 14.1), the volume of the solid (Section 14.2), and the centroid of the base R (Section 14.4).

In this section, you will learn how to find the upper **surface area** of the solid. Later, you will learn how to find the centroid of the solid (Section 14.6) and the lateral surface area (Section 15.2).



Figure 14.42

To begin, consider a surface S given by

$$z = f(x, y)$$ Surface defined over a region R



Figure 14.43

defined over a region R. Assume that R is closed and bounded and that f has continuous first partial derivatives. To find the surface area, construct an inner partition of R consisting of n rectangles, where the area of the ith rectangle R_i is $\Delta A_i = \Delta x_i \Delta y_i$, as shown in Figure 14.43. In each R_i, let (x_i, y_i) be the point that is closest to the origin. At the point $(x_i, y_i, z_i) = (x_i, y_i, f(x_i, y_i))$ on the surface S, construct a tangent plane T_i. The area of the portion of the tangent plane that lies directly above R_i is approximately equal to the area of the surface lying directly above R_i. That is, $\Delta T_i \approx \Delta S_i$. So, the surface area of S is approximated by

$$\sum_{i=1}^{n} \Delta S_i \approx \sum_{i=1}^{n} \Delta T_i.$$

To find the area of the parallelogram ΔT_i, note that its sides are given by the vectors

$$\mathbf{u} = \Delta x_i \mathbf{i} + f_x(x_i, y_i)\, \Delta x_i \mathbf{k}$$

and

$$\mathbf{v} = \Delta y_i \mathbf{j} + f_y(x_i, y_i)\, \Delta y_i \mathbf{k}.$$

From Theorem 11.8, the area of ΔT_i is given by $\|\mathbf{u} \times \mathbf{v}\|$, where

$$\begin{aligned} \mathbf{u} \times \mathbf{v} &= \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ \Delta x_i & 0 & f_x(x_i, y_i)\, \Delta x_i \\ 0 & \Delta y_i & f_y(x_i, y_i)\, \Delta y_i \end{vmatrix} \\ &= -f_x(x_i, y_i)\, \Delta x_i \Delta y_i \mathbf{i} - f_y(x_i, y_i)\, \Delta x_i \Delta y_i \mathbf{j} + \Delta x_i \Delta y_i \mathbf{k} \\ &= [-f_x(x_i, y_i)\mathbf{i} - f_y(x_i, y_i)\mathbf{j} + \mathbf{k}]\, \Delta A_i. \end{aligned}$$

So, the area of ΔT_i is $\|\mathbf{u} \times \mathbf{v}\| = \sqrt{[f_x(x_i, y_i)]^2 + [f_y(x_i, y_i)]^2 + 1}\, \Delta A_i$, and

$$\begin{aligned} \text{Surface area of } S &\approx \sum_{i=1}^{n} \Delta S_i \\ &\approx \sum_{i=1}^{n} \sqrt{1 + [f_x(x_i, y_i)]^2 + [f_y(x_i, y_i)]^2}\, \Delta A_i. \end{aligned}$$

This suggests the definition of surface area on the next page.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Definition of Surface Area

If f and its first partial derivatives are continuous on the closed region R in the xy-plane, then the **area of the surface S** given by $z = f(x, y)$ over R is defined as

$$\text{Surface area} = \iint_R dS = \iint_R \sqrt{1 + [f_x(x, y)]^2 + [f_y(x, y)]^2}\, dA.$$

REMARK Note that the differential ds of arc length in the xy-plane is

$$\sqrt{1 + [f'(x)]^2}\, dx$$

and the differential dS of surface area in space is

$$\sqrt{1 + [f_x(x, y)]^2 + [f_y(x, y)]^2}\, dA.$$

As an aid to remembering the double integral for surface area, it is helpful to note its similarity to the integral for arc length.

Length on x-axis: $\displaystyle\int_a^b dx$

Arc length in xy-plane: $\displaystyle\int_a^b ds = \int_a^b \sqrt{1 + [f'(x)]^2}\, dx$

Area in xy-plane: $\displaystyle\iint_R dA$

Surface area in space: $\displaystyle\iint_R dS = \iint_R \sqrt{1 + [f_x(x, y)]^2 + [f_y(x, y)]^2}\, dA$

Like integrals for arc length, integrals for surface area are often very difficult to evaluate. However, one type that is not as difficult to evaluate is demonstrated in the next example.

EXAMPLE 1 The Surface Area of a Plane Region

Find the surface area of the portion of the plane

$$z = 2 - x - y$$

that lies above the circle $x^2 + y^2 \le 1$ in the first quadrant, as shown in Figure 14.44.



Figure 14.44

Solution Note that $f(x, y) = 2 - x - y$, $f_x(x, y) = -1$, and $f_y(x, y) = -1$ are continuous on the region R. So, the surface area is given by

$$S = \iint_R \sqrt{1 + [f_x(x, y)]^2 + [f_y(x, y)]^2}\, dA \qquad \text{Formula for surface area}$$

$$= \iint_R \sqrt{1 + (-1)^2 + (-1)^2}\, dA \qquad \text{Substitute.}$$

$$= \iint_R \sqrt{3}\, dA$$

$$= \sqrt{3} \iint_R dA.$$

Note that the last integral is $\sqrt{3}$ times the area of the region R. Because R is a quarter circle of radius 1, the area of R is $\frac{1}{4}\pi(1^2)$ or $\pi/4$. So, the area of S is

$$S = \sqrt{3}\,(\text{area of } R)$$

$$= \sqrt{3}\left(\frac{\pi}{4}\right)$$

$$= \frac{\sqrt{3}\,\pi}{4}.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 14.45



Figure 14.46

EXAMPLE 2 Finding Surface Area

See LarsonCalculus.com for an interactive version of this type of example.

Find the area of the portion of the surface $f(x, y) = 1 - x^2 + y$ that lies above the triangular region with vertices $(1, 0, 0)$, $(0, -1, 0)$, and $(0, 1, 0)$, as shown in Figure 14.45.

Solution Because $f_x(x, y) = -2x$ and $f_y(x, y) = 1$, you have

$$S = \iint_R \sqrt{1 + [f_x(x, y)]^2 + [f_y(x, y)]^2}\, dA = \iint_R \sqrt{1 + 4x^2 + 1}\, dA.$$

In Figure 14.46, the bounds for R are $0 \le x \le 1$ and $x - 1 \le y \le 1 - x$. So, the integral becomes

$$\begin{aligned}
S &= \int_0^1 \int_{x-1}^{1-x} \sqrt{2 + 4x^2}\, dy\, dx && \text{Apply formula for surface area.} \\
&= \int_0^1 y\sqrt{2 + 4x^2} \Big]_{x-1}^{1-x} dx \\
&= \int_0^1 \left[(1 - x)\sqrt{2 + 4x^2} - (x - 1)\sqrt{2 + 4x^2}\right] dx \\
&= \int_0^1 \left(2\sqrt{2 + 4x^2} - 2x\sqrt{2 + 4x^2}\right) dx && \text{Integration tables (Appendix B), Formula 26 and Power Rule} \\
&= \left[x\sqrt{2 + 4x^2} + \ln\left(2x + \sqrt{2 + 4x^2}\right) - \frac{(2 + 4x^2)^{3/2}}{6}\right]_0^1 \\
&= \sqrt{6} + \ln\left(2 + \sqrt{6}\right) - \sqrt{6} - \ln\sqrt{2} + \frac{1}{3}\sqrt{2} \\
&\approx 1.618.
\end{aligned}$$

EXAMPLE 3 Change of Variables to Polar Coordinates

Find the surface area of the paraboloid $z = 1 + x^2 + y^2$ that lies above the unit circle, as shown in Figure 14.47.



Figure 14.47

Solution Because $f_x(x, y) = 2x$ and $f_y(x, y) = 2y$, you have

$$S = \iint_R \sqrt{1 + [f_x(x, y)]^2 + [f_y(x, y)]^2}\, dA = \iint_R \sqrt{1 + 4x^2 + 4y^2}\, dA.$$

You can convert to polar coordinates by letting $x = r\cos\theta$ and $y = r\sin\theta$. Then, because the region R is bounded by $0 \le r \le 1$ and $0 \le \theta \le 2\pi$, you have

$$\begin{aligned}
S &= \int_0^{2\pi} \int_0^1 \sqrt{1 + 4r^2}\, r\, dr\, d\theta && \text{Polar coordinates} \\
&= \int_0^{2\pi} \frac{1}{12}(1 + 4r^2)^{3/2} \Big]_0^1 d\theta && \text{Integrate with respect to } r. \\
&= \int_0^{2\pi} \frac{5\sqrt{5} - 1}{12}\, d\theta \\
&= \frac{5\sqrt{5} - 1}{12}\, \theta \Big]_0^{2\pi} && \text{Integrate with respect to } \theta. \\
&= \frac{\pi(5\sqrt{5} - 1)}{6} \\
&\approx 5.33.
\end{aligned}$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 14.48

GO DIGITAL

EXAMPLE 4 Finding Surface Area

Find the surface area S of the portion of the hemisphere

$$f(x, y) = \sqrt{25 - x^2 - y^2}$$ Hemisphere

that lies above the region R bounded by the circle $x^2 + y^2 \le 9$, as shown in Figure 14.48.

Solution The first partial derivatives of f are

$$f_x(x, y) = \frac{-x}{\sqrt{25 - x^2 - y^2}}$$

and

$$f_y(x, y) = \frac{-y}{\sqrt{25 - x^2 - y^2}}$$

and, from the formula for surface area, you have

$$\begin{aligned} dS &= \sqrt{1 + [f_x(x, y)]^2 + [f_y(x, y)]^2}\, dA \\ &= \sqrt{1 + \left(\frac{-x}{\sqrt{25 - x^2 - y^2}}\right)^2 + \left(\frac{-y}{\sqrt{25 - x^2 - y^2}}\right)^2}\, dA \\ &= \frac{5}{\sqrt{25 - x^2 - y^2}}\, dA. \end{aligned}$$

So, the surface area is

$$S = \iint_R \frac{5}{\sqrt{25 - x^2 - y^2}}\, dA.$$

You can convert to polar coordinates by letting $x = r\cos\theta$ and $y = r\sin\theta$. Then, because the region R is bounded by $0 \le r \le 3$ and $0 \le \theta \le 2\pi$, you obtain

$$\begin{aligned} S &= \int_0^{2\pi}\int_0^3 \frac{5}{\sqrt{25 - r^2}}\, r\, dr\, d\theta && \text{Polar coordinates} \\ &= 5\int_0^{2\pi} -\sqrt{25 - r^2}\,\Big]_0^3\, d\theta && \text{Integrate with respect to } r. \\ &= 5\int_0^{2\pi} d\theta \\ &= 10\pi. && \text{Integrate with respect to } \theta. \end{aligned}$$

The procedure used in Example 4 can be extended to find the surface area of a sphere by using the region R bounded by the circle $x^2 + y^2 \le a^2$, where $0 < a < 5$, as shown in Figure 14.49. The surface area of the portion of the hemisphere

$$f(x, y) = \sqrt{25 - x^2 - y^2}$$

lying above the circular region can be shown to be

$$\begin{aligned} S &= \iint_R \frac{5}{\sqrt{25 - x^2 - y^2}}\, dA \\ &= \int_0^{2\pi}\int_0^a \frac{5}{\sqrt{25 - r^2}}\, r\, dr\, d\theta \\ &= 10\pi\left(5 - \sqrt{25 - a^2}\right). \end{aligned}$$

By taking the limit as a approaches 5 and doubling the result, you obtain a total area of 100π. (The surface area of a sphere of radius r is $S = 4\pi r^2$.)



Figure 14.49

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

You can use Simpson's Rule or the Trapezoidal Rule to approximate the value of a double integral, *provided* you can get through the first integration. This is demonstrated in the next example.

EXAMPLE 5 Approximating Surface Area by Simpson's Rule



Figure 14.50

Find the area of the surface of the paraboloid

$$f(x, y) = 2 - x^2 - y^2$$ Paraboloid

that lies above the square region bounded by

$$-1 \le x \le 1 \quad \text{and} \quad -1 \le y \le 1$$

as shown in Figure 14.50.

Solution Using the partial derivatives

$$f_x(x, y) = -2x \quad \text{and} \quad f_y(x, y) = -2y$$

you have a surface area of

$$S = \iint_R \sqrt{1 + [f_x(x, y)]^2 + [f_y(x, y)]^2}\, dA$$ Formula for surface area

$$= \iint_R \sqrt{1 + (-2x)^2 + (-2y)^2}\, dA$$ Substitute.

$$= \iint_R \sqrt{1 + 4x^2 + 4y^2}\, dA.$$ Simplify.

In polar coordinates, the line $x = 1$ is given by

$$r \cos\theta = 1 \quad \text{or} \quad r = \sec\theta$$

and you can determine from Figure 14.51 that one-fourth of the region R is bounded by

$$0 \le r \le \sec\theta \quad \text{and} \quad -\frac{\pi}{4} \le \theta \le \frac{\pi}{4}.$$



One-fourth of the region R is bounded by $0 \le r \le \sec\theta$ and $-\frac{\pi}{4} \le \theta \le \frac{\pi}{4}$.

Figure 14.51

Letting $x = r\cos\theta$ and $y = r\sin\theta$ produces

$$\frac{1}{4}S = \frac{1}{4}\iint_R \sqrt{1 + 4x^2 + 4y^2}\, dA$$ One-fourth of surface area

$$= \int_{-\pi/4}^{\pi/4}\int_0^{\sec\theta} \sqrt{1 + 4r^2}\, r\, dr\, d\theta$$ Polar coordinates

$$= \int_{-\pi/4}^{\pi/4} \frac{1}{12}(1 + 4r^2)^{3/2}\Big]_0^{\sec\theta} d\theta$$ Integrate with respect to r.

$$= \frac{1}{12}\int_{-\pi/4}^{\pi/4} [(1 + 4\sec^2\theta)^{3/2} - 1]\, d\theta.$$

After multiplying each side by 4, you can approximate the integral using Simpson's Rule with $n = 10$ to find that the area of the surface is

$$S = 4\left(\frac{1}{12}\right)\int_{-\pi/4}^{\pi/4} [(1 + 4\sec^2\theta)^{3/2} - 1]\, d\theta \approx 7.450.$$

TECHNOLOGY Most graphing utilities that are capable of performing symbolic integration for multiple integrals are also capable of performing numerical approximation techniques. If you have access to a graphing utility with this feature, use it to approximate the value of the integral in Example 5.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

14.5 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. What is the differential of surface area, dS, in space?
2. Write a double integral that represents the surface area of the portion of the plane $z = 3$ that lies above the rectangular region with vertices $(0, 0)$, $(4, 0)$, $(0, 5)$, and $(4, 5)$. Then find the surface area without integrating.

Finding Surface Area **In Exercises 3–16, find the area of the surface given by $z = f(x, y)$ that lies above the region R.**

3. $f(x, y) = 2x + 2y$
   R: triangle with vertices $(0, 0)$, $(4, 0)$, $(0, 4)$
4. $f(x, y) = 15 + 2x - 3y$
   R: square with vertices $(0, 0)$, $(3, 0)$, $(0, 3)$, $(3, 3)$
5. $f(x, y) = 4 + 5x + 6y$, $R = \{(x, y): x^2 + y^2 \le 4\}$
6. $f(x, y) = 12 + 2x - 3y$, $R = \{(x, y): x^2 + y^2 \le 9\}$
7. $f(x, y) = 9 - x^2$
   R: square with vertices $(0, 0)$, $(2, 0)$, $(0, 2)$, $(2, 2)$
8. $f(x, y) = y^2$
   R: square with vertices $(0, 0)$, $(3, 0)$, $(0, 3)$, $(3, 3)$
9. $f(x, y) = 3 + 2x^{3/2}$
   R: rectangle with vertices $(0, 0)$, $(0, 4)$, $(1, 4)$, $(1, 0)$
10. $f(x, y) = 2 + \frac{2}{3}y^{3/2}$
    $R = \{(x, y): 0 \le x \le 2, 0 \le y \le 2 - x\}$
11. $f(x, y) = \ln|\sec x|$
    $R = \left\{(x, y): 0 \le x \le \frac{\pi}{4}, 0 \le y \le \tan x\right\}$
12. $f(x, y) = 13 + x^2 - y^2$
    $R = \{(x, y): x^2 + y^2 \le 4\}$
13. $f(x, y) = \sqrt{x^2 + y^2}$
    $R = \{(x, y): 0 \le f(x, y) \le 1\}$
14. $f(x, y) = xy$
    $R = \{(x, y): x^2 + y^2 \le 16\}$
15. $f(x, y) = \sqrt{a^2 - x^2 - y^2}$
    $R = \{(x, y): x^2 + y^2 \le b^2, \quad 0 < b < a\}$
16. $f(x, y) = \sqrt{a^2 - x^2 - y^2}$
    $R = \{(x, y): x^2 + y^2 \le a^2\}$

Finding Surface Area **In Exercises 17–20, find the area of the surface.**

17. The portion of the plane $z = 12 - 3x - 2y$ in the first octant
18. The portion of the paraboloid $z = 16 - x^2 - y^2$ in the first octant
19. The portion of the sphere $x^2 + y^2 + z^2 = 25$ inside the cylinder $x^2 + y^2 = 9$
20. The portion of the cone $z = 2\sqrt{x^2 + y^2}$ inside the cylinder $x^2 + y^2 = 4$

Finding Surface Area Using Technology **In Exercises 21–26, write a double integral that represents the surface area of $z = f(x, y)$ that lies above the region R. Use a graphing utility to evaluate the double integral.**

21. $f(x, y) = 2y + x^2$
    R: triangle with vertices $(0, 0)$, $(1, 0)$, $(1, 1)$
22. $f(x, y) = 2x + y^2$
    R: triangle with vertices $(0, 0)$, $(2, 0)$, $(2, 2)$
23. $f(x, y) = 9 - x^2 - y^2$
    $R = \{(x, y): 0 \le f(x, y)\}$
24. $f(x, y) = x^2 + y^2$
    $R = \{(x, y): 0 \le f(x, y) \le 16\}$
25. $f(x, y) = 4 - x^2 - y^2$
    $R = \{(x, y): 0 \le x \le 1, 0 \le y \le 1\}$
26. $f(x, y) = \frac{2}{3}x^{3/2} + \cos x$
    $R = \{(x, y): 0 \le x \le 1, 0 \le y \le 1\}$

Setting Up a Double Integral **In Exercises 27–29, set up a double integral that represents the area of the surface given by $z = f(x, y)$ that lies above the region R.**

27. $f(x, y) = e^{xy}$
    $R = \{(x, y): 0 \le x \le 4, 0 \le y \le 10\}$
28. $f(x, y) = x^2 - 3xy - y^2$
    $R = \{(x, y): 0 \le x \le 4, 0 \le y \le x\}$
29. $f(x, y) = \cos(x^2 + y^2)$
    $R = \left\{(x, y): x^2 + y^2 \le \frac{\pi}{2}\right\}$

30. **HOW DO YOU SEE IT?** Consider the surface $f(x, y) = x^2 + y^2$ (see figure) and the surface area of f that lies above each region R. Without integrating, order the surface areas from least to greatest. Explain.



(a) R: rectangle with vertices $(0, 0)$, $(2, 0)$, $(2, 2)$, $(0, 2)$
(b) R: triangle with vertices $(0, 0)$, $(2, 0)$, $(0, 2)$
(c) $R = \{(x, y): x^2 + y^2 \le 4$, first quadrant only$\}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploring Concepts

31. Will the surface area of the graph of a function $z = f(x, y)$ that lies above a region R increase when the graph is shifted k units vertically? Explain using the partial derivatives of z.

32. Surface Area Consider the surface $f(x, y) = x + y$. What is the relationship between the area of the surface that lies above the region

$R_1 = \{(x, y): x^2 + y^2 \leq 1\}$

and the area of the surface that lies above the region

$R_2 = \{(x, y): x^2 + y^2 \leq 4\}$?

33. Product Design A company produces a spherical object of radius 25 centimeters. A hole of radius 4 centimeters is drilled through the center of the object.

(a) Find the volume of the object.

(b) Find the outer surface area of the object.

34. Modeling Data

A company builds a warehouse with dimensions 30 feet by 50 feet. The symmetrical shape and selected heights of the roof are shown in the figure.



(a) Use the regression capabilities of a graphing utility to find a model of the form

$z = ay^3 + by^2 + cy + d$

for the roof line.

(b) Use the numerical integration capabilities of a graphing utility and the model in part (a) to approximate the volume of storage space in the warehouse.

(c) Use the numerical integration capabilities of a graphing utility and the model in part (a) to approximate the surface area of the roof.

(d) Approximate the arc length of the roof line and find the surface area of the roof by multiplying the arc length by the length of the warehouse. Compare the results and the integrations with those found in part (c).

AlexKZ/Shutterstock.com

35. Surface Area Find the surface area of the solid of intersection of the cylinders $x^2 + z^2 = 1$ and $y^2 + z^2 = 1$ (see figure).



36. Surface Area Show that the surface area of the cone $z = k\sqrt{x^2 + y^2}$, $k > 0$, that lies above the circular region $x^2 + y^2 \leq r^2$ in the xy-plane is $\pi r^2\sqrt{k^2 + 1}$ (see figure).



SECTION PROJECT

Surface Area in Polar Coordinates

(a) Use the formula for surface area in rectangular coordinates to derive the following formula for surface area in polar coordinates, where $z = f(x, y) = f(r\cos\theta, r\sin\theta)$. (*Hint:* You will need to use the Chain Rule for functions of two variables.)

$$S = \iint_R \sqrt{1 + f_r^2 + \frac{1}{r^2}f_\theta^2}\, r\, dr\, d\theta$$

(b) Use the formula from part (a) to find the surface area of the paraboloid $z = x^2 + y^2$ that lies above the circular region $x^2 + y^2 \leq 4$ in the xy-plane (see figure).



(c) Use the formula from part (a) to find the surface area of $z = xy$ that lies above the circular region $x^2 + y^2 \leq 16$ in the xy-plane. Compare your answer with your answer to Exercise 14.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

14.6 Triple Integrals and Applications

GO DIGITAL

- **Use a triple integral to find the volume of a solid region.**
- **Find the center of mass and moments of inertia of a solid region.**



Solid region Q



Volume of $Q \approx \sum_{i=1}^{n} \Delta V_i$

Figure 14.52

Triple Integrals

The procedure used to define a **triple integral** follows that used for double integrals. Consider a function f of three variables that is continuous over a bounded solid region Q. Then encompass Q with a network of boxes and form the **inner partition** consisting of all boxes lying entirely within Q, as shown in Figure 14.52. The volume of the ith box is

$$\Delta V_i = \Delta x_i \Delta y_i \Delta z_i. \qquad \text{Volume of } i\text{th box}$$

The **norm** $\|\Delta\|$ of the partition is the length of the longest diagonal of the n boxes in the partition. Choose a point (x_i, y_i, z_i) in each box and form the Riemann sum

$$\sum_{i=1}^{n} f(x_i, y_i, z_i)\, \Delta V_i.$$

Taking the limit as $\|\Delta\| \to 0$ leads to the following definition.

Definition of Triple Integral

If f is continuous over a bounded solid region Q, then the **triple integral of f over Q** is defined as

$$\iiint_Q f(x, y, z)\, dV = \lim_{\|\Delta\| \to 0} \sum_{i=1}^{n} f(x_i, y_i, z_i)\, \Delta V_i$$

provided the limit exists. The **volume** of the solid region Q is given by

$$\text{Volume of } Q = \iiint_Q dV.$$

Some of the properties of double integrals in Theorem 14.1 can be restated in terms of triple integrals.

1. $\displaystyle\iiint_Q cf(x, y, z)\, dV = c \iiint_Q f(x, y, z)\, dV$

2. $\displaystyle\iiint_Q [f(x, y, z) \pm g(x, y, z)]\, dV = \iiint_Q f(x, y, z)\, dV \pm \iiint_Q g(x, y, z)\, dV$

3. $\displaystyle\iiint_Q f(x, y, z)\, dV = \iiint_{Q_1} f(x, y, z)\, dV + \iiint_{Q_2} f(x, y, z)\, dV$

In the properties above, Q is the union of two nonoverlapping solid subregions Q_1 and Q_2. If the solid region Q is simple, then the triple integral $\iiint f(x, y, z)\, dV$ can be evaluated with an iterated integral using one of the six possible orders of integration listed below.

$dx\, dy\, dz$ $\quad dy\, dx\, dz$ $\quad dz\, dx\, dy$

$dx\, dz\, dy$ $\quad dy\, dz\, dx$ $\quad dz\, dy\, dx$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploration

Volume of a Paraboloid Sector In the Explorations on pages 983 and 992, you were asked to summarize the different ways you know of finding the volume of the solid bounded by the paraboloid

$z = a^2 - x^2 - y^2, \quad a > 0$

and the xy-plane. You now know one more way. Use it to find the volume of the solid.



The following version of Fubini's Theorem describes a region that is considered simple with respect to the order $dz\,dy\,dx$. Similar versions of this theorem can be given for the other five orders.

THEOREM 14.4 Evaluation by Iterated Integrals

Let f be continuous on a solid region Q defined by

$$a \le x \le b,$$
$$h_1(x) \le y \le h_2(x),$$
$$g_1(x, y) \le z \le g_2(x, y)$$

where h_1, h_2, g_1, and g_2 are continuous functions. Then,

$$\iiint_Q f(x, y, z)\,dV = \int_a^b \int_{h_1(x)}^{h_2(x)} \int_{g_1(x,y)}^{g_2(x,y)} f(x, y, z)\,dz\,dy\,dx.$$

To evaluate a triple iterated integral in the order $dz\,dy\,dx$, hold *both* x and y constant for the innermost integration. Then hold x constant for the second integration.

EXAMPLE 1 Evaluating a Triple Iterated Integral

Evaluate the triple iterated integral

$$\int_0^2 \int_0^x \int_0^{x+y} e^x(y + 2z)\,dz\,dy\,dx.$$

Solution For the first integration, hold x and y constant and integrate with respect to z.

$$\int_0^2 \int_0^x \int_0^{x+y} e^x(y + 2z)\,dz\,dy\,dx = \int_0^2 \int_0^x e^x(yz + z^2)\Big]_0^{x+y} dy\,dx$$
$$= \int_0^2 \int_0^x e^x(x^2 + 3xy + 2y^2)\,dy\,dx$$

For the second integration, hold x constant and integrate with respect to y.

$$\int_0^2 \int_0^x e^x(x^2 + 3xy + 2y^2)\,dy\,dx = \int_0^2 \left[e^x\left(x^2y + \frac{3xy^2}{2} + \frac{2y^3}{3}\right)\right]_0^x dx$$
$$= \frac{19}{6}\int_0^2 x^3e^x\,dx$$

Finally, integrate with respect to x.

$$\frac{19}{6}\int_0^2 x^3e^x\,dx = \frac{19}{6}\Big[e^x(x^3 - 3x^2 + 6x - 6)\Big]_0^2$$
$$= 19\left(\frac{e^2}{3} + 1\right)$$
$$\approx 65.797$$

REMARK To do the last integration in Example 1, use integration by parts three times.

Example 1 demonstrates the integration order $dz\,dy\,dx$. For other orders, you can follow a similar procedure. For instance, to evaluate a triple iterated integral in the order $dx\,dy\,dz$, hold both y and z constant for the innermost integration and integrate with respect to x. Then, for the second integration, hold z constant and integrate with respect to y. Finally, for the third integration, integrate with respect to z.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



Solid region Q lies between two surfaces.
Figure 14.53



Figure 14.54



Figure 14.55

To find the limits for a particular order of integration, it is generally advisable first to determine the innermost limits, which may be functions of the outer two variables. Then, by projecting the solid Q onto the coordinate plane of the outer two variables, you can determine their limits of integration by the methods used for double integrals. For instance, to evaluate

$$\iiint_Q f(x, y, z)\, dz\, dy\, dx$$

first determine the limits for z; the integral then has the form

$$\int\int\left[\int_{g_1(x, y)}^{g_2(x, y)} f(x, y, z)\, dz\right] dy\, dx.$$

By projecting the solid Q onto the xy-plane, you can determine the limits for x and y as you did for double integrals, as shown in Figure 14.53.

EXAMPLE 2 Using a Triple Integral to Find Volume

Find the volume of the ellipsoid given by $4x^2 + 4y^2 + z^2 = 16$.

Solution Because x, y, and z play similar roles in the equation, the order of integration is probably immaterial, and you can arbitrarily choose $dz\, dy\, dx$. Moreover, you can simplify the calculation by considering only the portion of the ellipsoid lying in the first octant, as shown in Figure 14.54. From the order $dz\, dy\, dx$, you first determine the bounds for z.

$$0 \le z \le 2\sqrt{4 - x^2 - y^2} \qquad \text{Bounds for } z$$

In Figure 14.55, the bounds for x and y are

$$0 \le x \le 2 \quad \text{and} \quad 0 \le y \le \sqrt{4 - x^2}. \qquad \text{Bounds for } x \text{ and } y$$

So, the volume of the ellipsoid is

$$V = \iiint_Q dV \qquad \text{Formula for volume}$$

$$= 8\int_0^2\int_0^{\sqrt{4-x^2}}\int_0^{2\sqrt{4-x^2-y^2}} dz\, dy\, dx \qquad \text{Convert to iterated integral.}$$

$$= 8\int_0^2\int_0^{\sqrt{4-x^2}} z\Big]_0^{2\sqrt{4-x^2-y^2}} dy\, dx$$

$$= 16\int_0^2\int_0^{\sqrt{4-x^2}} \sqrt{(4 - x^2) - y^2}\, dy\, dx \qquad \text{Integration tables (Appendix B), Formula 37}$$

$$= 8\int_0^2\left[y\sqrt{4 - x^2 - y^2} + (4 - x^2)\arcsin\left(\frac{y}{\sqrt{4 - x^2}}\right)\right]_0^{\sqrt{4-x^2}} dx$$

$$= 8\int_0^2 [0 + (4 - x^2)\arcsin(1) - 0 - 0]\, dx$$

$$= 8\int_0^2 (4 - x^2)\left(\frac{\pi}{2}\right) dx$$

$$= 4\pi\left[4x - \frac{x^3}{3}\right]_0^2$$

$$= \frac{64\pi}{3}.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Example 2 is unusual in that all six possible orders of integration produce integrals of comparable difficulty. Try setting up some other possible orders of integration to find the volume of the ellipsoid. For instance, the order $dx\,dy\,dz$ yields the integral

$$V = 8\int_0^4 \int_0^{\sqrt{16-z^2}/2} \int_0^{\sqrt{16-4y^2-z^2}/2} dx\,dy\,dz.$$

The evaluation of this integral yields the same volume obtained in Example 2. This is always the case—the order of integration does not affect the value of the integral. However, the order of integration often does affect the complexity of the integral. In Example 3, the given order of integration is not convenient, so you can change the order to simplify the problem.

EXAMPLE 3 Changing the Order of Integration

Evaluate $\displaystyle\int_0^{\sqrt{\pi/2}} \int_x^{\sqrt{\pi/2}} \int_1^3 \sin(y^2)\,dz\,dy\,dx.$

Solution Note that after one integration in the given order, you would encounter the integral $2\int \sin(y^2)\,dy$, which is not an elementary function. To avoid this problem, change the order of integration to $dz\,dx\,dy$ so that y is the outer variable. From Figure 14.56, the solid region Q is

$$0 \le x \le \sqrt{\frac{\pi}{2}}$$

$$x \le y \le \sqrt{\frac{\pi}{2}}$$

$$1 \le z \le 3$$

and the projection of Q in the xy-plane yields the bounds

$$0 \le y \le \sqrt{\frac{\pi}{2}}$$

and

$$0 \le x \le y.$$

So, evaluating the triple integral using the order $dz\,dx\,dy$ produces



Figure 14.56

$$\begin{aligned}
\int_0^{\sqrt{\pi/2}} \int_0^y \int_1^3 \sin(y^2)\,dz\,dx\,dy &= \int_0^{\sqrt{\pi/2}} \int_0^y z\sin(y^2)\Big]_1^3\,dx\,dy \\
&= 2\int_0^{\sqrt{\pi/2}} \int_0^y \sin(y^2)\,dx\,dy \\
&= 2\int_0^{\sqrt{\pi/2}} x\sin(y^2)\Big]_0^y\,dy \\
&= 2\int_0^{\sqrt{\pi/2}} y\sin(y^2)\,dy \\
&= -\cos(y^2)\Big]_0^{\sqrt{\pi/2}} \\
&= 1.
\end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



Q: $0 \le z \le 1 - y^2$
$1 - y \le x \le 3 - y$
$0 \le y \le 1$

Figure 14.57



Q: $0 \le z \le \sqrt{1 - x^2 - y^2}$
$-\sqrt{1 - y^2} \le x \le \sqrt{1 - y^2}$
$-1 \le y \le 1$

Figure 14.58



Q: $x^2 + y^2 \le z \le \sqrt{6 - x^2 - y^2}$
$-\sqrt{2 - x^2} \le y \le \sqrt{2 - x^2}$
$-\sqrt{2} \le x \le \sqrt{2}$

Figure 14.59

EXAMPLE 4 Determining the Limits of Integration

Set up a triple integral for the volume of each solid region.

a. The region in the first octant bounded above by the cylinder $z = 1 - y^2$ and lying between the vertical planes $x + y = 1$ and $x + y = 3$

b. The upper hemisphere $z = \sqrt{1 - x^2 - y^2}$

c. The region bounded below by the paraboloid $z = x^2 + y^2$ and above by the sphere $x^2 + y^2 + z^2 = 6$

Solution

a. In Figure 14.57, note that the solid is bounded below by the xy-plane ($z = 0$) and above by the cylinder $z = 1 - y^2$. So,

$$0 \le z \le 1 - y^2. \qquad \text{Bounds for } z$$

Projecting the region onto the xy-plane produces a parallelogram. Because two sides of the parallelogram are parallel to the x-axis, you have the following bounds:

$$1 - y \le x \le 3 - y \quad \text{and} \quad 0 \le y \le 1. \qquad \text{Bounds for } x \text{ and } y$$

So, the volume of the region is given by

$$V = \iiint_Q dV = \int_0^1 \int_{1-y}^{3-y} \int_0^{1-y^2} dz\, dx\, dy.$$

b. For the upper hemisphere $z = \sqrt{1 - x^2 - y^2}$, you have

$$0 \le z \le \sqrt{1 - x^2 - y^2}. \qquad \text{Bounds for } z$$

In Figure 14.58, note that the projection of the hemisphere onto the xy-plane is the circle

$$x^2 + y^2 = 1$$

and you can use either order $dx\, dy$ or $dy\, dx$. Choosing the first produces

$$-\sqrt{1 - y^2} \le x \le \sqrt{1 - y^2} \quad \text{and} \quad -1 \le y \le 1 \qquad \text{Bounds for } x \text{ and } y$$

which implies that the volume of the region is given by

$$V = \iiint_Q dV = \int_{-1}^{1} \int_{-\sqrt{1-y^2}}^{\sqrt{1-y^2}} \int_0^{\sqrt{1-x^2-y^2}} dz\, dx\, dy.$$

c. For the region bounded below by the paraboloid $z = x^2 + y^2$ and above by the sphere $x^2 + y^2 + z^2 = 6$, you have

$$x^2 + y^2 \le z \le \sqrt{6 - x^2 - y^2}. \qquad \text{Bounds for } z$$

The sphere and the paraboloid intersect at $z = 2$. Moreover, in Figure 14.59 the projection of the solid region onto the xy-plane is the circle

$$x^2 + y^2 = 2.$$

Using the order $dy\, dx$ produces

$$-\sqrt{2 - x^2} \le y \le \sqrt{2 - x^2} \quad \text{and} \quad -\sqrt{2} \le x \le \sqrt{2} \qquad \text{Bounds for } x \text{ and } y$$

which implies that the volume of the region is given by

$$V = \iiint_Q dV = \int_{-\sqrt{2}}^{\sqrt{2}} \int_{-\sqrt{2-x^2}}^{\sqrt{2-x^2}} \int_{x^2+y^2}^{\sqrt{6-x^2-y^2}} dz\, dy\, dx.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Center of Mass and Moments of Inertia

In the remainder of this section, two important engineering applications of triple integrals are discussed. Consider a solid region Q whose density is given by the **density function ρ.** The **center of mass** of a solid region Q of mass m is given by $(\bar{x}, \bar{y}, \bar{z})$, where

$$m = \iiint_Q \rho(x, y, z)\, dV \qquad \text{Mass of the solid}$$

$$M_{yz} = \iiint_Q x\rho(x, y, z)\, dV \qquad \text{First moment about } yz\text{-plane}$$

$$M_{xz} = \iiint_Q y\rho(x, y, z)\, dV \qquad \text{First moment about } xz\text{-plane}$$

$$M_{xy} = \iiint_Q z\rho(x, y, z)\, dV \qquad \text{First moment about } xy\text{-plane}$$

and

$$\bar{x} = \frac{M_{yz}}{m}, \quad \bar{y} = \frac{M_{xz}}{m}, \quad \bar{z} = \frac{M_{xy}}{m}.$$

The quantities M_{yz}, M_{xz}, and M_{xy} are called the **first moments** of the region Q about the yz-, xz-, and xy-planes, respectively.

The first moments for solid regions are taken about a plane, whereas the second moments for solids are taken about a line. The **second moments** (or **moments of inertia**) about the x-, y-, and z-axes are

$$I_x = \iiint_Q (y^2 + z^2)\rho(x, y, z)\, dV \qquad \text{Moment of inertia about } x\text{-axis}$$

$$I_y = \iiint_Q (x^2 + z^2)\rho(x, y, z)\, dV \qquad \text{Moment of inertia about } y\text{-axis}$$

and

$$I_z = \iiint_Q (x^2 + y^2)\rho(x, y, z)\, dV. \qquad \text{Moment of inertia about } z\text{-axis}$$

REMARK In engineering and physics, the moment of inertia of a mass is used to find the time required for the mass to reach a given speed of rotation about an axis, as shown in Figure 14.60. The greater the moment of inertia, the longer a force must be applied for the mass to reach the given speed.

Figure 14.60

For problems requiring the calculation of all three moments, considerable effort can be saved by applying the additive property of triple integrals and writing

$$I_x = I_{xz} + I_{xy}, \quad I_y = I_{yz} + I_{xy}, \quad \text{and} \quad I_z = I_{yz} + I_{xz}$$

where I_{xy}, I_{xz}, and I_{yz} are

$$I_{xy} = \iiint_Q z^2\rho(x, y, z)\, dV$$

$$I_{xz} = \iiint_Q y^2\rho(x, y, z)\, dV$$

and

$$I_{yz} = \iiint_Q x^2\rho(x, y, z)\, dV.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Variable density:
$\rho(x, y, z) = k(x^2 + y^2 + z^2)$
Figure 14.61

EXAMPLE 5 Finding the Center of Mass of a Solid Region

See LarsonCalculus.com for an interactive version of this type of example.

Find the center of mass of the unit cube shown in Figure 14.61, given that the density at the point (x, y, z) is proportional to the square of its distance from the origin.

Solution Because the density at (x, y, z) is proportional to the square of the distance between $(0, 0, 0)$ and (x, y, z), you have

$$\rho(x, y, z) = k(x^2 + y^2 + z^2)$$

where k is the constant of proportionality. You can use this density function to find the mass of the cube. Because of the symmetry of the region, any order of integration will produce an integral of comparable difficulty.

$$m = \int_0^1 \int_0^1 \int_0^1 k(x^2 + y^2 + z^2)\, dz\, dy\, dx$$ Apply formula for mass of a solid.

$$= k\int_0^1 \int_0^1 \left[(x^2 + y^2)z + \frac{z^3}{3}\right]_0^1 dy\, dx$$ Integrate with respect to z.

$$= k\int_0^1 \int_0^1 \left(x^2 + y^2 + \frac{1}{3}\right) dy\, dx$$

$$= k\int_0^1 \left[\left(x^2 + \frac{1}{3}\right)y + \frac{y^3}{3}\right]_0^1 dx$$ Integrate with respect to y.

$$= k\int_0^1 \left(x^2 + \frac{2}{3}\right) dx$$

$$= k\left[\frac{x^3}{3} + \frac{2x}{3}\right]_0^1$$ Integrate with respect to x.

$$= k$$

The first moment about the yz-plane is

$$M_{yz} = k\int_0^1 \int_0^1 \int_0^1 x(x^2 + y^2 + z^2)\, dz\, dy\, dx$$ Apply formula for first moment about yz-plane.

$$= k\int_0^1 x\left[\int_0^1 \int_0^1 (x^2 + y^2 + z^2)\, dz\, dy\right] dx.$$ Factor.

Note that x can be factored out of the two inner integrals, because it is constant with respect to y and z. After factoring, the two inner integrals are the same as for the mass m. Therefore, you have

$$M_{yz} = k\int_0^1 x\left(x^2 + \frac{2}{3}\right) dx$$

$$= k\left[\frac{x^4}{4} + \frac{x^2}{3}\right]_0^1$$ Integrate with respect to x.

$$= \frac{7k}{12}.$$ First moment about yz-plane

So,

$$\bar{x} = \frac{M_{yz}}{m} = \frac{7k/12}{k} = \frac{7}{12}.$$

Finally, from the nature of ρ and the symmetry of x, y, and z in this solid region, you have $\bar{x} = \bar{y} = \bar{z}$, and the center of mass is $\left(\frac{7}{12}, \frac{7}{12}, \frac{7}{12}\right)$. ■

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 6 Moments of Inertia for a Solid Region

Find the moments of inertia about the x- and y-axes for the solid region lying between the hemisphere

$$z = \sqrt{4 - x^2 - y^2}$$

and the xy-plane, given that the density at (x, y, z) is proportional to the distance between (x, y, z) and the xy-plane.



Variable density: $\rho(x, y, z) = kz$
Figure 14.62

Solution The density of the region is given by

$$\rho(x, y, z) = kz$$

where k is the constant of proportionality. Considering the symmetry of this problem, you know that $I_x = I_y$, and you need to find only one moment, such as I_x. From Figure 14.62, choose the order $dz\,dy\,dx$ and write

$$I_x = \iiint_Q (y^2 + z^2)\rho(x, y, z)\,dV \qquad \text{Moment of inertia about } x\text{-axis}$$

$$= \int_{-2}^{2}\int_{-\sqrt{4-x^2}}^{\sqrt{4-x^2}}\int_{0}^{\sqrt{4-x^2-y^2}} (y^2 + z^2)(kz)\,dz\,dy\,dx$$

$$= k\int_{-2}^{2}\int_{-\sqrt{4-x^2}}^{\sqrt{4-x^2}}\left[\frac{y^2z^2}{2} + \frac{z^4}{4}\right]_0^{\sqrt{4-x^2-y^2}} dy\,dx$$

$$= k\int_{-2}^{2}\int_{-\sqrt{4-x^2}}^{\sqrt{4-x^2}}\left[\frac{y^2(4 - x^2 - y^2)}{2} + \frac{(4 - x^2 - y^2)^2}{4}\right] dy\,dx$$

$$= \frac{k}{4}\int_{-2}^{2}\int_{-\sqrt{4-x^2}}^{\sqrt{4-x^2}}[(4 - x^2)^2 - y^4]\,dy\,dx$$

$$= \frac{k}{4}\int_{-2}^{2}\left[(4 - x^2)^2 y - \frac{y^5}{5}\right]_{-\sqrt{4-x^2}}^{\sqrt{4-x^2}} dx$$

$$= \frac{k}{4}\int_{-2}^{2}\frac{8}{5}(4 - x^2)^{5/2}\,dx$$

$$= \frac{4k}{5}\int_{0}^{2}(4 - x^2)^{5/2}\,dx$$

$$= \frac{4k}{5}\int_{0}^{\pi/2} 64\cos^6\theta\,d\theta \qquad \text{Trigonometric substitution: } x = 2\sin\theta$$

$$= \left(\frac{256k}{5}\right)\left(\frac{5\pi}{32}\right) \qquad \text{Wallis's Formula}$$

$$= 8k\pi.$$

So, $I_x = 8k\pi = I_y$. ■

In Example 6, notice that the moments of inertia about the x- and y-axes are equal to each other. The moment about the z-axis, however, is different. Does it seem that the moment of inertia about the z-axis should be less than or greater than the moments calculated in Example 6? By performing the calculations, you can determine that

$$I_z = \frac{16}{3}k\pi.$$

This tells you that the solid shown in Figure 14.62 has a greater resistance to rotation about the x- or y-axis than about the z-axis.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

14.6 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. What does $Q = \iiint_Q dV$ represent?
2. Explain why it is beneficial to be able to change the order of integration for a triple integral.

Evaluating a Triple Iterated Integral **In Exercises 3–10, evaluate the triple iterated integral.**

3. $\int_0^3 \int_0^2 \int_0^1 (x + y + z)\, dx\, dz\, dy$
4. $\int_0^2 \int_0^1 \int_{-1}^2 xyz^3\, dx\, dy\, dz$
5. $\int_0^1 \int_0^x \int_0^{\sqrt{x}y} x\, dz\, dy\, dx$
6. $\int_0^9 \int_0^{y/3} \int_0^{\sqrt{y^2-9x^2}} z\, dz\, dx\, dy$
7. $\int_1^4 \int_0^1 \int_0^x 2ze^{-x^2}\, dy\, dx\, dz$
8. $\int_1^4 \int_1^{e^2} \int_0^{1/xz} \ln z\, dy\, dz\, dx$
9. $\int_{-3}^4 \int_0^{\pi/2} \int_0^{1+3x} x \cos y\, dz\, dy\, dx$
10. $\int_0^{\pi/2} \int_0^{y/2} \int_0^{1/y} \sin y\, dz\, dx\, dy$

Evaluating a Triple Iterated Integral Using Technology **In Exercises 11 and 12, use a graphing utility to evaluate the triple iterated integral.**

11. $\int_0^3 \int_{-\sqrt{9-y^2}}^{\sqrt{9-y^2}} \int_0^{y^2} y\, dz\, dx\, dy$
12. $\int_0^3 \int_0^{2-(2y/3)} \int_0^{6-2y-3z} ze^{-x^2y^2}\, dx\, dz\, dy$

Setting Up a Triple Integral **In Exercises 13–18, set up a triple integral for the volume of the solid. Do not evaluate the integral.**

13. The solid in the first octant bounded by the coordinate planes and the plane $z = 7 - x - 2y$
14. The solid bounded by $z = 9 - x^2$, $z = 0$, $y = 0$, and $y = 2x$
15. The solid bounded by $z = 6 - x^2 - y^2$ and $z = 0$
16. The solid bounded by $z = \sqrt{1 - x^2 - y^2}$ and $z = 0$
17. The solid that is the common interior below the sphere $x^2 + y^2 + z^2 = 80$ and above the paraboloid $z = \frac{1}{2}(x^2 + y^2)$
18. The solid bounded above by the cylinder $z = 4 - x^2$ and below by the paraboloid $z = x^2 + 3y^2$

Volume **In Exercises 19–24, use a triple integral to find the volume of the solid bounded by the graphs of the equations.**

19.



20.



21. $z = 6x^2$, $y = 3 - 3x$, first octant
22. $z = 9 - x^3$, $y = -x^2 + 2$, $y = 0$, $z = 0$, $x \geq 0$
23. $z = 2 - y$, $z = 4 - y^2$, $x = 0$, $x = 3$, $y = 0$
24. $z = \sqrt{x}$, $y = x + 2$, $y = x^2$, first octant

Changing the Order of Integration **In Exercises 25–30, sketch the solid whose volume is given by the iterated integral. Then rewrite the integral using the indicated order of integration.**

25. $\int_0^1 \int_{-1}^0 \int_0^{y^2} dz\, dy\, dx$

Rewrite using $dy\, dz\, dx$.

26. $\int_{-1}^1 \int_{y^2}^1 \int_0^{1-x} dz\, dx\, dy$

Rewrite using $dx\, dz\, dy$.

27. $\int_0^4 \int_0^{(4-x)/2} \int_0^{(12-3x-6y)/4} dz\, dy\, dx$

Rewrite using $dy\, dx\, dz$.

28. $\int_0^3 \int_0^{\sqrt{9-x^2}} \int_0^{6-x-y} dz\, dy\, dx$

Rewrite using $dz\, dx\, dy$.

29. $\int_0^1 \int_y^1 \int_0^{\sqrt{1-y^2}} dz\, dx\, dy$

Rewrite using $dz\, dy\, dx$.

30. $\int_0^2 \int_{2x}^4 \int_0^{\sqrt{y^2-4x^2}} dz\, dy\, dx$

Rewrite using $dx\, dy\, dz$.

Orders of Integration **In Exercises 31–34, write a triple integral for $f(x, y, z) = xyz$ over the solid region Q for each of the six possible orders of integration. Then evaluate one of the triple integrals.**

31. $Q = \{(x, y, z):\ 0 \leq x \leq 1, 0 \leq y \leq 5x, 0 \leq z \leq 3\}$
32. $Q = \{(x, y, z):\ 0 \leq x \leq 2, x^2 \leq y \leq 4, 0 \leq z \leq 2 - x\}$
33. $Q = \{(x, y, z):\ x^2 + y^2 \leq 9, 0 \leq z \leq 4\}$
34. $Q = \{(x, y, z):\ 0 \leq x \leq 1, 0 \leq y \leq 1 - x^2, 0 \leq z \leq 6\}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Orders of Integration **In Exercises 35 and 36, the figure shows the region of integration for the given integral. Rewrite the integral as an equivalent iterated integral in the five other orders.**

35. $\int_0^1 \int_0^{1-y^2} \int_0^{1-y} dz\, dx\, dy$



36. $\int_0^3 \int_0^x \int_0^{9-x^2} dz\, dy\, dx$



Center of Mass **In Exercises 37–40, find the mass and the indicated coordinate of the center of mass of the solid region Q of density ρ bounded by the graphs of the equations.**

37. Find $\bar{x}$ using $\rho(x, y, z) = k$.

Q: $2x + 3y + 6z = 12,\ x = 0,\ y = 0,\ z = 0$

38. Find $\bar{y}$ using $\rho(x, y, z) = ky$.

Q: $3x + 3y + 5z = 15,\ x = 0,\ y = 0,\ z = 0$

39. Find $\bar{z}$ using $\rho(x, y, z) = kx$.

Q: $z = 4 - x,\ z = 0,\ y = 0,\ y = 4,\ x = 0$

40. Find $\bar{y}$ using $\rho(x, y, z) = k$.

Q: $\frac{x}{a} + \frac{y}{b} + \frac{z}{c} = 1\ (a, b, c > 0),\ x = 0,\ y = 0,\ z = 0$

Center of Mass **In Exercises 41 and 42, set up the triple integrals for finding the mass and the center of mass of the solid of density ρ bounded by the graphs of the equations. Do not evaluate the integrals.**

41. $x = 0,\ x = b,\ y = 0,\ y = b,\ z = 0,\ z = b,\ \rho(x, y, z) = kxy$

42. $x = 0,\ x = a,\ y = 0,\ y = b,\ z = 0,\ z = c,\ \rho(x, y, z) = kz$

Think About It **The center of mass of a solid of constant density is shown in the figure. In Exercises 43–46, make a conjecture about how the center of mass $(\bar{x}, \bar{y}, \bar{z})$ will change for the nonconstant density $\rho(x, y, z)$. Explain. (Make your conjecture *without* performing any calculations.)**



43. $\rho(x, y, z) = kx$

44. $\rho(x, y, z) = kz$

45. $\rho(x, y, z) = k(y + 2)$

46. $\rho(x, y, z) = kxz^2(y + 2)^2$

Centroid **In Exercises 47–52, find the centroid of the solid region bounded by the graphs of the equations or described by the figure. Use a graphing utility to evaluate the triple integrals. (Assume uniform density and find the center of mass.)**

47. $z = \frac{h}{r}\sqrt{x^2 + y^2},\ z = h$

48. $y = \sqrt{9 - x^2},\ z = y,\ z = 0$

49. $z = \sqrt{16 - x^2 - y^2},\ z = 0$

50. $z = \frac{1}{y^2 + 1},\ z = 0,\ x = -2,\ x = 2,\ y = 0,\ y = 1$

51.



52.



Moments of Inertia **In Exercises 53–56, find I_x, I_y, and I_z for the solid of given density. Use a graphing utility to evaluate the triple integrals.**

53. (a) $\rho = k$

(b) $\rho = kxyz$



54. (a) $\rho(x, y, z) = k$

(b) $\rho(x, y, z) = k(x^2 + y^2)$



55. (a) $\rho(x, y, z) = k$

(b) $\rho = ky$



56. (a) $\rho = kz$

(b) $\rho = k(4 - z)$



Moments of Inertia **In Exercises 57 and 58, verify the moments of inertia for the solid of uniform density. Use a graphing utility to evaluate the triple integrals.**

57. $I_x = \frac{1}{12}m(3a^2 + L^2)$

$I_y = \frac{1}{2}ma^2$

$I_z = \frac{1}{12}m(3a^2 + L^2)$



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

58. $I_x = \frac{1}{12}m(a^2 + b^2)$
$I_y = \frac{1}{12}m(b^2 + c^2)$
$I_z = \frac{1}{12}m(a^2 + c^2)$



Moments of Inertia **In Exercises 59 and 60, set up a triple integral for the moment of inertia about the z-axis of the solid region Q of density ρ. Do not evaluate the integral.**

59. $Q = \{(x, y, z): -1 \le x \le 1, -1 \le y \le 1, 0 \le z \le 1 - x\}$
$\rho = \sqrt{x^2 + y^2 + z^2}$

60. $Q = \{(x, y, z): x^2 + y^2 \le 1, 0 \le z \le 4 - x^2 - y^2\}$
$\rho = kx^2$

Setting Up Triple Integrals **In Exercises 61 and 62, use the description of the solid region to set up the triple integral for (a) the mass, (b) the center of mass, and (c) the moment of inertia about the z-axis. Do not evaluate the integrals.**

61. The solid bounded by $z = 4 - x^2 - y^2$ and $z = 0$ with density $\rho(x, y, z) = kz$

62. The solid in the first octant bounded by the coordinate planes and $x^2 + y^2 + z^2 = 25$ with density $\rho(x, y, z) = kxy$

Average Value **In Exercises 63–66, find the average value of the function over the given solid region. The average value of a continuous function $f(x, y, z)$ over a solid region Q is**

$$\text{Average value} = \frac{1}{V}\iiint_Q f(x, y, z)\, dV$$

where V is the volume of the solid region Q.

63. $f(x, y, z) = z^2 + 4$ over the cube in the first octant bounded by the coordinate planes and the planes $x = 1$, $y = 1$, and $z = 1$

64. $f(x, y, z) = xyz$ over the cube in the first octant bounded by the coordinate planes and the planes $x = 4$, $y = 4$, and $z = 4$

65. $f(x, y, z) = x + y + z$ over the tetrahedron in the first octant with vertices $(0, 0, 0)$, $(2, 0, 0)$, $(0, 2, 0)$, and $(0, 0, 2)$

66. $f(x, y, z) = x + y$ over the solid bounded by the sphere $x^2 + y^2 + z^2 = 3$

Exploring Concepts

67. Determine whether the moment of inertia about the y-axis of the cylinder in Exercise 57 will increase or decrease for the nonconstant density $\rho(x, y, z) = \sqrt{x^2 + z^2}$.

68. Find the volume of the sphere $x^2 + y^2 + z^2 = 9$ using the shell method and using a triple integral. Compare your answers.

Exploring Concepts (continued)

69. Which of the integrals below is equal to $\int_1^3 \int_0^2 \int_{-1}^1 f(x, y, z)\, dz\, dy\, dx$? Explain.

(a) $\int_1^3 \int_0^2 \int_{-1}^1 f(x, y, z)\, dz\, dx\, dy$

(b) $\int_{-1}^1 \int_0^2 \int_1^3 f(x, y, z)\, dx\, dy\, dz$

(c) $\int_0^2 \int_1^3 \int_{-1}^1 f(x, y, z)\, dy\, dx\, dz$

70. **HOW DO YOU SEE IT?** Consider two solids of equal weight, as shown below.



Solid A Solid B

(a) Which solid has the greater density? Explain.

(b) Which solid has the greater moment of inertia? Explain.

(c) The solids are rolled down an inclined plane. They are started at the same time and at the same height. Which will reach the bottom first? Explain.

71. Maximizing a Triple Integral Find the solid region Q where the triple integral

$$\iiint_Q (1 - 2x^2 - y^2 - 3z^2)\, dV$$

is a maximum. Use a graphing utility to approximate the maximum value. What is the exact maximum value?

72. Finding a Value Solve for a in the triple integral.

$$\int_0^1 \int_0^{3-a-y^2} \int_a^{4-x-y^2} dz\, dx\, dy = \frac{14}{15}$$

PUTNAM EXAM CHALLENGE

73. Evaluate

$$\lim_{n\to\infty} \int_0^1 \int_0^1 \cdots \int_0^1 \cos^2\left\{\frac{\pi}{2n}(x_1 + x_2 + \cdots + x_n)\right\} dx_1\, dx_2 \cdots dx_n.$$

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

14.7 Triple Integrals in Other Coordinates

GO DIGITAL

- **Write and evaluate a triple integral in cylindrical coordinates.**
- **Write and evaluate a triple integral in spherical coordinates.**

PIERRE SIMON DE LAPLACE (1749–1827)

One of the first to use a cylindrical coordinate system was the French mathematician Pierre Simon de Laplace. Laplace has been called the "Newton of France," and he published many important works in mechanics, differential equations, and probability.

See LarsonCalculus.com to read more of this biography.

Triple Integrals in Cylindrical Coordinates

Many common solid regions, such as spheres, ellipsoids, cones, and paraboloids, can yield difficult triple integrals in rectangular coordinates. In fact, it is precisely this difficulty that led to the introduction of nonrectangular coordinate systems. In this section, you will learn how to use *cylindrical* and *spherical* coordinates to evaluate triple integrals.

Recall from Section 11.7 that the rectangular conversion equations for cylindrical coordinates are

$$x = r\cos\theta$$
$$y = r\sin\theta$$
$$z = z.$$

An easy way to remember these conversions is to note that the equations for x and y are the same as in polar coordinates and z is unchanged.

In this coordinate system, the simplest solid region is a cylindrical block determined by

$$r_1 \le r \le r_2$$
$$\theta_1 \le \theta \le \theta_2$$

and

$$z_1 \le z \le z_2$$

as shown in Figure 14.63.



Volume of cylindrical block:
$\Delta V_i = r_i \Delta r_i \Delta\theta_i \Delta z_i$

Figure 14.63

To obtain the cylindrical coordinate form of a triple integral, consider a solid region Q whose projection R onto the xy-plane can be described in polar coordinates. That is,

$$Q = \{(x, y, z):\ (x, y) \text{ is in } R,\quad h_1(x, y) \le z \le h_2(x, y)\}$$

and

$$R = \{(r, \theta):\ \theta_1 \le \theta \le \theta_2,\quad g_1(\theta) \le r \le g_2(\theta)\}.$$

If f is a continuous function on the solid Q, then you can write the triple integral of f over Q as

$$\iiint_Q f(x, y, z)\,dV = \int_R\int\left[\int_{h_1(x,\,y)}^{h_2(x,\,y)} f(x, y, z)\,dz\right]dA$$

where the double integral over R is evaluated in polar coordinates. That is, R is a plane region that is either r-simple or θ-simple (see Section 14.3). If R is r-simple, then the iterated form of the triple integral in cylindrical form is

$$\iiint_Q f(x, y, z)\,dV = \int_{\theta_1}^{\theta_2}\int_{g_1(\theta)}^{g_2(\theta)}\int_{h_1(r\cos\theta,\,r\sin\theta)}^{h_2(r\cos\theta,\,r\sin\theta)} f(r\cos\theta, r\sin\theta, z)\,r\,dz\,dr\,d\theta.$$

This is only one of six possible orders of integration. The other five are $dz\,d\theta\,dr$, $dr\,dz\,d\theta$, $dr\,d\theta\,dz$, $d\theta\,dz\,dr$, and $d\theta\,dr\,dz$.

ART Collection/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Integrate with respect to r.



Integrate with respect to θ.



Integrate with respect to z.

Figure 14.64



Figure 14.65

To visualize a particular order of integration, it helps to view the iterated integral in terms of three sweeping motions, each adding another dimension to the solid. For instance, in the order $dr\,d\theta\,dz$, the first integration occurs in the r-direction as a point sweeps out a ray. Then, as θ increases, the line sweeps out a sector. Finally, as z increases, the sector sweeps out a solid wedge, as shown in Figure 14.64.

Exploration

Volume of a Paraboloid Sector In the Explorations on pages 983, 992, and 1014, you were asked to summarize the different ways you know of finding the volume of the solid bounded by the paraboloid

$$z = a^2 - x^2 - y^2, \quad a > 0$$

and the xy-plane. You now know one more way. Use it to find the volume of the solid. Compare the different methods. What are the advantages and disadvantages of each?



EXAMPLE 1 Finding Volume in Cylindrical Coordinates

Find the volume of the solid region Q cut from the sphere $x^2 + y^2 + z^2 = 4$ by the cylinder $r = 2 \sin\theta$, as shown in Figure 14.65.

Solution Because $x^2 + y^2 + z^2 = r^2 + z^2 = 4$, the bounds on z are

$$-\sqrt{4 - r^2} \le z \le \sqrt{4 - r^2}. \qquad \text{Bounds for } z$$

Let R be the circular projection of the solid onto the $r\theta$-plane. Then the bounds on R are

$$0 \le r \le 2\sin\theta \quad \text{and} \quad 0 \le \theta \le \pi. \qquad \text{Bounds for } R$$

So, the volume of Q is

$$V = \int_0^{\pi}\int_0^{2\sin\theta}\int_{-\sqrt{4-r^2}}^{\sqrt{4-r^2}} r\,dz\,dr\,d\theta \qquad \text{Apply formula for volume.}$$

$$= 2\int_0^{\pi/2}\int_0^{2\sin\theta}\int_{-\sqrt{4-r^2}}^{\sqrt{4-r^2}} r\,dz\,dr\,d\theta \qquad \text{Use symmetry to rewrite bounds for } \theta.$$

$$= 2\int_0^{\pi/2}\int_0^{2\sin\theta} 2r\sqrt{4 - r^2}\,dr\,d\theta \qquad \text{Integrate with respect to } z.$$

$$= 2\int_0^{\pi/2} -\frac{2}{3}(4 - r^2)^{3/2}\Big]_0^{2\sin\theta} d\theta \qquad \text{Integrate with respect to } r.$$

$$= \frac{4}{3}\int_0^{\pi/2} (8 - 8\cos^3\theta)\,d\theta$$

$$= \frac{32}{3}\int_0^{\pi/2} [1 - (\cos\theta)(1 - \sin^2\theta)]\,d\theta \qquad \text{Factor and use trigonometric identity } \cos^2\theta = 1 - \sin^2\theta.$$

$$= \frac{32}{3}\left[\theta - \sin\theta + \frac{\sin^3\theta}{3}\right]_0^{\pi/2} \qquad \text{Integrate with respect to } \theta.$$

$$= \frac{16}{9}(3\pi - 4)$$

$$\approx 9.644.$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



Figure 14.66

EXAMPLE 2 Finding Mass in Cylindrical Coordinates

Find the mass of the ellipsoid Q given by $4x^2 + 4y^2 + z^2 = 16$, lying above the xy-plane. The density at a point in the solid is proportional to the distance between the point and the xy-plane.

Solution The density function is $\rho(r, \theta, z) = kz$, where k is the constant of proportionality. The bounds on z are

$$0 \le z \le \sqrt{16 - 4x^2 - 4y^2} = \sqrt{16 - 4r^2}$$

where $0 \le r \le 2$ and $0 \le \theta \le 2\pi$, as shown in Figure 14.66. The mass of the solid is

$$\begin{aligned}
m &= \int_0^{2\pi}\int_0^{2}\int_0^{\sqrt{16-4r^2}} kzr\,dz\,dr\,d\theta && \text{Apply formula for mass of a solid.}\\
&= \frac{k}{2}\int_0^{2\pi}\int_0^{2} z^2 r\Big]_0^{\sqrt{16-4r^2}}\,dr\,d\theta && \text{Integrate with respect to } z.\\
&= \frac{k}{2}\int_0^{2\pi}\int_0^{2} (16r - 4r^3)\,dr\,d\theta\\
&= \frac{k}{2}\int_0^{2\pi}\Big[8r^2 - r^4\Big]_0^{2}\,d\theta && \text{Integrate with respect to } r.\\
&= 8k\int_0^{2\pi} d\theta\\
&= 16\pi k. && \text{Integrate with respect to } \theta.
\end{aligned}$$

Integration in cylindrical coordinates is useful when factors involving $x^2 + y^2$ appear in the integrand, as illustrated in Example 3.

EXAMPLE 3 Finding a Moment of Inertia

Find the moment of inertia about the axis of symmetry of the solid Q bounded by the paraboloid $z = x^2 + y^2$ and the plane $z = 4$, as shown in Figure 14.67. The density at each point is proportional to the distance between the point and the z-axis.

Solution Because the z-axis is the axis of symmetry and $\rho(x, y, z) = k\sqrt{x^2 + y^2}$, where k is the constant of proportionality, it follows that

$$I_z = \iiint_Q k(x^2 + y^2)\sqrt{x^2 + y^2}\,dV. \qquad \text{Moment of inertia about } z\text{-axis}$$

In cylindrical coordinates, $0 \le r \le \sqrt{x^2 + y^2} = \sqrt{z}$ and $0 \le \theta \le 2\pi$. So, you have

$$\begin{aligned}
I_z &= k\int_0^{4}\int_0^{2\pi}\int_0^{\sqrt{z}} r^2(r)r\,dr\,d\theta\,dz && \text{Cylindrical coordinates}\\
&= k\int_0^{4}\int_0^{2\pi} \frac{r^5}{5}\Big]_0^{\sqrt{z}}\,d\theta\,dz && \text{Integrate with respect to } r.\\
&= k\int_0^{4}\int_0^{2\pi} \frac{z^{5/2}}{5}\,d\theta\,dz\\
&= \frac{k}{5}\int_0^{4} z^{5/2}(2\pi)\,dz && \text{Integrate with respect to } \theta.\\
&= \frac{2\pi k}{5}\left[\frac{2}{7}z^{7/2}\right]_0^{4} && \text{Integrate with respect to } z.\\
&= \frac{512k\pi}{35}.
\end{aligned}$$



Figure 14.67

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Triple Integrals in Spherical Coordinates

Triple integrals involving spheres or cones are often easier to evaluate by converting to spherical coordinates. Recall from Section 11.7 that the rectangular conversion equations for spherical coordinates are

$$x = \rho \sin\phi \cos\theta$$
$$y = \rho \sin\phi \sin\theta$$
$$z = \rho \cos\phi.$$

REMARK The Greek letter ρ used in spherical coordinates is not related to density. Rather, it is the three-dimensional analog of the r used in polar coordinates. For problems involving spherical coordinates and a density function, this text uses a different symbol to denote density.

In this coordinate system, the simplest region is a spherical block determined by

$$\{(\rho, \theta, \phi):\ \rho_1 \le \rho \le \rho_2,\quad \theta_1 \le \theta \le \theta_2,\quad \phi_1 \le \phi \le \phi_2\}$$

where $\rho_1 \ge 0$, $\theta_2 - \theta_1 \le 2\pi$, and $0 \le \phi_1 \le \phi_2 \le \pi$, as shown in Figure 14.68. If (ρ, θ, ϕ) is a point in the interior of such a block, then the volume of the block can be approximated by $\Delta V \approx \rho^2 \sin\phi \Delta\rho \Delta\phi \Delta\theta$. (See Exercise 6 in the P.S. Problem Solving exercises at the end of this chapter.)

Using the usual process involving an inner partition, summation, and a limit, you can develop a triple integral in spherical coordinates for a continuous function f defined on the solid region Q. This formula, shown below, can be modified for different orders of integration and generalized to include regions with variable boundaries.



Spherical block: $\Delta V_i \approx \rho_i^2 \sin\phi_i \Delta\rho_i \Delta\phi_i \Delta\theta_i$

Figure 14.68

$$\iiint_Q f(x, y, z)\, dV = \int_{\theta_1}^{\theta_2} \int_{\phi_1}^{\phi_2} \int_{\rho_1}^{\rho_2} f(\rho \sin\phi \cos\theta, \rho \sin\phi \sin\theta, \rho \cos\phi)\rho^2 \sin\phi\, d\rho\, d\phi\, d\theta$$

Like triple integrals in cylindrical coordinates, triple integrals in spherical coordinates are evaluated with iterated integrals. As with cylindrical coordinates, you can visualize a particular order of integration by viewing the iterated integral in terms of three sweeping motions, each adding another dimension to the solid. For instance, the iterated integral

$$\int_0^{2\pi} \int_0^{\pi/4} \int_0^3 \rho^2 \sin\phi\, d\rho\, d\phi\, d\theta$$

(which is used in Example 4) is illustrated in Figure 14.69.



ρ varies from 0 to 3 with ϕ and θ held constant.



ϕ varies from 0 to $\pi/4$ with θ held constant.



θ varies from 0 to 2π.

Figure 14.69

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 14.70

EXAMPLE 4 Finding Volume in Spherical Coordinates

Find the volume of the solid region Q bounded below by the upper nappe of the cone $z^2 = x^2 + y^2$ and above by the sphere $x^2 + y^2 + z^2 = 9$, as shown in Figure 14.70.

Solution In spherical coordinates, the equation of the sphere is

$$\rho^2 = x^2 + y^2 + z^2 = 9 \quad \Rightarrow \quad \rho = 3.$$

Furthermore, the sphere and cone intersect when

$$(x^2 + y^2) + z^2 = (z^2) + z^2 = 9 \quad \Rightarrow \quad z = \frac{3}{\sqrt{2}}$$

and, because $z = \rho \cos\phi$, it follows that

$$\left(\frac{3}{\sqrt{2}}\right)\left(\frac{1}{3}\right) = \cos\phi \quad \Rightarrow \quad \phi = \frac{\pi}{4}.$$

Consequently, you can use the integration order $d\rho\, d\phi\, d\theta$, where $0 \le \rho \le 3$, $0 \le \phi \le \pi/4$, and $0 \le \theta \le 2\pi$. The volume is

$$\begin{aligned}
V &= \int_0^{2\pi}\int_0^{\pi/4}\int_0^3 \rho^2 \sin\phi\, d\rho\, d\phi\, d\theta && \text{Apply formula for volume.}\\
&= \int_0^{2\pi}\int_0^{\pi/4} 9\sin\phi\, d\phi\, d\theta && \text{Integrate with respect to } \rho.\\
&= 9\int_0^{2\pi} -\cos\phi\Big]_0^{\pi/4} d\theta && \text{Integrate with respect to } \phi.\\
&= 9\int_0^{2\pi}\left(1 - \frac{\sqrt{2}}{2}\right) d\theta\\
&= 9\pi\left(2 - \sqrt{2}\right) && \text{Integrate with respect to } \theta.\\
&\approx 16.563.
\end{aligned}$$

EXAMPLE 5 Finding the Center of Mass of a Solid Region

See LarsonCalculus.com for an interactive version of this type of example.

Find the center of mass of the solid region Q of uniform density from Example 4.

Solution Because the density is uniform, you can consider the density at the point (x, y, z) to be k. By symmetry, the center of mass lies on the z-axis, and you need only calculate $\bar{z} = M_{xy}/m$, where $m = kV = 9k\pi\left(2 - \sqrt{2}\right)$. Because $z = \rho\cos\phi$, it follows that

$$\begin{aligned}
M_{xy} &= \iiint_Q kz\, dV = k\int_0^3\int_0^{2\pi}\int_0^{\pi/4} (\rho\cos\phi)\rho^2\sin\phi\, d\phi\, d\theta\, d\rho\\
&= k\int_0^3\int_0^{2\pi} \rho^3 \frac{\sin^2\phi}{2}\Big]_0^{\pi/4} d\theta\, d\rho\\
&= \frac{k}{4}\int_0^3\int_0^{2\pi} \rho^3\, d\theta\, d\rho = \frac{k\pi}{2}\int_0^3 \rho^3\, d\rho = \frac{81k\pi}{8}.
\end{aligned}$$

So,

$$\bar{z} = \frac{M_{xy}}{m} = \frac{81k\pi/8}{9k\pi\left(2 - \sqrt{2}\right)} = \frac{9\left(2 + \sqrt{2}\right)}{16} \approx 1.920$$

and the center of mass is approximately $(0, 0, 1.920)$. ■

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

14.7 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain why triple integrals that represent the volumes of solids are sometimes easier to evaluate in cylindrical or spherical coordinates instead of rectangular coordinates.
2. What is the differential of volume, dV, for (a) cylindrical coordinates and (b) spherical coordinates? Choose one order of integration for each system.

Evaluating a Triple Iterated Integral **In Exercises 3–8, evaluate the triple iterated integral.**

3. $\int_{-1}^{5}\int_{0}^{\pi/2}\int_{0}^{3} r\cos\theta\, dr\, d\theta\, dz$
4. $\int_{0}^{\pi/4}\int_{0}^{6}\int_{0}^{6-r} rz\, dz\, dr\, d\theta$
5. $\int_{0}^{\pi/2}\int_{0}^{\cos\theta}\int_{0}^{3+r^2} 2r\sin\theta\, dz\, dr\, d\theta$
6. $\int_{0}^{\pi/2}\int_{0}^{\pi}\int_{0}^{2} e^{-\rho^3}\rho^2\, d\rho\, d\theta\, d\phi$
7. $\int_{0}^{2\pi}\int_{0}^{\pi/2}\int_{0}^{\sin\phi} \rho\cos\phi\, d\rho\, d\phi\, d\theta$
8. $\int_{0}^{\pi/4}\int_{0}^{\pi/4}\int_{0}^{\cos\theta} \rho^2\sin\phi\cos\phi\, d\rho\, d\theta\, d\phi$

Evaluating a Triple Iterated Integral Using Technology **In Exercises 9 and 10, use a graphing utility to evaluate the triple iterated integral.**

9. $\int_{0}^{4}\int_{0}^{z}\int_{0}^{\pi/2} re^{r}\, d\theta\, dr\, dz$
10. $\int_{0}^{\pi/2}\int_{0}^{\pi}\int_{0}^{\sin\theta} 2\rho^2\cos\phi\, d\rho\, d\theta\, d\phi$

Volume **In Exercises 11–14, sketch the solid region whose volume is given by the iterated integral and evaluate the iterated integral.**

11. $\int_{0}^{\pi/2}\int_{0}^{3}\int_{0}^{e^{-r^2}} r\, dz\, dr\, d\theta$
12. $\int_{0}^{2\pi}\int_{0}^{2\sqrt{2}}\int_{r^2-2}^{6} r\, dz\, dr\, d\theta$
13. $\int_{0}^{2\pi}\int_{\pi/6}^{\pi/2}\int_{0}^{4} \rho^2\sin\phi\, d\rho\, d\phi\, d\theta$
14. $\int_{0}^{2\pi}\int_{0}^{\pi}\int_{2}^{5} \rho^2\sin\phi\, d\rho\, d\phi\, d\theta$

Volume **In Exercises 15–20, use cylindrical coordinates to find the volume of the solid.**

15. Solid inside both $x^2 + y^2 + z^2 = 36$ and $(x-3)^2 + y^2 = 9$
16. Solid inside $x^2 + y^2 + z^2 = 16$ and outside $z = \sqrt{x^2 + y^2}$
17. Solid bounded above by $z = 2x$ and below by $z = 2x^2 + 2y^2$
18. Solid bounded above by $z = 2 - x^2 - y^2$ and below by $z = x^2 + y^2$
19. Solid bounded by the graphs of the sphere $r^2 + z^2 = 25$ and the cylinder $r = 5\cos\theta$
20. Solid inside the sphere $x^2 + y^2 + z^2 = 4$ and above the upper nappe of the cone $z^2 = x^2 + y^2$

Mass **In Exercises 21 and 22, use cylindrical coordinates to find the mass of the solid Q of density ρ.**

21. $Q = \{(x, y, z):\ 0 \le z \le 9 - x - 2y,\ x^2 + y^2 \le 4\}$
$\rho(x, y, z) = k\sqrt{x^2 + y^2}$
22. $Q = \{(x, y, z):\ 0 \le z \le 12e^{-(x^2+y^2)},\ x^2 + y^2 \le 4,\ x \ge 0,\ y \ge 0\}$
$\rho(x, y, z) = k$

Using Cylindrical Coordinates **In Exercises 23–28, use cylindrical coordinates to find the indicated characteristic of the cone shown in the figure.**



23. Find the volume of the cone.
24. Find the centroid of the cone.
25. Find the center of mass of the cone, assuming that its density at any point is proportional to the distance between the point and the axis of the cone. Use a graphing utility to evaluate the triple integral.
26. Find the center of mass of the cone, assuming that its density at any point is proportional to the distance between the point and the base. Use a graphing utility to evaluate the triple integral.
27. Assume that the cone has uniform density and show that the moment of inertia about the z-axis is
$I_z = \frac{3}{10}mr_0^2$.
28. Assume that the density of the cone is $\rho(x, y, z) = k\sqrt{x^2 + y^2}$ and find the moment of inertia about the z-axis.

Moment of Inertia **In Exercises 29 and 30, use cylindrical coordinates to verify the given moment of inertia of the solid of uniform density.**

29. Cylindrical shell: $I_z = \frac{1}{2}m(a^2 + b^2)$
$0 < a \le r \le b,\quad 0 \le z \le h$
30. Right circular cylinder: $I_z = \frac{3}{2}ma^2$
$r = 2a\sin\theta,\quad 0 \le z \le h$
(Use a graphing utility to evaluate the triple integral.)

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Volume **In Exercises 31–34, use spherical coordinates to find the volume of the solid.**

31. Solid inside

$x^2 + y^2 + z^2 = 9$

outside $z = \sqrt{x^2 + y^2}$, and above the xy-plane

32. Solid bounded above by

$x^2 + y^2 + z^2 = z$

and below by $z = \sqrt{x^2 + y^2}$

33. The torus given by $\rho = 4 \sin \phi$ (Use a graphing utility to evaluate the triple integral.)

34. The solid between the spheres

$x^2 + y^2 + z^2 = a^2$ and $x^2 + y^2 + z^2 = b^2, b > a,$

and inside the cone $z^2 = x^2 + y^2$

Mass **In Exercises 35 and 36, use spherical coordinates to find the mass of the sphere $x^2 + y^2 + z^2 = a^2$ with the given density.**

35. The density at any point is proportional to the distance between the point and the origin.

36. The density at any point is proportional to the distance between the point and the z-axis.

Center of Mass **In Exercises 37 and 38, use spherical coordinates to find the center of mass of the solid of uniform density.**

37. Hemispherical solid of radius r

38. Solid lying between two concentric hemispheres of radii r and R, where $r < R$

Moment of Inertia **In Exercises 39 and 40, use spherical coordinates to find the moment of inertia about the z-axis of the solid of uniform density.**

39. Solid bounded by the hemisphere $\rho = \cos \phi$, $\frac{\pi}{4} \le \phi \le \frac{\pi}{2}$, and the cone $\phi = \frac{\pi}{4}$

40. Solid lying between two concentric hemispheres of radii r and R, where $r < R$

Converting Coordinates **In Exercises 41–44, convert the integral from rectangular coordinates to both cylindrical and spherical coordinates, and evaluate the simplest iterated integral.**

41. $\displaystyle\int_{-2}^{2}\int_{-\sqrt{4-x^2}}^{\sqrt{4-x^2}}\int_{x^2+y^2}^{4} x \, dz \, dy \, dx$

42. $\displaystyle\int_{0}^{2}\int_{0}^{\sqrt{4-x^2}}\int_{0}^{\sqrt{16-x^2-y^2}} \sqrt{x^2 + y^2} \, dz \, dy \, dx$

43. $\displaystyle\int_{-1}^{1}\int_{-\sqrt{1-x^2}}^{\sqrt{1-x^2}}\int_{1}^{1+\sqrt{1-x^2-y^2}} x \, dz \, dy \, dx$

44. $\displaystyle\int_{0}^{3}\int_{0}^{\sqrt{9-x^2}}\int_{0}^{\sqrt{9-x^2-y^2}} \sqrt{x^2 + y^2 + z^2} \, dz \, dy \, dx$

Exploring Concepts

45. Describe the surface whose equation is a coordinate equal to a constant for each of the coordinates in (a) the cylindrical coordinate system and (b) the spherical coordinate system.

46. **HOW DO YOU SEE IT?** The solid is bounded below by the upper nappe of a cone and above by a sphere (see figure). Would it be easier to use cylindrical coordinates or spherical coordinates to find the volume of the solid? Explain.



PUTNAM EXAM CHALLENGE

47. Find the volume of the region of points (x, y, z) such that $(x^2 + y^2 + z^2 + 8)^2 \le 36(x^2 + y^2)$.

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

SECTION PROJECT

Wrinkled and Bumpy Spheres

In parts (a) and (b), find the volume of the wrinkled sphere or bumpy sphere. These solids are used as models for tumors.

(a) Wrinkled sphere

$\rho = 1 + 0.2 \sin 8\theta \sin \phi$

$0 \le \theta \le 2\pi, 0 \le \phi \le \pi$



Generated by Maple

(b) Bumpy sphere

$\rho = 1 + 0.2 \sin 8\theta \sin 4\phi$

$0 \le \theta \le 2\pi, 0 \le \phi \le \pi$



Generated by Maple

FOR FURTHER INFORMATION For more information on these types of spheres, see the article "Heat Therapy for Tumors" by Leah Edelstein-Keshet in *The UMAP Journal.*

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

14.8 Change of Variables: Jacobians

GO DIGITAL

- **Describe the concept of a Jacobian.**
- **Use a Jacobian to change variables in a double integral.**



CARL GUSTAV JACOBI (1804–1851)

The Jacobian is named after the German mathematician Carl Gustav Jacobi. Jacobi is known for his work in many areas of mathematics, but his interest in integration stemmed from the problem of finding the circumference of an ellipse. *See LarsonCalculus.com to read more of this biography.*

Jacobians

For the single integral

$$\int_a^b f(x)\,dx$$

you can change variables by letting $x = g(u)$, so that $dx = g'(u)\,du$, and obtain

$$\int_a^b f(x)\,dx = \int_c^d f(g(u))g'(u)\,du$$

where $a = g(c)$ and $b = g(d)$. Note that the change of variables process introduces an additional factor $g'(u)$ into the integrand. This also occurs in the case of double integrals

$$\int_R\int f(x, y)\,dA = \int_S\int f(g(u, v), h(u, v))\underbrace{\left|\frac{\partial x}{\partial u}\frac{\partial y}{\partial v} - \frac{\partial y}{\partial u}\frac{\partial x}{\partial v}\right|}_{\text{Jacobian}}\,du\,dv$$

where the change of variables $x = g(u, v)$ and $y = h(u, v)$ introduces a factor called the **Jacobian** of x and y with respect to u and v. In defining the Jacobian, it is convenient to use the determinant notation shown below.

Definition of the Jacobian

If $x = g(u, v)$ and $y = h(u, v)$, then the **Jacobian** of x and y with respect to u and v, denoted by $\partial(x, y)/\partial(u, v)$, is

$$\frac{\partial(x, y)}{\partial(u, v)} = \begin{vmatrix} \frac{\partial x}{\partial u} & \frac{\partial x}{\partial v} \\ \frac{\partial y}{\partial u} & \frac{\partial y}{\partial v} \end{vmatrix} = \frac{\partial x}{\partial u}\frac{\partial y}{\partial v} - \frac{\partial y}{\partial u}\frac{\partial x}{\partial v}.$$

EXAMPLE 1 The Jacobian for Rectangular-to-Polar Conversion

Find the Jacobian for the change of variables defined by

$$x = r\cos\theta \quad \text{and} \quad y = r\sin\theta.$$

Solution From the definition of the Jacobian, you obtain

$$\begin{aligned} \frac{\partial(x, y)}{\partial(r, \theta)} &= \begin{vmatrix} \frac{\partial x}{\partial r} & \frac{\partial x}{\partial \theta} \\ \frac{\partial y}{\partial r} & \frac{\partial y}{\partial \theta} \end{vmatrix} && \text{Definition of Jacobian} \\ &= \begin{vmatrix} \cos\theta & -r\sin\theta \\ \sin\theta & r\cos\theta \end{vmatrix} && \text{Substitute.} \\ &= r\cos^2\theta + r\sin^2\theta && \text{Find determinant.} \\ &= r(\cos^2\theta + \sin^2\theta) && \text{Factor.} \\ &= r. && \text{Trigonometric identity} \end{aligned}$$

INTERFOTO/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



S is the region in the $r\theta$-plane that corresponds to R in the xy-plane.
Figure 14.71



Region R in the xy-plane
Figure 14.72



Region S in the uv-plane
Figure 14.73

GO DIGITAL

Example 1 points out that the change of variables from rectangular to polar coordinates for a double integral can be written as

$$\iint_R f(x, y)\, dA = \iint_S f(r\cos\theta, r\sin\theta) r\, dr\, d\theta, \; r > 0$$
$$= \iint_S f(r\cos\theta, r\sin\theta) \left|\frac{\partial(x, y)}{\partial(r, \theta)}\right| dr\, d\theta$$

where S is the region in the $r\theta$-plane that corresponds to the region R in the xy-plane, as shown in Figure 14.71. Note that this formula is similar to the one in Theorem 14.3. (See Section 14.3).

In general, a change of variables using a one-to-one **transformation** T from a region S in the uv-plane to a region R in the xy-plane is given by

$$T(u, v) = (x, y) = (g(u, v), h(u, v))$$

where g and h have continuous first partial derivatives in the region S. Note that the point (u, v) lies in S and the point (x, y) lies in R. In most cases, you are hunting for a transformation in which the region S is simpler than the region R.

EXAMPLE 2 Finding a Change of Variables to Simplify a Region

Let R be the region bounded by the lines

$$x - 2y = 0, \quad x - 2y = -4, \quad x + y = 4, \quad \text{and} \quad x + y = 1$$

as shown in Figure 14.72. Find a transformation T from a region S to R such that S is a rectangular region (with sides parallel to the u- or v-axis).

Solution To begin, let $u = x + y$ and $v = x - 2y$. Solving this system of equations for x and y produces $T(u, v) = (x, y)$, where

$$x = \frac{1}{3}(2u + v) \quad \text{and} \quad y = \frac{1}{3}(u - v).$$

The four boundaries for R in the xy-plane give rise to the following bounds for S in the uv-plane.

Bounds in the xy-Plane		**Bounds in the uv-Plane**
$x + y = 1$	⇨	$u = 1$
$x + y = 4$	⇨	$u = 4$
$x - 2y = 0$	⇨	$v = 0$
$x - 2y = -4$	⇨	$v = -4$

The region S is shown in Figure 14.73. Note that the transformation

$$T(u, v) = (x, y) = \left(\frac{1}{3}[2u + v], \frac{1}{3}[u - v]\right)$$

maps the vertices of the region S onto the vertices of the region R, as shown below.

$$T(1, 0) = \left(\frac{1}{3}[2(1) + 0], \frac{1}{3}[1 - 0]\right) = \left(\frac{2}{3}, \frac{1}{3}\right)$$
$$T(4, 0) = \left(\frac{1}{3}[2(4) + 0], \frac{1}{3}[4 - 0]\right) = \left(\frac{8}{3}, \frac{4}{3}\right)$$
$$T(4, -4) = \left(\frac{1}{3}[2(4) - 4], \frac{1}{3}[4 - (-4)]\right) = \left(\frac{4}{3}, \frac{8}{3}\right)$$
$$T(1, -4) = \left(\frac{1}{3}[2(1) - 4], \frac{1}{3}[1 - (-4)]\right) = \left(-\frac{2}{3}, \frac{5}{3}\right)$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Change of Variables for Double Integrals

THEOREM 14.5 Change of Variables for Double Integrals

Let R be a vertically or horizontally simple region in the xy-plane, and let S be a vertically or horizontally simple region in the uv-plane. Let T from S to R be given by $T(u, v) = (x, y) = (g(u, v), h(u, v))$, where g and h have continuous first partial derivatives. Assume that T is one-to-one except possibly on the boundary of S. If f is continuous on R, and $\partial(x, y)/\partial(u, v)$ is nonzero on S, then

$$\int_R\int f(x, y)\, dx\, dy = \int_S\int f(g(u, v), h(u, v)) \left|\frac{\partial(x, y)}{\partial(u, v)}\right| du\, dv.$$



Area of $S = \Delta u\, \Delta v$
$\Delta u > 0, \Delta v > 0$
Figure 14.74



The vertices in the xy-plane are $M(g(u, v), h(u, v))$, $N(g(u + \Delta u, v), h(u + \Delta u, v))$, $P(g(u + \Delta u, v + \Delta v), h(u + \Delta u, v + \Delta v))$, and $Q(g(u, v + \Delta v), h(u, v + \Delta v))$.
Figure 14.75

Proof Consider the case in which S is a rectangular region in the uv-plane with vertices (u, v), $(u + \Delta u, v)$, $(u + \Delta u, v + \Delta v)$, and $(u, v + \Delta v)$, as shown in Figure 14.74. The images of these vertices in the xy-plane are shown in Figure 14.75. If Δu and Δv are small, then the continuity of g and h implies that R is approximately a parallelogram determined by the vectors $\overrightarrow{MN}$ and $\overrightarrow{MQ}$. So, the area of R is

$$\Delta A \approx \|\overrightarrow{MN} \times \overrightarrow{MQ}\|.$$

Moreover, for small Δu and Δv, the partial derivatives of g and h with respect to u can be approximated by

$$g_u(u, v) \approx \frac{g(u + \Delta u, v) - g(u, v)}{\Delta u} \quad \text{and} \quad h_u(u, v) \approx \frac{h(u + \Delta u, v) - h(u, v)}{\Delta u}.$$

Consequently,

$$\begin{aligned}\overrightarrow{MN} &= [g(u + \Delta u, v) - g(u, v)]\mathbf{i} + [h(u + \Delta u, v) - h(u, v)]\mathbf{j} \\ &\approx [g_u(u, v)\, \Delta u]\mathbf{i} + [h_u(u, v)\, \Delta u]\mathbf{j} \\ &= \frac{\partial x}{\partial u}\Delta u\mathbf{i} + \frac{\partial y}{\partial u}\Delta u\mathbf{j}.\end{aligned}$$

Similarly, you can approximate $\overrightarrow{MQ}$ by $\frac{\partial x}{\partial v}\Delta v\mathbf{i} + \frac{\partial y}{\partial v}\Delta v\mathbf{j}$, which implies that

$$\overrightarrow{MN} \times \overrightarrow{MQ} \approx \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ \frac{\partial x}{\partial u}\Delta u & \frac{\partial y}{\partial u}\Delta u & 0 \\ \frac{\partial x}{\partial v}\Delta v & \frac{\partial y}{\partial v}\Delta v & 0 \end{vmatrix} = \begin{vmatrix} \frac{\partial x}{\partial u} & \frac{\partial y}{\partial u} \\ \frac{\partial x}{\partial v} & \frac{\partial y}{\partial v} \end{vmatrix} \Delta u\, \Delta v\mathbf{k}.$$

It follows that, in Jacobian notation,

$$\Delta A \approx \|\overrightarrow{MN} \times \overrightarrow{MQ}\| \approx \left|\frac{\partial(x, y)}{\partial(u, v)}\right| \Delta u\, \Delta v.$$

Because this approximation improves as Δu and Δv approach 0, the limiting case can be written as

$$dA \approx \|\overrightarrow{MN} \times \overrightarrow{MQ}\| \approx \left|\frac{\partial(x, y)}{\partial(u, v)}\right| du\, dv.$$

So,

$$\int_R\int f(x, y)\, dx\, dy = \int_S\int f(g(u, v), h(u, v))\left|\frac{\partial(x, y)}{\partial(u, v)}\right| du\, dv.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

The next two examples show how a change of variables can simplify the integration process. The simplification can occur in various ways. You can make a change of variables to simplify either the *region R* or the *integrand* $f(x, y)$, or both.

EXAMPLE 3 Using a Change of Variables to Simplify a Region

See LarsonCalculus.com for an interactive version of this type of example.



Figure 14.76

Let R be the region bounded by the lines

$$x - 2y = 0, \quad x - 2y = -4, \quad x + y = 4, \quad \text{and} \quad x + y = 1$$

as shown in Figure 14.76. Evaluate the double integral

$$\iint_R 3xy\, dA.$$

Solution From Example 2, you can use the change of variables

$$x = \frac{1}{3}(2u + v) \quad \text{and} \quad y = \frac{1}{3}(u - v).$$



Figure 14.77

(Note that the region S is shown in Figure 14.77.) The partial derivatives of x and y are

$$\frac{\partial x}{\partial u} = \frac{2}{3}, \quad \frac{\partial x}{\partial v} = \frac{1}{3}, \quad \frac{\partial y}{\partial u} = \frac{1}{3}, \quad \text{and} \quad \frac{\partial y}{\partial v} = -\frac{1}{3}$$

which implies that the Jacobian is

$$\begin{aligned}
\frac{\partial(x, y)}{\partial(u, v)} &= \begin{vmatrix} \frac{\partial x}{\partial u} & \frac{\partial x}{\partial v} \\ \frac{\partial y}{\partial u} & \frac{\partial y}{\partial v} \end{vmatrix} \\
&= \begin{vmatrix} \frac{2}{3} & \frac{1}{3} \\ \frac{1}{3} & -\frac{1}{3} \end{vmatrix} \\
&= -\frac{2}{9} - \frac{1}{9} \\
&= -\frac{1}{3}.
\end{aligned}$$

So, by Theorem 14.5, you obtain

$$\begin{aligned}
\iint_R 3xy\, dA &= \iint_S 3\left[\frac{1}{3}(2u + v)\,\frac{1}{3}(u - v)\right]\left|\frac{\partial(x, y)}{\partial(u, v)}\right| dv\, du \\
&= \int_1^4 \int_{-4}^0 \frac{1}{9}(2u^2 - uv - v^2)\, dv\, du \\
&= \frac{1}{9}\int_1^4 \left[2u^2 v - \frac{uv^2}{2} - \frac{v^3}{3}\right]_{-4}^0 du \\
&= \frac{1}{9}\int_1^4 \left(8u^2 + 8u - \frac{64}{3}\right) du \\
&= \frac{1}{9}\left[\frac{8u^3}{3} + 4u^2 - \frac{64}{3}u\right]_1^4 \\
&= \frac{164}{9}.
\end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



Region R in the xy-plane
Figure 14.78



Region S in the uv-plane
Figure 14.79

EXAMPLE 4 Change of Variables: Simplifying an Integrand

Let R be the region bounded by the square with vertices $(0, 1)$, $(1, 2)$, $(2, 1)$, and $(1, 0)$. Evaluate the integral

$$\iint_R (x + y)^2 \sin^2(x - y)\, dA.$$

Solution Note that the sides of R lie on the lines $x + y = 1$, $x - y = 1$, $x + y = 3$, and $x - y = -1$, as shown in Figure 14.78. Letting $u = x + y$ and $v = x - y$, you can determine the bounds for region S in the uv-plane to be

$$1 \le u \le 3 \quad \text{and} \quad -1 \le v \le 1$$

as shown in Figure 14.79. Solving for x and y in terms of u and v produces

$$x = \frac{1}{2}(u + v) \quad \text{and} \quad y = \frac{1}{2}(u - v).$$

The partial derivatives of x and y are

$$\frac{\partial x}{\partial u} = \frac{1}{2}, \quad \frac{\partial x}{\partial v} = \frac{1}{2}, \quad \frac{\partial y}{\partial u} = \frac{1}{2}, \quad \text{and} \quad \frac{\partial y}{\partial v} = -\frac{1}{2}$$

which implies that the Jacobian is

$$\frac{\partial(x, y)}{\partial(u, v)} = \begin{vmatrix} \frac{\partial x}{\partial u} & \frac{\partial x}{\partial v} \\ \frac{\partial y}{\partial u} & \frac{\partial y}{\partial v} \end{vmatrix} = \begin{vmatrix} \frac{1}{2} & \frac{1}{2} \\ \frac{1}{2} & -\frac{1}{2} \end{vmatrix} = -\frac{1}{4} - \frac{1}{4} = -\frac{1}{2}.$$

By Theorem 14.5, it follows that

$$\begin{aligned}
\iint_R (x + y)^2 \sin^2(x - y)\, dA &= \int_{-1}^{1}\int_{1}^{3} u^2(\sin^2 v)\left(\frac{1}{2}\right) du\, dv \\
&= \frac{1}{2}\int_{-1}^{1} (\sin^2 v)\, \frac{u^3}{3}\Big]_1^3 dv \\
&= \frac{13}{3}\int_{-1}^{1} \sin^2 v\, dv \\
&= \frac{13}{6}\int_{-1}^{1} (1 - \cos 2v)\, dv \\
&= \frac{13}{6}\left[v - \frac{1}{2}\sin 2v\right]_{-1}^{1} \\
&= \frac{13}{6}\left[2 - \frac{1}{2}\sin 2 + \frac{1}{2}\sin(-2)\right] \\
&= \frac{13}{6}(2 - \sin 2) \\
&\approx 2.363.
\end{aligned}$$

In each of the change of variables examples in this section, the region S has been a rectangle with sides parallel to the u- or v-axis. Occasionally, a change of variables can be used for other types of regions. For instance, letting $T(u, v) = \left(x, \frac{1}{2}y\right)$ changes the circular region $u^2 + v^2 = 1$ to the elliptical region

$$x^2 + \frac{y^2}{4} = 1.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

14.8 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Describe how to find the Jacobian of x and y with respect to u and v for $x = g(u, v)$ and $y = h(u, v)$.
2. Explain when it is beneficial to use the Jacobian to change variables in a double integral.

Finding a Jacobian **In Exercises 3–10, find the Jacobian $\partial(x, y)/\partial(u, v)$ for the indicated change of variables.**

3. $x = -\frac{1}{2}(u - v),\ y = \frac{1}{2}(u + v)$
4. $x = 5u - v,\ y = 3u + 4v$
5. $x = u - v^2,\ y = u + v$
6. $x = uv - 2u,\ y = uv$
7. $x = u\cos\theta - v\sin\theta,\ y = u\sin\theta + v\cos\theta$
8. $x = u + 1,\ y = 9v$
9. $x = e^u \sin v,\ y = e^u \cos v$
10. $x = u/v,\ y = u + v$

Using a Transformation **In Exercises 11–14, sketch the image S in the uv-plane of the region R in the xy-plane using the given transformations.**

11. $x = 3u + 2v$, $y = 3v$



12. $x = \frac{1}{3}(4u - v)$, $y = \frac{1}{3}(u - v)$



13. $x = \frac{1}{2}(u + v)$, $y = \frac{1}{2}(u - v)$



14. $x = \frac{1}{3}(v - u)$, $y = \frac{1}{3}(2v + u)$



Verifying a Change of Variables **In Exercises 15 and 16, verify the result of the indicated example by setting up the integral using $dy\,dx$ or $dx\,dy$ for dA. Then use a graphing utility to evaluate the integral.**

15. Example 3

16. Example 4

Evaluating a Double Integral Using a Change of Variables **In Exercises 17–22, use the indicated change of variables to evaluate the double integral.**

17. $\iint_R 4(x^2 + y^2)\,dA$
$x = \frac{1}{2}(u + v)$
$y = \frac{1}{2}(u - v)$



18. $\iint_R (2y - x)\,dA$
$x = \frac{1}{2}(v - u)$
$y = \frac{1}{2}(3u - v)$



19. $\iint_R y(x - y)\,dA$
$x = u + v$
$y = u$



20. $\iint_R 4(x + y)e^{x-y}\,dA$
$x = \frac{1}{2}(u + v)$
$y = \frac{1}{2}(u - v)$



21. $\iint_R e^{-xy/2}\,dA$
$x = \sqrt{\frac{v}{u}},\quad y = \sqrt{uv}$



22. $\iint_R y\sin xy\,dA$
$x = \frac{u}{v},\quad y = v$



Finding Volume Using a Change of Variables **In Exercises 23–30, use a change of variables to find the volume of the solid region lying below the surface $z = f(x, y)$ and above the plane region R.**

23. $f(x, y) = 9xy$

R: region bounded by the square with vertices $(1, 0)$, $(0, 1)$, $(1, 2)$, $(2, 1)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

24. $f(x, y) = (3x + 2y)^2\sqrt{2y - x}$

R: region bounded by the parallelogram with vertices $(0, 0)$, $(-2, 3)$, $(2, 5)$, $(4, 2)$

25. $f(x, y) = (x + y)e^{x-y}$

R: region bounded by the square with vertices $(4, 0)$, $(6, 2)$, $(4, 4)$, $(2, 2)$

26. $f(x, y) = (x + y)^2 \sin^2(x - y)$

R: region bounded by the square with vertices $(\pi, 0)$, $(3\pi/2, \pi/2)$, (π, π), $(\pi/2, \pi/2)$

27. $f(x, y) = \sqrt{(x - y)(x + 4y)}$

R: region bounded by the parallelogram with vertices $(0, 0)$, $(1, 1)$, $(5, 0)$, $(4, -1)$

28. $f(x, y) = (3x + 2y)(2y - x)^{3/2}$

R: region bounded by the parallelogram with vertices $(0, 0)$, $(-2, 3)$, $(2, 5)$, $(4, 2)$

29. $f(x, y) = \sqrt{x + y}$

R: region bounded by the triangle with vertices $(0, 0)$, $(a, 0)$, $(0, a)$, where $a > 0$

30. $f(x, y) = \dfrac{xy}{1 + x^2y^2}$

R: region bounded by the graphs of $xy = 1$, $xy = 4$, $x = 1$, $x = 4$ (*Hint:* Let $x = u$, $y = v/u$.)

Exploring Concepts

31. The substitutions $u = 2x - y$ and $v = x + y$ make the region R (see figure) into a simpler region S in the uv-plane. Determine the total number of sides of S that are parallel to either the u-axis or the v-axis.



32. HOW DO YOU SEE IT? The region R is transformed into a simpler region S (see figure). Which substitution can be used to make the transformation?



(a) $u = 3y - x$, $v = y - x$ (b) $u = y - x$, $v = 3y - x$

33. Using an Ellipse Consider the region R in the xy-plane bounded by the ellipse

$$\frac{x^2}{a^2} + \frac{y^2}{b^2} = 1$$

and the transformations $x = au$ and $y = bv$.

(a) Sketch the graph of the region R and its image S under the given transformation.

(b) Find $\dfrac{\partial(x, y)}{\partial(u, v)}$.

(c) Find the area of the ellipse using the indicated change of variables.

34. Volume Use the result of Exercise 33 to find the volume of each dome-shaped solid lying below the surface $z = f(x, y)$ and above the elliptical region R. (*Hint:* After making the change of variables given by the results in Exercise 33, make a second change of variables to polar coordinates.)

(a) $f(x, y) = 16 - x^2 - y^2$; R: $\dfrac{x^2}{16} + \dfrac{y^2}{9} \le 1$

(b) $f(x, y) = A\cos\left(\dfrac{\pi}{2}\sqrt{\dfrac{x^2}{a^2} + \dfrac{y^2}{b^2}}\right)$; R: $\dfrac{x^2}{a^2} + \dfrac{y^2}{b^2} \le 1$

Finding a Jacobian **In Exercises 35–40, find the Jacobian**

$$\frac{\partial(x, y, z)}{\partial(u, v, w)}$$

for the indicated change of variables. If

$$x = f(u, v, w), \quad y = g(u, v, w), \quad \text{and} \quad z = h(u, v, w)$$

then the Jacobian of x, y, and z with respect to u, v, and w is

$$\frac{\partial(x, y, z)}{\partial(u, v, w)} = \begin{vmatrix} \dfrac{\partial x}{\partial u} & \dfrac{\partial x}{\partial v} & \dfrac{\partial x}{\partial w} \\ \dfrac{\partial y}{\partial u} & \dfrac{\partial y}{\partial v} & \dfrac{\partial y}{\partial w} \\ \dfrac{\partial z}{\partial u} & \dfrac{\partial z}{\partial v} & \dfrac{\partial z}{\partial w} \end{vmatrix}.$$

35. $x = u(1 - v)$, $y = uv(1 - w)$, $z = uvw$

36. $x = 4u - v$, $y = 4v - w$, $z = u + w$

37. $x = \frac{1}{2}(u + v)$, $y = \frac{1}{2}(u - v)$, $z = 2uvw$

38. $x = u - v + w$, $y = 2uv$, $z = u + v + w$

39. Spherical coordinates

$x = \rho \sin\phi \cos\theta$, $y = \rho \sin\phi \sin\theta$, $z = \rho \cos\phi$

40. Cylindrical coordinates

$x = r \cos\theta$, $y = r \sin\theta$, $z = z$

PUTNAM EXAM CHALLENGE

41. Let A be the area of the region in the first quadrant bounded by the line $y = \frac{1}{2}x$, the x-axis, and the ellipse $\frac{1}{9}x^2 + y^2 = 1$. Find the positive number m such that A is equal to the area of the region in the first quadrant bounded by the line $y = mx$, the y-axis, and the ellipse $\frac{1}{9}x^2 + y^2 = 1$.

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Review Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Exploring Concepts

In this chapter, you combined your knowledge of integration and functions of several variables to develop double and triple integrals. You are now able to integrate functions over many geometrical objects, from intervals on the x-axis to regions in the plane to complicated three-dimensional solids. You looked at a number of important applications, including volume, centers of mass, and surface area. You saw that many double integrals are easier to evaluate using polar coordinates. Similarly, many triple integrals are better analyzed using cylindrical or spherical coordinates.

1. Explain how to change from rectangular coordinates to polar coordinates in a double integral.

2. Identify the expression that is invalid. Explain your reasoning.

(a) $\int_0^2 \int_0^3 f(x, y)\, dy\, dx$ (b) $\int_0^2 \int_0^y f(x, y)\, dy\, dx$

(c) $\int_0^2 \int_x^3 f(x, y)\, dy\, dx$ (d) $\int_0^2 \int_0^x f(x, y)\, dy\, dx$

3. Give a geometric argument for the equality. Verify the equality analytically.

$$\int_0^2 \int_{3y/2}^{5-y} e^{x+y}\, dx\, dy = \int_0^3 \int_0^{2x/3} e^{x+y}\, dy\, dx + \int_3^5 \int_0^{5-x} e^{x+y}\, dy\, dx$$

4. Answer each question about the surface area S on a surface given by a positive function $z = f(x, y)$ that lies above a region R in the xy-plane. Explain each answer.

(a) Is it possible for S to equal the area of R?

(b) Can S be greater than the area of R?

(c) Can S be less than the area of R?

5. Each figure shows a region of integration for the double integral $\int_R \int f(x, y)\, dA$. For each region, state whether horizontal representative elements, vertical representative elements, or polar sectors would yield the easiest method for obtaining the limits of integration. Explain your reasoning.

(a)



(b)



(c)



6. Convert the integral from rectangular coordinates to both (a) cylindrical and (b) spherical coordinates. Without evaluating, which integral appears to be the simplest to evaluate? Why?

$$\int_0^a \int_0^{\sqrt{a^2-x^2}} \int_0^{\sqrt{a^2-x^2-y^2}} \sqrt{x^2 + y^2 + z^2}\, dz\, dy\, dx$$

Evaluating an Integral

In Exercises 7–10, evaluate the integral.

7. $\int_0^{3x} \sin xy\, dy$

8. $\int_y^{y^2} \frac{x}{y + 1}\, dx$

9. $\int_y^{2y} (x^2 + y^2)\, dx$

10. $\int_1^{x^2} x \ln y\, dy$

Evaluating an Iterated Integral

In Exercises 11–14, evaluate the iterated integral.

11. $\int_0^1 \int_0^{1+x} (3x + 2y)\, dy\, dx$

12. $\int_0^2 \int_{x^2}^{2x} (x^2 + 2y)\, dy\, dx$

13. $\int_0^1 \int_0^{\sqrt{1-x^4}} x^3\, dy\, dx$

14. $\int_0^1 \int_0^{2y} (9 + 3x^2 + 3y^2)\, dx\, dy$

Finding the Area of a Region

In Exercises 15–18, use an iterated integral to find the area of the region bounded by the graphs of the equations.

15. $x + 3y = 3,\ x = 0,\ y = 0$

16. $y = 6x - x^2,\ y = x^2 - 2x$

17. $y = x,\ y = 2x + 2,\ x = 0,\ x = 4$

18. $x = y^2 + 1,\ x = 0,\ y = 0,\ y = 2$

Changing the Order of Integration

In Exercises 19–22, sketch the region R whose area is given by the iterated integral. Then change the order of integration and show that both orders yield the same area.

19. $\int_1^5 \int_0^4 dy\, dx$

20. $\int_{-3}^3 \int_0^{9-y^2} dx\, dy$

21. $\int_0^2 \int_{y/2}^{3-y} dx\, dy$

22. $\int_0^3 \int_0^x dy\, dx + \int_3^6 \int_0^{6-x} dy\, dx$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Evaluating a Double Integral **In Exercises 23 and 24, set up integrals for both orders of integration. Use the more convenient order to evaluate the integral over the plane region R.**

23. $\iint_R 4xy\,dA$

R: rectangle with vertices $(0, 0)$, $(0, 4)$, $(2, 4)$, $(2, 0)$

24. $\iint_R 6x^2\,dA$

R: region bounded by $y = 0$, $y = \sqrt{x}$, $x = 1$

Finding Volume **In Exercises 25–28, use a double integral to find the volume of the indicated solid.**

25.



26.



27.



28.



Average Value **In Exercises 29 and 30, find the average value of $f(x, y)$ over the plane region R.**

29. $f(x) = 16 - x^2 - y^2$

R: rectangle with vertices $(2, 2)$, $(-2, 2)$, $(-2, -2)$, $(2, -2)$

30. $f(x) = 2x^2 + y^2$

R: square with vertices $(0, 0)$, $(3, 0)$, $(3, 3)$, $(0, 3)$

31. Average Temperature The temperature in degrees Celsius on the surface of a metal plate is

$$T(x, y) = 40 - 6x^2 - y^2$$

where x and y are measured in centimeters. Estimate the average temperature when x varies between 0 and 3 centimeters and y varies between 0 and 5 centimeters.

32. Average Profit A firm's profit P (in dollars) from marketing two television models is

$$P = 192x + 576y - x^2 - 5y^2 - 2xy - 5000$$

where x and y represent the numbers of units of the two television models. Estimate the average weekly profit when x varies between 40 and 50 units and y varies between 45 and 60 units.

Converting to Polar Coordinates **In Exercises 33 and 34, evaluate the iterated integral by converting to polar coordinates.**

33. $\int_0^{\sqrt{5}} \int_0^{\sqrt{5-x^2}} \sqrt{x^2 + y^2}\,dy\,dx$

34. $\int_0^4 \int_0^{\sqrt{16-y^2}} (x^2 + y^2)\,dx\,dy$

Volume **In Exercises 35 and 36, use a double integral in polar coordinates to find the volume of the solid bounded by the graphs of the equations.**

35. $z = xy^2$, $x^2 + y^2 = 9$, first octant

36. $z = \sqrt{25 - x^2 - y^2}$, $z = 0$, $x^2 + y^2 = 16$

Area **In Exercises 37 and 38, use a double integral to find the area of the shaded region.**

37.



38.



Area **In Exercises 39 and 40, sketch a graph of the region bounded by the graphs of the equations. Then use a double integral to find the area of the region.**

39. Inside the limaçon $r = 3 + 2\cos\theta$ and outside the circle $r = 4$

40. Inside the circle $r = 3\sin\theta$ and outside the cardioid $r = 1 + \sin\theta$

41. Area and Volume Consider the region R in the xy-plane bounded by $(x^2 + y^2)^2 = 9(x^2 - y^2)$.

(a) Convert the equation to polar coordinates. Use a graphing utility to graph the equation.

(b) Use a double integral to find the area of the region R.

(c) Use a graphing utility to find the volume of the solid region bounded above by the hemisphere

$$z = \sqrt{9 - x^2 - y^2}$$

and below by the region R.

42. Converting to Polar Coordinates Write the sum of the two iterated integrals as a single iterated integral by converting to polar coordinates. Evaluate the resulting iterated integral.

$$\int_0^{8/\sqrt{13}} \int_0^{3x/2} xy\,dy\,dx + \int_{8/\sqrt{13}}^4 \int_0^{\sqrt{16-x^2}} xy\,dy\,dx$$

Finding the Mass of a Lamina **In Exercises 43 and 44, find the mass of the lamina described by the inequalities, given that its density is $\rho(x, y) = x + 3y$.**

43. $0 \le x \le 1$, $0 \le y \le 2$

44. $x \ge 0$, $0 \le y \le \sqrt{4 - x^2}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding the Center of Mass **In Exercises 45–48, find the mass and center of mass of the lamina bounded by the graphs of the equations for the given density.**

45. $y = x^3,\ y = 0,\ x = 2,\ \rho = kx$

46. $y = \dfrac{2}{x},\ y = 0,\ x = 1,\ x = 2,\ \rho = ky$

47. $y = 2x,\ y = 2x^3,\ x \geq 0,\ y \geq 0,\ \rho = kxy$

48. $y = 6 - x,\ y = 0,\ x = 0,\ \rho = kx^2$

Finding Moments of Inertia and Radii of Gyration **In Exercises 49 and 50, find $I_x, I_y, I_0, \bar{\bar{x}}$, and $\bar{\bar{y}}$ for the lamina bounded by the graphs of the equations.**

49. $y = 0,\ y = 2,\ x = 0,\ x = 3,\ \rho = kx$

50. $y = 4 - x^2,\ y = 0,\ x > 0,\ \rho = ky$

Finding Surface Area **In Exercises 51–54, find the area of the surface given by $z = f(x, y)$ that lies above the region R.**

51. $f(x, y) = 25 - x^2 - y^2$

$R = \{(x, y):\ x^2 + y^2 \leq 25\}$

52. $f(x, y) = 8 + 4x - 5y$

$R = \{(x, y):\ x^2 + y^2 \leq 1\}$

53. $f(x, y) = 9 - y^2$

R: triangle with vertices $(-3, 3)$, $(0, 0)$, $(3, 3)$

54. $f(x, y) = 4 - x^2$

R: triangle with vertices $(-2, 2)$, $(0, 0)$, $(2, 2)$

55. Building Design A new auditorium is built with a foundation in the shape of one-fourth of a circle of radius 50 feet. So, it forms a region R bounded by the graph of $x^2 + y^2 = 50^2$ with $x \geq 0$ and $y \geq 0$. The following equations are models for the floor and ceiling.

$$\text{Floor: } z = \frac{x + y}{5} \qquad \text{Ceiling: } z = 20 + \frac{xy}{100}$$

(a) Calculate the volume of the room, which is needed to determine the heating and cooling requirements.

(b) Find the surface area of the ceiling.

56. Surface Area The roof over the stage of an open-air theater at a theme park is modeled by

$$f(x, y) = 25\left[1 + e^{-(x^2+y^2)/1000}\cos^2\left(\frac{x^2 + y^2}{1000}\right)\right]$$

where the stage is a semicircle bounded by the graphs of $y = \sqrt{50^2 - x^2}$ and $y = 0$.

(a) Use a graphing utility to graph the surface.

(b) Use a graphing utility to approximate the number of square feet of roofing required to cover the surface.

Evaluating a Triple Iterated Integral **In Exercises 57–60, evaluate the triple iterated integral.**

57. $\displaystyle\int_0^4 \int_0^1 \int_0^2 (2x + y + 4z)\, dy\, dz\, dx$

58. $\displaystyle\int_0^1 \int_0^{1+\sqrt{y}} \int_0^{xy} y\, dz\, dx\, dy$

59. $\displaystyle\int_0^2 \int_1^2 \int_0^1 (e^x + y^2 + z^2)\, dx\, dy\, dz$

60. $\displaystyle\int_0^3 \int_{\pi/2}^{\pi} \int_2^5 z \sin x\, dy\, dx\, dz$

Evaluating a Triple Iterated Integral Using Technology **In Exercises 61 and 62, use a graphing utility to evaluate the triple iterated integral.**

61. $\displaystyle\int_{-1}^1 \int_{-\sqrt{1-x^2}}^{\sqrt{1-x^2}} \int_{-\sqrt{1-x^2-y^2}}^{\sqrt{1-x^2-y^2}} (x^2 + y^2)\, dz\, dy\, dx$

62. $\displaystyle\int_0^2 \int_0^{\sqrt{4-x^2}} \int_0^{\sqrt{4-x^2-y^2}} xyz\, dz\, dy\, dx$

Volume **In Exercises 63 and 64, use a triple integral to find the volume of the solid bounded by the graphs of the equations.**

63. $z = xy,\ z = 0,\ 0 \leq x \leq 3,\ 0 \leq y \leq 4$

64. $z = 8 - x - y,\ z = 0,\ y = x,\ y = 3,\ x = 0$

Changing the Order of Integration **In Exercises 65 and 66, sketch the solid whose volume is given by the iterated integral. Then rewrite the integral using the indicated order of integration.**

65. $\displaystyle\int_0^1 \int_0^y \int_0^{\sqrt{1-x^2}} dz\, dx\, dy$

Rewrite using the order $dz\, dy\, dx$.

66. $\displaystyle\int_0^6 \int_0^{6-x} \int_0^{6-x-y} dz\, dy\, dx$

Rewrite using the order $dy\, dx\, dz$.

Center of Mass **In Exercises 67 and 68, find the mass and the indicated coordinate of the center of mass of the solid region Q of density ρ bounded by the graphs of the equations.**

67. Find $\bar{x}$ using $\rho(x, y, z) = k$.

$Q:\ x + y + z = 10,\ x = 0,\ y = 0,\ z = 0$

68. Find $\bar{y}$ using $\rho(x, y, z) = kx$.

$Q:\ z = 5 - y,\ z = 0,\ y = 0,\ x = 0,\ x = 5$

Evaluating a Triple Iterated Integral **In Exercises 69–72, evaluate the triple iterated integral.**

69. $\displaystyle\int_0^3 \int_{\pi/6}^{\pi/3} \int_0^4 r \cos\theta\, dr\, d\theta\, dz$

70. $\displaystyle\int_0^{\pi/2} \int_0^3 \int_0^{4-z} z\, dr\, dz\, d\theta$

71. $\displaystyle\int_0^{\pi} \int_0^{\pi/2} \int_0^{\sin\theta} \rho^2 \sin\theta \cos\theta\, d\rho\, d\theta\, d\phi$

72. $\displaystyle\int_0^{\pi/4} \int_0^{\pi/4} \int_0^{\cos\phi} \cos\theta\, d\rho\, d\phi\, d\theta$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Evaluating a Triple Iterated Integral Using Technology **In Exercises 73 and 74, use a graphing utility to evaluate the triple iterated integral.**

73. $\int_0^{\pi}\int_0^{2}\int_0^{3}\sqrt{z^2+4}\,dz\,dr\,d\theta$

74. $\int_0^{\pi/2}\int_0^{\pi/2}\int_0^{\cos\phi}\rho^2\cos\theta\,d\rho\,d\theta\,d\phi$

Volume **In Exercises 75 and 76, use cylindrical coordinates to find the volume of the solid.**

75. Solid bounded above by $z = 8 - x^2 - y^2$ and below by $z = x^2 + y^2$

76. Solid bounded above by $3x^2 + 3y^2 + z^2 = 45$ and below by the xy-plane

Volume **In Exercises 77 and 78, use spherical coordinates to find the volume of the solid.**

77. Solid bounded above by $x^2 + y^2 + z^2 = 4$ and below by $z^2 = 3x^2 + 3y^2$

78. Solid bounded above by $x^2 + y^2 + z^2 = 36$ and below by $z = \sqrt{x^2 + y^2}$

Finding a Jacobian **In Exercises 79–82, find the Jacobian**

$$\frac{\partial(x, y)}{\partial(u, v)}$$

for the indicated change of variables.

79. $x = 3uv,\ y = 2(u - v)$

80. $x = u^2 + v^2,\ y = u^2 - v^2$

81. $x = u\sin\theta + v\cos\theta,\ y = u\cos\theta + v\sin\theta$

82. $x = uv,\ y = \dfrac{v}{u}$

Evaluating a Double Integral Using a Change of Variables **In Exercises 83–86, use the indicated change of variables to evaluate the double integral.**

83. $\iint_R \ln(x + y)\,dA$

$x = \frac{1}{2}(u + v)$

$y = \frac{1}{2}(u - v)$



84. $\iint_R 16xy\,dA$

$x = \frac{1}{4}(u + v)$

$y = \frac{1}{2}(v - u)$



85. $\iint_R (xy + x^2)\,dA$

$x = u$

$y = \frac{1}{3}(u - v)$



86. $\iint_R \dfrac{x}{1 + x^2y^2}\,dA$

$x = u$

$y = \dfrac{v}{u}$



Building on Concepts

87. Show that

$$\sum_{n=1}^{\infty}\frac{1}{n^3} = \int_0^1\int_0^1\int_0^1\frac{1}{1 - xyz}\,dx\,dy\,dz.$$

88. Find the volume of the solid of intersection of the three cylinders

$x^2 + z^2 = 1,\quad y^2 + z^2 = 1,\quad$ and $\quad x^2 + y^2 = 1$

as shown in the figure.



89. Consider a spherical segment of height h from a sphere of radius a, where $h \le a$, and constant density $\rho(x, y, z) = k$, as shown in the figure.

(a) Find the volume of the solid.

(b) Find the centroid of the solid.

(c) Use the result of part (b) to find the centroid of a hemisphere of radius a.

(d) Find $\lim_{h\to 0}\bar{z}$.

(e) Find I_z.

(f) Use the result of part (e) to find I_z for a hemisphere.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.S. Problem Solving

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

1. Surface Area Let a, b, c, and d be positive real numbers. The portion of the plane $ax + by + cz = d$ in the first octant is shown in the figure. Show that the surface area of this portion of the plane is equal to

$$\frac{A(R)}{c}\sqrt{a^2 + b^2 + c^2}$$

where $A(R)$ is the area of the triangular region R in the xy-plane, as shown in the figure.



2. Sprinkler Consider a circular lawn with a radius of 10 feet, as shown in the figure. Assume that a sprinkler distributes water in a radial fashion according to the formula

$$f(r) = \frac{r}{16} - \frac{r^2}{160}$$

(measured in cubic feet of water per hour per square foot of lawn), where r is the distance in feet from the sprinkler. Find the amount of water that is distributed in 1 hour in the following two annular regions.

$A = \{(r, \theta): 4 \le r \le 5, 0 \le \theta \le 2\pi\}$

$B = \{(r, \theta): 9 \le r \le 10, 0 \le \theta \le 2\pi\}$

Is the distribution of water uniform? Determine the amount of water the entire lawn receives in 1 hour.



3. Volume Find the volume of the solid generated by revolving the region in the first quadrant bounded by $y = e^{-x^2}$ about the y-axis. Use this result to find

$$\int_{-\infty}^{\infty} e^{-x^2}\,dx.$$

4. Proof Prove that $\lim_{n\to\infty} \int_0^1 \int_0^1 x^n y^n\,dx\,dy = 0$.

5. Deriving a Sum Derive Euler's famous result that was mentioned in Section 9.3,

$$\sum_{n=1}^{\infty} \frac{1}{n^2} = \frac{\pi^2}{6}$$

by completing each step.

(a) Prove that

$$\int \frac{dv}{2 - u^2 + v^2} = \frac{1}{\sqrt{2 - u^2}} \arctan \frac{v}{\sqrt{2 - u^2}} + C.$$

(b) Prove that $I_1 = \int_0^{\sqrt{2}/2} \int_{-u}^{u} \frac{2}{2 - u^2 + v^2}\,dv\,du = \frac{\pi^2}{18}$ by using the substitution $u = \sqrt{2}\sin\theta$.

(c) Prove that

$$I_2 = \int_{\sqrt{2}/2}^{\sqrt{2}} \int_{u-\sqrt{2}}^{-u+\sqrt{2}} \frac{2}{2 - u^2 + v^2}\,dv\,du$$
$$= 4\int_{\pi/6}^{\pi/2} \arctan \frac{1 - \sin\theta}{\cos\theta}\,d\theta$$

by using the substitution $u = \sqrt{2}\sin\theta$.

(d) Prove the trigonometric identity

$$\frac{1 - \sin\theta}{\cos\theta} = \tan\left[\frac{(\pi/2) - \theta}{2}\right].$$

(e) Prove that $I_2 = \int_{\sqrt{2}/2}^{\sqrt{2}} \int_{u-\sqrt{2}}^{-u+\sqrt{2}} \frac{2}{2 - u^2 + v^2}\,dv\,du = \frac{\pi^2}{9}$.

(f) Use the formula for the sum of an infinite geometric series to verify that

$$\sum_{n=1}^{\infty} \frac{1}{n^2} = \int_0^1 \int_0^1 \frac{1}{1 - xy}\,dx\,dy.$$

(g) Use the change of variables

$$u = \frac{x + y}{\sqrt{2}} \quad \text{and} \quad v = \frac{y - x}{\sqrt{2}}$$

to prove that

$$\sum_{n=1}^{\infty} \frac{1}{n^2} = \int_0^1 \int_0^1 \frac{1}{1 - xy}\,dx\,dy = I_1 + I_2 = \frac{\pi^2}{6}.$$

6. Volume Show that the volume of a spherical block can be approximated by

$$\Delta V \approx \rho^2 \sin\phi\,\Delta\rho\,\Delta\phi\,\Delta\theta.$$

(*Hint:* See Section 14.7, page 1027.)

7. Changing the Order of Integration Sketch the solid whose volume is given by the sum of the iterated integrals

$$\int_0^6 \int_{z/2}^3 \int_{z/2}^{y} dx\,dy\,dz + \int_0^6 \int_3^{(12-z)/2} \int_{z/2}^{6-y} dx\,dy\,dz.$$

Then write the volume as a single iterated integral in the order $dy\,dz\,dx$ and find the volume of the solid.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

15 Vector Analysis

GO DIGITAL

15.1 Vector Fields
15.2 Line Integrals
15.3 Conservative Vector Fields and Independence of Path
15.4 Green's Theorem
15.5 Parametric Surfaces
15.6 Surface Integrals
15.7 Divergence Theorem
15.8 Stokes's Theorem

CalcView®



CalcChat®


Chapter 15
Section 5
Exercise 17
GO
$\mathbf{r}(u, v) = (u - \sin u)\cos v\mathbf{i} + (1 - \cos u)\sin v\mathbf{j} + u\mathbf{k}$,
$0 \le u \le \pi, \quad 0 \le v \le 2\pi$
PREV. 7 9 11 13 15 17 19 21 23 25 27 NEXT

Finding Surface Area *(Example 6, p. 1093)*

Building Design *(Exercise 74, p. 1068)*

left, Catmando/Shutterstock.com; right, nui7711/Shutterstock.com
© 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322
Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

15.1 Vector Fields

GO DIGITAL

- Describe the concept of a vector field.
- Determine whether a vector field is conservative.
- Find the curl of a vector field.
- Find the divergence of a vector field.

Big Ideas of Calculus

You have studied a wide variety of functions, including

- functions of a single variable $y = f(x)$,
- functions of two variables $z = f(x, y)$, and
- vector-valued functions $\mathbf{r}(t) = f(t)\mathbf{i} + g(t)\mathbf{j}$.

You will now study *vector fields*. Vector fields are functions which assign vectors to points in the plane (or in space). Examples of vector fields are velocity fields, electromagnetic fields, and gravitational fields. To analyze these applications, you will combine your knowledge of vectors with your knowledge of integral calculus. The integration in Sections 15.1 through 15.4 is done over a plane region bounded by curves, whereas in Sections 15.5 through 15.8, the integration is done over regions in space bounded by surfaces.

Vector Fields

In Chapter 12, you studied vector-valued functions—functions that assign a vector to a *real number*. There you learned that vector-valued functions of real numbers are useful in representing curves and motion along a curve. In this chapter, you will study two other types of vector-valued functions—functions that assign a vector to a *point in the plane* or a *point in space*. Such functions are called **vector fields,** and they are useful in representing various types of **force fields** and **velocity fields.**

Definition of Vector Field

A **vector field over a plane region R** is a function $\mathbf{F}$ that assigns a vector $\mathbf{F}(x, y)$ to each point in R.

A **vector field over a solid region Q in space** is a function $\mathbf{F}$ that assigns a vector $\mathbf{F}(x, y, z)$ to each point in Q.

Although a vector field consists of infinitely many vectors, you can get a good idea of what the vector field looks like by sketching several representative vectors $\mathbf{F}(x, y)$ whose initial points are (x, y).

The *gradient* is one example of a vector field. For instance, if

$$f(x, y) = x^2y + 3xy^3 \qquad \text{Function of two variables}$$

then the gradient of f

$$\begin{aligned}\nabla f(x, y) &= f_x(x, y)\mathbf{i} + f_y(x, y)\mathbf{j} \\ &= (2xy + 3y^3)\mathbf{i} + (x^2 + 9xy^2)\mathbf{j} \qquad \text{Vector field in the plane}\end{aligned}$$

is a vector field in the plane. From Chapter 13, the graphical interpretation of this field is a family of vectors, each of which points in the direction of maximum increase along the surface given by $z = f(x, y)$.

Similarly, if

$$f(x, y, z) = x^2 + y^2 + z^2 \qquad \text{Function of three variables}$$

then the gradient of f

$$\begin{aligned}\nabla f(x, y, z) &= f_x(x, y, z)\mathbf{i} + f_y(x, y, z)\mathbf{j} + f_z(x, y, z)\mathbf{k} \\ &= 2x\mathbf{i} + 2y\mathbf{j} + 2z\mathbf{k} \qquad \text{Vector field in space}\end{aligned}$$

is a vector field in space. Note that the component functions for this particular vector field are $2x$, $2y$, and $2z$.

A vector field

$$\mathbf{F}(x, y, z) = M(x, y, z)\mathbf{i} + N(x, y, z)\mathbf{j} + P(x, y, z)\mathbf{k}$$

is **continuous** at a point if and only if each of its component functions M, N, and P is continuous at that point.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Velocity field



Rotating wheel
Figure 15.1



Air flow vector field
Figure 15.2



m_1 is located at (x, y, z).
m_2 is located at $(0, 0, 0)$.
Gravitational force field
Figure 15.3

Some common *physical* examples of vector fields are **velocity fields, gravitational fields,** and **electric force fields.**

1. *Velocity fields* describe the motions of systems of particles in the plane or in space. For instance, Figure 15.1 shows the vector field determined by a wheel rotating on an axle. Notice that the velocity vectors are determined by the locations of their initial points—the farther a point is from the axle, the greater its velocity. Velocity fields are also determined by the flow of liquids through a container or by the flow of air currents around a moving object, as shown in Figure 15.2.
2. *Gravitational fields* are defined by **Newton's Law of Gravitation,** which states that the force of attraction exerted on a particle of mass m_1 located at (x, y, z) by a particle of mass m_2 located at $(0, 0, 0)$ is

$$\mathbf{F}(x, y, z) = \frac{-Gm_1m_2}{x^2 + y^2 + z^2}\mathbf{u}$$

where G is the gravitational constant and $\mathbf{u}$ is the unit vector in the direction from the origin to (x, y, z). In Figure 15.3, the gravitational field $\mathbf{F}$ has the properties that $\mathbf{F}(x, y, z)$ always points toward the origin, and that the magnitude of $\mathbf{F}(x, y, z)$ is the same at all points equidistant from the origin. A vector field with these two properties is called a **central force field.** Using the position vector

$$\mathbf{r} = x\mathbf{i} + y\mathbf{j} + z\mathbf{k}$$

for the point (x, y, z), you can write the gravitational field $\mathbf{F}$ as

$$\mathbf{F}(x, y, z) = \frac{-Gm_1m_2}{\|\mathbf{r}\|^2}\left(\frac{\mathbf{r}}{\|\mathbf{r}\|}\right) = \frac{-Gm_1m_2}{\|\mathbf{r}\|^2}\mathbf{u}.$$

3. *Electric force fields* are defined by **Coulomb's Law,** which states that the force exerted on a particle with electric charge q_1 located at (x, y, z) by a particle with electric charge q_2 located at $(0, 0, 0)$ is

$$\mathbf{F}(x, y, z) = \frac{cq_1q_2}{\|\mathbf{r}\|^2}\mathbf{u}$$

where $\mathbf{r} = x\mathbf{i} + y\mathbf{j} + z\mathbf{k}$, $\mathbf{u} = \mathbf{r}/\|\mathbf{r}\|$, and c is a constant that depends on the choice of units for $\|\mathbf{r}\|$, q_1, and q_2.

Note that an electric force field has the same form as a gravitational field. That is,

$$\mathbf{F}(x, y, z) = \frac{k}{\|\mathbf{r}\|^2}\mathbf{u}.$$

Such a force field is called an **inverse square field.**

Definition of Inverse Square Field

Let $\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j} + z(t)\mathbf{k}$ be a position vector. The vector field $\mathbf{F}$ is an **inverse square field** if

$$\mathbf{F}(x, y, z) = \frac{k}{\|\mathbf{r}\|^2}\mathbf{u}$$

where k is a real number and

$$\mathbf{u} = \frac{\mathbf{r}}{\|\mathbf{r}\|}$$

is a unit vector in the direction of $\mathbf{r}$.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Because vector fields consist of infinitely many vectors, it is not possible to create a sketch of the entire field. Instead, when you sketch a vector field, your goal is to sketch representative vectors that help you visualize the field.

EXAMPLE 1 Sketching a Vector Field

Sketch some vectors in the vector field

$$\mathbf{F}(x, y) = -y\mathbf{i} + x\mathbf{j}.$$

Solution You could plot vectors at several random points in the plane. It is more enlightening, however, to plot vectors of equal magnitude. This corresponds to finding level curves in scalar fields. In this case, vectors of equal magnitude lie on circles.

$$\|\mathbf{F}\| = c \qquad \text{Vectors of length } c$$
$$\sqrt{x^2 + y^2} = c$$
$$x^2 + y^2 = c^2 \qquad \text{Equation of circle}$$

To begin making the sketch, choose a value for c and plot several vectors on the resulting circle. For instance, the following vectors occur on the unit circle.

Point	Vector
$(1, 0)$	$\mathbf{F}(1, 0) = \mathbf{j}$
$(0, 1)$	$\mathbf{F}(0, 1) = -\mathbf{i}$
$(-1, 0)$	$\mathbf{F}(-1, 0) = -\mathbf{j}$
$(0, -1)$	$\mathbf{F}(0, -1) = \mathbf{i}$

These and several other vectors in the vector field are shown in Figure 15.4. Note in the figure that this vector field is similar to that given by the rotating wheel shown in Figure 15.1.



Figure 15.4

EXAMPLE 2 Sketching a Vector Field

Sketch some vectors in the vector field

$$\mathbf{F}(x, y) = 2x\mathbf{i} + y\mathbf{j}.$$

Solution For this vector field, vectors of equal magnitude lie on ellipses given by

$$\|\mathbf{F}\| = c$$
$$\sqrt{(2x)^2 + (y)^2} = c$$

which implies that

$$4x^2 + y^2 = c^2. \qquad \text{Equation of ellipse}$$

For $c = 1$, sketch several vectors $2x\mathbf{i} + y\mathbf{j}$ of magnitude 1 at points on the ellipse given by

$$4x^2 + y^2 = 1.$$

For $c = 2$, sketch several vectors $2x\mathbf{i} + y\mathbf{j}$ of magnitude 2 at points on the ellipse given by

$$4x^2 + y^2 = 4.$$

These vectors are shown in Figure 15.5.



Figure 15.5

TECHNOLOGY A graphing utility can be used to graph vectors in a vector field. If you have access to a graphing utility, use it to graph several representative vectors for the vector field in Example 2.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Velocity field:
$\mathbf{v}(x, y, z) = (16 - x^2 - y^2)\mathbf{k}$

Figure 15.6

EXAMPLE 3 Sketching a Velocity Field

Sketch some vectors in the velocity field

$$\mathbf{v}(x, y, z) = (16 - x^2 - y^2)\mathbf{k}$$

where $x^2 + y^2 \leq 16$.

Solution You can imagine that $\mathbf{v}$ describes the velocity of a liquid flowing through a tube of radius 4. Vectors near the z-axis are longer than those near the edge of the tube. For instance, at the point $(0, 0, 0)$, the velocity vector is $\mathbf{v}(0, 0, 0) = 16\mathbf{k}$, whereas at the point $(0, 3, 0)$, the velocity vector is $\mathbf{v}(0, 3, 0) = 7\mathbf{k}$. Figure 15.6 shows these and several other vectors for the velocity field. From the figure, notice that the speed of the liquid is greater near the center of the tube than near the edges of the tube. ■

Conservative Vector Fields

Notice in Figure 15.5 that all the vectors appear to be normal to the level curve from which they emanate. Because this is a property of gradients, it is natural to ask whether the vector field

$$\mathbf{F}(x, y) = 2x\mathbf{i} + y\mathbf{j}$$

is the *gradient* of some differentiable function f. The answer is that some vector fields can be represented as the gradients of differentiable functions and some cannot—those that can are called **conservative** vector fields.

Definition of Conservative Vector Field

A vector field $\mathbf{F}$ is called **conservative** when there exists a differentiable function f such that $\mathbf{F} = \nabla f$. The function f is called the **potential function** for $\mathbf{F}$.

EXAMPLE 4 Conservative Vector Fields

a. The vector field given by $\mathbf{F}(x, y) = 2x\mathbf{i} + y\mathbf{j}$ is conservative. To show this, consider the potential function $f(x, y) = x^2 + \frac{1}{2}y^2$. Because

$$\nabla f = 2x\mathbf{i} + y\mathbf{j} = \mathbf{F}$$

it follows that $\mathbf{F}$ is conservative.

b. Every inverse square field is conservative. To show this, let

$$\mathbf{F}(x, y, z) = \frac{k}{\|\mathbf{r}\|^2}\mathbf{u} \quad \text{and} \quad f(x, y, z) = \frac{-k}{\sqrt{x^2 + y^2 + z^2}}$$

where $\mathbf{u} = \mathbf{r}/\|\mathbf{r}\|$. Because

$$\begin{aligned}\nabla f &= \frac{kx}{(x^2 + y^2 + z^2)^{3/2}}\mathbf{i} + \frac{ky}{(x^2 + y^2 + z^2)^{3/2}}\mathbf{j} + \frac{kz}{(x^2 + y^2 + z^2)^{3/2}}\mathbf{k} \\ &= \frac{k}{x^2 + y^2 + z^2}\left(\frac{x\mathbf{i} + y\mathbf{j} + z\mathbf{k}}{\sqrt{x^2 + y^2 + z^2}}\right) \\ &= \frac{k}{\|\mathbf{r}\|^2}\left(\frac{\mathbf{r}}{\|\mathbf{r}\|}\right) \\ &= \frac{k}{\|\mathbf{r}\|^2}\mathbf{u}\end{aligned}$$

it follows that $\mathbf{F}$ is conservative. ■

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

As can be seen in Example 4(b), many important vector fields, including gravitational fields and electric force fields, are conservative. Most of the terminology in this chapter comes from physics. For example, the term "conservative" is derived from the classic physical law regarding the conservation of energy. This law states that the sum of the kinetic energy and the potential energy of a particle moving in a conservative force field is constant. (The kinetic energy of a particle is the energy due to its motion, and the potential energy is the energy due to its position in the force field.)

The next theorem gives a necessary and sufficient condition for a vector field *in the plane* to be conservative.

REMARK Theorem 15.1 is valid on *simply connected* domains. A plane region R is simply connected when every simple closed curve in R encloses only points that are in R. (See Figure 15.26 in Section 15.4.)

THEOREM 15.1 Test for Conservative Vector Field in the Plane

Let M and N have continuous first partial derivatives on an open disk R. The vector field $\mathbf{F}(x, y) = M\mathbf{i} + N\mathbf{j}$ is conservative if and only if

$$\frac{\partial N}{\partial x} = \frac{\partial M}{\partial y}.$$

Proof To prove that the given condition is necessary for $\mathbf{F}$ to be conservative, suppose there exists a potential function f such that

$$\mathbf{F}(x, y) = \nabla f(x, y) = M\mathbf{i} + N\mathbf{j}.$$

Then you have

$$f_x(x, y) = M \quad \Rightarrow \quad f_{xy}(x, y) = \frac{\partial M}{\partial y}$$

$$f_y(x, y) = N \quad \Rightarrow \quad f_{yx}(x, y) = \frac{\partial N}{\partial x}$$

and, by the equivalence of the mixed partials f_{xy} and f_{yx}, you can conclude that $\partial N/\partial x = \partial M/\partial y$ for all (x, y) in R. The sufficiency of this condition is proved in Section 15.4. ■

EXAMPLE 5 Testing for Conservative Vector Fields in the Plane

Determine whether the vector field given by $\mathbf{F}$ is conservative.

a. $\mathbf{F}(x, y) = x^2y\mathbf{i} + xy\mathbf{j}$

b. $\mathbf{F}(x, y) = 2x\mathbf{i} + y\mathbf{j}$

Solution

a. The vector field

$$\mathbf{F}(x, y) = x^2y\mathbf{i} + xy\mathbf{j}$$

is not conservative because

$$\frac{\partial M}{\partial y} = \frac{\partial}{\partial y}[x^2y] = x^2 \quad \text{and} \quad \frac{\partial N}{\partial x} = \frac{\partial}{\partial x}[xy] = y.$$

b. The vector field

$$\mathbf{F}(x, y) = 2x\mathbf{i} + y\mathbf{j}$$

is conservative because

$$\frac{\partial M}{\partial y} = \frac{\partial}{\partial y}[2x] = 0 \quad \text{and} \quad \frac{\partial N}{\partial x} = \frac{\partial}{\partial x}[y] = 0.$$

■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Theorem 15.1 tells you whether a vector field $\mathbf{F}$ is conservative. It does not tell you how to find a potential function of $\mathbf{F}$. The problem is comparable to antidifferentiation. Sometimes you will be able to find a potential function by simple inspection. For instance, in Example 4, you observed that

$$f(x, y) = x^2 + \frac{1}{2}y^2$$

has the property that

$$\nabla f(x, y) = 2x\mathbf{i} + y\mathbf{j}.$$

EXAMPLE 6 Finding a Potential Function for $\mathbf{F}(x, y)$

Find a potential function for

$$\mathbf{F}(x, y) = 2xy\mathbf{i} + (x^2 - y)\mathbf{j}.$$

Solution From Theorem 15.1, it follows that $\mathbf{F}$ is conservative because

$$\frac{\partial}{\partial y}[2xy] = 2x \quad \text{and} \quad \frac{\partial}{\partial x}[x^2 - y] = 2x.$$

If f is a function whose gradient is equal to $\mathbf{F}(x, y)$, then

$$\nabla f(x, y) = 2xy\mathbf{i} + (x^2 - y)\mathbf{j}$$

which implies that

$$f_x(x, y) = 2xy$$

and

$$f_y(x, y) = x^2 - y.$$

To reconstruct the function f from these two partial derivatives, integrate $f_x(x, y)$ with respect to x

$$f(x, y) = \int f_x(x, y)\, dx = \int 2xy\, dx = x^2y + g(y)$$

and integrate $f_y(x, y)$ with respect to y

$$f(x, y) = \int f_y(x, y)\, dy = \int (x^2 - y)\, dy = x^2y - \frac{y^2}{2} + h(x).$$

Notice that $g(y)$ is constant with respect to x and $h(x)$ is constant with respect to y. To find a single expression that represents $f(x, y)$, let

$$g(y) = -\frac{y^2}{2} + K_1 \quad \text{and} \quad h(x) = K_2.$$

Then you can write

$$f(x, y) = x^2y - \frac{y^2}{2} + K. \qquad K = K_1 + K_2$$

You can check this result by forming the gradient of f. You will find that it is equal to the original function $\mathbf{F}$. ■

Notice that the solution to Example 6 is comparable to that given by an indefinite integral. That is, the solution represents a family of potential functions, any two of which differ by a constant. To find a unique solution, you would have to be given an initial condition that is satisfied by the potential function.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Curl of a Vector Field

Theorem 15.1 has a counterpart for vector fields in space. Before stating that result, the definition of the **curl of a vector field** in space is given.

Definition of Curl of a Vector Field

The curl of $\mathbf{F}(x, y, z) = M\mathbf{i} + N\mathbf{j} + P\mathbf{k}$ is

$$\begin{aligned}\operatorname{curl} \mathbf{F}(x, y, z) &= \nabla \times \mathbf{F}(x, y, z) \\ &= \left(\frac{\partial P}{\partial y} - \frac{\partial N}{\partial z}\right)\mathbf{i} - \left(\frac{\partial P}{\partial x} - \frac{\partial M}{\partial z}\right)\mathbf{j} + \left(\frac{\partial N}{\partial x} - \frac{\partial M}{\partial y}\right)\mathbf{k}.\end{aligned}$$

If curl $\mathbf{F} = \mathbf{0}$, then $\mathbf{F}$ is said to be **irrotational.**

The cross-product notation used for curl comes from viewing the gradient ∇f as the result of the **differential operator** ∇ acting on the function f. In this context, you can use the following determinant form as an aid in remembering the formula for curl.

$$\begin{aligned}\operatorname{curl} \mathbf{F}(x, y, z) &= \nabla \times \mathbf{F}(x, y, z) \\ &= \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ \dfrac{\partial}{\partial x} & \dfrac{\partial}{\partial y} & \dfrac{\partial}{\partial z} \\ M & N & P \end{vmatrix} \\ &= \left(\frac{\partial P}{\partial y} - \frac{\partial N}{\partial z}\right)\mathbf{i} - \left(\frac{\partial P}{\partial x} - \frac{\partial M}{\partial z}\right)\mathbf{j} + \left(\frac{\partial N}{\partial x} - \frac{\partial M}{\partial y}\right)\mathbf{k}\end{aligned}$$

EXAMPLE 7 Finding the Curl of a Vector Field

See LarsonCalculus.com for an interactive version of this type of example.

Find curl $\mathbf{F}$ of the vector field

$$\mathbf{F}(x, y, z) = 2xy\mathbf{i} + (x^2 + z^2)\mathbf{j} + 2yz\mathbf{k}.$$

Is $\mathbf{F}$ irrotational?

Solution The curl of $\mathbf{F}$ is

$$\begin{aligned}\operatorname{curl} \mathbf{F}(x, y, z) &= \nabla \times \mathbf{F}(x, y, z) \\ &= \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ \dfrac{\partial}{\partial x} & \dfrac{\partial}{\partial y} & \dfrac{\partial}{\partial z} \\ 2xy & x^2 + z^2 & 2yz \end{vmatrix} \\ &= \begin{vmatrix} \dfrac{\partial}{\partial y} & \dfrac{\partial}{\partial z} \\ x^2 + z^2 & 2yz \end{vmatrix}\mathbf{i} - \begin{vmatrix} \dfrac{\partial}{\partial x} & \dfrac{\partial}{\partial z} \\ 2xy & 2yz \end{vmatrix}\mathbf{j} + \begin{vmatrix} \dfrac{\partial}{\partial x} & \dfrac{\partial}{\partial y} \\ 2xy & x^2 + z^2 \end{vmatrix}\mathbf{k} \\ &= (2z - 2z)\mathbf{i} - (0 - 0)\mathbf{j} + (2x - 2x)\mathbf{k} \\ &= \mathbf{0}.\end{aligned}$$

Because curl $\mathbf{F} = \mathbf{0}$, $\mathbf{F}$ is irrotational. ■

TECHNOLOGY Some graphing utilities have a command that can be used to find the curl of a vector field. If you have access to a graphing utility that has such a command, use it to find the curl of the vector field in Example 7.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Later in this chapter, you will assign a physical interpretation to the curl of a vector field. But for now, the primary use of curl is shown in the following test for conservative vector fields in space. The test states that for a vector field in space, the curl is $\mathbf{0}$ at every point in its domain if and only if $\mathbf{F}$ is conservative. The proof is similar to that given for Theorem 15.1.

REMARK Theorem 15.2 is valid for *simply connected* domains in space. A simply connected domain in space is a domain D for which every simple closed curve in D can be shrunk to a point in D without leaving D.

THEOREM 15.2 Test for Conservative Vector Field in Space

Suppose that M, N, and P have continuous first partial derivatives in an open sphere Q in space. The vector field

$$\mathbf{F}(x, y, z) = M\mathbf{i} + N\mathbf{j} + P\mathbf{k}$$

is conservative if and only if

$$\text{curl } \mathbf{F}(x, y, z) = \mathbf{0}.$$

That is, $\mathbf{F}$ is conservative if and only if

$$\frac{\partial P}{\partial y} = \frac{\partial N}{\partial z}, \quad \frac{\partial P}{\partial x} = \frac{\partial M}{\partial z}, \quad \text{and} \quad \frac{\partial N}{\partial x} = \frac{\partial M}{\partial y}.$$

From Theorem 15.2, you can conclude that the vector field given in Example 7 is conservative because curl $\mathbf{F}(x, y, z) = \mathbf{0}$. Try showing that the vector field

$$\mathbf{F}(x, y, z) = x^3y^2z\mathbf{i} + x^2z\mathbf{j} + x^2y\mathbf{k}$$

is not conservative—you can do this by showing that its curl is

$$\text{curl } \mathbf{F}(x, y, z) = (x^3y^2 - 2xy)\mathbf{j} + (2xz - 2x^3yz)\mathbf{k} \neq \mathbf{0}.$$

For vector fields in space that pass the test for being conservative, you can find a potential function by following the same pattern used in the plane (as demonstrated in Example 6).

REMARK Examples 6 and 8 are illustrations of a type of problem called *recovering a function from its gradient*. If you go on to take a course in differential equations, you will study other methods for solving this type of problem. One popular method gives an interplay between successive "partial integrations" and partial differentiations.

EXAMPLE 8 Finding a Potential Function for $\mathbf{F}(x, y, z)$

Find a potential function for

$$\mathbf{F}(x, y, z) = 2xy\mathbf{i} + (x^2 + z^2)\mathbf{j} + 2yz\mathbf{k}.$$

Solution From Example 7, you know that the vector field given by $\mathbf{F}$ is conservative. If f is a function such that $\mathbf{F}(x, y, z) = \nabla f(x, y, z)$, then

$$f_x(x, y, z) = 2xy, \quad f_y(x, y, z) = x^2 + z^2, \quad \text{and} \quad f_z(x, y, z) = 2yz$$

and integrating with respect to x, y, and z separately produces

$$f(x, y, z) = \int M\,dx = \int 2xy\,dx = x^2y + g(y, z)$$

$$f(x, y, z) = \int N\,dy = \int (x^2 + z^2)\,dy = x^2y + yz^2 + h(x, z)$$

$$f(x, y, z) = \int P\,dz = \int 2yz\,dz = yz^2 + k(x, y).$$

Comparing these three versions of $f(x, y, z)$, you can conclude that

$$g(y, z) = yz^2 + K_1, \quad h(x, z) = K_2, \quad \text{and} \quad k(x, y) = x^2y + K_3.$$

So, $f(x, y, z)$ is given by

$$f(x, y, z) = x^2y + yz^2 + K. \qquad K = K_1 + K_2 + K_3$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Divergence of a Vector Field

You have learned that the curl of a vector field $\mathbf{F}$ is itself a vector field. Another important function defined on a vector field is **divergence,** which is a scalar function.

Definition of Divergence of a Vector Field

The **divergence** of $\mathbf{F}(x, y) = M\mathbf{i} + N\mathbf{j}$ is

$$\operatorname{div} \mathbf{F}(x, y) = \nabla \cdot \mathbf{F}(x, y) = \frac{\partial M}{\partial x} + \frac{\partial N}{\partial y}.$$ Plane

The **divergence** of $\mathbf{F}(x, y, z) = M\mathbf{i} + N\mathbf{j} + P\mathbf{k}$ is

$$\operatorname{div} \mathbf{F}(x, y, z) = \nabla \cdot \mathbf{F}(x, y, z) = \frac{\partial M}{\partial x} + \frac{\partial N}{\partial y} + \frac{\partial P}{\partial z}.$$ Space

If $\operatorname{div} \mathbf{F} = 0$, then $\mathbf{F}$ is said to be **divergence free.**

The dot product notation used for divergence comes from considering ∇ as a **differential operator,** as follows.

$$\begin{aligned}\nabla \cdot \mathbf{F}(x, y, z) &= \left[\left(\frac{\partial}{\partial x}\right)\mathbf{i} + \left(\frac{\partial}{\partial y}\right)\mathbf{j} + \left(\frac{\partial}{\partial z}\right)\mathbf{k}\right] \cdot (M\mathbf{i} + N\mathbf{j} + P\mathbf{k}) \\ &= \frac{\partial M}{\partial x} + \frac{\partial N}{\partial y} + \frac{\partial P}{\partial z}\end{aligned}$$

TECHNOLOGY

Some graphing utilities have a command that can be used to find the divergence of a vector field. If you have access to a graphing utility that has this feature, use it to find the divergence of the vector field in Example 9.

EXAMPLE 9 Finding the Divergence of a Vector Field

Find the divergence at $(2, 1, -1)$ for the vector field

$$\mathbf{F}(x, y, z) = x^3y^2z\mathbf{i} + x^2z\mathbf{j} + x^2y\mathbf{k}.$$

Solution The divergence of $\mathbf{F}$ is

$$\operatorname{div} \mathbf{F}(x, y, z) = \frac{\partial}{\partial x}[x^3y^2z] + \frac{\partial}{\partial y}[x^2z] + \frac{\partial}{\partial z}[x^2y] = 3x^2y^2z.$$

At the point $(2, 1, -1)$, the divergence is

$$\operatorname{div} \mathbf{F}(2, 1, -1) = 3(2^2)(1^2)(-1) = -12.$$ ■

Divergence can be viewed as a type of derivative of $\mathbf{F}$ in that, for vector fields representing velocities of moving particles, the divergence measures the rate of particle flow per unit volume at a point. In hydrodynamics (the study of fluid motion), a velocity field that is divergence free is called **incompressible.** In the study of electricity and magnetism, a vector field that is divergence free is called **solenoidal.**

There are many important properties of the divergence and curl of a vector field $\mathbf{F}$ [see Exercise 77(a)–(g)]. One that is used often is described in Theorem 15.3. You are asked to prove this theorem in Exercise 77(h).

THEOREM 15.3 Divergence and Curl

If $\mathbf{F}(x, y, z) = M\mathbf{i} + N\mathbf{j} + P\mathbf{k}$ is a vector field, and M, N, and P have continuous second partial derivatives, then

$$\operatorname{div}(\operatorname{curl} \mathbf{F}) = 0.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

15.1 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Define a vector field in the plane and in space. Give some physical examples of vector fields.
2. What is a conservative vector field? Explain how to test whether a vector field is conservative in the plane and in space.
3. Describe how to find a potential function for a vector field that is conservative.
4. A vector field in space is conservative. Is the vector field irrotational? Explain.

Matching In Exercises 5–8, match the vector field with its graph. [The graphs are labeled (a), (b), (c), and (d).]

(a)



(b)



(c)



(d)



5. $\mathbf{F}(x, y) = y\mathbf{i}$
6. $\mathbf{F}(x, y) = x\mathbf{j}$
7. $\mathbf{F}(x, y) = y\mathbf{i} - x\mathbf{j}$
8. $\mathbf{F}(x, y) = x\mathbf{i} + 3y\mathbf{j}$

Sketching a Vector Field In Exercises 9–14, find $\|\mathbf{F}\|$ and sketch several representative vectors in the vector field.

9. $\mathbf{F}(x, y) = \mathbf{i} + \mathbf{j}$
10. $\mathbf{F}(x, y) = y\mathbf{i} - 2x\mathbf{j}$
11. $\mathbf{F}(x, y) = -\mathbf{i} + 3y\mathbf{j}$
12. $\mathbf{F}(x, y) = y\mathbf{i} + x\mathbf{j}$
13. $\mathbf{F}(x, y, z) = \mathbf{i} + \mathbf{j} + \mathbf{k}$
14. $\mathbf{F}(x, y, z) = x\mathbf{i} + y\mathbf{j} + z\mathbf{k}$

Graphing a Vector Field Using Technology In Exercises 15–18, use a graphing utility to graph several representative vectors in the vector field.

15. $\mathbf{F}(x, y) = \frac{1}{8}(2xy\mathbf{i} + y^2\mathbf{j})$
16. $\mathbf{F}(x, y) = \langle 2y - x, 2y + x \rangle$
17. $\mathbf{F}(x, y, z) = \dfrac{x\mathbf{i} + y\mathbf{j} + z\mathbf{k}}{\sqrt{x^2 + y^2 + z^2}}$
18. $\mathbf{F}(x, y, z) = \langle x, -y, z \rangle$

Finding a Conservative Vector Field In Exercises 19–28, find the conservative vector field for the potential function by finding its gradient.

19. $f(x, y) = x^2 + 2y^2$
20. $f(x, y) = x^3 - 2xy$
21. $g(x, y) = 5x^2 + 3xy + y^2$
22. $g(x, y) = \sin 3x \cos 4y$
23. $f(x, y, z) = 6xyz$
24. $f(x, y, z) = \sqrt{x^2y + z^2}$
25. $g(x, y, z) = z + ye^{x^2}$
26. $g(x, y, z) = \dfrac{y}{z} + \dfrac{z}{x} - \dfrac{xz}{y}$
27. $h(x, y, z) = xy \ln(x + y)$
28. $h(x, y, z) = x \arcsin yz$

Testing for a Conservative Vector Field In Exercises 29–36, determine whether the vector field is conservative.

29. $\mathbf{F}(x, y) = xy^2\mathbf{i} + x^2y\mathbf{j}$
30. $\mathbf{F}(x, y) = \dfrac{1}{x^2}(y\mathbf{i} - x\mathbf{j})$
31. $\mathbf{F}(x, y) = \sin y\mathbf{i} + x \sin y\mathbf{j}$
32. $\mathbf{F}(x, y) = 5y^2(y\mathbf{i} + 2x\mathbf{j})$
33. $\mathbf{F}(x, y) = \dfrac{1}{xy}(y\mathbf{i} - x\mathbf{j})$
34. $\mathbf{F}(x, y) = \dfrac{2}{y^2}e^{2x/y}(y\mathbf{i} - x\mathbf{j})$
35. $\mathbf{F}(x, y) = \dfrac{\mathbf{i} + \mathbf{j}}{\sqrt{x^2 + y^2}}$
36. $\mathbf{F}(x, y) = \dfrac{y\mathbf{i} + x\mathbf{j}}{\sqrt{1 + xy}}$

Finding a Potential Function In Exercises 37–44, determine whether the vector field is conservative. If it is, find a potential function for the vector field.

37. $\mathbf{F}(x, y) = (3y - x^2)\mathbf{i} + (3x + y)\mathbf{j}$
38. $\mathbf{F}(x, y) = (x^3 + e^y)\mathbf{i} + (xe^y - 6)\mathbf{j}$
39. $\mathbf{F}(x, y) = xe^{x^2y}(2y\mathbf{i} + x\mathbf{j})$
40. $\mathbf{F}(x, y) = \dfrac{1}{y^2}(y\mathbf{i} - 2x\mathbf{j})$
41. $\mathbf{F}(x, y) = \dfrac{2y}{x}\mathbf{i} - \dfrac{x^2}{y^2}\mathbf{j}$
42. $\mathbf{F}(x, y) = \dfrac{x\mathbf{i} + y\mathbf{j}}{x^2 + y^2}$
43. $\mathbf{F}(x, y) = \sin y\mathbf{i} + x \cos y\mathbf{j}$
44. $\mathbf{F}(x, y) = (\ln y + 2)\mathbf{i} + \dfrac{x}{y}\mathbf{j}$

Finding the Curl of a Vector Field In Exercises 45–48, find the curl of the vector field at the given point.

45. $\mathbf{F}(x, y, z) = xyz\mathbf{i} + xyz\mathbf{j} + xyz\mathbf{k}$; $(2, 1, 3)$
46. $\mathbf{F}(x, y, z) = x^2z\mathbf{i} - 2xz\mathbf{j} + yz\mathbf{k}$; $(2, -1, 3)$
47. $\mathbf{F}(x, y, z) = e^x \sin y\mathbf{i} - e^x \cos y\mathbf{j}$; $(0, 0, 1)$
48. $\mathbf{F}(x, y, z) = e^{-xyz}(\mathbf{i} + \mathbf{j} + \mathbf{k})$; $(3, 2, 0)$

Finding the Curl of a Vector Field Using Technology In Exercises 49 and 50, use a graphing utility to find the curl of the vector field.

49. $\mathbf{F}(x, y, z) = \arctan\left(\dfrac{x}{y}\right)\mathbf{i} + \ln\sqrt{x^2 + y^2}\,\mathbf{j} + \mathbf{k}$
50. $\mathbf{F}(x, y, z) = \dfrac{yz}{y - z}\mathbf{i} + \dfrac{xz}{x - z}\mathbf{j} + \dfrac{xy}{x - y}\mathbf{k}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding a Potential Function **In Exercises 51–56, determine whether the vector field is conservative. If it is, find a potential function for the vector field.**

51. $\mathbf{F}(x, y, z) = (3x^2 + yz)\mathbf{i} + (3y^2 + xz)\mathbf{j} + (3z^2 + xy)\mathbf{k}$

52. $\mathbf{F}(x, y, z) = y^2z^3\mathbf{i} + 2xyz^3\mathbf{j} + 3xy^2z^2\mathbf{k}$

53. $\mathbf{F}(x, y, z) = \sin z\mathbf{i} + \sin x\mathbf{j} + \sin y\mathbf{k}$

54. $\mathbf{F}(x, y, z) = ye^z\mathbf{i} + ze^x\mathbf{j} + xe^y\mathbf{k}$

55. $\mathbf{F}(x, y, z) = \frac{z}{y}\mathbf{i} - \frac{xz}{y^2}\mathbf{j} + \left(\frac{x}{y} - 1\right)\mathbf{k}$

56. $\mathbf{F}(x, y, z) = \frac{x}{x^2 + y^2}\mathbf{i} + \frac{y}{x^2 + y^2}\mathbf{j} + \mathbf{k}$

Finding the Divergence of a Vector Field **In Exercises 57–60, find the divergence of the vector field.**

57. $\mathbf{F}(x, y) = x^2\mathbf{i} + 2y^2\mathbf{j}$

58. $\mathbf{F}(x, y) = xe^x\mathbf{i} - x^2y^2\mathbf{j}$

59. $\mathbf{F}(x, y, z) = \sin^2 x\mathbf{i} + z\cos z\mathbf{j} + z^3\mathbf{k}$

60. $\mathbf{F}(x, y, z) = \ln(x^2 + y^2)\mathbf{i} + xy\mathbf{j} + \ln(y^2 + z^2)\mathbf{k}$

Finding the Divergence of a Vector Field **In Exercises 61–64, find the divergence of the vector field at the given point.**

61. $\mathbf{F}(x, y, z) = xyz\mathbf{i} + xz^2\mathbf{j} + 3yz^2\mathbf{k};\ (2, 4, 1)$

62. $\mathbf{F}(x, y, z) = x^2z\mathbf{i} - 2xz\mathbf{j} + yz\mathbf{k};\ (2, -1, 3)$

63. $\mathbf{F}(x, y, z) = e^x \sin y\mathbf{i} - e^x \cos y\mathbf{j} + z^2\mathbf{k};\ (3, 0, 0)$

64. $\mathbf{F}(x, y, z) = \ln(xyz)(\mathbf{i} + \mathbf{j} + \mathbf{k});\ (3, 2, 1)$

Exploring Concepts

In Exercises 65–67, consider a scalar function f and a vector field $\mathbf{F}$ in space. Determine whether the expression is a vector field, a scalar function, or neither. Explain.

65. $\text{curl}(\nabla f)$ **66.** $\text{div}[\text{curl}(\nabla f)]$

67. $\text{curl}(\text{div}\ \mathbf{F})$

68. HOW DO YOU SEE IT? Several representative vectors in the vector fields

$$\mathbf{F}(x, y) = \frac{x\mathbf{i} + y\mathbf{j}}{\sqrt{x^2 + y^2}} \quad \text{and} \quad \mathbf{G}(x, y) = \frac{x\mathbf{i} - y\mathbf{j}}{\sqrt{x^2 + y^2}}$$

are shown below. Match each vector field with its graph. Explain your reasoning.

(a)



(b)



Curl of a Cross Product **In Exercises 69 and 70, find $\text{curl}(\mathbf{F} \times \mathbf{G}) = \nabla \times (\mathbf{F} \times \mathbf{G})$.**

69. $\mathbf{F}(x, y, z) = \mathbf{i} + 3x\mathbf{j} + 2y\mathbf{k}$
$\mathbf{G}(x, y, z) = x\mathbf{i} - y\mathbf{j} + z\mathbf{k}$

70. $\mathbf{F}(x, y, z) = x\mathbf{i} - z\mathbf{k}$
$\mathbf{G}(x, y, z) = x^2\mathbf{i} + y\mathbf{j} + z^2\mathbf{k}$

Curl of the Curl of a Vector Field **In Exercises 71 and 72, find $\text{curl}(\text{curl}\ \mathbf{F}) = \nabla \times (\nabla \times \mathbf{F})$.**

71. $\mathbf{F}(x, y, z) = xyz\mathbf{i} + y\mathbf{j} + z\mathbf{k}$

72. $\mathbf{F}(x, y, z) = x^2z\mathbf{i} - 2xz\mathbf{j} + yz\mathbf{k}$

Divergence of a Cross Product **In Exercises 73 and 74, find $\text{div}(\mathbf{F} \times \mathbf{G}) = \nabla \cdot (\mathbf{F} \times \mathbf{G})$.**

73. $\mathbf{F}(x, y, z) = \mathbf{i} + 3x\mathbf{j} + 2y\mathbf{k}$
$\mathbf{G}(x, y, z) = x\mathbf{i} - y\mathbf{j} + z\mathbf{k}$

74. $\mathbf{F}(x, y, z) = x\mathbf{i} - z\mathbf{k}$
$\mathbf{G}(x, y, z) = x^2\mathbf{i} + y\mathbf{j} + z^2\mathbf{k}$

Divergence of the Curl of a Vector Field **In Exercises 75 and 76, find $\text{div}(\text{curl}\ \mathbf{F}) = \nabla \cdot (\nabla \times \mathbf{F})$.**

75. $\mathbf{F}(x, y, z) = xyz\mathbf{i} + y\mathbf{j} + z\mathbf{k}$

76. $\mathbf{F}(x, y, z) = x^2z\mathbf{i} - 2xz\mathbf{j} + yz\mathbf{k}$

77. Proof In parts (a)–(h), prove the property for vector fields $\mathbf{F}$ and $\mathbf{G}$ and scalar function f. (Assume that the required partial derivatives are continuous.)

(a) $\text{curl}(\mathbf{F} + \mathbf{G}) = \text{curl}\ \mathbf{F} + \text{curl}\ \mathbf{G}$

(b) $\text{curl}(\nabla f) = \nabla \times (\nabla f) = \mathbf{0}$

(c) $\text{div}(\mathbf{F} + \mathbf{G}) = \text{div}\ \mathbf{F} + \text{div}\ \mathbf{G}$

(d) $\text{div}(\mathbf{F} \times \mathbf{G}) = (\text{curl}\ \mathbf{F}) \cdot \mathbf{G} - \mathbf{F} \cdot (\text{curl}\ \mathbf{G})$

(e) $\nabla \times [\nabla f + (\nabla \times \mathbf{F})] = \nabla \times (\nabla \times \mathbf{F})$

(f) $\nabla \times (f\mathbf{F}) = f(\nabla \times \mathbf{F}) + (\nabla f) \times \mathbf{F}$

(g) $\text{div}(f\mathbf{F}) = f\,\text{div}\ \mathbf{F} + \nabla f \cdot \mathbf{F}$

(h) $\text{div}(\text{curl}\ \mathbf{F}) = 0$ (Theorem 15.3)

78. Earth's Magnetic Field

A cross section of Earth's magnetic field can be represented as a vector field in which the center of Earth is located at the origin and the positive y-axis points in the direction of the magnetic north pole. The equation for this field is



$$\mathbf{F}(x, y) = M(x, y)\mathbf{i} + N(x, y)\mathbf{j}$$
$$= \frac{m}{(x^2 + y^2)^{5/2}}[3xy\mathbf{i} + (2y^2 - x^2)\mathbf{j}]$$

where m is the magnetic moment of Earth. Show that this vector field is conservative.

vchal/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

15.2 Line Integrals

GO DIGITAL

- Describe the concept of a piecewise smooth curve.
- Write and evaluate a line integral.
- Write and evaluate a line integral of a vector field.
- Write and evaluate a line integral in differential form.

Piecewise Smooth Curves

A classic property of gravitational fields is that, subject to certain physical constraints, the work done by gravity on an object moving between two points in the field is independent of the path taken by the object. One of the constraints is that the **path** must be a piecewise smooth curve. Recall that a plane curve C given by

$$\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j}, \quad a \le t \le b$$ Vector-valued function in the plane

is **smooth** when

$$\frac{dx}{dt} \quad \text{and} \quad \frac{dy}{dt}$$

are continuous on $[a, b]$ and not simultaneously 0 on (a, b). Similarly, a space curve C given by

$$\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j} + z(t)\mathbf{k}, \quad a \le t \le b$$ Vector-valued function in space

is **smooth** when

$$\frac{dx}{dt}, \quad \frac{dy}{dt}, \quad \text{and} \quad \frac{dz}{dt}$$

are continuous on $[a, b]$ and not simultaneously 0 on (a, b). A curve C is **piecewise smooth** when the interval $[a, b]$ can be partitioned into a finite number of subintervals, on each of which C is smooth.

EXAMPLE 1 Finding a Piecewise Smooth Parametrization

Find a piecewise smooth parametrization of the graph of C shown in Figure 15.7.



Figure 15.7

Solution Because C consists of three line segments C_1, C_2, and C_3, you can construct a smooth parametrization for each segment and piece them together by making the last t-value in C_i correspond to the first t-value in C_{i+1}.

$$\begin{aligned} C_1\colon\ & x(t) = 0, & y(t) &= 2t, & z(t) &= 0, & 0 \le t \le 1 \\ C_2\colon\ & x(t) = t - 1, & y(t) &= 2, & z(t) &= 0, & 1 \le t \le 2 \\ C_3\colon\ & x(t) = 1, & y(t) &= 2, & z(t) &= t - 2, & 2 \le t \le 3 \end{aligned}$$

So, C is given by

$$\mathbf{r}(t) = \begin{cases} 2t\mathbf{j}, & 0 \le t \le 1 \\ (t-1)\mathbf{i} + 2\mathbf{j}, & 1 \le t \le 2. \\ \mathbf{i} + 2\mathbf{j} + (t-2)\mathbf{k}, & 2 \le t \le 3 \end{cases}$$

Because C_1, C_2, and C_3 are smooth, it follows that C is piecewise smooth. ■

Recall that parametrization of a curve induces an **orientation** to the curve. For instance, in Example 1, the curve is oriented such that the positive direction is from $(0, 0, 0)$, following the curve to $(1, 2, 1)$. Try finding a parametrization that induces the opposite orientation.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



JOSIAH WILLARD GIBBS (1839–1903)

Many physicists and mathematicians have contributed to the theory and applications described in this chapter—Newton, Gauss, Laplace, Hamilton, and Maxwell, among others. However, the use of vector analysis to describe these results is attributed primarily to the American mathematical physicist Josiah Willard Gibbs. *See LarsonCalculus.com to read more of this biography.*

Line Integrals

Up to this point in the text, you have studied various types of integrals. For a single integral

$$\int_a^b f(x)\,dx$$ Integrate over interval $[a, b]$.

you integrated over the interval $[a, b]$. Similarly, for a double integral

$$\int_R\int f(x, y)\,dA$$ Integrate over region R.

you integrated over the region R in the plane. In this section, you will study a new type of integral called a **line integral**

$$\int_C f(x, y)\,ds$$ Integrate over curve C.

for which you integrate over a piecewise smooth curve C. (The terminology is somewhat unfortunate—this type of integral might be better described as a "curve integral.")

To introduce the concept of a line integral, consider the mass of a wire of finite length, given by a curve C in space. The density (mass per unit length) of the wire at the point (x, y, z) is given by $f(x, y, z)$. Partition the curve C by the points

$$P_0, P_1, \ldots, P_n$$

producing n subarcs, as shown in Figure 15.8. The length of the ith subarc is given by Δs_i. Next, choose a point (x_i, y_i, z_i) in each subarc. If the length of each subarc is small, then the total mass of the wire can be approximated by the sum

$$\text{Mass of wire} \approx \sum_{i=1}^{n} f(x_i, y_i, z_i)\,\Delta s_i.$$



Partitioning of curve C
Figure 15.8

By letting $\|\Delta\|$ denote the length of the longest subarc and letting $\|\Delta\|$ approach 0, it seems reasonable that the limit of this sum approaches the mass of the wire. This leads to the next definition.

Definition of Line Integral

If f is defined in a region containing a smooth curve C of finite length, then the **line integral of f along C** is given by

$$\int_C f(x, y)\,ds = \lim_{\|\Delta\|\to 0} \sum_{i=1}^{n} f(x_i, y_i)\,\Delta s_i$$ Plane

or

$$\int_C f(x, y, z)\,ds = \lim_{\|\Delta\|\to 0} \sum_{i=1}^{n} f(x_i, y_i, z_i)\,\Delta s_i$$ Space

provided this limit exists.

As with the integrals discussed in Chapter 14, evaluation of a line integral is best accomplished by converting it to a definite integral. It can be shown that if f is *continuous*, then the limit given above exists and is the same for all smooth parametrizations of C.

Science History Images/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

To evaluate a line integral over a plane curve C given by $\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j}$, use the fact that

$$ds = \|\mathbf{r}'(t)\|\,dt = \sqrt{[x'(t)]^2 + [y'(t)]^2}\,dt.$$

A similar formula holds for a space curve, as indicated in Theorem 15.4.

THEOREM 15.4 Evaluation of a Line Integral as a Definite Integral

Let f be continuous in a region containing a smooth curve C. If C is given by $\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j}$, where $a \le t \le b$, then

$$\int_C f(x, y)\,ds = \int_a^b f(x(t), y(t))\sqrt{[x'(t)]^2 + [y'(t)]^2}\,dt.$$

If C is given by $\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j} + z(t)\mathbf{k}$, where $a \le t \le b$, then

$$\int_C f(x, y, z)\,ds = \int_a^b f(x(t), y(t), z(t))\sqrt{[x'(t)]^2 + [y'(t)]^2 + [z'(t)]^2}\,dt.$$

Note that if $f(x, y, z) = 1$, then the line integral gives the arc length of the curve C, as defined in Section 12.5. That is,

$$\int_C 1\,ds = \int_a^b \|\mathbf{r}'(t)\|\,dt = \text{length of curve } C.$$

EXAMPLE 2 Evaluating a Line Integral



Figure 15.9

Evaluate

$$\int_C (x^2 - y + 3z)\,ds$$

where C is the line segment shown in Figure 15.9.

Solution Begin by writing a parametric form of the equation of the line segment:

$$x = t, \quad y = 2t, \quad \text{and} \quad z = t, \quad 0 \le t \le 1.$$

Therefore, $x'(t) = 1$, $y'(t) = 2$, and $z'(t) = 1$, which implies that

$$\sqrt{[x'(t)]^2 + [y'(t)]^2 + [z'(t)]^2} = \sqrt{1^2 + 2^2 + 1^2} = \sqrt{6}.$$

So, the line integral takes the following form.

$$\begin{aligned}\int_C (x^2 - y + 3z)\,ds &= \int_0^1 (t^2 - 2t + 3t)\sqrt{6}\,dt \\ &= \sqrt{6}\int_0^1 (t^2 + t)\,dt \\ &= \sqrt{6}\left[\frac{t^3}{3} + \frac{t^2}{2}\right]_0^1 \\ &= \frac{5\sqrt{6}}{6}\end{aligned}$$

The value of the line integral in Example 2 does not depend on the parametrization of the line segment C; any smooth parametrization will produce the same value. To convince yourself of this, try some other parametrizations, such as $x = 1 + 2t$, $y = 2 + 4t$, and $z = 1 + 2t$, $-\frac{1}{2} \le t \le 0$, or $x = -t$, $y = -2t$, and $z = -t$, $-1 \le t \le 0$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Let C be a path composed of smooth curves $C_1, C_2, \ldots, C_n$. If f is continuous on C, then it can be shown that

$$\int_C f(x, y)\, ds = \int_{C_1} f(x, y)\, ds + \int_{C_2} f(x, y)\, ds + \cdots + \int_{C_n} f(x, y)\, ds.$$

This property is used in Example 3.

EXAMPLE 3 Evaluating a Line Integral Over a Path

Evaluate

$$\int_C x\, ds$$

where C is the piecewise smooth curve shown in Figure 15.10.



Figure 15.10

Solution Begin by integrating up the line $y = x$, using the following parametrization.

$$C_1\colon\ x = t, \quad y = t, \quad 0 \le t \le 1$$

For this curve, $\mathbf{r}(t) = t\mathbf{i} + t\mathbf{j}$, which implies that $x'(t) = 1$ and $y'(t) = 1$. So,

$$\sqrt{[x'(t)]^2 + [y'(t)]^2} = \sqrt{2}$$

and you have

$$\int_{C_1} x\, ds = \int_0^1 t\sqrt{2}\, dt = \frac{\sqrt{2}}{2}t^2\Big]_0^1 = \frac{\sqrt{2}}{2}.$$

Next, integrate down the parabola $y = x^2$, using the parametrization

$$C_2\colon x = 1 - t, \quad y = (1 - t)^2, \quad 0 \le t \le 1.$$

For this curve,

$$\mathbf{r}(t) = (1 - t)\mathbf{i} + (1 - t)^2\mathbf{j}$$

which implies that $x'(t) = -1$ and $y'(t) = -2(1 - t)$. So,

$$\sqrt{[x'(t)]^2 + [y'(t)]^2} = \sqrt{1 + 4(1 - t)^2}$$

and you have

$$\begin{aligned}\int_{C_2} x\, ds &= \int_0^1 (1 - t)\sqrt{1 + 4(1 - t)^2}\, dt \\ &= -\frac{1}{8}\left[\frac{2}{3}[1 + 4(1 - t)^2]^{3/2}\right]_0^1 \\ &= \frac{1}{12}(5^{3/2} - 1).\end{aligned}$$

Consequently,

$$\int_C x\, ds = \int_{C_1} x\, ds + \int_{C_2} x\, ds = \frac{\sqrt{2}}{2} + \frac{1}{12}(5^{3/2} - 1) \approx 1.56.$$

For parametrizations given by $\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j} + z(t)\mathbf{k}$, it is helpful to remember the form of ds as

$$ds = \|\mathbf{r}'(t)\|\, dt = \sqrt{[x'(t)]^2 + [y'(t)]^2 + [z'(t)]^2}\, dt.$$

This is demonstrated in Example 4.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 4 **Evaluating a Line Integral**

Evaluate $\int_C (x + 2)\, ds$, where C is the curve represented by

$$\mathbf{r}(t) = t\mathbf{i} + \frac{4}{3}t^{3/2}\mathbf{j} + \frac{1}{2}t^2\mathbf{k}, \quad 0 \le t \le 2.$$

Solution Because $\mathbf{r}'(t) = \mathbf{i} + 2t^{1/2}\mathbf{j} + t\mathbf{k}$ and

$$\|\mathbf{r}'(t)\| = \sqrt{[x'(t)^2] + [y'(t)]^2 + [z'(t)]^2} = \sqrt{1 + 4t + t^2}$$

it follows that

$$\begin{aligned}\int_C (x + 2)\, ds &= \int_0^2 (t + 2)\sqrt{1 + 4t + t^2}\, dt \\ &= \frac{1}{2}\int_0^2 2(t + 2)(1 + 4t + t^2)^{1/2}\, dt \\ &= \frac{1}{3}\Big[(1 + 4t + t^2)^{3/2}\Big]_0^2 \\ &= \frac{1}{3}\left(13\sqrt{13} - 1\right) \\ &\approx 15.29.\end{aligned}$$

The next example shows how a line integral can be used to find the mass of a spring whose density varies. In Figure 15.11, note that the density of this spring increases as the spring spirals up the z-axis.

EXAMPLE 5 **Finding the Mass of a Spring**

Find the mass of a spring in the shape of the circular helix

$$\mathbf{r}(t) = \frac{1}{\sqrt{2}}(\cos t\mathbf{i} + \sin t\mathbf{j} + t\mathbf{k})$$

where $0 \le t \le 6\pi$ and the density of the spring is

$$\rho(x, y, z) = 1 + z$$

as shown in Figure 15.11.



Figure 15.11

Solution Because

$$\|\mathbf{r}'(t)\| = \frac{1}{\sqrt{2}}\sqrt{(-\sin t)^2 + (\cos t)^2 + (1)^2} = 1$$

it follows that the mass of the spring is

$$\begin{aligned}\text{Mass} &= \int_C (1 + z)\, ds \\ &= \int_0^{6\pi} \left(1 + \frac{t}{\sqrt{2}}\right) dt \\ &= \left[t + \frac{t^2}{2\sqrt{2}}\right]_0^{6\pi} \\ &= 6\pi\left(1 + \frac{3\pi}{\sqrt{2}}\right) \\ &\approx 144.47.\end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Inverse square force field **F**



Vectors along a parabolic path in the force field **F**

Figure 15.12

Line Integrals of Vector Fields

One of the most important physical applications of line integrals is that of finding the **work** done on an object moving in a force field. For example, Figure 15.12 shows an inverse square force field similar to the gravitational field of the sun. Note that the magnitude of the force along a circular path about the center is constant, whereas the magnitude of the force along a parabolic path varies from point to point.

To understand how a line integral can be used to find work done in a force field **F**, consider an object moving along a path C in the field, as shown in Figure 15.13. To determine the work done by the force, you need consider only that part of the force that is acting in the same direction as that in which the object is moving (or the opposite direction). This means that at each point on C, you can consider the projection $\mathbf{F} \cdot \mathbf{T}$ of the force vector $\mathbf{F}$ onto the unit tangent vector $\mathbf{T}$. On a small subarc of length Δs_i, the increment of work is

$$\begin{aligned} \Delta W_i &= (\text{force})(\text{distance}) \\ &\approx [\mathbf{F}(x_i, y_i, z_i) \cdot \mathbf{T}(x_i, y_i, z_i)]\, \Delta s_i \end{aligned}$$

where (x_i, y_i, z_i) is a point in the ith subarc. Consequently, the total work done is given by the integral

$$W = \int_C \mathbf{F}(x, y, z) \cdot \mathbf{T}(x, y, z)\, ds.$$



At each point on C, the force in the direction of motion is $(\mathbf{F} \cdot \mathbf{T})\mathbf{T}$.

Figure 15.13

This line integral appears in other contexts and is the basis of the definition of the **line integral of a vector field** shown below. Note in the definition that

$$\begin{aligned} \mathbf{F} \cdot \mathbf{T}\, ds &= \mathbf{F} \cdot \frac{\mathbf{r}'(t)}{\|\mathbf{r}'(t)\|} \|\mathbf{r}'(t)\|\, dt \\ &= \mathbf{F} \cdot \mathbf{r}'(t)\, dt \\ &= \mathbf{F} \cdot d\mathbf{r}. \end{aligned}$$

Definition of the Line Integral of a Vector Field

Let $\mathbf{F}$ be a continuous vector field defined on a smooth curve C given by

$$\mathbf{r}(t), \quad a \le t \le b.$$

The **line integral** of $\mathbf{F}$ on C is given by

$$\begin{aligned} \int_C \mathbf{F} \cdot d\mathbf{r} &= \int_C \mathbf{F} \cdot \mathbf{T}\, ds \\ &= \int_a^b \mathbf{F}(x(t), y(t), z(t)) \cdot \mathbf{r}'(t)\, dt. \end{aligned}$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 15.14

GO DIGITAL

EXAMPLE 6 Work Done by a Force

See LarsonCalculus.com for an interactive version of this type of example.

Find the work done by the force field

$$\mathbf{F}(x, y, z) = -\frac{1}{2}x\mathbf{i} - \frac{1}{2}y\mathbf{j} + \frac{1}{4}\mathbf{k}$$ Force field **F**

on a particle as it moves along the helix given by

$$\mathbf{r}(t) = \cos t\mathbf{i} + \sin t\mathbf{j} + t\mathbf{k}$$ Space curve C

from the point $(1, 0, 0)$ to the point $(-1, 0, 3\pi)$, as shown in Figure 15.14.

Solution Because

$$\begin{aligned}\mathbf{r}(t) &= x(t)\mathbf{i} + y(t)\mathbf{j} + z(t)\mathbf{k} \\ &= \cos t\mathbf{i} + \sin t\mathbf{j} + t\mathbf{k}\end{aligned}$$

it follows that

$$x(t) = \cos t, \quad y(t) = \sin t, \quad \text{and} \quad z(t) = t.$$

So, the force field can be written as

$$\mathbf{F}(x(t), y(t), z(t)) = -\frac{1}{2}\cos t\mathbf{i} - \frac{1}{2}\sin t\mathbf{j} + \frac{1}{4}\mathbf{k}.$$

To find the work done by the force field in moving a particle along the curve C, use the fact that

$$\mathbf{r}'(t) = -\sin t\mathbf{i} + \cos t\mathbf{j} + \mathbf{k}$$

and write the following.

$$\begin{aligned}W &= \int_C \mathbf{F} \cdot d\mathbf{r} \\ &= \int_a^b \mathbf{F}(x(t), y(t), z(t)) \cdot \mathbf{r}'(t)\, dt \\ &= \int_0^{3\pi} \left(-\frac{1}{2}\cos t\mathbf{i} - \frac{1}{2}\sin t\mathbf{j} + \frac{1}{4}\mathbf{k}\right) \cdot (-\sin t\mathbf{i} + \cos t\mathbf{j} + \mathbf{k})\, dt \\ &= \int_0^{3\pi} \left(\frac{1}{2}\sin t\cos t - \frac{1}{2}\sin t\cos t + \frac{1}{4}\right) dt \\ &= \int_0^{3\pi} \frac{1}{4}\, dt \\ &= \frac{1}{4}t\Big]_0^{3\pi} \\ &= \frac{3\pi}{4}\end{aligned}$$



Generated by Mathematica

Figure 15.15

In Example 6, note that the x- and y-components of the force field end up contributing nothing to the total work. This occurs because *in this particular example*, the z-component of the force field is the only portion of the force that is acting in the same (or opposite) direction in which the particle is moving (see Figure 15.15).

TECHNOLOGY Figure 15.15 shows a computer-generated view of the force field in Example 6. The figure indicates that each vector in the force field points toward the z-axis.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

For line integrals of vector functions, the orientation of the curve C is important. When the orientation of the curve is reversed, the unit tangent vector $\mathbf{T}(t)$ is changed to $-\mathbf{T}(t)$, and you obtain

$$\int_{-C} \mathbf{F} \cdot d\mathbf{r} = -\int_{C} \mathbf{F} \cdot d\mathbf{r}.$$

EXAMPLE 7 Orientation and Parametrization of a Curve

Let $\mathbf{F}(x, y) = y\mathbf{i} + x^2\mathbf{j}$ and evaluate the line integral

$$\int_C \mathbf{F} \cdot d\mathbf{r}$$

for each parabolic curve shown in Figure 15.16.

a. C_1: $\mathbf{r}_1(t) = (4 - t)\mathbf{i} + (4t - t^2)\mathbf{j}, \quad 0 \le t \le 3$

b. C_2: $\mathbf{r}_2(t) = t\mathbf{i} + (4t - t^2)\mathbf{j}, \quad 1 \le t \le 4$



Figure 15.16

Solution

a. Because $\mathbf{r}_1'(t) = -\mathbf{i} + (4 - 2t)\mathbf{j}$ and

$$\mathbf{F}(x(t), y(t)) = (4t - t^2)\mathbf{i} + (4 - t)^2\mathbf{j}$$

the line integral is

$$\begin{aligned}
\int_{C_1} \mathbf{F} \cdot d\mathbf{r} &= \int_0^3 [(4t - t^2)\mathbf{i} + (4 - t)^2\mathbf{j}] \cdot [-\mathbf{i} + (4 - 2t)\mathbf{j}]\, dt \\
&= \int_0^3 (-4t + t^2 + 64 - 64t + 20t^2 - 2t^3)\, dt \\
&= \int_0^3 (-2t^3 + 21t^2 - 68t + 64)\, dt \\
&= \left[-\frac{t^4}{2} + 7t^3 - 34t^2 + 64t\right]_0^3 \\
&= \frac{69}{2}.
\end{aligned}$$

b. Because $\mathbf{r}_2'(t) = \mathbf{i} + (4 - 2t)\mathbf{j}$ and

$$\mathbf{F}(x(t), y(t)) = (4t - t^2)\mathbf{i} + t^2\mathbf{j}$$

the line integral is

$$\begin{aligned}
\int_{C_2} \mathbf{F} \cdot d\mathbf{r} &= \int_1^4 [(4t - t^2)\mathbf{i} + t^2\mathbf{j}] \cdot [\mathbf{i} + (4 - 2t)\mathbf{j}]\, dt \\
&= \int_1^4 (4t - t^2 + 4t^2 - 2t^3)\, dt \\
&= \int_1^4 (-2t^3 + 3t^2 + 4t)\, dt \\
&= \left[-\frac{t^4}{2} + t^3 + 2t^2\right]_1^4 \\
&= -\frac{69}{2}.
\end{aligned}$$

The answer in part (b) is the negative of that in part (a) because C_1 and C_2 represent opposite orientations of the same parabolic segment. ■

REMARK Although the value of the line integral in Example 7 depends on the orientation of C, it does not depend on the parametrization of C. To show this, let C_3 be represented by

$$\mathbf{r}_3(t) = (t + 2)\mathbf{i} + (4 - t^2)\mathbf{j}$$

where $-1 \le t \le 2$. The graph of this curve is the same parabolic segment shown in Figure 15.16. Does the value of the line integral over C_3 agree with the value over C_1 or C_2? Why or why not?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Line Integrals in Differential Form

A second commonly used form of line integrals is derived from the vector field notation used in Section 15.1. If $\mathbf{F}$ is a vector field of the form $\mathbf{F}(x, y) = M\mathbf{i} + N\mathbf{j}$ and C is given by $\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j}$, then $\mathbf{F} \cdot d\mathbf{r}$ is often written as $M\,dx + N\,dy$.

$$\begin{aligned}\int_C \mathbf{F} \cdot d\mathbf{r} &= \int_C \mathbf{F} \cdot \frac{d\mathbf{r}}{dt}\,dt \\ &= \int_a^b (M\mathbf{i} + N\mathbf{j}) \cdot (x'(t)\mathbf{i} + y'(t)\mathbf{j})\,dt \\ &= \int_a^b \left(M\frac{dx}{dt} + N\frac{dy}{dt}\right) dt \\ &= \int_C (M\,dx + N\,dy)\end{aligned}$$

This **differential form** can be extended to three variables.

REMARK The parentheses are often omitted from this differential form, as shown below.

$$\int_C M\,dx + N\,dy$$

In three variables, the differential form is

$$\int_C M\,dx + N\,dy + P\,dz.$$

EXAMPLE 8 Evaluating a Line Integral in Differential Form

Let C be the circle of radius 3 given by

$$\mathbf{r}(t) = 3\cos t\mathbf{i} + 3\sin t\mathbf{j}, \quad 0 \le t \le 2\pi$$

as shown in Figure 15.17. Evaluate the line integral

$$\int_C y^3\,dx + (x^3 + 3xy^2)\,dy.$$

Solution Because $x = 3\cos t$ and $y = 3\sin t$, you have $dx = -3\sin t\,dt$ and $dy = 3\cos t\,dt$. So, the line integral is

$$\begin{aligned}&\int_C M\,dx + N\,dy \\ &= \int_C y^3\,dx + (x^3 + 3xy^2)\,dy \\ &= \int_0^{2\pi} [(27\sin^3 t)(-3\sin t) + (27\cos^3 t + 81\cos t\sin^2 t)(3\cos t)]\,dt \\ &= 81\int_0^{2\pi} (\cos^4 t - \sin^4 t + 3\cos^2 t\sin^2 t)\,dt \\ &= 81\int_0^{2\pi} \left(\cos^2 t - \sin^2 t + \frac{3}{4}\sin^2 2t\right) dt \\ &= 81\int_0^{2\pi} \left[\cos 2t + \frac{3}{4}\left(\frac{1 - \cos 4t}{2}\right)\right] dt \\ &= 81\left[\frac{\sin 2t}{2} + \frac{3}{8}t - \frac{3\sin 4t}{32}\right]_0^{2\pi} \\ &= \frac{243\pi}{4}.\end{aligned}$$



Figure 15.17

The orientation of C affects the value of the differential form of a line integral. Specifically, if $-C$ has the orientation opposite to that of C, then

$$\int_{-C} M\,dx + N\,dy = -\int_C M\,dx + N\,dy.$$

So, of the three line integral forms presented in this section, the orientation of C does not affect the form $\int_C f(x, y)\,ds$, but it does affect the vector form and the differential form.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

For curves represented by $y = g(x)$, $a \le x \le b$, you can let $x = t$ and obtain the parametric form

$$x = t \quad \text{and} \quad y = g(t), \quad a \le t \le b.$$

Because $dx = dt$ for this form, you have the option of evaluating the line integral in the variable x or the variable t. This is demonstrated in Example 9.

EXAMPLE 9 Evaluating a Line Integral in Differential Form

Evaluate

$$\int_C y\,dx + x^2\,dy$$

where C is the parabolic arc given by $y = 4x - x^2$ from $(4, 0)$ to $(1, 3)$, as shown in Figure 15.18.



Figure 15.18

Solution Rather than converting to the parameter t, you can simply retain the variable x and write

$$y = 4x - x^2 \quad \Rightarrow \quad dy = (4 - 2x)\,dx.$$

Then, in the direction from $(4, 0)$ to $(1, 3)$, the line integral is

$$\begin{aligned}\int_C y\,dx + x^2\,dy &= \int_4^1 [(4x - x^2)\,dx + x^2(4 - 2x)\,dx] \\ &= \int_4^1 (4x + 3x^2 - 2x^3)\,dx \\ &= \left[2x^2 + x^3 - \frac{x^4}{2}\right]_4^1 \\ &= \frac{69}{2}.\end{aligned}$$

See Example 7.

Exploration

Finding Lateral Surface Area The figure below shows a piece of tin that has been cut from a circular cylinder. The base of the circular cylinder is modeled by $x^2 + y^2 = 9$. At any point (x, y) on the base, the height of the object is

$$f(x, y) = 1 + \cos\frac{\pi x}{4}.$$

Explain how to use a line integral to find the surface area of the piece of tin.



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

15.2 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. State the physical interpretation of each line integral.

(a) $\int_C 1\, ds$

(b) $\int_C f(x, y, z)\, ds$, where $f(x, y, z)$ is the density of a string of finite length

2. Describe how reversing the orientation of a curve C affects $\int_C \mathbf{F} \cdot d\mathbf{r}$.

Finding a Piecewise Smooth Parametrization **In Exercises 3–8, find a piecewise smooth parametrization of the path C. (There is more than one correct answer.)**

3.



4.



5.



6.



7.



8.



Evaluating a Line Integral **In Exercises 9–12, (a) find a parametrization of the path C and (b) evaluate $\int_C (x^2 + y^2)\, ds$.**

9. C: line segment from $(0, 0)$ to $(1, 1)$

10. C: line segment from $(0, 0)$ to $(2, 4)$

11. C: counterclockwise around the circle $x^2 + y^2 = 1$ from $(1, 0)$ to $(0, 1)$

12. C: counterclockwise around the circle $x^2 + y^2 = 4$ from $(2, 0)$ to $(-2, 0)$

Evaluating a Line Integral **In Exercises 13–16, (a) find a piecewise smooth parametrization of the path C and (b) evaluate**

$$\int_C \left(2x + 3\sqrt{y}\right) ds.$$

13. C: line segments from $(0, 0)$ to $(1, 0)$ and $(1, 0)$ to $(2, 4)$

14. C: line segments from $(0, 1)$ to $(0, 4)$ and $(0, 4)$ to $(3, 3)$

15. C: counterclockwise around the triangle with vertices $(0, 0)$, $(1, 0)$, and $(0, 1)$

16. C: counterclockwise around the square with vertices $(0, 0)$, $(2, 0)$, $(2, 2)$, and $(0, 2)$

Evaluating a Line Integral **In Exercises 17 and 18, (a) find a piecewise smooth parametrization of the path C shown in the figure and (b) evaluate $\int_C (2x + y^2 - z)\, ds$.**

17.



18.



Evaluating a Line Integral **In Exercises 19–22, evaluate the line integral along the given path.**

19. $\int_C xy\, ds$

C: $\mathbf{r}(t) = 4t\mathbf{i} + 3t\mathbf{j}$

$0 \le t \le 1$

20. $\int_C 3(x - y)\, ds$

C: $\mathbf{r}(t) = t\mathbf{i} + (2 - t)\mathbf{j}$

$0 \le t \le 2$

21. $\int_C (x^2 + y^2 + z^2)\, ds$

C: $\mathbf{r}(t) = \sin t\mathbf{i} + \cos t\mathbf{j} + 2\mathbf{k}$

$0 \le t \le \dfrac{\pi}{2}$

22. $\int_C 2xyz\, ds$

C: $\mathbf{r}(t) = 12t\mathbf{i} + 5t\mathbf{j} + 84t\mathbf{k}$

$0 \le t \le 1$

Mass **In Exercises 23 and 24, find the total mass of a spring with density ρ in the shape of the circular helix**

$$\mathbf{r}(t) = 2\cos t\mathbf{i} + 2\sin t\mathbf{j} + t\mathbf{k},\ 0 \le t \le 4\pi.$$

23. $\rho(x, y, z) = \frac{1}{2}(x^2 + y^2 + z^2)$

24. $\rho(x, y, z) = z$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Mass **In Exercises 25–28, find the total mass of the wire with density ρ whose shape is modeled by r.**

25. $\mathbf{r}(t) = \cos t\mathbf{i} + \sin t\mathbf{j},\ 0 \le t \le \pi,\ \rho(x, y) = x + y + 2$

26. $\mathbf{r}(t) = t^2\mathbf{i} + 2t\mathbf{j},\ 0 \le t \le 1,\ \rho(x, y) = \frac{3}{4}y$

27. $\mathbf{r}(t) = t^2\mathbf{i} + 2t\mathbf{j} + t\mathbf{k},\ 1 \le t \le 3,$
$\rho(x, y, z) = kz\ (k > 0)$

28. $\mathbf{r}(t) = 2\cos t\mathbf{i} + 2\sin t\mathbf{j} + 3t\mathbf{k},\ 0 \le t \le 2\pi,$
$\rho(x, y, z) = k + z\ (k > 0)$

Evaluating a Line Integral of a Vector Field **In Exercises 29–34, evaluate $\int_C \mathbf{F} \cdot d\mathbf{r}$.**

29. $\mathbf{F}(x, y) = x\mathbf{i} + y\mathbf{j}$

C: $\mathbf{r}(t) = (3t + 1)\mathbf{i} + t\mathbf{j},\quad 0 \le t \le 1$

30. $\mathbf{F}(x, y) = xy\mathbf{i} + y\mathbf{j}$

C: $\mathbf{r}(t) = 4\cos t\mathbf{i} + 4\sin t\mathbf{j},\quad 0 \le t \le \dfrac{\pi}{2}$

31. $\mathbf{F}(x, y) = x^2\mathbf{i} + 4y\mathbf{j}$

C: $\mathbf{r}(t) = e^t\mathbf{i} + t^2\mathbf{j},\quad 0 \le t \le 2$

32. $\mathbf{F}(x, y) = 3x\mathbf{i} + 4y\mathbf{j}$

C: $\mathbf{r}(t) = t\mathbf{i} + \sqrt{4 - t^2}\mathbf{j},\quad -2 \le t \le 2$

33. $\mathbf{F}(x, y, z) = xy\mathbf{i} + xz\mathbf{j} + yz\mathbf{k}$

C: $\mathbf{r}(t) = t\mathbf{i} + t^2\mathbf{j} + 2t\mathbf{k},\quad 0 \le t \le 1$

34. $\mathbf{F}(x, y, z) = x^2\mathbf{i} + y^2\mathbf{j} + z^2\mathbf{k}$

C: $\mathbf{r}(t) = 2\sin t\mathbf{i} + 2\cos t\mathbf{j} + \frac{1}{2}t^2\mathbf{k},\quad 0 \le t \le \pi$

Evaluating a Line Integral of a Vector Field Using Technology **In Exercises 35 and 36, use a graphing utility to evaluate $\int_C \mathbf{F} \cdot d\mathbf{r}$.**

35. $\mathbf{F}(x, y, z) = x^2z\mathbf{i} + 6y\mathbf{j} + yz^2\mathbf{k}$

C: $\mathbf{r}(t) = t\mathbf{i} + t^2\mathbf{j} + \ln t\mathbf{k},\quad 1 \le t \le 3$

36. $\mathbf{F}(x, y, z) = \dfrac{x\mathbf{i} + y\mathbf{j} + z\mathbf{k}}{\sqrt{x^2 + y^2 + z^2}}$

C: $\mathbf{r}(t) = t\mathbf{i} + t\mathbf{j} + e^t\mathbf{k},\quad 0 \le t \le 2$

Work **In Exercises 37–42, find the work done by the force field F on a particle moving along the given path.**

37. $\mathbf{F}(x, y) = x\mathbf{i} + 2y\mathbf{j}$

C: $x = t, y = t^3$ from $(0, 0)$ to $(2, 8)$



Figure for 37



Figure for 38

38. $\mathbf{F}(x, y) = x^2\mathbf{i} - xy\mathbf{j}$

C: $x = \cos^3 t, y = \sin^3 t$ from $(1, 0)$ to $(0, 1)$

39. $\mathbf{F}(x, y) = x\mathbf{i} + y\mathbf{j}$

C: counterclockwise around the triangle with vertices $(0, 0)$, $(1, 0)$, and $(0, 1)$



Figure for 39



Figure for 40

40. $\mathbf{F}(x, y) = -y\mathbf{i} - x\mathbf{j}$

C: counterclockwise around the semicircle $y = \sqrt{4 - x^2}$ from $(2, 0)$ to $(-2, 0)$

41. $\mathbf{F}(x, y, z) = x\mathbf{i} + y\mathbf{j} - 5z\mathbf{k}$

C: $\mathbf{r}(t) = 2\cos t\mathbf{i} + 2\sin t\mathbf{j} + t\mathbf{k},\quad 0 \le t \le 2\pi$



Figure for 41



Figure for 42

42. $\mathbf{F}(x, y, z) = yz\mathbf{i} + xz\mathbf{j} + xy\mathbf{k}$

C: line from $(0, 0, 0)$ to $(5, 3, 2)$

Work **In Exercises 43–46, determine whether the work done along the path C is positive, negative, or zero. Explain.**

43.



44.



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

45.



46.



Evaluating a Line Integral of a Vector Field

In Exercises 47 and 48, evaluate $\int_C \mathbf{F} \cdot d\mathbf{r}$ for each curve. Discuss the orientation of the curve and its effect on the value of the integral.

47. $\mathbf{F}(x, y) = x^2\mathbf{i} + xy\mathbf{j}$

(a) C_1: $\mathbf{r}_1(t) = 2t\mathbf{i} + (t - 1)\mathbf{j}, \quad 1 \le t \le 3$

(b) C_2: $\mathbf{r}_2(t) = 2(3 - t)\mathbf{i} + (2 - t)\mathbf{j}, \quad 0 \le t \le 2$

48. $\mathbf{F}(x, y) = x^2y\mathbf{i} + xy^{3/2}\mathbf{j}$

(a) C_1: $\mathbf{r}_1(t) = (t + 1)\mathbf{i} + t^2\mathbf{j}, \quad 0 \le t \le 2$

(b) C_2: $\mathbf{r}_2(t) = (1 + 2\cos t)\mathbf{i} + (4\cos^2 t)\mathbf{j}, \quad 0 \le t \le \pi/2$

Demonstrating a Property

In Exercises 49–52, demonstrate the property that $\int_C \mathbf{F} \cdot d\mathbf{r} = 0$ regardless of the initial and terminal points of C, where the tangent vector $\mathbf{r}'(t)$ is orthogonal to the force field $\mathbf{F}$.

49. $\mathbf{F}(x, y) = y\mathbf{i} - x\mathbf{j}$

C: $\mathbf{r}(t) = t\mathbf{i} - 2t\mathbf{j}$

50. $\mathbf{F}(x, y) = -3y\mathbf{i} + x\mathbf{j}$

C: $\mathbf{r}(t) = t\mathbf{i} - t^3\mathbf{j}$

51. $\mathbf{F}(x, y) = (x^3 - 2x^2)\mathbf{i} + \left(x - \frac{y}{2}\right)\mathbf{j}$

C: $\mathbf{r}(t) = t\mathbf{i} + t^2\mathbf{j}$

52. $\mathbf{F}(x, y) = x\mathbf{i} + y\mathbf{j}$

C: $\mathbf{r}(t) = 3\sin t\mathbf{i} + 3\cos t\mathbf{j}$

Evaluating a Line Integral in Differential Form

In Exercises 53–56, evaluate the line integral along the path C given by $x = 2t$, $y = 4t$, where $0 \le t \le 1$.

53. $\displaystyle\int_C (x + 3y^2)\, dy$

54. $\displaystyle\int_C (x^3 + 2y)\, dx$

55. $\displaystyle\int_C xy\, dx + y\, dy$

56. $\displaystyle\int_C (y - x)\, dx + 5x^2y^2\, dy$

Evaluating a Line Integral in Differential Form

In Exercises 57–64, evaluate

$$\int_C (2x - y)\, dx + (x + 3y)\, dy.$$

57. C: x-axis from $x = 0$ to $x = 5$

58. C: y-axis from $y = 0$ to $y = 2$

59. C: line segments from $(0, 0)$ to $(3, 0)$ and $(3, 0)$ to $(3, 3)$

60. C: line segments from $(0, 0)$ to $(0, -3)$ and $(0, -3)$ to $(2, -3)$

61. C: arc on $y = 1 - x^2$ from $(0, 1)$ to $(1, 0)$

62. C: arc on $y = x^{3/2}$ from $(0, 0)$ to $(4, 8)$

63. C: parabolic path $x = t$, $y = 2t^2$ from $(0, 0)$ to $(2, 8)$

64. C: elliptic path $x = 4\sin t$, $y = 3\cos t$ from $(0, 3)$ to $(4, 0)$

Lateral Surface Area

In Exercises 65–72, find the area of the lateral surface (see figure) over the curve C in the xy-plane and under the surface $z = f(x, y)$, where

$$\text{Lateral surface area} = \int_C f(x, y)\, ds.$$



C: Curve in xy-plane

65. $f(x, y) = h$, C: line from $(0, 0)$ to $(3, 4)$

66. $f(x, y) = y$, C: line from $(0, 0)$ to $(4, 4)$

67. $f(x, y) = xy$, C: $x^2 + y^2 = 1$ from $(1, 0)$ to $(0, 1)$

68. $f(x, y) = x + y$, C: $x^2 + y^2 = 1$ from $(1, 0)$ to $(0, 1)$

69. $f(x, y) = h$, C: $y = 1 - x^2$ from $(1, 0)$ to $(0, 1)$

70. $f(x, y) = y + 1$, C: $y = 1 - x^2$ from $(1, 0)$ to $(0, 1)$

71. $f(x, y) = xy$, C: $y = 1 - x^2$ from $(1, 0)$ to $(0, 1)$

72. $f(x, y) = x^2 - y^2 + 4$, C: $x^2 + y^2 = 4$

73. Engine Design A tractor engine has a steel component with a circular base modeled by the vector-valued function

$$\mathbf{r}(t) = 2\cos t\mathbf{i} + 2\sin t\mathbf{j}.$$

Its height is given by $z = 1 + y^2$. (All measurements of the component are in centimeters.)

(a) Find the lateral surface area of the component.

(b) The component is in the form of a shell of thickness 0.2 centimeter. Use the result of part (a) to approximate the amount of steel used to manufacture the component.

(c) Draw a sketch of the component.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

74. Building Design

The ceiling of a building has a height above the floor given by $z = 20 + \frac{1}{4}x$. One of the walls follows a path modeled by $y = x^{3/2}$. Find the surface area of the wall for $0 \le x \le 40$. (All measurements are in feet.)

Moments of Inertia **Consider a wire of density $\rho(x, y)$ given by the space curve**

$$C\text{: } \mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j}, \quad 0 \le t \le b.$$

The moments of inertia about the x- and y-axes are given by

$$I_x = \int_C y^2\rho(x, y)\,ds \quad \text{and} \quad I_y = \int_C x^2\rho(x, y)\,ds.$$

In Exercises 75 and 76, find the moments of inertia for the wire of density ρ.

75. A wire lies along $\mathbf{r}(t) = a\cos t\mathbf{i} + a\sin t\mathbf{j}$, where $0 \le t \le 2\pi$ and $a > 0$, with density $\rho(x, y) = 1$.

76. A wire lies along $\mathbf{r}(t) = a\cos t\mathbf{i} + a\sin t\mathbf{j}$, where $0 \le t \le 2\pi$ and $a > 0$, with density $\rho(x, y) = y$.

77. Investigation The top outer edge of a solid with vertical sides that is resting on the xy-plane is modeled by $\mathbf{r}(t) = 3\cos t\mathbf{i} + 3\sin t\mathbf{j} + (1 + \sin^2 2t)\mathbf{k}$, where all measurements are in centimeters. The intersection of the plane $y = b$, where $-3 < b < 3$, with the top of the solid is a horizontal line.

(a) Use a graphing utility to graph the solid.

(b) Use a graphing utility to approximate the lateral surface area of the solid.

(c) Find (if possible) the volume of the solid.

78. Work A particle moves along the path $y = x^2$ from the point $(0, 0)$ to the point $(1, 1)$. The force field $\mathbf{F}$ is measured at five points along the path, and the results are shown in the table. Use Simpson's Rule or a graphing utility to approximate the work done by the force field.

(x, y)	$(0, 0)$	$\left(\frac{1}{4}, \frac{1}{16}\right)$	$\left(\frac{1}{2}, \frac{1}{4}\right)$	$\left(\frac{3}{4}, \frac{9}{16}\right)$	$(1, 1)$
$\mathbf{F}(x, y)$	$\langle 5, 0\rangle$	$\langle 3.5, 1\rangle$	$\langle 2, 2\rangle$	$\langle 1.5, 3\rangle$	$\langle 1, 5\rangle$

79. Work Find the work done by a person weighing 175 pounds walking exactly one revolution up a circular helical staircase of radius 3 feet when the person rises 10 feet.

80. Investigation Determine the value of c such that the work done by the force field $\mathbf{F}(x, y) = 15[(4 - x^2y)\mathbf{i} - xy\mathbf{j}]$ on an object moving along the parabolic path $y = c(1 - x^2)$ between the points $(-1, 0)$ and $(1, 0)$ is a minimum. Compare the result with the work required to move the object along the straight-line path connecting the points.

Exploring Concepts

81. A path C is given by $x = t$, $y = 2t$, where $0 \le t \le 1$. Are $\int_C (x + y)\,dx$ and $\int_C (x + y)\,dy$ equivalent? Explain.

82. Let $\mathbf{F}(x, y) = 2x\mathbf{i} + xy^2\mathbf{j}$ and consider the curve $y = x^2$ from $(0, 0)$ to $(2, 4)$ in the xy-plane. Set up and evaluate line integrals of the forms $\int_C \mathbf{F} \cdot d\mathbf{r}$ and $\int_C M\,dx + N\,dy$. Compare your results. Which method do you prefer? Explain.

83. Order the surfaces in ascending order of the lateral surface area under the surface and over the curve $y = \sqrt{x}$ from $(0, 0)$ to $(4, 2)$ in the xy-plane. Explain your ordering without doing any calculations.

(a) $z_1 = 2 + x$ (b) $z_2 = 5 + x$

(c) $z_3 = 2$ (d) $z_4 = 10 + x + 2y$

84. HOW DO YOU SEE IT? For each of the following, determine whether the work done in moving an object from the first to the second point through the force field shown in the figure is positive, negative, or zero. Explain your answer. (In the figure, the circles have radii 1, 2, 3, 4, 5, and 6.)



(a) From $(-3, -3)$ to $(3, 3)$

(b) From $(-3, 0)$ to $(0, 3)$

(c) From $(5, 0)$ to $(0, 3)$

True or False? **In Exercises 85 and 86, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

85. If C is given by $x = t$, $y = t$, where $0 \le t \le 1$, then

$$\int_C xy\,ds = \int_0^1 t^2\,dt.$$

86. If $C_2 = -C_1$, then $\int_{C_1} f(x, y)\,ds + \int_{C_2} f(x, y)\,ds = 0$.

87. Work Consider a particle that moves through the force field

$$\mathbf{F}(x, y) = (y - x)\mathbf{i} + xy\mathbf{j}$$

from the point $(0, 0)$ to the point $(0, 1)$ along the curve $x = kt(1 - t)$, $y = t$. Find the value of k such that the work done by the force field is 1.

nui7711/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

15.3 Conservative Vector Fields and Independence of Path

GO DIGITAL

- Define the Fundamental Theorem of Line Integrals.
- Describe the concept of independence of path.
- Describe the concept of conservation of energy.

Fundamental Theorem of Line Integrals

The discussion at the beginning of Section 15.2 pointed out that in a gravitational field, the work done by gravity on an object moving between two points in the field is independent of the path taken by the object. In this section, you will study an important generalization of this result—it is called the **Fundamental Theorem of Line Integrals.** To begin, an example is presented in which the line integral of a *conservative vector field* is evaluated over three different paths.

EXAMPLE 1 **Line Integral of a Conservative Vector Field**

Find the work done by the force field

$$\mathbf{F}(x, y) = \frac{1}{2}xy\mathbf{i} + \frac{1}{4}x^2\mathbf{j}$$

on a particle that moves from $(0, 0)$ to $(1, 1)$ along each path, as shown in Figure 15.19.

a. C_1: $y = x$ **b.** C_2: $x = y^2$ **c.** C_3: $y = x^3$

Solution Note that $\mathbf{F}$ is conservative because the first partial derivatives are equal.

$$\frac{\partial}{\partial y}\left[\frac{1}{2}xy\right] = \frac{1}{2}x \quad \text{and} \quad \frac{\partial}{\partial x}\left[\frac{1}{4}x^2\right] = \frac{1}{2}x$$

a. Let $\mathbf{r}(t) = t\mathbf{i} + t\mathbf{j}$ for $0 \le t \le 1$, so that

$$d\mathbf{r} = (\mathbf{i} + \mathbf{j})\,dt \quad \text{and} \quad \mathbf{F}(x, y) = \frac{1}{2}t^2\mathbf{i} + \frac{1}{4}t^2\mathbf{j}.$$

Then the work done is

$$W = \int_{C_1} \mathbf{F} \cdot d\mathbf{r} = \int_0^1 \frac{3}{4}t^2\,dt = \frac{1}{4}t^3\Big]_0^1 = \frac{1}{4}.$$

b. Let $\mathbf{r}(t) = t\mathbf{i} + \sqrt{t}\mathbf{j}$ for $0 \le t \le 1$, so that

$$d\mathbf{r} = \left(\mathbf{i} + \frac{1}{2\sqrt{t}}\mathbf{j}\right)dt \quad \text{and} \quad \mathbf{F}(x, y) = \frac{1}{2}t^{3/2}\mathbf{i} + \frac{1}{4}t^2\mathbf{j}.$$

Then the work done is

$$W = \int_{C_2} \mathbf{F} \cdot d\mathbf{r} = \int_0^1 \frac{5}{8}t^{3/2}\,dt = \frac{1}{4}t^{5/2}\Big]_0^1 = \frac{1}{4}.$$

c. Let $\mathbf{r}(t) = \frac{1}{2}t\mathbf{i} + \frac{1}{8}t^3\mathbf{j}$ for $0 \le t \le 2$, so that

$$d\mathbf{r} = \left(\frac{1}{2}\mathbf{i} + \frac{3}{8}t^2\mathbf{j}\right)dt \quad \text{and} \quad \mathbf{F}(x, y) = \frac{1}{32}t^4\mathbf{i} + \frac{1}{16}t^2\mathbf{j}.$$

Then the work done is

$$W = \int_{C_3} \mathbf{F} \cdot d\mathbf{r} = \int_0^2 \frac{5}{128}t^4\,dt = \frac{1}{128}t^5\Big]_0^2 = \frac{1}{4}.$$

So, the work done by the conservative vector field $\mathbf{F}$ is the same for each path. ■



(a)



(b)



(c)

Figure 15.19

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

In Example 1, note that the vector field $\mathbf{F}(x, y) = \frac{1}{2}xy\mathbf{i} + \frac{1}{4}x^2\mathbf{j}$ is conservative because $\mathbf{F}(x, y) = \nabla f(x, y)$, where $f(x, y) = \frac{1}{4}x^2y$. In such cases, the next theorem states that the value of $\int_C \mathbf{F} \cdot d\mathbf{r}$ is given by

$$\begin{aligned}\int_C \mathbf{F} \cdot d\mathbf{r} &= f(x(1), y(1)) - f(x(0), y(0)) \\ &= \frac{1}{4} - 0 \\ &= \frac{1}{4}.\end{aligned}$$

REMARK Notice how the Fundamental Theorem of Line Integrals is similar to the Fundamental Theorem of Calculus (see Section 4.4), which states that

$$\int_a^b f(x)\,dx = F(b) - F(a)$$

where $F'(x) = f(x)$.

THEOREM 15.5 Fundamental Theorem of Line Integrals

Let C be a piecewise smooth curve lying in an open region R and given by

$$\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j}, \quad a \le t \le b.$$

If $\mathbf{F}(x, y) = M\mathbf{i} + N\mathbf{j}$ is conservative in R, and M and N are continuous in R, then

$$\int_C \mathbf{F} \cdot d\mathbf{r} = \int_C \nabla f \cdot d\mathbf{r} = f(x(b), y(b)) - f(x(a), y(a))$$

where f is a potential function of $\mathbf{F}$. That is, $\mathbf{F}(x, y) = \nabla f(x, y)$.

Proof A proof is provided only for a smooth curve. For piecewise smooth curves, the procedure is carried out separately on each smooth portion. Because

$$\mathbf{F}(x, y) = \nabla f(x, y) = f_x(x, y)\mathbf{i} + f_y(x, y)\mathbf{j}$$

it follows that

$$\begin{aligned}\int_C \mathbf{F} \cdot d\mathbf{r} &= \int_a^b \mathbf{F} \cdot \frac{d\mathbf{r}}{dt}\,dt \\ &= \int_a^b \left[f_x(x, y)\frac{dx}{dt} + f_y(x, y)\frac{dy}{dt}\right] dt\end{aligned}$$

and, by the Chain Rule (see Theorem 13.6 in Section 13.5), you have

$$\begin{aligned}\int_C \mathbf{F} \cdot d\mathbf{r} &= \int_a^b \frac{d}{dt}[f(x(t), y(t))]\,dt \\ &= f(x(b), y(b)) - f(x(a), y(a)).\end{aligned}$$

The last step is an application of the Fundamental Theorem of Calculus. ■

In space, the Fundamental Theorem of Line Integrals takes the following form. Let C be a piecewise smooth curve lying in an open region Q and given by

$$\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j} + z(t)\mathbf{k}, \quad a \le t \le b.$$

If $\mathbf{F}(x, y, z) = M\mathbf{i} + N\mathbf{j} + P\mathbf{k}$ is conservative, and M, N, and P are continuous, then

$$\int_C \mathbf{F} \cdot d\mathbf{r} = \int_C \nabla f \cdot d\mathbf{r} = f(x(b), y(b), z(b)) - f(x(a), y(a), z(a))$$

where $\mathbf{F}(x, y, z) = \nabla f(x, y, z)$.

The Fundamental Theorem of Line Integrals states that if the vector field $\mathbf{F}$ is conservative, then the line integral between any two points is simply the difference in the values of the *potential* function f at these points.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 15.20

EXAMPLE 2 Using the Fundamental Theorem of Line Integrals

Evaluate $\int_C \mathbf{F} \cdot d\mathbf{r}$, where C is a piecewise smooth curve from $(-1, 4)$ to $(1, 2)$ and

$$\mathbf{F}(x, y) = 2xy\mathbf{i} + (x^2 - y)\mathbf{j}$$

as shown in Figure 15.20.

Solution From Example 6 in Section 15.1, you know that $\mathbf{F}$ is the gradient of f, where

$$f(x, y) = x^2y - \frac{y^2}{2} + K.$$

Consequently, $\mathbf{F}$ is conservative, and by the Fundamental Theorem of Line Integrals, it follows that

$$\begin{aligned}\int_C \mathbf{F} \cdot d\mathbf{r} &= f(1, 2) - f(-1, 4) \\ &= \left[1^2(2) - \frac{2^2}{2}\right] - \left[(-1)^2(4) - \frac{4^2}{2}\right] \\ &= 4.\end{aligned}$$

Note that it is unnecessary to include a constant K as part of f, because it is canceled by subtraction.



Figure 15.21

EXAMPLE 3 Using the Fundamental Theorem of Line Integrals

Evaluate $\int_C \mathbf{F} \cdot d\mathbf{r}$, where C is a piecewise smooth curve from $(1, 1, 0)$ to $(0, 2, 3)$ and

$$\mathbf{F}(x, y, z) = 2xy\mathbf{i} + (x^2 + z^2)\mathbf{j} + 2yz\mathbf{k}$$

as shown in Figure 15.21.

Solution From Example 8 in Section 15.1, you know that $\mathbf{F}$ is the gradient of f, where

$$f(x, y, z) = x^2y + yz^2 + K.$$

Consequently, $\mathbf{F}$ is conservative, and by the Fundamental Theorem of Line Integrals, it follows that

$$\begin{aligned}\int_C \mathbf{F} \cdot d\mathbf{r} &= f(0, 2, 3) - f(1, 1, 0) \\ &= [(0)^2(2) + (2)(3)^2] - [(1)^2(1) + (1)(0)^2] \\ &= 17.\end{aligned}$$

In Examples 2 and 3, be sure you see that the value of the line integral is the same for any smooth curve C that has the given initial and terminal points. For instance, in Example 3, evaluate the line integral for the curve given by

$$\mathbf{r}(t) = (1 - t)\mathbf{i} + (1 + t)\mathbf{j} + 3t\mathbf{k}.$$

You should obtain

$$\begin{aligned}\int_C \mathbf{F} \cdot d\mathbf{r} &= \int_0^1 (30t^2 + 16t - 1)\, dt \\ &= 17.\end{aligned}$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



R_1 is connected. R_2 is not connected.

Figure 15.22

Independence of Path

From the Fundamental Theorem of Line Integrals, it is clear that if $\mathbf{F}$ is continuous and conservative in an open region R, then the value of $\int_C \mathbf{F} \cdot d\mathbf{r}$ is the same for every piecewise smooth curve C from one fixed point in R to another fixed point in R. This result is described by saying that the line integral $\int_C \mathbf{F} \cdot d\mathbf{r}$ is **independent of path** in the region R.

A region in the plane (or in space) is **connected** when any two points in the region can be joined by a piecewise smooth curve lying entirely within the region, as shown in Figure 15.22. In open regions that are *connected,* the path independence of $\int_C \mathbf{F} \cdot d\mathbf{r}$ is equivalent to the condition that $\mathbf{F}$ is conservative.

THEOREM 15.6 Independence of Path and Conservative Vector Fields

If $\mathbf{F}$ is continuous on an open connected region, then the line integral

$$\int_C \mathbf{F} \cdot d\mathbf{r}$$

is independent of path if and only if $\mathbf{F}$ is conservative.



Figure 15.23

Proof If $\mathbf{F}$ is conservative, then, by the Fundamental Theorem of Line Integrals, the line integral is independent of path. Now establish the converse for a plane region R. Let $\mathbf{F}(x, y) = M\mathbf{i} + N\mathbf{j}$, and let (x_0, y_0) be a fixed point in R. For any point (x, y) in R, choose a piecewise smooth curve C running from (x_0, y_0) to (x, y), and define f by

$$\begin{aligned} f(x, y) &= \int_C \mathbf{F} \cdot d\mathbf{r} \\ &= \int_C M\,dx + N\,dy. \end{aligned}$$

The existence of C in R is guaranteed by the fact that R is connected. You can show that f is a potential function of $\mathbf{F}$ by considering two different paths between (x_0, y_0) and (x, y). For the *first* path, choose (x_1, y) in R such that $x \neq x_1$. This is possible because R is open. Then choose C_1 and C_2, as shown in Figure 15.23. Using the independence of path, it follows that

$$\begin{aligned} f(x, y) &= \int_C M\,dx + N\,dy \\ &= \int_{C_1} M\,dx + N\,dy + \int_{C_2} M\,dx + N\,dy. \end{aligned}$$

Because the first integral does not depend on x and because $dy = 0$ in the second integral, you have

$$f(x, y) = g(y) + \int_{C_2} M\,dx$$

and it follows that the partial derivative of f with respect to x is $f_x(x, y) = M$. For the *second* path, choose a point (x, y_1). Using reasoning similar to that used for the first path, you can conclude that $f_y(x, y) = N$. Therefore,

$$\begin{aligned} \nabla f(x, y) &= f_x(x, y)\mathbf{i} + f_y(x, y)\mathbf{j} \\ &= M\mathbf{i} + N\mathbf{j} \\ &= \mathbf{F}(x, y) \end{aligned}$$

and it follows that $\mathbf{F}$ is conservative. ∎

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

EXAMPLE 4 **Finding Work in a Conservative Force Field**

For the force field given by

$$\mathbf{F}(x, y, z) = e^x \cos y\mathbf{i} - e^x \sin y\mathbf{j} + 2\mathbf{k}$$

show that $\int_C \mathbf{F} \cdot d\mathbf{r}$ is independent of path, and calculate the work done by $\mathbf{F}$ on an object moving along a curve C from $(0, \pi/2, 1)$ to $(1, \pi, 3)$.

Solution Writing the force field in the form $\mathbf{F}(x, y, z) = M\mathbf{i} + N\mathbf{j} + P\mathbf{k}$, you have $M = e^x \cos y$, $N = -e^x \sin y$, and $P = 2$, and it follows that

$$\frac{\partial P}{\partial y} = 0 = \frac{\partial N}{\partial z}$$
$$\frac{\partial P}{\partial x} = 0 = \frac{\partial M}{\partial z}$$

and

$$\frac{\partial N}{\partial x} = -e^x \sin y = \frac{\partial M}{\partial y}.$$

So, $\mathbf{F}$ is conservative. If f is a potential function of $\mathbf{F}$, then

$$f_x(x, y, z) = e^x \cos y$$
$$f_y(x, y, z) = -e^x \sin y$$

and

$$f_z(x, y, z) = 2.$$

By integrating with respect to x, y, and z separately, you obtain

$$f(x, y, z) = \int f_x(x, y, z)\, dx = \int e^x \cos y\, dx = e^x \cos y + g(y, z)$$
$$f(x, y, z) = \int f_y(x, y, z)\, dy = \int -e^x \sin y\, dy = e^x \cos y + h(x, z)$$

and

$$f(x, y, z) = \int f_z(x, y, z)\, dz = \int 2\, dz = 2z + k(x, y).$$

By comparing these three versions of $f(x, y, z)$, you can conclude that

$$f(x, y, z) = e^x \cos y + 2z + K.$$

Therefore, the work done by $\mathbf{F}$ along *any* curve C from $(0, \pi/2, 1)$ to $(1, \pi, 3)$ is

$$\begin{aligned} W &= \int_C \mathbf{F} \cdot d\mathbf{r} \\ &= f(1, \pi, 3) - f\left(0, \frac{\pi}{2}, 1\right) \\ &= (-e + 6) - (0 + 2) \\ &= 4 - e. \end{aligned}$$

For the object in Example 4, how much work is done when the object moves on a curve from $(0, \pi/2, 1)$ to $(1, \pi, 3)$ and then back to the starting point $(0, \pi/2, 1)$? The Fundamental Theorem of Line Integrals states that there is zero work done. Remember that, by definition, work can be negative. So, by the time the object gets back to its starting point, the amount of work that registers positively is canceled out by the amount of work that registers negatively.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

A curve C given by $\mathbf{r}(t)$ for $a \le t \le b$ is **closed** when $\mathbf{r}(a) = \mathbf{r}(b)$. By the Fundamental Theorem of Line Integrals, you can conclude that if $\mathbf{F}$ is continuous and conservative on an open region R, then the line integral over every closed curve C is 0.

REMARK Theorem 15.7 gives you options for evaluating a line integral involving a conservative vector field. You can use a potential function, or it might be more convenient to choose a particularly simple path, such as a straight line.

THEOREM 15.7 Equivalent Conditions

Let $\mathbf{F}(x, y, z) = M\mathbf{i} + N\mathbf{j} + P\mathbf{k}$ have continuous first partial derivatives in an open connected region R, and let C be a piecewise smooth curve in R. The conditions listed below are equivalent.

1. $\mathbf{F}$ is conservative. That is, $\mathbf{F} = \nabla f$ for some function f.
2. $\int_C \mathbf{F} \cdot d\mathbf{r}$ is independent of path.
3. $\int_C \mathbf{F} \cdot d\mathbf{r} = 0$ for every *closed* curve C in R.

EXAMPLE 5 Evaluating a Line Integral

See LarsonCalculus.com for an interactive version of this type of example.



Figure 15.24

Evaluate $\int_{C_1} \mathbf{F} \cdot d\mathbf{r}$, where

$$\mathbf{F}(x, y) = (y^3 + 1)\mathbf{i} + (3xy^2 + 1)\mathbf{j}$$

and C_1 is the semicircular path from $(0, 0)$ to $(2, 0)$, as shown in Figure 15.24.

Solution You have the following three options.

a. You can use the method presented in Section 15.2 to evaluate the line integral along the *given curve.* To do this, you can use the parametrization $\mathbf{r}(t) = (1 - \cos t)\mathbf{i} + \sin t\mathbf{j}$, where $0 \le t \le \pi$. For this parametrization, it follows that

$$d\mathbf{r} = \mathbf{r}'(t)\,dt = (\sin t\mathbf{i} + \cos t\mathbf{j})\,dt$$

and

$$\int_{C_1} \mathbf{F} \cdot d\mathbf{r} = \int_0^{\pi} (\sin t + \sin^4 t + \cos t + 3\sin^2 t \cos t - 3\sin^2 t \cos^2 t)\,dt.$$

This integral should discourage you from using this option.

b. You can try to find a *potential function* and evaluate the line integral by the Fundamental Theorem of Line Integrals. Using the technique demonstrated in Example 4, you can find the potential function to be $f(x, y) = xy^3 + x + y + K$, and, by the Fundamental Theorem,

$$W = \int_{C_1} \mathbf{F} \cdot d\mathbf{r} = f(2, 0) - f(0, 0) = 2.$$

c. Knowing that $\mathbf{F}$ is conservative, you have a third option. Because the value of the line integral is independent of path, you can replace the semicircular path with a *simpler path.* Choose the straight-line path C_2 from $(0, 0)$ to $(2, 0)$. Let $\mathbf{r}(t) = t\mathbf{i}$ for $0 \le t \le 2$, so that

$$d\mathbf{r} = \mathbf{i}\,dt \quad \text{and} \quad \mathbf{F}(x, y) = \mathbf{i} + \mathbf{j}.$$

Then the integral is

$$\int_{C_1} \mathbf{F} \cdot d\mathbf{r} = \int_{C_2} \mathbf{F} \cdot d\mathbf{r} = \int_0^2 1\,dt = t\Big]_0^2 = 2.$$

Of the three options, the third one is obviously the easiest. ■

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Conservation of Energy

MICHAEL FARADAY (1791–1867)

Several philosophers of science have considered Faraday's Law of Conservation of Energy to be the greatest generalization ever conceived by humankind. Many physicists have contributed to our knowledge of this law. Two early and influential ones were James Prescott Joule (1818–1889) and Hermann Ludwig Helmholtz (1821–1894).

In 1840, the English physicist Michael Faraday wrote, "Nowhere is there a pure creation or production of power without a corresponding exhaustion of something to supply it." This statement represents the first formulation of one of the most important laws of physics—the **Law of Conservation of Energy.** In modern terminology, the law is stated as follows: *In a conservative force field, the sum of the potential and kinetic energies of an object remains constant from point to point.*

You can use the Fundamental Theorem of Line Integrals to derive this law. From physics, the **kinetic energy** of a particle of mass m and speed v is

$$k = \frac{1}{2}mv^2. \qquad \text{Kinetic energy}$$

The **potential energy** p of a particle at point (x, y, z) in a conservative vector field $\mathbf{F}$ is defined as $p(x, y, z) = -f(x, y, z)$, where f is the potential function for $\mathbf{F}$. Consequently, the work done by $\mathbf{F}$ along a smooth curve C from A to B is

$$W = \int_C \mathbf{F} \cdot d\mathbf{r} = f(x, y, z)\Big]_A^B = -p(x, y, z)\Big]_A^B = p(A) - p(B)$$

as shown in Figure 15.25. In other words, work W is equal to the difference in the potential energies of A and B. Now, suppose that $\mathbf{r}(t)$ is the position vector for a particle moving along C from $A = \mathbf{r}(a)$ to $B = \mathbf{r}(b)$. At any time t, the particle's velocity, acceleration, and speed are $\mathbf{v}(t) = \mathbf{r}'(t)$, $\mathbf{a}(t) = \mathbf{r}''(t)$, and $v(t) = \|\mathbf{v}(t)\|$, respectively. So, by Newton's Second Law of Motion, $\mathbf{F} = m\mathbf{a}(t) = m(\mathbf{v}'(t))$, and the work done by $\mathbf{F}$ is

$$\begin{aligned}
W &= \int_C \mathbf{F} \cdot d\mathbf{r} \\
&= \int_a^b \mathbf{F} \cdot \mathbf{r}'(t)\, dt \\
&= \int_a^b \mathbf{F} \cdot \mathbf{v}(t)\, dt \\
&= \int_a^b [m\mathbf{v}'(t)] \cdot \mathbf{v}(t)\, dt \\
&= \int_a^b m[\mathbf{v}'(t) \cdot \mathbf{v}(t)]\, dt \\
&= \frac{m}{2}\int_a^b \frac{d}{dt}[\mathbf{v}(t) \cdot \mathbf{v}(t)]\, dt \\
&= \frac{m}{2}\int_a^b \frac{d}{dt}[\|\mathbf{v}(t)\|^2]\, dt \\
&= \frac{m}{2}\Big[\|\mathbf{v}(t)\|^2\Big]_a^b \\
&= \frac{m}{2}\Big[[v(t)]^2\Big]_a^b \\
&= \frac{1}{2}m[v(b)]^2 - \frac{1}{2}m[v(a)]^2 \\
&= k(B) - k(A).
\end{aligned}$$

Equating these two results for W produces

$$\begin{aligned}
p(A) - p(B) &= k(B) - k(A) \\
p(A) + k(A) &= p(B) + k(B)
\end{aligned}$$

which implies that the sum of the potential and kinetic energies remains constant from point to point.

GO DIGITAL



The work done by $\mathbf{F}$ along C is

$$W = \int_C \mathbf{F} \cdot d\mathbf{r} = p(A) - p(B).$$

Figure 15.25

Pictorial Press Ltd/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

15.3 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain how to evaluate a line integral using the Fundamental Theorem of Line Integrals.
2. Explain what it means for a line integral to be independent of path. State the method for determining whether a line integral is independent of path.

Line Integral of a Conservative Vector Field

In Exercises 3–8, (a) show that F is conservative and (b) verify that the value of

$$\int_C \mathbf{F} \cdot d\mathbf{r}$$

is the same for each parametric representation of C.

3. $\mathbf{F}(x, y) = x^2\mathbf{i} + y\mathbf{j}$
   (i) C_1: $\mathbf{r}_1(t) = t\mathbf{i} + t^2\mathbf{j}, \quad 0 \le t \le 1$
   (ii) C_2: $\mathbf{r}_2(\theta) = \sin\theta\mathbf{i} + \sin^2\theta\mathbf{j}, \quad 0 \le \theta \le \pi/2$
4. $\mathbf{F}(x, y) = (x^2 - y^2)\mathbf{i} - 2xy\mathbf{j}$
   (i) C_1: $\mathbf{r}_1(t) = t\mathbf{i} + \sqrt{t}\mathbf{j}, \quad 0 \le t \le 4$
   (ii) C_2: $\mathbf{r}_2(w) = w^2\mathbf{i} + w\mathbf{j}, \quad 0 \le w \le 2$
5. $\mathbf{F}(x, y) = 3y\mathbf{i} + 3x\mathbf{j}$
   (i) C_1: $\mathbf{r}_1(\theta) = \sec\theta\mathbf{i} + \tan\theta\mathbf{j}, \quad 0 \le \theta \le \pi/3$
   (ii) C_2: $\mathbf{r}_2(t) = \sqrt{t+1}\mathbf{i} + \sqrt{t}\mathbf{j}, \quad 0 \le t \le 3$
6. $\mathbf{F}(x, y) = y\mathbf{i} + x\mathbf{j}$
   (i) C_1: $\mathbf{r}_1(t) = (2 + t)\mathbf{i} + (3 - t)\mathbf{j}, \quad 0 \le t \le 1$
   (ii) C_2: $\mathbf{r}_2(w) = (2 + \ln w)\mathbf{i} + (3 - \ln w)\mathbf{j}, \quad 1 \le w \le e$
7. $\mathbf{F}(x, y, z) = y^2z\mathbf{i} + 2xyz\mathbf{j} + xy^2\mathbf{k}$
   (i) C_1: $\mathbf{r}_1(t) = t\mathbf{i} + 2t\mathbf{j} + 4t\mathbf{k}, \quad 0 \le t \le 1$
   (ii) C_2: $\mathbf{r}_2(\theta) = \sin\theta\mathbf{i} + 2\sin\theta\mathbf{j} + 4\sin\theta\mathbf{k}, \quad 0 \le \theta \le \pi/2$
8. $\mathbf{F}(x, y, z) = 2yz\mathbf{i} + 2xz\mathbf{j} + 2xy\mathbf{k}$
   (i) C_1: $\mathbf{r}_1(t) = t\mathbf{i} - 4t\mathbf{j} + t^2\mathbf{k}, \quad 0 \le t \le 3$
   (ii) C_2: $\mathbf{r}_2(s) = s^2\mathbf{i} - \frac{4}{3}s^4\mathbf{j} + s^4\mathbf{k}, \quad 0 \le s \le \sqrt{3}$

Using the Fundamental Theorem of Line Integrals

In Exercises 9–18, evaluate

$$\int_C \mathbf{F} \cdot d\mathbf{r}$$

using the Fundamental Theorem of Line Integrals. Use a graphing utility to verify your results.

9. $\mathbf{F}(x, y) = 3y\mathbf{i} + 3x\mathbf{j}$
   C: smooth curve from $(0, 0)$ to $(3, 8)$
10. $\mathbf{F}(x, y) = 2(x + y)\mathbf{i} + 2(x + y)\mathbf{j}$
    C: smooth curve from $(-1, 1)$ to $(3, 2)$
11. $\mathbf{F}(x, y) = \cos x \sin y\mathbf{i} + \sin x \cos y\mathbf{j}$
    C: line segment from $(0, -\pi)$ to $\left(\frac{3\pi}{2}, \frac{\pi}{2}\right)$
12. $\mathbf{F}(x, y) = \frac{y}{x^2 + y^2}\mathbf{i} - \frac{x}{x^2 + y^2}\mathbf{j}$
    C: line segment from $(1, 1)$ to $\left(2\sqrt{3}, 2\right)$
13. $\mathbf{F}(x, y) = e^x \sin y\mathbf{i} + e^x \cos y\mathbf{j}$
    C: cycloid $x = \theta - \sin\theta, y = 1 - \cos\theta$ from $(0, 0)$ to $(2\pi, 0)$
14. $\mathbf{F}(x, y) = \frac{2x}{(x^2 + y^2)^2}\mathbf{i} + \frac{2y}{(x^2 + y^2)^2}\mathbf{j}$
    C: clockwise around the circle $(x - 4)^2 + (y - 5)^2 = 9$ from $(7, 5)$ to $(1, 5)$
15. $\mathbf{F}(x, y, z) = (z + 2y)\mathbf{i} + (2x - z)\mathbf{j} + (x - y)\mathbf{k}$
    (a) C_1: line segment from $(0, 0, 0)$ to $(1, 1, 1)$
    (b) C_2: line segments from $(0, 0, 0)$ to $(0, 0, 1)$ and $(0, 0, 1)$ to $(1, 1, 1)$
    (c) C_3: line segments from $(0, 0, 0)$ to $(1, 0, 0)$, from $(1, 0, 0)$ to $(1, 1, 0)$, and from $(1, 1, 0)$ to $(1, 1, 1)$
16. Repeat Exercise 15 using
    $\mathbf{F}(x, y, z) = zy\mathbf{i} + xz\mathbf{j} + xy\mathbf{k}$.
17. $\mathbf{F}(x, y, z) = -\sin x\mathbf{i} + z\mathbf{j} + y\mathbf{k}$
    C: smooth curve from $(0, 0, 0)$ to $\left(\frac{\pi}{2}, 3, 4\right)$
18. $\mathbf{F}(x, y, z) = 6x\mathbf{i} - 4z\mathbf{j} - (4y - 20z)\mathbf{k}$
    C: smooth curve from $(0, 0, 0)$ to $(3, 4, 0)$

Finding Work in a Conservative Force Field

In Exercises 19–22, (a) show that

$$\int_C \mathbf{F} \cdot d\mathbf{r}$$

is independent of path and (b) calculate the work done by the force field F on an object moving along a curve from P to Q.

19. $\mathbf{F}(x, y) = 9x^2y^2\mathbf{i} + (6x^3y - 1)\mathbf{j}$
    $P(0, 0), Q(5, 9)$
20. $\mathbf{F}(x, y) = \frac{2x}{y}\mathbf{i} - \frac{x^2}{y^2}\mathbf{j}$
    $P(-1, 1), Q(3, 2)$
21. $\mathbf{F}(x, y, z) = 3\mathbf{i} + 4y\mathbf{j} - \sin z\mathbf{k}$
    $P\left(0, 1, \frac{\pi}{2}\right), Q(1, 4, \pi)$
22. $\mathbf{F}(x, y, z) = 8x^3\mathbf{i} + z^2\cos 2y\mathbf{j} + z\sin 2y\mathbf{k}$
    $P\left(0, \frac{\pi}{4}, 1\right), Q(-2, 0, -1)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Evaluating a Line Integral

In Exercises 23–32, evaluate

$$\int_C \mathbf{F} \cdot d\mathbf{r}$$

along each path. (*Hint:* If F is conservative, the integration may be easier on an alternative path.)

23. $\mathbf{F}(x, y) = 2xy\mathbf{i} + x^2\mathbf{j}$

(a) C_1: $\mathbf{r}_1(t) = t\mathbf{i} + t^2\mathbf{j}, \quad 0 \le t \le 1$

(b) C_2: $\mathbf{r}_2(t) = t\mathbf{i} + t^3\mathbf{j}, \quad 0 \le t \le 1$

24. $\mathbf{F}(x, y) = ye^{xy}\mathbf{i} + xe^{xy}\mathbf{j}$

(a) C_1: $\mathbf{r}_1(t) = t\mathbf{i} - (t - 3)\mathbf{j}, \quad 0 \le t \le 3$

(b) C_2: The closed path consisting of line segments from $(0, 3)$ to $(0, 0)$, from $(0, 0)$ to $(3, 0)$, and then from $(3, 0)$ to $(0, 3)$

25. $\displaystyle\int_C y^2\,dx + 2xy\,dy$

(a)



(b)



(c)



(d)



26. $\displaystyle\int_C (2x - 3y + 1)\,dx - (3x + y - 5)\,dy$

(a)



(b)



(c)



(d)



27. $\mathbf{F}(x, y, z) = yz\mathbf{i} + xz\mathbf{j} + xy\mathbf{k}$

(a) C_1: $\mathbf{r}_1(t) = t\mathbf{i} + 2\mathbf{j} + t\mathbf{k}, \quad 0 \le t \le 4$

(b) C_2: $\mathbf{r}_2(t) = t^2\mathbf{i} + t\mathbf{j} + t^2\mathbf{k}, \quad 0 \le t \le 2$

28. $\mathbf{F}(x, y, z) = \mathbf{i} + z\mathbf{j} + y\mathbf{k}$

(a) C_1: $\mathbf{r}_1(t) = \cos t\mathbf{i} + \sin t\mathbf{j} + t^2\mathbf{k}, \quad 0 \le t \le \pi$

(b) C_2: $\mathbf{r}_2(t) = (1 - 2t)\mathbf{i} + \pi^2 t\mathbf{k}, \quad 0 \le t \le 1$

29. $\mathbf{F}(x, y, z) = (2y + x)\mathbf{i} + (x^2 - z)\mathbf{j} + (2y - 4z)\mathbf{k}$

(a) C_1: $\mathbf{r}_1(t) = t\mathbf{i} + t^2\mathbf{j} + \mathbf{k}, \quad 0 \le t \le 1$

(b) C_2: $\mathbf{r}_2(t) = t\mathbf{i} + t\mathbf{j} + (2t - 1)^2\mathbf{k}, \quad 0 \le t \le 1$

30. $\mathbf{F}(x, y, z) = -y\mathbf{i} + x\mathbf{j} + 3xz^2\mathbf{k}$

(a) C_1: $\mathbf{r}_1(t) = \cos t\mathbf{i} + \sin t\mathbf{j} + t\mathbf{k}, \quad 0 \le t \le \pi$

(b) C_2: $\mathbf{r}_2(t) = (1 - 2t)\mathbf{i} + \pi t\mathbf{k}, \quad 0 \le t \le 1$

31. $\mathbf{F}(x, y, z) = e^z(y\mathbf{i} + x\mathbf{j} + xy\mathbf{k})$

(a) C_1: $\mathbf{r}_1(t) = 4\cos t\mathbf{i} + 4\sin t\mathbf{j} + 3\mathbf{k}, \quad 0 \le t \le \pi$

(b) C_2: $\mathbf{r}_2(t) = (4 - 8t)\mathbf{i} + 3\mathbf{k}, \quad 0 \le t \le 1$

32. $\mathbf{F}(x, y, z) = y\sin z\mathbf{i} + x\sin z\mathbf{j} + xy\cos x\mathbf{k}$

(a) C_1: $\mathbf{r}_1(t) = t^2\mathbf{i} + t^2\mathbf{j}, \quad 0 \le t \le 2$

(b) C_2: $\mathbf{r}_2(t) = 4t\mathbf{i} + 4t\mathbf{j}, \quad 0 \le t \le 1$

33. Work A stone weighing 1 pound is attached to the end of a two-foot string and is whirled horizontally with one end held fixed. It makes 1 revolution per second. Find the work done by the force **F** that keeps the stone moving in a circular path. [*Hint:* Use Force = (mass)(centripetal acceleration).]

34. Work A grappling hook weighing 1 kilogram is attached to the end of a five-meter rope and is whirled horizontally with one end held fixed. It makes 0.5 revolution per second. Find the work done by the force **F** that keeps the grappling hook moving in a circular path. [*Hint:* Use Force = (mass)(centripetal acceleration).]

35. Work

A zip line is installed 50 feet above ground level. It runs to a point on the ground 50 feet away from the base of the installation. Show that the work done by the gravitational force field for a 175-pound person moving the length of the zip line is the same for each path.

(a) C_1: $\mathbf{r}_1(t) = t\mathbf{i} + (50 - t)\mathbf{j}$

(b) C_2: $\mathbf{r}_2(t) = t\mathbf{i} + \frac{1}{50}(50 - t)^2\mathbf{j}$

36. Work Can you find a path for the zip line in Exercise 35 such that the work done by the gravitational force field would differ from the amounts of work done for the two paths given? Explain why or why not.

Igor Tichonow/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploring Concepts

37. Consider

$$\mathbf{F}(x, y) = \frac{y}{x^2 + y^2}\mathbf{i} - \frac{x}{x^2 + y^2}\mathbf{j}.$$

Explain how Theorem 15.7 allows you to compute $\int_C \mathbf{F} \cdot d\mathbf{r}$ easily.



38. Let

$$\mathbf{F}(x, y, z) = a_1\mathbf{i} + a_2\mathbf{j} + a_3\mathbf{k}$$

be a constant force vector field. Show that the work done in moving a particle along any path from P to Q is $W = \mathbf{F} \cdot \overrightarrow{PQ}$.

39. Use two different methods to evaluate $\int_C \mathbf{F} \cdot d\mathbf{r}$ along the path

$$\mathbf{r}(t) = \frac{1}{t}\mathbf{i} + 3t\mathbf{j}, \quad 0.5 \le t \le 2$$

where $\mathbf{F}(x, y) = (x^2y^2 - 3x)\mathbf{i} + \frac{2}{3}x^3y\mathbf{j}$.

40. **HOW DO YOU SEE IT?** Consider the force field shown in the figure. To print an enlarged copy of the graph, go to *MathGraphs.com.*



(a) Give a verbal argument that the force field is not conservative because you can identify two paths that require different amounts of work to move an object from $(-4, 0)$ to $(3, 4)$. Of the two paths, which requires the greater amount of work?

(b) Give a verbal argument that the force field is not conservative because you can find a closed curve C such that $\int_C \mathbf{F} \cdot d\mathbf{r} \neq 0$.

Graphical Reasoning **In Exercises 41 and 42, consider the force field shown in the figure. Is the force field conservative? Explain why or why not.**

41.



42.



True or False? **In Exercises 43–46, determine whether the statement is true or false. If it is false, explain why or give an example that shows it is false.**

43. If C_1, C_2, and C_3 have the same initial and terminal points and $\int_{C_1} \mathbf{F} \cdot d\mathbf{r}_1 = \int_{C_2} \mathbf{F} \cdot d\mathbf{r}_2$, then $\int_{C_1} \mathbf{F} \cdot d\mathbf{r}_1 = \int_{C_3} \mathbf{F} \cdot d\mathbf{r}_3$.

44. If $\mathbf{F} = y\mathbf{i} + x\mathbf{j}$ and C is given by $\mathbf{r}(t) = 4 \sin t\mathbf{i} + 3 \cos t\mathbf{j}$ for $0 \le t \le \pi$, then

$$\int_C \mathbf{F} \cdot d\mathbf{r} = 0.$$

45. If $\mathbf{F}$ is conservative in a region R bounded by a simple closed path and C lies within R, then $\int_C \mathbf{F} \cdot d\mathbf{r}$ is independent of path.

46. If $\mathbf{F} = M\mathbf{i} + N\mathbf{j}$ and $\frac{\partial M}{\partial x} = \frac{\partial N}{\partial y}$, then $\mathbf{F}$ is conservative.

47. **Harmonic Function** A function f is called *harmonic* when

$$\frac{\partial^2 f}{\partial x^2} + \frac{\partial^2 f}{\partial y^2} = 0.$$

Prove that if f is harmonic, then

$$\int_C \left(\frac{\partial f}{\partial y}\,dx - \frac{\partial f}{\partial x}\,dy\right) = 0$$

where C is a smooth closed curve in the plane.

48. **Kinetic and Potential Energy** The kinetic energy of an object moving through a conservative force field is decreasing at a rate of 15 units per minute. At what rate is the potential energy changing? Explain.

49. **Investigation** Let $\mathbf{F}(x, y) = \frac{y}{x^2 + y^2}\mathbf{i} - \frac{x}{x^2 + y^2}\mathbf{j}$.

(a) Show that $\frac{\partial N}{\partial x} = \frac{\partial M}{\partial y}$.

(b) Let $\mathbf{r}(t) = \cos t\mathbf{i} + \sin t\mathbf{j}$ for $0 \le t \le \pi$. Find $\int_C \mathbf{F} \cdot d\mathbf{r}$.

(c) Let $\mathbf{r}(t) = \cos t\mathbf{i} - \sin t\mathbf{j}$ for $0 \le t \le \pi$. Find $\int_C \mathbf{F} \cdot d\mathbf{r}$.

(d) Let $\mathbf{r}(t) = \cos t\mathbf{i} + \sin t\mathbf{j}$ for $0 \le t \le 2\pi$. Find $\int_C \mathbf{F} \cdot d\mathbf{r}$.

(e) Do the results of parts (b)–(d) contradict Theorem 15.7? Why or why not?

(f) Show that $\nabla\left(\arctan\frac{x}{y}\right) = \mathbf{F}$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

15.4 Green's Theorem

GO DIGITAL

- **Use Green's Theorem to evaluate a line integral.**
- **Use alternative forms of Green's Theorem.**



Figure 15.26

Green's Theorem

In this section, you will study **Green's Theorem,** named after the English mathematician George Green (1793–1841). This theorem states that the value of a double integral over a *simply connected* plane region R is determined by the value of a line integral around the boundary of R.

A curve C given by $\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j}$, where $a \le t \le b$, is **simple** when it does not cross itself—that is, $\mathbf{r}(c) \neq \mathbf{r}(d)$ for all c and d in the open interval (a, b). A connected plane region R is **simply connected** when every simple closed curve in R encloses only points that are in R (see Figure 15.26). Informally, a simply connected region cannot consist of separate parts or holes.

THEOREM 15.8 Green's Theorem

Let R be a simply connected region with a piecewise smooth boundary C, oriented counterclockwise (that is, C is traversed *once* so that the region R always lies to the *left*). If M and N have continuous first partial derivatives in an open region containing R, then

$$\int_C M\,dx + N\,dy = \iint_R \left(\frac{\partial N}{\partial x} - \frac{\partial M}{\partial y}\right) dA.$$



R is vertically simple.



R is horizontally simple.

Figure 15.27

Proof A proof is given only for a region that is both vertically simple and horizontally simple, as shown in Figure 15.27.

$$\begin{aligned}\int_C M\,dx &= \int_{C_1} M\,dx + \int_{C_2} M\,dx \\ &= \int_a^b M(x, f_1(x))\,dx + \int_b^a M(x, f_2(x))\,dx \\ &= \int_a^b [M(x, f_1(x)) - M(x, f_2(x))]\,dx\end{aligned}$$

On the other hand,

$$\begin{aligned}\iint_R \frac{\partial M}{\partial y}\,dA &= \int_a^b \int_{f_1(x)}^{f_2(x)} \frac{\partial M}{\partial y}\,dy\,dx \\ &= \int_a^b M(x, y)\Big]_{f_1(x)}^{f_2(x)}\,dx \\ &= \int_a^b [M(x, f_2(x)) - M(x, f_1(x))]\,dx.\end{aligned}$$

Consequently,

$$\int_C M\,dx = -\iint_R \frac{\partial M}{\partial y}\,dA.$$

Similarly, you can use $g_1(y)$ and $g_2(y)$ to show that $\int_C N\,dy = \iint_R (\partial N/\partial x)\,dA$. By adding the integrals $\int_C M\,dx$ and $\int_C N\,dy$, you obtain the conclusion stated in the theorem. ∎

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

An integral sign with a circle is sometimes used to indicate a line integral around a simple closed curve, as shown below. To indicate the orientation of the boundary, an arrow can be used. For instance, in the second integral, the arrow indicates that the boundary C is oriented counterclockwise.

1. $\oint_C M\,dx + N\,dy$ **2.** $\oint_C M\,dx + N\,dy$

EXAMPLE 1 Using Green's Theorem

Use Green's Theorem to evaluate the line integral

$$\int_C y^3\,dx + (x^3 + 3xy^2)\,dy$$

where C is the path from $(0, 0)$ to $(1, 1)$ along the graph of $y = x^3$ and from $(1, 1)$ to $(0, 0)$ along the graph of $y = x$, as shown in Figure 15.28.



C is simple and closed, and the region R always lies to the left of C.
Figure 15.28

Solution Because $M = y^3$ and $N = x^3 + 3xy^2$, it follows that

$$\frac{\partial N}{\partial x} = 3x^2 + 3y^2 \quad \text{and} \quad \frac{\partial M}{\partial y} = 3y^2.$$

Applying Green's Theorem, you then have

$$\begin{aligned}
\int_C y^3\,dx + (x^3 + 3xy^2)\,dy &= \int_R\int \left(\frac{\partial N}{\partial x} - \frac{\partial M}{\partial y}\right) dA \\
&= \int_0^1 \int_{x^3}^{x} \left[(3x^2 + 3y^2) - 3y^2\right] dy\,dx \\
&= \int_0^1 \int_{x^3}^{x} 3x^2\,dy\,dx \\
&= \int_0^1 3x^2 y \Big]_{x^3}^{x} dx \\
&= \int_0^1 (3x^3 - 3x^5)\,dx \\
&= \left[\frac{3x^4}{4} - \frac{x^6}{2}\right]_0^1 \\
&= \frac{1}{4}.
\end{aligned}$$

GEORGE GREEN (1793–1841)

Green, a self-educated miller's son, first published the theorem that bears his name in 1828 in an essay on electricity and magnetism. At that time, there was almost no mathematical theory to explain electrical phenomena. "Considering how desirable it was that a power of universal agency, like electricity, should, as far as possible, be submitted to calculation, . . . I was induced to try whether it would be possible to discover any general relations existing between this function and the quantities of electricity in the bodies producing it."

Green's Theorem cannot be applied to every line integral. Among other restrictions stated in Theorem 15.8, the curve C must be simple and closed. When Green's Theorem does apply, however, it can save time. To show this, try using the techniques described in Section 15.2 to evaluate the line integral in Example 1. To do this, you would need to write the line integral as

$$\begin{aligned}
&\int_C y^3\,dx + (x^3 + 3xy^2)\,dy \\
&\qquad = \int_{C_1} y^3\,dx + (x^3 + 3xy^2)\,dy + \int_{C_2} y^3\,dx + (x^3 + 3xy^2)\,dy
\end{aligned}$$

where C_1 is the cubic path given by

$$\mathbf{r}(t) = t\mathbf{i} + t^3\mathbf{j}$$

from $t = 0$ to $t = 1$, and C_2 is the line segment given by

$$\mathbf{r}(t) = (1 - t)\mathbf{i} + (1 - t)\mathbf{j}$$

from $t = 0$ to $t = 1$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 15.29

GO DIGITAL

EXAMPLE 2 Using Green's Theorem to Calculate Work

While subject to the force

$$\mathbf{F}(x, y) = y^3\mathbf{i} + (x^3 + 3xy^2)\mathbf{j}$$

a particle travels once around the circle of radius 3 shown in Figure 15.29. Use Green's Theorem to find the work done by $\mathbf{F}$.

Solution From Example 1, you know by Green's Theorem that

$$\int_C y^3\,dx + (x^3 + 3xy^2)\,dy = \iint_R 3x^2\,dA.$$

In polar coordinates, using $x = r\cos\theta$ and $dA = r\,dr\,d\theta$, the work done is

$$\begin{aligned}
W &= \iint_R 3x^2\,dA \\
&= \int_0^{2\pi}\int_0^3 3(r\cos\theta)^2 r\,dr\,d\theta \\
&= 3\int_0^{2\pi}\int_0^3 r^3\cos^2\theta\,dr\,d\theta \\
&= 3\int_0^{2\pi}\frac{r^4}{4}\cos^2\theta\,\Big]_0^3 d\theta \\
&= 3\int_0^{2\pi}\frac{81}{4}\cos^2\theta\,d\theta \\
&= \frac{243}{8}\int_0^{2\pi}(1 + \cos 2\theta)\,d\theta \\
&= \frac{243}{8}\left[\theta + \frac{\sin 2\theta}{2}\right]_0^{2\pi} \\
&= \frac{243\pi}{4}.
\end{aligned}$$

When evaluating line integrals over closed curves, remember that for conservative vector fields (those for which $\partial N/\partial x = \partial M/\partial y$), the value of the line integral is 0. This conclusion is a direct result from the statement of Green's Theorem:

$$\int_C M\,dx + N\,dy = \iint_R \left(\frac{\partial N}{\partial x} - \frac{\partial M}{\partial y}\right)dA = 0.$$



C is closed.

Figure 15.30

EXAMPLE 3 Green's Theorem and Conservative Vector Fields

Evaluate the line integral

$$\int_C y^3\,dx + 3xy^2\,dy$$

where C is the path shown in Figure 15.30.

Solution From this line integral, $M = y^3$ and $N = 3xy^2$. So, $\partial N/\partial x = 3y^2$ and $\partial M/\partial y = 3y^2$. This implies that the vector field $\mathbf{F} = M\mathbf{i} + N\mathbf{j}$ is conservative, and because C is closed, you can conclude that

$$\int_C y^3\,dx + 3xy^2\,dy = 0.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



C is piecewise smooth.
Figure 15.31

EXAMPLE 4 Using Green's Theorem

See LarsonCalculus.com for an interactive version of this type of example.

Evaluate

$$\int_C (\arctan x + y^2)\,dx + (e^y - x^2)\,dy$$

where C is the path enclosing the annular region shown in Figure 15.31.

Solution In polar coordinates, R is given by $1 \le r \le 3$ for $0 \le \theta \le \pi$. Moreover,

$$\frac{\partial N}{\partial x} - \frac{\partial M}{\partial y} = -2x - 2y = -2(r\cos\theta + r\sin\theta).$$

So, by Green's Theorem,

$$\begin{aligned}
\int_C (\arctan x + y^2)\,dx + (e^y - x^2)\,dy &= \iint_R -2(x + y)\,dA \\
&= \int_0^{\pi}\int_1^3 -2r(\cos\theta + \sin\theta)r\,dr\,d\theta \\
&= \int_0^{\pi} -2(\cos\theta + \sin\theta)\frac{r^3}{3}\Big]_1^3\,d\theta \\
&= \int_0^{\pi} -\frac{52}{3}(\cos\theta + \sin\theta)\,d\theta \\
&= -\frac{52}{3}\Big[\sin\theta - \cos\theta\Big]_0^{\pi} \\
&= -\frac{104}{3}.
\end{aligned}$$

In Examples 1, 2, and 4, Green's Theorem was used to evaluate line integrals as double integrals. You can also use the theorem to evaluate double integrals as line integrals. One useful application occurs when $\partial N/\partial x - \partial M/\partial y = 1$.

$$\begin{aligned}
\int_C M\,dx + N\,dy &= \iint_R \left(\frac{\partial N}{\partial x} - \frac{\partial M}{\partial y}\right)dA \\
&= \iint_R 1\,dA \qquad \frac{\partial N}{\partial x} - \frac{\partial M}{\partial y} = 1 \\
&= \text{area of region } R
\end{aligned}$$

Among the many choices for M and N satisfying the stated condition, the choice of

$$M = -\frac{y}{2} \quad \text{and} \quad N = \frac{x}{2}$$

produces the following line integral for the area of region R.

THEOREM 15.9 Line Integral for Area

If R is a plane region bounded by a piecewise smooth simple closed curve C, oriented counterclockwise, then the area of R is given by

$$A = \frac{1}{2}\int_C x\,dy - y\,dx.$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

EXAMPLE 5 Finding Area by a Line Integral

Use a line integral to find the area of the ellipse $(x^2/a^2) + (y^2/b^2) = 1$.



Figure 15.32

Solution Using Figure 15.32, you can induce a counterclockwise orientation to the elliptical path by letting $x = a\cos t$ and $y = b\sin t$, $0 \le t \le 2\pi$. So, the area is

$$\begin{aligned} A = \frac{1}{2}\int_C x\,dy - y\,dx &= \frac{1}{2}\int_0^{2\pi} [(a\cos t)(b\cos t)\,dt - (b\sin t)(-a\sin t)\,dt] \\ &= \frac{ab}{2}\int_0^{2\pi} (\cos^2 t + \sin^2 t)\,dt \\ &= \frac{ab}{2}\Big[t\Big]_0^{2\pi} \\ &= \pi ab. \end{aligned}$$

Green's Theorem can be extended to cover some regions that are not simply connected. This is demonstrated in the next example.

EXAMPLE 6 Green's Theorem Extended to a Region with a Hole

Let R be the region inside the ellipse $(x^2/9) + (y^2/4) = 1$ and outside the circle $x^2 + y^2 = 1$. Evaluate the line integral

$$\int_C 2xy\,dx + (x^2 + 2x)\,dy$$

where $C = C_1 + C_2$ is the boundary of R, as shown in Figure 15.33.



Figure 15.33

Solution To begin, introduce the line segments C_3 and C_4, as shown in Figure 15.33. Note that because the curves C_3 and C_4 have opposite orientations, the line integrals over them cancel. Furthermore, apply Green's Theorem to the region R using the boundary $C_1 + C_4 + C_2 + C_3$ to obtain

$$\begin{aligned} \int_C 2xy\,dx + (x^2 + 2x)\,dy &= \iint_R \left(\frac{\partial N}{\partial x} - \frac{\partial M}{\partial y}\right) dA \\ &= \iint_R (2x + 2 - 2x)\,dA \\ &= 2\iint_R dA \\ &= 2(\text{area of } R) \\ &= 2(\pi ab - \pi r^2) \\ &= 2[\pi(3)(2) - \pi(1^2)] \\ &= 10\pi. \end{aligned}$$

In Section 15.1, a necessary and sufficient condition for conservative vector fields was listed. There, only one direction of the proof was shown. You can now outline the other direction, using Green's Theorem. Let $\mathbf{F}(x, y) = M\mathbf{i} + N\mathbf{j}$ be defined on an open disk R. You want to show that if M and N have continuous first partial derivatives and $\partial M/\partial y = \partial N/\partial x$, then $\mathbf{F}$ is conservative. Let C be a closed path forming the boundary of a connected region lying in R. Then, using the fact that $\partial M/\partial y = \partial N/\partial x$, apply Green's Theorem to conclude that

$$\int_C \mathbf{F}\cdot d\mathbf{r} = \int_C M\,dx + N\,dy = \iint_R \left(\frac{\partial N}{\partial x} - \frac{\partial M}{\partial y}\right) dA = 0.$$

This, in turn, is equivalent to showing that $\mathbf{F}$ is conservative (see Theorem 15.7).

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Alternative Forms of Green's Theorem

This section concludes with the derivation of two vector forms of Green's Theorem for regions in the plane. The extension of these vector forms to three dimensions is the basis for the discussion in the remaining sections of this chapter. For a vector field $\mathbf{F}$ in the plane, you can write

$$\mathbf{F}(x, y, z) = M\mathbf{i} + N\mathbf{j} + 0\mathbf{k}$$

so that the curl of $\mathbf{F}$, as described in Section 15.1, is given by

$$\operatorname{curl} \mathbf{F} = \nabla \times \mathbf{F} = \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ \frac{\partial}{\partial x} & \frac{\partial}{\partial y} & \frac{\partial}{\partial z} \\ M & N & 0 \end{vmatrix} = -\frac{\partial N}{\partial z}\mathbf{i} + \frac{\partial M}{\partial z}\mathbf{j} + \left(\frac{\partial N}{\partial x} - \frac{\partial M}{\partial y}\right)\mathbf{k}.$$

Consequently,

$$(\operatorname{curl} \mathbf{F}) \cdot \mathbf{k} = \left[-\frac{\partial N}{\partial z}\mathbf{i} + \frac{\partial M}{\partial z}\mathbf{j} + \left(\frac{\partial N}{\partial x} - \frac{\partial M}{\partial y}\right)\mathbf{k}\right] \cdot \mathbf{k} = \frac{\partial N}{\partial x} - \frac{\partial M}{\partial y}.$$

With appropriate conditions on $\mathbf{F}$, C, and R, you can write Green's Theorem in the vector form

$$\begin{aligned} \int_C \mathbf{F} \cdot d\mathbf{r} &= \iint_R \left(\frac{\partial N}{\partial x} - \frac{\partial M}{\partial y}\right) dA \\ &= \iint_R (\operatorname{curl} \mathbf{F}) \cdot \mathbf{k}\, dA. \end{aligned}$$ First alternative form

The extension of this vector form of Green's Theorem to surfaces in space produces **Stokes's Theorem,** discussed in Section 15.8.

For the second vector form of Green's Theorem, assume the same conditions for $\mathbf{F}$, C, and R. Using the arc length parameter s for C, you have $\mathbf{r}(s) = x(s)\mathbf{i} + y(s)\mathbf{j}$. So, a unit tangent vector $\mathbf{T}$ to curve C is given by $\mathbf{r}'(s) = \mathbf{T} = x'(s)\mathbf{i} + y'(s)\mathbf{j}$. From Figure 15.34, note that the *outward* unit normal vector $\mathbf{N}$ can then be written as

$$\mathbf{N} = y'(s)\mathbf{i} - x'(s)\mathbf{j}.$$



$\mathbf{T} = \cos\theta\mathbf{i} + \sin\theta\mathbf{j}$

$\mathbf{n} = \cos\left(\theta + \frac{\pi}{2}\right)\mathbf{i} + \sin\left(\theta + \frac{\pi}{2}\right)\mathbf{j}$

$= -\sin\theta\mathbf{i} + \cos\theta\mathbf{j}$

$\mathbf{N} = \sin\theta\mathbf{i} - \cos\theta\mathbf{j}$

Figure 15.34

Consequently, for $\mathbf{F}(x, y) = M\mathbf{i} + N\mathbf{j}$, you can apply Green's Theorem to obtain

$$\begin{aligned} \int_C \mathbf{F} \cdot \mathbf{N}\, ds &= \int_a^b (M\mathbf{i} + N\mathbf{j}) \cdot (y'(s)\mathbf{i} - x'(s)\mathbf{j})\, ds \\ &= \int_a^b \left(M\frac{dy}{ds} - N\frac{dx}{ds}\right) ds \\ &= \int_C M\, dy - N\, dx \\ &= \int_C -N\, dx + M\, dy \\ &= \iint_R \left(\frac{\partial M}{\partial x} + \frac{\partial N}{\partial y}\right) dA \qquad \text{Green's Theorem} \\ &= \iint_R \operatorname{div} \mathbf{F}\, dA. \end{aligned}$$

Therefore,

$$\int_C \mathbf{F} \cdot \mathbf{N}\, ds = \iint_R \operatorname{div} \mathbf{F}\, dA.$$ Second alternative form

The extension of this form to three dimensions is called the **Divergence Theorem** and will be discussed in Section 15.7. The physical interpretations of divergence and curl will be discussed in Sections 15.7 and 15.8.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

15.4 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain what it means for a curve to be simple. Explain what it means for a plane region to be simply connected.
2. Explain the usefulness of Green's Theorem.
3. What information do you learn from the integral sign $\oint_C$?
4. Describe how to find the area of a plane region bounded by a piecewise smooth simple closed curve that is oriented counterclockwise.

Verifying Green's Theorem **In Exercises 5–8, verify Green's Theorem by evaluating both integrals**

$$\int_C y^2\,dx + x^2\,dy = \int_R\int \left(\frac{\partial N}{\partial x} - \frac{\partial M}{\partial y}\right) dA$$

for the given path.

5. C: boundary of the region lying between the graphs of $y = x$ and $y = x^2$
6. C: boundary of the region lying between the graphs of $y = x$ and $y = \sqrt{x}$
7. C: square with vertices $(0, 0)$, $(1, 0)$, $(1, 1)$, and $(0, 1)$
8. C: rectangle with vertices $(0, 0)$, $(3, 0)$, $(3, 4)$, and $(0, 4)$

Verifying Green's Theorem **In Exercises 9 and 10, verify Green's Theorem by using a graphing utility to evaluate both integrals**

$$\int_C xe^y\,dx + e^x\,dy = \int_R\int \left(\frac{\partial N}{\partial x} - \frac{\partial M}{\partial y}\right) dA$$

for the given path.

9. C: circle given by $x^2 + y^2 = 4$
10. C: boundary of the region lying between the graphs of $y = x$ and $y = x^3$ in the first quadrant

Evaluating a Line Integral Using Green's Theorem **In Exercises 11–14, use Green's Theorem to evaluate the line integral $\int_C (y - x)\,dx + (2x - y)\,dy$ for the given path.**

11. C: boundary of the region lying between the graphs of $y = x$ and $y = x^2 - 2x$
12. C: $x = 2\cos\theta$, $y = \sin\theta$
13. C: boundary of the region lying inside the rectangle with vertices $(5, 3)$, $(-5, 3)$, $(-5, -3)$, and $(5, -3)$, and outside the square with vertices $(1, 1)$, $(-1, 1)$, $(-1, -1)$, and $(1, -1)$
14. C: boundary of the region lying inside the semicircle $y = \sqrt{25 - x^2}$ and outside the semicircle $y = \sqrt{9 - x^2}$

Evaluating a Line Integral Using Green's Theorem **In Exercises 15–24, use Green's Theorem to evaluate the line integral.**

15. $\int_C 2xy\,dx + (x + y)\,dy$

    C: boundary of the region lying between the graphs of $y = 0$ and $y = 1 - x^2$
16. $\int_C y^2\,dx + xy\,dy$

    C: boundary of the region lying between the graphs of $y = 0$, $y = \sqrt{x}$, and $x = 9$
17. $\int_C (x^2 - y^2)\,dx + 2xy\,dy$

    C: $x^2 + y^2 = 16$
18. $\int_C (x^2 - y^2)\,dx + 2xy\,dy$

    C: $r = 1 + \cos\theta$
19. $\int_C e^x \cos 2y\,dx - 2e^x \sin 2y\,dy$

    C: $x^2 + y^2 = a^2$
20. $\int_C 2\arctan\frac{y}{x}\,dx + \ln(x^2 + y^2)\,dy$

    C: $x = 4 + 2\cos\theta$, $y = 4 + \sin\theta$
21. $\int_C \cos y\,dx + (xy - x\sin y)\,dy$

    C: boundary of the region lying between the graphs of $y = x$ and $y = \sqrt{x}$
22. $\int_C (e^{-x^2/2} - y)\,dx + (e^{-y^2/2} + x)\,dy$

    C: boundary of the region lying between the graphs of the circle $x = 6\cos\theta$, $y = 6\sin\theta$ and the ellipse $x = 3\cos\theta$, $y = 2\sin\theta$
23. $\int_C (x - 3y)\,dx + (x + y)\,dy$

    C: boundary of the region lying between the graphs of $x^2 + y^2 = 1$ and $x^2 + y^2 = 9$
24. $\int_C 3x^2e^y\,dx + e^y\,dy$

    C: boundary of the region lying between the squares with vertices $(1, 1)$, $(-1, 1)$, $(-1, -1)$, and $(1, -1)$, and $(2, 2)$, $(-2, 2)$, $(-2, -2)$, and $(2, -2)$

Work **In Exercises 25–28, use Green's Theorem to calculate the work done by the force $\mathbf{F}$ on a particle that is moving counterclockwise around the closed path C.**

25. $\mathbf{F}(x, y) = xy\mathbf{i} + (x + y)\mathbf{j}$

    C: $x^2 + y^2 = 1$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

26. $\mathbf{F}(x, y) = (e^x - 3y)\mathbf{i} + (e^y + 6x)\mathbf{j}$

C: $r = 2\cos\theta$

27. $\mathbf{F}(x, y) = (x^{3/2} - 3y)\mathbf{i} + \left(6x + 5\sqrt{y}\right)\mathbf{j}$

C: triangle with vertices $(0, 0)$, $(5, 0)$, and $(0, 5)$

28. $\mathbf{F}(x, y) = (3x^2 + y)\mathbf{i} + 4xy^2\mathbf{j}$

C: boundary of the region lying between the graphs of $y = \sqrt{x}$, $y = 0$, and $x = 9$

Area **In Exercises 29–32, use a line integral to find the area of the region R.**

29. R: region bounded by the graph of $x^2 + y^2 = 4$

30. R: triangle bounded by the graphs of $x = 0$, $3x - 2y = 0$, and $x + 2y = 8$

31. R: region bounded by the graphs of $y = 5x - 3$ and $y = x^2 + 1$

32. R: region inside the loop of the folium of Descartes bounded by the graph of

$$x = \frac{3t}{t^3 + 1}, \quad y = \frac{3t^2}{t^3 + 1}$$

Using Green's Theorem to Verify a Formula **In Exercises 33 and 34, use Green's Theorem to verify the line integral formula(s).**

33. The centroid of the region having area A bounded by the simple closed path C has coordinates

$$\bar{x} = \frac{1}{2A}\int_C x^2\,dy \quad \text{and} \quad \bar{y} = -\frac{1}{2A}\int_C y^2\,dx.$$

34. The area of a plane region bounded by the simple closed path C given in polar coordinates is

$$A = \frac{1}{2}\int_C r^2\,d\theta.$$

Centroid **In Exercises 35–38, use the results of Exercise 33 to find the centroid of the region.**

35. R: region bounded by the graphs of $y = 0$ and $4 - x^2$

36. R: region bounded by the graphs of $y = \sqrt{1 - x^2}$ and $y = 0$

37. R: region bounded by the graphs of $y = x^3$ and $y = x$, $0 \le x \le 1$

38. R: triangle with vertices $(-a, 0)$, $(a, 0)$, and (b, c), where $-a \le b \le a$

Area **In Exercises 39–42, use the result of Exercise 34 to find the area of the region bounded by the graph of the polar equation.**

39. $r = 6(1 - \cos\theta)$

40. $r = a\cos 3\theta$

41. $r = 1 + 2\cos\theta$ (inner loop)

42. $r = \dfrac{3}{2 - \cos\theta}$

43. Maximum Value

(a) Evaluate $\int_{C_1} y^3\,dx + (27x - x^3)\,dy$, where C_1 is the unit circle given by $\mathbf{r}(t) = \cos t\mathbf{i} + \sin t\mathbf{j}$, for $0 \le t \le 2\pi$.

(b) Find the maximum value of $\int_C y^3\,dx + (27x - x^3)\,dy$, where C is any circle centered at the origin in the xy-plane, oriented counterclockwise.

44. HOW DO YOU SEE IT? The figure shows a region R bounded by a piecewise smooth simple closed path C.



(a) Is R simply connected? Explain.

(b) Explain why $\int_C f(x)\,dx + g(y)\,dy = 0$, where f and g are differentiable functions.

45. Green's Theorem: Region with a Hole Let R be the region inside the circle $x = 5\cos\theta$, $y = 5\sin\theta$ and outside the ellipse $x = 2\cos\theta$, $y = \sin\theta$. Evaluate the line integral

$$\int_C (e^{-x^2/2} - y)\,dx + (e^{-y^2/2} + x)\,dy$$

where $C = C_1 + C_2$ is the boundary of R, as shown in the figure.



Figure for 45



Figure for 46

46. Green's Theorem: Region with a Hole Let R be the region inside the ellipse $x = 4\cos\theta$, $y = 3\sin\theta$ and outside the circle $x = 2\cos\theta$, $y = 2\sin\theta$. Evaluate the line integral

$$\int_C (3x^2y + 1)\,dx + (x^3 + 4x)\,dy$$

where $C = C_1 + C_2$ is the boundary of R, as shown in the figure.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Exploring Concepts

47. Let

$$I = \int_C \frac{y\,dx - x\,dy}{x^2 + y^2}$$

where C is a circle oriented counterclockwise.

(a) Show that $I = 0$ when C does not contain the origin.

(b) What is I when C does contain the origin?

48. For each given path, verify Green's Theorem by showing that

$$\int_C y^2\,dx + x^2\,dy = \iint_R \left(\frac{\partial N}{\partial x} - \frac{\partial M}{\partial y}\right) dA.$$

For each path, which integral is easier to evaluate? Explain.

(a) C: triangle with vertices $(0, 0)$, $(4, 0)$, and $(4, 4)$

(b) C: circle given by $x^2 + y^2 = 1$

49. Proof

(a) Let C be the line segment joining (x_1, y_1) and (x_2, y_2). Show that $\int_C -y\,dx + x\,dy = x_1y_2 - x_2y_1$.

(b) Let (x_1, y_1), (x_2, y_2), . . . , (x_n, y_n) be the vertices of a polygon. Prove that the area enclosed is

$$\tfrac{1}{2}[(x_1y_2 - x_2y_1) + (x_2y_3 - x_3y_2) + \cdots + (x_{n-1}y_n - x_ny_{n-1}) + (x_ny_1 - x_1y_n)].$$

50. Area Use the result of Exercise 49(b) to find the area enclosed by the polygon with the given vertices.

(a) Pentagon: $(0, 0)$, $(2, 0)$, $(3, 2)$, $(1, 4)$, and $(-1, 1)$

(b) Hexagon: $(0, 0)$, $(2, 0)$, $(3, 2)$, $(2, 4)$, $(0, 3)$, and $(-1, 1)$

Proof **In Exercises 51 and 52, prove the identity, where R is a simply connected region with piecewise smooth boundary C. Assume that the required partial derivatives of the scalar functions f and g are continuous. The expressions $D_{\mathbf{N}}f$ and $D_{\mathbf{N}}g$ are the derivatives in the direction of the outward normal vector $\mathbf{N}$ of C and are defined by $D_{\mathbf{N}}f = \nabla f \cdot \mathbf{N}$ and $D_{\mathbf{N}}g = \nabla g \cdot \mathbf{N}$.**

51. Green's first identity:

$$\iint_R (f\nabla^2 g + \nabla f \cdot \nabla g)\,dA = \int_C fD_{\mathbf{N}}g\,ds$$

[*Hint:* Use the second alternative form of Green's Theorem and the property $\operatorname{div}(f\mathbf{G}) = f \operatorname{div}\mathbf{G} + \nabla f \cdot \mathbf{G}$.]

52. Green's second identity:

$$\iint_R (f\nabla^2 g - g\nabla^2 f)\,dA = \int_C (fD_{\mathbf{N}}g - gD_{\mathbf{N}}f)\,ds$$

(*Hint:* Use Green's first identity from Exercise 51 twice.)

53. Proof Let $\mathbf{F} = M\mathbf{i} + N\mathbf{j}$, where M and N have continuous first partial derivatives in a simply connected region R. Prove that if C is simple, smooth, and closed, and $N_x = M_y$, then $\int_C \mathbf{F} \cdot d\mathbf{r} = 0$.

PUTNAM EXAM CHALLENGE

54. Find the least possible area of a convex set in the plane that intersects both branches of the hyperbola $xy = 1$ and both branches of the hyperbola $xy = -1$. (A set S in the plane is called *convex* if for any two points in S the line segment connecting them is contained in S.)

55. Let A and B be points on the same branch of the hyperbola $xy = 1$. Suppose that P is a point lying between A and B on this hyperbola, such that the area of the triangle APB is as large as possible. Show that the region bounded by the hyperbola and the chord AP has the same area as the region bounded by the hyperbola and the chord PB.

These problems were composed by the Committee on the Putnam Prize Competition. © The Mathematical Association of America. All rights reserved.

SECTION PROJECT

Hyperbolic and Trigonometric Functions

(a) Sketch the plane curve represented by the vector-valued function $\mathbf{r}(t) = \cosh t\mathbf{i} + \sinh t\mathbf{j}$ on the interval $0 \le t \le 5$. Show that the rectangular equation corresponding to $\mathbf{r}(t)$ is the hyperbola $x^2 - y^2 = 1$. Verify your sketch by using a graphing utility to graph the hyperbola.

(b) Let $P = (\cosh\phi, \sinh\phi)$ be the point on the hyperbola corresponding to $\mathbf{r}(\phi)$ for $\phi > 0$. Use the formula for area

$$A = \frac{1}{2}\int_C x\,dy - y\,dx$$

to verify that the area of the region shown in the figure is $\frac{1}{2}\phi$.

(c) Show that the area of the region shown in the figure is also given by the integral

$$A = \int_0^{\sinh\phi} \left[\sqrt{1 + y^2} - (\coth\phi)y\right] dy.$$

Confirm your answer in part (b) by evaluating this integral for $\phi = 1, 2, 4$, and 10.

(d) Consider the unit circle given by $x^2 + y^2 = 1$. Let θ be the angle formed by the x-axis and the radius to (x, y). The area of the corresponding sector is $\frac{1}{2}\theta$. That is, the trigonometric functions $f(\theta) = \cos\theta$ and $g(\theta) = \sin\theta$ could have been defined as the coordinates of the point $(\cos\theta, \sin\theta)$ on the unit circle that determines a sector of area $\frac{1}{2}\theta$. Write a short paragraph explaining how you could define the hyperbolic functions in a similar manner, using the "unit hyperbola" $x^2 - y^2 = 1$.



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

15.5 Parametric Surfaces

GO DIGITAL

- **Identify and sketch a parametric surface.**
- **Find a set of parametric equations to represent a surface.**
- **Find a normal vector and a tangent plane to a parametric surface.**
- **Find the area of a parametric surface.**

Parametric Surfaces

You already know how to represent a curve in the plane or in space by a set of parametric equations—or, equivalently, by a vector-valued function.

$$\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j} \qquad \text{Plane curve}$$

$$\mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j} + z(t)\mathbf{k} \qquad \text{Space curve}$$

In this section, you will learn how to represent a surface in space by a set of parametric equations—or by a vector-valued function. For curves, note that the vector-valued function $\mathbf{r}$ is a function of a *single* parameter t. For surfaces, the vector-valued function is a function of *two* parameters u and v.

Definition of Parametric Surface

Let x, y, and z be functions of u and v that are continuous on a domain D in the uv-plane. The set of points (x, y, z) given by

$$\mathbf{r}(u, v) = x(u, v)\mathbf{i} + y(u, v)\mathbf{j} + z(u, v)\mathbf{k} \qquad \text{Parametric surface}$$

is called a **parametric surface.** The equations

$$x = x(u, v), \quad y = y(u, v), \quad \text{and} \quad z = z(u, v) \qquad \text{Parametric equations}$$

are the **parametric equations** for the surface.

If S is a parametric surface given by the vector-valued function $\mathbf{r}$, then S is traced out by the position vector $\mathbf{r}(u, v)$ as the point (u, v) moves throughout the domain D, as shown in Figure 15.35.



The parametric surface S given by the vector-valued function $\mathbf{r}$, where $\mathbf{r}$ is a function of two variables u and v defined on a domain D

Figure 15.35

TECHNOLOGY Some graphing utilities are capable of graphing surfaces that are represented parametrically. If you have access to such a graphing utility, use it to graph some of the surfaces in the examples and exercises in this section.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 1 Sketching a Parametric Surface

Identify and sketch the parametric surface S given by

$$\mathbf{r}(u, v) = 3 \cos u\mathbf{i} + 3 \sin u\mathbf{j} + v\mathbf{k}$$

where $0 \le u \le 2\pi$ and $0 \le v \le 4$.

Solution Because $x = 3 \cos u$ and $y = 3 \sin u$, you know that for each point (x, y, z) on the surface, x and y are related by the equation

$$x^2 + y^2 = 3^2.$$

In other words, each cross section of S taken parallel to the xy-plane is a circle of radius 3, centered on the z-axis. Because $z = v$, where

$$0 \le v \le 4$$

you can see that the surface is a right circular cylinder of height 4. The radius of the cylinder is 3, and the z-axis forms the axis of the cylinder, as shown in Figure 15.36.



Figure 15.36

As with parametric representations of curves, parametric representations of surfaces are not unique. That is, there are many other sets of parametric equations that could be used to represent the surface shown in Figure 15.36.

EXAMPLE 2 Sketching a Parametric Surface

Identify and sketch the parametric surface S given by

$$\mathbf{r}(u, v) = \sin u \cos v\mathbf{i} + \sin u \sin v\mathbf{j} + \cos u\mathbf{k}$$

where $0 \le u \le \pi$ and $0 \le v \le 2\pi$.

Solution To identify the surface, you can try to use trigonometric identities to eliminate the parameters. After some experimentation, you can discover that

$$\begin{aligned} x^2 + y^2 + z^2 &= (\sin u \cos v)^2 + (\sin u \sin v)^2 + (\cos u)^2 \\ &= \sin^2 u \cos^2 v + \sin^2 u \sin^2 v + \cos^2 u \\ &= (\sin^2 u)(\cos^2 v + \sin^2 v) + \cos^2 u \\ &= \sin^2 u + \cos^2 u \\ &= 1. \end{aligned}$$

So, each point on S lies on the unit sphere, centered at the origin, as shown in Figure 15.37. For fixed $u = d_i$, $\mathbf{r}(u, v)$ traces out latitude circles

$$x^2 + y^2 = \sin^2 d_i, \quad 0 \le d_i \le \pi$$

that are parallel to the xy-plane, and for fixed $v = c_i$, $\mathbf{r}(u, v)$ traces out longitude (or meridian) half-circles.

To convince yourself further that $\mathbf{r}(u, v)$ traces out the entire unit sphere, recall that the parametric equations

$$x = \rho \sin \phi \cos \theta, \quad y = \rho \sin \phi \sin \theta, \quad \text{and} \quad z = \rho \cos \phi$$

where $0 \le \theta \le 2\pi$ and $0 \le \phi \le \pi$, describe the conversion from spherical to rectangular coordinates, as discussed in Section 11.7.



Figure 15.37

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Finding Parametric Equations for Surfaces

In Examples 1 and 2, you were asked to identify the surface described by a given set of parametric equations. The reverse problem—that of writing a set of parametric equations for a given surface—is generally more difficult. One type of surface for which this problem is straightforward, however, is a surface that is given by $z = f(x, y)$. You can parametrize such a surface as

$$\mathbf{r}(x, y) = x\mathbf{i} + y\mathbf{j} + f(x, y)\mathbf{k}.$$



Figure 15.38

EXAMPLE 3 Representing a Surface Parametrically

Write a set of parametric equations for the cone given by

$$z = \sqrt{x^2 + y^2}$$

as shown in Figure 15.38.

Solution Because this surface is given in the form $z = f(x, y)$, you can let x and y be the parameters. Then the cone is represented by the vector-valued function

$$\mathbf{r}(x, y) = x\mathbf{i} + y\mathbf{j} + \sqrt{x^2 + y^2}\mathbf{k}$$

where (x, y) varies over the entire xy-plane. ■

A second type of surface that is easily represented parametrically is a surface of revolution. For instance, to represent the surface formed by revolving the graph of

$$y = f(x), \quad a \le x \le b$$

about the x-axis, use

$$x = u, \quad y = f(u)\cos v, \quad \text{and} \quad z = f(u)\sin v$$

where $a \le u \le b$ and $0 \le v \le 2\pi$.

EXAMPLE 4 Representing a Surface of Revolution Parametrically

See LarsonCalculus.com for an interactive version of this type of example.

Write a set of parametric equations for the surface of revolution obtained by revolving

$$f(x) = \frac{1}{x}, \quad 1 \le x \le 10$$

about the x-axis.



Figure 15.39

Solution Use the parameters u and v as described above to write

$$x = u, \quad y = f(u)\cos v = \frac{1}{u}\cos v, \quad \text{and} \quad z = f(u)\sin v = \frac{1}{u}\sin v$$

where

$$1 \le u \le 10 \quad \text{and} \quad 0 \le v \le 2\pi.$$

The resulting surface is a portion of *Gabriel's Horn,* as shown in Figure 15.39. ■

The surface of revolution in Example 4 is formed by revolving the graph of $y = f(x)$ about the x-axis. For other types of surfaces of revolution, a similar parametrization can be used. For instance, to parametrize the surface formed by revolving the graph of $x = f(z)$ about the z-axis, you can use

$$z = u, \quad x = f(u)\cos v, \quad \text{and} \quad y = f(u)\sin v.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Normal Vectors and Tangent Planes

Let S be a parametric surface given by

$$\mathbf{r}(u, v) = x(u, v)\mathbf{i} + y(u, v)\mathbf{j} + z(u, v)\mathbf{k}$$

over an open region D such that x, y, and z have continuous partial derivatives on D. The **partial derivatives of r** with respect to u and v are defined as

$$\mathbf{r}_u = \frac{\partial x}{\partial u}(u, v)\mathbf{i} + \frac{\partial y}{\partial u}(u, v)\mathbf{j} + \frac{\partial z}{\partial u}(u, v)\mathbf{k}$$

and

$$\mathbf{r}_v = \frac{\partial x}{\partial v}(u, v)\mathbf{i} + \frac{\partial y}{\partial v}(u, v)\mathbf{j} + \frac{\partial z}{\partial v}(u, v)\mathbf{k}.$$

Each of these partial derivatives is a vector-valued function that can be interpreted geometrically in terms of tangent vectors. For instance, if $v = v_0$ is held constant, then $\mathbf{r}(u, v_0)$ is a vector-valued function of a single parameter and defines a curve C_1 that lies on the surface S. The tangent vector to C_1 at the point

$$(x(u_0, v_0), y(u_0, v_0), z(u_0, v_0))$$

is given by

$$\mathbf{r}_u(u_0, v_0) = \frac{\partial x}{\partial u}(u_0, v_0)\mathbf{i} + \frac{\partial y}{\partial u}(u_0, v_0)\mathbf{j} + \frac{\partial z}{\partial u}(u_0, v_0)\mathbf{k}$$

as shown in Figure 15.40. In a similar way, if $u = u_0$ is held constant, then $\mathbf{r}(u_0, v)$ is a vector-valued function of a single parameter and defines a curve C_2 that lies on the surface S. The tangent vector to C_2 at the point $(x(u_0, v_0), y(u_0, v_0), z(u_0, v_0))$ is given by

$$\mathbf{r}_v(u_0, v_0) = \frac{\partial x}{\partial v}(u_0, v_0)\mathbf{i} + \frac{\partial y}{\partial v}(u_0, v_0)\mathbf{j} + \frac{\partial z}{\partial v}(u_0, v_0)\mathbf{k}.$$

If the normal vector $\mathbf{r}_u \times \mathbf{r}_v$ is not $\mathbf{0}$ for any (u, v) in D, then the surface S is called **smooth** and will have a tangent plane. Informally, a smooth surface is one that has no sharp points or cusps. For instance, spheres, ellipsoids, and paraboloids are smooth, whereas the cone given in Example 3 is not smooth.



Figure 15.40

Normal Vector to a Smooth Parametric Surface

Let S be a smooth parametric surface

$$\mathbf{r}(u, v) = x(u, v)\mathbf{i} + y(u, v)\mathbf{j} + z(u, v)\mathbf{k}$$

defined over an open region D in the uv-plane. Let (u_0, v_0) be a point in D. A normal vector at the point

$$(x_0, y_0, z_0) = (x(u_0, v_0), y(u_0, v_0), z(u_0, v_0))$$

is given by

$$\mathbf{N} = \mathbf{r}_u(u_0, v_0) \times \mathbf{r}_v(u_0, v_0) = \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ \frac{\partial x}{\partial u} & \frac{\partial y}{\partial u} & \frac{\partial z}{\partial u} \\ \frac{\partial x}{\partial v} & \frac{\partial y}{\partial v} & \frac{\partial z}{\partial v} \end{vmatrix}.$$

Figure 15.40 shows the normal vector $\mathbf{r}_u \times \mathbf{r}_v$. The vector $\mathbf{r}_v \times \mathbf{r}_u$ is also normal to S and points in the opposite direction.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 5 **Finding a Tangent Plane to a Parametric Surface**

Find an equation of the tangent plane to the paraboloid

$$\mathbf{r}(u, v) = u\mathbf{i} + v\mathbf{j} + (u^2 + v^2)\mathbf{k}$$

at the point $(1, 2, 5)$.



Figure 15.41

Solution The point in the uv-plane that is mapped to the point $(x, y, z) = (1, 2, 5)$ is $(u, v) = (1, 2)$. The partial derivatives of $\mathbf{r}$ are

$$\mathbf{r}_u = \mathbf{i} + 2u\mathbf{k} \quad \text{and} \quad \mathbf{r}_v = \mathbf{j} + 2v\mathbf{k}.$$

The normal vector is given by

$$\mathbf{r}_u \times \mathbf{r}_v = \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ 1 & 0 & 2u \\ 0 & 1 & 2v \end{vmatrix} = -2u\mathbf{i} - 2v\mathbf{j} + \mathbf{k}$$

which implies that the normal vector at $(1, 2, 5)$ is

$$\mathbf{r}_u \times \mathbf{r}_v = -2\mathbf{i} - 4\mathbf{j} + \mathbf{k}.$$

So, an equation of the tangent plane at $(1, 2, 5)$ is

$$-2(x - 1) - 4(y - 2) + (z - 5) = 0$$
$$-2x - 4y + z = -5.$$

The tangent plane is shown in Figure 15.41.

Area of a Parametric Surface

To define the area of a parametric surface, you can use a development that is similar to that given in Section 14.5. Begin by constructing an inner partition of D consisting of n rectangles, where the area of the ith rectangle D_i is $\Delta A_i = \Delta u_i \Delta v_i$, as shown in Figure 15.42. In each D_i, let (u_i, v_i) be the point that is closest to the origin. At the point $(x_i, y_i, z_i) = (x(u_i, v_i), y(u_i, v_i), z(u_i, v_i))$ on the surface S, construct a tangent plane T_i. The area of the portion of S that corresponds to D_i, ΔS_i, can be approximated by a parallelogram ΔT_i in the tangent plane. That is, $\Delta T_i \approx \Delta S_i$. So, the surface area of S is given by $\Sigma\, \Delta S_i \approx \Sigma\, \Delta T_i$. The area of the parallelogram in the tangent plane is

$$\text{Area of } \Delta T_i = \|\Delta u_i \mathbf{r}_u \times \Delta v_i \mathbf{r}_v\| = \|\mathbf{r}_u \times \mathbf{r}_v\|\, \Delta u_i \Delta v_i$$

which leads to the next definition.





Figure 15.42

Area of a Parametric Surface

Let S be a smooth parametric surface

$$\mathbf{r}(u, v) = x(u, v)\mathbf{i} + y(u, v)\mathbf{j} + z(u, v)\mathbf{k}$$

defined over an open region D in the uv-plane. If each point on the surface S corresponds to exactly one point in the domain D, then the **surface area** of S is given by

$$\text{Surface area} = \iint_S dS = \iint_D \|\mathbf{r}_u \times \mathbf{r}_v\|\, dA$$

where

$$\mathbf{r}_u = \frac{\partial x}{\partial u}\mathbf{i} + \frac{\partial y}{\partial u}\mathbf{j} + \frac{\partial z}{\partial u}\mathbf{k} \quad \text{and} \quad \mathbf{r}_v = \frac{\partial x}{\partial v}\mathbf{i} + \frac{\partial y}{\partial v}\mathbf{j} + \frac{\partial z}{\partial v}\mathbf{k}.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

For a surface S given by $z = f(x, y)$, this formula for surface area corresponds to that given in Section 14.5. To show this, parametrize the surface using the vector-valued function $\mathbf{r}(x, y) = x\mathbf{i} + y\mathbf{j} + f(x, y)\mathbf{k}$ defined over the region R in the xy-plane. Using $\mathbf{r}_x = \mathbf{i} + f_x(x, y)\mathbf{k}$ and $\mathbf{r}_y = \mathbf{j} + f_y(x, y)\mathbf{k}$, you have

$$\mathbf{r}_x \times \mathbf{r}_y = \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ 1 & 0 & f_x(x, y) \\ 0 & 1 & f_y(x, y) \end{vmatrix} = -f_x(x, y)\mathbf{i} - f_y(x, y)\mathbf{j} + \mathbf{k}$$

and

$$\|\mathbf{r}_x \times \mathbf{r}_y\| = \sqrt{[f_x(x, y)]^2 + [f_y(x, y)]^2 + 1}.$$

This implies that the surface area of S is

$$\begin{aligned} \text{Surface area} &= \iint_R \|\mathbf{r}_x \times \mathbf{r}_y\| \, dA \\ &= \iint_R \sqrt{1 + [f_x(x, y)]^2 + [f_y(x, y)]^2} \, dA. \end{aligned}$$

EXAMPLE 6 Finding Surface Area

Because of high surface gravity, the shape of a neutron star is almost a perfect sphere. Using the surface area along with other data, scientists can estimate the mass and radius of the star.

Find the surface area of the unit sphere

$$\mathbf{r}(u, v) = \sin u \cos v\mathbf{i} + \sin u \sin v\mathbf{j} + \cos u\mathbf{k}$$

where the domain D is $0 \le u \le \pi$ and $0 \le v \le 2\pi$.

Solution Begin by calculating $\mathbf{r}_u$ and $\mathbf{r}_v$.

$$\mathbf{r}_u = \cos u \cos v\mathbf{i} + \cos u \sin v\mathbf{j} - \sin u\mathbf{k}$$
$$\mathbf{r}_v = -\sin u \sin v\mathbf{i} + \sin u \cos v\mathbf{j}$$

The cross product of these two vectors is

$$\begin{aligned} \mathbf{r}_u \times \mathbf{r}_v &= \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ \cos u \cos v & \cos u \sin v & -\sin u \\ -\sin u \sin v & \sin u \cos v & 0 \end{vmatrix} \\ &= \sin^2 u \cos v\mathbf{i} + \sin^2 u \sin v\mathbf{j} + \sin u \cos u\mathbf{k} \end{aligned}$$

which implies that

$$\begin{aligned} \|\mathbf{r}_u \times \mathbf{r}_v\| &= \sqrt{(\sin^2 u \cos v)^2 + (\sin^2 u \sin v)^2 + (\sin u \cos u)^2} \\ &= \sqrt{\sin^4 u + \sin^2 u \cos^2 u} \\ &= \sqrt{\sin^2 u} \\ &= \sin u. \qquad \sin u > 0 \text{ for } 0 \le u \le \pi \end{aligned}$$

Finally, the surface area of the sphere is

$$\begin{aligned} A &= \iint_D \|\mathbf{r}_u \times \mathbf{r}_v\| \, dA \\ &= \int_0^{2\pi} \int_0^{\pi} \sin u \, du \, dv \\ &= \int_0^{2\pi} 2 \, dv \\ &= 4\pi. \end{aligned}$$

The surface in Example 6 does not quite fulfill the hypothesis that each point on the surface corresponds to exactly one point in D. For this surface, $\mathbf{r}(u, 0) = \mathbf{r}(u, 2\pi)$ for any fixed value of u. However, because the overlap consists of only a semicircle (which has no area), you can still apply the formula for the area of a parametric surface.

Catmando/Shutterstock.com

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 15.43

EXAMPLE 7 Finding Surface Area

Find the surface area of the torus given by

$$\mathbf{r}(u, v) = (2 + \cos u)\cos v\mathbf{i} + (2 + \cos u)\sin v\mathbf{j} + \sin u\mathbf{k}$$

where the domain D is given by $0 \le u \le 2\pi$ and $0 \le v \le 2\pi$. (See Figure 15.43.)

Solution Begin by calculating $\mathbf{r}_u$ and $\mathbf{r}_v$.

$$\mathbf{r}_u = -\sin u \cos v\mathbf{i} - \sin u \sin v\mathbf{j} + \cos u\mathbf{k}$$
$$\mathbf{r}_v = -(2 + \cos u)\sin v\mathbf{i} + (2 + \cos u)\cos v\mathbf{j}$$

The cross product of these two vectors is

$$\mathbf{r}_u \times \mathbf{r}_v = \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ -\sin u \cos v & -\sin u \sin v & \cos u \\ -(2 + \cos u)\sin v & (2 + \cos u)\cos v & 0 \end{vmatrix}$$
$$= -(2 + \cos u)(\cos v \cos u\mathbf{i} + \sin v \cos u\mathbf{j} + \sin u\mathbf{k})$$

which implies that

$$\begin{aligned} \|\mathbf{r}_u \times \mathbf{r}_v\| &= (2 + \cos u)\sqrt{(\cos v \cos u)^2 + (\sin v \cos u)^2 + \sin^2 u} \\ &= (2 + \cos u)\sqrt{\cos^2 u(\cos^2 v + \sin^2 v) + \sin^2 u} \\ &= (2 + \cos u)\sqrt{\cos^2 u + \sin^2 u} \\ &= 2 + \cos u. \end{aligned}$$

Finally, the surface area of the torus is

$$\begin{aligned} A &= \iint_D \|\mathbf{r}_u \times \mathbf{r}_v\|\, dA \\ &= \int_0^{2\pi}\int_0^{2\pi} (2 + \cos u)\, du\, dv \\ &= \int_0^{2\pi} 4\pi\, dv \\ &= 8\pi^2. \end{aligned}$$

■

Exploration

For the torus in Example 7, describe the function $\mathbf{r}(u, v)$ for fixed u. Then describe the function $\mathbf{r}(u, v)$ for fixed v.

For a surface of revolution, you can show that the formula for surface area given in Section 7.4 is equivalent to the formula given in this section. For instance, suppose f is a nonnegative function such that f' is continuous over the interval $[a, b]$. Let S be the surface of revolution formed by revolving the graph of f, where $a \le x \le b$, about the x-axis. From Section 7.4, you know that the surface area is given by

$$\text{Surface area} = 2\pi\int_a^b f(x)\sqrt{1 + [f'(x)]^2}\, dx.$$

To represent S parametrically, let

$$x = u, \quad y = f(u)\cos v, \quad \text{and} \quad z = f(u)\sin v$$

where $a \le u \le b$ and $0 \le v \le 2\pi$. Then

$$\mathbf{r}(u, v) = u\mathbf{i} + f(u)\cos v\mathbf{j} + f(u)\sin v\mathbf{k}.$$

Try showing that the formula

$$\text{Surface area} = \iint_D \|\mathbf{r}_u \times \mathbf{r}_v\|\, dA$$

is equivalent to the formula given above (see Exercise 58).

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

15.5 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain how a parametric surface is represented by a vector-valued function and how the vector-valued function is used to sketch the parametric surface.
2. A surface S is represented by $z = f(x, y)$. What are the parametric equations for S?

Matching In Exercises 3–8, match the vector-valued function with its graph. [The graphs are labeled (a), (b), (c), (d), (e), and (f).]

(a)



(b)



(c)



(d)



(e)



(f)



3. $\mathbf{r}(u, v) = u\mathbf{i} + v\mathbf{j} + uv\mathbf{k}$
4. $\mathbf{r}(u, v) = u\cos v\mathbf{i} + u\sin v\mathbf{j} + u\mathbf{k}$
5. $\mathbf{r}(u, v) = u\mathbf{i} + \frac{1}{2}(u + v)\mathbf{j} + v\mathbf{k}$
6. $\mathbf{r}(u, v) = v\mathbf{i} + \cos u\mathbf{j} + \sin u\mathbf{k}$
7. $\mathbf{r}(u, v) = 2\cos v\cos u\mathbf{i} + 2\cos v\sin u\mathbf{j} + 2\sin v\mathbf{k}$
8. $\mathbf{r}(u, v) = u\mathbf{i} + \frac{1}{4}v^3\mathbf{j} + v\mathbf{k}$

Sketching a Parametric Surface In Exercises 9–12, find the rectangular equation for the surface by eliminating the parameters from the vector-valued function. Identify the surface and sketch its graph.

9. $\mathbf{r}(u, v) = u\mathbf{i} + v\mathbf{j} + \frac{v}{2}\mathbf{k}$
10. $\mathbf{r}(u, v) = 2u\cos v\mathbf{i} + 2u\sin v\mathbf{j} + \frac{1}{2}u^2\mathbf{k}$
11. $\mathbf{r}(u, v) = 2\cos u\mathbf{i} + v\mathbf{j} + 2\sin u\mathbf{k}$
12. $\mathbf{r}(u, v) = 3\cos v\cos u\mathbf{i} + 3\cos v\sin u\mathbf{j} + 5\sin v\mathbf{k}$

Graphing a Parametric Surface In Exercises 13–18, use a graphing utility to graph the surface represented by the vector-valued function.

13. $\mathbf{r}(u, v) = 2u\cos v\mathbf{i} + 2u\sin v\mathbf{j} + u^4\mathbf{k}$
$0 \le u \le 1, \quad 0 \le v \le 2\pi$
14. $\mathbf{r}(u, v) = 2\cos v\cos u\mathbf{i} + 4\cos v\sin u\mathbf{j} + \sin v\mathbf{k}$
$0 \le u \le 2\pi, \quad 0 \le v \le 2\pi$
15. $\mathbf{r}(u, v) = 2\sinh u\cos v\mathbf{i} + \sinh u\sin v\mathbf{j} + \cosh u\mathbf{k}$
$0 \le u \le 2, \quad 0 \le v \le 2\pi$
16. $\mathbf{r}(u, v) = 2u\cos v\mathbf{i} + 2u\sin v\mathbf{j} + v\mathbf{k}$
$0 \le u \le 1, \quad 0 \le v \le 3\pi$
17. $\mathbf{r}(u, v) = (u - \sin u)\cos v\mathbf{i} + (1 - \cos u)\sin v\mathbf{j} + u\mathbf{k}$
$0 \le u \le \pi, \quad 0 \le v \le 2\pi$
18. $\mathbf{r}(u, v) = \cos^3 u\cos v\mathbf{i} + \sin^3 u\sin v\mathbf{j} + u\mathbf{k}$
$0 \le u \le \frac{\pi}{2}, \quad 0 \le v \le 2\pi$

Representing a Surface Parametrically In Exercises 19–28, find a vector-valued function whose graph is the indicated surface.

19. The plane $z = 3y$
20. The plane $x + y + z = 6$
21. The cone $y = \sqrt{4x^2 + 9z^2}$
22. The cone $x = \sqrt{16y^2 + z^2}$
23. The cylinder $x^2 + y^2 = 25$
24. The cylinder $4x^2 + y^2 = 16$
25. The paraboloid $x = y^2 + z^2 + 7$
26. The ellipsoid $\frac{x^2}{9} + \frac{y^2}{4} + \frac{z^2}{1} = 1$
27. The part of the plane $z = 4$ that lies inside the cylinder $x^2 + y^2 = 9$
28. The part of the paraboloid $z = x^2 + y^2$ that lies inside the cylinder $x^2 + y^2 = 9$

Representing a Surface of Revolution Parametrically In Exercises 29–34, write a set of parametric equations for the surface of revolution obtained by revolving the graph of the function about the given axis.

	Function	Axis of Revolution
29.	$y = \frac{x}{2}, \quad 0 \le x \le 6$	x-axis
30.	$y = \sqrt{x}, \quad 0 \le x \le 4$	x-axis
31.	$x = \sin z, \quad 0 \le z \le \pi$	z-axis
32.	$x = z - 2, \quad 2 \le z \le 5$	z-axis
33.	$z = \cos^2 y, \quad \frac{\pi}{2} \le y \le \pi$	y-axis
34.	$z = y^2 + 1, \quad 0 \le y \le 2$	y-axis

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Finding a Tangent Plane **In Exercises 35–38, find an equation of the tangent plane to the surface represented by the vector-valued function at the given point.**

35. $\mathbf{r}(u, v) = 3\cos v\cos u\mathbf{i} + 2\cos v\sin u\mathbf{j} + 4\sin v\mathbf{k}$, $(0, \sqrt{3}, 2)$



Figure for 35



Figure for 36

36. $\mathbf{r}(u, v) = u\mathbf{i} + v\mathbf{j} + \sqrt{uv}\mathbf{k}$, $(1, 1, 1)$

37. $\mathbf{r}(u, v) = 2u\cos v\mathbf{i} + 3u\sin v\mathbf{j} + u^2\mathbf{k}$, $(0, 6, 4)$



38. $\mathbf{r}(u, v) = 2u\cosh v\mathbf{i} + 2u\sinh v\mathbf{j} + \frac{1}{2}u^2\mathbf{k}$, $(-4, 0, 2)$



Finding Surface Area **In Exercises 39–44, find the area of the surface over the given region. Use a graphing utility to verify your results.**

39. $\mathbf{r}(u, v) = 4u\mathbf{i} - v\mathbf{j} + v\mathbf{k}$, $0 \le u \le 2$, $0 \le v \le 1$

40. $\mathbf{r}(u, v) = 2u\cos v\mathbf{i} + 2u\sin v\mathbf{j} + u^2\mathbf{k}$, $0 \le u \le 2$, $0 \le v \le 2\pi$

41. $\mathbf{r}(u, v) = au\cos v\mathbf{i} + au\sin v\mathbf{j} + u\mathbf{k}$, $0 \le u \le b$, $0 \le v \le 2\pi$

42. $\mathbf{r}(u, v) = (a + b\cos v)\cos u\mathbf{i} + (a + b\cos v)\sin u\mathbf{j} + b\sin v\mathbf{k}$, $a > b$, $0 \le u \le 2\pi$, $0 \le v \le 2\pi$

43. $\mathbf{r}(u, v) = \sqrt{u}\cos v\mathbf{i} + \sqrt{u}\sin v\mathbf{j} + u\mathbf{k}$, $0 \le u \le 4$, $0 \le v \le 2\pi$

44. $\mathbf{r}(u, v) = \sin u\cos v\mathbf{i} + u\mathbf{j} + \sin u\sin v\mathbf{k}$, $0 \le u \le \pi$, $0 \le v \le 2\pi$

Exploring Concepts

In Exercises 45–48, determine how the graph of the surface $\mathbf{s}(u, v)$ differs from the graph of the surface $\mathbf{r}(u, v) = u\cos v\mathbf{i} + u\sin v\mathbf{j} + u^2\mathbf{k}$, where $0 \le u \le 2$ and $0 \le v \le 2\pi$, as shown in the figure. (It is not necessary to graph s.)



45. $\mathbf{s}(u, v) = u\cos v\mathbf{i} + u\sin v\mathbf{j} - u^2\mathbf{k}$
$0 \le u \le 2, \quad 0 \le v \le 2\pi$

46. $\mathbf{s}(u, v) = u\cos v\mathbf{i} + u^2\mathbf{j} + u\sin v\mathbf{k}$
$0 \le u \le 2, \quad 0 \le v \le 2\pi$

47. $\mathbf{s}(u, v) = u\cos v\mathbf{i} + u\sin v\mathbf{j} + u^2\mathbf{k}$
$0 \le u \le 3, \quad 0 \le v \le 2\pi$

48. $\mathbf{s}(u, v) = 4u\cos v\mathbf{i} + 4u\sin v\mathbf{j} + u^2\mathbf{k}$
$0 \le u \le 2, \quad 0 \le v \le 2\pi$

49. Representing a Cone Parametrically Show that the cone in Example 3 can be represented parametrically by $\mathbf{r}(u, v) = u\cos v\mathbf{i} + u\sin v\mathbf{j} + u\mathbf{k}$, where $u \ge 0$ and $0 \le v \le 2\pi$.

50. HOW DO YOU SEE IT? The figures below are graphs of $\mathbf{r}(u, v) = u\mathbf{i} + \sin u\cos v\mathbf{j} + \sin u\sin v\mathbf{k}$, where $0 \le u \le \pi/2$ and $0 \le v \le 2\pi$. Match each of the four graphs with the point in space from which the surface is viewed.

(a)



(b)



(c)



(d)



(i) $(10, 0, 0)$ (ii) $(-10, 10, 0)$

(iii) $(0, 10, 0)$ (iv) $(10, 10, 10)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

51. Astroidal Sphere An equation of an **astroidal sphere** in x, y, and z is

$$x^{2/3} + y^{2/3} + z^{2/3} = a^{2/3}.$$

A graph of an astroidal sphere is shown below. Show that this surface can be represented parametrically by

$$\mathbf{r}(u, v) = a \sin^3 u \cos^3 v\mathbf{i} + a \sin^3 u \sin^3 v\mathbf{j} + a \cos^3 u\mathbf{k}$$

where $0 \le u \le \pi$ and $0 \le v \le 2\pi$.



52. Different Views of a Surface Use a graphing utility to graph the vector-valued function

$$\mathbf{r}(u, v) = u \cos v\mathbf{i} + u \sin v\mathbf{j} + v\mathbf{k}, \quad 0 \le u \le \pi, \quad 0 \le v \le \pi$$

from each of the points $(10, 0, 0)$, $(0, 0, 10)$, and $(10, 10, 10)$.

53. Investigation Use a graphing utility to graph the torus

$$\mathbf{r}(u, v) = (a + b \cos v) \cos u\mathbf{i} + (a + b \cos v) \sin u\mathbf{j} + b \sin v\mathbf{k}$$

for each set of values of a and b, where $0 \le u \le 2\pi$ and $0 \le v \le 2\pi$. Use the results to describe the effects of a and b on the shape of the torus.

(a) $a = 4, \quad b = 1$

(b) $a = 4, \quad b = 2$

(c) $a = 8, \quad b = 1$

(d) $a = 8, \quad b = 3$

54. Investigation Consider the function in Exercise 16.

(a) Sketch a graph of the function where u is held constant at $u = 1$. Identify the graph.

(b) Sketch a graph of the function where v is held constant at $v = 2\pi/3$. Identify the graph.

(c) Assume that a surface is represented by the vector-valued function $\mathbf{r} = \mathbf{r}(u, v)$. What generalization can you make about the graph of the function when one of the parameters is held constant?

55. Surface Area The surface of the dome on a new museum is given by

$$\mathbf{r}(u, v) = 20 \sin u \cos v\mathbf{i} + 20 \sin u \sin v\mathbf{j} + 20 \cos u\mathbf{k}$$

where $0 \le u \le \pi/3$, $0 \le v \le 2\pi$, and $\mathbf{r}$ is in meters. Find the surface area of the dome.

56. Hyperboloid Find a vector-valued function for the hyperboloid

$$x^2 + y^2 - z^2 = 1$$

and determine the tangent plane at $(1, 0, 0)$.

57. Area Use a graphing utility to graph one turn of the spiral ramp $\mathbf{r}(u, v) = u \cos v\mathbf{i} + u \sin v\mathbf{j} + 2v\mathbf{k}$, where $0 \le u \le 3$ and $0 \le v \le 2\pi$. Then analytically find the area of one turn of the spiral ramp.

58. Surface Area Let f be a nonnegative function such that f' is continuous over the interval $[a, b]$. Let S be the surface of revolution formed by revolving the graph of f, where $a \le x \le b$, about the x-axis. Let $x = u$, $y = f(u) \cos v$, and $z = f(u) \sin v$, where $a \le u \le b$ and $0 \le v \le 2\pi$. Then S is represented parametrically by

$$\mathbf{r}(u, v) = u\mathbf{i} + f(u) \cos v\mathbf{j} + f(u) \sin v\mathbf{k}.$$

Show that the following formulas are equivalent.

$$\text{Surface area} = 2\pi \int_a^b f(x)\sqrt{1 + [f'(x)]^2}\, dx$$

$$\text{Surface area} = \int_D \int \|\mathbf{r}_u \times \mathbf{r}_v\|\, dA$$

59. Parametric Surfaces The parametric equations

$$x = 3 + [7 - \cos(3u - 2v) - 2 \cos(3u + v)]\sin u$$

$$y = 3 + [7 - \cos(3u - 2v) - 2 \cos(3u + v)]\cos u$$

$$z = \sin(3u - 2v) + 2 \sin(3u + v)$$

where $-\pi \le u \le \pi$ and $-\pi \le v \le \pi$, represent the surface shown below. Create your own parametric surface using a graphing utility.

60. Möbius Strip The surface shown in the figure is called a **Möbius strip** and can be represented by the parametric equations

$$x = \left(a + u \cos\frac{v}{2}\right) \cos v, \quad y = \left(a + u \cos\frac{v}{2}\right) \sin v, \quad z = u \sin\frac{v}{2}$$

where $-1 \le u \le 1$, $0 \le v \le 2\pi$, and $a = 3$. Graph other Möbius strips for different values of a using a graphing utility.



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

15.6 Surface Integrals

GO DIGITAL

- Evaluate a surface integral as a double integral.
- Evaluate a surface integral for a parametric surface.
- Determine the orientation of a surface.
- Describe the concept of a flux integral.

Surface Integrals

The remainder of this chapter deals primarily with **surface integrals.** In this section, you will first consider surfaces given by $z = g(x, y)$. Then, you will consider more general surfaces given in parametric form.

Let S be a surface given by $z = g(x, y)$ and let R be its projection onto the xy-plane, as shown in Figure 15.44. Let g, g_x, and g_y be continuous at all points in R and let f be a scalar function defined on S. Employing the procedure used to find surface area in Section 14.5, evaluate f at (x_i, y_i, z_i) and form the sum

$$\sum_{i=1}^{n} f(x_i, y_i, z_i)\,\Delta S_i$$

where

$$\Delta S_i \approx \sqrt{1 + [g_x(x_i, y_i)]^2 + [g_y(x_i, y_i)]^2}\,\Delta A_i.$$

Provided the limit of this sum as $\|\Delta\|$ approaches 0 exists, the **surface integral of f over S** is defined as

$$\iint_S f(x, y, z)\,dS = \lim_{\|\Delta\|\to 0} \sum_{i=1}^{n} f(x_i, y_i, z_i)\,\Delta S_i.$$

This integral can be evaluated by a double integral.



Scalar function f assigns a number to each point of S.

Figure 15.44

THEOREM 15.10 Evaluating a Surface Integral

Let S be a surface given by $z = g(x, y)$ and let R be its projection onto the xy-plane. If g, g_x, and g_y are continuous on R, and f is continuous on S, then the surface integral of f over S is

$$\iint_S f(x, y, z)\,dS = \iint_R f(x, y, g(x, y))\sqrt{1 + [g_x(x, y)]^2 + [g_y(x, y)]^2}\,dA.$$

For surfaces described by functions of x and z (or y and z), you can make the following adjustments to Theorem 15.10. If S is the graph of $y = g(x, z)$, and R is its projection onto the xz-plane, then

$$\iint_S f(x, y, z)\,dS = \iint_R f(x, g(x, z), z)\sqrt{1 + [g_x(x, z)]^2 + [g_z(x, z)]^2}\,dA.$$

If S is the graph of $x = g(y, z)$, and R is its projection onto the yz-plane, then

$$\iint_S f(x, y, z)\,dS = \iint_R f(g(y, z), y, z)\sqrt{1 + [g_y(y, z)]^2 + [g_z(y, z)]^2}\,dA.$$

If $f(x, y, z) = 1$, the surface integral over S yields the surface area of S. For instance, suppose the surface S is the plane given by $z = x$, where $0 \le x \le 1$ and $0 \le y \le 1$. The surface area of S is $\sqrt{2}$ square units. Try verifying that

$$\iint_S f(x, y, z)\,dS = \sqrt{2}.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 1 Evaluating a Surface Integral

Evaluate the surface integral

$$\iint_S (y^2 + 2yz)\, dS$$

where S is the first-octant portion of the plane

$$2x + y + 2z = 6.$$

Solution Begin by writing S as

$$z = g(x, y) = \frac{1}{2}(6 - 2x - y).$$

Using the partial derivatives $g_x(x, y) = -1$ and $g_y(x, y) = -\frac{1}{2}$, you can write

$$\sqrt{1 + [g_x(x, y)]^2 + [g_y(x, y)]^2} = \sqrt{1 + 1 + \frac{1}{4}} = \frac{3}{2}.$$



Figure 15.45

Using Figure 15.45 and Theorem 15.10, you obtain

$$\begin{aligned}
\iint_S (y^2 + 2yz)\, dS &= \iint_R f(x, y, g(x, y))\sqrt{1 + [g_x(x, y)]^2 + [g_y(x, y)]^2}\, dA \\
&= \iint_R \left[y^2 + 2y\left(\frac{1}{2}\right)(6 - 2x - y)\right]\left(\frac{3}{2}\right) dA \\
&= 3\int_0^3 \int_0^{2(3-x)} y(3 - x)\, dy\, dx && \text{Convert to iterated integral.} \\
&= 3\int_0^3 \frac{y^2}{2}(3 - x)\Big]_0^{2(3-x)}\, dx && \text{Integrate with respect to } y. \\
&= 6\int_0^3 (3 - x)^3\, dx \\
&= -\frac{3}{2}(3 - x)^4\Big]_0^3 && \text{Integrate with respect to } x. \\
&= \frac{243}{2}.
\end{aligned}$$



Figure 15.46

An alternative solution to Example 1 would be to project S onto the yz-plane, as shown in Figure 15.46. Then $x = \frac{1}{2}(6 - y - 2z)$, and

$$\sqrt{1 + [g_y(y, z)]^2 + [g_z(y, z)]^2} = \sqrt{1 + \frac{1}{4} + 1} = \frac{3}{2}.$$

So, the surface integral is

$$\begin{aligned}
\iint_S (y^2 + 2yz)\, dS &= \iint_R f(g(y, z), y, z)\sqrt{1 + [g_y(y, z)]^2 + [g_z(y, z)]^2}\, dA \\
&= \int_0^6 \int_0^{(6-y)/2} (y^2 + 2yz)\left(\frac{3}{2}\right) dz\, dy \\
&= \frac{3}{8}\int_0^6 (36y - y^3)\, dy \\
&= \frac{243}{2}.
\end{aligned}$$

Try reworking Example 1 by projecting S onto the xz-plane.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

In Example 1, you could have projected the surface S onto any one of the three coordinate planes. In Example 2, S is a portion of a cylinder centered about the x-axis, and you can project it onto either the xz-plane or the xy-plane.

EXAMPLE 2 Evaluating a Surface Integral

See LarsonCalculus.com for an interactive version of this type of example.



Figure 15.47

Evaluate the surface integral

$$\iint_S (x + z)\, dS$$

where S is the first-octant portion of the cylinder

$$y^2 + z^2 = 9$$

between $x = 0$ and $x = 4$, as shown in Figure 15.47.

Solution Project S onto the xy-plane so that

$$z = g(x, y) = \sqrt{9 - y^2}$$

and obtain

$$\sqrt{1 + [g_x(x, y)]^2 + [g_y(x, y)]^2} = \sqrt{1 + \left(\frac{-y}{\sqrt{9 - y^2}}\right)^2} = \frac{3}{\sqrt{9 - y^2}}.$$

Theorem 15.10 does not apply directly, because g_y is not continuous when $y = 3$. However, you can apply Theorem 15.10 for $0 \le b < 3$ and then take the limit as b approaches 3, as follows.

$$\begin{aligned}
\iint_S (x + z)\, dS &= \lim_{b \to 3^-} \int_0^b \int_0^4 \left(x + \sqrt{9 - y^2}\right) \frac{3}{\sqrt{9 - y^2}}\, dx\, dy \\
&= \lim_{b \to 3^-} 3 \int_0^b \int_0^4 \left(\frac{x}{\sqrt{9 - y^2}} + 1\right) dx\, dy \\
&= \lim_{b \to 3^-} 3 \int_0^b \left[\frac{x^2}{2\sqrt{9 - y^2}} + x\right]_0^4 dy && \text{Integrate with respect to } x. \\
&= \lim_{b \to 3^-} 3 \int_0^b \left(\frac{8}{\sqrt{9 - y^2}} + 4\right) dy \\
&= \lim_{b \to 3^-} 3 \left[4y + 8 \arcsin \frac{y}{3}\right]_0^b && \text{Integrate with respect to } y. \\
&= \lim_{b \to 3^-} 3 \left(4b + 8 \arcsin \frac{b}{3}\right) \\
&= 36 + 24\left(\frac{\pi}{2}\right) && \text{Evaluate limit.} \\
&= 36 + 12\pi
\end{aligned}$$

TECHNOLOGY Some graphing utilities are capable of evaluating improper integrals. If you have access to a graphing utility with this feature, use it to evaluate the improper integral

$$\int_0^3 \int_0^4 \left(x + \sqrt{9 - y^2}\right) \frac{3}{\sqrt{9 - y^2}}\, dx\, dy.$$

Do you obtain the same result as in Example 2?

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

You have already learned that when the function f defined on the surface S is simply $f(x, y, z) = 1$, the surface integral yields the *surface area* of S.

$$\text{Area of surface} = \iint_S 1 \, dS$$

If S is a lamina of variable density and $\rho(x, y, z)$ is the density at the point (x, y, z), then the *mass* of the lamina is given by

$$\text{Mass of lamina} = \iint_S \rho(x, y, z) \, dS.$$

EXAMPLE 3 Finding the Mass of a Surface Lamina

A cone-shaped surface lamina S is given by

$$z = 4 - 2\sqrt{x^2 + y^2}, \quad 0 \le z \le 4$$

as shown in Figure 15.48. At each point on S, the density is proportional to the distance between the point and the z-axis. Find the mass m of the lamina.



Figure 15.48

Solution Projecting S onto the xy-plane produces

$$S: \; z = 4 - 2\sqrt{x^2 + y^2} = g(x, y), \quad 0 \le z \le 4$$
$$R: \; x^2 + y^2 \le 4$$

with a density of

$$\rho(x, y, z) = k\sqrt{x^2 + y^2}$$

where k is the constant of proportionality. Using a surface integral, you can find the mass to be

$$\begin{aligned}
m &= \iint_S \rho(x, y, z) \, dS \\
&= \iint_R k\sqrt{x^2 + y^2}\sqrt{1 + [g_x(x, y)]^2 + [g_y(x, y)]^2} \, dA \\
&= k\iint_R \sqrt{x^2 + y^2}\sqrt{1 + \frac{4x^2}{x^2 + y^2} + \frac{4y^2}{x^2 + y^2}} \, dA \\
&= k\iint_R \sqrt{5}\sqrt{x^2 + y^2} \, dA \\
&= k\int_0^{2\pi}\int_0^2 \left(\sqrt{5}r\right) r \, dr \, d\theta \qquad \text{Polar coordinates} \\
&= \frac{\sqrt{5}k}{3}\int_0^{2\pi} r^3\Big]_0^2 \, d\theta \qquad \text{Integrate with respect to } r. \\
&= \frac{8\sqrt{5}k}{3}\int_0^{2\pi} d\theta \\
&= \frac{8\sqrt{5}k}{3}\Big[\theta\Big]_0^{2\pi} \qquad \text{Integrate with respect to } \theta. \\
&= \frac{16\sqrt{5}k\pi}{3}.
\end{aligned}$$

TECHNOLOGY Use a graphing utility to confirm the result shown in Example 3.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Parametric Surfaces and Surface Integrals

For a surface S given by the vector-valued function

$$\mathbf{r}(u, v) = x(u, v)\mathbf{i} + y(u, v)\mathbf{j} + z(u, v)\mathbf{k}$$ Parametric surface

defined over a region D in the uv-plane, it can be shown that the surface integral of $f(x, y, z)$ over S is given by

$$\iint_S f(x, y, z)\, dS = \iint_D f(x(u, v), y(u, v), z(u, v))\|\mathbf{r}_u(u, v) \times \mathbf{r}_v(u, v)\|\, dA.$$

Note the similarity to a line integral over a space curve C.

$$\int_C f(x, y, z)\, ds = \int_a^b f(x(t), y(t), z(t))\|\mathbf{r}'(t)\|\, dt$$ Line integral

Also, notice that ds and dS can be written as

$$ds = \|\mathbf{r}'(t)\|\, dt \quad \text{and} \quad dS = \|\mathbf{r}_u(u, v) \times \mathbf{r}_v(u, v)\|\, dA.$$

EXAMPLE 4 Evaluating a Surface Integral

Example 2 demonstrated an evaluation of the surface integral

$$\iint_S (x + z)\, dS$$

where S is the first-octant portion of the cylinder

$$y^2 + z^2 = 9$$

between $x = 0$ and $x = 4$, as shown in Figure 15.49. Reevaluate this integral in parametric form.



Figure 15.49

Solution In parametric form, the surface is given by

$$\mathbf{r}(x, \theta) = x\mathbf{i} + 3\cos\theta\mathbf{j} + 3\sin\theta\mathbf{k}$$

where $0 \le x \le 4$ and $0 \le \theta \le \pi/2$. To evaluate the surface integral in parametric form, begin by calculating the following.

$$\mathbf{r}_x = \mathbf{i}$$

$$\mathbf{r}_\theta = -3\sin\theta\mathbf{j} + 3\cos\theta\mathbf{k}$$

$$\mathbf{r}_x \times \mathbf{r}_\theta = \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ 1 & 0 & 0 \\ 0 & -3\sin\theta & 3\cos\theta \end{vmatrix} = -3\cos\theta\mathbf{j} - 3\sin\theta\mathbf{k}$$

$$\|\mathbf{r}_x \times \mathbf{r}_\theta\| = \sqrt{9\cos^2\theta + 9\sin^2\theta} = 3$$

So, the surface integral can be evaluated as follows.

$$\begin{aligned} \iint_D (x + 3\sin\theta)3\, dA &= \int_0^4 \int_0^{\pi/2} (3x + 9\sin\theta)\, d\theta\, dx \\ &= \int_0^4 \left[3x\theta - 9\cos\theta\right]_0^{\pi/2} dx \\ &= \int_0^4 \left(\frac{3\pi}{2}x + 9\right) dx \\ &= \left[\frac{3\pi}{4}x^2 + 9x\right]_0^4 \\ &= 12\pi + 36 \end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Orientation of a Surface

Unit normal vectors are used to induce an orientation to a surface S in space. A surface is **orientable** when a unit normal vector $\mathbf{N}$ can be defined at every nonboundary point of S in such a way that the normal vectors vary continuously over the surface S. The surface S is called an **oriented surface.**

An orientable surface S has two distinct sides. So, when you orient a surface, you are selecting one of the two possible unit normal vectors. For a closed surface such as a sphere, it is customary to choose the unit normal vector $\mathbf{N}$ to be the one that points outward from the sphere.

Most common surfaces, such as spheres, paraboloids, ellipses, and planes, are orientable. (See Exercise 43 for an example of a surface that is *not* orientable.) Moreover, for an orientable surface, the gradient provides a convenient way to find a unit normal vector. That is, for an orientable surface S given by

$$z = g(x, y)$$ Orientable surface

let

$$G(x, y, z) = z - g(x, y).$$

Then, S can be oriented by either the unit normal vector

$$\mathbf{N} = \frac{\nabla G(x, y, z)}{\|\nabla G(x, y, z)\|} = \frac{-g_x(x, y)\mathbf{i} - g_y(x, y)\mathbf{j} + \mathbf{k}}{\sqrt{1 + [g_x(x, y)]^2 + [g_y(x, y)]^2}}$$ Upward unit normal vector

or the unit normal vector

$$\mathbf{N} = \frac{-\nabla G(x, y, z)}{\|\nabla G(x, y, z)\|} = \frac{g_x(x, y)\mathbf{i} + g_y(x, y)\mathbf{j} - \mathbf{k}}{\sqrt{1 + [g_x(x, y)]^2 + [g_y(x, y)]^2}}$$ Downward unit normal vector

as shown in Figure 15.50. If the smooth orientable surface S is given in parametric form by

$$\mathbf{r}(u, v) = x(u, v)\mathbf{i} + y(u, v)\mathbf{j} + z(u, v)\mathbf{k}$$ Parametric surface

then the unit normal vectors are given by

$$\mathbf{N} = \frac{\mathbf{r}_u \times \mathbf{r}_v}{\|\mathbf{r}_u \times \mathbf{r}_v\|}$$ Upward unit normal vector

and

$$\mathbf{N} = \frac{\mathbf{r}_v \times \mathbf{r}_u}{\|\mathbf{r}_v \times \mathbf{r}_u\|}.$$ Downward unit normal vector

For an orientable surface given by

$$y = g(x, z) \quad \text{or} \quad x = g(y, z)$$

you can use the gradient

$$\nabla G(x, y, z) = -g_x(x, z)\mathbf{i} + \mathbf{j} - g_z(x, z)\mathbf{k}$$ $G(x, y, z) = y - g(x, z)$

or

$$\nabla G(x, y, z) = \mathbf{i} - g_y(y, z)\mathbf{j} - g_z(y, z)\mathbf{k}$$ $G(x, y, z) = x - g(y, z)$

to orient the surface.



Upward direction

S is oriented in an upward direction.



Downward direction

S is oriented in a downward direction.

Figure 15.50

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Flux Integrals



The velocity field **F** indicates the direction of the fluid flow.
Figure 15.51

One of the principal applications involving the vector form of a surface integral relates to the flow of a fluid through a surface. Consider an oriented surface S submerged in a fluid having a continuous velocity field $\mathbf{F}$. Let ΔS be the area of a small patch of the surface S over which $\mathbf{F}$ is nearly constant. Then the amount of fluid crossing this region per unit of time is approximated by the volume of the column of height $\mathbf{F} \cdot \mathbf{N}$, as shown in Figure 15.51. That is,

$$\begin{aligned}\Delta V &= (\text{height})(\text{area of base}) \\ &= (\mathbf{F} \cdot \mathbf{N})\, \Delta S.\end{aligned}$$

Consequently, the volume of fluid crossing the surface S per unit of time (called the **flux of F across *S***) is given by the surface integral in the next definition.

Definition of Flux Integral

Let $\mathbf{F}(x, y, z) = M\mathbf{i} + N\mathbf{j} + P\mathbf{k}$, where M, N, and P have continuous first partial derivatives on the surface S oriented by a unit normal vector $\mathbf{N}$. The **flux integral of F across *S*** is given by

$$\iint_S \mathbf{F} \cdot \mathbf{N}\, dS.$$

Geometrically, a flux integral is the surface integral over S of the *normal component* of $\mathbf{F}$. If $\rho(x, y, z)$ is the density of the fluid at (x, y, z), then the flux integral

$$\iint_S \rho \mathbf{F} \cdot \mathbf{N}\, dS$$

represents the *mass* of the fluid flowing across S per unit of time.

To evaluate a flux integral for a surface given by $z = g(x, y)$, let

$$G(x, y, z) = z - g(x, y).$$

Then $\mathbf{N}\, dS$ can be written as follows.

$$\begin{aligned}\mathbf{N}\, dS &= \frac{\nabla G(x, y, z)}{\|\nabla G(x, y, z)\|}\, dS \\ &= \frac{\nabla G(x, y, z)}{\sqrt{(g_x)^2 + (g_y)^2 + 1}} \sqrt{(g_x)^2 + (g_y)^2 + 1}\, dA \\ &= \nabla G(x, y, z)\, dA\end{aligned}$$

THEOREM 15.11 Evaluating a Flux Integral

Let S be an oriented surface given by $z = g(x, y)$, and let R be its projection onto the xy-plane.

$$\iint_S \mathbf{F} \cdot \mathbf{N}\, dS = \iint_R \mathbf{F} \cdot [-g_x(x, y)\mathbf{i} - g_y(x, y)\mathbf{j} + \mathbf{k}]\, dA \qquad \text{Oriented upward}$$

$$\iint_S \mathbf{F} \cdot \mathbf{N}\, dS = \iint_R \mathbf{F} \cdot [g_x(x, y)\mathbf{i} + g_y(x, y)\mathbf{j} - \mathbf{k}]\, dA \qquad \text{Oriented downward}$$

For the first integral, the surface is oriented upward, and for the second integral, the surface is oriented downward.

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 5 Using a Flux Integral to Find the Rate of Mass Flow

Let S be the portion of the paraboloid

$$z = g(x, y) = 4 - x^2 - y^2$$

lying above the xy-plane, oriented by an upward unit normal vector, as shown in Figure 15.52. A fluid of constant density ρ is flowing through the surface S according to the vector field

$$\mathbf{F}(x, y, z) = x\mathbf{i} + y\mathbf{j} + z\mathbf{k}.$$

Find the rate of mass flow through S.



Figure 15.52

Solution Note that S is oriented upward and the partial derivatives of g are

$$g_x(x, y) = -2x$$

and

$$g_y(x, y) = -2y.$$

So, the rate of mass flow through the surface S is

$$\begin{aligned}
\iint_S \rho\mathbf{F} \cdot \mathbf{N}\, dS &= \rho \iint_R \mathbf{F} \cdot [-g_x(x, y)\mathbf{i} - g_y(x, y)\mathbf{j} + \mathbf{k}]\, dA \\
&= \rho \iint_R [x\mathbf{i} + y\mathbf{j} + (4 - x^2 - y^2)\mathbf{k}] \cdot (2x\mathbf{i} + 2y\mathbf{j} + \mathbf{k})\, dA \\
&= \rho \iint_R [2x^2 + 2y^2 + (4 - x^2 - y^2)]\, dA \\
&= \rho \iint_R (4 + x^2 + y^2)\, dA \\
&= \rho \int_0^{2\pi} \int_0^2 (4 + r^2) r\, dr\, d\theta \qquad \text{Polar coordinates} \\
&= \rho \int_0^{2\pi} \left[2r^2 + \frac{r^4}{4} \right]_0^2 d\theta \\
&= \rho \int_0^{2\pi} 12\, d\theta \\
&= 24\pi\rho.
\end{aligned}$$

For an oriented upward surface S given by the vector-valued function

$$\mathbf{r}(u, v) = x(u, v)\mathbf{i} + y(u, v)\mathbf{j} + z(u, v)\mathbf{k} \qquad \text{Parametric surface}$$

defined over a region D in the uv-plane, you can define the flux integral of $\mathbf{F}$ across S as

$$\iint_S \mathbf{F} \cdot \mathbf{N}\, dS = \iint_D \mathbf{F} \cdot \left(\frac{\mathbf{r}_u \times \mathbf{r}_v}{\|\mathbf{r}_u \times \mathbf{r}_v\|} \right) \|\mathbf{r}_u \times \mathbf{r}_v\|\, dA = \iint_D \mathbf{F} \cdot (\mathbf{r}_u \times \mathbf{r}_v)\, dA.$$

Note the similarity of this integral to the line integral

$$\int_C \mathbf{F} \cdot d\mathbf{r} = \int_C \mathbf{F} \cdot \mathbf{T}\, ds.$$

A summary of formulas for line and surface integrals is presented on page 1107.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 15.53

EXAMPLE 6 Finding the Flux of an Inverse Square Field

Find the flux over the sphere S given by

$$x^2 + y^2 + z^2 = a^2 \qquad \text{Sphere } S$$

where $\mathbf{F}$ is an inverse square field given by

$$\mathbf{F}(x, y, z) = \frac{kq}{\|\mathbf{r}\|^2}\frac{\mathbf{r}}{\|\mathbf{r}\|} = \frac{kq\mathbf{r}}{\|\mathbf{r}\|^3} \qquad \text{Inverse square field } \mathbf{F}$$

and

$$\mathbf{r} = x\mathbf{i} + y\mathbf{j} + z\mathbf{k}.$$

Assume S is oriented outward, as shown in Figure 15.53.

Solution The sphere is given by

$$\begin{aligned}\mathbf{r}(u, v) &= x(u, v)\mathbf{i} + y(u, v)\mathbf{j} + z(u, v)\mathbf{k} \\ &= a \sin u \cos v\mathbf{i} + a \sin u \sin v\mathbf{j} + a \cos u\mathbf{k}\end{aligned}$$

where $0 \le u \le \pi$ and $0 \le v \le 2\pi$. The partial derivatives of $\mathbf{r}$ are

$$\mathbf{r}_u(u, v) = a \cos u \cos v\mathbf{i} + a \cos u \sin v\mathbf{j} - a \sin u\mathbf{k}$$

and

$$\mathbf{r}_v(u, v) = -a \sin u \sin v\mathbf{i} + a \sin u \cos v\mathbf{j}$$

which implies that the normal vector $\mathbf{r}_u \times \mathbf{r}_v$ is

$$\begin{aligned}\mathbf{r}_u \times \mathbf{r}_v &= \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ a \cos u \cos v & a \cos u \sin v & -a \sin u \\ -a \sin u \sin v & a \sin u \cos v & 0 \end{vmatrix} \\ &= a^2(\sin^2 u \cos v\mathbf{i} + \sin^2 u \sin v\mathbf{j} + \sin u \cos u\mathbf{k}).\end{aligned}$$

Now, using

$$\begin{aligned}\mathbf{F}(x, y, z) &= \frac{kq\mathbf{r}}{\|\mathbf{r}\|^3} \\ &= kq\frac{x\mathbf{i} + y\mathbf{j} + z\mathbf{k}}{\|x\mathbf{i} + y\mathbf{j} + z\mathbf{k}\|^3} \\ &= \frac{kq}{a^3}(a \sin u \cos v\mathbf{i} + a \sin u \sin v\mathbf{j} + a \cos u\mathbf{k})\end{aligned}$$

it follows that

$$\begin{aligned}\mathbf{F} \cdot (\mathbf{r}_u \times \mathbf{r}_v) &= \frac{kq}{a^3}[(a \sin u \cos v\mathbf{i} + a \sin u \sin v\mathbf{j} + a \cos u\mathbf{k}) \cdot \\ &\qquad a^2(\sin^2 u \cos v\mathbf{i} + \sin^2 u \sin v\mathbf{j} + \sin u \cos u\mathbf{k})] \\ &= kq(\sin^3 u \cos^2 v + \sin^3 u \sin^2 v + \sin u \cos^2 u) \\ &= kq \sin u.\end{aligned}$$

Finally, the flux over the sphere S is given by

$$\begin{aligned}\iint_S \mathbf{F} \cdot \mathbf{N}\, dS &= \iint_D kq \sin u\, dA \\ &= kq\int_0^{2\pi}\int_0^{\pi} \sin u\, du\, dv \\ &= kq\int_0^{2\pi} 2\, dv \\ &= 4\pi kq.\end{aligned}$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

The result in Example 6 shows that the flux across a sphere S in an inverse square field is independent of the radius of S. In particular, if $\mathbf{E}$ is an electric field, then the result in Example 6, along with Coulomb's Law (see Section 15.1), yields one of the basic laws of electrostatics, known as **Gauss's Law:**

$$\iint_S \mathbf{E} \cdot \mathbf{N}\, dS = 4\pi kq \qquad \text{Gauss's Law}$$

where q is a point charge located at the center of the sphere and k is the Coulomb constant. Gauss's Law is valid for more general closed surfaces that enclose the origin, and it relates the flux out of the surface to the total charge inside the surface.

Surface integrals are also used in the study of **heat flow.** Heat flows from areas of higher temperature to areas of lower temperature in the direction of greatest change. As a result, measuring **heat flux** involves the gradient of the temperature. The flux depends on the area of the surface. It is the normal direction to the surface that is important, because heat that flows in directions tangential to the surface will produce no heat loss. So, assume that the heat flux across a portion of the surface of area ΔS is given by $\Delta H \approx -k\nabla T \cdot \mathbf{N}\, dS$, where T is the temperature, $\mathbf{N}$ is the unit normal vector to the surface in the direction of the heat flow, and k is the thermal diffusivity of the material. The heat flux across the surface is given by

$$H = \iint_S -k\nabla T \cdot \mathbf{N}\, dS. \qquad \text{Heat flux across } S$$

This section concludes with a summary of different forms of line integrals and surface integrals.

Summary of Line and Surface Integrals

Line Integrals

$$ds = \|\mathbf{r}'(t)\|\, dt = \sqrt{[x'(t)]^2 + [y'(t)]^2 + [z'(t)]^2}\, dt$$

$$\int_C f(x, y, z)\, ds = \int_a^b f(x(t), y(t), z(t))\sqrt{[x'(t)]^2 + [y'(t)]^2 + [z'(t)]^2}\, dt \qquad \text{Scalar form}$$

$$\int_C \mathbf{F} \cdot d\mathbf{r} = \int_C \mathbf{F} \cdot \mathbf{T}\, ds = \int_a^b \mathbf{F}(x(t), y(t), z(t)) \cdot \mathbf{r}'(t)\, dt \qquad \text{Vector form}$$

Surface Integrals $[z = g(x, y)]$

$$dS = \sqrt{1 + [g_x(x, y)]^2 + [g_y(x, y)]^2}\, dA$$

$$\iint_S f(x, y, z)\, dS = \iint_R f(x, y, g(x, y))\sqrt{1 + [g_x(x, y)]^2 + [g_y(x, y)]^2}\, dA \qquad \text{Scalar form}$$

$$\iint_S \mathbf{F} \cdot \mathbf{N}\, dS = \iint_R \mathbf{F} \cdot [-g_x(x, y)\mathbf{i} - g_y(x, y)\mathbf{j} + \mathbf{k}]\, dA \qquad \text{Vector form (upward normal)}$$

Surface Integrals (parametric form)

$$dS = \|\mathbf{r}_u(u, v) \times \mathbf{r}_v(u, v)\|\, dA$$

$$\iint_S f(x, y, z)\, dS = \iint_D f(x(u, v), y(u, v), z(u, v))\|\mathbf{r}_u(u, v) \times \mathbf{r}_v(u, v)\|\, dA \qquad \text{Scalar form}$$

$$\iint_S \mathbf{F} \cdot \mathbf{N}\, dS = \iint_D \mathbf{F} \cdot (\mathbf{r}_u \times \mathbf{r}_v)\, dA \qquad \text{Vector form (upward normal)}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

15.6 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain how to set up a surface integral given that you will project the surface onto the xz-plane.
2. For what condition does the surface integral over S yield the surface area of S?
3. Describe a physical characteristic of an orientable surface.
4. What is the physical interpretation of the flux of $\mathbf{F}$ across S? How do you calculate it?

Evaluating a Surface Integral In Exercises 5–8, evaluate $\iint_S (x - 2y + z)\, dS$.

5. S: $z = 4 - x$, $0 \le x \le 4$, $0 \le y \le 3$
6. S: $z = 15 - 2x + 3y$, $0 \le x \le 2$, $0 \le y \le 4$
7. S: $z = 2$, $x^2 + y^2 \le 1$
8. S: $z = 3y$, $0 \le x \le 2$, $0 \le y \le x$

Evaluating a Surface Integral In Exercises 9 and 10, evaluate $\iint_S xy\, dS$.

9. S: $z = 3 - x - y$, first octant
10. S: $z = \frac{1}{4}x^4$, $0 \le x \le 1$, $0 \le y \le x^2$

Evaluating a Surface Integral In Exercises 11 and 12, use a graphing utility to evaluate $\iint_S (x^2 - 2xy)\, dS$.

11. S: $z = 10 - x^2 - y^2$, $0 \le x \le 2$, $0 \le y \le 2$
12. S: $z = \cos x$, $0 \le x \le \frac{\pi}{2}$, $0 \le y \le \frac{1}{2}x$

Mass In Exercises 13 and 14, find the mass of the surface lamina S of density ρ.

13. S: $2x + 3y + 6z = 12$, first octant, $\rho(x, y, z) = x^2 + y^2$
14. S: $z = \sqrt{a^2 - x^2 - y^2}$, $\rho(x, y, z) = kz$

Evaluating a Surface Integral In Exercises 15–18, evaluate $\iint_S f(x, y)\, dS$.

15. $f(x, y) = y + 5$
    S: $\mathbf{r}(u, v) = u\mathbf{i} + v\mathbf{j} + 2v\mathbf{k}$
    $0 \le u \le 1$, $0 \le v \le 2$
16. $f(x, y) = xy$
    S: $\mathbf{r}(u, v) = 2\cos u\mathbf{i} + 2\sin u\mathbf{j} + v\mathbf{k}$
    $0 \le u \le \frac{\pi}{2}$, $0 \le v \le 1$
17. $f(x, y) = 3y - x$
    S: $\mathbf{r}(u, v) = \cos u\mathbf{i} + \sin u\mathbf{j} + v\mathbf{k}$
    $0 \le u \le \frac{\pi}{3}$, $0 \le v \le 1$
18. $f(x, y) = x + y$
    S: $\mathbf{r}(u, v) = 4u\cos v\mathbf{i} + 4u\sin v\mathbf{j} + 3u\mathbf{k}$
    $0 \le u \le 4$, $0 \le v \le \pi$

Evaluating a Surface Integral In Exercises 19–24, evaluate $\iint_S f(x, y, z)\, dS$.

19. $f(x, y, z) = x^2 + y^2 + z^2$
    S: $z = x + y$, $x^2 + y^2 \le 1$
20. $f(x, y, z) = \dfrac{xy}{z}$
    S: $z = x^2 + y^2$, $4 \le x^2 + y^2 \le 16$
21. $f(x, y, z) = \sqrt{x^2 + y^2 + z^2}$
    S: $z = \sqrt{x^2 + y^2}$, $x^2 + y^2 \le 4$
22. $f(x, y, z) = \sqrt{x^2 + y^2 + z^2}$
    S: $z = \sqrt{x^2 + y^2}$, $(x - 1)^2 + y^2 \le 1$
23. $f(x, y, z) = x^2 + y^2 + z^2$
    S: $x^2 + y^2 = 9$, $0 \le x \le 3$, $0 \le y \le 3$, $0 \le z \le 9$
24. $f(x, y, z) = x^2 + y^2 + z^2$
    S: $x^2 + y^2 = 9$, $0 \le x \le 3$, $0 \le z \le x$

Evaluating a Flux Integral In Exercises 25–30, find the flux of $\mathbf{F}$ across S,

$$\iint_S \mathbf{F} \cdot \mathbf{N}\, dS$$

where $\mathbf{N}$ is the upward unit normal vector to S.

25. $\mathbf{F}(x, y, z) = 3z\mathbf{i} - 4\mathbf{j} + y\mathbf{k}$; S: $z = 1 - x - y$, first octant
26. $\mathbf{F}(x, y, z) = x\mathbf{i} + 2y\mathbf{j}$; S: $z = 6 - 3x - 2y$, first octant
27. $\mathbf{F}(x, y, z) = x\mathbf{i} + y\mathbf{j} + z\mathbf{k}$; S: $z = 1 - x^2 - y^2$, $z \ge 0$
28. $\mathbf{F}(x, y, z) = x\mathbf{i} + y\mathbf{j} + z\mathbf{k}$
    S: $x^2 + y^2 + z^2 = 36$, first octant
29. $\mathbf{F}(x, y, z) = 4\mathbf{i} - 3\mathbf{j} + 5\mathbf{k}$
    S: $z = x^2 + y^2$, $x^2 + y^2 \le 4$
30. $\mathbf{F}(x, y, z) = x\mathbf{i} + y\mathbf{j} - 2z\mathbf{k}$
    S: $z = \sqrt{a^2 - x^2 - y^2}$

Evaluating a Flux Integral In Exercises 31 and 32, find the flux of $\mathbf{F}$ over the closed surface. (Let $\mathbf{N}$ be the outward unit normal vector of the surface.)

31. $\mathbf{F}(x, y, z) = (x + y)\mathbf{i} + y\mathbf{j} + z\mathbf{k}$
    S: $z = 16 - x^2 - y^2$, $z = 0$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

32. $\mathbf{F}(x, y, z) = 4xy\mathbf{i} + z^2\mathbf{j} + yz\mathbf{k}$

S: unit cube bounded by the planes $x = 0$, $x = 1$, $y = 0$, $y = 1$, $z = 0$, $z = 1$

Flow Rate **In Exercises 33 and 34, use a graphing utility to find the rate of mass flow of a fluid of density ρ through the surface S oriented upward when the velocity field is given by $\mathbf{F}(x, y, z) = 0.5z\mathbf{k}$.**

33. S: $z = 16 - x^2 - y^2, \quad z \geq 0$

34. S: $z = \sqrt{16 - x^2 - y^2}$

Gauss's Law **In Exercises 35 and 36, evaluate $\iint_S \mathbf{E} \cdot \mathbf{N}\, dS$ to find the total charge of the electrostatic field $\mathbf{E}$ enclosed by the closed surface consisting of the hemisphere $z = \sqrt{1 - x^2 - y^2}$ and its circular base in the xy-plane.**

35. $\mathbf{E} = yz\mathbf{i} + xz\mathbf{j} + xy\mathbf{k}$

36. $\mathbf{E} = x\mathbf{i} + y\mathbf{j} + 2z\mathbf{k}$

Moments of Inertia **In Exercises 37–40, use the following formulas for the moments of inertia about the coordinate axes of a surface lamina of density ρ.**

$$I_x = \iint_S (y^2 + z^2)\rho(x, y, z)\, dS$$

$$I_y = \iint_S (x^2 + z^2)\rho(x, y, z)\, dS$$

$$I_z = \iint_S (x^2 + y^2)\rho(x, y, z)\, dS$$

37. Verify that the moment of inertia of a conical shell of uniform density about its axis is $\frac{1}{2}ma^2$, where m is the mass and a is the radius and height.

38. Verify that the moment of inertia of a spherical shell of uniform density about its diameter is $\frac{2}{3}ma^2$, where m is the mass and a is the radius.

39. Find the moment of inertia about the z-axis for the surface lamina $x^2 + y^2 = a^2$, where $0 \leq z \leq h$, with a uniform density of 1.

40. Find the moment of inertia about the z-axis for the surface lamina $z = x^2 + y^2$, where $0 \leq z \leq h$, with a uniform density of 1.

Exploring Concepts

41. Evaluate

$$\iint_S (x + 2y)\, dS$$

where S is the first-octant portion of the plane

$$2x + 2y + z = 4$$

by projecting S onto (a) the xy-plane, (b) the xz-plane, and (c) the yz-plane. Verify that all answers are the same.

42. **HOW DO YOU SEE IT?** Is the surface shown in the figure orientable? Explain why or why not.



Double twist

43. **Investigation**

(a) Use a graphing utility to graph the vector-valued function

$$\mathbf{r}(u, v) = (4 - v \sin u)\cos(2u)\mathbf{i} + (4 - v \sin u)\sin(2u)\mathbf{j} + v \cos u\mathbf{k}$$

where

$$0 \leq u \leq \pi \quad \text{and} \quad -1 \leq v \leq 1.$$

This surface is called a Möbius strip.

(b) Is the surface orientable? Explain why or why not.

(c) Use a graphing utility to graph the space curve represented by $\mathbf{r}(u, 0)$. Identify the curve.

(d) Cut a strip of paper and draw a line lengthwise through the center. Construct a Möbius strip by making a single twist and pasting the ends of the strip of paper together.

(e) Cut the Möbius strip along the line you drew in part (c), and describe the result.

SECTION PROJECT

Hyperboloid of One Sheet

Consider the parametric surface given by the function

$$\mathbf{r}(u, v) = a \cosh u \cos v\mathbf{i} + a \cosh u \sin v\mathbf{j} + b \sinh u\mathbf{k}.$$

(a) Use a graphing utility to graph $\mathbf{r}$ for various values of the constants a and b. Describe the effect of the constants on the shape of the surface.

(b) Show that the surface is a hyperboloid of one sheet given by

$$\frac{x^2}{a^2} + \frac{y^2}{a^2} - \frac{z^2}{b^2} = 1.$$

(c) For fixed values $u = u_0$, describe the curves given by

$$\mathbf{r}(u_0, v) = a \cosh u_0 \cos v\mathbf{i} + a \cosh u_0 \sin v\mathbf{j} + b \sinh u_0\mathbf{k}.$$

(d) For fixed values $v = v_0$, describe the curves given by

$$\mathbf{r}(u, v_0) = a \cosh u \cos v_0\mathbf{i} + a \cosh u \sin v_0\mathbf{j} + b \sinh u\mathbf{k}.$$

(e) Find a normal vector to the surface at $(u, v) = (0, 0)$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

15.7 Divergence Theorem

GO DIGITAL

- **Define and use the Divergence Theorem.**
- **Use the Divergence Theorem to calculate flux.**

CARL FRIEDRICH GAUSS (1777–1855)

The *Divergence Theorem* is also called *Gauss's Theorem*, after the famous German mathematician Carl Friedrich Gauss. Gauss is recognized, with Newton and Archimedes, as one of the three greatest mathematicians in history. One of his many contributions to mathematics was made at the age of 22, when, as part of his doctoral dissertation, he proved the *Fundamental Theorem of Algebra*.

See LarsonCalculus.com to read more of this biography.

Divergence Theorem

Recall from Section 15.4 that an alternative form of Green's Theorem is

$$\int_C \mathbf{F} \cdot \mathbf{N}\, ds = \iint_R \left(\frac{\partial M}{\partial x} + \frac{\partial N}{\partial y} \right) dA$$
$$= \iint_R \operatorname{div} \mathbf{F}\, dA.$$

In an analogous way, the **Divergence Theorem** gives the relationship between a triple integral over a solid region Q and a surface integral over the surface of Q. In the statement of the theorem, the surface S is **closed** in the sense that it forms the complete boundary of the solid Q. Regions bounded by spheres, ellipsoids, cubes, tetrahedrons, or combinations of these surfaces are typical examples of closed surfaces. Let Q be a solid region on which a triple integral can be evaluated, and let S be a closed surface that is oriented by *outward* unit normal vectors, as shown in Figure 15.54. With these restrictions on S and Q, the Divergence Theorem can be stated as shown below the figure.



Figure 15.54

THEOREM 15.12 The Divergence Theorem

Let Q be a solid region bounded by a closed surface S oriented by a unit normal vector directed outward from Q. If $\mathbf{F}$ is a vector field whose component functions have continuous first partial derivatives in Q, then

$$\iint_S \mathbf{F} \cdot \mathbf{N}\, dS = \iiint_Q \operatorname{div} \mathbf{F}\, dV.$$

REMARK As noted at the left above, the Divergence Theorem is sometimes called Gauss's Theorem. It is also sometimes called Ostrogradsky's Theorem, after the Russian mathematician Michel Ostrogradsky (1801–1861).

Colport/Alamy Stock Photo

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

REMARK This proof is restricted to a *simple* solid region. The general proof is best left to a course in advanced calculus.

Proof For $\mathbf{F}(x, y, z) = M\mathbf{i} + N\mathbf{j} + P\mathbf{k}$, the theorem takes the form

$$\iint_S \mathbf{F} \cdot \mathbf{N}\, dS = \iint_S (M\mathbf{i} \cdot \mathbf{N} + N\mathbf{j} \cdot \mathbf{N} + P\mathbf{k} \cdot \mathbf{N})\, dS$$
$$= \iiint_Q \left(\frac{\partial M}{\partial x} + \frac{\partial N}{\partial y} + \frac{\partial P}{\partial z} \right) dV.$$

You can prove this by verifying that the following three equations are valid.

$$\iint_S M\mathbf{i} \cdot \mathbf{N}\, dS = \iiint_Q \frac{\partial M}{\partial x}\, dV$$
$$\iint_S N\mathbf{j} \cdot \mathbf{N}\, dS = \iiint_Q \frac{\partial N}{\partial y}\, dV$$
$$\iint_S P\mathbf{k} \cdot \mathbf{N}\, dS = \iiint_Q \frac{\partial P}{\partial z}\, dV$$



Figure 15.55

Because the verifications of the three equations are similar, only the third is discussed. Restrict the proof to a **simple solid** region with upper surface

$$z = g_2(x, y) \qquad \text{Upper surface}$$

and lower surface

$$z = g_1(x, y) \qquad \text{Lower surface}$$

whose projections onto the xy-plane coincide and form region R. If Q has a lateral surface like S_3 in Figure 15.55, then a normal vector is horizontal, which implies that $P\mathbf{k} \cdot \mathbf{N} = 0$. Consequently, you have

$$\iint_S P\mathbf{k} \cdot \mathbf{N}\, dS = \iint_{S_1} P\mathbf{k} \cdot \mathbf{N}\, dS + \iint_{S_2} P\mathbf{k} \cdot \mathbf{N}\, dS + 0.$$

On the upper surface S_2, the outward normal vector is upward, whereas on the lower surface S_1, the outward normal vector is downward. So, by Theorem 15.11, you have

$$\iint_{S_1} P\mathbf{k} \cdot \mathbf{N}\, dS = \iint_R P(x, y, g_1(x, y))\mathbf{k} \cdot \left(\frac{\partial g_1}{\partial x}\mathbf{i} + \frac{\partial g_1}{\partial y}\mathbf{j} - \mathbf{k} \right) dA$$
$$= -\iint_R P(x, y, g_1(x, y))\, dA$$

and

$$\iint_{S_2} P\mathbf{k} \cdot \mathbf{N}\, dS = \iint_R P(x, y, g_2(x, y))\mathbf{k} \cdot \left(-\frac{\partial g_2}{\partial x}\mathbf{i} - \frac{\partial g_2}{\partial y}\mathbf{j} + \mathbf{k} \right) dA$$
$$= \iint_R P(x, y, g_2(x, y))\, dA.$$

Adding these results, you obtain

$$\iint_S P\mathbf{k} \cdot \mathbf{N}\, dS = \iint_R [P(x, y, g_2(x, y)) - P(x, y, g_1(x, y))]\, dA$$
$$= \iint_R \left[\int_{g_1(x, y)}^{g_2(x, y)} \frac{\partial P}{\partial z}\, dz \right] dA$$
$$= \iiint_Q \frac{\partial P}{\partial z}\, dV.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 15.56

Even though the Divergence Theorem was stated for a simple solid region Q bounded by a closed surface, the theorem is also valid for regions that are the finite unions of simple solid regions. For example, let Q be the solid bounded by the closed surfaces S_1 and S_2, as shown in Figure 15.56. To apply the Divergence Theorem to this solid, let $S = S_1 \cup S_2$. The normal vector $\mathbf{N}$ to S is given by $-\mathbf{N}_1$ on S_1 and by $\mathbf{N}_2$ on S_2. So, you can write

$$\begin{aligned}\iiint_Q \operatorname{div} \mathbf{F}\, dV &= \iint_S \mathbf{F} \cdot \mathbf{N}\, dS \\ &= \iint_{S_1} \mathbf{F} \cdot (-\mathbf{N}_1)\, dS + \iint_{S_2} \mathbf{F} \cdot \mathbf{N}_2\, dS \\ &= -\iint_{S_1} \mathbf{F} \cdot \mathbf{N}_1\, dS + \iint_{S_2} \mathbf{F} \cdot \mathbf{N}_2\, dS.\end{aligned}$$

For the remainder of this section, you will apply the Divergence Theorem to simple solid regions bounded by closed surfaces.

EXAMPLE 1 Using the Divergence Theorem

Let Q be the solid region bounded by the coordinate planes and the plane

$$2x + 2y + z = 6$$

and let $\mathbf{F} = x\mathbf{i} + y^2\mathbf{j} + z\mathbf{k}$. Find $\iint_S \mathbf{F} \cdot \mathbf{N}\, dS$, where S is the surface of Q.



Figure 15.57

Solution From Figure 15.57, note that Q is bounded by four subsurfaces. So, you would need four *surface integrals* to evaluate

$$\iint_S \mathbf{F} \cdot \mathbf{N}\, dS.$$

However, by the Divergence Theorem, you need only one triple integral. Because

$$\operatorname{div} \mathbf{F} = \frac{\partial M}{\partial x} + \frac{\partial N}{\partial y} + \frac{\partial P}{\partial z} = 1 + 2y + 1 = 2 + 2y$$

you have

$$\begin{aligned}\iint_S \mathbf{F} \cdot \mathbf{N}\, dS &= \iiint_Q \operatorname{div} \mathbf{F}\, dV \\ &= \int_0^3 \int_0^{3-y} \int_0^{6-2x-2y} (2 + 2y)\, dz\, dx\, dy \\ &= \int_0^3 \int_0^{3-y} (2z + 2yz) \Big]_0^{6-2x-2y} dx\, dy \\ &= \int_0^3 \int_0^{3-y} (12 - 4x + 8y - 4xy - 4y^2)\, dx\, dy \\ &= \int_0^3 \left[12x - 2x^2 + 8xy - 2x^2y - 4xy^2\right]_0^{3-y} dy \\ &= \int_0^3 (18 + 6y - 10y^2 + 2y^3)\, dy \\ &= \left[18y + 3y^2 - \frac{10y^3}{3} + \frac{y^4}{2}\right]_0^3 \\ &= \frac{63}{2}.\end{aligned}$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL



Figure 15.58

EXAMPLE 2 Verifying the Divergence Theorem

Let Q be the solid region between the paraboloid

$$z = 4 - x^2 - y^2$$

and the xy-plane. Verify the Divergence Theorem for

$$\mathbf{F}(x, y, z) = 2z\mathbf{i} + x\mathbf{j} + y^2\mathbf{k}.$$

Solution From Figure 15.58, note that the outward normal vector for the surface S_1 is $\mathbf{N}_1 = -\mathbf{k}$, whereas the outward normal vector for the surface S_2 is

$$\mathbf{N}_2 = \frac{2x\mathbf{i} + 2y\mathbf{j} + \mathbf{k}}{\sqrt{4x^2 + 4y^2 + 1}}.$$

So, by Theorem 15.11, you have

$$\begin{aligned}
\iint_S \mathbf{F} \cdot \mathbf{N}\, dS &= \iint_{S_1} \mathbf{F} \cdot \mathbf{N}_1\, dS + \iint_{S_2} \mathbf{F} \cdot \mathbf{N}_2\, dS \\
&= \iint_{S_1} \mathbf{F} \cdot (-\mathbf{k})\, dS + \iint_{S_2} \mathbf{F} \cdot \frac{(2x\mathbf{i} + 2y\mathbf{j} + \mathbf{k})}{\sqrt{4x^2 + 4y^2 + 1}}\, dS \\
&= \iint_R -y^2\, dA + \iint_R (4xz + 2xy + y^2)\, dA \\
&= -\int_{-2}^{2} \int_{-\sqrt{4-y^2}}^{\sqrt{4-y^2}} y^2\, dx\, dy + \int_{-2}^{2} \int_{-\sqrt{4-y^2}}^{\sqrt{4-y^2}} (4xz + 2xy + y^2)\, dx\, dy \\
&= \int_{-2}^{2} \int_{-\sqrt{4-y^2}}^{\sqrt{4-y^2}} (4xz + 2xy)\, dx\, dy \\
&= \int_{-2}^{2} \int_{-\sqrt{4-y^2}}^{\sqrt{4-y^2}} [4x(4 - x^2 - y^2) + 2xy]\, dx\, dy \\
&= \int_{-2}^{2} \int_{-\sqrt{4-y^2}}^{\sqrt{4-y^2}} (16x - 4x^3 - 4xy^2 + 2xy)\, dx\, dy \\
&= \int_{-2}^{2} \left[8x^2 - x^4 - 2x^2y^2 + x^2y \right]_{-\sqrt{4-y^2}}^{\sqrt{4-y^2}} dy \\
&= \int_{-2}^{2} 0\, dy \\
&= 0.
\end{aligned}$$

On the other hand, because

$$\begin{aligned}
\operatorname{div} \mathbf{F} &= \frac{\partial}{\partial x}[2z] + \frac{\partial}{\partial y}[x] + \frac{\partial}{\partial z}[y^2] \\
&= 0 + 0 + 0 \\
&= 0
\end{aligned}$$

you can apply the Divergence Theorem to obtain the equivalent result

$$\begin{aligned}
\iint_S \mathbf{F} \cdot \mathbf{N}\, dS &= \iiint_Q \operatorname{div} \mathbf{F}\, dV \\
&= \iiint_Q 0\, dV \\
&= 0.
\end{aligned}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 15.59

GO DIGITAL

EXAMPLE 3 Using the Divergence Theorem

Let Q be the solid bounded by the cylinder $x^2 + y^2 = 4$, the plane $x + z = 6$, and the xy-plane, as shown in Figure 15.59. Find

$$\iint_S \mathbf{F} \cdot \mathbf{N}\, dS$$

where S is the surface of Q and

$$\mathbf{F}(x, y, z) = (x^2 + \sin z)\mathbf{i} + (xy + \cos z)\mathbf{j} + e^y\mathbf{k}.$$

Solution Direct evaluation of this surface integral would be difficult. However, by the Divergence Theorem, you can evaluate the integral as follows.

$$\iint_S \mathbf{F} \cdot \mathbf{N}\, dS = \iiint_Q \operatorname{div} \mathbf{F}\, dV = \iiint_Q (2x + x + 0)\, dV = \iiint_Q 3x\, dV$$

Next, use cylindrical coordinates with $x = r\cos\theta$ and $dV = r\, dz\, dr\, d\theta$.

$$\iiint_Q 3x\, dV = \int_0^{2\pi}\int_0^2\int_0^{6 - r\cos\theta} (3r\cos\theta) r\, dz\, dr\, d\theta \qquad \text{Cylindrical coordinates}$$

$$= \int_0^{2\pi}\int_0^2 (18r^2\cos\theta - 3r^3\cos^2\theta)\, dr\, d\theta$$

$$= \int_0^{2\pi} (48\cos\theta - 12\cos^2\theta)\, d\theta$$

$$= \left[48\sin\theta - 6\left(\theta + \frac{1}{2}\sin 2\theta\right)\right]_0^{2\pi}$$

$$= -12\pi$$

Flux and the Divergence Theorem

To help understand the Divergence Theorem, consider the two sides of the equation

$$\iint_S \mathbf{F} \cdot \mathbf{N}\, dS = \iiint_Q \operatorname{div} \mathbf{F}\, dV.$$

You know from Section 15.6 that the flux integral on the left determines the total fluid flow across the surface S per unit of time. This can be approximated by summing the fluid flow across small patches of the surface. The triple integral on the right measures this same fluid flow across S but from a very different perspective—namely, by calculating the flow of fluid into (or out of) small *cubes* of volume ΔV_i. The flux of the ith cube is approximately $\operatorname{div} \mathbf{F}(x_i, y_i, z_i)\, \Delta V_i$ for some point (x_i, y_i, z_i) in the ith cube. Note that for a cube in the interior of Q, the gain (or loss) of fluid through any one of its six sides is offset by a corresponding loss (or gain) through one of the sides of an adjacent cube. After summing over all the cubes in Q, the only fluid flow that is not canceled by adjoining cubes is that on the outside edges of the cubes on the boundary. So, the sum

$$\sum_{i=1}^{n} \operatorname{div} \mathbf{F}(x_i, y_i, z_i)\, \Delta V_i$$

approximates the total flux into (or out of) Q and therefore through the surface S.

To understand what is meant by the divergence of $\mathbf{F}$ at a point, consider ΔV_α to be the volume of a small sphere S_α of radius α and center (x_0, y_0, z_0) contained in region Q, as shown in Figure 15.60.



Figure 15.60

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

Applying the Divergence Theorem to S_α produces

$$\text{Flux of } \mathbf{F} \text{ across } S_\alpha = \iiint_{Q_\alpha} \operatorname{div} \mathbf{F}\, dV \approx \operatorname{div} \mathbf{F}(x_0, y_0, z_0)\, \Delta V_\alpha$$

where Q_α is the interior of S_α. Consequently,

$$\operatorname{div} \mathbf{F}(x_0, y_0, z_0) \approx \frac{\text{flux of } \mathbf{F} \text{ across } S_\alpha}{\Delta V_\alpha}.$$

By taking the limit as $\alpha \to 0$, you obtain the divergence of $\mathbf{F}$ at the point (x_0, y_0, z_0).

$$\operatorname{div} \mathbf{F}(x_0, y_0, z_0) = \lim_{\alpha \to 0} \frac{\text{flux of } \mathbf{F} \text{ across } S_\alpha}{\Delta V_\alpha} = \text{flux per unit volume at } (x_0, y_0, z_0)$$

The point (x_0, y_0, z_0) in a vector field is classified as a source, a sink, or incompressible, as shown in the list below.

1. **Source,** for $\operatorname{div} \mathbf{F} > 0$ See Figure 15.61(a).
2. **Sink,** for $\operatorname{div} \mathbf{F} < 0$ See Figure 15.61(b).
3. **Incompressible,** for $\operatorname{div} \mathbf{F} = 0$ See Figure 15.61(c).

REMARK In hydrodynamics, a *source* is a point at which additional fluid is considered as being introduced to the region occupied by the fluid. A *sink* is a point at which fluid is considered as being removed.



(a) Source: $\operatorname{div} \mathbf{F} > 0$ **(b)** Sink: $\operatorname{div} \mathbf{F} < 0$ **(c)** Incompressible: $\operatorname{div} \mathbf{F} = 0$

Figure 15.61

EXAMPLE 4 Calculating Flux by the Divergence Theorem

See LarsonCalculus.com for an interactive version of this type of example.

Let Q be the region bounded by the sphere $x^2 + y^2 + z^2 = 4$. Find the outward flux of the vector field $\mathbf{F}(x, y, z) = 2x^3\mathbf{i} + 2y^3\mathbf{j} + 2z^3\mathbf{k}$ through the sphere.

Solution By the Divergence Theorem,

$$\text{Flux across } S = \iint_S \mathbf{F} \cdot \mathbf{N}\, dS = \iiint_Q \operatorname{div} \mathbf{F}\, dV = \iiint_Q 6(x^2 + y^2 + z^2)\, dV.$$

Next, use spherical coordinates with $\rho^2 = x^2 + y^2 + z^2$ and $dV = \rho^2 \sin\phi\, d\theta\, d\phi\, d\rho$.

$$\iiint_Q 6(x^2 + y^2 + z^2)\, dV = 6\int_0^2 \int_0^\pi \int_0^{2\pi} \rho^4 \sin\phi\, d\theta\, d\phi\, d\rho \qquad \text{Spherical coordinates}$$

$$= 6\int_0^2 \int_0^\pi 2\pi\rho^4 \sin\phi\, d\phi\, d\rho$$

$$= 12\pi \int_0^2 2\rho^4\, d\rho$$

$$= 24\pi\left(\frac{32}{5}\right)$$

$$= \frac{768\pi}{5}.$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

15.7 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Suppose that a solid region Q is bounded by $z = x^2 + y^2$ and $z = 2$, as shown in the figure. What methods can you use to evaluate

$$\iint_S \mathbf{F} \cdot \mathbf{N}\, dS$$

where $\mathbf{F} = 2x\mathbf{i} + 3y\mathbf{j} - z^2\mathbf{k}$? Which method do you prefer?



2. How do you determine whether a point (x_0, y_0, z_0) in a vector field is a source, a sink, or incompressible?

Verifying the Divergence Theorem

In Exercises 3–8, verify the Divergence Theorem by evaluating

$$\iint_S \mathbf{F} \cdot \mathbf{N}\, dS$$

as a surface integral and as a triple integral.

3. $\mathbf{F}(x, y, z) = 2x\mathbf{i} - 2y\mathbf{j} + z^2\mathbf{k}$

S: cube bounded by the planes $x = 0$, $x = 1$, $y = 0$, $y = 1$, $z = 0$, $z = 1$



Figure for 3



Figure for 4

4. $\mathbf{F}(x, y, z) = 2x\mathbf{i} - 2y\mathbf{j} + z^2\mathbf{k}$

S: cylinder $x^2 + y^2 = 4$, $\quad 0 \le z \le 3$

5. $\mathbf{F}(x, y, z) = (2x - y)\mathbf{i} - (2y - z)\mathbf{j} + z\mathbf{k}$

S: surface bounded by the plane $2x + 4y + 2z = 12$ and the coordinate planes



6. $\mathbf{F}(x, y, z) = xy\mathbf{i} + z\mathbf{j} + (x + y)\mathbf{k}$

S: surface bounded by the planes $y = 4$ and $z = 4 - x$ and the coordinate planes



7. $\mathbf{F}(x, y, z) = xz\mathbf{i} + zy\mathbf{j} + 2z^2\mathbf{k}$

S: surface bounded by $z = 1 - x^2 - y^2$ and $z = 0$



8. $\mathbf{F}(x, y, z) = xy^2\mathbf{i} + yx^2\mathbf{j} + e\mathbf{k}$

S: surface bounded by $z = \sqrt{x^2 + y^2}$ and $z = 4$



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Using the Divergence Theorem **In Exercises 9–18, use the Divergence Theorem to evaluate**

$$\iint_S \mathbf{F} \cdot \mathbf{N}\, dS$$

and find the outward flux of F through the surface of the solid S bounded by the graphs of the equations. Use a graphing utility to verify your results.

9. $\mathbf{F}(x, y, z) = x^2\mathbf{i} + y^2\mathbf{j} + z^2\mathbf{k}$

S: $x = 0, x = a, y = 0, y = a, z = 0, z = a$

10. $\mathbf{F}(x, y, z) = x^2z^2\mathbf{i} - 2y\mathbf{j} + 3xyz\mathbf{k}$

S: $x = 0, x = a, y = 0, y = a, z = 0, z = a$

11. $\mathbf{F}(x, y, z) = x^2\mathbf{i} - 2xy\mathbf{j} + xyz^2\mathbf{k}$

S: $z = \sqrt{a^2 - x^2 - y^2}, z = 0$

12. $\mathbf{F}(x, y, z) = xy\mathbf{i} + yz\mathbf{j} - yz\mathbf{k}$

S: $z = \sqrt{a^2 - x^2 - y^2}, z = 0$

13. $\mathbf{F}(x, y, z) = x\mathbf{i} + y\mathbf{j} + z\mathbf{k}$

S: $x^2 + y^2 + z^2 = 9$

14. $\mathbf{F}(x, y, z) = xyz\mathbf{j}$

S: $x^2 + y^2 = 4, z = 0, z = 5$

15. $\mathbf{F}(x, y, z) = x\mathbf{i} + y^2\mathbf{j} - z\mathbf{k}$

S: $x^2 + y^2 = 25, z = 0, z = 7$

16. $\mathbf{F}(x, y, z) = (xy^2 + \cos z)\mathbf{i} + (x^2y + \sin z)\mathbf{j} + e^z\mathbf{k}$

S: $z = \frac{1}{2}\sqrt{x^2 + y^2}, z = 8$

17. $\mathbf{F}(x, y, z) = xe^z\mathbf{i} + ye^z\mathbf{j} + e^z\mathbf{k}$

S: $z = 4 - y, z = 0, x = 0, x = 6, y = 0$

18. $\mathbf{F}(x, y, z) = xy\mathbf{i} + 4y\mathbf{j} + xz\mathbf{k}$

S: $x^2 + y^2 + z^2 = 16$

Classifying a Point **In Exercises 19–22, a vector field and a point in the vector field are given. Determine whether the point is a source, a sink, or incompressible.**

19. $\mathbf{F}(x, y, z) = 2\mathbf{i} + y\mathbf{j} + \mathbf{k}, \quad (2, 2, 1)$

20. $\mathbf{F}(x, y, z) = e^{-x}\mathbf{i} - xy^2\mathbf{j} + \ln z\mathbf{k}, \quad (0, -3, 1)$

21. $\mathbf{F}(x, y, z) = \sin x\mathbf{i} + \cos y\mathbf{j} + z^3 \sin y\mathbf{k}, \quad \left(\frac{\pi}{2}, \pi, 4\right)$

22. $\mathbf{F}(x, y, z) = (4xy + z^2)\mathbf{i} + (2x^2 + 6yz)\mathbf{j} + 2xz\mathbf{k}, \quad (1, -4, 2)$

23. Source Find a point that is a source in the vector field

$\mathbf{F}(x, y, z) = x^2yz\mathbf{i} + x\mathbf{j} - z\mathbf{k}$.

24. Sink Find a point that is a sink in the vector field

$\mathbf{F}(x, y, z) = e^{-x}\mathbf{i} + 4y\mathbf{j} + xyz^2\mathbf{k}$.

Exploring Concepts

25. What is the value of

$$\iint_S \text{curl } \mathbf{F} \cdot \mathbf{N}\, dS$$

for any closed surface S? Explain.

26. HOW DO YOU SEE IT? The graph of a vector field $\mathbf{F}$ is shown. Does the graph suggest that the divergence of $\mathbf{F}$ at P is positive, negative, or zero?



27. Volume

(a) Use the Divergence Theorem to verify that the volume of the solid bounded by a surface S is

$$\iint_S x\, dy\, dz = \iint_S y\, dz\, dx = \iint_S z\, dx\, dy.$$

(b) Verify the result of part (a) for the cube bounded by $x = 0$, $x = a$, $y = 0$, $y = a$, $z = 0$, and $z = a$.

28. Constant Vector Field For the constant vector field $\mathbf{F}(x, y, z) = a_1\mathbf{i} + a_2\mathbf{j} + a_3\mathbf{k}$, verify the following integral for any closed surface S.

$$\iint_S \mathbf{F} \cdot \mathbf{N}\, dS = 0$$

29. Volume For the vector field $\mathbf{F}(x, y, z) = x\mathbf{i} + y\mathbf{j} + z\mathbf{k}$, verify the following integral, where V is the volume of the solid bounded by the closed surface S.

$$\iint_S \mathbf{F} \cdot \mathbf{N}\, dS = 3V$$

30. Verifying an Identity For the vector field $\mathbf{F}(x, y, z) = x\mathbf{i} + y\mathbf{j} + z\mathbf{k}$, verify that

$$\frac{1}{\|\mathbf{F}\|}\iint_S \mathbf{F} \cdot \mathbf{N}\, dS = \frac{3}{\|\mathbf{F}\|}\iiint_Q dV.$$

Proof **In Exercises 31 and 32, prove the identity, assuming that Q, S, and $\mathbf{N}$ meet the conditions of the Divergence Theorem and that the required partial derivatives of the scalar functions f and g are continuous. The expressions $D_{\mathbf{N}}f$ and $D_{\mathbf{N}}g$ are the derivatives in the direction of the vector $\mathbf{N}$ and are defined by $D_{\mathbf{N}}f = \nabla f \cdot \mathbf{N}$ and $D_{\mathbf{N}}g = \nabla g \cdot \mathbf{N}$.**

31. $$\iiint_Q (f\nabla^2 g + \nabla f \cdot \nabla g)\, dV = \iint_S f D_{\mathbf{N}} g\, dS$$

[*Hint:* Use $\text{div}(f\mathbf{G}) = f \text{ div } \mathbf{G} + \nabla f \cdot \mathbf{G}$.]

32. $$\iiint_Q (f\nabla^2 g - g\nabla^2 f)\, dV = \iint_S (f D_{\mathbf{N}} g - g D_{\mathbf{N}} f)\, dS$$

(*Hint:* Use Exercise 31 twice.)

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

15.8 Stokes's Theorem

GO DIGITAL

- **Define and use Stokes's Theorem.**
- **Use curl to analyze the motion of a rotating liquid.**



GEORGE GABRIEL STOKES (1819–1903)

Stokes became a Lucasian professor of mathematics at Cambridge in 1849. Five years later, he published the theorem that bears his name as a prize examination question there. *See LarsonCalculus.com to read more of this biography.*

Stokes's Theorem

A second higher-dimension analog of Green's Theorem is called **Stokes's Theorem,** after the English mathematical physicist George Gabriel Stokes. Stokes was part of a group of English mathematical physicists referred to as the Cambridge School, which included William Thomson (Lord Kelvin) and James Clerk Maxwell. In addition to making contributions to physics, Stokes worked with infinite series and differential equations, as well as with the integration results presented in this section.

Stokes's Theorem gives the relationship between a surface integral over an oriented surface S and a line integral along a closed space curve C forming the boundary of S, as shown in Figure 15.62. The positive direction along C is counterclockwise relative to the normal vector $\mathbf{N}$. That is, when a person grasps the normal vector $\mathbf{N}$ with their right hand, with their thumb pointing in the direction of $\mathbf{N}$, their fingers will point in the positive direction C, as shown in Figure 15.63.



An oriented surface S bounded by a closed space curve C

Figure 15.62



The positive direction along C is counterclockwise relative to $\mathbf{N}$.

Figure 15.63

THEOREM 15.13 Stokes's Theorem

Let S be an oriented surface with unit normal vector $\mathbf{N}$, bounded by a piecewise smooth simple closed curve C with a positive orientation. If $\mathbf{F}$ is a vector field whose component functions have continuous first partial derivatives on an open region containing S and C, then

$$\int_C \mathbf{F} \cdot d\mathbf{r} = \iint_S (\text{curl } \mathbf{F}) \cdot \mathbf{N}\, dS.$$

In Theorem 15.13, note that the line integral may be written in the differential form $\int_C M\,dx + N\,dy + P\,dz$ or in the vector form $\int_C \mathbf{F} \cdot \mathbf{T}\,ds$.

Bettmann/Contributor/Getty Images

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 15.64

EXAMPLE 1 Using Stokes's Theorem

Let C be the oriented triangle lying in the plane

$$2x + 2y + z = 6$$

as shown in Figure 15.64. Evaluate

$$\int_C \mathbf{F} \cdot d\mathbf{r}$$

where $\mathbf{F}(x, y, z) = -y^2\mathbf{i} + z\mathbf{j} + x\mathbf{k}$.

Solution Using Stokes's Theorem, begin by finding the curl of $\mathbf{F}$.

$$\operatorname{curl} \mathbf{F} = \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ \frac{\partial}{\partial x} & \frac{\partial}{\partial y} & \frac{\partial}{\partial z} \\ -y^2 & z & x \end{vmatrix} = -\mathbf{i} - \mathbf{j} + 2y\mathbf{k}$$

Considering

$$z = g(x, y) = 6 - 2x - 2y$$

you can use Theorem 15.11 for an upward normal vector to obtain

$$\begin{aligned} \int_C \mathbf{F} \cdot d\mathbf{r} &= \iint_S (\operatorname{curl} \mathbf{F}) \cdot \mathbf{N}\, dS \\ &= \iint_R (-\mathbf{i} - \mathbf{j} + 2y\mathbf{k}) \cdot [-g_x(x, y)\mathbf{i} - g_y(x, y)\mathbf{j} + \mathbf{k}]\, dA \\ &= \iint_R (-\mathbf{i} - \mathbf{j} + 2y\mathbf{k}) \cdot (2\mathbf{i} + 2\mathbf{j} + \mathbf{k})\, dA \\ &= \int_0^3 \int_0^{3-y} (2y - 4)\, dx\, dy \\ &= \int_0^3 (-2y^2 + 10y - 12)\, dy \\ &= \left[-\frac{2y^3}{3} + 5y^2 - 12y\right]_0^3 \\ &= -9. \end{aligned}$$

Try evaluating the line integral in Example 1 directly, *without* using Stokes's Theorem. One way to do this would be to consider C as the union of C_1, C_2, and C_3, as follows.

$$\begin{aligned} C_1&: \ \mathbf{r}_1(t) = (3 - t)\mathbf{i} + t\mathbf{j}, \quad 0 \le t \le 3 \\ C_2&: \ \mathbf{r}_2(t) = (6 - t)\mathbf{j} + (2t - 6)\mathbf{k}, \quad 3 \le t \le 6 \\ C_3&: \ \mathbf{r}_3(t) = (t - 6)\mathbf{i} + (18 - 2t)\mathbf{k}, \quad 6 \le t \le 9 \end{aligned}$$

The value of the line integral is

$$\begin{aligned} \int_C \mathbf{F} \cdot d\mathbf{r} &= \int_{C_1} \mathbf{F} \cdot \mathbf{r}_1'(t)\, dt + \int_{C_2} \mathbf{F} \cdot \mathbf{r}_2'(t)\, dt + \int_{C_3} \mathbf{F} \cdot \mathbf{r}_3'(t)\, dt \\ &= \int_0^3 t^2\, dt + \int_3^6 (-2t + 6)\, dt + \int_6^9 (-2t + 12)\, dt \\ &= 9 - 9 - 9 \\ &= -9. \end{aligned}$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

EXAMPLE 2 Verifying Stokes's Theorem

See LarsonCalculus.com for an interactive version of this type of example.



Figure 15.65

Let S be the portion of the paraboloid

$$z = 4 - x^2 - y^2$$

lying above the xy-plane, oriented upward (see Figure 15.65). Let C be its boundary curve in the xy-plane, oriented counterclockwise. Verify Stokes's Theorem for

$$\mathbf{F}(x, y, z) = 2z\mathbf{i} + x\mathbf{j} + y^2\mathbf{k}$$

by evaluating the surface integral and the equivalent line integral.

Solution As a *surface integral,* you have $z = g(x, y) = 4 - x^2 - y^2$, $g_x = -2x$, $g_y = -2y$, and

$$\operatorname{curl} \mathbf{F} = \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ \frac{\partial}{\partial x} & \frac{\partial}{\partial y} & \frac{\partial}{\partial z} \\ 2z & x & y^2 \end{vmatrix} = 2y\mathbf{i} + 2\mathbf{j} + \mathbf{k}.$$

By Theorem 15.11 (for an upward normal vector), you obtain

$$\begin{aligned} \iint_S (\operatorname{curl} \mathbf{F}) \cdot \mathbf{N}\, dS &= \iint_R (2y\mathbf{i} + 2\mathbf{j} + \mathbf{k}) \cdot (2x\mathbf{i} + 2y\mathbf{j} + \mathbf{k})\, dA \\ &= \int_{-2}^{2} \int_{-\sqrt{4-x^2}}^{\sqrt{4-x^2}} (4xy + 4y + 1)\, dy\, dx \\ &= \int_{-2}^{2} \left[2xy^2 + 2y^2 + y \right]_{-\sqrt{4-x^2}}^{\sqrt{4-x^2}} dx \\ &= \int_{-2}^{2} 2\sqrt{4 - x^2}\, dx \\ &= \text{Area of circle of radius 2} \\ &= 4\pi. \end{aligned}$$

As a *line integral,* you can parametrize C as

$$\mathbf{r}(t) = 2\cos t\mathbf{i} + 2\sin t\mathbf{j} + 0\mathbf{k}, \quad 0 \le t \le 2\pi.$$

For $\mathbf{F}(x, y, z) = 2z\mathbf{i} + x\mathbf{j} + y^2\mathbf{k}$, you obtain

$$\begin{aligned} \int_C \mathbf{F} \cdot d\mathbf{r} &= \int_C M\, dx + N\, dy + P\, dz \\ &= \int_C 2z\, dx + x\, dy + y^2\, dz \\ &= \int_0^{2\pi} [0 + (2\cos t)(2\cos t) + 0]\, dt \\ &= \int_0^{2\pi} 4\cos^2 t\, dt \\ &= 2\int_0^{2\pi} (1 + \cos 2t)\, dt \\ &= 2\left[t + \frac{1}{2}\sin 2t \right]_0^{2\pi} \\ &= 4\pi. \end{aligned}$$

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.



Figure 15.66

Physical Interpretation of Curl

Stokes's Theorem provides insight into a physical interpretation of curl. In a vector field $\mathbf{F}$, let S_α be a *small* circular disk of radius α, centered at (x, y, z) and with boundary C_α, as shown in Figure 15.66. At each point on the circle C_α, $\mathbf{F}$ has a normal component $\mathbf{F} \cdot \mathbf{N}$ and a tangential component $\mathbf{F} \cdot \mathbf{T}$. The more closely $\mathbf{F}$ and $\mathbf{T}$ are aligned, the greater the value of $\mathbf{F} \cdot \mathbf{T}$. So, a fluid tends to move along the circle rather than across it. Consequently, you say that the line integral around C_α measures the **circulation of F around C_α.** That is,

$$\int_{C_\alpha} \mathbf{F} \cdot \mathbf{T}\, ds = \text{circulation of } \mathbf{F} \text{ around } C_\alpha.$$

Now consider a small disk S_α to be centered at some point (x, y, z) on the surface S, as shown in Figure 15.67. On such a small disk, curl $\mathbf{F}$ is nearly constant, because it varies little from its value at (x, y, z). Moreover, $(\text{curl } \mathbf{F}) \cdot \mathbf{N}$ is also nearly constant on S_α because all unit normals to S_α are about the same. Consequently, Stokes's Theorem yields



Figure 15.67

$$\begin{aligned}\int_{C_\alpha} \mathbf{F} \cdot \mathbf{T}\, ds &= \iint_{S_\alpha} (\text{curl } \mathbf{F}) \cdot \mathbf{N}\, dS \\ &\approx (\text{curl } \mathbf{F}) \cdot \mathbf{N} \iint_{S_\alpha} dS \\ &\approx (\text{curl } \mathbf{F}) \cdot \mathbf{N}(\pi\alpha^2).\end{aligned}$$

So,

$$\begin{aligned}(\text{curl } \mathbf{F}) \cdot \mathbf{N} &\approx \frac{\displaystyle\int_{C_\alpha} \mathbf{F} \cdot \mathbf{T}\, ds}{\pi\alpha^2} \\ &= \frac{\text{circulation of } \mathbf{F} \text{ around } C_\alpha}{\text{area of disk } S_\alpha} \\ &= \text{rate of circulation.}\end{aligned}$$

Assuming conditions are such that the approximation improves for smaller and smaller disks $(\alpha \to 0)$, it follows that

$$(\text{curl } \mathbf{F}) \cdot \mathbf{N} = \lim_{\alpha \to 0} \frac{1}{\pi\alpha^2} \int_{C_\alpha} \mathbf{F} \cdot \mathbf{T}\, ds$$

which is referred to as the **rotation of F about N.** That is,

$$\text{curl } \mathbf{F}(x, y, z) \cdot \mathbf{N} = \text{rotation of } \mathbf{F} \text{ about } \mathbf{N} \text{ at } (x, y, z).$$

In this case, the rotation of $\mathbf{F}$ is maximum when curl $\mathbf{F}$ and $\mathbf{N}$ have the same direction. Normally, this tendency to rotate will vary from point to point on the surface S, and Stokes's Theorem

$$\underbrace{\iint_S (\text{curl } \mathbf{F}) \cdot \mathbf{N}\, dS}_{\text{Surface integral}} = \underbrace{\int_C \mathbf{F} \cdot d\mathbf{r}}_{\text{Line integral}}$$

says that the collective measure of this *rotational* tendency taken over the entire surface S (surface integral) is equal to the tendency of a fluid to *circulate* around the boundary C (line integral).

GO DIGITAL

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

GO DIGITAL

EXAMPLE 3 An Application of Curl

A liquid is swirling around in a cylindrical container of radius 2, so that its motion is described by the velocity field

$$\mathbf{F}(x, y, z) = -y\sqrt{x^2 + y^2}\,\mathbf{i} + x\sqrt{x^2 + y^2}\,\mathbf{j}$$

as shown in the figure. Find

$$\iint_S (\text{curl } \mathbf{F}) \cdot \mathbf{N}\, dS$$

where S is the upper surface of the cylindrical container.



Solution The curl of $\mathbf{F}$ is given by

$$\text{curl } \mathbf{F} = \begin{vmatrix} \mathbf{i} & \mathbf{j} & \mathbf{k} \\ \dfrac{\partial}{\partial x} & \dfrac{\partial}{\partial y} & \dfrac{\partial}{\partial z} \\ -y\sqrt{x^2 + y^2} & x\sqrt{x^2 + y^2} & 0 \end{vmatrix} = 3\sqrt{x^2 + y^2}\,\mathbf{k}.$$

Letting $\mathbf{N} = \mathbf{k}$, you have

$$\begin{aligned} \iint_S (\text{curl } \mathbf{F}) \cdot \mathbf{N}\, dS &= \iint_R 3\sqrt{x^2 + y^2}\, dA \\ &= \int_0^{2\pi} \int_0^2 (3r) r\, dr\, d\theta \\ &= \int_0^{2\pi} r^3 \Big]_0^2 d\theta \\ &= \int_0^{2\pi} 8\, d\theta \\ &= 16\pi. \end{aligned}$$

If curl $\mathbf{F} = \mathbf{0}$ throughout region Q, then the rotation of $\mathbf{F}$ about each unit normal $\mathbf{N}$ is 0. That is, $\mathbf{F}$ is irrotational. From Section 15.1, you know that this is a characteristic of conservative vector fields.

Summary of Integration Formulas

Fundamental Theorem of Calculus

$$\int_a^b F'(x)\, dx = F(b) - F(a)$$

Fundamental Theorem of Line Integrals

$$\int_C \mathbf{F} \cdot d\mathbf{r} = \int_C \nabla f \cdot d\mathbf{r} = f(x(b), y(b)) - f(x(a), y(a))$$

Green's Theorem

$$\int_C M\, dx + N\, dy = \iint_R \left(\frac{\partial N}{\partial x} - \frac{\partial M}{\partial y}\right) dA = \int_C \mathbf{F} \cdot \mathbf{T}\, ds = \int_C \mathbf{F} \cdot d\mathbf{r} = \iint_R (\text{curl } \mathbf{F}) \cdot \mathbf{k}\, dA$$

$$\int_C \mathbf{F} \cdot \mathbf{N}\, ds = \iint_R \text{div } \mathbf{F}\, dA$$

Divergence Theorem

$$\iint_S \mathbf{F} \cdot \mathbf{N}\, dS = \iiint_Q \text{div } \mathbf{F}\, dV$$

Stokes's Theorem

$$\int_C \mathbf{F} \cdot d\mathbf{r} = \iint_S (\text{curl } \mathbf{F}) \cdot \mathbf{N}\, dS$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

15.8 Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Concept Check

1. Explain the benefit of Stokes's Theorem when the boundary of the surface is a piecewise curve.
2. What is a physical interpretation of curl?

Verifying Stokes's Theorem **In Exercises 3–6, verify Stokes's Theorem by evaluating $\int_C \mathbf{F} \cdot d\mathbf{r}$ as a line integral and as a double integral.**

3. $\mathbf{F}(x, y, z) = (-y + z)\mathbf{i} + (x - z)\mathbf{j} + (x - y)\mathbf{k}$
   S: $z = 9 - x^2 - y^2, \quad z \geq 0$
4. $\mathbf{F}(x, y, z) = (-y + z)\mathbf{i} + (x - z)\mathbf{j} + (x - y)\mathbf{k}$
   S: $z = \sqrt{1 - x^2 - y^2}$
5. $\mathbf{F}(x, y, z) = xyz\mathbf{i} + y\mathbf{j} + z\mathbf{k}$
   S: $6x + 6y + z = 12$, first octant
6. $\mathbf{F}(x, y, z) = z^2\mathbf{i} + x^2\mathbf{j} + y^2\mathbf{k}$
   S: $z = y^2, \quad 0 \leq x \leq a, \quad 0 \leq y \leq a$

Using Stokes's Theorem **In Exercises 7–16, use Stokes's Theorem to evaluate $\int_C \mathbf{F} \cdot d\mathbf{r}$. In each case, C is oriented counterclockwise as viewed from above.**

7. $\mathbf{F}(x, y, z) = 2y\mathbf{i} + 3z\mathbf{j} + x\mathbf{k}$
   C: triangle with vertices $(2, 0, 0)$, $(0, 2, 0)$, and $(0, 0, 2)$
8. $\mathbf{F}(x, y, z) = 4z\mathbf{i} + x^2\mathbf{j} + e^y\mathbf{k}$
   C: triangle with vertices $(4, 0, 0)$, $(0, 2, 0)$, and $(0, 0, 8)$
9. $\mathbf{F}(x, y, z) = z^2\mathbf{i} + 2x\mathbf{j} + y^2\mathbf{k}$
   S: $z = 1 - x^2 - y^2, \quad z \geq 0$
10. $\mathbf{F}(x, y, z) = 4xz\mathbf{i} + y\mathbf{j} + 4xy\mathbf{k}$
    S: $z = 9 - x^2 - y^2, \quad z \geq 0$
11. $\mathbf{F}(x, y, z) = z^2\mathbf{i} + y\mathbf{j} + z\mathbf{k}$
    S: $z = \sqrt{4 - x^2 - y^2}$
12. $\mathbf{F}(x, y, z) = x^2\mathbf{i} + z^2\mathbf{j} - xyz\mathbf{k}$
    S: $z = \sqrt{4 - x^2 - y^2}$
13. $\mathbf{F}(x, y, z) = -\ln\sqrt{x^2 + y^2}\,\mathbf{i} + \arctan\frac{x}{y}\mathbf{j} + \mathbf{k}$
    S: $z = 9 - 2x - 3y$ over $r = 2\sin 2\theta$ in the first octant
14. $\mathbf{F}(x, y, z) = yz\mathbf{i} + (2 - 3y)\mathbf{j} + (x^2 + y^2)\mathbf{k}, \quad x^2 + y^2 \leq 16$
    S: the first-octant portion of $x^2 + z^2 = 16$ over $x^2 + y^2 = 16$
15. $\mathbf{F}(x, y, z) = xyz\mathbf{i} + y\mathbf{j} + z\mathbf{k}$
    S: $z = x^2, \quad 0 \leq x \leq a, \quad 0 \leq y \leq a$
16. $\mathbf{F}(x, y, z) = xyz\mathbf{i} + y\mathbf{j} + z\mathbf{k}, \quad x^2 + y^2 \leq a^2$
    S: the first-octant portion of $z = x^2$ over $x^2 + y^2 = a^2$

Motion of a Liquid **In Exercises 17 and 18, the motion of a liquid in a cylindrical container of radius 3 is described by the velocity field $\mathbf{F}(x, y, z)$. Find $\int_S \int (\text{curl } \mathbf{F}) \cdot \mathbf{N}\, dS$, where S is the upper surface of the cylindrical container.**

17. $\mathbf{F}(x, y, z) = -\frac{1}{6}y^3\mathbf{i} + \frac{1}{6}x^3\mathbf{j} + 5\mathbf{k}$
18. $\mathbf{F}(x, y, z) = -z\mathbf{i} + y^2\mathbf{k}$

Exploring Concepts

19. Let $\mathbf{K}$ be a constant vector. Let S be an oriented surface with a unit normal vector $\mathbf{N}$, bounded by a smooth curve C. Determine whether

$$\int_S \int \mathbf{K} \cdot \mathbf{N}\, dS = \frac{1}{2}\int_C (\mathbf{K} \times \mathbf{r}) \cdot d\mathbf{r}.$$

Explain. (*Hint:* Use $\mathbf{r} = x\mathbf{i} + y\mathbf{j} + z\mathbf{k}$.)

20. **HOW DO YOU SEE IT?** Let S_1 be the portion of the paraboloid lying above the xy-plane, and let S_2 be the hemisphere, as shown in the figures. Both surfaces are oriented upward. For a vector field $\mathbf{F}(x, y, z)$ with continuous partial derivatives, does

$$\int_{S_1} \int (\text{curl } \mathbf{F}) \cdot \mathbf{N}\, dS_1 = \int_{S_2} \int (\text{curl } \mathbf{F}) \cdot \mathbf{N}\, dS_2?$$

Explain your reasoning.



PUTNAM EXAM CHALLENGE

21. Let $\mathbf{G}(x, y) = \left(\frac{-y}{x^2 + 4y^2}, \frac{x}{x^2 + 4y^2}, 0\right)$.

Prove or disprove that there is a vector-valued function $\mathbf{F}(x, y, z) = (M(x, y, z), N(x, y, z), P(x, y, z))$ with the following properties:

(i) M, N, P have continuous partial derivatives for all $(x, y, z) \neq (0, 0, 0)$;

(ii) Curl $\mathbf{F} = \mathbf{0}$ for all $(x, y, z) \neq (0, 0, 0)$;

(iii) $\mathbf{F}(x, y, 0) = \mathbf{G}(x, y)$.

This problem was composed by the Committee on the Putnam Prize Competition.
© The Mathematical Association of America. All rights reserved.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Review Exercises

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

Exploring Concepts

In this chapter, you developed the calculus of vector fields. The most important examples of vector fields are velocity fields, gravitational fields, and electric force fields. You also developed several important theorems that are fundamental to understanding calculus. These theorems, which build upon the Fundamental Theorem of Calculus, have an essential similarity. The cumulative (or integrated) effect of the derivatives of a function throughout a region is equal to the values of the function on the boundary of the region. For instance, consider the Fundamental Theorem of Calculus and the Fundamental Theorem of Line Integrals.

Fundamental Theorem of Calculus

$$\int_a^b f(x)\,dx = F(b) - F(a)$$

Fundamental Theorem of Line Integrals

$$\int_C \nabla f \cdot d\mathbf{r} = f(x(b), y(b)) - f(x(a), y(a))$$

This relationship also exists in other fundamental theorems of calculus, such as Green's Theorem, the Divergence Theorem, and Stokes's Theorem.

1. (a) Describe a conservative vector field.

(b) Describe a potential function.

2. Let $\mathbf{F}(x, y, z) = x\mathbf{i} + y\mathbf{j} + z\mathbf{k}$ and let S be the cube bounded by the planes $x = 0, x = 1, y = 0, y = 1, z = 0$, and $z = 1$. Verify the Divergence Theorem by evaluating

$$\iint_S \mathbf{F} \cdot \mathbf{N}\,dS$$

as a surface integral and as a triple integral.

3. Let $\mathbf{F}(x, y, z) = z^2\mathbf{i} + x^2\mathbf{j} + y^2\mathbf{k}$ and let S be the upward oriented surface given by the portion of the paraboloid $z = x^2 + y^2$ that lies below the plane $z = 4$. Verify Stokes's Theorem for $\mathbf{F}$. Is the line integral or the double integral easier to set up? to evaluate? Explain.

4. Define a line integral of a function f along a smooth curve C in the plane and in space. How do you evaluate the line integral as a definite integral?

5. Define a line integral of a continuous vector field $\mathbf{F}$ on a smooth curve C. How do you evaluate the line integral as a definite integral?

6. Consider the vector field $\mathbf{F}(x, y, z) = z\mathbf{i} + x\mathbf{j} + y\mathbf{k}$ and the orientable surface given in parametric form by

$\mathbf{r}(u, v) = (u + v^2)\mathbf{i} + (u - v)\mathbf{j} + u^2\mathbf{k}$

where $0 \le u \le 2$ and $-1 \le v \le 1$.

(a) Find and interpret $\mathbf{r}_u \times \mathbf{r}_v$.

(b) Find $\mathbf{F} \cdot (\mathbf{r}_u \times \mathbf{r}_v)$ as a function of u and v.

(c) Find u and v at the point $P(3, 1, 4)$.

(d) Explain how to find the normal component of $\mathbf{F}$ to the surface at P. Then find this value.

(e) Evaluate the flux integral

$$\iint_S \mathbf{F} \cdot \mathbf{N}\,dS.$$

Sketching a Vector Field

In Exercises 7 and 8, find $\|\mathbf{F}\|$ and sketch several representative vectors in the vector field. Use a graphing utility to verify your results.

7. $\mathbf{F}(x, y, z) = x\mathbf{i} + \mathbf{j} + 2\mathbf{k}$

8. $\mathbf{F}(x, y) = \mathbf{i} - 2y\mathbf{j}$

Finding a Conservative Vector Field

In Exercises 9–12, find the conservative vector field for the potential function by finding its gradient.

9. $f(x, y) = \sin xy - y^2$

10. $f(x, y) = \sqrt{xy}$

11. $f(x, y, z) = 2x^2 + xy + z^2$

12. $f(x, y, z) = x^2e^{yz}$

Testing for a Conservative Vector Field

In Exercises 13–16, determine whether the vector field is conservative.

13. $\mathbf{F}(x, y) = \cosh y\mathbf{i} + x \sinh x\mathbf{j}$

14. $\mathbf{F}(x, y) = \dfrac{y \ln x}{x}\mathbf{i} + (\ln x)^2\mathbf{j}$

15. $\mathbf{F}(x, y, z) = y^2\mathbf{i} + 2xy\mathbf{j} + \cos z\mathbf{k}$

16. $\mathbf{F}(x, y, z) = 3e^{xy}\mathbf{i} + 3e^{x+y}\mathbf{j} + e^{3yz}\mathbf{k}$

Finding a Potential Function

In Exercises 17–24, determine whether the vector field is conservative. If it is, find a potential function for the vector field.

17. $\mathbf{F}(x, y) = -\dfrac{y}{x^2}\mathbf{i} + \dfrac{1}{x}\mathbf{j}$

18. $\mathbf{F}(x, y) = \dfrac{1}{y}\mathbf{i} - \dfrac{y}{x^2}\mathbf{j}$

19. $\mathbf{F}(x, y) = (xy^2 - x^2)\mathbf{i} + (x^2y + y^2)\mathbf{j}$

20. $\mathbf{F}(x, y) = (-2y^3 \sin 2x)\mathbf{i} + 3y^2(1 + \cos 2x)\mathbf{j}$

21. $\mathbf{F}(x, y, z) = 4xy^2\mathbf{i} + 2x^2\mathbf{j} + 2z\mathbf{k}$

22. $\mathbf{F}(x, y, z) = (4xy + z^2)\mathbf{i} + (2x^2 + 6yz)\mathbf{j} + 2xz\mathbf{k}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

23. $\mathbf{F}(x, y, z) = \dfrac{yz\mathbf{i} - xz\mathbf{j} - xy\mathbf{k}}{y^2z^2}$

24. $\mathbf{F}(x, y, z) = (\sin z)(y\mathbf{i} + x\mathbf{j} + \mathbf{k})$

Divergence and Curl **In Exercises 25–32, find (a) the divergence of the vector field and (b) the curl of the vector field.**

25. $\mathbf{F}(x, y, z) = x^2\mathbf{i} + xy^2\mathbf{j} + x^2z\mathbf{k}$

26. $\mathbf{F}(x, y, z) = y^2\mathbf{j} - z^2\mathbf{k}$

27. $\mathbf{F}(x, y, z) = (\cos y + y\cos x)\mathbf{i} + (\sin x - x\sin y)\mathbf{j} + xyz\mathbf{k}$

28. $\mathbf{F}(x, y, z) = (3x - y)\mathbf{i} + (y - 2z)\mathbf{j} + (z - 3x)\mathbf{k}$

29. $\mathbf{F}(x, y, z) = \arcsin x\mathbf{i} + xy^2\mathbf{j} + yz^2\mathbf{k}$

30. $\mathbf{F}(x, y, z) = (x^2 - y)\mathbf{i} - (x + \sin^2 y)\mathbf{j}$

31. $\mathbf{F}(x, y, z) = \ln(x^2 + y^2)\mathbf{i} + \ln(x^2 + y^2)\mathbf{j} + z\mathbf{k}$

32. $\mathbf{F}(x, y, z) = \dfrac{z}{x}\mathbf{i} + \dfrac{z}{y}\mathbf{j} + z^2\mathbf{k}$

Evaluating a Line Integral **In Exercises 33–36, evaluate the line integral along the given path(s).**

33. $\displaystyle\int_C (x^2 + y^2)\,ds$

(a) C: line segment from $(0, 0)$ to $(3, 4)$

(b) C: one revolution counterclockwise around the circle $x^2 + y^2 = 1$, starting at $(1, 0)$

34. $\displaystyle\int_C xy\,ds$

(a) C: line segment from $(0, 0)$ to $(5, 4)$

(b) C: counterclockwise around the triangle with vertices $(0, 0)$, $(4, 0)$, and $(0, 2)$

35. $\displaystyle\int_C (x^2 + y^2)\,ds$

C: $\mathbf{r}(t) = (1 - \sin t)\mathbf{i} + (1 - \cos t)\mathbf{j}, \quad 0 \le t \le 2\pi$

36. $\displaystyle\int_C (x^2 + y^2)\,ds$

C: $\mathbf{r}(t) = (\cos t + t\sin t)\mathbf{i} + (\sin t - t\cos t)\mathbf{j}, \quad 0 \le t \le 2\pi$

Evaluating a Line Integral Using Technology **In Exercises 37 and 38, use a graphing utility to evaluate the line integral along the given path.**

37. $\displaystyle\int_C (2x + y)\,ds$

C: $\mathbf{r}(t) = a\cos^3 t\mathbf{i} + a\sin^3 t\mathbf{j}, \quad 0 \le t \le \dfrac{\pi}{2}$

38. $\displaystyle\int_C (x^2 + y^2 + z^2)\,ds$

C: $\mathbf{r}(t) = t\mathbf{i} + t^2\mathbf{j} + t^{3/2}\mathbf{k}, \quad 0 \le t \le 4$

Mass **In Exercises 39 and 40, find the total mass of the wire with density ρ whose shape is modeled by r.**

39. $\mathbf{r}(t) = 3\cos t\mathbf{i} + 3\sin t\mathbf{j}, \quad 0 \le t \le \pi, \quad \rho(x, y) = 1 + x$

40. $\mathbf{r}(t) = 3\mathbf{i} + t^2\mathbf{j} + 2t\mathbf{k}, \quad 2 \le t \le 4, \quad \rho(x, y, z) = xz$

Evaluating a Line Integral of a Vector Field **In Exercises 41–44, evaluate $\displaystyle\int_C \mathbf{F} \cdot d\mathbf{r}$.**

41. $\mathbf{F}(x, y) = xy\mathbf{i} + 2xy\mathbf{j}$

C: $\mathbf{r}(t) = t^2\mathbf{i} + t^2\mathbf{j}, \quad 0 \le t \le 1$

42. $\mathbf{F}(x, y) = (x - y)\mathbf{i} + (x + y)\mathbf{j}$

C: $\mathbf{r}(t) = 4\cos t\mathbf{i} + 3\sin t\mathbf{j}, \quad 0 \le t \le 2\pi$

43. $\mathbf{F}(x, y, z) = x\mathbf{i} + y\mathbf{j} + z\mathbf{k}$

C: $\mathbf{r}(t) = 2\cos t\mathbf{i} + 2\sin t\mathbf{j} + t\mathbf{k}, \quad 0 \le t \le 2\pi$

44. $\mathbf{F}(x, y, z) = (2y - z)\mathbf{i} + (z - x)\mathbf{j} + (x - y)\mathbf{k}$

C: $\mathbf{r}(t) = -3t\mathbf{i} + (2t + 1)\mathbf{j} + 4\mathbf{k}, \quad 0 \le t \le 2$

Work **In Exercises 45 and 46, find the work done by the force field F on a particle moving along the given path.**

45. $\mathbf{F}(x, y) = x\mathbf{i} - \sqrt{y}\mathbf{j}$

C: $x = t$, $y = t^{3/2}$ from $(0, 0)$ to $(4, 8)$



Figure for 45



Figure for 46

46. $\mathbf{F}(x, y, z) = 2\mathbf{i} + y\mathbf{j} + z\mathbf{k}$

C: $\mathbf{r}(t) = \cos t\mathbf{i} + \sin t\mathbf{j} + 2t\mathbf{k}, \quad 0 \le t \le \pi$

Evaluating a Line Integral in Differential Form **In Exercises 47 and 48, evaluate $\displaystyle\int_C (y - x)\,dx + (2x + 5y)\,dy$.**

47. C: line segments from $(0, 0)$ to $(2, -4)$ and $(2, -4)$ to $(4, -4)$

48. C: arc on $y = \sqrt{x}$ from $(0, 0)$ to $(9, 3)$

Lateral Surface Area **In Exercises 49 and 50, find the area of the lateral surface over the curve C in the xy-plane and under the surface $z = f(x, y)$, where**

Lateral surface area $= \displaystyle\int_C f(x, y)\,ds$.

49. $f(x, y) = 3 + \sin(x + y)$; C: $y = 2x$ from $(0, 0)$ to $(2, 4)$

50. $f(x, y) = 12 - x - y$; C: $y = x^2$ from $(0, 0)$ to $(2, 4)$

Line Integral of a Conservative Vector Field **In Exercises 51 and 52, (a) show that F is conservative and (b) verify that the value of $\displaystyle\int_C \mathbf{F} \cdot d\mathbf{r}$ is the same for each parametric representation of C.**

51. $\mathbf{F}(x, y) = (3x + 4)\mathbf{i} + y^3\mathbf{j}$

(i) $\mathbf{r}(t) = t\mathbf{i} + t\mathbf{j}, \; 0 \le t \le 4$

(ii) $\mathbf{r}(w) = w^2\mathbf{i} + w^2\mathbf{j}, \; 0 \le w \le 2$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

52. $\mathbf{F}(x, y) = xy\mathbf{i} + \frac{1}{2}x^2\mathbf{j}$

(i) $\mathbf{r}(\theta) = \sin\theta\mathbf{i} + \cos\theta\mathbf{j}, 0 \le \theta \le \dfrac{\pi}{2}$

(ii) $\mathbf{r}(t) = t\mathbf{i} + (1 - t)\mathbf{j}, 0 \le t \le 1$

Using the Fundamental Theorem of Line Integrals **In Exercises 53–56, evaluate $\int_C \mathbf{F} \cdot d\mathbf{r}$ using the Fundamental Theorem of Line Integrals.**

53. $\mathbf{F}(x, y) = e^{2x}\mathbf{i} + e^{2y}\mathbf{j}$

C: line segment from $(-1, -1)$ to $(0, 0)$

54. $\mathbf{F}(x, y) = -\sin y\mathbf{i} - x\cos y\mathbf{j}$

C: clockwise around the circle $(x + 1)^2 + y^2 = 16$ from $(-1, 4)$ to $(3, 0)$

55. $\mathbf{F}(x, y, z) = 2xyz\mathbf{i} + x^2z\mathbf{j} + x^2y\mathbf{k}$

C: smooth curve from $(0, 0, 0)$ to $(1, 3, 2)$

56. $\mathbf{F}(x, y, z) = y\mathbf{i} + x\mathbf{j} + \dfrac{1}{z}\mathbf{k}$

C: smooth curve from $(0, 0, 1)$ to $(4, 4, 4)$

Finding Work in a Conservative Force Field **In Exercises 57 and 58, (a) show that $\int_C \mathbf{F} \cdot d\mathbf{r}$ is independent of path and (b) calculate the work done by the force field F on an object moving along a curve from P to Q.**

57. $\mathbf{F}(x, y) = (1 - 3xy^2)\mathbf{i} - 3x^2y\mathbf{j}$; $P(4, 2), Q(0, 1)$

58. $\mathbf{F}(x, y) = e^{2y}\mathbf{i} + 2xe^{2y}\mathbf{j}$; $P(-1, 3), Q(4, 5)$

Evaluating a Line Integral Using Green's Theorem **In Exercises 59–64, use Green's Theorem to evaluate the line integral.**

59. $\displaystyle\int_C y\,dx + 2x\,dy$

C: square with vertices $(0, 0)$, $(0, 1)$, $(1, 0)$, and $(1, 1)$

60. $\displaystyle\int_C xy\,dx + (x^2 + y^2)\,dy$

C: square with vertices $(0, 0)$, $(0, 2)$, $(2, 0)$, and $(2, 2)$

61. $\displaystyle\int_C xy^2\,dx + x^2y\,dy$

C: $x = 4\cos t, y = 4\sin t$

62. $\displaystyle\int_C (x^2 - y^2)\,dx + 3y^2\,dy$

C: $x^2 + y^2 = 9$

63. $\displaystyle\int_C xy\,dx + x^2\,dy$

C: boundary of the region between the graphs of $y = x^2$ and $y = 1$

64. $\displaystyle\int_C y^2\,dx + x^{4/3}\,dy$

C: $x^{2/3} + y^{2/3} = 1$

Work **In Exercises 65 and 66, use Green's Theorem to calculate the work done by the force F on a particle that is moving counterclockwise around the closed path C.**

65. $\mathbf{F}(x, y) = y^2\mathbf{i} + 2xy\mathbf{j}$

C: $x^2 + y^2 = 36$

66. $\mathbf{F}(x, y) = 3\mathbf{i} + (x^3 + 1)\mathbf{j}$

C: boundary of the region lying between the graphs of $y = x^2$ and $y = 4$

Area **In Exercises 67 and 68, use a line integral to find the area of the region R.**

67. R: triangle bounded by the graphs of $y = \frac{1}{2}x$, $y = 6 - x$, and $y = x$

68. R: region bounded by the graphs of $y = 3x$ and $y = 4 - x^2$

Sketching a Parametric Surface **In Exercises 69 and 70, find the rectangular equation for the surface by eliminating the parameters from the vector-valued function. Identify the surface and sketch its graph.**

69. $\mathbf{r}(u, v) = 3u\cos v\mathbf{i} + 3u\sin v\mathbf{j} + 18u^2\mathbf{k}$

70. $\mathbf{r}(u, v) = 3(u + v)\mathbf{i} + u\mathbf{j} - 6v\mathbf{k}$

Graphing a Parametric Surface **In Exercises 71 and 72, use a graphing utility to graph the surface represented by the vector-valued function.**

71. $\mathbf{r}(u, v) = \sec u\cos v\mathbf{i} + (1 + 2\tan u)\sin v\mathbf{j} + 2u\mathbf{k}$

$0 \le u \le \dfrac{\pi}{3}, \quad 0 \le v \le 2\pi$

72. $\mathbf{r}(u, v) = e^{-u/4}\cos v\mathbf{i} + e^{-u/4}\sin v\mathbf{j} + \dfrac{u}{6}\mathbf{k}$

$0 \le u \le 4, \quad 0 \le v \le 2\pi$

Representing a Surface Parametrically **In Exercises 73 and 74, find a vector-valued function whose graph is the indicated surface.**

73. The ellipsoid $\dfrac{x^2}{1} + \dfrac{y^2}{8} + \dfrac{z^2}{9} = 1$

74. The part of the plane $z = 2$ that lies inside the cylinder $x^2 + y^2 = 25$

Representing a Surface of Revolution Parametrically **In Exercises 75 and 76, write a set of parametric equations for the surface of revolution obtained by revolving the graph of the function about the given axis.**

Function	Axis of Revolution
75. $y = 2x^3, 0 \le x \le 2$	x-axis
76. $z = \sqrt{y + 1}, 0 \le y \le 3$	y-axis

Finding Surface Area **In Exercises 77 and 78, find the area of the surface over the given region. Use a graphing utility to verify your results.**

77. $\mathbf{r}(u, v) = 4u\mathbf{i} + (3u - v)\mathbf{j} + v\mathbf{k}$

$0 \le u \le 3, \quad 0 \le v \le 1$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

78. $\mathbf{r}(u, v) = 3u \cos v\mathbf{i} + 3u \sin v\mathbf{j} + u\mathbf{k}$

$0 \le u \le 2, \quad 0 \le v \le 2\pi$

Evaluating a Surface Integral **In Exercises 79 and 80, evaluate $\int_S\int (5x + y - 2z)\, dS$.**

79. S: $z = x + \frac{y}{2}, \quad 0 \le x \le 2, \quad 0 \le y \le 5$

80. S: $z = e^2 - x, \quad 0 \le x \le 4, \quad 0 \le y \le \sqrt{x}$

Mass **In Exercises 81 and 82, find the mass of the surface lamina S of density ρ.**

81. S: $2y + 6x + z = 18$, first octant, $\rho(x, y, z) = 2x$

82. S: $z = 20 - 4x - 5y$, first octant, $\rho(x, y, z) = ky$

Evaluating a Surface Integral **In Exercises 83 and 84, evaluate $\int_S\int f(x, y)\, dS$.**

83. $f(x, y) = x + y$

S: $\mathbf{r}(u, v) = u\mathbf{i} + v\mathbf{j} + 5v\mathbf{k}, \quad 0 \le u \le 1, \quad 0 \le v \le 3$

84. $f(x, y) = x^2y$

S: $\mathbf{r}(u, v) = 5 \cos u\mathbf{i} + 5 \sin u\mathbf{j} + v\mathbf{k}$

$0 \le u \le \frac{\pi}{2}, \quad 0 \le v \le 1$

Evaluating a Flux Integral **In Exercises 85 and 86, find the flux of F across S,**

$$\int_S\int \mathbf{F} \cdot \mathbf{N}\, dS$$

where N is the upward unit normal vector to S.

85. $\mathbf{F}(x, y, z) = -2\mathbf{i} - 2\mathbf{j} + \mathbf{k}$

S: $z = 25 - x^2 - y^2, \quad z \ge 0$

86. $\mathbf{F}(x, y, z) = x\mathbf{i} + 2y\mathbf{j} + 2z\mathbf{k}$

S: $x + y + 3z = 3$, first octant

Using the Divergence Theorem **In Exercises 87 and 88, use the Divergence Theorem to evaluate**

$$\int_S\int \mathbf{F} \cdot \mathbf{N}\, dS$$

and find the outward flux of F through the surface of the solid bounded by the graphs of the equations.

87. $\mathbf{F}(x, y, z) = x^2\mathbf{i} + xy\mathbf{j} + z\mathbf{k}$

Q: solid region bounded by the coordinate planes and the plane $2x + 3y + 4z = 12$

88. $\mathbf{F}(x, y, z) = x\mathbf{i} + y\mathbf{j} + z\mathbf{k}$

Q: solid region bounded by the coordinate planes and the plane $2x + 3y + 4z = 12$

Using Stokes's Theorem **In Exercises 89 and 90, use Stokes's Theorem to evaluate $\int_C \mathbf{F} \cdot d\mathbf{r}$. In each case, C is oriented counterclockwise as viewed from above.**

89. $\mathbf{F}(x, y, z) = (\cos y + y \cos x)\mathbf{i} + (\sin x - x \sin y)\mathbf{j} + xyz\mathbf{k}$

S: portion of $z = y^2$ over the square in the xy-plane with vertices $(0, 0)$, $(a, 0)$, (a, a), and $(0, a)$

90. $\mathbf{F}(x, y, z) = (x - z)\mathbf{i} + (y - z)\mathbf{j} + x^2\mathbf{k}$

S: first-octant portion of the plane $3x + y + 2z = 12$

Motion of a Liquid **In Exercises 91 and 92, the motion of a liquid in a cylindrical container of radius 4 is described by the velocity field $\mathbf{F}(x, y, z)$. Find $\int_S\int (\text{curl } \mathbf{F}) \cdot \mathbf{N}\, dS$, where S is the upper surface of the cylindrical container.**

91. $\mathbf{F}(x, y, z) = \mathbf{i} + x\mathbf{j} - \mathbf{k}$

92. $\mathbf{F}(x, y, z) = y^2\mathbf{i} + 3z\mathbf{j} + \mathbf{k}$

Building on Concepts

93. Let $\mathbf{F}(x, y, z) = x\mathbf{i} + y\mathbf{j} + z\mathbf{k}$ and let $f(x, y, z) = \|\mathbf{F}(x, y, z)\|$.

(a) Show that $\nabla(\ln f) = \frac{\mathbf{F}}{f^2}$.

(b) Show that $\nabla\left(\frac{1}{f}\right) = -\frac{\mathbf{F}}{f^3}$.

(c) Show that $\nabla f^n = nf^{n-2}\mathbf{F}$.

(d) The **Laplacian** is the differential operator

$$\nabla^2 = \nabla \cdot \nabla = \frac{\partial^2}{\partial x^2} + \frac{\partial^2}{\partial y^2} + \frac{\partial^2}{\partial z^2}$$

and **Laplace's equation** is

$$\nabla^2 w = \frac{\partial^2 w}{\partial x^2} + \frac{\partial^2 w}{\partial y^2} + \frac{\partial^2 w}{\partial z^2} = 0.$$

Any function that satisfies this equation is called **harmonic.** Show that the function $w = 1/f$ is harmonic.

94. The figure shows the force field

$\mathbf{F}(x, y) = 3x^2y^2\mathbf{i} + 2x^3y\mathbf{j}$.

Three particles move from the point $(1, 1)$ to the point $(2, 4)$ along different paths. Explain why the work done is the same for each particle, and find the value of the work.



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

P.S. Problem Solving

See CalcChat.com for tutorial help and worked-out solutions to odd-numbered exercises.

GO DIGITAL

1. Heat Flux Consider a single heat source located at the origin with temperature

$$T(x, y, z) = \frac{25}{\sqrt{x^2 + y^2 + z^2}}.$$

(a) Calculate the heat flux across the surface

$$S = \left\{(x, y, z): z = \sqrt{1 - x^2}, -\frac{1}{2} \le x \le \frac{1}{2}, 0 \le y \le 1\right\}$$

as shown in the figure.



(b) Repeat the calculation in part (a) using the parametrization

$$x = \cos u, \quad y = v, \quad z = \sin u$$

where

$$\frac{\pi}{3} \le u \le \frac{2\pi}{3} \quad \text{and} \quad 0 \le v \le 1.$$

2. Green's Theorem Consider the line integral

$$\int_C y^n\,dx + x^n\,dy$$

where C is the boundary of the region lying between the graphs of $y = \sqrt{a^2 - x^2}$, $a > 0$, and $y = 0$.

(a) Use a graphing utility to verify Green's Theorem for n, an odd integer from 1 through 7.

(b) Use a graphing utility to verify Green's Theorem for n, an even integer from 2 through 8.

(c) For n an odd integer, make a conjecture about the value of the integral.

3. Area Use a line integral to find the area bounded by one arch of the cycloid $x(\theta) = a(\theta - \sin\theta)$, $y(\theta) = a(1 - \cos\theta)$, $0 \le \theta \le 2\pi$, as shown in the figure.



4. Verifying Identities

(a) Let f and g be scalar functions with continuous partial derivatives, and let C and S satisfy the conditions of Stokes's Theorem. Verify each identity.

(i) $\displaystyle\int_C (f\nabla g)\cdot d\mathbf{r} = \iint_S (\nabla f \times \nabla g)\cdot \mathbf{N}\,dS$

(ii) $\displaystyle\int_C (f\nabla f)\cdot d\mathbf{r} = 0$

(iii) $\displaystyle\int_C (f\nabla g + g\nabla f)\cdot d\mathbf{r} = 0$

(b) Demonstrate the results of part (a) for the functions

$$f(x, y, z) = xyz \quad \text{and} \quad g(x, y, z) = z.$$

Let S be the hemisphere

$$z = \sqrt{4 - x^2 - y^2}.$$

5. Moments of Inertia Consider a wire of density $\rho(x, y, z)$ given by the space curve

$$C: \mathbf{r}(t) = x(t)\mathbf{i} + y(t)\mathbf{j} + z(t)\mathbf{k}, \quad a \le t \le b.$$

The **moments of inertia** about the x-, y-, and z-axes are given by

$$I_x = \int_C (y^2 + z^2)\rho(x, y, z)\,ds$$

$$I_y = \int_C (x^2 + z^2)\rho(x, y, z)\,ds$$

$$I_z = \int_C (x^2 + y^2)\rho(x, y, z)\,ds.$$

Find the moments of inertia for a wire of uniform density $\rho = 1$ in the shape of the helix

$$\mathbf{r}(t) = 3\cos t\,\mathbf{i} + 3\sin t\,\mathbf{j} + 2t\,\mathbf{k}, \quad 0 \le t \le 2\pi \text{ (see figure).}$$



Figure for 5



Figure for 6

6. Moments of Inertia Using the formulas from Exercise 5, find the moments of inertia for a wire of density

$$\rho = \frac{1}{1 + t}$$

given by the curve

$$C: \mathbf{r}(t) = \frac{t^2}{2}\mathbf{i} + t\,\mathbf{j} + \frac{2\sqrt{2}t^{3/2}}{3}\mathbf{k}, \quad 0 \le t \le 1 \text{ (see figure).}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Appendices

Appendix A Proofs of Selected Theorems A2
Appendix B Integration Tables A3
Appendix C Precalculus Review (Online)
- **C.1** Real Numbers and the Real Number Line
- **C.2** The Cartesian Plane

Appendix D Rotation and the General Second-Degree Equation (Online)
Appendix E Complex Numbers (Online)
Appendix F Business and Economic Applications (Online)
Appendix G Fitting Models to Data (Online)

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

A Proofs of Selected Theorems

The text version of Appendix A, Proofs of Selected Theorems, is available at *LarsonCalculus.com* and by scanning the on this page. Also, to enhance your study of calculus, each proof is available in video format at *LarsonCalculus.com*. At this website, you can watch videos of Bruce Edwards explaining each proof in the text and in Appendix A. To access a video, visit the website at *LarsonCalculus.com* or scan the on the page where the proof (or its reference) occurs.

GO DIGITAL

Sample Video: Bruce Edwards's Proof of the Power Rule at *LarsonCalculus.com*


Proof: The Power Rule
GO DIGITAL
2.2 Basic Differentiation Rules and Rates of Change 111
The Power Rule
Before proving the next rule, it is important to review the procedure for expanding a binomial.
$(x + \Delta x)^2 = x^2 + 2x\Delta x + (\Delta x)^2$
$(x + \Delta x)^3 = x^3 + 3x^2\Delta x + 3x(\Delta x)^2 + (\Delta x)^3$
$(x + \Delta x)^4 = x^4 + 4x^3\Delta x + 6x^2(\Delta x)^2 + 4x(\Delta x)^3 + (\Delta x)^4$
$(x + \Delta x)^5 = x^5 + 5x^4\Delta x + 10x^3(\Delta x)^2 + 10x^2(\Delta x)^3 + 5x(\Delta x)^4 + (\Delta x)^5$
The general binomial expansion for a positive integer n is
$(x + \Delta x)^n = x^n + nx^{n-1}(\Delta x) + \frac{n(n-1)x^{n-2}}{2}(\Delta x)^2 + \cdots + (\Delta x)^n.$
$(\Delta x)^2$ is a factor of these terms.
This binomial expansion is used in proving a special case of the Power Rule.
THEOREM 2.3 The Power Rule
If n is a rational number, then the function $f(x) = x^n$ is differentiable and
$\frac{d}{dx}[x^n] = nx^{n-1}.$
For f to be differentiable at $x = 0$, n must be a number such that x^{n-1} is defined on an interval containing 0.
REMARK Recall from Example 7 in Section 2.1 that the function $f(x) = x^{1/3}$ is
Proof If n is a positive integer greater than 1, then the binomial expansion produces
$\frac{d}{dx}[x^n] = \lim_{\Delta x \to 0} \frac{(x + \Delta x)^n - x^n}{\Delta x}$
$= \lim_{\Delta x \to 0} \frac{x^n + nx^{n-1}(\Delta x) + \frac{n(n-1)x^{n-2}}{2}(\Delta x)^2 + \cdots + (\Delta x)^n - x^n}{\Delta x}$
$= \lim_{\Delta x \to 0} \left[nx^{n-1} + \frac{n(n-1)x^{n-2}}{2}(\Delta x) + \cdots + (\Delta x)^{n-1} \right]$
$= nx^{n-1} + 0 + \cdots + 0$
$= nx^{n-1}.$
This proves the case for which n is a positive integer greater than 1. It is left to you to prove the case for $n = 1$. Example 7 in Section 2.3 proves the case for which n is a negative integer. In Exercise 73 in Section 2.5, you are asked to prove the case for which n is rational. (In Section 5.5, the Power Rule will be extended to cover irrational values of n.)
When using the Power Rule, the case for which $n = 1$ is best thought of as a separate differentiation rule. That is,
$\frac{d}{dx}[x] = 1.$ Power Rule when $n = 1$
This rule is consistent with the fact that the slope of the line $y = x$ is 1, as shown in Figure 2.15.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

B Integration Tables

Forms Involving u^n

1. $\displaystyle\int u^n\,du = \frac{u^{n+1}}{n+1} + C, \quad n \neq -1$

2. $\displaystyle\int \frac{1}{u}\,du = \ln|u| + C$

Forms Involving $a + bu$

3. $\displaystyle\int \frac{u}{a+bu}\,du = \frac{1}{b^2}(bu - a\ln|a+bu|) + C$

4. $\displaystyle\int \frac{u}{(a+bu)^2}\,du = \frac{1}{b^2}\left(\frac{a}{a+bu} + \ln|a+bu|\right) + C$

5. $\displaystyle\int \frac{u}{(a+bu)^n}\,du = \frac{1}{b^2}\left[\frac{-1}{(n-2)(a+bu)^{n-2}} + \frac{a}{(n-1)(a+bu)^{n-1}}\right] + C, \quad n \neq 1, 2$

6. $\displaystyle\int \frac{u^2}{a+bu}\,du = \frac{1}{b^3}\left[-\frac{bu}{2}(2a - bu) + a^2\ln|a+bu|\right] + C$

7. $\displaystyle\int \frac{u^2}{(a+bu)^2}\,du = \frac{1}{b^3}\left(bu - \frac{a^2}{a+bu} - 2a\ln|a+bu|\right) + C$

8. $\displaystyle\int \frac{u^2}{(a+bu)^3}\,du = \frac{1}{b^3}\left[\frac{2a}{a+bu} - \frac{a^2}{2(a+bu)^2} + \ln|a+bu|\right] + C$

9. $\displaystyle\int \frac{u^2}{(a+bu)^n}\,du = \frac{1}{b^3}\left[\frac{-1}{(n-3)(a+bu)^{n-3}} + \frac{2a}{(n-2)(a+bu)^{n-2}} - \frac{a^2}{(n-1)(a+bu)^{n-1}}\right] + C, \quad n \neq 1, 2, 3$

10. $\displaystyle\int \frac{1}{u(a+bu)}\,du = \frac{1}{a}\ln\left|\frac{u}{a+bu}\right| + C$

11. $\displaystyle\int \frac{1}{u(a+bu)^2}\,du = \frac{1}{a}\left(\frac{1}{a+bu} + \frac{1}{a}\ln\left|\frac{u}{a+bu}\right|\right) + C$

12. $\displaystyle\int \frac{1}{u^2(a+bu)}\,du = -\frac{1}{a}\left(\frac{1}{u} + \frac{b}{a}\ln\left|\frac{u}{a+bu}\right|\right) + C$

13. $\displaystyle\int \frac{1}{u^2(a+bu)^2}\,du = -\frac{1}{a^2}\left[\frac{a+2bu}{u(a+bu)} + \frac{2b}{a}\ln\left|\frac{u}{a+bu}\right|\right] + C$

Forms Involving $a + bu + cu^2$, $b^2 \neq 4ac$

14. $\displaystyle\int \frac{1}{a+bu+cu^2}\,du = \begin{cases} \dfrac{2}{\sqrt{4ac-b^2}}\arctan\dfrac{2cu+b}{\sqrt{4ac-b^2}} + C, & b^2 < 4ac \\ \dfrac{1}{\sqrt{b^2-4ac}}\ln\left|\dfrac{2cu+b-\sqrt{b^2-4ac}}{2cu+b+\sqrt{b^2-4ac}}\right| + C, & b^2 > 4ac \end{cases}$

15. $\displaystyle\int \frac{u}{a+bu+cu^2}\,du = \frac{1}{2c}\left(\ln|a+bu+cu^2| - b\int \frac{1}{a+bu+cu^2}\,du\right)$

Forms Involving $\sqrt{a+bu}$

16. $\displaystyle\int u^n\sqrt{a+bu}\,du = \frac{2}{b(2n+3)}\left[u^n(a+bu)^{3/2} - na\int u^{n-1}\sqrt{a+bu}\,du\right]$

17. $\displaystyle\int \frac{1}{u\sqrt{a+bu}}\,du = \begin{cases} \dfrac{1}{\sqrt{a}}\ln\left|\dfrac{\sqrt{a+bu}-\sqrt{a}}{\sqrt{a+bu}+\sqrt{a}}\right| + C, & a > 0 \\ \dfrac{2}{\sqrt{-a}}\arctan\sqrt{\dfrac{a+bu}{-a}} + C, & a < 0 \end{cases}$

18. $\displaystyle\int \frac{1}{u^n\sqrt{a+bu}}\,du = \frac{-1}{a(n-1)}\left[\frac{\sqrt{a+bu}}{u^{n-1}} + \frac{(2n-3)b}{2}\int \frac{1}{u^{n-1}\sqrt{a+bu}}\,du\right], \quad n \neq 1$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

19. $\displaystyle\int \frac{\sqrt{a+bu}}{u}\,du = 2\sqrt{a+bu} + a\int \frac{1}{u\sqrt{a+bu}}\,du$

20. $\displaystyle\int \frac{\sqrt{a+bu}}{u^n}\,du = \frac{-1}{a(n-1)}\left[\frac{(a+bu)^{3/2}}{u^{n-1}} + \frac{(2n-5)b}{2}\int \frac{\sqrt{a+bu}}{u^{n-1}}\,du\right],\ n \neq 1$

21. $\displaystyle\int \frac{u}{\sqrt{a+bu}}\,du = \frac{-2(2a-bu)}{3b^2}\sqrt{a+bu} + C$

22. $\displaystyle\int \frac{u^n}{\sqrt{a+bu}}\,du = \frac{2}{(2n+1)b}\left(u^n\sqrt{a+bu} - na\int \frac{u^{n-1}}{\sqrt{a+bu}}\,du\right)$

Forms Involving $a^2 \pm u^2$, $a > 0$

23. $\displaystyle\int \frac{1}{a^2+u^2}\,du = \frac{1}{a}\arctan\frac{u}{a} + C$

24. $\displaystyle\int \frac{1}{u^2-a^2}\,du = -\int \frac{1}{a^2-u^2}\,du = \frac{1}{2a}\ln\left|\frac{u-a}{u+a}\right| + C$

25. $\displaystyle\int \frac{1}{(a^2 \pm u^2)^n}\,du = \frac{1}{2a^2(n-1)}\left[\frac{u}{(a^2 \pm u^2)^{n-1}} + (2n-3)\int \frac{1}{(a^2 \pm u^2)^{n-1}}\,du\right],\ n \neq 1$

Forms Involving $\sqrt{u^2 \pm a^2}$, $a > 0$

26. $\displaystyle\int \sqrt{u^2 \pm a^2}\,du = \frac{1}{2}\left(u\sqrt{u^2 \pm a^2} \pm a^2\ln\left|u + \sqrt{u^2 \pm a^2}\right|\right) + C$

27. $\displaystyle\int u^2\sqrt{u^2 \pm a^2}\,du = \frac{1}{8}\left[u(2u^2 \pm a^2)\sqrt{u^2 \pm a^2} - a^4\ln\left|u + \sqrt{u^2 \pm a^2}\right|\right] + C$

28. $\displaystyle\int \frac{\sqrt{u^2+a^2}}{u}\,du = \sqrt{u^2+a^2} - a\ln\left|\frac{a+\sqrt{u^2+a^2}}{u}\right| + C$

29. $\displaystyle\int \frac{\sqrt{u^2-a^2}}{u}\,du = \sqrt{u^2-a^2} - a\,\text{arcsec}\,\frac{|u|}{a} + C$

30. $\displaystyle\int \frac{\sqrt{u^2 \pm a^2}}{u^2}\,du = \frac{-\sqrt{u^2 \pm a^2}}{u} + \ln\left|u + \sqrt{u^2 \pm a^2}\right| + C$

31. $\displaystyle\int \frac{1}{\sqrt{u^2 \pm a^2}}\,du = \ln\left|u + \sqrt{u^2 \pm a^2}\right| + C$

32. $\displaystyle\int \frac{1}{u\sqrt{u^2+a^2}}\,du = \frac{-1}{a}\ln\left|\frac{a+\sqrt{u^2+a^2}}{u}\right| + C$

33. $\displaystyle\int \frac{1}{u\sqrt{u^2-a^2}}\,du = \frac{1}{a}\,\text{arcsec}\,\frac{|u|}{a} + C$

34. $\displaystyle\int \frac{u^2}{\sqrt{u^2 \pm a^2}}\,du = \frac{1}{2}\left(u\sqrt{u^2 \pm a^2} \mp a^2\ln\left|u + \sqrt{u^2 \pm a^2}\right|\right) + C$

35. $\displaystyle\int \frac{1}{u^2\sqrt{u^2 \pm a^2}}\,du = \mp\frac{\sqrt{u^2 \pm a^2}}{a^2u} + C$

36. $\displaystyle\int \frac{1}{(u^2 \pm a^2)^{3/2}}\,du = \frac{\pm u}{a^2\sqrt{u^2 \pm a^2}} + C$

Forms Involving $\sqrt{a^2 - u^2}$, $a > 0$

37. $\displaystyle\int \sqrt{a^2-u^2}\,du = \frac{1}{2}\left(u\sqrt{a^2-u^2} + a^2\arcsin\frac{u}{a}\right) + C$

38. $\displaystyle\int u^2\sqrt{a^2-u^2}\,du = \frac{1}{8}\left[u(2u^2-a^2)\sqrt{a^2-u^2} + a^4\arcsin\frac{u}{a}\right] + C$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

39. $\displaystyle\int \frac{\sqrt{a^2-u^2}}{u}\,du = \sqrt{a^2-u^2} - a\ln\left|\frac{a+\sqrt{a^2-u^2}}{u}\right| + C$

40. $\displaystyle\int \frac{\sqrt{a^2-u^2}}{u^2}\,du = \frac{-\sqrt{a^2-u^2}}{u} - \arcsin\frac{u}{a} + C$

41. $\displaystyle\int \frac{1}{\sqrt{a^2-u^2}}\,du = \arcsin\frac{u}{a} + C$

42. $\displaystyle\int \frac{1}{u\sqrt{a^2-u^2}}\,du = \frac{-1}{a}\ln\left|\frac{a+\sqrt{a^2-u^2}}{u}\right| + C$

43. $\displaystyle\int \frac{u^2}{\sqrt{a^2-u^2}}\,du = \frac{1}{2}\left(-u\sqrt{a^2-u^2} + a^2\arcsin\frac{u}{a}\right) + C$

44. $\displaystyle\int \frac{1}{u^2\sqrt{a^2-u^2}}\,du = \frac{-\sqrt{a^2-u^2}}{a^2u} + C$

45. $\displaystyle\int \frac{1}{(a^2-u^2)^{3/2}}\,du = \frac{u}{a^2\sqrt{a^2-u^2}} + C$

Forms Involving sin *u* or cos *u*

46. $\displaystyle\int \sin u\,du = -\cos u + C$

47. $\displaystyle\int \cos u\,du = \sin u + C$

48. $\displaystyle\int \sin^2 u\,du = \frac{1}{2}(u - \sin u\cos u) + C$

49. $\displaystyle\int \cos^2 u\,du = \frac{1}{2}(u + \sin u\cos u) + C$

50. $\displaystyle\int \sin^n u\,du = -\frac{\sin^{n-1}u\cos u}{n} + \frac{n-1}{n}\int \sin^{n-2}u\,du$

51. $\displaystyle\int \cos^n u\,du = \frac{\cos^{n-1}u\sin u}{n} + \frac{n-1}{n}\int \cos^{n-2}u\,du$

52. $\displaystyle\int u\sin u\,du = \sin u - u\cos u + C$

53. $\displaystyle\int u\cos u\,du = \cos u + u\sin u + C$

54. $\displaystyle\int u^n\sin u\,du = -u^n\cos u + n\int u^{n-1}\cos u\,du$

55. $\displaystyle\int u^n\cos u\,du = u^n\sin u - n\int u^{n-1}\sin u\,du$

56. $\displaystyle\int \frac{1}{1\pm\sin u}\,du = \tan u \mp \sec u + C$

57. $\displaystyle\int \frac{1}{1\pm\cos u}\,du = -\cot u \pm \csc u + C$

58. $\displaystyle\int \frac{1}{\sin u\cos u}\,du = \ln|\tan u| + C$

Forms Involving tan *u*, cot *u*, sec *u*, or csc *u*

59. $\displaystyle\int \tan u\,du = -\ln|\cos u| + C$

60. $\displaystyle\int \cot u\,du = \ln|\sin u| + C$

61. $\displaystyle\int \sec u\,du = \ln|\sec u + \tan u| + C$

62. $\displaystyle\int \csc u\,du = \ln|\csc u - \cot u| + C$ or $\displaystyle\int \csc u\,du = -\ln|\csc u + \cot u| + C$

63. $\displaystyle\int \tan^2 u\,du = -u + \tan u + C$

64. $\displaystyle\int \cot^2 u\,du = -u - \cot u + C$

65. $\displaystyle\int \sec^2 u\,du = \tan u + C$

66. $\displaystyle\int \csc^2 u\,du = -\cot u + C$

67. $\displaystyle\int \tan^n u\,du = \frac{\tan^{n-1}u}{n-1} - \int \tan^{n-2}u\,du,\ n \neq 1$

68. $\displaystyle\int \cot^n u\,du = -\frac{\cot^{n-1}u}{n-1} - \int \cot^{n-2}u\,du,\ n \neq 1$

69. $\displaystyle\int \sec^n u\,du = \frac{\sec^{n-2}u\tan u}{n-1} + \frac{n-2}{n-1}\int \sec^{n-2}u\,du,\ n \neq 1$

70. $\displaystyle\int \csc^n u\,du = -\frac{\csc^{n-2}u\cot u}{n-1} + \frac{n-2}{n-1}\int \csc^{n-2}u\,du,\ n \neq 1$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

71. $\displaystyle\int \frac{1}{1 \pm \tan u}\,du = \frac{1}{2}(u \pm \ln|\cos u \pm \sin u|) + C$

72. $\displaystyle\int \frac{1}{1 \pm \cot u}\,du = \frac{1}{2}(u \mp \ln|\sin u \pm \cos u|) + C$

73. $\displaystyle\int \frac{1}{1 \pm \sec u}\,du = u + \cot u \mp \csc u + C$

74. $\displaystyle\int \frac{1}{1 \pm \csc u}\,du = u - \tan u \pm \sec u + C$

Forms Involving Inverse Trigonometric Functions

75. $\displaystyle\int \arcsin u\,du = u \arcsin u + \sqrt{1 - u^2} + C$

76. $\displaystyle\int \arccos u\,du = u \arccos u - \sqrt{1 - u^2} + C$

77. $\displaystyle\int \arctan u\,du = u \arctan u - \ln\sqrt{1 + u^2} + C$

78. $\displaystyle\int \operatorname{arccot} u\,du = u \operatorname{arccot} u + \ln\sqrt{1 + u^2} + C$

79. $\displaystyle\int \operatorname{arcsec} u\,du = u \operatorname{arcsec} u - \ln\left|u + \sqrt{u^2 - 1}\right| + C$

80. $\displaystyle\int \operatorname{arccsc} u\,du = u \operatorname{arccsc} u + \ln\left|u + \sqrt{u^2 - 1}\right| + C$

Forms Involving e^u

81. $\displaystyle\int e^u\,du = e^u + C$

82. $\displaystyle\int ue^u\,du = (u - 1)e^u + C$

83. $\displaystyle\int u^n e^u\,du = u^n e^u - n\int u^{n-1}e^u\,du$

84. $\displaystyle\int \frac{1}{1 + e^u}\,du = u - \ln(1 + e^u) + C$

85. $\displaystyle\int e^{au} \sin bu\,du = \frac{e^{au}}{a^2 + b^2}(a \sin bu - b \cos bu) + C$

86. $\displaystyle\int e^{au} \cos bu\,du = \frac{e^{au}}{a^2 + b^2}(a \cos bu + b \sin bu) + C$

Forms Involving $\ln u$

87. $\displaystyle\int \ln u\,du = u(-1 + \ln u) + C$

88. $\displaystyle\int u \ln u\,du = \frac{u^2}{4}(-1 + 2 \ln u) + C$

89. $\displaystyle\int u^n \ln u\,du = \frac{u^{n+1}}{(n + 1)^2}[-1 + (n + 1)\ln u] + C,\ n \neq -1$

90. $\displaystyle\int (\ln u)^2\,du = u[2 - 2 \ln u + (\ln u)^2] + C$

91. $\displaystyle\int (\ln u)^n\,du = u(\ln u)^n - n\int (\ln u)^{n-1}\,du$

Forms Involving Hyperbolic Functions

92. $\displaystyle\int \cosh u\,du = \sinh u + C$

93. $\displaystyle\int \sinh u\,du = \cosh u + C$

94. $\displaystyle\int \operatorname{sech}^2 u\,du = \tanh u + C$

95. $\displaystyle\int \operatorname{csch}^2 u\,du = -\coth u + C$

96. $\displaystyle\int \operatorname{sech} u \tanh u\,du = -\operatorname{sech} u + C$

97. $\displaystyle\int \operatorname{csch} u \coth u\,du = -\operatorname{csch} u + C$

Forms Involving Inverse Hyperbolic Functions (in logarithmic form)

98. $\displaystyle\int \frac{du}{\sqrt{u^2 \pm a^2}} = \ln\left(u + \sqrt{u^2 \pm a^2}\right) + C$

99. $\displaystyle\int \frac{du}{a^2 - u^2} = \frac{1}{2a}\ln\left|\frac{a + u}{a - u}\right| + C$

100. $\displaystyle\int \frac{du}{u\sqrt{a^2 \pm u^2}} = -\frac{1}{a}\ln\frac{a + \sqrt{a^2 \pm u^2}}{|u|} + C$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Answers to Odd-Numbered Exercises

Chapter P

Section P.1 *(page 8)*

1. To find the x-intercepts of the graph of an equation, let y be zero and solve the equation for x. To find the y-intercepts of the graph of an equation, let x be zero and solve the equation for y.

3. b **4.** d **5.** a **6.** c

7.



9.



11.



13.



15.



17.



(a) $y \approx 1.73$ (b) $x = -4$

19. $(0, -5), \left(\frac{5}{2}, 0\right)$ **21.** $(0, -2), (-2, 0), (1, 0)$

23. $(0, 0), (4, 0), (-4, 0)$ **25.** $(0, 2), (4, 0)$ **27.** $(0, 0)$

29. Symmetric with respect to the y-axis

31. Symmetric with respect to the x-axis

33. Symmetric with respect to the origin **35.** No symmetry

37. Symmetric with respect to the origin

39. Symmetric with respect to the y-axis

41.



Symmetry: none

43.



Symmetry: y-axis

45.



Symmetry: none

47.



Symmetry: none

49.



Symmetry: origin

51.



Symmetry: origin

53.



Symmetry: y-axis

55.



x-intercepts: $(-3, 0), (3, 0)$;
y-intercepts: $(0, -3), (0, 3)$
Symmetry: x-axis, y-axis, origin

57.



Symmetry: x-axis

59. $(3, 5)$ **61.** $(-4, -1), (1, 14)$ **63.** $(-1, -2), (2, 1)$

65. $(-1, -5), (0, -1), (2, 1)$ **67.** $(-2, 2), \left(-3, \sqrt{3}\right)$

69. (a) $y = 0.74t + 7.2$

(b)



The model is a good fit for the data.

(c) \$28.7 trillion

CHAPTER P

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

71. 4480 units

73. Answers will vary. *Sample answer:*
$y = (2x + 3)(x - 4)(2x - 5)$

75. Yes. Assume that the graph has x-axis and origin symmetry. If (x, y) is on the graph, so is $(x, -y)$ by x-axis symmetry. Because $(x, -y)$ is on the graph, then so is $(-x, -(-y)) = (-x, y)$ by origin symmetry. Therefore, the graph is symmetric with respect to the y-axis. The argument is similar for y-axis and origin symmetry.

77. False. $(4, -5)$ is not a point on the graph of $x = y^2 - 29$.

79. True

Section P.2 *(page 16)*

1. Slope; y-intercept **3.** $m = 2$ **5.** $m = -1$

7.



$m = 3$

9.



m is undefined.

11.



$m = 2$

13.



15. Answers will vary. *Sample answers:* (0, 2), (1, 2), (5, 2)

17. Answers will vary. *Sample answers:* (0, 10), (2, 4), (3, 1)

19. $3x - 4y + 12 = 0$



21. $x = 1$



23. $3x - y - 11 = 0$



25. 12 ft

27. (a)



From 2018 to 2019 and from 2019 to 2020

(b) 2.01 million people per year (c) 350.2 million people

29. $m = 4$, $(0, -3)$ **31.** $m = -5$, $(0, 20)$

33. m is undefined, no y-intercept

35.



37.



39.



41.



43. $2x - y - 5 = 0$



45. $8x + 3y - 40 = 0$



47. $x - 6 = 0$



49. $y - 1 = 0$



51. $y = \left(\frac{1 - b}{3}\right)x + b$ **53.** $3x + 2y - 6 = 0$

55. $x + 2y - 5 = 0$ **57.** (a) $x + 7 = 0$ (b) $y + 2 = 0$

59. (a) $x + y + 1 = 0$ (b) $x - y + 5 = 0$

61. (a) $40x - 24y - 9 = 0$ (b) $24x + 40y - 53 = 0$

63. $V = 250t + 1600$ **65.** Not collinear, because $m_1 \neq m_2$

67. The adjacent line segments are perpendicular, and each line segment has a length of $\sqrt{8} = 2\sqrt{2}$ units.

69. $12y + 5x - 169 = 0$

71. (a) $\left(0, \frac{-a^2 + b^2 + c^2}{2c}\right)$ (b) $\left(\frac{b}{3}, \frac{c}{3}\right)$

73. $5F - 9C - 160 = 0$; $72°\text{F} \approx 22.2°\text{C}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

75. (a) $x = (1530 - p)/15$

(b)



45 units

(c) 49 units

77. Proof **79.** $\frac{5\sqrt{2}}{2}$ **81–83.** Proofs **85.** True

Section P.3 *(page 27)*

1. Yes; no; functions have exactly one output for every input.

3. Vertical shifts, horizontal shifts, reflections

5. (a) -2 (b) 13 (c) $3b - 2$ (d) $3x - 5$

7. (a) $2\sqrt{2}$ (b) $\sqrt{13}$ (c) $2\sqrt{2}$
(d) $\sqrt{x^2 + 2bx^2 + b^2x^2 + 4}$

9. (a) 5 (b) 0 (c) 1 (d) $4 + 2t - t^2$

11. $3x^2 + 3x\Delta x + (\Delta x)^2$, $\Delta x \neq 0$

13. Domain: $(-\infty, \infty)$; Range: $[0, \infty)$

15. Domain: $(-\infty, \infty)$; Range: $(-\infty, \infty)$

17. Domain: $[0, \infty)$; Range: $[0, \infty)$

19. Domain: $[-4, 4]$; Range: $[0, 4]$

21. Domain: $(-\infty, 0) \cup (0, \infty)$; Range: $(-\infty, 0) \cup (0, \infty)$

23. Domain: $[0, 1]$

25. Domain: $(-\infty, -3) \cup (-3, \infty)$

27. (a) -1 (b) 2 (c) 6 (d) $2t^2 + 4$
Domain: $(-\infty, \infty)$; Range: $(-\infty, 1) \cup [2, \infty)$

29. (a) 4 (b) 0 (c) -2 (d) $-b^2$
Domain: $(-\infty, \infty)$; Range: $(-\infty, 0] \cup [1, \infty)$

31.



Domain: $(-\infty, \infty)$
Range: $(-\infty, \infty)$

33.



Domain: $(-\infty, \infty)$
Range: $[5, \infty)$

35.



Domain: $(-\infty, \infty)$
Range: $(-\infty, \infty)$

37.



Domain: $[-3, 3]$
Range: $[0, 3]$

39.



Domain: $(-\infty, \infty)$
Range: $[-5, \infty)$

41.



Domain: $(-\infty, \infty)$
Range: $\left(0, \frac{1}{2}\right]$

43. y is not a function of x. **45.** y is a function of x.

47. y is a function of x. **49.** y is not a function of x.

51. Horizontal shift to the right two units
$y = \sqrt{x - 2}$

53. Horizontal shift to the right two units and vertical shift down one unit
$y = (x - 2)^2 - 1$

55. *d* **56.** *b* **57.** *c* **58.** *a* **59.** *e* **60.** *g*

61. (a)



(b)



(c)



(d)



(e)



(f)



(g)



(h)



63. (a) $-x - 1$ (b) $5x - 9$
(c) $-6x^2 + 23x - 20$ (d) $\frac{2x - 5}{4 - 3x}$

65. (a) 0 (b) 0 (c) -1 (d) $\sqrt{15}$
(e) $\sqrt{x^2 - 1}$ (f) $x - 1$ $(x \geq 0)$

CHAPTER P

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

67. $(f \circ g)(x) = x^2$; Domain: $(-\infty, \infty)$
$(g \circ f)(x) = x^2$; Domain: $(-\infty, \infty)$
Yes

69. $(f \circ g)(x) = x$; Domain: $[0, \infty)$
$(g \circ f)(x) = |x|$; Domain: $(-\infty, \infty)$
No, their domains are different.

71. $(f \circ g)(x) = \dfrac{3}{x^2 - 1}$;
Domain: $(-\infty, -1) \cup (-1, 1) \cup (1, \infty)$
$(g \circ f)(x) = \dfrac{9}{x^2} - 1$; Domain: $(-\infty, 0) \cup (0, \infty)$
No

73. (a) 4 (b) -2
(c) Undefined. The graph of g does not exist at $x = -5$.
(d) 3 (e) 2
(f) Undefined. The graph of f does not exist at $x = -4$.

75. Answers will vary.
Sample answer: $f(x) = \sqrt{x}$; $g(x) = 2x - 2$

77. (a) $\left(\frac{3}{2}, 4\right)$ (b) $\left(\frac{3}{2}, -4\right)$

79. f is even. g is neither even nor odd. h is odd.

81. Even; zeros: $x = -2, 0, 2$ **83.** Neither; zeros: $x = 0$

85. $f(x) = -5x - 6$, $-2 \le x \le 0$ **87.** $y = -\sqrt{-x}$

89. Answers will vary.
Sample answer:



91. Answers will vary.
Sample answer:



93. $c = 25$

95. No. A graph of a function that is intersected by a horizontal line more than once would mean that there is more than one x-value corresponding to the same y-value.

97. No. Consider $y = x^3 + x + 2$.
$f(-x) \neq -f(x)$
This is an odd-degree function that is not odd.

99. (a) $T(4) = 16°\text{C}$, $T(15) \approx 23°\text{C}$
(b) The changes in temperature occur 1 hour later.
(c) The temperatures are 1° lower.
(d) $T(t) = \begin{cases} 16, & 0 \le t \le 6 \\ 7t - 26, & 6 < t < 7 \\ 23, & 7 \le t \le 20 \\ -7t + 163, & 20 < t < 21 \\ 16, & 21 \le t \le 24 \end{cases}$

101. (a)



(b) $H\left(\dfrac{x}{1.6}\right) = 0.00001132x^3$

103–105. Proofs **107.** $L = \sqrt{x^2 + \left(\dfrac{2x}{x - 3}\right)^2}$

109. False. For example, if $f(x) = x^2$, then $f(-1) = f(1)$.

111. True

113. False. $f(x) = 0$ is symmetric with respect to the x-axis.

115. Putnam Problem A1, 1988

Section P.4 *(page 38)*

1. In general, if θ is any angle, then the angle $\theta + n(2\pi)$, n is a nonzero integer, is coterminal with θ.

3. $\sin\theta = \dfrac{7}{25}$
$\cos\theta = \dfrac{24}{25}$
$\tan\theta = \dfrac{7}{24}$

5. (a) 396°, $-324°$ (b) 240°, $-480°$

7. (a) $\dfrac{19\pi}{9}, -\dfrac{17\pi}{9}$ (b) $\dfrac{10\pi}{3}, -\dfrac{2\pi}{3}$

9. (a) $\dfrac{\pi}{6}$; 0.524 (b) $\dfrac{5\pi}{6}$; 2.618
(c) $\dfrac{7\pi}{4}$; 5.498 (d) $\dfrac{2\pi}{3}$; 2.094

11. (a) 270° (b) 210° (c) $-105°$ (d) $-135.62°$

13.

r	8 ft	15 in.	85 cm	24 in.	$\dfrac{12{,}963}{\pi}$ mi
s	12 ft	24 in.	63.75π cm	96 in.	8642 mi
θ	1.5	1.6	$\dfrac{3\pi}{4}$	4	$\dfrac{2\pi}{3}$

15. (a) $\sin\theta = \frac{4}{5}$ $\csc\theta = \frac{5}{4}$ $\cos\theta = \frac{3}{5}$ $\sec\theta = \frac{5}{3}$ $\tan\theta = \frac{4}{3}$ $\cot\theta = \frac{3}{4}$
(b) $\sin\theta = -\frac{5}{13}$ $\csc\theta = -\frac{13}{5}$ $\cos\theta = -\frac{12}{13}$ $\sec\theta = -\frac{13}{12}$ $\tan\theta = \frac{5}{12}$ $\cot\theta = \frac{12}{5}$

17.



$\cos\theta = \dfrac{\sqrt{3}}{2}$
$\tan\theta = \dfrac{\sqrt{3}}{3}$
$\csc\theta = 2$
$\sec\theta = \dfrac{2\sqrt{3}}{3}$
$\cot\theta = \sqrt{3}$

19.



$\sin\theta = \dfrac{3}{5}$
$\tan\theta = \dfrac{3}{4}$
$\csc\theta = \dfrac{5}{3}$
$\sec\theta = \dfrac{5}{4}$
$\cot\theta = \dfrac{4}{3}$

21. (a) $\sin 225° = -\dfrac{\sqrt{2}}{2}$ $\cos 225° = -\dfrac{\sqrt{2}}{2}$ $\tan 225° = 1$
(b) $\sin(-225°) = \dfrac{\sqrt{2}}{2}$ $\cos(-225°) = -\dfrac{\sqrt{2}}{2}$ $\tan(-225°) = -1$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

(c) $\sin\frac{5\pi}{3} = -\frac{\sqrt{3}}{2}$ $\cos\frac{5\pi}{3} = \frac{1}{2}$ $\tan\frac{5\pi}{3} = -\sqrt{3}$

(d) $\sin\frac{11\pi}{6} = -\frac{1}{2}$ $\cos\frac{11\pi}{6} = \frac{\sqrt{3}}{2}$ $\tan\frac{11\pi}{6} = -\frac{\sqrt{3}}{3}$

23. (a) $\frac{1}{2}$ (b) $\sqrt{3}$

25. (a) 0.1736 (b) 5.7588 **27.** (a) 0.3640 (b) 0.3640

29. (a) Quadrant III (b) Quadrant IV

31. (a) $\theta = \frac{\pi}{4}, \frac{7\pi}{4}$ (b) $\theta = \frac{3\pi}{4}, \frac{5\pi}{4}$

33. (a) $\theta = \frac{\pi}{4}, \frac{5\pi}{4}$ (b) $\theta = \frac{5\pi}{6}, \frac{11\pi}{6}$

35. $\theta = \frac{\pi}{4}, \frac{3\pi}{4}, \frac{5\pi}{4}, \frac{7\pi}{4}$ **37.** $\theta = 0, \frac{\pi}{4}, \pi, \frac{5\pi}{4}, 2\pi$

39. $\theta = \frac{\pi}{3}, \frac{5\pi}{3}, \pi$ **41.** $\theta = \frac{\pi}{3}, \frac{5\pi}{3}$ **43.** $\theta = 0, \frac{\pi}{2}, \pi, 2\pi$

45. $\theta = \frac{2\pi}{3}, \pi$ **47.** 5099 ft

49. Period: π
Amplitude: 2

51. Period: $\frac{1}{2}$
Amplitude: 3

53. Period: $\frac{\pi}{2}$ **55.** Period: $\frac{2\pi}{5}$

57. (a)



Change in amplitude

(b)



Change in period

(c)



Horizontal translation

59.



61.



63.



65.



67.



69.



71.



73. $a = 3, b = \frac{1}{2}, c = \frac{\pi}{2}$

75. No. You can use $1 + \tan^2\theta = \sec^2\theta$, but you are unable to determine the sign.

77. The range of the cosine function is $-1 \le y \le 1$. The range of the secant function is $y \le -1$ or $y \ge 1$.

79. $h = 51 + 50\sin\left(8\pi t - \frac{\pi}{2}\right)$

81.







The graph of $|f(x)|$ will reflect any parts of the graph of $f(x)$ below the x-axis about the x-axis. The graph of $f(|x|)$ will reflect the part of the graph of $f(x)$ right of the y-axis about the y-axis.

83. False. 4π radians (not 4 radians) corresponds to two complete revolutions from the initial side to the terminal side of an angle.

85. False. The amplitude of the function $y = \frac{1}{2}\sin 2x$ is one-half the amplitude of the function $y = \sin x$.

Review Exercises for Chapter P *(page 41)*

1. (i) b, e, f (ii) d (iii) No matches (iv) e, f (v) a (vi) d

CHAPTER P

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

3. Answers will vary. *Sample answers:*
(a) $\sin(1 + 2) \neq \sin 1 + \sin 2$
(b) $\cos(1 + 2) \neq \cos 1 + \cos 2$
(c) $\tan(1 + 2) \neq \tan 1 + \tan 2$

5. (a) Domain of f: $(-\infty, \infty)$; range of f: $[-3, 3]$
Domain of g: $(-\infty, \infty)$; range of g: $(-\infty, \infty)$
(b) Graph of f is symmetric with respect to the y-axis; graph of g is symmetric with respect to the origin.
(c) Intercepts of f: $\left(\frac{\pi}{4} + n\pi, 0\right), \left(\frac{3\pi}{4} + n\pi, 0\right), (0, 3)$
Intercepts of g: $(0, 0)$
(d)





(e) $f + g = 3\cos 2x + x|x|$, $f - g = 3\cos 2x - x|x|$, $fg = x|x|(3\cos 2x)$, $\frac{f}{g} = \frac{3\cos 2x}{x|x|}$, $x \neq 0$
(f) $f(g(x)) = 3\cos(2x|x|)$, $g(f(x)) = 9\cos 2x|\cos 2x|$

7. $\left(\frac{8}{5}, 0\right), (0, -8)$ **9.** $(3, 0), \left(0, \frac{3}{4}\right)$ **11.** Not symmetric

13. Symmetric with respect to the x-axis, the y-axis, and the origin

15.



Symmetry: none

17.



Symmetry: origin

19.



Symmetry: none

21. $(-2, 3)$ **23.** $(-2, 3), (3, 8)$

25.



$m = \frac{3}{7}$

27. $7x - 4y - 41 = 0$



29. $x = -8$ or $x + 8 = 0$



31. Slope: 3
y-intercept: $(0, 5)$

33.



35.



37. $x - 4y = 0$



39. (a) $7x - 16y + 101 = 0$
(b) $5x - 3y + 30 = 0$
(c) $4x - 3y + 27 = 0$
(d) $x + 3 = 0$

41. $V = 12{,}500 - 850t$; \$9950

43. (a) 4 (b) 29 (c) -11 (d) $5t + 9$

45. (a) 0 (b) 2 (c) 3 (d) 1

47. $8x + 4\Delta x$, $\Delta x \neq 0$

49. Domain: $(-\infty, \infty)$; Range: $[3, \infty)$

51. Domain: $(-\infty, \infty)$; Range: $(-\infty, 0]$

53.



Domain: $(-\infty, \infty)$
Range: $(-\infty, \infty)$

55.



Domain: $(-\infty, \infty)$
Range: $[0, \infty)$

57. Not a function **59.** Function

61. $f(x) = x^3 - 3x^2$



(a) $g(x) = -x^3 + 3x^2 + 1$
(b) $g(x) = (x - 2)^3 - 3(x - 2)^2 + 1$

63. $f(g(x)) = -3x + 1$; Domain: $(-\infty, \infty)$
$g(f(x)) = -3x - 1$; Domain: $(-\infty, \infty)$
No

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

65. Even; zeros: $x = -1, 0, 1$

67. $\frac{17\pi}{9} \approx 5.934$ **69.** $-\frac{8\pi}{3} \approx -8.378$

71. $30°$ **73.** $-120°$

75. $\sin(-45°) = -\frac{\sqrt{2}}{2}$

$\cos(-45°) = \frac{\sqrt{2}}{2}$

$\tan(-45°) = -1$

77. $\sin\frac{13\pi}{6} = \frac{1}{2}$

$\cos\frac{13\pi}{6} = \frac{\sqrt{3}}{2}$

$\tan\frac{13\pi}{6} = \frac{\sqrt{3}}{3}$

79. $\sin 405° = \frac{\sqrt{2}}{2}$

$\cos 405° = \frac{\sqrt{2}}{2}$

$\tan 405° = 1$

81. 0.6494 **83.** 3.2361 **85.** -0.3420 **87.** $\frac{2\pi}{3}, \frac{4\pi}{3}$

89. $\frac{7\pi}{6}, \frac{3\pi}{2}, \frac{11\pi}{6}$ **91.** $\frac{\pi}{3}, \pi, \frac{5\pi}{3}$

93.



95.



97.



99.



101. (a) $\frac{1}{5}$; greater than (b) $\frac{1}{3}$; less than

(c) $\frac{10}{41}$; greater than (d) $\frac{\sqrt{4+h}-2}{h}$

(e) $\frac{1}{4}$; As h gets closer to 0, the slope gets closer to $\frac{1}{4}$.

P.S. Problem Solving *(page 44)*

1. (a) Center: $(3, 4)$; Radius: 5

(b) $y = -\frac{3}{4}x$ (c) $y = \frac{3}{4}x - \frac{9}{2}$ (d) $\left(3, -\frac{9}{4}\right)$

3. $T(x) = \dfrac{2\sqrt{4+x^2} + \sqrt{(3-x)^2+1}}{4}$

5. (a) $A(x) = x\left(\dfrac{100-x}{2}\right)$; Domain: $(0, 100)$

(b)



Dimensions 50 m × 25 m yield maximum area of 1250 m².

(c) 50 m × 25 m; Area = 1250 m²

7. 80 km/h; Average speed is distance divided by time. Let d be the distance from the starting point to the beach. So, the total round trip distance is $2d$. The time for your drive to the beach is $d/120$ and the time for your drive back is $d/60$. So, simplify the equation

$$\text{Average speed} = \frac{\text{distance}}{\text{time}} = \frac{2d}{d/120 + d/60}$$

to find your average speed.

9. Proof



Chapter 1

Section 1.1 *(page 51)*

1. Calculus is the mathematics of change. Precalculus mathematics is more static.

Answers will vary. *Sample answer:*

Precalculus	Calculus
Area of a rectangle	Area under a curve
Work done by a constant force	Work done by a variable force
Center of a rectangle	Centroid of a region

3. Precalculus: 300 ft

5. Calculus: Slope of the tangent line at $x = 2$ is 0.16.

7. (a)



(b) $x = 1$: $m = \frac{1}{3}$

$x = 3$: $m = \dfrac{1}{\sqrt{3}+2} \approx 0.2679$

$x = 5$: $m = \dfrac{1}{\sqrt{5}+2} \approx 0.2361$

(c) $\frac{1}{4}$; You can improve your approximation of the slope at $x = 4$ by considering x-values very close to 4.

9. Area ≈ 10.417; Area ≈ 9.145; Use more rectangles.

11. (a) About 5.66 (b) About 6.11

(c) Increase the number of line segments.

Section 1.2 *(page 59)*

1. As the graph of the function approaches 8 on the horizontal axis, the graph approaches 25 on the vertical axis.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

3.



5.

x	3.9	3.99	3.999	4
$f(x)$	0.3448	0.3344	0.3334	?

x	4.001	4.01	4.1
$f(x)$	0.3332	0.3322	0.3226

$\lim_{x\to 4} \dfrac{x-4}{x^2-5x+4} \approx 0.3333$ $\left(\text{Actual limit is } \dfrac{1}{3}.\right)$

7.

x	-0.1	-0.01	-0.001	0
$f(x)$	0.5132	0.5013	0.5001	?

x	0.001	0.01	0.1
$f(x)$	0.4999	0.4988	0.4881

$\lim_{x\to 0} \dfrac{\sqrt{x+1}-1}{x} \approx 0.5000$ $\left(\text{Actual limit is } \dfrac{1}{2}.\right)$

9.

x	-0.1	-0.01	-0.001	0
$f(x)$	0.9983	0.99998	1.0000	?

x	0.001	0.01	0.1
$f(x)$	1.0000	0.99998	0.9983

$\lim_{x\to 0} \dfrac{\sin x}{x} \approx 1.0000$ (Actual limit is 1.)

11. 1 **13.** 2

15. Limit does not exist. The function approaches 1 from the right side of 2, but it approaches -1 from the left side of 2.

17. Limit does not exist. The function oscillates between 1 and -1 as x approaches 0.

19.

x	3.9	3.99	3.999	4
$f(x)$	7.9	7.99	7.999	?

x	4.001	4.01	4.1
$f(x)$	8.001	8.01	8.1

$\lim_{x\to 4} \dfrac{x^2-16}{x-4} \approx 8.0000$ (Actual limit is 8.)

21.

x	0.9	0.99	0.999	1
$f(x)$	0.2564	0.2506	0.2501	?

x	1.001	1.01	1.1
$f(x)$	0.2499	0.2494	0.2439

$\lim_{x\to 1} \dfrac{x-2}{x^2+x-6} \approx 0.2500$ $\left(\text{Actual limit is } \dfrac{1}{4}.\right)$

23.

x	0.9	0.99	0.999	1
$f(x)$	0.7340	0.6733	0.6673	?

x	1.001	1.01	1.1
$f(x)$	0.6660	0.6600	0.6015

$\lim_{x\to 1} \dfrac{x^4-1}{x^6-1} \approx 0.6666$ $\left(\text{Actual limit is } \dfrac{2}{3}.\right)$

25.

x	-6.1	-6.01	-6.001	-6
$f(x)$	-0.1248	-0.1250	-0.1250	?

x	-5.999	-5.99	-5.9
$f(x)$	-0.1250	-0.1250	-0.1252

$\lim_{x\to -6} \dfrac{\sqrt{10-x}-4}{x+6} \approx -0.1250$ $\left(\text{Actual limit is } -\dfrac{1}{8}.\right)$

27.

x	-0.1	-0.01	-0.001	0
$f(x)$	-0.5263	-0.5025	-0.5003	?

x	0.001	0.01	0.1
$f(x)$	-0.4998	-0.4975	-0.4762

$\lim_{x\to 0} \dfrac{[2/(x+2)]-1}{x} \approx -0.5000$ $\left(\text{Actual limit is } -\dfrac{1}{2}.\right)$

29.

x	-0.1	-0.01	-0.001	0
$f(x)$	1.9867	1.9999	2.0000	?

x	0.001	0.01	0.1
$f(x)$	2.0000	1.9999	1.9867

$\lim_{x\to 0} \dfrac{\sin 2x}{x} \approx 2.0000$ (Actual limit is 2.)

31.

x	-0.1	-0.01	-0.001	0
$f(x)$	-2000	-2×10^6	-2×10^9	?

x	0.001	0.01	0.1
$f(x)$	2×10^9	2×10^6	2000

As x approaches 0 from the left, the function decreases without bound. As x approaches 0 from the right, the function increases without bound.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

33. (a) 2
(b) Limit does not exist. The function approaches 1 from the right side of 1, but it approaches 3.5 from the left side of 1.
(c) Value does not exist. The function is undefined at $x = 4$.
(d) 2

35.



$\lim_{x \to c} f(x)$ exists for all points on the graph except where $c = 4$.

37.



39. $\delta = 0.4$ **41.** $\delta = \frac{1}{11} \approx 0.091$

43. $L = 8$
Answers will vary. *Sample answers:*
(a) $\delta \approx 0.0033$ (b) $\delta \approx 0.00167$

45. $L = 1$
Answers will vary.
Sample answers:
(a) $\delta = 0.002$
(b) $\delta = 0.001$

47. $L = 12$
Answers will vary.
Sample answers:
(a) $\delta = 0.00125$
(b) $\delta = 0.000625$

49. 6 **51.** -3 **53.** 3 **55.** 0 **57.** 10

59. 2 **61.** 4

63.



$\lim_{x \to 3} f(x) = \frac{1}{2}$
Domain: $(-\infty, 1) \cup (1, 3) \cup (3, \infty)$
The graph has a hole at $x = 3$.

65.



$\lim_{x \to 9} f(x) = 6$
Domain: $(-\infty, 9) \cup (9, \infty)$
The graph has a hole at $x = 9$.

67. (a) \$15; the cost to ship a package weighing 10.75 pounds
(b)



The limit does not exist because the limits from the right and left are not equal.

69. Choosing a smaller positive value of δ will still satisfy the inequality $|f(x) - L| < \varepsilon$.

71. No. The fact that $f(2) = 4$ has no bearing on the existence of the limit of $f(x)$ as x approaches 2.

73. (a) $r = \frac{3}{\pi} \approx 0.9549$ cm
(b) $\frac{5.5}{2\pi} \leq r \leq \frac{6.5}{2\pi}$, or approximately $0.8754 < r < 1.0345$
(c) $\lim_{r \to 3/\pi} 2\pi r = 6$; $\varepsilon = 0.5$; $\delta \approx 0.0796$

75.

x	-0.001	-0.0001	-0.00001
$f(x)$	2.7196	2.7184	2.7183

x	0.00001	0.0001	0.001
$f(x)$	2.7183	2.7181	2.7169

$\lim_{x \to 0} f(x) \approx 2.7183$



77.



$\delta = 0.001$, $(1.999, 2.001)$

79. False. The existence or nonexistence of $f(x)$ at $x = c$ has no bearing on the existence of the limit of $f(x)$ as $x \to c$.

81. False. See Exercise 13.

83. Yes. As x approaches 0.25 from either side, $\sqrt{x}$ becomes arbitrarily close to 0.5.

85–87. Proofs **89.** $\lim_{x \to 0} \frac{\sin nx}{x} = n$

91. Putnam Problem B1, 1986

Section 1.3 *(page 71)*

1. Substitute c for x and simplify.

3. If a function f is squeezed between two functions h and g, $h(x) \leq f(x) \leq g(x)$, and h and g have the same limit L as $x \to c$, then $\lim_{x \to c} f(x)$ exists and equals L.

5. 8 **7.** -1 **9.** 0 **11.** 7 **13.** $\sqrt{11}$ **15.** 125

17. $\frac{3}{5}$ **19.** $\frac{1}{5}$ **21.** 7 **23.** (a) 4 (b) 64 (c) 64

25. (a) 3 (b) 2 (c) 2 **27.** 1 **29.** $\frac{1}{2}$ **31.** 1

33. $\frac{1}{2}$ **35.** -1 **37.** (a) 10 (b) $\frac{12}{5}$ (c) $\frac{4}{5}$ (d) $\frac{1}{5}$

39. (a) 256 (b) 4 (c) 48 (d) 64

41. $f(x) = \frac{x^2 + 3x}{x}$ and $g(x) = x + 3$ agree except at $x = 0$.
$\lim_{x \to 0} f(x) = \lim_{x \to 0} g(x) = 3$

43. $f(x) = \frac{x^2 - 1}{x + 1}$ and $g(x) = x - 1$ agree except at $x = -1$.
$\lim_{x \to -1} f(x) = \lim_{x \to -1} g(x) = -2$

45. $f(x) = \frac{x^3 - 8}{x - 2}$ and $g(x) = x^2 + 2x + 4$ agree except at $x = 2$.
$\lim_{x \to 2} f(x) = \lim_{x \to 2} g(x) = 12$

47. -1 **49.** $\frac{1}{8}$ **51.** $\frac{5}{6}$ **53.** $\frac{1}{6}$ **55.** $\frac{\sqrt{5}}{10}$

57. $-\frac{1}{9}$ **59.** 2 **61.** $2x - 2$ **63.** $\frac{1}{5}$ **65.** 0

67. 0 **69.** 0 **71.** 0 **73.** $\frac{3}{2}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

75. 

The graph has a hole at $x = 0$.

Answers will vary. *Sample answer:*

x	-0.1	-0.01	-0.001	0.001	0.01	0.1
$f(x)$	0.358	0.354	0.354	0.354	0.353	0.349

$\lim_{x\to 0} \dfrac{\sqrt{x+2}-\sqrt{2}}{x} \approx 0.354$; Actual limit is $\dfrac{1}{2\sqrt{2}} = \dfrac{\sqrt{2}}{4}$.

77. 

The graph has a hole at $x = 0$.

Answers will vary. *Sample answer:*

x	-0.1	-0.01	-0.001
$f(x)$	-0.263	-0.251	-0.250

x	0.001	0.01	0.1
$f(x)$	-0.250	-0.249	-0.238

$\lim_{x\to 0} \dfrac{[1/(2+x)]-(1/2)}{x} \approx -0.250$; Actual limit is $-\dfrac{1}{4}$.

79. 

The graph has a hole at $t = 0$.

Answers will vary. *Sample answer:*

t	-0.1	-0.01	0	0.01	0.1
$f(t)$	2.96	2.9996	?	2.9996	2.96

$\lim_{t\to 0} \dfrac{\sin 3t}{t} \approx 3.0000$; Actual limit is 3.

81. 

The graph has a hole at $x = 0$.

Answers will vary. *Sample answer:*

x	-0.1	-0.01	-0.001	0	0.001	0.01	0.1
$f(x)$	-0.1	-0.01	-0.001	?	0.001	0.01	0.1

$\lim_{x\to 0} \dfrac{\sin x^2}{x} = 0$; Actual limit is 0.

83. 3 **85.** $2x - 4$ **87.** $x^{-1/2}$

89. $-1/(x+3)^2$ **91.** 4

93. 

0

95. 

0

The graph has a hole at $x = 0$.

97. f and g agree at all but one point if c is a real number such that $f(x) = g(x)$ for all $x \neq c$.

Sample answer: $f(x) = \dfrac{x^2-1}{x-1}$ and $g(x) = x + 1$ agree at all points except $x = 1$.

99. -29.4 m/sec **101.** -64 ft/sec (speed $= 64$ ft/sec)

103. 

The magnitudes of $f(x)$ and $g(x)$ are approximately equal when x is close to 0. Therefore, their ratio is approximately 1.

105. Let $f(x) = 1/x$ and $g(x) = -1/x$.

$\lim_{x\to 0} f(x)$ and $\lim_{x\to 0} g(x)$ do not exist. However,

$\lim_{x\to 0} [f(x) + g(x)] = \lim_{x\to 0} \left[\dfrac{1}{x} + \left(-\dfrac{1}{x}\right)\right] = \lim_{x\to 0} 0 = 0$

and so this limit does exist.

107–111. Proofs

113. The graphing utility was set in *degree* mode instead of *radian* mode.

115. False. The limit does not exist because the function approaches 1 from the right side of 0 and approaches -1 from the left side of 0.

117. True.

119. False. The limit does not exist because $f(x)$ approaches 3 from the left side of 2 and approaches 0 from the right side of 2.

121. Proof

123. (a) All $x \neq 0, \dfrac{\pi}{2} + n\pi$

(b) 

The domain is not obvious. The hole at $x = 0$ is not apparent from the graph.

(c) $\frac{1}{2}$ (d) $\frac{1}{2}$

125. $\lim_{x\to 0} f(x)$ does not exist; $\lim_{x\to 0} g(x) = 0$

Section 1.4 *(page 83)*

1. A function f is continuous at a point c if $f(c)$ is defined, $\lim_{x\to c} f(x)$ exists, and $\lim_{x\to c} f(x) = f(c)$.

3. The limit exists because the limit from the left and the limit from the right are equivalent.

5. (a) 3 (b) 3 (c) 3; $f(x)$ is continuous on $(-\infty, \infty)$.

7. (a) 0 (b) 0 (c) 0; Discontinuity at $x = 3$

9. (a) -3 (b) 3 (c) Limit does not exist.
Discontinuity at $x = 2$

11. $\frac{1}{16}$ **13.** $\frac{1}{10}$ **15.** 0

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

17. Limit does not exist. The function decreases without bound as x approaches -3 from the left.

19. -1 **21.** 1

23. Limit does not exist. The function decreases without bound as x approaches π from the left and increases without bound as x approaches π from the right.

25. 8 **27.** 2 **29.** $-\frac{1}{x^2}$ **31.** $\frac{5}{2}$ **33.** 2

35. Discontinuities at $x = -2$ and $x = 2$

37. Discontinuities at every integer

39. Continuous on $[-7, 7]$ **41.** Continuous on $[-1, 4]$

43. Nonremovable discontinuity at $x = 0$

45. Continuous for all real x

47. Nonremovable discontinuities at $x = -2$ and $x = 2$

49. Continuous for all real x

51. Nonremovable discontinuity at $x = 1$
Removable discontinuity at $x = 0$

53. Continuous for all real x

55. Removable discontinuity at $x = -2$
Nonremovable discontinuity at $x = 5$

57. Nonremovable discontinuity at $x = -7$

59. Nonremovable discontinuities at integer multiples of $\frac{\pi}{2}$

61. Nonremovable discontinuities at each integer

63. Continuous for all real x

65. Nonremovable discontinuity at $x = 2$

67. Continuous for all real x

69. $a = 7$ **71.** $a = 2$ **73.** $a = -1, b = 1$

75. Continuous for all real x

77. Nonremovable discontinuities at $x = 1$ and $x = -1$

79. Continuous on the open intervals
$\ldots, (-3\pi, -\pi), (-\pi, \pi), (\pi, 3\pi), \ldots$

81.



Nonremovable discontinuity at each integer

83.



Nonremovable discontinuity at $x = 4$

85. Continuous on $(-\infty, \infty)$ **87.** Continuous on $[0, \infty)$

89. Continuous on the open intervals $\ldots, (-6, -2), (-2, 2), (2, 6), \ldots$

91. Continuous on $(-\infty, \infty)$

93. Because $f(x)$ is continuous on the interval $[1, 2]$ and $f(1) = \frac{37}{12}$ and $f(2) = -\frac{8}{3}$, by the Intermediate Value Theorem there exists a real number c in $[1, 2]$ such that $f(c) = 0$.

95. Because $f(x)$ is continuous on the interval $[0, \pi]$ and $f(0) = -3$ and $f(\pi) \approx 8.87$, by the Intermediate Value Theorem there exists a real number c in $[0, \pi]$ such that $f(c) = 0$.

97. Consider the intervals $[1, 3]$ and $[3, 5]$.
$f(1) = 2 > 0$ and $f(3) = -2 < 0$. So, there is at least one zero in the interval $[1, 3]$.
$f(3) = -2 < 0$ and $f(5) = 2 > 0$. So, there is at least one zero in the interval $[3, 5]$.

99. 0.68, 0.6823 **101.** 0.56, 0.5636 **103.** 0.95, 0.9472

105. $f(3) = 11$; $c = 3$

107. $f(0) \approx 0.6458$, $f(5) \approx 1.464$; $c = 2$

109. $f(1) = 0$, $f(3) = 24$; $c = 2$

111. (a) Answers will vary. *Sample answer*:
$$f(x) = \frac{1}{(x - a)(x - b)}$$
(b) Answers will vary. *Sample answer:*
$$g(x) = \begin{cases} -1 & -2 \le x < 0 \\ 1 & 0 \le x \le 2 \end{cases}$$
No; The function g is not continuous at $x = 0$.

113. If f and g are continuous for all real x, then so is $f + g$ (Theorem 1.11, part 2). However, $\frac{f}{g}$ might not be continuous if $g(x) = 0$. For example, let $f(x) = x$ and $g(x) = x^2 - 1$. Then f and g are continuous for all real x, but $\frac{f}{g}$ is not continuous at $x = \pm 1$.

115. True

117. False. $f(x) = \cos x$ has two zeros in $[0, 2\pi]$. However, $f(0)$ and $f(2\pi)$ have the same sign.

119. False. A rational function can be written as $\frac{P(x)}{Q(x)}$, where P and Q are polynomials of degree m and n, respectively. It can have, at most, n discontinuities.

121. The functions differ by 1 for non-integer values of x.

123. (a) $C(t) = 3 - [\![1 - t]\!]$, $0 < t \le 13$

(b)



There is a nonremovable discontinuity at every integer value of t, or hour.

125–127. Proofs **129.** Answers will vary.

131. (a)



(b) No. The frequency is oscillating.

133. (a) $c = 0$, 1, or 2
(b) $c = \frac{-1 \pm \sqrt{5}}{2}$

135. Proof

137. $h(x)$ has a nonremovable discontinuity at every integer except 0.



139. Putnam Problem B2, 1988

CHAPTER 1

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Section 1.5 *(page 92)*

1. A limit in which $f(x)$ increases or decreases without bound as x approaches c is called an infinite limit. ∞ is not a number. Rather, the symbol $\lim_{x\to c} f(x) = \infty$ says how the limit fails to exist.

3. $\lim_{x\to -2^+} 2\left|\frac{x}{x^2-4}\right| = \infty, \quad \lim_{x\to -2^-} 2\left|\frac{x}{x^2-4}\right| = \infty$

5. $\lim_{x\to -2^+} \tan\frac{\pi x}{4} = -\infty, \quad \lim_{x\to -2^-} \tan\frac{\pi x}{4} = \infty$

7. $\lim_{x\to 4^+} \frac{1}{x-4} = \infty, \quad \lim_{x\to 4^-} \frac{1}{x-4} = -\infty$

9. $\lim_{x\to 4^+} \frac{1}{(x-4)^2} = \infty, \quad \lim_{x\to 4^-} \frac{1}{(x-4)^2} = \infty$

11.

x	-3.5	-3.1	-3.01	-3.001	-3
$f(x)$	0.31	1.64	16.6	167	?

x	-2.999	-2.99	-2.9	-2.5
$f(x)$	-167	-16.7	-1.69	-0.36

$\lim_{x\to -3^+} f(x) = -\infty; \quad \lim_{x\to -3^-} f(x) = \infty$

13.

x	-3.5	-3.1	-3.01	-3.001	-3
$f(x)$	3.8	16	151	1501	?

x	-2.999	-2.99	-2.9	-2.5
$f(x)$	-1499	-149	-14	-2.3

$\lim_{x\to -3^+} f(x) = -\infty; \quad \lim_{x\to -3^-} f(x) = \infty$

15.

x	-3.5	-3.1	-3.01	-3.001	-3
$f(x)$	-1.7321	-9.514	-95.49	-954.9	?

x	-2.999	-2.99	-2.9	-2.5
$f(x)$	954.9	95.49	9.514	1.7321

$\lim_{x\to -3^-} f(x) = -\infty; \quad \lim_{x\to -3^+} f(x) = \infty$

17.

x	-3.5	-3.1	-3.01	-3.001	-3
$f(x)$	-3.8637	-19.107	-190.99	-1909.9	?

x	-2.999	-2.99	-2.9	-2.5
$f(x)$	1909.9	190.99	19.107	3.8637

$\lim_{x\to -3^-} f(x) = -\infty; \quad \lim_{x\to -3^+} f(x) = \infty$

19. $x = 0$ **21.** $x = \pm 2$ **23.** No vertical asymptote

25. $x = -2, x = 1$ **27.** No vertical asymptote

29. $x = 0, x = 3$ **31.** $x = n\pi$, n is an integer

33. $t = n\pi$, n is a nonzero integer

35. Removable discontinuity at $x = -1$

37. Vertical asymptote at $x = -1$ **39.** ∞

41. ∞ **43.** $-\frac{1}{5}$ **45.** $-\infty$ **47.** $-\infty$

49. ∞ **51.** ∞ **53.** 0 **55.** ∞

57.



$\lim_{x\to 1^+} f(x) = \infty$

59. (a) ∞ (b) $-\infty$ (c) 0

61. Answers will vary. *Sample answer:* $f(x) = \dfrac{x-3}{x^2-4x-12}$

63.



65. (a)

x	1	0.5	0.2	0.1
$f(x)$	0.1585	0.0411	0.0067	0.0017

x	0.01	0.001	0.0001
$f(x)$	≈ 0	≈ 0	≈ 0



$\lim_{x\to 0^+} \frac{x-\sin x}{x} = 0$

(b)

x	1	0.5	0.2	0.1
$f(x)$	0.1585	0.0823	0.0333	0.0167

x	0.01	0.001	0.0001
$f(x)$	0.0017	≈ 0	≈ 0



$\lim_{x\to 0^+} \frac{x-\sin x}{x^2} = 0$

(c)

x	1	0.5	0.2	0.1
$f(x)$	0.1585	0.1646	0.1663	0.1666

x	0.01	0.001	0.0001
$f(x)$	0.1667	0.1667	0.1667



$\lim_{x\to 0^+} \frac{x-\sin x}{x^3} = 0.1\overline{6}$ or $\frac{1}{6}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

(d)

x	1	0.5	0.2	0.1
$f(x)$	0.1585	0.3292	0.8317	1.6658

x	0.01	0.001	0.0001
$f(x)$	16.67	166.7	1667.0



$\lim_{x\to 0^+} \dfrac{x - \sin x}{x^4} = \infty$

For $n > 3$, $\lim_{x\to 0^+} \dfrac{x - \sin x}{x^n} = \infty$.

67. (a) $\frac{3}{2}$ ft/sec (b) $\lim_{x\to 25^-} \dfrac{2x}{\sqrt{625 - x^2}} = \infty$

69. ∞ or $-\infty$ if $k < 0$

71. (a) $A = 50 \tan\theta - 50\theta$; Domain: $\left(0, \dfrac{\pi}{2}\right)$

(b)

θ	0.3	0.6	0.9	1.2	1.5
$f(\theta)$	0.47	4.21	18.0	68.6	630.1



(c) $\lim_{\theta\to \pi/2^-} A = \infty$

73. True. **75.** False. Let $f(x) = \tan x$

77. Let $f(x) = \dfrac{1}{x^2}$ and $g(x) = \dfrac{1}{x^4}$, and let $c = 0$. $\lim_{x\to 0} \dfrac{1}{x^2} = \infty$ and $\lim_{x\to 0} \dfrac{1}{x^4} = \infty$, but $\lim_{x\to 0} \left(\dfrac{1}{x^2} - \dfrac{1}{x^4}\right) = \lim_{x\to 0} \left(\dfrac{x^2 - 1}{x^4}\right) = -\infty \neq 0$.

79. Given $\lim_{x\to c} f(x) = \infty$, let $g(x) = 1$. Then $\lim_{x\to c} \dfrac{g(x)}{f(x)} = 0$ by Theorem 1.15.

81–83. Proofs

Review Exercises for Chapter 1 *(page 95)*

1. Answers will vary. Sample answer: $f(x) = \begin{cases} \dfrac{x^2 - 4}{x - 2}, & x \neq 2 \\ 0 & x = 2 \end{cases}$

3. (a) $(-\infty, 0] \cup [1, \infty)$ (b) 0 (c) 0

5. (a) 2 (b) Yes, if it is defined that $f(0) = 2$

7. (a) Precalculus: 10 sq. units (b) Calculus: 5 sq. units

9.

t	4.9	4.99	4.999	5
$f(t)$	9.9	9.99	9.999	?

t	5.001	5.01	5.1
$f(t)$	10.001	10.01	10.1

$\lim_{t\to 5} f(t) \approx 10.0000$ (Actual limit is 10.)

11.

x	−0.1	−0.01	−0.001	0
$f(x)$	0.2516	0.2502	0.2500	?

x	0.001	0.01	0.1
$f(x)$	0.2500	0.2498	0.2485

$\lim_{x\to 0} f(x) \approx 0.2500$ (Actual limit is $\frac{1}{4}$.)

13.

x	−0.1	−0.01	−0.001	0
$f(x)$	−0.0207	−0.0204	−0.0204	?

x	0.001	0.01	0.1
$f(x)$	−0.0204	−0.0204	−0.0201

$\lim_{x\to 0} f(x) \approx -0.0204$ $\left(\text{Actual limit is} -\dfrac{1}{49}.\right)$

15. (a) Limit does not exist. The function approaches 3 from the left side of 2, but it approaches 2 from the right side of 2.

(b) 0

17. 5; Proof **19.** −3; Proof **21.** 36 **23.** $\sqrt{6} \approx 2.45$

25. 16 **27.** $\frac{4}{3}$ **29.** −1 **31.** $\frac{1}{2}$ **33.** −1

35. 0 **37.** $\sqrt{3}/2$ **39.** −3 **41.** −5

43. The graph has a hole at $x = 0$.



x	−0.1	−0.01	−0.001	0
$f(x)$	0.3352	0.3335	0.3334	?

x	0.001	0.01	0.1
$f(x)$	0.3333	0.3331	0.3315

$\lim_{x\to 0} \dfrac{\sqrt{2x + 9} - 3}{x} \approx 0.3333$; Actual limit is $\dfrac{1}{3}$.

45.



The graph has a hole at $x = -9$.

x	−9.1	−9.01	−9.001	−9
$f(x)$	245.7100	243.2701	243.0270	?

x	−8.999	−8.99	−8.9
$f(x)$	242.9730	242.7301	240.3100

$\lim_{x\to -9} \dfrac{x^3 + 729}{x + 9} \approx 243.00$; Actual limit is 243.

47. −39.2 m/sec **49.** $\frac{1}{6}$ **51.** ∞

53. −1 **55.** 3 **57.** 0

CHAPTER 1

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

59. Limit does not exist. The function approaches 2 from the left side of 1, but it approaches 1 from the right side of 1.
61. Continuous on $[-2, 2]$ **63.** No discontinuities
65. Nonremovable discontinuity at $x = 5$
67. Nonremovable discontinuities at $x = -1$ and $x = 1$
Removable discontinuity at $x = 0$
69. $c = -\frac{1}{2}$ **71.** Continuous for all real x
73. Continuous on $[0, \infty)$
75. Removable discontinuity at $x = 1$
Continuous on $(-\infty, 1) \cup (1, \infty)$
77. Proof
79. $f(-1) = -8, f(2) = 10$
Because f is continuous on the closed interval $[-1, 2]$ and $-8 < 2 < 10$, there is at least one number c in $[-1, 2]$ such that $f(c) = 2$; $c = 1$
81. From the left: $-\infty$
From the right: ∞
83. $x = 0$ **85.** $x = \pm 3$
87. $x = 2n + 1$, where n is an integer **89.** $-\infty$ **91.** $\frac{1}{3}$
93. $-\infty$ **95.** $\frac{4}{5}$ **97.** ∞
99. (a) \$720,000.00 (b) ∞
101. (a)



(b) $\lim_{x \to a^+} P_{a,b}(x) = 1$
$\lim_{x \to a^-} P_{a,b}(x) = 0$
$\lim_{x \to b^+} P_{a,b}(x) = 0$
$\lim_{x \to b^-} P_{a,b}(x) = 1$
(c) Continuous for all positive real numbers except a and b
(d) The area under the graph of U and above the x-axis is 1.

P.S. Problem Solving *(page 98)*

1. (a) Perimeter $\triangle PAO = 1 + \sqrt{(x^2 - 1)^2 + x^2} + \sqrt{x^4 + x^2}$
Perimeter $\triangle PBO = 1 + \sqrt{x^4 + (x - 1)^2} + \sqrt{x^4 + x^2}$
(b)

x	4	2	1
Perimeter $\triangle PAO$	33.0166	9.0777	3.4142
Perimeter $\triangle PBO$	33.7712	9.5952	3.4142
$r(x)$	0.9777	0.9461	1.0000

x	0.1	0.01
Perimeter $\triangle PAO$	2.0955	2.0100
Perimeter $\triangle PBO$	2.0006	2.0000
$r(x)$	1.0475	1.0050

1
(c) Area $\triangle PAO = \frac{x}{2}$
Area $\triangle PBO = \frac{x^2}{2}$
(d)

x	4	2	1	0.1	0.01
Area $\triangle PAO$	2	1	1/2	1/20	1/200
Area $\triangle PBO$	8	2	1/2	1/200	1/20,000
$a(x)$	4	2	1	1/10	1/100

0
3. (a) $m = -\frac{12}{5}$ (b) $y = \frac{5}{12}x - \frac{169}{12}$
(c) $m_x = \dfrac{-\sqrt{169 - x^2} + 12}{x - 5}$
(d) $\frac{5}{12}$; It is the same as the slope of the tangent line found in part (b).
5. $a = 3, b = 6$ **7.** Proof

Chapter 2

Section 2.1 *(page 107)*

1. Let $(c, f(c))$ represent an arbitrary point on the graph of f. Then the slope of the tangent line at $(c, f(c))$ is
$m = \lim_{\Delta x \to 0} \dfrac{f(c + \Delta x) - f(c)}{\Delta x}$.
3. The limit used to define the slope of a tangent line is also used to define differentiation. The key is to rewrite the difference quotient so that Δx does not occur as a factor of the denominator.
5. $m_1 = 0, m_2 = 5/2$
7. (a)–(d)



9. $m = -5$
11. $m = 8$ **13.** $m = 3$ **15.** $f'(x) = 0$
17. $f'(x) = -5$ **19.** $h'(s) = \frac{2}{3}$ **21.** $f'(x) = 2x + 1$
23. $f'(x) = 3x^2 - 12$ **25.** $f'(x) = \dfrac{-1}{(x - 1)^2}$
27. $f'(x) = \dfrac{1}{2\sqrt{x + 4}}$
29. (a) Tangent line: $y = -2x + 2$
(b)



31. (a) Tangent line: $y = 12x - 16$
(b)



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

33. (a) Tangent line: $y = \frac{1}{2}x + \frac{1}{2}$

(b)



35. (a) Tangent line: $y = \frac{3}{4}x - 2$

(b)



37. $y = -x + 1$ **39.** $y = 3x - 2$; $y = 3x + 2$

41. $y = -\frac{1}{2}x + \frac{3}{2}$

43.



The slope of the graph of f is 1 for all x-values.

45.



The slope of the graph of f is negative for $x < 4$, positive for $x > 4$, and 0 at $x = 4$.

47.



The slope of the graph of f is negative for $x < 0$ and positive for $x > 0$. The slope is undefined at $x = 0$.

49. Answers will vary.

Sample answer: $y = -x$



51. No. Consider $f(x) = \sqrt{x}$ and its derivative.

53. $g(4) = 5$; $g'(4) = -\frac{5}{3}$

55. $f(x) = 5 - 3x$

$c = 1$

57. $f(x) = -x^2$

$c = 6$

59. $f(x) = -3x + 2$

61. $y = 2x + 1$, $y = -2x + 9$



63. (a)



For this function, the slopes of the tangent lines are always distinct for different values of x.

(b)



For this function, the slopes of the tangent lines are sometimes the same.

65. (a)



$f'(0) = 0$, $f'\left(\frac{1}{2}\right) = \frac{1}{2}$, $f'(1) = 1$, $f'(2) = 2$

(b) $f'\left(-\frac{1}{2}\right) = -\frac{1}{2}$, $f'(-1) = -1$, $f'(-2) = -2$

(c)



(d) $f'(x) = x$

67. $f(2) = 4$, $f(2.1) = 3.99$, $f'(2) \approx -0.1$ **69.** 6 **71.** 4

73. $g(x)$ is not differentiable at $x = 0$.

75. $f(x)$ is not differentiable at $x = 6$.

77. $h(x)$ is not differentiable at $x = -7$.

79. $(-\infty, -4) \cup (-4, \infty)$ **81.** $(-1, \infty)$

83.



$(-\infty, 5) \cup (5, \infty)$

85.



$(-\infty, 0) \cup (0, \infty)$

87. The derivative from the left is -1 and the derivative from the right is 1, so f is not differentiable at $x = 1$.

89. The derivatives from both the right and the left are 0, so $f'(1) = 0$.

91. f is differentiable at $x = 2$.

93. (a) $d = \dfrac{3|m + 1|}{\sqrt{m^2 + 1}}$

(b)



Not differentiable at $m = -1$

95. False. The slope is $\lim_{\Delta x \to 0} \dfrac{f(2 + \Delta x) - f(2)}{\Delta x}$.

97. False. For example, $f(x) = |x|$. The derivative from the left and the derivative from the right both exist but are not equal.

99. Proof

CHAPTER 2

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Section 2.2 *(page 118)*

1. If the constant c in the constant function $f(x) = c$ is a real number, then $\frac{d}{dx}[c] = 0$.

3. The derivative of the sine function is the cosine function. The derivative of the cosine function is the negative of the sine function.

5. (a) $\frac{1}{2}$ (b) 3 **7.** 0 **9.** $7x^6$ **11.** $-5/x^6$

13. $1/(9x^{8/9})$ **15.** 1 **17.** $-6t + 2$ **19.** $2x + 12x^2$

21. $3t^2 + 10t - 3$ **23.** $\frac{\pi}{2}\cos\theta$ **25.** $2x + \frac{1}{2}\sin x$

	Function	Rewrite	Differentiate	Simplify
27.	$y = \frac{2}{7x^4}$	$y = \frac{2}{7}x^{-4}$	$y' = -\frac{8}{7}x^{-5}$	$y' = -\frac{8}{7x^5}$
29.	$y = \frac{6}{(5x)^3}$	$y = \frac{6}{125}x^{-3}$	$y' = -\frac{18}{125}x^{-4}$	$y' = -\frac{18}{125x^4}$

31. -2 **33.** 0 **35.** 8 **37.** 3 **39.** $\frac{2x + 6}{x^3}$

41. $\frac{2t + 12}{t^4}$ **43.** $\frac{x^3 - 8}{x^3}$ **45.** $\frac{3t^2 - 4t + 24}{2t^{5/2}}$

47. $3x^2 + 1$ **49.** $\frac{1}{2\sqrt{x}} - \frac{2}{x^{2/3}}$ **51.** $\frac{3}{\sqrt{x}} - 5\sin x$

53. $18x + 5\sin x$

55. (a) $y = 2x - 2$

(b)



57. (a) $3x + 2y - 7 = 0$

(b)



59. $(-1, 2)$, $(0, 3)$, $(1, 2)$ **61.** No horizontal tangents

63. (π, π) **65.** $k = -8$ **67.** $k = 3$

69. $g'(x) = f'(x)$ **71.** $g'(x) = -5f'(x)$

73.



The rate of change of f is constant, and therefore f' is a constant function.

75.



77. $y = 2x - 1$ $y = 4x - 4$



79. $f'(x) = 3 + \cos x \neq 0$ for all x. **81.** $x - 4y + 4 = 0$

83. (a)



(3.9, 7.7019),
$S(x) = 2.981x - 3.924$

(b) $T(x) = 3(x - 4) + 8 = 3x - 4$

The slope (and equation) of the secant line approaches that of the tangent line at (4, 8) as you choose points closer and closer to (4, 8).

(c)



The approximation becomes less accurate.

(d)

Δx	-3	-2	-1	-0.5	-0.1	0
$f(4 + \Delta x)$	1	2.828	5.196	6.548	7.702	8
$T(4 + \Delta x)$	-1	2	5	6.5	7.7	8

Δx	0.1	0.5	1	2	3
$f(4 + \Delta x)$	8.302	9.546	11.180	14.697	18.520
$T(4 + \Delta x)$	8.3	9.5	11	14	17

85. False. Let $f(x) = x$ and $g(x) = x + 1$.

87. False. $\frac{dy}{dx} = 0$ **89.** False. $f'(x) = 0$

91. Average rate: 3
Instantaneous rates:
$f'(1) = 3$, $f'(2) = 3$

93. Average rate: $\frac{1}{2}$
Instantaneous rates:
$f'(1) = 1$, $f'(2) = \frac{1}{4}$

95. (a) $s(t) = -16t^2 + 1362$, $v(t) = -32t$ (b) -48 ft/sec
(c) $s'(1) = -32$ ft/sec, $s'(2) = -64$ ft/sec
(d) $t = \frac{\sqrt{1362}}{4} \approx 9.226$ sec (e) -295.242 ft/sec

97. $v(5) = 71$ m/sec; $v(10) = 22$ m/sec

99.



101. $V'(6) = 108$ cm^3/cm

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

103. (a) $R(v) = 0.417v - 0.02$

(b) $B(v) = 0.0056v^2 + 0.001v + 0.04$

(c) $T(v) = 0.0056v^2 + 0.418v + 0.02$

(d)



(e) $T'(v) = 0.0112v + 0.418$

$T'(40) = 0.866$

$T'(80) = 1.314$

$T'(100) = 1.538$

(f) Stopping distance increases at an increasing rate.

105. Proof **107.** $y = 2x^2 - 3x + 1$

109. $9x + y = 0,\ 9x + 4y + 27 = 0$ **111.** $a = \frac{1}{3},\ b = -\frac{4}{3}$

113. $f_1(x) = |\sin x|$ is differentiable for all $x \neq n\pi$, n an integer.
$f_2(x) = \sin|x|$ is differentiable for all $x \neq 0$.

115. Putnam Problem A2, 2010

Section 2.3 *(page 129)*

1. To find the derivative of the product of two differentiable functions f and g, multiply the first function f by the derivative of the second function g, and then add the second function g times the derivative of the first function f.

3. $\frac{d}{dx}\tan x = \sec^2 x$

$\frac{d}{dx}\cot x = -\csc^2 x$

$\frac{d}{dx}\sec x = \sec x \tan x$

$\frac{d}{dx}\csc x = -\csc x \cot x$

5. $-20x + 17$ **7.** $\frac{1 - 5t^2}{2\sqrt{t}}$ **9.** $x^2(3\cos x - x\sin x)$

11. $-\frac{5}{(x-5)^2}$ **13.** $\frac{1 - 5x^3}{2\sqrt{x}(x^3+1)^2}$ **15.** $\frac{x\cos x - 2\sin x}{x^3}$

17. $f'(x) = (x^3 + 4x)(6x + 2) + (3x^2 + 2x - 5)(3x^2 + 4)$
$= 15x^4 + 8x^3 + 21x^2 + 16x - 20$
$f'(0) = -20$

19. $f'(x) = \frac{x^2 - 6x + 4}{(x-3)^2}$ $f'(1) = -\frac{1}{4}$

21. $f'(x) = \cos x - x\sin x$ $f'\left(\frac{\pi}{4}\right) = \frac{\sqrt{2}}{8}(4 - \pi)$

	Function	Rewrite	Differentiate	Simplify
23.	$y = \frac{x^3 + 6x}{3}$	$y = \frac{1}{3}x^3 + 2x$	$y' = \frac{1}{3}(3x^2) + 2$	$y' = x^2 + 2$
25.	$y = \frac{6}{7x^2}$	$y = \frac{6}{7}x^{-2}$	$y' = -\frac{12}{7}x^{-3}$	$y' = -\frac{12}{7x^3}$
27.	$y = \frac{4x^{3/2}}{x}$	$y = 4x^{1/2}$, $x > 0$	$y' = 2x^{-1/2}$	$y' = \frac{2}{\sqrt{x}}$, $x > 0$

29. $\frac{3}{(x+1)^2},\ x \neq 1$ **31.** $\frac{x^2 + 6x - 3}{(x+3)^2}$ **33.** $\frac{3x+1}{2x^{3/2}}$

35. $-\frac{2x^2 - 2x + 3}{x^2(x-3)^2}$ **37.** $\frac{4s^2(3s^2 + 13s + 15)}{(s+2)^2}$

39. $10x^4 - 8x^3 - 21x^2 - 10x - 30$ **41.** $t(t\cos t + 2\sin t)$

43. $\frac{-(t\sin t + \cos t)}{t^2}$ **45.** $-1 + \sec^2 x$, or $\tan^2 x$

47. $\frac{1}{4t^{3/4}} - 6\csc t \cot t$ **49.** $\frac{3}{2}\sec x(\tan x - \sec x)$

51. $\cos x \cot^2 x$ **53.** $x(x\sec^2 x + 2\tan x)$

55. $4x\cos x + (2 - x^2)\sin x$ **57.** $\frac{2x^2 + 8x - 1}{(x+2)^2}$

59. $\frac{(1 - \sin\theta) + \theta\cos\theta}{(1 - \sin\theta)^2}$ **61.** $-4\sqrt{3}$ **63.** $\frac{1}{\pi^2}$

65. (a) $y = -3x - 1$

(b)



67. (a) $y = 4x + 25$

(b)



69. (a) $4x - 2y - \pi + 2 = 0$

(b)



71. $2y + x - 4 = 0$ **73.** $25y - 12x + 16 = 0$

75. $(1, 1)$ **77.** $(0, 0),\ (2, 4)$

79. Tangent lines: $2y + x = 7,\ 2y + x = -1$



81. $f(x) + 2 = g(x)$ **83.** (a) $p'(1) = 1$ (b) $q'(4) = -\frac{1}{3}$

85. $\frac{18t + 5}{2\sqrt{t}}$ cm²/sec

87. (a) −\$38.13 thousand/100 components

(b) −\$10.37 thousand/100 components

(c) −\$3.80 thousand/100 components

The cost decreases with increasing order size.

89. Proof

91. (a) $h(t) = 155.2t + 839.5$
$p(t) = 1.9t + 292.9$

(b)





(c) $A = \frac{155.2t + 839.5}{1.9t + 292.9}$



A represents the average health care expenditures per person (in thousands of dollars).

(d) $A'(t) = \frac{43863.03}{(1.9t + 292.9)^2}$

$A'(t)$ represents the rate of change of the average health care expenditures per person for the given year t.

CHAPTER 2

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

93. 2 **95.** $\frac{3}{\sqrt{x}}$ **97.** $\frac{2}{(x-1)^3}$

99. $2\cos x - x\sin x$ **101.** $\csc^3 x + \csc x \cot^2 x$

103. $6x + \frac{6}{25x^{8/5}}$ **105.** $\sin x$

107. 0 **109.** -10

111. $n-1$ or lower; Answers will vary. *Sample answer:* $f(x) = x^3$, $f'(x) = 3x^2$, $f''(x) = 6x$, $f'''(x) = 6$, $f^{(4)}(x) = 0$

113.



It appears that f is cubic, so f' would be quadratic and f'' would be linear.

115.



117. Answers will vary.
Sample answer: $f(x) = (x-2)^2$



119. $v(3) = 27$ m/sec
$a(3) = -6$ m/sec^2
The speed of the object is decreasing.

121.

t	0	1	2	3	4
$s(t)$	0	57.75	99	123.75	132
$v(t)$	66	49.5	33	16.5	0
$a(t)$	-16.5	-16.5	-16.5	-16.5	-16.5

The average velocity on $[0, 1]$ is 57.75 ft/sec, on $[1, 2]$ is 41.25 ft/sec, on $[2, 3]$ is 24.75 ft/sec, and on $[3, 4]$ is 8.25. ft/sec

123. $f^{(n)}(x) = n(n-1)(n-2)\cdot\cdot\cdot(2)(1) = n!$

125. (a)
$$\begin{aligned} f''(x) &= g(x)h''(x) + 2g'(x)h'(x) + g''(x)h(x) \\ f'''(x) &= g(x)h'''(x) + 3g'(x)h''(x) \\ &\quad + 3g''(x)h'(x) + g'''(x)h(x) \\ f^{(4)}(x) &= g(x)h^{(4)}(x) + 4g'(x)h'''(x) + 6g''(x)h''(x) \\ &\quad + 4g'''(x)h'(x) + g^{(4)}(x)h(x) \end{aligned}$$

(b) $$f^{(n)}(x) = g(x)h^{(n)}(x) + \frac{n!}{1!(n-1)!}g'(x)h^{(n-1)}(x) + \frac{n!}{2!(n-2)!}g''(x)h^{(n-2)}(x) + \cdots + \frac{n!}{(n-2)!1!}g^{(n-1)}(x)h'(x) + g^{(n)}(x)h(x)$$

127. $n=1$: $f'(x) = x\cos x + \sin x$
$n=2$: $f'(x) = x^2\cos x + 2x\sin x$
$n=3$: $f'(x) = x^3\cos x + 3x^2\sin x$
$n=4$: $f'(x) = x^4\cos x + 4x^3\sin x$
General rule: $f'(x) = x^n\cos x + nx^{(n-1)}\sin x$

129. $y' = -\frac{1}{x^2}$, $y'' = \frac{2}{x^3}$,
$$\begin{aligned} x^3y'' + 2x^2y' &= x^3\left(\frac{2}{x^3}\right) + 2x^2\left(\frac{-1}{x^2}\right) \\ &= 2 - 2 \\ &= 0 \end{aligned}$$

131. $y' = 2\cos x$, $y'' = -2\sin x$,
$y'' + y = -2\sin x + 2\sin x + 3 = 3$

133. False. $h'(x) = f(x)g'(x) + g(x)f'(x)$ **135.** True

137. True **139.** Proof

Section 2.4 *(page 140)*

1. To find the derivative of the composition of two differentiable functions, take the derivative of the outer function and keep the inner function the same. Then multiply by the derivative of the inner function.

$y = f(g(x))$	$u = g(x)$	$y = f(u)$
3. $y = (6x-5)^4$	$u = 6x - 5$	$y = u^4$
5. $y = \frac{1}{3x+5}$	$u = 3x + 5$	$y = \frac{1}{u}$
7. $y = \csc^3 x$	$u = \csc x$	$y = u^3$

9. $6(2x-7)^2$ **11.** $-\frac{45}{2(4-9x)^{1/6}}$ **13.** $-\frac{10s}{\sqrt{5s^2+3}}$

15. $\frac{4x}{\sqrt[3]{(6x^2+1)^2}}$ **17.** $-\frac{1}{(x-2)^2}$ **19.** $-\frac{54s^2}{(s^3-2)^4}$

21. $-\frac{3}{2\sqrt{(3x+5)^3}}$ **23.** $x(x-2)^6(9x-4)$

25. $\frac{1-2x^2}{\sqrt{1-x^2}}$ **27.** $\frac{1}{\sqrt{(x^2+1)^3}}$

29. $\frac{-2(x+5)(x^2+10x-2)}{(x^2+2)^3}$ **31.** $\frac{8(t+1)^3}{(t+3)^5}$

33. $20x(x^2+3)^9 + 2(x^2+3)^5 + 20x^2(x^2+3)^4 + 2x$

35. $-4\sin 4x$ **37.** $15\sec^2 3x$

39. $2\pi^2 x\cos(\pi x)^2$ **41.** $2\cos 4x$

43. $\frac{-1-\cos^2 x}{\sin^3 x}$ **45.** $8\sec^2 x\tan x$

47. $\sin 2\theta\cos 2\theta$, or $\frac{1}{2}\sin 4\theta$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

49. $6\pi(\pi t - 1)\sec(\pi t - 1)^2\tan(\pi t - 1)^2$

51. $(6x - \sin x)\cos(3x^2 + \cos x)$

53. $-\dfrac{3\pi\cos\sqrt{\cot 3\pi x}\csc^2(3\pi x)}{2\sqrt{\cot 3\pi x}}$

55. $\dfrac{1 - 3x^2 - 4x^{3/2}}{2\sqrt{x}(x^2 + 1)^2}$



The zero of y' corresponds to the point on the graph of the function where the tangent line is horizontal.

57. $-\dfrac{\pi x\sin(\pi x) + \cos(\pi x) + 1}{x^2}$



The zeros of y' correspond to the points on the graph of the function where the tangent lines are horizontal.

59. 3; 3 cycles in $[0, 2\pi]$ **61.** $\frac{5}{3}$

63. $-\frac{3}{5}$ **65.** -1 **67.** 0

69. (a) $8x - 5y - 7 = 0$

(b)



71. (a) $24x + y + 23 = 0$

(b)



73. (a) $y = 8x - 8\pi$

(b)



75. (a) $4x - y + (1 - \pi) = 0$

(b)



77. $3x + 4y - 25 = 0$



79. $\left(\dfrac{\pi}{6}, \dfrac{3\sqrt{3}}{2}\right), \left(\dfrac{5\pi}{6}, -\dfrac{3\sqrt{3}}{2}\right), \left(\dfrac{3\pi}{2}, 0\right)$

81. $2940(2 - 7x)^2$

83. $\dfrac{242}{(11x - 6)^3}$ **85.** $2(\cos x^2 - 2x^2\sin x^2)$

87. $h''(x) = 18x + 6$, 24 **89.** $g''(x) = -\dfrac{3}{(2x + 7)^{\frac{3}{2}}}$, -3

91. $f''(x) = -4x^2\cos x^2 - 2\sin x^2$, 0

93.



The zeros of f' correspond to the points where the graph of f has horizontal tangents.

95. (a) The rate of change of g is three times as fast as the rate of change of f.

(b) The rate of change of g is $2x$ times as fast as the rate of change of f.

97. (a) $g'(x) = f'(x)$ (b) $h'(x) = 2f'(x)$

(c) $r'(x) = -3f'(-3x)$ (d) $s'(x) = f'(x + 2)$

x	-2	-1	0	1	2	3
$f'(x)$	4	$\frac{2}{3}$	$-\frac{1}{3}$	-1	-2	-4
$g'(x)$	4	$\frac{2}{3}$	$-\frac{1}{3}$	-1	-2	-4
$h'(x)$	8	$\frac{4}{3}$	$-\frac{2}{3}$	-2	-4	-8
$r'(x)$		12	1			
$s'(x)$	$-\frac{1}{3}$	-1	-2	-4		

99. (a) $\frac{1}{2}$

(b) $s'(5)$ does not exist because g is not differentiable at 6.

101. (a) 1.461 (b) -1.016 **103.** 0.2 rad, 1.45 rad/sec

105. (a)



$T(t) = 27.3\sin(0.49t - 1.90) + 57.1$

(b)



The model is a good fit.

(c) $T'(t) = 13.377\cos(0.49t - 1.90)$



(d) The temperature changes most rapidly around spring (March–May) and fall (Oct.–Nov.)

The temperature changes most slowly around winter (Dec.–Feb.) and summer (Jun.–Aug.)

Yes. Explanations will vary.

CHAPTER 2

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

107. (a) 0 bacteria per day
(b) 177.8 bacteria per day
(c) 44.4 bacteria per day
(d) 10.8 bacteria per day
(e) 3.3 bacteria per day
(f) The rate of change of the population is decreasing as time passes.

109. (a) $f'(x) = \beta \cos \beta x$
$f''(x) = -\beta^2 \sin \beta x$
$f'''(x) = -\beta^3 \cos \beta x$
$f^{(4)}(x) = \beta^4 \sin \beta x$
(b) $f''(x) + \beta^2 f(x) = -\beta^2 \sin \beta x + \beta^2(\sin \beta x) = 0$
(c) $f^{(2k)}(x) = (-1)^k \beta^{2k} \sin \beta x$
$f^{(2k-1)}(x) = (-1)^{k+1}\beta^{2k-1} \cos \beta x$

111. (a) $r'(1) = 0$ (b) $s'(4) = \frac{5}{8}$

113. (a) and (b) Proofs

115. $g'(x) = 3\left(\dfrac{3x-5}{|3x-5|}\right), \quad x \neq \dfrac{5}{3}$

117. $h'(x) = -|x|\sin x + \dfrac{x}{|x|}\cos x, \quad x \neq 0$

119. (a) $P_1(x) = 2\left(x - \dfrac{\pi}{4}\right) + 1$

$P_2(x) = 2\left(x - \dfrac{\pi}{4}\right)^2 + 2\left(x - \dfrac{\pi}{4}\right) + 1$

(b)



(c) P_2

(d) The accuracy worsens as you move away from $x = \dfrac{\pi}{4}$.

121. True. **123.** True

125. Putnam Problem A1, 1967

Section 2.5 *(page 149)*

1. Answers will vary. *Sample answer:* In the explicit form of a function, the dependent variable y is explicitly written as a function of the independent variable x [$y = f(x)$]. In an implicit equation, the dependent variable y is not necessarily written in the form $y = f(x)$. An example of an implicit function is $x^2 + xy = 5$. In explicit form, it would be

$y = \dfrac{5 - x^2}{x}$.

3. You use implicit differentiation to find the derivative in cases where it is difficult to express y as a function of x explicitly.

5. $-\dfrac{x}{y}$ **7.** $-\dfrac{x^4}{y^4}$ **9.** $\dfrac{y - 3x^2}{2y - x}$

11. $\dfrac{1 - 3x^2y^3}{3x^3y^2 - 1}$ **13.** $\dfrac{6xy - 3x^2 - 2y^2}{4xy - 3x^2}$ **15.** $\dfrac{\cos x}{4 \sin 2y}$

17. $-\dfrac{\cot x \csc x + \tan y + 1}{x \sec^2 y}$ **19.** $\dfrac{y \cos xy}{1 - x \cos xy}$

21. (a) $y_1 = \sqrt{64 - x^2}$, $y_2 = -\sqrt{64 - x^2}$

(b)



(c) $\dfrac{dy}{dx} = \dfrac{\mp x}{\sqrt{64 - x^2}} = -\dfrac{x}{y}$ (d) $\dfrac{dy}{dx} = -\dfrac{x}{y}$

23. (a) $y_1 = \dfrac{\sqrt{x^2 + 16}}{4}$, $y_2 = \dfrac{-\sqrt{x^2 + 16}}{4}$

(b)



(c) $\dfrac{dy}{dx} = \dfrac{\pm x}{4\sqrt{x^2 + 16}} = \dfrac{x}{16y}$ (d) $\dfrac{dy}{dx} = \dfrac{x}{16y}$

25. $-\dfrac{y}{x}$; $-\dfrac{1}{6}$ **27.** $\dfrac{98x}{y(x^2 + 49)^2}$; Undefined

29. $-\dfrac{y(y + 2x)}{x(x + 2y)}$; -1 **31.** $-\sin^2(x + y)$ or $-\dfrac{x^2}{x^2 + 1}$; 0

33. $-\frac{1}{2}$ **35.** 0 **37.** $y = -x + 7$

39. $y = \dfrac{\sqrt{3}x}{6} + \dfrac{8\sqrt{3}}{3}$ **41.** $y = -\dfrac{2}{11}x + \dfrac{30}{11}$

43. Answers will vary. *Sample answers:*
$xy = 2$, $yx^2 + x = 2$; $x^2 + y^2 + y = 4$, $xy + y^2 = 2$

45. (a) $y = -2x + 4$ (b) Answers will vary.

47. $\cos^2 y$, $-\dfrac{\pi}{2} < y < \dfrac{\pi}{2}$, $\dfrac{1}{1 + x^2}$ **49.** $-\dfrac{4}{y^3}$

51. $\dfrac{6x^2y + 2y - 20x}{(x^2 - 1)^2}$ **53.** $\dfrac{x \sin x + 2 \cos x + 14y}{7x^2}$

55. $2x + 3y - 30 = 0$



57. At (4, 3):
Tangent line: $4x + 3y - 25 = 0$
Normal line: $3x - 4y = 0$



At $(-3, 4)$
Tangent line: $3x - 4y + 25 = 0$
Normal line: $4x + 3y = 0$



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

59. $x^2 + y^2 = r^2 \implies y' = -\dfrac{x}{y} \implies \dfrac{y}{x}$ = slope of normal line.

Then for (x_0, y_0) on the circle, $x_0 \neq 0$, an equation of the normal line is $y = \left(\dfrac{y_0}{x_0}\right)x$, which passes through the origin. If $x_0 = 0$, the normal line is vertical and passes through the origin.

61. Horizontal tangents: $(-4, 0)$, $(-4, 10)$

Vertical tangents: $(0, 5)$, $(-8, 5)$

63.



At $(1, 2)$:
Slope of ellipse: -1
Slope of parabola: 1
At $(1, -2)$:
Slope of ellipse: 1
Slope of parabola: -1

65.



At $(0, 0)$:
Slope of line: -1
Slope of sine curve: 1

67. Derivatives: $\dfrac{dy}{dx} = -\dfrac{y}{x}, \dfrac{dy}{dx} = \dfrac{x}{y}$





69.



Use starting point B.

71. (a)



(b)



$y_1 = \frac{1}{3}\left[\left(\sqrt{7} + 7\right)x + \left(8\sqrt{7} + 23\right)\right]$

$y_2 = -\frac{1}{3}\left[\left(-\sqrt{7} + 7\right)x - \left(23 - 8\sqrt{7}\right)\right]$

$y_3 = -\frac{1}{3}\left[\left(\sqrt{7} - 7\right)x - \left(23 - 8\sqrt{7}\right)\right]$

$y_4 = -\frac{1}{3}\left[\left(\sqrt{7} + 7\right)x - \left(8\sqrt{7} + 23\right)\right]$

(c) $\left(\dfrac{8\sqrt{7}}{7}, 5\right)$

73. Proof **75.** $y = -\dfrac{\sqrt{3}}{2}x + 2\sqrt{3}$, $y = \dfrac{\sqrt{3}}{2}x - 2\sqrt{3}$

77. (a) $y = 2x - 6$

(b)



(c) $\left(\frac{28}{17}, -\frac{46}{17}\right)$

Section 2.6 *(page 157)*

1. A related-rate equation is an equation that relates the rates of change of various quantities.

3. (a) $\frac{3}{4}$ (b) 20 **5.** (a) $-\frac{5}{8}$ (b) $\frac{3}{2}$

7. (a) -8 cm/sec
(b) 0 cm/sec
(c) 8 cm/sec

9. (a) 12 ft/sec
(b) 6 ft/sec
(c) 3 ft/sec

11. 296π cm^2/min

13. (a) 972π in.^{3}/min, $15{,}552\pi$ in.^{3}/min
(b) If $\dfrac{dr}{dt}$ is constant, $\dfrac{dV}{dt}$ is proportional to r^2.

15. (a) 72 cm^3/sec
(b) 1800 cm^3/sec

17. $\dfrac{8}{405\pi}$ ft/min

19. (a) 12.5% (b) $\dfrac{1}{144}$ m/min

21. (a) $-\frac{7}{12}$ ft/sec, $-\frac{3}{2}$ ft/sec, $-\frac{48}{7}$ ft/sec
(b) $\frac{527}{24}$ ft^2/sec (c) $\frac{1}{12}$ rad/sec

23. Rate of vertical change: $\dfrac{1}{5}$ m/sec

Rate of horizontal change: $-\dfrac{\sqrt{3}}{15}$ m/sec

25. (a) -750 mi/h (b) 30 min

27. $-\dfrac{50}{\sqrt{85}} \approx -5.42$ ft/sec

29. (a) $\frac{25}{3}$ ft/sec (b) $\frac{10}{3}$ ft/sec

31. (a) 12 sec (b) $\dfrac{1}{2}\sqrt{3}$ m (c) $\dfrac{\sqrt{5}\pi}{120}$ m/sec

33. Evaporation rate proportional to $S \implies \dfrac{dV}{dt} = k(4\pi r^2)$

$V = \left(\dfrac{4}{3}\right)\pi r^3 \implies \dfrac{dV}{dt} = 4\pi r^2 \dfrac{dr}{dt}$. So $k = \dfrac{dr}{dt}$.

35. (a) $\dfrac{dy}{dt} = 3\dfrac{dx}{dt}$ means that y changes three times as fast as x changes.
(b) y changes slowly when $x \approx 0$ or $x \approx L$. y changes more rapidly when x is near the middle of the interval.

37. 0.6 ohm/sec **39.** About 84.9797 mi/h

41. $\dfrac{2\sqrt{21}}{525} \approx 0.017$ rad/sec

43. (a) $\dfrac{200\pi}{3}$ ft/sec (b) 200π ft/sec
(c) About 427.43π ft/sec

45. (a) Proof (b) $\dfrac{\sqrt{3}s^2}{8}, \dfrac{s^2}{8}$

47. (a) $r(f) = -0.0406f^3 + 1.974f^2 - 31.21f + 161.6$
(b) $\dfrac{dr}{dt} = (-0.1218f^2 + 3.948f - 31.21)\dfrac{df}{dt}$,
-0.2899 million participants/yr

49. -0.1808 ft/sec^2

CHAPTER 2

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Review Exercises for Chapter 2 *(page 161)*

1. (a) 80, 144, 80
(b) -32, calculus is not needed
(c) -64, calculus is needed
(d) Limits allow you to find the derivative of a function, and with the derivative, you can now find the instantaneous velocity of the car.

3. Answers will vary.
Sample answer: $y = 2x$



5. Answers will vary. *Sample answer:*
$p(x) = 2x^2 + 2x + 1$
$(c, p(c)) = (0, 1)$
$(c + h, p(c + h)) = (1, 5)$
Tangent Line: $y = 2x + 1$
Secant Line: $y = 4x + 1$
(a)



(b) Answers will vary.
(c) Answers will vary.

7. 0 **9.** $3x^2 - 2$ **11.** 5

13. f is differentiable at all $x \neq 3$. **15.** 0

17. $3x^2 - 22x$ **19.** $\frac{3}{\sqrt{x}} + \frac{1}{\sqrt[3]{x^2}}$ **21.** $-\frac{4}{3t^3}$

23. $4 - 5\cos\theta$ **25.** $-3\sin\theta - \frac{\cos\theta}{4}$

27. -1 **29.** 2

31. (a) 50 vibrations/sec/lb
(b) 33.33 vibrations/sec/lb

33. (a) $s(t) = -16t^2 - 30t + 600$
$v(t) = -32t - 30$
(b) -94 ft/sec
(c) $v(1) = -62$ ft/sec, $v(3) = -126$ ft/sec
(d) About 5.258 sec
(e) About -198.256 ft/sec

35. $4(5x^3 - 15x^2 - 11x - 8)$

37. $9x\cos x - \cos x + 9\sin x$

39. $\frac{-(x^2 + 1)}{(x^2 - 1)^2}$ **41.** $\frac{4x^3\cos x + x^4\sin x}{\cos^2 x}$

43. $3x^2\sec x\tan x + 6x\sec x$ **45.** $-x\sin x$

47. $y = 4x + 10$ **49.** $y = -8x + 1$ **51.** $-48t$

53. $\frac{225}{4}\sqrt{x}$ **55.** $6\sec^2\theta\tan\theta$ **57.** $8\cot x\csc^2 x$

59. $v(3) = 11$ m/sec, $a(3) = -6$ m/sec^2 **61.** $28(7x + 3)^3$

63. $-\frac{6x}{(x^2 + 5)^4}$ **65.** $-45\sin(9x + 1)$

67. $\frac{1}{2}(1 - \cos 2x)$, or $\sin^2 x$ **69.** $(36x + 1)(6x + 1)^4$

71. $\frac{3x^2(x + 10)}{2(x + 5)^{5/2}}$ **73.** -2 **75.** -11 **77.** 0

79. $384(8x + 5)$ **81.** $2\csc^2 x\cot x$

83. (a) -18.667°F/h
(b) -7.284°F/h
(c) -3.240°F/h
(d) -0.747°F/h

85. $-\frac{x}{y}$ **87.** $\frac{y(y^2 - 3x^2)}{x(x^2 - 3y^2)}$ **89.** $\frac{y\sin x + \sin y}{\cos x - x\cos y}$

91. Tangent line: $3x + y - 10 = 0$
Normal line: $x - 3y = 0$



93. $2\sqrt{2}$ units/sec, 4 units/sec, 8 units/sec

95. 450π km/h

97. (a) $j(t)$ is the rate of change of acceleration.
(b) $j(t) = 0$, so the acceleration is constant.

P.S. Problem Solving *(page 164)*

1. (a) $r = \frac{1}{2}$; $x^2 + \left(y - \frac{1}{2}\right)^2 = \frac{1}{4}$
(b) Center: $\left(0, \frac{5}{4}\right)$; $x^2 + \left(y - \frac{5}{4}\right)^2 = 1$

3. $p(x) = 2x^3 + 4x^2 - 5$

5. (a) $v(t) = -\frac{27}{5}t + 27$ ft/sec
$a(t) = -\frac{27}{5}$ ft/sec^2
(b) 5 sec; 73.5 ft
(c) The acceleration due to gravity on Earth is greater in magnitude than that on the moon.

7. (a) Graph $\begin{cases} y_1 = \frac{1}{a}\sqrt{x^2(a^2 - x^2)} \\ y_2 = -\frac{1}{a}\sqrt{x^2(a^2 - x^2)} \end{cases}$ as separate equations.

(b) Answers will vary. *Sample answer:*



The intercepts will always be $(0, 0)$, $(a, 0)$, and $(-a, 0)$, and the maximum and minimum y-values appear to be $\pm\frac{1}{2}a$.

(c) $\left(\frac{a\sqrt{2}}{2}, \frac{a}{2}\right)$, $\left(\frac{a\sqrt{2}}{2}, -\frac{a}{2}\right)$, $\left(-\frac{a\sqrt{2}}{2}, \frac{a}{2}\right)$, $\left(-\frac{a\sqrt{2}}{2}, -\frac{a}{2}\right)$

9. Proof; The graph of L is a line passing through the origin $(0, 0)$.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Chapter 3

Section 3.1 *(page 171)*

1. $f(c)$ is the low point of the graph of f on the interval I.

3. A relative maximum is a peak of the graph. An absolute maximum is the greatest value on the interval I.

5. Find all x-values for which $f'(x) = 0$ and all x-values for which $f'(x)$ does not exist.

7. $f'(0) = 0$ **9.** $g'(2) = 0$ **11.** $f'(-2)$ is undefined.

13. 2, absolute maximum (and relative maximum)

15. 1, absolute maximum (and relative maximum);
2, absolute minimum (and relative minimum);
3, absolute maximum (and relative maximum)

17. $x = \frac{3}{4}$ **19.** $t = \frac{8}{3}$ **21.** $x = \frac{\pi}{3}, \pi, \frac{5\pi}{3}$

23. Minimum: $(2, 1)$
Maximum: $(-1, 4)$

25. Minimum: $(-3, -13)$
Maximum: $(0, 5)$

27. Minimum: $\left(-1, -\frac{5}{2}\right)$
Maximum: $(2, 2)$

29. Minimum: $(0, 0)$
Maximum: $(-1, 5)$

31. Minima: $(1, -6)$ and $(-2, -6)$
Maximum: $(0, 0)$

33. Minimum: $(-1, -1)$
Maximum: $(3, 3)$

35. Minimum value is -2 for $-2 \le x < -1$.
Maximum: $(2, 2)$

37. Minimum: $\left(\frac{3\pi}{2}, -1\right)$
Maximum: $\left(\frac{5\pi}{6}, \frac{1}{2}\right)$

39. Minimum: $(\pi, -3)$
Maxima: $(0, 3)$ and $(2\pi, 3)$

41. (a) Minimum: $(0, -3)$
Maximum: $(2, 1)$
(b) Minimum: $(0, -3)$
(c) Maximum: $(2, 1)$
(d) No extrema

43. (a) Minimum: $(1, -1)$
Maximum: $(-1, 3)$
(b) Maximum: $(3, 3)$
(c) Minimum: $(1, -1)$
(d) Minimum: $(1, -1)$

45.



Minimum: $(4, 1)$

47.



Minimum: $(0, 0)$
Maximum: $(2.7149, 1.7856)$

49. (a)



(b) Minimum: $(0.4398, -1.0613)$

51. Maximum: $\left|f''\left(\sqrt[3]{-10 + \sqrt{108}}\right)\right| = f''\left(\sqrt{3} - 1\right) \approx 1.47$

53. Maximum: $\left|f^{(4)}(0)\right| = \frac{56}{81}$

55. Answers will vary. *Sample answer:* Let $f(x) = \frac{1}{x}$. f is continuous on $(0, 1)$ but does not have a maximum or minimum.



57. (a) Yes. The value is defined.
(b) No. The value is undefined.

59. No. The function is not defined at $x = -2$.

61. Maximum: $P(12) = 72$; No. P is decreasing for $I > 12$.

63. $\theta = \text{arcsec}\ \sqrt{3} \approx 0.9553$ rad

65. False. The maximum would be 9 if the interval was closed.

67. True **69.** Proof **71.** Putnam Problem B3, 2004

Section 3.2 *(page 178)*

1. Rolle's Theorem gives conditions that guarantee the existence of an extreme value in the interior of a closed interval.

3. $f(-1) = f(1) = 1$; f is not continuous on $[-1, 1]$.

5. $f(0) = f(2) = 0$; f is not differentiable on $(0, 2)$.

7. $(2, 0), (-1, 0)$; $f'\left(\frac{1}{2}\right) = 0$ **9.** $(0, 0), (-4, 0)$; $f'\left(-\frac{8}{3}\right) = 0$

11. $f'\left(\frac{3}{2}\right) = 0$ **13.** $f'\left(\frac{6 - \sqrt{3}}{3}\right) = 0$; $f'\left(\frac{6 + \sqrt{3}}{3}\right) = 0$

15. Not differentiable at $x = 0$ **17.** $f'\left(-2 + \sqrt{5}\right) = 0$

19. $f'\left(\frac{\pi}{2}\right) = 0$; $f'\left(\frac{3\pi}{2}\right) = 0$ **21.** $f'(1) = 0$

23. Not continuous on $[0, \pi]$

25.



Rolle's Theorem does not apply.

27.



$f'\left(-\frac{6}{\pi}\arccos\frac{3}{\pi}\right) = 0$

29. (a) $f(1) = f(2) = 38$
(b) Velocity $= 0$ for some t in $(1, 2)$; $t = \frac{3}{2}$ sec

31.



33. The function is not continuous on $[0, 6]$.

35. The function is not continuous on $[0, 6]$.

CHAPTER 3

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

37. (a) Secant line: $x + y - 3 = 0$ (b) $c = \frac{1}{2}$
(c) Tangent line: $4x + 4y - 21 = 0$
(d)



39. $f'\left(\frac{\sqrt{21}}{3}\right) = 42$ **41.** $f'\left(-\frac{\sqrt{3}}{3}\right) = 3$

43. f is not continuous at $x = 1$.

45. f is not differentiable at $x = -\frac{1}{2}$. **47.** $f'\left(\frac{\pi}{2}\right) = 0$

49. (a)–(c)



(b) $y = \frac{2}{3}(x - 1)$
(c) $y = \frac{1}{3}\left(2x + 5 - 2\sqrt{6}\right)$

51. (a)–(c)



(b) $y = \frac{1}{4}x + \frac{3}{4}$
(c) $y = \frac{1}{4}x + 1$

53. (a) -14.7 m/sec (b) 1.5 sec

55. No. Let $f(x) = x^2$ on $[-1, 2]$.

57. No. $f(x)$ is not continuous on $[0, 1]$. So it does not satisfy the hypothesis of Rolle's Theorem.

59. By the Mean Value Theorem, there is a time when the speed of the plane must equal the average speed of 454.5 miles/hour. The speed was 400 miles/hour when the plane was accelerating to 454.5 miles/hour and decelerating from 454.5 miles/hour.

61. Proof

63. (a) Answers will vary. *Sample answer:*



(b)



65–67. Proofs **69.** $f(x) = 5$; $f(x) = c$ and $f(2) = 5$.

71. $f(x) = x^2 - 1$; $f(x) = x^2 + c$ and $f(1) = 0$, so $c = -1$.

73. False. f is not continuous on $[-1, 1]$. **75.** True

77–83. Proofs

Section 3.3 *(page 187)*

1. A positive derivative of a function on an open interval implies that the function is increasing on the interval. A negative derivative implies that the function is decreasing. A zero derivative implies that the function is constant.

3. (a) $(0, 6)$ (b) $(6, 8)$

5. Increasing on $(-\infty, -1)$; Decreasing on $(-1, \infty)$

7. Increasing on $(-\infty, -2)$ and $(2, \infty)$; Decreasing on $(-2, 2)$

9. Increasing on $(-\infty, -1)$; Decreasing on $(-1, \infty)$

11. Increasing on $(1, \infty)$; Decreasing on $(-\infty, 1)$

13. Increasing on $\left(-2\sqrt{2}, 2\sqrt{2}\right)$;
Decreasing on $\left(-4, -2\sqrt{2}\right)$ and $\left(2\sqrt{2}, 4\right)$

15. Increasing on $\left(0, \frac{\pi}{2}\right)$ and $\left(\frac{3\pi}{2}, 2\pi\right)$;
Decreasing on $\left(\frac{\pi}{2}, \frac{3\pi}{2}\right)$

17. Increasing on $\left(0, \frac{7\pi}{6}\right)$ and $\left(\frac{11\pi}{6}, 2\pi\right)$;
Decreasing on $\left(\frac{7\pi}{6}, \frac{11\pi}{6}\right)$

19. (a) Critical number: $x = 4$
(b) Increasing on $(4, \infty)$; Decreasing on $(-\infty, 4)$
(c) Relative minimum: $(4, -16)$

21. (a) Critical number: $x = 1$
(b) Increasing on $(-\infty, 1)$; Decreasing on $(1, \infty)$
(c) Relative maximum: $(1, 5)$

23. (a) Critical numbers: $x = -1, 1$
(b) Increasing on $(-1, 1)$;
Decreasing on $(-\infty, -1)$ and $(1, \infty)$
(c) Relative maximum: $(1, 17)$;
Relative minimum: $(-1, -11)$

25. (a) Critical numbers: $x = -\frac{5}{3}, 1$
(b) Increasing on $\left(-\infty, -\frac{5}{3}\right), (1, \infty)$;
Decreasing on $\left(-\frac{5}{3}, 1\right)$
(c) Relative maximum: $\left(-\frac{5}{3}, \frac{256}{27}\right)$;
Relative minimum: $(1, 0)$

27. (a) Critical numbers: $x = \pm 1$
(b) Increasing on $(-\infty, -1)$ and $(1, \infty)$;
Decreasing on $(-1, 1)$
(c) Relative maximum: $\left(-1, \frac{4}{5}\right)$; Relative minimum: $\left(1, -\frac{4}{5}\right)$

29. (a) Critical number: $x = 0$
(b) Increasing on $(-\infty, \infty)$
(c) No relative extrema

31. (a) Critical number: $x = -2$
(b) Increasing on $(-2, \infty)$; Decreasing on $(-\infty, -2)$
(c) Relative minimum: $(-2, 0)$

33. (a) Critical number: $x = 5$
(b) Increasing on $(-\infty, 5)$; Decreasing on $(5, \infty)$
(c) Relative maximum: $(5, 5)$

35. (a) Critical numbers: $x = \pm\frac{\sqrt{2}}{2}$; Discontinuity: $x = 0$
(b) Increasing on $\left(-\infty, -\frac{\sqrt{2}}{2}\right)$ and $\left(\frac{\sqrt{2}}{2}, \infty\right)$;
Decreasing on $\left(-\frac{\sqrt{2}}{2}, 0\right)$ and $\left(0, \frac{\sqrt{2}}{2}\right)$
(c) Relative maximum: $\left(-\frac{\sqrt{2}}{2}, -2\sqrt{2}\right)$;
Relative minimum: $\left(\frac{\sqrt{2}}{2}, 2\sqrt{2}\right)$

37. (a) Critical number: $x = 0$; Discontinuities: $x = \pm 3$
(b) Increasing on $(-\infty, -3)$ and $(-3, 0)$;
Decreasing on $(0, 3)$ and $(3, \infty)$
(c) Relative maximum: $(0, 0)$

39. (a) Critical number: $x = 0$
(b) Increasing on $(-\infty, 0)$; Decreasing on $(0, \infty)$
(c) Relative maximum: $(0, 4)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

41. (a) Critical numbers: $x = \frac{\pi}{3}, \frac{5\pi}{3}$; Increasing on $\left(\frac{\pi}{3}, \frac{5\pi}{3}\right)$;
Decreasing on $\left(0, \frac{\pi}{3}\right)$ and $\left(\frac{5\pi}{3}, 2\pi\right)$

(b) Relative maximum: $\left(\frac{5\pi}{3}, \frac{5\pi}{3} + \sqrt{3}\right)$;
Relative minimum: $\left(\frac{\pi}{3}, \frac{\pi}{3} - \sqrt{3}\right)$

43. (a) Critical numbers: $x = \frac{\pi}{4}, \frac{5\pi}{4}$;
Increasing on $\left(0, \frac{\pi}{4}\right), \left(\frac{5\pi}{4}, 2\pi\right)$;
Decreasing on $\left(\frac{\pi}{4}, \frac{5\pi}{4}\right)$

(b) Relative maximum: $\left(\frac{\pi}{4}, \sqrt{2}\right)$;
Relative minimum: $\left(\frac{5\pi}{4}, -\sqrt{2}\right)$

45. (a) Critical numbers:
$x = \frac{\pi}{4}, \frac{\pi}{2}, \frac{3\pi}{4}, \pi, \frac{5\pi}{4}, \frac{3\pi}{2}, \frac{7\pi}{4}$;
Increasing on $\left(\frac{\pi}{4}, \frac{\pi}{2}\right), \left(\frac{3\pi}{4}, \pi\right), \left(\frac{5\pi}{4}, \frac{3\pi}{2}\right), \left(\frac{7\pi}{4}, 2\pi\right)$;
Decreasing on $\left(0, \frac{\pi}{4}\right), \left(\frac{\pi}{2}, \frac{3\pi}{4}\right), \left(\pi, \frac{5\pi}{4}\right), \left(\frac{3\pi}{2}, \frac{7\pi}{4}\right)$

(b) Relative maxima: $\left(\frac{\pi}{2}, 1\right), (\pi, 1), \left(\frac{3\pi}{2}, 1\right)$;
Relative minima: $\left(\frac{\pi}{4}, 0\right), \left(\frac{3\pi}{4}, 0\right), \left(\frac{5\pi}{4}, 0\right), \left(\frac{7\pi}{4}, 0\right)$

47. (a) Critical numbers: $\frac{\pi}{2}, \frac{7\pi}{6}, \frac{3\pi}{2}, \frac{11\pi}{6}$;
Increasing on $\left(0, \frac{\pi}{2}\right), \left(\frac{7\pi}{6}, \frac{3\pi}{2}\right), \left(\frac{11\pi}{6}, 2\pi\right)$;
Decreasing on $\left(\frac{\pi}{2}, \frac{7\pi}{6}\right), \left(\frac{3\pi}{2}, \frac{11\pi}{6}\right)$

(b) Relative maxima: $\left(\frac{\pi}{2}, 2\right), \left(\frac{3\pi}{2}, 0\right)$;
Relative minima: $\left(\frac{7\pi}{6}, -\frac{1}{4}\right), \left(\frac{11\pi}{6}, -\frac{1}{4}\right)$

49. (a) $f'(x) = \dfrac{2(9 - 2x^2)}{\sqrt{9 - x^2}}$

(b)



(c) Critical numbers: $x = \pm\frac{3\sqrt{2}}{2}$

(d) $f' > 0$ on $\left(-\frac{3\sqrt{2}}{2}, \frac{3\sqrt{2}}{2}\right)$;
$f' < 0$ on $\left(-3, -\frac{3\sqrt{2}}{2}\right), \left(\frac{3\sqrt{2}}{2}, 3\right)$;
f is increasing when f' is positive and decreasing when f' is negative.

51. (a) $f'(t) = t(t\cos t + 2\sin t)$

(b)



(c) Critical numbers: $t = 2.2889, 5.0870$

(d) $f' > 0$ on $(0, 2.2889)$, $(5.0870, 2\pi)$; $f' < 0$ on $(2.2889, 5.0870)$; f is increasing when f' is positive and decreasing when f' is negative.

53. (a) $f'(x) = -\cos\dfrac{x}{3}$

(b)



(c) Critical numbers: $x = \frac{3\pi}{2}, \frac{9\pi}{2}$

(d) $f' > 0$ on $\left(\frac{3\pi}{2}, \frac{9\pi}{2}\right)$; $f' < 0$ on $\left(0, \frac{3\pi}{2}\right), \left(\frac{9\pi}{2}, 6\pi\right)$;
f is increasing when f' is positive and decreasing when f' is negative.

55. $f(x)$ is symmetric with respect to the origin.
Zeros: $(0, 0), \left(\pm\sqrt{3}, 0\right)$



$g(x)$ is continuous on $(-\infty, \infty)$, and $f(x)$ has holes at $x = 1$ and $x = -1$.

57.



59.



61.



63. $g'(0) < 0$ **65.** $g'(-6) < 0$

67. Answers will vary. *Sample answer:*



CHAPTER 3

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

69. No. For example, the product of $f(x) = x$ and $g(x) = x$ is $f(x) \cdot g(x) = x^2$, which is decreasing on $(-\infty, 0)$ and increasing on $(0, \infty)$.

71. $(5, f(5))$ is a relative minimum.

73. (a)



(b) Critical numbers: $x \approx -0.40$ and $x \approx 0.48$

(c) Relative maximum: $(0.48, 1.25)$;
Relative minimum: $(-0.40, 0.75)$

75. (a) $s'(t) = 9.8(\sin\theta)t$; speed $= |9.8(\sin\theta)t|$

(b)

θ	0	$\frac{\pi}{4}$	$\frac{\pi}{3}$	$\frac{\pi}{2}$	$\frac{2\pi}{3}$	$\frac{3\pi}{4}$	π
$s'(t)$	0	$4.9\sqrt{2}\,t$	$4.9\sqrt{3}\,t$	$9.8t$	$4.9\sqrt{3}\,t$	$4.9\sqrt{2}\,t$	0

The speed is maximum at $\theta = \frac{\pi}{2}$.

77. (a)

t	0	0.5	1	1.5	2	2.5	3
$C(t)$	0	0.055	0.107	0.148	0.171	0.176	0.167

$t = 2.5$ h

(b)



$t \approx 2.38$ h (c) $t \approx 2.38$ h

79. $r = \dfrac{2R}{3}$

81. (a) $v(t) = 6 - 2t$ (b) $[0, 3)$ (c) $(3, \infty)$ (d) $t = 3$

83. (a) $v(t) = 3t^2 - 10t + 4$

(b) $\left[0, \dfrac{5 - \sqrt{13}}{3}\right)$ and $\left(\dfrac{5 + \sqrt{13}}{3}, \infty\right)$

(c) $\left(\dfrac{5 - \sqrt{13}}{3}, \dfrac{5 + \sqrt{13}}{3}\right)$ (d) $t = \dfrac{5 \pm \sqrt{13}}{3}$

85. Answers will vary.

87. (a) Minimum degree: 3

(b) $a_3(0)^3 + a_2(0)^2 + a_1(0) + a_0 = 0$
$a_3(2)^3 + a_2(2)^2 + a_1(2) + a_0 = 2$
$3a_3(0)^2 + 2a_2(0) + a_1 = 0$
$3a_3(2)^2 + 2a_2(2) + a_1 = 0$

(c) $f(x) = -\frac{1}{2}x^3 + \frac{3}{2}x^2$

89. (a) Minimum degree: 4

(b) $a_4(0)^4 + a_3(0)^3 + a_2(0)^2 + a_1(0) + a_0 = 0$
$a_4(2)^4 + a_3(2)^3 + a_2(2)^2 + a_1(2) + a_0 = 4$
$a_4(4)^4 + a_3(4)^3 + a_2(4)^2 + a_1(4) + a_0 = 0$
$4a_4(0)^3 + 3a_3(0)^2 + 2a_2(0) + a_1 = 0$
$4a_4(2)^3 + 3a_3(2)^2 + 2a_2(2) + a_1 = 0$
$4a_4(4)^3 + 3a_3(4)^2 + 2a_2(4) + a_1 = 0$

(c) $f(x) = \frac{1}{4}x^4 - 2x^3 + 4x^2$

91. False. Let $f(x) = \sin x$. **93.** False. Let $f(x) = x^3$.

95. False. Let $f(x) = x^3$. There is a critical number at $x = 0$, but not a relative extremum.

97–99. Proofs **101.** Putnam Problem A3, 2003

Section 3.4 *(page 196)*

1. Find the second derivative of a function and form test intervals by using the values for which the second derivative is zero or does not exist and the values at which the function is not continuous. Determine the sign of the second derivative on these test intervals. If the second derivative is positive, then the graph is concave upward. If the second derivative is negative, then the graph is concave downward.

3. $f' > 0$, $f'' < 0$ **5.** Concave upward: $(-\infty, \infty)$

7. Concave upward: $(-\infty, 0)$, $\left(\frac{3}{2}, \infty\right)$;
Concave downward: $\left(0, \frac{3}{2}\right)$

9. Concave upward: $(-\infty, -2)$, $(2, \infty)$;
Concave downward: $(-2, 2)$

11. Concave upward: $\left(-\infty, -\frac{1}{6}\right)$;
Concave downward: $\left(-\frac{1}{6}, \infty\right)$

13. Concave upward: $(-\infty, -1)$, $(1, \infty)$;
Concave downward: $(-1, 1)$

15. Concave upward: $\left(-\dfrac{\pi}{2}, 0\right)$; Concave downward: $\left(0, \dfrac{\pi}{2}\right)$

17. Point of inflection: $(3, 0)$; Concave downward: $(-\infty, 3)$;
Concave upward: $(3, \infty)$

19. Points of inflection: None; Concave downward: $(-\infty, \infty)$

21. Points of inflection: $(2, -16)$, $(4, 0)$;
Concave upward: $(-\infty, 2)$, $(4, \infty)$;
Concave downward: $(2, 4)$

23. Points of inflection: None; Concave upward: $(-3, \infty)$

25. Points of inflection: None; Concave upward: $(0, \infty)$

27. Point of inflection: $(2\pi, 0)$;
Concave upward: $(2\pi, 4\pi)$; Concave downward: $(0, 2\pi)$

29. Points of inflection: None; Concave upward: $(0, \pi)$, $(2\pi, 3\pi)$;
Concave downward: $(\pi, 2\pi)$, $(3\pi, 4\pi)$

31. Points of inflection: $(\pi, 0)$, $(1.823, 1.452)$, $(4.46, -1.452)$;
Concave upward: $(1.823, \pi)$, $(4.46, 2\pi)$;
Concave downward: $(0, 1.823)$, $(\pi, 4.46)$

33. Relative maximum: $(3, 9)$

35. Relative maximum: $(0, 3)$; Relative minimum: $(2, -1)$

37. Relative minimum: $(3, -25)$

39. Relative minimum: $(0, -3)$

41. Relative maximum: $(-2, -4)$; Relative minimum: $(2, 4)$

43. No relative extrema, because f is nonincreasing.

45. (a) $f'(x) = 0.2x(x - 3)^2(5x - 6)$;
$f''(x) = 0.4(x - 3)(10x^2 - 24x + 9)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

(b) Relative maximum: $(0, 0)$;
Relative minimum: $(1.2, -1.6796)$;
Points of inflection: $(0.4652, -0.7048)$, $(1.9348, -0.9048)$, $(3, 0)$

(c) 

f is increasing when f' is positive and decreasing when f' is negative. f is concave upward when f'' is positive and concave downward when f'' is negative.

47. (a) $f'(x) = \cos x - \cos 3x + \cos 5x$;
$f''(x) = -\sin x + 3 \sin 3x - 5 \sin 5x$

(b) Relative maximum: $\left(\frac{\pi}{2}, 1.53333\right)$;
Points of inflection: $\left(\frac{\pi}{6}, 0.2667\right)$, $(1.1731, 0.9637)$, $(1.9685, 0.9637)$, $\left(\frac{5\pi}{6}, 0.2667\right)$

(c) 

f is increasing when f' is positive and decreasing when f' is negative. f is concave upward when f'' is positive and concave downward when f'' is negative.

49. (a) 

(b) 

51. 

53. 

55. 

57. *Sample answer:*


59. (a) $f(x) = (x - 2)^n$ has a point of inflection at $(2, 0)$ if n is odd and $n \geq 3$.









(b) Proof

61. $f(x) = \frac{1}{2}x^3 - 6x^2 + \frac{45}{2}x - 24$

63. (a) $f(x) = \frac{1}{32}x^3 + \frac{3}{16}x^2$ (b) Two miles from touchdown

65. $x = 100$ units

67. (a)

t	0.5	1	1.5	2	2.5	3
S	151.5	555.6	1097.6	1666.7	2193.0	2647.1

$1.5 < t < 2$

(b) 

(c) About 1.633 yr

$t \approx 1.5$

69. $P_1(x) = 2\sqrt{2}$

$P_2(x) = 2\sqrt{2} - \sqrt{2}\left(x - \frac{\pi}{4}\right)^2$

The values of f, P_1, and P_2 and their first derivatives are equal when $x = \frac{\pi}{4}$. The approximations worsen as you move away from $x = \frac{\pi}{4}$.



71. $P_1(x) = 1 - \frac{x}{2}$

$P_2(x) = 1 - \frac{x}{2} - \frac{x^2}{8}$

The values of f, P_1, and P_2 and their first derivatives are equal when $x = 0$. The approximations worsen as you move away from $x = 0$.



73. (a)–(b) Proofs **75.** True

77. False. f is concave upward at $x = c$ if $f''(c) > 0$.

79. Proof

Section 3.5 *(page 206)*

1. (a) As x increases without bound, $f(x)$ approaches -5.
(b) As x decreases without bound, $f(x)$ approaches 3.

3. 2; one from the left and one from the right

5. f **6.** c **7.** d **8.** a **9.** b **10.** e

11. (a) ∞ (b) 5 (c) 0 **13.** (a) 0 (b) 1 (c) ∞

CHAPTER 3

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

15. (a) 0 (b) $-\frac{2}{3}$ (c) $-\infty$ **17.** 4 **19.** $\frac{7}{9}$ **21.** 0
23. $-\infty$ **25.** -1 **27.** -2 **29.** $\frac{1}{2}$ **31.** ∞
33. 0 **35.** 0
37.



39.



41. 1 **43.** 0 **45.** $\frac{1}{6}$
47.

x	10^0	10^1	10^2	10^3	10^4	10^5	10^6
$f(x)$	1.000	0.513	0.501	0.500	0.500	0.500	0.500



$\lim_{x\to\infty}\left[x-\sqrt{x(x-1)}\right]=\frac{1}{2}$

49.

x	10^0	10^1	10^2	10^3	10^4	10^5	10^6
$f(x)$	0.479	0.500	0.500	0.500	0.500	0.500	0.500



The graph has a hole at $x = 0$.

$\lim_{x\to\infty} x\sin\frac{1}{2x}=\frac{1}{2}$

51. 100%
53. An infinite limit is a description of how a limit fails to exist. A limit at infinity deals with the end behavior of a function.
55. (a) 5 (b) -5
57. (a)



(b) Yes. $\lim_{t\to\infty} S=\frac{100}{1}=100$

59. (a) $\lim_{x\to\infty} f(x)=2$

(b) $x_1=\sqrt{\frac{4-2\varepsilon}{\varepsilon}}, x_2=-\sqrt{\frac{4-2\varepsilon}{\varepsilon}}$

(c) $M=\sqrt{\frac{4-2\varepsilon}{\varepsilon}}$ (d) $N=-\sqrt{\frac{4-2\varepsilon}{\varepsilon}}$

61. (a) Answers will vary. $M=\frac{5\sqrt{33}}{11}$

(b) Answers will vary. $M=\frac{29\sqrt{177}}{59}$

63–65. Proofs

67. (a) $d(m)=\frac{|3m+3|}{\sqrt{m^2+1}}$

(b)



(c) $\lim_{m\to\infty} d(m)=3$; $\lim_{m\to-\infty} d(m)=3$; As m approaches $\pm\infty$, the distance approaches 3.

69. Proof

Section 3.6 *(page 215)*

1. To analyze the graph of a function, determine the domain and range of the function, determine the intercepts, asymptotes, and symmetry of the graph, and locate the x-values for which $f'(x)$ and $f''(x)$ either are zero or do not exist. Then, use the results to determine the relative extrema and points of inflection.
3. Rational function; Use long division to rewrite the rational function as the sum of a first-degree polynomial and another rational function.
5. d **6.** c **7.** a **8.** b
9.



11.



13.



15.



17.



19.



21.



23.



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

25.



27.



29.



31.



33.



35.



37.



39.



41.



43.



45.



Minimum: $(-1.10, -9.05)$;
Maximum: $(1.10, 9.05)$;
Points of inflection:
$(-1.84, -7.86)$, $(1.84, 7.86)$;
Vertical asymptote: $x = 0$;
Horizontal asymptote: $y = 0$

47.



Point of inflection: $(0, 0)$;
Horizontal asymptotes: $y = \pm 2$

49.



Relative minimum: $\left(\pi, -\frac{5}{4}\right)$;
Points of inflection:
$\left(\frac{2\pi}{3}, -\frac{3}{8}\right), \left(\frac{4\pi}{3}, -\frac{3}{8}\right)$

51. *Sample answer:*



The zeros of f' correspond to the points where the graph of f has horizontal tangents. The zero of f'' corresponds to the point where the graph of f' has a horizontal tangent.

53.





55.





57. (a)



The graph has holes at $x = 0$ and at $x = 4$.
Visually approximated critical numbers: $\frac{1}{2}$, 1, $\frac{3}{2}$, 2, $\frac{5}{2}$, 3, $\frac{7}{2}$

(b) $f'(x) = \dfrac{-x\cos^2 \pi x}{(x^2 + 1)^{3/2}} - \dfrac{2\pi \sin \pi x \cos \pi x}{\sqrt{x^2 + 1}}$;

Approximate critical numbers: $\frac{1}{2}$, 0.97, $\frac{3}{2}$, 1.98, $\frac{5}{2}$, 2.98, $\frac{7}{2}$;
The critical numbers where maxima occur appear to be integers in part (a), but by approximating them using f', you can see that they are not integers.

59. Answers will vary. *Sample answer:* Let

$$f(x) = \frac{-6}{0.1(x - 2)^2 + 1} + 6.$$



61. f is decreasing on $(2, 8)$, and therefore $f(3) > f(5)$.

CHAPTER 3

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

63. (a)



(b) $\lim_{x\to\infty} f(x) = 3, \quad \lim_{x\to\infty} f'(x) = 0$

(c) Because $\lim_{x\to\infty} f(x) = 3$, the graph approaches that of a horizontal line, $\lim_{x\to\infty} f'(x) = 0$.

65.



The graph crosses the horizontal asymptote $y = 4$.

The graph of a function f does not cross its vertical asymptote $x = c$ because $f(c)$ does not exist.

67.



The graph has a hole at $x = 0$.

The graph crosses the horizontal asymptote $y = 0$.

The graph of a function h does not cross its vertical asymptote $x = c$ because $h(c)$ does not exist.

69.



The graph has a hole at $x = 3$. The rational function is not reduced to lowest terms.

71.



The graph appears to approach the line $y = -x + 1$, which is the slant asymptote.

73.



The graph appears to approach the line $y = 2x$, which is the slant asymptote.

75.



The graph appears to approach the line $y = x$, which is the slant asymptote.

77. (a)–(h) Proofs

79. Answers will vary. *Sample answer:* $y = \dfrac{1}{x - 3}$

81. Answers will vary.

Sample answer: $y = \dfrac{3x^2 - 7x - 5}{x - 3}$

83. False. Let $f(x) = \dfrac{2x}{\sqrt{x^2 + 2}}$, $f'(x) > 0$ for all real numbers.

85. False. For example,

$y = \dfrac{x^3 - 1}{x}$

does not have a slant asymptote.

87. (a) $(-3, 1)$ (b) $(-7, -1)$

(c) Relative maximum at $x = -3$, relative minimum at $x = 1$

(d) $x = -1$

89. Answers will vary. *Sample answer:* The graph has a vertical asymptote at $x = b$. If a and b are both positive or both negative, then the graph of f approaches ∞ as x approaches b, and the graph has a minimum at $x = -b$. If a and b have opposite signs, then the graph of f approaches $-\infty$ as x approaches b, and the graph has a maximum at $x = -b$.

91. $y = 4x$, $y = -4x$



93. (a) When n is even, f is symmetric about the y-axis. When n is odd, f is symmetric about the origin.

(b) $n = 0, 1, 2, 3$ (c) $n = 4$ (d) $y = 2x$

(e)





n	0	1	2	3	4	5
M	1	2	3	2	1	0
N	2	3	4	5	2	3

Section 3.7 *(page 224)*

1. A primary equation is a formula for the quantity to be optimized. A secondary equation can be solved for a variable and then substituted into the primary equation to obtain a function of just one variable. A feasible domain is the set of input values that makes sense in an optimization problem.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

3. (a)

First Number, x	Second Number	Product, P
10	$110 - 10$	$10(110 - 10) = 1000$
20	$110 - 20$	$20(110 - 20) = 1800$
30	$110 - 30$	$30(110 - 30) = 2400$
40	$110 - 40$	$40(110 - 40) = 2800$
50	$110 - 50$	$50(110 - 50) = 3000$
60	$110 - 60$	$60(110 - 60) = 3000$

The maximum is attained near $x = 50$ and 60.

(b) $P = x(110 - x)$ (c) 55; 55 and 55

(d)



5. $\frac{S}{2}$ and $\frac{S}{2}$ **7.** 21 and 7 **9.** 54 and 27

11. $\ell = w = 20$ m **13.** $\ell = w = 7$ ft

15. $\left(-\sqrt{\frac{5}{2}}, \frac{5}{2}\right), \left(\sqrt{\frac{5}{2}}, \frac{5}{2}\right)$ **17.** $(7/2, \sqrt{7/2})$

19. 40 in. $\times$ 20 in. **21.** 900 m $\times$ 450 m

23. Rectangular portion: $\frac{16}{\pi + 4} \times \frac{32}{\pi + 4}$ ft

25. (a) $L = \sqrt{x^2 + 4 + \frac{8}{x - 1} + \frac{4}{(x - 1)^2}}, \quad x > 1$

(b)



Minimum when $x \approx 2.587$

(c) (0, 0), (2, 0), (0, 4)

27. Width: $\frac{5\sqrt{2}}{2}$; Length: $5\sqrt{2}$

29. (a)



(b)

Length, x	Width, y	Area, xy
10	$(2/\pi)(100 - 10)$	$(10)(2/\pi)(100 - 10) \approx 573$
20	$(2/\pi)(100 - 20)$	$(20)(2/\pi)(100 - 20) \approx 1019$
30	$(2/\pi)(100 - 30)$	$(30)(2/\pi)(100 - 30) \approx 1337$
40	$(2/\pi)(100 - 40)$	$(40)(2/\pi)(100 - 40) \approx 1528$
50	$(2/\pi)(100 - 50)$	$(50)(2/\pi)(100 - 50) \approx 1592$
60	$(2/\pi)(100 - 60)$	$(60)(2/\pi)(100 - 60) \approx 1528$

The maximum area of the rectangle is approximately 1592 m^2.

(c) $A = \frac{2}{\pi}(100x - x^2), \ 0 < x < 100$

(d) $\frac{dA}{dx} = \frac{2}{\pi}(100 - 2x)$

$= 0$ when $x = 50$;

The maximum value is approximately 1592 when $x = 50$ and $y = \frac{100}{\pi}$.

(e)



31. No. The volume changes because the shape of the container changes when it is squeezed.

33. $r = \sqrt[3]{\frac{21}{2\pi}} \approx 1.50$ ($h = 0$, so the solid is a sphere.)

35. Side of square: $\frac{10\sqrt{3}}{9 + 4\sqrt{3}}$; Side of triangle: $\frac{30}{9 + 4\sqrt{3}}$

37. $w = \frac{20\sqrt{3}}{3}$ in., $h = \frac{20\sqrt{6}}{3}$ in. **39.** $6\sqrt{3}$

41.



The path of the pipe should go underwater from the oil well to the coast following the hypotenuse of a right triangle with leg lengths of 2 kilometers and $\frac{2}{\sqrt{3}}$ kilometers for a distance of $\frac{4}{\sqrt{3}}$ kilometers. Then the pipe should go down the coast to the refinery for a distance of $\left(4 - \frac{2}{\sqrt{3}}\right)$ kilometers.

43. One mile from the nearest point on the coast

45.



(a) Origin to y-intercept: 2;

Origin to x-intercept: $\frac{\pi}{2}$

(b) $d = \sqrt{x^2 + (2 - 2\sin x)^2}$

(c) Minimum distance is 0.9795 when $x \approx 0.7967$.

47. About 1.153 radians or 66°

49. $5.\overline{3}\%$ **51.** $y = \frac{64}{141}x$, $S \approx 6.1$ mi

53. $y = \frac{3}{10}x$, $S_3 \approx 4.50$ mi

55. (0, 0) **57.** Putnam Problem A1, 1986

CHAPTER 3

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Section 3.8 *(page 233)*

1. Answers will vary. *Sample answer:* If f is a function continuous on $[a, b]$ and differentiable on (a, b), where $c \in [a, b]$ and $f(c) = 0$, then Newton's Method uses tangent lines to approximate c. First, estimate an initial x_1 close to c. (See graph.) Then determine x_2 using $x_2 = x_1 - \dfrac{f(x_1)}{f'(x_1)}$. Calculate a third estimate x_3 using $x_3 = x_2 - \dfrac{f(x_2)}{f'(x_2)}$. Continue this process until $|x_n - x_{n+1}|$ is within the desired accuracy, and let x_{n+1} be the final approximation of c.



In the answers for Exercises 3 and 5, the values in the tables have been rounded for convenience. Because a calculator and a computer program calculate internally using more digits than they display, you may produce slightly different values from those shown in the tables.

3.

n	x_n	$f(x_n)$	$f'(x_n)$	$\dfrac{f(x_n)}{f'(x_n)}$	$x_n - \dfrac{f(x_n)}{f'(x_n)}$
1	2	-1	4	-0.25	2.25
2	2.25	0.0625	4.5	0.0139	2.2361

5.

n	x_n	$f(x_n)$	$f'(x_n)$	$\dfrac{f(x_n)}{f'(x_n)}$	$x_n - \dfrac{f(x_n)}{f'(x_n)}$
1	1.6	-0.0292	-0.9996	0.0292	1.5708
2	1.5708	0	-1	0	1.5708

7. -1.587 **9.** 0.682 **11.** 1.250, 5.000
13. 0.900, 1.100, 1.900 **15.** 1.935 **17.** 0.569
19. 4.493
21. (a)



(b) 1.347 (c) 2.532
(d)



If the initial estimate $x = x_1$ is not sufficiently close to the desired zero of a function, then the x-intercept of the corresponding tangent line to the function may approximate a second zero of the function.

23. $f'(x_1) = 0$ **25.** The values would be identical.
27. 0.74 **29.** Proof **31.** (1.939, 0.240)
33. $x \approx 1.563$ mi
35. (a) Proof (b) $\sqrt{5} \approx 2.236$, $\sqrt{7} \approx 2.646$ **37.** Proof
39. False; Let $f(x) = \dfrac{x^2 - 1}{x - 1}$. **41.** True **43.** 0.217

Section 3.9 *(page 240)*

1. $y = f(c) + f'(c)(x - c)$
3. Propagated error $= f(x + \Delta x) - f(x)$, relative error $= \left|\dfrac{dy}{y}\right|$, percent error $= \left|\dfrac{dy}{y}\right| \cdot 100$
5. $T(x) = 4x - 4$

x	1.9	1.99	2	2.01	2.1
$f(x)$	3.610	3.960	4	4.040	4.410
$T(x)$	3.600	3.960	4	4.040	4.400

7. $T(x) = 80x - 128$

x	1.9	1.99	2	2.01	2.1
$f(x)$	24.761	31.208	32	32.808	40.841
$T(x)$	24.000	31.200	32	32.800	40.000

9. $T(x) = (\cos 2)(x - 2) + \sin 2$

x	1.9	1.99	2	2.01	2.1
$f(x)$	0.946	0.913	0.909	0.905	0.863
$T(x)$	0.951	0.913	0.909	0.905	0.868

11. $y - f(0) = f'(0)(x - 0)$
$y - 2 = \frac{1}{4}x$
$y = 2 + \dfrac{x}{4}$



13. $\Delta y = 0.1655$, $dy = 0.15$
15. $\Delta y = -0.039$, $dy = -0.040$
17. $\Delta y \approx -0.053018$, $dy = -0.053$ **19.** $6x\,dx$
21. $(x \sec^2 x + \tan x)\,dx$ **23.** $-\dfrac{3}{(2x - 1)^2}\,dx$
25. $-\dfrac{x}{\sqrt{9 - x^2}}\,dx$ **27.** $(3 - \sin 2x)\,dx$
29. (a) 0.9 (b) 1.04 **31.** (a) 8.035 (b) 7.95
33. (a) $\pm\dfrac{5}{8}$ in.^{2} (b) 0.625%
35. (a) ± 20.25 in.^{3} (b) ± 5.4 in.^{2} (c) 0.6%, 0.4%
37. 4.7 ft, about 5.4% **39.** (a) $\frac{1}{4}$% (b) 216 sec = 3.6 min
41. 6407 ft
43. $f(x) = \sqrt{x}$, $dy = \dfrac{1}{2\sqrt{x}}\,dx$
$f(99.4) \approx \sqrt{100} + \dfrac{1}{2\sqrt{100}}(-0.6) = 9.97$
Calculator: 9.97

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

45. $f(x) = \sqrt[4]{x}$, $dy = \dfrac{1}{4x^{3/4}}\,dx$

$f(624) \approx \sqrt[4]{625} + \dfrac{1}{4(625)^{3/4}}(-1) = 4.998$

Calculator: 4.998

47. The value of dy becomes closer to the value of Δy as Δx approaches 0. Graphs will vary.

49. True **51.** True **53.** True

Review Exercises for Chapter 3 *(page 242)*

1. A critical number is a point on the graph of f where the derivative of f is zero or where f is not differentiable.

Answers will vary. Sample answer: $f(x) = \begin{cases} |x|, & x \le 1 \\ (x-2)^2, & x > 1 \end{cases}$



3. (a) *Answers will vary.*



X	Y1	Y2
0	1	1
2	1.7321	2
4	2.2361	3
6	2.6458	4
8	3	5
10	3.3166	6
12	3.6056	7

X=0

(b) Proof

5. (a) $V = x^2(108 - 4x) = 108x^2 - 4x^3$; The equation for volume is the same equation used in Exercise 4.

(b) 18 in. $\times$ 18 in. $\times$ 36 in.

7. Maximum: $(0, 0)$
Minimum: $\left(-\frac{5}{2}, -\frac{25}{4}\right)$

9. Maximum: $(4, 0)$
Minimum: $(0, -2)$

11. Maximum: $\left(3, \frac{2}{3}\right)$
Minimum: $\left(-3, -\frac{2}{3}\right)$

13. Maximum: $(2\pi, 17.57)$
Minimum: $(2.73, 0.88)$

15. $f'(1) = 0$ **17.** Not continuous on $[-2, 2]$

19. $f'\left(\dfrac{2744}{729}\right) = \dfrac{3}{7}$ **21.** f is not differentiable at $x = 5$.

23. $f'(0) = 1$

25. No; The function has a discontinuity at $x = 0$, which is in the interval $[-2, 1]$.

27. Increasing on $\left(-\frac{3}{2}, \infty\right)$; Decreasing on $\left(-\infty, -\frac{3}{2}\right)$

29. Increasing on $(-\infty, 1)$, $(2, \infty)$; Decreasing on $(1, 2)$

31. Increasing on $(1, \infty)$; Decreasing on $(0, 1)$

33. (a) Critical number: $x = 3$

(b) Increasing on $(3, \infty)$; Decreasing on $(-\infty, 3)$

(c) Relative minimum: $(3, -4)$

35. (a) Critical number: $t = 2$

(b) Increasing on $(2, \infty)$; Decreasing on $(-\infty, 2)$

(c) Relative minimum: $(2, -12)$

37. (a) Critical number: $x = -8$; Discontinuity: $x = 0$

(b) Increasing on $(-8, 0)$;
Decreasing on $(-\infty, -8)$ and $(0, \infty)$

(c) Relative minimum: $\left(-8, -\frac{1}{16}\right)$

39. (a) Critical numbers: $x = \dfrac{3\pi}{4}, \dfrac{7\pi}{4}$

(b) Increasing on $\left(\dfrac{3\pi}{4}, \dfrac{7\pi}{4}\right)$;

Decreasing on $\left(0, \dfrac{3\pi}{4}\right)$ and $\left(\dfrac{7\pi}{4}, 2\pi\right)$

(c) Relative minimum: $\left(\dfrac{3\pi}{4}, -\sqrt{2}\right)$;

Relative maximum: $\left(\dfrac{7\pi}{4}, \sqrt{2}\right)$

41. (a) $v(t) = 3 - 4t$ (b) $\left[0, \frac{3}{4}\right)$ (c) $\left(\frac{3}{4}, \infty\right)$ (d) $t = \frac{3}{4}$

43. Point of inflection: $(3, -54)$; Concave upward: $(3, \infty)$; Concave downward: $(-\infty, 3)$

45. Points of inflection: None; Concave upward: $(-5, \infty)$

47. Points of inflection: $\left(\dfrac{\pi}{2}, \dfrac{\pi}{2}\right), \left(\dfrac{3\pi}{2}, \dfrac{3\pi}{2}\right)$;

Concave upward: $\left(\dfrac{\pi}{2}, \dfrac{3\pi}{2}\right)$;

Concave downward: $\left(0, \dfrac{\pi}{2}\right), \left(\dfrac{3\pi}{2}, 2\pi\right)$

49. Relative minimum: $(-9, 0)$

51. Relative maxima: $\left(\dfrac{\sqrt{2}}{2}, \dfrac{1}{2}\right), \left(-\dfrac{\sqrt{2}}{2}, \dfrac{1}{2}\right)$;

Relative minimum: $(0, 0)$

53. Relative maximum: $(-3, -12)$; Relative minimum: $(3, 12)$

55.



57. Increasing and concave downward

59. (a)

$D = -0.05041t^4 + 3.5255t^3 - 83.134t^2 + 783.95t - 1810.9$

(b)



(c) 2011; 2015 (d) 2019

61. 8 **63.** $-\frac{1}{8}$ **65.** $-\infty$ **67.** 0 **69.** 6

71.



73.



CHAPTER 3

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

75.



77.



79.



81.



83.



85. 54, 36 **87.** $x = 50$ ft and $y = \frac{200}{3}$ ft

89. (0, 0), (5, 0), (0, 10) **91.** 14.05 ft **93.** $\frac{32\pi r^3}{81}$

95. $-1.532, -0.347, 1.879$ **97.** $-2.182, -0.795$

99. -0.755 **101.** $\Delta y = 5.044$, $dy = 4.8$

103. $dy = (1 - \cos x + x \sin x)\,dx$

105. (a) $f(x) = \sqrt{x}$, $dy = \dfrac{1}{2\sqrt{x}}dx$

$f(63.9) \approx \sqrt{64} + \dfrac{1}{2\sqrt{64}}(-0.1) = 7.99375$

Calculator: 7.99375

(b) $f(x) = x^4$, $dy = 4x^3\,dx$

$f(2.02) \approx 2^4 + 4(2^3)(0.02) = 16.64$

Calculator: 16.64966

107. Equation of line: $\dfrac{x}{3} + \dfrac{y}{4} = 1$ or $y = -\dfrac{4}{3}x + 4$.

Rectangle dimensions: $\dfrac{3}{2} \times 2$

Circle dimensions: $r = 1$

Semicircle dimensions: $r = \dfrac{12}{7}$

109. $a = 6$, $b = 1$, $c = 2$

P.S. Problem Solving *(page 246)*

1. Choices of a may vary.



(a) One relative minimum at $(0, 1)$ for $a \geq 0$

(b) One relative maximum at $(0, 1)$ for $a < 0$

(c) Two relative minima for $a < 0$ when $x = \pm\sqrt{-\dfrac{a}{2}}$

(d) If $a < 0$, then there are three critical points. If $a \geq 0$, then there is only one critical point.

3. (a) No point of inflection (b) One point of inflection

(c) $y' = ky - \dfrac{k}{L}y^2$

$y'' = ky'\left(1 - \dfrac{2}{L}y\right)$

If $y = \dfrac{L}{2}$, then $y'' = 0$, and this is a point of inflection.

5. Proof

7. The bug should head toward the midpoint of the opposite side. Without calculus, imagine opening up the cube. The shortest distance is the line PQ, passing through the midpoint as shown.



9. Proof

Chapter 4

Section 4.1 *(page 255)*

1. A function F is an antiderivative of f on an interval I when $F'(x) = f(x)$ for all x in I.

3. The particular solution results from knowing the value of $y = F(x)$ for one value of x. Using the initial condition in the general solution, you can solve for C to obtain the particular solution.

5. Proof **7.** $y = 3t^3 + C$ **9.** $y = \frac{2}{5}x^{5/2} + C$

	Original Integral	Rewrite	Integrate	Simplify
11.	$\int \sqrt[3]{x}\,dx$	$\int x^{1/3}\,dx$	$\dfrac{x^{4/3}}{4/3} + C$	$\dfrac{3}{4}x^{4/3} + C$
13.	$\int \dfrac{1}{x\sqrt{x}}dx$	$\int x^{-3/2}\,dx$	$\dfrac{x^{-1/2}}{-1/2} + C$	$-\dfrac{2}{\sqrt{x}} + C$

15. $\frac{1}{2}x^2 + 7x + C$ **17.** $\frac{1}{6}x^6 + x + C$

19. $\frac{2}{5}x^{5/2} + x^2 + x + C$ **21.** $\frac{3}{5}x^{5/3} + C$

23. $-\dfrac{1}{4x^4} + C$ **25.** $\dfrac{2}{3}x^{3/2} + 12x^{1/2} + C$

27. $x^3 + \frac{1}{2}x^2 - 2x + C$ **29.** $5 \sin x - 4 \cos x + C$

31. $-\csc x - x^2 + C$ **33.** $\tan\theta + \cos\theta + C$

35. $\tan y + C$ **37.** $f(x) = 3x^2 + 8$

39. $h(x) = x^7 + 5x - 7$ **41.** $f(x) = x^2 + x + 4$

43. $f(x) = -4\sqrt{x} + 3x$

45. (a) Answers will vary. (b) $y = \dfrac{x^3}{3} - x + \dfrac{7}{3}$

Sample answer:





Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

47. (a) 

(b) $y = x^2 - 6$

(c) 

49. Answers will vary. *Sample answer:*



51. $f(x) = \tan^2 x \implies f'(x) = 2 \tan x \cdot \sec^2 x$
$g(x) = \sec^2 x \implies g'(x) = 2 \sec x \cdot \sec x \tan x = f'(x)$
The derivatives are the same, so f and g differ by a constant.

53. $f(x) = \dfrac{x^3}{3} - 4x + \dfrac{16}{3}$

55. (a) $h(t) = \frac{3}{4}t^2 + 5t + 12$ (b) 69 cm **57.** 62.25 ft

59. (a) $t \approx 2.562$ sec (b) $v(t) \approx -65.970$ ft/sec

61. $v_0 \approx 62.3$ m/sec **63.** 320 m; -32 m/sec

65. (a) $v(t) = 3t^2 - 12t + 9$, $a(t) = 6t - 12$
(b) (0, 1), (3, 5) (c) -3

67. $a(t) = -\dfrac{1}{2t^{3/2}}$, $x(t) = 2\sqrt{t} + 2$

69. (a) 1.18 m/sec^2 (b) 190 m

71. (a) 300 ft (b) 60 ft/sec $\approx$ 41 mi/h

73. False. f has an infinite number of antiderivatives, each differing by a constant.

75. True **77.** True **79.** Proof

81. Putnam Problem B2, 1991

Section 4.2 *(page 267)*

1. The index of summation is i, the upper bound of summation is 8, and the lower bound of summation is 3.

3. You can use the line $y = x$ bounded by $x = a$ and $x = b$. The sum of the areas of the inscribed rectangles in the figure below is the lower sum.



The sum of the areas of the circumscribed rectangles in the figure below is the upper sum.



The rectangles in the first graph do not contain all of the area of the region, and the rectangles in the second graph cover more than the area of the region. The exact value of the area lies between these two sums.

5. 75 **7.** $\dfrac{158}{85}$ **9.** $8c$ **11.** $\displaystyle\sum_{i=1}^{11} \frac{1}{5i}$

13. $\displaystyle\sum_{j=1}^{6} \left[7\left(\frac{j}{6}\right) + 5\right]$ **15.** $\displaystyle\frac{2}{n}\sum_{i=1}^{n} \left[\left(\frac{2i}{n}\right)^3 - \left(\frac{2i}{n}\right)\right]$ **17.** 84

19. 1200 **21.** 2470 **23.** 1876

25. $\dfrac{n+2}{n}$
$n = 10$: $S = 1.2$
$n = 100$: $S = 1.02$
$n = 1000$: $S = 1.002$
$n = 10{,}000$: $S = 1.0002$

27. $\dfrac{2(n+1)(n-1)}{n^2}$
$n = 10$: $S = 1.98$
$n = 100$: $S = 1.9998$
$n = 1000$: $S = 1.999998$
$n = 10{,}000$: $S = 1.99999998$

29. $13 <$ (Area of region) < 15

31. $55 <$ (Area of region) < 74.5

33. $0.7908 <$ (Area of region) < 1.1835

35. The area of the shaded region falls between 12.5 square units and 16.5 square units.

37. $A \approx S \approx 0.768$
$A \approx s \approx 0.518$

39. $A \approx S \approx 0.746$
$A \approx s \approx 0.646$

41. $s(n) = 24 - \dfrac{24}{n}$, $S(n) = 24 + \dfrac{24}{n}$

43. $s(n) = \dfrac{5(2n^2 - 3n + 1)}{6n^2}$, $S(n) = \dfrac{5(2n^2 + 3n + 1)}{6n^2}$

45. (a) 

(b) $\Delta x = \dfrac{2-0}{n} = \dfrac{2}{n}$

(c) $s(n) = \displaystyle\sum_{i=1}^{n} f(x_{i-1})\,\Delta x = \sum_{i=1}^{n} \left[(i-1)\left(\frac{2}{n}\right)\right]\left(\frac{2}{n}\right)$

(d) $S(n) = \displaystyle\sum_{i=1}^{n} f(x_i)\,\Delta x = \sum_{i=1}^{n} \left[i\left(\frac{2}{n}\right)\right]\left(\frac{2}{n}\right)$

(e)

n	5	10	50	100
$s(n)$	1.6	1.8	1.96	1.98
$S(n)$	2.4	2.2	2.04	2.02

(f) $\displaystyle\lim_{n\to\infty} \sum_{i=1}^{n} \left[(i-1)\left(\frac{2}{n}\right)\right]\left(\frac{2}{n}\right) = 2$

$\displaystyle\lim_{n\to\infty} \sum_{i=1}^{n} \left[i\left(\frac{2}{n}\right)\right]\left(\frac{2}{n}\right) = 2$

47. $A = 3$



49. $A = \frac{7}{3}$



CHAPTER 4

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

51. $A = 54$



53. $A = 34$



55. $A = \frac{2}{3}$



57. $A = 8$



59. $A = \frac{125}{3}$



61. $A = \frac{44}{3}$



63. $\frac{69}{8}$ **65.** 0.345 **67.** b

69. An overestimate on one side of the midpoint compensates for an underestimate on the other side of the midpoint.

71. (a)



$s(4) = \frac{46}{3}$

(b)



$S(4) = \frac{326}{15}$

(c)



$M(4) = \frac{6112}{315}$

(d) Proof

(e)

n	4	8	20	100	200
$s(n)$	15.333	17.368	18.459	18.995	19.060
$S(n)$	21.733	20.568	19.739	19.251	19.188
$M(n)$	19.403	19.201	19.137	19.125	19.125

(f) Because f is an increasing function, $s(n)$ is always increasing and $S(n)$ is always decreasing.

73. True

75. Suppose there are n rows and $n + 1$ columns. The stars on the left total $1 + 2 + \cdots + n$, as do the stars on the right. There are $n(n + 1)$ stars in total. So, $2[1 + 2 + \cdots + n] = n(n + 1)$ and $1 + 2 + \cdots + n = \dfrac{n(n + 1)}{2}$.

77. When n is odd, there are $\left(\dfrac{n + 1}{2}\right)^2$ seats. When n is even, there are $\dfrac{n^2 + 2n}{4}$ seats.

79. Putnam Problem B1, 1989

Section 4.3 *(page 277)*

1. A Riemann sum represents the addition of all of the subregions for a function f on an interval $[a, b]$.

3. $2\sqrt{3} \approx 3.464$ **5.** 32 **7.** 0 **9.** $\frac{10}{3}$

11. $\displaystyle\int_{-1}^{5} (3x + 10)\,dx$ **13.** $\displaystyle\int_{0}^{4} 5\,dx$ **15.** $\displaystyle\int_{-4}^{4} \big(4 - |x|\big)\,dx$

17. $\displaystyle\int_{-5}^{5} (25 - x^2)\,dx$ **19.** $\displaystyle\int_{0}^{\pi/2} \cos x\,dx$ **21.** $\displaystyle\int_{0}^{2} y^3\,dy$

23.



$A = 12$

25.



$A = 8$

27.



$A = 14$

29.



$A = 1$

31.



$A = \dfrac{49\pi}{2}$

33. -320 **35.** 80 **37.** -40 **39.** 508

41. (a) 13 (b) -10 (c) 0 (d) 30

43. (a) 8 (b) -12 (c) -4 (d) 30 **45.** $-48, 88$

47. (a) $-\pi$ (b) 4 (c) $-(1 + 2\pi)$ (d) $3 - 2\pi$ (e) $5 + 2\pi$ (f) $23 - 2\pi$

49. (a) 14 (b) 4 (c) 8 (d) 0 **51.** 40 **53.** a

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

55. Answers will vary. *Sample answer:*



There is no region.

57. Geometric method:

$$\int_{-1}^{3} (x + 2)\,dx = \text{Area of large triangle} - \text{Area of small triangle}$$

$$= \frac{25}{2} - \frac{1}{2} = 12$$

Limit definition:

$$\int_{-1}^{3} (x + 2)\,dx = \lim_{n\to\infty} \sum_{i=1}^{n} \left[\left(-1 + \frac{4i}{n} + 2\right)\left(\frac{4}{n}\right)\right] = 12$$

59. $a = -2, b = 5$

61. Answers will vary. *Sample answer:* $a = \pi, b = 2\pi$

$$\int_{\pi}^{2\pi} \sin x\,dx < 0$$



63. True **65.** True **67.** False. $\int_0^2 (-x)\,dx = -2$

69. 272 **71.** Proof

73. No. No matter how small the subintervals, the number of both rational and irrational numbers within each subinterval is infinite, and $f(c_i) = 0$ or $f(c_i) = 1$.

75. $a = -1$ and $b = 1$ maximize the integral.

77. Answers will vary. *Sample answer:*



The integrals are equal when f is always greater than or equal to 0 on $[a, b]$.

79. $\frac{1}{3}$

Section 4.4 *(page 292)*

1. Find an antiderivative of the function and evaluate the difference of the antiderivative at the upper limit of integration and the lower limit of integration.

3. The average value of a function on an interval is the integral of the function on $[a, b]$ times $\dfrac{1}{b - a}$.

5.



Positive

7.



Zero

9. -2 **11.** $-\frac{28}{3}$ **13.** $\frac{1}{3}$ **15.** $\frac{1}{2}$ **17.** $\frac{2}{3}$

19. -4 **21.** $-\frac{1}{18}$ **23.** $-\frac{27}{20}$ **25.** $\frac{25}{2}$ **27.** $\frac{64}{3}$

29. $2 - 7\pi$ **31.** $\dfrac{\pi}{4}$ **33.** $\dfrac{2\sqrt{3}}{3}$ **35.** 0 **37.** $\dfrac{1}{6}$

39. 1 **41.** $\dfrac{52}{3}$ **43.** 20 **45.** $\dfrac{32}{3}$ **47.** $\dfrac{3\sqrt[3]{2}}{2} \approx 1.8899$

49. $2\sqrt{3} \approx 3.4641$ **51.** $\pm\arccos\dfrac{\sqrt{\pi}}{2} \approx \pm 0.4817$

53. Average value $= \frac{8}{3}$

$x = \pm\dfrac{2\sqrt{3}}{3}$

55. Average value $= 10.2$

$x \approx 1.3375$

57. Average value $= \dfrac{2}{\pi}$

$x \approx 0.690, x \approx 2.451$

59. (a) $F(x) = 500 \sec^2 x$ **61.** $\dfrac{2}{\pi} \approx 63.7\%$

(b) $\dfrac{1500\sqrt{3}}{\pi} \approx 827$ N

63. $F(x) = -\dfrac{20}{x} + 20$

$F(2) = 10$

$F(5) = 16$

$F(8) = \dfrac{35}{2}$

65. $F(x) = \sin x$

$F(0) = 0$

$F\left(\dfrac{\pi}{4}\right) = \dfrac{\sqrt{2}}{2}$

$F\left(\dfrac{\pi}{2}\right) = 1$

67. (a) $g(0) = 0, g(2) \approx 7, g(4) \approx 9, g(6) \approx 8, g(8) \approx 5$

(b) Increasing: $(0, 4)$; Decreasing: $(4, 8)$

(c) A maximum occurs at $x = 4$.

(d)



69. $\frac{1}{2}x^2 + 2x$ **71.** $\frac{3}{4}x^{4/3} - 12$ **73.** $\tan x - 1$

75. $x^2 - 2x$ **77.** $\sqrt{x^4 + 1}$ **79.** $\sqrt{x}\csc x$ **81.** 8

83. $\cos x\sqrt{\sin x}$ **85.** $3x^2 \sin x^6$

87.



An extremum of g occurs at $x = 2$.

89. 8190 L

91. About 540 ft **93.** (a) $\frac{3}{2}$ ft to the right (b) $\frac{113}{10}$ ft

95. (a) 0 ft (b) $\frac{63}{2}$ ft **97.** (a) 2 ft to the right (b) 2 ft

CHAPTER 4

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

99. (a)



The area above the x-axis equals the area below the x-axis. So, the average value is zero.

(b)



So, the average value of S appears to be g.

101. The displacement and total distance traveled are equal when the particle is always moving in the same direction on an interval.

103. The Fundamental Theorem of Calculus requires that f be continuous on $[a, b]$ and that F be an antiderivative for f on the entire interval. On an interval containing c, the function $f(x) = \dfrac{1}{x - c}$ is not continuous at c.

105. 28 units

107. $f(x) = x^{-2}$ has a nonremovable discontinuity at $x = 0$.

109. $f(x) = \sec^2 x$ has a nonremovable discontinuity at $x = \dfrac{\pi}{2}$.

111. True

113. $\dfrac{x|x|}{2} + C$

115. $f(x) = 2x + 1$, and $c = 1$ or $c = -2$

117. (a) 0 (b) 0 (c) $xf(x) + \int_0^x f(t)\,dt$ (d) 0

119. Putnam Problem B5, 2006

Section 4.5 *(page 305)*

1. You can move constant multiples outside the integral sign.
$\displaystyle\int kf(x)\,dx = k\int f(x)\,dx$

3. The integral of $[g(x)]^n g'(x)$ is $\dfrac{[g(x)]^{n+1}}{n+1} + C$, $n \neq -1$.

Recall the Power Rule for Polynomials.

$\int f(g(x))g'(x)\,dx$	$u = g(x)$	$du = g'(x)\,dx$
5. $\int (5x^2 + 1)^2(10x)\,dx$	$5x^2 + 1$	$10x\,dx$
7. $\int \tan^2 x \sec^2 x\,dx$	$\tan x$	$\sec^2 x\,dx$

9. $\frac{1}{5}(1 + 6x)^5 + C$ **11.** $\frac{2}{3}(25 - x^2)^{3/2} + C$

13. $\frac{1}{12}(x^4 + 3)^3 + C$ **15.** $\frac{1}{30}(2x^3 - 1)^5 + C$

17. $\frac{1}{3}(t^2 + 2)^{3/2} + C$ **19.** $-\frac{15}{8}(1 - x^2)^{4/3} + C$

21. $\dfrac{7}{4(1 - x^2)^2} + C$ **23.** $-\dfrac{1}{3(1 + x^3)} + C$

25. $-\sqrt{1 - x^2} + C$ **27.** $-\dfrac{1}{4}\left(1 + \dfrac{1}{t}\right)^4 + C$

29. $\sqrt{2x} + C$ **31.** $2x^2 - 4\sqrt{16 - x^2} + C$

33. $-\dfrac{1}{2(x^2 + 2x - 3)} + C$

35. (a) Answers will vary. *Sample answer:*



(b) $y = -\frac{1}{3}(4 - x^2)^{3/2} + 2$



37. $f(x) = (2x^3 + 1)^3 + 3$ **39.** $-\cos \pi x + C$

41. $\dfrac{1}{6}\sin 6x + C$ **43.** $-\sin\dfrac{1}{\theta} + C$

45. $\frac{1}{4}\sin^2 2x + C$ or $-\frac{1}{4}\cos^2 2x + C_1$ or $-\frac{1}{8}\cos 4x + C_2$

47. $\dfrac{1}{2}\tan^2 x + C$ or $\dfrac{1}{2}\sec^2 x + C_1$ **49.** $f(x) = 2\cos\dfrac{x}{2} + 4$

51. $f(x) = \frac{1}{12}(4x^2 - 10)^3 - 8$

53. $\frac{2}{5}(x + 6)^{5/2} - 4(x + 6)^{3/2} + C = \frac{2}{5}(x + 6)^{3/2}(x - 4) + C$

55. $-\left[\frac{2}{3}(1 - x)^{3/2} - \frac{4}{5}(1 - x)^{5/2} + \frac{2}{7}(1 - x)^{7/2}\right] + C =$
$-\frac{2}{105}(1 - x)^{3/2}(15x^2 + 12x + 8) + C$

57. $\frac{1}{8}\left[\frac{2}{5}(2x - 1)^{5/2} + \frac{4}{3}(2x - 1)^{3/2} - 6(2x - 1)^{1/2}\right] + C =$
$\dfrac{\sqrt{2x - 1}}{15}(3x^2 + 2x - 13) + C$

59. $-\frac{1}{8}\cos^4 2x + C$ **61.** 0 **63.** $12 - \frac{8}{9}\sqrt{2}$ **65.** 2

67. $\dfrac{1}{2}$ **69.** $\dfrac{28\pi}{15}$ **71.** $\dfrac{1209}{28}$ **73.** $2\left(\sqrt{3} - 1\right)$ **75.** $\dfrac{272}{15}$

77. 0 **79.** (a) 144 (b) 72 (c) -144 (d) 432

81. $2\displaystyle\int_0^3 (4x^2 - 6)\,dx = 36$

83. (a) $\displaystyle\int x^2\sqrt{x^3 + 1}\,dx$; Use substitution with $u = x^3 + 1$.

(b) $\displaystyle\int \cot^3(2x)\csc^2(2x)\,dx$; Use substitution with $u = \cot 2x$.

85. \$340,000

87. (a) 102.532 thousand units (b) 102.352 thousand units
(c) 74.5 thousand units

89. (a)



(b) g is nonnegative, because the graph of f is positive at the beginning and generally has more positive sections than negative ones.

(c) The points on g that correspond to the extrema of f are points of inflection of g.

(d) No, some zeros of f, such as $x = \dfrac{\pi}{2}$, do not correspond to extrema of g. The graph of g continues to increase after $x = \dfrac{\pi}{2}$, because f remains above the x-axis.

(e)



The graph of h is that of g shifted 2 units downward.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

91. (a) and (b) Proofs

93. True **95.** True **97.** True **99–101.** Proofs

103. Putnam Problem A1, 1958

Review Exercises for Chapter 4 *(page 309)*

1. (a) The derivative of g is negative the derivative of f.

(b) The behaviors of the graphs of the functions f and $-g$ differ by a constant C. Hence, $f(x) - (-g(x)) = \sin^2(x) + \cos^2(x) = C$.
By the Pythagorean Identity, $C = 1$.

3. c

5. (a) $v'(t)$ represents the acceleration of the particle at time t.

(b) $\int_a^c v(t)\,dt$ represents the displacement of the particle from time $t = a$ to $t = c$.

(c) $\int_a^c |v(t)|\,dt$ represents the total distance traveled by the particle from time $t = a$ to $t = c$.

(d) $\dfrac{d}{dx}\left[\int_a^x v(t)\,dt\right] = v(x)$ represents the velocity of the particle at time x.

(e) $A - B$ represents the displacement of the particle from time $t = a$ to $t = c$.

(f) $\int_a^b v(t)\,dt + \int_b^c v(t)\,dt$ represents the displacement of the particle from time $t = a$ to $t = c$.

7. $\dfrac{x^4}{4} + 4x + C$ **9.** $9x^{2/3} + C$ **11.** $f(x) = 1 - 3x^2$

13. (a) 3 sec; 144 ft (b) $\frac{3}{2}$ sec (c) 108 ft

15. 60 **17.** $\displaystyle\sum_{i=1}^{10} \frac{i}{5(i+2)}$ **19.** 192 **21.** 420

23. 3310 **25.** $9.038 < (\text{Area of region}) < 13.038$

27. $s(n) = 11 - \dfrac{2}{n}$, $S(n) = 11 + \dfrac{2}{n}$

29. $A = 15$



31. $A = 12$



33. 43 **35.** 48

37.



$A = \frac{25}{2}$

39. (a) 17 (b) 7 (c) 9 (d) 84

41. 12 **43.** $\dfrac{422}{5}$ **45.** $\dfrac{\sqrt{2}+2}{2}$ **47.** 1 **49.** 30

51. $\frac{1}{4}$ **53.** $\sqrt{\frac{13}{3}}$

55. Average value $= \frac{2}{5}$
$x = \frac{25}{4}$

57. $x^2\sqrt{1+x^3}$ **59.** $-\frac{1}{30}(1-3x^2)^5 + C = \frac{1}{30}(3x^2-1)^5 + C$

61. $\frac{1}{4}\sin^4 x + C$ **63.** $-2\sqrt{1-\sin\theta} + C$

65. $\frac{2}{5}(8-x)^{5/2} - \frac{16}{3}(8-x)^{3/2} + C$

67. $\dfrac{455}{2}$ **69.** 2 **71.** $\dfrac{468}{7}$ **73.** 0

75. (a)

x	0	$\pi/6$	$\pi/3$	$\pi/2$	$2\pi/3$
$F(x)$	0	0.04529	0.30709	0.78540	1.26370

x	$5\pi/6$	π
$F(x)$	1.52550	1.570780

The values are increasing.

(b)



(c)



The graph of $F'(x)$ is the same as graph y_1 in part (b).

(d) $y' = \dfrac{1}{2} - \dfrac{1}{2}\cos(2t) = \dfrac{(1-\cos(2t))}{2} = \sin^2(t)$



P.S. Problem Solving *(page 312)*

1. (a) $\displaystyle\lim_{n\to\infty}\left[\frac{32}{n^5}\sum_{i=1}^{n} i^4 - \frac{64}{n^4}\sum_{i=1}^{n} i^3 + \frac{32}{n^3}\sum_{i=1}^{n} i^2\right]$

(b) $\dfrac{16n^4 - 16}{15n^4}$ (c) $\dfrac{16}{15}$

3. (a)



CHAPTER 4

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

(b)



(c) Relative maxima at $x = \sqrt{2}, \sqrt{6}$
Relative minima at $x = 2, 2\sqrt{2}$

(d) Points of inflection at $x = 1, \sqrt{3}, \sqrt{5}, \sqrt{7}$

5–7. Proofs **9.** $\frac{2}{3}$ **11.** $a = -4$ and $b = 4$

Chapter 5

Section 5.1 *(page 321)*

1. For $x > 1$, $\ln x = \int_1^x \frac{1}{t}\,dt > 0$. For $0 < x < 1$,
$\ln x = \int_1^x \frac{1}{t}\,dt = -\int_x^1 \frac{1}{t}\,dt$.

3. The number e is the base for the natural logarithm:
$\ln e = \int_1^e \frac{1}{t}\,dt = 1$.

5. b **6.** d **7.** a **8.** c

9.



Domain: $x > 0$

11.



Domain: $x > 0$

13.



Domain: $x > 3$

15. (a) 1.7917 (b) −0.4055 (c) 4.3944 (d) 0.5493

17. $\ln x - \ln 4$ **19.** $\ln x + \ln y - \ln z$

21. $\ln x + \frac{1}{2}\ln(x^2 + 5)$ **23.** $\frac{1}{2}[\ln(x - 1) - \ln x]$

25. $\ln z + 2\ln(z - 1)$ **27.** $\ln \dfrac{x - 2}{x + 2}$

29. $\ln \sqrt[3]{\dfrac{x(x + 3)^2}{x^2 - 1}}$ **31.** $\ln \dfrac{16}{\sqrt{x^3 + 6x}}$

33. (a)



(b) $f(x) = \ln \dfrac{x^2}{4} = \ln x^2 - \ln 4$
$= 2\ln x - \ln 4$
$= g(x)$

35. $-\infty$ **37.** $\ln 4 \approx 1.3863$ **39.** $\dfrac{1}{x}$ **41.** $\dfrac{2x}{x^2 + 3}$

43. $\dfrac{4(\ln x)^3}{x}$ **45.** $\dfrac{2}{t + 1}$ **47.** $\dfrac{2x^2 - 1}{x(x^2 - 1)}$

49. $\dfrac{1 - x^2}{x(x^2 + 1)}$ **51.** $\dfrac{1 - 2\ln t}{t^3}$ **53.** $\dfrac{2}{x \ln x^2} = \dfrac{1}{x \ln x}$

55. $\dfrac{1}{1 - x^2}$ **57.** $\dfrac{-4}{x(x^2 + 4)}$ **59.** $\cot x$

61. $-\tan x + \dfrac{\sin x}{\cos x - 1}$

63. (a) $y = 4x - 4$

(b)



65. (a) $5x - y - 2 = 0$

(b)



67. (a) $y = \frac{1}{3}x - \frac{1}{12}\pi + \frac{1}{2}\ln\frac{3}{2}$

(b)



69. (a) $y = 4x + 4$

(b)



71. $\dfrac{2x^2 + 1}{\sqrt{x^2 + 1}}$ **73.** $\dfrac{3x^3 + 15x^2 - 8x}{2(x + 1)^3\sqrt{3x - 2}}$

75. $\dfrac{(2x^2 + 2x - 1)\sqrt{x - 1}}{(x + 1)^{3/2}}$ **77.** $\dfrac{2xy}{3 - 2y^2}$

79. $\dfrac{y(1 - 6x^2)}{1 + y}$ **81.** $xy'' + y' = x\left(-\dfrac{2}{x^2}\right) + \dfrac{2}{x} = 0$

83. Relative minimum: $\left(1, \frac{1}{2}\right)$

85. Relative minimum: $(e^{-1}, -e^{-1})$

87. Relative minimum: (e, e); Point of inflection: $\left(e^2, \dfrac{e^2}{2}\right)$

89. $x \approx 0.567$

91. Yes. If the graph of g is increasing, then $g'(x) > 0$. Because $f(x) > 0$, you know that $f'(x) = g'(x)f(x)$ and thus $f'(x) > 0$. Therefore, the graph of f is increasing.

93. No. For example,
$(\ln 2)(\ln 3) \approx 0.76 \neq 1.79 \approx \ln(2 \cdot 3) = \ln 6$.

95. True. **97.** False. π is a constant, so $\dfrac{d}{dx}[\ln \pi] = 0$.

99. $x = 2, x = 4$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

101. (a) 

(b) 30 yr; \$503,434.80
(c) 20 yr; \$386,685.60

(d) When $x = 1398.43$, $\frac{dt}{dx} \approx -0.0805$. When $x = 1611.19$, $\frac{dt}{dx} \approx -0.0287$.

(e) Two benefits of a higher monthly payment are a shorter term and a lower total amount paid.

103. (a) 

(c) 

(b) $T'(10) \approx 4.75°/\text{lb/in.}^2$
$T'(70) \approx 0.97°/\text{lb/in.}^2$

$\lim_{p\to\infty} T'(p) = 0$
Answers will vary.

105. (a) 

(b) When $x = 5$, $\frac{dy}{dx} = -\sqrt{3}$.
When $x = 9$, $\frac{dy}{dx} = -\frac{\sqrt{19}}{9}$.

(c) $\lim_{x\to 10^-} \frac{dy}{dx} = 0$

107. (a) 

For $x > 4$, $g'(x) > f'(x)$. g is increasing at a faster rate than f for large values of x.

(b) 

For $x > 256$, $g'(x) > f'(x)$. g is increasing at a faster rate than f for large values of x.

$f(x) = \ln x$ increases very slowly for large values of x.

Section 5.2 *(page 330)*

1. No. To use the Log Rule, look for quotients in which the numerator is the derivative of the denominator, with rewriting in mind.

3. Ways to alter an integrand are to rewrite using a trigonometric identity, multiply and divide by the same quantity, add and subtract the same quantity, or use long division.

5. $5\ln|x| + C$ **7.** $\frac{1}{2}\ln|2x + 5| + C$

9. $\frac{1}{2}\ln|x^2 - 3| + C$ **11.** $\ln|x^4 + 3x| + C$

13. $\frac{x^2}{14} - \ln|x| + C$ **15.** $\frac{1}{3}\ln|x^3 + 3x^2 + 9x| + C$

17. $\frac{1}{2}x^2 - 4x + 6\ln|x + 1| + C$

19. $\frac{1}{3}x^3 + 5\ln|x - 3| + C$

21. $\frac{1}{3}x^3 - 2x + \ln\sqrt{x^2 + 2} + C$ **23.** $\frac{1}{3}(\ln x)^3 + C$

25. $-\frac{2}{3}\ln\left|1 - 3\sqrt{x}\right| + C$ **27.** $6\ln|x - 5| - \frac{30}{x - 5} + C$

29. $\sqrt{2x} - \ln\left|1 + \sqrt{2x}\right| + C$

31. $x + 6\sqrt{x} + 18\ln\left|\sqrt{x} - 3\right| + C$ **33.** $3\ln\left|\sin\frac{\theta}{3}\right| + C$

35. $-\frac{1}{2}\ln|\csc 2x + \cot 2x| + C$ **37.** $5\theta - \frac{1}{3}\sin 3\theta + C$

39. $\ln|1 + \sin t| + C$ **41.** $\ln|\sec x - 1| + C$

43. $y = -3\ln|2 - x| + C$ **45.** $y = \ln|x^2 - 9| + C$





47. $f(x) = -2\ln x + 3x - 2$

49. (a) 

(b) $y = \ln\left(\frac{x + 2}{2}\right) + 1$



51. $\frac{5}{3}\ln 13 \approx 4.275$ **53.** $\frac{7}{3}$ **55.** $-\ln 3 \approx 1.099$

57. $\ln\left|\frac{2 - \sin 2}{1 - \sin 1}\right| \approx 1.929$

59. $4\sqrt{x} - x - 4\ln\left(1 + \sqrt{x}\right) + C$ **61.** $\frac{1}{x}$

63. $4\cot 4x$ **65.** $6\ln 3 \approx 6.592$

67. $\ln|\csc 1 + \cot 1| - \ln|\csc 2 + \cot 2| \approx 1.048$

69. $\frac{15}{2} + 8\ln 2 \approx 13.045$ **71.** $\frac{12}{\pi}\ln\left(2 + \sqrt{3}\right) \approx 5.03$

73. 1 **75.** $\frac{1}{e - 1} \approx 0.582$ **77.** About 13.077

79. d **81.** Proof **83.** $x = 2$ **85.** Proof

87. $-\ln|\cos x| + C = \ln\left|\frac{1}{\cos x}\right| + C = \ln|\sec x| + C$

89. $\ln|\sec x + \tan x| + C = \ln\left|\frac{\sec^2 x - \tan^2 x}{\sec x - \tan x}\right| + C$
$= -\ln|\sec x - \tan x| + C$

91. (a) $P(t) = 1000(12\ln|1 + 0.25t| + 1)$ (b) $P(3) \approx 7715$

93. About 4.15 min

95. 

(a) $A = \frac{1}{2}\ln 2 - \frac{1}{4}$
(b) $0 < m < 1$
(c) $A = \frac{1}{2}(m - \ln m - 1)$

97. True **99.** True **101.** Putnam Problem B2, 2014

Section 5.3 *(page 339)*

1. The functions f and g have the effect of "undoing" each other.

3. No. The domain of f^{-1} is the range of f.

CHAPTER 5

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

5. (a) $f(g(x)) = 5\left(\dfrac{x-1}{5}\right) + 1 = x$

$g(f(x)) = \dfrac{(5x+1)-1}{5} = x$

(b)



7. (a) $f(g(x)) = \left(\sqrt[3]{x}\right)^3 = x$

$g(f(x)) = \sqrt[3]{x^3} = x$

(b)



9. (a) $f(g(x)) = \sqrt{x^2+4-4} = x$

$g(f(x)) = \left(\sqrt{x-4}\right)^2 + 4 = x$

(b)



11. (a) $f(g(x)) = \dfrac{1}{1/x} = x$

$g(f(x)) = \dfrac{1}{1/x} = x$

(b)



13.



One-to-one, inverse exists

15.



Not one-to-one, inverse does not exist

17.



One-to-one, inverse exists

19.



One-to-one, inverse exists

21.



One-to-one, inverse exists

23. Strictly monotonic, inverse exists

25. Not strictly monotonic, inverse does not exist

27. Strictly monotonic, inverse exists

29. c **30.** b **31.** a **32.** d

33. $f'(x) = 2(x-4) > 0$ on $(4, \infty)$

35. $f'(x) = -\csc^2 x < 0$ on $(0, \pi)$

37. $f'(x) = -\sin x < 0$ on $(0, \pi)$

39. (a) $f^{-1}(x) = \dfrac{x+3}{2}$

(b)



(c) f and f^{-1} are symmetric about $y = x$.

(d) Domain of f and f^{-1}: all real numbers
Range of f and f^{-1}: all real numbers

41. (a) $f^{-1}(x) = x^{1/5}$

(b)



(c) f and f^{-1} are symmetric about $y = x$.

(d) Domain of f and f^{-1}: all real numbers
Range of f and f^{-1}: all real numbers

43. (a) $f^{-1}(x) = x^2, \quad x \geq 0$

(b)



(c) f and f^{-1} are symmetric about $y = x$.

(d) Domain of f and f^{-1}: $x \geq 0$
Range of f and f^{-1}: $y \geq 0$

45. (a) $f^{-1}(x) = \sqrt{4-x^2}, \quad 0 \leq x \leq 2$

(b)



(c) f and f^{-1} are symmetric about $y = x$.

(d) Domain of f and f^{-1}: $0 \leq x \leq 2$
Range of f and f^{-1}: $0 \leq y \leq 2$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

47. (a) $f^{-1}(x) = x^3 + 1$

(b)



(c) f and f^{-1} are symmetric about $y = x$.

(d) Domain of f and f^{-1}: all real numbers
Range of f and f^{-1}: all real numbers

49. (a) $f^{-1}(x) = \dfrac{\sqrt{7}x}{\sqrt{1 - x^2}}, \quad -1 < x < 1$

(b)



(c) f and f^{-1} are symmetric about $y = x$.

(d) Domain of f: all real numbers
Domain of f^{-1}: $-1 < x < 1$
Range of f: $-1 < y < 1$
Range of f^{-1}: all real numbers

51.

x	0	1	2	4
$f(x)$	1	2	3	4

x	1	2	3	4
$f^{-1}(x)$	0	1	2	4



53. (a) Proof

(b) $y^{-1} = \frac{2}{3}(137.5 - x)$
x: total cost
y: number of pounds of the less expensive commodity

(c) $[62.5, 137.5]$; $50(1.25) = 62.5$ gives the total cost when purchasing 50 pounds of the less expensive commodity, and $50(2.75) = 137.5$ gives the total cost when purchasing 50 pounds of the more expensive commodity.

(d) 43 lb

55. One-to-one
$f^{-1}(x) = x^2 + 2, \quad x \geq 0$

57. One-to-one
$f^{-1}(x) = 2 - x, \quad x \geq 0$

59. *Sample Answer:* $f^{-1}(x) = \sqrt{x} + 3, \quad x \geq 0$

61. *Sample Answer:* $f^{-1}(x) = x - 3, \quad x \geq 0$

63. Inverse exists. Volume is an increasing function and therefore is one-to-one. The inverse function gives the time t corresponding to the volume V.

65. Inverse does not exist. **67.** $-\frac{1}{6}$ **69.** 4

71. $(f^{-1})'(1)$ is undefined.

73. (a) Domain of f: $(-\infty, \infty)$
Domain of f^{-1}: $(-\infty, \infty)$

(b) Range of f: $(-\infty, \infty)$
Range of f^{-1}: $(-\infty, \infty)$

(c)



(d) $f'\left(\frac{1}{2}\right) = \frac{3}{4}, (f^{-1})'\left(\frac{1}{8}\right) = \frac{4}{3}$

75. (a) Domain of f: $[4, \infty)$
Domain of f^{-1}: $[0, \infty)$

(b) Range of f: $[0, \infty)$
Range of f^{-1}: $[4, \infty)$

(c)



(d) $f'(5) = \frac{1}{2}, (f^{-1})'(1) = 2$

77. 32 **79.** $2\sqrt[3]{(x + 3)}$

81. Yes. Functions of the form $f(x) = x^n$, n is odd, are always increasing or always decreasing. So, it is one-to-one and therefore has an inverse function.

83. Many x-values yield the same y-value. For example, $f(\pi) = 0 = f(0)$. The graph is not continuous at $\dfrac{(2n - 1)\pi}{2}$, where n is an integer.

85. False. Let $f(x) = x^2$.

87. (a)



(b) $c = 2$

f does not pass the Horizontal Line Test.

89–91. Proofs

93. Proof; The graph of f is symmetric about the line $y = x$.

95. Proof; $\dfrac{\sqrt{5}}{5}$ **97.** Proof; concave upward

Section 5.4 *(page 348)*

1. The graph of $f(x) = e^x$ is concave upward and increasing on the entire domain.

3. $x = 4$ **5.** $x \approx 2.485$ **7.** $x = 0$ **9.** $x \approx 0.511$

11. $x \approx 8.862$ **13.** $x \approx 7.389$ **15.** $x \approx 10.389$

17. $x \approx 5.389$

19.



21.



23.



25. c **26.** d **27.** a **28.** b

CHAPTER 5

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

29.



31.



33. $5e^{5x}$ **35.** $\dfrac{e^{\sqrt{x}}}{2\sqrt{x}}$ **37.** e^{x-4} **39.** $e^x\left(\dfrac{1}{x} + \ln x\right)$

41. $e^x(x + 1)(x + 3)$ **43.** $3(e^{-t} + e^t)^2(e^t - e^{-t})$

45. $-\dfrac{5e^{5x}}{2 - e^{5x}}$ **47.** $\dfrac{-2(e^x - e^{-x})}{(e^x + e^{-x})^2}$ **49.** $-\dfrac{2e^x}{(e^x - 1)^2}$

51. $2e^x \cos x$ **53.** $\dfrac{\cos x}{x}$ **55.** $y = 3x + 1$

57. $y = -3x + 10$ **59.** $y = \left(\dfrac{1}{e}\right)x - \dfrac{1}{e}$

61. $y = ex$ **63.** $\dfrac{10 - e^y}{xe^y + 3}$ **65.** $y = (-e - 1)x + 1$

67. $3(6x + 5)e^{-3x}$

69. $y'' - y = 0$

$4e^{-x} - 4e^{-x} = 0$

71. Relative minimum: $(0, 1)$



73. Relative maximum:

$\left(2, \dfrac{1}{\sqrt{2\pi}}\right)$

Points of inflection:

$\left(1, \dfrac{e^{-0.5}}{\sqrt{2\pi}}\right), \left(3, \dfrac{e^{-0.5}}{\sqrt{2\pi}}\right)$



75. Relative maximum: $(1, e)$

Point of inflection: $(0, 2)$



77. Relative maximum:

$(-1, 1 + e)$

Point of inflection: $(0, 3)$



79. $A = \sqrt{2}e^{-1/2}$

81. $\left(\frac{1}{2}, e\right)$



83. (a)



(b) When $t = 1$,

$\dfrac{dV}{dt} \approx -5028.84.$

When $t = 5$,

$\dfrac{dV}{dt} \approx -406.89.$

(c)



85. (a)



$\ln P = -0.1499h + 6.9797$

(b) $P = 1074.6e^{-0.1499h}$

(c)



(d) $h = 5$: -76.13 millibars/km

$h = 18$: -10.84 millibars/km

87. $P_1 = 1 + x$; $P_2 = 1 + x + \frac{1}{2}x^2$



The values of f, P_1, and P_2 and their first derivatives agree at $x = 0$.

89. $12! = 479{,}001{,}600$

Stirling's Formula: $12! \approx 475{,}687{,}487$

91. $e^{5x} + C$ **93.** $\frac{1}{5}e^{5x-3} + C$ **95.** $e^{x^2+x} + C$

97. $2e^{\sqrt{x}} + C$

99. $x - \ln(e^x + 1) + C_1$ or $-\ln(1 + e^{-x}) + C_2$

101. $-\frac{2}{3}(1 - e^x)^{3/2} + C$ **103.** $\ln|e^x - e^{-x}| + C$

105. $-\frac{5}{2}e^{-2x} + e^{-x} + C$ **107.** $\ln|\cos e^{-x}| + C$

109. $\dfrac{e^3 - 1}{3e^3}$ **111.** $\dfrac{e - 1}{2e}$ **113.** $\dfrac{e}{3}(e^2 - 1)$

115. $\dfrac{1}{4}\ln\dfrac{1 + e^8}{2}$ **117.** $\dfrac{1}{\pi}\left[e^{\sin(\pi^2/2)} - 1\right]$

119. $y = \frac{1}{18}e^{9x^2} + C$ **121.** $f(x) = \frac{1}{2}(e^x + e^{-x})$

123. $e^6 - 1 \approx 402.4$ **125.** $2(1 - e^{-3/2}) \approx 1.554$

127. 92.190

129. The natural exponential function has a horizontal asymptote $y = 0$ to the left, and the natural logarithmic function has a vertical asymptote $x = 0$ from the right.

131. False. The derivative is $e^x(g'(x) + g(x))$.

133. True

135. The probability that a given battery will last between 48 months and 60 months is approximately 47.72%.

137. (a) $R = 428.78e^{-0.6155t}$

(b)



(c) About 637.2 L

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

139. (a)



(b) When x increases without bound, $1/x$ approaches zero, and $e^{1/x}$ approaches 1. So, $f(x)$ approaches $2/(1 + 1) = 1$. So, $f(x)$ has a horizontal asymptote at $y = 1$. As x approaches zero from the right, $1/x$ approaches ∞, $e^{1/x}$ approaches ∞, and $f(x)$ approaches zero. As x approaches zero from the left, $1/x$ approaches $-\infty$, $e^{1/x}$ approaches zero, and $f(x)$ approaches 2. The limit does not exist because the left limit does not equal the right limit. Therefore, $x = 0$ is a nonremovable discontinuity.

141. $\displaystyle\int_0^x e^t\,dt \geq \int_0^x 1\,dt$; $e^x - 1 \geq x$; $e^x \geq x + 1$ for $x \geq 0$

143. Relative maximum: $\left(\frac{1}{k}, \frac{1}{ke}\right)$

Point of inflection: $\left(\frac{2}{k}, \frac{2}{ke^2}\right)$

145. Putnam Problem B1, 2012

Section 5.5 *(page 358)*

1. $a = 4, b = 6$

3. It is necessary when you have a function of the form $y = u(x)^{v(x)}$

5. -3 **7.** 0 **9.** $\frac{5}{6}$

11. (a) $\log_2 8 = 3$ (b) $\log_3\left(\frac{1}{3}\right) = -1$

13. (a) $10^{-2} = 0.01$ (b) $\left(\frac{1}{2}\right)^{-3} = 8$

15.



17.



19.



21. (a) $x = 3$ (b) $x = -1$ **23.** (a) $x = \frac{1}{3}$ (b) $x = \frac{1}{16}$

25. (a) $x = -1, 2$ (b) $x = \frac{1}{3}$ **27.** 1.965

29. -6.288 **31.** 12.253 **33.** 33.000 **35.** 3.429

37.



39. $(\ln 4)4^x$ **41.** $(-4 \ln 5)5^{-4x}$ **43.** $9^x(x \ln 9 + 1)$

45. $\dfrac{2t^2 \ln 8 - 4t}{8^t}$ **47.** $-2^{-\theta}[(\ln 2)\cos \pi\theta + \pi \sin \pi\theta]$

49. $\dfrac{6}{(\ln 4)(6x + 1)}$ **51.** $\dfrac{2}{(\ln 5)(t - 4)}$ **53.** $\dfrac{x}{(\ln 5)(x^2 - 1)}$

55. $\dfrac{x - 2}{(\ln 2)x(x - 1)}$ **57.** $\dfrac{3x - 2}{(2x \ln 3)(x - 1)}$ **59.** $\dfrac{5(1 - \ln t)}{t^2 \ln 2}$

61. $y = -2x \ln 2 - 2 \ln 2 + 2$ **63.** $y = \dfrac{1}{27 \ln 3}x + 3 - \dfrac{1}{\ln 3}$

65. $2(1 - \ln x)x^{(2/x)-2}$ **67.** $(x - 2)^{x+1}\left[\dfrac{x + 1}{x - 2} + \ln(x - 2)\right]$

69. $\dfrac{3^x}{\ln 3} + C$ **71.** $\dfrac{1}{3}x^3 - \dfrac{2^{-x}}{\ln 2} + C$

73. $-\dfrac{1}{2 \ln 5}(5^{-x^2}) + C$ **75.** $\dfrac{\ln(3^{2x} + 1)}{2 \ln 3} + C$ **77.** $\dfrac{7}{2 \ln 2}$

79. $\dfrac{4}{\ln 5} - \dfrac{2}{\ln 3}$ **81.** $\dfrac{(\ln 5)^2}{2 \ln 4} \approx 0.934$

83. The exponential function grows more rapidly as a becomes larger.

85. (a) $x > 0$ (b) 10^x (c) $3 \leq f(x) \leq 4$
(d) $0 < x < 1$ (e) 10 (f) 100^n

87. (a)



Yes, $y = (1/2)^x$ and $y = x$ intersect.

(b)



No, $y = 2^x$ and $y = x$ do not intersect.

89. (a) \$40.64 (b) $C'(1) \approx 0.051P$, $C'(8) \approx 0.072P$
(c) ln 1.05

91.

n	1	2	4	12
A	\$1410.60	\$1414.78	\$1416.91	\$1418.34

n	365	Continuous
A	\$1419.04	\$1419.07

93.

n	1	2	4	12
A	\$30,612.57	\$31,121.37	\$31,385.05	\$31,564.42

n	365	Continuous
A	\$31,652.22	\$31.655.22

95.

t	1	10	20	30
P	\$96,078.94	\$67,032.00	\$44,932.90	\$30,119.42

t	40	50
P	\$20,189.65	\$13,533.53

CHAPTER 5

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

97.

t	1	10	20	30
P	\$95,132.82	\$60,716.10	\$36,864.45	\$22,382.66

t	40	50
P	\$13,589.88	\$8251.24

99. c

101. (a) 0.75 million ft^3/acre

(b) $t = 20$: $\frac{dV}{dt} = 0.0015$; $t = 60$: $\frac{dV}{dt} = 0.0040$

103. (a)



(b) 6 months: 1487 fish
12 months: 3672 fish
24 months: 8648 fish
36 months: 9860 fish
48 months: 9987 fish
Limiting size: 10,000 fish

(c) 1 month: About 114 fish/mo
10 months: About 403 fish/mo

(d) About 15 mo

105. (a) $y_1 = 1024x - 2387.73$,
$y_2 = -2305.215 + 3674.168 \ln x$,
$y_3 = 427.996(1.363)^x$, $y_4 = 54.656x^{2.2225}$

(b)



Answers will vary.

(c) $y'_1(5) = 1024$, $y'_2(5) = 734.83$, $y'_3(5) = 623.51$, $y'_4(5) = 868.90$; y_1 is increasing at the greatest rate.

107. e **109.** e^2 **111.** $y = 1200(0.6^t)$

113. (a) $(2^3)^2 = 2^6 = 64$
$2^{(3^2)} = 2^9 = 512$

(b) No. $f(x) = (x^x)^x = x^{(x^2)}$ and $g(x) = x^{(x^x)}$

(c) $f'(x) = x^{x^2}(x + 2x \ln x)$
$g'(x) = x^{x^x + x - 1}[x(\ln x)^2 + x \ln x + 1]$

115. Proof

117. (a) $\frac{dy}{dx} = \frac{y^2 - yx \ln y}{x^2 - xy \ln x}$

(b) (i) 1 when $c \neq 0, c \neq e$ (ii) -3.1774
(iii) -0.3147

(c) (e, e)

119. Putnam Problem

Section 5.6 *(page 369)*

1. L'Hôpital's Rule allows you to address limits of the form $0/0$ and ∞/∞.

3.

x	-0.1	-0.01	-0.001	0
$f(x)$	1.3177	1.3332	1.3333	?

x	0.001	0.01	0.1
$f(x)$	1.3333	1.3332	1.3177

$\frac{4}{3}$

5.

x	1	10	10^2
$f(x)$	0.9900	90,483.7	3.7×10^9

x	10^3	10^4	10^5
$f(x)$	4.5×10^{10}	0	0

0

7. $\frac{3}{8}$ **9.** $\frac{1}{8}$ **11.** 0 **13.** $\frac{5}{3}$ **15.** 4 **17.** 0
19. ∞ **21.** $\frac{11}{4}$ **23.** $\frac{3}{5}$ **25.** $\frac{7}{6}$ **27.** ∞
29. 0 **31.** 1 **33.** 0 **35.** 0 **37.** ∞
39. $\frac{5}{9}$ **41.** ∞

43. (a) Not indeterminate
(b) ∞
(c)



45. (a) $0 \cdot \infty$
(b) 1
(c)



47. (a) 1^∞
(b) e^4
(c)



49. (a) ∞^0
(b) 1
(c)



51. (a) 1^∞ (b) e
(c)



53. (a) 0^0 (b) 3
(c)



55. (a) 0^0 (b) 1
(c)



57. (a) $\infty - \infty$ (b) $-\frac{3}{2}$
(c)



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

59. (a) $\infty - \infty$ (b) ∞

(c)



61. (a) $\infty - \infty$ (b) ∞

(c)



63. Answers will vary. *Sample answers:*

(a) $f(x) = x^2 - 25,\ g(x) = x - 5$

(b) $f(x) = (x - 5)^2,\ g(x) = x^2 - 25$

(c) $f(x) = x^2 - 25,\ g(x) = (x - 5)^3$

65. (a) Yes; $\frac{0}{0}$ (b) No; $\frac{0}{-1}$ (c) Yes; $\frac{\infty}{\infty}$ (d) Yes; $\frac{0}{0}$

(e) No; $\frac{-1}{0}$ (f) Yes; $\frac{0}{0}$

67.

x	10	10^2	10^4	10^6	10^8	10^{10}
$\frac{(\ln x)^4}{x}$	2.811	4.498	0.720	0.036	0.001	0.000

69. 0 **71.** 0 **73.** 0

75. Horizontal asymptote: $y = 1$

Relative maximum: $(e, e^{1/e})$



77. Horizontal asymptote: $y = 0$

Relative maximum: $\left(1, \frac{2}{e}\right)$



79. Limit is not of the form $\frac{0}{0}$ or $\frac{\infty}{\infty}$.

81. Limit is not of the form $\frac{0}{0}$ or $\frac{\infty}{\infty}$.

83. 1/6

85. (a) $\lim_{x\to\infty} \frac{x}{\sqrt{x^2+1}} = \lim_{x\to\infty} \frac{\sqrt{x^2+1}}{x} = \lim_{x\to\infty} \frac{x}{\sqrt{x^2+1}}$

Applying L'Hôpital's Rule twice results in the original limit, so L'Hôpital's Rule fails.

(b) 1

(c)



87.



As $x \to 0$, the graphs get closer together (they both approach 0.75). By L'Hôpital's Rule,

$$\lim_{x\to 0} \frac{\sin 3x}{\sin 4x} = \lim_{x\to 0} \frac{3\cos 3x}{4\cos 4x} = \frac{3}{4}.$$

89. $\frac{Vt}{L}$ **91.** Proof **93.** $c = \frac{2}{3}$ **95.** $c = \frac{\pi}{4}$

97. False. $\frac{\infty}{0} = \pm\infty$ **99.** True **101.** True **103.** $\frac{3}{4}$

105. $c = \frac{4}{3}$ **107.** $a = 1, b = \pm 2$ **109.** Proof

111. (a) $0 \cdot \infty$ (b) 0 **113.** Proof **115.** (a)–(c) 2

117. (a)



(b) $\lim_{x\to\infty} h(x) = 1$ (c) No

119. Putnam Problem A1, 1956

Section 5.7 *(page 379)*

1. arccos x is the angle, $0 \le \theta \le \pi$, whose cosine is x.

3. arccot **5.** $\left(-\frac{\sqrt{2}}{2}, \frac{3\pi}{4}\right), \left(\frac{1}{2}, \frac{\pi}{3}\right), \left(\frac{\sqrt{3}}{2}, \frac{\pi}{6}\right)$

7. $\frac{\pi}{6}$ **9.** $\frac{\pi}{3}$ **11.** $\frac{\pi}{6}$ **13.** $-\frac{\pi}{4}$ **15.** 1.52

17. $\arccos \frac{1}{1.269} \approx 0.66$ **19.** x **21.** $\frac{\sqrt{1-x^2}}{x}$

23. $\frac{1}{x}$ **25.** (a) $\frac{3}{5}$ (b) $\frac{5}{3}$ **27.** (a) $-\sqrt{3}$ (b) $-\frac{13}{5}$

29. $\sqrt{1-4x^2}$ **31.** $\frac{\sqrt{x^2-1}}{|x|}$ **33.** $\frac{\sqrt{x^2-9}}{3}$

35. $\frac{\sqrt{x^2+2}}{x}$ **37.** $x = \frac{1}{3}\left(\sin\frac{1}{2} + \pi\right) \approx 1.207$ **39.** $x = \frac{1}{3}$

41. $\frac{1}{\sqrt{2x-x^2}}$ **43.** $-\frac{3}{\sqrt{4-x^2}}$ **45.** $\frac{e^x}{1+e^{2x}}$

47. $\frac{3x - \sqrt{1-9x^2}\arcsin 3x}{x^2\sqrt{1-9x^2}}$ **49.** $-\frac{t}{\sqrt{1-t^2}}$

51. $2\arccos x$ **53.** $\frac{1}{1-x^4}$ **55.** $\frac{x^2}{\sqrt{16-x^2}}$

57. $y = \frac{1}{3}\left(4\sqrt{3}x - 2\sqrt{3} + \pi\right)$ **59.** $y = \frac{1}{4}x + \frac{\pi - 2}{4}$

61. $y = (2\pi - 4)x + 4$

63. Relative maximum: $(1.272, -0.606)$

Relative minimum: $(-1.272, 3.747)$

65. Relative maximum: $(2, 2.214)$

67.



Maximum: $\left(2, \frac{\pi}{2}\right)$

Minimum: $\left(0, -\frac{\pi}{2}\right)$

Point of inflection: $(1, 0)$

69.



Maximum: $\left(-\frac{1}{2}, \pi\right)$

Minimum: $\left(\frac{1}{2}, 0\right)$

Asymptote: $y = \frac{\pi}{2}$

CHAPTER 5

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

71. $y = -\dfrac{2\pi x}{\pi + 8} + 1 - \dfrac{\pi^2}{2\pi + 16}$ **73.** $y = -x + \sqrt{2}$

75. (a) $\arcsin(\arcsin 0.5) \approx 0.551$
$\arcsin(\arcsin 1)$ does not exist.
(b) $\sin(-1) \le x \le \sin 1$

77. No

79. To have a true inverse function, the domain of sine must be restricted. As a result, 2π is not in the range of the arcsine function.

81. (a) and (b) Proofs **83.** True **85.** True

87. (a) $\theta = \operatorname{arccot}\dfrac{x}{5}$
(b) $x = 10$: 16 rad/h
$x = 3$: 58.824 rad/h

89. (a) $h(t) = -16t^2 + 256$; $t = 4$ sec
(b) $t = 1$: -0.0520 rad/sec
$t = 2$: -0.1116 rad/sec

91. $50\sqrt{2} \approx 70.71$ ft **93.** Proof

95.



(a) The graph is a horizontal line at $\dfrac{\pi}{2}$.
(b) Proof

97. $c = 2$

99. (a)



(b) Proof

Section 5.8 *(page 387)*

1. (a) No
(b) Yes. Use the rule involving the arcsecant function.

3. $\arcsin\dfrac{x}{3} + C$ **5.** $\operatorname{arcsec}|2x| + C$

7. $\arcsin(x + 1) + C$ **9.** $\frac{1}{2}\arcsin t^2 + C$

11. $\dfrac{1}{10}\arctan\dfrac{t^2}{5} + C$ **13.** $\dfrac{1}{4}\arctan\dfrac{e^{2x}}{2} + C$

15. $\arcsin\dfrac{\csc x}{5} + C$ **17.** $2\arcsin\sqrt{x} + C$

19. $\frac{1}{2}\ln(x^2 + 1) - 3\arctan x + C$

21. $8\arcsin\dfrac{x - 3}{3} - \sqrt{6x - x^2} + C$ **23.** $\dfrac{\pi}{6}$ **25.** $\dfrac{\pi}{6}$

27. $\dfrac{1}{3}\left(\arctan 3 - \dfrac{\pi}{4}\right) \approx 0.155$ **29.** $\arctan 5 - \dfrac{\pi}{4} \approx 0.588$

31. $\dfrac{\pi}{4}$ **33.** $\dfrac{1}{32}\pi^2 \approx 0.308$ **35.** $\dfrac{\pi}{2}$

37. $\ln|x^2 + 6x + 13| - 3\arctan\left(\dfrac{x + 3}{2}\right) + C$

39. $\dfrac{\sqrt{2}}{2}\arcsin\left[\dfrac{\sqrt{6}}{6}(x - 2)\right] + C$ **41.** $\arcsin\dfrac{x + 2}{2} + C$

43. $4 - 2\sqrt{3} + \dfrac{1}{6}\pi \approx 1.059$

45. $2\sqrt{e^t - 3} - 2\sqrt{3}\arctan\dfrac{\sqrt{e^t - 3}}{\sqrt{3}} + C$ **47.** $\dfrac{\pi}{6}$

49. (a) $\arcsin x + C$ (b) $-\sqrt{1 - x^2} + C$ (c) Not possible

51. (a) $\frac{2}{3}(x - 1)^{3/2} + C$ (b) $\frac{2}{15}(x - 1)^{3/2}(3x + 2) + C$
(c) $\frac{2}{3}\sqrt{x - 1}(x + 2) + C$

53. Proof

55. No. Graphing $f(x) = \arcsin x$ and $g(x) = -\arccos x$, you can see that the graph of f is the graph of g shifted vertically.

57. (a)



(b) $y = \dfrac{2}{3}\arctan\dfrac{x}{3} + 2$



59.



61.



63. $y = \arcsin\dfrac{x}{2} + \pi$ **65.** $\dfrac{\pi}{3}$ **67.** $\dfrac{3\pi}{2}$

69. (a)



(b) 0.5708
(c) $\dfrac{\pi - 2}{2}$

71. (a) $F(x)$ represents the average value of $f(x)$ over the interval $[x, x + 2]$; Maximum at $x = -1$
(b) Maximum at $x = -1$

73. False. $\displaystyle\int \frac{dx}{3x\sqrt{9x^2 - 16}} = \frac{1}{12}\operatorname{arcsec}\frac{|3x|}{4} + C$

75–77. Proofs

79. (a) $\displaystyle\int_0^1 \frac{1}{1 + x^2}\,dx$ (b) About 0.7857

(c) Because $\displaystyle\int_0^1 \frac{1}{1 + x^2}\,dx = \frac{\pi}{4}$, you can use the Midpoint Rule to approximate $\dfrac{\pi}{4}$. Multiplying the result by 4 gives an estimation of π.

Section 5.9 *(page 397)*

1. Hyperbolic function came from the comparison of the area of a semicircular region with the area of a region under a hyperbola.

3. $\sinh^2 x = \dfrac{-1 + \cosh 2x}{2}$ **5.** (a) 10.018 (b) -0.964

7. (a) $\frac{4}{3}$ (b) $\frac{13}{12}$ **9.** (a) 1.317 (b) 0.962

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

11–17. Proofs

19. $\cosh x = \frac{\sqrt{13}}{2}$, $\tanh x = \frac{3\sqrt{13}}{13}$, $\operatorname{csch} x = \frac{2}{3}$, $\operatorname{sech} x = \frac{2\sqrt{13}}{13}$, $\coth x = \frac{\sqrt{13}}{3}$

21. ∞ **23.** 1 **25.** $9\cosh 9x$

27. $-10x(\operatorname{sech} 5x^2 \tanh 5x^2)$ **29.** $\coth x$

31. $-\frac{t}{2}\cosh(-3t) + \frac{\sinh(-3t)}{6}$ **33.** $\operatorname{sech} t$

35. $y = -2x + 2$ **37.** $y = 1 - 2x$

39. Relative maximum: $(1.20, 0.66)$
Relative minimum: $(-1.20, -0.66)$

41. Relative maxima: $(\pm\pi, \cosh \pi)$
Relative minimum: $(0, -1)$

43. (a)



(b) 33.146 units, 25 units
(c) $m = \sinh 1 \approx 1.175$

45. $\frac{1}{4}\sinh 4x + C$ **47.** $-\frac{1}{2}\cosh(1 - 2x) + C$

49. $\frac{1}{3}\cosh^3(x - 1) + C$ **51.** $\ln|\sinh x| + C$

53. $-\coth\frac{x^2}{2} + C$ **55.** $\ln\frac{5}{4}$ **57.** $\coth 1 - \coth 2$

59. $-\frac{1}{3}(\operatorname{csch} 2 - \operatorname{csch} 1)$

61.



The graphs do not intersect.

63. Proof **65.** $\frac{3}{\sqrt{9x^2 - 1}}$ **67.** $\frac{1}{2\sqrt{x}(1 - x)}$

69. $|\sec x|$ **71.** $-\csc x$ **73.** $2\sinh^{-1}(2x)$

75. $\frac{\sqrt{3}}{18}\ln\left|\frac{1 + \sqrt{3}x}{1 - \sqrt{3}x}\right| + C$ **77.** $\ln\left(\sqrt{e^{2x} + 1} - 1\right) - x + C$

79. $2\sinh^{-1}\sqrt{x} + C = 2\ln\left(\sqrt{x} + \sqrt{1 + x}\right) + C$

81. $\frac{1}{4}\ln\left|\frac{x - 4}{4}\right| + C$ **83.** $\ln\left(\frac{3 + \sqrt{5}}{2}\right)$ **85.** $\frac{\ln 7}{12}$

87. $-\frac{x^2}{2} - 4x - \frac{10}{3}\ln\left|\frac{x - 5}{x + 1}\right| + C$

89. $8\arctan e^2 - 2\pi \approx 5.207$ **91.** $\frac{5}{2}\ln\left(\sqrt{17} + 4\right) \approx 5.237$

93. (a) $-\frac{\sqrt{a^2 - x^2}}{x}$ (b) Proof

95–103. Proofs

105. (a) The identity is not correct. The correct identity is as follows: $\cosh^2 x + \sinh^2 x = \cosh(2x)$.
(b) The identity is correct.

107. Putnum Problem

Review Exercises for Chapter 5 *(page 400)*

1. $y_1(0.1) = -2.303$, $y_2(0.1) = 1.105$, $y_1(0.5) = -0.693$, $y_2(0.5) = 1.649$, $y_1(1) = 0$, $y_2(1) = 2.718$, $y_1(2) = 0.693$, $y_2(2) = 7.389$, $y_1(10) = 2.303$, $y_2(10) = 22026.47$



The graphs of $y_1 = \ln x$ and $y_2 = e^x$ are inverses of one another. This means that the domain of $\ln x$, $0 < x < \infty$, is the range of e^x and the range of $\ln x$, $-\infty < y < \infty$, is the domain of e^x. The graph of $\ln x$ has an asymptote at $x = 0$ while the graph of e^x has an asymptote at $y = 0$.

3. (a)



(b) 0.9997
(c) 1

5. (a) $y' = cx^{c-1}$ (b) $y' = c^x \ln c$
(c) $y' = x^x(\ln x + 1)$ (d) $y' = 0$

7.



Domain: $x > 0$

9. (a) 2.9957 (b) -0.2231 (c) 6.4376 (d) 0.8047

11. $\frac{1}{5}[\ln(2x + 1) + \ln(2x - 1) - \ln(4x^2 + 1)]$

13. $\ln\frac{3\sqrt[3]{4 - x^2}}{x}$ **15.** $\frac{1}{2x}$ **17.** $\frac{1 + 2\ln x}{2\sqrt{\ln x}}$

19. $-\frac{8x}{x^4 - 16}$ **21.** $\frac{7}{(1 - 7x)[\ln(1 - 7x)]^2}$

23. $y = -x + 1$ **25.** $\frac{5x^2 - 4x}{2\sqrt{x - 1}}$ **27.** $\frac{1}{7}\ln|7x - 2| + C$

29. $-\ln|1 + \cos x| + C$ **31.** $x - 3\ln(x^2 + 1) + C$

33. $3 + \ln 2$ **35.** $\ln\left(2 + \sqrt{3}\right)$ **37.** $2\ln\frac{123}{25} \approx 3.187$

39. (a) $f^{-1}(x) = 2x + 6$
(b)



(c) Proof
(d) Domain of f and f^{-1}: all real numbers
Range of f and f^{-1}: all real numbers

CHAPTER 5

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

41. (a) $f^{-1}(x) = x^2 - 1, \quad x \geq 0$

(b)



(c) Proof

(d) Domain of f: $x \geq -1$, Domain of f^{-1}: $x \geq 0$
Range of f: $y \geq 0$, Range of f^{-1}: $y \geq -1$

43. (a) $f^{-1}(x) = x^3 - 1$

(b)



(c) Proof

(d) Domain of f and f^{-1}: all real numbers
Range of f and f^{-1}: all real numbers

45. $\dfrac{1}{3\left(\sqrt[3]{-3}\right)^2} \approx 0.160$ **47.** $\dfrac{3}{4}$ **49.** $x \approx 1.134$

51. $e^4 - 1 \approx 53.598$ **53.** $te^t(t + 2)$ **55.** $\dfrac{e^{2x} - e^{-2x}}{\sqrt{e^{2x} + e^{-2x}}}$

57. $\dfrac{3x^2 - 2x^3}{e^{2x}}$ **59.** $y = 6x + 1$

61. Relative maximum: $(0, 1)$

Point of inflection: $\left(1, \dfrac{2}{e}\right)$



63. $-\dfrac{1}{2}e^{1-x^2} + C$ **65.** $\dfrac{e^{4x} - 3e^{2x} - 3}{3e^x} + C$

67. $\dfrac{1 - e^{-3}}{6}$ **69.** $\ln(e^2 + e + 1)$ **71.** About 1.729

73.



75. $1 - \dfrac{\ln 52}{\ln 4} \approx -1.850$ **77.** $\dfrac{\ln 3}{12 \ln 1.0025} \approx 36.666$

79. 35 **81.** $3^{x-1} \ln 3$ **83.** $\dfrac{8^t(t \ln 8 - 2)}{t^3}$

85. $-\dfrac{1}{(2 - 2x) \ln 3}$ **87.** $x^{2x+1}\left(2 \ln x + 2 + \dfrac{1}{x}\right)$

89. $\dfrac{5^{(x+1)^2}}{2 \ln 5} + C$ **91.** $\dfrac{30}{\ln 6}$

93. (a) \$613.92 (b) \$4723.67 (c) 6.93%

95. 0 **97.** ∞ **99.** 1 **101.** $1000e^{0.09} \approx 1094.17$

103. (a) $\dfrac{1}{2}$ (b) $\dfrac{\sqrt{3}}{2}$ **105.** $-\dfrac{2}{x\sqrt{4x^4 - 1}}$

107. $\dfrac{x}{|x|\sqrt{x^2 - 1}} + \operatorname{arcsec} x$ **109.** $(\arcsin x)^2$

111. $\frac{1}{2} \arctan e^{2x} + C$ **113.** $\frac{1}{2} \arcsin x^2 + C$

115. $\dfrac{1}{4}\left(\arctan \dfrac{x}{2}\right)^2 + C$ **117.** $\dfrac{\pi}{14}$

119. $\arctan \dfrac{e^4}{5} - \arctan \dfrac{e^{-2}}{5}$ **121.** $\dfrac{2}{3}\pi + \sqrt{3} - 2 \approx 1.826$

123. $y' = -4 \operatorname{sech}(4x - 1) \tanh(4x - 1)$

125. $y' = -16x \operatorname{csch}^2(8x^2)$ **127.** $y' = \dfrac{4}{\sqrt{16x^2 + 1}}$

129. $\frac{1}{3} \tanh x^3 + C$ **131.** $\ln|\tanh x| + C$

133. $\dfrac{1}{12} \ln\left|\dfrac{3 + 2x}{3 - 2x}\right| + C$ **135.** $-\dfrac{1}{2} \operatorname{sech} 4 + \dfrac{1}{2} \operatorname{sech} 2$

137. $\ln 2$

139. (a) Domain: $0 < x < \infty$ (b) $x = 4.81$ and $x = 0.009$
(c) $x = 0.208$ and $x = 0.0004$ (d) Range: $-1 \leq y \leq 1$

(e) $f'(x) = \dfrac{\cos(\ln x)}{x}$

Maximum: $y = 1$

(f)



The limit does not exist.

(g) The limit is indeterminate.

141. (a)



(b) Proof

(c) Proof

P.S. Problem Solving *(page 404)*

1. $a = 1, b = \frac{1}{2}, c = -\frac{1}{2}$

$f(x) = \dfrac{1 + x/2}{1 - x/2}$



3. $\ln 3$ **5.** Proof **7.** Area $= \frac{1}{2} \arctan\left(\frac{1}{2}\right)$

9.



$y = 0.5^x$ and $y = 1.2^x$
intersect the line $y = x$; $0 < a < e^{1/e}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Chapter 6

Section 6.1 *(page 411)*

1. Substitute $f(x)$ and its derivatives into the differential equation. If the equation is satisfied, then $f(x)$ is a solution.

3. The line segments show the general shape of all the solutions of a differential equation and give a visual perspective of the directions of the solutions of the differential equation.

5–13. Proofs **15.** Solution **17.** Not a solution

19. Solution **21.** Not a solution **23.** Not a solution

25. Solution **27.** Not a solution **29.** Not a solution

31. $y = 3e^{-x/2}$ **33.** $4y^2 = x^3$

35.



37. $y = 3e^{-6x}$ **39.** $y = 2\sin 3x - \frac{1}{3}\cos 3x$

41. $y = -2x + \frac{1}{2}x^3$ **43.** $4x^3 + C$

45. $y = \frac{1}{2}\ln(1 + x^2) + C$ **47.** $y = -\frac{1}{2}\cos 2x + C$

49. $y = \frac{2}{5}(x - 6)^{5/2} + 4(x - 6)^{3/2} + C$ **51.** $y = \frac{1}{2}e^{x^2} + C$

53.

x	-4	-2	0	2	4	8
y	2	0	4	4	6	8
dy/dx	-4	Undef.	0	1	$\frac{4}{3}$	2

55.

x	-4	-2	0	2	4	8
y	2	0	4	4	6	8
dy/dx	$-2\sqrt{2}$	-2	0	0	$-2\sqrt{2}$	-8

57. b **58.** c **59.** d **60.** a

61. (a) and (b)



(c) As $x \to \infty$, $y \to -\infty$
As $x \to -\infty$, $y \to -\infty$

63. (a) and (b)



(c) As $x \to \infty$, $y \to -\infty$
As $x \to -\infty$, $y \to -\infty$

65. (a)



As $x \to \infty$, $y \to \infty$

(b)



As $x \to \infty$, $y \to \infty$

67. (a) and (b)



69. (a) and (b)



71. (a) and (b)



73.

n	0	1	2	3	4	5	6
x_n	0	0.1	0.2	0.3	0.4	0.5	0.6
y_n	2	2.2	2.43	2.693	2.992	3.332	3.715

n	7	8	9	10
x_n	0.7	0.8	0.9	1.0
y_n	4.146	4.631	5.174	5.781

75.

n	0	1	2	3	4	5	6
x_n	0	0.05	0.1	0.15	0.2	0.25	0.3
y_n	3	2.7	2.438	2.209	2.010	1.839	1.693

n	7	8	9	10
x_n	0.35	0.4	0.45	0.5
y_n	1.569	1.464	1.378	1.308

77.

n	0	1	2	3	4	5	6
x_n	0	0.1	0.2	0.3	0.4	0.5	0.6
y_n	1	1.1	1.212	1.339	1.488	1.670	1.900

n	7	8	9	10
x_n	0.7	0.8	0.9	1.0
y_n	2.213	2.684	3.540	5.958

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

79.

x	0	0.2	0.4	0.6	0.8	1
$y(x)$ (exact)	3.0000	3.6642	4.4755	5.4664	6.6766	8.1548
$y(x)$ $(h = 0.2)$	3.0000	3.6000	4.3200	5.1840	6.2208	7.4650
$y(x)$ $(h = 0.1)$	3.0000	3.6300	4.3923	5.3147	6.4308	7.7812

81.

x	0	0.2	0.4	0.6	0.8	1
$y(x)$ (exact)	0.0000	0.2200	0.4801	0.7807	1.1231	1.5097
$y(x)$ $(h = 0.2)$	0.0000	0.2000	0.4360	0.7074	1.0140	1.3561
$y(x)$ $(h = 0.1)$	0.0000	0.2095	0.4568	0.7418	1.0649	1.4273

83. (a) $y(1) = 112.7141°$, $y(2) = 96.3770°$, $y(3) = 86.5954°$
(b) $y(1) = 113.2441°$, $y(2) = 97.0158°$, $y(3) = 87.1729°$
(c) Euler's Method: $y(1) = 112.9828°$, $y(2) = 96.6998°$, $y(3) = 86.8863°$
Exact solution: $y(1) = 113.2441°$, $y(2) = 97.0158°$, $y(3) = 87.1729°$
The approximations are better using $h = 0.05$.

85. Euler's Method produces an exact solution to an initial value problem when the exact solution is a line.

87. False. $y = x^3$ is a solution of $xy' - 3y = 0$, but $y = x^3 + 1$ is not a solution.

89. (a)

x	0	0.2	0.4	0.6	0.8	1
y	4	2.6813	1.7973	1.2048	0.8076	0.5413
y_1	4	2.56	1.6384	1.0486	0.6711	0.4295
y_2	4	2.4	1.44	0.864	0.5184	0.3110
e_1	0	0.1213	0.1589	0.1562	0.1365	0.1118
e_2	0	0.2813	0.3573	0.3408	0.2892	0.2303
r		0.4312	0.4447	0.4583	0.4720	0.4855

(b) If h is halved, then the error is approximately halved because r is approximately 0.5.
(c) The error will again be halved.

91. (a)



(b) $\lim_{t\to\infty} I(t) = 2$

93. $\omega = \pm 4$ **95.** Putnam Problem 3, morning session, 1954

Section 6.2 *(page 420)*

1. C is the initial value of y, and k is the proportionality constant.

3. $y = \frac{1}{2}x^2 + 3x + C$ **5.** $y = Ce^x - 3$

7. $y^2 - 5x^2 = C$ **9.** $y = Ce^{(2x^{3/2})/3}$ **11.** $y = C(1 + x^2)$

13. $\dfrac{dQ}{dt} = \dfrac{k}{t^2}$ $\quad Q = -\dfrac{k}{t} + C$

15. $\dfrac{dN}{ds} = k(500 - s)$ $\quad N = -\dfrac{k}{2}(500 - s)^2 + C$

17. (a)



(b) $y = 6 - 6e^{-x^2/2}$



19. $y = \frac{1}{4}t^2 + 10$



21. $y = 10e^{-t/2}$



23. $\dfrac{dN}{dt} = kN$, $N = 250^e\left(\ln\left(\dfrac{8}{5}\right)t\right)$; $N = \dfrac{8192}{5}$

25. $\dfrac{dV}{dt} = kV$, $V = 20{,}000^e\left[\dfrac{1}{4}\ln\left(\dfrac{5}{8}\right)t\right]$;
$V = 3125\sqrt{10} \approx 9882.118$

27. $y = 2e^{[(1/4)\ln(3/2)]t} \approx 2e^{0.1014t}$

29. $y = 5\left(\frac{5}{2}\right)^{1/4}e^{[\ln(2/5)/4]t} \approx 6.2872e^{-0.2291t}$

31. Quadrants I and III; $\dfrac{dy}{dx}$ is positive when both x and y are positive (Quadrant I) or when both x and y are negative (Quadrant III).

33. Amount after 1000 yr: 12.96 g
Amount after 10,000 yr: 0.26 g

35. Initial quantity: 7.63 g
Amount after 1000 yr: 4.95 g

37. Amount after 1000 yr: 4.43 g
Amount after 10,000 yr: 1.49 g

39. Initial quantity: 2.16 g
Amount after 10,000 yr: 1.62 g

41. 95.76%

43. Time to double: 5.78 yr
Amount after 10 yr: $3320.12

45. Annual rate: 4.62%
Amount after 10 yr: $238.09

47. Annual rate: 7.18%
Time to double: 9.65 yr

49. $224,174.18 **51.** $61,377.75

53. (a) 10.24 yr (b) 9.93 yr (c) 9.90 yr (d) 9.90 yr

55. (a) $P = 2.098e^{-0.011t}$ (b) 1.51 million
(c) Because $k < 0$, the population is decreasing.

57. (a) $P = 6.373e^{0.012t}$ (b) 9.13 million
(c) Because $k > 0$, the population is increasing.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

59. (a) $N = 100.1596(1.2455)^t$ (b) 6.3 h

61. (a) Because the population increases by a constant each month, the rate of change from month to month will always be the same. So, the slope is constant, and the model is linear.

(b) Although the percentage increase is constant each month, the rate of growth is not constant. The rate of change of y is $\frac{dy}{dt} = ry$, which is an exponential model.

63. (a) $M_1 = 2679.5e^{0.038t}$ (b) $M_2 = 235.4t + 1473$

(c) The exponential model fits the data better because the graph is closer to the data values than is the graph of the linear model.

(d) 2025 ($t \approx 45$); Yes. The exponential model indicates a reasonably slow growth rate.

65. (a) 20 dB (b) 70 dB (c) 120 dB

67. (a) $y = 1420e^{[\ln(52/71)]t} + 80 \approx 1420e^{-0.3114t} + 80$

(b) 299.2°F

69. False. It takes 1599 years.

71. (a) $I = 10^{8.3} \approx 199{,}526{,}231.5$

(b) It increases by a factor of $e^{2R \ln 10}$ or 10^R.

(c) $\frac{dR}{dI} = \frac{1}{I \ln(10)}$

Section 6.3 *(page 429)*

1. (a) Separable (b) Not separable

3. The carrying capacity is the maximum population that can be sustained over time.

5. $y^2 - x^2 = C$ **7.** $y^4 - 2x^2 + 4x = C$ **9.** $r = Ce^{(4/9)s}$

11. $y = C(x + 2)^3$ **13.** $y^3 = C - \frac{1}{3}\cos 9x$

15. $y = -\frac{1}{4}\sqrt{1 - 4x^2} + C$ **17.** $y = Ce^{(\ln x)^2/2}$

19. $y^2 = 4e^x + 32$ **21.** $y = e^{-(x^2+2x)/2}$

23. $y^2 = 4x^2 + 3$ **25.** $u = e^{(5-\cos v^2)/2}$ **27.** $P = P_0e^{kt}$

29. $4y^2 - x^2 = 16$ **31.** $y = \left(\frac{x}{3}\right)^{1/5}$ **33.** $f(x) = Ce^{-x/2}$

35.



$y = \frac{1}{2}x^2 + C$

37. (a) $\frac{dy}{dx} = k(y - 4)$ (b) i (c) Proof

38. (a) $\frac{dy}{dx} = k(x - 4)$ (b) ii (c) Proof

39. (a) $\frac{dy}{dx} = ky(y - 4)$ (b) iii (c) Proof

40. (a) $\frac{dy}{dx} = ky^2$ (b) iv (c) Proof

41. (a) $y \approx 0.1602$ (b) $y = 5e^{-3x^2}$ (c) $y \approx 0.2489$; Error: $0.2489 - 0.1602 \approx 0.0887$

43. (a) $y \approx 3.0318$ (b) $y^3 - 4y = x^2 + 12x - 13$

(c) $y = 3$; Error: $3.0318 - 3 = 0.0318$

45. 97.9% of the original amount

47. (a) $w = 1200 - 1140e^{-kt}$

(b) $w = 1200 - 1140e^{-0.8t}$



$w = 1200 - 1140e^{-0.9t}$



$w = 1200 - 1140e^{-t}$



(c) 1.31 yr, 1.16 yr, 1.05 yr (d) 1200 lb

49. Hyperbolas: $3x^2 - y^2 = C$

Orthogonal trajectory: $y = \frac{K}{\sqrt[3]{x}}$

Graphs will vary.



51. Parabolas: $x^2 = Cy$

Ellipses: $x^2 + 2y^2 = K$

Graphs will vary.



53. Curves: $y^2 = Cx^3$

Ellipses: $2x^2 + 3y^2 = K$

Graphs will vary.



55. d **56.** a **57.** b **58.** c

59. (a) $k = 0.75$ (b) 2100 (c) 70 (d) 4.49 yr

(e) $\frac{dP}{dt} = 0.75P\left(1 - \frac{P}{2100}\right)$

61. (a) $k = 3$ (b) 100

(c)



(d) 50

63. $y = \frac{36}{1 + 8e^{-t}}$ **65.** $y = \frac{120}{1 + 14e^{-0.8t}}$

67. (a) $P = \frac{200}{1 + 7e^{-0.2640t}}$ (b) 70 panthers (c) 7.37 yr

(d) $\frac{dP}{dt} = 0.2640P\left(1 - \frac{P}{200}\right)$; 65.6; This is close to the exact answer.

(e) 7.37 years; P is increasing most rapidly where $P = 200/2 = 100$, which corresponds to $t \approx 7.37$ years.

69. Yes. Rewrite the equation as $\frac{1}{g(y) - h(y)}\,dy = f(x)\,dx$.

71. Proof

CHAPTER 6

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

73. (a) $v = 20(1 - e^{-1.386t})$
(b) $s \approx 20t + 14.43(e^{-1.386t} - 1)$

75. False. $y' = \dfrac{x}{y}$ is separable, but $y = 0$ is not a solution.

77. True

Section 6.4 *(page 436)*

1. The derivative in the equation is first order.

3. Linear; can be written in the form $\dfrac{dy}{dx} + P(x)y = Q(x)$

5. Not linear; cannot be written in the form $\dfrac{dy}{dx} + P(x)y = Q(x)$

7. $y = 2x^2 + x + \dfrac{C}{x}$ **9.** $y = 5 + Ce^{-x^2}$

11. $y = -1 + Ce^{\sin x}$ **13.** $y = \dfrac{1}{6}e^{3x} + Ce^{-3x}$

15. (a) Answers will vary. (b) $y = \frac{1}{2}(e^x + e^{-x})$

(c)





17. $y = 3e^x$ **19.** $y = \sin x + (x + 1)\cos x$ **21.** $xy = 4$

23. $y = -2 + x\ln|x| + 12x$ **25.** $P = -\dfrac{N}{k} + \left(\dfrac{N}{k} + P_0\right)e^{kt}$

27. (a) \$4,212,796.94 (b) \$31,424,909.75

29. (a) $\dfrac{dN}{dt} = k(75 - N)$ (b) $N = 75 + Ce^{-kt}$
(c) $N = 75 - 55.9296e^{-0.0168t}$

31. $v(t) = -49.1(1 - e^{-0.1996t})$; -49.1 m/sec

33. $I = \dfrac{E_0}{R} + Ce^{-Rt/L}$ **35.** Proof

37. (a) $Q = 25e^{-t/20}$ (b) $-20\ln\left(\frac{3}{5}\right) \approx 10.2$ min (c) 0

39. a **41.** Use separation of variables or an integrating factor.

43. c **44.** d **45.** a **46.** b

47. (a)



(c)



(b) $(-2, 4)$: $y = \frac{1}{2}x(x^2 - 8)$
$(2, 8)$: $y = \frac{1}{2}x(x^2 + 4)$

49. $2e^x + e^{-2y} = C$ **51.** $y = Ce^{-\sin x} + 1$

53. $y = \dfrac{e^x(x - 1) + C}{x^2}$ **55.** $y = \dfrac{12}{5}x^2 + \dfrac{C}{x^3}$

57. $\dfrac{1}{y^2} = Ce^{2x^3} + \dfrac{1}{3}$ **59.** $y = \dfrac{1}{Cx - x^2}$ **61.** $\dfrac{1}{y^2} = 2x + Cx^2$

63. $y^{2/3} = 2e^x + Ce^{2x/3}$ **65.** False. $y' + xy = x^2$ is linear.

Review Exercises for Chapter 6 *(page 439)*

1. (a) False. If $y = Ce^{kt}$, $y' = Cke^{kt} \neq$ constant. (b) True
(c) True

3. $y = 5$ is clearly a solution, because then $y' = y'' = 0$.

5. (a) At $x = 3.1$, $y \approx 3.925$
At $x = 3.2$, $y \approx 3.846$

(b)



(c) $y^2(x) = 25 - x^2$

(d) To check our answer, we can graph our solution and verify that it matches our slope field from part (b).

7. Solution **9.** $y = \frac{4}{3}x^3 + 7x + C$ **11.** $y = \frac{1}{2}\sin 2x + C$

13. $y = -e^{2-x} + C$

15. (a) and (b)



17.

n	0	1	2	3	4	5
x_n	0	0.05	0.1	0.15	0.2	0.25
y_n	4	3.8	3.6125	3.4369	3.2726	3.1190

n	6	7	8	9	10
x_n	0.3	0.35	0.4	0.45	0.5
y_n	2.9756	2.8418	2.7172	2.6038	2.4986

19.

x	-4	-2	0	2	4	8
y	2	0	4	4	6	8
dy/dx	-10	-4	-4	0	2	8

21. $y = 3x^2 - \dfrac{1}{4}x^4 + C$ **23.** $y = 1 - \dfrac{1}{x + C}$

25. $y = \dfrac{Ce^x}{(2 + x)^2}$ **27.** $y = Ce^{2\sqrt{x+1}}$

29. $\dfrac{dy}{dt} = \dfrac{k}{t^3}$, $y = -\dfrac{k}{2t^2} + C$ **31.** $y \approx \dfrac{3}{4}e^{0.379t}$

33. $y = \dfrac{9}{20}e^{(1/2)\ln(10/3)t}$ **35.** About 7.79 in.

37. About 37.5 yr

39. (a) $S \approx 30e^{-1.7918/t}$ (b) 20,965 units

41. $y^2 = 5x^2 + C$ **43.** $y = -\ln\left(C - \dfrac{e^{4x}}{4}\right)$

45. $y^4 = 6x^2 - 8$ **47.** $y^4 = 2x^4 + 1$ **49.** $y^2 = 2x^2 + 7$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

51. Hyperbolas: $5x^2 - 4y^2 = C$
Orthogonal trajectory: $y = Kx^{-4/5}$
Graphs will vary.



53. (a) $k = 0.55$ (b) 5250 (c) 150 (d) 6.41 yr
(e) $\dfrac{dP}{dt} = 0.55P\left(1 - \dfrac{P}{5250}\right)$

55. $y = \dfrac{80}{1 + 9e^{-t}}$ **57.** 184 racoons **59.** $y = -10 + Ce^x$

61. $y = e^{x/4}\left(\frac{1}{4}x + C\right)$ **63.** $y = \dfrac{x + C}{x - 2}$

65. $y = \dfrac{1}{10}e^{5x} + \dfrac{29}{10}e^{-5x}$ **67.** $y = -\frac{5}{3} + \frac{5}{3}e^{3\sin x}$

69. (a) *Sample answer:* $f(x) = 0$
(b) $f(x) = e^{\int \frac{g'(x)}{g'(x) - g(x)}dx} + C$
(c) When $g(x) = e^x$, $(f(x)g(x))' = e^x(f(x) + f'(x))$

71. (a) The function is homogeneous with a degree of 3.
(b) The function is homogeneous with a degree of 0.
(c) The function is not homogeneous.
(d) The function is not homogeneous.

P.S. Problem Solving *(page 442)*

1. (a) $y = \dfrac{1}{(1 - 0.01t)^{100}}$; $T = 100$
(b) $y = 1/\left[\left(\dfrac{1}{y_0}\right)^{\varepsilon} - k\varepsilon t\right]^{1/\varepsilon}$; Explanations will vary.

3. 1481.45 sec $\approx$ 24 min, 41 sec

5. 2575.95 sec $\approx$ 42 min, 56 sec

7. (a) $s = 184.21 - Ce^{-0.019t}$
(b)



(c) As $t \to \infty$, $Ce^{-0.019t} \to 0$, and $s \to 184.21$.

Chapter 7

Section 7.1 *(page 450)*

1. In variable x, the area of the region between two graphs is the area under the graph of the top function minus the area under the graph of the bottom function.

3. The points of intersection are used to determine the vertical lines that bound the region.

5. $-\displaystyle\int_0^6 (x^2 - 6x)\,dx$ **7.** $\displaystyle\int_0^3 (-2x^2 + 6x)\,dx$

9. $-6\displaystyle\int_0^1 (x^3 - x)\,dx$

11.



13.



15.



$\frac{13}{6}$

17.



$\frac{9}{2}$

19.



$\frac{17}{18}$

21.



$\frac{2}{3}$

23.



$\frac{9}{2}$

25.



6

27.



$10 \ln 5 \approx 16.094$

29. (a) $\frac{125}{6}$ (b) $\frac{125}{6}$
(c) Integrating with respect to y; Answers will vary.

31. (a)



(b) $\frac{37}{12}$

33. (a)



(b) 8

CHAPTER 7

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

35. (a)



(b) $\frac{\pi}{2} - \frac{1}{3} \approx 1.237$

37.



$4\pi \approx 12.566$

39.



$2(1 - \ln 2) \approx 0.614$

41.



$\frac{1}{2}\left(1 - \frac{1}{e}\right) \approx 0.316$

43. (a)



(b) 4

45. (a)



(b) About 1.323

47. (a)



(b) The function is difficult to integrate.

(c) About 4.7721

49. (a)



(b) The intersections are difficult to find.

(c) About 6.3043

51. 2

53. $F(x) = \frac{1}{4}x^2 + x$

(a) $F(0) = 0$



(b) $F(2) = 3$



(c) $F(6) = 15$



55. $F(\alpha) = \frac{2}{\pi}\left(\sin\frac{\pi\alpha}{2} + 1\right)$

(a) $F(-1) = 0$



(b) $F(0) = \frac{2}{\pi} \approx 0.6366$



(c) $F\left(\frac{1}{2}\right) = \frac{\sqrt{2}+2}{\pi} \approx 1.0868$



57. 3 **59.** 16 **61.** $\int_{-2}^{1} [(2x^3 - 1) - (6x - 5)]\,dx = \frac{27}{2}$

63. $\int_0^1 \left[\frac{1}{x^2+1} - \left(-\frac{1}{2}x + 1\right)\right] dx \approx 0.0354$

65. Answers will vary.

Example: $x^4 - 2x^2 + 1 \le 1 - x^2$ on $[-1, 1]$

$\int_{-1}^{1} [(1 - x^2) - (x^4 - 2x^2 + 1)]\,dx$

67. (a) The integral $\int_0^5 [v_1(t) - v_2(t)]\,dt = 10$ means that the first car traveled 10 more meters than the second car between 0 and 5 seconds.

The integral $\int_0^{10} [v_1(t) - v_2(t)]\,dt = 30$ means that the first car traveled 30 more meters than the second car between 0 and 10 seconds.

The integral $\int_{20}^{30} [v_1(t) - v_2(t)]\,dt = -5$ means that the second car traveled 5 more meters than the first car between 20 and 30 seconds.

(b) No. You do not know when both cars started or the initial distance between the cars.

(c) The car with velocity v_1 is ahead by 30 meters.

(d) Car 1 is ahead by 8 meters.

69. $b = 9\left(1 - \frac{1}{\sqrt[3]{4}}\right) \approx 3.330$ **71.** $a = 4 - 2\sqrt{2} \approx 1.172$

73. Answers will vary. *Sample answer*: $\frac{1}{6}$



75. R_1; \$1.625 million

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

77. (a) $y = 0.0124x^2 - 0.385x + 7.85$

(b)



(c)



For $6 \le x \le 100$, the values of y are larger for the model $y = x$.

(d) About 2006.7

79. (a) About 6.031 m^2 (b) About 12.062 m^3 (c) 60,310 lb

81. $\frac{\sqrt{3}}{2} + \frac{7\pi}{24} + 1 \approx 2.7823$ **83.** True

85. False. Let $f(x) = x$ and $g(x) = 2x - x^2$. Then f and g intersect at $(1, 1)$, the midpoint of $[0, 2]$, but

$$\int_a^b [f(x) - g(x)]\,dx = \int_0^2 [x - (2x - x^2)]\,dx = \tfrac{2}{3} \neq 0.$$

87. Putnam Problem A1, 1993

Section 7.2 *(page 461)*

1. Find the integral of the square of the radius of the solid over the defined interval and then multiply by π.

3. It is necessary when the solid of revolution is formed by two or more distinct solids.

5. $\pi\int_1^4 \left(\sqrt{x}\right)^2 dx = \frac{15\pi}{2}$ **7.** $\pi\int_0^1 [(x^2)^2 - (x^5)^2]\,dx = \frac{6\pi}{55}$

9. $\pi\int_0^4 \left(\sqrt{y}\right)^2 dy = 8\pi$ **11.** $\pi\int_0^1 (y^{3/2})^2\,dy = \frac{\pi}{4}$

13. (a) $\frac{9\pi}{2}$ (b) $\frac{36\pi\sqrt{3}}{5}$ (c) $\frac{24\pi\sqrt{3}}{5}$ (d) $\frac{84\pi\sqrt{3}}{5}$

15. (a) $\frac{32\pi}{3}$ (b) $\frac{64\pi}{3}$ **17.** 18π **19.** $\pi\left(16\ln 5 - \frac{16}{5}\right)$

21. $\frac{124\pi}{3}$ **23.** $\frac{832\pi}{15}$ **25.** $\frac{\pi}{3}\ln\frac{11}{5}$ **27.** 24π

29. $\pi\left(\frac{1 - e^{-12}}{6}\right)$ **31.** $\frac{277\pi}{3}$ **33.** 8π **35.** $\frac{25\pi}{2}$

37. $\frac{\pi^2}{2} \approx 4.935$ **39.** $\frac{\pi}{2}(e^2 - 1) \approx 10.036$ **41.** $\frac{2\pi}{3}$

43. $\frac{\pi}{3}$ **45.** $\frac{2\pi}{15}$ **47.** $\frac{\pi}{2}$ **49.** 1.969 **51.** 15.4115

53. (a) A sine curve on $\left[0, \frac{\pi}{2}\right]$ revolved about the x-axis

(b) A polynomial function on $[2, 4]$ revolved about the y-axis

55. b < c < a **57.** $\sqrt{5}$ **59.** $V = \frac{4}{3}\pi(R^2 - r^2)^{3/2}$

61. Proof **63.** $\pi r^2 h\left(1 - \frac{h}{H} + \frac{h^2}{3H^2}\right)$

65.



$\frac{2\pi}{15}\,m^3$

67. (a) 60π (b) 50π

69. (a) $V = \pi\left(4b^2 - \frac{64}{3}b + \frac{512}{15}\right)$

(b)



(c) $b = \frac{8}{3} \approx 2.67$

$b \approx 2.67$

71. (a) ii; right circular cylinder of radius r and height h

(b) iv; ellipsoid whose underlying ellipse has the equation $\left(\frac{x}{b}\right)^2 + \left(\frac{y}{a}\right)^2 = 1$

(c) iii; sphere of radius r

(d) i; right circular cone of radius r and height h

(e) v; torus of cross-sectional radius r and outer radius R

73. (a) $\frac{81}{10}$ (b) $\frac{9}{2}$ **75.** $\frac{16}{3}r^3$

77. (a) $\frac{2}{3}r^3$ (b) $\frac{2}{3}r^3\tan\theta$; As $\theta \to 90°$, $V \to \infty$.

Section 7.3 *(page 470)*

1. Determine the distance from the center of a representative rectangle to the axis of revolution, and find the height of the rectangle. Then use the formula $V = 2\pi\int_c^d p(y)h(y)\,dy$ for a horizontal axis of revolution or $V = 2\pi\int_a^b p(x)h(x)\,dx$ for a vertical axis of revolution.

3. $2\pi\int_0^2 x^2\,dx = \frac{16\pi}{3}$ **5.** $2\pi\int_0^4 x\sqrt{x}\,dx = \frac{128\pi}{5}$

7. $2\pi\int_0^4 \frac{1}{4}x^3\,dx = 32\pi$ **9.** $2\pi\int_0^2 x(4x - 2x^2)\,dx = \frac{16\pi}{3}$

11. $2\pi\int_{5/2}^4 x\sqrt{2x - 5}\,dx = \frac{34\pi\sqrt{3}}{5}$

13. $2\pi\int_0^2 y(2 - y)\,dy = \frac{8\pi}{3}$

15. $2\pi\left[\int_0^{1/2} y\,dy + \int_{1/2}^1 y\left(\frac{1}{y} - 1\right)dy\right] = \frac{\pi}{2}$

17. $2\pi\int_0^8 y^{4/3}\,dy = \frac{768\pi}{7}$ **19.** $2\pi\int_0^2 y(4 - 2y)\,dy = \frac{16\pi}{3}$

21. $\int_0^1 y(y^2 - 3y + 2)\,dy = \frac{\pi}{2}$

23. 8π **25.** $\frac{45\pi}{16}$

27. Shell method; It is much easier to put x in terms of y rather than vice versa.

29. (a) $\frac{128\pi}{7}$ (b) $\frac{64\pi}{5}$ (c) $\frac{96\pi}{5}$

31. (a) $\frac{\pi a^3}{15}$ (b) $\frac{\pi a^3}{15}$ (c) $\frac{4\pi a^3}{15}$

CHAPTER 7

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

33. (a) 

(b) 1.506

35. (a) 

(b) 187.25

37. (a) Height: b, radius: k (b) Height: k, radius: b

39. Both integrals yield the volume of the solid generated by revolving the region bounded by the graphs of $y = \sqrt{x-1}$, $y = 0$, and $x = 5$ about the x-axis.

41. a, c, b

43. (a) Region bounded by $y = x^2$, $y = 0$, $x = 0$, $x = 2$
(b) Revolved about the y-axis

45. (a) Region bounded by $x = \sqrt{6-y}$, $y = 0$, $x = 0$
(b) Revolved about $y = -2$

47. Diameter $= 2\sqrt{4 - 2\sqrt{3}} \approx 1.464$ **49.** $4\pi^2$

51. (a) Proof (b) (i) $V = 2\pi$ (ii) $V = 6\pi^2$ **53.** Proof

55. (a) $R_1(n) = \dfrac{n}{n+1}$ (b) $\lim\limits_{n\to\infty} R_1(n) = 1$
(c) $V = \pi ab^{n+2}\left(\dfrac{n}{n+2}\right)$; $R_2(n) = \dfrac{n}{n+2}$
(d) $\lim\limits_{n\to\infty} R_2(n) = 1$
(e) As $n \to \infty$, the graph approaches the line $x = b$.

57. About 121,475 ft^3 **59.** $c = 2$

61. (a) $\dfrac{64\pi}{3}$ (b) $\dfrac{2048\pi}{35}$ (c) $\dfrac{8192\pi}{105}$

Section 7.4 *(page 481)*

1. The graph of a function f is rectifiable between $(a, f(a))$ and $(b, f(b))$ if f' is continuous on $[a, b]$.

3. Answers will vary by a constant. *Sample answer*: $f(x) = 2x^2$

5. (a) and (b) $\sqrt{13}$ **7.** $\frac{5}{3}$ **9.** $\frac{2}{3}\left(2\sqrt{2} - 1\right) \approx 1.219$

11. $5\sqrt{5} - 2\sqrt{2} \approx 8.352$ **13.** 309.3195

15. $\ln \dfrac{\sqrt{2}+1}{\sqrt{2}-1} \approx 1.763$ **17.** $\dfrac{1}{2}\left(e^2 - \dfrac{1}{e^2}\right) \approx 3.627$

19. $\dfrac{76}{3}$

21. (a) 

(b) $\displaystyle\int_0^2 \sqrt{1 + 4x^2}\,dx$
(c) About 4.647

23. (a) 

(b) $\displaystyle\int_1^3 \sqrt{1 + \frac{1}{x^4}}\,dx$
(c) About 2.147

25. (a) 

(b) $\displaystyle\int_0^{\pi} \sqrt{1 + \cos^2 x}\,dx$
(c) About 3.820

27. (a) 

(b) $\displaystyle\int_0^1 \sqrt{1 + \left(\frac{2}{1+x^2}\right)^2}\,dx$
(c) About 1.871

29. (a) 

(b) $\displaystyle\int_0^2 \sqrt{1 + e^{-2y}}\,dy = \int_{e^{-2}}^1 \sqrt{1 + \frac{1}{x^2}}\,dx$
(c) About 2.221

31. (a) 64.125 (b) 64.525 (c) 64.672

33. $\dfrac{20(e^2-1)}{e} \approx 47.0$ m **35.** About 1480

37. $3 \arcsin \frac{2}{3} \approx 2.1892$

39. $2\pi\displaystyle\int_0^3 \frac{1}{3}x^3\sqrt{1+x^4}\,dx = \frac{\pi}{9}\left(82\sqrt{82} - 1\right) \approx 258.85$

41. $2\pi\displaystyle\int_1^2 \left(\frac{x^3}{6} + \frac{1}{2x}\right)\left(\frac{x^2}{2} + \frac{1}{2x^2}\right)dx = \frac{47\pi}{16} \approx 9.23$

43. $2\pi\displaystyle\int_{-1}^1 2\,dx = 8\pi \approx 25.13$

45. $2\pi\displaystyle\int_1^8 x\sqrt{1 + \frac{1}{9x^{4/3}}}\,dx = \frac{\pi}{27}\left(145\sqrt{145} - 10\sqrt{10}\right) \approx 199.48$

47. $2\pi\displaystyle\int_0^2 x\sqrt{1 + \frac{x^2}{4}}\,dx = \frac{\pi}{3}\left(16\sqrt{2} - 8\right) \approx 15.318$

49. 14.424 **51.** b **53.** They have the same value.

55. (a) 

(b) y_1, y_2, y_3, y_4
(c) $s_1 \approx 5.657$, $s_2 \approx 5.759$, $s_3 \approx 5.916$, $s_4 \approx 6.063$

57. 20π **59.** $6\pi\left(3 - \sqrt{5}\right) \approx 14.40$

61. (a) Answers will vary. *Sample answer*: 5207.62 in.^{3}
(b) Answers will vary. *Sample answer*: 1168.64 in.^{2}
(c) $r = 0.0040y^3 - 0.142y^2 + 1.23y + 7.9$



(d) $V = 5279.64$ in.^{3}, $S = 1179.5$ in.^{2}

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

63. (a) $\pi\left(1-\frac{1}{b}\right)$ (b) $2\pi\int_1^b \frac{\sqrt{x^4+1}}{x^3}\,dx$

(c) $\lim_{b\to\infty} V = \lim_{b\to\infty} \pi\left(1-\frac{1}{b}\right) = \pi$

(d) Because $\frac{\sqrt{x^4+1}}{x^3} > \frac{\sqrt{x^4}}{x^3} = \frac{1}{x} > 0$ on $[1, b]$, you have $\int_1^b \frac{\sqrt{x^4+1}}{x^3}\,dx > \int_1^b \frac{1}{x}\,dx = \left[\ln x\right]_1^b = \ln b$ and $\lim_{b\to\infty} \ln b \to \infty$. So, $\lim_{b\to\infty} 2\pi\int_1^b \frac{\sqrt{x^4+1}}{x^3}\,dx = \infty$.

65. (a) Fleeing object: $\frac{2}{3}$ unit

Pursuer: $\frac{1}{2}\int_0^1 \frac{x+1}{\sqrt{x}}\,dx$

(b) The integral does not satisfy the definition of a definite integral because the integrand is not defined at 0.

(c) Using a graphing utility: $\frac{1}{2}\int_0^1 \frac{x+1}{\sqrt{x}}\,dx = \frac{4}{3}$

$\frac{4}{3} = 2\left(\frac{2}{3}\right)$, so the pursuer has traveled twice the distance that the fleeing object has traveled when it is caught.

67. (a) $s = 2\pi\int_0^8 x\sqrt{\frac{4}{x^{2/3}}}\,dx$

(b) The integral does not satisfy the definition of a definite integral because the integrand is not defined at 0.

(c) Using a graphing utility: $2\pi\int_0^8 x\sqrt{\frac{4}{x^{2/3}}}\,dx = \frac{384\pi}{5}$

The surface area is $\frac{384\pi}{5}$ square units.

69. Proof **71.** Proof; $g(x) = 1$

Section 7.5 *(page 491)*

1. Work is done by a force when it moves an object.

3. In Hooke's Law, F is the force required to compress or stretch a spring, d is the distance that the spring is compressed or stretched from its original length, and k is the constant of proportionality, dependent upon the specific nature of the spring.

5. 48,000 ft-lb **7.** 896 N-m

9. 40.833 in.-lb $\approx$ 3.403 ft-lb

11. 160 in.-lb $\approx$ 13.3 ft-lb **13.** 37.125 ft-lb

15. (a) 487.8 mile-tons $\approx 5.151 \times 10^9$ ft-lb

(b) 1395.3 mile-tons $\approx 1.473 \times 10^{10}$ ft-lb

17. (a) 29,333.3 mile-tons $\approx 3.098 \times 10^{11}$ ft-lb

(b) 33,846.2 mile-tons $\approx 3.574 \times 10^{11}$ ft-lb

19. (a) 2496 ft-lb (b) 9984 ft-lb

21. 470,400π N-m **23.** 2995.2π ft-lb

25. 20,217.6π ft-lb **27.** 2457π ft-lb

29. 600 ft-lb **31.** 450 ft-lb **33.** 168.75 ft-lb

35. No. Something can require a lot of physical effort but take no work. There is no work because there is no change in distance.

37. $Gm_1m_2\left(\frac{1}{a}-\frac{1}{b}\right)$ **39.** $\frac{3k}{4}$

41. (a) 54 ft-lb (b) 160 ft-lb

(c) 9 ft-lb (d) 18 ft-lb

43. 2000 ln $\frac{3}{2} \approx$ 810.93 ft-lb **45.** 3249.4 ft-lb

47. 10,330.3 ft-lb

49. (a) 16,000π ft-lb

(b) $F(x) = -16{,}261.36x^4 + 82{,}295.45x^3 - 157{,}738.64x^2 + 104{,}386.36x - 32.4675$



(c) 0.524 ft (d) 25,180.5 ft-lb

Section 7.6 *(page 502)*

1. Weight is a force that is dependent on gravity. Mass is a measure of a body's resistance to changes in motion and is independent of the gravitational system in which the body is located. The weight (or force) of an object is its mass times the acceleration due to gravity.

3. A planar lamina is a flat plate of material of constant density. The center of mass of a lamina is its balancing point.

5. $\bar{x} = -\frac{4}{3}$ **7.** $\bar{x} = 4$ **9.** $x = 6$ ft

11. $(\bar{x}, \bar{y}) = \left(\frac{10}{9}, -\frac{1}{9}\right)$ **13.** $(\bar{x}, \bar{y}) = \left(2, \frac{48}{25}\right)$

15. $M_x = \frac{\rho}{3}, M_y = \frac{4\rho}{3}, \quad (\bar{x}, \bar{y}) = \left(\frac{4}{3}, \frac{1}{3}\right)$

17. $M_x = 4\rho, M_y = \frac{64\rho}{5}, \quad (\bar{x}, \bar{y}) = \left(\frac{12}{5}, \frac{3}{4}\right)$

19. $M_x = \frac{\rho}{35}, M_y = \frac{\rho}{20}, \quad (\bar{x}, \bar{y}) = \left(\frac{3}{5}, \frac{12}{35}\right)$

21. $M_x = \frac{99\rho}{5}, M_y = \frac{27\rho}{4}, \quad (\bar{x}, \bar{y}) = \left(\frac{3}{2}, \frac{22}{5}\right)$

23. $M_x = \frac{192\rho}{7}, M_y = 96\rho, \quad (\bar{x}, \bar{y}) = \left(5, \frac{10}{7}\right)$

25. $M_x = 0, M_y = \frac{256\rho}{15}, \quad (\bar{x}, \bar{y}) = \left(\frac{8}{5}, 0\right)$

27. $M_x = \frac{27\rho}{4}, M_y = -\frac{27\rho}{10}, \quad (\bar{x}, \bar{y}) = \left(-\frac{3}{5}, \frac{3}{2}\right)$

29.



$(\bar{x}, \bar{y}) = (0, 16.2)$

31.



$(\bar{x}, \bar{y}) = \left(\frac{4+3\pi}{4+\pi}, 0\right)$

33.



$(\bar{x}, \bar{y}) = \left(0, \frac{135}{34}\right)$

35. $(\bar{x}, \bar{y}) = \left(\frac{2+3\pi}{2+\pi}, 0\right)$ **37.** $160\pi^2 \approx 1579.14$

39. $\frac{128\pi}{3} \approx 134.04$

41. The center of mass is translated k units as well.

CHAPTER 7

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

43. Answers will vary. *Sample answer*: Use three rectangles with width 1 and length 4 and place them as follows.



$(\bar{x}, \bar{y}) = (3, 1.5)$

45. $(\bar{x}, \bar{y}) = \left(\frac{b}{3}, \frac{c}{3}\right)$ **47.** $(\bar{x}, \bar{y}) = \left(\frac{(a + 2b)c}{3(a + b)}, \frac{a^2 + ab + b^2}{3(a + b)}\right)$

49. $(\bar{x}, \bar{y}) = \left(0, \frac{4b}{3\pi}\right)$

51. (a)



(b) $M_y = \int_{-\sqrt{b}}^{\sqrt{b}} x(b - x^2)\,dx = 0$ because $x(b - x^2)$ is an odd function; $\bar{x} = 0$ by symmetry.

(c) $\bar{y} > \frac{b}{2}$ because the area is greater for $y > \frac{b}{2}$.

(d) $\bar{y} = \frac{3}{5}b$

53. (a) $y = (-1.02 \times 10^{-5})x^4 - 0.0019x^2 + 29.28$

(b) $(\bar{x}, \bar{y}) = (0, 12.85)$

55. $9\pi\sqrt{2}$

57. $(\bar{x}, \bar{y}) = \left(\frac{n + 1}{n + 2}, \frac{n + 1}{4n + 2}\right)$; As $n \to \infty$, the region shrinks toward the line segments $y = 0$ for $0 \le x \le 1$ and $x = 1$ for $0 \le y \le 1$; $(\bar{x}, \bar{y}) \to \left(1, \frac{1}{4}\right)$.

59. Putnam Problem A1, 1982

Section 7.7 *(page 509)*

1. Fluid pressure is the force per unit area over the surface of a body submerged in a fluid.

3. 1497.6 lb **5.** 4992 lb **7.** 2223 lb **9.** 1123.2 lb

11. 748.8 lb **13.** 1064.96 lb **15.** 117,600 N

17. 2,381,400 N **19.** 2814 lb **21.** 6753.6 lb

23. 94.5 lb

25. Because you are measuring total force against a region between two depths

27. $\frac{3\sqrt{2}}{2} \approx 2.12$ ft; The pressure increases with increasing depth.

29–31. Proofs **33.** 960 lb **35.** 2936 lb

Review Exercises for Chapter 7 *(page 511)*

1. (a) $V = \pi R^2 w$

(b) $V = \pi(R^2 - r^2)w$

(c) $V = 2\pi phw$

(d) $S = 2\pi rL$ where $r = \frac{1}{2}(r_1 + r_2)$

3. d **5.** Proof

7.



$\frac{64}{3}$

9.



$\frac{\pi}{2}$

11.



$\frac{1}{2}$

13.



$e^2 + 1$

15.



$2\sqrt{2}$

17. (a)



(b) 170.6667

19. (a)



(b) 0.1667

21. $F(x) = \frac{3}{2}x^2 + x$

(a) $F(0) = 0$



(b) $F(2) = 8$



(c) $F(6) = 60$



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

23. R_1; \$1.125 million **25.** $\frac{\pi^2}{2}$ **27.** $\frac{\pi^2}{4}$

29. (a) 9π (b) 18π (c) 9π (d) 36π

31. $64\pi \approx 201.1$ ft^3 **33.** $\frac{8}{15}\left(1 + 6\sqrt{3}\right) \approx 6.076$

35. $2\pi\int_3^6 \frac{x^3}{18}\sqrt{1 + \frac{x^4}{36}}\,dx \approx 459.098$

37. $2\pi\int_0^2 x\sqrt{1 + x^2}\,dx \approx 21.322$ **39.** 5.208 ft-lb

41. 952.4 mile-tons $\approx 1.109 \times 10^{10}$ ft-lb **43.** 200 ft-lb

45. 693.15 ft-lb

47. 3.6 **49.** $M_x = \frac{544\rho}{15}$, $M_y = \frac{32\rho}{3}$, $(\bar{x}, \bar{y}) = \left(1, \frac{17}{5}\right)$

51. $V = 32\pi^2$

53. 374.4 lb **55.** 3072 lb **57.** 723,822.95 lb

59. (a) $\frac{ds}{dx} = \sqrt{1 + (f'(x))^2}$

(b) $ds = \sqrt{1 + (f'(x))^2} - \sqrt{1 + (f'(a))^2}$

$(ds)^2 = \left(\sqrt{1 + (f'(x))^2} - \sqrt{1 + (f'(a))^2}\right)^2$

(c) 4.66

(d) 2.09; This value represents the area under the curve, $ds/dx = \sqrt{1 + \left(\left(\frac{3}{2}x^{1/2}\right)\right)^2}$, from 1 to 2.

P.S. Problem Solving *(page 514)*

1. (a) By symmetry, $M_x = 0$ for L

(b) Because

$(M_y \text{ for } L) + (M_y \text{ for } A) = (M_y \text{ for } B)$,

you have

$(M_y \text{ for } L) = (M_y \text{ for } B) - (M_y \text{ for } A)$

(c) M_y for $B = 0$

M_y for $A = \pi r^3$

M_y for $L = -\pi r^3$

(d) $\left(-\frac{r}{3}, 0\right)$

3. 89.3% **5.** $(\bar{x}, \bar{y}) = \left(\frac{2(9\pi + 49)}{3(\pi + 9)}, 0\right)$

7. $V = 2\pi\left(d + \frac{1}{2}\sqrt{w^2 + l^2}\right)lw$

Chapter 8

Section 8.1 *(page 520)*

1. Use long division to rewrite the function as the sum of a polynomial and a proper rational function.

3. b

5. $\int u^n\,du$; $u = 5x - 3$, $n = 4$ **7.** $\int \frac{du}{u}$; $u = 1 - 2\sqrt{x}$ **9.** $\int \frac{du}{\sqrt{a^2 - u^2}}$; $u = t$, $a = 1$

11. $\int \sin u\,du$; $u = t^2$ **13.** $\int e^u\,du$; $u = \sin x$ **15.** $2(x - 5)^7 + C$

17. $-\frac{7}{6(z - 10)^6} + C$ **19.** $\frac{z^3}{3} - \frac{1}{5(z - 1)^5} + C$

21. $-\frac{1}{3}\ln|-t^3 + 9t + 1| + C$ **23.** $\frac{1}{2}x^2 + x + \ln|x - 1| + C$

25. $x + \ln|x + 1| + C$ **27.** $\frac{x}{15}(48x^4 + 200x^2 + 375) + C$

29. $\frac{\sin 2\pi x^2}{4\pi} + C$ **31.** $-2\sqrt{\cos x} + C$

33. $2\ln(1 + e^x) + C$ **35.** $(\ln x)^2 + C$

37. $-\ln|\csc\alpha + \cot\alpha| + \ln|\sin\alpha| + C$

39. $-\frac{1}{4}\arcsin(4t + 1) + C$ **41.** $\frac{1}{2}\ln\left|\cos\frac{2}{t}\right| + C$

43. $\frac{6}{5}\operatorname{arcsec}\frac{|3z|}{5} + C$ **45.** $\frac{1}{4}\arctan\frac{2x + 1}{8} + C$

47. (a)



(b) $\frac{1}{2}\arcsin t^2 - \frac{1}{2}$



49. $y = 4e^{0.8x}$



51. $y = \frac{1}{2}e^{2x} + 10e^x + 25x + C$ **53.** $r = 10\arcsin e^t + C$

55. $y = \frac{1}{2}\arctan\frac{\tan x}{2} + C$ **57.** $\frac{1}{15}$ **59.** $\frac{1}{2}$

61. $\frac{1}{2}(1 - e^{-1}) \approx 0.316$ **63.** $\frac{3}{2}[(\ln 4)^2 - (\ln 3)^2] \approx 1.072$

65. 8 **67.** $\ln 9 + \frac{8}{3} \approx 4.864$ **69.** $\frac{\pi}{18}$

71. $\frac{240}{\ln 3} \approx 218.457$

73. $\frac{1}{3}\arctan\left[\frac{1}{3}(x + 2)\right] + C$

Graphs will vary.

Example:



One graph is a vertical translation of the other.

75. $\tan\theta - \sec\theta + C$

Graphs will vary.

Example:



One graph is a vertical translation of the other.

77. $\frac{18\sqrt{6}}{5} \approx 8.82$ **79.** $\frac{4}{3} \approx 1.333$

81. No. When $u = x^2$, it does not follow that $x = \sqrt{u}$ because x is negative on $[-1, 0)$.

83. $a = \sqrt{2}$, $b = \frac{\pi}{4}$; $-\frac{1}{\sqrt{2}}\ln\left|\csc\left(x + \frac{\pi}{4}\right) + \cot\left(x + \frac{\pi}{4}\right)\right| + C$

85. (a) They are equivalent because

$e^{x + C_1} = e^x \cdot e^{C_1} = Ce^x$, $C = e^{C_1}$.

(b) They differ by a constant.

$\sec^2 x + C_1 = (\tan^2 x + 1) + C_1 = \tan^2 x + C$

87. a

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

89. (a)



(b)



(c)



91. (a) $\pi(1 - e^{-1}) \approx 1.986$

(b) $b = \sqrt{\ln \dfrac{3\pi}{3\pi - 4}} \approx 0.743$

93. $\ln\left(\sqrt{2} + 1\right) \approx 0.8814$

95. $\dfrac{8\pi}{3}\left(10\sqrt{10} - 1\right) \approx 256.545$ **97.** $\dfrac{1}{3}\arctan 3 \approx 0.416$

99. About 1.0320

101. (a) $\frac{1}{3}\sin x(\cos^2 x + 2)$

(b) $\frac{1}{15}\sin x(3\cos^4 x + 4\cos^2 x + 8)$

(c) $\frac{1}{35}\sin x(5\cos^6 x + 6\cos^4 x + 8\cos^2 x + 16)$

(d) $\displaystyle\int \cos^{15} x\,dx = \int (1 - \sin^2 x)^7 \cos x\,dx$

You would expand $(1 - \sin^2 x)^7$.

103. Proof

Section 8.2 *(page 529)*

1. The formula for the derivative of a product

3. Let $dv = dx$. **5.** $u = x$, $dv = e^{9x}\,dx$

7. $u = (\ln x)^2$, $dv = dx$ **9.** $u = x$, $dv = \sec^2 x\,dx$

11. $\frac{1}{16}x^4(4\ln x - 1) + C$

13. $-\frac{1}{4}(2x + 1)\cos 4x + \frac{1}{8}\sin 4x + C$

15. $\dfrac{e^{4x}}{16}(4x - 1) + C$ **17.** $e^x(x^3 - 3x^2 + 6x - 6) + C$

19. $\frac{1}{4}[2(t^2 - 1)\ln|t + 1| - t^2 + 2t] + C$ **21.** $\frac{1}{3}(\ln x)^3 + C$

23. $\dfrac{e^{2x}}{4(2x + 1)} + C$ **25.** $\dfrac{2}{15}(x - 5)^{3/2}(3x + 10) + C$

27. $-x\cot x + \ln|\sin x| + C$

29. $(6x - x^3)\cos x + (3x^2 - 6)\sin x + C$

31. $x\arctan x - \frac{1}{2}\ln(1 + x^2) + C$

33. $-\frac{3}{34}e^{-3x}\sin 5x - \frac{5}{34}e^{-3x}\cos 5x + C$

35. $x\ln x - x + C$

37. $y = \dfrac{2}{5}t^2\sqrt{3 + 5t} - \dfrac{8t}{75}(3 + 5t)^{3/2} + \dfrac{16}{1875}(3 + 5t)^{5/2} + C$

$= \dfrac{2}{625}\sqrt{3 + 5t}(25t^2 - 20t + 24) + C$

39. (a)



(b) $2\sqrt{y} - \cos x - x\sin x = 3$



41.



43. $2e^{3/2} + 4 \approx 12.963$ **45.** $\dfrac{\pi}{8} - \dfrac{1}{4} \approx 0.143$

47. $\dfrac{\pi - 3\sqrt{3} + 6}{6} \approx 0.658$

49. $\frac{1}{2}[e(\sin 1 - \cos 1) + 1] \approx 0.909$

51. $8\,\text{arcsec}\,4 + \dfrac{\sqrt{3}}{2} - \dfrac{\sqrt{15}}{2} - \dfrac{2\pi}{3} \approx 7.380$

53. $\dfrac{e^{2x}}{4}(2x^2 - 2x + 1) + C$

55. $-\cos x(x + 2)^2 + 2\sin x(x + 2) + 2\cos x + C$

57. $\frac{1}{20}(4x + 9)^{3/2}(2x + 17) + C$

59. Answers will vary. *Sample answer:* $\int x^3 \sin x\,dx$

It takes three applications until the algebraic factor becomes a constant.

61. (a) No, substitution (b) Yes, $u = \ln x$, $dv = x\,dx$

(c) Yes, $u = x^2$, $dv = e^{-3x}\,dx$ (d) No, substitution

(e) Yes, $u = x$, $dv = \dfrac{1}{\sqrt{x + 1}}\,dx$ (f) No, substitution

63. $2\left(\sin\sqrt{x} - \sqrt{x}\cos\sqrt{x}\right) + C$

65. $\frac{1}{2}\left(x^4e^{x^2} - 2x^2e^{x^2} + 2e^{x^2}\right) + C$

67. (a) and (b) $\frac{1}{3}\sqrt{4 + x^2}(x^2 - 8) + C$

69. $n = 0$: $x(\ln x - 1) + C$

$n = 1$: $\frac{1}{4}x^2(2\ln x - 1) + C$

$n = 2$: $\frac{1}{9}x^3(3\ln x - 1) + C$

$n = 3$: $\frac{1}{16}x^4(4\ln x - 1) + C$

$n = 4$: $\frac{1}{25}x^5(5\ln x - 1) + C$

$\displaystyle\int x^n \ln x\,dx = \frac{x^{n+1}}{(n + 1)^2}[(n + 1)\ln x - 1] + C$

71–75. Proofs **77.** $-x^2\cos x + 2x\sin x + 2\cos x + C$

79. $\frac{1}{36}x^6(6\ln x - 1) + C$

81. $\dfrac{e^{-3x}(-3\sin 4x - 4\cos 4x)}{25} + C$

83.



$2 - \dfrac{8}{e^3} \approx 1.602$

85.



$\dfrac{\pi}{1 + \pi^2}\left(\dfrac{1}{e} + 1\right) \approx 0.395$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

87. (a) 1 (b) $\pi(e-2) \approx 2.257$ (c) $\frac{1}{2}\pi(e^2+1) \approx 13.177$
(d) $\left(\frac{e^2+1}{4}, \frac{e-2}{2}\right) \approx (2.097, 0.359)$

89. In Example 7, we showed that the centroid of an equivalent region was $\left(1, \frac{\pi}{8}\right)$. By symmetry, the centroid of this region is $\left(\frac{\pi}{8}, 1\right)$.

91. $\frac{7}{10\pi}(1 - e^{-4\pi}) \approx 0.223$ **93.** \$931,265

95. Proof **97.** $b_n = \frac{8h}{(n\pi)^2}\sin\frac{n\pi}{2}$

99. For any integrable function, $\int f(x)\,dx = C + \int f(x)\,dx$, but this cannot be used to imply that $C = 0$.

Section 8.3 *(page 538)*

1. $\int \sin^8 x\,dx$; The other integral can be found using u-substitution.
3. $-\frac{1}{6}\cos^6 x + C$ **5.** $\frac{1}{5}\sin^5 x - \frac{1}{7}\sin^7 x + C$
7. $-\frac{1}{3}\cos^3 x + \frac{1}{5}\cos^5 x + C$
9. $-\frac{1}{3}(\cos 2\theta)^{3/2} + \frac{1}{7}(\cos 2\theta)^{7/2} + C$
11. $\frac{1}{12}(6x + \sin 6x) + C$ **13.** $2x^2 + 2x\sin 2x + \cos 2x + C$
15. $\frac{2}{3}$ **17.** $\frac{\pi}{4}$ **19.** $\frac{63\pi}{512}$ **21.** $\frac{1}{4}\ln|\sec 4x + \tan 4x| + C$
23. $\frac{\sec \pi x \tan \pi x + \ln|\sec \pi x + \tan \pi x|}{2\pi} + C$
25. $\frac{1}{2}\tan^4\frac{x}{2} - \tan^2\frac{x}{2} - 2\ln\left|\cos\frac{x}{2}\right| + C$
27. $\frac{1}{2}\left[\frac{\sec^5 2t}{5} - \frac{\sec^3 2t}{3}\right] + C$ **29.** $\frac{1}{24}\sec^6 4x + C$
31. $\frac{1}{7}\sec^7 x - \frac{1}{5}\sec^5 x + C$
33. $\ln|\sec x + \tan x| - \sin x + C$
35. $\frac{12\pi\theta - 8\sin 2\pi\theta + \sin 4\pi\theta}{32\pi} + C$
37. $y = \frac{1}{9}\sec^3 3x - \frac{1}{3}\sec 3x + C$
39. (a)



(b) $y = \frac{1}{2}x - \frac{1}{4}\sin 2x$



41.



43. $\frac{1}{16}(2\sin 4x + \sin 8x) + C$
45. $\frac{1}{14}\cos 7t - \frac{1}{22}\cos 11t + C$
47. $\frac{1}{8}(2\sin 2\theta - \sin 4\theta) + C$
49. $\frac{1}{4}(\ln|\csc^2 2x| - \cot^2 2x) + C$
51. $-\frac{1}{3}\cot 3x - \frac{1}{9}\cot^3 3x + C$
53. $\ln|\csc t - \cot t| + \cos t + C$
55. $\ln|\csc x - \cot x| + \cos x + C$ **57.** $t - 2\tan t + C$
59. π **61.** $3(1 - \ln 2)$ **63.** $\ln 2$ **65.** 4
67. (a) $\frac{1}{18}\tan^6 3x + \frac{1}{12}\tan^4 3x + C_1$, $\frac{1}{18}\sec^6 3x - \frac{1}{12}\sec^4 3x + C_2$
(b)



(c) Proof
69. (a) $\frac{1}{2}\sin^2 x + C$ (b) $-\frac{1}{2}\cos^2 x + C$
(c) $\frac{1}{2}\sin^2 x + C$ (d) $-\frac{1}{4}\cos 2x + C$
The answers are all the same, but they are written in different forms. Using trigonometric identities, you can rewrite each answer in the same form.
71. $\frac{1}{3}$ **73.** 1 **75.** $2\pi\left(1 - \frac{\pi}{4}\right) \approx 1.348$
77. (a) $\frac{\pi^2}{2}$ (b) $(\bar{x}, \bar{y}) = \left(\frac{\pi}{2}, \frac{\pi}{8}\right)$ **79–81.** Proofs
83. $-\frac{1}{15}\cos x(3\sin^4 x + 4\sin^2 x + 8) + C$
85. $-\frac{1}{48}(8\cos^3 x \sin^3 x + 6\cos^3 x \sin x - 3\cos x \sin x - 3x) + C$
87. (a) and (b) Proofs **89.** Proof

Section 8.4 *(page 547)*

1. (a) $x = 3\tan\theta$ (b) $x = 2\sin\theta$
(c) $x = 5\sin\theta$ (d) $x = 5\sec\theta$
3. $\frac{x}{16\sqrt{16 - x^2}} + C$
5. $4\ln\left|\frac{4 - \sqrt{16 - x^2}}{x}\right| + \sqrt{16 - x^2} + C$
7. $\ln\left|x + \sqrt{x^2 - 25}\right| + C$
9. $\frac{1}{15}(x^2 - 25)^{3/2}(3x^2 + 50) + C$
11. $\frac{(4 + x^2)^{3/2}}{6} + C$ **13.** $\frac{1}{4}\left(\arctan\frac{x}{2} + \frac{2x}{4 + x^2}\right) + C$
15. $\frac{1}{2}x\sqrt{49 - 16x^2} + \frac{49}{8}\arcsin\frac{4x}{7} + C$
17. $\frac{1}{2\sqrt{5}}\left(\sqrt{5}x\sqrt{36 - 5x^2} + 36\arcsin\frac{\sqrt{5}x}{6}\right) + C$
19. $4\arcsin\frac{x}{2} + x\sqrt{4 - x^2} + C$ **21.** $-\frac{(1 - x^2)^{3/2}}{3x^3} + C$
23. $-\frac{1}{3}\ln\left|\frac{\sqrt{4x^2 + 9} + 3}{2x}\right| + C$ **25.** $-\frac{x}{\sqrt{x^2 + 3}} + C$
27. $\frac{1}{2}\left(\arcsin e^x + e^x\sqrt{1 - e^{2x}}\right) + C$
29. $\frac{1}{4}\left(\frac{x}{x^2 + 2} + \frac{1}{\sqrt{2}}\arctan\frac{x}{\sqrt{2}}\right) + C$
31. $x\,\text{arcsec}\,2x - \frac{1}{2}\ln\left|2x + \sqrt{4x^2 - 1}\right| + C$
33. $2\arcsin\frac{x - 2}{2} - \sqrt{4x - x^2} + C$
35. $\sqrt{x^2 + 6x + 12} - 3\ln\left|\sqrt{x^2 + 6x + 12} + (x + 3)\right| + C$
37. (a) and (b) $\sqrt{3} - \frac{\pi}{3} \approx 0.685$
39. (a) and (b) $9\left(2 - \sqrt{2}\right) \approx 5.272$
41. (a) and (b) $-\frac{9}{2}\ln\left(\frac{2\sqrt{7}}{3} - \frac{4\sqrt{3}}{3} - \frac{\sqrt{21}}{3} + \frac{8}{3}\right) + 9\sqrt{3} - 2\sqrt{7} \approx 12.644$

CHAPTER 8

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

43. True **45.** False. $\displaystyle\int_0^{\sqrt{3}} \frac{dx}{(1+x^2)^{3/2}} = \int_0^{\pi/3} \cos\theta\, d\theta$

47. Substitution: $u = x^2 + 1$, $du = 2x\,dx$

49. (a) $-\sqrt{1-x^2} + C$; The answers are equivalent.

(b) $x - 3\arctan\dfrac{x}{3} + C$; The answers are equivalent.

51. πab

53. $\ln\dfrac{5\left(\sqrt{2}+1\right)}{\sqrt{26}+1} + \sqrt{26} - \sqrt{2} \approx 4.367$ **55.** $6\pi^2$

57. (0, 0.422)

59. (a) $V = \dfrac{3\pi}{2} + 3\arcsin(d-1) + 3(d-1)\sqrt{2d-d^2}$

(b)



(c) The full tank holds $3\pi \approx 9.4248$ cubic meters. The horizontal lines

$y = \dfrac{3\pi}{4}$, $y = \dfrac{3\pi}{2}$, $y = \dfrac{9\pi}{4}$

intersect the curve at $d = 0.596$, 1.0, 1.404. The dipstick would have these markings on it.

(d) $d'(t) = \dfrac{1}{24\sqrt{1-(d-1)^2}}$

(e)



The minimum occurs at $d = 1$, which is the widest part of the tank.

61. (a) Proof

(b) $y = -12\ln\dfrac{12-\sqrt{144-x^2}}{x} - \sqrt{144-x^2}$



(c) Vertical asymptote: $x = 0$ (d) About 5.2 m

63. (a) 187.2π lb (b) $62.4\pi d$ lb **65.** Proof

67. $12 + \dfrac{9\pi}{2} - 25\arcsin\dfrac{3}{5} \approx 10.050$

69. Proof

Section 8.5 *(page 557)*

1. (a) $\dfrac{A}{x} + \dfrac{B}{x-8}$ (b) $\dfrac{A}{x-3} + \dfrac{B}{(x-3)^2} + \dfrac{C}{(x-3)^3}$

(c) $\dfrac{A}{x} + \dfrac{Bx+C}{x^2+10}$ (d) $\dfrac{A}{x} + \dfrac{Bx+C}{x^2+1} + \dfrac{Dx+E}{(x^2+1)^2}$

3. $\dfrac{1}{6}\ln\left|\dfrac{x-3}{x+3}\right| + C$ **5.** $\ln\left|\dfrac{x-1}{x+4}\right| + C$

7. $5\ln|x-2| - \ln|x+2| - 3\ln|x| + C$

9. $x^2 + \frac{3}{2}\ln|x-4| - \frac{1}{2}\ln|x+2| + C$

11. $\dfrac{1}{x} + \ln|x^4 + x^3| + C$

13. $\dfrac{9}{x+1} + 2\ln|x| - \ln|x+1| + C$

15. $9\ln|x| - \dfrac{32}{7}\ln(7x^2+1) + C$

17. $\dfrac{1}{6}\left(\ln\left|\dfrac{x-2}{x+2}\right| + \sqrt{2}\arctan\dfrac{x}{\sqrt{2}}\right) + C$

19. $\ln|x+1| + \sqrt{2}\arctan\dfrac{x-1}{\sqrt{2}} + C$ **21.** $\ln 3$

23. $\dfrac{1}{2}\ln\dfrac{8}{5} - \dfrac{\pi}{4} + \arctan 2 \approx 0.557$ **25.** $\ln|1+\sec x| + C$

27. $\ln\left|\dfrac{\tan x + 2}{\tan x + 3}\right| + C$ **29.** $\dfrac{1}{5}\ln\left|\dfrac{e^x-1}{e^x+4}\right| + C$

31. $2\sqrt{x} + 2\ln\left|\dfrac{\sqrt{x}-2}{\sqrt{x}+2}\right| + C$ **33–35.** Proofs

37. $12\ln\frac{9}{7}$ **39.** $\frac{5}{2}\ln 5$ **41.** Substitution: $u = x^2 + 2x - 8$

43. Trigonometric substitution (tan) or inverse tangent rule

45. 4.90, or \$490,000

47. (a) $V = 2\pi\left(\arctan 3 - \frac{3}{10}\right) \approx 5.963$

(b) $(\bar{x}, \bar{y}) \approx (1.521, 0.412)$

49. $x = \dfrac{n\left[e^{(n+1)kt} - 1\right]}{n + e^{(n+1)kt}}$ **51.** $\dfrac{\pi}{8}$

53. Putnam Problem B4, 1992

Section 8.6 *(page 564)*

1. No. The integral can be easily evaluated using basic integration rules.

	Trapezoidal	Simpson's	Exact
3.	2.7500	2.6667	2.6667
5.	0.6970	0.6933	0.6931
7.	20.2222	20.0000	20.0000
9.	12.6640	12.6667	12.6667
11.	0.3352	0.3334	0.3333
13.	0.5706	0.5930	0.5940

	Trapezoidal	Simpson's	Graphing Utility
15.	3.2833	3.2396	3.2413
17.	0.7828	0.7854	0.7854
19.	102.5553	93.3752	92.7437
21.	0.5495	0.5483	0.5493
23.	0.1940	0.1860	0.1858

25. (a) $\frac{1}{12}$ (b) 0 **27.** (a) $\frac{1}{4}$ (b) $\frac{1}{12}$

29. (a) $n = 366$ (b) $n = 26$

31. (a) $n = 77$ (b) $n = 8$

33. (a) $n = 643$ (b) $n = 48$

35. Trapezoidal Rule: 24.5
Simpson's Rule: 25.67

37. 0.701 **39.** $T_n = \frac{1}{2}(L_n + R_n)$ **41.** 89,250 m²

43. 10,233.58 ft-lb **45.** 2.477 **47.** Proof

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Section 8.7 *(page 570)*

1. Formula 40 **3.** $-\frac{1}{2}x(10 - x) + 25\ln|5 + x| + C$

5. $-\frac{\sqrt{1 - x^2}}{x} + C$

7. $\frac{1}{24}(3x + \sin 3x \cos 3x + 2\cos^3 3x \sin 3x) + C$

9. $-2\left(\cot\sqrt{x} + \csc\sqrt{x}\right) + C$ **11.** $x - \frac{1}{2}\ln(1 + e^{2x}) + C$

13. $\frac{x^7}{49}(7\ln x - 1) + C$ **15.** (a) and (b) $x\left(\ln\frac{x}{3} - 1\right) + C$

17. (a) and (b) $\ln\left|\frac{x - 1}{x}\right| + \frac{1}{x} + C$

19. $\frac{1}{2}\left[(x^2 + 1)\operatorname{arccsc}(x^2 + 1) + \ln\left(x^2 + 1 + \sqrt{x^4 + 2x^2}\right)\right] + C$

21. $\frac{\sqrt{x^4 - 1}}{x^2} + C$ **23.** $\frac{1}{36}\left(\frac{7}{7 - 6x} + \ln|7 - 6x|\right) + C$

25. $e^x \arccos(e^x) - \sqrt{1 - e^{2x}} + C$

27. $\frac{1}{2}(x^2 + \cot x^2 + \csc x^2) + C$

29. $\frac{\sqrt{2}}{2}\arctan\frac{1 + \sin\theta}{\sqrt{2}} + C$ **31.** $-\frac{\sqrt{2 + 9x^2}}{2x} + C$

33. $\frac{1}{4}\left(2\ln|x| - 3\ln|3 + 2\ln|x||\right) + C$

35. $\frac{3x - 10}{2(x^2 - 6x + 10)} + \frac{3}{2}\arctan(x - 3) + C$

37. $\frac{1}{2}\ln\left|x^2 - 3 + \sqrt{x^4 - 6x^2 + 5}\right| + C$

39. $\frac{2}{1 + e^x} - \frac{1}{2(1 + e^x)^2} + \ln(1 + e^x) + C$

41. $\frac{2}{3}\left(2 - \sqrt{2}\right) \approx 0.3905$ **43.** $\frac{32}{5}\ln 2 - \frac{31}{25} \approx 3.1961$

45. $\frac{\pi}{2}$ **47.** $\frac{\pi^3}{8} - 3\pi + 6 \approx 0.4510$ **49–53.** Proofs

55. $\frac{1}{\sqrt{5}}\ln\left|\frac{2\tan(\theta/2) - 3 - \sqrt{5}}{2\tan(\theta/2) - 3 + \sqrt{5}}\right| + C$ **57.** $\ln 2$

59. $\frac{1}{2}\ln(3 - 2\cos\theta) + C$ **61.** $-2\cos\sqrt{\theta} + C$ **63.** $4\sqrt{3}$

65. (a) $\int x\ln x\,dx = \frac{1}{2}x^2\ln x - \frac{1}{4}x^2 + C$

$\int x^2\ln x\,dx = \frac{1}{3}x^3\ln x - \frac{1}{9}x^3 + C$

$\int x^3\ln x\,dx = \frac{1}{4}x^4\ln x - \frac{1}{16}x^4 + C$

(b) $\int x^n\ln x\,dx = \frac{x^{n+1}}{n + 1}\ln x - \frac{x^{n+1}}{(n + 1)^2} + C$

(c) Proof

67. 1919.145 ft-lb **69.** About 401.4 **71.** $32\pi^2$

73. Putnam Problem A3, 1980

Section 8.8 *(page 579)*

1. One of the limits of integration is infinite, both of the limits of integration are infinite, or the function has a finite number of infinite discontinuities on the interval you are considering.

3. To evaluate the improper integral $\int_a^\infty f(x)\,dx$, find the limit as $b \to \infty$ when f is continuous on $[a, \infty)$ or find the limit as $a \to -\infty$ when f is continuous on $(-\infty, b]$.

5. Improper; $0 \le \frac{3}{5} \le 1$

7. Not improper; continuous on $[0, 1]$

9. Not improper; continuous on $[0, 2]$

11. Improper; infinite limits of integration

13. Infinite discontinuity at $x = 0$; 4

15. Infinite discontinuity at $x = 1$; diverges

17. $\frac{1}{8}$ **19.** Diverges **21.** Diverges **23.** 2

25. $\frac{1}{2(\ln 4)^2}$ **27.** π **29.** $\frac{\pi}{4}$ **31.** Diverges

33. Diverges **35.** 0 **37.** $-\frac{1}{4}$ **39.** Diverges

41. $\frac{\pi}{3}$ **43.** $\ln 3$ **45.** $\frac{\pi}{6}$ **47.** $\frac{2\pi\sqrt{6}}{3}$ **49.** $p > 1$

51. Proof **53.** Converges **55.** Converges

57. Converges **59.** Converges

61. The improper integral diverges. **63.** $\frac{7}{8}$ **65.** π

67. (a) 1 (b) $\frac{\pi}{2}$ (c) 2π **69.** 2π

71. (a) $W = 20{,}000$ mile-tons (b) 4000 mi

73. (a) Proof (b) 48.66%

75. (a)



(b) About 0.1587 (c) 0.1587; same by symmetry

77. (a) \$807,992.41 (b) \$887,995.15 (c) \$1,116,666.67

79. $P = \frac{2\pi NI\left(\sqrt{r^2 + c^2} - c\right)}{kr\sqrt{r^2 + c^2}}$

81. False. Let $f(x) = \frac{1}{x + 1}$. **83.** True **85.** True

87. (a) and (b) Proofs

(c) The definition of the improper integral $\int_{-\infty}^{\infty} f(x)\,dx$ is not $\lim_{a\to\infty}\int_{-a}^{a} f(x)\,dx$.

89. Proof **91.** $\frac{1}{s}$, $s > 0$ **93.** $\frac{2}{s^3}$, $s > 0$

95. $\frac{s}{s^2 + a^2}$, $s > 0$ **97.** $\frac{s}{s^2 - a^2}$, $s > |a|$

99. (a) $\Gamma(1) = 1, \Gamma(2) = 1, \Gamma(3) = 2$ (b) Proof
(c) $\Gamma(n) = (n - 1)!$

101. $c = 1$; $\ln 2$ **103.** $8\pi\left[\frac{(\ln 2)^2}{3} - \frac{\ln 4}{9} + \frac{2}{27}\right] \approx 2.01545$

105. $\int_0^1 2\sin u^2\,du$; 0.6278 **107.** Proof

Review Exercises for Chapter 8 *(page 583)*

1. (a) (i) $u = 2x$, $dv = \sqrt{2x - 3}\,dx$, $du = 2\,dx$, $v = \frac{1}{3}(2x - 3)^{3/2}$

(ii) $u = \sqrt{2x - 3} \implies u^2 = 2x - 3$, $x = \frac{1}{2}(u^2 + 3)$, $dx = u\,du$

$\int 2x\sqrt{2x - 3}\,dx = \frac{2}{5}(x + 1)(2x - 3)^{3/2} + C$

(b) (i) $u = x$, $dv = \sqrt{9 + x}\,dx$, $du = dx$, $v = \frac{2}{3}(9 + x)^{3/2}$

(ii) $u = \sqrt{9 + x} \implies u^2 = 9 + x$, $x = u^2 - 9$, $dx = 2u\,du$

$\int x\sqrt{9 + x}\,dx = \frac{2}{5}(x - 6)(9 + x)^{3/2} + C$

CHAPTER 8

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

3. *Sample answers:*
(a) If m is positive and odd, separate one factor of $\sin x$ and convert the remaining factors to $(1 - \cos^2 x)^{(m-1)/2}$, then integrate using substitution and integration by parts.
(b) If n is positive and odd, separate one factor of $\cos x$ and convert the remaining factors to $(1 - \sin^2 x)^{(n-1)/2}$ then integrate using substitution and integration by parts.
(c) If both m and n are positive and even, use integration by parts, using a Power-Reducing Formula to determine the expression for v.

5. The Trapezoidal Rule is used to approximate a definite integral by using n trapezoids. The interval $[a, b]$ is partitioned into n subintervals and each subinterval then forms a trapezoid by connecting the points where vertical lines from each subinterval endpoint meets the graph of f. The area of each trapezoid is found to approximate the definite integral.

7. $\frac{2}{9}(x^3 - 27)^{3/2} + C$ **9.** $-4 \cot \frac{x+8}{4} + C$

11. $\frac{1}{2} + \ln 2 \approx 1.1931$ **13.** $100 \arcsin \frac{x}{10} + C$

15. $-xe^{1-x} - e^{1-x} + C$

17. $\frac{1}{13}e^{2x}(2 \sin 3x - 3 \cos 3x) + C$

19. $x \tan x + \ln|\cos x| + C$

21. $\frac{1}{16}\left[(8x^2 - 1) \arcsin 2x + 2x\sqrt{1 - 4x^2}\right] + C$

23. $-\frac{\cos^5 x}{5} + C$ **25.** $\frac{\sin(\pi x - 1)[\cos^2(\pi x - 1) + 2]}{3\pi} + C$

27. $\frac{2}{3}\left(\tan^3 \frac{x}{2} + 3 \tan \frac{x}{2}\right) + C$

29. $\frac{\tan^3 x^2}{6} - \frac{\tan x^2}{2} + \frac{x^2}{2} + C$ **31.** $\tan \theta + \sec \theta + C$

33. $\frac{3\pi}{16} + \frac{1}{2} \approx 1.0890$ **35.** $\frac{3\sqrt{4 - x^2}}{x} + C$

37. $\frac{1}{3}(x^2 + 4)^{1/2}(x^2 - 8) + C$ **39.** $256 - 62\sqrt{17} \approx 0.3675$

41. (a), (b), and (c) $\frac{1}{3}\sqrt{4 + x^2}(x^2 - 8) + C$

43. $2 \ln|x + 2| - \ln|x - 3| + C$

45. $\frac{1}{4}[6 \ln|x - 1| - \ln(x^2 + 1) + 6 \arctan x] + C$

47. $x + \frac{1}{1 - x} + 2 \ln|x - 1| + C$

49. $-\ln|e^x + 1| + \frac{1}{2}\ln|e^x + 3| + \frac{1}{2}\ln|e^x - 1| + C$

	Trapezoidal	Simpson's	Graphing Utility
51.	0.2848	0.2838	0.2838
53.	0.6366	0.6847	0.7041

55. $\frac{1}{25}\left(\frac{4}{4 + 5x} + \ln|4 + 5x|\right) + C$ **57.** $1 - \frac{\sqrt{2}}{2}$

59. $\frac{1}{2}\ln|x^2 + 4x + 8| - \arctan \frac{x+2}{2} + C$

61. $\frac{\ln|\tan \pi x|}{\pi} + C$ **63.** $\frac{1}{8}(\sin 2\theta - 2\theta \cos 2\theta) + C$

65. $\frac{4}{3}(x^{3/4} - 3x^{1/4} + 3 \arctan x^{1/4}) + C$

67. $2\sqrt{1 - \cos x} + C$ **69.** $\sin x \ln(\sin x) - \sin x + C$

71. $\frac{5}{2}\ln\left|\frac{x-5}{x+5}\right| + C$

73. $y = x \ln|x^2 + x| - 2x + \ln|x + 1| + C$ **75.** $\frac{1}{5}$

77. $\frac{1}{2}(\ln 4)^2 \approx 0.961$

79. $\pi^2 - 4 \sin 2 - 2 \cos 2 - 6 \approx 1.0647$ **81.** $\frac{\sqrt{27}}{5} \approx 1.0392$

83. $(\bar{x}, \bar{y}) = \left(0, \frac{4}{3\pi}\right)$ **85.** $\frac{32}{3}$ **87.** Diverges **89.** 1

91. $\frac{\pi}{4}$ **93.** (a) \$6,321,205.59 (b) \$10,000,000

95. (a) 0.4581 (b) 0.0135 **97.** Proof **99.** Proof

P.S. Problem Solving *(page 586)*

1. (a) $\frac{4}{3}, \frac{16}{15}$ (b) Proof

3. (a) $R(n)$, I, $T(n)$, $L(n)$
(b) $S(4) = \frac{1}{3}[f(0) + 4f(1) + 2f(2) + 4f(3) + f(4)] \approx 5.42$

5. $(\bar{x}, \bar{y}) = \left(0, \frac{\sqrt{2}}{4}\right)$ **7.** Proof

9. $s(t) = -16t^2 + 12{,}000t\left(1 + \ln \frac{50{,}000}{50{,}000 - 400t}\right) + 1{,}500{,}000 \ln \frac{50{,}000 - 400t}{50{,}000}$; 557,168.626 ft

Chapter 9

Section 9.1 *(page 596)*

1. You need to be given one or more of the first few terms of a sequence, and then all other terms are defined using previous terms.

3. g; Factorial functions grow faster than exponential functions.

5. 3, 9, 27, 81, 243 **7.** 1, 0, −1, 0, 1 **9.** $2, -1, \frac{2}{3}, -\frac{1}{2}, \frac{2}{5}$

11. 3, 4, 6, 10, 18 **13.** c **14.** a **15.** d **16.** b

17. $n^2 + n$ **19.** $n(n - 1)(n - 2)$ **21.** 1 **23.** 2

25.



Converges to 4

27.



Diverges

29. Converges to 0 **31.** Diverges **33.** Converges to $\frac{3}{4}$

35. Converges to 0 **37.** Diverges **39.** Converges to 0

41. Converges to 1 **43.** Converges to 0

45. $6n - 4$; diverges **47.** $n^2 - 3$; diverges

49. $\frac{n+1}{n+2}$; converges **51.** $\frac{n+1}{n}$; converges

53. Monotonic, bounded **55.** Not monotonic, bounded

57. Monotonic, bounded **59.** Not monotonic, bounded

61. (a) $\left|7 + \frac{1}{n}\right| \geq 7 \implies$ bounded
$a_n > a_{n+1} \implies$ monotonic
So, $\{a_n\}$ converges.

(b)



Limit = 7

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

63. (a) $\left|\frac{1}{3}\left(1-\frac{1}{3^n}\right)\right| < \frac{1}{3} \implies$ bounded

$a_n < a_{n+1} \implies$ monotonic

So, $\{a_n\}$ converges.

(b) 

Limit $= \frac{1}{3}$

65. Answers will vary. *Sample answers:*

(a) $a_n = 10 - \frac{1}{n}$ (b) $a_n = \frac{3n}{4n+1}$

67. The sequence $\{a_n\}$ could converge or diverge. If $\{a_n\}$ is increasing, then it converges to a limit less than or equal to 1. If $\{a_n\}$ is decreasing, then it could converge (example: $a_n = 1/n$) or diverge (example: $a_n = -n$).

69. (a) No. $\lim_{n\to\infty} A_n$ does not exist.

(b)

n	1	2	3	4
A_n	\$10,045.83	\$10,091.88	\$10,138.13	\$10,184.60

n	5	6	7
A_n	\$10,231.28	\$10,278.17	\$10,325.28

n	8	9	10
A_n	\$10,372.60	\$10,420.14	\$10,467.90

71. \$26,125.00, \$27,300.63, \$28,529.15, \$29,812.97, \$31,154.55

73. False. The sequence could also alternate between two values.

75. True

77. 1, 1.4142, 1.4422, 1.4142, 1.3797, 1.3480; Converges to 1

79. Proof

81. (a) 1, 1, 2, 3, 5, 8, 13, 21, 34, 55, 89, 144

(b) 1, 2, 1.5, 1.6667, 1.6, 1.6250, 1.6154, 1.6190, 1.6176, 1.6182 (c) Proof

(d) $\rho = \frac{1+\sqrt{5}}{2} \approx 1.6180$

83. (a) 1.4142, 1.8478, 1.9616, 1.9904, 1.9976

(b) $a_n = \sqrt{2 + a_{n-1}}$ (c) $\lim_{n\to\infty} a_n = 2$

85. (a) Proof

(b) 

(c) and (d) Proofs

(e) $\frac{\sqrt[20]{20!}}{20} \approx 0.4152$

$\frac{\sqrt[50]{50!}}{50} \approx 0.3897$

$\frac{\sqrt[100]{100!}}{100} \approx 0.3799$

87–89. Proofs **91.** Putnam Problem A1, 1990

Section 9.2 *(page 605)*

1. $\lim_{n\to\infty} a_n = 5$ means that the limit of the sequence $\{a_n\}$ is 5. $\sum_{n=1}^{\infty} a_n = a_1 + a_2 + \cdots = 5$ means that the limit of the partial sums is 5.

3. You cannot make a conclusion. The series may either converge or diverge.

5. 1, 1.25, 1.361, 1.424, 1.464

7. 3, −1.5, 5.25, −4.875, 10.3125

9. 3, 4.5, 5.25, 5.625, 5.8125

11. Geometric series: $r = \frac{5}{2} > 1$ **13.** $\lim_{n\to\infty} a_n = 1 \neq 0$

15. $\lim_{n\to\infty} a_n = 1 \neq 0$ **17.** $\lim_{n\to\infty} a_n = \frac{1}{4} \neq 0$

19. Geometric series: $r = \frac{5}{6} < 1$

21. Geometric series: $r = 0.9 < 1$

23. Telescoping series: $a_n = 1/n - 1/(n+1)$; Converges to 1.

25. (a) $\frac{11}{3}$

(b)

n	5	10	20	50	100
S_n	2.7976	3.1643	3.3936	3.5513	3.6078

(c) 

(d) The terms of the series decrease in magnitude relatively slowly, and the sequence of partial sums approaches the sum of the series relatively slowly.

27. (a) 20

(b)

n	5	10	20	50	100
S_n	8.1902	13.0264	17.5685	19.8969	19.9995

(c) 

(d) The terms of the series decrease in magnitude relatively slowly, and the sequence of partial sums approaches the sum of the series relatively slowly.

29. 15 **31.** 3 **33.** 32 **35.** $\frac{1}{2}$ **37.** $\frac{\sin 1}{1-\sin 1}$

39. (a) $\sum_{n=0}^{\infty} \frac{4}{10}(0.1)^n$ (b) $\frac{4}{9}$

41. (a) $\sum_{n=0}^{\infty} \frac{12}{100}\left(\frac{1}{100}\right)^n$ (b) $\frac{4}{33}$

43. (a) $\sum_{n=0}^{\infty} \frac{3}{40}(0.01)^n$ (b) $\frac{5}{66}$

45. Diverges **47.** Diverges **49.** Converges

51. Diverges **53.** Diverges **55.** Diverges

57. Diverges

59. Yes. If you remove a finite number of terms, the sum of the sequence of partial sums still diverges.

61. $|x| < \frac{1}{3}$; $\frac{3x}{1-3x}$ **63.** $0 < x < 2$; $\frac{x-1}{2-x}$

65. $-1 < x < 1$; $\frac{1}{1+x}$

CHAPTER 9

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

67. (a) x (b) $f(x) = \dfrac{1}{1-x}, \quad |x| < 1$

(c) 

Answers will vary.

69. The required terms for the two series are $n = 100$ and $n = 5$, respectively. The second series converges at a higher rate.

71. $160{,}000(1 - 0.95^n)$ units **73.** 152.42 ft

75. $\displaystyle\sum_{i=0}^{\infty} 200(0.75)^i$; Sum = \$800 million

77. $\dfrac{1}{8}$; $\displaystyle\sum_{n=0}^{\infty} \frac{1}{2}\left(\frac{1}{2}\right)^n = \frac{1/2}{1 - 1/2} = 1$

79. (a) $\displaystyle -1 + \sum_{n=0}^{\infty} \left(\frac{1}{2}\right)^n = -1 + \frac{a}{1-r} = -1 + \frac{1}{1 - 1/2} = 1$

(b) No (c) 2

81. (a) 126 in.^{2} (b) 128 in.^{2}

83. The \$2,000,000 sweepstakes has a present value of \$1,146,992.12. After accruing interest over the 20-year period, it attains its full value.

85. (a) \$5,368,709.11 (b) \$10,737,418.23 (c) \$21,474,836.47

87. (a) \$14,739.84 (b) \$14,742.45

89. (a) \$518,136.56 (b) \$518,168.67

91. False. $\displaystyle\sum_{n=1}^{\infty} ar^n = \frac{a}{1-r} - a$; The formula requires that the geometric series begins with $n = 0$.

93. True

95. Answers will vary. *Sample answer:* $\displaystyle\sum_{n=0}^{\infty} 1, \sum_{n=0}^{\infty} (-1)$

97–99. Proofs **101.** Putnam Problem A2, 1984

103. Putnam Problem B1, 2016

Section 9.3 *(page 613)*

1. f must be positive, continuous, and decreasing for $x \geq 1$ and $a_n = f(n)$.

3. Diverges **5.** Converges **7.** Converges

9. Diverges **11.** Diverges **13.** Converges

15. Converges **17.** Converges **19.** Diverges

21. Converges **23.** Diverges

25. $f(x)$ is not positive for $x \geq 1$.

27. $f(x)$ is not always decreasing. **29.** Converges

31. Diverges **33.** Diverges **35.** Converges

37. Converges

39. (a)

n	5	10	20	50	100
S_n	3.7488	3.75	3.75	3.75	3.75



The partial sums approach the sum 3.75 very quickly.

(b)

n	5	10	20	50	100
S_n	1.4636	1.5498	1.5962	1.6251	1.635



The partial sums approach the sum $\dfrac{\pi^2}{6} \approx 1.6449$ more slowly than the series in part (a).

41. No. Because $\displaystyle\sum_{n=1}^{\infty} \frac{1}{n}$ diverges, $\displaystyle\sum_{n=10{,}000}^{\infty} \frac{1}{n}$ also diverges. The convergence or divergence of a series is not determined by the first finite number of terms of the series.

43. (a) 

The area under the rectangles is greater than the area under the curve. Because $\displaystyle\int_1^{\infty} \frac{1}{\sqrt{x}}\,dx = \left[2\sqrt{x}\right]_1^{\infty} = \infty$ diverges, $\displaystyle\sum_{n=1}^{\infty} \frac{1}{\sqrt{n}}$ diverges.

(b) 

The area under the rectangles is less than the area under the curve. Because $\displaystyle\int_1^{\infty} \frac{1}{x^2}\,dx = \left[-\frac{1}{x}\right]_1^{\infty} = 1$ converges, $\displaystyle\sum_{n=2}^{\infty} \frac{1}{n^2}$ converges $\left(\text{and so does } \displaystyle\sum_{n=1}^{\infty} \frac{1}{n^2}\right)$.

45. $p > 1$ **47.** $p > 1$ **49.** $p > 3$ **51.** Proof

53. $S_3 \approx 1.0748$ **55.** $S_8 \approx 0.9597$
$R_3 \approx 0.0123$ $R_8 \approx 0.1244$

57. $S_4 \approx 0.4049$
$R_4 \approx 5.6 \times 10^{-8}$

59. $N \geq 7$ **61.** $N \geq 16$

63. (a) $\displaystyle\sum_{n=2}^{\infty} \frac{1}{n^{1.1}}$ converges by the p-Series Test because $1.1 > 1$.
$\displaystyle\sum_{n=2}^{\infty} \frac{1}{n \ln n}$ diverges by the Integral Test because
$\displaystyle\int_2^{\infty} \frac{1}{x \ln x}\,dx$ diverges.

(b) $\displaystyle\sum_{n=2}^{\infty} \frac{1}{n^{1.1}} = 0.4665 + 0.2987 + 0.2176 + 0.1703 + 0.1393 + \cdots$
$\displaystyle\sum_{n=2}^{\infty} \frac{1}{n \ln n} = 0.7213 + 0.3034 + 0.1803 + 0.1243 + 0.0930 + \cdots$

(c) $n \geq 3.431 \times 10^{15}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

65. (a) Let $f(x) = \frac{1}{x}$. f is positive, continuous, and decreasing on $[1, \infty)$.

$S_n - 1 \le \int_1^n \frac{1}{x}\,dx = \ln n$

$S_n \ge \int_1^{n+1} \frac{1}{x}\,dx \ln(n+1)$

So, $\ln(n+1) \le S_n \le 1 + \ln n$.

(b) $\ln(n+1) - \ln n \le S_n - \ln n \le 1$

Also, $\ln(n+1) - \ln n > 0$ for $n \ge 1$. So, $0 \le S_n - \ln n \le 1$, and the sequence $\{a_n\}$ is bounded.

(c) $a_n - a_{n+1} = [S_n - \ln n] - [S_{n+1} - \ln(n+1)]$

$= \int_n^{n+1} \frac{1}{x}\,dx - \frac{1}{n+1} \ge 0$

So, $a_n \ge a_{n+1}$.

(d) Because the sequence is bounded and monotonic, it converges to a limit, γ.

(e) 0.5822

67. (a) Diverges (b) Diverges

(c) $\sum_{n=2}^{\infty} x^{\ln n}$ converges for $x < \frac{1}{e}$.

69. Diverges **71.** Converges **73.** Converges

75. Diverges **77.** Diverges **79.** Converges **81.** Proof

Section 9.4 *(page 620)*

1. Yes. The test requires that $0 \le a_n \le b_n$ for all n greater than some integer N. The beginning terms do not affect the convergence or divergence of a series.

3. (a)



(b) $\sum_{n=1}^{\infty} \frac{6}{n^{3/2}}$; Converges

(c) The magnitudes of the terms are less than the magnitudes of the terms of the p-series. Therefore, the series converges.

(d) The smaller the magnitudes of the terms, the smaller the magnitudes of the terms of the sequence of partial sums.

5. Diverges **7.** Diverges **9.** Diverges

11. Converges **13.** Converges **15.** Converges

17. Diverges **19.** Diverges **21.** Converges

23. Converges **25.** Diverges

27. Diverges; p-Series Test

29. Converges; Direct Comparison Test with $\sum_{n=1}^{\infty} \left(\frac{1}{5}\right)^n$

31. Diverges; nth-Term Test **33.** Converges; Integral Test

35. $\lim_{n\to\infty} \frac{a_n}{1/n} = \lim_{n\to\infty} na_n$; $\lim_{n\to\infty} na_n \ne 0$ but is finite.

The series diverges by the Limit Comparison Test.

37. Diverges **39.** Converges

41. $\lim_{n\to\infty} n\left(\frac{n^3}{5n^4+3}\right) = \frac{1}{5} \ne 0$

43. Diverges **45.** Converges

47. Convergence or divergence is dependent on the form of the general term for the series and not necessarily on the magnitudes of the terms.

49. (a) Proof

(b)

n	5	10	20	50	100
S_n	1.1839	1.2087	1.2212	1.2287	1.2312

(c) 0.1226 (d) 0.0277

51. Proof **53.** False. Let $a_n = \frac{1}{n^3}$ and $b_n = \frac{1}{n^2}$.

55. True **57.** True **59.** Proof **61.** $\sum_{n=1}^{\infty} \frac{1}{n^2}$, $\sum_{n=1}^{\infty} \frac{1}{n^3}$

63–69. Proofs

71. Putnam Problem 1, afternoon session, 1953

Section 9.5 *(page 629)*

1. The series diverges because of the nth-Term Test for Divergence.

3. Σa_n is absolutely convergent if $\Sigma|a_n|$ converges. Σa_n is conditionally convergent if $\Sigma|a_n|$ diverges, but Σa_n converges.

5. (a)

n	1	2	3	4	5
S_n	1.0000	0.6667	0.8667	0.7238	0.8349

n	6	7	8	9	10
S_n	0.7440	0.8209	0.7543	0.8131	0.7605

(b)



(c) The points alternate sides of the horizontal line $y = \frac{\pi}{4}$ that represents the sum of the series. The distances between the successive points and the line decrease.

(d) The distance in part (c) is always less than the magnitude of the next term of the series.

7. (a)

n	1	2	3	4	5
S_n	1.0000	0.7500	0.8611	0.7986	0.8386

n	6	7	8	9	10
S_n	0.8108	0.8312	0.8156	0.8280	0.8180

(b)



(c) The points alternate sides of the horizontal line $y = \frac{\pi^2}{12}$ that represents the sum of the series. The distances between the successive points and the line decrease.

(d) The distance in part (c) is always less than the magnitude of the next term of the series.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

9. Converges **11.** Converges **13.** Diverges
15. Diverges **17.** Converges **19.** Diverges
21. Diverges **23.** Converges **25.** Converges
27. Converges **29.** Converges **31.** $1.8264 \le S \le 1.8403$
33. $1.7938 \le S \le 1.8054$ **35.** 10 **37.** 7
39. 7 (Note that the sum begins with $n = 0$.)
41. Converges absolutely **43.** Converges absolutely
45. Converges conditionally **47.** Diverges
49. Converges conditionally **51.** Converges absolutely
53. Converges absolutely **55.** Converges conditionally
57. Converges absolutely
59. Overestimate; The next term is negative.

61. (a) False. For example, let $a_n = \dfrac{(-1)^n}{n}$.

Then $\sum a_n = \sum \dfrac{(-1)^n}{n}$ converges

and $\sum (-a_n) = \sum \dfrac{(-1)^{n+1}}{n}$ converges.

But, $\sum |a_n| = \sum \dfrac{1}{n}$ diverges.

(b) True. If $\sum |a_n|$ converged, then so would $\sum a_n$ by Theorem 9.16.

63. $p > 0$

65. Proof; The converse is false. For example: Let $a_n = \dfrac{1}{n}$.

67. (a) $\displaystyle\sum_{n=1}^{\infty} \frac{x^n}{n}$
converges absolutely (by comparison) for $-1 < x < 1$ because
$\left|\dfrac{x^n}{n}\right| < |x^n|$ and $\sum x^n$
is a convergent geometric series for $-1 < x < 1$.

(b) When $x = -1$, you have the convergent alternating series $\displaystyle\sum_{n=1}^{\infty} \frac{(-1)^n}{n}$.
When $x = 1$, you have the divergent harmonic series $1/n$. Therefore,
$\displaystyle\sum_{n=1}^{\infty} \frac{x^n}{n}$ converges conditionally for $x = -1$.

69. (a) No; $a_{n+1} \le a_n$ is not satisfied for all n. For example, $\frac{1}{9} < \frac{1}{8}$.
(b) Yes; 0.5
71. Diverges; p-Series Test **73.** Diverges; nth-Term Test
75. Diverges; Geometric Series Test
77. Converges; Integral Test
79. Converges; Alternating Series Test
81. You cannot arbitrarily change 0 to $1 - 1$ and assume the series still converges. In fact, when regrouped with the 1 out front, the series diverges.

Section 9.6 *(page 637)*

1. Converges **3.** Diverges **5.** Inconclusive
7. Proof **9.** d **10.** c **11.** f
12. b **13.** a **14.** e

15. (a) Proof
(b)

n	5	10	15	20	25
S_n	13.7813	24.2363	25.8468	25.9897	25.9994

(c) 

(d) 26
(e) The more rapidly the terms of the series approach 0, the more rapidly the sequence of partial sums approaches the sum of the series.

17. Converges **19.** Diverges **21.** Diverges
23. Diverges **25.** Converges **27.** Converges
29. Diverges **31.** Converges **33.** Converges
35. Diverges **37.** Converges **39.** Converges
41. Diverges **43.** Converges **45.** Diverges
47. Converges **49.** Converges **51.** Converges
53. Converges; Alternating Series Test
55. Converges; p-Series Test **57.** Diverges; nth-Term Test
59. Diverges; Geometric Series Test
61. Converges; Limit Comparison Test with $b_n = \dfrac{1}{2^n}$
63. Converges; Direct Comparison Test with $b_n = \dfrac{1}{3^n}$
65. Diverges; Ratio Test **67.** Converges; Ratio Test
69. Converges; Ratio Test **71.** a and c **73.** a and b
75. $\displaystyle\sum_{n=0}^{\infty} \frac{n+1}{7^{n+1}}$ **77.** Diverges; $\displaystyle\lim_{n\to\infty} \left|\frac{a_{n+1}}{a_n}\right| > 1$
79. Converges; $\displaystyle\lim_{n\to\infty} \left|\frac{a_{n+1}}{a_n}\right| < 1$ **81.** Diverges; $\lim a_n \neq 0$
83. Converges **85.** Converges **87.** $(-3, 3)$
89. $(-2, 0]$ **91.** $x = 0$ **93.** The test is inconclusive.
95. No; The series $\displaystyle\sum_{n=1}^{\infty} \frac{1}{n + 10{,}000}$ diverges.
97–103. Proofs
105. (a) Diverges (b) Converges (c) Converges
(d) Converges for all integers $x \ge 2$
107. By the Root Test, $\sum b_n$ converges $\implies \sum a_n r^n$ converges.
109. Putnam Problem 7, morning session, 1951

Section 9.7 *(page 648)*

1. The graphs of the approximating polynomial P and the elementary function f both pass through the point $(c, f(c))$, and the slope of the graph of P is the same as the slope of the graph of f at the point $(c, f(c))$. If P is of degree n, then the first n derivatives of f and P agree at c. This allows the graph of P to resemble the graph of f near the point $(c, f(c))$.
3. The accuracy is represented by the remainder of the Taylor polynomial. The remainder is $R_n(x) = \dfrac{f^{(n+1)}(z)(x-c)^{n+1}}{(n+1)!}$.
5. d **6.** c **7.** a **8.** b

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

9. $P_1 = \frac{1}{16}x + \frac{1}{4}$



11. $P_1 = \frac{2\sqrt{3}}{3} + \frac{2}{3}\left(x - \frac{\pi}{6}\right)$



13.



x	0	0.8	0.9	1	1.1
$f(x)$	Error	4.4721	4.2164	4.0000	3.8139
$P_2(x)$	7.5000	4.4600	4.2150	4.0000	3.8150

x	1.2	2
$f(x)$	3.6515	2.8284
$P_2(x)$	3.6600	3.5000

15. (a)



(b) $f^{(2)}(0) = -1 \quad P_2^{(2)}(0) = -1$
$f^{(4)}(0) = 1 \quad P_4^{(4)}(0) = 1$
$f^{(6)}(0) = -1 \quad P_6^{(6)}(0) = -1$

(c) $f^{(n)}(0) = P_n^{(n)}(0)$

17. $1 + 4x + 8x^2 + \frac{32}{3}x^3 + \frac{32}{3}x^4$ **19.** $x - \frac{1}{6}x^3 + \frac{1}{120}x^5$

21. $x + x^2 + \frac{1}{2}x^3 + \frac{1}{6}x^4$ **23.** $1 + x + x^2 + x^3 + x^4 + x^5$

25. $1 + \frac{1}{2}x^2$ **27.** $2 - 2(x - 1) + 2(x - 1)^2 - 2(x - 1)^3$

29. $2 + \frac{1}{4}(x - 4) - \frac{1}{64}(x - 4)^2$

31. $\ln 2 + \frac{1}{2}(x - 2) - \frac{1}{8}(x - 2)^2 + \frac{1}{24}(x - 2)^3 - \frac{1}{64}(x - 2)^4$

33. (a) $P_3(x) = \pi x + \frac{\pi^3}{3}x^3$

(b) $Q_3(x) = 1 + 2\pi\left(x - \frac{1}{4}\right) + 2\pi^2\left(x - \frac{1}{4}\right)^2 + \frac{8\pi^3}{3}\left(x - \frac{1}{4}\right)^3$



35. (a)

x	0	0.25	0.50	0.75	1.00
$\sin x$	0	0.2474	0.4794	0.6816	0.8415
$P_1(x)$	0	0.25	0.50	0.75	1.00
$P_3(x)$	0	0.2474	0.4792	0.6797	0.8333
$P_5(x)$	0	0.2474	0.4794	0.6817	0.8417

(b)



(c) As the distance increases, the polynomial approximation becomes less accurate.

37. (a) $P_3(x) = x + \frac{1}{6}x^3$

(b)

x	−0.75	−0.50	−0.25	0	0.25
$f(x)$	−0.848	−0.524	−0.253	0	0.253
$P_3(x)$	−0.820	−0.521	−0.253	0	0.253

x	0.50	0.75
$f(x)$	0.524	0.848
$P_3(x)$	0.521	0.820

(c)



39. 2.7083 **41.** 0.227 **43.** 0.7419

45. $R_4 \le 2.03 \times 10^{-5}$; 0.000001

47. $R_5 \le 1.8 \times 10^{-8}$; 2.5×10^{-9}

49. $R_3 \le 7.82 \times 10^{-3}$; 0.00085 **51.** 3 **53.** 5 **55.** 2

57. $n = 9$; $\ln(1.5) \approx 0.4055$ **59.** $-0.3936 < x < 0$

61. $-0.9467 < x < 0.9467$

63. The tangent line to a function at a point is the first Taylor polynomial for the function at the point.

65. Substitute $2x$ into the polynomial for $f(x) = e^x$ to obtain the polynomial for $g(x) = e^{2x}$.

67. Proof

69. (a) $f(x) \approx P_4(x) = 1 + x + \frac{1}{2}x^2 + \frac{1}{6}x^3 + \frac{1}{24}x^4$
$g(x) \approx Q_5(x) = x + x^2 + \frac{1}{2}x^3 + \frac{1}{6}x^4 + \frac{1}{24}x^5$
$Q_5(x) = xP_4(x)$

(b) $g(x) \approx P_6(x) = x^2 - \frac{x^4}{3!} + \frac{x^6}{5!}$

(c) $g(x) \approx P_4(x) = 1 - \frac{x^2}{3!} + \frac{x^4}{5!}$

71. (a) $Q_2(x) = -1 + \left(\frac{\pi^2}{32}\right)(x + 2)^2$

(b) $R_2(x) = -1 + \left(\frac{\pi^2}{32}\right)(x - 6)^2$

(c) No. Horizontal translations of the result in part (a) are possible only at $x = -2 + 8n$ (where n is an integer) because the period of f is 8.

73. Proof

CHAPTER 9

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Section 9.8 *(page 658)*

1. A Maclaurin polynomial approximates a function, whereas a power series exactly represents a function. The Maclaurin polynomial has a finite number of terms, and the power series has an infinite number of terms.

3. $R = 5$ **5.** 0 **7.** 2 **9.** $R = 1$ **11.** $R = \frac{1}{4}$

13. $R = \infty$ **15.** $(-4, 4)$ **17.** $(-1, 1]$ **19.** $(-\infty, \infty)$

21. $x = 0$ **23.** $(-6, 6)$ **25.** $(-5, 13]$ **27.** $(0, 2]$

29. $(0, 6)$ **31.** $\left(-\frac{1}{2}, \frac{1}{2}\right)$ **33.** $(-\infty, \infty)$ **35.** $(-1, 1)$

37. $x = 3$ **39.** $R = c$ **41.** $(-k, k)$ **43.** $(-1, 1)$

45. $\sum_{n=1}^{\infty} \frac{x^{n-1}}{(n-1)!}$ **47.** $\sum_{n=1}^{\infty} \frac{x^n}{(7n+6)!}$

49. (a) $(-3, 3)$ (b) $(-3, 3)$ (c) $(-3, 3)$ (d) $[-3, 3)$

51. (a) $(0, 2]$ (b) $(0, 2)$ (c) $(0, 2)$ (d) $[0, 2]$

53. $\sum_{n=1}^{\infty} \left(\frac{x}{3}\right)^n$; Answers will vary.

55. Answers will vary. *Sample answer:*

$\sum_{n=1}^{\infty} \frac{x^n}{n}$ converges for $-1 \le x < 1$. At $x = -1$, the convergence is conditional because $\sum \frac{1}{n}$ diverges.

$\sum_{n=1}^{\infty} \frac{x^n}{n^2}$ converges for $-1 \le x \le 1$. At $x = \pm 1$, the convergence is absolute.

57. (a) For $f(x)$: $(-\infty, \infty)$; For $g(x)$: $(-\infty, \infty)$

(b) Proofs (c) $f(x) = \sin x$, $g(x) = \cos x$

59–63. Proofs

65. (a) and (b) Proofs

(c)



(d) 0.92

67. (a) $\frac{8}{3}$



(b) $\frac{8}{13}$



(c) The alternating series converges more rapidly. The partial sums of the series of positive terms approach the sum from below. The partial sums of the alternating series alternate sides of the horizontal line representing the sum.

(d)

M	10	100	1000	10,000
N	5	14	24	35

69.



$f(x) = \cos \pi x$

71.



$f(x) = \frac{1}{1+x}$

73. True **75.** True

77. (a) $(-1, 1)$ (b) $f(x) = \frac{c_0 + c_1 x + c_2 x^2}{1 - x^3}$ **79.** Proof

Section 9.9 *(page 666)*

1. You need to algebraically manipulate $\frac{b}{c-x}$ so that it resembles the form $\frac{a}{1-r}$.

3. $\sum_{n=0}^{\infty} \frac{x^n}{4^{n+1}}$ **5.** $\sum_{n=0}^{\infty} \frac{4}{3}\left(\frac{-x}{3}\right)^n$

7. $\sum_{n=0}^{\infty} \left(\frac{1}{5}\right)\left(\frac{x-1}{5}\right)^n$ $(-4, 6)$ **9.** $\sum_{n=0}^{\infty} (3x)^n$ $\left(-\frac{1}{3}, \frac{1}{3}\right)$

11. $-\frac{5}{9}\sum_{n=0}^{\infty}\left[\frac{2}{9}(x+3)\right]^n$ $\left(-\frac{15}{2}, \frac{3}{2}\right)$ **13.** $-2\sum_{n=0}^{\infty}[5(x+1)]^n$ $\left(-\frac{6}{5}, -\frac{4}{5}\right)$

15. $\sum_{n=0}^{\infty}\left[\frac{1}{(-3)^n} - 1\right]x^n$ $(-1, 1)$ **17.** $\sum_{n=0}^{\infty} x^n[1 + (-1)^n] = 2\sum_{n=0}^{\infty} x^{2n}$ $(-1, 1)$

19. $2\sum_{n=0}^{\infty} x^{2n}$ $(-1, 1)$ **21.** $\sum_{n=1}^{\infty} n(-1)^n x^{n-1}$ $(-1, 1)$ **23.** $\sum_{n=0}^{\infty} \frac{(-1)^n x^{n+1}}{n+1}$ $(-1, 1]$

25. $\sum_{n=0}^{\infty} (-1)^n x^{2n}$ $(-1, 1)$ **27.** $\sum_{n=0}^{\infty} (-1)^n (2x)^{2n}$ $\left(-\frac{1}{2}, \frac{1}{2}\right)$

29.



x	0.0	0.2	0.4	0.6	0.8	1.0
S_2	0.000	0.180	0.320	0.420	0.480	0.500
$\ln(x+1)$	0.000	0.182	0.336	0.470	0.588	0.693
S_3	0.000	0.183	0.341	0.492	0.651	0.833

31. (a)



(b) $\ln x$, $0 < x \le 2$, $R = 1$

(c) -0.6931

(d) $\ln(0.5)$; The error is approximately 0.

33. 0.245 **35.** 0.125 **37.** $\sum_{n=1}^{\infty} nx^{n-1}$, $-1 < x < 1$

39. $\sum_{n=0}^{\infty} (2n+1)x^n$, $-1 < x < 1$

41. $E(n) = 2$; Yes. Because the probability of obtaining a head on a single toss is $\frac{1}{2}$, it is expected that, on average, a head will be obtained in two tosses.

43. Proof **45.** (a) Proof (b) 3.14

47. $\ln \frac{3}{2} \approx 0.4055$; See Exercise 23.

49. $\ln \frac{7}{5} \approx 0.3365$; See Exercise 47.

51. $\arctan \frac{1}{2} \approx 0.4636$; See Exercise 50.

53. The series in Exercise 50 converges to its sum at a slower rate because its terms approach 0 at a much slower rate.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

55. The series converges on the interval $(-5, 3)$ and perhaps also at one or both endpoints.

57. $S_1 = \dfrac{1{,}130{,}173{,}253{,}125}{2{,}510{,}613{,}731{,}736\sqrt{2}} \approx 0.3183098862$,

$\dfrac{1}{\pi} \approx 0.3183098862$

Section 9.10 *(page 677)*

1. The Taylor series converges to f if and only if $R_n(x) \to 0$ as $n \to \infty$.

3. Multiply and divide as you would polynomials.

5. $\displaystyle\sum_{n=0}^{\infty} \frac{(2x)^n}{n!}$ **7.** $\dfrac{\sqrt{2}}{2}\displaystyle\sum_{n=0}^{\infty} \frac{(-1)^{n(n+1)/2}}{n!}\left(x - \frac{\pi}{4}\right)^n$

9. $\displaystyle\sum_{n=0}^{\infty} (-1)^n (x-1)^n$ **11.** $\displaystyle\sum_{n=0}^{\infty} \frac{(-1)^n (x-1)^{n+1}}{n+1}$

13. $\displaystyle\sum_{n=0}^{\infty} \frac{(-1)^n (3x)^{2n+1}}{(2n+1)!}$ **15.** $1 + \dfrac{x^2}{2!} + \dfrac{5x^4}{4!} + \cdots$

17–19. Proofs **21.** $1 + \displaystyle\sum_{n=1}^{\infty} \frac{1 \cdot 3 \cdot 5 \cdot \cdots (2n-1)x^n}{2^n n!}$

23. $1 + \displaystyle\sum_{n=1}^{\infty} \frac{1 \cdot 3 \cdot 5 \cdot \cdots (2n-1)x^{2n}}{2^n n!}$

25. $1 + \dfrac{1}{4}x + \displaystyle\sum_{n=2}^{\infty} \frac{(-1)^{n+1} 3 \cdot 7 \cdot 11 \cdot \cdots (4n-5)x^n}{4^n n!}$

27. $\displaystyle\sum_{n=0}^{\infty} \frac{x^{2n}}{2^n n!}$ **29.** $\displaystyle\sum_{n=1}^{\infty} \frac{(-1)^{n-1} x^n}{n}$ **31.** $\displaystyle\sum_{n=0}^{\infty} \frac{(-1)^n 4^{2n} x^{2n}}{(2n)!}$

33. $\displaystyle\sum_{n=0}^{\infty} \frac{(-1)^n (5x)^{2n+1}}{2n+1}$ **35.** $\displaystyle\sum_{n=0}^{\infty} \frac{(-1)^n x^{3n}}{(2n)!}$

37. $\displaystyle\sum_{n=0}^{\infty} \frac{x^{2n+1}}{(2n+1)!}$ **39.** $\dfrac{1}{2}\left[1 + \displaystyle\sum_{n=0}^{\infty} \frac{(-1)^n (2x)^{2n}}{(2n)!}\right]$

41. Proof **43.** $\displaystyle\sum_{n=0}^{\infty} \frac{(-1)^n x^{2n+2}}{(2n+1)!}$

45. $\begin{cases} \displaystyle\sum_{n=0}^{\infty} \frac{(-1)^n x^{2n}}{(2n+1)!}, & x \neq 0 \\ 1, & x = 0 \end{cases}$

47. $P_5(x) = x + x^2 + \frac{1}{3}x^3 - \frac{1}{30}x^5$

49. $P_5(x) = x - \frac{1}{2}x^2 - \frac{1}{6}x^3 + \frac{3}{40}x^5$

51. $P_4(x) = x - x^2 + \frac{5}{6}x^3 - \frac{5}{6}x^4$

53. $\displaystyle\sum_{n=0}^{\infty} \frac{(-1)^{(n+1)} x^{2n+3}}{(2n+3)(n+1)!}$ **55.** 0.6931 **57.** 7.3891

59. 0 **61.** 1 **63.** 0.8075 **65.** 0.9461 **67.** 0.4872

69. 0.2010 **71.** 0.7040 **73.** 0.3412

75. Square the series for $\cos x$, use a half-angle identity, or compute the coefficients using the definition.

First three terms: $1, \dfrac{x^2}{2}, \dfrac{x^4}{3}$

77. $f(x) = \dfrac{\sin(x+3)}{4}$; Answers will vary.

79. Proof

81. (a)



(b) Proof

(c) $\displaystyle\sum_{n=0}^{\infty} 0x^n = 0 \neq f(x)$; The series converges to f at $x = 0$ only.

83. Proof **85.** $\displaystyle\sum_{n=0}^{\infty} \binom{k}{n} x^n$ **87.** Proof

89. (a) $-\dfrac{1}{6}$ (b) $-\dfrac{1}{6}$

Review Exercises for Chapter 9 *(page 680)*

1. No, convergence implies that the limit is unique.

3. (a) False. Consider the Harmonic series.

(b) False. Consider when $a_n = \dfrac{(-1)^n}{n}$.

(c) False. Consider when $|r| > 1$.

(d) False. Consider when $a_n = \dfrac{1}{n^2}$ and $b_n = \dfrac{1}{n}$.

(e) False. Consider when $a_n = \dfrac{1}{n}\left(-\dfrac{1}{2}\right)^n$.

5.



7. 4, 34, 214, 1294, 7774 **9.** $-\frac{1}{4}, \frac{1}{16}, -\frac{1}{64}, \frac{1}{256}, -\frac{1}{1024}$

11.



Converges to 5

13. Converges to 0 **15.** Converges to 5 **17.** Diverges

19. Diverges **21.** $a_n = 5n - 2$; diverges

23. $a_n = \dfrac{1}{(n!+1)}$; converges **25.** Monotonic, bounded

27. (a)

n	1	2	3	4
A_n	\$8100.00	\$8201.25	\$8303.77	\$8407.56

n	5	6	7	8
A_n	\$8512.66	\$8619.07	\$8726.80	\$8835.89

(b) \$13,148.96

29. 3, 4.5, 5.5, 6.25, 6.85

31. (a)

n	5	10	15	20	25
S_n	13.2	113.3	873.8	6648.5	50,500.3

(b)



33. $\dfrac{5}{3}$ **35.** $\dfrac{35}{3}$ **37.** (a) $\displaystyle\sum_{n=0}^{\infty} (0.09)(0.01)^n$ (b) $\dfrac{1}{11}$

39. Diverges **41.** Diverges

43. $120{,}000[1 - 0.92^n]$, $n > 0$ **45.** Diverges

47. Converges **49.** Diverges **51.** Diverges

53. Converges **55.** Diverges **57.** Converges

59. Converges **61.** Diverges **63.** 10 **65.** Diverges

67. Diverges **69.** Converges

71. $P_3(x) = 1 - 2x + 2x^2 - \frac{4}{3}x^3$

73. $P_3(x) = 1 - 3(x-1) + 6(x-1)^2 - 10(x-1)^3$ **75.** 3

CHAPTER 9

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

77. (a) Proof

(b)

n	5	10	15	20	25
S_n	2.8752	3.6366	3.7377	3.7488	3.7499

(c) 

(d) 3.75

79. Converges; p-Series Test **81.** Diverges; nth-Term Test

83. Diverges; Limit Comparison Test

85. $(-10, 10)$ **87.** $[1, 3]$ **89.** Converges only at $x = 2$

91. (a) $(-5, 5)$ (b) $(-5, 5)$ (c) $(-5, 5)$ (d) $[-5, 5)$

93. Proof **95.** $\sum_{n=0}^{\infty} \frac{2}{3}\left(\frac{x}{3}\right)^n$ **97.** $\sum_{n=0}^{\infty} 2\left(\frac{x-1}{3}\right)^n$; $(-2, 4)$

99. $\ln \frac{5}{4} \approx 0.2231$ **101.** $e^{1/2} \approx 1.6487$

103. $\cos \frac{2}{3} \approx 0.7859$ **105.** $\frac{\sqrt{2}}{2} \sum_{n=0}^{\infty} \frac{(-1)^{n(n+1)/2}}{n!}\left(x - \frac{3\pi}{4}\right)^n$

107. $\sum_{n=0}^{\infty} \frac{(x \ln 3)^n}{n!}$ **109.** $-\sum_{n=0}^{\infty} (x+1)^n$

111. $1 + \frac{x}{5} - \frac{2x^2}{25} + \frac{6x^3}{125} - \frac{21x^4}{625} + \cdots$

113. (a)–(c) $1 + 2x + 2x^2 + \frac{4}{3}x^3$ **115.** $\sum_{n=0}^{\infty} \frac{(6x)^n}{n!}$

117. $\sum_{n=0}^{\infty} \frac{(-1)^n (5x)^{2n+1}}{(2n+1)!}$ **119.** 0.5 **121.** Proof

123. (a) 1 (b) Answers will vary. *Sample answer:* $0, \frac{1}{3}, \frac{2}{3}$
(c) 0

P.S. Problem Solving *(page 684)*

1. $\lim_{n\to\infty} A_n = \frac{\pi}{2} \cdot \frac{1}{4} = \frac{\pi}{8}$

3. (a) 3, 1.73205, 2.17533, 2.27493, 2.29672, 2.30146;
$\lim_{n\to\infty} a_n = \frac{1 + \sqrt{13}}{2}$

(b) Proof; $\frac{1 + \sqrt{1 + 4a}}{2}$

5. (a) Proof

(b) 1, 1.5, 1.4, $1.41\overline{6}$, 1.4140, 1.41429, 1.414201, 1.414216; $L = \sqrt{2}$

7. (a) $R = 1, S = (1 + 2x + 3x^2)\frac{1}{1 - x^3}$

(b) $R = 1, S = (a_0 + a_1 x + \cdots + a_{p-1}x^{p-1})\frac{1}{1 - x^p}$

(Assume all $a_n > 0$.)

Chapter 10

Section 10.1 *(page 696)*

1. A parabola is the set of all points that are equidistant from a fixed line, the directrix, and a fixed point, the focus, not on the line. An ellipse is the set of all points the sum of whose distances from two distinct fixed points called foci is constant. A hyperbola is the set of all points whose absolute value of the difference between the distances from two distinct fixed points called foci is constant.

3. (a) $0 < e < 1$

(b) As e gets closer to 1, the graph of the ellipse flattens.

5. a **6.** e **7.** c **8.** b **9.** f **10.** d

11. Vertex: $(-5, 3)$
Focus: $\left(-\frac{21}{4}, 3\right)$
Directrix: $x = -\frac{19}{4}$



13. Vertex: $(-1, 2)$
Focus: $(0, 2)$
Directrix: $x = -2$



15. Vertex: $(-2, 2)$
Focus: $(-2, 1)$
Directrix: $y = 3$



17. $(y - 4)^2 = 4(-2)(x - 5)$ **19.** $(x - 0)^2 = 4(8)(y - 5)$

21. $(x - 1)^2 = 4\left(-\frac{1}{3}\right)(y + 1)$ **23.** $\left(x - \frac{7}{5}\right)^2 = 4\left(\frac{3}{20}\right)\left(y + \frac{4}{15}\right)$

25. Center: $(0, 0)$
Foci: $\left(0, \pm\sqrt{15}\right)$
Vertices: $(0, \pm 4)$
$e = \frac{\sqrt{15}}{4}$



27. Center: $(3, 1)$
Foci: $(3, 4), (3, -2)$
Vertices: $(3, 6), (3, -4)$
$e = \frac{3}{5}$



29. Center: $(-2, 3)$
Foci: $\left(-2, 3 \pm \sqrt{5}\right)$
Vertices: $(-2, 6), (-2, 0)$
$e = \frac{\sqrt{5}}{3}$



31. $\frac{x^2}{36} + \frac{y^2}{11} = 1$ **33.** $\frac{(x-3)^2}{9} + \frac{(y-5)^2}{16} = 1$

35. $\frac{x^2}{16} + \frac{7y^2}{16} = 1$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

37. Center: $(0, 0)$
Foci: $\left(\pm\sqrt{41}, 0\right)$
Vertices: $(\pm 5, 0)$
$e = \dfrac{\sqrt{41}}{5}$
Asymptotes: $y = \pm\dfrac{4}{5}x$



39. Center: $(2, -3)$
Foci: $\left(2 \pm \sqrt{10}, -3\right)$
Vertices: $(1, -3), (3, -3)$
$e = \sqrt{10}$
Asymptotes: $y = -3 \pm 3(x - 2)$



41. $\dfrac{x^2}{1} - \dfrac{y^2}{25} = 1$ **43.** $\dfrac{y^2}{9} - \dfrac{(x-2)^2}{9/4} = 1$

45. $\dfrac{y^2}{4} - \dfrac{x^2}{12} = 1$ **47.** $\dfrac{(x-3)^2}{9} - \dfrac{(y-2)^2}{4} = 1$

49. (a) $\left(6, \sqrt{3}\right)$: $2x - 3\sqrt{3}y - 3 = 0$
$\left(6, -\sqrt{3}\right)$: $2x + 3\sqrt{3}y - 3 = 0$
(b) $\left(6, \sqrt{3}\right)$: $9x + 2\sqrt{3}y - 60 = 0$
$\left(6, -\sqrt{3}\right)$: $9x - 2\sqrt{3}y - 60 = 0$

51. Parabola **53.** Hyperbola **55.** Circle

57. (a) Ellipse (b) Hyperbola (c) Circle
(d) Answers will vary. *Sample answer:* Eliminate the y^2-term.

59. Recall that $0 \le \sin^2\theta \le 1$. The circumference is given by

$$C = 4\int_0^{\pi/2} \sqrt{a^2 - (a^2 - b^2)\sin^2\theta}\, d\theta$$



61. $\frac{9}{4}$ m **63.** (a) Proof (b) $(3, -3)$ **65.** $y = \frac{1}{180}x^2$

67. $\dfrac{16\left(4 + 3\sqrt{3} - 2\pi\right)}{3} \approx 15.536 \text{ ft}^2$

69. Minimum distance: 147,099,713.4 km
Maximum distance: 152,096,286.6 km

71. $e \approx 0.1373$ **73.** $e \approx 0.9671$

75. (a) Area $= 2\pi$
(b) Volume $= \dfrac{8\pi}{3}$
Surface area $= \dfrac{2\pi\left(9 + 4\sqrt{3}\pi\right)}{9} \approx 21.48$
(c) Volume $= \dfrac{16\pi}{3}$
Surface area $= \dfrac{4\pi\left[6 + \sqrt{3}\ln\left(2 + \sqrt{3}\right)\right]}{3} \approx 34.69$

77. 37.96 **79.** 40 **81.** $\dfrac{(x-6)^2}{9} - \dfrac{(y-2)^2}{7} = 1$

83. 110.3 mi **85.** Proof

87. False. See the definition of a parabola. **89.** True

91. True **93.** Putnam Problem B4, 1976

Section 10.2 *(page 707)*

1. The position, direction, and speed at a given time

3. Different parametric representations can be used to represent various speeds at which objects travel along a given path.

5.



$3x - 2y + 11 = 0$

7.



$y = (x - 1)^2$

9.



$y = \frac{1}{2}x^{2/3}$

11.



$y = x^2 - 5, \quad x \ge 0$

13.



$y = \dfrac{x + 3}{x}$

15.



$y = \dfrac{|x - 4|}{2}$

17.



$y = x^3 + 1, \quad x > 0$

19.



$x^2 + y^2 = 64$

21.



$y = \dfrac{1}{x}, \quad |x| \ge 1$

CHAPTER 10

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

23.



$\frac{x^2}{36} + \frac{y^2}{16} = 1$

25.



$\frac{(x-4)^2}{4} + \frac{(y+1)^2}{1} = 1$

27.



$\frac{(x+3)^2}{16} + \frac{(y-2)^2}{25} = 1$

29.



$\frac{x^2}{16} - \frac{y^2}{9} = 1$

31.



$y = \ln x$

33.



$y = \frac{1}{x^3}, \quad x > 0$

35. Both curves represent the parabola $y = x^2$.

	Domain	Orientation	Smooth
(a)	$-\infty < x < \infty$	Left to right	Yes
(b)	$-\infty < x < \infty$	Right to left	Yes

37. Each curve represents a portion of the line $y = 2x + 1$.

	Domain	Orientation	Smooth
(a)	$-\infty < x < \infty$	Up	Yes
(b)	$-1 \le x \le 1$	Oscillates	No, $\frac{dx}{d\theta} = \frac{dy}{d\theta} = 0$ when $\theta = 0, \pm\pi, \pm 2\pi, \ldots$
(c)	$0 < x < \infty$	Down	Yes
(d)	$0 < x < \infty$	Up	Yes

39. $y - y_1 = \frac{y_2 - y_1}{x_2 - x_1}(x - x_1)$

41. $\frac{(x-h)^2}{a^2} + \frac{(y-k)^2}{b^2} = 1$

43. $x = 4t$
$y = -7t$
(Solution is not unique.)

45. $x = 1 + 2\cos\theta$
$y = 1 + 2\sin\theta$
(Solution is not unique.)

47. $x = 2 + 5\cos\theta$
$y = 4\sin\theta$
(Solution is not unique.)

49. $x = 2\tan\theta$
$y = \sec\theta$
(Solution is not unique.)

51. $x = t$
$y = 6t - 5$;
$x = t + 1$
$y = 6t + 1$
(Solution is not unique.)

53. $x = t$
$y = t^3$;
$x = \tan t$
$y = \tan^3 t$
(Solution is not unique.)

55. $x = t + 3, y = 2t + 1$

57. $x = t, y = t^2$

59.



Not smooth at $\theta = 2n\pi$

61.



Smooth everywhere

63.



Not smooth at $\theta = \frac{1}{2}n\pi$

65.



Smooth everywhere

67. The orientation moves right to left on $[-1, 0]$ and left to right on $[0, 1]$, failing to determine a definite direction.

69. No. In the interval $0 < \theta < \pi$, $\cos\theta = \cos(-\theta)$ and $\sin^2\theta = \sin^2(-\theta)$. So, the parameter was not changed.

71. d; (4, 0) is on the graph. **72.** a; (0, 2) is on the graph.

73. b; (1, 0) is on the graph. **74.** c; (0, 0) is on the graph.

75. $x = a\theta - b\sin\theta$, $y = a - b\cos\theta$

77. False. The graph of the parametric equations is the portion of the line $y = x$ when $x \ge 0$.

79. True

81. (a) $x = \left(\frac{440}{3}\cos\theta\right)t$, $y = 3 + \left(\frac{440}{3}\sin\theta\right)t - 16t^2$

(b)



Not a home run

(c)



Home run

(d) 19.4°

Section 10.3 *(page 715)*

1. The slope of the curve at (x, y)

3. Horizontal tangent lines when $dy/dt = 0$ and $dx/dt \ne 0$ for some value of t; vertical tangent lines when $dx/dt = 0$ and $dy/dt \ne 0$ for some value of t

5. $-\frac{3}{t}$ **7.** -1

9. $\frac{dy}{dx} = \frac{3}{4}, \frac{d^2y}{dx^2} = 0$; Neither concave upward nor concave downward

11. $\frac{dy}{dx} = 2t + 3, \frac{d^2y}{dx^2} = 2$

At $t = -2$, $\frac{dy}{dx} = -1, \frac{d^2y}{dx^2} = 2$; Concave upward

13. $\frac{dy}{dx} = -\cot\theta, \frac{d^2y}{dx^2} = -\frac{(\csc\theta)^3}{4}$

At $\theta = \frac{\pi}{4}, \frac{dy}{dx} = -1, \frac{d^2y}{dx^2} = -\frac{\sqrt{2}}{2}$; Concave downward

15. $\frac{dy}{dx} = 2\csc\theta, \frac{d^2y}{dx^2} = -2\cot^3\theta$

At $\theta = -\frac{\pi}{3}, \frac{dy}{dx} = -\frac{4\sqrt{3}}{3}, \frac{d^2y}{dx^2} = \frac{2\sqrt{3}}{9}$;
Concave upward

17. $\frac{dy}{dx} = -\tan\theta, \frac{d^2y}{dx^2} = \sec^4\theta\csc\frac{\theta}{3}$

At $\theta = \frac{\pi}{4}, \frac{dy}{dx} = -1, \frac{d^2y}{dx^2} = \frac{4\sqrt{2}}{3}$; Concave upward

19. $\left(-\frac{2}{\sqrt{3}}, \frac{3}{2}\right)$: $3\sqrt{3}x - 8y + 18 = 0$
$(0, 2)$: $y - 2 = 0$
$\left(2\sqrt{3}, \frac{1}{2}\right)$: $\sqrt{3}x + 8y - 10 = 0$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

21. $(0, 0)$: $2y - x = 0$
$(-3, -1)$: $y + 1 = 0$
$(-3, 3)$: $2x - y + 9 = 0$

23. (a) and (d)



(b) At $t = -\frac{1}{2}$, $\frac{dx}{dt} = 6$, $\frac{dy}{dt} = 4$, and $\frac{dy}{dx} = \frac{2}{3}$.

(c) $y = \frac{2}{3}x + 2$

25. (a) and (d)



(b) At $t = -1$, $\frac{dx}{dt} = -3$, $\frac{dy}{dt} = 0$, and $\frac{dy}{dx} = 0$.

(c) $y = 2$

27. $y = \pm\frac{3}{4}x$ **29.** $y = 3x - 5$ and $y = 1$

31. Horizontal: $(-1, -\pi)$, $(-1, \pi)$, $(1, 2\pi)$, $(1, -2\pi)$
Vertical: $\left(\frac{\pi}{2}, 1\right)$, $\left(\frac{\pi}{2}, -1\right)$, $\left(-\frac{3\pi}{2}, 1\right)$, $\left(-\frac{3\pi}{2}, -1\right)$

33. Horizontal: $(9, 0)$
Vertical: None

35. Horizontal: $(2, 22)$, $(6, -10)$
Vertical: None

37. Horizontal: $(0, 7)$, $(0, -7)$
Vertical: $(7, 0)$, $(-7, 0)$

39. Horizontal: $(5, -1)$, $(5, -3)$
Vertical: $(8, -2)$, $(2, -2)$

41. Horizontal: None
Vertical: $(4, 0)$

43. Concave downward: $-\infty < t < 0$
Concave upward: $0 < t < \infty$

45. Concave upward: $t > 0$

47. Concave downward: $0 < t < \frac{\pi}{2}$
Concave upward: $\frac{\pi}{2} < t < \pi$

49. $4\sqrt{13} \approx 14.422$ **51.** $\sqrt{2}(1 - e^{-\pi/2}) \approx 1.12$

53. $\frac{1}{12}\left[\ln\left(\sqrt{37} + 6\right) + 6\sqrt{37}\right] \approx 3.249$ **55.** $6a$ **57.** $8a$

59. (a)



(b) 219.2 ft (c) 230.8 ft

61. (a)



(b) $(0, 0)$, $\left(\frac{4\sqrt[3]{2}}{3}, \frac{4\sqrt[3]{4}}{3}\right)$

(c) About 6.557

63. (a) $27\pi\sqrt{13}$ (b) $18\pi\sqrt{13}$ **65.** 50π **67.** $\frac{12\pi a^2}{5}$

69. $S = 2\pi\int_0^2 (t + 2)\sqrt{9t^4 + 1}\,dt \approx 185.78$

71. $S = 2\pi\int_0^{\pi/2} \left(\sin\theta\cos\theta\sqrt{4\cos^2\theta + 1}\right) d\theta$
$= \frac{\left(5\sqrt{5} - 1\right)\pi}{6}$
≈ 5.330

73. (a)



(b) The average speed of the particle on the second path is twice the average speed of the particle on the first path.

(c) 4π

75. Answers will vary. *Sample answer:* Let $x = -3t$, $y = -4t$.



77. Proof **79.** $\frac{3\pi}{2}$ **81.** d **82.** b **83.** f **84.** c

85. a **86.** e **87.** $\left(\frac{3}{4}, \frac{8}{5}\right)$ **89.** 288π

91. (a) $\frac{dy}{dx} = \frac{\sin\theta}{1 - \cos\theta}$, $\frac{d^2y}{dx^2} = -\frac{1}{a(\cos\theta - 1)^2}$

(b) $y = \left(2 + \sqrt{3}\right)\left[x - a\left(\frac{\pi}{6} - \frac{1}{2}\right)\right] + a\left(1 - \frac{\sqrt{3}}{2}\right)$

(c) $(a(2n + 1)\pi, 2a)$

(d) Concave downward on $(0, 2\pi)$, $(2\pi, 4\pi)$, etc.

(e) $s = 8a$

93. Proof

95. (a)



(b) Circle of radius 1 and center at $(0, 0)$ except the point $(-1, 0)$

(c) As t increases from -20 to 0, the speed increases, and as t increases from 0 to 20, the speed decreases.

97. False. $\frac{d^2y}{dx^2} = \frac{\frac{d}{dt}\left[\frac{g'(t)}{f'(t)}\right]}{f'(t)} = \frac{f'(t)g''(t) - g'(t)f''(t)}{\left[f'(t)\right]^3}$.

99. False. The resulting rectangular equation is a line.

Section 10.4 *(page 726)*

1. r is the directed distance from the origin to the point in the plane. θ is the directed angle, counterclockwise from the polar axis to the segment from the origin to the point in the plane.

3. The rectangular coordinate system is a collection of points of the form (x, y), where x is the directed distance from the y-axis to the point and y is the directed distance from the x-axis to the point. Every point has a unique representation.

The polar coordinate system is a collection of points of the form (r, θ), where r is the directed distance from the origin O to a point P and θ is the directed angle, measured counterclockwise, from the polar axis to the segment $\overline{OP}$. Polar coordinates do not have unique representations.

CHAPTER 10

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

5.



$(0, 8)$

7.



$\left(2\sqrt{2}, 2\sqrt{2}\right) \approx (2.828, 2.828)$

9.



$(-4.95, -4.95)$

11.



$(-1.004, 0.996)$

13.



$(-5.854, -5.453)$

15.



$(1, 0), (-1, \pi)$

17.



$(5, 2.214), (-5, 5.356)$

19.



$\left(10, \frac{4\pi}{3}\right), \left(-10, \frac{\pi}{3}\right)$

21.



$\left(\sqrt{14}, \frac{7\pi}{4}\right), \left(-\sqrt{14}, \frac{3\pi}{4}\right)$

23.



$\left(\sqrt{41}, 0.8961\right)$,
$\left(-\sqrt{41}, 4.0376\right)$

25. $r = 3$



27. $r = a$



29. $r = 8 \csc \theta$



31. $r = \dfrac{-2}{3 \cos \theta - \sin \theta}$



33. $r = 9 \csc^2 \theta \cos \theta$



35. $x^2 + y^2 = 16$



37. $x^2 + y^2 - 3y = 0$



39. $\sqrt{x^2 + y^2} = \arctan \dfrac{y}{x}$



41. $x - 3 = 0$



43. $x^2 - y = 0$



45.



$0 \le \theta < 2\pi$

47.



$0 \le \theta < 2\pi$

49.



$-\pi < \theta < \pi$

51.



$0 \le \theta < 4\pi$

53.



$0 \le \theta < \dfrac{\pi}{2}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

55. $(x - h)^2 + (y - k)^2 = h^2 + k^2$
Radius: $\sqrt{h^2 + k^2}$
Center: (h, k)

57. (a) 

(b) 

(c) 

59. $\sqrt{17}$ **61.** About 5.6

63. $\dfrac{dy}{dx} = \dfrac{-2\cos\theta\sin\theta + 2\cos\theta(1 - \sin\theta)}{-2\cos\theta\cos\theta - 2\sin\theta(1 - \sin\theta)}$

$(2, 0)$: $\dfrac{dy}{dx} = -1$

$\left(3, \dfrac{7\pi}{6}\right)$: $\dfrac{dy}{dx}$ is undefined.

$\left(4, \dfrac{3\pi}{2}\right)$: $\dfrac{dy}{dx} = 0$

65. (a) and (b) 

(c) $\dfrac{dy}{dx} = -1$

67. (a) and (b) 

(c) $\dfrac{dy}{dx} = -\sqrt{3}$

69. Horizontal: $\left(2, \dfrac{3\pi}{2}\right), \left(\dfrac{1}{2}, \dfrac{\pi}{6}\right), \left(\dfrac{1}{2}, \dfrac{5\pi}{6}\right)$

Vertical: $\left(\dfrac{3}{2}, \dfrac{7\pi}{6}\right), \left(\dfrac{3}{2}, \dfrac{11\pi}{6}\right)$

71. $\left(5, \dfrac{\pi}{2}\right), \left(1, \dfrac{3\pi}{2}\right)$

73. 

$\theta = 0$

75. 

77. 

$\theta = \dfrac{\pi}{6}, \dfrac{\pi}{2}, \dfrac{5\pi}{6}$

79. 

$\theta = 0, \dfrac{\pi}{2}$

81. 

83. 

85. 

87. 

89. 

91. 

93. 

95. 

97. 

99. (a) To test for symmetry about the x-axis, replace (r, θ) by $(r, -\theta)$ or $(-r, \pi - \theta)$. If the substitution yields an equivalent equation, then the graph is symmetric about the x-axis.

(b) To test for symmetry about the y-axis, replace (r, θ) by $(r, \pi - \theta)$ or $(-r, -\theta)$. If the substitution yields an equivalent equation, then the graph is symmetric about the y-axis.

101. Proof

CHAPTER 10

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

103. (a) $r = 2 - \sin\left(\theta - \dfrac{\pi}{4}\right) = 2 - \dfrac{\sqrt{2}(\sin\theta - \cos\theta)}{2}$ (b) $r = 2 + \cos\theta$




(c) $r = 2 + \sin\theta$ (d) $r = 2 - \cos\theta$




105. (a) (b)




107.



$\psi = \dfrac{\pi}{2}$

109.



$\psi = \arctan\frac{1}{3} \approx 18.4°$

111.



$\psi = \dfrac{\pi}{3}, 60°$

113. True **115.** True

Section 10.5 *(page 735)*

1. f must be continuous and either nonnegative or nonpositive on the interval of consideration.

3. $8\displaystyle\int_0^{\pi/2} \sin^2\theta\, d\theta$ **5.** $\dfrac{1}{2}\displaystyle\int_{\pi/2}^{3\pi/2} (3 - 2\sin\theta)^2\, d\theta$ **7.** 9π

9. $\dfrac{\pi}{3}$ **11.** $\dfrac{\pi}{16}$ **13.** $\dfrac{97\pi}{4} - 60 \approx 16.184$ **15.** $\dfrac{33\pi}{2}$

17. 4

19.



$\dfrac{2\pi - 3\sqrt{3}}{2}$

21.



$\dfrac{2\pi - 3\sqrt{3}}{2}$

23.



$\pi + 3\sqrt{3}$

25.



$9\pi + 27\sqrt{3}$

27. $\left(1, \dfrac{\pi}{2}\right), \left(1, \dfrac{3\pi}{2}\right), (0, 0)$

29. $\left(\dfrac{2 - \sqrt{2}}{2}, \dfrac{3\pi}{4}\right), \left(\dfrac{2 + \sqrt{2}}{2}, \dfrac{7\pi}{4}\right), (0, 0)$

31. $\left(\dfrac{3}{2}, \dfrac{\pi}{6}\right), \left(\dfrac{3}{2}, \dfrac{5\pi}{6}\right), (0, 0)$ **33.** $(2, 4), (-2, -4)$

35.



$(0, 0), (0.935, 0.363), (0.535, -1.006)$

The graphs reach the pole at different times (θ-values).

37.



$\frac{4}{3}\left(4\pi - 3\sqrt{3}\right)$

39.



$11\pi - 24$

41.



$\frac{2}{3}\left(4\pi - 3\sqrt{3}\right)$

43.



$\dfrac{\pi}{3} + \dfrac{\sqrt{3}}{2}$

45. $\dfrac{5\pi a^2}{4}$ **47.** $\dfrac{a^2}{2}(\pi - 2)$

49. (a) $(x^2 + y^2)^{3/2} = ax^2$

(b)



(c) $\dfrac{15\pi}{2}$

51. The area enclosed by the function is $\dfrac{\pi a^2}{4}$ if n is odd and is $\dfrac{\pi a^2}{2}$ if n is even.

53. $\dfrac{4\pi}{3}$ **55.** 4π **57.** 8

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

59.



About 4.16

61.



About 0.71

63.



About 4.39

65. 36π **67.** $\dfrac{2\pi\sqrt{1+a^2}}{1+4a^2}(e^{\pi a}-2a)$ **69.** 21.87

71. (a)



(b) $0 \le \theta < \pi$

(c) and (d) 25π

73. Answers will vary. *Sample answer:* $f(\theta) = \cos^2\theta + 1$, $g(\theta) = -\frac{3}{2}$

75. $40\pi^2$

77. (a) 16π

(b)

θ	0.2	0.4	0.6	0.8	1.0	1.2	1.4
A	6.32	12.14	17.06	20.80	23.27	24.60	25.08

(c) and (d) For $\frac{1}{4}$ of area ($4\pi \approx 12.57$): 0.42

For $\frac{1}{2}$ of area ($8\pi \approx 25.13$): 1.57

For $\frac{3}{4}$ of area ($12\pi \approx 37.70$): 2.73

(e) No; Answers will vary.

79. (a)



The graph becomes larger and more spread out. The graph is reflected over the y-axis.

(b) $(an\pi, n\pi)$, where $n = 1, 2, 3, \ldots$

(c) About 21.26 (d) $\dfrac{4}{3\pi^3}$

81. $r = \sqrt{2}\cos\theta$

83. (a) $r = \dfrac{3\cos\theta\sin\theta}{\cos^3\theta + \sin^3\theta}$

(b)



(c) $\frac{3}{2}$

Section 10.6 *(page 743)*

1. (a) Hyperbola (b) Parabola
(c) Ellipse (d) Hyperbola

3.



(a) Parabola
(b) Ellipse
(c) Hyperbola

5.



Ellipse
As $e \to 1^-$, the ellipse becomes more elliptical, and as $e \to 0^+$, it becomes more circular.

7. c **8.** f **9.** a **10.** e **11.** b **12.** d

13. $e = 1$
Distance $= 1$
Parabola



15. $e = 2$
Distance $= \frac{7}{8}$
Hyperbola



17. $e = \frac{3}{2}$
Distance $= 2$
Hyperbola



19. $e = \frac{1}{2}$
Distance $= 6$
Ellipse



CHAPTER 10

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

21. $e = \frac{1}{2}$

Distance $= 50$

Ellipse



23.



Ellipse

$e = \frac{1}{2}$

25.



Parabola

$e = 1$

27.



Rotated $\frac{\pi}{3}$ radian counterclockwise.

29.



Rotated $\frac{\pi}{6}$ radian clockwise.

31. $r = \dfrac{8}{8 + 5\cos\left(\theta + \dfrac{\pi}{6}\right)}$

33. $r = \dfrac{3}{1 - \cos\theta}$ **35.** $r = \dfrac{1}{4 + \sin\theta}$

37. $r = \dfrac{8}{3 + 4\cos\theta}$ **39.** $r = \dfrac{2}{1 - \sin\theta}$

41. $r = \dfrac{16}{5 + 3\cos\theta}$ **43.** $r = \dfrac{9}{4 - 5\sin\theta}$

45. No. The flatness of the ellipse does not depend on the distance between foci.

47. $r = \dfrac{4}{2 + \cos\theta}$ **49.** Proof

51. $r^2 = \dfrac{9}{1 - (16/25)\cos^2\theta}$ **53.** $r^2 = \dfrac{-16}{1 - (25/9)\cos^2\theta}$

55. 10.88 **57.** 1.88

59. $r = \dfrac{7979.21}{1 - 0.9372\cos\theta}$, 11,015 mi

61. $r = \dfrac{149{,}558{,}278.0560}{1 - 0.0167\cos\theta}$

Perihelion: 147,101,680 km

Aphelion: 152,098,320 km

63. $r = \dfrac{4{,}494{,}426{,}033}{1 - 0.0113\cos\theta}$

Perihelion: 4,444,206,500 km

Aphelion: 4,545,793,500 km

65. Answers will vary. *Sample answers:*

(a) 3.591×10^{18} km^2; 9.322 yr

(b) $\alpha \approx 0.361 + \pi$; Larger angle with the smaller ray to generate an equal area

(c) Part (a): 1.583×10^9 km; 1.698×10^8 km/yr

Part (b): 1.610×10^9 km; 1.727×10^8 km/yr

67. Proof

Review Exercises for Chapter 10 *(page 746)*

1. Answers will vary. *Sample answer:*



3. Answers will vary. *Sample answers:* $x = 2t + 3$, $y = -4t - 8$



5. (a) Rotated 90 degrees counterclockwise

(b) Reflected across the x-axis

(c) Rotated 90 degrees clockwise

(d) Rotated 135 degrees clockwise

7. Circle

Center: $(1, 4)$

Radius: 5



9. Hyperbola

Center: $(-4, 3)$

Vertices: $\left(-4 \pm \sqrt{2}, 3\right)$

Foci: $\left(-4 \pm \sqrt{5}, 3\right)$

$e = \sqrt{\dfrac{5}{2}}$

Asymptotes:

$y = 3 \pm \dfrac{\sqrt{3}}{\sqrt{2}}(x + 4)$



11. Circle

Center: $\left(\frac{1}{2}, -\frac{3}{4}\right)$

Radius: 1



13. Parabola

Vertex: $(-5, -1)$

Directrix: $y = -4$

Focus: $(-5, 2)$



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

15. $(y-0)^2 = 4(2)(x-7)$ **17.** $\dfrac{x^2}{36} + \dfrac{(y-1)^2}{20} = 1$

19. $\dfrac{(x-3)^2}{5} + \dfrac{(y-4)^2}{9} = 1$ **21.** $\dfrac{y^2}{64} - \dfrac{x^2}{16} = 1$

23. $\dfrac{x^2}{49} - \dfrac{(y+1)^2}{32} = 1$ **25.** $\dfrac{x^2}{4} + \dfrac{y^2}{1} = 1$

27. $\dfrac{x^2}{1} - \dfrac{y^2}{4} = 1$ **29.** (a) $(0, 50)$ (b) About 38,294.49

31.



$x + 2y - 7 = 0$

33.



$y = (x-1)^2 - 3,\ x \geq 1$

35.



$x^2 + y^2 = 36$

37.



$(x-2)^2 - (y-3)^2 = 1$

39. $x = t,\ y = 4t + 3;\ x = t + 1,\ y = 4t + 7$
(Solution is not unique.)

41.



43. $\dfrac{dy}{dx} = -\dfrac{5}{6},\ \dfrac{d^2y}{dx^2} = 0$

At $t = 3,\ \dfrac{dy}{dx} = -\dfrac{5}{6},\ \dfrac{d^2y}{dx^2} = 0$; Neither concave upward nor downward

45. $\dfrac{dy}{dx} = -2t^3,\ \dfrac{d^2y}{dx^2} = 6t^4$

At $t = -2,\ \dfrac{dy}{dx} = 16,\ \dfrac{d^2y}{dx^2} = 96$; Concave upward

47. $\dfrac{dy}{dx} = -e^{-2t},\ \dfrac{d^2y}{dx^2} = \dfrac{2}{e^{3t}}$

At $t = 1,\ \dfrac{dy}{dx} = -\dfrac{1}{e^2},\ \dfrac{d^2y}{dx^2} = \dfrac{2}{e^3}$; Concave upward

49. $\dfrac{dy}{dx} = -\cot\theta,\ \dfrac{d^2y}{dx^2} = -\dfrac{1}{10}\csc^3\theta$

At $\theta = \dfrac{\pi}{4},\ \dfrac{dy}{dx} = -1,\ \dfrac{d^2y}{dx^2} = -\dfrac{\sqrt{2}}{5}$; Concave downward

51. (a) and (d)



(b) $\dfrac{dx}{d\theta} = -4,\ \dfrac{dy}{d\theta} = 1,\ \dfrac{dy}{dx} = -\dfrac{1}{4}$ (c) $y = -\dfrac{1}{4}x + \dfrac{3\sqrt{3}}{4}$

53. Horizontal: $(5, 0)$ **55.** Horizontal: $(2, 2), (2, 0)$
Vertical: None Vertical: $(4, 1), (0, 1)$

57. $\frac{1}{54}(145^{3/2} - 1) \approx 32.315$

59. (a) 25π (b) 20π **61.** $A = 3\pi$

63.



$(0, -5)$

65.



$(-2.6302, -0.2863)$

67.



$\left(4\sqrt{2}, \dfrac{7\pi}{4}\right), \left(-4\sqrt{2}, \dfrac{3\pi}{4}\right)$

69.



$\left(\sqrt{10}, 1.89\right), \left(-\sqrt{10}, 5.03\right)$

71. $r = 5$



73. $r = 9\csc\theta$



75. $r = \dfrac{3}{4\sin\theta - \cos\theta}$



77. $x^2 + y^2 - 6x = 0$



79. $x = -4$



81. $y = -x$



CHAPTER 10

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

83.



$0 \le \theta \le \pi$

85.



$0 \le \theta \le \pi$

87. Horizontal: $\left(\frac{3}{2}, \frac{2\pi}{3}\right), \left(\frac{3}{2}, \frac{4\pi}{3}\right)$

Vertical: $\left(\frac{1}{2}, \frac{\pi}{3}\right), (2, \pi), \left(\frac{1}{2}, \frac{5\pi}{3}\right)$

89.



$\theta = 0, \frac{\pi}{3}, \frac{2\pi}{3}$

91. Circle



93. Line



95. Limaçon



97. Spiral



99. Lemniscate



101. $\frac{9\pi}{20}$ **103.** $\frac{9\pi}{2}$

105. $\left(1 + \frac{\sqrt{2}}{2}, \frac{3\pi}{4}\right), \left(1 - \frac{\sqrt{2}}{2}, \frac{7\pi}{4}\right), (0, 0)$

107.



$9\pi - \frac{27\sqrt{3}}{2}$

109.



$9\pi + 27\sqrt{3}$

111.



$27\pi - 40$

113. $\frac{5\pi}{2}$ **115.** $4\pi^2$

117. $e = 1$
Distance $= 6$
Parabola



119. $e = \frac{2}{3}$
Distance $= 3$
Ellipse



121. $e = \frac{3}{2}$
Distance $= \frac{4}{3}$
Hyperbola



123. $r = \dfrac{5}{1 + \cos\theta}$ **125.** $r = \dfrac{9}{1 + 3\sin\theta}$

127. $r = \dfrac{4}{1 + \sin\theta}$ **129.** $r = \dfrac{5}{3 - 2\cos\theta}$

131. Proof

P.S. Problem Solving *(page 750)*

1. (a)



3. Proof

(b) and (c) Proofs

5. (a) $y^2 = x^2\left(\dfrac{1 - x}{1 + x}\right)$ (b) $r = \cos 2\theta \cdot \sec\theta$

(c)



(d) $y = x, y = -x$

(e) $\left(\dfrac{\sqrt{5} - 1}{2}, \pm\dfrac{\sqrt{5} - 1}{2}\sqrt{-2 + \sqrt{5}}\right)$

7. $\dfrac{\pi}{2} = (r^2 - 2)\cos^{-1}\left(\dfrac{r}{2}\right) + \pi - \sin\left(2\cos^{-1}\left(\dfrac{r}{2}\right)\right)$,
$r \approx 1.1587$ km

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Chapter 11

Section 11.1 *(page 759)*

1. Answers will vary. *Sample answer:* A scalar is a single real number, such as 2. A vector is a line segment having both direction and magnitude. The vector $\langle \sqrt{3}, 1 \rangle$, given in component form, has a direction of $\pi/6$ and a magnitude of 2.

3. (a) $\langle 4, 2 \rangle$

(b)



5. $\mathbf{u} = \mathbf{v} = \langle 2, 4 \rangle$ **7.** $\mathbf{u} = \mathbf{v} = \langle 6, -5 \rangle$

9. (a) and (d)



(b) $\langle 3, 5 \rangle$

(c) $\mathbf{v} = 3\mathbf{i} + 5\mathbf{j}$

11. (a) and (d)



(b) $\langle -2, -4 \rangle$

(c) $\mathbf{v} = -2\mathbf{i} - 4\mathbf{j}$

13. (a) and (d)



(b) $\langle 0, 4 \rangle$ (c) $\mathbf{v} = 4\mathbf{j}$

15. (a) and (d)



(b) $\langle -1, \frac{5}{3} \rangle$

(c) $\mathbf{v} = -\mathbf{i} + \frac{5}{3}\mathbf{j}$

17. (3, 5) **19.** 4 **21.** 17 **23.** $\sqrt{26}$

25. (a) $\langle 6, 10 \rangle$



(b) $\langle -9, -15 \rangle$



(c) $\left\langle \frac{21}{2}, \frac{35}{2} \right\rangle$



(d) $\left\langle 2, \frac{10}{3} \right\rangle$



27. (a) $\left\langle \frac{8}{3}, 6 \right\rangle$ (b) $\langle 6, -15 \rangle$

(c) $\langle -2, -14 \rangle$ (d) $\langle 18, -7 \rangle$

29.



31.



33.



35. $\left\langle \frac{\sqrt{17}}{17}, \frac{4\sqrt{17}}{17} \right\rangle$ **37.** $\left\langle \frac{3\sqrt{34}}{34}, \frac{5\sqrt{34}}{34} \right\rangle$

39. (a) $\sqrt{2}$ (b) $\sqrt{5}$ (c) 1 (d) 1 (e) 1 (f) 1

41. (a) $\frac{\sqrt{5}}{2}$ (b) $\sqrt{13}$ (c) $\frac{\sqrt{85}}{2}$ (d) 1 (e) 1 (f) 1

43.



$\|\mathbf{u}\| + \|\mathbf{v}\| = \sqrt{5} + \sqrt{41}$ and $\|\mathbf{u} + \mathbf{v}\| = \sqrt{74}$

$\sqrt{74} \leq \sqrt{5} + \sqrt{41}$

45. $\langle 0, 6 \rangle$ **47.** $\langle -\sqrt{5}, 2\sqrt{5} \rangle$ **49.** $\langle 3, 0 \rangle$

51. $\langle -\sqrt{3}, 1 \rangle$ **53.** $\left\langle \frac{2 + 3\sqrt{2}}{2}, \frac{3\sqrt{2}}{2} \right\rangle$

55. $\langle 2 \cos 4 + \cos 2, 2 \sin 4 + \sin 2 \rangle$

57. $\theta = 0°$

59. $\mathbf{0}$; The starting point and ending point are the same.

61. $a = 3, b = 1$ **63.** $a = -2, b = -4$

65. $a = -\frac{2}{3}, b = \frac{5}{3}$

67. (a) $\pm \frac{1}{\sqrt{37}} \langle 1, 6 \rangle$

(b) $\pm \frac{1}{\sqrt{37}} \langle 6, -1 \rangle$

69. (a) $\pm \frac{1}{\sqrt{10}} \langle 1, 3 \rangle$

(b) $\pm \frac{1}{\sqrt{10}} \langle 3, -1 \rangle$





CHAPTER 11

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

71. (a) $\pm\frac{1}{5}\langle -4, 3\rangle$

(b) $\pm\frac{1}{5}\langle 3, 4\rangle$



73. $\left\langle -\frac{\sqrt{2}}{2}, \frac{\sqrt{2}}{2} \right\rangle$ **75.** 10.7°, 584.6 lb **77.** 71.3°, 228.5 lb

79. Tension in cable CB: 1958.1 lb
Tension in cable CA: 2638.2 lb

81. Proof

83. 38.3° north of west, 882.9 km/h

85. False. Weight has direction. **87.** True

89. True **91.** True **93.** False. $\|a\mathbf{i} + b\mathbf{j}\| = \sqrt{2}|a|$

95–97. Proofs **99.** $x^2 + y^2 = 25$

Section 11.2 *(page 767)*

1. x_0 is directed distance to yz-plane.
y_0 is directed distance to xz-plane.
z_0 is directed distance to xy-plane.

3. (a) Point (b) Vertical line (c) Plane

5.



7.



9. $(-3, 4, 5)$ **11.** $(12, 0, 0)$

13. One unit above the xy-plane

15. Three units behind the yz-plane

17. To the left of the xz-plane

19. Within three units of the xz-plane

21. Three units below the xy-plane and below either Quadrant I or Quadrant III

23. Above the xy-plane and above Quadrants II or IV *or* below the xy-plane and below Quadrants I or III

25. $3\sqrt{2}$ **27.** 5 **29.** $7, 7\sqrt{5}, 14$; Right triangle

31. $\sqrt{41}, \sqrt{41}, \sqrt{14}$; Isosceles triangle **33.** $(6, 4, 7)$

35. $(2, 6, 3)$

37. $(x - 7)^2 + (y - 1)^2 + (z + 2)^2 = 1$

39. $\left(x - \frac{3}{2}\right)^2 + (y - 2)^2 + (z - 1)^2 = \frac{21}{4}$

41. $(x + 7)^2 + (y - 7)^2 + (z - 6)^2 = 36$

43. $(x - 1)^2 + (y + 3)^2 + (z + 4)^2 = 25$
Center: $(1, -3, -4)$ Radius: 5

45. $\left(x - \frac{1}{3}\right)^2 + (y + 1)^2 + z^2 = 1$
Center: $\left(\frac{1}{3}, -1, 0\right)$ Radius: 1

47. (a) $\langle -2, 2, 2\rangle$

(b) $\mathbf{v} = -2\mathbf{i} + 2\mathbf{j} + 2\mathbf{k}$

(c)



49. (a) and (d)



(b) $\langle 4, 1, 1\rangle$

(c) $\mathbf{v} = 4\mathbf{i} + \mathbf{j} + \mathbf{k}$

51. $\mathbf{v} = \langle 1, -1, 6\rangle$
$\|\mathbf{v}\| = \sqrt{38}$
$\mathbf{u} = \frac{1}{\sqrt{38}}\langle 1, -1, 6\rangle$

53. $\mathbf{v} = \langle -4, 3, 2\rangle$
$\|\mathbf{v}\| = \sqrt{29}$
$\mathbf{u} = \frac{1}{\sqrt{29}}\langle -4, 3, 2\rangle$

55. $(3, 1, 8)$

57. (a)



(b)



(c)



(d)



59. $\langle 3, 0, 0\rangle$ **61.** $\langle 21, 18, 15\rangle$ **63.** a and b

65. a **67.** Collinear **69.** Not collinear

71. $\overrightarrow{AB} = \langle 1, 2, 3\rangle$, $\overrightarrow{CD} = \langle 1, 2, 3\rangle$, $\overrightarrow{BD} = \langle -2, 1, 1\rangle$, $\overrightarrow{AC} = \langle -2, 1, 1\rangle$; Because $\overrightarrow{AB} = \overrightarrow{CD}$ and $\overrightarrow{BD} = \overrightarrow{AC}$, the given points form the vertices of a parallelogram.

73. $\sqrt{2}$ **75.** $\sqrt{34}$ **77.** $\sqrt{14}$

79. (a) $\frac{1}{3}\langle 2, -1, 2\rangle$ (b) $-\frac{1}{3}\langle 2, -1, 2\rangle$

81. (a) $\frac{2\sqrt{2}}{5}\mathbf{i} - \frac{\sqrt{2}}{2}\mathbf{j} + \frac{3\sqrt{2}}{10}\mathbf{k}$

(b) $-\frac{2\sqrt{2}}{5}\mathbf{i} + \frac{\sqrt{2}}{2}\mathbf{j} - \frac{3\sqrt{2}}{10}\mathbf{k}$

83. $\left\langle 0, \frac{10}{\sqrt{2}}, \frac{10}{\sqrt{2}} \right\rangle$ **85.** $\left\langle 1, -1, \frac{1}{2} \right\rangle$

87. $\langle 0, \sqrt{3}, \pm 1\rangle$ **89.** $(2, -1, 2)$



91. A sphere of radius 4 centered at (x_1, y_1, z_1):
$(x - x_1)^2 + (y - y_1)^2 + (z - z_1)^2 = 16$

93. The set of points outside a sphere of radius 1 centered at the origin

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

95. The terminal points of the vectors $t\mathbf{v}$, $\mathbf{u} + t\mathbf{v}$, and $s\mathbf{u} + t\mathbf{v}$ are collinear.



97. $\frac{\sqrt{3}}{3}\langle 1, 1, 1\rangle$

99. (a) $T = \dfrac{8L}{\sqrt{L^2 - 18^2}}$, $L > 18$

(b)

L	20	25	30	35	40	45	50
T	18.4	11.5	10	9.3	9.0	8.7	8.6

(c) 

(d) Proof (e) 30 in.

101. Tension in cable AB: 202.919 N
Tension in cable AC: 157.909 N
Tension in cable AD: 226.521 N

103. $\left(x - \frac{4}{3}\right)^2 + (y - 3)^2 + \left(z + \frac{1}{3}\right)^2 = \frac{44}{9}$
Sphere; center: $\left(\frac{4}{3}, 3, -\frac{1}{3}\right)$, radius: $\frac{2\sqrt{11}}{3}$

Section 11.3 *(page 777)*

1. The vectors are orthogonal.
3. (a) 17 (b) 25 (c) 26 (d) $\langle -17, 85\rangle$ (e) 51
5. (a) -26 (b) 52 (c) 13 (d) $\langle 78, -52\rangle$ (e) -78
7. (a) 2 (b) 29 (c) 61 (d) $\langle 0, 12, 10\rangle$ (e) 6
9. (a) 1 (b) 6 (c) 2 (d) $\mathbf{i} - \mathbf{k}$ (e) 3
11. (a) $\frac{\pi}{2}$ (b) 90° **13.** (a) 1.7127 (b) 98.1°
15. (a) 1.0799 (b) 61.9° **17.** (a) 2.0306 (b) 116.3°
19. 20 **21.** Orthogonal **23.** Neither **25.** Orthogonal
27. Right triangle; Answers will vary.
29. Acute triangle; Answers will vary.

31. $\cos\alpha = \frac{1}{3}$, $\alpha \approx 70.5°$
$\cos\beta = \frac{2}{3}$, $\beta \approx 48.2°$
$\cos\gamma = \frac{2}{3}$, $\gamma \approx 48.2°$

33. $\cos\alpha = \frac{7}{\sqrt{51}}$, $\alpha \approx 11.4°$
$\cos\beta = \frac{1}{\sqrt{51}}$, $\beta \approx 82.0°$
$\cos\gamma = -\frac{1}{\sqrt{51}}$, $\gamma \approx 98.0°$

35. $\cos\alpha = 0$, $\alpha \approx 90°$
$\cos\beta = \frac{3}{\sqrt{13}}$, $\beta \approx 33.7°$
$\cos\gamma = -\frac{2}{\sqrt{13}}$, $\gamma \approx 123.7°$

37. (a) $\langle 2, 8\rangle$ (b) $\langle 4, -1\rangle$ **39.** (a) $\left\langle \frac{5}{2}, \frac{1}{2}\right\rangle$ (b) $\left\langle -\frac{1}{2}, \frac{5}{2}\right\rangle$
41. (a) $\langle -2, 2, 2\rangle$ (b) $\langle 2, 1, 1\rangle$
43. (a) $\langle 0, -3, -3\rangle$ (b) $\langle -9, 1, -1\rangle$
45. You cannot add a vector to a scalar.
47. Yes **49.** \$17,490.25; Total revenue
51. Answers will vary. *Sample answer:* $\langle 12, 2\rangle$ and $\langle -12, -2\rangle$
53. Answers will vary. *Sample answer:* $\langle 2, 0, 3\rangle$ and $\langle -2, 0, -3\rangle$
55. $\arccos \frac{1}{\sqrt{3}} \approx 54.7°$
57. (a) 8335.1 lb (b) 47,270.8 lb
59. 425 ft-lb **61.** 2900.2 km-N
63. False. For example, $\langle 1, 1\rangle \cdot \langle 2, 3\rangle = 5$ and $\langle 1, 1\rangle \cdot \langle 1, 4\rangle = 5$, but $\langle 2, 3\rangle \neq \langle 1, 4\rangle$.
65. (a) $(0, 0)$, $(1, 1)$
(b) To $y = x^2$ at $(1, 1)$: $\left\langle \pm\frac{\sqrt{5}}{5}, \pm\frac{2\sqrt{5}}{5}\right\rangle$
To $y = x^{1/3}$ at $(1, 1)$: $\left\langle \pm\frac{3\sqrt{10}}{10}, \pm\frac{\sqrt{10}}{10}\right\rangle$
To $y = x^2$ at $(0, 0)$: $\langle \pm 1, 0\rangle$
To $y = x^{1/3}$ at $(0, 0)$: $\langle 0, \pm 1\rangle$
(c) At $(1, 1)$: $\theta = 45°$
At $(0, 0)$: $\theta = 90°$
67. (a) $(-1, 0)$, $(1, 0)$
(b) To $y = 1 - x^2$ at $(1, 0)$: $\left\langle \pm\frac{\sqrt{5}}{5}, \mp\frac{2\sqrt{5}}{5}\right\rangle$
To $y = x^2 - 1$ at $(1, 0)$: $\left\langle \pm\frac{\sqrt{5}}{5}, \pm\frac{2\sqrt{5}}{5}\right\rangle$
To $y = 1 - x^2$ at $(-1, 0)$: $\left\langle \pm\frac{\sqrt{5}}{5}, \pm\frac{2\sqrt{5}}{5}\right\rangle$
To $y = x^2 - 1$ at $(-1, 0)$: $\left\langle \pm\frac{\sqrt{5}}{5}, \mp\frac{2\sqrt{5}}{5}\right\rangle$
(c) At $(1, 0)$: $\theta = 53.13°$
At $(-1, 0)$: $\theta = 53.13°$
69. Proof
71. (a) 

(b) $k\sqrt{2}$ (c) 60° (d) 109.5°
73–75. Proofs

Section 11.4 *(page 785)*

1. $\mathbf{u} \times \mathbf{v}$ is a vector that is perpendicular to both $\mathbf{u}$ and $\mathbf{v}$.
3. The two vectors are scalar multiples of each other.
5. $-\mathbf{k}$ 

7. $-\mathbf{j}$ 

9. (a) $20\mathbf{i} + 10\mathbf{j} - 16\mathbf{k}$ (b) $-20\mathbf{i} - 10\mathbf{j} + 16\mathbf{k}$ (c) $\mathbf{0}$
11. (a) $17\mathbf{i} - 33\mathbf{j} - 10\mathbf{k}$ (b) $-17\mathbf{i} + 33\mathbf{j} + 10\mathbf{k}$ (c) $\mathbf{0}$
13. $\langle 0, 0, 6\rangle$ **15.** $\langle -2, 3, -1\rangle$

CHAPTER 11

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

17. $\left\langle -\frac{7}{9\sqrt{3}}, -\frac{5}{9\sqrt{3}}, \frac{13}{9\sqrt{3}} \right\rangle$ or $\left\langle \frac{7}{9\sqrt{3}}, \frac{5}{9\sqrt{3}}, -\frac{13}{9\sqrt{3}} \right\rangle$

19. $\left\langle \frac{3}{\sqrt{59}}, \frac{7}{\sqrt{59}}, \frac{1}{\sqrt{59}} \right\rangle$ or $\left\langle -\frac{3}{\sqrt{59}}, -\frac{7}{\sqrt{59}}, -\frac{1}{\sqrt{59}} \right\rangle$

21. 1 **23.** $6\sqrt{5}$ **25.** $9\sqrt{5}$ **27.** $\frac{11}{2}$

29. $10 \cos 40° \approx 7.66$ ft-lb

31. (a) $\overrightarrow{AB} = -\frac{5}{4}\mathbf{j} + \mathbf{k}$; $\mathbf{F} = -180(\cos\theta\mathbf{j} + \sin\theta\mathbf{k})$

(b) $\|\overrightarrow{AB} \times \mathbf{F}\| = |225 \sin\theta + 180 \cos\theta|$

(c) $\|\overrightarrow{AB} \times \mathbf{F}\| = 225\left(\frac{1}{2}\right) + 180\left(\frac{\sqrt{3}}{2}\right) \approx 268.38$

(d) $\theta \approx 51.34°$

$\overrightarrow{AB}$ and $\mathbf{F}$ are perpendicular.

(e) 

$\theta \approx 141.34°$; The vectors are parallel.

33. 1 **35.** 6 **37.** 2 **39.** 75

41. a = b = c = h and e = f = g

43. On the x-axis; The cross product has the form $\langle k, 0, 0 \rangle$.

45. False. The cross product of two vectors is not defined in a two-dimensional coordinate system.

47. False. Let $\mathbf{u} = \langle 1, 0, 0 \rangle$, $\mathbf{v} = \langle 1, 0, 0 \rangle$, and $\mathbf{w} = \langle -1, 0, 0 \rangle$. Then $\mathbf{u} \times \mathbf{v} = \mathbf{u} \times \mathbf{w} = \mathbf{0}$, but $\mathbf{v} \neq \mathbf{w}$.

49–57. Proofs

Section 11.5 *(page 794)*

1. Parametric equations: $x = x_1 + at$, $y = y_1 + bt$, $z = z_1 + ct$

Symmetric equations: $\frac{x - x_1}{a} = \frac{y - y_1}{b} = \frac{z - z_1}{c}$

You need a vector $\mathbf{v} = \langle a, b, c \rangle$ parallel to the line and a point $P(x_1, y_1, z_1)$ on the line.

3. $\langle 2, 4, -1 \rangle$

5. (a) Yes (b) No (c) Yes

	Parametric Equations (a)	Symmetric Equations (b)	Direction Numbers
7.	$x = 3t$ $y = t$ $z = 5t$	$\frac{x}{3} = y = \frac{z}{5}$	3, 1, 5
9.	$x = -2 + 2t$ $y = 4t$ $z = 3 - 2t$	$\frac{x+2}{2} = \frac{y}{4} = \frac{z-3}{-2}$	2, 4, −2
	Parametric Equations (a)	**Symmetric Equations (b)**	**Direction Numbers**
11.	$x = 1 + 3t$ $y = -2t$ $z = 1 + t$	$\frac{x-1}{3} = \frac{y}{-2} = \frac{z-1}{1}$	3, −2, 1
13.	$x = 5 + 17t$ $y = -3 - 11t$ $z = -2 - 9t$	$\frac{x-5}{17} = \frac{y+3}{-11} = \frac{z+2}{-9}$	17, −11, −9
15.	$x = 7 - 10t$ $y = -2 + 2t$ $z = 6$	Not possible	−10, 2, 0

17. $x = 2$, $y = 3$, $z = 4 + t$

19. $x = 2 + 3t$, $y = 3 + 2t$, $z = 4 - t$

21. $x = 5 + 2t$, $y = -3 - t$, $z = -4 + 3t$

23. $x = 2 - t$, $y = 1 + t$, $z = 2 + t$

25. $P(3, -1, -2)$, $\mathbf{v} = \langle -1, 2, 0 \rangle$

27. $P(7, -6, -2)$, $\mathbf{v} = \langle 4, 2, 1 \rangle$

29. Identical **31.** Identical **33.** (2, 3, 1), 55.5°

35. Not intersecting **37.** (a) Yes (b) Yes (c) No

39. $y - 3 = 0$ **41.** $2x + 3y - z = 10$

43. $2x - y - 2z + 6 = 0$ **45.** $3x - 19y - 2z = 0$

47. $4x - 3y + 4z = 10$ **49.** $z = 3$ **51.** $x + y + z = 5$

53. $7x + y - 11z = 5$ **55.** $y - z = -1$ **57.** $x - z = 0$

59. $9x - 3y + 2z - 21 = 0$ **61.** Parallel **63.** Identical

65. (a) $\theta \approx 65.91°$

(b) $x = 2$, $y = 1 + t$, $z = 1 + 2t$

67. (a) $\theta \approx 69.67°$

(b) $x = 2 - 9t$, $y = -1 - 5t$, $z = 22t$

69. Orthogonal **71.** Neither; 83.5° **73.** Parallel

75.



77.



79.



81.



83. The line lies in the plane. **85.** Not intersecting

87. $\frac{6\sqrt{14}}{7}$ **89.** $\frac{11\sqrt{6}}{6}$ **91.** $\frac{2\sqrt{26}}{13}$ **93.** $\frac{27\sqrt{94}}{188}$

95. $\frac{\sqrt{2533}}{17}$ **97.** $\frac{7\sqrt{3}}{3}$ **99.** $\frac{\sqrt{66}}{3}$ **101.** Exactly 1

103. Yes. Consider three points, two on one line and one on the second line. A unique plane contains all three points.

105. (a)

Year	2012	2013	2014	2015	2016	2017
z (approx.)	20.52	21.90	22.47	23.37	24.25	25.23

The approximations are close to the actual values.

(b) An increase

107. (a) $\sqrt{70}$ in.

(b) 

(c) The distance is never zero.

(d) 5 in.

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

109. $\left(\frac{77}{13}, \frac{48}{13}, -\frac{23}{13}\right)$ **111.** $x = 21t,\ y = 1 + 11t,\ z = 4 + 13t$

113. True **115.** True

117. False. Plane $7x + y - 11z = 5$ and plane $5x + 2y - 4z = 1$ are both perpendicular to plane $2x - 3y + z = 3$ but are not parallel.

Section 11.6 *(page 806)*

1. Quadric surfaces are the three-dimensional analogs of conic sections.

3. The trace of a surface is the intersection of the surface with a plane. You find a trace by setting one variable equal to a constant, such as $x = 0$ or $z = 2$.

5. c **6.** e **7.** f **8.** b **9.** d **10.** a

11. Right circular cylinder



13. Elliptic cylinder



15. Hyperboloid of two sheets



17. Hyperboloid of one sheet



19. Ellipsoid



21. Elliptic cone



23. Hyperbolic paraboloid



25. Elliptic paraboloid



27. There have to be two minus signs to have a hyperboloid of two sheets. The number of sheets is the same as the number of minus signs.

29. No. See table on pages 800 and 801.

31. $x^2 + z^2 = 25y^2$ **33.** $x^2 + y^2 = 4z^{2/3}$

35. $y^2 + z^2 = \dfrac{4}{x^2}$ **37.** $y = \sqrt{2z}$ $\left(\text{or } x = \sqrt{2z}\right)$

39. $y = \sqrt{5 - 8x^2}$ $\left(\text{or } z = \sqrt{5 - 8x^2}\right)$ **41.** $\dfrac{128\pi}{3}$

43. (a) Major axis: $4\sqrt{2}$ (b) Major axis: $8\sqrt{2}$
Minor axis: 4 Minor axis: 8
Foci: $(0, \pm 2, 2)$ Foci: $(0, \pm 4, 8)$

45. $x^2 + z^2 = 8y$, elliptic paraboloid

47. $\dfrac{x^2}{3963^2} + \dfrac{y^2}{3963^2} + \dfrac{z^2}{3950^2} = 1$

49. $x = at,\ y = -bt,\ z = 0$;
$x = at,\ y = bt + ab^2,\ z = 2abt + a^2b^2$

51. The Klein bottle does not have both an "inside" and an "outside." It is formed by inserting the small open end through the side of the bottle and making it contiguous with the top of the bottle.

Section 11.7 *(page 813)*

1. The cylindrical coordinate system is an extension of the polar coordinate system. In this system, a point P in space is represented by an ordered triple (r, θ, z). (r, θ) is a polar representation of the projection of P in the xy-plane, and z is the directed distance from (r, θ) to P.

3. $(-7, 0, 5)$ **5.** $\left(\dfrac{3\sqrt{2}}{2}, \dfrac{3\sqrt{2}}{2}, 1\right)$ **7.** $\left(-2\sqrt{3}, -2, -3\right)$

9. $\left(5, \dfrac{\pi}{2}, 1\right)$ **11.** $\left(2\sqrt{2}, -\dfrac{\pi}{4}, -4\right)$ **13.** $\left(2, \dfrac{\pi}{3}, 4\right)$

15. $z = 4$ **17.** $r^2 - 2z^2 = 5$ **19.** $r = \sec\theta \tan\theta$

21. $r^2 \sin^2\theta = 10 - z^2$

23. $x^2 + y^2 = 9$



25. $x - \sqrt{3}y = 0$



27. $x^2 + y^2 + z^2 = 5$



29. $x^2 + (y - 2)^2 = 4$



31. $\left(4, 0, \dfrac{\pi}{2}\right)$ **33.** $\left(4\sqrt{2}, \dfrac{2\pi}{3}, \dfrac{\pi}{4}\right)$ **35.** $\left(4, \dfrac{\pi}{6}, \dfrac{\pi}{6}\right)$

37. $\left(\sqrt{6}, \sqrt{2}, 2\sqrt{2}\right)$ **39.** $(0, 0, 12)$

41. $(0.915, 0.915, 4.830)$ **43.** $\rho = 2 \csc\phi \csc\theta$

45. $\rho = 7$ **47.** $\rho = 4 \csc\phi$ **49.** $\tan^2\phi = 2$

51. $x^2 + y^2 + z^2 = 1$



53. $3x^2 + 3y^2 - z^2 = 0$



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

55. $x^2 + y^2 + (z - 2)^2 = 4$ **57.** $x^2 + y^2 = 1$




59. $\left(4, \frac{\pi}{4}, \frac{\pi}{2}\right)$ **61.** $\left(6\sqrt{2}, \frac{\pi}{2}, \frac{3\pi}{4}\right)$ **63.** $\left(13, \pi, \arccos\frac{5}{13}\right)$

65. $\left(10, \frac{\pi}{6}, 0\right)$ **67.** $\left(3\sqrt{3}, -\frac{\pi}{6}, 3\right)$ **69.** $\left(4, \frac{7\pi}{6}, 4\sqrt{3}\right)$

71. d **72.** e **73.** c **74.** a **75.** f **76.** b

77. Because of the restriction $r \geq 0$

79. (a) $r^2 + z^2 = 27$ (b) $\rho = 3\sqrt{3}$

81. (a) $r^2 + (z - 1)^2 = 1$ (b) $\rho = 2\cos\phi$

83. (a) $r = 4\sin\theta$ (b) $\rho = \dfrac{4\sin\theta}{\sin\phi} = 4\sin\theta\csc\phi$

85. (a) $r^2 = \dfrac{9}{\cos^2\theta - \sin^2\theta}$ (b) $\rho^2 = \dfrac{9\csc^2\phi}{\cos^2\theta - \sin^2\theta}$

87.



89.



91.



93.



95. Rectangular: $0 \leq x \leq 10, 0 \leq y \leq 10, 0 \leq z \leq 10$

97. Spherical: $4 \leq \rho \leq 6$

99. Cylindrical: $r^2 + z^2 \leq 9, r \leq 3\cos\theta, 0 \leq \theta \leq \pi$

101. False. See page 809. **103.** Ellipse

Review Exercises for Chapter 11 *(page 815)*

1. A point (x, y, z) describes one position in a space and has neither magnitude nor direction. A vector (x, y, z) has a magnitude and direction but does not refer to one specific position in space.

3. (a) Solve $\cos(\theta) = \dfrac{\mathbf{u} \cdot \mathbf{v}}{\|\mathbf{u}\|\|\mathbf{v}\|}$ where θ is the angle between the vectors, and $0 \leq \theta \leq \pi$.

(b) Find the cross product of two nonparallel vectors which lie on the plane.

(c) Any set of exactly three points is contained by a plane.

(d) Use a point (x_0, y_0, z_0) on the first plane and use the coefficients a, b, c, and d from the second plane's standard equation: $ax + by + cz + d = 0$ to solve the equation: $D = \dfrac{|ax_0 + by_0 + cz_0 + d|}{\sqrt{a^2 + b^2 + c^2}}$.

5. (a) $\langle -2, -3\rangle$ (b) $\mathbf{0}$

7. (a) $\mathbf{u} = \langle 3, -1\rangle, \mathbf{v} = \langle 4, 2\rangle$ (b) $\mathbf{u} = 3\mathbf{i} - \mathbf{j}, \mathbf{v} = 4\mathbf{i} + 2\mathbf{j}$
(c) $\|\mathbf{u}\| = \sqrt{10}, \|\mathbf{v}\| = 2\sqrt{5}$ (d) $\langle -5, 5\rangle$

9. $\mathbf{v} = \langle 4, 4\sqrt{3}\rangle$ **11.** $(-5, 4, 0)$ **13.** $\sqrt{22}$

15. $(x - 3)^2 + (y + 2)^2 + (z - 6)^2 = 16$

17. $(x - 2)^2 + (y - 3)^2 + z^2 = 9$
Center: $(2, 3, 0)$ Radius: 3

19. (a) and (d)



(b) $\mathbf{u} = \langle 2, 5, -10\rangle$ (c) $\mathbf{u} = 2\mathbf{i} + 5\mathbf{j} - 10\mathbf{k}$

21. $\langle -8, 5, 1\rangle$ **23.** Collinear **25.** $\dfrac{1}{\sqrt{38}}\langle 2, 3, 5\rangle$

27. (a) $\mathbf{u} = \langle -1, 4, 0\rangle$
$\mathbf{v} = \langle -3, 0, 6\rangle$
(b) 3 (c) 45

29. (a) $\dfrac{\pi}{12}$ (b) 15° **31.** Orthogonal

33. (a) $\left\langle \frac{12}{5}, \frac{16}{5}\right\rangle$ (b) $\left\langle \frac{8}{5}, -\frac{6}{5}\right\rangle$

35. Answers will vary. *Sample answer:* $\langle -6, 5, 0\rangle, \langle 6, -5, 0\rangle$

37. (a) $-9\mathbf{i} + 26\mathbf{j} - 7\mathbf{k}$ (b) $9\mathbf{i} - 26\mathbf{j} + 7\mathbf{k}$ (c) $\mathbf{0}$

39. $\left\langle \dfrac{8}{\sqrt{377}}, \dfrac{12}{\sqrt{377}}, \dfrac{13}{\sqrt{377}}\right\rangle$ or $\left\langle -\dfrac{8}{\sqrt{377}}, -\dfrac{12}{\sqrt{377}}, -\dfrac{13}{\sqrt{377}}\right\rangle$

41. 15 ft-lb

43. (a) $x = 3 + 6t, y = 11t, z = 2 + 4t$
(b) $\dfrac{x - 3}{6} = \dfrac{y}{11} = \dfrac{z - 2}{4}$

45. $x = -6, y = -8 + t, z = 2$

47. $27x + 4y + 32z + 33 = 0$ **49.** $x + 2y = 1$ **51.** $\frac{8}{7}$

53. $\dfrac{\sqrt{35}}{7}$

55. Plane



57. Plane



59. Ellipsoid



61. Hyperboloid of two sheets



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

63. Cylinder



65. $x^2 + z^2 = 2y$

67. $(-5, 0, 1)$

69. $z = y^2 + 3x$



71. (a) $\left(2\sqrt{3}, -\frac{\pi}{3}, -5\right)$ (b) $\left(\sqrt{37}, -\frac{\pi}{3}, \arccos\left(-\frac{5\sqrt{37}}{37}\right)\right)$

73. $\left(-2\sqrt{2}, 0, 2\sqrt{2}\right)$

75. $x^2 + y^2 - z^2 = 0$



77. (a) $r^2 \cos 2\theta = 2z$

(b) $\rho = 2 \sec 2\theta \cos\phi \csc^2\phi$

79. Los Angeles: $(4000, -118.24°, 55.95)$
Rio de Janeiro: $(4000, -43.23°, 112.90°)$

81. $\theta \approx 1.59$ radians

83. (a) $\frac{3\sqrt{2}}{2} \approx 2.12$ (b) $\sqrt{5} \approx 2.24$

P.S. Problem Solving *(page 817)*

1–3. Proofs

5. (a)



(b)



7. (a) $\frac{\pi}{2}$ (b) $\frac{1}{2}(\pi abk)k$

(c) $V = \frac{1}{2}(\pi ab)k^2$

$V = \frac{1}{2}$(area of base)height

9–11. Proofs

Chapter 12

Section 12.1 *(page 825)*

1. You can use a vector-valued function to trace the graph of a curve. Recall that the terminal point of the position vector $\mathbf{r}(t)$ coincides with a point on the curve.

3. $(-\infty, -1) \cup (-1, \infty)$ **5.** $(0, \infty)$

7. $[0, \infty)$ **9.** $(-\infty, \infty)$

11. (a) $\frac{1}{2}\mathbf{i}$ (b) $\mathbf{j}$ (c) $\frac{1}{2}(s+1)^2\mathbf{i} - s\mathbf{j}$

(d) $\frac{1}{2}\Delta t(\Delta t + 4)\mathbf{i} - \Delta t\mathbf{j}$

13. $\mathbf{r}(t) = 5t\mathbf{i} + 2t\mathbf{j} + 2t\mathbf{k}$, $0 \le t \le 1$

$x = 5t$, $y = 2t$, $z = 2t$, $0 \le t \le 1$

15. $\mathbf{r}(t) = (-3 + 2t)\mathbf{i} + (-6 - 3t)\mathbf{j} + (-1 - 7t)\mathbf{k}$, $0 \le t \le 1$

$x = -3 + 2t$, $y = -6 - 3t$, $z = -1 - 7t$, $0 \le t \le 1$

17. $t^2(5t - 1)$; No, the dot product is a scalar.

19. b **20.** c **21.** d **22.** a

23.



25.



27.



29.



31.



33.



35.



37.



39.



Parabola

41.



(a) The helix is translated two units back on the x-axis.

(b) The height of the helix increases at a greater rate.

(c) The orientation of the graph is reversed.

(d) The radius of the helix is increased from 2 to 6.

CHAPTER 12

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

43. $\mathbf{u}(t) = 3t^2\mathbf{i} + (t-1)\mathbf{j} + (t+2)\mathbf{k}$

45. $\mathbf{u}(t) = 3t^2\mathbf{i} + 2(t-1)\mathbf{j} + t\mathbf{k}$

47–53. Answers will vary.

55.



$\mathbf{r}(t) = t\mathbf{i} - t\mathbf{j} + 2t^2\mathbf{k}$

57.



$\mathbf{r}(t) = 2\sin t\mathbf{i} + 2\cos t\mathbf{j} + 4\sin^2 t\mathbf{k}$

59.



$\mathbf{r}(t) = (1+\sin t)\mathbf{i} + \sqrt{2}\cos t\mathbf{j} + (1-\sin t)\mathbf{k}$ and
$\mathbf{r}(t) = (1+\sin t)\mathbf{i} - \sqrt{2}\cos t\mathbf{j} + (1-\sin t)\mathbf{k}$

61. $\mathbf{r}(t) = t\mathbf{i} + t\mathbf{j} + \sqrt{4-t^2}\mathbf{k}$



63. Let $x = t$, $y = 2t\cos t$, and $z = 2t\sin t$. Then

$$\begin{aligned} y^2 + z^2 &= (2t\cos t)^2 + (2t\sin t)^2 \\ &= 4t^2\cos^2 t + 4t^2\sin^2 t \\ &= 4t^2(\cos^2 t + \sin^2 t) \\ &= 4t^2. \end{aligned}$$

Because $x = t$, $y^2 + z^2 = 4x^2$.



65. $\pi\mathbf{i} - \mathbf{j}$ **67.** $\mathbf{0}$ **69.** $\mathbf{i} + \mathbf{j} + \mathbf{k}$

71. $\left(-\infty, -\frac{1}{2}\right), \left(-\frac{1}{2}, 0\right), (0, \infty)$ **73.** $[-1, 1]$

75. $\left(-\frac{\pi}{2} + n\pi, \frac{\pi}{2} + n\pi\right)$, n is an integer.

77. It is a line; Answers will vary.

79. $\mathbf{r}(t) = \begin{cases} \mathbf{i} + \mathbf{j}, & t \geq 3 \\ -\mathbf{i} + \mathbf{j}, & t < 3 \end{cases}$

81. $\mathbf{r}(t) = \cos t\mathbf{i} + \sin t\mathbf{j} + \frac{1}{\pi}t\mathbf{k}$, $0 \leq t \leq 4\pi$



83–85. Proofs **87.** Yes; yes **89.** Not necessarily

Section 12.2 *(page 834)*

1. $\mathbf{r}'(t_0)$ represents the vector that is tangent to the curve represented by $\mathbf{r}(t)$ at the point t_0.

3. $\mathbf{r}'(t) = -2t\mathbf{i} + \mathbf{j}$
$\mathbf{r}(3) = -8\mathbf{i} + 3\mathbf{j}$
$\mathbf{r}'(3) = -6\mathbf{i} + \mathbf{j}$



5. $\mathbf{r}'(t) = -\sin t\mathbf{i} + \cos t\mathbf{j}$
$\mathbf{r}\left(\frac{\pi}{2}\right) = \mathbf{j}$
$\mathbf{r}'\left(\frac{\pi}{2}\right) = -\mathbf{i}$



7. $\mathbf{r}'(t) = \langle e^t, 2e^{2t}\rangle$
$\mathbf{r}(0) = \mathbf{i} + \mathbf{j}$
$\mathbf{r}'(0) = \mathbf{i} + 2\mathbf{j}$



9. $\mathbf{r}'(t) = -2\sin t\mathbf{i} + 2\cos t\mathbf{j} + \mathbf{k}$
$\mathbf{r}\left(\frac{3\pi}{2}\right) = -2\mathbf{j} + \left(\frac{3\pi}{2}\right)\mathbf{k}$
$\mathbf{r}'\left(\frac{3\pi}{2}\right) = 2\mathbf{i} + \mathbf{k}$



11. $4t^3\mathbf{i} - 5\mathbf{j}$ **13.** $-9\sin t\cos^2 t\mathbf{i} + 6\sin^2 t\cos t\mathbf{j}$

15. $-e^{-t}\mathbf{i} + (5te^t + 5e^t)\mathbf{k}$

17. $\langle \sin t + t\cos t, \cos t - t\sin t, 1\rangle$

19. (a) $3t^2\mathbf{i} + t\mathbf{j}$ (b) $6t\mathbf{i} + \mathbf{j}$ (c) $18t^3 + t$

21. (a) $-4\sin t\mathbf{i} + 4\cos t\mathbf{j}$ (b) $-4\cos t\mathbf{i} - 4\sin t\mathbf{j}$ (c) 0

23. (a) $t\mathbf{i} - \mathbf{j} + \frac{1}{2}t^2\mathbf{k}$ (b) $\mathbf{i} + t\mathbf{k}$ (c) $\frac{t^3}{2} + t$

(d) $-t\mathbf{i} - \frac{1}{2}t^2\mathbf{j} + \mathbf{k}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

25. (a) $\langle t\cos t, t\sin t, 1\rangle$
(b) $\langle \cos t - t\sin t, \sin t + t\cos t, 0\rangle$ (c) t
(d) $\langle -\sin t - t\cos t, \cos t - t\sin t, t^2\rangle$

27. $(-\infty, 0), (0, \infty)$ **29.** $\left(\frac{\pi}{2}, 2\pi\right)$

31. $(-\infty, -2), (-2, \infty)$

33. $\left(-\frac{\pi}{2} + n\pi, \frac{\pi}{2} + n\pi\right)$, n is an integer

35. (a) $\mathbf{i} + 3\mathbf{j} + 2t\mathbf{k}$ (b) $-\mathbf{i} + (9 - 2t)\mathbf{j} + (6t - 3t^2)\mathbf{k}$
(c) $40t\mathbf{i} + 15t^2\mathbf{j} + 20t^3\mathbf{k}$ (d) $8t + 9t^2 + 5t^4$
(e) $8t^3\mathbf{i} + (12t^2 - 4t^3)\mathbf{j} + (3t^2 - 24t)\mathbf{k}$
(f) $2\mathbf{i} + 6\mathbf{j} + 8t\mathbf{k}$

37. (a) $7t^6$ (b) $12t^5\mathbf{i} - 5t^4\mathbf{j}$ **39.** $t^2\mathbf{i} + t\mathbf{j} + 9t\mathbf{k} + \mathbf{C}$

41. $\ln|t|\mathbf{i} + t\mathbf{j} - \frac{2}{5}t^{5/2}\mathbf{k} + \mathbf{C}$ **43.** $t\mathbf{i} + t^4\mathbf{j} + \frac{5^t}{\ln 5}\mathbf{k} + \mathbf{C}$

45. $e^t\mathbf{i} + t\mathbf{j} + (t\sin t + \cos t)\mathbf{k} + \mathbf{C}$

47. $4\mathbf{i} + \frac{1}{2}\mathbf{j} - \mathbf{k}$ **49.** $5\mathbf{i} + 6\mathbf{j} + \frac{\pi}{2}\mathbf{k}$

51. $2\mathbf{i} + (e^2 - 1)\mathbf{j} - (e^2 + 1)\mathbf{k}$

53. $2e^{2t}\mathbf{i} + 3(e^t - 1)\mathbf{j}$ **55.** $600\sqrt{3}t\mathbf{i} + (-16t^2 + 600t)\mathbf{j}$

57. $\frac{2 - e^{-t^2}}{2}\mathbf{i} + (e^{-t} - 2)\mathbf{j} + (t + 1)\mathbf{k}$

59. The three components of $\mathbf{u}$ are increasing functions of t at $t = t_0$.

61–67. Proofs

69. (a) 

The curve is a cycloid.

(b) The maximum of $\|\mathbf{r}'\|$ is 2, and the minimum of $\|\mathbf{r}'\|$ is 0. The maximum and the minimum of $\|\mathbf{r}'\|$ are 1.

71. Proof **73.** True

75. False. Let $\mathbf{r}(t) = \cos t\mathbf{i} + \sin t\mathbf{j} + \mathbf{k}$, then $\frac{d}{dt}\big[\|\mathbf{r}(t)\|\big] = 0$, but $\|\mathbf{r}'(t)\| = 1$.

Section 12.3 *(page 842)*

1. The direction of the velocity vector provides the direction of motion at time t, and the magnitude of the velocity vector provides the speed of the object.

3. (a) $\mathbf{v}(t) = 3\mathbf{i} + \mathbf{j}$
$\|\mathbf{v}(t)\| = \sqrt{10}$
$\mathbf{a}(t) = \mathbf{0}$
(b) $\mathbf{v}(1) = 3\mathbf{i} + \mathbf{j}$
$\mathbf{a}(1) = \mathbf{0}$
(c) 

5. (a) $\mathbf{v}(t) = 2t\,\mathbf{i} + 3t^2\mathbf{j}$
$\|\mathbf{v}(t)\| = \sqrt{4t^2 + 9t^4}$
$\mathbf{a}(t) = 2\mathbf{i} + 6t\mathbf{j}$
(b) $\mathbf{v}(1) = 2\mathbf{i} + 3\mathbf{j}$
$\mathbf{a}(1) = 2\mathbf{i} + 6\mathbf{j}$
(c) 

7. (a) $\mathbf{v}(t) = 2t\mathbf{i} + \mathbf{j}$
$\|\mathbf{v}(t)\| = \sqrt{4t^2 + 1}$
$\mathbf{a}(t) = 2\mathbf{i}$
(b) $\mathbf{v}(2) = 4\mathbf{i} + \mathbf{j}$
$\mathbf{a}(2) = 2\mathbf{i}$
(c) 

9. (a) $\mathbf{v}(t) = -2\sin t\mathbf{i} + 2\cos t\mathbf{j}$
$\|\mathbf{v}(t)\| = 2$
$\mathbf{a}(t) = -2\cos t\mathbf{i} - 2\sin t\mathbf{j}$
(b) $\mathbf{v}\left(\frac{\pi}{4}\right) = -\sqrt{2}\mathbf{i} + \sqrt{2}\mathbf{j}$
$\mathbf{a}\left(\frac{\pi}{4}\right) = -\sqrt{2}\mathbf{i} - \sqrt{2}\mathbf{j}$
(c) 

11. (a) $\mathbf{v}(t) = \langle 1 - \cos t, \sin t\rangle$
$\|\mathbf{v}(t)\| = \sqrt{2 - 2\cos t}$
$\mathbf{a}(t) = \langle \sin t, \cos t\rangle$
(b) $\mathbf{v}(\pi) = \langle 2, 0\rangle$
$\mathbf{a}(\pi) = \langle 0, -1\rangle$
(c) 

13. (a) $\mathbf{v}(t) = \mathbf{i} + 5\mathbf{j} + 3\mathbf{k}$
$\|\mathbf{v}(t)\| = \sqrt{35}$
$\mathbf{a}(t) = \mathbf{0}$
(b) $\mathbf{v}(1) = \mathbf{i} + 5\mathbf{j} + 3\mathbf{k}$
$\mathbf{a}(1) = \mathbf{0}$

15. (a) $\mathbf{v}(t) = \mathbf{i} + 2t\mathbf{j} + t\mathbf{k}$
$\|\mathbf{v}(t)\| = \sqrt{1 + 5t^2}$
$\mathbf{a}(t) = 2\mathbf{j} + \mathbf{k}$
(b) $\mathbf{v}(4) = \mathbf{i} + 8\mathbf{j} + 4\mathbf{k}$
$\mathbf{a}(4) = 2\mathbf{j} + \mathbf{k}$

17. (a) $\mathbf{v}(t) = \mathbf{i} - \mathbf{j} - \frac{t}{\sqrt{9 - t^2}}\mathbf{k}$
$\|\mathbf{v}(t)\| = \sqrt{\frac{18 - t^2}{9 - t^2}}$
$\mathbf{a}(t) = -\frac{9}{(9 - t^2)^{3/2}}\mathbf{k}$
(b) $\mathbf{v}(0) = \mathbf{i} - \mathbf{j}$
$\mathbf{a}(0) = -\frac{1}{3}\mathbf{k}$

19. (a) $\mathbf{v}(t) = 4\mathbf{i} - 3\sin t\mathbf{j} + 3\cos t\mathbf{k}$
$\|\mathbf{v}(t)\| = 5$
$\mathbf{a}(t) = -3\cos t\mathbf{j} - 3\sin t\mathbf{k}$
(b) $\mathbf{v}(\pi) = \langle 4, 0, -3\rangle$
$\mathbf{a}(\pi) = \langle 0, 3, 0\rangle$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

21. (a) $\mathbf{v}(t) = (e^t \cos t - e^t \sin t)\mathbf{i} + (e^t \sin t + e^t \cos t)\mathbf{j} + e^t\mathbf{k}$
$\|\mathbf{v}(t)\| = e^t\sqrt{3}$
$\mathbf{a}(t) = -2e^t \sin t\,\mathbf{i} + 2e^t \cos t\,\mathbf{j} + e^t\mathbf{k}$
(b) $\mathbf{v}(0) = \langle 1, 1, 1\rangle$
$\mathbf{a}(0) = \langle 0, 2, 1\rangle$

23. $\mathbf{v}(t) = t(\mathbf{i} + \mathbf{j} + \mathbf{k})$
$\mathbf{r}(t) = \frac{t^2}{2}(\mathbf{i} + \mathbf{j} + \mathbf{k})$
$\mathbf{r}(2) = 2(\mathbf{i} + \mathbf{j} + \mathbf{k})$

25. $\mathbf{v}(t) = \left(\frac{t^2}{2} + \frac{9}{2}\right)\mathbf{j} + \left(\frac{t^2}{2} - \frac{1}{2}\right)\mathbf{k}$
$\mathbf{r}(t) = \left(\frac{t^3}{6} + \frac{9}{2}t - \frac{14}{3}\right)\mathbf{j} + \left(\frac{t^3}{6} - \frac{1}{2}t + \frac{1}{3}\right)\mathbf{k}$
$\mathbf{r}(2) = \frac{17}{3}\mathbf{j} + \frac{2}{3}\mathbf{k}$

27. $\mathbf{v}(t) = -\sin t\,\mathbf{i} + \cos t\,\mathbf{j} + \mathbf{k}$
$\mathbf{r}(t) = \cos t\,\mathbf{i} + \sin t\,\mathbf{j} + t\mathbf{k}$
$\mathbf{r}(2) = (\cos 2)\mathbf{i} + (\sin 2)\mathbf{j} + 2\mathbf{k}$

29. 45.5 ft; The ball will clear the fence.

31. $v_0 = 40\sqrt{6}$ ft/sec; 78 ft **33.** Proof

35. (a) $\mathbf{r}(t) = \left(\frac{440}{3}\cos\theta_0\right)t\mathbf{i} + \left[3 + \left(\frac{440}{3}\sin\theta_0\right)t - 16t^2\right]\mathbf{j}$
(b)



The minimum angle appears to be $\theta_0 = 20°$.
(c) $\theta_0 \approx 19.38°$

37. (a) $v_0 = 28.78$ ft/sec, $\theta = 58.28°$ (b) $v_0 \approx 32$ ft/sec

39. 1.91°

41. (a)



Maximum height: 2.1 ft
Range: 46.6 ft

(b)



Maximum height: 10.0 ft
Range: 227.8 ft

(c)



Maximum height: 34.0 ft
Range: 136.1 ft

(d)



Maximum height: 166.5 ft
Range: 666.1 ft

(e)



Maximum height: 51.0 ft
Range: 117.9 ft

(f)



Maximum height: 249.8 ft
Range: 576.9 ft

43. Maximum height: 129.1 m; Range: 886.3 m **45.** Proof

47. $\mathbf{v}(t) = b\omega[(1 - \cos\omega t)\mathbf{i} + \sin\omega t\mathbf{j}]$
$\mathbf{a}(t) = b\omega^2(\sin\omega t\mathbf{i} + \cos\omega t\mathbf{j})$
(a) $\|\mathbf{v}(t)\| = 0$ when $\omega t = 0, 2\pi, 4\pi, \ldots$
(b) $\|\mathbf{v}(t)\|$ is maximum when $\omega t = \pi, 3\pi, \ldots$

49. $\mathbf{v}(t) = -b\omega \sin\omega t\mathbf{i} + b\omega\cos\omega t\mathbf{j}$
$\mathbf{v}(t) \cdot \mathbf{r}(t) = 0$

51. $\mathbf{a}(t) = -b\omega^2(\cos\omega t\mathbf{i} + \sin\omega t\mathbf{j}) = -\omega^2\mathbf{r}(t)$; $\mathbf{a}(t)$ is a negative multiple of a unit vector from (0, 0) to $(\cos\omega t, \sin\omega t)$, so $\mathbf{a}(t)$ is directed toward the origin.

53. $8\sqrt{2}$ ft/sec

55. The velocity of an object involves both magnitude and direction of motion, whereas speed involves only magnitude.

57. This is true for uniform circular motion but not true for non-uniform circular motion.

59–61. Proofs **63.** True

65. False. Consider $\mathbf{r}(t) = \langle t^2, -t^2\rangle$. Then $\mathbf{v}(t) = \langle 2t, -2t\rangle$ and $\|\mathbf{v}(t)\| = \sqrt{8t^2}$.

Section 12.4 *(page 852)*

1. The unit tangent vector points in the direction of motion.

3. $\mathbf{T}(1) = \frac{\sqrt{2}}{2}(\mathbf{i} + \mathbf{j})$ **5.** $\mathbf{T}\left(\frac{\pi}{3}\right) = -\frac{\sqrt{3}}{2}\mathbf{i} + \frac{1}{2}\mathbf{j}$

7. $\mathbf{T}(e) = \frac{3e\mathbf{i} - \mathbf{j}}{\sqrt{9e^2 + 1}} \approx 0.9926\mathbf{i} - 0.1217\mathbf{j}$

9. $\mathbf{T}(0) = \frac{\sqrt{2}}{2}(\mathbf{i} + \mathbf{k})$
$x = t$
$y = 0$
$z = t$

11. $\mathbf{T}(0) = \frac{\sqrt{2}}{2}(\mathbf{j} + \mathbf{k})$
$x = 1$
$y = 3t$
$z = -4 + 3t$

13. $\mathbf{T}\left(\frac{\pi}{4}\right) = \frac{1}{2}\langle -\sqrt{2}, \sqrt{2}, 0\rangle$
$x = \sqrt{2} - \sqrt{2}t$
$y = \sqrt{2} + \sqrt{2}t$
$z = 4$

15. $\mathbf{N}(2) = \frac{\sqrt{5}}{5}(-2\mathbf{i} + \mathbf{j})$

17. $\mathbf{N}(1) = -\frac{\sqrt{14}}{14}(\mathbf{i} - 2\mathbf{j} + 3\mathbf{k})$

19. $\mathbf{N}\left(\frac{3\pi}{4}\right) = \frac{\sqrt{2}}{2}(\mathbf{i} - \mathbf{j})$

21. $\mathbf{r}(2) = 2\mathbf{i} + \frac{1}{2}\mathbf{j}$
$\mathbf{T}(2) = \frac{\sqrt{17}}{17}(4\mathbf{i} - \mathbf{j})$
$\mathbf{N}(2) = \frac{\sqrt{17}}{17}(\mathbf{i} + 4\mathbf{j})$



23. $\mathbf{r}(2) = 5\mathbf{i} - 4\mathbf{j}$
$\mathbf{T}(2) = \frac{\mathbf{i} - 2\mathbf{j}}{\sqrt{5}}$
$\mathbf{N}(2) = \frac{-2\mathbf{i} - \mathbf{j}}{\sqrt{5}}$,
perpendicular to $\mathbf{T}(2)$



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

25. $a_{\mathbf{T}} = -\sqrt{2}$ $a_{\mathbf{N}} = \sqrt{2}$ **27.** $a_{\mathbf{T}} = -\frac{7\sqrt{5}}{5}$ $a_{\mathbf{N}} = \frac{6\sqrt{5}}{5}$ **29.** $a_{\mathbf{T}} = \sqrt{2}e^{\pi/2}$ $a_{\mathbf{N}} = \sqrt{2}e^{\pi/2}$

31. $\mathbf{T}(t) = -\sin \omega t\mathbf{i} + \cos \omega t\mathbf{j}$
$\mathbf{N}(t) = -\cos \omega t\mathbf{i} - \sin \omega t\mathbf{j}$
$a_{\mathbf{T}} = 0$
$a_{\mathbf{N}} = a\omega^2$

33. $\|\mathbf{v}(t)\| = a\omega$; The speed is constant because $a_{\mathbf{T}} = 0$.

35. $a_{\mathbf{T}}$ is undefined. $a_{\mathbf{N}}$ is undefined. **37.** $a_{\mathbf{T}} = \frac{5\sqrt{6}}{6}$ $a_{\mathbf{N}} = \frac{\sqrt{30}}{6}$

39. $a_{\mathbf{T}} = \sqrt{3}$
$a_{\mathbf{N}} = \sqrt{2}$

41. The particle's motion is in a straight line.

43. $\mathbf{v}(t) = \mathbf{r}'(t) = 3\mathbf{i} + 4\mathbf{j}$
$\|\mathbf{v}(t)\| = \sqrt{9 + 16} = 5$
$\mathbf{a}(t) = \mathbf{v}'(t) = \mathbf{0}$
$\mathbf{T}(t) = \frac{\mathbf{v}(t)}{\|\mathbf{v}(t)\|} = \frac{3}{5}\mathbf{i} + \frac{4}{5}\mathbf{j}$
$\mathbf{T}'(t) = 0 \implies \mathbf{N}(t)$ does not exist.
The path is a line. The speed is constant (5).

45. (a) $t = \frac{1}{2}$: $a_{\mathbf{T}} = \frac{\sqrt{2}\pi^2}{2}$, $a_{\mathbf{N}} = \frac{\sqrt{2}\pi^2}{2}$
$t = 1$: $a_{\mathbf{T}} = 0$, $a_{\mathbf{N}} = \pi^2$
$t = \frac{3}{2}$: $a_{\mathbf{T}} = -\frac{\sqrt{2}\pi^2}{2}$, $a_{\mathbf{N}} = \frac{\sqrt{2}\pi^2}{2}$
(b) $t = \frac{1}{2}$: Increasing because $a_{\mathbf{T}} > 0$.
$t = 1$: Maximum because $a_{\mathbf{T}} = 0$.
$t = \frac{3}{2}$: Decreasing because $a_{\mathbf{T}} < 0$.

47. $\mathbf{T}\left(\frac{\pi}{2}\right) = \frac{\sqrt{17}}{17}(-4\mathbf{i} + \mathbf{k})$
$\mathbf{N}\left(\frac{\pi}{2}\right) = -\mathbf{j}$
$\mathbf{B}\left(\frac{\pi}{2}\right) = \frac{\sqrt{17}}{17}(\mathbf{i} + 4\mathbf{k})$

49. $\mathbf{T}\left(\frac{\pi}{4}\right) = \frac{\sqrt{2}}{2}(\mathbf{j} - \mathbf{k})$
$\mathbf{N}\left(\frac{\pi}{4}\right) = -\frac{\sqrt{2}}{2}(\mathbf{j} + \mathbf{k})$
$\mathbf{B}\left(\frac{\pi}{4}\right) = -\mathbf{i}$

51. $\mathbf{T}\left(\frac{\pi}{3}\right) = \frac{\sqrt{5}}{5}\left(\mathbf{i} - \sqrt{3}\mathbf{j} + \mathbf{k}\right)$
$\mathbf{N}\left(\frac{\pi}{3}\right) = -\frac{1}{2}\left(\sqrt{3}\mathbf{i} + \mathbf{j}\right)$
$\mathbf{B}\left(\frac{\pi}{3}\right) = \frac{\sqrt{5}}{10}\left(\mathbf{i} - \sqrt{3}\mathbf{j} - 4\mathbf{k}\right)$

53. $\mathbf{N}(t) = \frac{1}{\sqrt{16t^2 + 9}}(-4t\mathbf{i} + 3\mathbf{j})$

55. $\mathbf{N}(t) = \frac{1}{\sqrt{5t^2 + 25}}(-t\mathbf{i} - 2t\mathbf{j} + 5\mathbf{k})$

57. $a_{\mathbf{T}} = \frac{-32(v_0 \sin \theta - 32t)}{\sqrt{v_0^2 \cos^2 \theta + (v_0 \sin \theta - 32t)^2}}$
$a_{\mathbf{N}} = \frac{32v_0 \cos \theta}{\sqrt{v_0^2 \cos^2 \theta + (v_0 \sin \theta - 32t)^2}}$
At maximum height, $a_{\mathbf{T}} = 0$ and $a_{\mathbf{N}} = 32$.

59. (a) $\mathbf{r}(t) = 60\sqrt{3}t\mathbf{i} + (5 + 60t - 16t^2)\mathbf{j}$
(b)



Maximum height $\approx$ 61.245 ft
Range $\approx$ 398.186 ft
(c) $\mathbf{v}(t) = 60\sqrt{3}\mathbf{i} + (60 - 32t)\mathbf{j}$
$\|\mathbf{v}(t)\| = 8\sqrt{16t^2 - 60t + 225}$
$\mathbf{a}(t) = -32\mathbf{j}$
(d)

t	0.5	1.0	1.5
Speed	112.85	107.63	104.61

t	2.0	2.5	3.0
Speed	104	105.83	109.98

(e)



The speed is decreasing when $a_{\mathbf{T}}$ and $a_{\mathbf{N}}$ have opposite signs.

61. (a) $4\sqrt{625\pi^2 + 1} \approx 314$ mi/h
(b) $a_{\mathbf{T}} = 0$, $a_{\mathbf{N}} = 1000\pi^2$
$a_{\mathbf{T}} = 0$ because the speed is constant.

63. (a) The centripetal component is quadrupled.
(b) The centripetal component is halved.

65. 4.74 mi/sec **67.** 4.67 mi/sec

69. False. These vectors are perpendicular for an object traveling at a constant speed but not for an object traveling at a variable speed.

71. (a) and (b) Proofs **73–75.** Proofs

Section 12.5 *(page 864)*

1. The curve bends more sharply at Q than at P.

3.



$3\sqrt{10}$

5.



$\frac{13\sqrt{13} - 8}{27}$

7.



$6a$

9. 362.9

CHAPTER 12

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

11.



$\sqrt{26}$

13.



$\dfrac{3\sqrt{17}\pi}{2}$

15.



$2\pi\sqrt{a^2 + b^2}$

17. (a) $2\sqrt{21} \approx 9.165$ (b) 9.529
(c) Increase the number of line segments. (d) 9.571

19. 0 **21.** $\dfrac{1}{4}$ **23.** 0 **25.** $\dfrac{\sqrt{2}}{2}$ **27.** 1 **29.** $\dfrac{1}{4}$

31. $\dfrac{1}{a}$ **33.** $\dfrac{\sqrt{5}}{(1 + 5t^2)^{3/2}}$ **35.** $\dfrac{3}{25}$ **37.** $\dfrac{12}{125}$

39. $\dfrac{7\sqrt{26}}{676}$ **41.** $K = 0$, $\dfrac{1}{K}$ is undefined.

43. $K = \dfrac{10}{101^{3/2}}, \dfrac{1}{K} = \dfrac{101^{3/2}}{10}$ **45.** $K = 4, \dfrac{1}{K} = \dfrac{1}{4}$

47. $K = \dfrac{12}{145^{3/2}}, \dfrac{1}{K} = \dfrac{145^{3/2}}{12}$ **49.** (a) $(1, 3)$ (b) 0

51. (a) $K \to \infty$ as $x \to 0$ (No maximum) (b) 0

53. (a) $\left(\dfrac{1}{\sqrt{2}}, -\dfrac{\ln 2}{2}\right)$ (b) 0 **55.** $(0, 1)$

57. $(\pi + 2n\pi, 0)$ **59.** $c = \pm\sqrt{2}$

61. (a) $K = \dfrac{2|6x^2 - 1|}{(16x^6 - 16x^4 + 4x^2 + 1)^{3/2}}$

(b) $x = 0$: $x^2 + \left(y + \dfrac{1}{2}\right)^2 = \dfrac{1}{4}$

$x = 1$: $x^2 + \left(y - \dfrac{1}{2}\right)^2 = \dfrac{5}{4}$



(c)



The curvature tends to be greatest near the extrema of the function and decreases as $x \to \pm\infty$. However, f and K do not have the same critical numbers.

Critical numbers of f: $x = 0, \pm\dfrac{\sqrt{2}}{2} \approx \pm 0.7071$

Critical numbers of K: $x = 0, \pm 0.7647, \pm 0.4082$

63. $a = \frac{1}{4}, b = 2$



65. (a) 12.25 units (b) $\frac{1}{2}$ **67–69.** Proofs

71. (a) 0 (b) 0 **73.** $\frac{1}{4}$ **75.** Proof

77. $K = \dfrac{1}{4a}\left|\csc\dfrac{\theta}{2}\right|$

Minimum: $K = \dfrac{1}{4a}$

There is no maximum.

79. 3327.5 lb **81.** Proof

83. False. See Exploration on page 855.

85. True **87–93.** Proofs

Review Exercises for Chapter 12 *(page 867)*

1. The domain of a vector-valued function is the intersection of the domains of the component functions and is a set of real numbers. The range of a vector-valued function is a set of vectors.

3. Even though the speed is constant, the velocity vector might be changing direction, making the acceleration nonzero. For example, consider $\mathbf{r}(t) = \cos t\mathbf{i} + \sin t\mathbf{j}$.

5. (a) $\left(x - \dfrac{\pi}{2}\right)^2 + y^2 = 1$

(b) Because the curvature is not as great, the radius of the curvature is greater.

7. (a) All reals except $\dfrac{\pi}{2} + n\pi$, n is an integer.

(b) Continuous except at $t = \dfrac{\pi}{2} + n\pi$, n is an integer.

9. (a) $[3, \infty)$ (b) Continuous for all $t \geq 3$

11. (a) $\mathbf{i} - \sqrt{2}\mathbf{k}$ (b) $-3\mathbf{i} + 4\mathbf{j}$
(c) $(2c - 1)\mathbf{i} + (c - 1)^2\mathbf{j} - \sqrt{c + 1}\mathbf{k}$
(d) $2\Delta t\mathbf{i} + \Delta t(\Delta t + 2)\mathbf{j} - \left(\sqrt{\Delta t + 3} - \sqrt{3}\right)\mathbf{k}$

13. $\mathbf{r}(t) = (3 - t)\mathbf{i} - 2t\mathbf{j} + (5 - 2t)\mathbf{k}, \quad 0 \leq t \leq 1$
$x = 3 - t, y = -2t, z = 5 - 2t, \quad 0 \leq t \leq 1$

15.



17.



19. $\mathbf{r}(t) = t\mathbf{i} + \left(-\frac{3}{4}t + 3\right)\mathbf{j}$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

21.



$x = t,\ y = 2,\ z = t^2 + 4$

23. $\ln 3\mathbf{j} - \frac{1}{3}\mathbf{k}$

25. (a) $(2t + 4)\mathbf{i} - 6t\mathbf{j}$
(b) $2\mathbf{i} - 6\mathbf{j}$
(c) $40t + 8$

27. (a) $6t^2\mathbf{i} + 4\mathbf{j} - 2t\mathbf{k}$
(b) $12t\mathbf{i} - 2\mathbf{k}$
(c) $72t^3 + 4t$
(d) $-8\mathbf{i} - 12t^2\mathbf{j} - 48t\mathbf{k}$

29. $(-\infty, 1), (1, \infty)$

31. (a) $3\mathbf{i} + \mathbf{j}$ (b) $-5\mathbf{i} + (2t - 2)\mathbf{j} + 2t^2\mathbf{k}$
(c) $18t\mathbf{i} + (6t - 3)\mathbf{j}$ (d) $4t + 3t^2$
(e) $\left(\frac{8}{3}t^3 - 2t^2\right)\mathbf{i} - 8t^3\mathbf{j} + (9t^2 - 2t + 1)\mathbf{k}$
(f) $2\mathbf{i} + 8t\mathbf{j} + 16t^2\mathbf{k}$

33. $\frac{1}{3}t^3\mathbf{i} + \frac{5}{2}t^2\mathbf{j} + 2t^4\mathbf{k} + \mathbf{C}$ **35.** $2t^{3/2}\mathbf{i} + 2\ln|t|\mathbf{j} + t\mathbf{k} + \mathbf{C}$

37. $\frac{32}{3}\mathbf{j}$ **39.** $2(e - 1)\mathbf{i} - 8\mathbf{j} - 2\mathbf{k}$

41. $\mathbf{r}(t) = (t^2 + 1)\mathbf{i} + (e^t + 2)\mathbf{j} - (e^{-t} + 4)\mathbf{k}$

43. (a) $\mathbf{v}(t) = 4\mathbf{i} + 3t^2\mathbf{j} - \mathbf{k}$
$\|\mathbf{v}(t)\| = \sqrt{17 + 9t^4}$
$\mathbf{a}(t) = 6t\mathbf{j}$
(b) $\mathbf{v}(1) = 4\mathbf{i} + 3\mathbf{j} - \mathbf{k}$
$\mathbf{a}(1) = 6\mathbf{j}$

45. (a) $\mathbf{v}(t) = \langle -3\cos^2 t \sin t, 3\sin^2 t \cos t, 3\rangle$
$\|\mathbf{v}(t)\| = 3\sqrt{\sin^2 t \cos^2 t + 1}$
$\mathbf{a}(t) = \langle 3\cos t(2\sin^2 t - \cos^2 t), 3\sin t(2\cos^2 t - \sin^2 t), 0\rangle$
(b) $\mathbf{v}(\pi) = \langle 0, 0.\ 3\rangle$
$\mathbf{a}(\pi) = \langle 3, 0, 0\rangle$

47. 11.67 ft; The ball will clear the fence.

49. $\mathbf{T}(2) = \dfrac{3\mathbf{i} - 2\mathbf{j}}{\sqrt{13}}$

51. $\mathbf{T}(0) = \dfrac{2\mathbf{i} - 3\mathbf{k}}{\sqrt{13}}$; $x = 1 + 2t,\ y = 1,\ z = -3t$

53. $\mathbf{N}(1) = -\dfrac{3\sqrt{10}}{10}\mathbf{i} + \dfrac{\sqrt{10}}{10}\mathbf{j}$ **55.** $\mathbf{N}\left(\dfrac{\pi}{4}\right) = -\mathbf{j}$

57. $a_{\mathbf{T}} = -\dfrac{2\sqrt{13}}{585}$
$a_{\mathbf{N}} = \dfrac{4\sqrt{13}}{65}$

59. $a_{\mathbf{T}} = 0$
$a_{\mathbf{N}} = 1$

61.



$5\sqrt{13}$

63.



2

65.



$3\sqrt{29}$

67.



$\dfrac{\sqrt{65}\pi}{2}$

69. 0 **71.** $\dfrac{2\sqrt{5}}{(4 + 5t^2)^{3/2}}$ **73.** $\dfrac{\sqrt{2}}{3}$

75. $K = \dfrac{1}{26^{3/2}}, \dfrac{1}{K} = 26\sqrt{26}$ **77.** $K = \dfrac{\sqrt{2}}{4}, r = 2\sqrt{2}$

79. Unit tangent: $\left\langle -\frac{4}{5}, 0, \frac{3}{5}\right\rangle$
Principal unit normal: $\langle 0, -1, 0\rangle$
Binormal: $\left\langle \frac{3}{5}, 0, \frac{4}{5}\right\rangle$



81. (a) and (b) Proofs

P.S. Problem Solving *(page 870)*

1. Initial speed: 447.21 ft/sec; $\theta \approx 63.43°$

3. Proofs **5.** Proofs

7. At the point (4, 1), $K = \dfrac{120}{(89)^{3/2}} \implies r = \dfrac{1}{K} = \dfrac{(89)^{3/2}}{120} \approx 7.$

Chapter 13

Section 13.1 *(page 880)*

1. There is not a unique value of z for each ordered pair.

3. z is a function of x and y. **5.** z is a function of x and y.

7. z is not a function of x and y.

9. (a) 1 (b) 1 (c) -17
(d) $9 - y$ (e) $2x - 1$ (f) $13 - t$

11. (a) -1 (b) 0 (c) xe^3 (d) te^{-y}

13. (a) 3 (b) 2 (c) $\dfrac{16}{t}$ (d) $-\dfrac{6}{5}$

15. (a) $\sqrt{2}$ (b) $3\sin 1$ (c) 0 (d) 4

17. (a) -4 (b) -6 (c) $-\frac{25}{4}$ (d) $\frac{9}{4}$

19. (a) $2, \Delta x \neq 0$ (b) $2y + \Delta y, \Delta y \neq 0$

21. Domain: $\{(x, y)$: x is any real number, y is any real number$\}$
Range: all real numbers

23. Domain: $\{(x, y)$: $y \geq 0\}$
Range: all real numbers

25. Domain: $\{(x, y)$: $x \neq 0, y \neq 0\}$
Range: all real numbers

27. Domain: $\{(x, y)$: $x^2 + y^2 \leq 4\}$
Range: $0 \leq z \leq 2$

29. Domain: $\{(x, y)$: $-1 \leq x + y \leq 1\}$
Range: $0 \leq z \leq \pi$

CHAPTER 13

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

31. Domain: $\{(x, y): y < -x + 5\}$
Range: all real numbers

33. (a) (20, 0, 0) (b) (−15, 10, 20)
(c) (20, 15, 25) (d) (20, 20, 0)

35. Plane



37. Cylinder with rulings parallel to the x-axis



39. Paraboloid



41. Cylinder with rulings parallel to the y-axis



43.



45.



47. c **48.** d **49.** b **50.** a

51. Lines: $x + y = c$



53. Ellipses: $x^2 + 4y^2 = c$ [except $x^2 + 4y^2 = 0$ is the point (0, 0)]



55. Hyperbolas: $xy = c$



57. Circles passing through (0, 0)
Centered at $\left(\frac{1}{2c}, 0\right)$



59.



61.



63. Yes; The definition of a function of two variables requires that z be unique for each ordered pair (x, y) in the domain.

65. $f(x, y) = \frac{x}{y}$ $\left(\text{The level curves are the lines } y = \frac{x}{c}.\right)$

67. The surface may be shaped like a saddle. For example, let $f(x, y) = xy$. The graph is not unique because any vertical translation will produce the same level curves.

69.

	Inflation Rate		
Tax Rate	0	0.03	0.05
0	\$1790.85	\$1332.56	\$1099.43
0.28	\$1526.43	\$1135.80	\$937.09
0.35	\$1466.07	\$1090.90	\$900.04

71. Plane



73. Sphere



75. Elliptic cone



77. (a) 243 board-ft (b) 507 board-ft

79.



81. 36,661 units

83. Proof

85. (a) $k = \frac{520}{3}$

(b) $P = \frac{520T}{3V}$

The level curves are lines.

87. (a) C (b) A (c) B

89. $C = 4.50xy + 5.00(xz + yz)$

91. False. Let $f(x, y) = 4$.

93. False. The equation of a sphere is not a function.

95. Putnam Problem A1, 2008

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Section 13.2 *(page 891)*

1. As x approaches -1 and y approaches 3, z approaches 1.
3–5. Proofs **7.** 9 **9.** -20 **11.** 7, continuous
13. e^2, continuous **15.** 0, continuous for $y \neq 0$
17. $\frac{1}{2}$, continuous except at $(0, 0)$ **19.** -1, continuous
21. 0, continuous for $xy \neq 1$, $|xy| \leq 1$
23. $2\sqrt{2}$, continuous for $x + y + z \geq 0$ **25.** 0
27. Limit does not exist. **29.** Limit does not exist.
31. Limit does not exist. **33.** 0
35. Limit does not exist.
37. No. The existence of $f(2, 3)$ has no bearing on the existence of the limit as $(x, y) \to (2, 3)$.
39. $\lim_{x\to 0} f(x, 0) = 0$ if $f(x, 0)$ exists. **41.** Continuous, 1
43.

(x, y)	$(1, 0)$	$(0.5, 0)$	$(0.1, 0)$	$(0.01, 0)$	$(0.001, 0)$
$f(x, y)$	0	0	0	0	0

$y = 0$: 0

(x, y)	$(1, 1)$	$(0.5, 0.5)$	$(0.1, 0.1)$
$f(x, y)$	$\frac{1}{2}$	$\frac{1}{2}$	$\frac{1}{2}$

(x, y)	$(0.01, 0.01)$	$(0.001, 0.001)$
$f(x, y)$	$\frac{1}{2}$	$\frac{1}{2}$

$y = x$: $\frac{1}{2}$
Limit does not exist.
Continuous except at $(0, 0)$

45.

(x, y)	$(1, 0)$	$(0.5, 0)$	$(0.1, 0)$	$(0.01, 0)$	$(0.001, 0)$
$f(x, y)$	0	0	0	0	0

$y = 0$: 0

(x, y)	$(1, 1)$	$(0.5, 0.5)$	$(0.1, 0.1)$
$f(x, y)$	$\frac{1}{2}$	1	5

(x, y)	$(0.01, 0.01)$	$(0.001, 0.001)$
$f(x, y)$	50	500

$y = x$: ∞
The limit does not exist.
Continuous except at $(0, 0)$

47. (a) $\dfrac{1 + a^2}{a}$, $a \neq 0$ (b) Limit does not exist.
(c) No; Different paths result in different limits.
49. f is continuous. g is continuous except at $(0, 0)$. g has a removable discontinuity at $(0, 0)$.
51. 0 **53.** 0 **55.** 1 **57.** 1 **59.** 0
61. Continuous except at $(0, 0, 0)$ **63.** Continuous
65. Continuous **67.** Continuous
69. Continuous for $y \neq \dfrac{2x}{3}$ **71.** (a) $2x$ (b) -4
73. (a) $\dfrac{1}{y}$ (b) $-\dfrac{x}{y^2}$ **75.** (a) $3 + y$ (b) $x - 2$
77. 0 **79.** True
81. False. Let $f(x, y) = \begin{cases} \ln(x^2 + y^2), & x \neq 0, y \neq 0 \\ 0, & x = 0, y = 0 \end{cases}$.
83. $\dfrac{\pi}{2}$ **85.** Proof

Section 13.3 *(page 900)*

1. z_x, $f_x(x, y)$, $\dfrac{\partial z}{\partial x}$
3. (a) Differentiate first with respect to y, then with respect to x, and last with respect to z.
(b) Differentiate first with respect to z and then with respect to x.
5. No. Because you are finding the partial derivative with respect to x, you consider y to be constant. So, the denominator is considered a constant and does not contain any variables.
7. No. Because you are finding the partial derivative with respect to y, you consider x to be constant. So, the denominator is considered a constant and does not contain any variables.
9. Yes. Because you are finding the partial derivative with respect to x, you consider y to be constant. So, both the numerator and denominator contain variables.
11. $f_x(x, y) = 2$, $f_y(x, y) = -5$
13. $\dfrac{\partial z}{\partial x} = 6 - 2xy$, $\dfrac{\partial z}{\partial y} = -x^2 + 16y$
15. $\dfrac{\partial z}{\partial x} = \sqrt{y}$, $\dfrac{\partial z}{\partial y} = \dfrac{x}{2\sqrt{y}}$
17. $\dfrac{\partial z}{\partial x} = ye^{xy}$, $\dfrac{\partial z}{\partial y} = xe^{xy}$
19. $\dfrac{\partial z}{\partial x} = 2xe^{2y}$, $\dfrac{\partial z}{\partial y} = 2x^2e^{2y}$
21. $\dfrac{\partial z}{\partial x} = \dfrac{1}{x}$, $\dfrac{\partial z}{\partial y} = -\dfrac{1}{y}$
23. $\dfrac{\partial z}{\partial x} = \dfrac{2x}{x^2 + y^2}$, $\dfrac{\partial z}{\partial y} = \dfrac{2y}{x^2 + y^2}$
25. $\dfrac{\partial z}{\partial x} = \dfrac{x^3 - 3y^3}{x^2y}$, $\dfrac{\partial z}{\partial y} = \dfrac{-x^3 + 12y^3}{2xy^2}$
27. $h_x(x, y) = -2xe^{-(x^2+y^2)}$, $h_y(x, y) = -2ye^{-(x^2+y^2)}$
29. $f_x(x, y) = \dfrac{x}{\sqrt{x^2 + y^2}}$, $f_y(x, y) = \dfrac{y}{\sqrt{x^2 + y^2}}$
31. $\dfrac{\partial z}{\partial x} = -y \sin xy$, $\dfrac{\partial z}{\partial y} = -x \sin xy$
33. $\dfrac{\partial z}{\partial x} = 2 \sec^2(2x - y)$, $\dfrac{\partial z}{\partial y} = -\sec^2(2x - y)$
35. $\dfrac{\partial z}{\partial x} = 8ye^y \cos 8xy$, $\dfrac{\partial z}{\partial y} = e^y(8x \cos 8xy + \sin 8xy)$
37. $\dfrac{\partial z}{\partial x} = 2 \cosh(2x + 3y)$, $\dfrac{\partial z}{\partial y} = 3 \cosh(2x + 3y)$
39. $f_x(x, y) = 1 - x^2$, $f_y(x, y) = y^2 - 1$
41. $f_x(x, y) = 3$, $f_y(x, y) = 2$

CHAPTER 13

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

43. $f_x(x, y) = \dfrac{1}{2\sqrt{x + y}}$

$f_y(x, y) = \dfrac{1}{2\sqrt{x + y}}$

45. $f_x = 12$

$f_y = 12$

47. $f_x = -1$

$f_y = \frac{1}{2}$

49. $f_x = \frac{1}{4}$

$f_y = \frac{1}{4}$

51. $f_x = -\dfrac{1}{4}$

$f_y = \dfrac{1}{4}$

53. $\dfrac{\partial z}{\partial x}(1, 2) = 2$

$\dfrac{\partial z}{\partial y}(1, 2) = 1$

55. $g_x(1, 1) = -2$

$g_y(1, 1) = -2$

57. $H_x(x, y, z) = \cos(x + 2y + 3z)$

$H_y(x, y, z) = 2\cos(x + 2y + 3z)$

$H_z(x, y, z) = 3\cos(x + 2y + 3z)$

59. $\dfrac{\partial w}{\partial x} = \dfrac{x}{\sqrt{x^2 + y^2 + z^2}}$

$\dfrac{\partial w}{\partial y} = \dfrac{y}{\sqrt{x^2 + y^2 + z^2}}$

$\dfrac{\partial w}{\partial z} = \dfrac{z}{\sqrt{x^2 + y^2 + z^2}}$

61. $F_x(x, y, z) = \dfrac{x}{x^2 + y^2 + z^2}$

$F_y(x, y, z) = \dfrac{y}{x^2 + y^2 + z^2}$

$F_z(x, y, z) = \dfrac{z}{x^2 + y^2 + z^2}$

63. $f_x = 3, f_y = 1, f_z = 2$ **65.** $f_x = 1, f_y = 0, f_z = 0$

67. $f_x = 4, f_y = 24, f_z = 0$ **69.** $x = 2, y = -2$

71. $x = -6, y = 4$ **73.** $x = 1, y = 1$ **75.** $x = 0, y = 0$

77. $\dfrac{\partial^2 z}{\partial x^2} = 0$

$\dfrac{\partial^2 z}{\partial y^2} = 6x$

$\dfrac{\partial^2 z}{\partial y \partial x} = \dfrac{\partial^2 z}{\partial x \partial y} = 6y$

79. $\dfrac{\partial^2 z}{\partial x^2} = 12x^2$

$\dfrac{\partial^2 z}{\partial y^2} = 18y$

$\dfrac{\partial^2 z}{\partial y \partial x} = \dfrac{\partial^2 z}{\partial x \partial y} = -2$

81. $\dfrac{\partial^2 z}{\partial x^2} = \dfrac{y^2}{(x^2 + y^2)^{3/2}}$

$\dfrac{\partial^2 z}{\partial y^2} = \dfrac{x^2}{(x^2 + y^2)^{3/2}}$

$\dfrac{\partial^2 z}{\partial y \partial x} = \dfrac{\partial^2 z}{\partial x \partial y} = \dfrac{-xy}{(x^2 + y^2)^{3/2}}$

83. $\dfrac{\partial^2 z}{\partial x^2} = e^x \tan y$

$\dfrac{\partial^2 z}{\partial y^2} = 2e^x \sec^2 y \tan y$

$\dfrac{\partial^2 z}{\partial y \partial x} = \dfrac{\partial^2 z}{\partial x \partial y} = e^x \sec^2 y$

85. $\dfrac{\partial^2 z}{\partial x^2} = -y^2 \cos xy$

$\dfrac{\partial^2 z}{\partial y^2} = -x^2 \cos xy$

$\dfrac{\partial^2 z}{\partial y \partial x} = \dfrac{\partial^2 z}{\partial x \partial y} = -xy \cos xy - \sin xy$

87. $\dfrac{\partial z}{\partial x} = \sec y$

$\dfrac{\partial z}{\partial y} = x \sec y \tan y$

$\dfrac{\partial^2 z}{\partial x^2} = 0$

$\dfrac{\partial^2 z}{\partial y^2} = x \sec y(\sec^2 y + \tan^2 y)$

$\dfrac{\partial^2 z}{\partial y \partial x} = \dfrac{\partial^2 z}{\partial x \partial y} = \sec y \tan y$

No values of x and y exist such that $f_x(x, y) = f_y(x, y) = 0$.

89. $\dfrac{\partial z}{\partial x} = \dfrac{y^2 - x^2}{x(x^2 + y^2)}$

$\dfrac{\partial z}{\partial y} = \dfrac{-2y}{x^2 + y^2}$

$\dfrac{\partial^2 z}{\partial x^2} = \dfrac{x^4 - 4x^2y^2 - y^4}{x^2(x^2 + y^2)^2}$

$\dfrac{\partial^2 z}{\partial y^2} = \dfrac{2(y^2 - x^2)}{(x^2 + y^2)^2}$

$\dfrac{\partial^2 z}{\partial y \partial x} = \dfrac{\partial^2 z}{\partial x \partial y} = \dfrac{4xy}{(x^2 + y^2)^2}$

No values of x and y exist such that $f_x(x, y) = f_y(x, y) = 0$.

91. $f_{xyy}(x, y, z) = f_{yxy}(x, y, z) = f_{yyx}(x, y, z) = 0$

93. $f_{xyy}(x, y, z) = f_{yxy}(x, y, z) = f_{yyx}(x, y, z) = z^2 e^{-x} \sin yz$

95. $\dfrac{\partial^2 z}{\partial x^2} + \dfrac{\partial^2 z}{\partial y^2} = 0 + 0 = 0$

97. $\dfrac{\partial^2 z}{\partial x^2} + \dfrac{\partial^2 z}{\partial y^2} = e^x \sin y - e^x \sin y = 0$

99. $\dfrac{\partial^2 z}{\partial t^2} = -c^2 \sin(x - ct) = c^2\left(\dfrac{\partial^2 z}{\partial x^2}\right)$

101. $\dfrac{\partial^2 z}{\partial t^2} = \dfrac{-c^2}{(x + ct)^2} = c^2\left(\dfrac{\partial^2 z}{\partial x^2}\right)$

103. $\dfrac{\partial z}{\partial t} = \dfrac{-e^{-t}\cos x}{c} = c^2\left(\dfrac{\partial^2 z}{\partial x^2}\right)$ **105.** Proof

107. Yes; $f(x, y) = \cos(3x - 2y)$

109. No. Let $z = x + y + 1$.

111.



113. $S_{max} = 2304\ \text{m}^2$; $S_{min} = 576\ \text{m}^2$

115. (a) $\sqrt{2}$ (b) $\frac{5}{2}$ **117.** (a) 72 (b) 72

119. $IQ_M = \dfrac{100}{C}, IQ_M(12, 10) = 10$

IQ increases at a rate of 10 points per year of mental age when the mental age is 12 and the chronological age is 10.

$IQ_C = -\dfrac{100M}{C^2}, IQ_C(12, 10) = -12$

IQ decreases at a rate of 12 points per year of chronological age when the mental age is 12 and the chronological age is 10.

121. An increase in either the charge for food and housing or the tuition will cause a decrease in the number of applicants.

123. $\dfrac{\partial T}{\partial x} = -2.4°/\text{m}, \dfrac{\partial T}{\partial y} = -9°/\text{m}$

125. $T = \dfrac{PV}{nR} \implies \dfrac{\partial T}{\partial P} = \dfrac{v}{nR}$

$P = \dfrac{nRT}{V} \implies \dfrac{\partial P}{\partial V} = \dfrac{-nRT}{V^2}$

$V = \dfrac{nRT}{P} \implies \dfrac{\partial V}{\partial T} = \dfrac{nR}{P}$

$\dfrac{\partial T}{\partial P} \cdot \dfrac{\partial P}{\partial V} \cdot \dfrac{\partial V}{\partial T} = -\dfrac{nRT}{VP} = -\dfrac{nRT}{nRT} = -1$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

127. (a) $\frac{\partial z}{\partial x} = 0.54, \frac{\partial z}{\partial y} = -0.6$

(b) As the expenditures on amusement parks and campgrounds increase, the expenditures on spectator sports increase. As the expenditures on live entertainment increase, the expenditures on spectator sports decrease.

129. (a) $f_x(x, y) = \frac{y(x^4 + 4x^2y^2 - y^4)}{(x^2 + y^2)^2}$

$f_y(x, y) = \frac{x(x^4 - 4x^2y^2 - y^4)}{(x^2 + y^2)^2}$

(b) $f_x(0, 0) = 0, f_y(0, 0) = 0$

(c) $f_{xy}(0, 0) = -1, f_{yx}(0, 0) = 1$

(d) f_{xy} or f_{yx} or both are not continuous at $(0, 0)$.

131. Proof

Section 13.4 *(page 909)*

1. In general, the accuracy worsens as Δx and Δy increase.

3. $dz = 15x^2y^2\,dx + 10x^3y\,dy$

5. $dz = (e^{x^2+y^2} + e^{-x^2-y^2})(x\,dx + y\,dy)$

7. $dw = 2xyz^2\,dx + (x^2z^2 + z\cos yz)\,dy + (2x^2yz + y\cos yz)$

9. (a) $f(2, 1) = 1, f(2.1, 1.05) = 1.05, \Delta z = 0.05$

(b) $dz = 0.05$

11. (a) $f(2, 1) = 11, f(2.1, 1.05) = 10.4875, \Delta z = -0.5125$

(b) $dz = -0.5$

13. (a) $f(2, 1) = e^2 \approx 7.3891, f(2.1, 1.05) = 1.05e^{2.1} \approx 8.5745, \Delta z \approx 1.1854$

(b) $dz \approx 1.1084$

15. 0.44 **17.** 0

19. Yes. Because f_x and f_y are continuous on R, you know that f is differentiable on R. Because f is differentiable on R, you know that f is continuous on R.

21. $dA = h\,dl + l\,dh$



$\Delta A - dA = dl\,dh$

23. $dV = \pm 3.92$ in.^{3}, $\frac{dV}{V} = 0.82\%$

25.

Δr	Δh	dV	ΔV	$\Delta V - dV$
0.1	0.1	8.3776	8.5462	0.1686
0.1	−0.1	5.0265	5.0255	−0.0010
0.001	0.002	0.1005	0.1006	0.0001
−0.0001	0.0002	−0.0034	−0.0034	0.0000

27. $dC = \pm 2.4418°, \frac{dC}{C} = 19\%$ **29.** 10%

31. (a) $V = 18\sin\theta$ ft^3, $\theta = \frac{\pi}{2}$ (b) 1.047 ft^3

33. $L \approx 8.096 \times 10^{-4} \pm 6.6 \times 10^{-6}$ microhenrys

35. Answers will vary.
Sample answer:
$\varepsilon_1 = \Delta x$
$\varepsilon_2 = 0$

37. Answers will vary.
Sample answer:
$\varepsilon_1 = y\,\Delta x$
$\varepsilon_2 = 2x\,\Delta x + (\Delta x)^2$

39–41. Proofs

Section 13.5 *(page 917)*

1. You can convert w into a function of s and t, or you can use the Chain Rule given in Theorem 13.7.

3. $8t + 5$; 21 **5.** $e^t(\sin t + \cos t)$; 1

7. (a) and (b) $2e^{2t} + \frac{3}{t^4}$ **9.** (a) and (b) $2e^{2t}$

11. (a) and (b) $3(2t^2 - 1)$ **13.** $\frac{-11\sqrt{29}}{29} \approx -2.04$

15. $\frac{\partial w}{\partial s} = 4s, 4$
$\frac{\partial w}{\partial t} = 4t, 12$

17. $\frac{\partial w}{\partial s} = 5\cos(5s - t), 0$
$\frac{\partial w}{\partial t} = -\cos(5s - t), 0$

19. (a) and (b)
$\frac{\partial w}{\partial s} = t^2(3s^2 - t^2)$
$\frac{\partial w}{\partial t} = 2st(s^2 - 2t^2)$

21. (a) and (b)
$\frac{\partial w}{\partial s} = te^{s^2-t^2}(2s^2 + 1)$
$\frac{\partial w}{\partial t} = se^{s^2-t^2}(1 - 2t^2)$

23. $\frac{y - 2x + 1}{2y - x + 1}$ **25.** $-\frac{x^2 + y^2 + x}{x^2 + y^2 + y}$

27. $\frac{\partial z}{\partial x} = -\frac{x}{z}$
$\frac{\partial z}{\partial y} = -\frac{y}{z}$

29. $\frac{\partial z}{\partial x} = -\frac{x}{y + z}$
$\frac{\partial z}{\partial y} = -\frac{z}{y + z}$

31. $\frac{\partial z}{\partial x} = \frac{\partial z}{\partial y} = \frac{\sec^2(x + y)}{\sin z}$

33. $\frac{\partial z}{\partial x} = -\frac{(ze^{xz} + y)}{xe^{xz}}$
$\frac{\partial z}{\partial y} = -e^{-xz}$

35. $\frac{\partial w}{\partial x} = \frac{7y + w^2}{4z - 2wz - 2wx}$
$\frac{\partial w}{\partial y} = \frac{7x + z^2}{4z - 2wz - 2wx}$
$\frac{\partial w}{\partial z} = \frac{2yz - 4w + w^2}{4z - 2wz - 2wx}$

37. $\frac{\partial w}{\partial x} = \frac{y\sin xy}{z}$
$\frac{\partial w}{\partial y} = \frac{x\sin xy - z\cos yz}{z}$
$\frac{\partial w}{\partial z} = -\frac{y\cos yz + w}{z}$

39. (a) $f(tx, ty) = 2(tx)^2 - 5(tx)(ty)$
$= t^2(2x^2 - 5xy) = t^2 f(x, y); n = 2$

(b) $xf_x(x, y) + yf_y(x, y) = 4x^2 - 10xy = 2f(x, y)$

41. (a) $f(tx, ty) = e^{tx/ty} = e^{x/y} = f(x, y);\ n = 0$

(b) $xf_x(x, y) + yf_y(x, y) = \frac{xe^{x/y}}{y} - \frac{xe^{x/y}}{y} = 0$

43. 47 **45.** Proof

47. (a) $\frac{\partial F}{\partial u}\frac{\partial u}{dx} + \frac{\partial F}{\partial v}\frac{\partial v}{\partial x} = 4\frac{\partial F}{\partial u}$

(b) $\frac{\partial F}{\partial u}\frac{\partial u}{\partial x} + \frac{\partial F}{\partial v}\frac{\partial v}{\partial x} = -2\frac{\partial F}{\partial u} + 2x\frac{\partial F}{\partial v}$

49. 4608π in.^{3}/min, 624π in.^{2}/min **51.** $28m$ cm^2/sec

53–55. Proofs

CHAPTER 13

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Section 13.6 *(page 928)*

1. The partial derivative with respect to x is the directional derivative in the direction of the positive x-axis. That is, the directional derivative for $\theta = 0$.

3. $-\sqrt{2}$ **5.** $\frac{1}{2} + \sqrt{3}$ **7.** 1 **9.** $-\frac{7}{25}$ **11.** 6

13. $\frac{2\sqrt{5}}{5}$ **15.** $3\mathbf{i} + 10\mathbf{j}$ **17.** $2\mathbf{i} - \frac{1}{2}\mathbf{j}$

19. $20\mathbf{i} - 14\mathbf{j} - 30\mathbf{k}$ **21.** -1 **23.** $\frac{2\sqrt{3}}{3}$ **25.** $3\sqrt{2}$

27. $-\frac{8}{\sqrt{5}}$ **29.** $-\sqrt{y}\mathbf{i} + \left(2y - \frac{x}{2\sqrt{y}}\right)\mathbf{j}$; $\sqrt{39}$

31. $\tan y\mathbf{i} + x\sec^2 y\mathbf{j}$; $\sqrt{17}$

33. $\cos x^2y^3(2x\mathbf{i} + 3y^2\mathbf{j})$; $\frac{1}{\pi}\sqrt{4 + 9\pi^6}$

35. $\frac{x\mathbf{i} + y\mathbf{j} + z\mathbf{k}}{\sqrt{x^2 + y^2 + z^2}}$; 1 **37.** $yz(yz\mathbf{i} + 2xz\mathbf{j} + 2xy\mathbf{k})$; $\sqrt{33}$

39. $-2\mathbf{i} - 3\mathbf{j}$ **41.** $3\mathbf{i} - \mathbf{j}$

43. (a) $16\mathbf{i} - \mathbf{j}$ (b) $\frac{\sqrt{257}}{257}(16\mathbf{i} - \mathbf{j})$ (c) $y = 16x - 22$

(d)



45. (a) $6\mathbf{i} - 4\mathbf{j}$ (b) $\frac{\sqrt{13}}{13}(3\mathbf{i} - 2\mathbf{j})$ (c) $y = \frac{3}{2}x - \frac{1}{2}$

(d)



47. (a)



(b) (i) $-\frac{5\sqrt{2}}{12}$ (ii) $\frac{2 - 3\sqrt{3}}{12}$

(iii) $\frac{2 + 3\sqrt{3}}{12}$ (iv) $\frac{3 - 2\sqrt{3}}{12}$

(c) (i) $-\frac{5\sqrt{2}}{12}$ (ii) $\frac{3}{5}$ (iii) $-\frac{1}{5}$ (iv) $-\frac{11\sqrt{10}}{60}$

(d) $-\frac{1}{3}\mathbf{i} - \frac{1}{2}\mathbf{j}$ (e) $\frac{\sqrt{13}}{6}$

(f) $\mathbf{u} = \frac{1}{\sqrt{13}}(3\mathbf{i} - 2\mathbf{j})$

$D_{\mathbf{u}}f(3, 2) = \nabla f \cdot \mathbf{u} = 0$

∇f is the direction of the greatest rate of change of f. So, in a direction orthogonal to ∇f, the rate of change of f is 0.

49. (a)



(b) $D_{\mathbf{u}}f(4, -3) = 8\cos\theta + 6\sin\theta$



Generated by Mathematica

(c) $\theta \approx 2.21$, $\theta \approx 5.36$

Directions in which there is no change in f

(d) $\theta \approx 0.64$, $\theta \approx 3.79$

Directions of greatest rate of change in f

(e) 10; Magnitude of the greatest rate of change

(f)



Generated by Mathematica

Orthogonal to the level curve

51. No; Answers will vary. **53.** $5\nabla h = -(5\mathbf{i} + 12\mathbf{j})$

55. $\frac{1}{625}(7\mathbf{i} - 24\mathbf{j})$ **57.** $6\mathbf{i} - 10\mathbf{j}$; 11.66°/cm **59.** $y^2 = 10x$

61. True **63.** True **65.** $f(x, y, z) = e^x\cos y + \frac{1}{2}z^2 + C$

67. (a) and (b) Proofs

(c)



Section 13.7 *(page 937)*

1. $\nabla F(x_0, y_0, z_0)$ and any tangent vector $\mathbf{v}$ at (x_0, y_0, z_0) are orthogonal. So, $\nabla F(x_0, y_0, z_0) \cdot \mathbf{v} = 0$.

3. The level surface can be written as $3x - 5y + 3z = 15$, which is an equation of a plane in space.

5. The level surface can be written as $4x^2 + 9y^2 - 4z^2 = 0$, which is an elliptic cone that lies on the z-axis.

7. $\frac{1}{13}(3\mathbf{i} + 4\mathbf{j} + 12\mathbf{k})$

9. $4x + 2y - z = 2$ **11.** $3x + 4y - 5z = 0$

13. $2x - 2y - z = 2$ **15.** $3x + 4y - 25z = 25(1 - \ln 5)$

17. $4x + 2y + 5z = -15$

19. (a) $x + y + z = 9$ (b) $x - 3 = y - 3 = z - 3$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

21. (a) $x - 2y + 2z = 7$ (b) $x - 1 = \dfrac{y+1}{-2} = \dfrac{z-2}{2}$

23. (a) $6x - 4y - z = 5$ (b) $\dfrac{x-3}{6} = \dfrac{y-2}{-4} = \dfrac{z-5}{-1}$

25. (a) $10x + 5y + 2z = 30$ (b) $\dfrac{x-1}{10} = \dfrac{y-2}{5} = \dfrac{z-5}{2}$

27. (a) $8x + y - z = 0$ (b) $\dfrac{x}{8} = \dfrac{y-2}{1} = \dfrac{z-2}{-1}$

29. $x = t + 1, y = 1 - t, z = t + 1$

31. $x = 4t + 3, y = 4t + 3, z = 4 - 3t$

33. $x = t + 3, y = 5t + 1, z = 2 - 4t$

35. 86.0° **37.** 77.4° **39.** (0, 3, 12) **41.** (2, 2, −4)

43. (0, 0, 0) **45.** Proof **47.** (a) and (b) Proofs

49. Not necessarily; They only need to be parallel.

51. $\left(-\frac{1}{2}, \frac{1}{4}, \frac{1}{4}\right)$ or $\left(\frac{1}{2}, -\frac{1}{4}, -\frac{1}{4}\right)$ **53.** $(-2, 1, -1)$ or $(2, -1, 1)$

55. (a) Line: $x = 1, y = 1, z = 1 - t$
Plane: $z = 1$

(b) Line: $x = -1, y = 2 + \frac{6}{25}t, z = -\frac{4}{5} - t$
Plane: $6y - 25z - 32 = 0$

(c)



57. (a) $x = 1 + t$
$y = 2 - 2t$
$z = 4$
$\theta \approx 48.2°$

(b)



59. $F(x, y, z) = \dfrac{x^2}{a^2} + \dfrac{y^2}{b^2} + \dfrac{z^2}{c^2} - 1$

$F_x(x, y, z) = \dfrac{2x}{a^2}$

$F_y(x, y, z) = \dfrac{2y}{b^2}$

$F_z(x, y, z) = \dfrac{2z}{c^2}$

Plane: $\dfrac{2x_0}{a^2}(x - x_0) + \dfrac{2y_0}{b^2}(y - y_0) + \dfrac{2z_0}{c^2}(z - z_0) = 0$

$\dfrac{x_0 x}{a^2} + \dfrac{y_0 y}{b^2} + \dfrac{z_0 z}{c^2} = 1$

61. $F(x, y, z) = a^2x^2 + b^2y^2 - z^2$
$F_x(x, y, z) = 2a^2x$
$F_y(x, y, z) = 2b^2y$
$F_z(x, y, z) = -2z$
Plane: $2a^2x_0(x - x_0) + 2b^2y_0(y - y_0) - 2z_0(z - z_0) = 0$
$a^2x_0x + b^2y_0y - z_0z = 0$
So, the plane passes through the origin.

63. (a) $P_1(x, y) = 1 + x - y$
(b) $P_2(x, y) = 1 + x - y + \frac{1}{2}x^2 - xy + \frac{1}{2}y^2$
(c) If $x = 0$, $P_2(0, y) = 1 - y + \frac{1}{2}y^2$.
This is the second-degree Taylor polynomial for e^{-y}.
If $y = 0$, $P_2(x, 0) = 1 + x + \frac{1}{2}x^2$.
This is the second-degree Taylor polynomial for e^x.

(d)

x	y	$f(x, y)$	$P_1(x, y)$	$P_2(x, y)$
0	0	1	1	1
0	0.1	0.9048	0.9000	0.9050
0.2	0.1	1.1052	1.1000	1.1050
0.2	0.5	0.7408	0.7000	0.7450
1	0.5	1.6487	1.5000	1.6250

(e)



65. Proof

Section 13.8 *(page 946)*

1. (a) To say that f has a relative minimum at (x_0, y_0) means that the point (x_0, y_0, z_0) is at least as low as all nearby points on the graph of $z = f(x, y)$.

(b) To say that f has a relative maximum at (x_0, y_0) means that the point (x_0, y_0, z_0) is at least as high as all nearby points in the graph of $z = f(x, y)$.

(c) Critical points of f are the points at which the gradient of f is 0 or the points at which one of the partial derivatives does not exist.

(d) A critical point is a saddle point if it is neither a relative minimum nor a relative maximum.

3. Relative minimum: $(1, 3, 0)$

5. Relative minimum: $(0, 0, 1)$

7. Relative minimum: $(-1, 3, -4)$

9. Relative minimum: $(-4, 6, -55)$

11. Every point along the x- or y-axis is a critical point. Each of the critical points yields an absolute maximum.

13. Relative maximum: $\left(\frac{1}{2}, -1, \frac{31}{4}\right)$

15. Relative minimum: $\left(\frac{1}{2}, -4, -\frac{187}{4}\right)$

17. Relative minimum: $(3, -4, -5)$

19. Relative maximum: $(0, 0, -12)$

21. Saddle point: $(1, -1, -1)$

23. No critical numbers

25.



Relative maximum: $(-1, 0, 2)$
Relative minimum: $(1, 0, -2)$

27.



Relative minimum: $(0, 0, 0)$
Relative maxima: $(0, \pm 1, 4)$
Saddle points: $(\pm 1, 0, 1)$

CHAPTER 13

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

29. z is never negative. Minimum: $z = 0$ when $x = y \neq 0$.



31. Insufficient information **33.** Saddle point

35. (a) $(0, 0)$ (b) Saddle point: $(0, 0, 0)$ (c) $(0, 0)$

(d)



37. (a) $(1, a)$, $(b, -4)$

(b) Absolute minima: $(1, a, 0)$, $(b, -4, 0)$

(c) $(1, a)$, $(b, -4)$

(d)



39. Absolute maximum: $(4, 0, 21)$
Absolute minimum: $(4, 2, -11)$

41. Absolute maximum: $(0, 1, 10)$
Absolute minimum: $(1, 2, 5)$

43. Absolute maxima: $(\pm 2, 4, 28)$
Absolute minimum: $(0, 1, -2)$

45. Absolute maxima: $(-2, -1, 9)$, $(2, 1, 9)$
Absolute minima: $(x, -x, 0)$, $|x| \leq 1$

47. Relative minimum: $(0, 3, -1)$ **49.** $-4 < f_{xy}(3, 7) < 4$

51.



Extrema at all (x, y)

53. (a) $f_x = 2x = 0$, $f_y = -2y = 0 \implies (0, 0)$ is a critical point.
$g_x = 2x = 0$, $g_y = 2y = 0 \implies (0, 0)$ is a critical point.

(b) $d = 2(-2) - 0 < 0 \implies (0, 0)$ is a saddle point.
$d = 2(2) - 0 > 0 \implies (0, 0)$ is a relative minimum.

55. False. Let $f(x, y) = 1 - |x| - |y|$ at the point $(0, 0, 1)$.

57. False. Let $f(x, y) = x^2y^2$ (see Example 4 on page 944).

Section 13.9 *(page 953)*

1. Write the equation to be maximized or minimized as a function of two variables. Take the partial derivatives and set them equal to zero or undefined to obtain the critical points. Use the Second Partials Test to test for relative extrema using the critical points. Check the boundary points.

3. $\sqrt{3}$ **5.** $\sqrt{7}$ **7.** $x = y = z = 3$

9. $x = y = z = 10$ **11.** 9 ft × 9 ft × 8.25 ft; \$26.73

13. Let x, y, and z be the length, width, and height, respectively, and let V_0 be the given volume. Then $V_0 = xyz$ and $z = \dfrac{V_0}{xy}$.

The surface area is

$$S = 2xy + 2yz + 2xz = 2\left(xy + \frac{V_0}{x} + \frac{V_0}{y}\right).$$

$$\left.\begin{aligned} S_x &= 2\left(y - \frac{V_0}{x^2}\right) = 0 \\ S_y &= 2\left(x - \frac{V_0}{y^2}\right) = 0 \end{aligned}\right\} \begin{aligned} x^2y - V_0 &= 0 \\ xy^2 - V_0 &= 0 \end{aligned}$$

So, $x = \sqrt[3]{V_0}$, $y = \sqrt[3]{V_0}$, and $z = \sqrt[3]{V_0}$.

15. $x_1 = 3$, $x_2 = 6$ **17.** Proof

19. $x = \dfrac{\sqrt{2}}{2} \approx 0.707$ km

$y = \dfrac{3\sqrt{2} + 2\sqrt{3}}{6} \approx 1.284$ km

21. (a) $y = \frac{3}{4}x + \frac{4}{3}$ (b) $\frac{1}{6}$ **23.** (a) $y = -2x + 4$ (b) 2

25. $y = \frac{84}{43}x - \frac{12}{43}$ **27.** $y = -\frac{175}{148}x + \frac{945}{148}$





29. (a) $y = 0.636x - 10.095$ (b) \$816.71 billion
(c) The new model is $y = 0.6302x + 5.973$.

31. $a\sum_{i=1}^{n} x_i^4 + b\sum_{i=1}^{n} x_i^3 + c\sum_{i=1}^{n} x_i^2 = \sum_{i=1}^{n} x_i^2 y_i$

$a\sum_{i=1}^{n} x_i^3 + b\sum_{i=1}^{n} x_i^2 + c\sum_{i=1}^{n} x_i = \sum_{i=1}^{n} x_i y_i$

$a\sum_{i=1}^{n} x_i^2 + b\sum_{i=1}^{n} x_i + cn = \sum_{i=1}^{n} y_i$

33. $y = \frac{3}{7}x^2 + \frac{6}{5}x + \frac{26}{35}$ **35.** $y = x^2 - x$





Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

37. (a) $y = -0.22x^2 + 9.66x - 1.79$

(b)



39. (a) $\ln P = -0.1499h + 9.3018$ (b) $P = 10{,}957.7e^{-0.1499h}$

(c)



41. Proof

Section 13.10 *(page 962)*

1. Optimization problems that have restrictions or constraints on the values that can be used to produce the optimal solutions are called constrained optimization problems.

3. $f(5, 5) = 25$ **5.** $f(1, 2) = 5$ **7.** $f(25, 50) = 2600$

9. $f(1, 1) = 2$ **11.** $f(3, 3, 3) = 27$ **13.** $f\left(\frac{1}{3}, \frac{1}{3}, \frac{1}{3}\right) = \frac{1}{3}$

15. Maxima: $f\left(\frac{\sqrt{2}}{2}, \frac{\sqrt{2}}{2}\right) = \frac{5}{2}$

$f\left(-\frac{\sqrt{2}}{2}, -\frac{\sqrt{2}}{2}\right) = \frac{5}{2}$

Minima: $f\left(-\frac{\sqrt{2}}{2}, \frac{\sqrt{2}}{2}\right) = -\frac{1}{2}$

$f\left(\frac{\sqrt{2}}{2}, -\frac{\sqrt{2}}{2}\right) = -\frac{1}{2}$

17. $f(8, 16, 8) = 1024$ **19.** $\frac{\sqrt{2}}{2}$ **21.** $3\sqrt{2}$ **23.** $\frac{\sqrt{11}}{2}$

25. 2 **27.** $\sqrt{3}$ **29.** $(-4, 0, 4)$ **31.** $\sqrt{3}$

33. $x = y = z = 3$ **35.** 9 ft × 9 ft × 8.25 ft; \$26.73

37. Proof **39.** $\frac{2\sqrt{3}a}{3} \times \frac{2\sqrt{3}b}{3} \times \frac{2\sqrt{3}c}{3}$

41. At (0, 0), the Lagrange equations are inconsistent.

43. $\sqrt[3]{360} \times \sqrt[3]{360} \times \frac{4}{3}\sqrt[3]{360}$ ft

45. $r = \sqrt[3]{\frac{v_0}{2\pi}}$ and $h = 2\sqrt[3]{\frac{v_0}{2\pi}}$ **47.** Proof

49. $P\left(\frac{15{,}625}{28}, 3125\right) \approx 203{,}144$

51. $x \approx 237.4$

$y \approx 640.9$

Cost ≈ \$68,364.80

53. Putnam Problem 2, morning session, 1938

Review Exercises for Chapter 13 *(page 964)*

1. Find the domain and range of the function. Then use traces in planes parallel to the coordinate planes.

3. z is not a function of x and y. The graph is of an ellipsoid, so there exists inputs for x and y that give multiple values for z.

5. A and B may be relative extrema; C and D may be saddle points.

7. (a) -3 (b) -7 (c) 15 (d) $7x^2 - 3$

9. Domain: $\{(x, y): x \geq 0 \text{ and } y \neq 0\}$

Range: all real numbers

11.



Plane

13. Lines: $y = 2x - 3 + c$



15. (a)



(b) g is a vertical translation of f two units upward.

(c) g is a horizontal translation of f two units to the right.

(d)





17. Elliptic paraboloid



19. Limit: $\frac{1}{2}$

Continuous except at (0, 0)

21. Limit: 0

Continuous

23. Limit: $-\frac{\ln 2}{5}$

Continuous for $x \neq \frac{z}{y}$

25. $f_x(x, y) = 15x^2$

$f_y(x, y) = 7$

27. $f_x(x, y) = e^x \cos y$

$f_y(x, y) = -e^x \sin y$

29. $f_x(x, y) = -\frac{y^4}{x^2}e^{y/x}$

$f_y(x, y) = \frac{y^3}{x}e^{y/x} + 3y^2e^{y/x}$

31. $f_x(x, y, z) = 2z^2 + 6yz$

$f_y(x, y, z) = 6xz$

$f_z(x, y, z) = 4xz + 6xy$

CHAPTER 13

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

33. $f_x(0, 2) = 0$
$f_y(0, 2) = -1$

35. $f_x\left(2, 3, -\frac{\pi}{3}\right) = -\sqrt{3}\pi - \frac{3}{2}$

$f_y\left(2, 3, -\frac{\pi}{3}\right) = -1$

$f_z\left(2, 3, -\frac{\pi}{3}\right) = 6\sqrt{3}$

37. $f_{xx}(x, y) = 6$
$f_{yy}(x, y) = 12y$
$f_{xy}(x, y) = f_{yx}(x, y) = -1$

39. $h_{xx}(x, y) = -y \cos x$
$h_{yy}(x, y) = -x \sin y$
$h_{xy}(x, y) = h_{yx}(x, y) = \cos y - \sin x$

41. Slope in x-direction: 0
Slope in y-direction: 4

43. $(xy \cos xy + \sin xy)\,dx + (x^2 \cos xy)\,dy$

45. $(3y^2 - 6x^2yz^2)\,dx + (6xy - 2x^3z^2)\,dy + (-4x^3yz)\,dz$

47. (a) $f(2, 1) = 10$ (b) $dz = 0.5$
$f(2.1, 1.05) = 10.5$
$\Delta z = 0.5$

49. $dV = \pm\pi$ in.^{3}, $\frac{dV}{V} = 15\%$ **51.** Proof

53. (a) and (b) $\frac{dw}{dt} = \frac{8t - 1}{4t^2 - t + 4}$

55. (a) and (b) $\frac{dw}{dt} = 2t^2e^{2t} + 2te^{2t} + 2t + 1$

57. (a) and (b) $\frac{\partial w}{\partial r} = \frac{4r^2t - 4rt^2 - t^3}{(2r - t)^2}$
$\frac{\partial w}{\partial t} = \frac{4r^2t - rt^2 - 4r^3}{(2r - t)^2}$

59. $\frac{-3x^2 + y}{-x + 5}$

61. $\frac{\partial z}{\partial x} = \frac{-2x - y}{y + 2z}$
$\frac{\partial z}{\partial y} = \frac{-x - 2y - z}{y + 2z}$

63. -50 **65.** $\frac{2}{3}$ **67.** $\langle 4, 4\rangle$, $4\sqrt{2}$ **69.** $\left\langle -\frac{1}{2}, 0\right\rangle$, $\frac{1}{2}$

71. $\langle -2, -3, -1\rangle$, $\sqrt{14}$

73. (a) $54\mathbf{i} - 16\mathbf{j}$ (b) $\frac{27}{\sqrt{793}}\mathbf{i} - \frac{8}{\sqrt{793}}\mathbf{j}$ (c) $y = \frac{27}{8}x - \frac{65}{8}$

(d)



75. $2x + 6y - z = 8$ **77.** $z = 4$

79. (a) $4x + 4y - z = 8$
(b) $x = 2 + 4t$, $y = 1 + 4t$, $z = 4 - t$

81. 36.7° **83.** $(0, 0, 9)$

85. Relative maximum: $(4, -1, 9)$

87. Relative minimum: $\left(-4, \frac{4}{3}, -2\right)$

89. Relative minimum: $(1, 1, 3)$ **91.** $\sqrt{3}$

93. $x_1 = 2$, $x_2 = 4$

95. $y = \frac{161}{226}x + \frac{456}{113}$



97. $y = 0.138x + 22.1$; 46.25 bushels/acre

99. $f(4, 4) = 32$ **101.** $f(15, 7) = 352$ **103.** $f(3, 6) = 36$

105. $x = \frac{\sqrt{2}}{2} \approx 0.707$ km, $y = \frac{\sqrt{3}}{3} \approx 0.577$ km,
$z = \left(60 - 3\sqrt{2} - 2\sqrt{3}\right)6 \approx 8.716$ km

107. $\frac{\partial P}{\partial V} = \frac{2an^2}{V^3} - \frac{nRT}{(V - nb)^2}$, $\frac{\partial T}{\partial P} = \frac{1}{nR}(V - nb)$

P.S. Problem Solving *(page 968)*

1. (a) $y_0z_0(x - x_0) + x_0z_0(y - y_0) + x_0y_0(z - z_0) = 0$

(b) $x_0y_0z_0 = 1 \implies z_0 = \frac{1}{x_0y_0}$

Then the tangent plane is

$$y_0\left(\frac{1}{x_0y_0}\right)(x - x_0) + x_0\left(\frac{1}{x_0y_0}\right)(y - y_0) + x_0y_0\left(z - \frac{1}{x_0y_0}\right) = 0.$$

Intercepts: $(3x_0, 0, 0)$, $(0, 3y_0, 0)$, $\left(0, 0, \frac{3}{x_0y_0}\right)$

3. (a)



Maximum value: $2\sqrt{2}$

(b)



Maximum and minimum value: 0
The method of Lagrange multipliers does not work because $\nabla g(x_0, y_0) = \mathbf{0}$.

5. (a) $x\frac{\partial f}{\partial x} + y\frac{\partial f}{\partial y} = xCy^{1-a}ax^{a-1} + yCx^a(1 - a)y^{1-a-1}$
$= ax^aCy^{1-a} + (1 - a)x^aC(y^{1-a})$
$= Cx^ay^{1-a}[a + (1 - a)]$
$= Cx^ay^{1-a}$
$= f(x, y)$

(b) $f(tx, ty) = C(tx)^a(ty)^{1-a}$
$= Ctx^ay^{1-a}$
$= tCx^ay^{1-a}$
$= tf(x, y)$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

7. (a)



Minimum: $(0, 0, 0)$
Maxima: $(0, \pm 1, 2e^{-1})$
Saddle points: $(\pm 1, 0, e^{-1})$

(b)



Minima: $(\pm 1, 0, -e^{-1})$
Maxima: $(0, \pm 1, 2e^{-1})$
Saddle point: $(0, 0, 0)$

(c) $\alpha > 0$
Minimum: $(0, 0, 0)$
Maxima: $(0, \pm 1, \beta e^{-1})$
Saddle points: $(\pm 1, 0, \alpha e^{-1})$

$\alpha < 0$
Minima: $(\pm 1, 0, \alpha e^{-1})$
Maxima: $(0, \pm 1, \beta e^{-1})$
Saddle point: $(0, 0, 0)$

9–13. Proofs

Chapter 14

Section 14.1 *(page 976)*

1. An iterated integral is an integral of a function of several variables. Integrate with respect to one variable while holding the other variables constant.

3. $\frac{3x^2}{2}$ **5.** $\frac{4x^2 - x^4}{2}$ **7.** $\frac{y}{2}[(\ln y)^2 - y^2]$

9. $x^2(1 - e^{-x^2} - x^2e^{-x^2})$ **11.** 3 **13.** $\frac{\sqrt{2}}{4}$ **15.** 64

17. $\frac{3}{2}$ **19.** $\frac{1}{3}$ **21.** $\frac{2}{3}$ **23.** 4 **25.** $\frac{\pi}{2}$ **27.** $\frac{\pi^2}{32} + \frac{1}{8}$

29. $\frac{1}{2}$ **31.** Diverges **33.** 8 **35.** $\frac{16}{3}$ **37.** 36

39. $\frac{8}{3}$ **41.** $\frac{9}{2}$

43.



$$\int_0^4 \int_x^4 f(x, y)\, dy\, dx$$

45.



$$\int_0^2 \int_{-\sqrt{4-y^2}}^{\sqrt{4-y^2}} f(x, y)\, dx\, dy$$

47.



$$\int_0^{\ln 10} \int_{e^x}^{10} f(x, y)\, dy\, dx$$

49.



$$\int_0^1 \int_{-\sqrt{y}}^{\sqrt{y}} f(x, y)\, dx\, dy$$

51.



$$\int_0^1 \int_0^2 dy\, dx = \int_0^2 \int_0^1 dx\, dy = 2$$

53.



$$\int_0^1 \int_{2y}^2 dx\, dy = \int_0^2 \int_0^{x/2} dy\, dx = 1$$

55.



$$\int_0^1 \int_{-\sqrt{1-y^2}}^{\sqrt{1-y^2}} dx\, dy = \int_{-1}^1 \int_0^{\sqrt{1-x^2}} dy\, dx = \frac{\pi}{2}$$

57.



$$\int_0^2 \int_0^x dy\, dx + \int_2^4 \int_0^{4-x} dy\, dx = \int_0^2 \int_y^{4-y} dx\, dy = 4$$

59.



$$\int_0^1 \int_{y^2}^{\sqrt[3]{y}} dx\, dy = \int_0^1 \int_{x^3}^{\sqrt{x}} dy\, dx = \frac{5}{12}$$

61.



$$\int_0^2 \int_x^2 x\sqrt{1 + y^3}\, dy\, dx = \frac{26}{9}$$

63.



$$\int_0^1 \int_{2x}^2 4e^{y^2}\, dy\, dx = e^4 - 1 \approx 53.598$$

CHAPTER 14

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

65.



$$\int_0^1 \int_y^1 \sin x^2 \, dx \, dy = \frac{1}{2}(1 - \cos 1) \approx 0.230$$

67. $4\displaystyle\int_0^5 \int_0^{\sqrt{25-x^2}} dy \, dx = 25\pi$ square units

69. (a) No (b) Yes (c) Yes **71.** $\frac{1664}{105}$

73. $\frac{\sin 2}{2} - \frac{\sin 3}{3}$ **75.** $(\ln 5)^2$ **77.** $\frac{15\pi}{2}$

79. (a)



(b) $\displaystyle\int_0^8 \int_{x^2/32}^{\sqrt[3]{x}} (x^2y - xy^2) \, dy \, dx$ (c) $\frac{67{,}520}{693}$

81. True

Section 14.2 *(page 987)*

1. Use rectangular prisms to approximate the volume, where $f(x_i, y_i)$ is the height of prism i and ΔA_i is the area of the rectangular base of the prism. You can improve the approximation by using more rectangular prisms of smaller rectangular bases.

3. 24; Approximation is exact.

5. Approximation: 52; Exact: $\frac{160}{3}$

7.



2

9.



36

11.



0

13. $\displaystyle\int_0^3 \int_0^5 xy \, dy \, dx = \frac{225}{4}$

$\displaystyle\int_0^5 \int_0^3 xy \, dx \, dy = \frac{225}{4}$

15. $\displaystyle\int_1^2 \int_x^{2x} \frac{y}{x^2 + y^2} \, dy \, dx = \frac{1}{2} \ln \frac{5}{2}$

$\displaystyle\int_1^2 \int_1^y \frac{y}{x^2 + y^2} \, dx \, dy + \int_2^4 \int_{y/2}^2 \frac{y}{x^2 + y^2} \, dx \, dy = \frac{1}{2} \ln \frac{5}{2}$

17. $\displaystyle\int_0^1 \int_{4-x}^{4-x^2} -2y \, dy \, dx = -\frac{6}{5}$

$\displaystyle\int_3^4 \int_{4-y}^{\sqrt{4-y}} -2y \, dx \, dy = -\frac{6}{5}$

19. $\displaystyle\int_0^3 \int_{4y/3}^{\sqrt{25-y^2}} x \, dx \, dy = 25$

$\displaystyle\int_0^4 \int_0^{3x/4} x \, dy \, dx + \int_4^5 \int_0^{\sqrt{25-x^2}} x \, dy \, dx = 25$

21. 4 **23.** 12 **25.** $\frac{3}{8}$ **27.** 1

29. $\displaystyle\int_0^1 \int_0^{x^3} xy \, dy \, dx = \frac{1}{16}$ **31.** $\displaystyle\int_0^2 \int_0^{\sqrt{4-x^2}} (x + y) \, dy \, dx = \frac{16}{3}$

33. $\displaystyle\int_0^2 \int_0^{4-x^2} (4 - x^2) \, dy \, dx = \frac{256}{15}$

35. $\displaystyle 2\int_0^2 \int_0^{\sqrt{1-(x-1)^2}} (2x - x^2 + y^2) \, dy \, dx$

37. $\displaystyle 4\int_0^2 \int_0^{\sqrt{4-x^2}} (x^2 + y^2) \, dy \, dx$

39. $\displaystyle\int_0^2 \int_{-\sqrt{2-2(y-1)^2}}^{\sqrt{2-2(y-1)^2}} (4y - x^2 - 2y^2) \, dx \, dy$

41. $\frac{81\pi}{2}$ **43.** 1.2315

45.



$$\int_0^{1/2} \int_0^{2x} e^{-x^2} \, dy \, dx = 1 - e^{-1/4} \approx 0.221$$

47.



$$\int_{-2}^2 \int_{-\sqrt{4-y^2}}^{\sqrt{4-y^2}} \sqrt{4 - y^2} \, dx \, dy = \frac{64}{3}$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

49.



$$\int_0^4 \int_0^{y/2} \sin y^2 \, dx \, dy = \frac{1 - \cos 16}{4} \approx 0.489$$

51. 2 **53.** $\frac{8}{3}$ **55.** $(e - 1)^2$ **57.** 25,645.24

59. kB; Answers will vary. **61.** Proof; $\frac{2}{3}$ **63.** Proof; $\frac{4}{9}$

65. Proof **67.** 400; 272

69. False. $V = 8\int_0^1 \int_0^{\sqrt{1-y^2}} \sqrt{1 - x^2 - y^2} \, dx \, dy$

71. R: $x^2 + y^2 \leq 9$ **73.** $\frac{1}{2}(1 - e)$

75. Putnam Problem A2, 1989

Section 14.3 *(page 995)*

1. Rectangular

3. r-Simple regions have fixed bounds for θ and variable bounds for r. θ-Simple regions have variable bounds for θ and fixed bounds for r.

5. $R = \{(r, \theta): 0 \leq r \leq 8, 0 \leq \theta \leq \pi\}$

7. $R = \left\{(r, \theta): 4 \leq r \leq 8, 0 \leq \theta \leq \frac{\pi}{2}\right\}$

9. π **11.** 0





13. $\frac{8\sqrt{2}\pi}{3}$ **15.** $\frac{9}{8} + \frac{3\pi^2}{32}$





17. 9 **19.** 4π **21.** $\frac{\pi}{10}$ **23.** $\frac{2}{3}$

25. $\frac{\pi}{2} \sin 1$ **27.** $\int_0^{\pi/4} \int_0^{2\sqrt{2}} r^2 \, dr \, d\theta = \frac{4\sqrt{2}\pi}{3}$

29. $\int_0^{\pi/2} \int_0^6 (\cos\theta + \sin\theta) r^2 \, dr \, d\theta = 144$

31. $\int_0^{\pi/4} \int_1^2 r\theta \, dr \, d\theta = \frac{3\pi^2}{64}$ **33.** $\frac{1}{8}$ **35.** $\frac{250\pi}{3}$

37. $\frac{64}{9}(3\pi - 4)$ **39.** $2\sqrt{4 - 2\sqrt[3]{2}}$ **41.** 9π

43. $\frac{3\pi}{2}$ **45.** π

47.



$\frac{\pi}{3} + \frac{\sqrt{3}}{2}$

49.



π

51.



$\frac{4\pi}{3} + 2\sqrt{3}$

53. $\int_0^{\pi/6} \int_1^{\sqrt{3}\sec\theta} r \, dr \, d\theta + \int_{\pi/6}^{\pi/2} \int_1^{\csc\theta} r \, dr \, d\theta = \sqrt{3} - \frac{\pi}{4}$

55. 486,788 **57.** 1.2858 **59.** 56.051

61. False. Let $f(r, \theta) = r - 1$ and let R be a sector where $0 \leq r \leq 6$ and $0 \leq \theta \leq \pi$.

63. (a) 2π (b) $\sqrt{2\pi}$

65. (a) $\int_2^4 \int_{y/\sqrt{3}}^{y} f \, dx \, dy$

(b) $\int_{2/\sqrt{3}}^{2} \int_2^{\sqrt{3}x} f \, dy \, dx + \int_2^{4/\sqrt{3}} \int_x^{\sqrt{3}x} f \, dy \, dx + \int_{4/\sqrt{3}}^{4} \int_x^4 f \, dy \, dx$

(c) $\int_{\pi/4}^{\pi/3} \int_{2\csc\theta}^{4\csc\theta} fr \, dr \, d\theta$

67. $\frac{4}{\pi}$

Section 14.4 *(page 1004)*

1. Use a double integral when the density of the lamina is not constant.

3. $m = 4$ **5.** $m = \frac{1}{8}$

7. (a) $m = ka^2, \left(\frac{a}{2}, \frac{a}{2}\right)$ (b) $m = \frac{ka^3}{2}, \left(\frac{a}{2}, \frac{2a}{3}\right)$

(c) $m = \frac{ka^3}{2}, \left(\frac{2a}{3}, \frac{a}{2}\right)$

9. (a) $m = \frac{ka^2}{2}, \left(\frac{a}{3}, \frac{2a}{3}\right)$ (b) $m = \frac{ka^3}{3}, \left(\frac{3a}{8}, \frac{3a}{4}\right)$

(c) $m = \frac{ka^3}{6}, \left(\frac{a}{2}, \frac{3a}{4}\right)$

11. (a) $\left(\frac{a}{2} + 5, \frac{a}{2}\right)$ (b) $\left(\frac{a}{2} + 5, \frac{2a}{3}\right)$

(c) $\left(\frac{2(a^2 + 15a + 75)}{3(a + 10)}, \frac{a}{2}\right)$

13. $m = \frac{k}{4}, \left(\frac{2}{3}, \frac{8}{15}\right)$ **15.** $m = 30k, \left(\frac{14}{5}, \frac{4}{5}\right)$

17. $m = k(e - 1), \left(\frac{1}{e - 1}, \frac{e + 1}{4}\right)$

CHAPTER 14

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

19. $m = \frac{256k}{15}, \left(0, \frac{16}{7}\right)$ **21.** $m = \frac{6k}{\pi}, \left(\frac{3}{2}, \frac{\pi}{8}\right)$

23. $m = \frac{9\pi k}{2}, \left(\frac{8\sqrt{2}}{\pi}, \frac{8(2-\sqrt{2})}{\pi}\right)$

25. $m = \frac{k}{8}(1 - 5e^{-4}), \left(\frac{e^4 - 13}{e^4 - 5}, \frac{8}{27}\left[\frac{e^6 - 7}{e^6 - 5e^2}\right]\right)$

27. $m = \frac{k\pi}{3}, \left(\frac{81\sqrt{3}}{40\pi}, 0\right)$

29. $\bar{\bar{x}} = \frac{\sqrt{3}b}{3}$ $\bar{\bar{y}} = \frac{\sqrt{3}h}{3}$ **31.** $\bar{\bar{x}} = \frac{a}{2}$ $\bar{\bar{y}} = \frac{a}{2}$ **33.** $\bar{\bar{x}} = \frac{a}{2}$ $\bar{\bar{y}} = \frac{a}{2}$

35. $I_x = \frac{32k}{3}$ $I_y = \frac{16k}{3}$ $I_0 = 16k$ $\bar{\bar{x}} = \frac{2\sqrt{3}}{3}$ $\bar{\bar{y}} = \frac{2\sqrt{6}}{3}$

37. $I_x = 16k$ $I_y = \frac{512k}{5}$ $I_0 = \frac{592k}{5}$ $\bar{\bar{x}} = \frac{4\sqrt{15}}{5}$ $\bar{\bar{y}} = \frac{\sqrt{6}}{2}$

39. $2k\int_{-b}^{b}\int_{0}^{\sqrt{b^2-x^2}} (x-a)^2\,dy\,dx = \frac{k\pi b^2}{4}(b^2 + 4a^2)$

41. $\int_{-a}^{a}\int_{0}^{\sqrt{a^2-x^2}} ky(y-a)^2\,dy\,dx = ka^5\left(\frac{56 - 15\pi}{60}\right)$

43. $\frac{L}{3}$ **45.** $\frac{L}{2}$

47. The object with a greater polar moment of inertia has more resistance, so more torque is required to twist the object.

49. Proof

Section 14.5 *(page 1011)*

1. If f and its first partial derivatives are continuous on the closed region R in the xy-plane, then the differential of the surface area given by $z = f(x, y)$ over R is $dS = \sqrt{1 + [f_x(x, y)]^2 + [f_y(x, y)]^2}\,dA$.

3. 24 **5.** $4\pi\sqrt{62}$ **7.** $\frac{1}{2}\left[4\sqrt{17} + \ln\left(4 + \sqrt{17}\right)\right]$

9. $\frac{8}{27}\left(10\sqrt{10} - 1\right)$ **11.** $\sqrt{2} - 1$ **13.** $\sqrt{2}\pi$

15. $2\pi a\left(a - \sqrt{a^2 - b^2}\right)$ **17.** $12\sqrt{14}$ **19.** 20π

21. $\int_0^1\int_0^x \sqrt{5 + 4x^2}\,dy\,dx = \frac{27 - 5\sqrt{5}}{12} \approx 1.3183$

23. $\int_{-3}^{3}\int_{-\sqrt{9-x^2}}^{\sqrt{9-x^2}} \sqrt{1 + 4x^2 + 4y^2}\,dy\,dx$

$= \frac{\pi}{6}\left(37\sqrt{37} - 1\right) \approx 117.3187$

25. $\int_0^1\int_0^1 \sqrt{1 + 4x^2 + 4y^2}\,dy\,dx \approx 1.8616$

27. $\int_0^4\int_0^{10} \sqrt{1 + e^{2xy}(x^2 + y^2)}\,dy\,dx$

29. $\int_{-\sqrt{\pi/2}}^{\sqrt{\pi/2}}\int_{-\sqrt{(\pi/2)-x^2}}^{\sqrt{(\pi/2)-x^2}} \sqrt{1 + 4(x^2 + y^2)\sin^2(x^2 + y^2)}\,dy\,dx$

31. No. The size and shape of the graph stay the same, just the position is changed. So, the surface area does not increase.

33. (a) $812\pi\sqrt{609}\ \text{cm}^3$ (b) $100\pi\sqrt{609}\ \text{cm}^2$ **35.** 16

Section 14.6 *(page 1021)*

1. The volume of the solid region Q **3.** 18 **5.** $\frac{1}{9}$

7. $\frac{15}{2}\left(1 - \frac{1}{e}\right)$ **9.** $\frac{189}{2}$ **11.** $\frac{324}{5}$

13. $\int_0^7\int_0^{(7-x)/2}\int_0^{7-x-2y} dz\,dy\,dx$

15. $\int_{-\sqrt{6}}^{\sqrt{6}}\int_{-\sqrt{6-y^2}}^{\sqrt{6-y^2}}\int_0^{6-x^2-y^2} dz\,dx\,dy$

17. $\int_{-4}^{4}\int_{-\sqrt{16-x^2}}^{\sqrt{16-x^2}}\int_{(x^2+y^2)/2}^{\sqrt{80-x^2-y^2}} dz\,dy\,dx$ **19.** $\frac{256}{15}$

21. $\frac{3}{2}$ **23.** 10

25.



$\int_0^1\int_0^1\int_{-1}^{-\sqrt{z}} dy\,dz\,dx$

27.



$\int_0^3\int_0^{(12-4z)/3}\int_0^{(12-4z-3x)/6} dy\,dx\,dz$

29.



$\int_0^1\int_0^x\int_0^{\sqrt{1-y^2}} dz\,dy\,dx$

31. $\int_0^3\int_0^5\int_{y/5}^1 xyz\,dx\,dy\,dz$, $\int_0^3\int_0^1\int_0^{5x} xyz\,dy\,dx\,dz$, $\int_0^5\int_0^3\int_{y/5}^1 xyz\,dx\,dz\,dy$, $\int_0^1\int_0^3\int_0^{5x} xyz\,dy\,dz\,dx$, $\int_0^5\int_{y/5}^1\int_0^3 xyz\,dz\,dx\,dy$, $\int_0^1\int_0^{5x}\int_0^3 xyz\,dz\,dy\,dx$; $\frac{225}{16}$

33. $\int_{-3}^{3}\int_{-\sqrt{9-x^2}}^{\sqrt{9-x^2}}\int_0^4 xyz\,dz\,dy\,dx$, $\int_{-3}^{3}\int_{-\sqrt{9-y^2}}^{\sqrt{9-y^2}}\int_0^4 xyz\,dz\,dx\,dy$, $\int_{-3}^{3}\int_0^4\int_{-\sqrt{9-x^2}}^{\sqrt{9-x^2}} xyz\,dy\,dz\,dx$, $\int_0^4\int_{-3}^{3}\int_{-\sqrt{9-x^2}}^{\sqrt{9-x^2}} xyz\,dy\,dx\,dz$, $\int_0^4\int_{-3}^{3}\int_{-\sqrt{9-y^2}}^{\sqrt{9-y^2}} xyz\,dx\,dy\,dz$, $\int_{-3}^{3}\int_0^4\int_{-\sqrt{9-y^2}}^{\sqrt{9-y^2}} xyz\,dx\,dz\,dy$; 0

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

35. $\int_0^1\int_0^{1-z}\int_0^{1-y^2} dx\,dy\,dz$, $\int_0^1\int_0^{1-y}\int_0^{1-y^2} dx\,dz\,dy$,
$\int_0^1\int_0^{2z-z^2}\int_0^{1-z} 1\,dy\,dx\,dz + \int_0^1\int_{2z-z^2}^1\int_0^{\sqrt{1-x}} 1\,dy\,dx\,dz$,
$\int_0^1\int_{1-\sqrt{1-x}}^1\int_0^{1-z} 1\,dy\,dz\,dx + \int_0^1\int_0^{1-\sqrt{1-x}}\int_0^{\sqrt{1-x}} 1\,dy\,dz\,dx$,
$\int_0^1\int_0^{\sqrt{1-x}}\int_0^{1-y} dz\,dy\,dx$

37. $m = 8k$, $\bar{x} = \frac{3}{2}$ **39.** $m = \frac{128k}{3}$, $\bar{z} = 1$

41. $m = k\int_0^b\int_0^b\int_0^b xy\,dz\,dy\,dx$

$M_{yz} = k\int_0^b\int_0^b\int_0^b x^2y\,dz\,dy\,dx$

$M_{xz} = k\int_0^b\int_0^b\int_0^b xy^2\,dz\,dy\,dx$

$M_{xy} = k\int_0^b\int_0^b\int_0^b xyz\,dz\,dy\,dx$

43. $\bar{x}$ will be greater than 2, and $\bar{y}$ and $\bar{z}$ will be unchanged.

45. $\bar{x}$ and $\bar{z}$ will be unchanged, and $\bar{y}$ will be greater than 0.

47. $\left(0, 0, \frac{3h}{4}\right)$ **49.** $\left(0, 0, \frac{3}{2}\right)$ **51.** $\left(5, 6, \frac{5}{4}\right)$

53. (a) $I_x = \frac{2ka^5}{3}$ **55.** (a) $I_x = 256k$

$I_y = \frac{2ka^5}{3}$ $I_y = \frac{512k}{3}$

$I_z = \frac{2ka^5}{3}$ $I_z = 256k$

(b) $I_x = \frac{ka^8}{8}$ (b) $I_x = \frac{2048k}{3}$

$I_y = \frac{ka^8}{8}$ $I_y = \frac{1024k}{3}$

$I_z = \frac{ka^8}{8}$ $I_z = \frac{2048k}{3}$

57. Proof

59. $\int_{-1}^1\int_{-1}^1\int_0^{1-x} (x^2 + y^2)\sqrt{x^2 + y^2 + z^2}\,dz\,dy\,dx$

61. (a) $m = \int_{-2}^2\int_{-\sqrt{4-x^2}}^{\sqrt{4-x^2}}\int_0^{4-x^2-y^2} kz\,dz\,dy\,dx$

(b) $\bar{x} = \bar{y} = 0$ by symmetry.

$\bar{z} = \frac{1}{m}\int_{-2}^2\int_{-\sqrt{4-x^2}}^{\sqrt{4-x^2}}\int_0^{4-x^2-y^2} kz^2\,dz\,dy\,dx$

(c) $I_z = \int_{-2}^2\int_{-\sqrt{4-x^2}}^{\sqrt{4-x^2}}\int_0^{4-x^2-y^2} kz(x^2 + y^2)\,dz\,dy\,dx$

63. $\frac{13}{3}$ **65.** $\frac{3}{2}$ **67.** Increase

69. b **71.** $2x^2 + y^2 + 3z^2 \le 1$; 0.684; $\frac{4\sqrt{6}\pi}{45}$

73. Putnam Problem B1, 1965

Section 14.7 *(page 1029)*

1. Some solids are represented by equations involving x^2 and y^2. Often, converting these equations to cylindrical or spherical coordinates yields equations you can work with more easily.

3. 27 **5.** $\frac{11}{10}$ **7.** $\frac{\pi}{3}$ **9.** $\pi(e^4 + 3)$

11.



13.



$\frac{64\sqrt{3}\pi}{3}$

$\frac{\pi}{4}(1 - e^{-9})$

15. $48(3\pi - 4)$ **17.** $\frac{\pi}{6}$ **19.** $\frac{250}{9}(3\pi - 4)$ **21.** $48k\pi$

23. $\frac{\pi r_0^2 h}{3}$ **25.** $\left(0, 0, \frac{h}{5}\right)$

27. $I_z = 4k\int_0^{\pi/2}\int_0^{r_0}\int_0^{h(r_0-r)/r_0} r^3\,dz\,dr\,d\theta = \frac{3mr_0^2}{10}$

29. Proof **31.** $9\pi\sqrt{2}$ **33.** $16\pi^2$ **35.** $k\pi a^4$

37. $\left(0, 0, \frac{3r}{8}\right)$ **39.** $\frac{k\pi}{192}$

41. Cylindrical: $\int_0^{2\pi}\int_0^2\int_{r^2}^4 r^2\cos\theta\,dz\,dr\,d\theta = 0$

Spherical: $\int_0^{2\pi}\int_0^{\arctan(1/2)}\int_0^{4\sec\phi} \rho^3\sin^2\phi\cos\theta\,d\rho\,d\phi\,d\theta$
$+ \int_0^{2\pi}\int_{\arctan(1/2)}^{\pi/2}\int_0^{\cot\phi\csc\phi} \rho^3\sin^2\phi\cos\phi\,d\rho\,d\phi\,d\theta = 0$

43. Cylindrical: $\int_0^{2\pi}\int_0^1\int_1^{1+\sqrt{1-r^2}} r^2\cos\theta\,dz\,dr\,d\theta = 0$

Spherical: $\int_0^{\pi/4}\int_0^{2\pi}\int_{\sec\phi}^{2\cos\phi} \rho^3\sin^2\phi\cos\theta\,d\rho\,d\theta\,d\phi = 0$

45. (a) r constant: right circular cylinder about z-axis
θ constant: plane parallel to z-axis
z constant: plane parallel to xy-plane
(b) ρ constant: sphere
θ constant: plane parallel to z-axis
ϕ constant: cone

47. Putnam Problem A1, 2006

Section 14.8 *(page 1036)*

1. $\frac{\partial x}{\partial u}\frac{\partial y}{\partial v} - \frac{\partial y}{\partial u}\frac{\partial x}{\partial v}$ **3.** $-\frac{1}{2}$ **5.** $1 + 2v$

7. 1 **9.** $-e^{2u}$

11.



13.



15. $\int_R\int 3xy\,dA = \int_{-2/3}^{2/3}\int_{1-x}^{(1/2)x+2} 3xy\,dy\,dx$
$+ \int_{2/3}^{4/3}\int_{(1/2)x}^{(1/2)x+2} 3xy\,dy\,dx + \int_{4/3}^{8/3}\int_{(1/2)x}^{4-x} 3xy\,dy\,dx = \frac{164}{9}$

CHAPTER 14

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

17. $\frac{8}{3}$ **19.** 36 **21.** $(e^{-1/2} - e^{-2})\ln 8 \approx 0.9798$ **23.** 18
25. $12(e^4 - 1)$ **27.** $\frac{100}{9}$ **29.** $\frac{2}{5}a^{5/2}$ **31.** One
33. (a)





(b) ab (c) πab
35. u^2v **37.** $-uv$ **39.** $-\rho^2 \sin\phi$
41. Putnam Problem A2, 1994

Review Exercises for Chapter 14 *(page 1038)*

1. Use Theorem 14.3 on page 992 to change from rectangular coordinates to polar coordinates in a double integral:

$$\int_R\int f(x, y)dA = \int_\alpha^\beta \int_{g_1(\theta)}^{g_2(\theta)} f(r\cos\theta, r\sin\theta)r\,dr\,d\theta.$$

3. Proof **5.** (a) Horizontal (b) Polar (c) Vertical
7. $\frac{1 - \cos 3x^2}{x}$ **9.** $\frac{10y^3}{3}$ **11.** $\frac{29}{6}$
13. $\frac{1}{6}$ **15.** $\frac{3}{2}$ **17.** 16
19.



$$\int_1^5\int_0^4 dy\,dx = \int_0^4\int_1^5 dx\,dy = 16$$

21.



$$\int_0^2\int_{y/2}^{3-y} dx\,dy = \int_0^1\int_0^{2x} dy\,dx + \int_1^3\int_0^{3-x} dy\,dx = 3$$

23. $\int_0^2\int_0^4 4xy\,dy\,dx = \int_0^4\int_0^2 4xy\,dx\,dy = 64$ **25.** 21
27. $\frac{40}{3}$ **29.** $\frac{40}{3}$ **31.** 13.67°C **33.** $\frac{5\sqrt{5}\pi}{6}$
35. $\frac{81}{5}$ **37.** $\frac{3\pi}{2}$
39.



$$\frac{13\sqrt{3}}{2} - \frac{5\pi}{3}$$

41. (a) $r = 3\sqrt{\cos 2\theta}$



(b) 9 (c) $3\left(3\pi - 16\sqrt{2} + 20\right) \approx 20.392$
43. 7 **45.** $m = \frac{32k}{5}, \left(\frac{5}{3}, \frac{5}{2}\right)$ **47.** $m = \frac{k}{4}, \left(\frac{32}{45}, \frac{64}{55}\right)$
49. $I_x = 12k$

$I_y = \frac{81k}{2}$

$I_0 = \frac{105k}{2}$

$\bar{\bar{x}} = \frac{3\sqrt{2}}{2}$

$\bar{\bar{y}} = \frac{2\sqrt{3}}{3}$

51. $\frac{\pi}{6}\left(101\sqrt{101} - 1\right)$ **53.** $\frac{1}{6}\left(37\sqrt{37} - 1\right)$
55. (a) 30,415.74 ft^3 (b) 2081.53 ft^2 **57.** 56
59. $\frac{16}{3} + 2e$ **61.** $\frac{8\pi}{5}$ **63.** 36
65.



$$\int_0^1\int_x^1\int_0^{\sqrt{1-x^2}} dz\,dy\,dx$$

67. $m = \frac{500k}{3}, \bar{x} = \frac{5}{2}$ **69.** $12\left(\sqrt{3} - 1\right)$ **71.** $\frac{\pi}{15}$
73. $\pi\left(3\sqrt{13} + 4\ln\frac{3 + \sqrt{13}}{2}\right) \approx 48.995$ **75.** 16π
77. $\frac{8\pi}{3}\left(2 - \sqrt{3}\right)$ **79.** $-6(v + u)$ **81.** $\sin^2\theta - \cos^2\theta$
83. $5\ln 5 - 3\ln 3 - 2 \approx 2.751$ **85.** 81 **87.** Proof
89. (a) $\frac{1}{3}\pi h^2(3a - h)$ (b) $\left(0, 0, \frac{3(2a - h)^2}{4(3a - h)}\right)$ (c) $\left(0, 0, \frac{3}{8}a\right)$
(d) a (e) $(\pi/30)h^3(20a^2 - 15ah + 3h^2)$ (f) $4\pi a^5/15$

P.S. Problem Solving *(page 1042)*

1. Proof **3.** $\int_0^\infty e^{-x^2}\,dx = \frac{\sqrt{\pi}}{2}$. **5.** (a)–(g) Proofs
7.



$$\int_0^3\int_0^{2x}\int_x^{6-x} dy\,dz\,dx = 18$$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Chapter 15

Section 15.1 *(page 1053)*

1. See "Definition of Vector Field" on page 1044. Some physical examples of vector fields include velocity fields, gravitational fields, and electric force fields.

3. Reconstruct a function from its partial derivatives by integrating and comparing versions of the function to determine constants.

5. d **6.** c **7.** a **8.** b

9. $\sqrt{2}$ **11.** $\sqrt{1 + 9y^2}$




13. $\sqrt{3}$ **15.**




17.



19. $2x\mathbf{i} + 4y\mathbf{j}$ **21.** $(10x + 3y)\mathbf{i} + (3x + 2y)\mathbf{j}$

23. $6yz\mathbf{i} + 6xz\mathbf{j} + 6xy\mathbf{k}$ **25.** $2xye^{x^2}\mathbf{i} + e^{x^2}\mathbf{j} + \mathbf{k}$

27. $\left[\dfrac{xy}{x + y} + y\ln(x + y)\right]\mathbf{i} + \left[\dfrac{xy}{x + y} + x\ln(x + y)\right]\mathbf{j}$

29. Conservative **31.** Not conservative **33.** Conservative

35. Not conservative

37. Conservative; $f(x, y) = 3xy - \dfrac{x^3}{3} + \dfrac{y^2}{2} + K$

39. Conservative; $f(x, y) = e^{x^2y} + K$ **41.** Not conservative

43. Conservative; $f(x, y) = x\sin y + K$ **45.** $4\mathbf{i} - \mathbf{j} - 3\mathbf{k}$

47. $-2\mathbf{k}$ **49.** $\dfrac{2x}{x^2 + y^2}\mathbf{k}$

51. Conservative; $f(x, y, z) = x^3 + y^3 + z^3 + xyz + K$

53. Not conservative

55. Conservative; $f(x, y, z) = \dfrac{xz}{y} - z + K$ **57.** $2x + 4y$

59. $2\sin x\cos x + 3z^2$ **61.** 28 **63.** 0

65. Vector field; The curl of a vector field is a vector field.

67. Neither; The expression is meaningless because you can only take the curl of a vector field.

69. $9x\mathbf{j} - 2y\mathbf{k}$ **71.** $z\mathbf{j} + y\mathbf{k}$ **73.** $3z + 2x$ **75.** 0

77. (a)–(h) Proofs

Section 15.2 *(page 1065)*

1. (a) The arc length of C (b) The mass of the string

3. $\mathbf{r}(t) = \begin{cases} t\mathbf{i} + t\mathbf{j}, & 0 \le t \le 1 \\ (2 - t)\mathbf{i} + \sqrt{2 - t}\,\mathbf{j}, & 1 \le t \le 2 \end{cases}$

5. $\mathbf{r}(t) = \begin{cases} t\mathbf{i}, & 0 \le t \le 3 \\ 3\mathbf{i} + (t - 3)\mathbf{j}, & 3 \le t \le 6 \\ (9 - t)\mathbf{i} + 3\mathbf{j}, & 6 \le t \le 9 \\ (12 - t)\mathbf{j}, & 9 \le t \le 12 \end{cases}$

7. $\mathbf{r}(t) = 3\cos t\mathbf{i} + 3\sin t\mathbf{j},\ 0 \le t \le 2\pi$

9. (a) C: $\mathbf{r}(t) = t\mathbf{i} + t\mathbf{j},\ 0 \le t \le 1$ (b) $\dfrac{2\sqrt{2}}{3}$

11. (a) C: $\mathbf{r}(t) = \cos t\mathbf{i} + \sin t\mathbf{j},\ 0 \le t \le \dfrac{\pi}{2}$ (b) $\dfrac{\pi}{2}$

13. (a) C: $\mathbf{r}(t) = \begin{cases} t\mathbf{i}, & 0 \le t \le 1 \\ t\mathbf{i} + (4t - 4)\mathbf{j}, & 1 \le t \le 2 \end{cases}$

(b) $1 + 7\sqrt{17}$

15. (a) C: $\mathbf{r}(t) = \begin{cases} t\mathbf{i}, & 0 \le t \le 1 \\ (2 - t)\mathbf{i} + (t - 1)\mathbf{j}, & 1 \le t \le 2 \\ (3 - t)\mathbf{j}, & 2 \le t \le 3 \end{cases}$

(b) $3 + 3\sqrt{2}$

17. (a) C: $\mathbf{r}(t) = \begin{cases} t\mathbf{i}, & 0 \le t \le 1 \\ \mathbf{i} + (t - 1)\mathbf{k}, & 1 \le t \le 2 \\ \mathbf{i} + (t - 2)\mathbf{j} + \mathbf{k}, & 2 \le t \le 3 \end{cases}$ (b) $\dfrac{23}{6}$

19. 20 **21.** $\dfrac{5\pi}{2}$ **23.** $8\sqrt{5}\pi\left(1 + \dfrac{4\pi^2}{3}\right) \approx 795.7$

25. $2\pi + 2$ **27.** $\dfrac{k}{12}\left(41\sqrt{41} - 27\right)$ **29.** 8

31. $\frac{1}{3}e^6 + \frac{95}{3}$ **33.** $\frac{9}{4}$ **35.** About 249.49 **37.** 66

39. 0 **41.** $-10\pi^2$

43. Positive; The vector field determined by $\mathbf{F}$ points in the general direction of the path C, so $\mathbf{F} \cdot \mathbf{T} > 0$.

45. Zero; The vector field determined by $\mathbf{F}$ is perpendicular to the path C.

47. (a) $\frac{236}{3}$; Orientation is from left to right, so the value is positive.

(b) $-\frac{236}{3}$; Orientation is from right to left, so the value is negative.

49. $\mathbf{F}(t) = -2t\mathbf{i} - t\mathbf{j}$

$\mathbf{r}'(t) = \mathbf{i} - 2\mathbf{j}$

$\mathbf{F}(t) \cdot \mathbf{r}'(t) = -2t + 2t = 0$

$\displaystyle\int_C \mathbf{F} \cdot d\mathbf{r} = 0$

51. $\mathbf{F}(t) = (t^3 - 2t^2)\mathbf{i} + \left(t - \dfrac{t^2}{2}\right)\mathbf{j}$

$\mathbf{r}'(t) = \mathbf{i} + 2t\mathbf{j}$

$\mathbf{F}(t) \cdot \mathbf{r}'(t) = t^3 - 2t^2 + 2t^2 - t^3 = 0$

$\displaystyle\int_C \mathbf{F} \cdot d\mathbf{r} = 0$

53. 68 **55.** $\frac{40}{3}$ **57.** 25 **59.** $\frac{63}{2}$ **61.** $-\frac{11}{6}$

63. $\dfrac{316}{3}$ **65.** $5h$ **67.** $\dfrac{1}{2}$ **69.** $\dfrac{h}{4}\left[2\sqrt{5} + \ln\left(2 + \sqrt{5}\right)\right]$

71. $\dfrac{1}{120}\left(25\sqrt{5} - 11\right)$

CHAPTER 15

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

73. (a) $12\pi \approx 37.70 \text{ cm}^2$ (b) $\frac{12\pi}{5} \approx 7.54 \text{ cm}^3$

(c)



75. $I_x = I_y = a^3\pi$

77. (a)



(b) $9\pi \text{ cm}^2 \approx 28.274 \text{ cm}^2$ (c) $\frac{27\pi}{2} \text{ cm}^3 \approx 42.412 \text{ cm}^3$

79. 1750 ft-lb **81.** No. $y = 2x$, so $dy = 2\,dx$.

83. z_3, z_1, z_2, z_4; The greater the height of the surface over the curve $y = \sqrt{x}$, the greater the lateral surface area.

85. False. $\displaystyle\int_C xy\,ds = \sqrt{2}\int_0^1 t^2\,dt$ **87.** -12

Section 15.3 *(page 1076)*

1. Verify that the vector field is conservative. Find a potential function. Calculate the difference of the values of the function evaluated at the endpoints.

3. (a) Proof

(b) $\displaystyle\int_{C_1} \mathbf{F}\cdot d\mathbf{r} = \int_0^1 (t^2 + 2t^3)\,dt = \frac{5}{6}$

$\displaystyle\int_{C_2} \mathbf{F}\cdot d\mathbf{r} = \int_0^{\pi/2} (\sin^2\theta\cos\theta + 2\sin^3\theta\cos\theta)\,d\theta = \frac{5}{6}$

5. (a) Proof

(b) $\displaystyle\int_{C_1} \mathbf{F}\cdot d\mathbf{r} = \int_0^{\pi/3} (3\tan^2\theta\sec\theta + 3\sec^3\theta)\,d\theta \approx 10.392$

$\displaystyle\int_{C_2} \mathbf{F}\cdot d\mathbf{r} = \int_0^3 \left(\frac{3\sqrt{t}}{2\sqrt{t+1}} + \frac{3\sqrt{t+1}}{2\sqrt{t}}\right) dt \approx 10.392$

7. (a) Proof

(b) $\displaystyle\int_{C_1} \mathbf{F}\cdot d\mathbf{r} = \int_0^1 64t^3\,dt = 16$

$\displaystyle\int_{C_2} \mathbf{F}\cdot d\mathbf{r} = \int_0^{\pi/2} 64\sin^3\theta\cos\theta\,d\theta = 16$

9. 72 **11.** -1 **13.** 0 **15.** (a) 2 (b) 2 (c) 2

17. 11 **19.** (a) Proof (b) 30,366

21. (a) Proof (b) 32 **23.** (a) 1 (b) 1

25. (a) 64 (b) 0 (c) 0 (d) 0

27. (a) 32 (b) 32 **29.** (a) $\frac{2}{3}$ (b) $\frac{17}{6}$ **31.** (a) 0 (b) 0

33. 0

35. (a) $d\mathbf{r} = (\mathbf{i} - \mathbf{j})\,dt \implies \displaystyle\int_0^{50} 175\,dt = 8750 \text{ ft-lb}$

(b) $d\mathbf{r} = \left(\mathbf{i} - \frac{1}{25}(50 - t)\mathbf{j}\right) dt$

$\displaystyle 7\int_0^{50} (50 - t)\,dt = 8750 \text{ ft-lb}$

37. $\mathbf{F}$ is conservative because $\nabla\left(\arctan\frac{x}{y}\right) = \mathbf{F}$. Furthermore, the closed path C lies above the x-axis. Hence, the line integral equals 0.

39. 1.125

41. Yes, because the work required to get from point to point is independent of the path taken.

43. False. It would be true if $\mathbf{F}$ were conservative.

45. True **47.** Proof

49. (a) Proof (b) $-\pi$ (c) π (d) -2π

(e) No, because $\mathbf{F}$ is not continuous at $(0, 0)$ in R enclosed by C.

(f) $\nabla\left(\arctan\frac{x}{y}\right) = \frac{1/y}{1 + (x/y)^2}\mathbf{i} + \frac{-x/y^2}{1 + (x/y)^2}\mathbf{j}$

Section 15.4 *(page 1085)*

1. A curve is simple when it does not cross itself. A connected plane region is simply connected when every simple closed curve in the region encloses only points that are in the region. For example, a region with a hole is not simply connected.

3. You are working with a simple closed curve with a boundary whose orientation is counterclockwise.

5. $\frac{1}{30}$ **7.** 0 **9.** About 19.99 **11.** $\frac{9}{2}$ **13.** 56

15. $\frac{4}{3}$ **17.** 0 **19.** 0 **21.** $\frac{1}{12}$ **23.** 32π

25. π **27.** $\frac{225}{2}$ **29.** 4π **31.** $\frac{9}{2}$ **33.** Proof

35. $\left(0, \frac{8}{5}\right)$ **37.** $\left(\frac{8}{15}, \frac{8}{21}\right)$ **39.** 54π **41.** $\pi - \frac{3\sqrt{3}}{2}$

43. (a) $\frac{51\pi}{2}$ (b) $\frac{243\pi}{2}$ **45.** 46π

47. (a) $\displaystyle\int_C \mathbf{F}\cdot d\mathbf{r} = \int_C M\,dx + N\,dy = \iint_R \left(\frac{\partial N}{\partial x} - \frac{\partial M}{\partial y}\right) dA = 0$

(b) $I = -2\pi$ when C is a circle that contains the origin.

49–53. Proofs **55.** Putnam Problem, A1 2015

Section 15.5 *(page 1095)*

1. S is traced out by the position vector $\mathbf{r}(u, v)$ as the point (u, v) moves throughout the domain. To sketch the surface, it is helpful to relate x, y, and z, where x, y, and z are functions of u and v.

3. e **4.** f **5.** b **6.** c **7.** d **8.** a

9. $y - 2z = 0$

Plane



11. $x^2 + z^2 = 4$

Cylinder



Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

13.



15.



17.



19. $\mathbf{r}(u, v) = u\mathbf{i} + v\mathbf{j} + 3v\mathbf{k}$

21. $\mathbf{r}(u, v) = \frac{1}{2}u \cos v\mathbf{i} + u\mathbf{j} + \frac{1}{3}u \sin v\mathbf{k}$, $u \geq 0$, $0 \leq v \leq 2\pi$ or $\mathbf{r}(x, y) = x\mathbf{i} + \sqrt{4x^2 + 9y^2}\mathbf{j} + z\mathbf{k}$

23. $\mathbf{r}(u, v) = 5 \cos u\mathbf{i} + 5 \sin u\mathbf{j} + v\mathbf{k}$

25. $\mathbf{r}(u, v) = u\mathbf{i} + \sqrt{u - 7} \cos v\mathbf{j} + \sqrt{u - 7} \sin v\mathbf{k}$ or $\mathbf{r}(y, z) = (y^2 + z^2 + 7)\mathbf{i} + y\mathbf{j} + z\mathbf{k}$

27. $\mathbf{r}(u, v) = v \cos u\mathbf{i} + v \sin u\mathbf{j} + 4\mathbf{k}$, $0 \leq v \leq 3$

29. $x = u$, $y = \frac{u}{2}\cos v$, $z = \frac{u}{2}\sin v$, $0 \leq u \leq 6$, $0 \leq v \leq 2\pi$

31. $x = \sin u \cos v$, $y = \sin u \sin v$, $z = u$
$0 \leq u \leq \pi$, $0 \leq v \leq 2\pi$

33. $x = \cos^2 u \cos v$, $y = u$, $z = \cos^2 u \sin v$
$\frac{\pi}{2} \leq u \leq \pi$, $0 \leq v \leq 2\pi$

35. $9y + \frac{3\sqrt{3}}{2}z = 12\sqrt{3}$ **37.** $4y - 3z = 12$ **39.** $8\sqrt{2}$

41. $\pi ab^2\sqrt{a^2 + 1}$ **43.** $\frac{\pi}{6}\left(17\sqrt{17} - 1\right) \approx 36.177$

45. The paraboloid is reflected (inverted) through the xy-plane.

47. The height of the paraboloid is increased from 4 to 9.

49–51. Proofs

53. (a)



(b)



(c)



(d)



The radius of the generating circle that is revolved about the z-axis is b, and its center is a units from the axis of revolution.

55. 400π m^2

57.



$2\pi\left[\frac{3}{2}\sqrt{13} + 2\ln\left(3 + \sqrt{13}\right) - 2\ln 2\right]$

59. Answers will vary. *Sample answer:* Let
$x = (2 - u)(5 + \cos v)\cos 3\pi u$
$y = (2 - u)(5 + \cos v)\sin 3\pi u$
$z = 5u + (2 - u)\sin v$
where $-\pi \leq u \leq \pi$ and $-\pi \leq v \leq \pi$.

Section 15.6 *(page 1108)*

1. Solve for y in the equation of the surface. Then use the integral $\iint_S f(x, g(x, z), z)\sqrt{1 + [g_x(x, z)]^2 + [g_z(x, z)]^2}\, dA$.

3. An orientable surface has two distinct sides.

5. $12\sqrt{2}$ **7.** 2π **9.** $\frac{27\sqrt{3}}{8}$ **11.** About -11.47

13. $\frac{364}{3}$ **15.** $12\sqrt{5}$ **17.** $\frac{3 - \sqrt{3}}{2}$ **19.** $\sqrt{3}\pi$

21. $\frac{32\pi}{3}$ **23.** 486π **25.** $-\frac{4}{3}$ **27.** $\frac{3\pi}{2}$ **29.** 20π

31. 384π **33.** $64\pi\rho$ **35.** 0 **37.** Proof **39.** $2\pi a^3 h$

41. (a) 12 (b) 12 (c) 12

43. (a)



(b) No. If a normal vector at a point P on the surface is moved around the Möbius strip once, it will point in the opposite direction.

(c)



Circle

(d) Construction

(e) You obtain a strip with a double twist that is twice as long as the Möbius strip.

Section 15.7 *(page 1116)*

1. Divergence Theorem or two surface integrals; In this case, it is easier to use the Divergence Theorem.

3. 1 **5.** 18 **7.** π **9.** $3a^4$ **11.** 0 **13.** 108π

15. 0 **17.** $18(e^4 - 5)$ **19.** Source

21. Incompressible **23.** Any point that satisfies $xyz > \frac{1}{2}$

25. 0; Proof **27–31.** Proofs

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Section 15.8 *(page 1123)*

1. Stokes's Theorem allows you to evaluate a line integral using a single double integral.

3. 18π **5.** 0 **7.** -12 **9.** 2π **11.** 0 **13.** $\frac{8}{3}$

15. $-\frac{a^5}{4}$ **17.** $\frac{81\pi}{4}$ **19.** Yes; Proof

21. Putnam Problem A5, 1987

Review Exercises for Chapter 15 *(page 1124)*

1. (a) A vector field $\mathbf{F}$ is conservative when there exists a differentiable function f such that $\mathbf{F} = \nabla f$.

(b) A potential function for $\mathbf{F}$ is the differentiable function f such that $\mathbf{F} = \nabla f$.

3. Proof; Answers will vary.

5. If $\mathbf{F}$ is a continuous vector field on a smooth curve C given by $\mathbf{r}(t)$, $a \le x \le b$, then the line integral of $\mathbf{F}$ on C is $\int_C \mathbf{F}\,d\mathbf{r} = \int_C \mathbf{F}\cdot\mathbf{T}\,ds$, which can be evaluated as the definite integral $\int_a^b \mathbf{F}(x(t), y(t), z(t))\cdot\mathbf{r}'(t)\,dt$.

7. $\sqrt{x^2+5}$



9. $y\cos xy\mathbf{i} + (x\cos xy - 2y)\mathbf{j}$ **11.** $(4x+y)\mathbf{i} + x\mathbf{j} + 2z\mathbf{k}$

13. Not conservative **15.** Conservative

17. Conservative; $f(x,y) = \frac{y}{x} + K$

19. Conservative; $f(x,y) = \frac{1}{2}x^2y^2 - \frac{1}{3}x^3 + \frac{1}{3}y^3 + K$

21. Not conservative **23.** Conservative; $f(x,y,z) = \frac{x}{yz} + K$

25. (a) $\operatorname{div}\mathbf{F} = 2x + 2xy + x^2$ (b) $\operatorname{curl}\mathbf{F} = -2xz\mathbf{j} + y^2\mathbf{k}$

27. (a) $\operatorname{div}\mathbf{F} = -y\sin x - x\cos y + xy$

(b) $\operatorname{curl}\mathbf{F} = xz\mathbf{i} - yz\mathbf{j}$

29. (a) $\operatorname{div}\mathbf{F} = \frac{1}{\sqrt{1-x^2}} + 2xy + 2yz$

(b) $\operatorname{curl}\mathbf{F} = z^2\mathbf{i} + y^2\mathbf{k}$

31. (a) $\operatorname{div}\mathbf{F} = \frac{2x+2y}{x^2+y^2} + 1$ (b) $\operatorname{curl}\mathbf{F} = \frac{2x-2y}{x^2+y^2}\mathbf{k}$

33. (a) $\frac{125}{3}$ (b) 2π **35.** 6π **37.** $\frac{9a^2}{5}$ **39.** 3π

41. 1 **43.** $2\pi^2$ **45.** $\frac{8}{3}\left(3 - 4\sqrt{2}\right) \approx -7.085$ **47.** 12

49. $\frac{\sqrt{5}}{3}(19 - \cos 6) \approx 13.446$

51. (a) Proof

(b) (i) $\int_C \mathbf{F}\cdot d\mathbf{r} = \int_0^4 (3t + 4 + t^3)\,dt = 104$

(ii) $\int_C \mathbf{F}\cdot d\mathbf{r} = \int_0^2 \left[(3w^2+4)(2w) + w^6(2w)\right]dw = 104$

53. $1 - \frac{1}{e^2}$ **55.** 6 **57.** (a) Proof (b) 92 **59.** 1

61. 0 **63.** 0 **65.** 0 **67.** 3

69. $z = 2(x^2+y^2)$

Paraboloid



71.



73. $\mathbf{r}(u,v) = \cos v\cos u\mathbf{i} + 2\sqrt{2}\cos v\sin u\mathbf{j} + 3\sin v\mathbf{k}$

75. $x = u,\ y = 2u^3\cos v,\ z = 2u^3\sin v,\ 0 \le u \le 2,\ 0 \le v \le 2\pi$

77. $3\sqrt{41}$ **79.** 45 **81.** $27\sqrt{41}$ **83.** $6\sqrt{26}$

85. 25π **87.** 66 **89.** $\frac{2a^6}{5}$ **91.** 16π

93. (a)–(d) Proofs

P.S. Problem Solving *(page 1128)*

1. (a) and (b) $\frac{25\sqrt{2}k\pi}{6}$ **3.** $3a^2\pi$

5. $I_x = \frac{\sqrt{13}\pi}{3}(27 + 32\pi^2)$

$I_y = \frac{\sqrt{13}\pi}{3}(27 + 32\pi^2)$

$I_z = 18\sqrt{13}\pi$

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Index

A

Abel, Niels Henrik (1802–1829), 232
Absolute convergence, 626
Absolute maximum of a function, 166
  of two variables, 940
Absolute minimum of a function, 166
  of two variables, 940
Absolute value, 54
  derivative involving, 320
  function, 22
Absolute Value Theorem, 592
Absolute zero, 78
Absolutely convergent series, 626
Acceleration, 128, 837, 861
  centripetal component of, 850
  tangential and normal components of, 849, 850, 863
  vector, 849, 861, 863
Accumulation function, 287
Acute angle, 31
Addition of vectors, 754, 764
Additive Identity Property of Vectors, 755
Additive Interval Property, 275
Additive Inverse Property of Vectors, 755
Agnesi, Maria Gaetana (1718–1799), 202
Algebraic function(s), 24, 25, 378
Algebraic properties of the cross product, 780
Alternating series, 623
  geometric, 623
  harmonic, 624, 626, 628
Alternating Series Remainder, 625
Alternating Series Test, 623
Alternative form
  of the derivative, 105
  of the directional derivative, 922
  of dot product, 772
  of Green's Theorem, 1084
  of L'Hôpital's Rule, 364
  of Log Rule for Integration, 324
  of Mean Value Theorem, 177
Amplitude of a function, 37
Angle(s), 31
  acute, 31
  between two nonzero vectors, 771
  between two planes, 789
  coterminal, 31
  directed, 719
  of incidence, 688
  of inclination of a plane, 935
  initial ray (or side) of, 31
  obtuse, 31
  radian measure of, 32
  reference, 35
  of reflection, 688
  standard position of, 31
  terminal ray (or side) of, 31
  trigonometric values of common, 34
  vertex of, 31
Angular speed, 1003
Antiderivative, 248
  of f with respect to x, 249
  finding by integration by parts, 523
  general, 249
  notation for, 249
  representation of, 248
  of a vector-valued function, 832
Antidifferentiation, 249
  of a composite function, 296
Aphelion, 698, 745
Apogee, 698
Approximating zeros
  bisection method, 82
  Intermediate Value Theorem, 81
  Newton's Method, 229
Approximation
  linear, 235, 906
  Padé, 403
  polynomial, 640
  Stirling's, 525
  tangent line, 235
  Two-Point Gaussian Quadrature, 312
Arc length, 32, 474, 475, 856
  derivative of, 856
  parameter, 856, 857
  in parametric form, 713
  of a polar curve, 733
  of a space curve, 855
  in the xy-plane, 1007
Arccosecant function, 373
Arccosine function, 373
Arccotangent function, 373
Archimedes (287–212 B.C.), 260
  Principle, 514
  spiral of, 721, 737
Arcsecant function, 373
Arcsine function, 373
  series for, 674
Arctangent function, 373
  series for, 674
Area
  of an ellipse, 545, 691, 692
  found by exhaustion method, 260
  line integral for, 1082
  of a parametric surface, 1092
  in polar coordinates, 729
  problem, 50
  of a rectangle, 260
  of a region between two curves, 445
  of a region in the plane, 264
  of a surface of revolution, 479
    in parametric form, 714
    in polar coordinates, 734
  of the surface S, 1007
  in the xy-plane, 1007
Associative Property
  of the Dot Product, 770
  of Vector Addition, 755
Astroid, 149
Astroidal sphere, 1097
Asymptote(s)
  horizontal, 200
  of a hyperbola, 693
  slant, 205, 211
  vertical, 89
Average rate of change, 12
Average value of a function
  on an interval, 285
  over a region R, 986
  over a solid region Q, 1023
Average velocity, 116
Axis
  conjugate, of a hyperbola, 693
  major, of an ellipse, 689
  minor, of an ellipse, 689
  of a parabola, 687
  polar, 719
  of revolution, 454
  transverse, of a hyperbola, 693

B

Barrow, Isaac (1630–1677), 148
Base(s), 317, 352
  of the natural exponential function, 352
  of a natural logarithm, 317
  other than e
    derivatives for, 354
    exponential function, 352
    logarithmic function, 353
Basic differentiation rules for elementary functions, 378
Basic equation obtained in a partial fraction decomposition, 552
  guidelines for solving, 556
Basic integration rules, 250, 385, 516
  procedures for fitting integrands to, 519
Basic limits, 63
Basic types of transformations, 23
Bearing, 758
Bernoulli equation, 438
  general solution of, 438
Bernoulli, James (1654–1705), 706
Bernoulli, John (1667–1748), 550
Bessel function, 659
Bifolium, 149
Binomial coefficient, 679
Binomial series, 673
Binormal vector, 853, 869
Bisection method, 82
Boundary point of a region, 884
Bounded
  above, 595
  below, 595
  monotonic sequence, 595
  region, 940
  sequence, 595
Brachistochrone problem, 706
Breteuil, Emilie de (1706–1749), 486
Bullet-nose curve, 141

C

Cantor set, 683
Cardioid, 724, 725

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Carrying capacity, 425, 427
Cassini, Giovanni Domenico (1625-1712), 728
Cassini oval, 728
Catenary, 393
Cauchy, Augustin-Louis (1789–1857), 79
Cauchy-Riemann equations, 901, 918
Cauchy-Schwarz Inequality, 778
Cavalieri, Bonaventura (1598–1647), 459
Cavalieri's Theorem, 464
Center
  of curvature, 860
  of an ellipse, 689
  of gravity, 496, 497
    of a one-dimensional system, 496
    of a two-dimensional system, 497
  of a hyperbola, 693
  of mass, 495, 496, 497
    of a one-dimensional system, 495, 496
    of a planar lamina, 498
      of variable density, 1000
    of a solid region, 1018
    of a two-dimensional system, 497
  of a power series, 651
Centered at c, 640
Central force field, 1045
Centripetal component of acceleration, 850
Centripetal force, 854
Centroid, 499
  of a simple region, 1000
Chain Rule, 133, 134, 139
  implicit differentiation, 916
  one independent variable, 911
  three or more independent variables, 914
  and trigonometric functions, 138
  two independent variables, 913
Change in x, 101
Change in y, 101
Change of variables, 299
  for definite integrals, 302
  for double integrals, 1033
  guidelines for making, 300
  for homogeneous equations, 431
  to polar form, 992
  using a Jacobian, 1031, 1037
Charles, Jacques (1746–1823), 78
Charles's Law, 78
Chebyshev polynomials, 1156
Chebyshev's equation, 1156
Circle, 149, 686, 725
  of curvature, 164, 860
  unit, 32
Circular function definitions of trigonometric functions, 33
Circulation of $\mathbf{F}$ around C_α, 1121
Circumference of an ellipse, 692
Circumscribed rectangle, 262
Cissoid, 149
Classification of conics by eccentricity, 738
Closed
  curve, 1074
  disk, 884
  region R, 884
  surface, 1110
Cobb-Douglas production function, 877
Coefficient(s), 24
  binomial, 679
  leading, 24
Cofunction identities, 33
Collinear, 17
Combinations of functions, 25
Common logarithmic function, 353
Common types of behavior associated with nonexistence of a limit, 55
Commutative Property
  of the Dot Product, 770
  of Vector Addition, 755
Comparison Test
  Direct, 616
  for improper integrals, 580
  Limit, 618
Completeness, 81, 595
Completing the square, 384
Component of acceleration
  centripetal, 850
  normal, 849, 850, 863
  tangential, 849, 850, 863
Component form of a vector in the plane, 753
Component functions, 820
Components of a vector, 774
  along $\mathbf{v}$, 774
  in the direction of $\mathbf{v}$, 775
  orthogonal to $\mathbf{v}$, 774
  in the plane, 753
Composite function, 25
  antidifferentiation of, 296
  continuity of, 79
  derivative of, 133
  limit of, 65
  of two variables, 873
    continuity of, 889
Composition of functions, 25, 873
Compound interest formulas, 356
Compounding, continuous, 356
Concave downward, 191
Concave upward, 191
Concavity, 191
  test for, 192
Conditional convergence, 626
Conditionally convergent series, 626
Conic(s), 686
  circle, 686
  classification by eccentricity, 738
  degenerate, 686
  directrix of, 738
  eccentricity, 738
  ellipse, 686, 689
  focus of, 738
  hyperbola, 686, 693
  parabola, 686, 687
  polar equations of, 739
  section, 686
Conjugate axis of a hyperbola, 693
Connected region, 1072
Conservative vector field, 1047, 1069
  independence of path, 1072
  test for, 1048, 1051
Constant
  Euler's, 615
  force, 485
  function, 24
  gravitational, 487
  of integration, 249
  Multiple Rule, 113, 139
    differential form, 238
    for integration, 298
  Rule, 110, 139
  term of a polynomial function, 24
Constraint, 956
Continued fraction expansion, 684
Continuity
  on a closed interval, 77
  of a composite function, 79
    of two variables, 889
  differentiability implies, 106
  and differentiability of inverse functions, 337
  implies integrability, 272
  properties of, 79
  of a vector-valued function, 824
Continuous, 74
  at c, 63, 74
  on the closed interval $[a, b]$, 77
  compounding, 356
  everywhere, 74
  function of two variables, 888
  on an interval, 824
  from the left and from the right, 77
  on an open interval (a, b), 74
  in the open region R, 888, 890
  at a point, 824, 888, 890
  vector field, 1044
Continuously differentiable, 474
Contour lines, 875
Converge, 231, 589, 599
Convergence
  absolute, 626
  conditional, 626
  endpoint, 654
  of a geometric series, 601
  of improper integral with infinite discontinuities, 575
  interval of, 652, 656
  of Newton's Method, 231, 232
  of a power series, 652
  of p-series, 611
  radius of, 652, 656
  of a sequence, 589
  of a series, 599
  of Taylor series, 670
  tests for series
    Alternating Series Test, 623
    Direct Comparison Test, 616
    geometric series, 601
    guidelines, 635
    Integral Test, 609
    Limit Comparison Test, 618
    p-series, 611

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Ratio Test, 631
Root Test, 634
summary, 636
Convergent power series, form of, 668
Convergent series, limit of *n*th term of, 603
Conversion factors, 485, 494
Convex limaçon, 725
Coordinate conversion
cylindrical to rectangular, 808
cylindrical to spherical, 811
polar to rectangular, 720
rectangular to cylindrical, 808
rectangular to polar, 720
rectangular to spherical, 811
spherical to cylindrical, 811
spherical to rectangular, 811
Coordinate planes, 762
xy-plane, 762
xz-plane, 762
yz-plane, 762
Coordinate system
cylindrical, 808
polar, 719
spherical, 811
three-dimensional, 762
Coordinates
polar, 719
area in, 729
area of a surface of revolution in, 734
converting to rectangular, 720
Distance Formula in, 727
surface area in, 1012
rectangular
converting to cylindrical, 808
converting to polar, 720
converting to spherical, 811
curvature in, 860, 863
Copernicus, Nicolaus (1473–1543), 689
Cornu spiral, 750, 869
Cosecant function, 33
derivative of, 126, 139
integral of, 329
inverse of, 373
derivative of, 376
Cosine function, 33
derivative of, 115, 139
integral of, 329
inverse of, 373
derivative of, 376
series for, 674
Cotangent function, 33
derivative of, 126, 139
integral of, 329
inverse of, 373
derivative of, 376
Coterminal angles, 31
Coulomb's Law, 487, 1045
Critical number(s)
of a function, 168
relative extrema occur only at, 168
Critical point(s)
of a function of two variables, 941
relative extrema occur only at, 941
Cross product of two vectors in space, 779
algebraic properties of, 780
determinant form, 779
geometric properties of, 781
torque, 783
Cruciform, 149
Cubic function, 24
Cubing function, 22
Curl of a vector field, 1050
and divergence, 1052
Curtate cycloid, 708
Curvature, 858
center of, 860
circle of, 164, 860
formulas for, 859, 863
radius of, 860
in rectangular coordinates, 860, 863
related to acceleration and speed, 861
Curve(s)
astroid, 149
bifolium, 149
bullet-nose, 141
cissoid, 149
closed, 1074
cruciform, 149
equipotential, 426
folium of Descartes, 149, 737
isothermal, 426
kappa, 148, 150
lateral surface area over, 1067
lemniscate, 44, 147, 150, 725
level, 875
logistic, 427
natural equation for, 870
orientation of, 1055
piecewise smooth, 705, 1055
plane, 700, 820
pursuit, 395
rectifiable, 474
rose, 722, 725
simple, 1079
smooth, 474, 705, 830, 845, 1055
piecewise, 705, 1055
space, 820
tangent line to, 846
Curve sketching, summary of, 209
Cusps, 705, 830, 1091
Cycloid, 705, 709
curtate, 708
prolate, 712
Cylinder, 798
directrix of, 798
equations of, 798
generating curve of, 798
right, 798
rulings of, 798
Cylindrical coordinate system, 808
pole of, 808
Cylindrical coordinates
converting to rectangular, 808
converting to spherical, 811
Cylindrical surface, 798

D

d'Alembert, Jean Le Rond (1717–1783), 894
Darboux's Theorem, 246
Decay model, exponential, 416
Decomposition of $N(x)/D(x)$ into partial fractions, 551
Decreasing function, 181
test for, 181
Definite integral(s), 272
approximating
Midpoint Rule, 561
Simpson's Rule, 562
Trapezoidal Rule, 560
as the area of a region, 273
change of variables, 302
evaluation of a line integral as a, 1057
properties of, 276
two special, 275
of a vector-valued function, 832
Degenerate conic, 686
line, 686
point, 686
two intersecting lines, 686
Degree of a polynomial function, 24
Delta-neighborhood, 884
Demand, 18
Density, 498
Density function ρ, 998, 1018
Dependent variable, 19
of a function of two variables, 872
Derivative(s)
alternative form, 105
of arc length function, 856
Chain Rule, 133, 134, 139
implicit differentiation, 916
one independent variable, 911
three or more independent variables, 914
two independent variables, 913
of a composite function, 133
Constant Multiple Rule, 113, 139
Constant Rule, 110, 139
of cosecant function, 126, 139
of cosine function, 115, 139
of cotangent function, 126, 139
Difference Rule, 114, 139
directional, 919, 920, 927
of an exponential function, base a, 354
from the left and from the right, 105
of a function, 103
General Power Rule, 135, 139
higher-order, 128
of hyperbolic functions, 392
implicit, 145
of an inverse function, 337
of inverse trigonometric functions, 376
involving absolute value, 320
of a logarithmic function, base a, 354
of the natural exponential function, 344
of the natural logarithmic function, 318
notation, 103
parametric form, 710
higher-order, 711
partial, 894
Power Rule, 111, 139
Product Rule, 122, 139

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Quotient Rule, 124, 139
of secant function, 126, 139
second, 128
Simple Power Rule, 111, 139
simplifying, 137
of sine function, 115, 139
Sum Rule, 114, 139
of tangent function, 126, 139
third, 128
of trigonometric functions, 126, 139
of a vector-valued function, 828
higher-order, 829
properties of, 830
Descartes, René (1596–1650), 2
Determinant form of cross product, 779
Difference quotient, 20, 101
Difference Rule, 114, 139
differential form, 238
Difference of two functions, 25
Difference of two vectors, 754
Differentiability
and continuity of inverse functions, 337
implies continuity, 106, 907
sufficient condition for, 905
Differentiable at x, 103
Differentiable, continuously, 474
Differentiable function
on the closed interval $[a, b]$, 105
on an open interval (a, b), 103
in a region R, 905
of three variables, 906
of two variables, 905
vector-valued, 828
Differential, 236
as an approximation, 906
function of three or more variables, 904
function of three variables, 906
function of two variables, 904
of x, 236
of y, 236
Differential equation, 132, 249, 406
Bernoulli equation, 438
doomsday, 442
Euler's, 1160
Euler's Method, 410
first-order linear, 432
general solution of, 249, 406
Gompertz, 442
homogeneous, 431
change of variables, 431
initial condition, 253, 407
integrating factor, 432
logistic, 246, 427
order of, 406
particular solution of, 253, 407
separable, 423
separation of variables, 415, 423
singular solution of, 406
solution of, 406
Differential form, 238
of a line integral, 1063
Differential formulas, 238
constant multiple, 238
product, 238
quotient, 238
sum or difference, 238
Differential operator, 1050, 1052
Laplacian, 1127
Differentiation, 103
applied minimum and maximum problems, guidelines for solving, 220
basic rules for elementary functions, 378
formulas, 250
implicit, 144
Chain Rule, 916
guidelines for, 145
involving inverse hyperbolic functions, 396
logarithmic, 319
numerical, 106
partial, 894
of power series, 656
of a vector-valued function, 828
Differentiation rules
basic, 378
Chain, 133, 134, 139
Constant, 110, 139
Constant Multiple, 113, 139
cosecant function, 126, 139
cosine function, 115, 139
cotangent function, 126, 139
Difference, 114, 139
general, 139
General Power, 135, 139
Power, 111, 139
for Real Exponents, 355
Product, 122, 139
Quotient, 124, 139
secant function, 126, 139
Simple Power, 111, 135, 139
sine function, 115, 139
Sum, 114, 139
summary of, 139
tangent function, 126, 139
Diminishing returns, point of, 227
Dimpled limaçon, 725
Direct Comparison Test, 616
Direct substitution, 63, 64
Directed angle, 719
Directed distance
from points to a line, 497
polar coordinates, 719
Directed line segment(s), 752
equivalent, 752
initial point of, 752
length of, 752
magnitude of, 752
terminal point of, 752
Direction angles of a vector, 773
Direction cosines of a vector, 773
Direction field, 255, 315, 408
Direction of motion, 836
Direction numbers, 787
Direction vector, 787
Directional derivative, 919, 920
alternative form of, 922
of f in the direction of $\mathbf{u}$, 920, 927
of a function in three variables, 927
Directrix
of a conic, 738
of a cylinder, 798
of a parabola, 687
Dirichlet function, 55
Dirichlet, Peter Gustav (1805–1859), 55
Discontinuity, 75
infinite, 572
nonremovable, 75
removable, 75
Disk, 454, 884
closed, 884
method, 455
compared to shell, 467
open, 884
Displacement, 116
of a particle, 290, 291
Distance
between a point and a line, 18
in space, 793
between a point and a plane, 792
directed, 497
Formula in space, 763
total, traveled on $[a, b]$, 291
Distance Formula
in polar coordinates, 727
in space, 763
Distributive Property
for the Dot Product, 770
for vectors, 755
Diverge, 589, 599
Divergence
of improper integral with infinite discontinuities, 575
of a sequence, 589
of a series, 599
Test, 603
tests for series
Direct Comparison Test, 616
geometric series, 601
guidelines, 635
Integral Test, 609
Limit Comparison Test, 618
nth-Term Test, 603
p-series, 611
Ratio Test, 631
Root Test, 634
summary, 636
Theorem, 1084, 1110
of a vector field, 1052
and curl, 1052
Divergence-free vector field, 1052
Divide out like factors, 67
Domain
feasible, 219
of a function, 19
explicitly defined, 21
of two variables, 872
implied, 21
of a power series, 652
of a vector-valued function, 821
Doomsday equation, 442

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Dot product
Alternative form of, 772
Associative Property of, 770
Commutative Property of, 770
Distributive Property for, 770
form of work, 776
projection using the, 775
properties of, 770
of two vectors, 770
Double integral(s), 978, 979, 980
change of variables for, 1033
of f over R, 980
properties of, 980
Double-angle formulas, 33
Doyle Log Rule, 882
Dummy variable, 274
Dyne, 485

E

e, the number, 317
limit involving, 356
Eccentricity, 738
classification of conics by, 738
of an ellipse, 691
of a hyperbola, 694
Eight curve, 164
Electric force field, 1045
Elementary function(s), 24, 378
basic differentiation rules for, 378
polynomial approximation of, 640
power series for, 674
Eliminating the parameter, 702
Ellipse, 686, 689
area of, 545, 691, 692
center of, 689
circumference of, 692
eccentricity of, 691
foci of, 689
major axis of, 689
minor axis of, 689
reflective property of, 691
standard equation of, 689
vertices of, 689
Ellipsoid, 799, 800
Elliptic cone, 799, 801
Elliptic integral, 565
Elliptic paraboloid, 799, 801
Endpoint convergence, 654
Endpoint extrema, 166
Energy
kinetic, 1075
potential, 1075
Epicycloid, 708, 709, 713
Epsilon-delta, ε-δ definition of limit, 56
Equal vectors, 753, 764
Equality of mixed partial derivatives, 899
Equation(s)
basic, 552
guidelines for solving, 556
Bernoulli, 438
Cauchy-Riemann, 901
Chebyshev's, 1156
of conics, polar, 739
of a cylinder, 798
doomsday, 442
of an ellipse, 689
Euler's differential, 1160
general second-degree, 686
Gompertz, 442
graph of, 2
harmonic, 1127
heat, 901
of a hyperbola, 693
Laplace's, 901, 968, 1127
of a line
general form, 14
horizontal, 14
point-slope form, 11, 14
slope-intercept form, 13, 14
in space, parametric, 787
in space, symmetric, 787
summary, 14
vertical, 14
of a parabola, 687
parametric, 700, 1088
finding, 704
graph of, 700
of a plane in space
general form, 788
standard form, 788
primary, 219, 220
related-rate, 152
secondary, 220
separable, 423
solution point of, 2
of tangent plane, 932
van der Waals, 967
wave, 901, 967, 968
Equilibrium, 495
Equipotential
curves, 426
lines, 875
Equivalent
conditions, 1074
directed line segments, 752
Error
in approximating a Taylor polynomial, 646
in measurement, 237
percent error, 237
propagated error, 237
relative error, 237
in Simpson's Rule, 563
in Trapezoidal Rule, 563
Escape velocity, 98
Euler, Leonhard (1707–1783), 20
Euler's
constant, 615
differential equation, 1160
Method, 410
Evaluate a function, 19
Evaluating
a flux integral, 1104
a surface integral, 1098
Evaluation
by iterated integrals, 1014
of a line integral as a definite integral, 1057
Even function, 26
integration of, 304
test for, 26
Even/odd identities, 33
Everywhere continuous, 74
Existence
of an inverse function, 335
of a limit, 77
theorem, 81, 166
Expanded about c, approximating polynomial, 640
Explicit form of a function, 19, 144
Explicitly defined domain, 21
Exponential decay, 416
Exponential function, 24
to base a, 352
derivative of, 354
integration rules, 346
natural, 342
derivative of, 344
operations with, 343
properties of, 343
series for, 674
Exponential growth and decay model, 416
initial value, 416
proportionality constant, 416
Exponentiate, 343
Extended Mean Value Theorem, 246, 363
Extrema
endpoint, 166
of a function, 166, 940
guidelines for finding, 169
relative, 167
Extreme Value Theorem, 166, 940
Extreme values of a function, 166

F

Factorial, 591
Family of functions, 272
Famous curves
astroid, 149
bifolium, 149
bullet-nose curve, 141
circle, 149, 686, 725
cissoid, 149
cruciform, 149
eight curve, 164
folium of Descartes, 149, 737
kappa curve, 148, 150
lemniscate, 44, 147, 150, 725
parabola, 2, 149, 686, 687
pear-shaped quartic, 164
semicircle, 21, 141
serpentine, 130
witch of Agnesi, 130, 149, 202, 827
Faraday, Michael (1791–1867), 1075
Feasible domain, 219
Fermat, Pierre de (1601–1665), 168
Fibonacci sequence, 598, 608
Field
central force, 1045
direction, 255, 315, 408
electric force, 1045
force, 1044

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

gravitational, 1045
inverse square, 1045
slope, 255, 305, 315, 408
vector, 1044
over a plane region R, 1044
over a solid region Q, 1044
velocity, 1044, 1045
Finite Fourier series, 540
First Derivative Test, 183
First moments, 1002, 1018
First partial derivatives, 894
notation for, 895
First-order linear differential equations, 432
solution of, 433
Fitting integrands to basic rules, 519
Fixed plane, 866
Fixed point, 180, 233
Fluid(s)
force, 506
pressure, 505
weight-densities of, 505
Flux integral, 1104
evaluating, 1104
Focal chord of a parabola, 687
Focus
of a conic, 738
of an ellipse, 689
of a hyperbola, 693
of a parabola, 687
Folium of Descartes, 149, 737
Force, 485
constant, 485
exerted by a fluid, 506
of friction, 862
resultant, 758
variable, 486
Force field, 1044
central, 1045
electric, 1045
work, 1060
Form of a convergent power series, 668
Formula(s)
compound interest, 356
for curvature, 859, 863
differential, 238
differentiation, 250
Distance, in space, 763
double-angle, 33
Frenet-Serret, 869
Heron's, 967
integration, 250
Midpoint, in space, 763
power-reducing, 33
reduction, 540, 568
special integration, 545
Stirling's, 350
sum and difference, 33
summation, 259
Wallis's, 534
Fourier, Joseph (1768–1830), 661
Fourier series, finite, 540
Fourier Sine Series, 531
Fraction expansion, continued, 684
Fractions, partial, 550
decomposition of $N(x)/D(x)$ into, 551
method of, 550
Frenet-Serret formulas, 869
Fresnel function, 312
Friction, 862
Fubini's Theorem, 982
for a triple integral, 1014
Function(s), 19
absolute maximum of, 166
absolute minimum of, 166
absolute value, 22
acceleration, 128
accumulation, 287
addition of, 25
algebraic, 24, 25, 378
amplitude of, 37
antiderivative of, 248
arc length, 474, 475, 856
arccosecant, 373
arccosine, 373
arccotangent, 373
arcsecant, 373
arcsine, 373
arctangent, 373
average value of, 285, 986
Bessel, 659
Cobb-Douglas production, 877
combinations of, 25
common logarithmic, 353
component, 820
composite, 25, 873
composition of, 25, 873
concave downward, 191
concave upward, 191
constant, 24
continuous, 74
continuously differentiable, 474
cosecant, 33
cosine, 33
cotangent, 33
critical number of, 168
cubic, 24
cubing, 22
decreasing, 181
test for, 181
defined by power series, properties of, 656
density, 998, 1018
derivative of, 103
difference of, 25
differentiable, 103, 105
Dirichlet, 55
domain of, 19
implied, 21
elementary, 24, 378
algebraic, 24, 25
exponential, 24
logarithmic, 24
trigonometric, 24, 33
evaluate, 19
even, 26
explicit form, 19, 144
exponential to base a, 352
extrema of, 166
extreme values of, 166
family of, 272
feasible domain of, 219
Fresnel, 312
Gamma, 371, 582
global maximum of, 166
global minimum of, 166
graph of, guidelines for analyzing, 209
greatest integer, 76
Gudermannian, 399
Heaviside, 23
homogeneous, 431, 918
hyperbolic, 390
identity, 22
implicit form, 19
implicitly defined, 144
increasing, 181
test for, 181
inner product of two, 540
integrable, 272
inverse, 333
inverse hyperbolic, 394
inverse trigonometric, 373
involving a radical, limit of, 64
jerk, 163
joint density, 989
limit of, 52
linear, 24
local extrema of, 167
local maximum of, 167
local minimum of, 167
logarithmic, 314
to base a, 353
logistic growth, 357
natural exponential, 342
natural logarithmic, 314
notation, 19
odd, 26
one-to-one, 21
onto, 21
orthogonal, 540
period of, 36
periodic, 36
point of inflection, 193, 194
polynomial, 24, 64, 873
position, 116, 841
potential, 1047
present value of, 531
product of, 25
pulse, 97
quadratic, 24
quotient of, 25
radius, 804
range of, 19
rational, 22, 25, 873
real-valued, 19
relative extrema of, 167, 940
relative maximum of, 167, 940
relative minimum of, 167, 940
representation by power series, 661
Riemann zeta, 615
scalar, 820
secant, 33
signum, 86

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

sine, 33
square root, 22
squaring, 22
standard normal probability density, 345
step, 76
strictly monotonic, 182, 335
sum of, 25
tangent, 33
that agree at all but one point, 66
of three variables
continuity of, 890
directional derivative of, 927
gradient of, 927
transcendental, 25, 378
transformation of a graph of, 23
horizontal shift, 23
reflection about origin, 23
reflection about x-axis, 23
reflection about y-axis, 23
reflection in the line $y = x$, 334
vertical shift, 23
trigonometric, 24, 33
of two variables, 872
absolute maximum of, 940
absolute minimum of, 940
continuity of, 888
critical point of, 941
dependent variable, 872
differentiability implies continuity, 907
differentiable, 905
differential of, 904
domain of, 872
gradient of, 922
graph of, 874
independent variables, 872
limit of, 885
maximum of, 940
minimum of, 940
nonremovable discontinuity of, 888
partial derivative of, 894
range of, 872
relative extrema of, 940
relative maximum of, 940, 943
relative minimum of, 940, 943
removable discontinuity of, 888
total differential of, 904
unit pulse, 97
vector-valued, 820
Vertical Line Test, 22
of x and y, 872
zero of, 26
approximating with Newton's Method, 229
Fundamental Theorem
of Algebra, 1110
of Calculus, 281, 282
guidelines for using, 282
Second, 288
of Line Integrals, 1069, 1070

G

Gabriel's Horn, 578, 1090
Galilei, Galileo (1564–1642), 312, 378
Galois, Evariste (1811–1832), 232
Gamma function, 371, 582
Gauss, Carl Friedrich (1777–1855), 259, 1110
Gaussian Quadrature Approximation, Two-Point, 312
Gauss's Law, 1107
Gauss's Theorem, 1110
General antiderivative, 249
General differentiation rules, 139
General form
of the equation of a line, 14
of the equation of a plane in space, 788
of the equation of a quadric surface, 799
of a second-degree equation, 686
General harmonic series, 611
General partition, 271
General Power Rule
for differentiation, 135, 139
for Integration, 301
General second-degree equation, 686
General solution
of the Bernoulli equation, 438
of a differential equation, 249, 406
Generating curve of a cylinder, 798
Geometric power series, 661
Geometric properties of the cross product, 781
Geometric property of triple scalar product, 784
Geometric series, 601
alternating, 623
convergence of, 601
divergence of, 601
nth partial sum of, 601
sum of, 601
Gibbs, Josiah Willard (1839–1903), 780, 1056
Global maximum of a function, 166
Global minimum of a function, 166
Golden ratio, 598
Gompertz equation, 442
Grad, 922
Gradient, 1044, 1047
of a function of three variables, 927
of a function of two variables, 922
normal to level curves, 926
normal to level surfaces, 936
properties of, 924
recovering a function from, 1051
Graph(s)
of absolute value function, 22
of cubing function, 22
of an equation, 2
of a function
guidelines for analyzing, 209
transformation of, 23
of two variables, 874
of hyperbolic functions, 391
of identity function, 22
intercepts of, 4
of inverse hyperbolic functions, 395
of inverse trigonometric functions, 374
orthogonal, 150
of parametric equations, 700
polar, 721
points of intersection, 731
special polar graphs, 725
of rational function, 22
of the six trigonometric functions, 36
of square root function, 22
of squaring function, 22
symmetry of, 5
Gravitation
Newton's Law of, 1045
Newton's Law of Universal, 487, 854
Gravitational
constant, 487
field, 1045
Greatest integer function, 76
Green, George (1793–1841), 1080
Green's Theorem, 1079
alternative forms of, 1084
Gregory, James (1638–1675), 656
Gudermannian function, 399
Guidelines
for analyzing the graph of a function, 209
for evaluating integrals involving secant and tangent, 535
for evaluating integrals involving sine and cosine, 532
for finding extrema on a closed interval, 169
for finding intervals on which a function is increasing or decreasing, 182
for finding an inverse function, 335
for finding limits at infinity of rational functions, 202
for finding a Taylor series, 672
for implicit differentiation, 145
for integration, 327
for integration by parts, 523
for making a change of variables, 300
for solving applied minimum and maximum problems, 220
for solving the basic equation, 556
for solving related-rate problems, 153
for testing a series for convergence or divergence, 635
for using the Fundamental Theorem of Calculus, 282
Gyration, radius of, 1003

H

Half-life, 352, 417
Hamilton, William Rowan (1805–1865), 754
Harmonic equation, 1127
Harmonic series, 611, 615
alternating, 624, 626, 628
Heat equation, 901
Heat flow, 1107
Heat flux, 1107
Heaviside function, 23
Heaviside, Oliver (1850–1925), 23

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Helix, 821
Heron's Formula, 967
Herschel, Caroline (1750–1848), 695
Higher-order derivative, 128
  partial, 898
  of a vector-valued function, 829
Homogeneous of degree n, 431, 918
Homogeneous differential equation, 431
  change of variables for, 431
Homogeneous function, 431, 918
Hooke's Law, 487
Horizontal asymptote, 200
Horizontal component of a vector, 757
Horizontal line, 14
Horizontal Line Test, 335
Horizontal shift of a graph of a function, 23
Horizontally simple region of integration, 972
Huygens, Christian (1629–1795), 475
Hypatia (370–415 A.D.), 686
Hyperbola, 686, 693
  asymptotes of, 693
  center of, 693
  conjugate axis of, 693
  eccentricity of, 694
  foci of, 693
  standard equation of, 693
  transverse axis of, 693
  vertices of, 693
Hyperbolic functions, 390
  derivatives of, 392
  graphs of, 391
  identities, 391
  integrals of, 392
  inverse, 394
    differentiation involving, 396
    graphs of, 395
    integration involving, 396
Hyperbolic identities, 391
Hyperbolic paraboloid, 799, 801
Hyperboloid
  of one sheet, 799, 800, 1109
  of two sheets, 799, 800
Hypocycloid, 709

I

Identities
  cofunction, 33
  even/odd, 33
  hyperbolic, 391
  Pythagorean, 33
  quotient, 33
  reciprocal, 33
  trigonometric, 33
Identity function, 22
If and only if, 14
Image of x under f, 19
Implicit derivative, 145
Implicit differentiation, 144, 916
  Chain Rule, 916
  guidelines for, 145
Implicit form of a function, 19
Implicitly defined function, 144
Implied domain, 21
Improper integral(s), 572
  comparison test for, 580
  with infinite discontinuities, 575
    convergence of, 575
    divergence of, 575
  with infinite integration limits, 572
    convergence of, 572
    divergence of, 572
  special type, 578
Incidence, angle of, 688
Inclination of a plane, angle of, 935
Incompressible, 1052, 1115
Increasing function, 181
  test for, 181
Increment of z, 904
Increments of x and y, 904
Indefinite integral, 249
  pattern recognition, 296
  of a vector-valued function, 832
Indefinite integration, 249
Independence of path and conservative vector fields, 1072
Independent of path, 1072
Independent variable, 19
  of a function of two variables, 872
Indeterminate form, 67, 90, 201, 362, 363, 365
Index of summation, 258
Inductive reasoning, 593
Inequality
  Cauchy-Schwarz, 778
  Napier's, 331
  preservation of, 276
  triangle, 757
Inertia, moment of, 1002, 1018, 1109, 1128
  polar, 1002
Infinite discontinuities, 572
  improper integrals with, 575
    convergence of, 575
    divergence of, 575
Infinite integration limits, 572
  improper integrals with, 572
    convergence of, 572
    divergence of, 572
Infinite interval, 199
Infinite limit(s), 87
  at infinity, 205
  from the left and from the right, 87
  properties of, 91
Infinite series (or series), 599
  absolutely convergent, 626
  alternating, 623
    geometric, 623
    harmonic, 624, 626
    remainder, 625
  conditionally convergent, 626
  convergence of, 599
  convergent, limit of nth term, 603
  divergence of, 599
    nth-term test for, 603
  geometric, 601
  guidelines for testing for convergence or divergence of, 635
  harmonic, 611
    alternating, 624, 626, 628
  nth partial sum, 599
  properties of, 603
  p-series, 611
  sum of, 599
  telescoping, 600
  terms of, 599
Infinity
  infinite limit at, 205
  limit at, 199, 200
Inflection point, 193, 194
Initial condition(s), 253, 407
Initial point, directed line segment, 752
Initial ray (or side) of an angle, 31
Initial value, 416
Inner partition, 978, 1013
  polar, 991
Inner product
  of two functions, 540
  of two vectors, 770
Inner radius of a solid of revolution, 457
Inscribed rectangle, 262
Inside limits of integration, 971
Instantaneous rate of change, 103, 116
Instantaneous velocity, 117
Integrability and continuity, 272
Integrable function, 272, 980
Integral(s)
  of cosecant function, 329
  of cosine function, 329
  of cotangent function, 329
  definite, 272
    properties of, 276
    two special, 275
  double, 978, 979, 980
  elliptic, 565
  flux, 1104
  of hyperbolic functions, 392
  improper, 572
  indefinite, 249
  involving inverse trigonometric functions, 382
  involving secant and tangent, guidelines for evaluating, 535
  involving sine and cosine, guidelines for evaluating, 532
  involving sine-cosine products, 537
  iterated, 971
  line, 1056
  Mean Value Theorem, 284
  of $p(x) = Ax^2 + Bx + C$, 561
  of secant function, 329
  of sine function, 329
  single, 980
  of the six basic trigonometric functions, 329
  surface, 1098
  of tangent function, 329
  trigonometric, 532
  triple, 1013
Integral Test, 609
Integrand(s), procedures for fitting to basic rules, 519
Integrating factor, 432

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Integration
as an accumulation process, 449
Additive Interval Property, 275
basic rules of, 250, 385, 516
change of variables, 299
guidelines for, 300
constant of, 249
Constant Multiple Rule for, 298
of even and odd functions, 304
guidelines for, 327
indefinite, 249
pattern recognition, 296
involving inverse hyperbolic function, 396
Log Rule, 324
lower limit of, 272
of power series, 656
preservation of inequality, 276
region R of, 971
rules for exponential functions, 346
upper limit of, 272
of a vector-valued function, 832
Integration by parts, 523
guidelines for, 523
summary of common integrals using, 528
tabular method, 528
Integration by tables, 566
Integration formulas, 250
reduction formulas, 540, 568
special, 545
summary of, 1122
Integration rules
basic, 250, 385, 516
General Power Rule, 301
Power Rule, 250
Integration techniques
basic integration rules, 250, 385, 516
integration by parts, 523
method of partial fractions, 550
substitution for rational functions of sine and cosine, 569
tables, 566
trigonometric substitution, 541
Intercept(s), 4
x-intercept, 4
y-intercept, 4
Interest formulas, summary of, 356
Interior point of a region R, 884, 890
Intermediate Value Theorem, 81
Interpretation of concavity, 191
Interval of convergence, 652
Interval, infinite, 199
Inverse function(s), 333
continuity and differentiability of, 337
derivative of, 337
existence of, 335
guidelines for finding, 335
Horizontal Line Test, 335
properties of, 353
reciprocal slopes of, 338
reflective property of, 334
Inverse hyperbolic functions, 394
differentiation involving, 396
graphs of, 395
integration involving, 396
Inverse square field, 1045
Inverse trigonometric functions, 373
derivatives of, 376
graphs of, 374
integrals involving, 382
properties of, 375
Irrotational vector field, 1050
Isobars, 875
Isothermal curves, 426
Isothermal surfaces, 878
Isotherms, 875
Iterated integral, 971
evaluation by, 1014
inside limits of integration, 971
outside limits of integration, 971
Iteration, 229
ith term of a sum, 258

J

Jacobi, Carl Gustav (1804–1851), 1031
Jacobian, 1031, 1037
Jerk function, 163
Joint density function, 989

K

Kappa curve, 148, 150
Kepler, Johannes, (1571–1630), 689, 741
Kepler's Laws, 741, 866
Kinetic energy, 1075
Kirchhoff's Second Law, 434
Kovalevsky, Sonya (1850–1891), 884

L

Lagrange form of the remainder, 646
Lagrange, Joseph-Louis (1736–1813), 176, 956
Lagrange multiplier, 956, 957
Lagrange's Theorem, 957
Lambert, Johann Heinrich (1728–1777), 390
Lamina, planar, 498
Laplace, Pierre Simon de (1749–1827), 1024
Laplace Transform, 582
Laplace's equation, 901, 968, 1127
Laplacian, 1127
Lateral surface area over a curve, 1067
Latus rectum, of a parabola, 687
Law of Conservation of Energy, 1075
Law of Cosines, 33
Leading coefficient
of a polynomial function, 24
test, 24
Least squares
method of, 950
regression, 7
line, 950, 951
Least upper bound, 595
Left-hand limit, 76
Left-handed orientation, 762
Legendre, Adrien-Marie (1752–1833), 951
Leibniz, Gottfried Wilhelm (1646–1716), 238
Leibniz notation, 238
Lemniscate, 44, 147, 150, 725
Length
of an arc, 32, 474, 475
parametric form, 713
polar form, 733
of a directed line segment, 752
of the moment arm, 495
of a scalar multiple, 756
of a vector in the plane, 753
of a vector in space, 764
on x-axis, 1007
Level curve, 875
gradient is normal to, 926
Level surface, 877
gradient is normal to, 936
L'Hôpital, Guillaume (1661–1704), 363
L'Hôpital's Rule, 363
alternative form of, 364
Limaçon, 725
convex, 725
dimpled, 725
with inner loop, 725
Limit(s), 49, 52
basic, 63
of a composite function, 65
definition of, 56
ε-δ definition of, 56
evaluating
direct substitution, 63, 64
divide out like factors, 67
rationalize the numerator, 68
existence of, 77
of a function involving a radical, 64
of a function of two variables, 885
indeterminate form, 67
infinite, 87
from the left and from the right, 87
properties of, 91
at infinity, 199, 200
infinite, 205
of a rational function, guidelines for finding, 202
of integration
inside, 971
lower, 272
outside, 971
upper, 272
involving e, 356
from the left and from the right, 76
of the lower and upper sums, 264
nonexistence of, common types of behavior, 55
of nth term of a convergent series, 603
one-sided, 76
of polynomial and rational functions, 64
properties of, 63
of a sequence, 589
properties of, 590
strategy for finding, 66
of trigonometric functions, 65
two special trigonometric, 69
of a vector-valued function, 823
Limit Comparison Test, 618

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Line(s)
contour, 875
as a degenerate conic, 686
equation of
general form, 14
horizontal, 14
point-slope form, 11, 14
slope-intercept form, 13, 14
summary, 14
vertical, 14
equipotential, 875
of impact, 931
integral, 1056
for area, 1082
differential form of, 1063
evaluation of as a definite integral, 1057
of f along C, 1056
independent of path, 1072
summary of, 1107
of a vector field, 1060
least squares regression, 950, 951
moment about, 495
normal, 150, 217, 931, 932
parallel, 14
perpendicular, 14
radial, 719
secant, 49, 101
segment, directed, 752
slope of, 10
in space
direction number of, 787
direction vector of, 787
parametric equations of, 787
skew, 797
symmetric equations of, 787
tangent, 49, 100, 101
approximation, 235
at the pole, 724
with slope, 101
vertical, 102
Linear approximation, 235, 906
Linear combination of **i** and **j**, 757
Linear function, 24
Local maximum, 167
Local minimum, 167
Locus, 686
Log Rule for Integration, 324
Logarithmic differentiation, 319
Logarithmic function, 24, 314
to base a, 353
derivative of, 354
common, 353
natural, 314
derivative of, 318
properties of, 315
Logarithmic properties, 316
Logarithmic spiral, 737
Logistic curve, 427
Logistic differential equation, 246, 427
carrying capacity, 427
Logistic growth function, 357
Lorenz curves, 452
Lower bound of a sequence, 595
Lower bound of summation, 258
Lower limit of integration, 272
Lower sum, 262
limit of, 264
Lune, 549

M

Macintyre, Sheila Scott (1910–1960), 532
Maclaurin, Colin (1698–1746), 669
Maclaurin polynomial, 642
Maclaurin series, 669
Madhava (1350–1425), 668
Magnitude
of a directed line segment, 752
of a vector in the plane, 753
Major axis of an ellipse, 689
Marginal productivity of money, 959
Mass, 494
center of, 495, 496, 497
of a one-dimensional system, 495, 496
of a planar lamina, 498
of variable density, 1000
of a solid region Q, 1018
of a two-dimensional system, 497
of a fluid flowing across a surface per unit of time, 1104
moments of, 1000
of a planar lamina of variable density, 998
pound mass, 494
total, 496, 497
Mathematical model, 7, 950
Maximum
absolute, 166
of f on I, 166
of a function of two variables, 940
global, 166
local, 167
relative, 167
Mean Value Theorem, 176
alternative form of, 177
Extended, 246, 363
for Integrals, 284
Measurement, error in, 237
Mechanic's Rule, 234
Mercator, Gerardus (1512–1594), 399
Mercator map, 399
Method of
Lagrange Multipliers, 956, 957
least squares, 950
partial fractions, 550
Midpoint Formula in space, 763
Midpoint Rule, 266, 561
Minimum
absolute, 166
of f on I, 166
of a function of two variables, 940
global, 166
local, 167
relative, 167
Minor axis of an ellipse, 689
Mixed partial derivatives, 898
equality of, 899
Möbius Strip, 1097, 1109
Model
exponential growth and decay, 416
mathematical, 7, 950
Moment(s)
about a line, 495
about the origin, 495, 496
about a point, 495
about the x-axis
of a planar lamina, 498
of a two-dimensional system, 497
about the y-axis
of a planar lamina, 498
of a two-dimensional system, 497
arm, length of, 495
first, 1018
of a force about a point, 783
of inertia, 1002, 1018, 1109, 1128
polar, 1002
for a space curve, 1068
of mass, 1000
of a one-dimensional system, 496
of a planar lamina, 498
second, 1002, 1018
Monotonic sequence, 594
bounded, 595
Monotonic, strictly, 182, 335
Mutually orthogonal, 426

N

n factorial, 591
Napier, John (1550–1617), 314
Napier's inequality, 331
Natural equation for a curve, 870
Natural exponential function, 342
derivative of, 344
integration rules, 346
operations with, 343
properties of, 343
series for, 674
Natural logarithmic base, 317
Natural logarithmic function, 314
base of, 317
derivative of, 318
properties of, 315
series for, 674
Negative of a vector, 754
Net change, 290
Net Change Theorem, 290
Newton (unit of force), 485
Newton, Isaac (1642–1727), 100, 229
Newton's Law of Cooling, 419
Newton's Law of Gravitation, 1045
Newton's Law of Universal Gravitation, 487, 854
Newton's Method for approximating the zeros of a function, 229
convergence of, 231, 232
iteration, 229
Newton's Second Law of Motion, 433, 840
Nodes, 830
Noether, Emmy (1882–1935), 755
Nonexistence of a limit, common types of behavior, 55

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Nonremovable discontinuity, 75, 888
Norm
of a partition, 271, 978, 991, 1013
polar, 991
of a vector in the plane, 753
Normal component
of acceleration, 849, 850, 863
of a vector field, 1104
Normal line, 150, 217, 931, 932
Normal probability density function, 345
standard, 345
Normal vector(s), 772
principal unit, 846, 863
to a smooth parametric surface, 1091
Normalization of **v**, 756
Notation
antiderivative, 249
derivative, 103
for first partial derivatives, 895
function, 19
Leibniz, 238
sigma, 258
*n*th Maclaurin polynomial for *f*, 642
*n*th partial sum, 599
of geometric series, 601
*n*th Taylor polynomial for *f* at *c*, 642
*n*th term
of a convergent series, 603
of a sequence, 588
*n*th-Term Test for Divergence, 603
Number, critical, 168
Number *e*, 317
limit involving, 356
Numerical differentiation, 106

O

Obtuse angle, 31
Octants, 762
Odd function, 26
integration of, 304
test for, 26
Ohm's Law, 241
One-dimensional system
center of gravity of, 496
center of mass of, 495, 496
moment of, 495, 496
total mass of, 496
One-sided limit, 76
One-to-one function, 21
Onto function, 21
Open disk, 884
Open interval
continuous on, 74
differentiable on, 103
Open region *R*, 884, 890
continuous in, 888, 890
Open sphere, 890
Operations
with exponential functions, 343
with power series, 663
Order of a differential equation, 406
Orientable surface, 1103
Orientation
of a curve, 1055
of a plane curve, 701
of a space curve, 820
Oriented surface, 1103
Origin
moment about, 495, 496
of a polar coordinate system, 719
reflection about, 23
symmetry, 5
Orthogonal
functions, 540
graphs, 150
trajectory, 150, 426
vectors, 772
Ostrogradsky, Michel (1801–1861), 1110
Ostrogradsky's Theorem, 1110
Outer radius of a solid of revolution, 457
Outside limits of integration, 971

P

Padé approximation, 404
Pappus
Second Theorem of, 504
Theorem of, 501
Parabola, 2, 149, 686, 687
axis of, 687
directrix of, 687
focal chord of, 687
focus of, 687
latus rectum of, 687
reflective property of, 688
standard equation of, 687
vertex of, 687
Parabolic spandrel, 503
Parallel
lines, 14
planes, 789
vectors, 765
Parameter, 700
arc length, 856, 857
eliminating, 702
Parametric equations, 700
finding, 704
graph of, 700
of a line in space, 787
for a surface, 1088
Parametric form
of arc length, 713
of the area of a surface of revolution, 714
of the derivative, 710
higher-order, 711
Parametric surface, 1088
area of, 1092
equations for, 1088
partial derivatives of, 1091
smooth, 1091
normal vector to, 1091
surface area of, 1092
Partial derivatives, 894
first, 894
of a function of three or more variables, 897
of a function of two variables, 894
higher-order, 898
mixed, 898
equality of, 899
notation for, 895
of a parametric surface, 1091
Partial differentiation, 894
Partial fractions, 550
decomposition of $N(x)/D(x)$ into, 551
method of, 550
Partial sum(s)
*n*th, 599
of geometric series, 601
sequence of, 599
Particular solution of a differential equation, 253, 407
Partition
general, 271
inner, 978, 1013
polar, 991
norm of, 271, 978, 1013
polar, 991
regular, 271
Pascal, Blaise (1623–1662), 505
Pascal's Principle, 505
Path, 885, 1055
Pear-shaped quartic, 164
Percent error, 237
Perigee, 698
Perihelion, 698, 745
Period of a function, 36
Periodic function, 36
Perpendicular
lines, 14
planes, 789
vectors, 772
Piecewise smooth curve, 705, 1055
Planar lamina, 498
center of mass of, 498
moment of, 498
Plane
angle of inclination of, 935
distance between a point and, 792
region
area of, 264
simply connected, 1048, 1079
tangent, 932
equation of, 932
vector in, 752
Plane curve, 700, 820
orientation of, 701
smooth, 1055
Plane(s) in space
angle between two, 789
equation of
general form, 788
standard form, 788
parallel, 789
to the axis, 791
to the coordinate plane, 791
perpendicular, 789
trace of, 791
Point
as a degenerate conic, 686
of diminishing returns, 227

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

fixed, 180, 233
of inflection, 193, 194
of intersection, 6
of polar graphs, 731
moment about, 495
in a vector field
incompressible, 1115
sink, 1115
source, 1115
Point-slope equation of a line, 11, 14
Polar axis, 719
Polar coordinate system, 719
polar axis of, 719
pole (or origin), 719
Polar coordinates, 719
area in, 729
area of a surface of revolution in, 734
converting to rectangular, 720
Distance Formula in, 727
surface area in, 1012
Polar curve, arc length of, 733
Polar equations of conics, 739
Polar form of slope, 723
Polar graphs, 721
cardioid, 724, 725
circle, 725
convex limaçon, 725
dimpled limaçon, 725
lemniscate, 725
limaçon with inner loop, 725
points of intersection, 731
rose curve, 722, 725
Polar moment of inertia, 1002
Polar sectors, 990
Pole, 719
of cylindrical coordinate system, 808
tangent lines at, 724
Polynomial
Chebyshev, 1156
Maclaurin, 642
Taylor, 164, 642
Polynomial approximation, 640
centered at c, 640
expanded about c, 640
Polynomial function, 24, 64
constant term of, 24
degree of, 24
leading coefficient of, 24
limit of, 64
of two variables, 873
zero, 24
Position function, 116, 128
for a projectile, 841
Position vector for a projectile, 841
Potential energy, 1075
Potential function for a vector field, 1047
Pound mass, 494
Power-reducing formulas, 33
Power Rule
for differentiation, 111, 139
for integration, 250, 301
for Real Exponents, 355
Power series, 651
centered at c, 651
convergence of, 652
convergent, form of, 668
differentiation of, 656
domain of, 652
for elementary functions, 674
endpoint convergence, 654
geometric, 661
integration of, 656
interval of convergence, 652
operations with, 663
properties of functions defined by, 656
interval of convergence, 656
radius of convergence, 656
radius of convergence, 652
representation of functions by, 661
Present value of a function, 531
Preservation of inequality, 276
Pressure, fluid, 505
Primary equation, 219, 220
Prime Number Theorem, 323
Principal unit normal vector, 846, 863
Probability density function, 581
normal, 345
standard normal, 345
Procedures for fitting integrands to basic rules, 519
Product
of two functions, 25
inner, 540
of two vectors in space, cross, 779
Product Rule, 122, 139
differential form, 238
Projectile, position function for, 841
Projection form of work, 776
Projection of **u** onto **v**, 774
using the dot product, 775
Prolate cycloid, 712
Propagated error, 237
Properties
of continuity, 79
of the cross product
algebraic, 780
geometric, 781
of definite integrals, 276
of the derivative of a vector-valued function, 830
of the dot product, 770
of double integrals, 980
of functions defined by power series, 656
of the gradient, 924
of infinite limits, 91
of infinite series, 603
of inverse functions, 353
of inverse trigonometric functions, 375
of limits, 63
of limits of sequences, 590
logarithmic, 316
of the natural exponential function, 343
of the natural logarithmic function, 315
of vector operations, 755
Proportionality constant, 416
p-series, 611
convergence of, 611
divergence of, 611
harmonic, 611
Pulse function, 97
unit, 97
Pursuit curve, 395
Pythagorean identities, 33, 541

Q

Quadratic function, 24
Quadric surfaces, 799
ellipsoid, 799, 800
elliptic cone, 799, 801
elliptic paraboloid, 799, 801
general form of the equation of, 799
hyperbolic paraboloid, 799, 801
hyperboloid of one sheet, 799, 800, 1109
hyperboloid of two sheets, 799, 800
standard form of the equations of, 799, 800, 801
Quaternions, 754
Quotient, difference, 20, 101
Quotient identities, 33
Quotient Rule, 124, 139
differential form, 238
Quotient of two functions, 25

R

Radial lines, 719
Radian measure of angles, 32, 374
Radical, limit of a function involving a, 64
Radicals, solution by, 232
Radioactive isotopes, half-lives of, 417
Radius
of convergence, 652
of curvature, 860
function, 804
of gyration, 1003
inner, 457
outer, 457
Ramanujan, Srinivasa (1887–1920), 665
Range of a function, 19
of two variables, 872
Raphson, Joseph (1648–1715), 229
Rate of change, 12, 116, 897
average, 12
instantaneous, 103, 116
Ratio, 12
golden, 598
Ratio Test, 631
Rational function(s), 22, 25
guidelines for finding limits at infinity of, 202
limit of, 64
of two variables, 873
Rationalize the numerator, 68
Rationalizing technique, 68
Real Exponents, Power Rule for, 355
Real numbers, completeness of, 81, 595
Real-valued function f of a real variable x, 19
Reasoning, inductive, 593
Reciprocal identities, 33
Recovering a function from its gradient, 1051

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Rectangle
area of, 260
circumscribed, 262
inscribed, 262
representative, 444
Rectangular coordinates
converting to cylindrical, 808
converting to polar, 720
converting to spherical, 811
curvature in, 860, 863
Rectifiable curve, 474
Recursively defined sequence, 588
Reduction formulas, 540, 568
Reference angle, 35
Reflection
about the origin, 23
about the x-axis, 23
about the y-axis, 23
angle of, 688
in the line $y = x$, 334
Reflective property
of an ellipse, 691
of inverse functions, 334
of a parabola, 688
Reflective surface, 688
Refraction, 227, 963
Region of integration R, 971
horizontally simple, 972
r-simple, 992
θ-simple, 992
vertically simple, 972
Region in the plane
area of, 264, 972
between two curves, 445
centroid of, 499
connected, 1072
Region R
boundary point of, 884
bounded, 940
closed, 884
differentiable function in, 905
interior point of, 884, 890
open, 884, 890
continuous in, 888, 890
simply connected, 1048, 1079
Regression, least squares, 7
line, 950, 951
Regular partition, 271
Related-rate equation, 152
Related-rate problems, guidelines for solving, 153
Relation, 19
Relative error, 237
Relative extrema
First Derivative Test for, 183
of a function, 167, 940
occur only at critical numbers, 168
occur only at critical points, 941
Second Derivative Test for, 195
Second Partials Test for, 943
Relative maximum
at $(c, f(c))$, 167
First Derivative Test for, 183
of a function, 167, 940, 943
Second Derivative Test for, 195
Second Partials Test for, 943
Relative minimum
at $(c, f(c))$, 167
First Derivative Test for, 183
of a function, 167, 940, 943
Second Derivative Test for, 195
Second Partials Test for, 943
Remainder
alternating series, 625
of a Taylor polynomial, 646
Removable discontinuity, 75
of a function of two variables, 888
Representation of antiderivatives, 248
Representative element, 449
disk, 454
rectangle, 444
shell, 465
washer, 457
Resultant force, 758
Resultant vector, 754
Review
of basic differentiation rules, 378
of basic integration rules, 385, 516
Revolution
axis of, 454
solid of, 454
surface of, 478
area of, 479, 714, 734
volume of solid of
disk method, 454
shell method, 465, 466
washer method, 457
Riemann, Georg Friedrich Bernhard (1826–1866), 271, 628
Riemann sum, 271
Riemann zeta function, 615
Right cylinder, 798
Right triangle definitions of trigonometric functions, 33
Right-hand limit, 76
Right-handed orientation, 762
Rolle, Michel (1652–1719), 174
Rolle's Theorem, 174
Root Test, 634
Rose curve, 722, 725
Rotation of **F** about **N**, 1121
r-simple region of integration, 992
Rulings of a cylinder, 798

S

Saddle point, 943
Scalar, 752
field, 875
function, 820
multiple, 754
multiplication, 754, 764
product of two vectors, 770
quantity, 752
Secant function, 33
derivative of, 126, 139
integral of, 329
inverse of, 373
derivative of, 376
Secant line, 49, 101
Second derivative, 128
Second Derivative Test, 195
Second Fundamental Theorem of Calculus, 288
Second moment, 1002, 1018
Second Partials Test, 943
Second Theorem of Pappus, 504
Secondary equation, 220
Second-degree equation, general, 686
Semicircle, 21, 141
Separable differential equation, 423
Separation of variables, 415, 423
Sequence, 588
Absolute Value Theorem, 592
bounded, 595
bounded above, 595
bounded below, 595
bounded monotonic, 595
convergence of, 589
divergence of, 589
Fibonacci, 598, 608
least upper bound of, 595
limit of, 589
properties of, 590
lower bound of, 595
monotonic, 594
nth term of, 588
of partial sums, 599
pattern recognition for, 592
recursively defined, 588
Squeeze Theorem, 591
terms of, 588
upper bound of, 595
Series, 599
absolutely convergent, 626
alternating, 623
geometric, 623
harmonic, 624, 626, 628
Alternating Series Test, 623
binomial, 673
conditionally convergent, 626
convergence of, 599
convergent, limit of nth term, 603
Direct Comparison Test, 616
divergence of, 599
nth-term test for, 603
finite Fourier, 540
Fourier Sine, 531
geometric, 601
alternating, 623
convergence of, 601
divergence of, 601
guidelines for testing for convergence or divergence, 635
harmonic, 611, 615
alternating, 624, 626, 628
infinite, 599
properties of, 603
Integral Test, 609
Limit Comparison Test, 618
Maclaurin, 669
nth partial sum, 599
nth term of convergent, 603

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

power, 651
p-series, 611
Ratio Test, 631
Root Test, 634
sum of, 599
summary of tests for, 636
Taylor, 668, 669
telescoping, 600
terms of, 599
Serpentine, 130
Shell method, 465, 466
and disk method, comparison of, 467
Shift of a graph
horizontal, 23
vertical, 23
Sigma notation, 258
index of summation, 258
*i*th term, 258
lower bound of summation, 258
upper bound of summation, 258
Signum function, 86
Simple curve, 1079
Simple Power Rule, 111, 135, 139
Simple solid region, 1111
Simply connected plane region, 1079
Simpson's Rule, 562
error in, 563
Sine function, 33
derivative of, 115, 139
integral of, 329
inverse of, 373
derivative of, 376
series for, 674
Sine Series, Fourier, 531
Single integral, 980
Singular solution, differential equation, 406
Sink, 1115
Skew lines in space, 797
Slant asymptote, 205, 211
Slope(s)
field, 255, 305, 315, 408
of the graph of f at $x = c$, 101
of a line, 10
reciprocal, of inverse functions, 338
of a surface in x- and y-directions, 895
of a tangent line, 101
parametric form, 710
polar form, 723
Slope-intercept equation of a line, 13, 14
Smooth
curve, 474, 705, 830, 845
on an open interval, 830
piecewise, 705
parametric surface, 1091
plane curve, 1055
space curve, 1055
Snell's Law of Refraction, 227, 963
Solenoidal, 1052
Solid region, simple, 1111
Solid of revolution, 454
volume of
disk method, 454
shell method, 465, 466
washer method, 457
Solution
curves, 407
of a differential equation, 406
Bernoulli, 438
Euler's Method, 410
first-order linear, 433
general, 249, 406
particular, 253, 407
singular, 406
point of an equation, 2
by radicals, 232
Some basic limits, 63
Somerville, Mary Fairfax (1780–1872), 873
Source, 1115
Space curve, 820
arc length of, 855
moments of inertia for, 1068
smooth, 1055
Spandrel, parabolic, 503
Special integration formulas, 545
Special polar graphs, 725
Special type of improper integral, 578
Speed, 117, 836, 837, 861, 863
angular, 1003
Sphere, 763
astroidal, 1097
open, 890
standard equation of, 763
Spherical coordinate system, 811
Spherical coordinates
converting to cylindrical, 811
converting to rectangular, 811
Spiral
of Archimedes, 721, 737
cornu, 750, 869
logarithmic, 737
Square root function, 22
Squared errors, sum of, 950
Squaring function, 22
Squeeze Theorem, 69
for Sequences, 591
Standard equation of
an ellipse, 689
a hyperbola, 693
a parabola, 687
a sphere, 763
Standard form of the equation of
an ellipse, 689
a hyperbola, 693
a parabola, 687
a plane in space, 788
a quadric surface, 799, 800, 801
Standard form of a first-order linear differential equation, 432
Standard normal probability density function, 345
Standard position
of an angle, 31
of a vector, 753
Standard unit vector, 757
notation, 764
Step function, 76
Stirling's approximation, 525
Stirling's Formula, 350
Stokes, George Gabriel (1819–1903), 1118
Stokes's Theorem, 1084, 1118
Strategy for finding limits, 66
Strictly monotonic function, 182, 335
Strophoid, 750
Substitution for rational functions of sine and cosine, 569
Sufficient condition for differentiability, 905
Sum(s)
and difference formulas, 33
of geometric series, 601
*i*th term of, 258
lower, 262
limit of, 264
*n*th partial, 599
of geometric series, 601
Riemann, 271
Rule, 114, 139
differential form, 238
of a series, 599
sequence of partial, 599
of the squared errors, 950
of two functions, 25
of two vectors, 754
upper, 262
limit of, 264
Summary
of common integrals using integration by parts, 528
of compound interest formulas, 356
of curve sketching, 209
of differentiation rules, 139
of equations of lines, 14
of integration formulas, 1122
of line and surface integrals, 1107
of tests for series, 636
of velocity, acceleration, and curvature, 863
Summation
formulas, 259
index of, 258
lower bound of, 258
upper bound of, 258
Surface
closed, 1110
cylindrical, 798
isothermal, 878
level, 877
orientable, 1103
oriented, 1103
parametric, 1088
parametric equations for, 1088
quadric, 799
reflective, 688
trace of, 799
Surface area
of a parametric surface, 1092
in polar coordinates, 1012

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s).
Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

of a solid, 1006, 1007
Surface integral, 1098
evaluating, 1098
summary of, 1107
Surface of revolution, 478, 804
area of, 479
parametric form, 714
polar form, 734
Symmetric equations, line in space, 787
Symmetry
tests for, 5
with respect to the origin, 5
with respect to the x-axis, 5
with respect to the y-axis, 5

T

Table of values, 2
Tables, integration by, 566
Tabular method for integration by parts, 528
Tangent function, 33
derivative of, 126, 139
integral of, 329
inverse of, 373
derivative of, 376
Tangent line(s), 49, 100, 101
approximation of f at c, 235
to a curve, 846
at the pole, 724
problem, 49
slope of, 101
parametric form, 710
polar form, 723
with slope m, 101
vertical, 102
Tangent plane, 932
equation of, 932
Tangent vector, 836
Tangential component of acceleration, 849, 850, 863
Tautochrone problem, 706
Taylor, Brook (1685–1731), 642
Taylor polynomial, 164, 642
error in approximating, 646
remainder, Lagrange form of, 646
Taylor series, 668, 669
convergence of, 670
guidelines for finding, 672
Taylor's Theorem, 646
Telescoping series, 600
Terminal point, directed line segment, 752
Terminal ray (or side) of an angle, 31
Terms
of a sequence, 588
of a series, 599
Test(s)
comparison, for improper integrals, 580
for concavity, 192
conservative vector field in the plane, 1048
conservative vector field in space, 1051
for convergence
Alternating Series, 623
Direct Comparison, 616
geometric series, 601
guidelines, 635
Integral, 609
Limit Comparison, 618
p-series, 611
Ratio, 631
Root, 634
summary, 636
for even and odd functions, 26
First Derivative, 183
Horizontal Line, 335
for increasing and decreasing functions, 181
Leading Coefficient, 24
Second Derivative, 195
for symmetry, 5
Vertical Line, 22
Theorem
Absolute Value, 592
of Calculus, Fundamental, 281, 282
guidelines for using, 282
of Calculus, Second Fundamental, 288
Cavalieri's, 464
Darboux's, 246
Divergence, 1084, 1110
existence, 81, 166
Extended Mean Value, 246, 363
Extreme Value, 166, 940
Fubini's, 982
for a triple integral, 1014
Intermediate Value, 81
Mean Value, 176
alternative form, 177
Extended, 246, 363
for Integrals, 284
Net Change, 290
of Pappus, 501
Second, 504
Prime Number, 323
Rolle's, 174
Squeeze, 69
for sequences, 591
Taylor's, 646
Theta, θ
simple region of integration, 992
Third derivative, 128
Three-dimensional coordinate system, 762
left-handed orientation, 762
right-handed orientation, 762
Topographic map, 875
Topological surfaces, 807
Torque, 496, 783
Torricelli, Evangelista (1608–1647), 435
Torricelli's Law, 442
Torsion, 869
Total differential, 904
Total distance traveled on $[a, b]$, 291
Total mass, 496, 497
of a one-dimensional system, 496
of a two-dimensional system, 497
Trace
of a plane in space, 791
of a surface, 799
Tractrix, 323, 395
Trajectories, orthogonal, 150, 426
Transcendental function, 25, 378
Transformation, 23, 1032
Transformation of a graph of a function, 23
basic types, 23
horizontal shift, 23
reflection about origin, 23
reflection about x-axis, 23
reflection about y-axis, 23
reflection in the line $y = x$, 334
vertical shift, 23
Transverse axis of a hyperbola, 693
Trapezoidal Rule, 560
error in, 563
Triangle inequality, 757
Trigonometric function(s), 24, 33
and the Chain Rule, 138
circular function definitions of, 33
derivatives of, 126, 139
integrals of the six basic, 329
inverse, 373
derivatives of, 376
graphs of, 374
integrals involving, 382
properties of, 375
limit of, 65
right triangle definitions of, 33
Trigonometric identities, 33
Trigonometric integrals, 532
Trigonometric substitution, 541
Trigonometric values of common angles, 34
Triple integral, 1013
in cylindrical coordinates, 1024
in spherical coordinates, 1027
Triple scalar product, 783
geometric property of, 784
Two special definite integrals, 275
Two special trigonometric limits, 69
Two-dimensional system
center of gravity of, 497
center of mass of, 497
moment of, 497
total mass of, 497
Two-Point Gaussian Quadrature Approximation, 312

U

Unit circle, 32
Unit pulse function, 97
Unit tangent vector, 845, 863
Unit vector, 753
in the direction of $\mathbf{v}$, 756, 764
standard, 757
Universal Gravitation, Newton's Law of, 487
Upper bound
least, 595
of a sequence, 595

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

of summation, 258
Upper limit of integration, 272
Upper sum, 262
limit of, 264
u-substitution, 296

V

Value of f at x, 19
van der Waals equation, 967
Variable
dependent, 19
dummy, 274
force, 486
independent, 19
Vector(s)
acceleration, 849, 861, 863
addition, 754, 755
associative property of, 755
commutative property of, 755
Additive Identity Property, 755
Additive Inverse Property, 755
angle between two, 771
binormal, 853, 869
component
of **u** along **v**, 774
of **u** orthogonal to **v**, 774
component form of, 753
components, 753, 774
cross product of, 779
difference of two, 754
direction, 787
direction angles of, 773
direction cosines of, 773
Distributive Property, 755
dot product of, 770
equal, 753, 764
horizontal component of, 757
initial point, 752
inner product of, 770
length of, 753, 764
linear combination of, 757
magnitude of, 753
negative of, 754
norm of, 753
normal, 772
normalization of, 756
operations, properties of, 755
orthogonal, 772
parallel, 765
perpendicular, 772
in the plane, 752
position, for a projectile, 841
principal unit normal, 846, 863
product, 779
projection of, 774
resultant, 754
scalar multiplication, 754, 764
scalar product of, 770
in space, 764
standard position, 753
standard unit notation, 764
sum, 754
tangent, 836
terminal point, 752
triple scalar product, 783
unit, 753
in the direction of **v**, 756, 764
standard, 757
unit tangent, 845, 863
velocity, 836, 863
vertical component of, 757
zero, 753, 764
Vector field, 1044
circulation of, 1121
conservative, 1047, 1069
test for, 1048, 1051
continuous, 1044
curl of, 1050
divergence of, 1052
divergence-free, 1052
incompressible, 1115
irrotational, 1050
line integral of, 1060
normal component of, 1104
over a plane region R, 1044
over a solid region Q, 1044
potential function for, 1047
rotation of, 1121
sink, 1115
solenoidal, 1052
source, 1115
Vector space, 755
axioms, 755
Vector-valued function(s), 820
antiderivative of, 832
continuity of, 824
continuous on an interval, 824
continuous at a point, 824
definite integral of, 832
derivative of, 828
higher-order, 829
properties of, 830
differentiation of, 828
domain of, 821
indefinite integral of, 832
integration of, 832
limit of, 823
Velocity, 117, 837
average, 116
escape, 98
function, 128
instantaneous, 117
potential curves, 426
Velocity field, 1044, 1045
incompressible, 1052
Velocity vector, 836, 863
Vertéré, 202
Vertex
of an angle, 31
of an ellipse, 689
of a hyperbola, 693
of a parabola, 687
Vertical asymptote, 89
Vertical component of a vector, 757
Vertical line, 14
Vertical Line Test, 22
Vertical shift of a graph of a function, 23
Vertical tangent line, 102
Vertically simple region of integration, 972
Volume of a solid
disk method, 455
with known cross sections, 459
shell method, 465, 466
washer method, 457
Volume of a solid region, 980, 1013

W

Wallis, John (1616–1703), 534, 540
Wallis Product, 540
Wallis's Formulas, 534
Washer, 457
Washer method, 457
Wave equation, 901, 967, 968
Weierstrass, Karl (1815–1897), 941
Weight-densities of fluids, 505
Wheeler, Anna Johnson Pell (1883–1966), 432
Witch of Agnesi, 130, 149, 202, 827
Work, 485, 776
done by a constant force, 485
done by a variable force, 486
dot product form, 776
force field, 1060
projection form, 776

X

x-axis
moment about, of a planar lamina, 498
moment about, of a two-dimensional system, 497
reflection about, 23
symmetry, 5
x-intercept, 4
xy-plane, 762
xz-plane, 762

Y

y-axis
moment about, of a planar lamina, 498
moment about, of a two-dimensional system, 497
reflection about, 23
symmetry, 5
y-intercept, 4
Young, Grace Chisholm (1868–1944), 49
yz-plane, 762

Z

Zero factorial, 591
Zero of a function, 26
approximating
bisection method, 82
Intermediate Value Theorem, 81
with Newton's Method, 229
Zero polynomial, 24
Zero vector, 753, 764

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

ALGEBRA

Factors and Zeros of Polynomials

Let $p(x) = a_n x^n + a_{n-1}x^{n-1} + \cdots + a_1 x + a_0$ be a polynomial. If $p(a) = 0$, then a is a *zero* of the polynomial and a solution of the equation $p(x) = 0$. Furthermore, $(x - a)$ is a *factor* of the polynomial.

Fundamental Theorem of Algebra

An nth degree polynomial has n (not necessarily distinct) zeros. Although all of these zeros may be imaginary, a real polynomial of odd degree must have at least one real zero.

Quadratic Formula

If $p(x) = ax^2 + bx + c$, and $0 \le b^2 - 4ac$, then the real zeros of p are $x = \left(-b \pm \sqrt{b^2 - 4ac}\right)/2a$.

Special Factors

$$x^2 - a^2 = (x - a)(x + a)$$

$$x^3 - a^3 = (x - a)(x^2 + ax + a^2)$$

$$x^3 + a^3 = (x + a)(x^2 - ax + a^2)$$

$$x^4 - a^4 = (x - a)(x + a)(x^2 + a^2)$$

Binomial Theorem

$$(x + y)^2 = x^2 + 2xy + y^2$$

$$(x - y)^2 = x^2 - 2xy + y^2$$

$$(x + y)^3 = x^3 + 3x^2y + 3xy^2 + y^3$$

$$(x - y)^3 = x^3 - 3x^2y + 3xy^2 - y^3$$

$$(x + y)^4 = x^4 + 4x^3y + 6x^2y^2 + 4xy^3 + y^4$$

$$(x - y)^4 = x^4 - 4x^3y + 6x^2y^2 - 4xy^3 + y^4$$

$$(x + y)^n = x^n + nx^{n-1}y + \frac{n(n-1)}{2!}x^{n-2}y^2 + \cdots + nxy^{n-1} + y^n$$

$$(x - y)^n = x^n - nx^{n-1}y + \frac{n(n-1)}{2!}x^{n-2}y^2 - \cdots \pm nxy^{n-1} \mp y^n$$

Rational Zero Theorem

If $p(x) = a_n x^n + a_{n-1}x^{n-1} + \cdots + a_1 x + a_0$ has integer coefficients, then every *rational zero* of p is of the form $x = r/s$, where r is a factor of a_0 and s is a factor of a_n.

Factoring by Grouping

$$acx^3 + adx^2 + bcx + bd = ax^2(cx + d) + b(cx + d) = (ax^2 + b)(cx + d)$$

Arithmetic Operations

$$ab + ac = a(b + c)$$

$$\frac{a}{b} + \frac{c}{d} = \frac{ad + bc}{bd}$$

$$\frac{a + b}{c} = \frac{a}{c} + \frac{b}{c}$$

$$\frac{\left(\frac{a}{b}\right)}{\left(\frac{c}{d}\right)} = \left(\frac{a}{b}\right)\left(\frac{d}{c}\right) = \frac{ad}{bc}$$

$$\frac{\left(\frac{a}{b}\right)}{c} = \frac{a}{bc}$$

$$\frac{a}{\left(\frac{b}{c}\right)} = \frac{ac}{b}$$

$$a\left(\frac{b}{c}\right) = \frac{ab}{c}$$

$$\frac{a - b}{c - d} = \frac{b - a}{d - c}$$

$$\frac{ab + ac}{a} = b + c$$

Exponents and Radicals

$$a^0 = 1, \quad a \neq 0$$

$$(ab)^x = a^x b^x$$

$$a^x a^y = a^{x+y}$$

$$\sqrt{a} = a^{1/2}$$

$$\frac{a^x}{a^y} = a^{x-y}$$

$$\sqrt[n]{a} = a^{1/n}$$

$$\left(\frac{a}{b}\right)^x = \frac{a^x}{b^x}$$

$$\sqrt[n]{a^m} = a^{m/n}$$

$$a^{-x} = \frac{1}{a^x}$$

$$\sqrt[n]{ab} = \sqrt[n]{a}\sqrt[n]{b}$$

$$(a^x)^y = a^{xy}$$

$$\sqrt[n]{\frac{a}{b}} = \frac{\sqrt[n]{a}}{\sqrt[n]{b}}$$

© Cengage Learning

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

FORMULAS FROM GEOMETRY

Triangle

$h = a \sin \theta$

Area $= \frac{1}{2}bh$

(Law of Cosines)

$c^2 = a^2 + b^2 - 2ab \cos \theta$



Right Triangle

(Pythagorean Theorem)

$c^2 = a^2 + b^2$



Equilateral Triangle

$h = \frac{\sqrt{3}s}{2}$

Area $= \frac{\sqrt{3}s^2}{4}$



Parallelogram

Area $= bh$



Trapezoid

Area $= \frac{h}{2}(a + b)$



Circle

Area $= \pi r^2$

Circumference $= 2\pi r$



Sector of Circle

(θ in radians)

Area $= \frac{\theta r^2}{2}$

$s = r\theta$



Circular Ring

(p = average radius,
w = width of ring)

Area $= \pi(R^2 - r^2)$
$= 2\pi pw$



Sector of Circular Ring

(p = average radius,
w = width of ring,
θ in radians)

Area $= \theta pw$



Ellipse

Area $= \pi ab$

Circumference $\approx 2\pi \sqrt{\frac{a^2 + b^2}{2}}$



Cone

(A = area of base)

Volume $= \frac{Ah}{3}$



Right Circular Cone

Volume $= \frac{\pi r^2 h}{3}$

Lateral Surface Area $= \pi r\sqrt{r^2 + h^2}$



Frustum of Right Circular Cone

Volume $= \frac{\pi(r^2 + rR + R^2)h}{3}$

Lateral Surface Area $= \pi s(R + r)$



Right Circular Cylinder

Volume $= \pi r^2 h$

Lateral Surface Area $= 2\pi rh$



Sphere

Volume $= \frac{4}{3}\pi r^3$

Surface Area $= 4\pi r^2$



Wedge

(A = area of upper face,
B = area of base)

$A = B \sec \theta$



Tear out Formula Cards for Homework Success.

© Cengage Learning

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.

Index of Applications (continued from front inside cover)

Torque, 783, 785, 816
Torricelli's Law, 442
Tossing bales, 843
Tractrix, 323, 395, 399, 549, 718
Velocity, 117, 121, 156, 180, 294, 295, 452, 586
Velocity and acceleration, 312, 431
  on the moon, 164
Velocity in a resisting medium, 371
Vertical motion, 120, 162, 178, 179, 254, 256, 309, 310, 389
Vibrating string, 162, 531
Wave equation, 901, 968
Wave motion, 142
Wind chill, 910
Work, 512, 514, 565
  done in closing a door, 776
  done by an expanding gas, 490
  done by a force field, 1066, 1068, 1077, 1125
  done by hoisting a car, 491
  done by a hydraulic cylinder, 493, 571
  done by a hydraulic press, 493
  done in lifting a box, 493
  done in lifting a chain, 490, 492
  done in lifting a steel beam, 491
  done in moving a particle, 1068, 1085
  done by a person walking up a staircase, 1068
  done by propelling a rocket, 580
  done in propelling a satellite, 491, 512
  done in pulling an object, 815
  done in pulling a pallet truck, 778
  done in pulling a train car, 491
  done in pulling a wagon, 778
  done in pumping gasoline, 492
  done in pumping water, 491, 492, 512
  done in sliding a cement block, 491
  done in splitting a piece of wood, 493
  done in towing a car, 778
  done in winding a chain, 492, 512

Business and Economics

Annuities, 607
Apartment rental, 18
Average cost, 198
Average price, 332
Average production, 988
Average profit, 1039
Biomass-based diesel fuel production, 17
Break-even analysis, 42
Break-even point, 9
Building a pipeline, 955
Capitalized cost, 581
Cobb-Douglas production function, 877, 882, 883, 959, 965, 968
Compound interest, 356, 357, 359, 360, 371, 402, 421, 440, 597, 681
Cost, 97, 121, 142, 178, 244, 340, 422, 558, 883
Declining sales, 418
Depreciation, 143, 307, 349, 359, 402, 606, 681
Eliminating budget deficits, 452
Government expenditures, 597
Gross Domestic Product (GDP), 9
Gross income tax collections, 954
Health care expenditures, 131, 903
Home mortgage, 323
Income distribution in a country, 452
Inflation, 359, 597
Inventory management, 85, 121
Inventory replenishment, 130
Investment, 882, 902
Investment growth, 436
Manufacturing, 459, 463
Marginal costs, 902
Marginal productivity, 902
Marginal productivity of money, 959
Marginal revenue, 902
Marginal utility, 903
Marketing, 606, 681
Maximum profit, 227, 949, 953, 966
Maximum revenue, 953, 966
Medicare Hospital Insurance Trust Fund, 189
Minimum cost, 226, 953, 963, 967
Multiplier effect, 606
Outlays for national defense, 244
Personal consumption expenditures, 796, 903
Present value, 531, 585, 607
Profit, 452
Revenue, 452, 512, 778
Salary, 607
Sales, 40, 179, 196, 307, 332, 440, 883
Sales growth, 198, 244
Veterans with service-connected disabilities, 955

Social and Behavioral Sciences

Cell phone subscriptions, 9
Free lunch program, 160
Group project in learning theory, 360
Learning curve, 436
Memory model, 531
Population, 12, 16, 421, 598, 996
Population growth, 431, 436, 440, 441, 571
Psychology, intelligence test, 902

Life Sciences

Acid rain, 883
Agronomy, 967
Bacterial culture growth, 143, 357, 421, 431
Biomass, 442
Carbon dioxide concentration, 7
Concentration of a chemical in the bloodstream, 189, 234
Diversity of wildflowers in a meadow, 939
DNA molecule, 821
Endangered species, 431
Epidemic model, 441, 558
Forestry, 422, 882
Grand Canyon, 257
Growth of a dog, 294
Hardy-Weinberg Law, 953
Intravenous feeding, 437
Near point of the eye, 955
Oxygen level in a pond, 204
Population growth
  of bacteria, 130, 256, 332
  of brook trout, 440
  of coyotes, 425
  of elk, 428
  of fish, 360
  of fruit flies, 418
  of raccoons, 440
Respiratory cycle, 293
Shannon diversity index, 953
Systolic blood pressure, 954
Topographic map, 150
Trachea contraction, 189
Tree growth, 256

General

Area, 120, 130, 157, 240, 260, 607, 678
Average typing speed, 198, 207
Baseball, 910
Cantor set, 683
Cantor's disappearing table, 608
Distance traveled by a bouncing ball, 604, 606, 681
Error, 237, 241, 907, 909
Football, 843
Maximizing an angle, 377, 381
Maximum area, 43, 223, 225, 226, 244
Maximum volume, 219, 220, 224, 225, 227, 948, 953, 962
Mercator map, 399
Minimum area, 221, 225
Minimum distance, 221, 224, 228, 246
Minimum length, 222, 225, 226, 244, 245
Minimum perimeter, 224
Minimum surface area, 226
Minimum time, 226, 227, 228, 234
Probability, 308, 351, 581, 585, 606, 667, 678, 989, 997
Shot put, 843
Speed, 29, 155, 177, 180, 865, 955
Sphereflake, 607
Sprinkler, 173, 1042
Surface area, 157, 162, 163, 241, 482, 483, 484, 578, 698
Volume, 30, 86, 120, 130, 152, 157, 227, 460, 463, 469, 472, 473, 548, 997
Weight gain, 430
Weight loss, 438

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. WCN 02-200-322

Copyright 2023 Cengage Learning. All Rights Reserved. May not be copied, scanned, or duplicated, in whole or in part. Due to electronic rights, some third party content may be suppressed from the eBook and/or eChapter(s). Editorial review has deemed that any suppressed content does not materially affect the overall learning experience. Cengage Learning reserves the right to remove additional content at any time if subsequent rights restrictions require it.